

Project: Paint interior gypsum walls

SPECIFICATIONS PAGE 1 OF 1

Location: Kenosha SWEF

Approved:

Part 1 General Description

- .1 Project Overview:
 - .1.1 Prepare and paint interior gypsum walls and ceilings as noted in Part 3 Installation.
- .2 Site Location:
 - .2.1 The Kenosha Safety Weight Enforcement Facility is located on I94 westbound approximately .5 miles north of the Illinois ~~border~~ in Kenosha County, Wisconsin.

border
- .3 Quality Assurance
 - .3.1 Vendor shall follow manufacturer's directions and specifications for paint.
- .4 Warranty
 - .4.1 Provide manufacturer's warranty for specified individual products (if applicable).
 - .4.2 Installation warranty shall be as directed by product manufacturer.

Part 2 Products

- 2.1 Acceptable Manufacturer(s)
 - 2.1.1 Sherwin-Williams or like quality manufacturer.
- 2.2 Products
 - 2.2.1.1 Sherwin-Williams ProMar 200 Interior Latex Eggshell B20 Series semi-gloss or like quality and color paint.

Part 3 Installation

- 3.1 Method of Installation
 - 3.1.1 Patch and sand any and all damaged areas on gypsum walls and ceilings in lobby, public restrooms, ~~receiving and operations~~ area, hallways, offices and staff room in preparation for painting.

vestibules?
 - 3.1.2 Assure all gypsum walls and ceilings in designated painting areas are clean and ready for paint application.
 - 3.1.3 Apply one coat of Interior Latex Eggshell semi-gloss to gypsum walls and ceilings in designated areas.

Primer or extra coat on repaired areas?
- 3.2 Cleaning of Work Areas
 - 3.2.1 Leave all work areas broom clean.

Clean up all paint spills
 - 3.2.2 Provide all warranty information to project advisor.
 - 3.2.3 Provide one full gallon of paint to project advisor.