




GAS WORK REQUEST	CRITICAL SAFETY RULES - GO:	CONSTRUCTION REMARKS:	
4134038	Confined space procedures     Excavation and shoring		
	3. Live gas emergency procedures 4. Lock out - Tag out	* ALL PROPOSED 6" HIGH PRESSURE STEEL MAIN IS TO BE INSTALLED AT A MINIMUM OF 4' FROM EXISTING GRADE UNLESS OTHERWISE NOTED IN THE CUT SHEETS LISTED	
CX T V: GREENVILLE  CUST/PROJ NAME: GREENVILLE CAPACITY PROJECT	<ul><li>5. Seat belts</li><li>6. Securing parked vehicles</li></ul>	ON SHEETS 17 AND 18. THE 10,932' OF 6" STEEL PIPE IS SPECIAL ORDER.	
PROJECT LOCATION: CTH OO/STH 15 FROM BLUEMOUND	JOB INFO:	*CONSTRUCTION OF THE 6" PE IN THE EAST RIGHT OF WAY OF N MAYFLOWER ROAD IS	
DR WEST TO MAYFLOWER DR THEN SOUTH	SECTION / TOWN / RANGE: SE1/4 SEC17, T21N, R17E	TO BE CONSTRUCTED PRIOR TO THE 6" HIGH PRESSURE STEEL UNDER WORK REQUEST 4370332. CONSTRUCTED BY SEPARATE CONTRACTOR.	
PREPARED BY: CODY BECKMAN	SITE VISIT COMPLETED BY: CODY BECKMAN		
E-MAIL: cody.beckman@we-energies.com	JOB OWNER: CODY BECKMAN	*CONSTRUCTION OF THE NEW 6" STEEL MAIN IS TO BE PERFORMED AT THE SAME TIME AS THE REGULATION STATION. CONSTRUCTION SCHEDULING MUST BE	
		COORDINATED BETWEEN THE TWO CONTRACTORS. THE GAS MAIN IS TO BE INSTALLED FROM WEST TO EAST TO CLEAR THE PROPOSED REGULATOR SITE.	⊑
	CONTINGENCIES & COMMENTS:		Н. ф
PROJECT ID: <u>WI4134038</u> IO #: <u>MEL21300301</u>	DIGGERS HOTLINE REQUIRED.	*APPROXIMATE STATION 138+00 TO 140+00 THE LOCATION OF CURVE IN EXISTING RIGHT OF WAY FOR THE OFF RAMP MAY BE INCORRECT. VERIFY THE RIGHT OF	ETC
CGS #:	WE ENERGIES WILL RESTORE	WAY PRIOR TO CONSTRUCTION AND STAKE THE TWO 45 DEGREE ELBOW TO	S S
TYPE OF WORK:	WE ENERGIES WILL NOT HAUL SPOIL	INSURE THAT THEY ARE IN ROAD RIGHT OF WAY. THIS MAY CHANGE THE LOCATION OF THE 2 - 45 DEGREE ELBOWS TO AVOID PRIVATE PROPERTY.	4038
GDAM MAIN REPLACEMENT MAIN EXTENSION	CUSTOMER IS REQUIRED TO LOCATE ALL		413
PAVING RELOCATION SERVICE	PRIVATE UNDERGROUND FACILITIES PRIOR	*THIS AREA RECTIFIED PROTECTED. CONTACT TODD LENSMEYER AT 920-428-4493 THREE DAYS PRIOR TO THE TIE INS TO TURN OFF RECTIFIER R122 (LOCATED AT	038
OTHER	TO INSTALLATION.	E NORTHLAND AVE, EAST TIE IN) AND R115 (LOCATED AT W GREENVILLE/SILVER	4134
STAKING REQUIREMENTS: MAIN / SERVICE IN EASEMENT:	WE ENERGIES IS NOT RESPONSIBLE FOR	SPRING DR, WEST TIE IN).	\666
SURVEYOR STAKED	ROOT DAMAGE	*HOT WRAP OR EPOXY MUST BE USED FOR ALL HP COATING REPAIRS.	11398
	· -	*CONTACT TODD LENSMEYER TO PERFORM BORE TESTS ON ALL BORED PIPE.	-
CORROSION CONTACT: JOHN HOOPER PHONE #: 414-221-4871		*XRAY 100% OF THE WELDS FOR THE PROPOSED 6" AND 12" STEEL MAIN.	0000
RESTORE PRIVATE PROPERTY: X WE ENERGIES CUSTOMER			412(
RAILROAD PERMITTING/FLAGGING REQUIRED XYES NO		T 6 T 7 T 17 T 10 SHEET SHEET	Δ Σ
RR NAME CANADIAN NATIONAL  MAIN SIZE, MAT'L, FT INSTALL METHOD & FOOTAGE		ET 6 ET 7 ET 10 SHEE SHEE	@ F\
6" STEEL 10,993' BORE 10932' TRENCH 61'	SHEE.	· 후 · 불 · 통 : ' 보 · ! · · · · · · · · · · · · · · · · ·	cts
12" STEEL 20' TRENCH 20'	S - S - S		roje
		W NORTH AND AVE CTH OO	jor F
		STH 15 W. NORTHLAND AVE CTH 00	Σ
	STH 15		аПе
		THE STATE OF THE S	> ×
RELATED WR's	SHEET 2	0 Q	t/Fo
MAIN RETIREMENT WR NA FOOTAGE NA			emer
SERVICE REPLACEMENT WR NA NO. NA	Ų WŽ.	HATCH AREA MARKS	nag
SERVICE RECONNECT WR <u>4254604</u> NO. <u>2</u>	ż ő	HATCH AREA MARKS WETLAND AREAS WETLAND AREAS	Σ
	GREE		Work
	EENVILLE		a \ @
	GREENVILLE DR.		Dat
EROSION CONTROL NOTES			
	HALL BE PERMANENT SEED AND PROPERLY ANCHORED MULCH, UNL TABILIZATION SHALL BE SOIL STABILIZER, TYPE A, UNLESS NOTED.	D.   S   REV.   BY DATE	E
FINAL STABILIZATION IS REQUIRED IN SPRING.  IF DISTURBANCE OCCURS WITHIN THE SLOPE INTERCEPT. FINAL	AL STABILIZATION SHALL BE SOIL STABILIZER, TYPE A. UNLESS NOTE	0 DESIGN APPROVED FOR CONSTRUCTION DF 01/28/	/19
IF DISTURBANCE OCCURS OUTSIDE THE SLOPE INTERCEPT, F	INAL STABILIZATION SHALL BE PERMANENT SEED AND PROPERLY		
ANCHORED MULCH, UNLESS NOTED.  IF DISTURBANCE OCCURS IN AGRICULTURAL FIELDS, SOIL SEG	REGATION WILL NEED TO TAKE PLACE TO RETURN FIELDS TO PRE-		
CONSTRUCTION SOIL STRATIFICATION AND TO PRE-CONSTRU	ICTION ELEVATIONS. S, CONSIDER USING PLATES/MATS IN WETLANDS OR CROSSING DITC	4	
STOCKPILE MATERIALS SHALL BE PLACED UPSLOPE FROM EXC	CAVATION. IF STOCKPILE MATERIALS MUST BE PLACED DOWNSLOPE	DPE OF S	
EXCAVATION, PROTECT STOCKPILES WITH 12" WATTLES.  PROJECT SPECIFIC EROSION CONTROL NOTES:			$\dashv$
		Printed 7/2/2019 3:05:05 PM SHEET 1 OF 30	





































4134038



### N MAYFLOWER DRIVE CROSSING 6" ST - 175' STATION 29+77 SHEET 2

STATION	29+77	29+77	29+77	29+77	29+77	29+77	29+77	29+77
OFFSET	LT 195'	LT 41'	LT 27'	LT 24'	LT 8'	0	RT 19'	RT 30'
TOP OF MAIN ELEVATION	844	844	845	845	846	846	843	842
APPROX DEPTH FROM EXISTING	41	4'	4'	4'	4'	4'	4'	4'
LOCATION	P-CAP	E-FIBER	E-FIBER	E-CLVRT	E-SAN		E-GAS	P-ELL
NOTES	WEST						UNDER	EAST
	END							END

### N MCCARTHY ROAD CROSSING 6" ST - 160' STATION 18+64 SHEET 6

STATION	18+64	18+64	18+64	18+64	18+64	18+64	
OFFSET	LT 102'	LT 44'	LT 26'	0	RT 25'	RT 58'	
TOP OF MAIN ELEVATION	829	829	830	830	829	826	
APPROX DEPTH FROM EXISTING		4'	4'	4'	4'	4'	
LOCATION	P-ELL	E-CURB	E-SAN		E-CURB	EAST	
NOTES	WEST	WEST			EAST	END	
	END						

# CASALOMA DRIVE CROSSING 6" ST - 235' STATION 17+92 CONTINUED SHEET 9

CTATION					
STATION	17+92	17+92			
OFFSET	RT 102'	RT 111'			
TOP OF MAIN ELEVATION	802	802			
APPROX DEPTH FROM EXISTING		4'			
LOCATION	E-FIBER	P-ELL			
NOTES		END			

### CASALOMA DRIVE CROSSING 6" ST - 235' STATION 17+92 SHEET 9

STATION	17+92	17+92	17+92	17+92	17+92	17+92	17+92	17+92
OFFSET	LT 124'	LT 83'	LT 30'	LT 7'	0	RT 28'	RT 32'	RT 64'
TOP OF MAIN ELEVATION	804	807	807	808	807	807	807	806
APPROX DEPTH FROM EXISTING	41	4'	4'	4'	4'	4'	4'	4'
LOCATION	WEST	E-FIBER	E-FIBER	E-SAN	E-ELEC	E-GAS	E-WAT	E-FIBER
NOTES	END							

# NORTHBOUND USH 41 OFF RAMP TO WEST STH 15 CROSSING 6" ST - 175' STATION 133+50 TO 135+25 SHEET 13

• • • • • • • • • • • • • • • • • • • •	• • • • • • • • • • • • • • • • • • • •				• · · • • · ·	- •	
STATION	129+41	129+60	129+80	130+03			
OFFSET	RT 142'	RT 142'	RT 142'	RT 142'			
TOP OF MAIN ELEVATION	801	801	801	801			
APPROX DEPTH FROM EXISTING		7'	7'	4'			
LOCATION	WEST			EAST			
NOTES	DITCH	SHLDER	SHLDER	DITCH			


# NORTHBOUND USH 41 OFF RAMP TO EAST NORTHLAND AVE CROSSING 6" ST - 175' STATION 133+50 TO 135+25 SHEET 14

STATION	133+50	134+00	134+50	135+00	135+25		
OFFSET	RT 138.5	RT 138'	RT 137.5	RT 139'	RT 139'		
TOP OF MAIN ELEVATION		788	788	788			
APPROX DEPTH FROM EXISTING		5'	5'	5'	4'		
LOCATION	WEST				EAST		
NOTES	SHLDER				DITCH		

# BLUEMOUND DR CROSSING 6" ST - 213' STATION 18+91 SHEET 15

STATION	18+91	18+91	18+91	18+91	18+91		
OFFSET	RT 40'	RT 28'	LT 13'	LT 53'	LT 173'		
TOP OF MAIN ELEVATION	783	783	783	783	784		
APPROX DEPTH FROM EXISTING		5'	5'	5'	4'		
LOCATION	P-ELL	HP GAS	E-SAN		P-ELL		
NOTES	EAST			WEST			
	вос			вос			

4134038



Transition Fitting

Test / Locate Point

Type # 4

17# Anode

Grade

Connect all wires with solderless

split bolt connector. Mark wire

direction and material

ANODE) on each wire.

Locate Wire

(N,S,E,W,ST,PE

Maller


Marker Post or

-Anode Wire


Steel Main

Mount Box

Malhi




NOTE: ANODES ARE NOT REQUIRED FOR LOCATE POINTS ON THIS HIGH PRESSURE MAIN PER CORROSION GROUP



BORE PROFILE WEST OF WEST EDGE OF WETLAND TO EAST OF USH 41 NB OFF RAMP APPROXIMATELY 2579' OF 6" STEEL

# **DELINEATED WETLAND**




4134038

BORE PROFILE WEST OF WEST EDGE OF WETLAND TO EAST OF USH 41 NB OFF RAMP APPROXIMATELY 2579' OF 6" STEEL

# NOT TO SCALE

# **DELINEATED WETLAND**




Printed 7/2/2019

**NOT TO SCALE** 

4134038

BORE PROFILE WEST OF WEST EDGE OF WETLAND TO EAST OF USH 41 NB OFF RAMP APPROXIMATELY 2579' OF 6" STEEL

# **DELINEATED WETLAND**





NOT TO SCALE

4134038

BORE PROFILE WEST OF WEST EDGE OF WETLAND TO EAST OF USH 41 NB OFF RAMP APPROXIMATELY 2579' OF 6" STEEL

# **DELINEATED WETLAND**







Printed 7/2/2019

3:05:15 PM

SCALE 1" = NA ' \_\_\_\_\_ SHEET 24 OF 30







SCALE 1" = NA ' \_\_\_\_\_


\_\_ SHEET 26 OF 30

4134038

**Printed** 7/2/2019

3:05:16 PM

BORE PROFILE WEST OF WEST EDGE OF WETLAND TO EAST OF USH 41 NB OFF RAMP APPROXIMATELY 2579' OF 6" STEEL




Printed 7/2/2019

3:05:16 PM


SCALE 1" = NA ' \_\_\_\_\_


\_\_| SHEET 27 OF 30












Typical Cross Section
Utility Crossing (Uncased) Under Railway



### **WE ENERGIES - GAS OPERATIONS**

Unless otherwise noted in this document, the following notes apply:

Existing facilities should be field verified prior to excavation.

Utility information shown are from plans and have not been field verified.

Maintain 12" min vertical clearance at crossing of existing electrical facilities.

Maintain 6" min vertical clearance at crossing of other existing facilities.

Maintain 18" min vertical clearance at crossing of existing storm sewer pipes.

Maintain 5' clearance from storm sewer inlets.

Staking of route or ROW by surveyor required prior to construction.

Clearances shown are min distances - reference permit for specific clearance requirements.

Additional information on excavation, backfilling & clearances can be found in the Gas CRS 201. Restore all pavement, ROW, sidewalks, and customer's private property.

# CONVENTIONAL SYMBOLS



END OF MAIN CAPPED WITH AN ANODE ATTACHED TO THE TRACER WIRE - 2' x 4' EXCAVATION.



VALVE IN AN 8" DIAMETER METALLIC BOX SET TO GRADE



17# ANODE ATTACHED TO THE MAIN IN THE SAME TRENCH



GAS MAIN CUT OFF AND CAPPED 4' x 5' EXCAVATION



METER CHANGE




**TEST & RECONNECT SERVICE** 



REPLACE SERVICE

# **EROSION CONTROL LEGEND**



UNDERGROUND FACILITY EXCAVATION



INLET PROTECTION, TYPE



12" WATTLE or 12"/20" SEDIMENT LOG or 9.5"/20" EROSION EEL



STONE DITCH CHECK



**ROCK BAG** 

MULCH

SOIL STABILIZER, TYPE A



**EROSION MAT CLASS I, TYPE A** 



-|-|-|-|-

**EROSION MAT CLASS I, TYPE B** 



EROSION MAT CLASS I, TYPE B URBAN

EROSION MAT CLASS I, TYPE A URBAN



**EROSION MAT CLASS II** 



**EROSION MAT CLASS III** 

VEGETATIVE BUFFER




TRACKING PAD



TIMBER MAT

SILT FENCE



TEMPORARY SEDIMENT BASIN



SURFACE WATER FLOW

# WE ENERGIES WORK REQUEST ENVIRONMENTAL NOTES (Notes 1 through 7 apply to ALL work requests)

1. If WDNR and/or USACE permits were obtained for the project, all permit conditions shall be met during construction of the project.

### **Erosion Control**

- 2. If soil disturbance occurs on slopes or channels/ditches leading to wetlands or waterways, or within wetlands, the disturbed areas shall be stabilized and appropriate erosion control Best Management Practices (BMP's) shall be implemented.
- 3. Erosion Control BMP's shall meet or exceed the approved WDNR Storm Water Management Technical Standards (http://dnr.wi.gov/topic/stormwater/standards/const standards.html). Refer to We Energies Construction Site Sediment and Erosion Control Standards.
- 4. Inspect installed erosion control BMP's at least one time per week and after ½" rain events: repair as necessary.
- 5. When temporary stabilization is required (e.g. for winter or short-term construction) prior to final restoration, soil stabilizer shall be installed wherever possible. Erosion mat shall be used temporarily only where appropriate, in accordance with state standards, and when approved by the Operations Supervisor.

### **Contaminated Soils**

6. Whenever soil exhibiting obvious signs of contamination (e.g., discoloration, petroleum or solvent odor, free liquids other than water, buried containers or tanks, or other obvious signs of environmental impacts) is encountered during excavation or installation, cease work immediately, take appropriate immediate precautions to ensure worker health and safety, and contact the Operations Supervisor or Inspector.

### Spills

- 7. If an oil spill occurs during construction, call the Environmental Incident Response Team (EIRT) at 414-430-3478:
  - a. Any quantity of oil is spilled into surface water;
  - b. Any oil spill greater than 50 ppm PCB into a sewer, vegetable garden, or grazing land;
  - c. Any oil spill containing greater than 500 ppm PCB;
  - d. Five gallons or more of oil spilled to the ground;
  - e. Any oil spill involving a police department, fire department, DNR, or concerned property owner.

### Notes 8 through 27 apply as noted at specific points within each work request:

### **Dewatering**

8. Dewatering of pits or trenches shall be done in accordance with state standards. Use an approved sediment bag, a straw bale dewatering basin, a combination of both, or equivalent.

### **Wetlands**

- 9. As much as practicable, the majority of the work shall be staged from the public roadways and road shoulders, keeping equipment out of adjacent wetlands.
- 10. All work shall be conducted to minimize soil disturbance. No rutting will be allowed within the wetlands.
- 11. If soils are not frozen or stable to a point that avoids rutting, timber mats, mud tracks, or equivalent shall be utilized to access pole locations.
- 12. Excavated soils cannot be stockpiled in wetlands.

- 13. All excess spoils shall be removed from wetlands and placed in a suitable upland location.
- 14. Trenching and pit excavations within wetlands shall include soil segregation to facilitate restoration of pre-construction soil stratification, and restoration to pre-construction
- 15. Poles scheduled to be removed, and that occur within wetland, shall be cut at the ground surface.

### **Waterways**

- 16. No work can be performed within the banks or below the ordinary high watermark of any navigable waterways/streams.
- 17. No crossing of navigable waterways with equipment can occur. Foot traffic is allowed.
- 18. Any disturbed soil within 75-feet of the ordinary high water mark of any navigable waterways/streams shall be stabilized within 24 hours of construction completion.

### **Threatened and Endangered Species**

- 19. Threatened or endangered species are known to occur in the work area. It is illegal to harass, harm, or kill a protected species under state and federal regulations. Proper precautions shall be taken to ensure harm to individuals is avoided.
- 20. In order to protect the threatened or endangered species, work must be conducted between November 5 and March 15.
- 21. Exclusion fencing must be installed at the work area prior to March 15.
- 22. A qualified biologist must be present when conducting work at this location.

### **Invasive Species**

23. State regulated invasive species are known to occur in the work area. Reasonable precautions are legally required to prevent the spread of these species. The Wisconsin Council on Forestry Transportation and Utility Right-of Way Best Management Practices should be followed: (http://council.wisconsinforestry.org/invasives/transportation/).

### **Cultural and Historical Resources, cont.**

- 24. The project is within or adjacent to an area that is identified by the State of Wisconsin as potentially having Native American artifacts, burial mounds or burial sites, which could be encountered during construction.
- 25. If human bone or any artifacts are discovered during construction, work must cease immediately. Contact the Environmental Department who will contact the State Burial Sites Preservation Office and determine the next steps that must be taken in order to comply with state law. Work at that site MAY NOT PROCEED until the Environmental Department authorizes it.
- 26. A "qualified archaeologist," as specified under Wis. Stats 157.70 (1) (i) and Wis. Admin. Code HS 2.04 (6), must be present to monitor all ground disturbing activities.

### **Frac-out Contingency Plan**

- 27. A frac-out contingency plan shall be on-site and implemented accordingly. The contingency plan shall incorporate the following components.
  - a. Continuously inspect the bore paths for frac-outs in order to respond quickly and appropriately.
  - b. Containment materials (e.g. silt fence, straw bales, sand bags, etc.) shall be on site and available should a frac-out occur.

