

HIGHWAY WORK PROPOSAL

Wisconsin Department of Transportation
DT1502 10/2010 s.66.29(7) Wis. Stats.

Proposal Number:

Ø 1

<u>COUNTY</u>	<u>STATE PROJECT ID</u>	<u>FEDERAL PROJECT ID</u>	<u>PROJECT DESCRIPTION</u>	<u>HIGHWAY</u>
La Crosse	1071-06-65		STH 157 Interchange Bridges B-32-55 & 56 over I-90 at STH 157	IH 90

This proposal, submitted by the undersigned bidder to the Wisconsin Department of Transportation, is in accordance with the advertised request for proposals. The bidder is to furnish and deliver all materials, and to perform all work for the improvement of the designated project in the time specified, in accordance with the appended Proposal Requirements and Conditions.

Proposal Guaranty Required, \$ \$75,000.00 Payable to: Wisconsin Department of Transportation	Attach Proposal Guaranty on back of this PAGE.
Bid Submittal Due Date: April 9, 2013 Time (Local Time): 9:00 AM	Firm Name, Address, City, State, Zip Code
Contract Completion Time October 31, 2013	SAMPLE NOT FOR BIDDING PURPOSES
Assigned Disadvantaged Business Enterprise Goal 0%	This contract is exempt from federal oversight.

This certifies that the undersigned bidder, duly sworn, is an authorized representative of the firm named above; that the bidder has examined and carefully prepared the bid from the plans, Highway Work Proposal, and all addenda, and has checked the same in detail before submitting this proposal or bid; and that the bidder or agents, officer, or employees have not, either directly or indirectly, entered into any agreement, participated in any collusion, or otherwise taken any action in restraint of free competitive bidding in connection with this proposal bid.

Do not sign, notarize, or submit this Highway Work Proposal when submitting an electronic bid on the Internet.

Subscribed and sworn to before me this date _____

(Signature, Notary Public, State of Wisconsin)

(Print or Type Name, Notary Public, State Wisconsin)

(Date Commission Expires)

Notary Seal

(Bidder Signature)

(Print or Type Bidder Name)

(Bidder Title)

For Department Use Only

Type of Work Deck replacement B-32-55, PCC pavement, approach slabs, cross overs, temporary traffic control, guard rail, Type 1 and 2 signing and bridge overlay B-32-56.	Date Guaranty Returned
Notice of Award Dated	

**PLEASE ATTACH
PROPOSAL GUARANTY HERE**

Effective with November 2007 Letting

PROPOSAL REQUIREMENTS AND CONDITIONS

The bidder, signing and submitting this proposal, agrees and declares as a condition thereof, to be bound by the following conditions and requirements.

If the bidder has a corporate relationship with the proposal design engineering company, the bidder declares that it did not obtain any facts, data, or other information related to this proposal from the design engineering company that was not available to all bidders.

The bidder declares that they have carefully examined the site of, and the proposal, plans, specifications and contract forms for the work contemplated, and it is assumed that the bidder has investigated and is satisfied as to the conditions to be encountered, as to the character, quality, and quantities of work to be performed and materials to be furnished, and as to the requirements of the specifications, special provisions and contract. It is mutually agreed that submission of a proposal shall be considered conclusive evidence that the bidder has made such examination.

The bidder submits herewith a proposal guaranty in proper form and amount payable to the party as designated in the advertisement inviting proposals, to be retained by and become the property of the owner of the work in the event the undersigned shall fail to execute the contract and contract bond and return the same to the office of the engineer within fourteen (14) days after having been notified in writing to do so; otherwise to be returned.

The bidder declares that they understand that the estimate of quantities in the attached schedule is approximate only and that the attached quantities may be greater or less in accordance with the specifications.

The bidder agrees to perform the said work, for and in consideration of the payment of the amount becoming due on account of work performed, according to the unit prices bid in the following schedule, and to accept such amounts in full payment of said work.

The bidder declares that all of the said work will be performed at their own proper cost and expense, that they will furnish all necessary materials, labor, tools, machinery, apparatus, and other means of construction in the manner provided in the applicable specifications and the approved plans for the work together with all standard and special designs that may be designed on such plans, and the special provisions in the contract of which this proposal will become a part, if and when accepted. The bidder further agrees that the applicable specifications and all plans and working drawings are made a part hereof, as fully and completely as if attached hereto.

The bidder, if awarded the contract, agrees to begin the work not later than ten (10) days after the date of written notification from the engineer to do so, unless otherwise stipulated in the special provisions.

The bidder declares that if they are awarded the contract, they will execute the contract agreement and begin and complete the work within the time named herein, and they will file a good and sufficient surety bond for the amount of the contract for performance and also for the full amount of the contract for payment.

The bidder, if awarded the contract, shall pay all claims as required by Section 779.14, Statutes of Wisconsin, and shall be subject to and discharge all liabilities for injuries pursuant to Chapter 102 of the Statutes of Wisconsin, and all acts amendatory thereto. They shall further be responsible for any damages to property or injury to persons occurring through their own negligence or that of their employees or agents, incident to the performance of work under this contract, pursuant to the Standard Specifications for Road and Bridge Construction applicable to this contract.

In connection with the performance of work under this contract, the contractor agrees to comply with all applicable state and federal statutes relating to non-discrimination in employment. No otherwise qualified person shall be excluded from employment or otherwise be subject to discrimination in employment in any manner on the basis of age, race, religion, color, gender, national origin or ancestry, disability, arrest or conviction record (in keeping with s.111.32), sexual orientation, marital status, membership in the military reserve, honesty testing, genetic testing, and outside use of lawful products. This provision shall include, but not be limited to the following: employment, upgrading, demotion or transfer; recruitment or recruitment advertising; layoff or termination; rates of pay or other forms of compensation, and selection for training, including apprenticeship. The contractor further agrees to ensure equal opportunity in employment to all applicants and employees and to take affirmative action to attain a representative workforce.

The contractor agrees to post notices and posters setting forth the provisions of the nondiscrimination clause, in a conspicuous and easily accessible place, available for employees and applicants for employment.

If a state public official (section 19.42, Stats.) or an organization in which a state public official holds at least a 10% interest is a party to this agreement, this contract is voidable by the state unless appropriate disclosure is made to the State of Wisconsin Ethics Board.

BID PREPARATION

Preparing the Proposal Schedule of Items

A General

- (1) Obtain bidding proposals as specified in **section 102** of the standard specifications prior to 11:45 AM of the last business day preceding the letting. Submit bidding proposals using one of the following methods:
 1. Electronic bid on the internet.
 2. Electronic bid on a printout with accompanying diskette or CD ROM.
 3. Paper bid under a waiver of the electronic submittal requirements.
- (2) Bids submitted on a printout with accompanying diskette or CD ROM or paper bids submitted under a waiver of the electronic submittal requirements govern over bids submitted on the internet.
- (3) The department will provide bidding information through the department's web site at <http://www.dot.wisconsin.gov/business/engrserv/bid-letting-information.htm>. The contractor is responsible for reviewing this web site for general notices as well as information regarding proposals in each letting. The department will also post special notices of all addenda to each proposal through this web site no later than 4:00 P.M. local time on the Thursday before the letting. Check the department's web site after 5:00 P.M. local time on the Thursday before the letting to ensure all addenda have been accounted for before preparing the bid. When bidding using methods 1 and 2 above, check the Bid Express™ on-line bidding exchange at <http://www.bidx.com/> after 5:00 P.M. local time on the Thursday before the letting to ensure that the latest schedule of items Expedite file (*.ebs or *.00x) is used to submit the final bid.
- (4) Interested parties can subscribe to the Bid Express™ on-line bidding exchange by following the instructions provided at the www.bidx.com web site or by contacting:

Info Tech Inc.
5700 SW 34th Street, Suite 1235
Gainesville, FL 32608-5371
email: <mailto:customer.support@bidx.com>

- (5) The department will address equipment and process failures, if the bidder can demonstrate that those failures were beyond their control.
- (6) Contractors are responsible for checking on the issuance of addenda and for obtaining the addenda. Notice of issuance of addenda is posted on the department's web site at <http://www.dot.wisconsin.gov/business/engrserv/bid-letting-information.htm> or by calling the department at (608) 266-1631. Addenda can ONLY be obtained from the departments web site listed above or by picking up the addenda at the Bureau of Highway Construction, Room 601, 4802 Sheboygan Avenue, Madison, WI, during regular business hours.

B Submitting Electronic Bids

B.1 On the Internet

- (1) Do the following before submitting the bid:
 1. Have a properly executed annual bid bond on file with the department.
 2. Have a digital ID on file with and enabled by Info Tech Inc. Using this digital ID will constitute the bidder's signature for proper execution of the bidding proposal.
- (2) In lieu of preparing, delivering, and submitting the proposal as specified in **102.6** and **102.9** of the standard specifications, submit the proposal on the internet as follows:

1. Download the latest schedule of items reflecting all addenda from the Bid Express™ web site.
 2. Use Expedite™ software to enter a unit price for every item in the schedule of items.
 3. Submit the bid according to the requirements of Expedite™ software and the Bid Express™ web site. Do not submit a bid on a printout with accompanying diskette or CD ROM or a paper bid. If the bidder does submit a bid on a printout with accompanying diskette or a paper bid in addition to the internet submittal, the department will disregard the internet bid.
 4. Submit the bid before the hour and date the Notice to Contractors designates.
 5. Do not sign, notarize, and return the bidding proposal described in 102.2 of the standard specifications.
- (3) The department will not consider the bid accepted until the hour and date the Notice to Contractors designates.

B.2 On a Printout with Accompanying Diskette or CD ROM

- (1) Download the latest schedule of items from the Wisconsin pages of the Bid Express™ web site reflecting the latest addenda posted on the department's web site at <http://www.dot.wisconsin.gov/business/engrserve/bid-letting-information.htm>. Use Expedite™ software to prepare and print the schedule of items. Provide a valid amount for all price fields. Follow instructions and review the help screens provided on the Bid Express™ web site to assure that the schedule of items is prepared properly.
- (2) Staple an 8 1/2 by 11 inch printout of the Expedite™ generated schedule of items to the other proposal documents submitted to the department as a part of the bidder's sealed bid. As a separate submittal not in the sealed bid envelop but due at the same time and place as the sealed bid, also provide the Expedite™ generated schedule of items on a 3 1/2 inch computer diskette or CD ROM. Label each diskette or CD ROM with the bidder's name, the 4 character department-assigned bidder identification code from the top of the bidding proposal, and a list of the proposal numbers included on that diskette or CD ROM as indicated in the following example:

Bidder Name

BN00

Proposals: 1, 12, 14, & 22

- (3) If bidding on more than one proposal in the letting, the bidder may include all proposals for that letting on one diskette or CD ROM. Include only submitted proposals with no incomplete or other files on the diskette or CD ROM.
- (4) The bidder-submitted printout of the Expedite™ generated schedule of items is the governing contract document and must conform to the requirements of section 102 of the standard specifications. If a printout needs to be altered, cross out the printed information with ink or typewriter and enter the new information and initial it in ink. If there is a discrepancy between the printout and the diskette or CD ROM, the department will analyze the bid using the printout information.
- (5) In addition to the reasons specified in section 102 of the standard specifications, proposals are irregular and the department may reject them for one or more of the following:
 1. The check code printed on the bottom of the printout of the Expedite™ generated schedule of items is not the same on each page.
 2. The check code printed on the printout of the Expedite™ generated schedule of items is not the same as the check code for that proposal provided on the diskette or CD ROM.

3. The diskette or CD ROM is not submitted at the time and place the department designates.

C Waiver of Electronic Submittal

- (1) The bidder may request a waiver of the electronic submittal requirements. Submit a written request for a waiver in lieu of bids submitted on the internet or on a printout with accompanying diskette or CD ROM. Use the waiver that was included with the paper bid document sent to the bidder or type up a waiver on the bidder's letterhead. The department will waive the electronic submittal requirements for a bidding entity (individual, partnership, joint venture, corporation, or limited liability company) for up to 4 individual proposals in a calendar year. The department may allow additional waivers for equipment malfunctions.
- (2) Submit a schedule of items on paper conforming to [section 102](#) of the standard specifications. The department charges the bidder a \$75 administrative fee per proposal, payable at the time and place the department designates for receiving bids, to cover the costs of data entry. The department will accept a check or money order payable to: "Wisconsin, Dept. of Transportation."
- (3) In addition to the reasons specified in [section 102](#) of the standard specifications, proposals are irregular and the department may reject them for one or more of the following:
 1. The bidder fails to provide the written request for waiver of the electronic submittal requirements.
 2. The bidder fails to pay the \$75 administrative fee before the time the department designates for the opening of bids unless the bidder requests on the waiver that they be billed for the \$75.
 3. The bidder exceeds 4 waivers of electronic submittal requirements within a calendar year.
- (4) In addition to the reasons specified in [section 102](#) of the standard specifications, the department may refuse to issue bidding proposals for future contracts to a bidding entity that owes the department administrative fees for a waiver of electronic submittal requirements.

PROPOSAL BID BOND

DT1303 1/2006

Wisconsin Department of Transportation

Proposal Number	Project Number	Letting Date
Name of Principal		
Name of Surety	State in Which Surety is Organized	

We, the above-named Principal and the above-named Surety, are held and firmly bound unto the State of Wisconsin in the sum equal to the Proposal Guaranty for the total bid submitted for the payment to be made; we jointly and severally bind ourselves, our heirs, executors, administrators, successors and assigns. The condition of this obligation is that the Principal has submitted a bid proposal to the State of Wisconsin acting through the Department of Transportation for the improvement designated by the Proposal Number and Letting Date indicated above.

If the Principal is awarded the contract and, within the time and manner required by law after the prescribed forms are presented for signature, enters into a written contract in accordance with the bid, and files the bond with the Department of Transportation to guarantee faithful performance and payment for labor and materials, as required by law, or if the Department of Transportation shall reject all bids for the work described, then this obligation shall be null and void; otherwise, it shall be and remain in full force and effect. In the event of failure of the Principal to enter into the contract or give the specified bond, the Principal shall pay to the Department of Transportation **within 10 business days of demand** a total equal to the Proposal Guaranty as liquidated damages; the liability of the Surety continues for the full amount of the obligation as stated until the obligation is paid in full.

The Surety, for value received, agrees that the obligations of it and its bond shall not be impaired or affected by any extension of time within which the Department of Transportation may accept the bid; and the Surety does waive notice of any such extension.

IN WITNESS, the Principal and Surety have agreed and have signed by their proper officers and have caused their corporate seals to be affixed this date: **(DATE MUST BE ENTERED)**

PRINCIPAL

(Company Name) **(Affix Corporate Seal)**

(Signature and Title)

(Company Name)

(Signature and Title)

(Company Name)

(Signature and Title)

(Company Name)

(Signature and Title)

NOTARY FOR PRINCIPAL

(Date)

State of Wisconsin)
) ss.
_____ County)

On the above date, this instrument was acknowledged before me by the named person(s).

(Signature, Notary Public, State of Wisconsin)

(Print or Type Name, Notary Public, State of Wisconsin)

(Date Commission Expires)

Notary Seal

(Name of Surety) **(Affix Seal)**

(Signature of Attorney-in-Fact)

NOTARY FOR SURETY

(Date)

State of Wisconsin)
) ss.
_____ County)

On the above date, this instrument was acknowledged before me by the named person(s).

(Signature, Notary Public, State of Wisconsin)

(Print or Type Name, Notary Public, State of Wisconsin)

(Date Commission Expires)

Notary Seal

IMPORTANT: A certified copy of Power of Attorney of the signatory agent must be attached to the bid bond.

CERTIFICATE OF ANNUAL BID BOND

DT1305 8/2003

Wisconsin Department of Transportation

Time Period Valid (From/To)	
Name of Surety	
Name of Contractor	
Certificate Holder	Wisconsin Department of Transportation

This is to certify that an annual bid bond issued by the above-named Surety is currently on file with the Wisconsin Department of Transportation.

This certificate is issued as a matter of information and conveys no rights upon the certificate holder and does not amend, extend or alter the coverage of the annual bid bond.

Cancellation: Should the above policy be cancelled before the expiration date, the issuing surety will give thirty (30) days written notice to the certificate holder indicated above.

(Signature of Authorized Contractor Representative)

(Date)

FEBRUARY 1999

LIST OF SUBCONTRACTORS

Section 66.29(7), Wisconsin Statutes, provides that a bidder, as a part of his proposal, shall submit a list of the subcontractors he proposes to contract with and the class of work to be performed by each, provided that to qualify for such listing each subcontractor must first submit his bid in writing to the general contractor at least 48 hours prior to the time of bid closing. It further provides that a proposal of a bidder shall not be invalid if any subcontractor, and the class of work to be performed by such subcontractor, has been omitted from a proposal.

No subcontract, whether listed herein or later proposed, may be entered into without the written consent of the Engineer as provided in Subsection 108.1 of the Standard Specifications.

Name of Subcontractor	Class of Work	Estimated Value
_____	_____	_____
_____	_____	_____
_____	_____	_____
_____	_____	_____
_____	_____	_____
_____	_____	_____
_____	_____	_____

DECEMBER 2000

**CERTIFICATION REGARDING DEBARMENT, SUSPENSION, AND OTHER
RESPONSIBILITY MATTERS - PRIMARY COVERED TRANSACTIONS**

Instructions for Certification

1. By signing and submitting this proposal, the prospective contractor is providing the certification set out below.
2. The inability of a person to provide the certification required below will not necessarily result in denial of participation in this covered transaction. The prospective contractor shall submit an explanation of why it cannot provide the certification set out below. The certification or explanation will be considered in connection with the department or agency's determination whether to enter into this transaction. However, failure of the prospective contractor to furnish a certification or an explanation shall disqualify such person from participation in this transaction.
3. The certification in this clause is a material representation of fact upon which reliance was placed when the department determined to enter into this transaction. If it is later determined that the contractor knowingly rendered an erroneous certification in addition to other remedies available to the Federal Government the department may terminate this transaction for cause or default.
4. The prospective contractor shall provide immediate written notice to the department to whom this proposal is submitted if at any time the prospective contractor learns that its certification was erroneous when submitted or has become erroneous by reason of changed circumstances.
5. The terms "covered transaction," "debarred," "suspended," "ineligible," "lower tier covered transaction," "participant," "person," "primary covered transaction," "principal," "proposal," and "voluntarily excluded," as used in this clause, have the meanings set out in the Definitions and Coverage sections of the rules implementing Executive Order 12549. You may contact the department to which this proposal is being submitted for assistance in obtaining a copy of those regulations.
6. The prospective contractor agrees by submitting this proposal that, should this contract be entered into, it shall not knowingly enter into any lower tier covered transaction with a person who is debarred, suspended, declared ineligible, or voluntarily excluded from participation in this covered transaction, unless authorized by the department entering into this transaction.
7. The prospective contractor further agrees by submitting this proposal that it will include the clause titled "Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion-Lower Tier Covered Transaction," which is included as an addendum to PR-1273 - "Required Contract Provisions Federal Aid Construction Contracts," without

modification, in all lower tier covered transactions and in all solicitations for lower tier covered transactions.

8. The contractor may rely upon a certification of a prospective subcontractor/materials supplier that it is not debarred, suspended, ineligible, or voluntarily excluded from the covered transaction, unless it knows that the certification is erroneous. A contractor may decide the method and frequency by which it determines the eligibility of its principals. Each contractor may, but is not required to, check the Disapproval List (telephone # 608/266/1631).
9. Nothing contained in the foregoing shall be construed to require establishment of a system of records in order to render in good faith the certification required by this clause. The knowledge and information of a contractor is not required to exceed that which is normally possessed by a prudent person in the ordinary course of business dealings.
10. Except for transactions authorized under paragraph 6 of these instructions, if a contractor in a covered transaction knowingly enters into a lower tier covered transaction with a person who is suspended, debarred, ineligible or voluntarily excluded from participation in this transaction, in addition to other remedies available to the Federal Government, the department may terminate this transaction for cause or default.

Certification Regarding Debarment, Suspension, and Other Responsibility Matters - Primary Covered Transactions

- (1) The prospective contractor certifies to the best of its knowledge and belief, that it and its principals:
 - (a) Are not presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from covered transactions by any Federal department or agency;
 - (b) Have not within a three-year period preceding this proposal been convicted of or had a civil judgment rendered against them for commission of fraud or a criminal offense in connection with obtaining, attempting to obtain, or performing a public (Federal, State or local) transaction or contract under a public transaction; violation of Federal or State antitrust statutes or commission of embezzlement, theft, forgery, bribery, falsification or destruction of records, making false statements or receiving stolen property;
 - (c) Are not presently indicted for or otherwise criminally or civilly charged by a governmental entity (Federal, State or local) with commission of any of the offense enumerated in paragraph (1)(b) of this certification; and
 - (d) Have not within a three-year period preceding this proposal had one or more public transactions (Federal, State or local) terminated for cause or default.
- (2) Where the prospective contractor is unable to certify to any of the statements in this certification, such prospective contractor shall attach an explanation to this proposal.

Special Provisions

Table of Contents

Article	Description	Page #
1.	General.....	2
2.	Scope of Work.	2
3.	Prosecution and Progress.	2
4.	Traffic.	3
5.	Holiday Work Restrictions.	5
6.	Utilities.....	5
7.	Notice to Contractor, Notification of Demolition and/or Renovation No Asbestos Found.	6
8.	Debris Containment Structure B-32-0055, Item 203.0225.S.01; Debris Containment Structure B-32-0056, Item 203.0225.S.02.	7
9.	Select Borrow.....	8
10.	QMP Base Aggregate.	8
11.	Base Aggregate Dense, ¾ Inch.	16
12.	Base Aggregate Dense 1¼-Inch.....	16
13.	Rout and Seal, Item 415.6000.S.....	17
14.	Concrete Pavement Partial Depth Repair Joint Repair, Item 416.0750.S; Crack Repair, Item 416.0752.S.	19
15.	Expansion Device, Structure B-32-0055; Expansion Device, Structure B-32-0056.	25
16.	Bearing Replacement B-32-0055, Item 506.7000.S.01.	26
17.	Epoxy Crack Sealing, Item 509.9020.S.....	27
18.	Structure Repainting General.....	28
19.	Structure Overcoating Cleaning and Priming B-32-0055, Item 517.3000.S.01; Structure Overcoating Cleaning and Priming B-32-56, Item 517.3000.S.02.	29
20.	Preparation and Coating of Top Flanges B-32-0055, Item 517.0900.S.01.....	30
21.	Containment and Collection of Waste Materials B-32-0055, Item 517.4000.S.01; Containment and Collection of Waste Materials B-32-0056, Item 517.4000.S.02.	32
22.	Slope Paving Repair Crushed Aggregate, Item 604.9010.S.	33
23.	Reseal Crushed Aggregate Slope Paving, Item 604.9015.S.	33
24.	Traffic Control.	34
25.	Pavement Marking Wet Reflective Tape 4-Inch, Item 646.0871.S; 8-Inch, Item 646.0873.S.	34
26.	Inlet Repair, SPV.0060.01.	35
27.	Weld Inspection Structure B-32-55, Item SPV.0105.01.....	36
28.	Pigmented Concrete Surface Treatment, SPV.0180.01.....	38

SPECIAL PROVISIONS

1. General.

Perform the work under this construction contract for project 1071-06-65 STH 157 Interchange Bridge B-32-0055 and 0056 over IH 90 at STH 157, in La Crosse County, Wisconsin as the plans show and execute the work as specified in the State of Wisconsin, Department of Transportation, Standard Specifications for Highway and Structure Construction, 2013 Edition, as published by the department, and these special provisions.

If all or a portion of the plans and special provisions are developed in the SI metric system and the schedule of prices is developed in the US standard measure system, the department will pay for the work as bid in the US standard system.

100-005 (20120615)

2. Scope of Work.

The work under this contract shall consist of bridge re-deck B-32-0055, bridge overlay B-32-0056 approach slabs, approach roadways, concrete pavement, crossovers, temporary traffic control, detour, beamguard, Type 1&2 sign replacement, and all incidental items necessary to complete the work as shown on the plans and included in the proposal and contract.

104-005 (20090901)

3. Prosecution and Progress.

Begin work within ten calendar days after the engineer issues a written notice to do so.

Provide the start date to the engineer in writing within a month after executing the contract but at least 14 calendar days before the preconstruction conference. Upon approval, the engineer will issue the notice to proceed within ten calendar days before the approved start date.

To revise the start date, submit a written request to the engineer at least two weeks before the intended start date. The engineer will approve or deny that request based on the conditions cited in the request and its effect on the department's scheduled resources.

The schedule of operations as required under standard spec 108.9.2 shall provide for:

- Site preparation
- Construction of crossovers and shoulders
- B-32-0055 re-deck with accompanied approach slabs, and concrete pavement
- B-32-0056 overlay with accompanied approach slabs, and concrete pavement
- Removals of the two cross overs
- Restoration of existing pavement markings

The project cannot start prior to May 28, 2013 due to construction activities on STH 16 between STH 157 and South Kinney Coulee Road. This segment is proposed as a detour route during bridge construction activities on STH 157. Prior to beginning operations under this contract, submit in writing the proposed schedule of operations to the engineer for approval.

Construction of temporary widening and ramp crossovers along westbound IH-90. Construction activities will impact westbound and eastbound IH-90 traffic and are anticipated to take place fall 2013 under construction ID 1071-06-80.

Complete all construction operations and reopen on STH 157 interchange to through traffic prior to 12:01 AM November 1, 2013.

Supplement standard spec 108.11 as follows:

If the contractor fails to complete all construction operations and reopen STH 157 interchange to through traffic prior to 12:01 AM November 1, 2013, the department will assess the contractor \$5,000 in liquidated damages for each calendar day that the roadway remains closed after 12:01 AM, November 1, 2013. An entire calendar day will be charged for any period of time within a calendar day that the road remains closed beyond 12:01 AM.

4. Traffic.

Perform work in such a manner to ensure emergency vehicles and pedestrian access to adjacent residences and business at all times.

Work includes re-decking Structure B-32-55 (STH 157 southbound), concrete overlay on Structure B-32-56 (STH 157 northbound) along with concrete pavement approaches at both structures. Beamguard upgrade and Type 1&2 sign replacement are also proposed. This work is planned to be accomplished in 5 stages.

Stage 1 - Shoulder Widening and Temporary Crossover Construction:

STH 157 traffic on both Northbound and Southbound will be reduced from the current three 12-foot lanes (2 through lanes and 1 auxiliary lane) to two 12-foot lanes to allow for construction of crossovers and shoulder widening.

Shift the two lanes of northbound STH 157 traffic to the right to accommodate closing the inner lane to provide a work zone area. Traffic will be using the middle and auxiliary lane. Removal of the pavement marking within the lane shift area and placement of temporary pavement marking will occur.

Shift the two lanes of southbound STH 157 traffic to the right to accommodate closing the inner lane to provide a work zone area. Traffic will be using the middle and auxiliary lane. Removal of the pavement marking within the lane shift area and placement of temporary pavement marking will occur.

There will be no traffic restrictions on I-90 during this stage.

Stage 2 - STH 157 Southbound Bridge Closure:

Southbound STH 157 will be closed to traffic at the I-90 bridge (B-32-55). Southbound traffic will be reduced to two 11-foot lanes and shifted onto the northbound road through the temporary crossovers between the eastbound and westbound ramps and then on the two 11-foot lanes on the northbound structure. They will then cross back to the southbound roadway using the temporary crossover south of the bridges. Northbound STH 157 traffic will be shifted to the right to utilize the two 11-foot traffic lanes across the northbound structure.

Both eastbound and westbound I-90 traffic will be reduced to one 12-foot minimal lane when passing under the structures. The eastbound lane closure will begin after the Eastbound off ramp to STH 157. The westbound lane closure will begin before the westbound off ramp to STH 157. There will be lane shifts to accommodate bridge construction activities from occurring directly overhead of the travelling public.

Both the eastbound on-ramp from southbound STH 157 traffic and westbound on-ramp from northbound STH 157 traffic will be closed during this stage to prevent potential conflicts on I-90 during the lane closures.

Stage 3 - STH 157 Northbound Bridge Closure:

Northbound STH 157 will be closed to traffic at the I-90 bridge (B-32-56). Northbound traffic will be reduced to two 11-foot lanes and shifted onto the southbound road through the temporary crossovers between the eastbound and westbound ramps and then on the two 11-foot lanes on the southbound structure. They will then cross back to the northbound roadway using the temporary crossover north of the bridges. Southbound STH 157 traffic will be shifted to the right to utilize the two 11-foot traffic lanes across the southbound structure.

There will be no traffic restrictions on I-90 during this stage.

No ramp closures needed during this stage.

Stage 4 - Temporary Crossover Removal:

Shift the two lanes of northbound STH 157 traffic to the right to accommodate closing the inner lane to provide a work zone area for crossover removal and restoration of disturbed areas. Traffic will be using the middle and auxiliary lane.

Shift the two lanes of southbound STH 157 traffic to the right to accommodate closing the inner lane to provide a work zone area for crossover removal and restoration of disturbed areas. Traffic will be using the middle and auxiliary lane.

There will be no traffic restrictions on I-90 during this stage.

Stage 5 - Type 1 Sign Replacement

This stage could occur before or after the other 4 stages. Work is restricted to off-peak hours and would involve short term single lane closures on STH 157. Work is restricted to the following times of the day: Between 8:30 AM to 3:00 PM and 7:00 PM to 6:00 AM

There will be no traffic restrictions on I-90 during this stage.

5. Holiday Work Restrictions.

Do not perform work on, nor haul materials of any kind along or across any portion of the highway carrying STH 157 traffic, and entirely clear the traveled way and shoulders of such portions of the highway of equipment, barricades, signs, lights, and any other material that might impede the free flow of traffic during the following holiday periods:

- From noon Wednesday, July 3, 2013 to 6:00 AM Monday July 8, 2013 for Independence Day;
- From noon Friday, August 30, 2013 to 6:00 AM Tuesday, September 3, 2013 for Labor Day;
- From 6:00 AM Friday, September 27, 2013 to 6:00 AM Monday, September 30, 2013 for Oktoberfest.

107-005 (20050502)

6. Utilities.

This contract comes under the provisions of Administrative Rule Trans 220.

107-065 (20080501)

Wisconsin Department of Transportation to replace existing interconnect cable during construction located in Structure B-32-0055. Existing cable will be removed by the department in advance of construction and replaced during construction. Contractor shall protect existing conduits as shown on the plans. Contact for the department Interconnect Facility is: Andy Winga, (608) 785-9061. Contractor is required to contact effected utilities 5 day prior.

7. Notice to Contractor, Notification of Demolition and/or Renovation No Asbestos Found.

John Roelke, License Number All-119523, inspected Structure B-32-0055 and 0056 for asbestos on February 22, 2012. No regulated Asbestos Containing Material (RACM) was found on this structure. A copy of the inspection report is available from: Anthony Vador Wielen at (608) 789-7878.

In accordance to NR447 and DHS159, ensure that DNR or DHS receives a completed Notification of Demolition and/or Renovation (DNR Form 4500-113 (R 4/11), or subsequent revision) via U.S. mail, hand-delivery, or using the online notification system at least 10 working days prior to beginning any construction or demolition. Pay all associated fees. Provide a copy of the completed 4500-113 form to Anthony Vador Wielen at 3550 Mormon Coulee Rd, La Crosse WI 54601 and DOT BTS-ESS attn: Hazardous Materials Specialist PO Box 7965, Madison, WI 53707-7965. In addition, comply with all local or municipal asbestos requirements.

Use the following information to complete WisDNR form 4500-113:

- Site Name: Structure B-32-0055, STH 157 over I-90 over I-90 at STH 157
- Site Address: Latitude 43°52'27"; Longitude 91°12'36"; Section 10; Town 16N; Range 7W; Town of Medary.
- Ownership Information: WisDOT Transportation Southwest Region
- Contact: Jennifer Fredrickson
- Phone: (608) 785-9945
- Age: 46 years old. This structure was constructed in 1967.
- Area: 12,347 SF of deck

- Site Name: Structure B-32-0056, STH 157 over I-90 over I-90 at STH 157
- Site Address: Latitude 43°52'26"; Longitude 91°12'34"; Section 10; Town 16N; Range 7W; City of Onalaska.
- Ownership Information: WisDOT Transportation Southwest Region
- Contact: Jennifer Fredrickson
- Phone: (608) 785-9945
- Age: 29 years. This structure was constructed in 1984.
- Area: 12,446 SF of deck

Insert the following paragraph in Section 6.g.:

- If asbestos not previously identified is found or previously non-friable asbestos becomes crumbled, pulverized, or reduced to a powder, stop work immediately, notify the engineer, and the engineer will notify the department's Bureau of Technical Services at (608) 266-1476 for an emergency response in accordance to standard spec 107.24. Keep material wet until it is abated or until it is determined to be non-asbestos containing material.

107-125 (20120615)

8. Debris Containment Structure B-32-0055, Item 203.0225.S.01; Debris Containment Structure B-32-0056, Item 203.0225.S.02.

A Description

This special provision describes providing a containment system to prevent debris from structure removal, reconstruction, or other construction operations from falling onto facilities located under the structure. Using this containment system does not relieve the contractor of requirements under standard spec 107.17 and standard spec 107.19 or requirements under a US Army Corps of Engineers Section 404 Permit.

B (Vacant)

C Construction

Prior to starting work, submit a debris containment plan to the engineer for review. Incorporate engineer-requested modifications. Do not start work over Interstate Highway 90 until the engineer approves the debris containment plan.

Maintain adequate protection throughout construction for people and property within the potential fall zone. Ensure that a containment system capable of protecting underlying facilities from falling construction debris is in place before beginning deck repair, parapet removal, or other operations that may generate debris.

At least 15 working days before conducting potential debris generating operations, contact the following owners or lessees:

1. Anthony VanderWielen (608) 789-7878

D Measurement

The department will measure Debris Containment Structure B-32-0055 and Debris Containment Structure B-32-0056 as a single lump sum unit of work for each structure, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
203.0225.S.01	Debris Containment Structure B-32-0055	LS
203.0225.S.01	Debris Containment Structure B-32-0056	LS

Payment is full compensation for furnishing, installing, maintaining, and removing a debris containment system.

203-010 (20080902)

9. Select Borrow.

Conform to the requirements of standard spec 208 and as hereinafter provided.

Material

Furnish and use material that consists of granular material meeting the following requirements: The maximum aggregate size is 6-inch and the maximum P200 is 15 percent.

208-005 (20031103)

10. QMP Base Aggregate.

A Description

A.1 General

- (1) This special provision describes contractor quality control (QC) sampling and testing for base aggregates, documenting those test results, and documenting related production and placement process changes. This special provision also describes department quality verification (QV), independent assurance (IA), and dispute resolution.
- (2) Conform to standard spec 301, standard spec 305, and standard spec 310 as modified here in this special provision. Apply this special provision to material placed under all of the Base Aggregate Dense and Base Aggregate Open Graded bid items, except do not apply this special provision to material classified as reclaimed asphaltic pavement placed under the Base Aggregate Dense bid items.
- (3) Do not apply this special provision to material placed under the Aggregate Detours, Salvaged Asphaltic Pavement Base, Breaker Run, Select Crushed, Pit Run, Subbase, or Riprap bid items.
- (4) Provide and maintain a quality control program, defined as all activities related to and documentation of the following:
 1. Production and placement control and inspection.
 2. Material sampling and testing.
- (5) Chapter 8 of the department's construction and materials manual (CMM) provides additional detailed guidance for QMP work and describes required sampling and testing procedures. The contractor may obtain the CMM from the department's web site at:

<http://roadwaystandards.dot.wi.gov/standards/cmm/index.htm>

A.2 Contractor Testing for Small Quantities

- (1) The department defines a small quantity, for each individual Base Aggregate bid item, as a plan quantity of 9000 tons or less of material as shown in the schedule of items under that bid item.
- (2) The requirements under this special provision apply equally to a small quantity for an individual bid item except as follows:
 1. The contractor need not submit a full quality control plan but shall provide an organizational chart to the engineer including names, telephone numbers, and current certifications of all persons involved in the quality control program for material under affected bid items.
 2. Divide the aggregate into uniformly sized sublots for testing as follows:

Plan Quantity	Minimum Required Testing
≤ 1500 tons	One test from production, load-out, or placement at the contractor's option ^[1]
> 1500 tons and ≤ 6000 tons	Two tests of the same type, either from production, load-out, or placement at the contractor's option ^[1]
> 6000 tons and ≤ 9000 tons	Three placement tests ^{[2][3]}

- ^[1] If using production tests for acceptance, submit test results to the engineer for review prior to incorporating the material into the work. Production test results are valid for a period of 3 years.
 - ^[2] For 3-inch material, obtain samples at load-out.
 - ^[3] If the actual quantity overruns 9000 tons, create overrun sublots to test at a rate of one additional placement test for each 3000 tons, or fraction of 3000 tons, of overrun.
 3. No control charts are required. Submit aggregate load-out and placement test results to the engineer within one business day of obtaining the sample. Assure that all properties are within the limits specified for each test.
 4. Department verification testing is optional for quantities of 6000 tons or less.
- (3) Material represented by a subplot with any property outside the specification limits is nonconforming. The department may reject material or otherwise determine the final disposition of nonconforming material as specified in standard spec 106.5.

B Materials

B.1 Quality Control Plan

- (1) Submit a comprehensive written quality control plan to the engineer at or before the pre-construction meeting. Do not place base before the engineer reviews and comments on the plan. Construct the project as that plan provides.
- (2) Do not change the quality control plan without the engineer's review. Update the plan with changes as they become effective. Provide a current copy of the plan to the engineer and post in each of the contractor's laboratories as changes are adopted. Ensure that the plan provides the following elements:

1. An organizational chart with names, telephone numbers, current certifications and/or titles, and roles and responsibilities of QC personnel.
2. The process used to disseminate QC information and corrective action efforts to the appropriate persons. Include a list of recipients, the communication means that will be used, and action time frames.
3. A list of source and processing locations, section and quarter descriptions, for all aggregate materials requiring QC testing.
4. Test results for wear, sodium sulfate soundness, freeze/thaw soundness, and plasticity index of all aggregates requiring QC testing. Obtain this information from the region materials unit or from the engineer.
5. Descriptions of stockpiling and hauling methods.
6. Locations of the QC laboratory, retained sample storage, and where control charts and other documentation is posted.
7. An outline for resolving a process control problem. Include responsible personnel, required documentation, and appropriate communication steps.

B.2 Personnel

- (1) Have personnel certified under the department's highway technician certification program (HTCP) perform sampling, testing, and documentation as follows:

Required Certification Level:	Sampling or Testing Roles:
Aggregate Technician IPP Aggregate Sampling Technician Aggregate Assistant Certified Technician (ACT-AGG)	Aggregate Sampling ^[1]
Aggregate Technician IPP Aggregate Assistant Certified Technician (ACT-AGG)	Aggregate Gradation Testing, Aggregate Fractured Particle Testing, Aggregate Liquid Limit and Plasticity Index Testing

^[1] Plant personnel under the direct observation of an aggregate technician certified at level one or higher may operate equipment to obtain samples.

- (2) A certified technician must coordinate and take responsibility for the work an ACT performs. Have a certified technician ensure that all sampling and testing is performed correctly, analyze test results, and post resulting data. No more than one ACT can work under a single certified technician.

B.3 Laboratory

- (1) Perform QC testing at a department-qualified laboratory. Obtain information on the Wisconsin laboratory qualification program from:

Materials Management Section
3502 Kinsman Blvd.
Madison, WI 53704
Telephone: (608) 246-5388

<http://www.dot.state.wi.us/business/engrserv/lab-qualification.htm>

B.4 Quality Control Documentation

B.4.1 General

- (1) Submit base aggregate placement documentation to the engineer within 10 business days after completing base placement. Ensure that the submittal is complete, neatly organized, and includes applicable project records and control charts.

B.4.2 Records

- (1) Document all placement observations, inspection records, and control adjustments daily in a permanent field record. Also include all test results in the project records. Provide test results to the engineer within 6 hours after obtaining a sample. For 3-inch base, extend this 6-hour limit to 24 hours. Post or distribute tabulated results using a method mutually agreeable to the engineer and contractor.

B.4.3 Control Charts

- (1) Plot gradation and fracture on the appropriate control chart as soon as test results are available. Format control charts according to CMM 8.30. Include the project number on base placement control charts. Maintain separate control charts for each base aggregate size, source or classification, and type.
- (2) Provide control charts to the engineer within 6 hours after obtaining a sample. For 3-inch base, extend this 6-hour limit to 24 hours. Post or distribute charts using a method mutually agreeable to the engineer and contractor. Update control charts daily to include the following:
 1. Contractor individual QC tests.
 2. Department QV tests.
 3. Department IA tests.
 4. Four-point running average of the QC tests.
- (3) Except as specified under B.8.2.1 for nonconforming QV tests, include only QC tests in the running average. The contractor may plot process control or informational tests on control charts, but do not include these tests, conforming QV tests, or IA tests in the running average.

B.5 Contractor Testing

- (1) Test gradation, fracture, liquid limit and plasticity index during placement for each base aggregate size, source or classification, and type.
- (2) Test gradation once per 3000 tons of material placed. Determine random sample locations and provide those sample locations to the engineer. Obtain samples after the material has been bladed, mixed, and shaped but before compacting; except collect 3-inch samples from the stockpile at load-out. Do not sample from material used to maintain local traffic or from areas of temporary base that will not have an overlying pavement. On days when placing only material used to maintain local traffic or only temporary base that will not have an overlying pavement, no placement testing is required.

- (3) Split each contractor QC sample and identify it according to CMM 8.30. Retain the split for 7 calendar days in a dry, protected location. If requested for department comparison testing, deliver the split to the engineer within one business day.
- (4) The engineer may require additional sampling and testing to evaluate suspect material or the technician's sampling and testing procedures.
- (5) Test fracture for each gradation test until the fracture running average is above the lower warning limit. Subsequently, the contractor may reduce the frequency to one test per 10 gradation tests if the fracture running average remains above the warning limit.
- (6) Test the liquid limit and plasticity index for the first gradation test. Subsequently, test the liquid limit and plasticity index a minimum of once per 10 gradation tests.

B.6 Test Methods

B.6.1 Gradation

- (1) Test gradation using a washed analysis conforming to the following as modified in CMM 8.60:
 Gradation..... AASHTO T 27
 Material finer than the No. 200 sieve..... AASHTO T 11
- (2) For 3-inch base, if 3 consecutive running average points for the percent passing the No. 200 sieve are 8.5 percent or less, the contractor may use an unwashed analysis. Wash at least one sample out of 10. If a single running average for the percent passing the No. 200 sieve exceeds 8.5 percent, resume washed analyses until 3 consecutive running average points are again 8.5 percent passing or less.
- (3) Maintain a separate control chart for each sieve size specified in standard spec 305 or standard spec 310 for each base aggregate size, source or classification, and type. Set control and warning limits based on the standard specification gradation limits as follows:
 1. Control limits are at the upper and lower specification limits.
 2. There are no upper warning limits for sieves allowing 100 percent passing and no lower control limits for sieves allowing 0 percent passing.
 3. Dense graded warning limits, except for the No. 200 sieve, are 2 percent within the upper and lower control limits. Warning limits for the No. 200 sieve are set 0.5 percent within the upper and lower control limits.
 4. Open graded warning limits for the 1-inch, 3/8-inch, and No. 4 sieves are 2 percent within the upper and lower control limits. Upper warning limits for the No. 10, No. 40, and No. 200 sieves are 1 percent inside the upper control limit.

B.6.2 Fracture

- (1) Test fracture conforming to CMM 8.60. The engineer will waive fractured particle testing on quarried stone.

- (2) Maintain a separate fracture control chart for each base aggregate size, source or classification, and type. Set the lower control limit at the contract specification limit, either specified in another special provision or in table 301-2 of standard spec 301.2.4.5. Set the lower warning limit 2 percent above the lower control limit. There are no upper limits.

B.6.3 Liquid Limit and Plasticity

- (1) Test the liquid limit and plasticity according to AASHTO T 89 and T 90.
- (2) Ensure the material conforms to the limits specified in standard spec table 301-2.

B.7 Corrective Action

B.7.1 General

- (1) Consider corrective action when the running average trends toward a warning limit. Take corrective action if an individual test exceeds the contract specification limit. Document all corrective actions both in the project records and on the appropriate control chart.

B.7.2 Placement Corrective Action

- (1) Do not blend additional material on the roadbed to correct gradation problems.
- (2) Notify the engineer whenever the running average exceeds a warning limit. When 2 consecutive running averages exceed a warning limit, the engineer and contractor will discuss appropriate corrective action. Perform the engineer's recommended corrective action and increase the testing frequency as follows:
 1. For gradation, increase the QC testing frequency to at least one randomly sampled test per 1000 tons placed.
 2. For fracture, increase the QC testing frequency to at least one test per gradation test.
- (3) If corrective action improves the property in question such that the running average after 4 additional tests is within the warning limits, the contractor may return to the testing frequency specified in B.5.3. If corrective action does not improve the property in question such that the running average after 4 additional individual tests is still in the warning band, repeat the steps outlined above starting with engineer notification.
- (4) If the running average exceeds a control limit, material starting from the first running average exceeding the control limit and ending at the first subsequent running average inside the control limit is nonconforming and subject to pay reduction.
- (5) For individual test results significantly outside the control limits, notify the engineer, stop placing base, and suspend other activities that may affect the area in question. The engineer and contractor will jointly review data, data reduction, and data analysis; evaluate sampling and testing procedures; and perform additional testing as required to determine the extent of potentially unacceptable material. The engineer

may direct the contractor to remove and replace that material. Individual test results are significantly outside the control limits if meeting one or more of the following criteria:

1. A gradation control limit for the No. 200 sieve is exceeded by more than 3.0 percent.
2. A gradation control limit for any sieve, except the No. 200, is exceeded by more than 5.0 percent.
3. The fracture control limit is exceeded by more than 10.0 percent.

B.8 Department Testing

B.8.1 General

- (1) The department will conduct verification testing to validate the quality of the product and independent assurance testing to evaluate the sampling and testing. The department will provide the contractor with a listing of names and telephone numbers of all QV and IA personnel for the project, and provide test results to the contractor within 2 business days after the department obtains the sample.

B.8.2 Verification Testing

B.8.2.1 General

- (1) The department will have an HTCP technician, or ACT working under a certified technician, perform QV sampling and testing. Department verification testing personnel must meet the same certification level requirements specified in B.2 for contractor testing personnel for each test result being verified. The department will notify the contractor before sampling so the contractor can observe QV sampling.
- (2) The department will conduct QV tests of each base aggregate size, source or classification, and type during placement conforming to the following:
 1. One non-random test on the first day of placement.
 2. At least one random test per 30,000 tons, or fraction of 30,000 tons, placed.
- (3) The department will sample randomly, at locations independent of the contractor's QC work, collecting one sample at each QV location. The department will collect QV samples after the material has been bladed, mixed, and shaped but before compacting; except, for 3-inch aggregates, the department will collect samples from the stockpile at load-out. The department will split each sample, test half for QV, and retain half.
- (4) The department will conduct QV tests in a separate laboratory and with separate equipment from the contractor's QC tests. The department will use the same methods specified for QC testing.
- (5) The department will assess QV results by comparing to the appropriate specification limits. If QV test results conform to the specification, the department will take no further action. If QV test results are nonconforming, add the QV to the QC test results as if it were an additional QC test.

B.8.3 Independent Assurance

- (1) Independence assurance is unbiased testing the department performs to evaluate the department's QV and the contractor's QC sampling and testing including personnel qualifications, procedures, and equipment. The department will perform an IA review according to the department's independent assurance program. That review may include one or more of the following:
 1. Split sample testing.
 2. Proficiency sample testing.
 3. Witnessing sampling and testing.
 4. Test equipment calibration checks.
 5. Reviewing required worksheets and control charts.
 6. Requesting that testing personnel perform additional sampling and testing.
- (2) If the department identifies a deficiency, and after further investigation confirms it, correct that deficiency. If the contractor does not correct or fails to cooperate in resolving identified deficiencies, the engineer may suspend placement until action is taken. Resolve disputes as specified in B.9.

B.9 Dispute Resolution

- (1) The engineer and contractor should make every effort to avoid conflict. If a dispute between some aspect of the contractor's and the engineer's testing program does occur, seek a solution mutually agreeable to the project personnel. The department and contractor may review the data, examine data reduction and analysis methods, evaluate sampling and testing procedures, and perform additional testing. Use ASTM E 178 to evaluate potential statistically outlying data.
- (2) Production test results, and results from other process control testing, may be considered when resolving a dispute.
- (3) If the project personnel cannot resolve a dispute, and the dispute affects payment or could result in incorporating non-conforming product, the department will use third party testing to resolve the dispute. The department's central office laboratory, or a mutually agreed on independent testing laboratory, will provide this testing. The engineer and contractor will abide by the results of the third party tests. The party in error will pay service charges incurred for testing by an independent laboratory. The department may use third party test results to evaluate the quality of questionable materials and determine the appropriate payment. The department may reject material or otherwise determine the final disposition of nonconforming material as specified in standard spec 106.5.

C (Vacant)

D (Vacant)

E Payment

- (1) Costs for all sampling, testing, and documentation required under this special provision are incidental to this work. If the contractor fails to perform the work required under this special provision, the department may reduce the contractor's pay. The department will administer pay reduction under the non-performance of QMP administrative item.
- (2) For material represented by a running average exceeding a control limit, the department will reduce pay by 10 percent of the contract price for the affected Base Aggregate bid items listed in subsection A. The department will administer pay reduction under the Nonconforming QMP Base Aggregate Gradation or Nonconforming QMP Base Aggregate Fracture Administrative items. The department will determine the quantity of nonconforming material as specified in B.7.2.

301-010 (20100709)

11. Base Aggregate Dense, ¾ Inch.

This work shall be in accordance to the pertinent requirement of Section 305 of the Standard Specification, except that the material used in all paved field entrances and private entrances and the top 4 inches of all paved portions of the shoulders, as shown in the plan, shall consist of crushed stone.

305-015 (20080902)

12. Base Aggregate Dense 1¼-Inch.

Revise standard spec 305.2.2.1 as follows:

Use 1¼-inch base aggregate that confirms to the following gradation requirements.
Percentage by weight passing

	Percentage of Mass Passing
1 1/4 inch	95 - 100
1 inch	---
3/4 inch	70 - 90
3/8 inch	45 - 75
No. 4	30 - 60
No. 10	20 - 40
No. 40	7 - 25
No. 200	2 - 12 ^{[1], [3]}

^[1] Limited to a maximum of eight percent for base placed between old and new pavement.

^[2] 3-10 percent passing when base is ≥ 50% crushed gravel

305-020 (20080902)

13. Rout and Seal, Item 415.6000.S.

A Description

This special provision describes routing, cleaning, drying, and sealing the longitudinal edge of pavement joints in new asphaltic pavement shoulders immediately adjacent to the edge of the concrete mainline pavement. The work shall conform to the plan details and as hereinafter provided.

B Materials

Furnish material that conforms to the requirements of the Specifications for Joint Sealants, Hot-Poured, for Concrete and Asphalt Pavements, ASTM Designation: D 6690, Type II, modified to require that the bond strength test be run at -20 degrees F. (The unmodified ASTM D 6690, Type II allows this test to be run at either 0 degrees F or -20 degrees F.)

Deliver each lot or batch of sealing compound to the jobsite in the manufacturer's original sealed container. Mark each container with the manufacturer's name, batch or lot number, and the safe heating temperature. Present the manufacturer's certification stating that the compound meets the requirements of this specification. Prior to applying the sealant, furnish to the engineer a certificate of compliance and a copy of the manufacturer's recommendations on heating and applying the sealant.

C Construction

C.1 Equipment

Heat the sealing compound to the pouring temperature recommended by the manufacturer in an approved kettle or tank, constructed as a double boiler, with the space between the inner and outer shells filled with oil or other satisfactory heat transfer medium. If and when using the heating kettle on concrete or asphaltic pavement, properly insulate the heating kettle to ensure heat is not radiated to the pavement surface.

Make rout cuts in a single pass. Two-pass cutting will not be allowed. Use a self-propelled mechanical router capable of routing the bituminous pavement to provide a 1.0:1.0 depth to width ratio of all routed cracks. The router blade or blades shall be of such size and configuration to cut the desired joint reservoir in one pass of the rout. No spacers between blades shall be allowed unless the contractor can demonstrate to the engineer that the desired reservoir and rout cut can be obtained with them. Either wet or dry routing will be permitted provided the above conditions are met. Use a pressure distributor for applying sealing material through a hand-operated wand or nozzle according to sealant manufacturer's instructions.

C.2 Methods

Conduct the operation so that the routing, cleaning, and sealing are continuous operations. Traffic shall not be allowed to knead together or damage the routed joints. Rerout, if necessary, routed joints not sealed before traffic is allowed on the pavement when routing and sealing operations resume at no additional cost to the department. Do

not perform rout cutting, cleaning, and sealing, within 48 hours of the placement of the shoulder's surface course.

Rout the longitudinal joint to a minimum width of $\frac{3}{4}$ -inches and a minimum depth of $\frac{3}{4}$ -inches. Use a power vacuum or equivalent to immediately remove any routing slurry, dirt, or deleterious matter adhering to the joint walls or remaining in the joint cavity, or both. Prior to sealing, dry the cleaned joints either by air-drying or by using a high capacity torch. Immediately prior to sealing, blow out the dried crack with a blast of compressed air, 80-psi minimum. Continue cleaning until the joint is dry, and until all dirt, dust, or deleterious matter is removed from the joint and adjacent pavement to the satisfaction of the engineer. If the air compressor produces dirt or other residue in the joint cavity, the contractor shall be required to clean the joint again.

If cleaning operations could cause damage to, or interfere with, traffic in adjacent lanes, or both, provide protective screening that is subject to the approval of the engineer to the cleaning operation.

Following cleaning, dry the routed joints and warm them with a hot air lance. Take care not to burn the pavement surface. Under no circumstances shall more than two minutes elapse between the time the hot air lance is used and the sealant is placed.

Provide positive temperature control and mechanical agitation. Do not heat the sealant to more than 20 degrees F below the safe heating temperature. The safe heating temperature can be obtained from the manufacturer's shipping container. Provide a direct connecting pressure type extruding device with nozzles shaped for insertion into the joint. Immediately remove sealant spilled on the surface of the pavement.

Seal the joints when the sealant material is at the pouring temperature recommended by the manufacturer. Fill the joint such that after cooling, the sealant is flush with the adjacent pavement surface. Do not overfill the joint; the engineer may allow a very slight overband. Sand shall not be spread on the sealed joints to allow for opening to traffic. Before opening to traffic, the sealant shall be tack free.

D Measurement

The department will measure Rout and Seal in length by the linear foot, completed according to the contract and accepted

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
415.6000.S	Rout and Seal	LF

Payment is full compensation for rout cutting; cleaning the joint; furnishing and installing all materials, including sealant.

415-100 (20080902)

14. Concrete Pavement Partial Depth Repair Joint Repair, Item 416.0750.S; Crack Repair, Item 416.0752.S.

A Description

This special provision describes removal of deteriorated concrete, furnishing, placing and curing concrete to the original slope and grade, and reestablishing cracks or joints at areas shown on the plans and as directed by the engineer, all according to the requirements of the plans, the standard specifications, and as hereinafter provided.

The item Concrete Pavement Partial Depth Repair Joint Repair consists of removing deteriorated concrete at the areas designated in the plans, furnishing, placing, and curing concrete to the original slope and grade, and reestablishing joints.

The item Concrete Pavement Partial Depth Repair Crack Repair consists of removing deteriorated concrete at the areas designated in the plans, furnishing, placing, and curing concrete to the original slope and grade, and reestablishing cracks.

The item Concrete Pavement Partial Depth Repair Surface Repair consists of removing deteriorated concrete at the areas designated in the plans, furnishing, placing, and curing concrete to the original slope and grade.

The item Concrete Pavement Partial Depth Repair Edge Repair consists of removing deteriorated concrete at the areas designated in the plans, furnishing, placing, and curing concrete to the original slope and grade.

The item Concrete Pavement Partial Depth Repair Full Depth Adjustment consists of removing deteriorated concrete at the areas designated in the plans, furnishing and installing required pavement tie, furnishing, placing, and curing concrete to the original slope and grade, and reestablishing joints.

A.1 General

In advance of the beginning of the rehabilitation operation, establish traffic control for rehabilitation surveys and marking of locations.

Any removal and replacement of existing asphaltic concrete pavement in conjunction with the concrete pavement operations shall be incidental work for which no direct payment will be made unless otherwise shown in the plan.

Perform the removal operation in a manner that precludes damage to the remaining pavement. Any damage to the in-place concrete pavement by the contractor's operations, shall be repaired prior to final acceptance as directed by the engineer and at no expense to the department.

Milling is generally completed with one pass of the milling machine. The nominal width of Joint Repair or Crack Repair shall not exceed 12 inches (305 mm). Any repair area required, beyond the nominal 12-inch (305 mm) width will be paid for as Surface Repair.

The length of Full Depth Adjustment, along the transverse joint, from the nearest longitudinal joint, shall not be greater than 18 inches (458 mm).

If during removal operations it is determined that a full-lane width, full-depth repair is required, the contractor will receive partial payment for a measured quantity of the intended repair item, and the work shall be completed under the item of Concrete Pavement Repair, Item 416.0710. If after milling a transverse joint deteriorated concrete exists greater than 4 inches wide and 6 feet in length, the joint shall be converted to a full-depth Concrete Pavement Repair.

Do not place repair concrete when the ambient air temperature is below 50° F (10° C), except as permitted by the engineer. When the ambient air temperature is below 50° F (10° C) the engineer may require covering during the initial curing period.

Partial depth repair areas should be inspected for possible debonding, by chain dragging or other suitable procedure, before opening to public traffic. Debonded repairs must be removed and replaced.

Opening of pavement repairs to traffic will be controlled by cylinder tests, as set forth in standard spec 415.3.17.

Replace any area of the asphaltic shoulder damaged during the pavement removal operations under this item with a commercially produced asphaltic patching material to the elevation of the adjacent shoulder.

At no expense to the department, remove and replace any areas of failure that appear within one month of the original repair, or any subsequent repair, including traffic control. Failures include but may not be limited to loss of bonding to the in-place concrete, spalling, or crack apparent in the repair other than the desired crack in the newly constructed joint or reestablished crack.

A.2 Equipment

Use only concrete milling machines that are equipped with a device for stopping at preset depths to prevent damage to dowel bars. Additionally, shroud the equipment to prevent discharge of any loosened material into adjacent work areas or live traffic lanes.

Use air chippers or breakers for chipping the old concrete surface that have a total weight not exceeding 30 lb. (13.6 kg) and are equipped with flat, chisel-type points that have cutting edges not less than .75 inch (19 mm) or greater than 3 inches (76.2 mm) wide.

Use concrete mixing equipment that provides material of uniform consistency. Do not prepare site-mixed concrete more than ½ hour prior to placement. Do not prepare ready-mixed concrete more than 1 hour prior to placement.

Use mechanical vibrators that are capable of operating at frequencies sufficient to achieve thorough and uniform consolidation, but not less than 7000 impulses per minute. Have available at least one spare vibrator, in working order and of sufficient frequency, on the work site before concrete placement is started.

B Materials

All materials used in the work shall conform to the requirements specified for the class of material named.

B.1 Concrete

The replacement concrete shall comply with the standard specifications except as modified below. It shall be furnished, placed, and cured according to the provisions in the plans, specifications, and contract.

Use the following proportions for 1 cubic yard (cubic meter) of concrete:

850 lb. (505 kg) Portland Concrete (Type 1 or Type III)
1338 lb. (794 kg) Fine Aggregate (Per standard specifications except max'm
P200=2.5%)
1338 lb. (794 kg) Coarse Aggregate (See table below for gradation)

* These quantities assume a specific gravity of 2.65.

Coarse Aggregate Gradation		
Sieve	% Passing	
3/8	(9.5 mm)	100
#4	(4.75 mm)	55-95
#50	(300 µm)	0-5
#200	(75 µm)	0-1.0

Maximum slump shall be 1 inch (25 mm).

Air Content shall be 6% ±1.5%

ASTM C494 Type A admixture shall be used, unless Type E is used.

ASTM C494 Type E admixture may be used, according to the manufacturer's recommendations, to achieve the required opening strength in the desired time period. Dosage will vary with ambient temperature and desired opening time.

The use of more than 50% of the maximum manufacturer's recommended dosage of Type E admixture will require the concrete to be sprayed with curing compound and covered with wet burlene.

B.2 Compression Relief Material

Provide compression relief material that is made of a rigid, compressible, non-absorbent material.

B.3 Bonding Agent

Use bonding grout that consists of equal portions of Portland cement and sand, mixed with sufficient water to form a slurry having the consistency of thick cream.

B.4 Concrete Curing Agent

Provide a concrete curing agent that is a resin of 100 percent poly-alpha-methylstyrene type curing compound meeting ASTM C309, Type 2, Class B specifications and conforming to all requirements according to the following table:

Properties	Minimum	Maximum
Total Solids, % by weight of compound	42	
Reflectance in 72 hours (ASTM E1347	65	
Loss of Water, kg/m ² in 24 hours (ASTM C156)		0.15
Loss of water, kg/m ² in 72 hours (ASTM C156)		0.40
Settling Test, ml/100 ml in 72 hours ¹		2
V.O.C. Content, g/L		350
Infrared Spectrum, Vehicle ²	100% alpha-methylstyrene	

¹ Test Method on file at the department's Materials Testing Lab.

² The infrared scan for the dried vehicle from the curing compound shall match the infrared scan on file at the department's Materials Testing Lab.

Shelf life of the product shall be six months from date of manufacture. The product may be re-tested by the department's Materials Testing Lab and re-approved, if the physical and chemical properties have not changed, for an additional six months. However, the maximum shelf life shall not exceed one year from manufacture date.

C Construction

Remove the concrete by milling to the depths and dimensions as shown on the plan or as determined by the engineer, or both.

Milling may be accomplished either longitudinally or transversely to the joint, crack, or edge. The removal process must not damage dowel bars. In the event a dowel bar exhibits excessive corrosion, cut, or burn-off the bar.

The removal of the concrete surface in the designated repair areas shall have a minimum depth of 2 inches (50.8 mm) with all deteriorated concrete removed to a maximum depth of one-half the pavement thickness, or the top of the dowel bars. Using air chippers, remove all cracked or deteriorated concrete exposed after milling to sound concrete. Chipping at the milled surface of the crack or joint shall be a minimum 2 inches wide and shall be at a 1:1 slope.

When dowel bars are present, take precaution not to disturb unsound concrete below the tops of the dowels. If some of this unsound material is accidentally blown out during the cleaning process, fill in the voids with clean, dry sand.

Use air chippers only for final preparation of the repair area.

Storage of the removed material on the roadway will only be permitted in conjunction with a continuous removal and pick-up operation. During non-working hours, clear the roadway of all materials and equipment.

The removed pavement shall become the property of the contractor and disposed of according to standard spec 204.3.1.3.

Install pavement ties according to standard spec 416.3.6.

Sandblast all exposed surfaces within 24 hours prior to concrete placement. If it rains prior to concrete placement, sandblast the repair areas again. Additionally, clean the repair areas of loose material by air blasting before applying the bonding grout.

Coat exposed surfaces of dowel bars to prevent bonding between the bar and the repair concrete. Take precaution to prevent contamination of existing concrete in the repair area.

Place compression relief material to maintain the continuity of the existing crack or to reestablish the joint in a full-depth adjustment. Install compression relief material such that it remains in position and is tight to all edges during placement of the repair concrete. During concrete placement and vibrating, keep the compression relief material in contact with the bottom of the repair area. To ensure that cracks are reestablished in their original locations, scribe their locations on the adjoining pavement outside the removal area, prior to removal operations.

Reestablish cracks and joints to a ¼-inch width, or to the existing crack or joint width, whichever is greater.

Immediately prior to placing the concrete, coat the repair surface with bonding grout. The surface shall be completely dry for at least one-half hour before coating with bonding grout. If the surface isn't completely dry, dry the surface using heat to remove all moisture from the repair surface. Mix the grout by mechanical means and thoroughly brush it over the prepared concrete surface to ensure that all parts receive an even coating. No excess grout shall be permitted to collect in pockets. Place grout within 1½ hours of mixing. If the grout whitens, sandblast, and re-grout.

Vibrate concrete as necessary to uniformly and thoroughly consolidate the entire mass of fresh concrete without causing segregation of the aggregates or the formation of localized areas of grout.

Concrete repairs shall not protrude beyond the original cross-section of the pavement by more than 3/8 inch (9.5 mm). The edges shall be formed or sawn full-depth.

Strike-off the surface of the repaired area flush with the adjacent concrete and finish the surface to a uniform texture, true to grade and cross section and free from porous areas. As a final finishing operation, float the concrete toward the edges of the repair.

While the concrete is still plastic, the repair shall be tested for trueness with a straightedge.

Reestablish cracks using compression relief material to or beyond the surface of the repair. Initially reestablish joints in plastic concrete by using a jointing tool. Establish tooled joints to a minimum depth of 2 inches. Tooled edges shall be provided, adjacent to all compression relief material, in fresh concrete. Complete the removal of excess compression relief material above the pavement surface without damage to the repair area. The method of removal will be reviewed and approved by the engineer prior to any removal.

Surface texturing, if required by the engineer, shall consist of a broomed finish in the long dimension direction of the repair.

Apply curing compound to the fresh concrete as soon as possible. Apply the compound uniformly, at a minimum rate of one gallon per 100 square feet (0.41 L/m²).

Restore joints by sawing. Saw the joints in a single cut, to the width and depth shown on the plans, and according to standard spec 415.3.9.

Thoroughly clean the joint or crack after sawing to remove loose compressible material.

D Measurement

The department will measure Concrete Pavement Partial Depth Repair Joint Repair; Concrete Pavement Partial Depth Repair Crack Repair by the linear foot, completed according to the contract and accepted.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid items:

ITEM NUMBER	DESCRIPTION	UNIT
416.0750.S	Concrete Pavement Partial Depth Repair Joint Repair	LF
416.0752.S	Concrete Pavement Partial Depth Repair Crack Repair	LF

If a Partial Depth Repair item is changed, by the project engineer, to a full-depth repair, the contractor shall be paid at a measured quantity of 40 percent of the intended repair plus the full cost for Full Depth Repair.

Payment for Concrete Pavement Partial Depth Repair Joint Repair; Concrete Pavement Partial Depth Repair Crack Repair, and Concrete Pavement Partial Depth Repair Edge Repair, is full compensation for removing the concrete; disposing of materials; furnishing and placing sand where required; furnishing and placing compression relief material where required; furnishing and placing preformed joint filler where required; placement and curing of the concrete; and for reestablishing cracks or joints.

Payment for Concrete Pavement Partial Depth Repair Surface Repair and Concrete Pavement Partial Depth Repair Full Depth Adjustment, is full compensation for removing the concrete; for disposing of materials; furnishing and installing pavement ties where necessary; furnishing and placing preformed joint filler where required; furnishing and placing compression relief material where required; replacing the concrete; and reestablishing joints. The item Partial Depth Repair, Full Depth Adjustment will be paid for as a separate item at locations where it is necessary to extend the repair through the full remaining concrete pavement thickness.

416-015 (20110615)

15. Expansion Device, Structure B-32-0055; Expansion Device, Structure B-32-0056.

A Description

This special provision describes furnishing and installing an expansion device in accordance to standard spec 502, as shown on the plans, and as hereinafter provided.

B Materials

The minimum thickness of the polychloroprene strip seal shall be ¼-inch for non-reinforced elastomeric glands and 1/8-inch for reinforced glands. Furnish the strip seal gland in lengths suitable for a continuous one-piece installation at each individual expansion joint location. Provide preformed polychloroprene strip seals that conform to the requirements ASTM D3542, and have the following physical properties:

Property Requirements	Value	Test Method
Tensile Strength, min.	2000 psi	ASTM D412
Elongation @ Break, min	250%	ASTM D412
Hardness, Type A, Durometer	60 ± 5 pts.	ASTM D2240
Compression Set, 70 hours @212°F, max.	35%	D395 Method B Modified
Ozone Resistance, after 70 hrs. at 100°F under 20% Strain with 100 pphm ozone	No Cracks	ASTM D1149 Method A
Mass Change in Oil 3 after 70 hr. 212°F	45%	ASTM D471
Mass Change, max.		

Install the elastomeric strip seal gland with tools recommended by the manufacturer, and with a lubricant adhesive conforming to the requirements of ASTM D4070.

The manufacturer and model number shall be one of the following approved strip seal expansion device products:

Manufacturer	Model Number Strip Seal Gland Size*		
	4-Inch	5-Inch	6-Inch
D.S. Brown	SSA2-A2R-400	SSA2-A2R-XTRA	SSA2-A2R-XTRA
R.J. Watson	RJA-RJ400	RJA-RJ500	RJA-RJ600
Watson Bowman Acme	A-SE400	A-SE500	A-SE800
Commercial Fabricators	A-AS400	-----	-----

*Expansion device strip seal gland size requirement of 4", 5", and 6" shall be as shown on the plans.

Furnish manufacturer's certification for production of polychloroprene represented showing test results for the cured material supplied, and certifying that it meets all specified requirements.

The steel extrusion or retainer shall conform to ASTM designation A 709 grade 36 steel. After fabrication, steel shall be galvanized conforming to the requirements ASTM A123.

Manufacturer's certifications for adhesive and steel shall attest that the materials meet the specification requirements.
502-020 (20110615)

16. Bearing Replacement B-32-0055, Item 506.7000.S.01.

A Description

This special provision describes raising the girders, removing the existing bearings, and furnishing and placing new bearings as shown on the plans and as hereinafter provided.

B (Vacant)

C Construction

Raise the structure's girders, remove the existing bearings, and furnish and place the bearings as shown in the plans.

Obtain prior approval from the engineer for the method of jacking the girders and of supporting them during replacement operations.

D Measurement

The department will measure Bearing Replacement B-32-0055 by the unit for each bearing removed and replaced.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
506.7000.S.01	Bearing Replacement B-32-0055	Each

Payment is full compensation for raising the bridge; removing the old bearings; furnishing and placing new bearings; and resetting anchor bolts as required.
506-025 (20030820)

17. Epoxy Crack Sealing, Item 509.9020.S.**A Description**

Seal vertical cracks in the abutments according to the plan details and as hereinafter provided.

B Materials

Furnish a penetrating epoxy sealant manufactured by Sika, Adhesive Engineering, Technical Sealants, Dayton Superior, or equal. Before using, obtain the engineer's approval for the epoxy system which is proposed to seal the cracks.

C Construction

Before sealing, clean the cracks by chipping and by using high-pressure air.

After all of the cleaning is completed, inject epoxy sealant into the cracks to be sealed. Seal the cracks using the penetrating epoxy sealant as recommended by the sealant manufacturer.

D Measurement

The department will measure Epoxy Crack Sealing in length by the linear foot of crack, acceptably sealed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
509.9020.S	Epoxy Crack Sealing	LF

Payment is full compensation for cleaning the cracks; and for furnishing and placing the epoxy sealant.
509-020 (20100709)

18. Structure Repainting General.

A General

A.1 Inspection

On all structures in this contract, notify the engineer of any missing or broken bolts or nuts, any missing or broken rivets, or of any cracks or flaws in the steel members while cleaning or painting.

A.2 Date Painted

At the completion of all painting work, stencil in black paint or contrasting color paint the date of painting the bridge. The numbers shall be three inches (75 mm) in height and shall show the month and year in which the painting was completed: e.g., 11-95 (November 1995). On each bridge painted, stencil the date at two locations. On truss bridges, stencil the date on the cover plates of end posts near and above the top of the railings at the oncoming traffic end. On steel girder bridges, stencil the date on the **inside** of the outside stringers at the abutments. The date on grade separation bridges shall be readable when going under the structure or at some equally visible surface near the ends of the bridge, as designated by the engineer.

A.3 Graffiti Removal

Remove any graffiti on concrete abutments, piers, pier caps, parapet railings, slope paving or any other location at the direction of the engineer. Use a brush sandblast to remove graffiti.

The above work will not be measured and paid for separately, but will be considered incidental to other items in the contract.

B (Vacant)

C Construction

C.1 Repainting Methods

Do not perform blasting, cleaning and painting on days of high winds. Prevailing winds in excess of 15 mph (25 km/hr) shall be considered high winds.

Prior to final acceptance, completely clean and free from spent abrasive and other waste materials resulting from the contractor's operation the bridge deck surfaces, gutter lines, drains, curbs, bridge seats, pier caps, slope paving, roadway below, and all structural members and assemblies.

Place the final field coat of paint on the exterior of the exterior beams as a continuous painting operation. Stop at splices, vertical stiffeners or other appropriate locations so that lap marks are not evident or noticeable.

C.2 Inspection

Supplement standard spec 105.9 as follows:

Furnish, erect and move scaffolding and other appropriate equipment to permit the inspector the opportunity to closely observe all affected surfaces. The scaffolding, with appropriate safety devices, shall meet the approval of the engineer.

517-005 (20030820)

19. Structure Overcoating Cleaning and Priming B-32-0055, Item 517.3000.S.01; Structure Overcoating Cleaning and Priming B-32-56, Item 517.3000.S.02.

A Description

This special provision describes cleaning and painting with two or three coats of paint the metal surfaces as hereinafter provided.

A.1 Areas to be Cleaned and Painted

Structure B-32-0055, B-32-56 each

1. Two Coat Area: 0 SF with SP 1 cleaning.
2. Three Coat Area:
 - 0 SF with SP 2 cleaning.
 - B-32-55: 1050 SF with SP3 cleaning.
 - B-32-56: 1105 SF with SP3 cleaning.
 - 0 SF with SP 11 cleaning.
 - 0 SF total three-coat area.

B (Vacant)

C Construction

C.1 Surface Preparation

Prior to overcoating or power tool cleaning, solvent clean all surfaces to be coated in accordance to SSPC-SP1. A SSPC-SP 3 power Tool Cleaning according to Steel Structures Painting Council Specification 3 will be required on all metal surfaces to be painted with a three-coat system. Prime the same day, or re-clean before application, all metal surfaces receiving a No. 3 cleaning.

Remove all abrasive or paint residue from steel surfaces with a High Efficiency Particulate Abatement (HEPA-VAC) vacuum cleaner equipped with a brush-type cleaning tool, or by double blowing. If the double blowing method is used, vacuum the exposed top surfaces of all structural steel, including flanges, longitudinal stiffeners, splices, plates, and hangers, after the double blowing operations are completed. The air line used for blowing the steel clean shall have an inline water trap and the air shall be free of oil and water as it leaves the air line.

Take care to protect freshly coated surfaces from subsequent cleaning operations. Thoroughly wire brush damaged primed surfaces with a non-rusting tool. Clean and re-prime the brushed surfaces within the time recommended by the manufacturer.

C.2 Painting

Paint by applying two or three coats of an approved coating system as specified herein to the surfaces as described in A.1 from the department's approved products list.

C.3 Coating Application

Apply paint in a neat, workmanlike manner. The resultant paint film shall be smooth and uniform without skips or areas of excessive paint. Apply coating in accordance to the manufacturer's recommendations.

Prior to applying the prime coat, coat with primer all edges, rivet and bolt heads, nuts and washers by using either a brush, roller, or spray application.

Dry Film Thickness per coat shall be a minimum of 3-mil. The dry film thickness shall be determined by use of a magnetic film thickness gage. The gage shall be calibrated for dry film thickness measurement in accordance to SSPC-PA 2.

During surface preparation and coating application, the ambient and steel temperature shall be between 39 and 100 degrees F. The steel temperature shall be at least 5 degrees F above the dew point temperature, and the relative humidity shall not exceed 85%.

D Measurement

The department will measure Structure Overcoating Cleaning and Priming (Structure), completed in accordance to the contract and accepted, as a single complete unit of work.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
517.3000.S.01	Structure Overcoating Cleaning and Priming B-32-0055	LS
517.3000.S.02	Structure Overcoating Cleaning and Priming B-32-0056	LS

Payment is full compensation for preparing and cleaning the designated surfaces; and for furnishing and applying the paint.

517-036 (20080501)

20. Preparation and Coating of Top Flanges B-32-0055, Item 517.0900.S.01.

A Description

This special provision describes thoroughly cleaning and coating the top surface and edges of the top flanges, removing loose paint, rust, mill scale, dirt, oil, grease, or other foreign substances until the specified finish is obtained.

B (Vacant)

C Construction

In accordance to SSPC SP-10, blast clean to a near white finish the top surface and edges of the top flanges that have no paint on them, and paint them with one coat of an approved zinc rich primer. No collection of blast waste material is required.

In accordance to SSPC SP-2 or SP-3, clean all areas of rust and loose paint on the top surface and edges of the top flanges, which have paint on them, by wire brushing, grinding or other mechanical means. Wash the top surface and edges of the top flanges and give them one coat of an approved zinc-rich primer.

Where plans call for the cleaning of other painted structural steel including hanger assemblies, bearings, field splices, and connections, clean areas of loose paint and rust by wire brushing, grinding, or other mechanical means as necessary and in accordance to SSPC SP-2, SP-3, or SP-11. Sound paint need not be removed with the exception of an area 12-inches on either side of hanger assembly centerlines. Clean this area to base metal in accordance to SSPC SP-10, or SP-11.

In accordance to SSPC SP-2, or SP-3, thoroughly clean by wire brushing, grinding or other mechanical means as necessary the surface area of exposed steel members that are to be imbedded in the new concrete, and wash and give one coat of an approved zinc rich primer to these areas.

Furnish and erect tarpaulins or other materials to collect all of the spent paint containing material resulting from blasting or hand and power tool cleaning and coating. Minimize dust during all clean-up activities. Collect and store waste material at the end of each work day or more often if needed. Store waste materials in the hazardous waste containers provided. Lock and secure all waste containers at the end of each work day. Cover the container(s) at all times except when adding or removing waste material. Store the containers in an accessible and secured area, not located in a storm water runoff course, flood plain or exposed to standing water. Transportation and disposal of such waste material will be the responsibility of the department.

Damage to existing painted surfaces as a result of construction operations, shall be restored to the approval of the engineer at the contractor's expense.

D Measurement

The department will measure Preparation and Coating of Top Flanges (Structure), completed in accordance to the contract and accepted, as a single complete unit of work for the structure.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
517.0900.S.01	Preparation and Coating of Top Flanges B-32-0055	LS

Payment is full compensation for preparing and cleaning the designated surfaces; and for furnishing and applying the coating.

517-010 (20100709)

21. Containment and Collection of Waste Materials B-32-0055, Item 517.4000.S.01; Containment and Collection of Waste Materials B-32-0056, Item 517.4000.S.02.

A Description

This special provision describes furnishing and erecting tarpaulins to contain, collect and store the spent material from surface preparation of steel surfaces, collecting such spent material, and labeling and storing the spent material in waste containers in accordance to the contract and as hereinafter provided.

B Materials

Provide 5-gallon lidded plastic containers for containing the spent material.

C Construction

Erect tarpaulins or other materials to collect all of the spent material from power tool cleaning. Consider and treat all spent material as hazardous waste because it contains lead.

Collect and store all waste material collected by this operation at the bridge site for disposal. Collect and store all waste materials at the end of each workday or more often if needed. Store materials in 5-gallon lidded plastic containers.

Label each container with the date the first waste was placed in the container and the words "Hazardous Waste – EPA Waste Code D008." Lock and secure all containers at the end of each workday. Keep the containers covered at all times except to add or remove waste material. Store the containers in an accessible and secured area, not located in a storm water runoff course, flood plain or exposed to standing water.

Collect the spent debris by vacuuming, shoveling, sweeping, or by channeling it directly to disposal containers. The enclosure shall be thoroughly cleaned at the end of each work day.

D Measurement

The department will measure Containment and Collection of Waste Materials (Structure), completed in accordance to the contract and accepted, as a single complete unit of work for each structure designated in the contract.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
517.4000.S.01	Containment and Collection of Waste Materials B-32-055	LS
517.4000.S.02	Containment and Collection of Waste Materials B-32-056	LS

Payment is full compensation for designing, erecting, operating, maintaining and disassembling the containment devices; collecting, labeling and storing spent materials in appropriate containers.

517-037 (20080902)

22. Slope Paving Repair Crushed Aggregate, Item 604.9010.S.

A Description

Furnish and place crushed aggregate slope paving where erosion has occurred, according to standard spec 604, the plans, and as hereinafter provided.

B Materials

Furnish materials conforming to standard spec 604.2.

C Construction

Replace paragraph (1) of standard spec 604.3.2 with the following:

Place the crushed aggregate on the prepared foundation in areas where erosion has occurred. Shape and consolidate it using mechanical or hand methods to provide a stable, even and uniform surface.

D Measurement

The department will measure Slope Paving Repair Crushed Aggregate by the cubic yard, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
604.9010.S	Slope Paving Repair Crushed Aggregate	CY

Payment is full compensation for furnishing all excavating and backfilling required to prepare the foundation; disposing of surplus materials; providing, handling, placing, and consolidating the crushed aggregate; providing, handling, heating, and for applying the asphaltic material.

604-010 (20100709)

23. Reseal Crushed Aggregate Slope Paving, Item 604.9015.S.

A Description

Seal the existing crushed aggregate slope paving in accordance to standard spec 604, as directed by the engineer, and as hereinafter provided.

B Materials

Furnish materials conforming to standard spec 604.2.

C Construction

Clean all debris from the surface of the slope paving before applying asphalt. Apply sufficient asphalt so that it penetrates to seal the top two inches of aggregate; where existing asphalt is closer to the surface of the aggregate, apply less asphalt.

D Measurement

The department will measure Reseal Crushed Aggregate Slope Paving in area by the square yard of slope paving, acceptably resealed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
604.9015.S	Reseal Crushed Aggregate Slope Paving	SY

Payment is full compensation for cleaning the surface; furnishing and applying the asphalt.

604-015 (20100709)

24. Traffic Control.

Supplement standard spec 643.3.1 with the following:

Have available at all the times sufficient experienced personnel to promptly install, remove and reinstall the required traffic control devices to route traffic in order to perform the operations.

Provide the La Crosse County Sheriff's Department, State Patrol, emergency services, fire department, and engineer a telephone number with which the contractor or representative can be contacted non-working hours in the event a safety hazard develops.

Replace standard spec 643.31(6) with the following:

Provide 24-hour a day availability of the equipment, forces and materials to promptly restore barricades, lights, or other traffic control devices that the damaged or disturbed. Restore any barricade, light or other traffic control so that the device is not out of service for more than two hours.

25. Pavement Marking Wet Reflective Tape 4-Inch, Item 646.0871.S; 8-Inch, Item 646.0873.S.

A Description

This special provision describes furnishing and installing preformed wet reflective pavement marking tape for hot inlaid applications as shown on the plans, according to standard spec 646, and as hereinafter provided.

B Materials

Furnish wet reflective pavement marking tape if required, from the department's approved products list.

Furnish a copy of the manufacturer's recommendations to the engineer before inlaying the pavement marking.

C Construction**C.1 Inlaying Tape into New Asphaltic Pavement**

Inlay the material into the fresh asphalt mat at temperatures between 130 and 180 degrees Fahrenheit for a coarse mix and at temperatures between 130 and 160 degrees Fahrenheit for a fine mix. Place the tape per manufacturer's recommendations as close behind the asphalt paver as soon as compacting steps are completed and temperature permits and according to the plan details. If necessary, supply a dedicated asphalt roller to the striping operation for proper inlay application.

D Measurement

The department will measure Pavement Marking Wet Reflective Tape (Width) in length by the linear foot of tape placed according to the contract and accepted.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid items:

ITEM NUMBER	DESCRIPTION	UNIT
646.0871.S	Pavement Marking Wet Reflective Tape 4-Inch	LF
646.0873.S	Pavement Marking Wet Reflective Tape 8-Inch	LF

Payment is full compensation for cleaning and preparing the pavement surface; including heating as required by the manufacturer; and for furnishing and installing the material.
646-017 (20100709)

26. Inlet Repair, SPV.0060.01.**A Description**

Work under this item includes repairing the inlets to be adjusted.

B Material

Contractor shall repair inlets to be adjusted by grouting and sealing existing adjustment rings, structure walls, pipe connections and bottom of structure with Type A Mortar.

C (Vacant)**D Measurement**

The department will measure Inlet Repair as each individual item, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0060.01	Inlet Repair	Each

Payment is full compensation for repairing each inlet to be adjusted shown in the plan.

27. Weld Inspection Structure B-32-55, Item SPV.0105.01.

A Description

Work under the item of Weld Inspection consists of visual inspection, ultrasonic testing (UT), and magnetic particle testing (MT) of welds to identify discontinuities, cracks, or other defects. Work under this item will also include grinding out shallow cracks found during the inspection/testing. Complete this work after the deck has been removed.

B (Vacant)

C Construction

The welds to be inspected and tested are as shown on the plans and as describe below.

Butt spliced flange shop welds in the area of negative moment on either side of the pier. 12 total welds shall be inspected. Submerged arc welds are also present at the web and flange junction that shall be inspected concurrently with the butt spliced welds.

Notify the department of any deficiencies found. Once inspection has been completed, do not continue with construction operations in the area of the welds without approval of the engineer. Do not perform any remedial work including grinding without approval of the engineer.

C.1 Qualifications

Submit all inspector qualifications/certifications to the engineer for approval prior to performing inspections.

Visual Inspection: Complete the visual inspection by an American Welding Society (AWS) certified weld inspector (CWI).

Non-destructive Testing: Complete all non-destructive testing (NDT) with qualified NDT Level II individuals in conformance with the current edition of the American Society for Nondestructive Testing Recommended Practice No. SNT-TC-1A as required in AWS D1.5.

C.2 Preparation of Areas for Testing

Clean a minimum of 6 inches on each side of the weld to be tested of all concrete, paint, rust, and other contaminants that impede the testing/inspection process.

C.3 Visual Inspection

Visually inspect the existing weld areas for discontinuities, cracks, or other defects. If a crack is found through visual inspection, follow the requirements for magnetic particle testing and grinding.

C.4 Ultrasonic Testing (UT)

Perform ultrasonic testing to identify any internal discontinuities or defects in the welds. Follow the procedures and techniques of ASTM E164, Standard Practices for Contact Ultrasonic Testing of Weldments.

C.5 Magnetic Particle Inspection (MT)

Perform magnetic particle testing to identify any cracks in the welds. Follow the procedures and techniques for dry powder magnetic particle examination using the yoke method, ASTM E709, Practices for Magnetic Particle Examination.

C.5 Grinding

If surface cracks are approved for grinding, grind welds and base metal to eliminate shallow cracks and blend the weld to the base metal with a smooth transition. Where grinding the transition into the base metal, flare/transition the surface at a minimum of 15 to 1 slope. Provide an ANSI 250 finish (smooth). Grind no more than 1/8" into the base metal without the permission of the engineer. After grinding, test the area for flaws, voids, or defects.

C.6 Report

Provide a written report (including color photographs) of the inspection, ultrasonic testing, and magnetic particle testing to the department. In the report, include the names of the inspectors, the date of the inspection, the physical condition of the welds, the location of any deficiencies found, and any remedial action taken.

C.7 Extra Work

Repairs required to correct any deficiencies found during the inspection or testing beyond grinding shallow cracks will be paid for as extra work.

D Measurement

The department will measure Weld Inspection Structure B-32-55, completed in accordance to the contract and accepted, as a single complete lump sum unit of work for each structure designated in the contract.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0105.01	Weld Inspection Structure B-32-55	LS

Payment is full compensation for visual inspection, ultrasonic testing, magnetic particle testing, grinding cracks, for furnishing all preparation work required to accomplish the work under this specification (including removing paint), for the written report, and for furnishing all incidentals related to work under this specification.

28. Pigmented Concrete Surface Treatment, SPV.0180.01.

A Description

Work under this item includes furnishing and installing a pigmented high silicone-content, acrylic concrete sealer treatment to the concrete surfaces as shown in the plans.

B Materials

Furnish a high silicone-content, acrylic concrete sealer of the color the plans show.

Approved products:

Sherwin-Williams SWD DOT Bridge and Highway Sealer B-97 Series
The Sherwin Williams Company
www.sherwin-williams.com
(800) 474-3794

Anvil Siliconized Acrylic Concrete Opaque Sealer
Anvil Paints and Coatings
www.anvilpaints.com
(800) 822-6776

Advanced Concrete Stain Pigmented Sealer
Advanced Surfaces Inc.
www.advancedsurfaces.com
(800) 952-5980

C Construction

C.1 Surface Preparation

Prepare the concrete surfaces per the coating manufacturer's recommendations. Surfaces must be cleaned of grease, oil, and other possible bond breakers. At a minimum, prepare the concrete surfaces with a light sandblast or brush blast followed by an air blast to remove dust or loose particles. Surfaces must be dry for 24 hours prior to coating application.

C.2 Application

Apply a minimum of 2 coats under dry conditions per the manufacturer's recommendations. Follow the manufacturer's recommendation for coating thickness. Allow at least 12 hours between coats. Do not apply if rain is expected within 12 hours following application.

D Measurement

The department will measure Pigmented Concrete Surface Treatment by the square yard, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0180.01	Pigmented Concrete Surface Treatment	SY

Payment is full compensation for furnishing and applying the treatment; including surface preparation and cleaning.

ADDITIONAL SPECIAL PROVISION 4

Payment to all Subcontractors. Within 10 calendar days of receipt by a contractor of a progress payment for work performed, materials furnished, or materials stockpiled by a subcontractor, the contractor shall pay that subcontractor for all work satisfactorily performed and for all materials furnished or stockpiled.

The contractor agrees further to release retainage amounts to each subcontractor within 10 calendar days after the subcontractor's work is satisfactorily completed. In addition, whenever the Department reduces the contract retainage amount, within 10 calendar days of receipt by a contractor of a retainage payment, the contractor must reduce the total amount retained from subcontractors to no more than remains retained by the Department.

The contractor shall pay the subcontractor within the time frames described above unless the contractor complies with both of the following within 10 calendar days of receiving the Department's progress payment:

- 1) The contractor notifies the subcontractor in writing that the work is not satisfactorily completed.
- 2) The contractor requests approval from the Department to delay payment because the subcontractor has not satisfactorily completed the work.

The contractor's request for approval should include the written notification to the subcontractor and shall provide sufficient documentation of good cause to assist the engineer in making a timely decision. If the engineer does not grant approval, the contractor shall pay the subcontractor within 10 calendar days of the Department's decision.

All subcontracting agreements made by a contractor shall include the above provisions and shall be binding on all contractors and subcontractors.

The contractor certifies compliance with the requirements of this Additional Special Provision by signing the contract. This clause applies to both DBE and non-DBE subcontractors.

ADDITIONAL SPECIAL PROVISION 6
ASP 6 - Modifications to the standard specifications

Make the following revisions to the 2013 edition of the standard specifications:

106.3.4.3.1 General

Replace paragraph two with the following effective with the November 2012 letting:

- (2) Required sampling and testing methodologies and documentation are specified in CMM chapter 8.
 - (3) If disputed, approval of materials and components, as well as acceptance of the work incorporating those materials or components, is subject to review under the QMP dispute resolution process.
-

107.17.3 Railroad Insurance Requirements

Replace the entire text with the following effective with the August 2012 letting:

- (1) If required by the special provisions, provide or arrange for a subcontractor to provide railroad protective liability insurance in addition to the types and limits of insurance required in 107.26. Keep railroad protective liability insurance coverage in force until completing all work, under or incidental to the contract, on the railroad right of way or premises of the railroad and until the department has accepted the work as specified in 105.11.2.4.
- (2) Provide railroad protective liability insurance coverage written as specified in 23 CFR part 646 subpart A. Provide a separate policy for each railroad owning tracks on the project. Ensure that the railroad protective liability insurance policies provide the following minimum limits of coverage:
 - 1. Coverage A, bodily injury liability and property damage liability; \$2 million per occurrence.
 - 2. Coverage B, physical damage to property liability; \$2 million per occurrence.
 - 3. An annual aggregate amount of \$6 million that shall apply separately to each policy renewal or extension.
- (3) Obtain coverage from insurance companies licensed to do business in Wisconsin that have an A.M. Best rating of A- or better. The cost of providing the required insurance coverage and limits is incidental to the contract. The department will make no additional or special payment for providing insurance.
- (4) Submit the following to each railroad owning tracks on the project as evidence of that railroad's respective coverage:
 - 1. A certificate of insurance for the types and limits of insurance specified in 107.26.
 - 2. The railroad protective liability insurance policy or other acceptable documentation to the railroad company.
- (5) Submit the following to the region as evidence of the required coverage:
 - 1. A copy of the letter to the railroad company transmitting the submittal documents specified in 107.17.3(4).
 - 2. A certificate of insurance for the required railroad protective liability coverages.
- (6) Do not begin work on the right of way or premises of the railroad company until the region receives the submittals specified in 107.17.3(5) and notification from the railroad company that the contractor has provided sufficient insurance information to begin work.
- (7) Notify the railroad and the region immediately upon cancellation or initiating cancellation, whichever is earlier, or any material change in coverage. Cease operations within 50 feet of the railroad right of way immediately if insurance is cancelled or reduced. Do not resume operations until the required coverage is in force.

460.2.8.3.1.4 Department Verification Testing Requirements

Replace paragraph four with the following effective with the December 2012 letting:

- (4) The department will randomly test each design mixture at the following minimum frequency:
- FOR TONNAGES TOTALING:
- Less than 501 tons no tests required
- From 501 to 5,000 tons..... one test
- More than 5,000 tons..... add one test for each additional 5,000-ton increment

501.2.1 Portland Cement

Replace paragraph one with the following effective with the March 2013 letting:

- (1) Use cement conforming to ASTM specifications as follows:
- Type I portland cement; ASTM C150.
 - Type II portland cement; ASTM C150.
 - Type III portland cement; ASTM C50, for high early strength.
 - Type IP portland-pozzolan cement; ASTM C595, except maximum loss on ignition is 2.0 percent.
 - Type IS portland blast-furnace slag cement; ASTM C595.
 - Type IL portland-limestone cement; ASTM C595, except maximum nominal limestone content is 10 percent with no individual test result exceeding 12.0 percent.

501.2.5.5 Sampling and Testing

Replace the entire text with the following effective with the January 2013 letting:

- (1) Sample and test aggregates for concrete according to the following:
- | | |
|--|---------------------------|
| Sampling aggregates | AASHTO T2 |
| Lightweight pieces in aggregate | AASHTO T113 |
| Material finer than No. 200 sieve | AASHTO T11 |
| Unit weight of aggregate | AASHTO T19 |
| Organic impurities in sands | AASHTO T21 |
| Sieve analysis of aggregates | AASHTO T27 |
| Effect of organic impurities in fine aggregate | AASHTO T71 |
| Los Angeles abrasion of coarse aggregate | AASHTO T96 |
| Freeze-thaw soundness of coarse aggregate..... | AASHTO T103 |
| Sodium sulfate soundness of aggregates..... | AASHTO T104 |
| Specific gravity and absorption of fine aggregate | AASHTO T84 |
| Specific gravity and absorption of coarse aggregate | AASHTO T85 |
| Flat & elongated pieces based on a 3:1 ratio..... | ASTM D4791 ^[1] |
| Sampling fresh concrete | AASHTO R60 |
| Making and curing concrete compressive strength test specimens | AASHTO T23 |
| Compressive strength of molded concrete cylinders | AASHTO T22 |

^[1] As modified in CMM 8-60.

501.2.6 Fly Ash

Replace paragraph three with the following effective with the March 2013 letting:

- (3) Test fly ash using a recognized laboratory, as defined in 501.2.2(1), starting at least 30 days before its proposed use, and continuing at ASTM-required frequencies as the work progresses. The manufacturer shall test the chemical and physical properties listed in tables 1 and 2 of ASTM C618 at the frequencies and by the test methods prescribed in ASTM C311.

501.3.1.1.1 Air-Entrained Concrete

Replace paragraph one with the following effective with the March 2013 letting:

- (1) Prepare air-entrained concrete with type I, IL, II, IS, or IP portland cement and sufficient air-entraining admixture to produce concrete with the air content specified in 501.3.2.4.

503.2.2 Concrete

Replace paragraph five with the following effective with the March 2013 letting:

- (5) Furnish prestressed concrete members cast from air-entrained concrete, except I-type girders may use non-air-entrained concrete. Use type I, IL, IS, , IP, II, or III portland cement. The contractor may replace up to 30 percent of type I, IL, II, or III portland cement with an equal weight of fly ash, slag, or a combination of fly ash and slag, except for prestressed box girders and slabs, the contractor shall replace 20-30 percent of the cement with fly ash, slag, or a combination of fly ash and slag. Ensure that fly ash conforms to 501.2.6 and slag conforms to 501.2.7. Use only one source and replacement rate for work under a single bid item. Use a department-approved air-entraining admixture conforming to 501.2.2 for air-entrained concrete. Use only size No. 1 coarse aggregate conforming to 501.2.5.4.

506.3.22 Shop Inspection

Replace paragraph one with the following effective with the July 2010 letting:

- (1) The engineer or an independent inspection agency under department contract may inspect all structural steel and miscellaneous metals furnished. The department will provide the contractor with monthly consultant inspection invoices and identify any quality deficiencies at the fabrication facility.

506.5 Payment

Add paragraph nine as follows effective with the June 2010 letting:

- (9) The department will limit costs for inspections conducted under 506.3.2 to \$0.05 per pound of material and deduct costs in excess of that amount from payment due the contractor. The department will determine costs for in-house inspections based on hourly rates for department staff plus overhead and use invoiced costs for contracted-out inspections. The department will administer deductions for the contractor's share of the total inspection cost under the Excess Costs For Fabrication Shop Inspection administrative item.

507.2.2.1 General

Replace paragraph four with the following effective with the December 2012 letting:

- (4) Ensure that there are no unsound knots or knot holes. Also ensure that there are no tight knots of a diameter exceeding one-quarter of the greater dimension at the point where they occur. Measure a knot by taking its diameter at right angles to the length of the timber. Ensure that the sum of sizes of all knots in any one-foot length does not exceed 2 times the size of the largest allowed single knot. The engineer will treat cluster knots as if they were a single knot. A cluster knot is 2 or more knots grouped together, with the fibers of the wood deflected around the entire unit.

512.3.1 Driving and Cutting Off

Replace the entire text with the following effective with the December 2012 letting:

512.3.1.1 General

- (1) Coordinate driving operations to prevent damage or displacement of concrete in substructure units or damage to adjacent facilities due to vibrations.
- (2) Drive sheeting with a variation of 1/4 inch or less per foot from the vertical or from the batter the plans show. Ensure that the sheetpiles are within 6 inches of the plan position after driving. Do not damage sheetpiles attempting to correct for misalignment.

- (3) Remove and replace, or otherwise correct, sheetpiles the engineer deems unacceptable under 105.3. Submit details of planned corrections to the engineer for review and approval before initiating any corrective actions.
- (4) Drive sheetpiles to or beyond the required tip elevation the plans show.

512.3.1.2 Driving System

- (1) Furnish a sheetpile driving system capable of driving the sheetpiles to the required minimum tip elevation the plans show.
- (2) The engineer may order the contractor to remove a pile driving system component from service if it causes insufficient energy transfer or damages the sheetpiles. Do not return a component to service until the engineer determines that it has been satisfactorily repaired or adjusted.
- (3) Drive sheetpiles with diesel, air, steam, gravity, hydraulic, or vibratory hammers.

512.3.1.3 Cut-Offs

- (1) Cut off sheetpiles at the elevations the plans show or as the engineer directs. Pile cut-offs become the property of the contractor. Dispose of cut-offs not incorporated into the work.

518.2.1 General

Replace paragraph one with the following effective with the March 2013 letting:

- (1) Furnish portland cement and water as specified in 501.2. Unless the engineer allows an alternate, use either type I, IL, IS, , or IP portland cement.

526.3.3 Temporary Structures

Replace paragraphs two through four with the following effective with the January 2013 letting:

- (2) Inspect temporary structures conforming to the National Bridge Inspection Standards (NBIS) and the department's structure inspection manual before opening to traffic. Perform additional inspections, as the department's structure inspection manual requires, based on structure type and time in service. Submit inspection reports on department form DT2007 to the engineer and electronic copies to the department's bureau of structures maintenance section. Ensure that a department-certified active team leader, listed online in the department's highway structures information system (HSIS), performs the inspections.
- (3) Maintain temporary structures and approaches in place until no longer needed. Unless the engineer directs otherwise, completely remove and dispose of as specified in 203.3.4. Contractor-furnished materials remain the contractor's property upon removal.

614.2.5 Wood Posts and Offset Blocks

Retitle and replace the entire text with the following effective with the July 2012 letting:

614.2.5 Posts and Offset Blocks

614.2.5.1 Wood Posts and Offset Blocks

- (1) Furnish sawed posts and offset blocks of one of the following species:

Douglas fir	Southern pine	Ponderosa pine	Jack pine	White pine
Red pine	Western hemlock	Western larch	Hem-fir	Oak
- (2) Ensure that posts are the size the plans show and conform to the nominal and minimum dimensions tabulated in 507.2.2.3. The contractor does not have to surface the posts. Provide posts of the net length the plans show after setting and cut off.
- (3) Use stress graded posts rated at 1200 psi f_b or higher. Determine the stress grade rating for douglas fir, western larch, and southern pine as specified in 507.2.2.4.
- (4) For hem-fir, hemlock, red pine, white pine, jack pine, ponderosa pine, and oak conform to the following:

TABLE 614-1 PROPERTIES FOR WOOD POSTS AND BLOCKS

SPECIES			WESTERN HEMLOCK, HEM-FIR, RED PINE, WHITE PINE, JACK PINE, PONDEROSA PINE		OAK	
MAXIMUM SLOPE OF GRAIN			1 in 15		1 in 12	
NOMINAL WIDTH OF FACE			6"	8"	6"	8"
SHAKES, CHECKS, AND SPLITS	GREEN		1"	1 3/8"	2 3/8"	3 1/8"
	SEASONED		1 1/2"	2"	2 5/8"	3 1/2"
MAXIMUM WANE			1"	1 3/8"	1 1/8"	1 5/8"
MAXIMUM ALLOWABLE KNOTS	NARROW FACE	MIDDLE 1/3 OF LENGTH	1 3/8"	1 5/8"	2 1/8"	2 3/8"
		END ^[1]	2 3/4"	3 1/4"	4 1/4"	4 3/4"
		SUM IN MIDDLE 1/2 OF LENGTH ^[2]	11"	13"	17"	19
	WIDE FACE	EDGE KNOT N MIDDLE 1/3 OF LENGTH	1 3/8"	1 5/8"		
		EDGE KNOT AT END ^[1]	2 3/4" 7	3 1/4"		
		CENTERLINE	1 3/8"	1 7/8"	2 1/4"	2 7/8"
		SUM IN MIDDLE 1/2 OF LENGTH	5 1/2"	7 1/2"	9"	11 1/2"

^[1] But do not exceed the maximum allowable knot on the centerline of the wide face of the same piece.

^[2] But do not exceed 4 times the maximum allowable knot on the centerline of the wide face of the same piece.

- (5) Pressure treat posts and offset blocks as specified in 507.2.2.6. Use one of the oil-soluble preservatives or chromated copper arsenate conforming to 507.2.3. Use the same material for offset blocks and posts and treat material used in each continuous installation with the same type of preservative.

614.2.5.2 Steel Posts

- (1) Furnish steel posts conforming to AASHTO M270 Grade 36 and galvanized according to AASTHO M111.

614.2.5.3 Plastic Offset Blocks

- (1) Furnish plastic offset blocks from the department's approved products list.

614.3.1 General

Replace the entire text with the following effective with the July 2012 letting:

- (1) Paint the ends of cut-off galvanized posts, rail, bolts, cut or drilled surfaces of galvanized components, and areas of damaged zinc coating with 2 coats of zinc dust/zinc oxide paint. Clean the damaged and adjacent areas thoroughly before applying paint.
- (2) Apply 2 coats of wood preservative to cut surfaces of wood components. Use the same preservative originally used to treat that component or use a 2-percent solution of copper naphthenate conforming to AWWA Standard P8 or P36.

614.3.2.1 Installing Posts

Replace paragraph four with the following effective with the July 2012 letting:

- (4) Cut post tops to the finished elevation the plans show.

628.2.13 Rock Bags

Replace paragraph one with the following effective with the November 2012 letting:

- (1) Furnish rock bags made of a porous, ultraviolet resistant, high-density polyethylene or geotextile fabric that will retain 70% of its original strength after 500 hours of exposure according to ASTM D4355 and a minimum in-place filled size of 18-inches long by 12-inches wide by 6-inches high. Ensure that the fabric conforms to the following:

TEST REQUIREMENT	METHOD	VALUE
Minimum Tensile	ASTM D4632	
Machine direction		70 lb minimum
Cross direction		40 lb minimum
Elongation	ASTM D4632	
Machine direction		20% minimum
Cross direction		10 % min
Puncture	ASTM 4833	65 lbs minimum
Minimum Apparent Opening		0.0234 inches (No. 30 sieve)
Maximum Apparent Opening		0.0787 inches (No. 10 sieve)

639.2.1 General

Replace paragraph two with the following effective with the March 2013 letting:

- (2) For grout use fine aggregate conforming to 501.2.5.3 and type I, IL, IS, or IP portland cement.

649.3.1 General

Replace paragraphs three and four with the following effective with the March 2013 letting:

- (3) For pavements open to all traffic, apply centerline and no-passing barrier line markings as follows:
- On intermediate pavement layers, including milled surfaces, on the same day the pavement is placed or milled.
 - On the upper layer of pavement, on the same day the pavement is placed unless the contractor applies permanent marking on the same day the pavement is placed.

If weather conditions preclude same-day application, apply as soon as weather allows. Do not resume next-day construction operations until these markings are completed unless the engineer allows otherwise.

- (4) If required to apply no passing zone temporary pavement marking, reference the beginning and end of all existing no-passing barrier lines. Apply temporary no-passing barrier lines at those existing locations. If the contract contains the Locating No-Passing Zones bid item, relocate the no-passing zones as specified in section 648 for permanent marking.

701.4.2 Verification Testing

Replace paragraph two with the following effective with the December 2012 letting:

- (2) The department will sample randomly at locations independent of the contractor's QC tests and use separate equipment and laboratories. The department will conduct a minimum of one verification test for each 5 contractor QC tests unless specific QMP provisions specify otherwise.

715.2.3.1 Pavements

Replace paragraph two with the following effective with the March 2013 letting:

- (2) Provide a minimum cement content of 565 pounds per cubic yard, except if using type I, IL, or III portland cement in a mix where the geologic composition of the coarse aggregate is primarily igneous or metamorphic materials, provide a minimum cement content of 660 pounds per cubic yard.

715.3.1.3 Department Verification Testing

Replace paragraph one with the following effective with the December 2012 letting:

- (1) The department will perform verification testing as specified in 701.4.2 except as follows:
 - Air content, slump, and temperature: a minimum of 1 verification test per lot.
 - Compressive strength: a minimum of 1 verification test per lot.

Errata

Make the following corrections to the 2013 edition of the standard specifications:

102.12 Public Opening of Proposals

Correct 102.12(1) errata by changing htm to shtm in the web link.

- (1) The department will publicly open proposals at the time and place indicated in the notice to contractors. The department will post the total bid for each proposal on the Bid Express web site beginning at 9:30 AM except as specified in 102.8. If a proposal has no total bid shown, the department will not post the bid. After verification for accuracy under 103.1, the department will post bid totals on the department's HCCI web site.

<http://roadwaystandards.dot.wi.gov/hcci/bid-letting/index.shtm>

107.22 Contractor's Responsibility for Utility Facilities, Property, and Services

Correct errata by eliminating references to the department. Costs are determined by statute.

- (3) If the contractor damages or interrupts service, the contractor shall notify the utility promptly. Coordinate and cooperate with the utility in the repair of the facility. Determine who is responsible for repair costs according to Wisconsin statutes 66.0831 and 182.0175(2).
-

204.3.2.2 Removing Items

Correct errata by changing the reference from 490.3.2 to 490.3.

- (5) Under the Removing Asphaltic Surface Milling bid item, remove and dispose of existing asphaltic pavement or surfacing by milling at the location and to the depth the plans show. Mill the asphaltic pavement or surfacing as specified for milling salvaged asphaltic pavement in 490.3.
-

501.2.9 Concrete Curing Materials.

Correct errata by changing AASHTO M171 to ASTM C171.

- (4) Furnish polyethylene-coated burlap conforming to ASTM C171 for white burlap-polyethylene sheets.
-

506.2.6.5.2 Pad Construction

Correct errata by changing ASTM A570 to ASTM A1011.

- (4) For the internal steel plates use rolled mild steel conforming to ASTM A36, or ASTM A1011 grade
-

512.3.3 Painting

Correct errata by changing 511.3.5 to 550.3.11.3.

- (1) Paint permanent steel sheet piling as specified for painting steel piling in 550.3.11.3.

513.2.2.8 Toggle BoltsCorrect errata by changing ASTM A570 to ASTM A1011.

- (1) Use toggle bolts made of steel, conforming to the plans. Make the assembly from the material specified below:

Toggle bolt and pin Cold finished steel heat-treated Brinell 311-363 ASTM A354.
 Toggle washer Hot rolled steel ASTM A1011. Manufacturer's standard washer.
 Spacer nut Grade 1213, ASTM A108. Cold finished steel heat-treated ASTM A325.

660.2.1 GeneralCorrect errata by changing section 511 to 550.

- (1) Furnish materials conforming to the following:

Concrete section 501
 Concrete bridges section 502
 Luminaires section 659
 Steel piling section 550
 Steel reinforcement..... section 505

660.3.2.3 Pile Type FoundationsCorrect errata by changing section 511 to 550.

- (1) Drive piles as specified in for steel piling in section 550.

701.3 Contractor TestingCorrect errata by updating AASHTO T141 to AASHTO R60 and changing AASHTO T309 to ASTM C1064.

- (1) Perform contract required QC tests for samples randomly located according to CMM 8-30. Also perform other tests as necessary to control production and construction processes, and additional testing enumerated in the contractor's quality control plan or that the engineer directs. Use test methods as follows:

TABLE 701-2 TESTING STANDARDS

TEST	TEST STANDARD
Washed P 200 analysis	AASHTO T11 ^[1]
Sieve analysis of fine and coarse aggregate	AASHTO T27 ^[1]
Aggregate moisture	AASHTO T255 ^[1]
Sampling freshly mixed concrete	AASHTO R60
Air content of fresh concrete	AASHTO T152 ^[2]
Concrete slump	AASHTO T119 ^[2]
Concrete temperature	ASTM C1064
Concrete compressive strength	AASHTO T22
Making and curing concrete cylinders	AASHTO T23
Standard moist curing for concrete cylinders	AASHTO M201

^[1] As modified in CMM 8-60.

^[2] As modified in CMM 8-70.

ADDITIONAL SPECIAL PROVISION 7

- A. Reporting 1st Tier and DBE Payments During Construction
1. Comply with reporting requirements specified in the department's Civil Rights Compliance, Contractor's User Manual, Sublets and Payments.
 2. Report payments to all DBE firms within 10 calendar days of receipt of a progress payment by the department or a contractor for work performed, materials furnished, or materials stockpiled by a DBE firm. Report the payment as specified in A(1) for all work satisfactorily performed and for all materials furnished or stockpiled.
 3. Report payments to all first tier subcontractor relationships within 10 calendar days of receipt of a progress payment by the department for work performed. Report the payment as specified in A(1) for all work satisfactorily performed.
 4. All tiers shall report payments as necessary to comply with the DBE payment requirement as specified in A(2).
 5. Require all first tier relationships, DBE firms and all other tier relationships necessary to comply with the DBE payment requirement in receipt of a progress payment by contractor to acknowledge receipt of payment as specified in A(1), (2), (3) and (4).
 6. All agreements made by a contractor shall include the provisions in A(1), (2), (3), (4) and (5), and shall be binding on all first tier subcontractor relationships and all contractors and subcontractors utilizing DBE firms on the project.
- B. Costs for conforming to this special provision are incidental to the contract.

ADDITIONAL SPECIAL PROVISION 9
Electronic Certified Payroll Submittal

(1) Use the department's Civil Rights Compliance System (CRCS) to submit certified payrolls electronically. Details are available online through the department's highway construction contractor information (HCCI) site on the Labor, Wages, and EEO Information page at:

<http://roadwaystandards.dot.wi.gov/hcci/labor-wages-eeo/index.shtm>

(2) Ensure that all tiers of subcontractors, as well as all trucking firms, submit their weekly certified payrolls electronically through CRCS. These payrolls are due within seven calendar days following the close of the payroll period. Every firm providing physical labor towards completing the project is a subcontractor under this special provision.

(3) Upon receipt of contract execution, promptly make all affected firms aware of the requirements under this special provision and arrange for them to receive CRCS training as they are about to begin payrolls. The department will provide training either in a classroom setting at one of our regional offices or by telephone. Contact Tess Mulrooney at 608-267-4489 to schedule the training.

(4) The department will reject all paper submittals of forms DT-1816 and DT-1929 for information required under this special provision. All costs for conforming to this special provision are incidental to the contract.

(5) Firms wishing to export payroll data from their computer system into CRCS should have their payroll coordinator send several sample electronic files to Tess two months before a payroll needs to be submitted. Not every contractor's payroll system is capable of producing export files. For details, see pages 17-22 of the CRCS System Background Information manual available online on the Labor, Wages, and EEO Information page at:

<http://roadwaystandards.dot.wi.gov/hcci/labor-wages-eeo/crc-basic-info.pdf>

Effective with September 2004 Letting

**WISCONSIN DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS AND TRANSPORTATION FACILITIES**

SUPPLEMENTAL REQUIRED CONTRACT PROVISIONS

- I. Wage Rates, Hours of labor and payment of Wages
- II. Payroll Requirements
- III. Postings at the Site of the Work
- IV. Affidavits
- V. Wage Rate Redistribution
- VI. Additional Classifications

I. WAGE RATES, HOURS OF LABOR AND PAYMENT OF WAGES

The schedule of "Minimum Wage Rates" attached hereto and made a part hereof furnishes the prevailing wage rates that have been determined pursuant to Section 103.50 of the Wisconsin Statutes. These wage rates are the minimum required to be paid to the various laborers, workers, mechanics and truck drivers employed by contractors and subcontractors on the construction work embraced by the contract and subject to prevailing hours and wages under Section 103.50, Stats. If necessary to employ laborers, workers, mechanics or truck drivers whose classification is not listed on the schedule, they shall be paid at rates conformable to those listed for similar classifications. Apprentices shall be paid at rates not less than those prescribed in their state indenture contracts.

While the wage rates shown are the minimum rates required by the contract to be paid during its life, this is not a representation that labor can be obtained at these rates. It is the responsibility of bidders to inform themselves as to the local labor conditions and prospective changes or adjustments of wage rates. No increase in the contract price shall be allowed or authorized on account of the payment of wage rates in excess of those listed herein.

Pursuant to Section 103.50 of the Wisconsin Statutes, the prevailing hours of labor have been determined to be up to 10 hours per day and 40 hours per calendar week Monday through Friday. If any laborer, worker, mechanic or truck driver is permitted or required to work more than the prevailing number of hours per day or per calendar week on this contract, they shall be paid for all hours in excess of the prevailing hours at a rate of at least one and one-half (1 1/2) times their hourly rate of pay. All work on Saturday, Sunday and the following holidays is to be paid at time and a half: (1) January 1, (2) the last Monday in May, (3) July 4, (4) the first Monday in September, (5) the fourth Thursday in November, (6) December 25, (7) the day before if January 1, July 4 or December 25 falls on a Saturday and (8) the day following if January 1, July 4 or December 25 falls on a Sunday.

All laborers, workers, mechanics and truck drivers shall be paid unconditionally not less often than once a week. Persons who own and operate their own trucks must receive the prevailing truck driver rate for the applicable type of truck (i.e. 2 axle, 3 or more axle, articulated, eculid or dumptor) he or she operates, plus an agreed upon amount for the use of his or her truck. Every owner-operator MUST be paid separately for their driving and for the use of their truck.

For those projects subject to the requirements of the Davis-Bacon Act, the Secretary of Labor will also have determined "Minimum Wage Rates" for work to be performed under the contract. These rates are, for all or most of the labor, worker, mechanic or truck driver classifications, identical to those established under Section 103.50 of the Wisconsin Statutes. In the event the rates are not identical, the higher of the two rates will govern.

II. PAYROLL REQUIREMENTS

All contractors and subcontractors must submit weekly Certified Payrolls and Compliance Statement verifying that all laborers, workers, mechanics and truck drivers working on the project have been paid the prevailing wage rates for all work performed under the contract required by Section 103.50 of the Wisconsin Statutes.

III. POSTINGS AT THE SITE OF THE WORK

In addition to the required postings furnished by the Department, the contractor shall post the following in at least one conspicuous place at the site of work:

- a. "NOTICE TO EMPLOYEES," which provides information required to be posted by the provisions of Section 103.50 of the Wisconsin Statutes.
- b. A copy of the State of Wisconsin Minimum Wages Rates. (Four pages.)
- c. A copy of the contractor's Equal Employment Opportunity Policy.
- d. On any project involving federal aid, in addition to the furnished postings, the contractor shall post a copy of the "Davis-Bacon Act, Minimum Wage Rates". (Three pages.)

IV. WAGE RATE REDISTRIBUTION

The amount specified as the hourly basic rate of pay and the amount(s) specified as the fringe benefit contribution(s), for all classes of laborers, workers, mechanics or truck drivers may be redistributed, when necessary, to conform to those specified in any applicable collective bargaining agreement, provided that both parties to such agreement

request and receive the approval for any such redistribution from both the Department of Transportation and the Department of Workforce Development prior to the implementation of such redistribution.

V. ADDITIONAL CLASSIFICATIONS

Any unlisted laborer or mechanic classification that is needed to perform work on this project, and is not included within the scope of any of the classifications listed in the application prevailing wage rate determination, may be added after award only if all of the following criteria have been met:

1. The affected employer(s) must make a written request to WisDOT Central Office to utilize the unlisted classification on this project.
2. The request must indicate the scope of the work to be performed by the unlisted classification and must indicate the proposed wage/fringe benefit package that the unlisted classification is to receive.
3. The work to be performed by the unlisted classification must not be performed by a classification that is included in the applicable prevailing wage rate determination.
4. The unlisted classification must be commonly employed in the area where the project is located.
5. The proposed wage/fringe benefit package must bear a reasonable relationship to those set forth in the applicable prevailing wage rate determination.
6. The request should be made prior to the actual performance of the work by the unlisted classification.
7. DWD must approve the use of the unlisted classification and the proposed wage/fringe benefit package. USDOL also must approve the use of the unlisted classification and the proposed wage/fringe benefit package on federal aid projects.
8. WisDOT and DWD may amend the proposed wage/fringe benefit package, as deemed necessary, and may set forth specific employment ratios and scope of work requirements in the approval document.

The approved wage/fringe benefit package shall be paid to all laborers, workers, mechanics or truck drivers performing work within the scope of that performed by the unlisted classification, from the first day on which such work is performed. In the event that work is performed by the unlisted classification prior to approval, the wage/fringe benefit package to be paid for such work must be in conformance with the wage/fringe

benefit package approved for such work. Under this arrangement a retroactive adjustment in wages and/or fringe benefits may be required to be made to the affected laborers, workers, mechanics or truck drivers by the affected employer(s).

**ANNUAL PREVAILING WAGE RATE DETERMINATION
FOR ALL STATE HIGHWAY PROJECTS
LA CROSSE COUNTY**

Compiled by the State of Wisconsin - Department of Workforce Development
for the Department of Transportation
Pursuant to s. 103.50, Stats.
Issued on April 1, 2012

CLASSIFICATION: Contractors are required to call the Department of Workforce Development if there are any questions regarding the proper trade or classification to be used for any worker on a public works project.

OVERTIME: Time and one-half must be paid for all hours worked over 10 hours per day and 40 hours per calendar week and for all hours worked on Saturday, Sunday and the following six (6) holidays: January 1; the last Monday in May; July 4; the 1st Monday in September; the 4th Thursday in November; December 25; the day before if January 1, July 4 or December 25 falls on a Saturday; the day following if January 1, July 4 or December 25 falls on a Sunday.

FUTURE INCREASE: If indicated for a specific trade or occupation, the full amount of such increase MUST be added to the "TOTAL" indicated for such trade or occupation on the date(s) such increase(s) becomes effective.

PREMIUM PAY: If indicated for a specific trade or occupation, the full amount of such pay MUST be added to the "HOURLY BASIC RATE OF PAY" indicated for such trade or occupation, whenever such pay is applicable.

SUBJOURNEY: Wage rates may be available for some of the classifications indicated below. Any employer that desires to use any subjourney classification on a project MUST request the applicable wage rate from the Department of Workforce Development PRIOR to the date such classification is used on such project. Form ERD-10880 is available for this purpose and can be obtained by writing to the Department of Workforce Development, Equal Rights Division, P.O. Box 8928, Madison, WI 53708.

<u>TRADE OR OCCUPATION</u>	<u>HOURLY BASIC RATE OF PAY</u>	<u>HOURLY FRINGE BENEFITS</u>	<u>TOTAL</u>
	\$	\$	\$
Bricklayer, Blocklayer or Stonemason	32.66	15.92	48.58
Carpenter	29.06	15.16	44.22
Cement Finisher	29.91	16.45	46.36
Future Increase(s): Add \$1.86 on 6/1/12; Add \$1.87 on 6/1/13; Add \$1.87 on 6/1/14; Add \$1.87 on 6/1/15; Add \$1.75 on 6/ 1/ 16.			
Premium Pay: DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.40/hr when the Wisconsin Department of Transportation or responsible governing agency requires that work be performed at night under artificial illumination with traffic control and the work is completed after sunset and before sunrise.			
Electrician	37.25	14.05	51.30
Fence Erector	35.62	0.00	35.62
Ironworker	30.90	19.11	50.01
Line Constructor (Electrical)	35.97	18.08	54.05
Painter	20.85	7.34	28.19
Pavement Marking Operator	26.04	13.16	39.20
Piledriver	28.11	23.37	51.48
Roofer or Waterproofer	18.95	11.88	30.83
Teledata Technician or Installer	17.25	4.94	22.19
Tuckpointer, Caulker or Cleaner	30.65	12.08	42.73
Underwater Diver (Except on Great Lakes)	36.20	18.81	55.01
Heavy Equipment Operator - ELECTRICAL LINE CONSTRUCTION ONLY	33.87	16.10	49.97
Light Equipment Operator -ELECTRICAL LINE CONSTRUCTION ONLY	28.78	16.21	44.99
Heavy Truck Driver - ELECTRICAL LINE CONSTRUCTION ONLY	25.18	13.07	38.25
Light Truck Driver - ELECTRICAL LINE CONSTRUCTION ONLY	23.38	12.48	35.86

<u>TRADE OR OCCUPATION</u>	<u>HOURLY BASIC RATE OF PAY</u>	<u>HOURLY FRINGE BENEFITS</u>	<u>TOTAL</u>
	\$	\$	\$
Groundman - ELECTRICAL LINE CONSTRUCTION ONLY	21.30	10.97	32.27

TRUCK DRIVERS

Single Axle or Two Axle	22.35	16.19	38.54
Future Increase(s): Add \$1.75/hr on 6/1/2012; Add \$1.85/hr on 6/1/2013. Premium Pay: DOT PREMIUM: Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day.			
Three or More Axle	22.50	16.19	38.69
Future Increase(s): Add \$1.75/hr on 6/1/2012; Add \$1.85/hr on 6/1/2013. Premium Pay: DOT PREMIUM: Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day.			
Articulated, Euclid, Dumptror, Off Road Material Hauler	24.91	15.63	40.54
Pavement Marking Vehicle	23.84	14.76	38.60
Shadow or Pilot Vehicle	24.76	15.35	40.11
Truck Mechanic	24.91	15.35	40.26

LABORERS

General Laborer	26.92	13.45	40.37
Future Increase(s): Add \$1.60/hr on 6/1/2012; Add \$1.70/hr on 6/1/2013; Add \$1.60/hr on 6/1/2014. Premium Pay: Add \$.10/hr for topman, air tool operator, vibrator or tamper operator (mechanical hand operated), chain saw operator and demolition burning torch laborer; Add \$.15/hr for bituminous worker (raker and luteman), formsetter (curb, sidewalk and pavement) and strike off man; Add \$.20/hr for blaster and powderman; Add \$.25/hr for bottomman; Add \$.35/hr for line and grade specialist; Add \$.45/hr for pipelayer. DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.25/hr for work on projects involving temporary traffic control setup, for lane and shoulder closures, when work under artificial illumination conditions is necessary as required by the project provisions (including prep time prior to and/or cleanup after such time period).			
Asbestos Abatement Worker	24.26	13.77	38.03
Landscaper	26.92	13.45	40.37
Future Increase(s): Add \$1.60/hr on 6/1/12; Add \$1.70/hr on 6/1/13; Add \$1.60/hr on 6/1/14. Premium Pay: DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.25/hr for work on projects involving temporary traffic control setup, for lane and shoulder closures, when work under artificial illumination conditions is necessary as required by the project provisions (including prep time prior to and/or cleanup after such time period).			
Flagperson or Traffic Control Person	21.40	14.00	35.40
Fiber Optic Laborer (Outside, Other Than Concrete Encased)	15.00	0.92	15.92
Railroad Track Laborer	23.96	9.48	33.44

HEAVY EQUIPMENT OPERATORS

Crane, Tower Crane, Pedestal Tower or Derrick, With Boom, Leads &/or Jib Lengths Measuring 176 Ft or Over; Crane, Tower Crane, Pedestal Tower or Derrick, With or Without Attachments, With a Lifting Capacity of Over 100 Tons, Self-Erecting Tower Crane With a Lifting Capacity Of Over 4,000 Lbs.,	34.22	18.90	53.12
--	-------	-------	-------

<u>TRADE OR OCCUPATION</u>	<u>HOURLY BASIC RATE OF PAY</u>	<u>HOURLY FRINGE BENEFITS</u>	<u>TOTAL</u>
	\$	\$	\$
Crane With Boom Dollies; Traveling Crane (Bridge Type). Future Increase(s): Add \$2/hr on 6/1/12; Add \$2/hr on 6/1/13; Add \$1.75/hr on 6/1/14. Premium Pay: DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.25/hr for work on projects involving temporary traffic control setup, for lane and shoulder closures, when work under artificial illumination conditions is necessary as required by the project provisions (including prep time prior to and/or cleanup after such time period).			
Backhoe (Track Type) Having a Mfgr.'s Rated Capacity of 130,000 Lbs. or Over; Caisson Rig; Crane, Tower Crane, Portable Tower, Pedestal Tower or Derrick, With Boom, Leads &/or Jib Lengths Measuring 175 Ft or Under; Crane, Tower Crane, Portable Tower, Pedestal Tower or Derrick, With or Without Attachments, With a Lifting Capacity of 100 Tons or Under, Self-Erecting Tower Crane With A Lifting Capacity Of 4,000 Lbs., & Under; Dredge (NOT Performing Work on the Great Lakes); Licensed Boat Pilot (NOT Performing Work on the Great Lakes); Pile Driver. Future Increase(s): Add \$2/hr on 6/1/12; Add \$2/hr on 6/1/13; Add \$1.75/hr on 6/1/14. Premium Pay: DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.25/hr for work on projects involving temporary traffic control setup, for lane and shoulder closures, when work under artificial illumination conditions is necessary as required by the project provisions (including prep time prior to and/or cleanup after such time period).	33.72	18.90	52.62
Air Track, Rotary or Percussion Drilling Machine &/or Hammers, Blaster; Asphalt Heater, Planer & Scarifier; Asphalt Milling Machine; Asphalt Screed; Automatic Subgrader (Concrete); Backhoe (Track Type) Having a Mfgr.'s Rated Capacity of Under 130,000 Lbs., Backhoe (Mini, 15,000 Lbs. & Under); Bituminous (Asphalt) Plant & Paver, Screed; Boatmen (NOT Performing Work on the Great Lakes); Boring Machine (Directional, Horizontal or Vertical); Bridge (Bidwell) Paver; Bulldozer or Endloader; Concrete Batch Plant, Batch Hopper; Concrete Breaker (Large, Auto, Vibratory/Sonic, Manual or Remote); Concrete Bump Cutter, Grinder, Planing or Grooving Machine; Concrete Conveyor System; Concrete Laser/Screed; Concrete Paver (Slipform); Concrete Pump, Concrete Conveyor (Rotec or Bidwell Type); Concrete Slipform Placer Curb & Gutter Machine; Concrete Spreader & Distributor; Crane (Carry Deck, Mini) or Truck Mounted Hydraulic Crane (10 Tons or Under); Crane With a Lifting Capacity of 25 Tons or Under; Forestry Equipment, Timbco, Tree Shear, Tub Grinder, Processor; Gradall (Cruz-Aire Type); Grader or Motor Patrol; Grout Pump; Hydro-Blaster (10,000 PSI or Over); Loading Machine (Conveyor); Material or Stack Hoist; Mechanic or Welder; Milling Machine; Post Hole Digger or Driver; Roller (Over 5 Ton); Scraper (Self Propelled or Tractor Drawn) 5 cu yds or More Capacity; Shoulder Widener; Sideboom; Skid Rig; Stabilizing or Concrete Mixer (Self-Propelled or 14S or Over); Straddle Carrier or Travel Lift; Tractor (Scraper, Dozer, Pusher, Loader); Tractor or Truck Mounted Hydraulic Backhoe; Trencher (Wheel Type or Chain Type); Tube Finisher; Tugger (NOT Performing Work on the Great Lakes); Winches & A- Frames. Future Increase(s): Add \$2/hr on 6/1/12; Add \$2/hr on 6/1/13; Add \$1.75/hr on 6/1/14. Premium Pay: DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.25/hr for work on projects involving temporary traffic control setup, for lane and shoulder closures, when work under artificial illumination conditions is necessary as required by the project provisions (including prep time prior to and/or cleanup after such time period).	33.22	18.90	52.12
Belting, Burlap, Texturing Machine; Broom or Sweeper; Compactor	32.96	18.90	51.86

<u>TRADE OR OCCUPATION</u>	<u>HOURLY BASIC RATE OF PAY</u>	<u>HOURLY FRINGE BENEFITS</u>	<u>TOTAL</u>
	\$	\$	\$
(Self-Propelled or Tractor Mounted, Towed & Light Equipment); Concrete Finishing Machine (Road Type); Environmental Burner; Farm or Industrial Type Tractor; Fireman (Asphalt Plant, Pile Driver & Derrick NOT Performing Work on the Great Lakes); Forklift; Greaser; Hoist (Tugger, Automatic); Jeep Digger; Joint Sawyer (Multiple Blade); Launch (NOT Performing Work on the Great Lakes); Lift Slab Machine; Mechanical Float; Mulcher; Power Subgrader; Robotic Tool Carrier (With or Without Attachments); Roller (Rubber Tire, 5 Ton or Under); Self Propelled Chip Spreader; Shouldering Machine; Skid Steer Loader (With or Without Attachments); Telehandler; Tining or Curing Machine. Future Increase(s): Add \$2/hr on 6/1/12; Add \$2/hr on 6/1/13; Add \$1.75/hr on 6/1/14. Premium Pay: DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.25/hr for work on projects involving temporary traffic control setup, for lane and shoulder closures, when work under artificial illumination conditions is necessary as required by the project provisions (including prep time prior to and/or cleanup after such time period).			
Air Compressor (&/or 400 CFM or Over); Air, Electric or Hydraulic Jacking System; Augers (Vertical & Horizontal); Automatic Belt Conveyor & Surge Bin; Boiler (Temporary Heat); Concrete Proportioning Plant; Crusher, Screening or Wash Plant; Generator (&/or 150 KW or Over); Heaters (Mechanical); High Pressure Utility Locating Machine (Daylighting Machine); Mudjack; Oiler; Prestress Machine; Pug Mill; Pump (3 Inch or Over) or Well Points; Rock, Stone Breaker; Screed (Milling Machine); Stump Chipper; Tank Car Heaters; Vibratory Hammer or Extractor, Power Pack. Future Increase(s): Add \$2/hr on 6/1/12; Add \$2/hr on 6/1/13; Add \$1.75/hr on 6/1/14. Premium Pay: DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.25/hr for work on projects involving temporary traffic control setup, for lane and shoulder closures, when work under artificial illumination conditions is necessary as required by the project provisions (including prep time prior to and/or cleanup after such time period).	32.67	18.90	51.57
Fiber Optic Cable Equipment.	26.00	0.65	26.65

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20130409001PROJECT(S):
1071-06-65FEDERAL ID(S):
N/A

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS

SECTION 0001 CONTRACT ITEMS

0010	203.0200 REMOVING OLD STRUCTURE (STATION) 01. 66'S'+45.05	LUMP	LUMP		.	
0020	203.0225.S DEBRIS CONTAINMENT (STRUCTURE) 01. B-32-55	LUMP	LUMP		.	
0030	203.0225.S DEBRIS CONTAINMENT (STRUCTURE) 02. B-32-56	LUMP	LUMP		.	
0040	204.0100 REMOVING PAVEMENT	8,350.000 SY	.		.	
0050	204.0165 REMOVING GUARDRAIL	850.000 LF	.		.	
0060	205.0100 EXCAVATION COMMON	4,324.000 CY	.		.	
0070	206.1000 EXCAVATION FOR STRUCTURES BRIDGES (STRUCTURE) 01. B-32-55	LUMP	LUMP		.	
0080	208.0100 BORROW	630.000 CY	.		.	
0090	208.1100 SELECT BORROW	533.000 CY	.		.	
0100	210.0100 BACKFILL STRUCTURE	230.000 CY	.		.	

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20130409001PROJECT(S):
1071-06-65FEDERAL ID(S):
N/A

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	213.0100 FINISHING ROADWAY (PROJECT) 01. 1071-06-65	1.000 EACH	.		.	
0120	305.0110 BASE AGGREGATE DENSE 3/4-INCH	385.000 TON	.		.	
0130	305.0120 BASE AGGREGATE DENSE 1 1/4-INCH	5,190.000 TON	.		.	
0140	311.0110 BREAKER RUN	210.000 TON	.		.	
0150	415.0100 CONCRETE PAVEMENT 10-INCH	6,370.000 SY	.		.	
0160	415.0410 CONCRETE PAVEMENT APPROACH SLAB	700.000 SY	.		.	
0170	415.6000.S ROUTE AND SEAL	2,225.000 LF	.		.	
0180	416.0610 DRILLED TIE BARS	165.000 EACH	.		.	
0190	416.0620 DRILLED DOWEL BARS	491.000 EACH	.		.	
0200	416.0750.S CONCRETE PAVEMENT PARTIAL DEPTH REPAIR JOINT REPAIR	96.000 LF	.		.	
0210	416.0752.S CONCRETE PAVEMENT PARTIAL DEPTH REPAIR CRACK REPAIR	96.000 LF	.		.	

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20130409001PROJECT(S):
1071-06-65FEDERAL ID(S):
N/A

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0220	465.0105 ASPHALTIC SURFACE	301.000 TON	.		.	
0230	465.0125 ASPHALTIC SURFACE TEMPORARY	1,080.000 TON	.		.	
0240	502.0100 CONCRETE MASONRY BRIDGES	492.000 CY	.		.	
0250	502.3100 EXPANSION DEVICE (STRUCTURE) 01. B-32-55	LUMP	LUMP		.	
0260	502.3100 EXPANSION DEVICE (STRUCTURE) 02. B-32-56	LUMP	LUMP		.	
0270	502.3200 PROTECTIVE SURFACE TREATMENT	3,100.000 SY	.		.	
0280	502.5005 MASONRY ANCHORS TYPE L NO. 5 BARS	364.000 EACH	.		.	
0290	505.0605 BAR STEEL REINFORCEMENT HS COATED BRIDGES	106,990.000 LB	.		.	
0300	506.2610 BEARING PADS ELASTOMERIC LAMINATED	14.000 EACH	.		.	
0310	506.3025 WELDED STUD SHEAR CONNECTORS 7/8X8-INCH	2,556.000 EACH	.		.	
0320	506.7000.S BEARING REPLACEMENT (STRUCTURE) 01. B-32-55	14.000 EACH	.		.	

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20130409001PROJECT(S):
1071-06-65FEDERAL ID(S):
N/A

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0330	509.0301 PREPARATION DECKS TYPE 1	62.000 SY	.		.	
0340	509.0302 PREPARATION DECKS TYPE 2	25.000 SY	.		.	
0350	509.0500 CLEANING DECKS	625.000 SY	.		.	
0360	509.1000 JOINT REPAIR	50.000 SY	.		.	
0370	509.1500 CONCRETE SURFACE REPAIR	80.000 SF	.		.	
0380	509.2000 FULL-DEPTH DECK REPAIR	5.000 SY	.		.	
0390	509.2500 CONCRETE MASONRY OVERLAY DECKS	142.000 CY	.		.	
0400	509.9020.S EPOXY CRACK SEALING	200.000 LF	.		.	
0410	516.0500 RUBBERIZED MEMBRANE WATERPROOFING	70.000 SY	.		.	
0420	517.0900.S PREPARATION AND COATING OF TOP FLANGES (STRUCTURE) 01. B-32-55	LUMP	LUMP		.	

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20130409001PROJECT(S):
1071-06-65FEDERAL ID(S):
N/A

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0430	517.3000.S STRUCTURE OVERCOATING CLEANING AND PRIMING (STRUCTURE) 01. B-32-55	LUMP	LUMP		.	
0440	517.3000.S STRUCTURE OVERCOATING CLEANING AND PRIMING (STRUCTURE) 02. B-32-56	LUMP	LUMP		.	
0450	517.4000.S CONTAINMENT AND COLLECTION OF WASTE MATERIALS (STRUCTURE) 01. B-32-55	LUMP	LUMP		.	
0460	517.4000.S CONTAINMENT AND COLLECTION OF WASTE MATERIALS (STRUCTURE) 02. B-32-56	LUMP	LUMP		.	
0470	520.4012 CULVERT PIPE TEMPORARY 12-INCH	748.000 LF	.		.	
0480	601.0409 CONCRETE CURB & GUTTER 30-INCH TYPE A	515.000 LF	.		.	
0490	603.8000 CONCRETE BARRIER TEMPORARY PRECAST DELIVERED	1,730.000 LF	.		.	
0500	603.8125 CONCRETE BARRIER TEMPORARY PRECAST INSTALLED	3,280.000 LF	.		.	
0510	604.9010.S SLOPE PAVING REPAIR CRUSHED AGGREGATE	48.000 CY	.		.	
0520	604.9015.S RESEAL CRUSHED AGGREGATE SLOPE PAVING	768.000 SY	.		.	

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20130409001PROJECT(S):
1071-06-65FEDERAL ID(S):
N/A

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0530	611.8115 ADJUSTING INLET COVERS	7.000 EACH	.		.	
0540	614.0150 ANCHOR ASSEMBLIES FOR STEEL PLATE BEAM GUARD	2.000 EACH	.		.	
0550	614.0200 STEEL THRIE BEAM STRUCTURE APPROACH	84.000 LF	.		.	
0560	614.0230 STEEL THRIE BEAM	100.000 LF	.		.	
0570	614.0905 CRASH CUSHIONS TEMPORARY	4.000 EACH	.		.	
0580	614.2300 MGS GUARDRAIL 3	450.000 LF	.		.	
0590	614.2500 MGS THRIE BEAM TRANSITION	40.000 LF	.		.	
0600	614.2610 MGS GUARDRAIL TERMINAL EAT	6.000 EACH	.		.	
0610	614.2620 MGS GUARDRAIL TERMINAL TYPE 2	3.000 EACH	.		.	
0620	619.1000 MOBILIZATION	1.000 EACH	.		.	
0630	623.0200 DUST CONTROL SURFACE TREATMENT	7,550.000 SY	.		.	

Wisconsin Department of Transportation

PAGE: 7

DATE: 02/01/13

REVISED:

SCHEDULE OF ITEMS

CONTRACT:
20130409001PROJECT(S):
1071-06-65FEDERAL ID(S):
N/A

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0640	624.0100 WATER	30.000 MGAL	.		.	
0650	625.0100 TOPSOIL	390.000 SY	.		.	
0660	625.0500 SALVAGED TOPSOIL	7,350.000 SY	.		.	
0670	628.1104 EROSION BALES	5.000 EACH	.		.	
0680	628.1504 SILT FENCE	3,080.000 LF	.		.	
0690	628.1520 SILT FENCE MAINTENANCE	3,080.000 LF	.		.	
0700	628.1905 MOBILIZATIONS EROSION CONTROL	3.000 EACH	.		.	
0710	628.1910 MOBILIZATIONS EMERGENCY EROSION CONTROL	2.000 EACH	.		.	
0720	628.2002 EROSION MAT CLASS I TYPE A	6,000.000 SY	.		.	
0730	628.2021 EROSION MAT CLASS II TYPE A	1,750.000 SY	.		.	
0740	628.7005 INLET PROTECTION TYPE A	5.000 EACH	.		.	

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20130409001PROJECT(S):
1071-06-65FEDERAL ID(S):
N/A

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0750	628.7010 INLET PROTECTION TYPE B	1.000 EACH	.		.	
0760	628.7015 INLET PROTECTION TYPE C	6.000 EACH	.		.	
0770	628.7504 TEMPORARY DITCH CHECKS	45.000 LF	.		.	
0780	628.7560 TRACKING PADS	2.000 EACH	.		.	
0790	629.0205 FERTILIZER TYPE A	1.000 CWT	.		.	
0800	630.0130 SEEDING MIXTURE NO. 30	30.000 LB	.		.	
0810	634.0614 POSTS WOOD 4X6-INCH X 14-FT	4.000 EACH	.		.	
0820	635.0300 SIGN SUPPORTS REPLACING BASE CONNECTION BOLTS	2.000 EACH	.		.	
0830	637.0101 SIGNS TYPE I	2,260.500 SF	.		.	
0840	637.0202 SIGNS REFLECTIVE TYPE II	84.000 SF	.		.	
0850	638.2601 REMOVING SIGNS TYPE I	16.000 EACH	.		.	

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20130409001PROJECT(S):
1071-06-65FEDERAL ID(S):
N/A

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0860	638.2602 REMOVING SIGNS TYPE II	5.000 EACH	.		.	
0870	638.3000 REMOVING SMALL SIGN SUPPORTS	4.000 EACH	.		.	
0880	642.5201 FIELD OFFICE TYPE C	1.000 EACH	.		.	
0890	643.0100 TRAFFIC CONTROL (PROJECT) 01. 1071-06-65	1.000 EACH	.		.	
0900	643.0300 TRAFFIC CONTROL DRUMS	19,330.000 DAY	.		.	
0910	643.0420 TRAFFIC CONTROL BARRICADES TYPE III	700.000 DAY	.		.	
0920	643.0705 TRAFFIC CONTROL WARNING LIGHTS TYPE A	1,240.000 DAY	.		.	
0930	643.0715 TRAFFIC CONTROL WARNING LIGHTS TYPE C	6,550.000 DAY	.		.	
0940	643.0800 TRAFFIC CONTROL ARROW BOARDS	120.000 DAY	.		.	
0950	643.0900 TRAFFIC CONTROL SIGNS	4,920.000 DAY	.		.	
0960	643.0910 TRAFFIC CONTROL COVERING SIGNS TYPE I	2.000 EACH	.		.	

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20130409001PROJECT(S):
1071-06-65FEDERAL ID(S):
N/A

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0970	643.0920 TRAFFIC CONTROL COVERING SIGNS TYPE II	1.000 EACH	.		.	
0980	643.1050 TRAFFIC CONTROL SIGNS PCMS	2.000 DAY	.		.	
0990	643.2000 TRAFFIC CONTROL DETOUR (PROJECT) 01. 1071-06-65	1.000 EACH	.		.	
1000	643.3000 TRAFFIC CONTROL DETOUR SIGNS	240.000 DAY	.		.	
1010	646.0106 PAVEMENT MARKING EPOXY 4-INCH	6,200.000 LF	.		.	
1020	646.0600 REMOVING PAVEMENT MARKINGS	17,965.000 LF	.		.	
1030	646.0871.S PAVEMENT MARKING WET REFLECTIVE TAPE 4-INCH	1,650.000 LF	.		.	
1040	646.0873.S PAVEMENT MARKING WET REFLECTIVE TAPE 8-INCH	650.000 LF	.		.	
1050	647.0746 PAVEMENT MARKING DIAGONAL EPOXY 24-INCH	125.000 LF	.		.	
1060	649.0400 TEMPORARY PAVEMENT MARKING REMOVABLE TAPE 4-INCH	28,535.000 LF	.		.	
1070	650.4000 CONSTRUCTION STAKING STORM SEWER	2.000 EACH	.		.	

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20130409001PROJECT(S):
1071-06-65FEDERAL ID(S):
N/A

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
1080	650.4500 CONSTRUCTION STAKING SUBGRADE	860.000 LF	.		.	
1090	650.7000 CONSTRUCTION STAKING CONCRETE PAVEMENT	860.000 LF	.		.	
1100	650.9910 CONSTRUCTION STAKING SUPPLEMENTAL CONTROL (PROJECT) 01. 1071-06-65	LUMP	LUMP		.	
1110	650.9920 CONSTRUCTION STAKING SLOPE STAKES	860.000 LF	.		.	
1120	652.0130 CONDUIT RIGID METALLIC 2 1/2-INCH	1,040.000 LF	.		.	
1130	652.0225 CONDUIT RIGID NONMETALLIC SCHEDULE 40 2-INCH	300.000 LF	.		.	
1140	653.0135 PULL BOXES STEEL 24X36-INCH	6.000 EACH	.		.	
1150	690.0250 SAWING CONCRETE	565.000 LF	.		.	
1160	715.0415 INCENTIVE STRENGTH CONCRETE PAVEMENT	2,121.000 DOL	1.00000		2121.00	
1170	715.0502 INCENTIVE STRENGTH CONCRETE STRUCTURES	2,952.000 DOL	1.00000		2952.00	
1180	SPV.0060 SPECIAL 01. INLET REPAIR	7.000 EACH	.		.	

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20130409001PROJECT(S):
1071-06-65FEDERAL ID(S):
N/A

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
1190	SPV.0105 SPECIAL 01. WELD INSPECTION STRUCTURE B-32-55	LUMP	LUMP		.	
1200	SPV.0180 SPECIAL 01. PIGMENTED CONCRETE SURFACE TREATMENT	270.000 SY	.		.	
	SECTION 0001 TOTAL				.	
	TOTAL BID				.	

PLEASE ATTACH SCHEDULE OF ITEMS HERE