

HIGHWAY WORK PROPOSAL

Wisconsin Department of Transportation
DT1502 10/2010 s.66.29(7) Wis. Stats.

Proposal Number:

11

COUNTY	STATE PROJECT ID	FEDERAL PROJECT ID	PROJECT DESCRIPTION	HIGHWAY
Washington	1410-12-70		Washington St, City of West Bend, Trenton Road to 4000' E Of Oak Road	STH 33

This proposal, submitted by the undersigned bidder to the Wisconsin Department of Transportation, is in accordance with the advertised request for proposals. The bidder is to furnish and deliver all materials, and to perform all work for the improvement of the designated project in the time specified, in accordance with the appended Proposal Requirements and Conditions.

Proposal Guaranty Required, \$ 75,000.00 Payable to: Wisconsin Department of Transportation	Attach Proposal Guaranty on back of this PAGE.
Bid Submittal Due Date: December 10, 2013 Time (Local Time): 9:00 AM	Firm Name, Address, City, State, Zip Code
Contract Completion Time Twenty-five (25) Working Days	SAMPLE NOT FOR BIDDING PURPOSES
Assigned Disadvantaged Business Enterprise Goal 0%	This contract is exempt from federal oversight.

This certifies that the undersigned bidder, duly sworn, is an authorized representative of the firm named above; that the bidder has examined and carefully prepared the bid from the plans, Highway Work Proposal, and all addenda, and has checked the same in detail before submitting this proposal or bid; and that the bidder or agents, officer, or employees have not, either directly or indirectly, entered into any agreement, participated in any collusion, or otherwise taken any action in restraint of free competitive bidding in connection with this proposal bid.

Do not sign, notarize, or submit this Highway Work Proposal when submitting an electronic bid on the Internet.

Subscribed and sworn to before me this date _____

(Signature, Notary Public, State of Wisconsin)

(Print or Type Name, Notary Public, State Wisconsin)

(Date Commission Expires)

Notary Seal

(Bidder Signature)

(Print or Type Bidder Name)

(Bidder Title)

For Department Use Only

Type of Work Asphaltic surface milling, grading, base aggregate, HMA pavement, pipe culverts, pavement marking and permanent signing.	
Notice of Award Dated	Date Guaranty Returned

**PLEASE ATTACH
PROPOSAL GUARANTY HERE**

Effective with November 2007 Letting

PROPOSAL REQUIREMENTS AND CONDITIONS

The bidder, signing and submitting this proposal, agrees and declares as a condition thereof, to be bound by the following conditions and requirements.

If the bidder has a corporate relationship with the proposal design engineering company, the bidder declares that it did not obtain any facts, data, or other information related to this proposal from the design engineering company that was not available to all bidders.

The bidder declares that they have carefully examined the site of, and the proposal, plans, specifications and contract forms for the work contemplated, and it is assumed that the bidder has investigated and is satisfied as to the conditions to be encountered, as to the character, quality, and quantities of work to be performed and materials to be furnished, and as to the requirements of the specifications, special provisions and contract. It is mutually agreed that submission of a proposal shall be considered conclusive evidence that the bidder has made such examination.

The bidder submits herewith a proposal guaranty in proper form and amount payable to the party as designated in the advertisement inviting proposals, to be retained by and become the property of the owner of the work in the event the undersigned shall fail to execute the contract and contract bond and return the same to the office of the engineer within fourteen (14) days after having been notified in writing to do so; otherwise to be returned.

The bidder declares that they understand that the estimate of quantities in the attached schedule is approximate only and that the attached quantities may be greater or less in accordance with the specifications.

The bidder agrees to perform the said work, for and in consideration of the payment of the amount becoming due on account of work performed, according to the unit prices bid in the following schedule, and to accept such amounts in full payment of said work.

The bidder declares that all of the said work will be performed at their own proper cost and expense, that they will furnish all necessary materials, labor, tools, machinery, apparatus, and other means of construction in the manner provided in the applicable specifications and the approved plans for the work together with all standard and special designs that may be designed on such plans, and the special provisions in the contract of which this proposal will become a part, if and when accepted. The bidder further agrees that the applicable specifications and all plans and working drawings are made a part hereof, as fully and completely as if attached hereto.

The bidder, if awarded the contract, agrees to begin the work not later than ten (10) days after the date of written notification from the engineer to do so, unless otherwise stipulated in the special provisions.

The bidder declares that if they are awarded the contract, they will execute the contract agreement and begin and complete the work within the time named herein, and they will file a good and sufficient surety bond for the amount of the contract for performance and also for the full amount of the contract for payment.

The bidder, if awarded the contract, shall pay all claims as required by Section 779.14, Statutes of Wisconsin, and shall be subject to and discharge all liabilities for injuries pursuant to Chapter 102 of the Statutes of Wisconsin, and all acts amendatory thereto. They shall further be responsible for any damages to property or injury to persons occurring through their own negligence or that of their employees or agents, incident to the performance of work under this contract, pursuant to the Standard Specifications for Road and Bridge Construction applicable to this contract.

In connection with the performance of work under this contract, the contractor agrees to comply with all applicable state and federal statutes relating to non-discrimination in employment. No otherwise qualified person shall be excluded from employment or otherwise be subject to discrimination in employment in any manner on the basis of age, race, religion, color, gender, national origin or ancestry, disability, arrest or conviction record (in keeping with s.111.32), sexual orientation, marital status, membership in the military reserve, honesty testing, genetic testing, and outside use of lawful products. This provision shall include, but not be limited to the following: employment, upgrading, demotion or transfer; recruitment or recruitment advertising; layoff or termination; rates of pay or other forms of compensation, and selection for training, including apprenticeship. The contractor further agrees to ensure equal opportunity in employment to all applicants and employees and to take affirmative action to attain a representative workforce.

The contractor agrees to post notices and posters setting forth the provisions of the nondiscrimination clause, in a conspicuous and easily accessible place, available for employees and applicants for employment.

If a state public official (section 19.42, Stats.) or an organization in which a state public official holds at least a 10% interest is a party to this agreement, this contract is voidable by the state unless appropriate disclosure is made to the State of Wisconsin Ethics Board.

BID PREPARATION

Preparing the Proposal Schedule of Items

A General

- (1) Obtain bidding proposals as specified in **section 102** of the standard specifications prior to 11:45 AM of the last business day preceding the letting. Submit bidding proposals using one of the following methods:
 1. Electronic bid on the internet.
 2. Electronic bid on a printout with accompanying diskette or CD ROM.
 3. Paper bid under a waiver of the electronic submittal requirements.
- (2) Bids submitted on a printout with accompanying diskette or CD ROM or paper bids submitted under a waiver of the electronic submittal requirements govern over bids submitted on the internet.
- (3) The department will provide bidding information through the department's web site at <http://www.dot.wisconsin.gov/business/engrserv/bid-letting-information.htm>. The contractor is responsible for reviewing this web site for general notices as well as information regarding proposals in each letting. The department will also post special notices of all addenda to each proposal through this web site no later than 4:00 P.M. local time on the Thursday before the letting. Check the department's web site after 5:00 P.M. local time on the Thursday before the letting to ensure all addenda have been accounted for before preparing the bid. When bidding using methods 1 and 2 above, check the Bid Express™ on-line bidding exchange at <http://www.bidx.com/> after 5:00 P.M. local time on the Thursday before the letting to ensure that the latest schedule of items Expedite file (*.ebs or *.00x) is used to submit the final bid.
- (4) Interested parties can subscribe to the Bid Express™ on-line bidding exchange by following the instructions provided at the www.bidx.com web site or by contacting:

Info Tech Inc.
5700 SW 34th Street, Suite 1235
Gainesville, FL 32608-5371
email: <mailto:customer.support@bidx.com>

- (5) The department will address equipment and process failures, if the bidder can demonstrate that those failures were beyond their control.
- (6) Contractors are responsible for checking on the issuance of addenda and for obtaining the addenda. Notice of issuance of addenda is posted on the department's web site at <http://www.dot.wisconsin.gov/business/engrserv/bid-letting-information.htm> or by calling the department at (608) 266-1631. Addenda can ONLY be obtained from the departments web site listed above or by picking up the addenda at the Bureau of Highway Construction, Room 601, 4802 Sheboygan Avenue, Madison, WI, during regular business hours.

B Submitting Electronic Bids

B.1 On the Internet

- (1) Do the following before submitting the bid:
 1. Have a properly executed annual bid bond on file with the department.
 2. Have a digital ID on file with and enabled by Info Tech Inc. Using this digital ID will constitute the bidder's signature for proper execution of the bidding proposal.
- (2) In lieu of preparing, delivering, and submitting the proposal as specified in **102.6** and **102.9** of the standard specifications, submit the proposal on the internet as follows:

1. Download the latest schedule of items reflecting all addenda from the Bid Express™ web site.
 2. Use Expedite™ software to enter a unit price for every item in the schedule of items.
 3. Submit the bid according to the requirements of Expedite™ software and the Bid Express™ web site. Do not submit a bid on a printout with accompanying diskette or CD ROM or a paper bid. If the bidder does submit a bid on a printout with accompanying diskette or a paper bid in addition to the internet submittal, the department will disregard the internet bid.
 4. Submit the bid before the hour and date the Notice to Contractors designates.
 5. Do not sign, notarize, and return the bidding proposal described in 102.2 of the standard specifications.
- (3) The department will not consider the bid accepted until the hour and date the Notice to Contractors designates.

B.2 On a Printout with Accompanying Diskette or CD ROM

- (1) Download the latest schedule of items from the Wisconsin pages of the Bid Express™ web site reflecting the latest addenda posted on the department's web site at <http://www.dot.wisconsin.gov/business/engrserve/bid-letting-information.htm>. Use Expedite™ software to prepare and print the schedule of items. Provide a valid amount for all price fields. Follow instructions and review the help screens provided on the Bid Express™ web site to assure that the schedule of items is prepared properly.
- (2) Staple an 8 1/2 by 11 inch printout of the Expedite™ generated schedule of items to the other proposal documents submitted to the department as a part of the bidder's sealed bid. As a separate submittal not in the sealed bid envelop but due at the same time and place as the sealed bid, also provide the Expedite™ generated schedule of items on a 3 1/2 inch computer diskette or CD ROM. Label each diskette or CD ROM with the bidder's name, the 4 character department-assigned bidder identification code from the top of the bidding proposal, and a list of the proposal numbers included on that diskette or CD ROM as indicated in the following example:

Bidder Name

BN00

Proposals: 1, 12, 14, & 22

- (3) If bidding on more than one proposal in the letting, the bidder may include all proposals for that letting on one diskette or CD ROM. Include only submitted proposals with no incomplete or other files on the diskette or CD ROM.
- (4) The bidder-submitted printout of the Expedite™ generated schedule of items is the governing contract document and must conform to the requirements of section 102 of the standard specifications. If a printout needs to be altered, cross out the printed information with ink or typewriter and enter the new information and initial it in ink. If there is a discrepancy between the printout and the diskette or CD ROM, the department will analyze the bid using the printout information.
- (5) In addition to the reasons specified in section 102 of the standard specifications, proposals are irregular and the department may reject them for one or more of the following:
 1. The check code printed on the bottom of the printout of the Expedite™ generated schedule of items is not the same on each page.
 2. The check code printed on the printout of the Expedite™ generated schedule of items is not the same as the check code for that proposal provided on the diskette or CD ROM.

3. The diskette or CD ROM is not submitted at the time and place the department designates.

C Waiver of Electronic Submittal

- (1) The bidder may request a waiver of the electronic submittal requirements. Submit a written request for a waiver in lieu of bids submitted on the internet or on a printout with accompanying diskette or CD ROM. Use the waiver that was included with the paper bid document sent to the bidder or type up a waiver on the bidder's letterhead. The department will waive the electronic submittal requirements for a bidding entity (individual, partnership, joint venture, corporation, or limited liability company) for up to 4 individual proposals in a calendar year. The department may allow additional waivers for equipment malfunctions.
- (2) Submit a schedule of items on paper conforming to [section 102](#) of the standard specifications. The department charges the bidder a \$75 administrative fee per proposal, payable at the time and place the department designates for receiving bids, to cover the costs of data entry. The department will accept a check or money order payable to: "Wisconsin, Dept. of Transportation."
- (3) In addition to the reasons specified in [section 102](#) of the standard specifications, proposals are irregular and the department may reject them for one or more of the following:
 1. The bidder fails to provide the written request for waiver of the electronic submittal requirements.
 2. The bidder fails to pay the \$75 administrative fee before the time the department designates for the opening of bids unless the bidder requests on the waiver that they be billed for the \$75.
 3. The bidder exceeds 4 waivers of electronic submittal requirements within a calendar year.
- (4) In addition to the reasons specified in [section 102](#) of the standard specifications, the department may refuse to issue bidding proposals for future contracts to a bidding entity that owes the department administrative fees for a waiver of electronic submittal requirements.

PROPOSAL BID BOND

DT1303 1/2006

Wisconsin Department of Transportation

Proposal Number	Project Number	Letting Date
Name of Principal		
Name of Surety	State in Which Surety is Organized	

We, the above-named Principal and the above-named Surety, are held and firmly bound unto the State of Wisconsin in the sum equal to the Proposal Guaranty for the total bid submitted for the payment to be made; we jointly and severally bind ourselves, our heirs, executors, administrators, successors and assigns. The condition of this obligation is that the Principal has submitted a bid proposal to the State of Wisconsin acting through the Department of Transportation for the improvement designated by the Proposal Number and Letting Date indicated above.

If the Principal is awarded the contract and, within the time and manner required by law after the prescribed forms are presented for signature, enters into a written contract in accordance with the bid, and files the bond with the Department of Transportation to guarantee faithful performance and payment for labor and materials, as required by law, or if the Department of Transportation shall reject all bids for the work described, then this obligation shall be null and void; otherwise, it shall be and remain in full force and effect. In the event of failure of the Principal to enter into the contract or give the specified bond, the Principal shall pay to the Department of Transportation **within 10 business days of demand** a total equal to the Proposal Guaranty as liquidated damages; the liability of the Surety continues for the full amount of the obligation as stated until the obligation is paid in full.

The Surety, for value received, agrees that the obligations of it and its bond shall not be impaired or affected by any extension of time within which the Department of Transportation may accept the bid; and the Surety does waive notice of any such extension.

IN WITNESS, the Principal and Surety have agreed and have signed by their proper officers and have caused their corporate seals to be affixed this date: **(DATE MUST BE ENTERED)**

PRINCIPAL

(Company Name) **(Affix Corporate Seal)**

(Signature and Title)

(Company Name)

(Signature and Title)

(Company Name)

(Signature and Title)

(Company Name)

(Signature and Title)

NOTARY FOR PRINCIPAL

(Date)

State of Wisconsin)
) ss.
_____ County)

On the above date, this instrument was acknowledged before me by the named person(s).

(Signature, Notary Public, State of Wisconsin)

(Print or Type Name, Notary Public, State of Wisconsin)

(Date Commission Expires)

Notary Seal

(Name of Surety) **(Affix Seal)**

(Signature of Attorney-in-Fact)

NOTARY FOR SURETY

(Date)

State of Wisconsin)
) ss.
_____ County)

On the above date, this instrument was acknowledged before me by the named person(s).

(Signature, Notary Public, State of Wisconsin)

(Print or Type Name, Notary Public, State of Wisconsin)

(Date Commission Expires)

Notary Seal

IMPORTANT: A certified copy of Power of Attorney of the signatory agent must be attached to the bid bond.

CERTIFICATE OF ANNUAL BID BOND

DT1305 8/2003

Wisconsin Department of Transportation

Time Period Valid (From/To)	
Name of Surety	
Name of Contractor	
Certificate Holder	Wisconsin Department of Transportation

This is to certify that an annual bid bond issued by the above-named Surety is currently on file with the Wisconsin Department of Transportation.

This certificate is issued as a matter of information and conveys no rights upon the certificate holder and does not amend, extend or alter the coverage of the annual bid bond.

Cancellation: Should the above policy be cancelled before the expiration date, the issuing surety will give thirty (30) days written notice to the certificate holder indicated above.

(Signature of Authorized Contractor Representative)

(Date)

March 2010

LIST OF SUBCONTRACTORS

Section 66.0901(7), Wisconsin Statutes, provides that as a part of the proposal, the bidder also shall submit a list of the subcontractors the bidder proposes to contract with and the class of work to be performed by each. In order to qualify for inclusion in the bidder's list a subcontractor shall first submit a bid in writing, to the general contractor at least 48 hours prior to the time of the bid closing. The list may not be added to or altered without the written consent of the municipality. A proposal of a bidder is not invalid if any subcontractor and the class of work to be performed by the subcontractor has been omitted from a proposal; the omission shall be considered inadvertent or the bidder will perform the work personally.

No subcontract, whether listed herein or later proposed, may be entered into without the written consent of the Engineer as provided in Subsection 108.1 of the Standard Specifications.

[illegible]

DECEMBER 2000

**CERTIFICATION REGARDING DEBARMENT, SUSPENSION, AND OTHER
RESPONSIBILITY MATTERS - PRIMARY COVERED TRANSACTIONS**

Instructions for Certification

1. By signing and submitting this proposal, the prospective contractor is providing the certification set out below.
2. The inability of a person to provide the certification required below will not necessarily result in denial of participation in this covered transaction. The prospective contractor shall submit an explanation of why it cannot provide the certification set out below. The certification or explanation will be considered in connection with the department or agency's determination whether to enter into this transaction. However, failure of the prospective contractor to furnish a certification or an explanation shall disqualify such person from participation in this transaction.
3. The certification in this clause is a material representation of fact upon which reliance was placed when the department determined to enter into this transaction. If it is later determined that the contractor knowingly rendered an erroneous certification in addition to other remedies available to the Federal Government the department may terminate this transaction for cause or default.
4. The prospective contractor shall provide immediate written notice to the department to whom this proposal is submitted if at any time the prospective contractor learns that its certification was erroneous when submitted or has become erroneous by reason of changed circumstances.
5. The terms "covered transaction," "debarred," "suspended," "ineligible," "lower tier covered transaction," "participant," "person," "primary covered transaction," "principal," "proposal," and "voluntarily excluded," as used in this clause, have the meanings set out in the Definitions and Coverage sections of the rules implementing Executive Order 12549. You may contact the department to which this proposal is being submitted for assistance in obtaining a copy of those regulations.
6. The prospective contractor agrees by submitting this proposal that, should this contract be entered into, it shall not knowingly enter into any lower tier covered transaction with a person who is debarred, suspended, declared ineligible, or voluntarily excluded from participation in this covered transaction, unless authorized by the department entering into this transaction.
7. The prospective contractor further agrees by submitting this proposal that it will include the clause titled "Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion-Lower Tier Covered Transaction," which is included as an addendum to PR-1273 - "Required Contract Provisions Federal Aid Construction Contracts," without

modification, in all lower tier covered transactions and in all solicitations for lower tier covered transactions.

8. The contractor may rely upon a certification of a prospective subcontractor/materials supplier that it is not debarred, suspended, ineligible, or voluntarily excluded from the covered transaction, unless it knows that the certification is erroneous. A contractor may decide the method and frequency by which it determines the eligibility of its principals. Each contractor may, but is not required to, check the Disapproval List (telephone # 608/266/1631).
9. Nothing contained in the foregoing shall be construed to require establishment of a system of records in order to render in good faith the certification required by this clause. The knowledge and information of a contractor is not required to exceed that which is normally possessed by a prudent person in the ordinary course of business dealings.
10. Except for transactions authorized under paragraph 6 of these instructions, if a contractor in a covered transaction knowingly enters into a lower tier covered transaction with a person who is suspended, debarred, ineligible or voluntarily excluded from participation in this transaction, in addition to other remedies available to the Federal Government, the department may terminate this transaction for cause or default.

Certification Regarding Debarment, Suspension, and Other Responsibility Matters - Primary Covered Transactions

- (1) The prospective contractor certifies to the best of its knowledge and belief, that it and its principals:
 - (a) Are not presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from covered transactions by any Federal department or agency;
 - (b) Have not within a three-year period preceding this proposal been convicted of or had a civil judgment rendered against them for commission of fraud or a criminal offense in connection with obtaining, attempting to obtain, or performing a public (Federal, State or local) transaction or contract under a public transaction; violation of Federal or State antitrust statutes or commission of embezzlement, theft, forgery, bribery, falsification or destruction of records, making false statements or receiving stolen property;
 - (c) Are not presently indicted for or otherwise criminally or civilly charged by a governmental entity (Federal, State or local) with commission of any of the offense enumerated in paragraph (1)(b) of this certification; and
 - (d) Have not within a three-year period preceding this proposal had one or more public transactions (Federal, State or local) terminated for cause or default.
- (2) Where the prospective contractor is unable to certify to any of the statements in this certification, such prospective contractor shall attach an explanation to this proposal.

Special Provisions

Table of Contents

Article	Description	Page #
1.	General.....	2
2.	Scope of Work.	2
3.	Prosecution and Progress.	2
4.	Traffic.	3
5.	Holiday Work Restrictions.	4
6.	Utilities.....	4
7.	Water Quality Certification.....	6
8.	Information to Bidders, U.S. Army corps of Engineers Section 404 Permit.....	6
9.	Construction Over or Adjacent to Navigable Waters:	6
10.	Erosion Control.....	7
11.	Airport.....	7
12.	QMP Base Aggregate.	8
13.	QMP Ride; Incentive IRI Ride, Item 440.4410.S.....	16
14.	QMP HMA Pavement Nuclear Density.....	23
15.	Reheating HMA Pavement Longitudinal Joints, Item 460.4110.S.....	31
16.	Locating No-Passing Zones, Item 648.0100.....	32
17.	Pavement Marking Grooved Preformed Thermoplastic Arrows Type 2, Item SPV.0060.01; Arrows Type 3, Item SPV.0060.02; Words, Item SPV.0060.03; Stop Line 18-Inch, Item SPV.0090.01.....	32
18.	Pavement Marking Grooved Preformed Plastic Tape 8-Inch, Item SPV.0090.02; 4-Inch, Item SPV.0090.03.	34
19.	Milling and Removing Temporary Joint, Item SPV.0105.01.....	36
20.	Same Day Paving HMA Pavement Type E-3, Item SPV.0195.01.....	37

SPECIAL PROVISIONS

1. General.

Perform the work under this construction contract for Project 1410-12-70 Washington Street, City of West Bend, Trenton Road to 4000' E of Oak Road, STH 33, Washington County, Wisconsin as the plans show and execute the work as specified in the State of Wisconsin, Department of Transportation, Standard Specifications for Highway and Structure Construction, 2014 Edition, as published by the department, and these special provisions.

If all or a portion of the plans and special provisions are developed in the SI metric system and the schedule of prices is developed in the US standard measure system, the department will pay for the work as bid in the US standard system.

100-005 (20130615)

2. Scope of Work.

The work under this contract shall consist of asphaltic surface milling, grading, base aggregate, HMA pavement, pipe culverts, pavement marking and permanent signing, and all incidental items necessary to complete the work as shown on the plans and included in the proposal and contract.

104-005 (20090901)

3. Prosecution and Progress.

Begin work within ten calendar days after the engineer issues a written notice to do so.

Provide the time frame for construction of the project within the 2014 construction season to the engineer in writing within a month after executing the contract but at least 14 calendar days before the preconstruction conference. Assure that the time frame is consistent with the contract completion time. Upon approval, the engineer will issue the notice to proceed within ten calendar days before the beginning of the approved time frame.

To revise the time frame, submit a written request to the engineer at least two weeks before the beginning of the intended time frame. The engineer will approve or deny that request based on the conditions cited in the request and its effect on the department's scheduled resources.

All common and marsh excavation shall be filled with granular backfill and/or base aggregate dense 1.25" at the end of each day and have the drop off from mainline STH 33 traffic ramped at a maximum 3:1 slope to excavated area.

All mainline pavements, except Station 94+60 to 96+26 shall have a minimum new lower lift of asphalt at the end of each day. Work will be paid under Same Day Paving HMA Pavement Type E-3, Item SPV.0195.01. Each culvert pipe crossings shall be completed within same day and an asphalt layer over each pipe location.

Temporary centerline pavement markings shall be applied to all layers of asphaltic pavement or surface, including milled surfaces, the same day such courses, layers or surfaces are placed or milled. Apply temporary no-passing zone and centerline pavement markings to all intermediate layers of asphaltic surfaces open to through traffic, including milled surfaces, within 3 calendar days after completion of the milling or the placement of each pavement layer. During the time when no-passing zone and centerline pavement markings are not in place on intermediate or final surfaces open to through traffic, the center of the pavement shall be indicated with yellow 4-inch wide, 8-inch long temporary pavement markings, spaced every 50 feet. Apply such markings to all intermediate and final layers of asphaltic surfaces, including milled surfaces, the day such layers or surfaces are placed or milled. Removal of such markings shall not be required between pavement layers or when no-passing zone and centerline pavement markings are placed. When adverse weather conditions preclude the application of temporary pavement markings required in this paragraph, resume pavement marking operations when conditions permit. Do not use broken line pavement markings with stripe lengths longer than 8 inches to indicate the center of the pavement during the time when no-passing zone pavement markings are not in place. Temporary pavement marking shall be incidental to paving operations.

Final centerline Pavement Marking Epoxy 4-INCH shall be completed on the same day, after the Asphaltic Centerline Rumble Strip is completed.

4. Traffic.

Keep STH 33 open to traffic at all times with minimum 11 feet lanes widths. A flagger shall be used utilized per standard spec 104.6.1.4 and the standard detailed drawings. Lane closures will require flagging in a moving operation as specified per the standard detail drawing. Keep flagging operations limited 2500 feet from 3:00 PM to 4:00 PM and 1500 feet from 4:00 PM to 6:00 PM. When construction operations are located at an intersection, use additional flaggers to maintain safe vehicular movements. Maintain access to driveways and side roads at all times during the contract. Flagging shall be staged to maintain one lane of traffic at all times.

Stage 1 work shall be completed with granular backfill, base aggregate dense to finished layer, and salvaged topsoil on foreslopes and ditches, before stage 2 shall begin.

Traffic control drums shall be provided for shoulder drop offs. Have available at all times sufficient experienced personnel to promptly install, remove and reinstall the required traffic control devices to route traffic in order to perform the operations.

5. **Holiday Work Restrictions.**

Do not perform work on, nor haul materials of any kind along or across any portion of the highway carrying STH 33 traffic, and entirely clear the traveled way and shoulders of such portions of the highway of equipment, barricades, signs, lights, and any other material that might impede the free flow of traffic during the following holiday periods:

- From noon Friday, May 23, 2014 to 6:00 AM Tuesday, May 27, 2014 for Memorial Day;
- From noon Thursday, July 3, 2014 to 6:00 AM Monday, July 7, 2014 for Independence Day;
- From noon Friday, August 29, 2014 to 6:00 AM Tuesday, Sept 2, 2014 for Labor Day.

107-005 (20050502)

6. **Utilities.**

The provisions of administrative rule TRANS 220 apply to this project.

Underground and overhead utility facilities are located within the project limits. Utility adjustments are anticipated for this construction project. Coordinate construction activities with a call to Diggers Hotline or a direct call to the utilities that have facilities in the area as required per statutes. Use caution to ensure the integrity of underground facilities and maintain code clearances from overhead facilities at all times.

When utility adjustments become necessary during construction, such as at intersections, culvert pipe extensions and/or replacements the utility owner will make the required adjustments in coordination with the contractor's construction operation.

Contact each utility company listed in the plans, prior to preparing bids, to obtain current information on the status of existing and any new utility relocation work.

107-SER4 (20101021)

Paetec has underground fiber optic lines that cross STH 33 on north and south side from Chopper drive east to project limits. No relocations are anticipated and no adjustments are required.

Charter Communications has Fiber optic lines that cross STH 83 North of the project area near Golf Road. No relocations are anticipated and no adjustments are required.

WE Energies(Electric) has overhead electric lines are located throughout the project, crossing STH 33. No relocations are anticipated and no adjustments are required.

WE Energies(Gas) has underground gas lines cross STH 33 at Trenton road to East project limits. Gas lines are also buried along Trenton Road, Chopper Drive, Kaelin Lane, Earl Stier Drive, Ariel Drive and Oak Road. No relocations are anticipated. Gas valve at Station 120+63LT need to be adjusted during construction.

Contact Dennis Singakovic, (414) 540-5715, 2 weeks prior to paving.

City of West Bend, Sanitary Sewer lines runs West of Chopper Drive and continues South on STH 33. No relocations are anticipated and no adjustments are required.

City of West Bend, Water main crosses STH 33 and runs along the West of Trenton Road on the South side to just East of Chopper Drive. No relocations are anticipated. Couple water valves need to be adjusted during construction.

Contact John Hemauer, (262) 335-5040, 7 days prior to paving.

City of West Bend, Storm Sewer lines cross the intersection at STH 33 and Trenton Road, Chopper Dr to Earl Stier drive along ditch on the south side. No relocations are anticipated and no adjustments are required.

AT&T Wisconsin has telephone wires on poles and underground at various locations along STH 33. AT&T Wisconsin will lower, retire and install new cable prior to construction. Please see below for detail description.

- a) South side of STH 33, Station 157+50 to 159+00 lower existing cables in place.
 - Lower in place (1) 48 cnt F/O cable from Station 157+50 to 159+00.
 - Lower in place (1) 25 pr cable from Station 157+50 to existing ped at ~Station 158+75.
 - Lowering depth required is 6 - 7' minimum from existing grade to avoid WIS ditch grading conflict.
 - Excavation location will be approximately 41' - 48' South of CL STH 33
- b) South Side of STH 33, STA 158+75 to 160+75 retirement.
 - Retire existing 25 pr cable from existing ped at ~Station 158+75 East and North to existing ped at ~Station 160+75.
- c) North side of STH 33, STA 158+68 to ~STA 158+75 install new 25 pr cable.
 - Install new 25 pr cable, crossing STH 33 from existing ped at ~Station 158+60 South and East to existing ped at ~Station 158+75.
 - Crossing depth, minimum of 15' below existing road surface.
- d) North side of STH 33, Station 158+68 to ~Station 160+75. Install new 100 pr cable.
 - Install new 100 pr cable from existing ped at ~Station 158+68 East to existing ped at ~Station 160+75 approximately 50' North of CL STH 33.
 - Crossing depth of Oak Road North, minimum of 15' below existing road surface to avoid WIS DOT sub cuts under Oak Road North.

- e) North side of STH 33, Station 158+68 to ~Station 160+75 retirement.
 - Retire existing 400 pr cable from existing ped at ~Station 158+68 East to existing ped at ~Station 160+75.
- f) North side of STH 33, ~Station 160+75 to Station 162+50. Move existing cable North to avoid WIS DOT sub cut STH33 WBL.
 - Excavate beside existing 400 pr and shift to the North ~3-5'.
 - Excavation location will be ~27-35' North of CL STH 33.

Contact: Jay Bulanek, (414) 535-7407.

West Shore Pipeline has petroleum lines crossing STH 33 from Trenton Road to East with crossings at various locations. No relocations are anticipated and no adjustments are required. Special caution should be used in operating heavy equipment near these pipelines. West shore pipeline is 5' deep at south ditch, 6.5' deep at north ditch and 8.5' deep at black top.

7. Water Quality Certification.

The department has obtained a WisDNR 401 Water Quality Certification for work being performed on this project in or adjacent to wetlands. A copy of this certification letter is available from the regional office by contacting John Kanzenbach at (262) 548-6467.

Comply with the requirements of the permit and certification in addition to the requirements of the contract. Perform remedial activities without extra compensation if not in compliance.

8. Information to Bidders, U.S. Army corps of Engineers Section 404 Permit.

The department has obtained a U.S. Army Corps of Engineers Section 404 permit. Comply with the requirements of the permit in addition to the requirements of the special provisions. A copy of the permit is available from regional office by contacting John Kanzenbach at (262) 548-6467.

Comply with the requirement and certification in addition to requirements of the contract. Perform remedial activities without extra compensation if not in compliance.

9. Construction Over or Adjacent to Navigable Waters:

Supplement standard spec 107.19 with the following:

The stream crossings at Station 101+75, Station 149+90, and Station 172+00 flowing to the Milwaukee River are classified as navigable waterways.

No in water work will be allowed between March 15 and May 15 in navigable water to protect endemic fish spawning and populations. Please work with the department for an approved schedule of activities in these areas.

10. Erosion Control.

Prepare and submit an erosion control implementation plan (ECIP) for the project including borrow sites, material disposal sites, dust control, and dewatering in accordance to Chapter TRANS 401 requirements. The erosion control implementation plan shall supplement information shown on the plans and shall not reproduce it. The erosion control implementation plan will identify how the contractor intends to implement the project's erosion control plan.

Provide the ECIP 14 calendar days prior to the pre-construction conference. Pursue operations in a timely and diligent manner, continuing all construction operations methodically from the initial removals and topsoil stripping operations through the subsequent grading, paving, and re-top soiling to minimize the period of exposure to possible erosion. Do not implement the ECIP until it has been approved by the department.

Re-topsoil of graded areas, as designated by the engineer, immediately after grading is completed within those areas. Seed, fertilizer, and mulch top-soiled areas, as designated by the engineer, within 5 calendar days after placement of topsoil. If graded areas are left exposed for more than 14 calendar days, seed those areas with temporary seed.

When performing roadway cleaning operations, use equipment having vacuum or water spray mechanism to eliminate the dispersion of dust. If vacuum equipment is employed, it shall have suitable self-contained particulate collectors to prevent discharge from the collection bin into the atmosphere.

Stockpile excess material or spoils on upland areas away from wetlands, floodplains and waterways. Stockpiled soil shall be protected against erosion. If stockpiled material is left for more than 14 calendar days, seed the stockpile with temporary seed.

11. Airport.

The contractor is advised that the construction site is located adjacent to West Bend Municipal Airport and is in the flight path for the airport. The contractor may be required to use smaller cranes and other construction equipment to construct the culverts, and other items on the project.

The contractor is required to fill out FAA form 7460 (notice of proposed construction) and submit the form to the Manager, Air Traffic Division, Federal Aviation Administration –Great Lakes Region 30 days prior to the date the application for a construction permit is filed.

12. QMP Base Aggregate.

A Description

A.1 General

- (1) This special provision describes contractor quality control (QC) sampling and testing for base aggregates, documenting those test results, and documenting related production and placement process changes. This special provision also describes department quality verification (QV), independent assurance (IA), and dispute resolution.
- (2) Conform to standard spec 301, standard spec 305, and standard spec 310 as modified here in this special provision. Apply this special provision to material placed under all of the Base Aggregate Dense and Base Aggregate Open Graded bid items, except do not apply this special provision to material classified as reclaimed asphaltic pavement placed under the Base Aggregate Dense bid items.
- (3) Do not apply this special provision to material placed under the Aggregate Detours, Salvaged Asphaltic Pavement Base, Breaker Run, Select Crushed, Pit Run, Subbase, or Riprap bid items.
- (4) Provide and maintain a quality control program, defined as all activities related to and documentation of the following:
 1. Production and placement control and inspection.
 2. Material sampling and testing.
- (5) Chapter 8 of the department's construction and materials manual (CMM) provides additional detailed guidance for QMP work and describes required sampling and testing procedures. The contractor may obtain the CMM from the department's web site at:

<http://roadwaystandards.dot.wi.gov/standards/cmm/index.htm>

A.2 Contractor Testing for Small Quantities

- (1) The department defines a small quantity, for each individual Base Aggregate bid item, as a plan quantity of 9000 tons or less of material as shown in the schedule of items under that bid item.
- (2) The requirements under this special provision apply equally to a small quantity for an individual bid item except as follows:
 1. The contractor need not submit a full quality control plan but shall provide an organizational chart to the engineer including names, telephone numbers, and current certifications of all persons involved in the quality control program for material under affected bid items.

2. Divide the aggregate into uniformly sized sublots for testing as follows:

Plan Quantity	Minimum Required Testing
≤ 1500 tons	One test from production, load-out, or placement at the contractor's option ^[1]
> 1500 tons and ≤ 6000 tons	Two tests of the same type, either from production, load-out, or placement at the contractor's option ^[1]
> 6000 tons and ≤ 9000 tons	Three placement tests ^{[2][3]}

^[1] If using production tests for acceptance, submit test results to the engineer for review prior to incorporating the material into the work. Production test results are valid for a period of 3 years.

^[2] For 3-inch material, obtain samples at load-out.

^[3] If the actual quantity overruns 9000 tons, create overrun sublots to test at a rate of one additional placement test for each 3000 tons, or fraction of 3000 tons, of overrun.

3. No control charts are required. Submit aggregate load-out and placement test results to the engineer within one business day of obtaining the sample. Assure that all properties are within the limits specified for each test.

4. Department verification testing is optional for quantities of 6000 tons or less.

(3) Material represented by a subplot with any property outside the specification limits is nonconforming. The department may reject material or otherwise determine the final disposition of nonconforming material as specified in standard spec 106.5.

B Materials

B.1 Quality Control Plan

(1) Submit a comprehensive written quality control plan to the engineer at or before the pre-construction meeting. Do not place base before the engineer reviews and comments on the plan. Construct the project as that plan provides.

(2) Do not change the quality control plan without the engineer's review. Update the plan with changes as they become effective. Provide a current copy of the plan to the engineer and post in each of the contractor's laboratories as changes are adopted. Ensure that the plan provides the following elements:

1. An organizational chart with names, telephone numbers, current certifications and/or titles, and roles and responsibilities of QC personnel.

2. The process used to disseminate QC information and corrective action efforts to the appropriate persons. Include a list of recipients, the communication means that will be used, and action time frames.

3. A list of source and processing locations, section and quarter descriptions, for all aggregate materials requiring QC testing.

4. Test results for wear, sodium sulfate soundness, freeze/thaw soundness, and plasticity index of all aggregates requiring QC testing. Obtain this information from the region materials unit or from the engineer.

5. Descriptions of stockpiling and hauling methods.
6. Locations of the QC laboratory, retained sample storage, and where control charts and other documentation is posted.
7. An outline for resolving a process control problem. Include responsible personnel, required documentation, and appropriate communication steps.

B.2 Personnel

- (1) Have personnel certified under the department's highway technician certification program (HTCP) perform sampling, testing, and documentation as follows:

Required Certification Level:	Sampling or Testing Roles:
Aggregate Technician IPP Aggregate Sampling Technician Aggregate Assistant Certified Technician (ACT-AGG)	Aggregate Sampling ^[1]
Aggregate Technician IPP Aggregate Assistant Certified Technician (ACT-AGG)	Aggregate Gradation Testing, Aggregate Fractured Particle Testing, Aggregate Liquid Limit and Plasticity Index Testing

^[1] Plant personnel under the direct observation of an aggregate technician certified at level one or higher may operate equipment to obtain samples.

- (2) A certified technician must coordinate and take responsibility for the work an ACT performs. Have a certified technician ensure that all sampling and testing is performed correctly, analyze test results, and post resulting data. No more than one ACT can work under a single certified technician.

B.3 Laboratory

- (1) Perform QC testing at a department-qualified laboratory. Obtain information on the Wisconsin laboratory qualification program from:

Materials Management Section
3502 Kinsman Blvd.
Madison, WI 53704
Telephone: (608) 246-5388

<http://www.dot.state.wi.us/business/engrserv/lab-qualification.htm>

B.4 Quality Control Documentation

B.4.1 General

- (1) Submit base aggregate placement documentation to the engineer within 10 business days after completing base placement. Ensure that the submittal is complete, neatly organized, and includes applicable project records and control charts.

B.4.2 Records

- (1) Document all placement observations, inspection records, and control adjustments daily in a permanent field record. Also include all test results in the project records. Provide test results to the engineer within 6 hours after obtaining a sample. For 3-inch base, extend this 6-hour limit to 24 hours. Post or distribute tabulated results using a method mutually agreeable to the engineer and contractor.

B.4.3 Control Charts

- (1) Plot gradation and fracture on the appropriate control chart as soon as test results are available. Format control charts according to CMM 8.30. Include the project number on base placement control charts. Maintain separate control charts for each base aggregate size, source or classification, and type.
- (2) Provide control charts to the engineer within 6 hours after obtaining a sample. For 3-inch base, extend this 6-hour limit to 24 hours. Post or distribute charts using a method mutually agreeable to the engineer and contractor. Update control charts daily to include the following:
 1. Contractor individual QC tests.
 2. Department QV tests.
 3. Department IA tests.
 4. Four-point running average of the QC tests.
- (3) Except as specified under B.8.2.1 for nonconforming QV tests, include only QC tests in the running average. The contractor may plot process control or informational tests on control charts, but do not include these tests, conforming QV tests, or IA tests in the running average.

B.5 Contractor Testing

- (1) Test gradation, fracture, liquid limit and plasticity index during placement for each base aggregate size, source or classification, and type.
- (2) Test gradation once per 3000 tons of material placed. Determine random sample locations and provide those sample locations to the engineer. Obtain samples after the material has been bladed, mixed, and shaped but before compacting; except collect 3-inch samples from the stockpile at load-out. Do not sample from material used to maintain local traffic or from areas of temporary base that will not have an overlying pavement. On days when placing only material used to maintain local traffic or only temporary base that will not have an overlying pavement, no placement testing is required.
- (3) Split each contractor QC sample and identify it according to CMM 8.30. Retain the split for 7 calendar days in a dry, protected location. If requested for department comparison testing, deliver the split to the engineer within one business day.
- (4) The engineer may require additional sampling and testing to evaluate suspect material or the technician's sampling and testing procedures.

- (5) Test fracture for each gradation test until the fracture running average is above the lower warning limit. Subsequently, the contractor may reduce the frequency to one test per 10 gradation tests if the fracture running average remains above the warning limit.
- (6) Test the liquid limit and plasticity index for the first gradation test. Subsequently, test the liquid limit and plasticity index a minimum of once per 10 gradation tests.

B.6 Test Methods

B.6.1 Gradation

- (1) Test gradation using a washed analysis conforming to the following as modified in CMM 8.60:
 Gradation..... AASHTO T 27
 Material finer than the No. 200 sieve..... AASHTO T 11
- (2) For 3-inch base, if 3 consecutive running average points for the percent passing the No. 200 sieve are 8.5 percent or less, the contractor may use an unwashed analysis. Wash at least one sample out of 10. If a single running average for the percent passing the No. 200 sieve exceeds 8.5 percent, resume washed analyses until 3 consecutive running average points are again 8.5 percent passing or less.
- (3) Maintain a separate control chart for each sieve size specified in standard spec 305 or standard spec 310 for each base aggregate size, source or classification, and type. Set control and warning limits based on the standard specification gradation limits as follows:
 1. Control limits are at the upper and lower specification limits.
 2. There are no upper warning limits for sieves allowing 100 percent passing and no lower control limits for sieves allowing 0 percent passing.
 3. Dense graded warning limits, except for the No. 200 sieve, are 2 percent within the upper and lower control limits. Warning limits for the No. 200 sieve are set 0.5 percent within the upper and lower control limits.
 4. Open graded warning limits for the 1-inch, 3/8-inch, and No. 4 sieves are 2 percent within the upper and lower control limits. Upper warning limits for the No. 10, No. 40, and No. 200 sieves are 1 percent inside the upper control limit.

B.6.2 Fracture

- (1) Test fracture conforming to CMM 8.60. The engineer will waive fractured particle testing on quarried stone.
- (2) Maintain a separate fracture control chart for each base aggregate size, source or classification, and type. Set the lower control limit at the contract specification limit, either specified in another special provision or in table 301-2 of standard spec 301.2.4.5. Set the lower warning limit 2 percent above the lower control limit. There are no upper limits.

B.6.3 Liquid Limit and Plasticity

- (1) Test the liquid limit and plasticity according to AASHTO T 89 and T 90.
- (2) Ensure the material conforms to the limits specified in standard spec table 301-2.

B.7 Corrective Action

B.7.1 General

- (1) Consider corrective action when the running average trends toward a warning limit. Take corrective action if an individual test exceeds the contract specification limit. Document all corrective actions both in the project records and on the appropriate control chart.

B.7.2 Placement Corrective Action

- (1) Do not blend additional material on the roadbed to correct gradation problems.
- (2) Notify the engineer whenever the running average exceeds a warning limit. When 2 consecutive running averages exceed a warning limit, the engineer and contractor will discuss appropriate corrective action. Perform the engineer's recommended corrective action and increase the testing frequency as follows:
 1. For gradation, increase the QC testing frequency to at least one randomly sampled test per 1000 tons placed.
 2. For fracture, increase the QC testing frequency to at least one test per gradation test.
- (3) If corrective action improves the property in question such that the running average after 4 additional tests is within the warning limits, the contractor may return to the testing frequency specified in B.5.3. If corrective action does not improve the property in question such that the running average after 4 additional individual tests is still in the warning band, repeat the steps outlined above starting with engineer notification.
- (4) If the running average exceeds a control limit, material starting from the first running average exceeding the control limit and ending at the first subsequent running average inside the control limit is nonconforming and subject to pay reduction.
- (5) For individual test results significantly outside the control limits, notify the engineer, stop placing base, and suspend other activities that may affect the area in question. The engineer and contractor will jointly review data, data reduction, and data analysis; evaluate sampling and testing procedures; and perform additional testing as required to determine the extent of potentially unacceptable material. The engineer may direct the contractor to remove and replace that material. Individual test results are significantly outside the control limits if meeting one or more of the following criteria:

1. A gradation control limit for the No. 200 sieve is exceeded by more than 3.0 percent.
2. A gradation control limit for any sieve, except the No. 200, is exceeded by more than 5.0 percent.
3. The fracture control limit is exceeded by more than 10.0 percent.

B.8 Department Testing

B.8.1 General

- (1) The department will conduct verification testing to validate the quality of the product and independent assurance testing to evaluate the sampling and testing. The department will provide the contractor with a listing of names and telephone numbers of all QV and IA personnel for the project, and provide test results to the contractor within 2 business days after the department obtains the sample.

B.8.2 Verification Testing

B.8.2.1 General

- (1) The department will have an HTCP technician, or ACT working under a certified technician, perform QV sampling and testing. Department verification testing personnel must meet the same certification level requirements specified in B.2 for contractor testing personnel for each test result being verified. The department will notify the contractor before sampling so the contractor can observe QV sampling.
- (2) The department will conduct QV tests of each base aggregate size, source or classification, and type during placement conforming to the following:
 1. One non-random test on the first day of placement.
 2. At least one random test per 30,000 tons, or fraction of 30,000 tons, placed.
- (3) The department will sample randomly, at locations independent of the contractor's QC work, collecting one sample at each QV location. The department will collect QV samples after the material has been bladed, mixed, and shaped but before compacting; except, for 3-inch aggregates, the department will collect samples from the stockpile at load-out. The department will split each sample, test half for QV, and retain half.
- (4) The department will conduct QV tests in a separate laboratory and with separate equipment from the contractor's QC tests. The department will use the same methods specified for QC testing.
- (5) The department will assess QV results by comparing to the appropriate specification limits. If QV test results conform to the specification, the department will take no further action. If QV test results are nonconforming, add the QV to the QC test results as if it were an additional QC test.

B.8.3 Independent Assurance

- (1) Independence assurance is unbiased testing the department performs to evaluate the department's QV and the contractor's QC sampling and testing including personnel qualifications, procedures, and equipment. The department will perform an IA review

according to the department's independent assurance program. That review may include one or more of the following:

1. Split sample testing.
 2. Proficiency sample testing.
 3. Witnessing sampling and testing.
 4. Test equipment calibration checks.
 5. Reviewing required worksheets and control charts.
 6. Requesting that testing personnel perform additional sampling and testing.
- (2) If the department identifies a deficiency, and after further investigation confirms it, correct that deficiency. If the contractor does not correct or fails to cooperate in resolving identified deficiencies, the engineer may suspend placement until action is taken. Resolve disputes as specified in B.9.

B.9 Dispute Resolution

- (1) The engineer and contractor should make every effort to avoid conflict. If a dispute between some aspect of the contractor's and the engineer's testing program does occur, seek a solution mutually agreeable to the project personnel. The department and contractor may review the data, examine data reduction and analysis methods, evaluate sampling and testing procedures, and perform additional testing. Use ASTM E 178 to evaluate potential statistically outlying data.
- (2) Production test results, and results from other process control testing, may be considered when resolving a dispute.
- (3) If the project personnel cannot resolve a dispute, and the dispute affects payment or could result in incorporating non-conforming product, the department will use third party testing to resolve the dispute. The department's central office laboratory, or a mutually agreed on independent testing laboratory, will provide this testing. The engineer and contractor will abide by the results of the third party tests. The party in error will pay service charges incurred for testing by an independent laboratory. The department may use third party test results to evaluate the quality of questionable materials and determine the appropriate payment. The department may reject material or otherwise determine the final disposition of nonconforming material as specified in standard spec 106.5.

C (Vacant)

D (Vacant)

E Payment

- (1) Costs for all sampling, testing, and documentation required under this special provision are incidental to this work. If the contractor fails to perform the work required under this special provision, the department may reduce the contractor's pay. The department will administer pay reduction under the non-performance of QMP administrative item.

- (2) For material represented by a running average exceeding a control limit, the department will reduce pay by 10 percent of the contract price for the affected Base Aggregate bid items listed in subsection A. The department will administer pay reduction under the Nonconforming QMP Base Aggregate Gradation or Nonconforming QMP Base Aggregate Fracture Administrative items. The department will determine the quantity of nonconforming material as specified in B.7.2.

301-010 (20100709)

13. QMP Ride; Incentive IRI Ride, Item 440.4410.S.

A Description

- (1) This special provision describes profiling pavements with a non-contact profiler, locating areas of localized roughness, and determining the International Roughness Index (IRI) for each wheel path segment.
- (2) Profile the final riding surface of all mainline pavements. Include auxiliary lanes in Category I and II segments; crossroads with county, state or U.S. highway designations greater than 1500 feet in continuous length; bridges, bridge approaches; and railroad crossings. Exclude roundabouts and pavements within 150 feet of the points of curvature of roundabout intersections.
- (3) The engineer may direct straightedging under standard spec 415.3.10 for pavement excluded from localized roughness under C.5.2 (1); for bridges; and for roundabouts and pavements within 150 feet of the points of curvature of roundabout intersections. Other surfaces being tested under this provision are exempt from straightedging requirements.

B (Vacant)

C Construction

C.1 Quality Control Plan

- (1) Submit a written quality control plan to the engineer at or before the pre-pave meeting. Ensure that the plan provides the following elements:
 1. An organizational chart with names, telephone numbers, current certifications and/or titles, and roles and responsibilities of all quality control personnel.
 2. The process by which quality control information and corrective action efforts will be disseminated to the appropriate persons. Include a list of recipients, the communication means that will be used, and action time frames.
 3. The methods and timing used for monitoring and/or testing ride quality throughout the paving process. Also indicate the approximate timing of acceptance testing in relation to the paving operations.
 4. The segment locations of each profile run used for acceptance testing.
 5. Traffic Control Plan

C.2 Personnel

- (1) Have a profiler operator, certified under the department's highway technician certification program (HTCP), operate the equipment, collect the required data, and analyze the results using the methods taught in the HTCP profiling course. Ensure that an HTCP-certified profiler operator supervises data entry into the material records system (MRS).

C.3 Equipment

- (1) Furnish a profile-measuring device capable of measuring IRI from the list of department-approved devices published on the department's web site:
<http://roadwaystandards.dot.wi.gov/standards/qmp/index.htm>
- (2) Unless the engineer and contractor mutually agree otherwise, arrange to have a calibrated profiler available when paving the final riding surface.
- (3) Perform daily calibration verification of the profiler using test methods according to the manufacturer's recommendations. Notify the engineer before performing the calibration verification. If the engineer requests, arrange to have the engineer observe the calibration verification and operation. Maintain records of the calibration verification activities, and provide the records to the engineer upon request.

C.4 Testing

C.4.1 Run and Reduction Parameters

- (1) Enter the equipment-specific department-approved filter settings and parameters given in the approved profilers list on the department's QMP ride web site.
<http://roadwaystandards.dot.wi.gov/standards/qmp/profilers.pdf>

C.4.2 Contractor Testing

- (1) Operate profilers within the manufacturer's recommended speed tolerances. Perform all profile runs in the direction of travel. Measure the longitudinal profile of each wheel track of each lane. The wheel tracks are 6.0 feet apart and centered in the traveled way of the lane.
- (2) Coordinate with the engineer to schedule profile runs for acceptance. The department may require testing to accommodate staged construction or if corrective action may be required.
- (3) Measure the profiles of each standard or partial segment. Define primary segments starting at a project terminus and running contiguously along the mainline to the other project terminus. Field-locate the beginning and ending points for each profile run. When applicable, align segment limits with the subplot limits used for testing under the QMP Concrete Pavement specification. Define segments one wheel path wide and distinguished by length as follows:

1. Standard segments are 500 feet long.
 2. Partial segments are less than 500 feet long.
- (4) Treat partial segments as independent segments.

The department will categorize each standard or partial segment as follows:

Segments with a Posted Speed Limit of 55 MPH or Greater	
Category	Description
HMA I	Asphalt pavement with multiple opportunities to achieve a smooth ride. The following operations performed under this contract are considered as opportunities: a layer of HMA, a leveling or wedging layer of HMA, and diamond grinding or partial depth milling of the underlying pavement surface.
HMA II	Asphalt pavement with a single opportunity to achieve a smooth ride.
HMA III	Asphalt pavement segments containing any portion of a bridge, bridge approach, railroad crossing, or intersection. An intersection is defined as the area within the points of curvature of the intersection radii.
PCC II	Concrete pavement.
PCC III	Concrete pavement segments containing any portion of a bridge, bridge approach, railroad crossing, intersection or gap. An intersection is defined as the area within the points of curvature of the intersection radii.

Segments with Any Portion Having a Posted Speed Limit Less Than 55 MPH	
Category	Description
HMA IV	Asphalt pavement including intersections, bridges, approaches, and railroad crossings.
PCC IV	Concrete pavement including gaps, intersections, bridges, approaches, and railroad crossings.

C.4.3 Verification Testing

- (1) The department may conduct verification testing (QV) to validate the quality of the product. A HTCP certified profiler operator will perform the QV testing. The department will provide the contractor with a listing of the names and telephone numbers of all verification personnel for the project.
- (2) The department will notify the contractor before testing so the contractor can observe the QV testing. Verification testing will be performed independent of the contractor's QC work using separate equipment from the contractor's QC tests. The department will provide test results to the contractor within 1 business day after the department completes the testing.

- (3) The engineer and contractor will jointly investigate any testing discrepancies. The investigation may include additional testing as well as review and observation of both the department's and contractor's testing procedures and equipment. Both parties will document all investigative work.
- (4) If the contractor does not respond to an engineer request to resolve a testing discrepancy, the engineer may suspend production until action is taken. Resolve disputes as specified in C.6.

C.4.4 Documenting Profile Runs

- (1) Compute the IRI for each segment and analyze areas of localized roughness using the ProVAL software. Also, the contractor shall prepare the ProVAL Ride Quality Module Reports, showing the IRI for each segment and the areas of localized roughness exceeding an IRI of 200 in/mile. Use ride quality module report as follows:

	<u>Fixed Interval</u>	<u>Continuous (Localized Roughness)</u>
Base-length	500'	25'
Threshold	140"/Mile	200"/Mile

The ProVAL software is available for download at:

<http://www.roadprofile.com>.

- (2) As part of the profiler software outputs and ProVAL reports, document the areas of localized roughness. Field-locate the areas of localized roughness prior to the engineer's assessment for corrective actions. Document the reasons for areas excluded and submit to the engineer.
- (3) Within 5 business days after completing profiling of the pavement covered under this special provision, unless the engineer and contractor mutually agree to a different timeline, submit the electronic ProVAL project file containing the .ppf files for each profiler acceptance run data and Ride Quality Module Reports, in .pdf format using the department's Materials Reporting System (MRS) software available on the department's web site:

<http://www.atwoodsystems.com/mrs>

Notify the engineer when the Profiler Acceptance Run data and the Ride Quality Report have been submitted to the MRS system.

C.5 Corrective Actions

C.5.1 General

- (1) Analyze the data from the PROVAL reports and make corrective action recommendations to the department. The department will independently assess whether a repair will help or hurt the long-term pavement performance before deciding on corrective action. Correct the ride as the engineer directs in writing.

C.5.2 Corrective Actions for Localized Roughness

- (1) Apply localized roughness requirements to all pavements, including HMA III, PCC III, HMA IV, and PCC IV; except localized roughness requirements will not be applied to pavements within 25 feet of the following surfaces if they are not constructed under this contract: bridges, bridge approaches, or railroad crossings. The department may direct the contractor to make corrections to the pavement within the 25-foot exclusionary zones.
- (2) The engineer will review each individual wheel track for areas of localized roughness. The engineer will assess areas of localized roughness within 5 business days of receiving notification that the reports were uploaded. The engineer will analyze the report documenting areas that exceed an IRI of 200 in/mile and do one of the following for each location:
 1. Direct the contractor to correct the area to minimize the effect on the ride.
 2. Leave the area of localized roughness in place with no pay reduction.
 3. Except for HMA IV and PCC IV segments, assess a pay reduction as follows for each location in each wheel path:

Localized Roughness IRI (in/mile)	Pay Reduction^[1] (dollars)
> 200	(Length in Feet) x (IRI –200)

^[1] A maximum \$250 pay reduction may be assessed for locations of localized roughness that are less than or equal to 25 feet long. Locations longer than 25 feet may be assessed a maximum pay reduction of \$10 per foot.

- (3) The engineer will not direct corrective action or assess a pay reduction for an area of localized roughness without independent identification of that area as determined by physically riding the pavement. For corrections, use only techniques the engineer approves.
- (4) Re-profile corrected areas to verify that the IRI is less than 140 in/mile after correction. Submit a revised ProVAL ride quality module report to the reference documents section of the MRS for the corrected areas to validate the results.

C.5.3 Corrective Actions for Excessive IRI

- (1) If an individual segment IRI exceeds 140 in/mile for HMA I, HMA II, and PCC II pavements after correction for localized roughness, the engineer may require the contractor to correct that segment. Correct the segment final surface as follows:

- HMA I: Correct to an IRI of 60 in/mile using whichever of the following methods as approved by the engineer:
Mill and replace the full lane width of the riding surface excluding the paved shoulder.
Continuous diamond grinding or fine-tooth milling the full lane width, if required, of the riding surface including adjustment of the paved shoulders.
- HMA II: Correct to an IRI of 85 in/mile using whichever of the following methods as approved by the engineer:
Mill and replace the full lane width of the riding surface excluding the paved shoulder.
Continuous diamond grinding or fine-tooth milling of the full lane width, if required, of the riding surface including adjustment of the paved shoulders
- PCC II: Correct to an IRI of 85 in/mile using whichever of the following methods as approved by the engineer:
Continuous diamond grinding of the full lane width, if required, of the riding surface including adjustment of the paved shoulders. Conform to sections C.1 through C.4 of Concrete Pavement Continuous Diamond Grinding Special provision contained elsewhere in the contract.
Remove and replace the full lane width of the riding surface.

- (2) Re-profile corrected segments to verify that the final IRI meets the above correction limits and there are no areas of localized roughness. Enter a revised ProVAL ride quality module report for the corrected areas to the reference documents section of the MRS. Segments failing these criteria after correction are subject to the engineer's right to adjust pay for non-conforming work under standard spec 105.3.

C.6 Dispute Resolution

- (1) The engineer and contractor should make every effort to avoid conflict. If a dispute between some aspect of the contractor's and the engineer's testing program does occur, seek a solution mutually agreeable to the project personnel. The department and contractor may review the data, examine data reduction and analysis methods, evaluate testing procedures, and perform additional testing.
- (2) If the project personnel cannot resolve a dispute and the dispute affects payment or could result in incorporating nonconforming pavement, the department will use third party testing to resolve the dispute. The department's Quality Assurance Unit, or a mutually agreed on independent testing company, will provide this testing. The engineer and contractor will abide by the results of the third party tests. The party in

error will pay service charges incurred for testing by an independent tester. The department may use third party tests to evaluate the quality of questionable pavement and determine the appropriate payment.

D Measurement

- (1) The department will measure Incentive IRI Ride by the dollar, adjusted as specified in E.2.

E Payment

E.1 Payment for Profiling

- (1) Costs for furnishing and operating the profiler, documenting profile results, and correcting the final pavement surface are incidental to the contract. The department will pay separately for engineer-directed corrective action performed within the 25-foot exclusionary zones under C.5.2 as extra work.

E.2 Pay Adjustment

- (1) The department will pay incentive for ride under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
440.4410.S	Incentive IRI Ride	DOL

- (2) Incentive payment is not limited, either up or down, to the amount the schedule of items shows.
- (3) The department will administer disincentives for ride under the Disincentive IRI Ride administrative item.
- (4) The department will not assess disincentive on HMA III or PCC III segments. Incentive pay for HMA III and PCC III segments will be according to the requirements for the category of the adjoining segments.
- (5) The department will adjust pay for each segment based on the initial IRI for that segment. If corrective action is required, the department will base disincentives on the IRI after correction for pavement meeting the following conditions:
 - All Pavement: The corrective work is performed in a contiguous, full lane width section 500 feet long, or a length as agreed with the engineer.
 - HMA Pavements: The corrective work is a mill and inlay or full depth replacement and the inlay or replacement layer thickness conforms to standard spec 460.3.2.
 - Concrete Pavements: The corrective work is a full depth replacement and conforms to standard spec 415.
- (6) The department will adjust pay for 500-foot long standard segments nominally one wheel path wide using equation “QMP 1.04” as follows:

HMA I	
Initial IRI (inches/mile)	Pay Adjustment^[1] (dollars per standard segment)
< 30	250
≥ 30 to <35	1750 – (50 x IRI)
≥ 35 to < 60	0
≥ 60 to < 75	1000 – (50/3 x IRI)
≥ 75	-250

HMA II and PCC II	
Initial IRI (inches/mile)	Pay Adjustment^{[1][2]} (dollars per standard segment)
< 50	250
≥ 50 to < 55	2750 – (50 x IRI)
≥ 55 to < 85	0
≥ 85 to < 100	(4250/3) – (50/3 x IRI)
≥ 100	-250

HMA IV and PCC IV	
Initial IRI (inches/mile)	Pay Adjustment^{[1][2]} (dollars per standard segment)
< 35	250
≥ 35 to < 45	1125-(25xIRI)
≥ 45	0

^[1] If the engineer directs placing upper layer asphaltic mixtures between October 15 and May 1 for department convenience as specified in standard spec 450.3.2.1(5), the department will not adjust pay for ride on pavement the department orders the contractor to place when the temperature, as defined in standard spec 450.3.2.1(2), is less than 36 F.

^[2] If the engineer directs placing concrete pavement for department convenience, the department will not adjust pay for ride on pavement the department orders the contractor to place when the air temperature falls below 35 F.

(7) The department will prorate the pay adjustment for partial segments based on their length.

440-010 (20130615)

14. QMP HMA Pavement Nuclear Density.

A Description

Replace standard spec 460.3.3.2 (1) and standard spec 460.3.3.2 (4) with the following:

- (1) This special provision describes density testing of in-place HMA pavement with the use of nuclear density gauges. Conform to standard spec 460 as modified in this special provision.

- (2) Provide and maintain a quality control program defined as all activities and documentation of the following:
 1. Selection of test sites.
 2. Testing.
 3. Necessary adjustments in the process.
 4. Process control inspection.
- (3) Chapter 8 of the department's construction and materials manual (CMM) provides additional detailed guidance for QMP work and describes required procedures. Obtain the CMM from the department's web site at:
<http://roadwaystandards.dot.wi.gov/standards/cmm/index.htm>
- (4) The department's Materials Reporting System (MRS) software allows contractors to submit data to the department electronically, estimate pay adjustments, and print selected reports. Qualified personnel may obtain MRS software from the department's web site at:
<http://www.atwoodsystems.com/mrs>

B Materials

B.1 Personnel

- (1) Perform HMA pavement density (QC, QV) testing using a HTCP certified nuclear technician I, or a nuclear assistant certified technician (ACT-NUC) working under a certified technician.
- (2) If an ACT is performing sampling or testing, a certified technician must coordinate and take responsibility for the work an ACT performs. Have a certified technician ensure that all sampling and testing is performed correctly, analyze test results, and post resulting data. No more than one ACT can work under a single certified technician.

B.2 Testing

- (1) Conform to ASTM D2950 and CMM 8.15 for density testing and gauge monitoring methods. Perform nuclear gauge measurements using gamma radiation in the backscatter position. Perform each test for 4 minutes of nuclear gauge count time.

B.3 Equipment

B.3.1 General

- (1) Furnish nuclear gauges from the department's approved product list at
<http://www.dot.wisconsin.gov/business/engrserve/approvedprod.htm>.
- (2) Have the gauge calibrated by the manufacturer or an approved calibration service within 12 months of its use on the project. Retain a copy of the manufacturer's calibration certificate with the gauge.

- (3) Prior to each construction season, and following any calibration of the gauge, the contractor must perform calibration verification for each gauge using the reference blocks located in the department's central office materials laboratory. To obtain information or schedule a time to perform calibration verification, contact the department's Radiation Safety Officer at:
Materials Management Section
3502 Kinsman Blvd.
Madison, Wisconsin 53704
Telephone: (608) 243-5998

B.3.2 Correlation of Nuclear Gauges

B.3.2.1 Correlation of QC and QV Nuclear Gauges

- (1) Select a representative section of the compacted pavement prior to or on the first day of paving for the correlation process. The section does not have to be the same mix design.
- (2) Correlate the 2 or more gauges used for density measurement (QC, QV). The QC and QV gauge operators will perform the correlation on 5 test sites jointly located. Record each density measurement of each test site for the QC, QV and back up gauges.
- (3) Calculate the average of the difference in density of the 5 test sites between the QC and QV gauges. Locate an additional 5 test sites if the average difference exceeds 1.0 lb/ft³. Measure and record the density on the 5 additional test sites for each gauge.
- (4) Calculate the average of the difference in density of the 10 test sites between the QC and QV gauges. Replace one or both gauges if the average difference of the 10 tests exceeds 1.0 lb/ft³ and repeat correlation process from B.3.2.1 (2).
- (5) Furnish one of the QC gauges passing the allowable correlation tolerances to perform density testing on the project.

B.3.2.2 Correlation Monitoring

- (1) After performing the gauge correlation specified in B.3.2.1, establish a project reference site approved by the department. Clearly mark a flat surface of concrete or asphalt or other material that will not be disturbed during the duration of the project. Perform correlation monitoring of the QC, QV, and all back-up gauges at the project reference site.
- (2) Conduct an initial 10 density tests with each gauge on the project reference site and calculate the average value for each gauge to establish the gauge's reference value. Use the gauge's reference value as a control to monitor the calibration of the gauge for the duration of the project.
- (3) Check each gauge on the project reference site a minimum of one test per day if paving on the project. Calculate the difference between the gauge's daily test result and its reference value. Investigate if a daily test result is not within 1.5 lb/ft³ of its

reference value. Conduct 5 additional tests at the reference site once the cause of deviation is corrected. Calculate and record the average of the 5 additional tests. Remove the gauge from the project if the 5-test average is not within 1.5 lb/ft³ of its reference value established in B.3.2.2(2).

- (4) Maintain the reference site test data for each gauge at an agreed location.

B.4 Quality Control Testing and Documentation

B.4.1 Lot and Sublot Requirements

B.4.1.1 Mainline Traffic Lanes, Shoulders, and Appurtenances

- (1) A lot consists of the tonnage placed each day for each layer and target density specified in standard spec 460.3.3.1. A lot may include partial sublots.
- (2) Divide the roadway into sublots. A sublot is 1500 lane feet for each layer and target density.
- (3) A sublot may include HMA placed on more than one day of paving. Test sublots at the pre-determined random locations regardless of when the HMA is placed. No additional testing is required for partial sublots at the beginning or end of a day's paving.
- (4) If a resulting partial quantity at the end of the project is less than 750 lane feet, include that partial quantity with the last full sublot of the lane. If a resulting partial quantity at the end of the project is 750 lane feet or more, create a separate sublot for that partial quantity.
- (5) Randomly select test locations for each sublot as specified in CMM 8.15 prior to paving and provide a copy to the engineer. Locate and mark QC density test sites when performing the tests. Perform density tests prior to opening the roadway to traffic.
- (6) Use Table 1 to determine the number of tests required at each station, depending on the width of the lane being tested. When more than one test is required at a station, offset the tests 10 feet longitudinally from one another to form a diagonal testing row across the lane.

Lane Width	No. of Tests	Transverse Location
5 ft or less	1	Random
Greater than 5 ft to 9 ft	2	Random within 2 equal widths
Greater than 9 ft	3	Random within 3 equal widths

Table 1

B.4.1.2 Side Roads, Crossovers, Turn Lanes, Ramps, and Roundabouts

- (1) A lot represents a combination of the total daily tonnage for each layer and target density.

- (2) Each side road, crossover, turn lane, ramp, and roundabout must contain at least one subplot for each layer.
- (3) If a side road, crossover, turn lane, or ramp is 1500 feet or longer, determine sublots and random test locations as specified in B.4.1.1.
- (4) If a side road, crossover, turn lane, or ramp is less than 1500 feet long, determine sublots using a maximum of 750 tons per subplot and perform the number of random tests as specified in Table 2.

Side Roads, Turn Lanes, Crossovers, Ramps, Roundabouts: Sublot/Layer tonnage	Minimum Number of Tests Required
25 to 100 tons	1
101 to 250 tons	3
251 to 500 tons	5
501 to 750 tons	7

Table 2

B.4.2 Pavement Density Determination

B.4.2.1 Mainline Traffic Lanes and Appurtenances

- (1) Calculate the average subplot densities using the individual test results in each subplot.
- (2) If all subplot averages are no more than one percent below the target density, calculate the daily lot density by averaging the results of each random QC test taken on that day's material.
- (3) If any subplot average is more than one percent below the target density, do not include the individual test results from that subplot when computing the lot average density and remove that subplot's tonnage from the daily quantity for incentive. The tonnage from any such subplot is subject to disincentive pay according to standard spec 460.5.2.2.

B.4.2.2 Mainline Shoulders

B.4.2.2.1 Width Greater Than 5 Feet

- (1) Determine the pavement density as specified in B.4.2.1.

B.4.2.2.2 Width of 5 Feet or Less

- (1) If all subplot test results are no more than 3.0 percent below the minimum target density, calculate the daily lot density by averaging all individual test results for the day.
- (2) If a subplot test result is more than 3.0 percent below the target density, the engineer may require the unacceptable material to be removed and replaced with acceptable material or allow the nonconforming material to remain in place with a 50 percent pay reduction. Determine the limits of the unacceptable material according to B.4.3.

B.4.2.3 Side Roads, Crossovers, Turn Lanes, Ramps, and Roundabouts

- (1) Determine the pavement density as specified in B.4.2.1.

B.4.2.4 Documentation

- (1) Document QC density test data as specified in CMM 8.15. Provide the engineer with the data for each lot within 24 hours of completing the QC testing for the lot.

B.4.3 Corrective Action

- (1) Notify the engineer immediately when an individual test is more than 3.0 percent below the specified minimum in standard spec 460.3.3.1. Investigate and determine the cause of the unacceptable test result.
- (2) The engineer may require unacceptable material specified in B.4.3(1) to be removed and replaced with acceptable material or allow the nonconforming material to remain in place with a 50 percent pay reduction. Determine limits of the unacceptable area by measuring density of the layer at 50-foot increments both ahead and behind the point of unacceptable density and at the same offset as the original test site. Continue testing at 50-foot increments until a point of acceptable density is found as specified in standard spec 460.5.2.2(1). Removal and replacement of material may be required if extended testing is in a previously accepted subplot. Testing in a previously accepted subplot will not be used to recalculate a new lot density.
- (3) Compute unacceptable pavement area using the product of the longitudinal limits of the unacceptable density and the full subplot width within the traffic lanes or shoulders.
- (4) Retesting and acceptance of replaced pavement will be according to standard spec 105.3.
- (5) Tests indicating density more than 3.0 percent below the specified minimum, and further tests taken to determine the limits of unacceptable area, are excluded from the computations of the subplot and lot densities.
- (6) If 2 consecutive subplot averages within the same paving pass and same target density are more than one percent below the specified target density, notify the engineer and take necessary corrective action. Document the locations of such sublots and the corrective action that was taken.

B.5 Department Testing

B.5.1 Verification Testing

- (1) The department will have a HTCP certified technician, or ACT working under a certified technician, perform verification testing. The department will test randomly at locations independent of the contractor's QC work. The department will perform verification testing at a minimum frequency of 10 percent of the sublots and a minimum of one subplot per mix design. The sublots selected will be within the active

work zone. The contractor will supply the necessary traffic control for the department's testing activities.

- (2) The QV tester will test each selected subplot using the same testing requirements and frequencies as the QC tester.
- (3) If the verification subplot average is not more than one percent below the specified minimum target density, use the QC tests for acceptance.
- (4) If the verification subplot average is more than one percent below the specified target density, compare the QC and QV subplot averages. If the QV subplot average is within 1.0 lb/ft³ of the QC subplot average, use the QC tests for acceptance.
- (5) If the first QV/QC subplot average comparison shows a difference of more than 1.0 lb/ft³ each tester will perform an additional set of tests within that subplot. Combine the additional tests with the original set of tests to compute a new subplot average for each tester. If the new QV and QC subplot averages compare to within 1.0 lb/ft³, use the original QC tests for acceptance.
- (6) If the QV and QC subplot averages differ by more than 1.0 lb/ft³ after a second set of tests, resolve the difference with dispute resolution specified in B.6. The engineer will notify the contractor immediately when density deficiencies or testing precision exceeding the allowable differences are observed.

B.5.2 Independent Assurance Testing

- (1) Independent assurance is unbiased testing the department performs to evaluate the department's verification and the contractor's QC sampling and testing including personnel qualifications, procedures, and equipment. The department will perform the independent assurance review according to the department's independent assurance program.

B.6 Dispute Resolution

- (1) The testers may perform investigation in the work zone by analyzing the testing, calculation, and documentation procedures. The testers may perform gauge correlation according to B.3.2.1.
- (2) The testers may use correlation monitoring according to B.3.2.2 to determine if one of the gauges is out of tolerance. If a gauge is found to be out of tolerance with its reference value, remove the gauge from the project and use the other gauge's test results for acceptance.
- (3) If the testing discrepancy cannot be identified, the contractor may elect to accept the QV subplot density test results or retesting of the subplot in dispute within 48 hours of paving. Traffic control costs will be split between the department and the contractor.

- (4) If investigation finds that both gauges are in error, the contractor and engineer will reach a decision on resolution through mutual agreement.

B.7 Acceptance

- (1) The department will not accept QMP HMA Pavement Nuclear Density if a non-correlated gauge is used for contractor QC tests.

C (Vacant)

D (Vacant)

E Payment

E.1 QMP Testing

- (1) Costs for all sampling, testing, and documentation required under this special provision are incidental to the work. If the contractor fails to perform the work required under this special provision, the department may reduce the contractor's pay. The department will administer pay reduction under the Non-performance of QMP administrative item.

E.2 Disincentive for HMA Pavement Density

- (1) The department will administer density disincentives according to standard spec 460.5.2.2.

E.3 Incentive for HMA Pavement Density

- (1) Delete standard spec 460.5.2.3.
- (2) If the lot density is greater than the minimum specified in standard spec table 460-3 and all individual air voids test results for that mixture are within +1.0 percent or -0.5 percent of the design target in standard spec table 460-2, the department will adjust pay for that lot as follows:

Percent Lot Density Above Minimum	Pay Adjustment Per Ton
From -0.4 to 1.0 inclusive	\$0
From 1.1 to 1.8 inclusive	\$0.40
More than 1.8	\$0.80

- (3) The department will adjust pay under the Incentive Density HMA Pavement bid item. Adjustment under this item is not limited, either up or down, to the bid amount shown on the schedule of items.
 - (4) If a traffic lane meets the requirements for disincentive, the department will not pay incentive on the integrally paved shoulder.
 - (5) Submit density results to the department electronically using the MRS software. The department will validate all contractor data before determining pay adjustments.
- 460-020 (20100709)

15. Reheating HMA Pavement Longitudinal Joints, Item 460.4110.S.

A Description

This Special provision describes reheating the abutting edge of the previously compacted layer in the adjacent lane while paving mainline asphalt pavements.

B (Vacant)

C Construction

C.1. Equipment

Provide a self contained heating unit that heats by convention only. Do not use forced air to enhance the flame. Provide a fire proof barrier between the flame and the heater's fuel source. The heater must produce a uniform distribution of heat with in the heat box. Provide automatic controls to regulate the heater output and shutoff the heater when the paver stops or the heater control system loses power.

Mount the heater on the paver inside the paver's automatic leveling device.

C.2. Reheating Joints

Evenly reheat at least 8 inch (200 mm) wide strip of the previously compacted layer in the adjacent lane as follows:

- Ambient air temperature at or above 60 degrees F (15 degrees C), reheat to 290 to 340 degrees F (143 – 171 degrees C).
- Ambient air temperature below 60 degrees F (15 degrees C), reheat 240 to 290 degrees F (115-143 degrees C).

The engineer may modify the required joint reheat temperatures to adjust for weather, wind and other field conditions. Coordinate the heater output and paver speed to achieve the required joint reheat temperature without visible smoke emission.

D Measurement

The department will measure Reheating HMA Pavement Longitudinal Joints by the linear foot, acceptably completed, as measured along each joint for each layer of asphalt placed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
460.4110. S	Reheating HMA Pavement Longitudinal Joints	LF

Payment in full compensation for furnishing all the work required under this bid item.
460-015(20120615)

16. Locating No-Passing Zones, Item 648.0100.

For this project, the spotting sight distance in areas with a 55 mph posted speed limit is 0.21 miles (1108 feet).

17. Pavement Marking Grooved Preformed Thermoplastic Arrows Type 2, Item SPV.0060.01; Arrows Type 3, Item SPV.0060.02; Words, Item SPV.0060.03; Stop Line 18-Inch, Item SPV.0090.01.

A Description

This special provision describes grooving the pavement surface, and furnishing and installing preformed thermoplastic pavement marking as shown on the plans, in accordance to standard spec 647, and as hereinafter provided.

B Materials

Furnish 125 mils preformed thermoplastic pavement marking from the department's approved products list. If required, furnish sealant material recommended by the manufacturer.

C Construction

C.1 General

For quality assurance, provide the engineer and the region's Marking Section evidence of manufacturer training in the proper placement and installation of preformed thermoplastic pavement marking.

Plane the grooved lines in accordance to the plan details. Use grooving equipment with a free-floating, independent cutting or grinding head. Plane a minimum number of passes to create a smooth groove.

C.2 Groove Depth

Cut the groove to a depth of 120 mils \pm 10 mils deep from the pavement surface or, if tined, from the high point of the tined surface. Measure depth using a straightedge placed perpendicular to the groove. The department may periodically check groove depths.

C.3 Groove Width – Linear Markings

Cut the groove 1-inch wider than the width of the thermoplastic.

C.4 Groove Position

Position the groove edge in accordance to the plan details.

C.4.1 Linear Marking

Groove at a minimum of 4-inches, but not greater than, 12-inches from both ends of the line segment. Achieve straight alignment with the grooving equipment.

C.4.2 Special Marking

Groove at a minimum of 4-inches from the perimeter of the special marking. Groove separate areas for Word Items.

C.5 Groove Cleaning

C.5.1 Concrete

Cooling the cutting head with water may be necessary for some applications and equipment. If cooling water is necessary, flush the groove immediately with water after cutting to remove any build-up of cement dust and water slurry. If this is not done, the slurry may harden in the groove.

If water is used in the grooving process, allow the groove to dry a minimum of 24 hours after groove cleaning, after removal of excess water, and prior to pavement marking application. Clean and dry the groove for proper application of the sealant, and placement of the pavement marking. Use a high-pressure air blower with at least 185 ft³/min air flow and 90 psi air pressure to clean the groove; use of the air blower does not decrease the amount of time required for the groove to dry.

C.5.2 Asphalt

Use a high-pressure air blower with at least 185 ft³/min air flow and 90 psi air pressure to clean the groove.

Check for structural integrity in supporting grooving operations. If the structural integrity of the asphalt pavement is inadequate to support grooving operations, immediately notify the engineer.

C.6 Preformed Thermoplastic Application

Preheat the surface if necessary based on manufacturer's recommendation.

Apply preformed thermoplastic in the groove as per manufacturer's recommendations. If manufacturer's recommendations require a sealant, apply a sealant lower than 91g/l VOC during the following period of time due to Volatile Organic Compound Limitations:

May 1 to September 30, both dates inclusive – the Southeast Region and the ozone non-attainment Northeast Region counties of Sheboygan, Manitowoc, and Kewaunee.

Use any sealant in the remainder counties and for the remainder of the year. The sealant must be wet.

D Measurement

The department will measure Pavement Marking Grooved Preformed Thermoplastic (Type) by each individual unit, acceptably completed.

The department will measure Pavement Marking Grooved Preformed Thermoplastic Stop Line 18-Inch in length by the linear foot of tape placed, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid items:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0060.01	Pavement Marking Grooved Preformed Thermoplastic Arrows Type 2	Each
SPV.0060.02	Pavement Marking Grooved Preformed Thermoplastic Arrows Type 3	Each
SPV.0060.03	Pavement Marking Grooved Preformed Thermoplastic Words	Each
SPV.0090.01	Pavement Marking Grooved Preformed Thermoplastic Stop Line 18-Inch	LF

Payment is full compensation for cleaning and preparing the pavement surface, and for furnishing and installing the material.

18. Pavement Marking Grooved Preformed Plastic Tape 8-Inch, Item SPV.0090.02; 4-Inch, Item SPV.0090.03.

A Description

This special provision describes furnishing, grooving, and installing preformed plastic pavement marking tape as shown on the plans, in accordance to standard spec 646, and as hereinafter provided.

B Materials

Furnish grooved preformed plastic pavement marking tape and adhesive material, if required, from the department's approved products list.

Furnish a copy of the manufacturer's recommendations to the engineer before preparing the pavement marking grooves.

C Construction**C.1 General**

For quality assurance, provide the engineer and the region's Marking Section evidence of manufacturer training in the proper placement and installation of pavement marking tape.

Plane the grooved lines in accordance to details in the plan. Use grooving equipment with a free-floating, independent cutting or grinding head. Plane a minimum number of passes to create a smooth groove.

C.2 Groove Depth

Cut the groove to a depth of 120 mils \pm 10 mils from the pavement surface or, if tined, from the high point of the tined surface. Measure depth using a straightedge placed perpendicular to the groove. The department may periodically check groove depths.

C.3 Groove Width – Longitudinal Markings

Cut the groove one-inch wider than the width of the tape.

C.4 Groove Position

Position the groove edge in accordance to plan details. Groove a minimum of 4 inches, but not greater than, 12 inches from both ends of the tape segment. Achieve straight alignment with the grooving equipment.

C.5 Groove Cleaning

C.5.1 Concrete

Cooling the cutting head with water may be necessary for some applications and equipment. If cooling water is necessary, flush the groove immediately with water after cutting to remove any build-up of cement dust and water slurry. If this is not done, the slurry may harden in the groove.

If water is used in the grooving process, allow the groove to dry a minimum of 24 hours after groove cleaning, after removal of excess water, and prior to pavement marking application. Clean and dry the groove for proper application of the adhesive, and placement of the pavement marking. Use a high-pressure air blower with at least 185 ft³/min air flow and 90 psi air pressure to clean the groove; use of the air blower does not decrease the amount of time required for the groove to dry.

C.5.2 New Asphalt

Groove pavement 5 or more days after paving.

If opening to traffic an asphalt lane that is not grooved, place temporary pavement marking. For asphalt lanes not open to traffic, temporary pavement marking is not required.

Use a high-pressure air blower with at least 185 ft³/min air flow and 90 psi air pressure to clean the groove.

C.5.3 Existing Asphalt

Check for structural integrity in supporting grooving operations. If the structural integrity of the asphalt pavement is inadequate to support grooving operations, immediately notify the engineer.

Use a high-pressure air blower with at least 185 ft³/min air flow and 90 psi air pressure to clean the groove.

C.6 Tape Application

Apply the tape when both the air and surface temperature are 40 degrees F and rising.

Apply tape in the groove as per manufacturer's recommendations. If manufacturer's recommendations require surface preparation adhesive, apply an adhesive with lower than 91g/l VOC during the following period of time due to Volatile Organic Compound Limitations:

May 1 to September 30, both dates inclusive – the Southeast Region and the ozone non-attainment Northeast Region counties of Sheboygan, Manitowoc, and Kewaunee.

Use any adhesive from the preformed plastic approved products list in the remainder counties and for the remainder of the year.

The adhesive must be dry (feels tacky but is no longer in liquid form) and have a matte finish rather than a glossy wet appearance.

Tamp the pavement marking tape with a tamper cart roller cut to fit the groove. Tamp three complete cycles with grooved modified equipment.

D Measurement

The department will measure Pavement Marking Grooved Preformed Plastic Tape (Width) in length by the linear foot of tape placed, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid items:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0090.02	Pavement Marking Grooved Preformed Plastic Tape 8-Inch	LF
SPV.0090.03	Pavement Marking Grooved Preformed Plastic Tape 4-Inch	LF

Payment is full compensation for cleaning and preparing the pavement surface; furnishing and installing the material; furnishing, placing, and removing temporary pavement marking, if necessary.

19. Milling and Removing Temporary Joint, Item SPV.0105.01.

A Description

This special provision describes the milling and removing of the upper layer HMA wedge joints and any other temporary longitudinal or transverse joints, including sweeping and cleaning of the affected area prior to the abutting pavement placement.

B (Vacant)

C Construction

Immediately prior to placement of the adjoining lane, mill any temporary wedge joint to a true line with a face perpendicular to the surface of the existing asphaltic surface pavement.

Immediately prior to continuation of paving operations, mill any temporary transverse joint to a true line with a face perpendicular to the surface of the existing asphaltic surface pavement.

The contractor becomes the owner of the asphaltic pavement and is responsible for disposing of materials under standard spec 204.3.1.3.

D Measurement

The department will measure Milling and Removing Temporary Joint as a single lump sum unit of work for removing wedge joints, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0105.01	Milling and Removing Temporary Joint	LS

Payment is full compensation for milling, removing, sweeping, cleaning and disposing of materials.

20. Same Day Paving HMA Pavement Type E-3, Item SPV.0195.01.

A Description

This work shall consist of paving HMA pavement lower lift and any full depth milling the same day that milling operations occur. Work shall be done in accordance to the requirements of standard spec 460 and as shown in the plans.

B Materials

The materials shall conform to standard spec 460.2.

C Construction

The construction shall conform to standard spec 460.3.

D Measurement

The department will measure Same Day Paving HMA Pavement Type E-3 in accordance to standard spec 460.4.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0195.01	Same Day Paving HMA Pavement E-3	TON

Payment is full compensation in accordance to standard spec 460.5.

ADDITIONAL SPECIAL PROVISION 4

Payment to First-Tier Subcontractors

Within 10 calendar days of receiving a progress payment for work completed by a subcontractor, pay the subcontractor for that work. The prime contractor may withhold payment to a subcontractor if, within 10 calendar days of receipt of that progress payment, the prime contractor provides written notification to the subcontractor and the department documenting "just cause" for withholding payment.

The prime contractor may also withhold routine retainage from payments due subcontractors.

Payment to Lower-Tier Subcontractors

Ensure that subcontracting agreements at all tiers provide prompt payment rights to lower-tier subcontractors that parallel those granted first-tier subcontractors in this provision.

Release of Routine Retainage

After granting substantial completion the department may reduce the routine retainage withheld from the prime contractor to 75 percent of the original total amount retained.

When the Department sends the semi-final estimate the department may reduce the routine retainage withheld from the prime contractor to 10 percent of the original total amount retained.

Within 30 calendar days of receiving the semi-final estimate from the department, submit written certification that subcontractors at all tiers are paid in full for acceptably completed work and that no routine retainage is being withheld. The department will pay the prime contractor in full and reduce the routine retainage withheld from the prime contractor to zero when the department approves the final estimate.

This special provision does not limit the right of the department, prime contractor, or subcontractors at any tier to withhold payment for work not acceptably completed or work subject to an unresolved contract dispute.

ADDITIONAL SPECIAL PROVISION 6

ASP 6 - Modifications to the standard specifications

Make the following revisions to the 2014 edition of the standard specifications:

101.3 Definitions

Replace the definition of semi-final estimate with the following effective with the December 2013 letting:

Semi-final estimate An estimate indicating the engineer has measured and reported all contract quantities and materials requirements.

105.11.1 Partial Acceptance

Replace paragraph two with the following effective with the December 2013 letting:

- (2) Partial acceptance will relieve the contractor of maintenance responsibility for the designated portion of the work. By relieving the contractor of maintenance, the department does not relieve the contractor of responsibility for defective work or damages caused by the contractor's operations. Do not construe partial acceptance to be conditional final acceptance or final acceptance of any part of the project, or a waiver of any legal rights specified under 107.16.
-

105.11.2 Final Acceptance

Retitle and replace the entire text with the following effective with the December 2013 letting:

105.11.2 Project Acceptance

105.11.2.1 Inspection

105.11.2.1.1 General

- (1) Notify the engineer when the project is substantially complete as defined in 105.11.2.1.3. As soon as it is practical, the engineer will inspect the work and categorize it as one of the following:
 1. Unacceptable or not complete.
 2. Substantially complete.
 3. Complete.

105.11.2.1.2 Unacceptable or Not Complete

- (1) The engineer will identify, in writing, work that is unacceptable or not complete. Immediately correct or complete that work. The engineer will assess contract time until the work is corrected or completed.
- (2) Proceed as specified in 105.11.2.1.1 until the engineer determines that the work is complete.

105.11.2.1.3 Substantially Complete

- (1) The project is substantially complete and the engineer will no longer assess contract time if the contractor has completed all contract bid items and change order work, except for the punch-list. As applicable, the following must have occurred:
 1. All lanes of traffic are open on a finished surface.
 2. All signage and traffic control devices are in place and operating.
 3. All drainage, erosion control, excavation, and embankments are completed.
 4. All safety appurtenances are completed.
- (2) The engineer will provide a written punch-list enumerating work the contractor must perform and documents the contractor must submit before the the engineer will categorize the work as complete.
 1. Punch-list work includes uncompleted cleanup work required under 104.9 and minor corrective work. Immediately correct or complete the punch-list work. The engineer may restart contract time if the contractor does not complete the punch-list work within 5 business days after receiving the written punch-list. The engineer and contractor may mutually agree to extend this 5-day requirement.
 2. Punch-list documents include whatever contract required documentation is missing. The engineer may restart contract time if the contractor does not submit the punch-list documents within 15 business days after receiving the written punch-list. The engineer and contractor may mutually agree to extend this 15-day requirement.

- (3) Proceed as specified in 105.11.2.1.1 until the work is complete.

105.11.2.1.4 Complete

- (1) The project is complete when the contractor has completed all contract bid items, change order work, and punch-list work including the submission of all missing documentation.

105.11.2.2 Conditional Final Acceptance

- (1) When the engineer determines that the project is complete, the engineer will give the contractor written notice of conditional final acceptance relieving the contractor of maintenance responsibility for the completed work.

105.11.2.3 Final Acceptance

- (1) The engineer will grant final acceptance of the project after determining that all contract is work complete; all contract, materials, and payroll records are reviewed and approved; and the semi-final estimate quantities are final under 109.7.
- (2) Failure to discover defective work or materials before final acceptance does not prevent the department from rejecting that work or those materials later. The department may revoke final acceptance if the department discovers defective work or materials after it has accepted the work.
-

105.13.3 Submission of Claim

Replace paragraph one with the following effective with the December 2013 letting:

- (1) Submit the claim to the project engineer as promptly as possible following the submission of the Notice of Claim, but not later than final acceptance of the project as specified in 105.11.2.3. If the contractor does not submit the claim before final acceptance of the project, the department will deny the claim.
-

107.17.3 Railroad Insurance Requirements

Replace paragraph one with the following effective with the December 2013 letting:

- (1) If required by the special provisions, provide or arrange for a subcontractor to provide railroad protective liability insurance in addition to the types and limits of insurance required in 107.26. Keep railroad protective liability insurance coverage in force until completing all work, under or incidental to the contract, on the railroad right of way or premises of the railroad and until the engineer determines that the work is complete as specified in 105.11.2.1.4.

107.26 Standard Insurance Requirements

Replace paragraph one with the following effective with the December 2013 letting:

- (1) Maintain the following types and limits of commercial insurance in force until the engineer determines that the work is complete as specified in 105.11.2.1.4.

TABLE 107-1 REQUIRED INSURANCE AND MINIMUM COVERAGES

TYPE OF INSURANCE	MINIMUM LIMITS REQUIRED ^[1]
1. Commercial general liability insurance endorsed to include blanket contractual liability coverage. ^[2]	\$2 million combined single limits per occurrence with an annual aggregate limit of not less than \$4 million.
2. Workers' compensation.	Statutory limits
3. Employers' liability insurance.	Bodily injury by accident: \$100,000 each accident Bodily injury by disease: \$500,000 each accident \$100,000 each employee
4. Commercial automobile liability insurance covering all contractor-owned, non-owned, and hired vehicles used in carrying out the contract. ^[2]	\$1 million-combined single limits per occurrence.

^[1] The contractor may satisfy these requirements with primary insurance coverage or with excess/umbrella policies.

^[2] The Wisconsin Department of Transportation, its officers, agents, and employees shall be named as an additional insured under the general liability and automobile liability insurance.

108.14 Terminating the Contractor's Responsibility

Replace paragraph one with the following effective with the December 2013 letting:

- (1) The contractor's responsibilities are terminated, except as set forth in the contract bond and specified in 107.16, when the department grants final acceptance as specified in 105.11.2.3.

109.2 Scope of Payment

Replace paragraph two with the following effective with the December 2013 letting:

- (2) The department will pay for the quantity of work acceptably completed and measured for payment as the measurement subsection for each bid item specifies. Within the contract provide means to furnish and install the work complete and in-place. Payment is full compensation for everything required to perform the work under the applicable bid items including, but not limited to, the work elements listed in the payment subsection. Payment also includes all of the following not specifically excluded in that payment subsection:
1. Furnishing and installing all materials as well as furnishing the labor, tools, supplies, equipment, and incidentals necessary to perform the work.
 2. All losses or damages, except as specified in 107.14, arising from one or more of the following:
 - The nature of the work.
 - The action of the elements.
 - Unforeseen difficulties encountered during prosecution of the work.
 3. All insurance costs, expenses, and risks connected with the prosecution of the work.
 4. All expenses incurred because of an engineer-ordered suspension, except as specified in 104.2.2.3.
 5. All infringements of patents, trademarks, or copyrights.
 6. All other expenses incurred to complete and protect the work under the contract.

109.6.1 General

Replace paragraphs three and four with the following effective with the December 2013 letting:

- (3) The department's payment of an estimate before conditional final acceptance of the work does not constitute the department's acceptance of the work, and does not relieve the contractor of responsibility for:
 - 1. Protecting, repairing, correcting, or renewing the work.
 - 2. Replacing all defects in the construction or in the materials used in the construction of the work under the contract, or responsibility for damage attributable to these defects.
 - (4) The contractor is responsible for all defects or damage that the engineer may discover on or before the engineer's conditional final acceptance of the work. The engineer is the sole judge of these defects or damage, and the contractor is liable to the department for not correcting all defects or damage.
-

109.7 Acceptance and Final Payment

Replace paragraphs one and two with the following effective with the December 2013 letting:

- (1) After the engineer grants conditional final acceptance of the work as specified in 105.11.2.2 and reviews required document submittals and materials test reports, the engineer will issue the semi-final estimate.
 - (2) Within 30 calendar days after receiving the semi-final estimate, submit to the engineer a written statement of agreement or disagreement with the semi-final estimate. For an acceptable statement of disagreement, submit an item-by-item list with reasons for each disagreement. If the contractor does not submit this written statement within those 30 days, the engineer will process the final estimate for payment. The engineer and the contractor can mutually agree to extend this 30-day submission requirement.
-

450.3.3 Maintaining the Work

Replace paragraph one with the following effective with the December 2013 letting:

- (1) Protect and repair the prepared foundation, tack coat, base, paved traffic lanes, shoulders, and seal coat. Correct all rich or bleeding areas, breaks, raveled spots, or other nonconforming areas in the paved surface.
-

455.3.2.5 Maintaining Tack Coat

Replace paragraph one with the following effective with the December 2013 letting:

- (1) Protect and repair the existing surface and the tack coat. Correct areas with excess or deficient tack material and any breaks, raveled spots, or other areas where bond might be affected.
-

520.3.8 Protection After Laying

Delete the entire subsection.

614.2.1 General

Replace paragraphs five and six with the following effective with the December 2013 letting:

- (5) Furnish zinc coated wire rope and fitting conforming to the plans and galvanized according to ASTM A741.
- (6) Before installation store galvanized components above ground level and away from surface run off. The department may reject material if the zinc coating is physically damaged or oxidized.
- (7) Provide manufacturer's drawings, and installation and maintenance instructions when providing proprietary systems.

614.2.3 Steel Rail and Fittings

Replace paragraph one with the following effective with the December 2013 letting:

- (1) Furnish galvanized steel rail conforming to AASHTO M180 class A, type II beam using the single-spot test coating requirements. Furnish plates, anchor plates, post mounting brackets, and other structural steel components conforming to 506.2.2.1 and hot-dip galvanized according to ASTM A123.

614.2.7 Crash Cushions

Replace paragraph one with the following effective with the December 2013 letting:

- (1) Furnish permanent and temporary crash cushions from the department's approved products list. Use cushions as wide or wider than the plan back-width. Furnish transitions conforming to the crash cushion manufacturer's design and specifications. Submit manufacturer crash cushion and transition design details to engineer before installing.

616.3.1 General

Replace paragraph six with the following effective with the December 2013 letting:

- (6) Remove and dispose of all excess excavation and surplus materials from the fence site.

618.3.3 Restoration

Replace paragraph one with the following effective with the December 2013 letting:

- (1) Upon termination of hauling operations and before conditional final acceptance, restore all haul roads, including drainage facilities and other components, to the equivalent of pre-hauling conditions.

627.3.1 General

Replace paragraph four with the following effective with the December 2013 letting:

- (4) Maintain the mulched areas and repair all areas damaged by wind, erosion, traffic, fire or other causes.

637.3.2.1 General

Delete paragraph three effective with the December 2013 letting.

670.3.4.2 Post-Construction Work

Replace paragraph one with the following effective with the December 2013 letting:

- (1) Submit 5 copies of ITS documentation including but not limited to the following:
 - Operator's manual: for contractor furnished equipment, submit a manual containing detailed operating instructions for each different type or model of equipment and or operation performed.
 - Maintenance procedures manuals: for contractor furnished equipment, submit a manual containing detailed preventive and corrective maintenance procedures for each type or model of equipment furnished.
 - Cabinet fiber optic wiring diagram: submit a cabinet wiring diagram, identified by location for each cabinet. Include both electrical wiring and fiber optic conductor and cable connections. Place one copy of the fiber optic wiring diagram in a weatherproof holder in the cabinet. Deliver the other copies to the engineer.
 - As-built drawings: submit final as-built drawings that detail the final placement of all conduit, cabling, equipment, and geometric modifications within the contract. Provide all documentation in an electronic format adhering to the region's ITS computer aided drafting standards and according to the department's as-built requirements. The department will review the as-built drawings for content and electronic format. Modify both the content and format of as-built drawings until meeting all requirements.
 - Equipment inventory list: submit an inventory list including serial number, make, model, date installed, and location installed of all equipment installed under the contract.

Errata

Make the following corrections to the 2013 edition of the standard specifications:

415.3.14 Protecting Concrete

Correct errata by referencing the opening to service specification.

- (1) Erect and maintain suitable barricades and, if necessary, provide personnel to keep traffic off the newly constructed pavement until it is opened for service as specified in 415.3.15. Conform to 104.6 for methods of handling and facilitating traffic.

501.2.9 Concrete Curing Materials

Correct errata by changing AASHTO M171 to ASTM C171.

- (2) Furnish sheeting conforming to ASTM C171 for white opaque polyethylene film, except that the contractor may use clear or black polyethylene for cold weather protection.

607.2 Materials

Correct errata by changing AASHTO M198 to ASTM C990.

- (1) Use materials conforming to the requirements for the class of material named and specified below.

Composite pipe, couplings, fittings and joint materials	ASTM D2680
Annular rubber and plastic gaskets for flexible, watertight joints	ASTM C990
External rubber gaskets, mastic, and protective film.....	ASTM C877
Mortar	519.2.3

637.2.1.3 Sheet Aluminum

Correct errata by changing ASTM B449 to B921 and eliminating the specification for coating thickness.

- (4) Degrease, etch, and coat the sign blank on both sides with a chromate treatment conforming to ASTM B921, class 2.

637.3.3.4 Performance

Correct errata to reference to 105.11.2.3 as revised to implement changes to the finals process.

- (1) Under 105.11.2.3 the department may revoke acceptance and direct the contractor to repair or replace previously accepted sign installations if the department subsequently discovers evidence of defective materials or improper installation. Deficiencies that warrant department action include but are not limited to the following:
 - Sign posts more than five degrees out of plumb.
 - Signs twisted by more than 5 degrees from plan orientation.
 - Signs with delaminated or warped plywood.
 - Signs with bubbling, fading, delaminating, or buckling sheeting.

646.3.3.4 Proving Period

Correct errata to reference to 105.11.2.3 as revised to implement changes to the finals process.

- (4) Replace all marking within sections with a percent failing more than 10% and repair or replace all markings that, in the engineer's assessment, show evidence of improper construction. If post-acceptance inspections uncover evidence of defective materials or improper construction, the department may revoke acceptance under 105.11.2.3.

ADDITIONAL SPECIAL PROVISION 7

- A. Reporting 1st Tier and DBE Payments During Construction
1. Comply with reporting requirements specified in the department's Civil Rights Compliance, Contractor's User Manual, Sublets and Payments.
 2. Report payments to all DBE firms within 10 calendar days of receipt of a progress payment by the department or a contractor for work performed, materials furnished, or materials stockpiled by a DBE firm. Report the payment as specified in A(1) for all work satisfactorily performed and for all materials furnished or stockpiled.
 3. Report payments to all first tier subcontractor relationships within 10 calendar days of receipt of a progress payment by the department for work performed. Report the payment as specified in A(1) for all work satisfactorily performed.
 4. All tiers shall report payments as necessary to comply with the DBE payment requirement as specified in A(2).
 5. Require all first tier relationships, DBE firms and all other tier relationships necessary to comply with the DBE payment requirement in receipt of a progress payment by contractor to acknowledge receipt of payment as specified in A(1), (2), (3) and (4).
 6. All agreements made by a contractor shall include the provisions in A(1), (2), (3), (4) and (5), and shall be binding on all first tier subcontractor relationships and all contractors and subcontractors utilizing DBE firms on the project.
- B. Costs for conforming to this special provision are incidental to the contract.

ADDITIONAL SPECIAL PROVISION 9

Electronic Certified Payroll Submittal

(1) Use the department's Civil Rights Compliance System (CRCS) to submit certified payrolls electronically. Details are available online through the department's highway construction contractor information (HCCI) site on the Labor, Wages, and EEO Information page at:

<http://roadwaystandards.dot.wi.gov/hcci/labor-wages-eeo/index.shtm>

(2) Ensure that all tiers of subcontractors, as well as all trucking firms, submit their weekly certified payrolls electronically through CRCS. These payrolls are due within seven calendar days following the close of the payroll period. Every firm providing physical labor towards completing the project is a subcontractor under this special provision.

(3) Upon receipt of contract execution, promptly make all affected firms aware of the requirements under this special provision and arrange for them to receive CRCS training as they are about to begin payrolls. The department will provide training either in a classroom setting at one of our regional offices or by telephone. Contact Tess Mulrooney at 608-267-4489 to schedule the training.

(4) The department will reject all paper submittals of forms DT-1816 and DT-1929 for information required under this special provision. All costs for conforming to this special provision are incidental to the contract.

(5) Firms wishing to export payroll data from their computer system into CRCS should have their payroll coordinator send several sample electronic files to Tess two months before a payroll needs to be submitted. Not every contractor's payroll system is capable of producing export files. For details, see pages 17-22 of the CRCS System Background Information manual available online on the Labor, Wages, and EEO Information page at:

<http://roadwaystandards.dot.wi.gov/hcci/labor-wages-eeo/crc-basic-info.pdf>

APRIL 2013

BUY AMERICA PROVISION

All steel and iron materials permanently incorporated in this project shall be domestic products and all manufacturing and coating processes for these materials from smelting forward in the manufacturing process must have occurred within the United States. Coating includes epoxy coating, galvanizing, painting and any other coating that protects or enhances the value of a material subject to the requirements of Buy America. The exemption of this requirement is the minimal use of foreign materials if the total cost of such material permanently incorporated in the product does not exceed one-tenth of one percent (1/10 of 1%) of the total contract cost or \$2,500.00, whichever is greater. For purposes of this paragraph, the cost is that shown to be the value of the subject products as they are delivered to the project. The contractor shall take actions and provide documentation conforming to CMM 2-28.4 to ensure compliance with this "Buy America" provision.

<http://roadwaystandards.dot.wi.gov/standards/cmm/cm-02-28.pdf#cm2-28.4>

Upon completion of the project certify to the engineer, in writing using department form WS4567, that all steel, iron, and coating processes for steel or iron incorporated into the contract work conform to these "Buy America" provisions. Attach a list of exemptions and their associated costs to the certification form. Department form WS4567 is available at:

<http://roadwaystandards.dot.wi.gov/standards/forms/ws4567.doc>

Effective with September 2004 Letting

**WISCONSIN DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS AND TRANSPORTATION FACILITIES**

SUPPLEMENTAL REQUIRED CONTRACT PROVISIONS

- I. Wage Rates, Hours of labor and payment of Wages
- II. Payroll Requirements
- III. Postings at the Site of the Work
- IV. Affidavits
- V. Wage Rate Redistribution
- VI. Additional Classifications

I. WAGE RATES, HOURS OF LABOR AND PAYMENT OF WAGES

The schedule of "Minimum Wage Rates" attached hereto and made a part hereof furnishes the prevailing wage rates that have been determined pursuant to Section 103.50 of the Wisconsin Statutes. These wage rates are the minimum required to be paid to the various laborers, workers, mechanics and truck drivers employed by contractors and subcontractors on the construction work embraced by the contract and subject to prevailing hours and wages under Section 103.50, Stats. If necessary to employ laborers, workers, mechanics or truck drivers whose classification is not listed on the schedule, they shall be paid at rates conformable to those listed for similar classifications. Apprentices shall be paid at rates not less than those prescribed in their state indenture contracts.

While the wage rates shown are the minimum rates required by the contract to be paid during its life, this is not a representation that labor can be obtained at these rates. It is the responsibility of bidders to inform themselves as to the local labor conditions and prospective changes or adjustments of wage rates. No increase in the contract price shall be allowed or authorized on account of the payment of wage rates in excess of those listed herein.

Pursuant to Section 103.50 of the Wisconsin Statutes, the prevailing hours of labor have been determined to be up to 10 hours per day and 40 hours per calendar week Monday through Friday. If any laborer, worker, mechanic or truck driver is permitted or required to work more than the prevailing number of hours per day or per calendar week on this contract, they shall be paid for all hours in excess of the prevailing hours at a rate of at least one and one-half (1 1/2) times their hourly rate of pay. All work on Saturday, Sunday and the following holidays is to be paid at time and a half: (1) January 1, (2) the last Monday in May, (3) July 4, (4) the first Monday in September, (5) the fourth Thursday in November, (6) December 25, (7) the day before if January 1, July 4 or December 25 falls on a Saturday and (8) the day following if January 1, July 4 or December 25 falls on a Sunday.

All laborers, workers, mechanics and truck drivers shall be paid unconditionally not less often than once a week. Persons who own and operate their own trucks must receive the prevailing truck driver rate for the applicable type of truck (i.e. 2 axle, 3 or more axle, articulated, eculid or dumptor) he or she operates, plus an agreed upon amount for the use of his or her truck. Every owner-operator MUST be paid separately for their driving and for the use of their truck.

For those projects subject to the requirements of the Davis-Bacon Act, the Secretary of Labor will also have determined "Minimum Wage Rates" for work to be performed under the contract. These rates are, for all or most of the labor, worker, mechanic or truck driver classifications, identical to those established under Section 103.50 of the Wisconsin Statutes. In the event the rates are not identical, the higher of the two rates will govern.

II. PAYROLL REQUIREMENTS

All contractors and subcontractors must submit weekly Certified Payrolls and Compliance Statement verifying that all laborers, workers, mechanics and truck drivers working on the project have been paid the prevailing wage rates for all work performed under the contract required by Section 103.50 of the Wisconsin Statutes.

III. POSTINGS AT THE SITE OF THE WORK

In addition to the required postings furnished by the Department, the contractor shall post the following in at least one conspicuous place at the site of work:

- a. "NOTICE TO EMPLOYEES," which provides information required to be posted by the provisions of Section 103.50 of the Wisconsin Statutes.
- b. A copy of the State of Wisconsin Minimum Wages Rates. (Four pages.)
- c. A copy of the contractor's Equal Employment Opportunity Policy.
- d. On any project involving federal aid, in addition to the furnished postings, the contractor shall post a copy of the "Davis-Bacon Act, Minimum Wage Rates". (Three pages.)

IV. WAGE RATE REDISTRIBUTION

The amount specified as the hourly basic rate of pay and the amount(s) specified as the fringe benefit contribution(s), for all classes of laborers, workers, mechanics or truck drivers may be redistributed, when necessary, to conform to those specified in any applicable collective bargaining agreement, provided that both parties to such agreement

request and receive the approval for any such redistribution from both the Department of Transportation and the Department of Workforce Development prior to the implementation of such redistribution.

V. ADDITIONAL CLASSIFICATIONS

Any unlisted laborer or mechanic classification that is needed to perform work on this project, and is not included within the scope of any of the classifications listed in the application prevailing wage rate determination, may be added after award only if all of the following criteria have been met:

1. The affected employer(s) must make a written request to WisDOT Central Office to utilize the unlisted classification on this project.
2. The request must indicate the scope of the work to be performed by the unlisted classification and must indicate the proposed wage/fringe benefit package that the unlisted classification is to receive.
3. The work to be performed by the unlisted classification must not be performed by a classification that is included in the applicable prevailing wage rate determination.
4. The unlisted classification must be commonly employed in the area where the project is located.
5. The proposed wage/fringe benefit package must bear a reasonable relationship to those set forth in the applicable prevailing wage rate determination.
6. The request should be made prior to the actual performance of the work by the unlisted classification.
7. DWD must approve the use of the unlisted classification and the proposed wage/fringe benefit package. USDOL also must approve the use of the unlisted classification and the proposed wage/fringe benefit package on federal aid projects.
8. WisDOT and DWD may amend the proposed wage/fringe benefit package, as deemed necessary, and may set forth specific employment ratios and scope of work requirements in the approval document.

The approved wage/fringe benefit package shall be paid to all laborers, workers, mechanics or truck drivers performing work within the scope of that performed by the unlisted classification, from the first day on which such work is performed. In the event that work is performed by the unlisted classification prior to approval, the wage/fringe benefit package to be paid for such work must be in conformance with the wage/fringe

benefit package approved for such work. Under this arrangement a retroactive adjustment in wages and/or fringe benefits may be required to be made to the affected laborers, workers, mechanics or truck drivers by the affected employer(s).

**ANNUAL PREVAILING WAGE RATE DETERMINATION
FOR ALL STATE HIGHWAY PROJECTS
WASHINGTON COUNTY**

Compiled by the State of Wisconsin - Department of Workforce Development
for the Department of Transportation
Pursuant to s. 103.50, Stats.
Issued on September 1, 2013

CLASSIFICATION: Contractors are required to call the Department of Workforce Development if there are any questions regarding the proper trade or classification to be used for any worker on a public works project.

OVERTIME: Time and one-half must be paid for all hours worked over 10 hours per day and 40 hours per calendar week and for all hours worked on Saturday, Sunday and the following six (6) holidays: January 1; the last Monday in May; July 4; the 1st Monday in September; the 4th Thursday in November; December 25; the day before if January 1, July 4 or December 25 falls on a Saturday; the day following if January 1, July 4 or December 25 falls on a Sunday.

FUTURE INCREASE: If indicated for a specific trade or occupation, the full amount of such increase MUST be added to the "TOTAL" indicated for such trade or occupation on the date(s) such increase(s) becomes effective.

PREMIUM PAY: If indicated for a specific trade or occupation, the full amount of such pay MUST be added to the "HOURLY BASIC RATE OF PAY" indicated for such trade or occupation, whenever such pay is applicable.

SUBJOURNEY: Wage rates may be available for some of the classifications indicated below. Any employer that desires to use any subjourney classification on a project MUST request the applicable wage rate from the Department of Workforce Development PRIOR to the date such classification is used on such project. Form ERD-10880 is available for this purpose and can be obtained by writing to the Department of Workforce Development, Equal Rights Division, P.O. Box 8928, Madison, WI 53708.

<u>TRADE OR OCCUPATION</u>	<u>HOURLY BASIC RATE OF PAY</u>	<u>HOURLY FRINGE BENEFITS</u>	<u>TOTAL</u>
	\$	\$	\$
Bricklayer, Blocklayer or Stonemason	35.58	19.20	54.78
Carpenter	32.93	19.81	52.74
Future Increase(s): Add \$.75/hr on 6/3/2013. Add \$1.25/hr on 6/2/2014. Premium Pay: DOT PREMIUM: Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day.			
Cement Finisher	30.69	17.53	48.22
Future Increase(s): Add \$1.87 on 6/1/13; Add \$1.87 on 6/1/14; Add \$1.87 on 6/1/15; Add \$1.75 on 6/1/16. Premium Pay: DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.40/hr when the Wisconsin Department of Transportation or responsible governing agency requires that work be performed at night under artificial illumination with traffic control and the work is completed after sunset and before sunrise.			
Electrician	31.54	21.14	52.68
Fence Erector	28.00	4.50	32.50
Ironworker	31.31	21.00	52.31
Line Constructor (Electrical)	31.29	15.34	46.63
Painter	29.22	16.69	45.91
Pavement Marking Operator	29.22	16.69	45.91
Piledriver	30.66	15.31	45.97
Roofer or Waterproofer	29.40	12.34	41.74
Teledata Technician or Installer	24.65	15.67	40.32
Tuckpointer, Caulker or Cleaner	34.35	12.88	47.23
Underwater Diver (Except on Great Lakes)	37.45	19.45	56.90
Heavy Equipment Operator - ELECTRICAL LINE CONSTRUCTION ONLY	29.64	17.06	46.70
Light Equipment Operator -ELECTRICAL LINE CONSTRUCTION ONLY	29.64	16.53	46.17
Heavy Truck Driver - ELECTRICAL LINE CONSTRUCTION ONLY	25.94	13.57	39.51

TRADE OR OCCUPATION	HOURLY BASIC RATE OF PAY	HOURLY FRINGE BENEFITS	TOTAL
	\$	\$	\$
Light Truck Driver - ELECTRICAL LINE CONSTRUCTION ONLY	24.08	12.96	37.04
Groundman - ELECTRICAL LINE CONSTRUCTION ONLY	21.75	11.90	33.65

TRUCK DRIVERS

Single Axle or Two Axle	33.22	18.90	52.12
Three or More Axle	23.31	17.13	40.44
Future Increase(s): Add \$1.85/hr on 6/1/2013. Premium Pay: DOT PREMIUM: Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day.			
Articulated, Euclid, Dumptor, Off Road Material Hauler	27.77	19.90	47.67
Future Increase(s): Add \$2/hr on 6/1/13; Add \$1.75/hr on 6/1/14. Premium Pay: DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.50/hr night work premium. See DOT's website for details about the applicability of this night work premium at: http://roadwaystandards.dot.wi.gov/hcci/labor-wages-eeo/index.shtm .			
Pavement Marking Vehicle	23.84	14.93	38.77
Shadow or Pilot Vehicle	33.22	18.90	52.12
Truck Mechanic	22.50	16.19	38.69

LABORERS

General Laborer	24.64	18.40	43.04
Future Increase(s): Add \$1.70/hr on 6/1/2013; Add \$1.60/hr on 6/1/2014. Premium Pay: Add \$.10/hr for air tool operator, vibrator or tamper operator (mechanical hand operated), chain saw operator and demolition burning torch laborer; Add \$.15/hr for bituminous worker (raker and luteman), formsetter (curb, sidewalk and pavement) and strike off man; Add \$.20/hr for blaster and powderman; Add \$.35/hr for line and grade specialist; Add \$2.79/hr for topman; Add \$3.21/hr for bottomman; Add \$3.98/hr for pipelayer. DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.25/hr for work on projects involving temporary traffic control setup, for lane and shoulder closures, when work under artificial illumination conditions is necessary as required by the project provisions (including prep time prior to and/or cleanup after such time period).			
Asbestos Abatement Worker	37.16	0.00	37.16
Landscaper	25.39	18.40	43.79
Future Increase(s): Add \$1.70/hr on 6/1/13; Add \$1.60/hr on 6/1/14. Premium Pay: DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.25/hr for work on projects involving temporary traffic control setup, for lane and shoulder closures, when work under artificial illumination conditions is necessary as required by the project provisions (including prep time prior to and/or cleanup after such time period).			
Flagperson or Traffic Control Person	21.73	18.40	40.13
Future Increase(s): Add \$1.70/hr on 6/1/2013; Add \$1.60/hr on 6/1/2014. Premium Pay: DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.25/hr when the Wisconsin Department of Transportation or responsible governing agency requires that work be performed at night under artificial illumination with traffic control and the work is completed after sunset and before sunrise.			
Fiber Optic Laborer (Outside, Other Than Concrete Encased)	17.24	15.03	32.27
Railroad Track Laborer	23.41	11.29	34.70

<u>TRADE OR OCCUPATION</u>	<u>HOURLY BASIC RATE OF PAY</u>	<u>HOURLY FRINGE BENEFITS</u>	<u>TOTAL</u>
	\$	\$	\$
HEAVY EQUIPMENT OPERATORS			
Crane, Tower Crane, Pedestal Tower or Derrick, With Boom, Leads &/or Jib Lengths Measuring 176 Ft or Over; Crane, Tower Crane, Pedestal Tower or Derrick, With or Without Attachments, With a Lifting Capacity of Over 100 Tons, Self-Erecting Tower Crane With a Lifting Capacity Of Over 4,000 Lbs., Crane With Boom Dollies; Traveling Crane (Bridge Type). Future Increase(s): Add \$2/hr on 6/1/13; Add \$1.75/hr on 6/1/14. Premium Pay: DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.50/hr night work premium. See DOT's website for details about the applicability of this night work premium at: http://roadwaystandards.dot.wi.gov/hcci/labor-wages-eeo/index.shtm .	35.22	19.90	55.12
Backhoe (Track Type) Having a Mfr.'s Rated Capacity of 130,000 Lbs. or Over; Caisson Rig; Crane, Tower Crane, Portable Tower, Pedestal Tower or Derrick, With Boom, Leads &/or Jib Lengths Measuring 175 Ft or Under; Crane, Tower Crane, Portable Tower, Pedestal Tower or Derrick, With or Without Attachments, With a Lifting Capacity of 100 Tons or Under, Self-Erecting Tower Crane With A Lifting Capacity Of 4,000 Lbs., & Under; Dredge (NOT Performing Work on the Great Lakes); Licensed Boat Pilot (NOT Performing Work on the Great Lakes); Pile Driver. Future Increase(s): Add \$2/hr on 6/1/13; Add \$1.75/hr on 6/1/14. Premium Pay: DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.50/hr night work premium. See DOT's website for details about the applicability of this night work premium at: http://roadwaystandards.dot.wi.gov/hcci/labor-wages-eeo/index.shtm .	34.72	19.90	54.62
Air Track, Rotary or Percussion Drilling Machine &/or Hammers, Blaster; Asphalt Heater, Planer & Scarifier; Asphalt Milling Machine; Asphalt Screed; Automatic Subgrader (Concrete); Backhoe (Track Type) Having a Mfr.'s Rated Capacity of Under 130,000 Lbs., Backhoe (Mini, 15,000 Lbs. & Under); Bituminous (Asphalt) Plant & Paver, Screed; Boatmen (NOT Performing Work on the Great Lakes); Boring Machine (Directional, Horizontal or Vertical); Bridge (Bidwell) Paver; Bulldozer or Endloader; Concrete Batch Plant, Batch Hopper; Concrete Breaker (Large, Auto, Vibratory/Sonic, Manual or Remote); Concrete Bump Cutter, Grinder, Planing or Grooving Machine; Concrete Conveyor System; Concrete Laser/Screed; Concrete Paver (Slipform); Concrete Pump, Concrete Conveyor (Rotec or Bidwell Type); Concrete Slipform Placer Curb & Gutter Machine; Concrete Spreader & Distributor; Crane (Carry Deck, Mini) or Truck Mounted Hydraulic Crane (10 Tons or Under); Crane With a Lifting Capacity of 25 Tons or Under; Forestry Equipment, Timbco, Tree Shear, Tub Grinder, Processor; Gradall (Cruz-Aire Type); Grader or Motor Patrol; Grout Pump; Hydro-Blaster (10,000 PSI or Over); Loading Machine (Conveyor); Material or Stack Hoist; Mechanic or Welder; Milling Machine; Post Hole Digger or Driver; Roller (Over 5 Ton); Scraper (Self Propelled or Tractor Drawn) 5 cu yds or More Capacity; Shoulder Widener; Sideboom; Skid Rig; Stabilizing or Concrete Mixer (Self-Propelled or 14S or Over); Straddle Carrier or Travel Lift; Tractor (Scraper, Dozer, Pusher, Loader); Tractor or Truck Mounted Hydraulic Backhoe; Trencher (Wheel Type or Chain Type); Tube Finisher; Tugger (NOT Performing Work on the Great Lakes); Winches & A- Frames. Future Increase(s): Add \$2/hr on 6/1/13; Add \$1.75/hr on 6/1/14.	34.22	19.90	54.12

<u>TRADE OR OCCUPATION</u>	<u>HOURLY BASIC RATE OF PAY</u>	<u>HOURLY FRINGE BENEFITS</u>	<u>TOTAL</u>
	\$	\$	\$
Premium Pay: DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.50/hr night work premium. See DOT's website for details about the applicability of this night work premium at: http://roadwaystandards.dot.wi.gov/hcci/labor-wages-eeo/index.shtm .			
Belting, Burlap, Texturing Machine; Broom or Sweeper; Compactor (Self-Propelled or Tractor Mounted, Towed & Light Equipment); Concrete Finishing Machine (Road Type); Environmental Burner; Farm or Industrial Type Tractor; Fireman (Asphalt Plant, Pile Driver & Derrick NOT Performing Work on the Great Lakes); Forklift; Greaser; Hoist (Tugger, Automatic); Jeep Digger; Joint Sawyer (Multiple Blade); Launch (NOT Performing Work on the Great Lakes); Lift Slab Machine; Mechanical Float; Mulcher; Power Subgrader; Robotic Tool Carrier (With or Without Attachments); Roller (Rubber Tire, 5 Ton or Under); Self Propelled Chip Spreader; Shouldering Machine; Skid Steer Loader (With or Without Attachments); Telehandler; Tining or Curing Machine.	33.96	19.90	53.86
Future Increase(s): Add \$2/hr on 6/1/13; Add \$1.75/hr on 6/1/14. Premium Pay: DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.50/hr night work premium. See DOT's website for details about the applicability of this night work premium at: http://roadwaystandards.dot.wi.gov/hcci/labor-wages-eeo/index.shtm .			
Air Compressor (&/or 400 CFM or Over); Air, Electric or Hydraulic Jacking System; Augers (Vertical & Horizontal); Automatic Belt Conveyor & Surge Bin; Boiler (Temporary Heat); Concrete Proportioning Plant; Crusher, Screening or Wash Plant; Generator (&/or 150 KW or Over); Heaters (Mechanical); High Pressure Utility Locating Machine (Daylighting Machine); Mudjack; Oilier; Prestress Machine; Pug Mill; Pump (3 Inch or Over) or Well Points; Rock, Stone Breaker; Screed (Milling Machine); Stump Chipper; Tank Car Heaters; Vibratory Hammer or Extractor, Power Pack.	33.67	19.90	53.57
Future Increase(s): Add \$2/hr on 6/1/13; Add \$1.75/hr on 6/1/14. Premium Pay: DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.50/hr night work premium. See DOT's website for details about the applicability of this night work premium at: http://roadwaystandards.dot.wi.gov/hcci/labor-wages-eeo/index.shtm .			
Fiber Optic Cable Equipment.	20.00	9.90	29.90

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20131210011PROJECT(S):
1410-12-70FEDERAL ID(S):
N/A

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS

SECTION 0001 ROADWAY ITEMS

0010	203.0100 REMOVING SMALL PIPE CULVERTS	6.000 EACH	.		.	
0020	203.0200 REMOVING OLD STRUCTURE (STATION) 01. 172+00	LUMP	LUMP		.	
0030	204.0110 REMOVING ASPHALTIC SURFACE	15.000 SY	.		.	
0040	204.0115 REMOVING ASPHALTIC SURFACE BUTT JOINTS	1,543.000 SY	.		.	
0050	204.0125 REMOVING ASPHALTIC SURFACE MILLING	6,446.000 TON	.		.	
0060	204.0150 REMOVING CURB & GUTTER	157.000 LF	.		.	
0070	205.0100 EXCAVATION COMMON	946.710 CY	.		.	
0080	205.0400 EXCAVATION MARSH	3,209.360 CY	.		.	
0090	209.0100 BACKFILL GRANULAR	4,011.430 CY	.		.	
0100	211.0400 PREPARE FOUNDATION FOR ASPHALTIC SHOULDERS	204.000 STA	.		.	

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20131210011PROJECT(S):
1410-12-70FEDERAL ID(S):
N/A

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	213.0100 FINISHING ROADWAY (PROJECT) 01. 1410-12-70	1.000 EACH	.		.	
0120	305.0110 BASE AGGREGATE DENSE 3/4-INCH	320.000 TON	.		.	
0130	305.0120 BASE AGGREGATE DENSE 1 1/4-INCH	1,167.000 TON	.		.	
0140	440.4410.S INCENTIVE IRI RIDE	4,000.000 DOL	1.00000		4000.00	
0150	455.0105 ASPHALTIC MATERIAL PG58-28	612.000 TON	.		.	
0160	455.0605 TACK COAT	2,124.000 GAL	.		.	
0170	460.1103 HMA PAVEMENT TYPE E-3	4,454.000 TON	.		.	
0180	460.2000 INCENTIVE DENSITY HMA PAVEMENT	6,610.000 DOL	1.00000		6610.00	
0190	460.4110.S REHEATING HMA PAVEMENT LONGITUDINAL JOINTS	10,582.000 LF	.		.	
0200	465.0120 ASPHALTIC SURFACE DRIVEWAYS AND FIELD ENTRANCES	238.000 TON	.		.	
0210	465.0315 ASPHALTIC FLUMES	40.000 SY	.		.	

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20131210011PROJECT(S):
1410-12-70FEDERAL ID(S):
N/A

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0220	465.0425 ASPHALTIC SHOULDER RUMBLE STRIP 2-LANE RURAL	12,186.000 LF	.		.	
0230	465.0475 ASPHALT CENTER LINE RUMBLE STRIP 2-LANE RURAL	5,775.000 LF	.		.	
0240	521.0115 CULVERT PIPE CORRUGATED STEEL 15-INCH	24.000 LF	.		.	
0250	521.0118 CULVERT PIPE CORRUGATED STEEL 18-INCH	34.000 LF	.		.	
0260	521.1015 APRON ENDWALLS FOR CULVERT PIPE STEEL 15-INCH	2.000 EACH	.		.	
0270	521.1018 APRON ENDWALLS FOR CULVERT PIPE STEEL 18-INCH	2.000 EACH	.		.	
0280	522.0330 CULVERT PIPE REINFORCED CONCRETE CLASS IV 30-INCH	65.000 LF	.		.	
0290	522.1030 APRON ENDWALLS FOR CULVERT PIPE REINFORCED CONCRETE 30-INCH	2.000 EACH	.		.	
0300	523.0148 CULVERT PIPE REINFORCED CONCRETE HORIZONTAL ELLIPTICAL CLASS HE-III 48X76-INCH	64.000 LF	.		.	
0310	523.0419 CULVERT PIPE REINFORCED CONCRETE HORIZONTAL ELLIPTICAL CLASS HE-IV 19X30-INCH	82.000 LF	.		.	

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20131210011PROJECT(S):
1410-12-70FEDERAL ID(S):
N/A

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0320	523.0519 APRON ENDWALLS FOR CULVERT PIPE REINFORCED CONCRETE HORIZONTAL ELLIPTICAL 19X30-INCH	EACH 2.000	.		.	
0330	523.0548 APRON ENDWALLS FOR CULVERT PIPE REINFORCED CONCRETE HORIZONTAL ELLIPTICAL 48X76-INCH	EACH 2.000	.		.	
0340	601.0557 CONCRETE CURB AND GUTTER 6-INCH SLOPED 36-INCH TYPE D	LF 151.000	.		.	
0350	618.0100 MAINTENANCE AND REPAIR OF HAUL ROADS (PROJECT) 01. 1410-12-70	EACH 1.000	.		.	
0360	619.1000 MOBILIZATION	EACH 1.000	.		.	
0370	625.0100 TOPSOIL	SY 420.000	.		.	
0380	625.0500 SALVAGED TOPSOIL	SY 2,300.000	.		.	
0390	627.0200 MULCHING	SY 420.000	.		.	
0400	628.1504 SILT FENCE	LF 1,605.000	.		.	
0410	628.1520 SILT FENCE MAINTENANCE	LF 802.000	.		.	

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20131210011PROJECT(S):
1410-12-70FEDERAL ID(S):
N/A

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0420	628.1905 MOBILIZATIONS EROSION CONTROL	3.000 EACH	.		.	
0430	628.1910 MOBILIZATIONS EMERGENCY EROSION CONTROL	1.000 EACH	.		.	
0440	628.2004 EROSION MAT CLASS I TYPE B	2,350.000 SY	.		.	
0450	628.2023 EROSION MAT CLASS II TYPE B	158.000 SY	.		.	
0460	628.7555 CULVERT PIPE CHECKS	25.000 EACH	.		.	
0470	628.7570 ROCK BAGS	20.000 EACH	.		.	
0480	629.0210 FERTILIZER TYPE B	161.000 CWT	.		.	
0490	630.0120 SEEDING MIXTURE NO. 20	36.000 LB	.		.	
0500	630.0160 SEEDING MIXTURE NO. 60	21.000 LB	.		.	
0510	630.0200 SEEDING TEMPORARY	20.000 LB	.		.	
0520	633.5200 MARKERS CULVERT END	6.000 EACH	.		.	

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20131210011PROJECT(S):
1410-12-70FEDERAL ID(S):
N/A

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0530	634.0616 POSTS WOOD 4X6-INCH X 16-FT	48.000 EACH	.		.	
0540	634.0618 POSTS WOOD 4X6-INCH X 18-FT	21.000 EACH	.		.	
0550	637.2210 SIGNS TYPE II REFLECTIVE H	327.420 SF	.		.	
0560	637.2230 SIGNS TYPE II REFLECTIVE F	144.750 SF	.		.	
0570	638.2102 MOVING SIGNS TYPE II	9.000 EACH	.		.	
0580	638.2602 REMOVING SIGNS TYPE II	53.000 EACH	.		.	
0590	638.3000 REMOVING SMALL SIGN SUPPORTS	56.000 EACH	.		.	
0600	642.5201 FIELD OFFICE TYPE C	1.000 EACH	.		.	
0610	643.0200 TRAFFIC CONTROL SURVEILLANCE AND MAINTENANCE (PROJECT) 01. 1410-12-70	50.000 DAY	.		.	
0620	643.0300 TRAFFIC CONTROL DRUMS	3,000.000 DAY	.		.	
0630	643.0420 TRAFFIC CONTROL BARRICADES TYPE III	120.000 DAY	.		.	

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20131210011PROJECT(S):
1410-12-70FEDERAL ID(S):
N/A

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0640	643.0710 TRAFFIC CONTROL WARNING LIGHTS TYPE B	240.000 DAY	.		.	
0650	643.0715 TRAFFIC CONTROL WARNING LIGHTS TYPE C	360.000 DAY	.		.	
0660	643.0900 TRAFFIC CONTROL SIGNS	1,200.000 DAY	.		.	
0670	643.1050 TRAFFIC CONTROL SIGNS PCMS	10.000 DAY	.		.	
0680	646.0106 PAVEMENT MARKING EPOXY 4-INCH	32,125.000 LF	.		.	
0690	647.0606 PAVEMENT MARKING ISLAND NOSE EPOXY	3.000 EACH	.		.	
0700	647.0726 PAVEMENT MARKING DIAGONAL EPOXY 12-INCH	246.000 LF	.		.	
0710	647.0856 PAVEMENT MARKING CONCRETE CORRUGATED MEDIAN EPOXY	132.000 SF	.		.	
0720	648.0100 LOCATING NO-PASSING ZONES	1.990 MI	.		.	
0730	650.4500 CONSTRUCTION STAKING SUBGRADE	917.000 LF	.		.	
0740	650.5000 CONSTRUCTION STAKING BASE	917.000 LF	.		.	

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20131210011PROJECT(S):
1410-12-70FEDERAL ID(S):
N/A

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0750	650.5500 CONSTRUCTION STAKING CURB GUTTER AND CURB & GUTTER	151.000 LF	.		.	
0760	650.6000 CONSTRUCTION STAKING PIPE CULVERTS	5.000 EACH	.		.	
0770	650.8000 CONSTRUCTION STAKING RESURFACING REFERENCE	12,200.000 LF	.		.	
0780	650.9920 CONSTRUCTION STAKING SLOPE STAKES	867.000 LF	.		.	
0790	690.0150 SAWING ASPHALT	1,266.000 LF	.		.	
0800	690.0250 SAWING CONCRETE	80.000 LF	.		.	
0810	SPV.0060 SPECIAL 01. PAVEMENT MARKING GROOVED PREFORMED THERMOPLASTIC ARROWS TYPE 2	3.000 EACH	.		.	
0820	SPV.0060 SPECIAL 02. PAVEMENT MARKING GROOVED PREFORMED THERMOPLASTIC ARROWS TYPE 3	2.000 EACH	.		.	
0830	SPV.0060 SPECIAL 03. PAVEMENT MARKING GROOVED PREFORMED THERMOPLASTIC WORDS	3.000 EACH	.		.	
0840	SPV.0090 SPECIAL 01. PAVEMENT MARKING GROOVED PREFORMED THERMOPLASTIC STOP LINE 18-INCH	147.000 LF	.		.	

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20131210011PROJECT(S):
1410-12-70FEDERAL ID(S):
N/A

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0850	SPV.0090 SPECIAL 02. PAVEMENT MARKING GROOVED PREFORMED PLASTIC TAPE 8-INCH	728.000 LF	.		.	
0860	SPV.0090 SPECIAL 03. PAVEMENT MARKING GROOVED PREFORMED PLASTIC 4-INCH	120.000 LF	.		.	
0870	SPV.0105 SPECIAL 01. MILLING AND REMOVING TEMPORARY JOINT	LUMP	LUMP		.	
0880	SPV.0195 SPECIAL 01. SAME DAY PAVING HMA PAVEMENT TYPE E-3	5,694.000 TON	.		.	
	SECTION 0001 TOTAL				.	
	TOTAL BID				.	

PLEASE ATTACH SCHEDULE OF ITEMS HERE