

HIGHWAY WORK PROPOSAL

Wisconsin Department of Transportation
DT1502 10/2010 s.66.29(7) Wis. Stats.

Proposal Number:

11

<u>COUNTY</u>	<u>STATE PROJECT ID</u>	<u>FEDERAL PROJECT ID</u>	<u>PROJECT DESCRIPTION</u>	<u>HIGHWAY</u>
Dane	5310-02-74		Spring Green - Madison, CTH KP to Westview Ct / V Cross Plains	USH 14
Dane	5657-00-70	WISC 2014 187	Pine Bluff - V Cross Plains, Black Earth CR BR, B-13-0646	CTH P

This proposal, submitted by the undersigned bidder to the Wisconsin Department of Transportation, is in accordance with the advertised request for proposals. The bidder is to furnish and deliver all materials, and to perform all work for the improvement of the designated project in the time specified, in accordance with the appended Proposal Requirements and Conditions.

Proposal Guaranty Required, \$ 75,000.00 Payable to: Wisconsin Department of Transportation	Attach Proposal Guaranty on back of this PAGE.
Bid Submittal Due Date: May, 13, 2014 Time (Local Time): 9:00 AM	Firm Name, Address, City, State, Zip Code
Contract Completion Time Completion Date: March 15, 2015	SAMPLE NOT FOR BIDDING PURPOSES
Assigned Disadvantaged Business Enterprise Goal 5%	This contract is exempt from federal oversight.

This certifies that the undersigned bidder, duly sworn, is an authorized representative of the firm named above; that the bidder has examined and carefully prepared the bid from the plans, Highway Work Proposal, and all addenda, and has checked the same in detail before submitting this proposal or bid; and that the bidder or agents, officer, or employees have not, either directly or indirectly, entered into any agreement, participated in any collusion, or otherwise taken any action in restraint of free competitive bidding in connection with this proposal bid.

Do not sign, notarize, or submit this Highway Work Proposal when submitting an electronic bid on the Internet.

Subscribed and sworn to before me this date _____

(Signature, Notary Public, State of Wisconsin)

(Print or Type Name, Notary Public, State Wisconsin)

(Date Commission Expires)

Notary Seal

(Bidder Signature)

(Print or Type Bidder Name)

(Bidder Title)

For Department Use Only

Type of Work Construction of structure B-13-0646, removal of existing structure B-13-0339, pavement removal, clearing, grubbing, common excavation, borrow, select crushed material, dense graded base, storm sewer, concrete pavement, concrete curb and gutter, HMA pavement, traffic signals, permanent signing, pavement marking.	Date Guaranty Returned
Notice of Award Dated	

**PLEASE ATTACH
PROPOSAL GUARANTY HERE**

Effective with November 2007 Letting

PROPOSAL REQUIREMENTS AND CONDITIONS

The bidder, signing and submitting this proposal, agrees and declares as a condition thereof, to be bound by the following conditions and requirements.

If the bidder has a corporate relationship with the proposal design engineering company, the bidder declares that it did not obtain any facts, data, or other information related to this proposal from the design engineering company that was not available to all bidders.

The bidder declares that they have carefully examined the site of, and the proposal, plans, specifications and contract forms for the work contemplated, and it is assumed that the bidder has investigated and is satisfied as to the conditions to be encountered, as to the character, quality, and quantities of work to be performed and materials to be furnished, and as to the requirements of the specifications, special provisions and contract. It is mutually agreed that submission of a proposal shall be considered conclusive evidence that the bidder has made such examination.

The bidder submits herewith a proposal guaranty in proper form and amount payable to the party as designated in the advertisement inviting proposals, to be retained by and become the property of the owner of the work in the event the undersigned shall fail to execute the contract and contract bond and return the same to the office of the engineer within fourteen (14) days after having been notified in writing to do so; otherwise to be returned.

The bidder declares that they understand that the estimate of quantities in the attached schedule is approximate only and that the attached quantities may be greater or less in accordance with the specifications.

The bidder agrees to perform the said work, for and in consideration of the payment of the amount becoming due on account of work performed, according to the unit prices bid in the following schedule, and to accept such amounts in full payment of said work.

The bidder declares that all of the said work will be performed at their own proper cost and expense, that they will furnish all necessary materials, labor, tools, machinery, apparatus, and other means of construction in the manner provided in the applicable specifications and the approved plans for the work together with all standard and special designs that may be designed on such plans, and the special provisions in the contract of which this proposal will become a part, if and when accepted. The bidder further agrees that the applicable specifications and all plans and working drawings are made a part hereof, as fully and completely as if attached hereto.

The bidder, if awarded the contract, agrees to begin the work not later than ten (10) days after the date of written notification from the engineer to do so, unless otherwise stipulated in the special provisions.

The bidder declares that if they are awarded the contract, they will execute the contract agreement and begin and complete the work within the time named herein, and they will file a good and sufficient surety bond for the amount of the contract for performance and also for the full amount of the contract for payment.

The bidder, if awarded the contract, shall pay all claims as required by Section 779.14, Statutes of Wisconsin, and shall be subject to and discharge all liabilities for injuries pursuant to Chapter 102 of the Statutes of Wisconsin, and all acts amendatory thereto. They shall further be responsible for any damages to property or injury to persons occurring through their own negligence or that of their employees or agents, incident to the performance of work under this contract, pursuant to the Standard Specifications for Road and Bridge Construction applicable to this contract.

In connection with the performance of work under this contract, the contractor agrees to comply with all applicable state and federal statutes relating to non-discrimination in employment. No otherwise qualified person shall be excluded from employment or otherwise be subject to discrimination in employment in any manner on the basis of age, race, religion, color, gender, national origin or ancestry, disability, arrest or conviction record (in keeping with s.111.32), sexual orientation, marital status, membership in the military reserve, honesty testing, genetic testing, and outside use of lawful products. This provision shall include, but not be limited to the following: employment, upgrading, demotion or transfer; recruitment or recruitment advertising; layoff or termination; rates of pay or other forms of compensation, and selection for training, including apprenticeship. The contractor further agrees to ensure equal opportunity in employment to all applicants and employees and to take affirmative action to attain a representative workforce.

The contractor agrees to post notices and posters setting forth the provisions of the nondiscrimination clause, in a conspicuous and easily accessible place, available for employees and applicants for employment.

If a state public official (section 19.42, Stats.) or an organization in which a state public official holds at least a 10% interest is a party to this agreement, this contract is voidable by the state unless appropriate disclosure is made to the State of Wisconsin Ethics Board.

BID PREPARATION

Preparing the Proposal Schedule of Items

A General

- (1) Obtain bidding proposals as specified in **section 102** of the standard specifications prior to 11:45 AM of the last business day preceding the letting. Submit bidding proposals using one of the following methods:
 1. Electronic bid on the internet.
 2. Electronic bid on a printout with accompanying diskette or CD ROM.
 3. Paper bid under a waiver of the electronic submittal requirements.
- (2) Bids submitted on a printout with accompanying diskette or CD ROM or paper bids submitted under a waiver of the electronic submittal requirements govern over bids submitted on the internet.
- (3) The department will provide bidding information through the department's web site at <http://www.dot.wisconsin.gov/business/engrserv/bid-letting-information.htm>. The contractor is responsible for reviewing this web site for general notices as well as information regarding proposals in each letting. The department will also post special notices of all addenda to each proposal through this web site no later than 4:00 P.M. local time on the Thursday before the letting. Check the department's web site after 5:00 P.M. local time on the Thursday before the letting to ensure all addenda have been accounted for before preparing the bid. When bidding using methods 1 and 2 above, check the Bid Express™ on-line bidding exchange at <http://www.bidx.com/> after 5:00 P.M. local time on the Thursday before the letting to ensure that the latest schedule of items Expedite file (*.ebs or *.00x) is used to submit the final bid.
- (4) Interested parties can subscribe to the Bid Express™ on-line bidding exchange by following the instructions provided at the www.bidx.com web site or by contacting:

Info Tech Inc.
5700 SW 34th Street, Suite 1235
Gainesville, FL 32608-5371
email: <mailto:customer.support@bidx.com>

- (5) The department will address equipment and process failures, if the bidder can demonstrate that those failures were beyond their control.
- (6) Contractors are responsible for checking on the issuance of addenda and for obtaining the addenda. Notice of issuance of addenda is posted on the department's web site at <http://www.dot.wisconsin.gov/business/engrserv/bid-letting-information.htm> or by calling the department at (608) 266-1631. Addenda can ONLY be obtained from the departments web site listed above or by picking up the addenda at the Bureau of Highway Construction, Room 601, 4802 Sheboygan Avenue, Madison, WI, during regular business hours.

B Submitting Electronic Bids

B.1 On the Internet

- (1) Do the following before submitting the bid:
 1. Have a properly executed annual bid bond on file with the department.
 2. Have a digital ID on file with and enabled by Info Tech Inc. Using this digital ID will constitute the bidder's signature for proper execution of the bidding proposal.
- (2) In lieu of preparing, delivering, and submitting the proposal as specified in **102.6** and **102.9** of the standard specifications, submit the proposal on the internet as follows:

1. Download the latest schedule of items reflecting all addenda from the Bid Express™ web site.
 2. Use Expedite™ software to enter a unit price for every item in the schedule of items.
 3. Submit the bid according to the requirements of Expedite™ software and the Bid Express™ web site. Do not submit a bid on a printout with accompanying diskette or CD ROM or a paper bid. If the bidder does submit a bid on a printout with accompanying diskette or a paper bid in addition to the internet submittal, the department will disregard the internet bid.
 4. Submit the bid before the hour and date the Notice to Contractors designates.
 5. Do not sign, notarize, and return the bidding proposal described in 102.2 of the standard specifications.
- (3) The department will not consider the bid accepted until the hour and date the Notice to Contractors designates.

B.2 On a Printout with Accompanying Diskette or CD ROM

- (1) Download the latest schedule of items from the Wisconsin pages of the Bid Express™ web site reflecting the latest addenda posted on the department's web site at <http://www.dot.wisconsin.gov/business/engrserve/bid-letting-information.htm>. Use Expedite™ software to prepare and print the schedule of items. Provide a valid amount for all price fields. Follow instructions and review the help screens provided on the Bid Express™ web site to assure that the schedule of items is prepared properly.
- (2) Staple an 8 1/2 by 11 inch printout of the Expedite™ generated schedule of items to the other proposal documents submitted to the department as a part of the bidder's sealed bid. As a separate submittal not in the sealed bid envelop but due at the same time and place as the sealed bid, also provide the Expedite™ generated schedule of items on a 3 1/2 inch computer diskette or CD ROM. Label each diskette or CD ROM with the bidder's name, the 4 character department-assigned bidder identification code from the top of the bidding proposal, and a list of the proposal numbers included on that diskette or CD ROM as indicated in the following example:

Bidder Name

BN00

Proposals: 1, 12, 14, & 22

- (3) If bidding on more than one proposal in the letting, the bidder may include all proposals for that letting on one diskette or CD ROM. Include only submitted proposals with no incomplete or other files on the diskette or CD ROM.
- (4) The bidder-submitted printout of the Expedite™ generated schedule of items is the governing contract document and must conform to the requirements of section 102 of the standard specifications. If a printout needs to be altered, cross out the printed information with ink or typewriter and enter the new information and initial it in ink. If there is a discrepancy between the printout and the diskette or CD ROM, the department will analyze the bid using the printout information.
- (5) In addition to the reasons specified in section 102 of the standard specifications, proposals are irregular and the department may reject them for one or more of the following:
 1. The check code printed on the bottom of the printout of the Expedite™ generated schedule of items is not the same on each page.
 2. The check code printed on the printout of the Expedite™ generated schedule of items is not the same as the check code for that proposal provided on the diskette or CD ROM.

3. The diskette or CD ROM is not submitted at the time and place the department designates.

C Waiver of Electronic Submittal

- (1) The bidder may request a waiver of the electronic submittal requirements. Submit a written request for a waiver in lieu of bids submitted on the internet or on a printout with accompanying diskette or CD ROM. Use the waiver that was included with the paper bid document sent to the bidder or type up a waiver on the bidder's letterhead. The department will waive the electronic submittal requirements for a bidding entity (individual, partnership, joint venture, corporation, or limited liability company) for up to 4 individual proposals in a calendar year. The department may allow additional waivers for equipment malfunctions.
- (2) Submit a schedule of items on paper conforming to [section 102](#) of the standard specifications. The department charges the bidder a \$75 administrative fee per proposal, payable at the time and place the department designates for receiving bids, to cover the costs of data entry. The department will accept a check or money order payable to: "Wisconsin, Dept. of Transportation."
- (3) In addition to the reasons specified in [section 102](#) of the standard specifications, proposals are irregular and the department may reject them for one or more of the following:
 1. The bidder fails to provide the written request for waiver of the electronic submittal requirements.
 2. The bidder fails to pay the \$75 administrative fee before the time the department designates for the opening of bids unless the bidder requests on the waiver that they be billed for the \$75.
 3. The bidder exceeds 4 waivers of electronic submittal requirements within a calendar year.
- (4) In addition to the reasons specified in [section 102](#) of the standard specifications, the department may refuse to issue bidding proposals for future contracts to a bidding entity that owes the department administrative fees for a waiver of electronic submittal requirements.

PROPOSAL BID BOND

DT1303 1/2006

Wisconsin Department of Transportation

Proposal Number	Project Number	Letting Date
Name of Principal		
Name of Surety	State in Which Surety is Organized	

We, the above-named Principal and the above-named Surety, are held and firmly bound unto the State of Wisconsin in the sum equal to the Proposal Guaranty for the total bid submitted for the payment to be made; we jointly and severally bind ourselves, our heirs, executors, administrators, successors and assigns. The condition of this obligation is that the Principal has submitted a bid proposal to the State of Wisconsin acting through the Department of Transportation for the improvement designated by the Proposal Number and Letting Date indicated above.

If the Principal is awarded the contract and, within the time and manner required by law after the prescribed forms are presented for signature, enters into a written contract in accordance with the bid, and files the bond with the Department of Transportation to guarantee faithful performance and payment for labor and materials, as required by law, or if the Department of Transportation shall reject all bids for the work described, then this obligation shall be null and void; otherwise, it shall be and remain in full force and effect. In the event of failure of the Principal to enter into the contract or give the specified bond, the Principal shall pay to the Department of Transportation **within 10 business days of demand** a total equal to the Proposal Guaranty as liquidated damages; the liability of the Surety continues for the full amount of the obligation as stated until the obligation is paid in full.

The Surety, for value received, agrees that the obligations of it and its bond shall not be impaired or affected by any extension of time within which the Department of Transportation may accept the bid; and the Surety does waive notice of any such extension.

IN WITNESS, the Principal and Surety have agreed and have signed by their proper officers and have caused their corporate seals to be affixed this date: **(DATE MUST BE ENTERED)**

PRINCIPAL

(Company Name) **(Affix Corporate Seal)**

(Signature and Title)

(Company Name)

(Signature and Title)

(Company Name)

(Signature and Title)

(Company Name)

(Signature and Title)

NOTARY FOR PRINCIPAL

(Date)

State of Wisconsin)
) ss.
_____ County)

On the above date, this instrument was acknowledged before me by the named person(s).

(Signature, Notary Public, State of Wisconsin)

(Print or Type Name, Notary Public, State of Wisconsin)

(Date Commission Expires)

Notary Seal

(Name of Surety) **(Affix Seal)**

(Signature of Attorney-in-Fact)

NOTARY FOR SURETY

(Date)

State of Wisconsin)
) ss.
_____ County)

On the above date, this instrument was acknowledged before me by the named person(s).

(Signature, Notary Public, State of Wisconsin)

(Print or Type Name, Notary Public, State of Wisconsin)

(Date Commission Expires)

Notary Seal

IMPORTANT: A certified copy of Power of Attorney of the signatory agent must be attached to the bid bond.

CERTIFICATE OF ANNUAL BID BOND

DT1305 8/2003

Wisconsin Department of Transportation

Time Period Valid (From/To)	
Name of Surety	
Name of Contractor	
Certificate Holder	Wisconsin Department of Transportation

This is to certify that an annual bid bond issued by the above-named Surety is currently on file with the Wisconsin Department of Transportation.

This certificate is issued as a matter of information and conveys no rights upon the certificate holder and does not amend, extend or alter the coverage of the annual bid bond.

Cancellation: Should the above policy be cancelled before the expiration date, the issuing surety will give thirty (30) days written notice to the certificate holder indicated above.

(Signature of Authorized Contractor Representative)

(Date)

March 2010

LIST OF SUBCONTRACTORS

Section 66.0901(7), Wisconsin Statutes, provides that as a part of the proposal, the bidder also shall submit a list of the subcontractors the bidder proposes to contract with and the class of work to be performed by each. In order to qualify for inclusion in the bidder's list a subcontractor shall first submit a bid in writing, to the general contractor at least 48 hours prior to the time of the bid closing. The list may not be added to or altered without the written consent of the municipality. A proposal of a bidder is not invalid if any subcontractor and the class of work to be performed by the subcontractor has been omitted from a proposal; the omission shall be considered inadvertent or the bidder will perform the work personally.

No subcontract, whether listed herein or later proposed, may be entered into without the written consent of the Engineer as provided in Subsection 108.1 of the Standard Specifications.

[illegible]

DECEMBER 2000

**CERTIFICATION REGARDING DEBARMENT, SUSPENSION, AND OTHER
RESPONSIBILITY MATTERS - PRIMARY COVERED TRANSACTIONS**

Instructions for Certification

1. By signing and submitting this proposal, the prospective contractor is providing the certification set out below.
2. The inability of a person to provide the certification required below will not necessarily result in denial of participation in this covered transaction. The prospective contractor shall submit an explanation of why it cannot provide the certification set out below. The certification or explanation will be considered in connection with the department or agency's determination whether to enter into this transaction. However, failure of the prospective contractor to furnish a certification or an explanation shall disqualify such person from participation in this transaction.
3. The certification in this clause is a material representation of fact upon which reliance was placed when the department determined to enter into this transaction. If it is later determined that the contractor knowingly rendered an erroneous certification in addition to other remedies available to the Federal Government the department may terminate this transaction for cause or default.
4. The prospective contractor shall provide immediate written notice to the department to whom this proposal is submitted if at any time the prospective contractor learns that its certification was erroneous when submitted or has become erroneous by reason of changed circumstances.
5. The terms "covered transaction," "debarred," "suspended," "ineligible," "lower tier covered transaction," "participant," "person," "primary covered transaction," "principal," "proposal," and "voluntarily excluded," as used in this clause, have the meanings set out in the Definitions and Coverage sections of the rules implementing Executive Order 12549. You may contact the department to which this proposal is being submitted for assistance in obtaining a copy of those regulations.
6. The prospective contractor agrees by submitting this proposal that, should this contract be entered into, it shall not knowingly enter into any lower tier covered transaction with a person who is debarred, suspended, declared ineligible, or voluntarily excluded from participation in this covered transaction, unless authorized by the department entering into this transaction.
7. The prospective contractor further agrees by submitting this proposal that it will include the clause titled "Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion-Lower Tier Covered Transaction," which is included as an addendum to PR-1273 - "Required Contract Provisions Federal Aid Construction Contracts," without

modification, in all lower tier covered transactions and in all solicitations for lower tier covered transactions.

8. The contractor may rely upon a certification of a prospective subcontractor/materials supplier that it is not debarred, suspended, ineligible, or voluntarily excluded from the covered transaction, unless it knows that the certification is erroneous. A contractor may decide the method and frequency by which it determines the eligibility of its principals. Each contractor may, but is not required to, check the Disapproval List (telephone # 608/266/1631).
9. Nothing contained in the foregoing shall be construed to require establishment of a system of records in order to render in good faith the certification required by this clause. The knowledge and information of a contractor is not required to exceed that which is normally possessed by a prudent person in the ordinary course of business dealings.
10. Except for transactions authorized under paragraph 6 of these instructions, if a contractor in a covered transaction knowingly enters into a lower tier covered transaction with a person who is suspended, debarred, ineligible or voluntarily excluded from participation in this transaction, in addition to other remedies available to the Federal Government, the department may terminate this transaction for cause or default.

Certification Regarding Debarment, Suspension, and Other Responsibility Matters - Primary Covered Transactions

- (1) The prospective contractor certifies to the best of its knowledge and belief, that it and its principals:
 - (a) Are not presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from covered transactions by any Federal department or agency;
 - (b) Have not within a three-year period preceding this proposal been convicted of or had a civil judgment rendered against them for commission of fraud or a criminal offense in connection with obtaining, attempting to obtain, or performing a public (Federal, State or local) transaction or contract under a public transaction; violation of Federal or State antitrust statutes or commission of embezzlement, theft, forgery, bribery, falsification or destruction of records, making false statements or receiving stolen property;
 - (c) Are not presently indicted for or otherwise criminally or civilly charged by a governmental entity (Federal, State or local) with commission of any of the offense enumerated in paragraph (1)(b) of this certification; and
 - (d) Have not within a three-year period preceding this proposal had one or more public transactions (Federal, State or local) terminated for cause or default.
- (2) Where the prospective contractor is unable to certify to any of the statements in this certification, such prospective contractor shall attach an explanation to this proposal.

Special Provisions

Table of Contents

Article	Description	Page #
1.	General.....	3
2.	Scope of Work.	3
3.	Prosecution and Progress.	3
4.	Traffic.	7
5.	Holiday Work Restrictions.	10
6.	Utilities.....	10
7.	Railroad Insurance and Coordination.	12
8.	Information to Bidders, U.S. Army Corps of Engineers Section 404 Permit.....	13
9.	Salvage of Materials.	13
10.	Advanced Notice for Lane Closure System.....	13
11.	Removing Pavement.	14
12.	Hauling Restrictions.....	14
13.	Environmental.....	14
14.	Erosion Control Structures.....	15
15.	Pedestrian Access.....	16
16.	Notice to Contractor, Notification of Demolition and/or Renovation No Asbestos Found.	16
17.	Removing Old Structure Over Waterway With Minimal Debris Station 13+00 ‘P’, Item 203.0600.S.01.	17
18.	Removing Type II Sign Structures, Item 204.9060.S.01.....	18
19.	Removing Concrete Median, Item 204.9090.S.02.....	19
20.	Excavation, Hauling, and Disposal of Petroleum Contaminated Soil, Item 205.0501.S.	19
21.	Base Aggregate Dense, $\frac{3}{4}$ Inch.	22
22.	Base Aggregate Dense 1 $\frac{1}{4}$ -Inch, Item 305.0120.	23
23.	QMP Base Aggregate.	23
24.	Pier Construction.	31
25.	Polymer Overlay, Item 509.5100.S.....	31
26.	Concrete Staining B-13-0646, Item 517.1010.S.01.....	37
27.	Architectural Surface Treatment B-13-0646, Item 517.1050.S.01.....	39
28.	Traffic Signals.....	40
29.	Department Maintained Traffic Signals.....	41
30.	Temporary Traffic Signals.....	41
31.	Seismograph, Item 999.1000.S.	42
32.	Crack and Damage Survey, Item 999.1500.S.	43
33.	Removing Traffic Signal Controller Cabinet, Item SPV.0060.01.....	44
34.	Temporary Opticom Signal Preempt, SPV.0060.02.....	45
35.	Removing Electrical Service Meter Breaker Pedestal, Item SPV.0060.03.	45
36.	Permanent Traffic Control Drum, Item SPV.0060.04.	46
37.	Signs Flashing LED, Stop, Item SPV.0060.05.	47

38.	Signs Flashing LED, Vehicle Entrance, Item SPV.0060.06.....	47
39.	Removing Traffic Signals CTH P and USH 14 Intersection, Item SPV.0105.01.	48
40.	Temporary Vehicle Detection USH 14 and CTH P, Item SPV.0105.02; Temporary Vehicle Detection CTH P and Bourbon Road, Item SPV.0105.03; Temporary Vehicle Detection CTH KP and Bourbon Road, Item SPV.0105.04.....	49
41.	Temporary Crosswalk Access (CTH P and USH 14), Item SPV.0105.05.	50
42.	Concrete Pavement Joint Layout, Item SPV.0105.06.....	51
43.	Geogrid Reinforcement, Item SPV.0180.01.	51

SPECIAL PROVISIONS

1. General.

Perform the work under this construction contract for Project 5310-02-74 Spring Green – Madison, CTH KP to Westview Court, Village of Cross Plains, USH 14 Dane County and Project 5657-00-70, Pine Bluff – Village of Cross Plains, Black Earth Creek Bridge, B-13-0646, CTH P, Dane County, Wisconsin as the plans show and execute the work as specified in the State of Wisconsin, Department of Transportation, Standard Specifications for Highway and Structure Construction, 2014 Edition, as published by the department, and these special provisions.

If all or a portion of the plans and special provisions are developed in the SI metric system and the schedule of prices is developed in the US standard measure system, the department will pay for the work as bid in the US standard system.

100-005 (20130615)

2. Scope of Work.

The work under this contract shall consist of construction of structure B-13-0646, removal of existing structure B-13-0339, pavement removal, clearing, grubbing, common excavation, borrow, select crushed material, dense graded base, storm sewer, concrete pavement, concrete curb and gutter, HMA pavement, traffic signals, permanent signing, pavement marking, finishing and all incidental items necessary to complete the work as shown on the plans and included in the proposal and contract.

104-005 (20090901)

3. Prosecution and Progress.

Begin work within ten calendar days after the engineer issues a written notice to do so.

Provide the start date to the engineer in writing within a month after executing the contract but at least 14 calendar days before the preconstruction conference. Upon approval, the engineer will issue the notice to proceed within ten calendar days before the approved start date.

To revise the start date, submit a written request to the engineer at least two weeks before the intended start date. The engineer will approve or deny that request based on the conditions cited in the request and its effect on the department's scheduled resources.

Prior to beginning operations under this contract, submit in writing the proposed schedule of operations to the engineer for approval.

Complete all work necessary to reopen CTH P and Structure B-13-0626 to traffic prior to 12:01 AM October 17, 2014.

Supplement standard spec 108.11 as follows:

If the contractor fails to complete the work necessary to reopen CTH P and structure B-13-0626 to traffic prior to 12:01 AM October 17, 2014, the department will assess the contractor \$2,000 in interim liquidated damages for each calendar day contract work remains incomplete beyond 12:01 AM October 17, 2014. An entire calendar day will be charged for any period of time within a calendar day that the road remains closed beyond 12:01 AM. Work completed prior to 12:01 AM October 17, 2014 shall include all items with the exception of maintaining both permanent traffic control drums and temporary signals.

If contract time expires prior to completing all work specified in the contract, additional liquidated damages will be affixed according to standard spec 108.11.

Install signing and pavement marking improvements on Bourbon Road to the maximum extent possible prior to use as the CTH P detour.

Migratory Birds

Swallow and other migratory birds' nests have been observed on or under the existing bridge. All active nests (when eggs or young are present) of migratory birds are protected under the federal Migratory Bird Treaty Act.

The nesting season for swallows and other birds is usually between May 1 and August 30. Either prevent active nests from becoming established, or apply for a depredation permit from the US Fish and Wildlife Service for work that may disturb or destroy active nests. The need for a permit may be avoided by removing the existing bridge structure prior to nest occupation by birds, or clearing nests from all structures before the nests become active in early spring. As a last resort, prevent birds from nesting by installing a suitable netting device on the remaining structure prior to nesting activity. Include the cost for preventing nesting in the cost of Removing Old Structure Over Waterway with Minimal Debris.

The Dane County Highway Department will install netting on the CTH P structure prior to May 1. Take over maintenance of the netting when the construction contract is executed.

Fish Spawning

There shall be no instream disturbance of Black Earth Creek as a result of construction activity under or for this contract, from May 15, 2014 or after September 15, 2014 both dates inclusive, in order to avoid adverse impacts upon the spawning of trout.

Any change to this limitation will require submitting a written request by the contractor to the engineer, subsequent review and concurrence by the Department of Natural Resources in the request, and final approval by the engineer. The approval will include all conditions to the request as mutually agreed upon by WisDOT and DNR.
Fish (20090901)

Aquatic Exotic Species Control

Wisconsin Ch. NR 40 prohibits exotic invasive organisms, and the New Zealand Mud Snail (*Potamopyrgus antpodarum*), has been identified in Black Earth Creek. This organism poses adverse effects to waters of the state. Wisconsin State Statutes 30.07, "Transportation of Aquatic Plants and Animals; Placement of Objects in Navigable Waters", details the state law that requires the removal of aquatic plants and organisms from objects that are put into state waters. However, this invasive organism requires additional cleaning and disinfecting procedures to protect other waters of the state. Black Earth Creek is nationally known for great trout fishing.

The New Zealand Mud snail has the ability to reproduce quickly and mass in high densities impacting the food chain of native organisms including trout and can alter the physical characteristics of the streams themselves. Mudsnailed are able to withstand harsh conditions such as prolonged periods of desiccation, a variety of temperature regimes and have been observed surviving immersion in various sanitizing agents. Due to its small size (about the size of a grain of rice), the New Zealand mudsnail can easily hitchhike on a variety of recreational and commercial equipment that comes in contact with the water and riparian zone and it is able to survive out of the water for an extended period of time. Pathways of invasion include but are not limited to boots, waders and other fishing gear, watercraft, and construction equipment and materials. Anyone that comes into contact with the water or stream bank vegetation must be vigilant in checking their gear and ensuring that it is free of mud and any noticeable snails, otherwise they may be in violation of NR 40, and associated fines.

At construction sites that involve navigable water or wetlands, use the follow procedures to minimize the chance of spreading the exotic invasive species to other areas. Use these procedures for all equipment, materials, boots and clothing that come in contact with Black Earth Creek waters (including tributaries) or stream bank vegetation. Rock or spoils will not be allowed to leave the site, unless prior approval has been made by WDNR and WisDOT.

Ensure that all equipment that has been in contact with waters of the state, or with infested or potentially infested waters, has been decontaminated for aquatic plants and organisms prior to being used in other waters of the state. Before and after using equipment on this project, thoroughly disinfect all equipment that has come into contact with potentially infested waters. Use the following inspection and removal procedures:

1. Prior to entering or transporting equipment to or from Black Earth Creek, steam clean (water temp ~212° F) machinery and ensure that the machinery is free of all soil and other substances that could possibly contain exotic invasive species;
2. Drain any area where water may be trapped;

3. Inspect machinery and scrape off any attached organisms and aquatic plant materials (fragments, stems, leaves, seeds, or roots), and dispose of the aquatic organism and plant materials in a garbage can prior to leaving the area or invested waters; and
4. Disinfect all clothing (boots, waders, gloves, life jackets) and all equipment and materials that come in contact with the water or stream bank vegetation with:
 - a. ~212° F water (steam clean), or
 - b. Construct disinfecting stations supplied with basins with 1:100 solution (38 grams per gallon) of Virkon Aquatic for 20- to 30-minute contact time. If possible this disinfectant should be used in conjunction with a hot water (>104° F), and rinsed after disinfection. Disposal of disinfection and rinse waters should not occur in waters of the state or areas that drain to waters of the state.

Complete the inspection and removal procedure before equipment is brought to the project site and before the equipment leaves the project site. Debris, spoils and other waste material including bridge pieces that may have come in contact with Black Earth Creek may contain mudsnails and cannot be transported to or utilized in any other waterway or wasted in any area that drains to another waterway. All erosion control devices or other materials that have come into contact with the water or banks of Black Earth Creek or its tributaries will need to be disinfected according to the procedures above if they could be utilized on another project site. Pumps and hoses used on the project site will need to be disinfected according to the procedures above before they are transported from the project site.

Perform the inspection and disinfection procedures outlined above without applying for additional compensation. The inspection and disinfection procedures are considered incidental to the work within the contract.

Water to be utilized for dust control or other construction purposes should not be withdrawn from Black Earth Creek for this project.

Track Pads

To minimize impacts to wetland soil and vegetation the use of Track Pads are required when applicable. All track pads that may have been exposed to water from Black Earth Creek or its tributaries must be steam cleaned or disinfected as indicated above.

Pedestrian Access

Maintain existing sidewalk at all times, as shown on the plans, except under direction of the engineer. In areas of sidewalk construction, provide a temporary surface for pedestrian access at all times. Construct temporary surface meeting Americans with Disabilities Act Accessibility Guidelines (ADAAG) requirements and consisting of temporary asphaltic surface, any grade of concrete, skid resistant steel plating, or alternative material as approved by the engineer. Gravel or base course material is not acceptable. Maintaining sidewalk is considered incidental to the contract. Maintain sidewalk access to all businesses and residences at all times.

Maintain existing pedestrian movements crossing the construction zone at all intersections at all times as hereby noted. Construct pedestrian crossings of intersections meeting requirements of the Americans with Disabilities Act Accessibility Guidelines (ADAAG) and consisting of temporary asphaltic surface. Gravel or base course material is not acceptable. Maintain ADA accessible pedestrian walkways that are free from mud, sand, and construction debris. The Temporary Crosswalk Access bid item is payment for maintaining crosswalks through the construction zone where existing crosswalk exist. Any closures of sidewalk will be approved by the engineer. At locations where crosswalks crossing exist on both sides of the intersection, closure of one of the two crosswalks is permitted as long as all other crossings are completely open. At intersections where only one crosswalk exists, crossing work should be staged to maintain crosswalk at all times.

4. Traffic.

The work under this contract shall be performed in a manner that will not interfere with the travel lanes and shoulders on USH 14 except as indicated on the plans. Vehicles, equipment and materials may be stored within the road right-of-way at locations approved by the engineer. A clear width of at least 12 feet shall be maintained from the edge of the traveled lanes on USH 14 except during the performance of required work within this clear zone.

Vehicles not engaged in the construction operations, or authorized by the engineer, shall not be parked within the right-of-way for USH 14 or CTH P. All vehicles and equipment entering or leaving the live traffic lanes on USH 14 and shall be equipped with a hazard identification beam (flashing yellow signal) visible in all directions. Activate the beam when merging into, leaving, or crossing a live traffic lane, and wherever working off the roadway within the clear zone.

Perform this work in accordance to standard spec 643, as shown on the plans or as approved by the engineer, except as hereinafter modified.

Coordinate all arrangements for handling traffic with the engineer before starting work. Ensure that all traffic control devices are in place and approved by the engineer before the beginning of each stage.

Do not disturb, remove or obliterate any traffic control signs, advisory signs or delineators not included in the plan, along the traveled roadways without the approval of the engineer. Temporarily cover or remove signs which conflict with temporary traffic control. For further direction regarding existing signs, refer to the traffic control plan.

Prior to the installation of traffic control devices, provide the engineer and the State Highway Patrol with the name and telephone number of a local person responsible for the emergency maintenance of traffic control that can be contacted during non-working hours in the event a safety hazard develops.

During the life of this contract, provide 24 hour-a-day availability of equipment and forces to promptly restore barricades, or other traffic control devices that are damaged or disturbed. In no case shall any barricade or other traffic control device be out of service for more than 24 hours.

Use drums or barricades to delineate traffic and/or protect hazards in the work zone such as exposed manholes or dropoffs. The use of such devices shall be incidental to operations that created the hazard.

Conduct operations in such a manner that causes the least interference and inconvenience to the free flow of vehicles on USH 14. This includes the following:

1. Immediately repair or replace at contractor expense any damage done to traffic control signs or advisory signs along the traveled roadway during construction operations.
2. Deliver materials and equipment off the live traveled lanes and shoulders.
3. Completely cover any signs containing messages conflicting with nearby signs.
4. Immediately clean up debris falling onto the roadway.

Notify all local emergency services at least 1 week prior to any of the following:

1. Detouring traffic / closing CTH P.

Submit the weekly schedule of lane closures at least one week in advance of the first closing to the Wisconsin Department of Transportation.

USH 14

USH 14 shall remain open to all traffic. Construction operations should not impact through traffic on USH 14. A shoulder closure adjacent to temporary pavement may occur if needed for equipment access.

CTH P

CTH P will be closed to through traffic during the construction of B-13-646 and the approaches. Traffic will be detoured on Bourbon Road, CTH KP and USH 14 as defined in the plans. The construction of the CTH P / Bourbon Road intersection will occur under traffic utilizing flagging operations.

CTH KP

Lane closures on CTH KP will be allowed for the milling and overlay operations. The work will be performed under flagging operations.

Bourbon Road

Bourbon Road pavement marking will occur under flagging operations.

CTH P / Bourbon Road Intersection

When existing CTH P / Bourbon Road pavement must be removed adjacent to a live traffic lane, the contractor shall grade the aggregate existing under the removed pavement up against the pavement slab or add aggregate to form a compacted shoulder, with a minimum of two feet of width. This work shall be completed to eliminate any dropoffs from the pavement slab to the subgrade. This aggregate shoulder shall remain in place until the fine grading operation for the pavement placement is in progress. In these areas, the contractor shall schedule his operations to minimize the period of time between removal of the existing pavement and placement of the new pavement.

Construction Staging

Work Zone Area 1

- Mill and overlay CTH KP.
- Pavement marking and signing on Bourbon Road.

Traffic Control Area 1

- Work performed under flagging operations.

Work Zone Area 2

- Grading for CTH P structure approaches lanes.
- Remove existing and construct proposed CTH P structure,

Traffic Control Area 2

- CTH P will be closed at the Black Earth Creek bridge.
- A detour will be in place using Bourbon Road, CTH KP and USH 14.

Work Zone Area 3

- Construct CTH P / Bourbon Road intersection.

Traffic Control Area 3

- Work performed under flagging operations during daytime hours.
- Roadway will be fully opened during night hours. Traffic may run on base for no more than one week.

Work Zone Area 4

- Construct temporary pavement north of USH 14 / CTH P intersection.

Traffic Control Area 4

- Work performed under flagging operations during daytime hours.
- Roadway will be fully opened during night hours. CTH P traffic may run on base for no more than one week.

5. Holiday Work Restrictions.

Do not perform work on, nor haul materials of any kind along or across any portion of the highway carrying USH 14 traffic, and entirely clear the traveled way and shoulders of such portions of the highway of equipment, barricades, signs, lights, and any other material that might impede the free flow of traffic during the following holiday periods:

- From 6:00 AM, Thursday, July 3, 2014 to 8:00 PM Monday, July 7, 2014 for Independence Day;
- From 6:00 AM, Friday, Aug. 29, 2014 to 8:00 PM Monday, Sept. 1, 2014 for Labor Day.

107-005 (20050502)

6. Utilities.

This contract comes under the provisions of Administrative Rule TRANS 220. (090208) 107-065. On this project Administrative Rule TRANS 220 utility coordination process was followed.

There are underground and overhead utility facilities located within the project limits. The contractor shall coordinate their construction activities with a call to Diggers Hotline or a direct call to the utilities that have facilities in the area as required per statutes. The contractor shall use caution to ensure the integrity of the underground facilities and shall maintain code clearances from overhead facilities at all times.

Madison Gas & Electric – Gas

Madison Gas & Electric has a gas line located within the project limits. Work will be completed during construction.

Madison Gas & Electric will replace the existing gas line between Station 12+30 – Station 14+00. The new gas line will be placed west of its existing location, approximately four feet from the future bridge wing wall.

Madison Gas & Electric will open cut this line across Black Earth Creek while environmental controls have been placed for the CTH P bridge replacement. The work will take place after the existing structure has been demolished but prior to the wing wall construction of the new bridge.

Work is anticipated to take 7 working days to complete. Contact MG&E 14 days prior to the completion of the existing bridge's demolition.

Contact for MG&E gas – Steve Beversdorf, 133 S. Blair St. Madison, WI 53788, Cell (608) 444-9620, E-mail - SBeversdorf@mge.com.

Madison Gas & Electric – Electric

Madison Gas & Electric has overhead facilities located within the project limits. Work will be completed prior to construction.

Madison Gas & Electric has current overhead electric on the east side of the CTH P bridge. The line will be relocated starting from an existing pole located at approximately Station 11+50 "P" 40 feet right. The overhead line will head west to a new pole and anchor located behind the curb on the south side of Bourbon Road at approximately Station 12+00 "P" 94 feet left. The line will then head in a north easterly direction crossing the Black Earth Creek to a new pole at approximately Station 13+50 "P" 80 feet left the new pole will be approximately 30 feet from the new bridge's north western wing wall. The line then continues in a northern direction to a pole at approximately Station 146+09 26 feet right. The line then crosses USH 14 to a new pole and anchor at approximately Station 145+90 53 feet left. The existing two poles on the east side of the structure will be removed prior to construction.

The relocation of these poles will take approximately 15 working days and will be completed by May 31, 2014.

Contact for MG&E electric – Rich Parker, 133 S. Blair St. Madison, WI 53788, Cell (608) 444-9619, E-mail RParker@mge.com.

Charter Communication

Charter communications has overhead coax and fiber attached to MG&E poles. Relocation of fiber and coax will be done in conjunction with the relocation of MG&E electric poles. Work will be completed prior to construction within roughly the same time line as the MG&E electric relocation. For more information regarding the relocation refer to "Madison Gas & Electric – Electric" portion of the specials.

Contact for Charter Communication is Randy Lettman, 2701 Daniels St. Madison, WI 53718, Cell (608) 575-6415, E-mail randall.lettman@charter.com.

TDS Telecom

TDS has both aerial and underground facilities located within the project limits. The relocation will be done in conjunction with MG&E electric and will be done prior to construction within roughly the same time period. For more information regarding the relocation refer to "Madison Gas & Electric – Electric" portion of the specials.

TDS will leave MG&E's last pole at approximately Station 145+90 53 feet left, go underground and head north east to approximately Station 146+35 83 feet left then turns slightly heading in a south easterly direction to an existing TDS manhole located at Station 147+30 60 feet left.

Contact for TDS is Jerry Myers, 525 Junction Rd. Madison, WI, Cell (608) 279-7104, E-mail jerry.myers@tdstelecom.com.

7. Railroad Insurance and Coordination.

A Description

Comply with standard spec 107.17 for all work affecting Wisconsin and Southern Railroad Company property and any existing tracks.

A.1 Railroad Insurance Requirements

In addition to standard spec 107.26, provide railroad protective liability insurance coverage as specified in standard spec 107.17.3. Insurance is filed in the name of Wisconsin and Southern Railroad Company.

Notify evidence of the required coverage, and duration to Roger Schaalma at (414) 438-8820, Ext. 4201; 1890 East Johnson Street, Madison, WI, 53704. Include the following information on the insurance document:

Project: 5310-02-74
Route Name: USH 14, Dane County
Crossing ID: #391 766J
Railroad Subdivision: Prairie
Railroad Milepost: 0152.72

A.2 Work by Railroad

The railroad will perform the work described in this section, except for work described in other special provisions and will be accomplished without cost to the contractor.

The railroad crossing surface at CTH P will be reconstructed with precast planks prior to construction under this contract. In addition, railroad signal upgrades will also be constructed at both CTH P and Bourbon Road.

A.3 Names and addresses of Railroad Representatives for Consultation and Coordination

Contact Roger Schaalma, Superintendent of Maintenance of Way, Wisconsin and Southern Railroad Co., 1890 East Johnson Street, Madison, WI 53704; TELEPHONE (414) 438-8820; Ext. 4201; FAX (608) 243-9225; email rschaalma@watcocompanies.com for consultation on railroad requirements during construction.

Amend standard spec 108.4 to include the railroad in the distribution of the initial bar chart, and monthly schedule updates. The bar chart shall specifically show work involving coordination with the railroad.

A.4 Temporary Grade Crossing

If a temporary grade crossing is desired, submit a written request to the railroad representative named in A.3 several weeks prior to the time needed. Approval is subject to the discretion of the railroad. The department has made no arrangements for a temporary grade crossing.

A.5 Train Operation

Approximately 0 passenger trains and 4-5 through freight trains operate daily through the construction site. Through freight trains operate at up to 25 mph.

A.6 Rail Security Awareness and Contractor Orientation

Prior to entry on railroad right-of-way, the contractor shall arrange for on-line security awareness and contractor orientation training and testing, and be registered through “e-RAILSAFE” for all contractor and subcontractor employees working on railroad right-of-way. See e-railsafe.com “Information”. The security awareness and contractor orientation training is shown under the railroad’s name. The department has secured right of entry to railroad property; neither the contractor nor subcontractors or their employees will be required to sign a right-of-entry form. The security awareness and contractor orientation certification is valid for one year and must be renewed for projects that will carry over beyond the one year period. Contractor and subcontractor employees shall wear the identification badge issued by e-RAILSAFE when on railroad right-of-way. Costs associated with training and registration are incidental to other items in the contract.

8. Information to Bidders, U.S. Army Corps of Engineers Section 404 Permit.

The department has obtained a U.S. Army Corps of Engineers Section 404 permit. Comply with the requirements of the permit in addition to requirements of the special provisions. A copy of the permit is available from the regional office by contacting Lalitha Balachandran at (608) 243-3382.
107-054 (20080901)

9. Salvage of Materials.

The work under this contract shall include removing, salvaging and reinstalling select light poles, light fixtures, signal standards, signal assemblies and preemption devices. Contractor is responsible for stockpiling the salvaged materials to prevent damage until reinstallation.

10. Advanced Notice for Lane Closure System.

Provide the engineer with a schedule of requested width restrictions for the following week a minimum of one week in advance and by noon on Thursday of the previous week. In addition, provide the following minimum advanced notification to the engineer for incorporation into the Wisconsin Lane Closure (LCS). The LCS is linked to the 511 System and the WisDOT web site.

Shoulder closures	2 calendar days
Detouring	10 calendar days
Lane closures	5 calendar days
Construction stage changes	5 calendar days

Notify the engineer and WisDOT Statewide Traffic Operations Center at (414) 227-2142 if there are any changes in the schedule, early completions, or cancelations of scheduled work.

The department has the authority to disallow any requested closures or width restrictions.

11. Removing Pavement.

The work under this item shall be in accordance to the requirements of standard spec 204, as shown on the plans, and as hereinafter provided.

Remove existing concrete pavement in a manner that causes minimal disturbance to the underlying base material.

All removed pavement shall be considered unusable material, and shall become the property of the contractor and shall be disposed of by the contractor in an environmentally acceptable manner. The cost to dispose of all excess materials, including steel reinforcement, shall be included in the item of Removing Pavement.

12. Hauling Restrictions.

Access to USH 14 for the delivery or hauling of construction materials for this project shall be at the existing or temporary roadways unless approved by the department.

The contractor shall provide personnel to control the movement of trucks entering and leaving the work sites adjacent to the “open to public areas”.

Equip all vehicles traveling on public roads that are hauling materials or removals that are subject to spillage, either by wind or vibration, with tailgates and adequate sideboards. Use canvas covers and any other protective devices to prevent spillage as determined necessary by the engineer.

13. Environmental.

Supplement standard spec 107.20 with the following:

Pursue operations in a timely and diligent manner, continuing all construction operations methodically from the initial topsoil stripping operation through the subsequent grading, re-topsoiling, and installation of erosion control devices in order to minimize the period of exposure to possible erosion.

Stockpile spoil material on upland sites an adequate distance from the stream and any open water created by excavation. Install filter fabric silt fence between spoil material and the stream and between the entire disturbed area and the waterway.

WDNR mandates that appropriate erosion control measures be applied to borrow and waste areas during and following construction. Following completion of the project, restore borrow and waste areas and properly seed, mulch and protect them from the effects of erosion.

When engaged in roadway clearing operations, the contractor shall use equipment having vacuum or water spray mechanisms to eliminate the dispersion of particulate matter into the atmosphere. If vacuum equipment is employed, it must have a suitable self-contained particulate collector to prevent discharge from the collector bin into the atmosphere.

Remove all temporary erosion control measures after disturbed areas are stabilized or at the direction of the engineer.

Existing waterways and sensitive areas shall be protected. Do not disturb or store any equipment or materials in these areas without prior approval from the engineer. Store materials upland and away from the waterway. Do not wash out equipment in drainage ways or direct conduits to waters of the state. Keep slurry out of drainage ways.

If dewatering is required, filter or settle the dirty water prior to off-site release or into a waterway. Dissipate the release as to not cause any scour outflow area.

Provide the Erosion Control Implementation Plan (ECIP) 14 days prior to the pre-construction conference. The contractor shall prepare and submit an ECIP for the project, including borrow sites and material disposal sites, in accordance to Wis. Adm. Code Chapter TRANS 401 requirements. The erosion control implementation plan shall supplement information shown on the plans and shall not reproduce it. The erosion control implementation plan will identify how the contractor intends to implement the project's erosion control plan.

14. Erosion Control Structures.

Within seven calendar days after the commencement of work on the bridge superstructure, place all permanent erosion control devices, including riprap, erosion mat, ditch checks, seed, fertilizer, mulch, soil stabilizer, or any other item required by the contract or deemed necessary by the engineer. These devices shall be in place in the area under the bridge and on both sides of the roadway, from the waterway to a point 100-feet behind the backwall of the abutment. Within said limits, place these devices to a height equivalent to the calculated water elevation resulting from a storm that occurs on the average of once every two years (Q2) as shown on the plan, or as directed by the engineer. Prior to initial construction operations, place turbidity barriers, silt screens, and other temporary erosion control measures as shown on the plans, and remove them after the permanent erosion control devices are in place unless directed otherwise by the engineer.

In the event that construction activity does not disturb the existing ground below the Q2 elevation, the above timing requirements for permanent erosion control shall be waived.
107-070 (20030820)

15. Pedestrian Access.

At the intersection of USH 14 and CTH P, maintain pedestrian access on existing or department approved temporary facilities.

At the intersection of USH 14 and CTH P, there are currently facilities for pedestrian crossings and sidewalks on the north side of the roadway. There are no bike facilities in the construction area. Temporary pedestrian crossings and push button signals will be provided for the locations where they currently exist. Temporary pedestrian crossings will be paved surfaces with provisions for handicap access and will be relocated as necessary as the construction progresses. Maintain temporary access on the south side of the intersection while construction occurs on the north side of the intersection.

Supplement standard spec 643 as follows:

Use drums, barricades or temporary fencing to delineate and or protect hazards in the work zone, such as exposed manholes, trenches or other drops-offs for vehicles and pedestrians. The use of such devices will be incidental to the operations that creates the hazard.

Pedestrian movements shall be maintained at all times at the signalized intersection. Pedestrian corridors shall be guided by safety fencing or traffic drums. Pedestrian crossings of the intersection shall meet requirements of the Americans with Disabilities Act (ADA). Pedestrian walkways shall be surfaced as described in the Prosecution and Progress special provision provided herein and be maintained ADA accessible, and free from mud, sand, and construction debris. Sections of the walkways that are disturbed or removed during construction activities shall be replaced with temporary surfaced pedestrian route prior to reopening the walkway.

16. Notice to Contractor, Notification of Demolition and/or Renovation No Asbestos Found.

John Roelke, License Number AII-119523, inspected Structure B-13-0339, for asbestos on December 22, 2011. No regulated Asbestos Containing Material (RACM) was found on this structure. A copy of the inspection report is available from: Kris Sommers, (608) 242-8014.

In accordance to NR447 and DHS159, ensure that DNR or DHS receives a completed Notification of Demolition and/or Renovation (DNR Form 4500-113 (R 4/11), or subsequent revision) via U.S. mail, hand-delivery, or using the online notification system at least 10 working days prior to beginning any construction or demolition. Pay all associated fees. Provide a copy of the completed 4500-113 form to Kris Sommers, (608) 242-8014 and DOT BTS-ESS attn: Hazardous Materials Specialist PO Box 7965, Madison, WI 53707-7965. In addition, comply with all local or municipal asbestos requirements.

Use the following information to complete WisDNR form 4500-113:

- Site Name: Structure B-13-0339, CTH P over Black Earth Creek
- Site Address: 0.05M S JCT USH 14 / CTH P
- Ownership Information: Dane County Highway Department, 2302 Fish Hatchery Road, Madison, WI 53713-2495
- Contact: Kris Sommers, PE
- Phone: (608) 242-8014
- Age: 77 years. This structure was constructed in 1937.
- Area: 1256 SF of deck

Insert the following paragraph in Section 6.g.:

If asbestos not previously identified is found or previously non-friable asbestos becomes crumbled, pulverized, or reduced to a powder, stop work immediately, notify the engineer, and the engineer will notify the department's Bureau of Technical Services at (608) 266-1476 for an emergency response in accordance to standard spec 107.24. Keep material wet until it is abated or until it is determined to be non-asbestos containing material.

107-125 (20120615)

17. Removing Old Structure Over Waterway With Minimal Debris Station 13+00 'P', Item 203.0600.S.01.

Conform to standard spec 203 as modified in this special provision.

Add the following to standard spec 203:

203.3.6 Removals Over Waterways and Wetlands

203.3.6.2 Removing Old Structure Over Waterway with Minimal Debris

- (1) Remove the existing structure B-13-0339 over the Black Earth Creek in large sections and conforming to the contractor's approved structure removal and clean-up plan. During superstructure removal, prevent all large pieces and minimize the number of small pieces from entering the waterway or wetland. Remove all reinforcing steel, all concrete, and all other debris that falls into the waterway or wetland. The contractor may leave limited amounts of small concrete pieces scattered over the waterway floor or wetland only if the engineer allows.
- (2) Submit a structure removal and clean-up plan as part of the erosion control implementation plan required under standard spec 107.20. Do not start work under the structure removal and clean-up plan without the department's written approval of the plan. Include the following information in the structure removal and clean-up plan:
 - Methods and schedule to remove the structure.
 - Methods to control potentially harmful environmental impacts.
 - Methods for superstructure removal that prevent all large pieces and minimize the number of small pieces from entering the waterway or wetlands.
 - Methods to control dust and contain slurry.

- Methods for removing piers and abutments. If blasting in water, include restrictions that regulatory agencies and the contract require.
 - Methods for cleaning the waterway or wetlands.
- (3) If stockpiling spoil material, place it on an upland site an adequate distance from the waterway, wetland, or any open water created by excavation. Install silt fence between the spoil pile and the waterway, wetland, or excavation site.

Add the following Removing Old Structure bid item to standard spec 203.5.1:

ITEM NUMBER	DESCRIPTION	UNIT
203.0600.S.01	Removing Old Structure Over Waterway With Minimal Debris Station 13+00 'P'	LS
203-020 (20080902)		

18. Removing Type II Sign Structures, Item 204.9060.S.01.

A Description

This special provision describes removing Type II Sign Structures in accordance to the pertinent provisions of standard spec 204 and as hereinafter provided.

B (Vacant)

C (Vacant)

D Measurement

The department will measure Removing Type II Sign Structures in each unit for removing type II sign structures, acceptably completed.

E Payment

Supplement standard spec 204.5 to include the following:

ITEM NUMBER	DESCRIPTION	UNIT
204.9060.S.01	Removing Type II Sign Structures	Each

Payment is full compensation for sawing and excavating, furnishing the equipment, including all required materials, tools, and supplies; for furnishing all labor; for clean-up and waste disposal; and for furnishing all incidentals necessary to complete this item of work.

204-025 (20041005)

19. Removing Concrete Median, Item 204.9090.S.02.

A Description

This special provision describes removing constant width concrete median in accordance to the pertinent provisions of standard spec 204 and as hereinafter provided.

B (Vacant)

C (Vacant)

D Measurement

The department will measure Removing Concrete Median in linear feet units for removing concrete median, acceptably completed.

E Payment

Supplement standard spec 204.5 to include the following:

ITEM NUMBER	DESCRIPTION	UNIT
204.9090.S.02	Removing Concrete Median	LF

Payment is full compensation for sawing and excavating, furnishing the equipment, including all required materials, tools, and supplies; for furnishing all labor; for clean-up and waste disposal; and for furnishing all incidentals necessary to complete this item of work.

204-025 (20041005)

20. Excavation, Hauling, and Disposal of Petroleum Contaminated Soil, Item 205.0501.S.

A Description

A.1 General

This special provision describes excavating, loading, hauling, and disposing of petroleum contaminated soil at a DNR approved bioremediation facility. The closest DNR approved bioremediation facility is

Waste Management of Wisconsin Madison Prairie Landfill
6002 Nelson Rd.
Sun Prairie, WI 53590

Perform this work in accordance to standard spec 205 and with pertinent parts of Chapters NR 700-754 of the Wisconsin Administrative Code, as supplemented herein. Per NR 718.07, a solid waste collection and transportation service-operating license is required under NR 502.06 for each vehicle used to transport contaminated soil.

A.2 Notice to the Contractor – Contaminated Soil Location(s)

The department completed testing for soil and groundwater contamination for locations within this project where excavation is required. Testing indicated that petroleum-contaminated soil is present at the following location(s) as shown on the plans:

1. Station 147+00 to 148+75, from 30 feet left of reference line to construction limits right, from 5 feet below ground surface to the maximum depth of excavation. The estimated volume of petroleum-contaminated soil to be excavated at this location is 180 cubic yards (estimated 300 tons).

If contaminated soils are encountered elsewhere on the project, terminate excavation activities in the area and notify the engineer.

For further information regarding previous investigation and remediation activities at these sites contact:

Name: TRC Environmental Corp., Mr. Dan Haak or Mr. Mark Walter
Address: 708 Heartland Trail, Suite 3000, Madison, WI 53717
Phone: (608) 826-3600
Fax: (608) 826-3941
E-mail: dhaak@trcsolutions.com, mwalter@trcsolutions.com

A.3 Coordination

Coordinate work under this contract with the environment consultant:

Name: TRC Environmental Corp.
Address: 708 Heartland Trail, Suite 3000 Madison, WI 53717
Contact: Mr. Dan Haak or Mr. Mark Walter
Phone: (608) 826-3600
Fax: (608) 826-3941
E-mail: dhaak@trcsolutions.com, mwalter@trcsolutions.com

The role of the environmental consultant will be limited to:

1. Determining the location and limits of contaminated soil to be excavated based on soil analytical results from previous investigations, visual observations, and field screening of soil that is excavated;
2. Identifying contaminated soils to be hauled to the bioremediation facility;
3. Documenting that activities associated with management of contaminated soil are in conformance with the contaminated soil management methods for this project as specified herein; and
4. Obtaining the necessary approvals for disposal of contaminated soil from the bioremediation facility.

Provide at least a 14-calendar day notice of the preconstruction conference date to the environmental consultant. At the preconstruction conference, provide a schedule for all excavation activities in the areas of contamination to the environmental consultant. Also notify the environmental consultant at least three calendar days prior to commencement of excavation activities in each of the contaminated areas.

Coordinate with the environmental consultant to ensure that the environmental consultant is present during excavation activities in the contaminated areas. Perform excavation work in each of the contaminated areas on a continuous basis until excavation work is completed.

Identify the DNR approved bioremediation facility that will be used for disposal of contaminated soils, and provide this information to the environmental consultant no later than 30 calendar days prior to commencement of excavation activities in the contaminated areas or at the preconstruction conference, whichever comes first. The environmental consultant will be responsible for obtaining the necessary approvals for disposal of contaminated soils from the bioremediation facility. Do not transport contaminated soil offsite without prior approval from the environmental consultant.

A.4 Health and Safety Requirements

Supplement standard spec 107.1 with the following:

During excavation activities, expect to encounter soil contaminated with gasoline, diesel fuel, fuel oil, or other petroleum related products. Site workers taking part in activities that will result in the reasonable probability of exposure to safety and health hazards associated with hazardous materials shall have completed health and safety training that meets the Occupational Safety and Health Administration (OSHA) requirements for Hazardous Waste Operations and Emergency Response (HAZWOPER), as provided in 29 CFR 1910.120.

Prepare a site-specific Health and Safety Plan, and develop, delineate and enforce the health and safety exclusion zones for each contaminated site location as required by 29 CFR 1910.120. Submit the site-specific health and safety plan and written documentation of up-to-date OSHA training to the engineer prior to the start of work.

B (Vacant)

C Construction

Supplement standard spec 205.3 with the following:

Control operations in the contaminated areas to minimize the quantity of contaminated soil excavated.

The environmental consultant will periodically evaluate soil excavated from the contaminated areas to determine if the soil will require offsite bioremediation. The environmental consultant will evaluate excavated soil based on field screening results, visual observations, and soil analytical results from previous environmental investigations. Assist the environmental consultant in collecting soil samples for evaluation using excavation equipment. The sampling frequency shall be a maximum of one sample for every 15 cubic yards excavated.

Directly load and haul soils designated by the environmental consultant for offsite bioremediation to the DNR approved bioremediation facility. Use loading and hauling practices that are appropriate to prevent any spills or releases of petroleum-contaminated soils or residues. Prior to transport, sufficiently dewater soils designated for off-site bioremediation so as not to contain free liquids.

D Measurement

The department will measure Excavation, Hauling, and Disposal of Petroleum Contaminated Soil in tons of contaminated soil, accepted by the bioremediation facility as documented by weight tickets generated by the bioremediation facility.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
205.0501.S	Excavation, Hauling, and Disposal of Petroleum Contaminated Soil	Ton

Payment is full compensation for excavating, segregating, loading, hauling, and treatment via bioremediation of contaminated soil; obtaining solid waste collection and transportation service operating licenses; assisting in the collection soil samples for field evaluation; and dewatering of soils prior to transport, if necessary.
205-003 (20080902)

21. Base Aggregate Dense, ¾ Inch.

Revise standard spec 301.2.4.3 as follows:

Furnish aggregate classified as crushed stone for ¾-Inch base when used in the top 3 inches of the unpaved portion of the shoulder or for unpaved driveways and field entrances.

22. Base Aggregate Dense 1 1/4-Inch, Item 305.0120.

Revise standard spec 305.2.2.1 as follows:

Use 1 1/4-Inch base aggregate that conforms to the following gradation requirements:

SIEVE	PERCENT PASSING BY WEIGHT
1 1/4 inch	95 - 100
1 inch	---
3/4 inch	70 - 90
3/8 inch	45 - 75
No. 4	30 - 60
No. 10	20 - 40
No. 40	7 - 25
No. 200	2 - 12 ^{[1], [2]}

^[1] Limited to a maximum of 8.0 percent for base placed between old and new pavement.

^[2] 3 - 10 percent passing when base is ³ 50% crushed gravel

23. QMP Base Aggregate.

A Description

A.1 General

- (1) This special provision describes contractor quality control (QC) sampling and testing for base aggregates, documenting those test results, and documenting related production and placement process changes. This special provision also describes department quality verification (QV), independent assurance (IA), and dispute resolution.
- (2) Conform to standard spec 301, standard spec 305, and standard spec 310 as modified here in this special provision. Apply this special provision to material placed under all of the Base Aggregate Dense and Base Aggregate Open Graded bid items, except do not apply this special provision to material classified as reclaimed asphaltic pavement placed under the Base Aggregate Dense bid items.
- (3) Do not apply this special provision to material placed under the Aggregate Detours, Salvaged Asphaltic Pavement Base, Breaker Run, Select Crushed, Pit Run, Subbase, or Riprap bid items.
- (4) Provide and maintain a quality control program, defined as all activities related to and documentation of the following:
 1. Production and placement control and inspection.
 2. Material sampling and testing.

- (5) Chapter 8 of the department's construction and materials manual (CMM) provides additional detailed guidance for QMP work and describes required sampling and testing procedures. The contractor may obtain the CMM from the department's web site at:

<http://roadwaystandards.dot.wi.gov/standards/cmm/index.htm>

A.2 Contractor Testing for Small Quantities

- (1) The department defines a small quantity, for each individual Base Aggregate bid item, as a plan quantity of 9000 tons or less of material as shown in the schedule of items under that bid item.
- (2) The requirements under this special provision apply equally to a small quantity for an individual bid item except as follows:

1. The contractor need not submit a full quality control plan but shall provide an organizational chart to the engineer including names, telephone numbers, and current certifications of all persons involved in the quality control program for material under affected bid items.

2. Divide the aggregate into uniformly sized sublots for testing as follows:

Plan Quantity	Minimum Required Testing
≤ 1500 tons	One test from production, load-out, or placement at the contractor's option ^[1]
> 1500 tons and ≤ 6000 tons	Two tests of the same type, either from production, load-out, or placement at the contractor's option ^[1]
> 6000 tons and ≤ 9000 tons	Three placement tests ^{[2][3]}

- ^[1] If using production tests for acceptance, submit test results to the engineer for review prior to incorporating the material into the work. Production test results are valid for a period of 3 years.

- ^[2] For 3-inch material, obtain samples at load-out.

- ^[3] If the actual quantity overruns 9000 tons, create overrun sublots to test at a rate of one additional placement test for each 3000 tons, or fraction of 3000 tons, of overrun.

3. No control charts are required. Submit aggregate load-out and placement test results to the engineer within one business day of obtaining the sample. Assure that all properties are within the limits specified for each test.
 4. Department verification testing is optional for quantities of 6000 tons or less.
- (3) Material represented by a subplot with any property outside the specification limits is nonconforming. The department may reject material or otherwise determine the final disposition of nonconforming material as specified in standard spec 106.5.

B Materials

B.1 Quality Control Plan

- (1) Submit a comprehensive written quality control plan to the engineer at or before the pre-construction meeting. Do not place base before the engineer reviews and comments on the plan. Construct the project as that plan provides.
- (2) Do not change the quality control plan without the engineer's review. Update the plan with changes as they become effective. Provide a current copy of the plan to the engineer and post in each of the contractor's laboratories as changes are adopted. Ensure that the plan provides the following elements:
 1. An organizational chart with names, telephone numbers, current certifications and/or titles, and roles and responsibilities of QC personnel.
 2. The process used to disseminate QC information and corrective action efforts to the appropriate persons. Include a list of recipients, the communication means that will be used, and action time frames.
 3. A list of source and processing locations, section and quarter descriptions, for all aggregate materials requiring QC testing.
 4. Test results for wear, sodium sulfate soundness, freeze/thaw soundness, and plasticity index of all aggregates requiring QC testing. Obtain this information from the region materials unit or from the engineer.
 5. Descriptions of stockpiling and hauling methods.
 6. Locations of the QC laboratory, retained sample storage, and where control charts and other documentation is posted.
 7. An outline for resolving a process control problem. Include responsible personnel, required documentation, and appropriate communication steps.

B.2 Personnel

- (1) Have personnel certified under the department's highway technician certification program (HTCP) perform sampling, testing, and documentation as follows:

Required Certification Level:	Sampling or Testing Roles:
Aggregate Technician IPP Aggregate Sampling Technician Aggregate Assistant Certified Technician (ACT-AGG)	Aggregate Sampling ^[1]
Aggregate Technician IPP Aggregate Assistant Certified Technician (ACT-AGG)	Aggregate Gradation Testing, Aggregate Fractured Particle Testing, Aggregate Liquid Limit and Plasticity Index Testing

^[1] Plant personnel under the direct observation of an aggregate technician certified at level one or higher may operate equipment to obtain samples.

- (2) A certified technician must coordinate and take responsibility for the work an ACT performs. Have a certified technician ensure that all sampling and testing is performed correctly, analyze test results, and post resulting data. No more than one ACT can work under a single certified technician.

B.3 Laboratory

- (1) Perform QC testing at a department-qualified laboratory. Obtain information on the Wisconsin laboratory qualification program from:

Materials Management Section

3502 Kinsman Blvd.

Madison, WI 53704

Telephone: (608) 246-5388

<http://www.dot.state.wi.us/business/engrserv/lab-qualification.htm>

B.4 Quality Control Documentation

B.4.1 General

- (1) Submit base aggregate placement documentation to the engineer within 10 business days after completing base placement. Ensure that the submittal is complete, neatly organized, and includes applicable project records and control charts.

B.4.2 Records

- (1) Document all placement observations, inspection records, and control adjustments daily in a permanent field record. Also include all test results in the project records. Provide test results to the engineer within 6 hours after obtaining a sample. For 3-inch base, extend this 6-hour limit to 24 hours. Post or distribute tabulated results using a method mutually agreeable to the engineer and contractor.

B.4.3 Control Charts

- (1) Plot gradation and fracture on the appropriate control chart as soon as test results are available. Format control charts according to CMM 8.30. Include the project number on base placement control charts. Maintain separate control charts for each base aggregate size, source or classification, and type.
- (2) Provide control charts to the engineer within 6 hours after obtaining a sample. For 3-inch base, extend this 6-hour limit to 24 hours. Post or distribute charts using a method mutually agreeable to the engineer and contractor. Update control charts daily to include the following:
 1. Contractor individual QC tests.
 2. Department QV tests.
 3. Department IA tests.
 4. Four-point running average of the QC tests.
- (3) Except as specified under B.8.2.1 for nonconforming QV tests, include only QC tests in the running average. The contractor may plot process control or informational tests on control charts, but do not include these tests, conforming QV tests, or IA tests in the running average.

B.5 Contractor Testing

- (1) Test gradation, fracture, liquid limit and plasticity index during placement for each base aggregate size, source or classification, and type.

- (2) Test gradation once per 3000 tons of material placed. Determine random sample locations and provide those sample locations to the engineer. Obtain samples after the material has been bladed, mixed, and shaped but before compacting; except collect 3-inch samples from the stockpile at load-out. Do not sample from material used to maintain local traffic or from areas of temporary base that will not have an overlying pavement. On days when placing only material used to maintain local traffic or only temporary base that will not have an overlying pavement, no placement testing is required.
- (3) Split each contractor QC sample and identify it according to CMM 8.30. Retain the split for 7 calendar days in a dry, protected location. If requested for department comparison testing, deliver the split to the engineer within one business day.
- (4) The engineer may require additional sampling and testing to evaluate suspect material or the technician's sampling and testing procedures.
- (5) Test fracture for each gradation test until the fracture running average is above the lower warning limit. Subsequently, the contractor may reduce the frequency to one test per 10 gradation tests if the fracture running average remains above the warning limit.
- (6) Test the liquid limit and plasticity index for the first gradation test. Subsequently, test the liquid limit and plasticity index a minimum of once per 10 gradation tests.

B.6 Test Methods

B.6.1 Gradation

- (1) Test gradation using a washed analysis conforming to the following as modified in CMM 8.60:
 Gradation..... AASHTO T 27
 Material finer than the No. 200 sieve..... AASHTO T 11
- (2) For 3-inch base, if 3 consecutive running average points for the percent passing the No. 200 sieve are 8.5 percent or less, the contractor may use an unwashed analysis. Wash at least one sample out of 10. If a single running average for the percent passing the No. 200 sieve exceeds 8.5 percent, resume washed analyses until 3 consecutive running average points are again 8.5 percent passing or less.
- (3) Maintain a separate control chart for each sieve size specified in standard spec 305 or standard spec 310 for each base aggregate size, source or classification, and type. Set control and warning limits based on the standard specification gradation limits as follows:
 1. Control limits are at the upper and lower specification limits.
 2. There are no upper warning limits for sieves allowing 100 percent passing and no lower control limits for sieves allowing 0 percent passing.

3. Dense graded warning limits, except for the No. 200 sieve, are 2 percent within the upper and lower control limits. Warning limits for the No. 200 sieve are set 0.5 percent within the upper and lower control limits.
4. Open graded warning limits for the 1-inch, 3/8-inch, and No. 4 sieves are 2 percent within the upper and lower control limits. Upper warning limits for the No. 10, No. 40, and No. 200 sieves are 1 percent inside the upper control limit.

B.6.2 Fracture

- (1) Test fracture conforming to CMM 8.60. The engineer will waive fractured particle testing on quarried stone.
- (2) Maintain a separate fracture control chart for each base aggregate size, source or classification, and type. Set the lower control limit at the contract specification limit, either specified in another special provision or in table 301-2 of standard spec 301.2.4.5. Set the lower warning limit 2 percent above the lower control limit. There are no upper limits.

B.6.3 Liquid Limit and Plasticity

- (1) Test the liquid limit and plasticity according to AASHTO T 89 and T 90.
- (2) Ensure the material conforms to the limits specified in standard spec table 301-2.

B.7 Corrective Action

B.7.1 General

- (1) Consider corrective action when the running average trends toward a warning limit. Take corrective action if an individual test exceeds the contract specification limit. Document all corrective actions both in the project records and on the appropriate control chart.

B.7.2 Placement Corrective Action

- (1) Do not blend additional material on the roadbed to correct gradation problems.
- (2) Notify the engineer whenever the running average exceeds a warning limit. When 2 consecutive running averages exceed a warning limit, the engineer and contractor will discuss appropriate corrective action. Perform the engineer's recommended corrective action and increase the testing frequency as follows:
 1. For gradation, increase the QC testing frequency to at least one randomly sampled test per 1000 tons placed.
 2. For fracture, increase the QC testing frequency to at least one test per gradation test.
- (3) If corrective action improves the property in question such that the running average after 4 additional tests is within the warning limits, the contractor may return to the testing frequency specified in B.5.3. If corrective action does not improve the property in question such that the running average after 4 additional individual tests is still in the warning band, repeat the steps outlined above starting with engineer notification.

- (4) If the running average exceeds a control limit, material starting from the first running average exceeding the control limit and ending at the first subsequent running average inside the control limit is nonconforming and subject to pay reduction.
- (5) For individual test results significantly outside the control limits, notify the engineer, stop placing base, and suspend other activities that may affect the area in question. The engineer and contractor will jointly review data, data reduction, and data analysis; evaluate sampling and testing procedures; and perform additional testing as required to determine the extent of potentially unacceptable material. The engineer may direct the contractor to remove and replace that material. Individual test results are significantly outside the control limits if meeting one or more of the following criteria:
 1. A gradation control limit for the No. 200 sieve is exceeded by more than 3.0 percent.
 2. A gradation control limit for any sieve, except the No. 200, is exceeded by more than 5.0 percent.
 3. The fracture control limit is exceeded by more than 10.0 percent.

B.8 Department Testing

B.8.1 General

- (1) The department will conduct verification testing to validate the quality of the product and independent assurance testing to evaluate the sampling and testing. The department will provide the contractor with a listing of names and telephone numbers of all QV and IA personnel for the project, and provide test results to the contractor within 2 business days after the department obtains the sample.

B.8.2 Verification Testing

B.8.2.1 General

- (1) The department will have an HTCP technician, or ACT working under a certified technician, perform QV sampling and testing. Department verification testing personnel must meet the same certification level requirements specified in B.2 for contractor testing personnel for each test result being verified. The department will notify the contractor before sampling so the contractor can observe QV sampling.
- (2) The department will conduct QV tests of each base aggregate size, source or classification, and type during placement conforming to the following:
 1. One non-random test on the first day of placement.
 2. At least one random test per 30,000 tons, or fraction of 30,000 tons, placed.
- (3) The department will sample randomly, at locations independent of the contractor's QC work, collecting one sample at each QV location. The department will collect QV samples after the material has been bladed, mixed, and shaped but before compacting; except, for 3-inch aggregates, the department will collect samples from the stockpile at load-out. The department will split each sample, test half for QV, and retain half.

- (4) The department will conduct QV tests in a separate laboratory and with separate equipment from the contractor's QC tests. The department will use the same methods specified for QC testing.
- (5) The department will assess QV results by comparing to the appropriate specification limits. If QV test results conform to the specification, the department will take no further action. If QV test results are nonconforming, add the QV to the QC test results as if it were an additional QC test.

B.8.3 Independent Assurance

- (1) Independence assurance is unbiased testing the department performs to evaluate the department's QV and the contractor's QC sampling and testing including personnel qualifications, procedures, and equipment. The department will perform an IA review according to the department's independent assurance program. That review may include one or more of the following:
 1. Split sample testing.
 2. Proficiency sample testing.
 3. Witnessing sampling and testing.
 4. Test equipment calibration checks.
 5. Reviewing required worksheets and control charts.
 6. Requesting that testing personnel perform additional sampling and testing.
- (2) If the department identifies a deficiency, and after further investigation confirms it, correct that deficiency. If the contractor does not correct or fails to cooperate in resolving identified deficiencies, the engineer may suspend placement until action is taken. Resolve disputes as specified in B.9.

B.9 Dispute Resolution

- (1) The engineer and contractor should make every effort to avoid conflict. If a dispute between some aspect of the contractor's and the engineer's testing program does occur, seek a solution mutually agreeable to the project personnel. The department and contractor may review the data, examine data reduction and analysis methods, evaluate sampling and testing procedures, and perform additional testing. Use ASTM E 178 to evaluate potential statistically outlying data.
- (2) Production test results, and results from other process control testing, may be considered when resolving a dispute.
- (3) If the project personnel cannot resolve a dispute, and the dispute affects payment or could result in incorporating non-conforming product, the department will use third party testing to resolve the dispute. The department's central office laboratory, or a mutually agreed on independent testing laboratory, will provide this testing. The engineer and contractor will abide by the results of the third party tests. The party in error will pay service charges incurred for testing by an independent laboratory. The department may use third party test results to evaluate the quality of questionable materials and determine the appropriate payment. The department may reject material

or otherwise determine the final disposition of nonconforming material as specified in standard spec 106.5.

C (Vacant)

D (Vacant)

E Payment

- (1) Costs for all sampling, testing, and documentation required under this special provision are incidental to this work. If the contractor fails to perform the work required under this special provision, the department may reduce the contractor's pay. The department will administer pay reduction under the non-performance of QMP administrative item.
- (2) For material represented by a running average exceeding a control limit, the department will reduce pay by 10 percent of the contract price for the affected Base Aggregate bid items listed in subsection A. The department will administer pay reduction under the Nonconforming QMP Base Aggregate Gradation or Nonconforming QMP Base Aggregate Fracture Administrative items. The department will determine the quantity of nonconforming material as specified in B.7.2.

301-010 (20100709)

24. Pier Construction.

Determine the method of construction, and observe the following conditions:

1. If a cofferdam is used, build the cofferdam of non-erodable material.
2. Concrete poured under water will be allowed; pour the concrete according to standard spec 502.3.5.3. Ensure that the forms are tight to prevent leakage of concrete into the stream. Treat all displaced water by filtration, settling basin, or other means sufficient to reduce the cement content before discharging the water into the stream.
3. Excavated material from the stream may be utilized in the fill slopes so long as it is covered with other suitable material to prevent it from eroding back into the stream.

502-010 (20050502)

25. Polymer Overlay, Item 509.5100.S.

A Description

This special provision describes furnishing and applying two layers of a two-component polymer overlay system to the bridge decks shown on the plans. The minimum total thickness of the overlay system shall be 1/4".

B Materials

B.1 General

Furnish materials specifically designed for use over concrete bridge decks. Furnish polymer liquid binders from the department's approved product list.

B.2 Polymer Resin

The polymer resin base and hardener shall be composed of two-component, 100% solids, 100% reactive, thermosetting compound with the following properties:

Property	Requirements	Test Method
Gel Time ^A	15 - 45 minutes @ 73° to 75° F	ASTM C881
Viscosity ^A	7 - 70 poises	ASTM D2393, Brookfield RVT, Spindle No. 3, 20 rpm
Shore D Hardness ^B	60-75	ASTM D2240
Absorption ^B	1% maximum at 24 hr	ASTM D570
Tensile Elongation ^B	30% - 70% @ 7 days	ASTM D638
Tensile Strength ^B	>2000 psi @ 7 days	ASTM D638
Chloride Permeability ^B	<100 coulombs @ 28 days	AASHTO T277

^A Uncured, mixed polymer binder

^B Cured, mixed polymer binder

B.3 Aggregates

Furnish natural or synthetic aggregates that have a proven record of performance in applications of this type. Furnish aggregates that are non-polishing, clean, free of surface moisture, fractured or angular in shape; free from silt, clay, asphalt, or other organic materials; and meet the following properties and gradation requirements:

Aggregate Properties:

Property	Requirement	Test Method
Moisture Content*	½ of the measured aggregate absorption, %	ASTM C566
Hardness	³ 6.5	Mohs Scale
Fractured Faces	100% with at least 1 fractured face & 80% with at least 2 fractured faces of material retained on No.16	ASTM 5821
Absorption	≤1%	ASTM C128

* Sampled and tested at the time of placement.

Gradation:

Sieve Size	% Passing by Weight
No. 4	100
No. 8	30 – 75
No. 16	0 – 5
No. 30	0 – 1

B.4 Required Properties of Overlay System

The required properties of the overlay system are listed in the table below:

Property	Requirement ^A	Test Method
Minimum Compressive Strength at 8 Hrs. (psi)	1,000 psi @ 8 hrs 5,000 psi @ 24 hrs	ASTM C 579 Method B, Modified ^B
Thermal Compatibility	No Delaminations	ASTM C 884
Minimum Pull-off Strength	250 psi @ 24 hrs	ACI 503R, Appendix A

^A Based on samples cured or aged and tested at 75°F

^B Plastic inserts that will provide 2-inch by 2-inch cubes shall be placed in the oversized brass molds.

B.5 Approval of Bridge Deck Polymer Overlay System

A minimum of 20 working days prior to application, submit product data sheets and specifications from the manufacturer, and a certified test report to the engineer for approval. The engineer may request samples of the polymer and/or aggregate, prior to application, for the purpose of acceptance testing by the department.

For materials not pre-qualified, in addition to the above submittals, submit product history/reference projects and a certified test report from an independent testing laboratory showing compliance with the requirements of the specification.

The product history/reference projects consist of a minimum of 5 bridge/roadway locations where the proposed overlay system has been applied in Wisconsin or in locations with a similar climate - include contact names for the facility owner, current phone number or e-mail address, and a brief description of the project.

Product data sheets and specifications from the manufacture consists of literature from the manufacturer showing general instructions, application recommendations/methods, product properties, general instructions, or any other applicable information.

C Construction

C.1 General

Conduct a pre-installation conference with the manufacturer's representative prior to construction to establish procedures for maintaining optimum working conditions and coordination of work. Furnish the engineer a copy of the recommended procedures and apply the overlay system according to the manufacturer's instructions. The manufacturer's representative familiar with the overlay system installation procedures shall be present at all times during surface preparation and overlay placement to provide quality assurance that the work is being performed properly.

Store resin materials in their original containers in a dry area. Store and handle materials according to the manufacturer's recommendations. Store all aggregates in a dry environment and protect aggregates from contaminants on the job site.

C.2 Deck Preparation

C.2.1. Deck Repair

Remove all asphaltic patches and unsound or disintegrated areas of the concrete decks as the plans show, or as the engineer directs. Work performed to repair the concrete deck will be paid for under other items. Ensure that products used for deck patching are compatible with the polymer overlay system.

NOTE: Some polymer systems require concrete patch material to be in place a minimum of 28-days before overlaying - contact polymer manufacturer before completing deck patching/repair.

C.2.2 Surface Preparation

Determine an acceptable shotblasting machine operation (size of shot, flow of shot, forward speed, and/or number of passes) that provides a surface a profile meeting CSP 5 according to the International Concrete Repair Institute Technical Guideline No. 03732. If the engineer requires additional verification of the surface preparation, test the tensile bond strength according to ACI 503R, Appendix A of the *ACI Manual of Concrete Practice*. The surface preparation will be considered acceptable if the tensile bond strength is greater than or equal to 250 psi or the failure area at a depth of ¼ inches or more is greater than 50% of the test area. Continue adjustment of the shotblasting machine and necessary testing until the surface is acceptable to the engineer or a passing test result is obtained.

Prepare the entire deck using the final accepted adjustments to the shotblasting machine as determined above. Thoroughly blast clean with hand-held equipment any areas inaccessible by the shotblasting equipment. Do not perform surface preparation more than 24 hours prior to the application of the overlay system.

Prepare the vertical concrete surfaces adjacent to the deck a minimum of 2" above the overlay according to SSPC-SP 13 by sand blasting, using wire wheels, or other approved method.

Just prior to overlay placement, clean all dust, debris, and concrete fines from the prepared surfaces including the vertical surfaces with compressed air. When using compressed air, the air stream must be free of oil. Any grease, oil, or other foreign matter that rests on or has absorbed into the concrete shall be removed completely. If any prepared surfaces (including the first layer of the polymer overlay) are exposed to rain or dew, lightly sandblast (breeze blast) the exposed surfaces.

Protect drains, expansion joints, access hatches, or other appurtenances on the deck from damage by the shot and sand blasting operations and from materials adhering and entering. Tape or form all construction joints to provide a clean straight edge.

Create a transitional area approaching transverse expansion joints and ends of the deck using the shotblasting machine or other approved method. Remove 5/16" to 3/8" of concrete adjacent to the joint or end of deck and taper a distance of 3 feet.

The engineer may consider alternate surface preparation methods per the overlay system manufacturer's recommendations. The engineer will approve the final surface profile and deck cleanliness prior to the contractor placing the polymer overlay.

C.3 Application of the Overlay

Perform the handling and mixing of the polymer resin and hardening agent in a safe manner to achieve the desired results according to the manufacturer's instructions. Do not apply the overlay system if any of the following exists:

- a. Ambient air temperature is below 50°F;
- b. Deck temperature is below 50°F;
- c. Moisture content in the deck exceeds 4.5% when measured by an electronic moisture meter or shows visible moisture after 2 hours when measured in accordance with ASTM D4263;
- d. Rain is forecasted during the minimum curing periods listed under C.5;
- e. Materials component temperatures below 50°F or above 99°F;
- f. Concrete age is less than 28 days unless approved by the engineer.
- g. The deck temperature exceeds 100°F.
- h. If the gel time is 10 minutes or less at the predicted high air temperature for the day.

After the deck has been shotblasted or during the overlay curing period, only necessary surface preparation and overlay application equipment will be allowed on the deck. Begin overlay placement as soon as possible after surface preparation operations.

The polymer overlay shall consist of a two-course application of polymer and aggregate. Each of the two courses shall consist of a layer of polymer covered with a layer of aggregate in sufficient quantity to completely cover the polymer. Apply the polymer and aggregate according to the manufacturer's requirements. Apply the overlay using equipment designed for this purpose. The application machine shall feature positive displacement volumetric metering and be capable of storing and mixing the polymer resins at the proper mix ratio. Disperse the aggregate using a standard chip spreader or equivalent

machine that can provide a uniform, consistent coverage of aggregate. First course applications that do not receive enough aggregate before the polymer gels shall be removed and replaced. A second course applied with insufficient aggregate may be left in place, but will require additional applications before opening to traffic.

After completion of each course, cure the overlay according to the manufacturer's instructions. Follow the minimum cure times listed under C.5 or as prescribed by the manufacturer. Remove the excess aggregate from the surface treatment by sweeping, blowing, or vacuuming without tearing or damaging the surface; the material may be re-used if approved by the engineer and manufacturer. Apply all courses of the overlay system before opening the area to traffic. Do not allow traffic on the treated area until directed by the engineer.

After the first layer of coating has cured to the point where the aggregate cannot be pulled out, apply the second layer. Prior to applying the second layer, broom and blow off the first layer with compressed air to remove all loose excess aggregate.

Prior to opening to traffic, clean expansion joints and joint seals of all debris and polymer. If required by the engineer, a minimum of 3 days following opening to traffic, remove loosened aggregates from the deck, expansion joints, and approach pavement.

C.4 Application Rates

Apply the polymer overlay in two separate courses in accordance with the manufacturer's instructions, but not less than the following rate of application.

Course	Minimum Polymer Rate A (GAL/100 SF)	Aggregate B (LBS/SY)
1	2.5	10+
2	5.0	14+

^A The minimum total applications rate is 7.5 GAL/100 SF.

^B Application of aggregate shall be of sufficient quantity to completely cover the polymer.

C.5 Minimum Curing Periods

As a minimum, cure the coating as follows:

	Average temperature of deck, polymer and aggregate components in °F							
Course	50-54	55-59	60-64	65-69	70-74	75-79	80-84	85-99
1	6 hrs.	5 hrs.	4 hrs.	3 hrs.	2.5 hrs.	2 hrs.	1.5 hrs.	1 hr.
2	8 hrs.	6.5 hrs.	6.5 hrs.	5 hrs.	4 hrs.	3 hrs.	3 hrs.	3 hrs.

C.6 Repair of Polymer Overlay

Repair all areas of unbonded, uncured, or damaged polymer overlay for no additional compensation. Submit repair procedures from the manufacturer to the engineer for approval. Absent a manufacturer's repair procedures and with the approval of the engineer, complete repairs according to the following: Saw cut the limits of the area to the top of the

Tri-Sheen Concrete Surfacers, Smooth by TK Products
Tri-Sheen Acrylic by TK Products
TK-1450 Natural Look Urethane Anti-Graffiti Primers by TK Products
Safe-Cure & Seal EPX by Chem Masters
H + C Shield Plus by Sherwin-Williams

C Construction

C.1 General

Furnish, prepare, apply, cure, and store all materials in accordance to the product manufacturer's specifications for the type and condition of application required.

Match or exceed the stain manufacturer's minimum recommended curing time of the concrete or 28 days, whichever is greater, prior to staining.

C.2 Preparation of Concrete Surfaces

Provide a sack rubbed finish in accordance to standard spec 502.3.7.5, using mortar as indicated above on concrete surfaces with open voids or honeycombing.

Following the sack rubbing, clean all concrete surfaces that are to be coated to ensure that the surface is free of all laitance, dirt, dust, grease, efflorescence, and any foreign material and that the surface will accept the coating material according to product requirements. As a minimum, clean the surface using a 3000-psi water blast. Hold the nozzle of the water blaster approximately 6 inches from the concrete surface and move it continuously in a sweeping motion. Give special attention to smooth concrete surfaces to produce an acceptable surface texture. Correct any surface problems resulting from the surface preparation methods. Grit blasting of the concrete surface is not allowed.

C.3 Staining Concrete Surfaces

Apply the concrete stain in accordance to the manufacturer's recommendations.

Apply the concrete stain when the temperature of the concrete surface is 45° F or higher, or as given by the manufacturer.

The color of the stain shall be as given on the plan. Tint the base coat to match the finish coat; the two coats shall be compatible with each other.

Do not begin staining the structure until earthwork operations are completed to a point where this work can begin without receiving damage. Where this work is adjacent to exposed soil or pavement areas, provide temporary covering protection from overspray or splatter.

C.4 Test Areas

Prior to applying stain to the structure, apply the stain to sample panels measuring a minimum of 48-inches x 48-inches and constructed to demonstrate workmanship in the use of the form liner specified on the structure if applicable. Match or exceed the stain manufacturer's minimum recommended curing time of the concrete or 28 days, whichever

is greater, prior to staining. Prepare the concrete surfaces of the sample panels and apply stain using the same materials and in the same manner as proposed for the structure, including staining of the joints between the stones produced by the form liner if applicable. Do not apply stain to the structure until the department approves the test panels.

C.5 Surfaces to be Coated.

Apply concrete stain to the surfaces in accordance to the plan.

D Measurement

The department will measure Concrete Staining (Structure) in area by the square foot of surface, acceptably prepared and stained.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
517.1010.S.01	Concrete Staining B-13-0646	SF

Payment is full compensation for furnishing and applying the two coat system; for preparing the concrete surface; and for preparing the sample panels.
517-110 (20100709)

27. Architectural Surface Treatment B-13-0646, Item 517.1050.S.01.

A Description

Construct a concrete masonry architectural surface treatment on the exposed concrete surfaces of the structure, as detailed in the plans and as hereinafter provided.

B Materials

Use form liners that attach easily to the forming system, and do not compress more than 1/4-inch when poured at a rate of 10 vertical feet/hour.

Use a release agent that is compatible with the form liner and coloring materials.

Wall ties shall have set "break-backs" at a minimum of 3/4-inches from the finished concrete surface.

C Construction

C.1 Equipment

Equipment and tools necessary for performing all parts of the work shall be satisfactory as to design, capacity, and mechanical condition for the purposes intended. Repair, improve, replace, or supplement all equipment that is not maintained in full working order, or which is proven inadequate to obtain the results prescribed.

C.2 Form Liner Preparation

Clean the form liner prior to each pour and ensure that it is free of any build-up. Visually inspect each liner for blemishes or tears, and repair if necessary per manufacturer's recommendations.

Apply form release per manufacturer's recommendations.

C.3 Form Liner Attachment

Place adjacent liners less than 1/4-inch from each other, attach liner securely to forms in accordance to the manufacturer's recommendations, and coordinate wall ties with form liner and form manufacturer, e.g., diameter, size, and frequency.

C.4 Surface Finishing

Ensure that the textured surface is free of laitance; sandblasting is not permitted.

Grind or fill pouring blemishes.

D Measurement

The department will measure Architectural Surface Treatment (Structure) in area by the square foot of architectural surface, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
517.1050.S.01	Architectural Surface Treatment B-13-0646	SF

Payment is full compensation for producing the proposed architectural surface treatment including: preparing the foundation; finishing and protecting the surface treatment; and for properly disposing of surplus material.

517-150 (20110615)

28. Traffic Signals.

General Provisions for Traffic Signals

Perform all work on the lighting and conduit/pull box system in accordance to the Wisconsin Electrical Code, and applicable provisions of the standard specifications, and these special provisions and plans. Each pedestrian push button installation shall include "Push Button for Walk Signal" signs. Single direction arrow signing shall also be used with all buttons except single buttons on median poles.

General Provisions for Conduit Installation

Supplement standard spec 652 as follows:

Mark the location of each conduit, where conduit crosses traffic areas, by a permanent chiseled arrow or other appropriate permanent stamp on top of the curb head. Install and connect all conduit to the concrete bases, manholes, handholes, existing conduit, or

conduit elbows so as to provide a continuous network, unless otherwise indicated on the plan. All connections shall be watertight. Do not install drainage holes in conduit. Uncover the ends or mid-sections of all existing conduit that is being extended by or incorporated into this project work.

When connections are to be made to an existing conduit, first verify that the existing conduit is fully clear and useable for its entire cross-section and length. When the existing conduit is found to be defective, notify the engineer and do not proceed until the engineer so directs. If the contractor connects to an existing defective conduit without the express direction from the engineer, the contractor shall make any and all necessary repairs and replacements to all conduits, including conduit that was “existing” prior to the contractor starting work and to the satisfaction of the engineer. All costs of this work shall be at the expense of the contractor.

Turn up conduits terminating in a non-paved location and not in a structure, and end at terrace finish grade with a PVC cap securely attached, per duct termination detail. Where conduit runs parallel to curb and gutter, place the conduit within 12 inches of the back of the curb, except as directed by the engineer. The engineer will determine termination points not within pull boxes or concrete bases.

Unless the contract provides for installation of cable, cap the ends of each run of conduit with standard conduit caps or otherwise appropriately plug the ends to preclude infiltration of water and soil. Install a pull wire in each conduit, except those with only streetlight wire. A pull wire shall be approximately 4 feet longer than the conduit run, and shall be doubled back for at least 2 feet at each terminal. The pull wire shall be #10 AWG copper, stranded, with THHN insulation and green color coding. Install the pull wire within seven days of completing a conduit installation from structure-to-structure.

Use a 6-inch minimum sand padding below the conduit and a 6-inch minimum sand lift above the conduit. Do not backfill trench with any rocks larger than 4 inches in diameter or any foreign debris.

29. Department Maintained Traffic Signals.

All traffic signal work shall be in accordance to the standard specifications, current online version, and these plans and specifications.

Note that failure to comply with the state standards and specifications may result in the cost of the corrections to be made at the contractor’s expense.

30. Temporary Traffic Signals.

Temporary traffic signals will be installed at three intersections outlined below.

USH 14 / CTH P Intersection

This installation shall be operational upon completion of the roadway improvements and removal of the CTH P detour. Coordinate installation of the temporary signal with the

decommissioning of the existing signal to avoid a gap in signal operations. Maintain operation of the signal until March 15, 2015 when the responsibility for the signal is assigned under a separate let contract under construction ID 5310-02-70.

CTH P / Bourbon Road

This installation shall be prepared to be fully operational upon completion of the project. The signage will not be activated until required under construction ID 5310-02-70. Verify the signal is operational on March 15, 2015.

CTH KP / Bourbon Road

This installation shall be prepared to be fully operational upon completion of the project. The signage will not be activated until required under construction ID 5310-02-70. Verify the signal is operational on March 15, 2015.

All temporary traffic signal installations shall upon completion of the contract become the property of the department to be used as traffic control for construction project 5310-02-70 during a later let. Maintain and verify operation of each temporary traffic signal prior to completion of this contract.

31. Seismograph, Item 999.1000.S.

A Description

This special provision describes furnishing a seismograph and employing trained operators to continuously monitor building vibration.

B Material

Use seismographs that are in accordance to ILHR 7.63, and are continuous strip recorders supplied with all the accessories necessary for making seismographic observations.

C Construction

Monitoring procedures shall be in accordance to ILHR 7.64 and the following: Take seismograph readings prior to construction activities to establish an ambient index.

Place the seismograph to continuously monitor all construction activities or as directed by the engineer. If construction activities generate ground vibration in excess of the Peak Particle Velocity Limits as shown in ILHR 7.64, stop the construction operation in progress and consider and implement alternate construction methods.

D Measurement

The department will measure Seismograph as a single complete lump sum unit of work.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
999.1000.S	Seismograph	LS

Payment is full compensation for furnishing and operating a seismograph, an operator, and accessories.
999-005 (20030820)

32. Crack and Damage Survey, Item 999.1500.S.

A Description

This special provision describes conducting a crack and damage survey of the business located at Kwik Trip, 2508 Main Street, Cross Plains, Wisconsin.

This Crack and Damage Survey shall consist of two parts. The first part, performed prior to construction activities, shall include a visual inspection, photographs, and a written report describing the existing defects in the building(s) being inspected. The second part, performed after the construction activities, shall also include a visual inspection, photographs, and written report describing any change in the building's condition.

B (Vacant)

C Construction

Prior to any construction activities, thoroughly inspect the building structures for existing defects, including interior and exterior walls. Submit a written report of the inspector's name, date of inspection, descriptions and locations of defects, and photographs. The intent of the written report and photographs is to procure a record of the general physical condition of the building's interior and exterior walls and foundation. The report shall be typed on bond paper and be in text form.

The photographs shall be taken by a professional photographer capable of producing sharp, grain free, high-contrast colored pictures with good shadow details. The photographs shall be 3½ inch by 5 inch color prints, glossy, and mounted in protective storage pages with clear slip-in pockets and clear background. Each sheet shall hold four prints. The back of each photograph shall contain the following information:

ID _____
Building Location _____
View looking _____
Date _____
Photographer _____

Prior to the start of any construction activities pertinent to this survey, submit a copy of the written report and photographs to the engineer.

After the construction activities are complete, conduct another survey in the same manner, take photographs, and submit another written report to the engineer.

In lieu of photographs, a professional videographer may be hired to use a video camera capable of producing a video with the clarity required to perform this work.

D Measurement

The department will measure Crack and Damage Survey as single complete lump sum unit of work.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
999.1500.S	Crack and Damage Survey	LS

Payment is full compensation for providing the before and after written reports, and for photographs or video.
999-010 (20130615)

33. Removing Traffic Signal Controller Cabinet, Item SPV.0060.01.**A Description**

This special provision describes removing an existing traffic signal controller cabinet, disconnecting all connected cable, equipment and power wires, and disposing of the equipment appropriately.

B Materials

Materials include existing traffic signal controller cabinet and installed equipment.

C Construction

Existing traffic signal controller cabinet shall be removed only after the new traffic signal controller cabinet are installed and approved by the Wisconsin Department of Transportation. Coordinate for removal of the existing cabinet with the Wisconsin Department of Transportation. Coordinate for removal of existing electrical service with the local electric company.

Disconnect all connected cables, equipment and power wires and coordinate with the engineer to deliver them to location determined by the engineer, which will be in Dane County. Dispose of all the remaining materials properly away from the project area.

D Measurement

The department will measure Removing Traffic Signal Controller Cabinet by each individual removed unit, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0060.01	Removing Traffic Signal Controller Cabinet	Each

Payment is full compensation for coordination with MG&E - Electric; for disconnection of wires; for removal and disposal of the pedestal.

34. Temporary Opticom Signal Preempt, SPV.0060.02.

A Description

This work shall consist of furnishing and installing Opticom brand optical signal preempt equipment for the signalized intersection.

B Materials

Furnish the following:

1. Model 454 discriminator for one signal intersection, one total.
2. Model 711 detectors, four total.
3. Model 760 card rack for each intersection, one total.
4. Model 138 detector cable as necessary.
5. Cables and auxiliary equipment as necessary for a complete operating system.

C Construction

Temporary Opticom Signal Preemption detectors shall be installed on the temporary overhead signal wire, as shown on the plans and approved by the engineer.

Temporary Opticom Signal Preemption detectors shall be installed on the temporary overhead signal wire, as shown on the plans and approved by the engineer. The temporary Opticom Signal Preemption detectors will be on the far side of the intersection, and shall be aimed at approaching traffic, as further directed by the engineer. Detector cable shall be installed from the detector to the control cabinet at each intersection, using the shortest path. All installation methods shall be consistent with the manufacturer's instructions. Card rack and discriminator installation, as well as cabinet connections, will be made by contractor and approved by the engineer.

D Measurement

The department will measure Opticom Signal Preempt by each individual installation, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0060.02	Opticom Signal Preemption	Each

Payment is full compensation for furnishing, delivering and installing detectors and cable, discriminators, card racks, cables and miscellaneous materials.

35. Removing Electrical Service Meter Breaker Pedestal, Item SPV.0060.03.

A Description

This special provision describes removing an existing electrical service meter breaker pedestal, disconnecting all connected power wires, and disposing of the equipment appropriately.

B Materials

Existing electrical service meter breaker pedestal.

C Construction

Coordinate for removal of the existing electrical service meter breaker pedestal with the local electric company.

Disconnect all connected power wires, remove the pedestal and dispose of all materials properly away from the project area.

D Measurement

The department will measure Removing Electrical Service Meter Breaker Pedestal by each individual unit, acceptably removed.

E Payment

The department will pay for measured quantities at the contract unit price under the following item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0060.03	Removing Electrical Service Meter Breaker Pedestal	Each

Payment is full compensation for coordination with MG&E - Electric; for disconnection of wires; for removal and disposal of the pedestal.

36. Permanent Traffic Control Drum, Item SPV.0060.04.**A Description**

This special provision describes furnishing and installing permanent traffic control drums.

B Materials

Furnish traffic control drums that conform to the pertinent requirements of standard spec 643.2.3. All drums are to be new and not to have been used for any purpose before this project.

C Construction

Place the permanent traffic control drums at the locations called out in the plans. Maintenance of the traffic control drums is required after the interim completion date. Inspect drum placement weekly and relocate drums that have been displaced by weather, traffic, or snow plowing operations. Inspect drum placement after weather events in which a snowfall of 3 or more inches occurs in a 24 hour period.

D Measurement

The department will measure Permanent Traffic Control Drum as each individual unit, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0060.04	Permanent Traffic Control Drum	Each

Payment is full compensation for furnishing and installing the unit; for inspection and realignment of drum placement.

37. Signs Flashing LED, Stop, Item SPV.0060.05.

A Description

This special provision describes furnishing and installing permanent solar powered flashing LED stop signs.

B Materials

Furnish signs that conform to the pertinent requirements of standard spec 637. Provide installations that meet the following:

Sign	R1-1
Size	30" x 30"
Sign substrate	Per standard spec 637.2.1.3
Battery	Nickel metal hydride, 14,000 mAh
Flash pattern	MUTCD compliant
LED type	High power – 1 watt, white color
LED life expectancy	100,000 hours

C Construction

Place the signs at the locations called out in the plans. Install signs according to manufacturer's specifications and according to the standard specifications.

D Measurement

The department will measure Signs Flashing LED Stop as each individual unit, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0060.05	Signs Flashing LED Stop	Each

Payment is full compensation for furnishing and installing the unit; and for aligning solar array.

38. Signs Flashing LED, Vehicle Entrance, Item SPV.0060.06.

A Description

This special provision describes furnishing and installing permanent solar powered flashing LED vehicle entrance signs.

B Materials

Furnish signs that conform to the pertinent requirements of standard spec 637. Provide installations that meet the following:

Sign	W11-8
Size	30" x 30"
Sign substrate	Per standard spec 637.2.1.3
Battery	Nickel metal hydride
Flash pattern	MUTCD compliant
LED type	High power – 1 watt, white color
LED life expectancy	100,000 hours
Activation	Key fob or remote switch

C Construction

Place the signs at the locations called out in the plans. Install signs according to manufacturer's specifications and according to the standard specification.

D Measurement

The department will measure Signs Flashing LED, Vehicle Entrance as each individual unit, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0060.06	Signs Flashing LED, Vehicle Entrance	Each

Payment is full compensation for furnishing and installing the unit; and for aligning solar array.

39. Removing Traffic Signals CTH P and USH 14 Intersection, Item SPV.0105.01.

A Description

This special provision describes removing selected existing traffic signals at the intersection of CTH P with USH 14

B (Vacant)**C Construction**

Arrange for the removal of the traffic signal equipment after receiving approval from the engineer that the existing equipment can be removed.

The contractor shall remove existing traffic signals, including street lights that have traffic signal equipment on them, as indicated of the plans. Remove and properly dispose of all cables and wires. Remove conduit, as shown on the plans, or abandon in place. Conduit

may be abandoned in place only if it does not interfere with new construction or present a risk of damage to newly constructed items.

D Measurement

The department will measure Removing Traffic Signals CTH P and USH 14 Intersection as a single lump sum unit of work for the intersection, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0105.01	Removing Traffic Signals CTH P and USH 14 Intersection	LS

Payment is full compensation for removing and disassembling, scrapping of some materials; storing salvaged items on site; disposing of scrap material.

40. Temporary Vehicle Detection USH 14 and CTH P, Item SPV.0105.02; Temporary Vehicle Detection CTH P and Bourbon Road, Item SPV.0105.03; Temporary Vehicle Detection CTH KP and Bourbon Road, Item SPV.0105.04.

A General

Work under this item shall consist of furnishing, installing, and maintaining vehicle detection systems at the intersection of USH 14 and CTH P in conjunction with temporary traffic signals, as shown in the Plans.

The vehicle detection zones will vary according to each stage and will be defined by the engineer. The contractor, with prior approval of the engineer, shall select the vehicle detection technology best suited for the site conditions and the anticipated construction work zones and activities. That vehicle detection technology will not include any intrusive loops or any underground installation. The engineer reserves the right to request a demonstration of any or all temporary vehicle detection technologies prior to said approval. Vehicle detection technologies considered shall include but are not limited to microwave detection or video detection. Damage to new pavement or existing pavement that will remain after the project is complete for temporary detection loops will not be allowed.

The temporary vehicle detection system shall be considered part of the temporary traffic signals and is subject to the same maintenance and repair requirements as described in the Temporary Traffic Signal bid item.

B Materials

Provide all necessary equipment for the approved method of temporary vehicle detection.

C (Vacant)

D Measurement

The department will measure Temporary Vehicle Detection (Intersection) as a single lump sum unit of work per intersection, complete in place and accepted.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0105.02	Temporary Vehicle Detection USH 14 and CTH P	LS
SPV.0105.03	Temporary Vehicle Detection CTH P and Bourbon Road	LS
SPV.0105.04	Temporary Vehicle Detection CTH KP and Bourbon Road	LS

Payment is full compensation for demonstrating and selecting the vehicle detector technology, furnishing and installing the equipment, including all required materials, tools, and supplies.

41. Temporary Crosswalk Access (CTH P and USH 14), Item SPV.0105.05.**A Description**

This work shall consist of furnishing, installing and maintaining temporary access for pedestrian crossings and access of the project area.

B (Vacant)**C Construction**

Construct Temporary Crosswalk Access at intersections noted below to meet requirements of the Americans with Disabilities Act Accessibility Guidelines (ADAAG) consisting of temporary asphaltic surface, any grade of concrete, skid resistant steel plating, or alternative material as approved by the engineer. Gravel or base course material is not acceptable. Maintain ADAAG accessible crosswalk accesses that are free from mud, sand, and construction debris.

D Measurement

The department will measure Temporary Crosswalk Access (Location), completed in accordance to the contract and accepted, as a single complete lump sum unit of work, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid items:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0105.05	Temporary Crosswalk Access (CTH P and USH 14)	LS

Payment is full compensation for furnishing, installing, maintaining and removing temporary access materials required for maintain crosswalk access.

42. Concrete Pavement Joint Layout, Item SPV.0105.06.

A Description

Provide a concrete pavement joint layout design for intersections and mark the location of all joints in the field.

B (Vacant)

C Construction

Plan and locate all points necessary to establish the horizontal position of the transverse and longitudinal joints in the concrete pavement to prevent uncontrolled cracking. Submit a joint layout design to the engineer before paving each intersection. Mark the location of all concrete pavement joints in the field. Follow the plan details for joints in concrete pavements making adjustments as required to fit field conditions.

D Measurement

The department will measure Concrete Pavement Joint Layout as a single lump sum unit of work for all joint layout designs and marking, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0105.06	Concrete Pavement Joint Layout	LS

Payment is full compensation for providing the intersection joint layout designs and marking all joints in the field. The department will adjust pay for crack repairs as specified in standard spec 415.5.3.

43. Geogrid Reinforcement, Item SPV.0180.01.

A Description

This special provision describes furnishing and installing geogrids for subgrade stabilization, base reinforcement, or pavement structure applications in accordance to the plans, the standard specifications, and as hereinafter provided.

B Materials

Provide geogrid that consists of either single or joined multiple layers of a uniform rectangular grid of bonded, formed, or fused polymer tensile strands crossing with a nominal right angle orientation. The polymer shall consist of polyester, polypropylene, polyamide, or polyethylene. The grid shall maintain dimensional stability during handling, placing, and installation. The geogrid shall be insect, rodent, mildew, and rot resistant. Minimum geogrid width shall be 6.0 feet.

Provide geogrid that complies with the following physical properties:

Test	Method	Value ⁽¹⁾
Tensile Strength at 5% Strain, Both Principal Directions (lb/ft)	ASTM D 4595 ⁽²⁾	450 min.
Flexural Rigidity Both Principal Directions (mg-cm)	ASTM D 1388 ⁽³⁾	150,000 min.
Aperture Area (in ²)	Inside Measurement ⁽⁴⁾	5.0 max.
Aperture Dimension (in)	Inside Measurement ⁽⁴⁾	0.5 min.

⁽¹⁾ All numerical values represent minimum/maximum average roll values, i.e. the average minimum test results on any roll in a lot should meet or exceed the minimum specified value.

⁽²⁾ The tensile strength (T) of a joined multi-layered geogrid shall be computed using the following equation:

$$T = n(f)t$$

where

n = the number of individual layers in the joined multi-layered geogrid,

t = the tensile strength of a single layer of geogrid as determined using testing method ASTM D4595, and

f = reduction factor based on the number of layers comprising the multi-layered system and determined by the equation $f = 1.00 - [0.04(n - 1)]$.

⁽³⁾ Values shall be determined by Option “A” (Cantilever Test) of testing method ASTM D1388 using test specimens that are 36 inches \pm 0.04 inch long. Test specimen widths for differing geogrids shall be variable and equal to 1 element plus $\frac{1}{2}$ the aperture width on both sides of that element. An element is defined as the minimum number of parallel strands which form a distinguishable repeating pattern.

⁽⁴⁾ Aperture Area and Aperture Dimension for joined multi-layer geogrids shall be determined based on measurement of a single layer of the geogrid.

Protect the geogrid from ultraviolet radiation and from damage due to shipping and handling. Keep the geogrid dry until it is installed. The geogrid rolls shall be clearly marked to identify the material contained.

Deliver a sample of the geogrid material to the engineer at least 10 days prior to its incorporation into the work. At the same time, furnish a manufacturer's Certified Report of Test or Analysis that verifies that the geogrid delivered for use on the work meets the above requirements. Samples of geogrid for test purposes will be obtained from the job site for each 10,000 square yards or portions thereof used on the contract.

C Construction

Prior to placement of the geogrid, bring the indicated placement surface to the required lines, grades, and dimensions as shown on the plans. Smooth and shape the surface to eliminate any rocks, clods, roots, or other items that may cause damage to the geogrid during placement or covering.

Place the geogrid on the prepared surface at the locations and to the limits as shown on the plans. After placement, pull the geogrid taut and secure it using pins, clips, staples, or other devices to prevent movement or displacement. Place parallel strips of geogrid with a minimum overlap of 6 inches. Lap butt joints between roll ends a minimum of 12 inches. Fasten all lapped sections together by using ties, straps, clips, or other devices to develop a secure joint that meets the approval of the engineer. No vehicles or construction equipment shall be permitted to operate directly on the geogrid.

Cover small rips, tears, or defects in the geogrid with an additional section of geogrid; secure the additional geogrid in place so that it overlaps the damaged area by at least 3 feet in all directions. Remove and replace geogrid sections with large rips, tears, defects, or other damage at the direction of the engineer. All costs to repair or replace damaged or defective geogrid shall be the responsibility of the contractor.

After placement, cover the geogrid to the indicated depth with the type of material required on the plans or in the special provisions. Placing, spreading, and compacting of this material shall comply with the applicable sections of the standard specifications or special provisions except that the initial lift of material placed on the geogrid must be at least 4 inches. Placing, spreading, and compaction operations shall be conducted so that at least 4 inches of material is placed over the geogrid. Placing, spreading, and compaction operations shall be conducted so that the geogrid is not displaced or damaged. The engineer may require changes in equipment and/or operations to prevent such damage or displacement.

D Measurement

The department will measure Geogrid Reinforcement by the square yard of surface area upon which the geogrid has been placed, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM	DESCRIPTION	UNIT
SPV.0180.01	Geogrid Reinforcement	SY

Payment is full compensation for furnishing, transporting, and installing the geogrid; furnishing and installing all devices and materials necessary to join or secure the geogrid in place.

**ADDITIONAL SPECIAL PROVISION 1 (ASP 1)
FOR TRANSPORTATION ALLIANCE FOR NEW SOLUTIONS (TrANS)
PROGRAM EMPLOYMENT PLACEMENTS AND APPRENTICESHIPS**

The Safe, Accountable, Flexible, Efficient Transportation Equity Act: A Legacy for Users (SAFETEA-LU), Section 5204(e) – Surface Transportation Workforce Development Training and Education, provides for 100 percent Federal funding if the core program funds are used for training, education, or workforce development purposes, including “pipeline” activities. The core programs includes: Congestion Mitigation and Air Quality Improvement (CMAQ) Program, Highway Bridge Program (HBP), Interstate Maintenance (IM), National Highway System (NHS), and Surface Transportation Program (STP). These workforce development activities cover surface transportation workers, including OJT/SS programs for women and minorities as authorized in 23 U.S.C. §140(b).

TrANS is an employment program originally established in 1995 in Southeastern Wisconsin. Currently TrANS has expanded to include TrANS program locations to serve contractors in Southeast (Milwaukee and surrounding counties), Southcentral (Dane County and surrounding counties including Rock County), and most Northeastern Wisconsin counties from locations in Keshena, Rhinelander and surrounding far Northern areas. TrANS attempts to meet contractor’s needs in other geographic locations as possible. It is an industry driven plan of services to address the outreach, preparation, placement and retention of women, minorities and non-minorities as laborers and apprentices in the highway skilled trades. These candidate preparation and contractor coordination services are provided by community based organizations. For a list of the TrANS Coordinators contact the Disadvantaged Business Enterprise Office at (414) 438-4583 in Milwaukee or (608) 266-6961 in Madison. These services are provided to you at no cost.

I. BASIC CONCEPTS

Training reimbursements to employing contractors for new placements, rehires or promotions to apprentice of TrANS Program graduates will be made as follows:

- 1) **On-the-Job Training, Item ASP.1T0G, ASP 1 Graduate.** At the rate of \$5.00 per hour on federal aid projects when TrANS graduates are initially hired, or seasonally rehired, as unskilled laborers or the equivalent.

Eligibility and Duration: To the employing contractor, for up to 2000 hours from the point of initial hire as a TrANS program placement.

Contract Goal: To maintain the intent of the Equal Employment Opportunity program, it is a goal that 1 (number) TrANS Graduate(s) be utilized on this contract.

- 2) **On-the-Job Training, Item ASP.1T0A, ASP 1 Apprentice.** At the rate of \$5.00 per hour on federal aid projects at the point when an employee who came out of the TrANS Program is subsequently entered into an apprenticeship contract in an underutilized skilled trade (this will include the Skilled Laborer Apprenticeship when that standard is implemented).

Eligibility and Duration: To the employing contractor, for the length of time the TrANS graduate is in apprentice status.

Contract Goal: To maintain the intent of the Equal Employment Opportunity program, it is a goal that 1 (number) TrANS Apprentice(s) be utilized on this contract.

- 3) The maximum duration of reimbursement is two years as a TrANS graduate plus time in apprentice status.
- 4) If a TrANS program is not available in the contractor's area and another training program is utilized, payment of On-the-Job Training hours may be approved by the Wisconsin Department of Transportation (WisDOT) if the training program meets the established acceptance criteria. Only On-the-Job Training Hours accumulated after WisDOT approval will be reimbursed as specified under Items ASP.1T0G and ASP.1T0A. For more information, contact the Disadvantaged Business Enterprise Office at the phone numbers listed above.
- 5) WisDOT reserves the right to deny payments under items ASP.1T0G and ASP.1T0A if the contractor either fails to provide training or there is evidence of a lack of good faith in meeting the requirements of this training special provision.

I. RATIONALE AND SPECIAL NOTE

The \$5.00 per hour now being paid for TrANS placements is intended to cover the duration of two years to allow for reaching entry-level laborer status. An additional incentive, the \$5.00 rate, would promote movement into the underutilized skilled trades' apprenticeships and applies until the individual completes their apprenticeship. These incentives benefit TrANS candidates by giving them a better opportunity to enter a skilled trade; benefits contractors who will be assisted in meeting their EEO profiles and goals; and benefits the public who will see the program reinforce larger public-private employment reform in Wisconsin. The pool of TrANS graduates was created for the purpose of addressing underutilization in the skilled trades, an objective that is further reinforced by a parallel retention pilot program, known as the Companywide Reporting. *Whether or not reimbursement is involved, the WisDOT reassures contractors who are in the Companywide Program that TrANS placements still contribute toward fulfilling the new hire goal of 50% women and minorities.* Based on data administered by United States Department of Labor (US DOL), the highway skilled trades remain underutilized for women statewide (less than 6.9%); and for minorities in all counties (% varies by county).

NOTE: *Unless using other advancement strategies, contractors are encouraged to use some or all of this monetary incentive to offset the cut in hourly wages an individual may incur when entering an apprenticeship if the full general laborer hourly rate has been previously paid. No special accounting measures are required.*

II. IMPLEMENTATION

The implementation of ASP 1 is intended to cover only the amount of time it takes for underutilization to be resolved across the trades. This will be measured annually at the county and/or state levels using data administered by WisDWD in relation to goals set by the USDOL-

OFCCP. With appropriate state and federal approvals, we may also do some measurement at the company level.

It is the contractor's responsibility to note on their Certified Payrolls if their employee is a TrANS graduate or a TrANS apprentice. The District EEO Coordinators utilize the information on the Certified Payrolls to track the hours accumulated by TrANS Graduates and TrANS apprentices on WisDOT contracts. Payment under this ASP 1 is made based on the hours recorded off of the Certified Payrolls. Tracking may eventually include improved linkages with the WisDWD apprentice database, information from company and committee level sources.

TrANS is nondiscriminatory by regulation, and is a tool for optional use by contractors to address the underutilization of women and minorities as laborers and apprentices in our industry's skilled trades.

IV. TRANS TRAINING

As part of the contractor's equal employment opportunity affirmative action program, training shall be provided to employees enrolled in apprenticeship and on-the-job training programs as follows:

The contractor shall provide on-the-job training aimed at developing full journey workers in the type of trade or job classifications involved. In the event the contractor subcontracts a portion of the contract work, the contractor shall determine how many, if any, of the trainees are to be trained by the subcontractor provided, however, that the contractor shall retain the primary responsibility for meeting the training requirements imposed by this special provision. The contractor shall also insure that this training special provision is made applicable to such subcontract.

Training and upgrading of minorities and women toward journey workers status is a primary objective of this training special provision. Accordingly, the contractor shall make every effort to enroll minority trainees and women (e.g., by conducting systematic and direct recruitment through public and private sources likely to yield minority trainees and women trainees); to the extent such persons are available within a reasonable area of recruitment. The contractor will be given an opportunity and will be responsible for demonstrating the steps that they have taken in pursuance thereof, prior to determination as to whether the contractor is in compliance with this training special provision. This training commitment is not intended, and shall not be used, to discriminate against any applicant for training, whether a member of a minority group or not.

No employee shall be employed as a trainee in any classification in which they have successfully completed a training course leading to journey workers status or in which they have been employed as a journey worker. The contractor should satisfy this requirement by including appropriate questions in the employee application or by other suitable means. Regardless of the method used, the contractor's records should document the findings in each case.

V. APPRENTICESHIP TRAINING

The Federal Highway Administration's (FHWA) policy is to require full use of all available training and skill improvement opportunities to assure increased participation of minority groups, disadvantaged persons and women in all phases of the highway construction industry. The FHWA On-the-Job Training (OJT) Program requires the State transportation agencies (STAs) to establish apprenticeships and training programs targeted to move women, minorities, and disadvantaged individuals into journey-level positions to ensure that a competent workforce is available to meet highway construction hiring needs, and to address the historical underrepresentation of members of these groups in highway construction skilled crafts.

The OJT Supportive Services (OJT/SS) Program was established in Title 23 Code of Federal Regulations (CFR), Part 230) to supplement the OJT program and support STA training programs by providing services to highway construction contractors and assistance to highway construction apprentices and trainees. The primary objectives of OJT/SS are:

- (1) To increase the overall effectiveness of the State highway agencies' approved training programs.
- (2) To seek other ways to increase the training opportunities for women, minorities, and disadvantaged individuals.

The STAs are responsible for establishing procedures, subject to the availability of Surface Transportation and Bridge Funds under 23 U.S.C. §140(b) (Nondiscrimination), for the provision of supportive services with respect to training programs approved under 23 CFR, Part 230(a) (Equal Employment Opportunity on Federal and Federal-aid Construction Contracts – including Supportive Services).

The contractor and subcontractor shall maintain records to demonstrate compliance with these apprenticeship requirements. Reasonable exemptions and modifications to and from any or all of these requirements will be determined by the Wisconsin Department of Transportation-Civil Rights Office. A request for an exemption or modification, with justification, shall be made in writing, addressed to WisDOT Civil Rights Office, 4802 Sheboygan Avenue, P.O. Box 7965, Rm. 451, Madison, WI 53707.

ADDITIONAL SPECIAL PROVISION 3 DISADVANTAGED BUSINESS ENTERPRISE PROGRAM

1. Description

General

- a. The disadvantaged business enterprise (DBE) requirements of 49 CFR Part 26 apply to this contract. The department's DBE goal is shown on the cover of the bidding proposal. The contractor can meet the specified contract DBE goal by procuring services or materials from a DBE or by subcontracting work to a DBE. The department calculates the DBE participation as the dollar value of DBE participation included in the bid expressed as a percentage of the total contract bid amount.
- b. Under the contract, the contractor agrees to provide the assistance to participating DBE's in the following areas:
 - i. Produce accurate and complete quotes.
 - ii. Understand highway plans applicable to their work.
 - iii. Understand specifications and contract requirements applicable to their work.
 - iv. Understand contracting reporting requirements.
- c. The department encourages the contractor to assist and develop DBE firms to become fully knowledgeable contractors to successfully perform on its contracts.
- d. For information on the disadvantaged business program, visit the department's Civil Rights and Compliance Section website at:

<http://www.dot.wisconsin.gov/business/engrserv/dbe-main.htm>

2. Definitions

- a. Interpret these terms, used throughout this additional special provision, as follows:
 - i. **Bid Percentage:** The DBE percentage indicated in the bidding proposal at the time of bid.
 - ii. **DBE:** A disadvantaged business enterprise (DBE) certified as a DBE by the department and included on the department's list of certified DBE's who are determined to be ready, willing and able.
 - iii. **DBE goal:** The amount of DBE participation expected in the contract as shown on the cover of the Highway Work Proposal.
 - iv. **Discretionary Goal:** A contractor assigned DBE goal, typically abbreviated as "Disc" on the cover of the Highway Work Proposal, which is enforced as committed.
 - v. **Manufacturer:** A firm that operates or maintains a factory or establishment that produces, on the premises, the materials, supplies, articles, or equipment required under the contract.
 - vi. **Supplier:** A firm that owns, operates, or maintains a store, warehouse, or other establishment in which the materials, supplies, articles or equipment required under the contract are bought, kept in stock, and regularly sold or leased to the public.
 - vii. **Voluntary Achievement:** The amount of DBE participation achieved and reported in the contract in excess of the assigned goal.

3. DBE Percentage Required at Bid Submission

Indicate the bid percentage (i.e. 0% through 100%) of DBE participation on the completed bidding proposal, including projects with discretionary goals. For electronic submittals, show the percentage in the miscellaneous data folder, Item 3, DBE Percent. For paper submittals, show the percentage on the sheet included after the schedule of items. By submission of the bid, the bidder contractually commits to DBE participation at or above the bid percentage, or certifies that they have utilized

comprehensive good faith efforts to solicit and utilize DBE firms to meet the DBE participation requirements of this contract proposal, and that the bid percentage is reflective of these good faith efforts. If the bidder does not indicate the bid percentage of DBE participation on the completed bidding proposal, the department will consider the bid irregular and may reject the bid.

4. Department's DBE Evaluation Process

a. Documentation Submittal

Within 10 business days after the notification of contract award, the contractor is to identify, by name, the DBE firms whose utilization is intended to satisfy this provision, the items of work of the DBE subcontract or supply agreement and the dollar value of those items of work by completing the Commitment to Subcontract to DBE Form [DT1506] and all necessary attachment A forms, as well as, Good Faith Waiver Form [DT1202] and supporting documentation as necessary. If the contractor fails to furnish the required forms within the specified time, the department may cancel the award. Delay in fulfilling this requirement is not a cause for extension of the contract time and shall not be used as a tool to delay execution.

i. Bidder Meets DBE Goal

If the bidder indicates that the contract DBE goal is met, after award and before execution, the department will evaluate the Commitment to Subcontract to DBE Form DT1506 and attachment A(s) to verify the actual DBE percentage achieved. If the DBE commitment is verified, the contract is eligible for execution with respect to the DBE commitment.

ii. Bidder Does Not Meet DBE Goal

- (1) If the bidder indicates a bid percentage on the Commitment to Subcontract to DBE Form [DT1506] that does not meet the contract DBE goal, the bidder must submit a Good Faith Waiver Form [DT1202] and supporting documentation. After award and before execution, the department will evaluate the bidder's DBE commitment and consider the bidder's good faith waiver request.
- (2) The department will review the bidder's good faith waiver request and notify the bidder of one of the following:
 - a. If the department grants a good faith waiver, the bid is eligible for contract execution with respect to DBE commitment.
 - b. If the department rejects the good faith waiver request, the department may declare the bid ineligible for execution. The department will provide a written explanation of why the good faith waiver request was rejected. The bidder may appeal the department's rejection as allowed under 7 a. & b.

5. Department's Criteria for Good Faith Effort

The Code of Federal Regulations {CFR}, 49 CFR Part 26-Appendix A, is the guiding regulation concerning good faith efforts. However, the federal regulations do not define "good faith" but states that bidder must actively and aggressively attempt to meet the goal. The federal regulations are general and do not include every factor or effort that can be considered. As a result, each state must establish its own processes and consider the factors established in its own process when making a determination of good faith.

- a. The department will only grant a good faith waiver if the bidder has made the effort, given the relevant circumstances under the contract that a bidder actively and aggressively seeking to meet the goal would make. The department will evaluate the bidder's good faith effort to determine whether a good faith waiver will be granted. The bidder must demonstrate, on the DT1202 that they have aggressively solicited DBE participation in an attempt to meet the contract DBE goal and attaining the stated DBE goal is not feasible.

- b. The department, in conjunction with industry stakeholders, has developed the following guidance for contractor good faith effort. The guidance and the attached appendices provide a framework for the actions required by all parties in the processing and evaluation of bidder's total efforts to achieve the project specific DBE goal prior to the bid letting date.
- c. Prime Contractors should:
 - i. Document all efforts and decisions made toward achieving the DBE goal on the contract. The bidder should use the Civil Rights & Compliance System [CRCS] and related WisDOT-approved DBE outreach tools, including the Bid Express Small Business Network, to foster DBE participation on all applicable contracts.
 - ii. Request quotes by identifying potential items to subcontract and solicit. Prime contractors are strongly encouraged to include in their initial contacts a single page including a detailed list of items for which they are accepting quotes, by project, within a letting. *See attached sample entitled "Sample Contractor Solicitation Letter" in Appendix A.* Prime contractors should also indicate a willingness to accept quotes in areas they are planning to perform themselves, **as required by federal rules**. In some cases, it might be appropriate to use DBE's to do work in a prime contractor's area of specialization.
 - (1) Solicit quotes through all reasonable and available means from certified DBE firms who match 'possible items to subcontract' and send copies to DBESS office, highlighting areas in which you are seeking quotes. Email is acceptable.
 - (2) SBN is the preferred outreach tool. <https://www.bidx.com/wi/main>. Other acceptable means include postal mail, email, fax, phone call.
 - a. Primes must ask DBE firms for a response in their solicitations. See *Sample Contractors Solicitation Letter* in Appendix. This letter can be included as an attachment to the SBN sub-quote request.
 - b. Solicit quotes at least 10 calendar days prior to the letting date {ideally two Fridays before the letting} to allow DBE firms sufficient time to respond. Prime contractors should contact DBE firms early, asking them if they need help in putting together a quote, or helping to arrange for equipment needs, or solve other problems.
 - (3) Second solicitation should take place within 5 days
 - a. An email solicitation is highly recommended for this second solicitation
 - (4) Upon request, provide interested DBE firms with adequate information about plans, specifications and the requirements of the contract by letter, information session, email, phone call and/or referral.
 - (5) When potential exists, advise interested DBE firms on how to obtain bonding, line of credit or insurance as may be requested.
 - (6) Document DBE firm's interest in quoting by taking appropriate steps to follow up initial solicitation with:
 - a. Email to all prospective DBE firms in relevant work areas
 - b. Phone call log to DBE firms who express interest via written response or call.
 - c. Fax/letter confirmation
 - d. Copy of the DBE quotes
 - e. Signed copy of Bid Express SBN Record of Subcontractor Outreach Effort.
- d. Evaluate DBE quotes as documentation is critical if the prime does not utilize the DBE firm's quote for any reason.
 - i. Evaluate DBE firm's capability to perform 'possible items to subcontract' using legitimate reasons, including but not limited to, **a discussion with the DBE firm** regarding its

- capabilities prior to the bid letting. If lack of capacity is your reason for not utilizing the DBE quote, you are required to contact the DBE directly regarding their ability to perform the work indicated in the UCP directory as their work area [NAICS code]; only the work area and/or NAICS code listed in the UCP directory will be counted for DBE credit. Documentation of the conversation is required.
- ii. In striving to meet a DBE conscious contract goal, prime contractors are expected to use DBE quotes that are responsive and reasonable. This includes DBE quotes that are not the low quote.
 - iii. **Special Circumstance:** Evaluation of DBE quotes with tied bid items. "Tied quotes are the condition in which a subcontractor submits quotes including multiple areas of expertise across multiple work areas noting that the items and price are tied. Typically this type of quoting represents a cost saving to the prime but is not clearly stated as a discount; tied quotes are usually presented as 'all or none' quote to the prime." When non-DBE subcontractors submit tied bid items in their quotes to the prime, the DBE firms' quote may seem not competitive. In such a case, the following steps are taken in comparing the relevant quotes. These are qualitative examples.
 - (1) Compare bid items common to both quotes, noting the reasonableness in the price comparison.
 - (2) Review quotes from other firms for the bid items not quoted by the DBE firm to see if combining both can provide the same competitive advantage that the tied bid items offered.
- e. After notification of contract award, submit '**Commitment to Subcontract**' form within the time period specified in the contract.
 - i. Provide the following information along with department form DT1202:
 - (1) The names, addresses, e-mail addresses, telephone numbers of DBE's contacted. The dates of both initial and follow-up contact. A printed copy of SBN solicitation is acceptable.
 - (2) A description of information provided to the DBE's regarding the plans, specifications, and estimated quantities for portions of the work to be performed by that DBE.
 - (3) Photocopies or electronic copies of all written solicitations to DBE's.
 - (4) Documentation of each quote received from a DBE and, if rejected, the reason for that rejection.
 - (5) Bidder attendance at any pre-solicitation or pre-bid meetings the department held to inform DBE's of participation opportunities available on the project.
 - f. The department's DBE Support Services Office is available by phone, email or in writing to request assistance in meeting the DBE goal:

DBE Support Services Office
6150 Fond du Lac Ave.
Milwaukee, WI 53218
Phone: 414-438-4583 / 608-266-6961
Fax: 414-438-5392
E-mail: DOTDBESupportServices@dot.wi.gov

6. Bidder's Appeal Process

- a. A bidder can appeal the department's decision to deny the bidder's good faith waiver request. The bidder must provide written documentation refuting the specific reasons for rejection as stated in the department's rejection notice. The bidder may meet in person with the department if so

requested. Failure to appeal within 7 calendar days after receiving the department's written notice of rejection of a good faith waiver request under constitutes a forfeiture of the bidder's right of appeal. If the bidder does not appeal, the department may declare the bid ineligible for execution.

- b. The department will appoint a representative, who did not participate in the original determination, to assess the bidder's appeal. The department will issue a written decision within 7 calendar days after the bidder presents all written and oral testimony. In that written decision, the department will explain the basis for finding that the bidder did or did not meet the contract DBE goal or make an adequate good faith effort to meet the contract DBE goal. The department's decision is final. If the department finds that the bidder did not meet the contract DBE goal or did not make adequate efforts to meet the DBE goal, the department may declare the bid ineligible for execution.

7. Department's Criteria for DBE Participation

Department's DBE List

- a. The department maintains a DBE list on the department's website at <http://app.mylcm.com/wisdot/Reports/WisDotUCPDirectory.aspx>
- b. The DBE office is also available to assist at 414-438-4583 or 608-266-6961.

8. Counting DBE Participation

Assessing DBE Work

- a. The department will only count the DBE usage towards the contract DBE goal if the DBE firm is certified as a DBE by one of the unified certification program agencies. If a firm becomes DBE certified before entering into a subcontract, the department may consider that DBE usage towards the contract goal. The department only counts the value of the work a DBE actually performs towards the DBE goal. The department assesses the DBE work as follows:
- b. The department counts work performed by the DBE's own resources. The department includes the cost of materials and supplies the DBE obtains for the work. The department also includes the cost of equipment the DBE leases for the work. The department will not include the cost of materials, supplies, or equipment the DBE purchases or leases from the prime contractor or its affiliate, except the department will count non-project specific leases the DBE has in place before the work is advertised.
- c. The department counts fees and commissions the DBE charges for providing a bona fide professional, technical, consultant, or managerial services. The department also counts fees and commissions the DBE charges for providing bonds or insurance. The department will only count costs the engineer deems reasonable based on experience or prevailing market rates.
- d. If a DBE subcontracts work, the department counts the value of the subcontracted work only if the DBE's subcontractor is also a DBE.
- e. The contractor shall maintain records and may be required to furnish periodic reports documenting its performance under this item.
- f. It is the prime contractor's responsibility to determine the DBE's ability to perform the work with the use of the UCP directory.

9. Commercially Useful Function

- a. The department counts expenditures of a DBE toward the DBE goal only if the DBE is performing a commercially useful function on that contract.
- b. A DBE is performing a commercially useful function if the following conditions are met:
- c. For contract work, the DBE is responsible for executing a distinct portion of the contract work and it is carrying out its responsibilities by actually performing, managing, and supervising that work.
- d. For materials and supplies, the DBE is responsible for negotiating price, determining quality and quantity, ordering, and paying for those materials and supplies.

10. Trucking

All bidders are expected to adhere to the department's current trucking policy posted on the HCCI website at

<http://www.dot.wisconsin.gov/business/engrserv/docs/dbe-trucking-notice.pdf>

11. Manufacturers and Suppliers

The department counts material and supplies a DBE provides under the contract. The department will give full credit toward the DBE goal if the DBE is a manufacturer of those materials or supplies. The department will give 60 percent credit toward the DBE goal if the DBE is merely a supplier of those materials or supplies. It is the bidder's responsibility to find out if the DBE is considered a supplier or a manufacturer before listing them on Commitment to Subcontract to DBE form DT1506.

12. DBE Prime

If the prime contractor is a DBE, the department will only count the work the contractor performs with its own forces, the work DBE subcontractors perform, and the work DBE suppliers or manufacturers perform.

13. Joint Venture

If a DBE performs as a participant in a joint venture, the department will only count that portion of the total dollar value of the contract equal to that portion of the work that the DBE performs with its own forces.

14. Mentor Protégé

- a. If a DBE performs as a participant in a mentor protégé agreement, the department will credit the portion of the work performed by the DBE protégé firm
- b. On every other project that the mentor protégé team identifies itself on.
- c. For no more than one half of the total contracted DBE goal on any WisDOT project.

15. DBE Replacement

In the event a Prime Contractor needs to replace a DBE firm originally listed on the approved DBE Commitment Form DT1506, the Prime Contractor must comply with the department's DBE Replacement Policy located on the DBE page on the following web site:

<http://www.dot.wisconsin.gov/business/engrserv/docs/policyreplacingdbe.pdf>

16. Changes to the approved DBE Commitment Form DT1506

If there are any changes to the approved Commitment to Subcontract to DBE Form DT1506, the prime contractor must submit a revised DBE Commitment Form DT1506 and relevant attachment A(s) to the DBE Programs Office within 5 business days.

17. Contract Modifications

When additional opportunity is available by contract modifications, the Prime Contractor shall utilize DBE Subcontractors, that were committed to equal work items, in the original contract.

18. Payment

Costs for conforming to this Additional Special Provision (ASP) and any associated DBE requirements are incidental to the contract.

APPENDIX A
Sample Contractor Solicitation Letter Page 1
This sample is provided as a guide not a requirement

GFW SAMPLE MEMORANDUM

TO: DBE FIRMS
FROM: POTENTIAL PRIME CONTRACTOR OR MAJOR SUBCONTRACTOR
SUBJECT: REQUEST FOR DBE QUOTES
LET DATE & TIME
DATE: MONTH DAY YEAR
CC: DBE OFFICE ENGINEER

Our company is considering bidding on the projects indicated on the next page, as a prime and/or a subcontractor for the Wisconsin Department of Transportation Month- date -year Letting. Page 2 lists the projects and work items that we may subcontract for this letting. We are interested in obtaining subcontractor quotes for these projects and work categories. Also note that we are willing to accept quotes in areas we may be planning to perform ourselves as required by federal rules.

Please review page 2, respond whether you plan to quote, highlight the projects and work items you are interested in performing and return it via fax or email within 3 days. Plans, specifications and addenda are available through WisDOT at the DBE Support Services office or at the Highway Construction Contract Information (HCCI) site at <http://roadwaystandards.dot.wi.gov/hcci/>

Your quote should include all of the costs required to complete the items you propose to perform including labor, equipment, material, and related bonding or insurance. The quote should note items that you are DBE certified to perform, tied items, and any special terms. Page 2, with the indicated projects and items you plan to quote, should be used as a cover sheet for your quote.

Please make every effort to have your quotes into our office by time deadline the prior to the letting date. **Make sure the correct letting date, project ID and proposal number, unit price and extension are included in your quote.** We prefer quotes be sent via SBN but prime's alternative's are acceptable. Our office hours are include hours and days. Please call our office as soon as possible prior to the letting if you need information/clarification to prepare your quote at contact number.

If you wish to discuss or evaluate your quote in more detail, contact us after the contract is awarded. Status of the contract can be checked at WisDOT's HCCI site at <http://roadwaystandards.dot.wi.gov/hcci/>

All questions should be directed to:

Project Manager, John Doe,
Phone: (000) 123-4567
Email: Joe@joetheplumber.com
Fax: (000) 123- 4657

Sample Contractor Solicitation Letter Page 2

This sample is provided as a guide not a requirement

REQUEST FOR QUOTATION

Prime's Name: _____

Letting Date: _____

Project ID: _____

Please check all that apply

- ☐ Yes, we will be quoting on the projects and items listed below
- ☐ No, we are not interested in quoting on the letting or its items referenced below
- ☐ Please take our name off your monthly DBE contact list
- ☐ We have questions about quoting this letting. Please have some one contact me at this number

Prime Contractor's Contact Person

Phone: _____
Fax: _____
Email: _____

DBE Contractor Contact Person

Phone: _____
Fax: _____
Email: _____

Please circle the jobs and items you will be quoting below

Proposal No.	1	2	3	4	5	6	7
County							

WORK DESCRIPTION:

Clear and Grub	X		X	X		X	X
Dump Truck Hauling	X		X	X		X	X
Curb & Gutter/Sidewalk, Etc.	X		X	X		X	X
Erosion Control Items	X		X	X		X	X
Signs and Posts/Markers	X		X	X		X	X
Traffic Control		X	X	X		X	X
Electrical Work/Traffic Signals		X	X	X		X	
Pavement Marking		X	X	X	X	X	X
Sawing Pavement		X	X	X	X	X	X
QMP, Base	X	X		X	X	X	X
Pipe Underdrain	X			X			
Beam Guard				X	X	X	X
Concrete Staining							X
Trees/Shrubs	X						X

Again please make every effort to have your quotes into our office by time deadline prior to the letting date.

We prefer quotes be sent via SBN but prime's preferred alternative's are acceptable.

If there are further questions please direct them to the prime contractor's contact person at phone number.

APPENDIX B BEST PRACTICES FOR PRIME CONTRACTOR & DBE SUBCONTRACTOR GOOD FAITH EFFORT

This list is not a set of requirements; it is a list of potential strategies

Primes

- Prime contractor open houses inviting DBE firms to see the bid “war room” or providing technical assistance
- Participate in speed networking and mosaic exercises as arranged by DBE office
- Host information sessions not directly associated with a bid letting;
- Participate in a formal mentor protégé or joint venture with a DBE firm
- Participate in WisDOT advisory committees i.e. TRANSAC, or Mega Project committee meetings
- Facilitate a small group DBE ‘training session’ Clarifying how your firm prepares for bid letting, evaluates subcontractors, preferred qualifications and communication methods
- Encourage subcontractors to solicit and highlight DBE participation in their quotes to you
- Quality of communication, not quantity creates the best results. Contractors should do as thorough a job as possible in communicating with DBE firms before the bid and provide any assistance requested to assure best possible bid.

DBE

- DBE firms should contact primes as soon as possible with questions regarding their quotes or bid; seven days prior is optimal.
- Continually check for contract addendums on the HCCI website through the Thursday prior to letting to stay abreast of changes.
- Review the status of contracts on the HCCI website reviewing the ‘apparent low bidder’ list, and bid tabs at a minimum.
- Prepare a portfolio or list of related projects and prime and supplier references; be sure to note transportation-related projects of similar size and scope, firm expertise and staffing.
- Participate in DBE office assessment programs
- Participate on advisory and mega-project committees
- Sign up to receive the DBE Contracting Update
- Consider membership in relevant industry or contractor organizations
- Active participation is a must. Quote as many projects as you can reasonably work on; quoting the primes and bidding as a prime with the department are the only ways to get work.

APPENDIX C

Types of Efforts considered in determining GFE

This list represents concepts being assessed; analysis requires additional steps

1. Whether the contractor attended any pre-solicitation or pre-bid meetings that were scheduled by WisDOT to inform DBEs of contracting and subcontracting opportunities;
2. Whether the contractor provided written notice to a reasonable number of specific DBEs that their interest in the contract was being solicited, in sufficient time to allow the DBEs to participate effectively;
3. Whether the contractor followed up initial solicitations of interest by contacting DBEs to determine if the DBEs were interested; returned the phone calls of interested DBE firms.
4. Whether the contractor selected portions of the work to be performed by DBEs in order to increase the likelihood of meeting the DBE goal;
5. Whether the contractor provided interested DBEs with adequate information about the plans, specifications and requirements of the contract;
6. Whether the contractor negotiated in good faith with interested DBEs, not rejected DBEs as unqualified without sound reasons based on a thorough investigation of their capabilities;
7. Whether the contractor made efforts to assist interested DBEs in being more competitive.
8. Whether the contractor effectively used the services of available minority community organizations: minority contractors groups, local, state, and Federal minority business assistance offices, and other organizations that provide assistance to small businesses and DBE firms.
9. Whether Prime used CRCS to identify DBE who specialize in relevant work areas.
10. Whether the contractor used available resources including contacting the DBE office, using WisDOT's website
11. Whether the contractor returned calls of firms expressing interest in a timely manner.

APPENDIX D
Good Faith Effort Evaluation Guidance
Excerpt from Appendix A of 49 CFR Part 26

APPENDIX A TO PART 26 -- GUIDANCE CONCERNING GOOD FAITH EFFORTS

- I. When, as a recipient, you establish a contract goal on a DOT assisted contract, a bidder must, in order to be responsible and/or responsive, make good faith efforts to meet the goal. The bidder can meet this requirement in either of two ways. First, the bidder can meet the goal, documenting commitments for participation by DBE firms sufficient for this purpose. Second, even if it doesn't meet the goal, the bidder can document adequate good faith efforts. This means that the bidder must show that it took all necessary and reasonable steps to achieve a DBE goal or other requirement of this part which, by their scope, intensity, and appropriateness to the objective, could reasonably be expected to obtain sufficient DBE participation, even if they were not fully successful.
- II. In any situation in which you have established a contract goal, part 26 requires you to use the good faith efforts mechanism of this part. As a recipient, it is up to you to make a fair and reasonable judgment whether a bidder that did not meet the goal made adequate good faith efforts. It is important for you to consider the quality, quantity, and intensity of the different kinds of efforts that the bidder has made. The efforts employed by the bidder should be those that one could reasonably expect a bidder to take if the bidder were actively and aggressively trying to obtain DBE participation sufficient to meet the DBE contract goal. Mere pro forma efforts are not good faith efforts to meet the DBE contract requirements. We emphasize, however, that your determination concerning the sufficiency of the firm's good faith efforts is a judgment call: meeting quantitative formulas is not required.
- III. The Department also strongly cautions you against requiring that a bidder meet a contract goal (i.e., obtain a specified amount of DBE participation) in order to be awarded a contract, even though the bidder makes an adequate good faith efforts showing. This rule specifically prohibits you from ignoring bona fide good faith efforts.
- IV. The following is a list of types of actions which you should consider as part of the bidder's good faith efforts to obtain DBE participation. It is not intended to be a mandatory checklist, nor is it intended to be exclusive or exhaustive. Other factors or types of efforts may be relevant in appropriate cases.
 - A. Soliciting through all reasonable and available means (e.g. attendance at pre-bid meetings, advertising and/or written notices) the interest of all certified DBEs who have the capability to perform the work of the contract. The bidder must solicit this interest within sufficient time to allow the DBEs to respond to the solicitation. The bidder must determine with certainty if the DBEs are interested by taking appropriate steps to follow up initial solicitations.
 - B. Selecting portions of the work to be performed by DBEs in order to increase the likelihood that the DBE goals will be achieved. This includes, where appropriate, breaking out contract work items into economically feasible units to facilitate DBE participation, even when the prime contractor might otherwise prefer to perform these work items with its own forces.
 - C. Providing interested DBEs with adequate information about the plans, specifications, and requirements of the contract in a timely manner to assist them in responding to a solicitation.

- D.
 - (1) Negotiating in good faith with interested DBEs. It is the bidder's responsibility to make a portion of the work available to DBE subcontractors and suppliers and to select those portions of the work or material needs consistent with the available DBE subcontractors and suppliers, so as to facilitate DBE participation. Evidence of such negotiation includes the names, addresses, and telephone numbers of DBEs that were considered; a description of the information provided regarding the plans and specifications for the work selected for subcontracting; and evidence as to why additional agreements could not be reached for DBEs to perform the work.
 - (2) A bidder using good business judgment would consider a number of factors in negotiating with subcontractors, including DBE subcontractors, and would take a firm's price and capabilities as well as contract goals into consideration. However, the fact that there may be some additional costs involved in finding and using DBEs is not in itself sufficient reason for a bidder's failure to meet the contract DBE goal, as long as such costs are reasonable. Also, the ability or desire of a prime contractor to perform the work of a contract with its own organization does not relieve the bidder of the responsibility to make good faith efforts. Prime contractors are not, however, required to accept higher quotes from DBEs if the price difference is excessive or unreasonable.
 - E. Not rejecting DBEs as being unqualified without sound reasons based on a thorough investigation of their capabilities. The contractor's standing within its industry, membership in specific groups, organizations, or associations and political or social affiliations (for example union vs. non-union employee status) are not legitimate causes for the rejection or non solicitation of bids in the contractor's efforts to meet the project goal.
 - F. Making efforts to assist interested DBEs in obtaining bonding, lines of credit, or insurance as required by the recipient or contractor.
 - G. Making efforts to assist interested DBEs in obtaining necessary equipment, supplies, materials, or related assistance or services.
 - H. Effectively using the services of available minority/women community organizations; minority/women contractors' groups; local, state, and Federal minority/women business assistance offices; and other organizations as allowed on a case-by-case basis to provide assistance in the recruitment and placement of DBEs.
- V. In determining whether a bidder has made good faith efforts, you may take into account the performance of other bidders in meeting the contract. For example, when the apparent successful bidder fails to meet the contract goal, but others meet it, you may reasonably raise the question of whether, with additional reasonable efforts, the apparent successful bidder could have met the goal. If the apparent successful bidder fails to meet the goal, but meets or exceeds the average DBE participation obtained by other bidders, you may view this, in conjunction with other factors, as evidence of the apparent successful bidder having made good faith efforts.

Appendix E

Small Business Network [SBN] Overview

The Small Business Network is a part of the Bid Express® service that was created to ensure that prime bidders have a centralized online location to find subs - including small and disadvantaged business enterprises (DBEs). It is available for prime bidders to use as part of their Basic Service subscription. Within the Small Business Network, **Prime Contractors** can:

1. Easily select proposals, work types and items:
 - a. After adding applicable work types, select items that you wish to quote. Enter the sub-quote quantities and add comments, if desired. Adding or removing items and work types can be done quickly. If needed, you can save the sub-quote for completion at a later time.
2. Create sub-quotes for the subcontracting community:
 - a. Create sub-quotes with ease using the intuitive sub-quote creator. In seven short steps, you can rapidly create a custom sub-quote directed to all subcontractors that bid on the applicable work types. Steps include: provide contact information and sub-quote expiration date, select letting and proposal, add work types and items, specify terms and conditions, upload attachments, and select vendors.
 - b. Create a sub-quote to send to subcontractors or suppliers that lists the items in a proposal that you want quoted
 - c. Create an unlimited number of sub-quotes for items you want quoted, and optionally mark them as a DBE-preferred request
 - d. Add attachments to sub-quotes
3. View sub-quote requests & responses:
 - a. After logging into the Bid Express service, you can quickly review all of your sub-quote requests and all unsolicited sub-quote requests from subcontractors. To simplify the Small Business Network home screen, sub-quote requests can be hidden with one click if they are not applicable.
 - b. View or receive unsolicited sub-quotes that subcontractors have posted, complete with terms, conditions and pricing
4. View Record of Subcontractor Outreach Effort:
 - a. For each sub-quote produced, a *Record of Subcontractor Outreach Effort* is generated that shows the response statistics for a particular sub-quote. If accepted by the letting agency, this report may serve as proof of a “Good Faith” effort in reaching out to the DBE community.
 - b. Easily locate pre-qualified and certified small and disadvantaged businesses
 - c. Advertise to small and disadvantaged businesses more efficiently and cost effectively
 - d. Document your interactions with subs/DBEs by producing an Outreach Report (may be accepted as proof of DBE outreach at the discretion of each agency)

The Small Business Network is a part of the Bid Express® service that was created to ensure that small businesses have a centralized area to access information about upcoming projects. It can help small businesses learn more about opportunities, compete more effectively, network with other contractors and subcontractors, and win more jobs.

1. View and reply to sub-quote requests from primes:
 - a. After logging into the Bid Express service, you can quickly review all incoming sub-quote requests and all unsolicited sub-quotes created by your company. Receive notifications by selected work type. To simplify on the Small Business Network home screen, sub-quote requests can be filtered by work types relevant to your interests, or hidden with one click if they are not applicable.
2. Select items when responding to sub-quote requests from primes:
 - a. You have the freedom to choose and price any number of items when responding to a sub-quote request. Quantities can be modified, and per-item comments are also available.
 - b. View requests for sub-quotes for work that primes have posted for projects they are bidding, add your pricing, terms, and conditions, and submit completed sub-quotes to the requesting primes
 - c. Add attachments to a sub-quote
3. Create and send unsolicited sub-quotes to specific contractors:
 - a. Create unsolicited sub-quotes with ease using the intuitive sub-quote creator. In eight short steps, you can rapidly create a custom sub-quote directed at any number of specific vendors of your choosing. Steps include: provide contact information and sub-quote expiration date, select letting and proposal, add work types and items, specify terms and conditions, upload attachments, and select vendors.
4. Easily select and price items for unsolicited sub-quotes:
 - a. After adding applicable work types, select items that you wish to quote. The extended price calculates automatically, cutting out costly calculation errors. Comments can be provided on an per-item basis as well.
 - b. Create an unsolicited sub-quote that lists the items from a proposal that you want to quote, include pricing, terms and conditions, and send it to selected prime/plan holder
 - c. Add attachments to a sub-quote
 - d. Add unsolicited work items to sub-quotes that you are responding to
5. Easy Access to Valuable Information
 - a. Receive a confirmation that your sub-quote was opened by a prime
 - b. View Bid Tab Analysis data from past bids, including the high, average and low prices of items.
 - c. View important notices and publications from DOT targeted to small and disadvantaged businesses
6. Accessing Small Business Network for WisDOT contracting opportunities
 - a. If you are a contractor not yet subscribing to the Bid Express service, go to **www.bidx.com** and select “Order Bid Express.” The Small Business Network is a part of the Bid Express Basic Service.
 - b. DBE firms can request a Bid Express Small Business Network Account at no cost by calling 414-438-4588

ADDITIONAL SPECIAL PROVISION 4

Payment to First-Tier Subcontractors

Within 10 calendar days of receiving a progress payment for work completed by a subcontractor, pay the subcontractor for that work. The prime contractor may withhold payment to a subcontractor if, within 10 calendar days of receipt of that progress payment, the prime contractor provides written notification to the subcontractor and the department documenting "just cause" for withholding payment.

The prime contractor may also withhold routine retainage from payments due subcontractors.

Payment to Lower-Tier Subcontractors

Ensure that subcontracting agreements at all tiers provide prompt payment rights to lower-tier subcontractors that parallel those granted first-tier subcontractors in this provision.

Release of Routine Retainage

After granting substantial completion the department may reduce the routine retainage withheld from the prime contractor to 75 percent of the original total amount retained.

When the Department sends the semi-final estimate the department may reduce the routine retainage withheld from the prime contractor to 10 percent of the original total amount retained.

Within 30 calendar days of receiving the semi-final estimate from the department, submit written certification that subcontractors at all tiers are paid in full for acceptably completed work and that no routine retainage is being withheld. The department will pay the prime contractor in full and reduce the routine retainage withheld from the prime contractor to zero when the department approves the final estimate.

This special provision does not limit the right of the department, prime contractor, or subcontractors at any tier to withhold payment for work not acceptably completed or work subject to an unresolved contract dispute.

ADDITIONAL SPECIAL PROVISION 6**ASP 6 - Modifications to the standard specifications**

Make the following revisions to the 2014 edition of the standard specifications:

101.3 Definitions

Replace the definition of semi-final estimate with the following effective with the December 2013 letting:

Semi-final estimate An estimate indicating the engineer has measured and reported all contract quantities and materials requirements.

105.11.1 Partial Acceptance

Replace paragraph two with the following effective with the December 2013 letting:

- (2) Partial acceptance will relieve the contractor of maintenance responsibility for the designated portion of the work. By relieving the contractor of maintenance, the department does not relieve the contractor of responsibility for defective work or damages caused by the contractor's operations. Do not construe partial acceptance to be conditional final acceptance or final acceptance of any part of the project, or a waiver of any legal rights specified under 107.16.
-

105.11.2 Final Acceptance

Retitle and replace the entire text with the following effective with the December 2013 letting:

105.11.2 Project Acceptance**105.11.2.1 Inspection****105.11.2.1.1 General**

- (1) Notify the engineer when the project is substantially complete as defined in 105.11.2.1.3. As soon as it is practical, the engineer will inspect the work and categorize it as one of the following:
1. Unacceptable or not complete.
 2. Substantially complete.
 3. Complete.

105.11.2.1.2 Unacceptable or Not Complete

- (1) The engineer will identify, in writing, work that is unacceptable or not complete. Immediately correct or complete that work. The engineer will assess contract time until the work is corrected or completed.
- (2) Proceed as specified in 105.11.2.1.1 until the engineer determines that the work is complete.

105.11.2.1.3 Substantially Complete

- (1) The project is substantially complete and the engineer will no longer assess contract time if the contractor has completed all contract bid items and change order work, except for the punch-list. As applicable, the following must have occurred:
1. All lanes of traffic are open on a finished surface.
 2. All signage and traffic control devices are in place and operating.
 3. All drainage, erosion control, excavation, and embankments are completed.
 4. All safety appurtenances are completed.
- (2) The engineer will provide a written punch-list enumerating work the contractor must perform and documents the contractor must submit before the the engineer will categorize the work as complete.
1. Punch-list work includes uncompleted cleanup work required under 104.9 and minor corrective work. Immediately correct or complete the punch-list work. The engineer may restart contract time if the contractor does not complete the punch-list work within 5 business days after receiving the written punch-list. The engineer and contractor may mutually agree to extend this 5-day requirement.
 2. Punch-list documents include whatever contract required documentation is missing. The engineer may restart contract time if the contractor does not submit the punch-list documents within 15 business days after receiving the written punch-list. The engineer and contractor may mutually agree to extend this 15-day requirement.
- (3) Proceed as specified in 105.11.2.1.1 until the work is complete.

105.11.2.1.4 Complete

- (1) The project is complete when the contractor has completed all contract bid items, change order work, and punch-list work including the submission of all missing documentation.

105.11.2.2 Conditional Final Acceptance

- (1) When the engineer determines that the project is complete, the engineer will give the contractor written notice of conditional final acceptance relieving the contractor of maintenance responsibility for the completed work.

105.11.2.3 Final Acceptance

- (1) The engineer will grant final acceptance of the project after determining that all contract is work complete; all contract, materials, and payroll records are reviewed and approved; and the semi-final estimate quantities are final under 109.7.
- (2) Failure to discover defective work or materials before final acceptance does not prevent the department from rejecting that work or those materials later. The department may revoke final acceptance if the department discovers defective work or materials after it has accepted the work.

105.13.3 Submission of Claim

Replace paragraph one with the following effective with the December 2013 letting:

- (1) Submit the claim to the project engineer as promptly as possible following the submission of the Notice of Claim, but not later than final acceptance of the project as specified in 105.11.2.3. If the contractor does not submit the claim before final acceptance of the project, the department will deny the claim.

107.17.3 Railroad Insurance Requirements

Replace paragraph one with the following effective with the December 2013 letting:

- (1) If required by the special provisions, provide or arrange for a subcontractor to provide railroad protective liability insurance in addition to the types and limits of insurance required in 107.26. Keep railroad protective liability insurance coverage in force until completing all work, under or incidental to the contract, on the railroad right of way or premises of the railroad and until the engineer determines that the work is complete as specified in 105.11.2.1.4.

107.26 Standard Insurance Requirements

Replace paragraph one with the following effective with the December 2013 letting:

- (1) Maintain the following types and limits of commercial insurance in force until the engineer determines that the work is complete as specified in 105.11.2.1.4.

TABLE 107-1 REQUIRED INSURANCE AND MINIMUM COVERAGES

TYPE OF INSURANCE	MINIMUM LIMITS REQUIRED ^[1]
1. Commercial general liability insurance endorsed to include blanket contractual liability coverage. ^[2]	\$2 million combined single limits per occurrence with an annual aggregate limit of not less than \$4 million.
2. Workers' compensation.	Statutory limits
3. Employers' liability insurance.	Bodily injury by accident: \$100,000 each accident Bodily injury by disease: \$500,000 each accident \$100,000 each employee
4. Commercial automobile liability insurance covering all contractor-owned, non-owned, and hired vehicles used in carrying out the contract. ^[2]	\$1 million-combined single limits per occurrence.

^[1] The contractor may satisfy these requirements with primary insurance coverage or with excess/umbrella policies.

^[2] The Wisconsin Department of Transportation, its officers, agents, and employees shall be named as an additional insured under the general liability and automobile liability insurance.

108.14 Terminating the Contractor's Responsibility

Replace paragraph one with the following effective with the December 2013 letting:

- (1) The contractor's responsibilities are terminated, except as set forth in the contract bond and specified in 107.16, when the department grants final acceptance as specified in 105.11.2.3.
-

109.2 Scope of Payment

Replace paragraph two with the following effective with the December 2013 letting:

- (2) The department will pay for the quantity of work acceptably completed and measured for payment as the measurement subsection for each bid item specifies. Within the contract provide means to furnish and install the work complete and in-place. Payment is full compensation for everything required to perform the work under the applicable bid items including, but not limited to, the work elements listed in the payment subsection. Payment also includes all of the following not specifically excluded in that payment subsection:
 1. Furnishing and installing all materials as well as furnishing the labor, tools, supplies, equipment, and incidentals necessary to perform the work.
 2. All losses or damages, except as specified in 107.14, arising from one or more of the following:
 - The nature of the work.
 - The action of the elements.
 - Unforeseen difficulties encountered during prosecution of the work.
 3. All insurance costs, expenses, and risks connected with the prosecution of the work.
 4. All expenses incurred because of an engineer-ordered suspension, except as specified in 104.2.2.3.
 5. All infringements of patents, trademarks, or copyrights.
 6. All other expenses incurred to complete and protect the work under the contract.
-

109.6.1 General

Replace paragraphs three and four with the following effective with the December 2013 letting:

- (3) The department's payment of an estimate before conditional final acceptance of the work does not constitute the department's acceptance of the work, and does not relieve the contractor of responsibility for:
 1. Protecting, repairing, correcting, or renewing the work.
 2. Replacing all defects in the construction or in the materials used in the construction of the work under the contract, or responsibility for damage attributable to these defects.
 - (4) The contractor is responsible for all defects or damage that the engineer may discover on or before the engineer's conditional final acceptance of the work. The engineer is the sole judge of these defects or damage, and the contractor is liable to the department for not correcting all defects or damage.
-

109.7 Acceptance and Final Payment

Replace paragraphs one and two with the following effective with the December 2013 letting:

- (1) After the engineer grants conditional final acceptance of the work as specified in 105.11.2.2 and reviews required document submittals and materials test reports, the engineer will issue the semi-final estimate.
- (2) Within 30 calendar days after receiving the semi-final estimate, submit to the engineer a written statement of agreement or disagreement with the semi-final estimate. For an acceptable statement of disagreement, submit an item-by-item list with reasons for each disagreement. If the contractor does not submit this written statement within those 30 days, the engineer will process the final estimate for payment. The engineer and the contractor can mutually agree to extend this 30-day submission requirement.

450.3.3 Maintaining the Work

Replace paragraph one with the following effective with the December 2013 letting:

- (1) Protect and repair the prepared foundation, tack coat, base, paved traffic lanes, shoulders, and seal coat. Correct all rich or bleeding areas, breaks, raveled spots, or other nonconforming areas in the paved surface.

455.3.2.5 Maintaining Tack Coat

Replace paragraph one with the following effective with the December 2013 letting:

- (1) Protect and repair the existing surface and the tack coat. Correct areas with excess or deficient tack material and any breaks, raveled spots, or other areas where bond might be affected.

460.2.2.3 Aggregate Gradation Master Range

Replace paragraph one with the following effective with the January 2014 letting:

- (1) Ensure that the aggregate blend, including recycled material and mineral filler, conforms to the gradation requirements in table 460-1. The values listed are design limits; production values may exceed those limits.

TABLE 460-1 AGGREGATE GRADATION MASTER RANGE AND VMA REQUIREMENTS

SIEVE	PERCENTS PASSING DESIGNATED SIEVES						
	NOMINAL SIZE						
	37.5 mm	25.0 mm	19.0 mm	12.5 mm	9.5 mm	SMA 12.5 mm	SMA 9.5 mm
50.0-mm	100						
37.5-mm	90 – 100	100					
25.0-mm	90 max	90 - 100	100				
19.0-mm	—	90 max	90 - 100	100		100	
12.5-mm	—	—	90 max	90 - 100	100	90 - 97	100
9.5-mm	—	—	—	90 max	90 - 100	58 - 72	90 - 100
4.75-mm	—	—	—	—	90 max	25 - 35	35 - 45
2.36-mm	15 – 41	19 - 45	23 - 49	28 - 58	20 - 65	15 - 25	18 - 28
75-µm	0 – 6.0	1.0 - 7.0	2.0 - 8.0	2.0 - 10.0	2.0 - 10.0	8.0 - 12.0	10.0 - 14.0
% MINIMUM VMA	11.0	12.0	13.0	14.0 ^[1]	15.0 ^[2]	16.0	17.0

^[1] 14.5 for E-3 mixes.

^[2] 15.5 for E-3 mixes.

460.2.7 HMA Mixture Design

Replace paragraph one with the following effective with the January 2014 letting:

- (1) For each HMA mixture type used under the contract, develop and submit an asphaltic mixture design according to the department's test method number 1559 as described in CMM 8-66 and conforming to the requirements of table 460-1 and table 460-2. The values listed are design limits; production values may exceed those limits. The department will review mixture designs and report the results of that review to the designer according to the department's test method number 1559.

TABLE 460-2 MIXTURE REQUIREMENTS

Mixture type	E - 0.3	E - 1	E - 3	E - 10	E - 30	E - 30x	SMA
ESALs x 10 ⁶ (20 yr design life)	< 0.3	0.3 - < 1	1 - < 3	3 - < 10	10 - < 30	>= 30	—
LA Wear (AASHTO T96)							
100 revolutions(max % loss)	13	13	13	13	13	13	13
500 revolutions(max % loss)	50	50	45	45	45	45	40
Soundness (AASHTO T104) (sodium sulfate, max % loss)	12	12	12	12	12	12	12
Freeze/Thaw (AASHTO T103) (specified counties, max % loss)	18	18	18	18	18	18	18
Fractured Faces (ASTM 5821) (one face/2 face, % by count)	60 / —	65 / —	75 / 60	85 / 80	98 / 90	100/100	100/90
Flat & Elongated (ASTM D4791) (max %, by weight)	5 (5:1 ratio)	5 (5:1 ratio)	5 (5:1 ratio)	5 (5:1 ratio)	5 (5:1 ratio)	5 (5:1 ratio)	20 (3:1ratio)
Fine Aggregate Angularity (AASHTO T304, method A, min)	40	40	43	45	45	45	45
Sand Equivalency (AASHTO T176, min)	40	40	40	45	45	50	50
Gyratory Compaction							
Gyrations for N _{ini}	6	7	7	8	8	9	8
Gyrations for N _{des}	40	60	75	100	100	125	65
Gyrations for N _{max}	60	75	115	160	160	205	160
Air Voids, %V _a (%G _{mm} N _{des})	4.0 (96.0)	4.0 (96.0)	4.0 (96.0)	4.0 (96.0)	4.0 (96.0)	4.0 (96.0)	4.0 (96.0)
% G _{mm} N _{ini}	<= 91.5 ^[1]	<= 90.5 ^[1]	<= 89.0 ^[1]	<= 89.0	<= 89.0	<= 89.0	—
% G _{mm} N _{max}	<= 98.0	<= 98.0	<= 98.0	<= 98.0	<= 98.0	<= 98.0	—
Dust to Binder Ratio ^[2] (% passing 0.075/P _{be})	0.6 - 1.2	0.6 - 1.2	0.6 - 1.2	0.6 - 1.2	0.6 - 1.2	0.6 - 1.2	1.2 - 2.0
Voids filled with Binder (VFB or VFA, %)	68 - 80 ^{[4] [5]}	65 - 78 ^[4]	65 - 75 ^{[3] [4]}	65 - 75 ^{[3] [4]}	65 - 75 ^{[3] [4]}	65 - 75 ^{[3] [4]}	70 - 80
Tensile Strength Ratio (TSR) (ASTM 4867)							
no antistripping additive	0.70	0.70	0.70	0.70	0.70	0.70	0.70
with antistripping additive	0.75	0.75	0.75	0.75	0.75	0.75	0.75
Draindown at Production Temperature (%)	—	—	—	—	—	—	0.30

^[1] The percent maximum density at initial compaction is only a guideline.

^[2] For a gradation that passes below the boundaries of the caution zone(ref. AASHTO MP3), the dust to binder ratio limits are 0.6 - 1.6.

^[3] For 9.5mm and 12.5 mm nominal maximum size mixtures, the specified VFB range is 70 - 76%.

^[4] For 37.5mm nominal maximum size mixes, the specified VFB lower limit is 67%.

^[5] For 25.0mm nominal maximum size mixes, the specified VFB lower limit is 67%.

460.2.8.2.1.5 Control Limits

Replace paragraph one with the following effective with the January 2014 letting:

- (1) Conform to the following control limits for the JMF and warning limits based on a running average of the last 4 data points:

ITEM	JMF LIMITS	WARNING LIMITS
Percent passing given sieve:		
37.5-mm	+/- 6.0	+/- 4.5
25.0-mm	+/- 6.0	+/- 4.5
19.0-mm	+/- 5.5	+/- 4.0
12.5-mm	+/- 5.5	+/- 4.0
9.5-mm	+/- 5.5	+/- 4.0
2.36-mm	+/- 5.0	+/- 4.0
75-µm	+/- 2.0	+/- 1.5
Asphaltic content in percent	- 0.3	- 0.2
Air voids in percent	+/- 1.3	+/- 1.0
VMA in percent ^[1]	- 0.5	- 0.2

^[1] VMA limits based on minimum requirement for mix design nominal maximum aggregate size in Table 460-1.

- (2) Warning bands are defined as the area between the JMF limits and the warning limits.

460.2.8.2.1.6 Job Mix Formula Adjustment

Replace the entire text with the following effective with the January 2014 letting:

- (1) The contractor may request adjustment of the JMF according to the department's test method number 1559. Have an HTCP HMA technician certified at a level appropriate for process control and troubleshooting or mix design submit a written JMF adjustment request. Ensure that the resulting JMF is within specified master gradation bands. The department will have an HMA technician certified at level III review the proposed adjustment and, if acceptable, issue a revised JMF.
- (2) The department will not allow adjustments that do the following:
- Exceed specified JMF tolerance limits.
 - Reduce the JMF asphalt content unless the production VMA running average meets or exceeds the minimum VMA design requirement defined in table 460-1 for the mixture produced.
- (3) Have an HMA technician certified at level II make related process adjustments. If mixture redesign is necessary, submit a new JMF, subject to the same specification requirements as the original JMF.

520.3.8 Protection After Laying

Delete the entire subsection.

614.2.1 General

Replace paragraphs five and six with the following effective with the December 2013 letting:

- (5) Furnish zinc coated wire rope and fitting conforming to the plans and galvanized according to ASTM A741.
- (6) Before installation store galvanized components above ground level and away from surface run off. The department may reject material if the zinc coating is physically damaged or oxidized.
- (7) Provide manufacturer's drawings, and installation and maintenance instructions when providing proprietary systems.

614.2.3 Steel Rail and Fittings

Replace paragraph one with the following effective with the December 2013 letting:

- (1) Furnish galvanized steel rail conforming to AASHTO M180 class A, type II beam using the single-spot test coating requirements. Furnish plates, anchor plates, post mounting brackets, and other structural steel components conforming to 506.2.2.1 and hot-dip galvanized according to ASTM A123.

614.2.7 Crash Cushions

Replace paragraph one with the following effective with the December 2013 letting:

- (1) Furnish permanent and temporary crash cushions from the department's approved products list. Use cushions as wide or wider than the plan back-width. Furnish transitions conforming to the crash cushion manufacturer's design and specifications. Submit manufacturer crash cushion and transition design details to engineer before installing.

616.3.1 General

Replace paragraph six with the following effective with the December 2013 letting:

- (6) Remove and dispose of all excess excavation and surplus materials from the fence site.

618.3.3 Restoration

Replace paragraph one with the following effective with the December 2013 letting:

- (1) Upon termination of hauling operations and before conditional final acceptance, restore all haul roads, including drainage facilities and other components, to the equivalent of pre-hauling conditions.

627.3.1 General

Replace paragraph four with the following effective with the December 2013 letting:

- (4) Maintain the mulched areas and repair all areas damaged by wind, erosion, traffic, fire or other causes.

637.3.2.1 General

Delete paragraph three effective with the December 2013 letting.

670.3.4.2 Post-Construction Work

Replace paragraph one with the following effective with the December 2013 letting:

- (1) Submit 5 copies of ITS documentation including but not limited to the following:
 - Operator's manual: for contractor furnished equipment, submit a manual containing detailed operating instructions for each different type or model of equipment and or operation performed.
 - Maintenance procedures manuals: for contractor furnished equipment, submit a manual containing detailed preventive and corrective maintenance procedures for each type or model of equipment furnished.
 - Cabinet fiber optic wiring diagram: submit a cabinet wiring diagram, identified by location for each cabinet. Include both electrical wiring and fiber optic conductor and cable connections. Place one copy of the fiber optic wiring diagram in a weatherproof holder in the cabinet. Deliver the other copies to the engineer.
 - As-built drawings: submit final as-built drawings that detail the final placement of all conduit, cabling, equipment, and geometric modifications within the contract. Provide all documentation in an electronic format adhering to the region's ITS computer aided drafting standards and according to the department's as-built requirements. The department will review the as-built drawings for content and electronic format. Modify both the content and format of as-built drawings until meeting all requirements.
 - Equipment inventory list: submit an inventory list including serial number, make, model, date installed, and location installed of all equipment installed under the contract.

Errata

Make the following corrections to the 2014 edition of the standard specifications:

415.3.14 Protecting Concrete

Correct errata by referencing the opening to service specification.

- (1) Erect and maintain suitable barricades and, if necessary, provide personnel to keep traffic off the newly constructed pavement until it is opened for service as specified in 415.3.15. Conform to 104.6 for methods of handling and facilitating traffic.
-

501.2.9 Concrete Curing Materials

Correct errata by changing AASHTO M171 to ASTM C171.

- (2) Furnish sheeting conforming to ASTM C171 for white opaque polyethylene film, except that the contractor may use clear or black polyethylene for cold weather protection.
-

607.2 Materials

Correct errata by changing AASHTO M198 to ASTM C990.

- (1) Use materials conforming to the requirements for the class of material named and specified below.
- | | |
|--|------------|
| Composite pipe, couplings, fittings and joint materials | ASTM D2680 |
| Annular rubber and plastic gaskets for flexible, watertight joints | ASTM C990 |
| External rubber gaskets, mastic, and protective film..... | ASTM C877 |
| Mortar | 519.2.3 |
-

637.2.1.3 Sheet Aluminum

Correct errata by changing ASTM B449 to B921 and eliminating the specification for coating thickness.

- (4) Degrease, etch, and coat the sign blank on both sides with a chromate treatment conforming to ASTM B921, class 2.
-

637.3.3.4 Performance

Correct errata to reference to 105.11.2.3 as revised to implement changes to the finals process.

- (1) Under 105.11.2.3 the department may revoke acceptance and direct the contractor to repair or replace previously accepted sign installations if the department subsequently discovers evidence of defective materials or improper installation. Deficiencies that warrant department action include but are not limited to the following:
- Sign posts more than five degrees out of plumb.
 - Signs twisted by more than 5 degrees from plan orientation.
 - Signs with delaminated or warped plywood.
 - Signs with bubbling, fading, delaminating, or buckling sheeting.
-

646.3.3.4 Proving Period

Correct errata to reference to 105.11.2.3 as revised to implement changes to the finals process.

- (4) Replace all marking within sections with a percent failing more than 10% and repair or replace all markings that, in the engineer's assessment, show evidence of improper construction. If post-acceptance inspections uncover evidence of defective materials or improper construction, the department may revoke acceptance under 105.11.2.3.

ADDITIONAL SPECIAL PROVISION 7

- A. Reporting 1st Tier and DBE Payments During Construction
1. Comply with reporting requirements specified in the department's Civil Rights Compliance, Contractor's User Manual, Sublets and Payments.
 2. Report payments to all DBE firms within 10 calendar days of receipt of a progress payment by the department or a contractor for work performed, materials furnished, or materials stockpiled by a DBE firm. Report the payment as specified in A(1) for all work satisfactorily performed and for all materials furnished or stockpiled.
 3. Report payments to all first tier subcontractor relationships within 10 calendar days of receipt of a progress payment by the department for work performed. Report the payment as specified in A(1) for all work satisfactorily performed.
 4. All tiers shall report payments as necessary to comply with the DBE payment requirement as specified in A(2).
 5. Require all first tier relationships, DBE firms and all other tier relationships necessary to comply with the DBE payment requirement in receipt of a progress payment by contractor to acknowledge receipt of payment as specified in A(1), (2), (3) and (4).
 6. All agreements made by a contractor shall include the provisions in A(1), (2), (3), (4) and (5), and shall be binding on all first tier subcontractor relationships and all contractors and subcontractors utilizing DBE firms on the project.
- B. Costs for conforming to this special provision are incidental to the contract.

ADDITIONAL SPECIAL PROVISION 9
Electronic Certified Payroll Submittal

(1) Use the department's Civil Rights Compliance System (CRCS) to submit certified payrolls electronically. Details are available online through the department's highway construction contractor information (HCCI) site on the Labor, Wages, and EEO Information page at:

<http://roadwaystandards.dot.wi.gov/hcci/labor-wages-eeo/index.shtm>

(2) Ensure that all tiers of subcontractors, as well as all trucking firms, submit their weekly certified payrolls electronically through CRCS. These payrolls are due within seven calendar days following the close of the payroll period. Every firm providing physical labor towards completing the project is a subcontractor under this special provision.

(3) Upon receipt of contract execution, promptly make all affected firms aware of the requirements under this special provision and arrange for them to receive CRCS training as they are about to begin payrolls. The department will provide training either in a classroom setting at one of our regional offices or by telephone. Contact Tess Mulrooney at 608-267-4489 to schedule the training.

(4) The department will reject all paper submittals of forms DT-1816 and DT-1929 for information required under this special provision. All costs for conforming to this special provision are incidental to the contract.

(5) Firms wishing to export payroll data from their computer system into CRCS should have their payroll coordinator send several sample electronic files to Tess two months before a payroll needs to be submitted. Not every contractor's payroll system is capable of producing export files. For details, see pages 17-22 of the CRCS System Background Information manual available online on the Labor, Wages, and EEO Information page at:

<http://roadwaystandards.dot.wi.gov/hcci/labor-wages-eeo/crc-basic-info.pdf>

REQUIRED CONTRACT PROVISIONS FEDERAL-AID CONSTRUCTION CONTRACTS

- I. General
- II. Nondiscrimination
- III. Nonsegregated Facilities
- IV. Davis-Bacon and Related Act Provisions
- V. Contract Work Hours and Safety Standards Act Provisions
- VI. Subletting or Assigning the Contract
- VII. Safety: Accident Prevention
- VIII. False Statements Concerning Highway Projects
- IX. Implementation of Clean Air Act and Federal Water Pollution Control Act
- X. Compliance with Governmentwide Suspension and Debarment Requirements
- XI. Certification Regarding Use of Contract Funds for Lobbying

ATTACHMENTS

A. Employment and Materials Preference for Appalachian Development Highway System or Appalachian Local Access Road Contracts (included in Appalachian contracts only)

I. GENERAL

1. Form FHWA-1273 must be physically incorporated in each construction contract funded under Title 23 (excluding emergency contracts solely intended for debris removal). The contractor (or subcontractor) must insert this form in each subcontract and further require its inclusion in all lower tier subcontracts (excluding purchase orders, rental agreements and other agreements for supplies or services).

The applicable requirements of Form FHWA-1273 are incorporated by reference for work done under any purchase order, rental agreement or agreement for other services. The prime contractor shall be responsible for compliance by any subcontractor, lower-tier subcontractor or service provider.

Form FHWA-1273 must be included in all Federal-aid design-build contracts, in all subcontracts and in lower tier subcontracts (excluding subcontracts for design services, purchase orders, rental agreements and other agreements for supplies or services). The design-builder shall be responsible for compliance by any subcontractor, lower-tier subcontractor or service provider.

Contracting agencies may reference Form FHWA-1273 in bid proposal or request for proposal documents, however, the Form FHWA-1273 must be physically incorporated (not referenced) in all contracts, subcontracts and lower-tier subcontracts (excluding purchase orders, rental agreements and other agreements for supplies or services related to a construction contract).

2. Subject to the applicability criteria noted in the following sections, these contract provisions shall apply to all work performed on the contract by the contractor's own organization and with the assistance of workers under the contractor's immediate superintendence and to all work performed on the contract by piecework, station work, or by subcontract.

3. A breach of any of the stipulations contained in these Required Contract Provisions may be sufficient grounds for withholding of progress payments, withholding of final payment, termination of the contract, suspension / debarment or any other action determined to be appropriate by the contracting agency and FHWA.

4. Selection of Labor: During the performance of this contract, the contractor shall not use convict labor for any purpose within the limits of a construction project on a Federal-aid highway unless it is labor performed by convicts who are on parole, supervised release, or probation. The term Federal-aid highway does not include roadways functionally classified as local roads or rural minor collectors.

II. NONDISCRIMINATION

The provisions of this section related to 23 CFR Part 230 are applicable to all Federal-aid construction contracts and to all related construction subcontracts of \$10,000 or more. The provisions of 23 CFR Part 230 are not applicable to material supply, engineering, or architectural service contracts.

In addition, the contractor and all subcontractors must comply with the following policies: Executive Order 11246, 41 CFR 60, 29 CFR 1625-1627, Title 23 USC Section 140, the Rehabilitation Act of 1973, as amended (29 USC 794), Title VI of the Civil Rights Act of 1964, as amended, and related regulations including 49 CFR Parts 21, 26 and 27; and 23 CFR Parts 200, 230, and 633.

The contractor and all subcontractors must comply with: the requirements of the Equal Opportunity Clause in 41 CFR 60-1.4(b) and, for all construction contracts exceeding \$10,000, the Standard Federal Equal Employment Opportunity Construction Contract Specifications in 41 CFR 60-4.3.

Note: The U.S. Department of Labor has exclusive authority to determine compliance with Executive Order 11246 and the policies of the Secretary of Labor including 41 CFR 60, and 29 CFR 1625-1627. The contracting agency and the FHWA have the authority and the responsibility to ensure compliance with Title 23 USC Section 140, the Rehabilitation Act of 1973, as amended (29 USC 794), and Title VI of the Civil Rights Act of 1964, as amended, and related regulations including 49 CFR Parts 21, 26 and 27; and 23 CFR Parts 200, 230, and 633.

The following provision is adopted from 23 CFR 230, Appendix A, with appropriate revisions to conform to the U.S. Department of Labor (US DOL) and FHWA requirements.

1. Equal Employment Opportunity: Equal employment opportunity (EEO) requirements not to discriminate and to take affirmative action to assure equal opportunity as set forth under laws, executive orders, rules, regulations (28 CFR 35, 29 CFR 1630, 29 CFR 1625-1627, 41 CFR 60 and 49 CFR 27) and orders of the Secretary of Labor as modified by the provisions prescribed herein, and imposed pursuant to 23 U.S.C. 140 shall constitute the EEO and specific affirmative action standards for the contractor's project activities under

this contract. The provisions of the Americans with Disabilities Act of 1990 (42 U.S.C. 12101 et seq.) set forth under 28 CFR 35 and 29 CFR 1630 are incorporated by reference in this contract. In the execution of this contract, the contractor agrees to comply with the following minimum specific requirement activities of EEO:

a. The contractor will work with the contracting agency and the Federal Government to ensure that it has made every good faith effort to provide equal opportunity with respect to all of its terms and conditions of employment and in their review of activities under the contract.

b. The contractor will accept as its operating policy the following statement:

"It is the policy of this Company to assure that applicants are employed, and that employees are treated during employment, without regard to their race, religion, sex, color, national origin, age or disability. Such action shall include: employment, upgrading, demotion, or transfer; recruitment or recruitment advertising; layoff or termination; rates of pay or other forms of compensation; and selection for training, including apprenticeship, pre-apprenticeship, and/or on-the-job training."

2. EEO Officer: The contractor will designate and make known to the contracting officers an EEO Officer who will have the responsibility for and must be capable of effectively administering and promoting an active EEO program and who must be assigned adequate authority and responsibility to do so.

3. Dissemination of Policy: All members of the contractor's staff who are authorized to hire, supervise, promote, and discharge employees, or who recommend such action, or who are substantially involved in such action, will be made fully cognizant of, and will implement, the contractor's EEO policy and contractual responsibilities to provide EEO in each grade and classification of employment. To ensure that the above agreement will be met, the following actions will be taken as a minimum:

a. Periodic meetings of supervisory and personnel office employees will be conducted before the start of work and then not less often than once every six months, at which time the contractor's EEO policy and its implementation will be reviewed and explained. The meetings will be conducted by the EEO Officer.

b. All new supervisory or personnel office employees will be given a thorough indoctrination by the EEO Officer, covering all major aspects of the contractor's EEO obligations within thirty days following their reporting for duty with the contractor.

c. All personnel who are engaged in direct recruitment for the project will be instructed by the EEO Officer in the contractor's procedures for locating and hiring minorities and women.

d. Notices and posters setting forth the contractor's EEO policy will be placed in areas readily accessible to employees, applicants for employment and potential employees.

e. The contractor's EEO policy and the procedures to implement such policy will be brought to the attention of employees by means of meetings, employee handbooks, or other appropriate means.

4. Recruitment: When advertising for employees, the contractor will include in all advertisements for employees the notation: "An Equal Opportunity Employer." All such advertisements will be placed in publications having a large circulation among minorities and women in the area from which the project work force would normally be derived.

a. The contractor will, unless precluded by a valid bargaining agreement, conduct systematic and direct recruitment through public and private employee referral sources likely to yield qualified minorities and women. To meet this requirement, the contractor will identify sources of potential minority group employees, and establish with such identified sources procedures whereby minority and women applicants may be referred to the contractor for employment consideration.

b. In the event the contractor has a valid bargaining agreement providing for exclusive hiring hall referrals, the contractor is expected to observe the provisions of that agreement to the extent that the system meets the contractor's compliance with EEO contract provisions. Where implementation of such an agreement has the effect of discriminating against minorities or women, or obligates the contractor to do the same, such implementation violates Federal nondiscrimination provisions.

c. The contractor will encourage its present employees to refer minorities and women as applicants for employment. Information and procedures with regard to referring such applicants will be discussed with employees.

5. Personnel Actions: Wages, working conditions, and employee benefits shall be established and administered, and personnel actions of every type, including hiring, upgrading, promotion, transfer, demotion, layoff, and termination, shall be taken without regard to race, color, religion, sex, national origin, age or disability. The following procedures shall be followed:

a. The contractor will conduct periodic inspections of project sites to insure that working conditions and employee facilities do not indicate discriminatory treatment of project site personnel.

b. The contractor will periodically evaluate the spread of wages paid within each classification to determine any evidence of discriminatory wage practices.

c. The contractor will periodically review selected personnel actions in depth to determine whether there is evidence of discrimination. Where evidence is found, the contractor will promptly take corrective action. If the review indicates that the discrimination may extend beyond the actions reviewed, such corrective action shall include all affected persons.

d. The contractor will promptly investigate all complaints of alleged discrimination made to the contractor in connection with its obligations under this contract, will attempt to resolve such complaints, and will take appropriate corrective action within a reasonable time. If the investigation indicates that the discrimination may affect persons other than the complainant, such corrective action shall include such other persons. Upon completion of each investigation, the contractor will inform every complainant of all of their avenues of appeal.

6. Training and Promotion:

a. The contractor will assist in locating, qualifying, and increasing the skills of minorities and women who are

applicants for employment or current employees. Such efforts should be aimed at developing full journey level status employees in the type of trade or job classification involved.

b. Consistent with the contractor's work force requirements and as permissible under Federal and State regulations, the contractor shall make full use of training programs, i.e., apprenticeship, and on-the-job training programs for the geographical area of contract performance. In the event a special provision for training is provided under this contract, this subparagraph will be superseded as indicated in the special provision. The contracting agency may reserve training positions for persons who receive welfare assistance in accordance with 23 U.S.C. 140(a).

c. The contractor will advise employees and applicants for employment of available training programs and entrance requirements for each.

d. The contractor will periodically review the training and promotion potential of employees who are minorities and women and will encourage eligible employees to apply for such training and promotion.

7. Unions: If the contractor relies in whole or in part upon unions as a source of employees, the contractor will use good faith efforts to obtain the cooperation of such unions to increase opportunities for minorities and women. Actions by the contractor, either directly or through a contractor's association acting as agent, will include the procedures set forth below:

a. The contractor will use good faith efforts to develop, in cooperation with the unions, joint training programs aimed toward qualifying more minorities and women for membership in the unions and increasing the skills of minorities and women so that they may qualify for higher paying employment.

b. The contractor will use good faith efforts to incorporate an EEO clause into each union agreement to the end that such union will be contractually bound to refer applicants without regard to their race, color, religion, sex, national origin, age or disability.

c. The contractor is to obtain information as to the referral practices and policies of the labor union except that to the extent such information is within the exclusive possession of the labor union and such labor union refuses to furnish such information to the contractor, the contractor shall so certify to the contracting agency and shall set forth what efforts have been made to obtain such information.

d. In the event the union is unable to provide the contractor with a reasonable flow of referrals within the time limit set forth in the collective bargaining agreement, the contractor will, through independent recruitment efforts, fill the employment vacancies without regard to race, color, religion, sex, national origin, age or disability; making full efforts to obtain qualified and/or qualifiable minorities and women. The failure of a union to provide sufficient referrals (even though it is obligated to provide exclusive referrals under the terms of a collective bargaining agreement) does not relieve the contractor from the requirements of this paragraph. In the event the union referral practice prevents the contractor from meeting the obligations pursuant to Executive Order 11246, as amended, and these special provisions, such contractor shall immediately notify the contracting agency.

8. Reasonable Accommodation for Applicants / Employees with Disabilities: The contractor must be familiar

with the requirements for and comply with the Americans with Disabilities Act and all rules and regulations established there under. Employers must provide reasonable accommodation in all employment activities unless to do so would cause an undue hardship.

9. Selection of Subcontractors, Procurement of Materials and Leasing of Equipment: The contractor shall not discriminate on the grounds of race, color, religion, sex, national origin, age or disability in the selection and retention of subcontractors, including procurement of materials and leases of equipment. The contractor shall take all necessary and reasonable steps to ensure nondiscrimination in the administration of this contract.

a. The contractor shall notify all potential subcontractors and suppliers and lessors of their EEO obligations under this contract.

b. The contractor will use good faith efforts to ensure subcontractor compliance with their EEO obligations.

10. Assurance Required by 49 CFR 26.13(b):

a. The requirements of 49 CFR Part 26 and the State DOT's U.S. DOT-approved DBE program are incorporated by reference.

b. The contractor or subcontractor shall not discriminate on the basis of race, color, national origin, or sex in the performance of this contract. The contractor shall carry out applicable requirements of 49 CFR Part 26 in the award and administration of DOT-assisted contracts. Failure by the contractor to carry out these requirements is a material breach of this contract, which may result in the termination of this contract or such other remedy as the contracting agency deems appropriate.

11. Records and Reports: The contractor shall keep such records as necessary to document compliance with the EEO requirements. Such records shall be retained for a period of three years following the date of the final payment to the contractor for all contract work and shall be available at reasonable times and places for inspection by authorized representatives of the contracting agency and the FHWA.

a. The records kept by the contractor shall document the following:

(1) The number and work hours of minority and non-minority group members and women employed in each work classification on the project;

(2) The progress and efforts being made in cooperation with unions, when applicable, to increase employment opportunities for minorities and women; and

(3) The progress and efforts being made in locating, hiring, training, qualifying, and upgrading minorities and women;

b. The contractors and subcontractors will submit an annual report to the contracting agency each July for the duration of the project, indicating the number of minority, women, and non-minority group employees currently engaged in each work classification required by the contract work. This information is to be reported on [Form FHWA-1391](#). The staffing data should represent the project work force on board in all or any part of the last payroll period preceding the end of July. If on-the-job training is being required by special provision, the contractor

will be required to collect and report training data. The employment data should reflect the work force on board during all or any part of the last payroll period preceding the end of July.

III. NONSEGREGATED FACILITIES

This provision is applicable to all Federal-aid construction contracts and to all related construction subcontracts of \$10,000 or more.

The contractor must ensure that facilities provided for employees are provided in such a manner that segregation on the basis of race, color, religion, sex, or national origin cannot result. The contractor may neither require such segregated use by written or oral policies nor tolerate such use by employee custom. The contractor's obligation extends further to ensure that its employees are not assigned to perform their services at any location, under the contractor's control, where the facilities are segregated. The term "facilities" includes waiting rooms, work areas, restaurants and other eating areas, time clocks, restrooms, washrooms, locker rooms, and other storage or dressing areas, parking lots, drinking fountains, recreation or entertainment areas, transportation, and housing provided for employees. The contractor shall provide separate or single-user restrooms and necessary dressing or sleeping areas to assure privacy between sexes.

IV. DAVIS-BACON AND RELATED ACT PROVISIONS

This section is applicable to all Federal-aid construction projects exceeding \$2,000 and to all related subcontracts and lower-tier subcontracts (regardless of subcontract size). The requirements apply to all projects located within the right-of-way of a roadway that is functionally classified as Federal-aid highway. This excludes roadways functionally classified as local roads or rural minor collectors, which are exempt. Contracting agencies may elect to apply these requirements to other projects.

The following provisions are from the U.S. Department of Labor regulations in 29 CFR 5.5 "Contract provisions and related matters" with minor revisions to conform to the FHWA-1273 format and FHWA program requirements.

1. Minimum wages

a. All laborers and mechanics employed or working upon the site of the work, will be paid unconditionally and not less often than once a week, and without subsequent deduction or rebate on any account (except such payroll deductions as are permitted by regulations issued by the Secretary of Labor under the Copeland Act (29 CFR part 3)), the full amount of wages and bona fide fringe benefits (or cash equivalents thereof) due at time of payment computed at rates not less than those contained in the wage determination of the Secretary of Labor which is attached hereto and made a part hereof, regardless of any contractual relationship which may be alleged to exist between the contractor and such laborers and mechanics.

Contributions made or costs reasonably anticipated for bona fide fringe benefits under section 1(b)(2) of the Davis-Bacon Act on behalf of laborers or mechanics are considered wages paid to such laborers or mechanics, subject to the provisions

of paragraph 1.d. of this section; also, regular contributions made or costs incurred for more than a weekly period (but not less often than quarterly) under plans, funds, or programs which cover the particular weekly period, are deemed to be constructively made or incurred during such weekly period. Such laborers and mechanics shall be paid the appropriate wage rate and fringe benefits on the wage determination for the classification of work actually performed, without regard to skill, except as provided in 29 CFR 5.5(a)(4). Laborers or mechanics performing work in more than one classification may be compensated at the rate specified for each classification for the time actually worked therein: Provided, That the employer's payroll records accurately set forth the time spent in each classification in which work is performed. The wage determination (including any additional classification and wage rates conformed under paragraph 1.b. of this section) and the Davis-Bacon poster (WH-1321) shall be posted at all times by the contractor and its subcontractors at the site of the work in a prominent and accessible place where it can be easily seen by the workers.

b. (1) The contracting officer shall require that any class of laborers or mechanics, including helpers, which is not listed in the wage determination and which is to be employed under the contract shall be classified in conformance with the wage determination. The contracting officer shall approve an additional classification and wage rate and fringe benefits therefore only when the following criteria have been met:

(i) The work to be performed by the classification requested is not performed by a classification in the wage determination; and

(ii) The classification is utilized in the area by the construction industry; and

(iii) The proposed wage rate, including any bona fide fringe benefits, bears a reasonable relationship to the wage rates contained in the wage determination.

(2) If the contractor and the laborers and mechanics to be employed in the classification (if known), or their representatives, and the contracting officer agree on the classification and wage rate (including the amount designated for fringe benefits where appropriate), a report of the action taken shall be sent by the contracting officer to the Administrator of the Wage and Hour Division, Employment Standards Administration, U.S. Department of Labor, Washington, DC 20210. The Administrator, or an authorized representative, will approve, modify, or disapprove every additional classification action within 30 days of receipt and so advise the contracting officer or will notify the contracting officer within the 30-day period that additional time is necessary.

(3) In the event the contractor, the laborers or mechanics to be employed in the classification or their representatives, and the contracting officer do not agree on the proposed classification and wage rate (including the amount designated for fringe benefits, where appropriate), the contracting officer shall refer the questions, including the views of all interested parties and the recommendation of the contracting officer, to the Wage and Hour Administrator for determination. The Wage and Hour Administrator, or an authorized representative, will issue a determination within 30 days of receipt and so advise the contracting officer or

will notify the contracting officer within the 30-day period that additional time is necessary.

(4) The wage rate (including fringe benefits where appropriate) determined pursuant to paragraphs 1.b.(2) or 1.b.(3) of this section, shall be paid to all workers performing work in the classification under this contract from the first day on which work is performed in the classification.

c. Whenever the minimum wage rate prescribed in the contract for a class of laborers or mechanics includes a fringe benefit which is not expressed as an hourly rate, the contractor shall either pay the benefit as stated in the wage determination or shall pay another bona fide fringe benefit or an hourly cash equivalent thereof.

d. If the contractor does not make payments to a trustee or other third person, the contractor may consider as part of the wages of any laborer or mechanic the amount of any costs reasonably anticipated in providing bona fide fringe benefits under a plan or program. Provided, That the Secretary of Labor has found, upon the written request of the contractor, that the applicable standards of the Davis-Bacon Act have been met. The Secretary of Labor may require the contractor to set aside in a separate account assets for the meeting of obligations under the plan or program.

2. Withholding

The contracting agency shall upon its own action or upon written request of an authorized representative of the Department of Labor, withhold or cause to be withheld from the contractor under this contract, or any other Federal contract with the same prime contractor, or any other federally-assisted contract subject to Davis-Bacon prevailing wage requirements, which is held by the same prime contractor, so much of the accrued payments or advances as may be considered necessary to pay laborers and mechanics, including apprentices, trainees, and helpers, employed by the contractor or any subcontractor the full amount of wages required by the contract. In the event of failure to pay any laborer or mechanic, including any apprentice, trainee, or helper, employed or working on the site of the work, all or part of the wages required by the contract, the contracting agency may, after written notice to the contractor, take such action as may be necessary to cause the suspension of any further payment, advance, or guarantee of funds until such violations have ceased.

3. Payrolls and basic records

a. Payrolls and basic records relating thereto shall be maintained by the contractor during the course of the work and preserved for a period of three years thereafter for all laborers and mechanics working at the site of the work. Such records shall contain the name, address, and social security number of each such worker, his or her correct classification, hourly rates of wages paid (including rates of contributions or costs anticipated for bona fide fringe benefits or cash equivalents thereof of the types described in section 1(b)(2)(B) of the Davis-Bacon Act), daily and weekly number of hours worked, deductions made and actual wages paid. Whenever the Secretary of Labor has found under 29 CFR 5.5(a)(1)(iv) that the wages of any laborer or mechanic include the amount of any costs reasonably anticipated in providing benefits under a plan or program described in section 1(b)(2)(B) of the Davis-

Bacon Act, the contractor shall maintain records which show that the commitment to provide such benefits is enforceable, that the plan or program is financially responsible, and that the plan or program has been communicated in writing to the laborers or mechanics affected, and records which show the costs anticipated or the actual cost incurred in providing such benefits. Contractors employing apprentices or trainees under approved programs shall maintain written evidence of the registration of apprenticeship programs and certification of trainee programs, the registration of the apprentices and trainees, and the ratios and wage rates prescribed in the applicable programs.

b. (1) The contractor shall submit weekly for each week in which any contract work is performed a copy of all payrolls to the contracting agency. The payrolls submitted shall set out accurately and completely all of the information required to be maintained under 29 CFR 5.5(a)(3)(i), except that full social security numbers and home addresses shall not be included on weekly transmittals. Instead the payrolls shall only need to include an individually identifying number for each employee (e.g., the last four digits of the employee's social security number). The required weekly payroll information may be submitted in any form desired. Optional Form WH-347 is available for this purpose from the Wage and Hour Division Web site at <http://www.dol.gov/esa/whd/forms/wh347instr.htm> or its successor site. The prime contractor is responsible for the submission of copies of payrolls by all subcontractors. Contractors and subcontractors shall maintain the full social security number and current address of each covered worker, and shall provide them upon request to the contracting agency for transmission to the State DOT, the FHWA or the Wage and Hour Division of the Department of Labor for purposes of an investigation or audit of compliance with prevailing wage requirements. It is not a violation of this section for a prime contractor to require a subcontractor to provide addresses and social security numbers to the prime contractor for its own records, without weekly submission to the contracting agency..

(2) Each payroll submitted shall be accompanied by a "Statement of Compliance," signed by the contractor or subcontractor or his or her agent who pays or supervises the payment of the persons employed under the contract and shall certify the following:

(i) That the payroll for the payroll period contains the information required to be provided under §5.5 (a)(3)(ii) of Regulations, 29 CFR part 5, the appropriate information is being maintained under §5.5 (a)(3)(i) of Regulations, 29 CFR part 5, and that such information is correct and complete;

(ii) That each laborer or mechanic (including each helper, apprentice, and trainee) employed on the contract during the payroll period has been paid the full weekly wages earned, without rebate, either directly or indirectly, and that no deductions have been made either directly or indirectly from the full wages earned, other than permissible deductions as set forth in Regulations, 29 CFR part 3;

(iii) That each laborer or mechanic has been paid not less than the applicable wage rates and fringe benefits or cash equivalents for the classification of work performed, as specified in the applicable wage determination incorporated into the contract.

(3) The weekly submission of a properly executed certification set forth on the reverse side of Optional Form WH-347 shall satisfy the requirement for submission of the "Statement of Compliance" required by paragraph 3.b.(2) of this section.

(4) The falsification of any of the above certifications may subject the contractor or subcontractor to civil or criminal prosecution under section 1001 of title 18 and section 231 of title 31 of the United States Code.

c. The contractor or subcontractor shall make the records required under paragraph 3.a. of this section available for inspection, copying, or transcription by authorized representatives of the contracting agency, the State DOT, the FHWA, or the Department of Labor, and shall permit such representatives to interview employees during working hours on the job. If the contractor or subcontractor fails to submit the required records or to make them available, the FHWA may, after written notice to the contractor, the contracting agency or the State DOT, take such action as may be necessary to cause the suspension of any further payment, advance, or guarantee of funds. Furthermore, failure to submit the required records upon request or to make such records available may be grounds for debarment action pursuant to 29 CFR 5.12.

4. Apprentices and trainees

a. Apprentices (programs of the USDOL).

Apprentices will be permitted to work at less than the predetermined rate for the work they performed when they are employed pursuant to and individually registered in a bona fide apprenticeship program registered with the U.S. Department of Labor, Employment and Training Administration, Office of Apprenticeship Training, Employer and Labor Services, or with a State Apprenticeship Agency recognized by the Office, or if a person is employed in his or her first 90 days of probationary employment as an apprentice in such an apprenticeship program, who is not individually registered in the program, but who has been certified by the Office of Apprenticeship Training, Employer and Labor Services or a State Apprenticeship Agency (where appropriate) to be eligible for probationary employment as an apprentice.

The allowable ratio of apprentices to journeymen on the job site in any craft classification shall not be greater than the ratio permitted to the contractor as to the entire work force under the registered program. Any worker listed on a payroll at an apprentice wage rate, who is not registered or otherwise employed as stated above, shall be paid not less than the applicable wage rate on the wage determination for the classification of work actually performed. In addition, any apprentice performing work on the job site in excess of the ratio permitted under the registered program shall be paid not less than the applicable wage rate on the wage determination for the work actually performed. Where a contractor is performing construction on a project in a locality other than that in which its program is registered, the ratios and wage rates (expressed in percentages of the journeyman's hourly rate) specified in the contractor's or subcontractor's registered program shall be observed.

Every apprentice must be paid at not less than the rate specified in the registered program for the apprentice's level of progress, expressed as a percentage of the journeymen hourly

rate specified in the applicable wage determination. Apprentices shall be paid fringe benefits in accordance with the provisions of the apprenticeship program. If the apprenticeship program does not specify fringe benefits, apprentices must be paid the full amount of fringe benefits listed on the wage determination for the applicable classification. If the Administrator determines that a different practice prevails for the applicable apprentice classification, fringes shall be paid in accordance with that determination.

In the event the Office of Apprenticeship Training, Employer and Labor Services, or a State Apprenticeship Agency recognized by the Office, withdraws approval of an apprenticeship program, the contractor will no longer be permitted to utilize apprentices at less than the applicable predetermined rate for the work performed until an acceptable program is approved.

b. Trainees (programs of the USDOL).

Except as provided in 29 CFR 5.16, trainees will not be permitted to work at less than the predetermined rate for the work performed unless they are employed pursuant to and individually registered in a program which has received prior approval, evidenced by formal certification by the U.S. Department of Labor, Employment and Training Administration.

The ratio of trainees to journeymen on the job site shall not be greater than permitted under the plan approved by the Employment and Training Administration.

Every trainee must be paid at not less than the rate specified in the approved program for the trainee's level of progress, expressed as a percentage of the journeyman hourly rate specified in the applicable wage determination. Trainees shall be paid fringe benefits in accordance with the provisions of the trainee program. If the trainee program does not mention fringe benefits, trainees shall be paid the full amount of fringe benefits listed on the wage determination unless the Administrator of the Wage and Hour Division determines that there is an apprenticeship program associated with the corresponding journeyman wage rate on the wage determination which provides for less than full fringe benefits for apprentices. Any employee listed on the payroll at a trainee rate who is not registered and participating in a training plan approved by the Employment and Training Administration shall be paid not less than the applicable wage rate on the wage determination for the classification of work actually performed. In addition, any trainee performing work on the job site in excess of the ratio permitted under the registered program shall be paid not less than the applicable wage rate on the wage determination for the work actually performed.

In the event the Employment and Training Administration withdraws approval of a training program, the contractor will no longer be permitted to utilize trainees at less than the applicable predetermined rate for the work performed until an acceptable program is approved.

c. Equal employment opportunity. The utilization of apprentices, trainees and journeymen under this part shall be in conformity with the equal employment opportunity requirements of Executive Order 11246, as amended, and 29 CFR part 30.

d. Apprentices and Trainees (programs of the U.S. DOT).

Apprentices and trainees working under apprenticeship and skill training programs which have been certified by the Secretary of Transportation as promoting EEO in connection with Federal-aid highway construction programs are not subject to the requirements of paragraph 4 of this Section IV. The straight time hourly wage rates for apprentices and trainees under such programs will be established by the particular programs. The ratio of apprentices and trainees to journeymen shall not be greater than permitted by the terms of the particular program.

5. Compliance with Copeland Act requirements. The contractor shall comply with the requirements of 29 CFR part 3, which are incorporated by reference in this contract.

6. Subcontracts. The contractor or subcontractor shall insert Form FHWA-1273 in any subcontracts and also require the subcontractors to include Form FHWA-1273 in any lower tier subcontracts. The prime contractor shall be responsible for the compliance by any subcontractor or lower tier subcontractor with all the contract clauses in 29 CFR 5.5.

7. Contract termination: debarment. A breach of the contract clauses in 29 CFR 5.5 may be grounds for termination of the contract, and for debarment as a contractor and a subcontractor as provided in 29 CFR 5.12.

8. Compliance with Davis-Bacon and Related Act requirements. All rulings and interpretations of the Davis-Bacon and Related Acts contained in 29 CFR parts 1, 3, and 5 are herein incorporated by reference in this contract.

9. Disputes concerning labor standards. Disputes arising out of the labor standards provisions of this contract shall not be subject to the general disputes clause of this contract. Such disputes shall be resolved in accordance with the procedures of the Department of Labor set forth in 29 CFR parts 5, 6, and 7. Disputes within the meaning of this clause include disputes between the contractor (or any of its subcontractors) and the contracting agency, the U.S. Department of Labor, or the employees or their representatives.

10. Certification of eligibility.

a. By entering into this contract, the contractor certifies that neither it (nor he or she) nor any person or firm who has an interest in the contractor's firm is a person or firm ineligible to be awarded Government contracts by virtue of section 3(a) of the Davis-Bacon Act or 29 CFR 5.12(a)(1).

b. No part of this contract shall be subcontracted to any person or firm ineligible for award of a Government contract by virtue of section 3(a) of the Davis-Bacon Act or 29 CFR 5.12(a)(1).

c. The penalty for making false statements is prescribed in the U.S. Criminal Code, 18 U.S.C. 1001.

V. CONTRACT WORK HOURS AND SAFETY STANDARDS ACT

The following clauses apply to any Federal-aid construction contract in an amount in excess of \$100,000 and subject to the overtime provisions of the Contract Work Hours and Safety Standards Act. These clauses shall be inserted in addition to the clauses required by 29 CFR 5.5(a) or 29 CFR 4.6. As used in this paragraph, the terms laborers and mechanics include watchmen and guards.

1. Overtime requirements. No contractor or subcontractor contracting for any part of the contract work which may require or involve the employment of laborers or mechanics shall require or permit any such laborer or mechanic in any workweek in which he or she is employed on such work to work in excess of forty hours in such workweek unless such laborer or mechanic receives compensation at a rate not less than one and one-half times the basic rate of pay for all hours worked in excess of forty hours in such workweek.

2. Violation; liability for unpaid wages; liquidated damages. In the event of any violation of the clause set forth in paragraph (1.) of this section, the contractor and any subcontractor responsible therefor shall be liable for the unpaid wages. In addition, such contractor and subcontractor shall be liable to the United States (in the case of work done under contract for the District of Columbia or a territory, to such District or to such territory), for liquidated damages. Such liquidated damages shall be computed with respect to each individual laborer or mechanic, including watchmen and guards, employed in violation of the clause set forth in paragraph (1.) of this section, in the sum of \$10 for each calendar day on which such individual was required or permitted to work in excess of the standard workweek of forty hours without payment of the overtime wages required by the clause set forth in paragraph (1.) of this section.

3. Withholding for unpaid wages and liquidated damages. The FHWA or the contracting agency shall upon its own action or upon written request of an authorized representative of the Department of Labor withhold or cause to be withheld, from any moneys payable on account of work performed by the contractor or subcontractor under any such contract or any other Federal contract with the same prime contractor, or any other federally-assisted contract subject to the Contract Work Hours and Safety Standards Act, which is held by the same prime contractor, such sums as may be determined to be necessary to satisfy any liabilities of such contractor or subcontractor for unpaid wages and liquidated damages as provided in the clause set forth in paragraph (2.) of this section.

4. Subcontracts. The contractor or subcontractor shall insert in any subcontracts the clauses set forth in paragraph (1.) through (4.) of this section and also a clause requiring the subcontractors to include these clauses in any lower tier subcontracts. The prime contractor shall be responsible for compliance by any subcontractor or lower tier subcontractor with the clauses set forth in paragraphs (1.) through (4.) of this section.

VI. SUBLETTING OR ASSIGNING THE CONTRACT

This provision is applicable to all Federal-aid construction contracts on the National Highway System.

1. The contractor shall perform with its own organization contract work amounting to not less than 30 percent (or a greater percentage if specified elsewhere in the contract) of the total original contract price, excluding any specialty items designated by the contracting agency. Specialty items may be performed by subcontract and the amount of any such specialty items performed may be deducted from the total original contract price before computing the amount of work required to be performed by the contractor's own organization (23 CFR 635.116).

a. The term "perform work with its own organization" refers to workers employed or leased by the prime contractor, and equipment owned or rented by the prime contractor, with or without operators. Such term does not include employees or equipment of a subcontractor or lower tier subcontractor, agents of the prime contractor, or any other assignees. The term may include payments for the costs of hiring leased employees from an employee leasing firm meeting all relevant Federal and State regulatory requirements. Leased employees may only be included in this term if the prime contractor meets all of the following conditions:

(1) the prime contractor maintains control over the supervision of the day-to-day activities of the leased employees;

(2) the prime contractor remains responsible for the quality of the work of the leased employees;

(3) the prime contractor retains all power to accept or exclude individual employees from work on the project; and

(4) the prime contractor remains ultimately responsible for the payment of predetermined minimum wages, the submission of payrolls, statements of compliance and all other Federal regulatory requirements.

b. "Specialty Items" shall be construed to be limited to work that requires highly specialized knowledge, abilities, or equipment not ordinarily available in the type of contracting organizations qualified and expected to bid or propose on the contract as a whole and in general are to be limited to minor components of the overall contract.

2. The contract amount upon which the requirements set forth in paragraph (1) of Section VI is computed includes the cost of material and manufactured products which are to be purchased or produced by the contractor under the contract provisions.

3. The contractor shall furnish (a) a competent superintendent or supervisor who is employed by the firm, has full authority to direct performance of the work in accordance with the contract requirements, and is in charge of all construction operations (regardless of who performs the work) and (b) such other of its own organizational resources (supervision, management, and engineering services) as the contracting officer determines is necessary to assure the performance of the contract.

4. No portion of the contract shall be sublet, assigned or otherwise disposed of except with the written consent of the contracting officer, or authorized representative, and such consent when given shall not be construed to relieve the contractor of any responsibility for the fulfillment of the contract. Written consent will be given only after the contracting agency has assured that each subcontract is

evidenced in writing and that it contains all pertinent provisions and requirements of the prime contract.

5. The 30% self-performance requirement of paragraph (1) is not applicable to design-build contracts; however, contracting agencies may establish their own self-performance requirements.

VII. SAFETY: ACCIDENT PREVENTION

This provision is applicable to all Federal-aid construction contracts and to all related subcontracts.

1. In the performance of this contract the contractor shall comply with all applicable Federal, State, and local laws governing safety, health, and sanitation (23 CFR 635). The contractor shall provide all safeguards, safety devices and protective equipment and take any other needed actions as it determines, or as the contracting officer may determine, to be reasonably necessary to protect the life and health of employees on the job and the safety of the public and to protect property in connection with the performance of the work covered by the contract.

2. It is a condition of this contract, and shall be made a condition of each subcontract, which the contractor enters into pursuant to this contract, that the contractor and any subcontractor shall not permit any employee, in performance of the contract, to work in surroundings or under conditions which are unsanitary, hazardous or dangerous to his/her health or safety, as determined under construction safety and health standards (29 CFR 1926) promulgated by the Secretary of Labor, in accordance with Section 107 of the Contract Work Hours and Safety Standards Act (40 U.S.C. 3704).

3. Pursuant to 29 CFR 1926.3, it is a condition of this contract that the Secretary of Labor or authorized representative thereof, shall have right of entry to any site of contract performance to inspect or investigate the matter of compliance with the construction safety and health standards and to carry out the duties of the Secretary under Section 107 of the Contract Work Hours and Safety Standards Act (40 U.S.C.3704).

VIII. FALSE STATEMENTS CONCERNING HIGHWAY PROJECTS

This provision is applicable to all Federal-aid construction contracts and to all related subcontracts.

In order to assure high quality and durable construction in conformity with approved plans and specifications and a high degree of reliability on statements and representations made by engineers, contractors, suppliers, and workers on Federal-aid highway projects, it is essential that all persons concerned with the project perform their functions as carefully, thoroughly, and honestly as possible. Willful falsification, distortion, or misrepresentation with respect to any facts related to the project is a violation of Federal law. To prevent any misunderstanding regarding the seriousness of these and similar acts, Form FHWA-1022 shall be posted on each Federal-aid highway project (23 CFR 635) in one or more places where it is readily available to all persons concerned with the project:

18 U.S.C. 1020 reads as follows:

"Whoever, being an officer, agent, or employee of the United States, or of any State or Territory, or whoever, whether a person, association, firm, or corporation, knowingly makes any false statement, false representation, or false report as to the character, quality, quantity, or cost of the material used or to be used, or the quantity or quality of the work performed or to be performed, or the cost thereof in connection with the submission of plans, maps, specifications, contracts, or costs of construction on any highway or related project submitted for approval to the Secretary of Transportation; or

Whoever knowingly makes any false statement, false representation, false report or false claim with respect to the character, quality, quantity, or cost of any work performed or to be performed, or materials furnished or to be furnished, in connection with the construction of any highway or related project approved by the Secretary of Transportation; or

Whoever knowingly makes any false statement or false representation as to material fact in any statement, certificate, or report submitted pursuant to provisions of the Federal-aid Roads Act approved July 1, 1916, (39 Stat. 355), as amended and supplemented;

Shall be fined under this title or imprisoned not more than 5 years or both."

IX. IMPLEMENTATION OF CLEAN AIR ACT AND FEDERAL WATER POLLUTION CONTROL ACT

This provision is applicable to all Federal-aid construction contracts and to all related subcontracts.

By submission of this bid/proposal or the execution of this contract, or subcontract, as appropriate, the bidder, proposer, Federal-aid construction contractor, or subcontractor, as appropriate, will be deemed to have stipulated as follows:

1. That any person who is or will be utilized in the performance of this contract is not prohibited from receiving an award due to a violation of Section 508 of the Clean Water Act or Section 306 of the Clean Air Act.

2. That the contractor agrees to include or cause to be included the requirements of paragraph (1) of this Section X in every subcontract, and further agrees to take such action as the contracting agency may direct as a means of enforcing such requirements.

X. CERTIFICATION REGARDING DEBARMENT, SUSPENSION, INELIGIBILITY AND VOLUNTARY EXCLUSION

This provision is applicable to all Federal-aid construction contracts, design-build contracts, subcontracts, lower-tier subcontracts, purchase orders, lease agreements, consultant contracts or any other covered transaction requiring FHWA approval or that is estimated to cost \$25,000 or more – as defined in 2 CFR Parts 180 and 1200.

1. Instructions for Certification – First Tier Participants:

a. By signing and submitting this proposal, the prospective first tier participant is providing the certification set out below.

b. The inability of a person to provide the certification set out below will not necessarily result in denial of participation in this

covered transaction. The prospective first tier participant shall submit an explanation of why it cannot provide the certification set out below. The certification or explanation will be considered in connection with the department or agency's determination whether to enter into this transaction. However, failure of the prospective first tier participant to furnish a certification or an explanation shall disqualify such a person from participation in this transaction.

c. The certification in this clause is a material representation of fact upon which reliance was placed when the contracting agency determined to enter into this transaction. If it is later determined that the prospective participant knowingly rendered an erroneous certification, in addition to other remedies available to the Federal Government, the contracting agency may terminate this transaction for cause of default.

d. The prospective first tier participant shall provide immediate written notice to the contracting agency to whom this proposal is submitted if any time the prospective first tier participant learns that its certification was erroneous when submitted or has become erroneous by reason of changed circumstances.

e. The terms "covered transaction," "debarred," "suspended," "ineligible," "participant," "person," "principal," and "voluntarily excluded," as used in this clause, are defined in 2 CFR Parts 180 and 1200. "First Tier Covered Transactions" refers to any covered transaction between a grantee or subgrantee of Federal funds and a participant (such as the prime or general contract). "Lower Tier Covered Transactions" refers to any covered transaction under a First Tier Covered Transaction (such as subcontracts). "First Tier Participant" refers to the participant who has entered into a covered transaction with a grantee or subgrantee of Federal funds (such as the prime or general contractor). "Lower Tier Participant" refers any participant who has entered into a covered transaction with a First Tier Participant or other Lower Tier Participants (such as subcontractors and suppliers).

f. The prospective first tier participant agrees by submitting this proposal that, should the proposed covered transaction be entered into, it shall not knowingly enter into any lower tier covered transaction with a person who is debarred, suspended, declared ineligible, or voluntarily excluded from participation in this covered transaction, unless authorized by the department or agency entering into this transaction.

g. The prospective first tier participant further agrees by submitting this proposal that it will include the clause titled "Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion-Lower Tier Covered Transactions," provided by the department or contracting agency, entering into this covered transaction, without modification, in all lower tier covered transactions and in all solicitations for lower tier covered transactions exceeding the \$25,000 threshold.

h. A participant in a covered transaction may rely upon a certification of a prospective participant in a lower tier covered transaction that is not debarred, suspended, ineligible, or voluntarily excluded from the covered transaction, unless it knows that the certification is erroneous. A participant is responsible for ensuring that its principals are not suspended, debarred, or otherwise ineligible to participate in covered transactions. To verify the eligibility of its principals, as well as the eligibility of any lower tier prospective participants, each participant may, but is not required to, check the Excluded Parties List System website (<https://www.epls.gov/>), which is compiled by the General Services Administration.

i. Nothing contained in the foregoing shall be construed to require the establishment of a system of records in order to render in good faith the certification required by this clause. The knowledge and information of the prospective participant is not required to exceed that which is normally possessed by a prudent person in the ordinary course of business dealings.

j. Except for transactions authorized under paragraph (f) of these instructions, if a participant in a covered transaction knowingly enters into a lower tier covered transaction with a person who is suspended, debarred, ineligible, or voluntarily excluded from participation in this transaction, in addition to other remedies available to the Federal Government, the department or agency may terminate this transaction for cause or default.

* * * * *

2. Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion – First Tier Participants:

a. The prospective first tier participant certifies to the best of its knowledge and belief, that it and its principals:

(1) Are not presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from participating in covered transactions by any Federal department or agency;

(2) Have not within a three-year period preceding this proposal been convicted of or had a civil judgment rendered against them for commission of fraud or a criminal offense in connection with obtaining, attempting to obtain, or performing a public (Federal, State or local) transaction or contract under a public transaction; violation of Federal or State antitrust statutes or commission of embezzlement, theft, forgery, bribery, falsification or destruction of records, making false statements, or receiving stolen property;

(3) Are not presently indicted for or otherwise criminally or civilly charged by a governmental entity (Federal, State or local) with commission of any of the offenses enumerated in paragraph (a)(2) of this certification; and

(4) Have not within a three-year period preceding this application/proposal had one or more public transactions (Federal, State or local) terminated for cause or default.

b. Where the prospective participant is unable to certify to any of the statements in this certification, such prospective participant shall attach an explanation to this proposal.

2. Instructions for Certification - Lower Tier Participants:

(Applicable to all subcontracts, purchase orders and other lower tier transactions requiring prior FHWA approval or estimated to cost \$25,000 or more - 2 CFR Parts 180 and 1200)

a. By signing and submitting this proposal, the prospective lower tier is providing the certification set out below.

b. The certification in this clause is a material representation of fact upon which reliance was placed when this transaction was entered into. If it is later determined that the prospective lower tier participant knowingly rendered an erroneous certification, in addition to other remedies available to the Federal Government, the department, or agency with which

this transaction originated may pursue available remedies, including suspension and/or debarment.

c. The prospective lower tier participant shall provide immediate written notice to the person to which this proposal is submitted if at any time the prospective lower tier participant learns that its certification was erroneous by reason of changed circumstances.

d. The terms "covered transaction," "debarred," "suspended," "ineligible," "participant," "person," "principal," and "voluntarily excluded," as used in this clause, are defined in 2 CFR Parts 180 and 1200. You may contact the person to which this proposal is submitted for assistance in obtaining a copy of those regulations. "First Tier Covered Transactions" refers to any covered transaction between a grantee or subgrantee of Federal funds and a participant (such as the prime or general contract). "Lower Tier Covered Transactions" refers to any covered transaction under a First Tier Covered Transaction (such as subcontracts). "First Tier Participant" refers to the participant who has entered into a covered transaction with a grantee or subgrantee of Federal funds (such as the prime or general contractor). "Lower Tier Participant" refers any participant who has entered into a covered transaction with a First Tier Participant or other Lower Tier Participants (such as subcontractors and suppliers).

e. The prospective lower tier participant agrees by submitting this proposal that, should the proposed covered transaction be entered into, it shall not knowingly enter into any lower tier covered transaction with a person who is debarred, suspended, declared ineligible, or voluntarily excluded from participation in this covered transaction, unless authorized by the department or agency with which this transaction originated.

f. The prospective lower tier participant further agrees by submitting this proposal that it will include this clause titled "Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion-Lower Tier Covered Transaction," without modification, in all lower tier covered transactions and in all solicitations for lower tier covered transactions exceeding the \$25,000 threshold.

g. A participant in a covered transaction may rely upon a certification of a prospective participant in a lower tier covered transaction that is not debarred, suspended, ineligible, or voluntarily excluded from the covered transaction, unless it knows that the certification is erroneous. A participant is responsible for ensuring that its principals are not suspended, debarred, or otherwise ineligible to participate in covered transactions. To verify the eligibility of its principals, as well as the eligibility of any lower tier prospective participants, each participant may, but is not required to, check the Excluded Parties List System website (<https://www.epls.gov/>), which is compiled by the General Services Administration.

h. Nothing contained in the foregoing shall be construed to require establishment of a system of records in order to render in good faith the certification required by this clause. The knowledge and information of participant is not required to exceed that which is normally possessed by a prudent person in the ordinary course of business dealings.

i. Except for transactions authorized under paragraph e of these instructions, if a participant in a covered transaction knowingly enters into a lower tier covered transaction with a person who is suspended, debarred, ineligible, or voluntarily excluded from participation in this transaction, in addition to other remedies available to the Federal Government, the

department or agency with which this transaction originated may pursue available remedies, including suspension and/or debarment.

* * * * *

Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion--Lower Tier Participants:

1. The prospective lower tier participant certifies, by submission of this proposal, that neither it nor its principals is presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from participating in covered transactions by any Federal department or agency.

2. Where the prospective lower tier participant is unable to certify to any of the statements in this certification, such prospective participant shall attach an explanation to this proposal.

* * * * *

XI. CERTIFICATION REGARDING USE OF CONTRACT FUNDS FOR LOBBYING

This provision is applicable to all Federal-aid construction contracts and to all related subcontracts which exceed \$100,000 (49 CFR 20).

1. The prospective participant certifies, by signing and submitting this bid or proposal, to the best of his or her knowledge and belief, that:

a. No Federal appropriated funds have been paid or will be paid, by or on behalf of the undersigned, to any person for influencing or attempting to influence an officer or employee of any Federal agency, a Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress in connection with the awarding of any Federal contract, the making of any Federal grant, the making of any Federal loan, the entering into of any cooperative agreement, and the extension, continuation, renewal, amendment, or modification of any Federal contract, grant, loan, or cooperative agreement.

b. If any funds other than Federal appropriated funds have been paid or will be paid to any person for influencing or attempting to influence an officer or employee of any Federal agency, a Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress in connection with this Federal contract, grant, loan, or cooperative agreement, the undersigned shall complete and submit Standard Form-LLL, "Disclosure Form to Report Lobbying," in accordance with its instructions.

2. This certification is a material representation of fact upon which reliance was placed when this transaction was made or entered into. Submission of this certification is a prerequisite for making or entering into this transaction imposed by 31 U.S.C. 1352. Any person who fails to file the required certification shall be subject to a civil penalty of not less than \$10,000 and not more than \$100,000 for each such failure.

3. The prospective participant also agrees by submitting its bid or proposal that the participant shall require that the language of this certification be included in all lower tier subcontracts, which exceed \$100,000 and that all such recipients shall certify and disclose accordingly.

**ATTACHMENT A - EMPLOYMENT AND MATERIALS
PREFERENCE FOR APPALACHIAN DEVELOPMENT
HIGHWAY SYSTEM OR APPALACHIAN LOCAL ACCESS
ROAD CONTRACTS**

This provision is applicable to all Federal-aid projects funded under the Appalachian Regional Development Act of 1965.

1. During the performance of this contract, the contractor undertaking to do work which is, or reasonably may be, done as on-site work, shall give preference to qualified persons who regularly reside in the labor area as designated by the DOL wherein the contract work is situated, or the subregion, or the Appalachian counties of the State wherein the contract work is situated, except:

a. To the extent that qualified persons regularly residing in the area are not available.

b. For the reasonable needs of the contractor to employ supervisory or specially experienced personnel necessary to assure an efficient execution of the contract work.

c. For the obligation of the contractor to offer employment to present or former employees as the result of a lawful collective bargaining contract, provided that the number of nonresident persons employed under this subparagraph (1c) shall not exceed 20 percent of the total number of employees employed by the contractor on the contract work, except as provided in subparagraph (4) below.

2. The contractor shall place a job order with the State Employment Service indicating (a) the classifications of the laborers, mechanics and other employees required to perform the contract work, (b) the number of employees required in each classification, (c) the date on which the participant estimates such employees will be required, and (d) any other pertinent information required by the State Employment Service to complete the job order form. The job order may be placed with the State Employment Service in writing or by telephone. If during the course of the contract work, the information submitted by the contractor in the original job order is substantially modified, the participant shall promptly notify the State Employment Service.

3. The contractor shall give full consideration to all qualified job applicants referred to him by the State Employment Service. The contractor is not required to grant employment to any job applicants who, in his opinion, are not qualified to perform the classification of work required.

4. If, within one week following the placing of a job order by the contractor with the State Employment Service, the State Employment Service is unable to refer any qualified job applicants to the contractor, or less than the number requested, the State Employment Service will forward a certificate to the contractor indicating the unavailability of applicants. Such certificate shall be made a part of the contractor's permanent project records. Upon receipt of this certificate, the contractor may employ persons who do not normally reside in the labor area to fill positions covered by the certificate, notwithstanding the provisions of subparagraph (1c) above.

5. The provisions of 23 CFR 633.207(e) allow the contracting agency to provide a contractual preference for the use of mineral resource materials native to the Appalachian region.

6. The contractor shall include the provisions of Sections 1 through 4 of this Attachment A in every subcontract for work which is, or reasonably may be, done as on-site work.

SEPTEMBER 2002

**NOTICE OF REQUIREMENT FOR AFFIRMATIVE ACTION TO ENSURE
EQUAL EMPLOYMENT OPPORTUNITY (EXECUTIVE ORDER 11246)**

1. The Offeror's or Bidder's attention is called to the "Employment Practices" and "Equal Opportunity Clause" set forth in the Required Contract Provisions, FHWA 1273.
2. The goals and timetables for minority and female participation expressed in percentage terms for the contractor's aggregate work force in each trade, on all construction work in the covered area, are as follows:

Goals for Minority Participation for Each Trade:

<u>County</u>	<u>%</u>	<u>County</u>	<u>%</u>	<u>County</u>	<u>%</u>
Adams	1.7	Iowa	1.7	Polk	2.2
Ashland	1.2	Iron	1.2	Portage	0.6
Barron	0.6	Jackson	0.6	Price	0.6
Bayfield	1.2	Jefferson	7.0	Racine	8.4
Brown	1.3	Juneau	0.6	Richland	1.7
Buffalo	0.6	Kenosha	3.0	Rock	3.1
Burnett	2.2	Kewaunee	1.0	Rusk	0.6
Calumet	0.9	La Crosse	0.9	St. Croix	2.9
Chippewa	0.5	Lafayette	0.5	Sauk	1.7
Clark	0.6	Langlade	0.6	Sawyer	0.6
Columbia	1.7	Lincoln	0.6	Shawano	1.0
Crawford	0.5	Manitowoc	1.0	Sheboygan	7.0
Dane	2.2	Marathon	0.6	Taylor	0.6
Dodge	7.0	Marinette	1.0	Trempealeau	0.6
Door	1.0	Marquette	1.7	Vernon	0.6
Douglas	1.0	Menominee	1.0	Vilas	0.6
Dunn	0.6	Milwaukee	8.0	Walworth	7.0
Eau Claire	0.5	Monroe	0.6	Washburn	0.6
Florence	1.0	Oconto	1.0	Washington	8.0
Fond du Lac	1.0	Oneida	0.6	Waukesha	8.0
Forest	1.0	Outagamie	0.9	Waupaca	1.0
Grant	0.5	Ozaukee	8.0	Waushara	1.0
Green	1.7	Pepin	0.6	Winnebago	0.9
Green Lake	1.0	Pierce	2.2	Wood	0.6

Goals for female participation for each trade: 6.9%

These goals are applicable to all the contractor's construction work, (whether or not it is federal or federally assisted), performed in the covered area. If the contractor performs construction work in the geographical area located outside of the covered area, it shall apply the goals established for such geographical area where the work is actually performed. With regard to this second area, the contractor also is subject to the goals for both its federally involved and nonfederally involved construction.

The contractor's compliance with the Executive Order and the Regulations in 41 CFR Part 60-4 shall be based on its implementation of the Equal Opportunity Clause, specific affirmative action obligations required by the specifications set forth in 41 CFR 60-4.3(a), and its efforts to meet the goals. The hours of minority and female employment and training must be substantially uniform throughout the length of the contract, and in each trade, and the contractor shall make a good faith effort to employ minorities and women evenly on each of its projects. The transfer of minority or female employees or trainees from contractor to contractor or from project to project for the sole purpose of meeting the contractor's goals shall be a violation of the contract, the Executive Order and the Regulations in 41 CFR Part 60-4. Compliance with the goals will be measured against the total work hours performed.

3. The contractor shall provide written notification to the Director of the Office of Federal Contract Compliance Programs within ten (10) working days of award of any construction subcontract in excess of \$10,000.00 at any tier for construction work under the contract resulting from this solicitation. The notification shall list the name, address and telephone number of the subcontractor, employer identification number of the subcontractor; estimated dollar amount of the subcontract; estimated starting and completion dates of the subcontract; and the geographical area in which the subcontract is to be performed.

As referred to in this section, the Director means:

Director
Office of Federal Contract Compliance Programs
Ruess Federal Plaza
310 W. Wisconsin Ave., Suite 1115
Milwaukee, WI 53202

The "Employer Identification Number" means the Federal Social Security number used on the Employer's Quarterly Federal Tax Return, U.S. Treasury Department Form 941.

4. As used in this notice, and in the contract resulting from solicitation, the "covered area" is the county(ies) in Wisconsin to which this proposal applies.

APRIL 2013

ADDITIONAL FEDERAL-AID PROVISIONS

NOTICE TO ALL BIDDERS

To report bid rigging activities call:

1-800-424-9071

The U.S. Department of Transportation (DOT) operates the above toll-free "hotline" Monday through Friday, 8:00 a.m. to 5:00 p.m., Eastern Time. Anyone with knowledge of possible bid rigging, bidding collusion, or other fraudulent activities should use the "hotline" to report such activities.

The "hotline" is part of the DOT's continuing effort to identify and investigate highway construction contract fraud and abuse and is operated under the direction of the DOT Inspector General. All information will be treated confidentially and caller anonymity will be respected.

DECEMBER 2013

BUY AMERICA PROVISION

All steel and iron materials permanently incorporated in this project shall be domestic products and all manufacturing and coating processes for these materials from smelting forward in the manufacturing process must have occurred within the United States. Coating includes epoxy coating, galvanizing, painting and any other coating that protects or enhances the value of a material subject to the requirements of Buy America. The exemption of this requirement is the minimal use of foreign materials if the total cost of such material permanently incorporated in the product does not exceed one-tenth of one percent (1/10 of 1%) of the total contract cost or \$2,500.00, whichever is greater. For purposes of this paragraph, the cost is that shown to be the value of the subject products as they are delivered to the project. The contractor shall take actions and provide documentation conforming to CMM 2-28.5 to ensure compliance with this "Buy America" provision.

<http://roadwaystandards.dot.wi.gov/standards/cmm/cm-02-28.pdf#cm2-28.5>

Upon completion of the project certify to the engineer, in writing using department form WS4567, that all steel, iron, and coating processes for steel or iron incorporated into the contract work conform to these "Buy America" provisions. Attach a list of exemptions and their associated costs to the certification form. Department form WS4567 is available at:

<http://roadwaystandards.dot.wi.gov/standards/forms/ws4567.doc>

Effective with September 2004 Letting

**WISCONSIN DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS AND TRANSPORTATION FACILITIES**

SUPPLEMENTAL REQUIRED CONTRACT PROVISIONS

- I. Wage Rates, Hours of labor and payment of Wages
- II. Payroll Requirements
- III. Postings at the Site of the Work
- IV. Affidavits
- V. Wage Rate Redistribution
- VI. Additional Classifications

I. WAGE RATES, HOURS OF LABOR AND PAYMENT OF WAGES

The schedule of "Minimum Wage Rates" attached hereto and made a part hereof furnishes the prevailing wage rates that have been determined pursuant to Section 103.50 of the Wisconsin Statutes. These wage rates are the minimum required to be paid to the various laborers, workers, mechanics and truck drivers employed by contractors and subcontractors on the construction work embraced by the contract and subject to prevailing hours and wages under Section 103.50, Stats. If necessary to employ laborers, workers, mechanics or truck drivers whose classification is not listed on the schedule, they shall be paid at rates conformable to those listed for similar classifications. Apprentices shall be paid at rates not less than those prescribed in their state indenture contracts.

While the wage rates shown are the minimum rates required by the contract to be paid during its life, this is not a representation that labor can be obtained at these rates. It is the responsibility of bidders to inform themselves as to the local labor conditions and prospective changes or adjustments of wage rates. No increase in the contract price shall be allowed or authorized on account of the payment of wage rates in excess of those listed herein.

Pursuant to Section 103.50 of the Wisconsin Statutes, the prevailing hours of labor have been determined to be up to 10 hours per day and 40 hours per calendar week Monday through Friday. If any laborer, worker, mechanic or truck driver is permitted or required to work more than the prevailing number of hours per day or per calendar week on this contract, they shall be paid for all hours in excess of the prevailing hours at a rate of at least one and one-half (1 1/2) times their hourly rate of pay. All work on Saturday, Sunday and the following holidays is to be paid at time and a half: (1) January 1, (2) the last Monday in May, (3) July 4, (4) the first Monday in September, (5) the fourth Thursday in November, (6) December 25, (7) the day before if January 1, July 4 or December 25 falls on a Saturday and (8) the day following if January 1, July 4 or December 25 falls on a Sunday.

All laborers, workers, mechanics and truck drivers shall be paid unconditionally not less often than once a week. Persons who own and operate their own trucks must receive the prevailing truck driver rate for the applicable type of truck (i.e. 2 axle, 3 or more axle, articulated, eculid or dumptor) he or she operates, plus an agreed upon amount for the use of his or her truck. Every owner-operator MUST be paid separately for their driving and for the use of their truck.

For those projects subject to the requirements of the Davis-Bacon Act, the Secretary of Labor will also have determined "Minimum Wage Rates" for work to be performed under the contract. These rates are, for all or most of the labor, worker, mechanic or truck driver classifications, identical to those established under Section 103.50 of the Wisconsin Statutes. In the event the rates are not identical, the higher of the two rates will govern.

II. PAYROLL REQUIREMENTS

All contractors and subcontractors must submit weekly Certified Payrolls and Compliance Statement verifying that all laborers, workers, mechanics and truck drivers working on the project have been paid the prevailing wage rates for all work performed under the contract required by Section 103.50 of the Wisconsin Statutes.

III. POSTINGS AT THE SITE OF THE WORK

In addition to the required postings furnished by the Department, the contractor shall post the following in at least one conspicuous place at the site of work:

- a. "NOTICE TO EMPLOYEES," which provides information required to be posted by the provisions of Section 103.50 of the Wisconsin Statutes.
- b. A copy of the State of Wisconsin Minimum Wages Rates. (Four pages.)
- c. A copy of the contractor's Equal Employment Opportunity Policy.
- d. On any project involving federal aid, in addition to the furnished postings, the contractor shall post a copy of the "Davis-Bacon Act, Minimum Wage Rates". (Three pages.)

IV. WAGE RATE REDISTRIBUTION

The amount specified as the hourly basic rate of pay and the amount(s) specified as the fringe benefit contribution(s), for all classes of laborers, workers, mechanics or truck drivers may be redistributed, when necessary, to conform to those specified in any applicable collective bargaining agreement, provided that both parties to such agreement

request and receive the approval for any such redistribution from both the Department of Transportation and the Department of Workforce Development prior to the implementation of such redistribution.

V. ADDITIONAL CLASSIFICATIONS

Any unlisted laborer or mechanic classification that is needed to perform work on this project, and is not included within the scope of any of the classifications listed in the application prevailing wage rate determination, may be added after award only if all of the following criteria have been met:

1. The affected employer(s) must make a written request to WisDOT Central Office to utilize the unlisted classification on this project.
2. The request must indicate the scope of the work to be performed by the unlisted classification and must indicate the proposed wage/fringe benefit package that the unlisted classification is to receive.
3. The work to be performed by the unlisted classification must not be performed by a classification that is included in the applicable prevailing wage rate determination.
4. The unlisted classification must be commonly employed in the area where the project is located.
5. The proposed wage/fringe benefit package must bear a reasonable relationship to those set forth in the applicable prevailing wage rate determination.
6. The request should be made prior to the actual performance of the work by the unlisted classification.
7. DWD must approve the use of the unlisted classification and the proposed wage/fringe benefit package. USDOL also must approve the use of the unlisted classification and the proposed wage/fringe benefit package on federal aid projects.
8. WisDOT and DWD may amend the proposed wage/fringe benefit package, as deemed necessary, and may set forth specific employment ratios and scope of work requirements in the approval document.

The approved wage/fringe benefit package shall be paid to all laborers, workers, mechanics or truck drivers performing work within the scope of that performed by the unlisted classification, from the first day on which such work is performed. In the event that work is performed by the unlisted classification prior to approval, the wage/fringe benefit package to be paid for such work must be in conformance with the wage/fringe

benefit package approved for such work. Under this arrangement a retroactive adjustment in wages and/or fringe benefits may be required to be made to the affected laborers, workers, mechanics or truck drivers by the affected employer(s).

**ANNUAL PREVAILING WAGE RATE DETERMINATION
FOR ALL STATE HIGHWAY PROJECTS
DANE COUNTY**

Compiled by the State of Wisconsin - Department of Workforce Development
for the Department of Transportation
Pursuant to s. 103.50, Stats.
Issued on January 1, 2014

CLASSIFICATION: Contractors are required to call the Department of Workforce Development if there are any questions regarding the proper trade or classification to be used for any worker on a public works project.

OVERTIME: Time and one-half must be paid for all hours worked over 10 hours per day and 40 hours per calendar week and for all hours worked on Saturday, Sunday and the following six (6) holidays: January 1; the last Monday in May; July 4; the 1st Monday in September; the 4th Thursday in November; December 25; the day before if January 1, July 4 or December 25 falls on a Saturday; the day following if January 1, July 4 or December 25 falls on a Sunday.

FUTURE INCREASE: If indicated for a specific trade or occupation, the full amount of such increase MUST be added to the "TOTAL" indicated for such trade or occupation on the date(s) such increase(s) becomes effective.

PREMIUM PAY: If indicated for a specific trade or occupation, the full amount of such pay MUST be added to the "HOURLY BASIC RATE OF PAY" indicated for such trade or occupation, whenever such pay is applicable.

SUBJOURNEY: Wage rates may be available for some of the classifications indicated below. Any employer that desires to use any subjourney classification on a project MUST request the applicable wage rate from the Department of Workforce Development PRIOR to the date such classification is used on such project. Form ERD-10880 is available for this purpose and can be obtained by writing to the Department of Workforce Development, Equal Rights Division, P.O. Box 8928, Madison, WI 53708.

<u>TRADE OR OCCUPATION</u>	<u>HOURLY BASIC RATE OF PAY</u>	<u>HOURLY FRINGE BENEFITS</u>	<u>TOTAL</u>
	\$	\$	\$
Bricklayer, Blocklayer or Stonemason	32.01	17.35	49.36
Carpenter	30.48	15.90	46.38
Cement Finisher	33.51	16.13	49.64
Future Increase(s): Add \$1.87 on 6/1/14; Add \$1.87 on 6/1/15; Add \$1.75 on 6/1/16.			
Premium Pay: DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.40/hr when the Wisconsin Department of Transportation or responsible governing agency requires that work be performed at night under artificial illumination with traffic control and the work is completed after sunset and before sunrise.			
Electrician	34.07	19.25	53.32
Premium Pay: DOT PREMIUM: Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day.			
Fence Erector	24.72	0.00	24.72
Ironworker	31.25	19.46	50.71
Line Constructor (Electrical)	38.25	17.31	55.56
Painter	21.87	11.37	33.24
Pavement Marking Operator	30.00	0.00	30.00
Piledriver	30.98	15.90	46.88
Roofer or Waterproofor	29.40	6.25	35.65
Teledata Technician or Installer	21.89	11.85	33.74
Tuckpointer, Caulker or Cleaner	35.25	13.15	48.40
Underwater Diver (Except on Great Lakes)	34.48	15.90	50.38
Heavy Equipment Operator - ELECTRICAL LINE CONSTRUCTION ONLY	34.43	15.24	49.67
Light Equipment Operator -ELECTRICAL LINE CONSTRUCTION ONLY	35.50	15.89	51.39
Heavy Truck Driver - ELECTRICAL LINE CONSTRUCTION ONLY	26.78	13.63	40.41
Light Truck Driver - ELECTRICAL LINE CONSTRUCTION ONLY	24.86	12.97	37.83

<u>TRADE OR OCCUPATION</u>	<u>HOURLY BASIC RATE OF PAY</u>	<u>HOURLY FRINGE BENEFITS</u>	<u>TOTAL</u>
	\$	\$	\$
Groundman - ELECTRICAL LINE CONSTRUCTION ONLY	21.75	12.70	34.45

TRUCK DRIVERS

Single Axle or Two Axle	34.22	19.90	54.12
Three or More Axle	24.52	17.77	42.29
Future Increase(s): Add \$1.30/hr on 6/1/2014. Premium Pay: DOT PREMIUM: Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day.			
Articulated, Euclid, Dumptror, Off Road Material Hauler	29.27	20.40	49.67
Future Increase(s): Add \$1.75/hr on 6/1/14; Add \$1.25/hr on 6/1/15; Add \$1.30/hr on 6/1/16; Add \$1.25/hr on 6/ 1/ 17. Premium Pay: DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.50/hr night work premium. See DOT'S website for details about the applicability of this night work premium at: http:// www.dot.wi.gov/ business/ civilrights/ laborwages/ pwc. htm .			
Pavement Marking Vehicle	23.31	17.13	40.44
Shadow or Pilot Vehicle	34.22	19.90	54.12
Truck Mechanic	23.31	17.13	40.44

LABORERS

General Laborer	29.32	14.63	43.95
Future Increase(s): Add \$1.60/hr on 6/1/2014. Premium Pay: Add \$.10/hr for topman, air tool operator, vibrator or tamper operator (mechanical hand operated), chain saw operator and demolition burning torch laborer; Add \$.15/hr for bituminous worker (raker and luteman), formsetter (curb, sidewalk and pavement) and strike off man; Add \$.20/hr for blaster and powderman; Add \$.25/hr for bottomman; Add \$.35/hr for line and grade specialist; Add \$.45/hr for pipelayer. / DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.25/hr for work on projects involving temporary traffic control setup, for lane and shoulder closures, when work under artificial illumination conditions is necessary as required by the project provisions (including prep time prior to and/or cleanup after such time period).			
Asbestos Abatement Worker	24.36	14.44	38.80
Landscaper	29.32	14.63	43.95
Future Increase(s): Add \$1.60/hr on 6/1/14. Premium Pay: DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.25/hr for work on projects involving temporary traffic control setup, for lane and shoulder closures, when work under artificial illumination conditions is necessary as required by the project provisions (including prep time prior to and/or cleanup after such time period).			
Flagperson or Traffic Control Person	25.67	14.63	40.30
Future Increase(s): Add \$1.60/hr on 6/1/2014. Premium Pay: DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.25/hr when the Wisconsin Department of Transportation or responsible governing agency requires that work be performed at night under artificial illumination with traffic control and the work is completed after sunset and before sunrise.			
Fiber Optic Laborer (Outside, Other Than Concrete Encased)	18.31	12.67	30.98
Railroad Track Laborer	23.46	3.30	26.76

<u>TRADE OR OCCUPATION</u>	<u>HOURLY BASIC RATE OF PAY</u>	<u>HOURLY FRINGE BENEFITS</u>	<u>TOTAL</u>
	\$	\$	\$
HEAVY EQUIPMENT OPERATORS			
Crane, Tower Crane, Pedestal Tower or Derrick, With Boom, Leads &/or Jib Lengths Measuring 176 Ft or Over; Crane, Tower Crane, Pedestal Tower or Derrick, With or Without Attachments, With a Lifting Capacity of Over 100 Tons, Self-Erecting Tower Crane With a Lifting Capacity Of Over 4,000 Lbs., Crane With Boom Dollies; Traveling Crane (Bridge Type). Future Increase(s): Add \$1.75/hr on 6/1/2014); Add \$1.25/hr on 6/1/2015); Add \$1.30/hr on 6/1/2016); Add \$1.25/hr on 6/ 1/ 2017. Premium Pay: DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.50/hr night work premium. See DOT'S website for details about the applicability of this night work premium at: http:// www.dot.wi.gov/business/civilrights/laborwages/pwc. htm .	36.72	20.40	57.12
Backhoe (Track Type) Having a Mfrg.'s Rated Capacity of 130,000 Lbs. or Over; Caisson Rig; Crane, Tower Crane, Portable Tower, Pedestal Tower or Derrick, With Boom, Leads &/or Jib Lengths Measuring 175 Ft or Under; Crane, Tower Crane, Portable Tower, Pedestal Tower or Derrick, With or Without Attachments, With a Lifting Capacity of 100 Tons or Under, Self-Erecting Tower Crane With A Lifting Capacity Of 4,000 Lbs., & Under; Dredge (NOT Performing Work on the Great Lakes); Licensed Boat Pilot (NOT Performing Work on the Great Lakes); Pile Driver. Future Increase(s): Add \$1.75/hr on 6/1/2014); Add \$1.25/hr on 6/1/2015); Add \$1.30/hr on 6/1/2016); Add \$1.25/hr on 6/ 1/ 2017. Premium Pay: DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.50/hr night work premium. See DOT'S website for details about the applicability of this night work premium at: http:// www.dot.wi.gov/business/civilrights/laborwages/pwc. htm .	36.22	20.40	56.62
Air Track, Rotary or Percussion Drilling Machine &/or Hammers, Blaster; Asphalt Heater, Planer & Scarifier; Asphalt Milling Machine; Asphalt Screed; Automatic Subgrader (Concrete); Backhoe (Track Type) Having a Mfrg.'s Rated Capacity of Under 130,000 Lbs., Backhoe (Mini, 15,000 Lbs. & Under); Bituminous (Asphalt) Plant & Paver, Screed; Boatmen (NOT Performing Work on the Great Lakes); Boring Machine (Directional, Horizontal or Vertical); Bridge (Bidwell) Paver; Bulldozer or Endloader; Concrete Batch Plant, Batch Hopper; Concrete Breaker (Large, Auto, Vibratory/Sonic, Manual or Remote); Concrete Bump Cutter, Grinder, Planing or Grooving Machine; Concrete Conveyor System; Concrete Laser/Screed; Concrete Paver (Slipform); Concrete Pump, Concrete Conveyor (Rotec or Bidwell Type); Concrete Slipform Placer Curb & Gutter Machine; Concrete Spreader & Distributor; Crane (Carry Deck, Mini) or Truck Mounted Hydraulic Crane (10 Tons or Under); Crane With a Lifting Capacity of 25 Tons or Under; Forestry Equipment, Timbco, Tree Shear, Tub Grinder, Processor; Gradall (Cruz-Aire Type); Grader or Motor Patrol; Grout Pump; Hydro-Blaster (10,000 PSI or Over); Loading Machine (Conveyor); Material or Stack Hoist; Mechanic or Welder; Milling Machine; Post Hole Digger or Driver; Roller (Over 5 Ton); Scraper (Self Propelled or Tractor Drawn) 5 cu yds or More Capacity; Shoulder Widener; Sideboom; Skid Rig; Stabilizing or Concrete Mixer (Self-Propelled or 14S or Over); Straddle Carrier or Travel Lift; Tractor (Scraper, Dozer, Pusher, Loader); Tractor or Truck Mounted Hydraulic Backhoe; Trencher (Wheel Type or Chain Type); Tube Finisher; Tugger (NOT Performing Work on the Great Lakes); Winches	35.72	20.40	56.12

<u>TRADE OR OCCUPATION</u>	<u>HOURLY BASIC RATE OF PAY</u>	<u>HOURLY FRINGE BENEFITS</u>	<u>TOTAL</u>
	\$	\$	\$

& A- Frames.			
Future Increase(s): Add \$1.75/hr on 6/1/2014); Add \$1.25/hr on 6/1/2015); Add \$1.30/hr on 6/1/2016); Add \$1.25/hr on 6/ 1/ 2017.			
Premium Pay: DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.50/hr night work premium. See DOT'S website for details about the applicability of this night work premium at: http://www.dot.wi.gov/business/civilrights/laborwages/pwc.htm .			

Belting, Burlap, Texturing Machine; Broom or Sweeper; Compactor (Self-Propelled or Tractor Mounted, Towed & Light Equipment); Concrete Finishing Machine (Road Type); Environmental Burner; Farm or Industrial Type Tractor; Fireman (Asphalt Plant, Pile Driver & Derrick NOT Performing Work on the Great Lakes); Forklift; Greaser; Hoist (Tugger, Automatic); Jeep Digger; Joint Sawyer (Multiple Blade); Launch (NOT Performing Work on the Great Lakes); Lift Slab Machine; Mechanical Float; Mulcher; Power Subgrader; Robotic Tool Carrier (With or Without Attachments); Roller (Rubber Tire, 5 Ton or Under); Self Propelled Chip Spreader; Shouldering Machine; Skid Steer Loader (With or Without Attachments); Telehandler; Tining or Curing Machine.	35.46	20.40	55.86
Future Increase(s): Add \$1.75/hr on 6/1/2014); Add \$1.25/hr on 6/1/2015); Add \$1.30/hr on 6/1/2016); Add \$1.25/hr on 6/ 1/ 2017.			
Premium Pay: DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.50/hr night work premium. See DOT'S website for details about the applicability of this night work premium at: http://www.dot.wi.gov/business/civilrights/laborwages/pwc.htm .			

Air Compressor (&/or 400 CFM or Over); Air, Electric or Hydraulic Jacking System; Augers (Vertical & Horizontal); Automatic Belt Conveyor & Surge Bin; Boiler (Temporary Heat); Concrete Proportioning Plant; Crusher, Screening or Wash Plant; Generator (&/or 150 KW or Over); Heaters (Mechanical); High Pressure Utility Locating Machine (Daylighting Machine); Mudjack; Oiler; Prestress Machine; Pug Mill; Pump (3 Inch or Over) or Well Points; Rock, Stone Breaker; Screed (Milling Machine); Stump Chipper; Tank Car Heaters; Vibratory Hammer or Extractor, Power Pack.	35.17	20.40	55.57
Future Increase(s): Add \$1.75/hr on 6/1/2014); Add \$1.25/hr on 6/1/2015); Add \$1.30/hr on 6/1/2016); Add \$1.25/hr on 6/ 1/ 2017.			
Premium Pay: DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.50/hr night work premium. See DOT'S website for details about the applicability of this night work premium at: http://www.dot.wi.gov/business/civilrights/laborwages/pwc.htm .			

Fiber Optic Cable Equipment.	26.69	16.65	43.34

SUPERSEDES DECISION WI20120010
U. S. DEPARTMENT OF LABOR
(DAVIS-BACON ACT, MINIMUM WAGE RATES)

STATE: Wisconsin

GENERAL DECISION NUMBER: WI140010

DATE: March 14, 2014

DESCRIPTION OF WORK: Highways and Airport Runway and Taxiway Construction

LABORERS CLASSIFICATION:		Basic Hourly Rates	Fringe Benefits		Basic Hourly Rates	Fringe Benefits
Group 1:	General Laborer; Tree Trimmer; Conduit Layer; Demolition and Wrecking Laborer; Guard Rail, Fence and Bridge Builder; Landscaper, Multiplate Culvert Assembler; Stone Handler; Bituminous Worker (Shoveler, Loader, Utility Man); Batch Truck Dumper; or Cement Handler; Bituminous Worker; (Dumper, Ironer, Smoother, Tamper); Concrete Handler	\$29.32	14.53	<u>Truck Drivers:</u>		
				1 & 2 Axles	23.82	18.32
				Three or More Axles; Euclids, Dumptr & Articulated, Truck Mechanic.....	23.97	18.32
Group 2:	Air Tool Operator; Joint Sawyer and Filler (Pavement); Vibrator or Tamper Operator (Mechanical Hand Operated); Chain Saw Operator; Demolition Burning Torch Laborer	29.42	14.53			
Group 3:	Bituminous Worker (Raker and Luteman); Formsetter (Curb, Sidewalk, and Pavement); Strike Off man	29.47	14.53			
Group 4:	Line and Grade Specialist	29.67	14.53			
Group 5:	Blaster and Powderman	29.52	14.53			
Group 6:	Flagperson and Traffic Control Person	25.67	14.53			

CLASSES OF LABORER AND MECHANICS

Bricklayer	28.41	12.81
Carpenter	30.48	15.80
Millwright	32.11	15.80
Piledriverman	30.98	15.80
Ironworker	31.50	20.03
Cement Mason/Concrete Finisher	32.09	16.13
Electrician		See Page 3
Line Construction		
Lineman.....	39.50	32% + 5.00
Heavy Equipment Operator	37.53	32% + 5.00
Equipment Operator.....	31.60	32% + 5.00
Heavy Groundman Driver	26.78	14.11
Light Groundman Driver	24.86	13.45
Groundsman	21.73	32% + 5.00
Painter, Brush	24.50	16.27
Painter, Spray, Structural Steel,Bridges.....	25.50	16.27
Well Drilling:		
Well Driller.....	16.52	3.70

Notes: Welders receive rate prescribed for craft performing operation to which welding is incidental. Unlisted classifications needed for work not included within the scope of the classifications listed may be added after award only as provided in the labor standards contract clauses (29 CFR, 5.5(a)(1)(ii)). Includes Modification #0, dated January 3, 2014; Modification #1, dated February 7, 2014; Modification #2, dated March 14, 2014.

SUPERSEDES DECISION WI20120010
U. S. DEPARTMENT OF LABOR
(DAVIS-BACON ACT, MINIMUM WAGE RATES)

STATE: Wisconsin

GENERAL DECISION NUMBER: WI140010

DESCRIPTION OF WORK: Highways and Airport Runway and Taxiway Construction

DATE: March 14, 2014

<u>POWER EQUIPMENT OPERATORS CLASSIFICATION:</u>	<u>Basic Hourly Rates</u>	<u>Fringe Benefits</u>	<u>POWER EQUIPMENT OPERATORS CLASSIFICATION: (Continued)</u>	<u>Basic Hourly Rates</u>	<u>Fringe Benefits</u>
Group 1: Cranes, tower cranes and derricks, with or without attachments, with a lifting capacity of over 100 tons or cranes, tower cranes and derricks with boom, leads and/or jib lengths measuring 176 feet or longer	\$36.72	\$20.10	(scraper, dozer, pusher, loader); scraper - rubber tired (single or twin engine); endloader hydraulic backhoe (tractor-type); trenching machine; skid rigs; tractor, side boom (heavy); drilling or boring machine (mechanical heavy); roller (over 5 tons); percussion or rotary drilling machine; air track; blaster; loading machine (conveyor); tugger; boatmen; winches and A-frames; post driver; material hoist operator.	\$35.72	\$20.10
Group 2: Cranes, tower cranes and derricks, with or without attachments, with a lifting capacity of 100 tons or less or cranes, tower cranes and derricks with boom, leads and/or jib lengths measuring 175 feet or less, and backhoes (excavators) having a manufacturer's rated capacity of 3 cu. yds. and over, caisson rigs, pile driver, dredge operator, dredge engineer.	\$36.22	\$20.10	Group 4: Greaser, roller steel (5 tons or less); roller (pneumatic tired) - self-propelled; tractor (mounted or towed compactors and light equipment); shouldering machine; self-propelled chip spreader; concrete spreader; finishing machine; mechanical float; curing machine; power subgrader; joint saw (multiple blade) belting machine; burlap machine; texturing machine; tractor, endloader (rubber tired) - light; jeep digger; fork lift; mulcher; launch operator; fireman; environmental burner.	\$35.46	\$20.10
Group 3: Mechanic or welder - heavy duty equipment, cranes with a lifting capacity of 25 tons or less, concrete breaker (manual or remote); vibrator/sonic concrete breaker; concrete laser screed; concrete slipform paver; concrete batch plant operator; concrete pavement spreader - heavy duty (rubber tired); concrete spreader and distributor, automatic subgrader (concrete); concrete grinder and planing machine; concrete slipform curb and gutter machine; slipform concrete placer; tube finisher; hydro blaster (10,000 psi and over); bridge paver; concrete conveyor system; concrete pump; stabilizing mixer (self propelled); shoulder widener; asphalt plant engineer; bituminous paver; bump cutter and grooving machine; milling machine; screed (bituminous paver); asphalt heater, planer and scarifier; backhoes (excavators) having a manufacturers rated capacity of under 3 cu. yds.; grader or motor patrol; tractor			Group 5: Air compressor; power pack; vibratory hammer and extractor; heavy equipment, leadman; tank car heaters; stump chipper; curb machine operator; concrete proportioning plants generators; mudjack operator; rock breaker; crusher or screening plant; screed (milling machine); automatic belt conveyor and surge bin; pug mill operator; oiler; pump (over 3 inches); drilling machine helper.	\$35.17	\$20.10
			Group 6: Off - road material hauler with or without ejector.....	\$29.27	\$20.10
			Premium Pay: EPA Level "A" protection - \$3.00 per hour EPA Level "B" protection - \$2.00 per hour EPA Level "C" protection - \$1.00 per hours		

SUPERSEDES DECISION WI20120010
U. S. DEPARTMENT OF LABOR
(DAVIS-BACON ACT, MINIMUM WAGE RATES)

STATE: Wisconsin

GENERAL DECISION NUMBER: WI140010

DESCRIPTION OF WORK: Highways and Airport Runway and Taxiway Construction

DATE: March 14, 2014

LABORERS CLASSIFICATION:

Rates

Benefits

			Area 4 -	BROWN, DOOR, KEWAUNEE, MANITOWOC (except Schleswig), MARINETTE (Wausauke and area south thereof), OCONTO, MENOMINEE (East of a line 6 miles West of the West boundary of Oconto County), SHAWANO (except area North of Townships of Aniwa and Hutchins) COUNTIES.
Electricians				
Area 1	\$28.40	16.676		
Area 2:				
Electricians.....	29.13	17.92	Area 5 -	ADAMS, CLARK (Colby, Freemont, Lynn, Mayville, Sherman, Sherwood, Unity), FOREST, JUNEAU, LANGLADE, LINCOLN, MARATHON, MARINETTE (Area North of the town of Wausauke), MENOMINEE (Area West of a line 6 miles West of the West boundary of Oconto County), ONEIDA, PORTAGE, SHAWANO (Area North of the townships of Aniwa and Hutchins), VILAS AND WOOD COUNTIES
Area 3:				
Electrical contracts under \$130,000	26.24	16.85		
Electrical contracts over \$130,000	29.41	16.97		
Area 4:	28.50	28.75% + 9.27	Area 6 -	KENOSHA COUNTY
Area 5	28.96	24.85% + 9.70		
Area 6	35.25	19.30	Area 8 -	DODGE, (Emmet Township only), GREEN, JEFFERSON, LAFAYETTE, RACINE (Burlington township), ROCK and WALWORTH COUNTIES
Area 8				
Electricians.....	30.60	24.95% + 10.33	Area 9 -	COLUMBIA, DANE, DODGE, (area west of Hwy. 26, except Chester & Emmet Townships), GREEN LAKE (except townships of Berlin, Seneca and St. Marie), IOWA, MARQUETTE (except townships of Neshkoka, Crystal Lake, Newton and Springfield), and SAUK COUNTIES
Area 9:				
Electricians.....	32.94	18.71	Area 10 -	CALUMET (Township of New Holstein), DODGE (East of Hwy. 26 including Chester Township), FOND DU LAC, MANITOWOC (Schleswig), and SHEBOYGAN COUNTIES
Area 10	28.97	19.55	Area 11 -	DOUGLAS COUNTY
Area 11	31.91	23.60	Area 12 -	RACINE (except Burlington township) COUNTY
Area 12	32.87	19.23	Area 13 -	MILWAUKEE, OZAUKEE, WASHINGTON and WAUKESHA COUNTIES
Area 13	32.82	22.51	Area 14 -	Statewide.
Teledata System Installer			Area 15 -	DODGE (East of Hwy 26 including Chester Twp, excluding Emmet Twp), FOND DU LAC (Except Waupun), MILWAUKEE, OZAUKEE, MANITOWOC (Schleswig), WASHINGTON, AND WAUKESHA COUNTIES.
Area 14				
Installer/Technician	21.89	11.83		
Sound & Communications				
Area 15				
Installer	16.47	14.84		
Technician	24.75	16.04		
Area 1 -	CALUMET (except township of New Holstein), GREEN LAKE (N. part, including Townships of Berlin, St. Marie and Seneca), MARQUETTE (N. part, including Townships of Crystal Lake, Neshkoro, Newton & Springfield), OUTAGAMIE, WAUPACA, WAUSHARA and WINNEBAGO COUNTIES.			
Area 2 -	ASHLAND, BARRON, BAYFIELD, BUFFALO, BURNETT, CHIPPEWA, CLARK (except Mayville, Colby, Unity, Sherman, Fremont, Lynn and Sherwood), CRAWFORD, DUNN, EAU CLAIRE, GRANT, IRON, JACKSON, LA CROSSE, MONROE, PEPIN, PIERCE, POLK, PRICE, RICHLAND, RUSK, ST. CROIX, SAWYER, TAYLOR, TREMPLEAU, VERNON and WASHBURN COUNTIES			
Area 3 -	FLORENCE (townships of Aurora, Commonwealth, Fern, Florence and Homestead), MARINETTE (Niagara township)			

FEBRUARY 1999

**NOTICE TO BIDDERS
WAGE RATE DECISION**

The wage rate decision of the Secretary of Labor which has been incorporated in these advertised specifications is incomplete in that the classifications may be omitted from the Secretary of Labor's decision.

Since the bidder is responsible, independently, for ascertaining area practice with respect to the necessity, or lack of necessity, for the use of these classifications in the prosecution of the work contemplated by this project, no inference may be drawn from the omission of these classifications concerning prevailing area practices relative to their use. Further, this omission will not, per se, be construed as establishing any governmental liability for increased labor cost if it is subsequently determined that such classifications are required.

There may be omissions and/or errors in the federal wage rates. The bidder is responsible for evaluating and determining the correct applicable rate. The higher of state or federal rate will apply.

Wisconsin Department of Transportation

PAGE: 1

DATE: 03/14/14

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20140513011PROJECT(S):
5310-02-74
5657-00-70FEDERAL ID(S):
N/A
WISC 2014187

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS

SECTION 0001 CONTRACT ITEMS

0010	201.0105 CLEARING	2.000 STA
0020	201.0205 GRUBBING	2.000 STA
0030	203.0600.S REMOVING OLD STRUCTURE OVER WATERWAY WITH MINIMAL DEBRIS (STATION) 01. 13+00 'P'	LUMP	LUMP	.	.	.
0040	204.0115 REMOVING ASPHALTIC SURFACE BUTT JOINTS	166.000 SY
0050	204.0120 REMOVING ASPHALTIC SURFACE MILLING	1,480.000 SY
0060	204.0150 REMOVING CURB & GUTTER	620.000 LF
0070	204.0155 REMOVING CONCRETE SIDEWALK	48.000 SY
0080	204.0195 REMOVING CONCRETE BASES	5.000 EACH
0090	204.0210 REMOVING MANHOLES	2.000 EACH

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20140513011PROJECT(S):
5310-02-74
5657-00-70FEDERAL ID(S):
N/A
WISC 2014187

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0100	204.0220 REMOVING INLETS	2.000				
	EACH		.		.	
0110	204.0245 REMOVING STORM SEWER (SIZE) 01. 12-INCH	60.000				
	LF		.		.	
0120	204.0245 REMOVING STORM SEWER (SIZE) 02. 30-INCH	160.000				
	LF		.		.	
0130	204.9060.S REMOVING (ITEM DESCRIPTION) 01. TYPE II SIGN STRUCTURES	2.000				
	EACH		.		.	
0140	204.9090.S REMOVING (ITEM DESCRIPTION) 02. CONCRETE MEDIAN	145.000				
	LF		.		.	
0150	205.0100 EXCAVATION COMMON	3,432.000				
	CY		.		.	
0160	205.0501.S EXCAVATION, HAULING, AND DISPOSAL OF PETROLEUM CONTAMINATED SOIL	300.000				
	TON		.		.	
0170	206.1000 EXCAVATION FOR STRUCTURES BRIDGES (STRUCTURE) 01. B-13-0646		LUMP			
					.	
0180	206.5000 COFFERDAMS (STRUCTURE) 01. B-13-0646		LUMP			
					.	
0190	210.0100 BACKFILL STRUCTURE	410.000				
	CY		.		.	

Wisconsin Department of Transportation

PAGE: 3

DATE: 03/14/14

REVISED:

SCHEDULE OF ITEMS

CONTRACT:
20140513011PROJECT(S):
5310-02-74
5657-00-70FEDERAL ID(S):
N/A
WISC 2014187

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0200	213.0100 FINISHING ROADWAY (PROJECT) 01. 5310-02-74	1.000 EACH	.		.	
0210	213.0100 FINISHING ROADWAY (PROJECT) 02. 5657-00-70	1.000 EACH	.		.	
0220	305.0110 BASE AGGREGATE DENSE 3/4-INCH	35.000 TON	.		.	
0230	305.0120 BASE AGGREGATE DENSE 1 1/4-INCH	1,835.000 TON	.		.	
0240	311.0115 BREAKER RUN	20.000 CY	.		.	
0250	312.0110 SELECT CRUSHED MATERIAL	3,025.000 TON	.		.	
0260	415.0080 CONCRETE PAVEMENT 8-INCH	905.000 SY	.		.	
0270	415.0410 CONCRETE PAVEMENT APPROACH SLAB	325.000 SY	.		.	
0280	416.0180 CONCRETE DRIVEWAY 8-INCH	53.000 SY	.		.	
0290	455.0105 ASPHALTIC MATERIAL PG58-28	32.000 TON	.		.	
0300	455.0605 TACK COAT	70.000 GAL	.		.	

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20140513011PROJECT(S):
5310-02-74
5657-00-70FEDERAL ID(S):
N/A
WISC 2014187

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0310	460.1103 HMA PAVEMENT TYPE E-3	585.000 TON	.		.	
0320	460.2000 INCENTIVE DENSITY HMA PAVEMENT	380.000 DOL	1.00000		380.00	
0330	465.0125 ASPHALTIC SURFACE TEMPORARY	290.000 TON	.		.	
0340	502.0100 CONCRETE MASONRY BRIDGES	505.000 CY	.		.	
0350	502.3200 PROTECTIVE SURFACE TREATMENT	163.000 SY	.		.	
0360	502.5005 MASONRY ANCHORS TYPE L NO. 5 BARS	32.000 EACH	.		.	
0370	505.0405 BAR STEEL REINFORCEMENT HS BRIDGES	12,500.000 LB	.		.	
0380	505.0605 BAR STEEL REINFORCEMENT HS COATED BRIDGES	64,520.000 LB	.		.	
0390	509.5100.S POLYMER OVERLAY	370.000 SY	.		.	
0400	513.7015 RAILING STEEL TYPE C3 (STRUCTURE) 01. B-13-0646	LUMP	LUMP		.	
0410	516.0500 RUBBERIZED MEMBRANE WATERPROOFING	28.000 SY	.		.	

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20140513011PROJECT(S):
5310-02-74
5657-00-70FEDERAL ID(S):
N/A
WISC 2014187

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0420	517.1010.S CONCRETE STAINING (STRUCTURE) 01. B-13-0646	256.000 SF	.		.	
0430	517.1050.S ARCHITECTURAL SURFACE TREATMENT (STRUCTURE) 01. B-13-0646	256.000 SF	.		.	
0440	522.1024 APRON ENDWALLS FOR CULVERT PIPE REINFORCED CONCRETE 24-INCH	1.000 EACH	.		.	
0450	550.1100 PILING STEEL HP 10-INCH X 42 LB	2,605.000 LF	.		.	
0460	601.0409 CONCRETE CURB & GUTTER 30-INCH TYPE A	790.000 LF	.		.	
0470	601.0411 CONCRETE CURB & GUTTER 30-INCH TYPE D	270.000 LF	.		.	
0480	602.0405 CONCRETE SIDEWALK 4-INCH	2,705.000 SF	.		.	
0490	602.0515 CURB RAMP DETECTABLE WARNING FIELD NATURAL PATINA	48.000 SF	.		.	
0500	606.0300 RIPRAP HEAVY	425.000 CY	.		.	
0510	608.0412 STORM SEWER PIPE REINFORCED CONCRETE CLASS IV 12-INCH	71.000 LF	.		.	

SCHEDULE OF ITEMS

CONTRACT:
20140513011PROJECT(S):
5310-02-74
5657-00-70FEDERAL ID(S):
N/A
WISC 2014187

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0520	608.0418 STORM SEWER PIPE REINFORCED CONCRETE CLASS IV 18-INCH	89.000 LF	.		.	
0530	608.0424 STORM SEWER PIPE REINFORCED CONCRETE CLASS IV 24-INCH	185.000 LF	.		.	
0540	611.0612 INLET COVERS TYPE C	2.000 EACH	.		.	
0550	611.0624 INLET COVERS TYPE H	2.000 EACH	.		.	
0560	611.0639 INLET COVERS TYPE H-S	4.000 EACH	.		.	
0570	611.2005 MANHOLES 5-FT DIAMETER	1.000 EACH	.		.	
0580	611.2066 MANHOLES 6X6-FT	1.000 EACH	.		.	
0590	611.3230 INLETS 2X3-FT	6.000 EACH	.		.	
0600	612.0406 PIPE UNDERDRAIN WRAPPED 6-INCH	593.000 LF	.		.	
0610	614.0150 ANCHOR ASSEMBLIES FOR STEEL PLATE BEAM GUARD	1.000 EACH	.		.	
0620	614.2300 MGS GUARDRAIL 3	12.500 LF	.		.	

Wisconsin Department of Transportation

PAGE: 7

DATE: 03/14/14

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20140513011PROJECT(S):
5310-02-74
5657-00-70FEDERAL ID(S):
N/A
WISC 2014187

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0630	614.2500 MGS THRIE BEAM TRANSITION	39.000 LF	.		.	
0640	614.2610 MGS GUARDRAIL TERMINAL EAT	1.000 EACH	.		.	
0650	618.0100 MAINTENANCE AND REPAIR OF HAUL ROADS (PROJECT) 01. 5657-00-70	1.000 EACH	.		.	
0660	619.1000 MOBILIZATION	1.000 EACH	.		.	
0670	620.0200 CONCRETE MEDIAN BLUNT NOSE	72.000 SF	.		.	
0680	624.0100 WATER	5.000 MGAL	.		.	
0690	625.0100 TOPSOIL	1,435.000 SY	.		.	
0700	628.1504 SILT FENCE	810.000 LF	.		.	
0710	628.1520 SILT FENCE MAINTENANCE	810.000 LF	.		.	
0720	628.1905 MOBILIZATIONS EROSION CONTROL	3.000 EACH	.		.	

Wisconsin Department of Transportation

PAGE: 8

DATE: 03/14/14

REVISED:

SCHEDULE OF ITEMS

CONTRACT:
20140513011PROJECT(S):
5310-02-74
5657-00-70FEDERAL ID(S):
N/A
WISC 2014187

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0730	628.1910 MOBILIZATIONS EMERGENCY EROSION CONTROL	5.000 EACH	.		.	
0740	628.2006 EROSION MAT URBAN CLASS I TYPE A	1,735.000 SY	.		.	
0750	628.7010 INLET PROTECTION TYPE B	1.000 EACH	.		.	
0760	628.7015 INLET PROTECTION TYPE C	6.000 EACH	.		.	
0770	628.7020 INLET PROTECTION TYPE D	1.000 EACH	.		.	
0780	628.7560 TRACKING PADS	1.000 EACH	.		.	
0790	629.0210 FERTILIZER TYPE B	1.000 CWT	.		.	
0800	630.0140 SEEDING MIXTURE NO. 40	27.000 LB	.		.	
0810	630.0200 SEEDING TEMPORARY	25.000 LB	.		.	
0820	634.0614 POSTS WOOD 4X6-INCH X 14-FT	24.000 EACH	.		.	
0830	634.0616 POSTS WOOD 4X6-INCH X 16-FT	19.000 EACH	.		.	

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20140513011PROJECT(S):
5310-02-74
5657-00-70FEDERAL ID(S):
N/A
WISC 2014187

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0840	634.0814 POSTS TUBULAR STEEL 2X2-INCH X 14-FT	4.000 EACH	.		.	
0850	634.0816 POSTS TUBULAR STEEL 2X2-INCH X 16-FT	5.000 EACH	.		.	
0860	637.2220 SIGNS TYPE II REFLECTIVE SH	184.980 SF	.		.	
0870	637.2230 SIGNS TYPE II REFLECTIVE F	135.080 SF	.		.	
0880	638.2102 MOVING SIGNS TYPE II	2.000 EACH	.		.	
0890	638.2602 REMOVING SIGNS TYPE II	50.000 EACH	.		.	
0900	638.3000 REMOVING SMALL SIGN SUPPORTS	38.000 EACH	.		.	
0910	638.4000 MOVING SMALL SIGN SUPPORTS	1.000 EACH	.		.	
0920	642.5201 FIELD OFFICE TYPE C	1.000 EACH	.		.	
0930	643.0100 TRAFFIC CONTROL (PROJECT) 01. 5310-02-74	1.000 EACH	.		.	

SCHEDULE OF ITEMS

CONTRACT:
20140513011PROJECT(S):
5310-02-74
5657-00-70FEDERAL ID(S):
N/A
WISC 2014187

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0940	643.0100 TRAFFIC CONTROL (PROJECT) 02. 5657-00-70	1.000 EACH	.		.	
0950	643.0300 TRAFFIC CONTROL DRUMS	3,320.000 DAY	.		.	
0960	643.0420 TRAFFIC CONTROL BARRICADES TYPE III	1,000.000 DAY	.		.	
0970	643.0705 TRAFFIC CONTROL WARNING LIGHTS TYPE A	2,000.000 DAY	.		.	
0980	643.0900 TRAFFIC CONTROL SIGNS	5,375.000 DAY	.		.	
0990	643.2000 TRAFFIC CONTROL DETOUR (PROJECT) 01. 5657-00-70	1.000 EACH	.		.	
1000	643.3000 TRAFFIC CONTROL DETOUR SIGNS	15,500.000 DAY	.		.	
1010	645.0120 GEOTEXTILE FABRIC TYPE HR	760.000 SY	.		.	
1020	646.0106 PAVEMENT MARKING EPOXY 4-INCH	9,900.000 LF	.		.	
1030	646.0126 PAVEMENT MARKING EPOXY 8-INCH	926.000 LF	.		.	
1040	646.0600 REMOVING PAVEMENT MARKINGS	490.000 LF	.		.	

SCHEDULE OF ITEMS

CONTRACT:
20140513011PROJECT(S):
5310-02-74
5657-00-70FEDERAL ID(S):
N/A
WISC 2014187

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
1050	647.0110 PAVEMENT MARKING RAILROAD CROSSINGS EPOXY	4.000 EACH	.		.	
1060	647.0156 PAVEMENT MARKING ARROWS EPOXY TYPE 1	1.000 EACH	.		.	
1070	647.0166 PAVEMENT MARKING ARROWS EPOXY TYPE 2	8.000 EACH	.		.	
1080	647.0176 PAVEMENT MARKING ARROWS EPOXY TYPE 3	3.000 EACH	.		.	
1090	647.0356 PAVEMENT MARKING WORDS EPOXY	1.000 EACH	.		.	
1100	647.0456 PAVEMENT MARKING CURB EPOXY	220.000 LF	.		.	
1110	647.0566 PAVEMENT MARKING STOP LINE EPOXY 18-INCH	295.000 LF	.		.	
1120	647.0606 PAVEMENT MARKING ISLAND NOSE EPOXY	2.000 EACH	.		.	
1130	647.0726 PAVEMENT MARKING DIAGONAL EPOXY 12-INCH	105.000 LF	.		.	
1140	647.0766 PAVEMENT MARKING CROSSWALK EPOXY 6-INCH	312.000 LF	.		.	
1150	647.0955 REMOVING PAVEMENT MARKINGS ARROWS	9.000 EACH	.		.	

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20140513011PROJECT(S):
5310-02-74
5657-00-70FEDERAL ID(S):
N/A
WISC 2014187

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
1160	647.0965 REMOVING PAVEMENT MARKINGS WORDS	5.000 EACH	.		.	
1170	650.4000 CONSTRUCTION STAKING STORM SEWER	9.000 EACH	.		.	
1180	650.4500 CONSTRUCTION STAKING SUBGRADE	751.000 LF	.		.	
1190	650.5000 CONSTRUCTION STAKING BASE	527.000 LF	.		.	
1200	650.5500 CONSTRUCTION STAKING CURB GUTTER AND CURB & GUTTER	365.000 LF	.		.	
1210	650.7000 CONSTRUCTION STAKING CONCRETE PAVEMENT	224.000 LF	.		.	
1220	650.8000 CONSTRUCTION STAKING RESURFACING REFERENCE	306.000 LF	.		.	
1230	650.8500 CONSTRUCTION STAKING ELECTRICAL INSTALLATIONS (PROJECT) 01. 5657-00-70	LUMP	LUMP		.	
1240	650.9910 CONSTRUCTION STAKING SUPPLEMENTAL CONTROL (PROJECT) 01. 5657-00-70	LUMP	LUMP		.	
1250	650.9920 CONSTRUCTION STAKING SLOPE STAKES	751.000 LF	.		.	

SCHEDULE OF ITEMS

CONTRACT:
20140513011PROJECT(S):
5310-02-74
5657-00-70FEDERAL ID(S):
N/A
WISC 2014187

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
1260	652.0225 CONDUIT RIGID NONMETALLIC SCHEDULE 40 2-INCH	795.000 LF	.		.	
1270	652.0325 CONDUIT RIGID NONMETALLIC SCHEDULE 80 2-INCH	188.000 LF	.		.	
1280	652.0800 CONDUIT LOOP DETECTOR	272.000 LF	.		.	
1290	653.0135 PULL BOXES STEEL 24X36-INCH	6.000 EACH	.		.	
1300	653.0140 PULL BOXES STEEL 24X42-INCH	4.000 EACH	.		.	
1310	653.0905 REMOVING PULL BOXES	5.000 EACH	.		.	
1320	654.0102 CONCRETE BASES TYPE 2	5.000 EACH	.		.	
1330	655.0800 LOOP DETECTOR WIRE	688.000 LF	.		.	
1340	661.0200 TEMPORARY TRAFFIC SIGNALS FOR INTERSECTIONS (LOCATION) 01. USH 14 & CTH P	LUMP	LUMP		.	
1350	661.0200 TEMPORARY TRAFFIC SIGNALS FOR INTERSECTIONS (LOCATION) 02. CTH P & BOURBON ROAD	LUMP	LUMP		.	

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20140513011PROJECT(S):
5310-02-74
5657-00-70FEDERAL ID(S):
N/A
WISC 2014187

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
1360	661.0200 TEMPORARY TRAFFIC SIGNALS FOR INTERSECTIONS (LOCATION) 03. CTH KP & BOURBON ROAD	LUMP	LUMP			.
1370	690.0150 SAWING ASPHALT	818.000 LF	.		.	
1380	690.0250 SAWING CONCRETE	10.000 LF	.		.	
1390	715.0415 INCENTIVE STRENGTH CONCRETE PAVEMENT	500.000 DOL	1.00000		500.00	
1400	715.0502 INCENTIVE STRENGTH CONCRETE STRUCTURES	5,050.000 DOL	1.00000		5050.00	
1410	999.1000.S SEISMOGRAPH	LUMP	LUMP			.
1420	999.1500.S CRACK AND DAMAGE SURVEY	LUMP	LUMP			.
1430	ASP.1T0A ON-THE-JOB TRAINING APPRENTICE AT \$5.00/HR	350.000 HRS	5.00000		1750.00	
1440	ASP.1T0G ON-THE-JOB TRAINING GRADUATE AT \$5. 00/HR	225.000 HRS	5.00000		1125.00	
1450	SPV.0060 SPECIAL 01. REMOVING TRAFFIC SIGNAL CONTROLLER CABINET	1.000 EACH	.		.	

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20140513011PROJECT(S):
5310-02-74
5657-00-70FEDERAL ID(S):
N/A
WISC 2014187

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
1460	SPV.0060 SPECIAL 02. TEMPORARY OPTICOM SIGNAL PREEMPT	4.000 EACH	.		.	
1470	SPV.0060 SPECIAL 03. REMOVING ELECTRICAL SERVICE METER BREAKER PEDESTAL	1.000 EACH	.		.	
1480	SPV.0060 SPECIAL 04. PERMANENT TRAFFIC CONTROL DRUM	45.000 EACH	.		.	
1490	SPV.0060 SPECIAL 05. SIGNS FLASHING LED, STOP	2.000 EACH	.		.	
1500	SPV.0060 SPECIAL 06. SIGNS FLASHING LED, VEHICLE ENTRANCE	2.000 EACH	.		.	
1510	SPV.0105 SPECIAL 01. REMOVING TRAFFIC SIGNALS CTH P & USH 14 INTERSECTION	LUMP	LUMP		.	
1520	SPV.0105 SPECIAL 02. TEMPORARY VEHICLE DETECTION USH 14 & CTH P	LUMP	LUMP		.	
1530	SPV.0105 SPECIAL 03. TEMPORARY VEHICLE DETECTION CTH P & BOURBON ROAD	LUMP	LUMP		.	
1540	SPV.0105 SPECIAL 04. TEMPORARY VEHICLE DETECTION CTH KP & BOURBON ROAD	LUMP	LUMP		.	

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20140513011PROJECT(S):
5310-02-74
5657-00-70FEDERAL ID(S):
N/A
WISC 2014187

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
1550	SPV.0105 SPECIAL 05. TEMPORARY CROSSWALK ACCESS CTH P & USH 14	LUMP	LUMP			.
1560	SPV.0105 SPECIAL 06. CONCRETE PAVEMENT JOINT LAYOUT	LUMP	LUMP			.
1570	SPV.0180 SPECIAL 01. GEOGRID REINFORCEMENT	2,835.000 SY		.		.
	SECTION 0001 TOTAL					.
	TOTAL BID					.

PLEASE ATTACH SCHEDULE OF ITEMS HERE