

HIGHWAY WORK PROPOSAL

Proposal Number:

17

Wisconsin Department of Transportation
 DT1502 10/2010 s.66.29(7) Wis. Stats.

<u>COUNTY</u>	<u>STATE PROJECT ID</u>	<u>FEDERAL PROJECT ID</u>	<u>PROJECT DESCRIPTION</u>	<u>HIGHWAY</u>
Washington	2707-03-71		USH 45 to West Bend Paradise Drive Park and Ride Lot 66-55	Non Hwy

This proposal, submitted by the undersigned bidder to the Wisconsin Department of Transportation, is in accordance with the advertised request for proposals. The bidder is to furnish and deliver all materials, and to perform all work for the improvement of the designated project in the time specified, in accordance with the appended Proposal Requirements and Conditions.

Attach Proposal Guaranty on back of this PAGE.

Proposal Guaranty Required, \$ 20,000.00 Payable to: Wisconsin Department of Transportation Bid Submittal Due Date: July 8, 2014 Time (Local Time): 9:00 AM Contract Completion Time Twenty-Seven (27) Working Days Assigned Disadvantaged Business Enterprise Goal 0 %	Firm Name, Address, City, State, Zip Code <div style="text-align: center; font-size: 2em; font-weight: bold;"> SAMPLE NOT FOR BIDDING PURPOSES </div> This contract is exempt from federal oversight.
---	---

This certifies that the undersigned bidder, duly sworn, is an authorized representative of the firm named above; that the bidder has examined and carefully prepared the bid from the plans, Highway Work Proposal, and all addenda, and has checked the same in detail before submitting this proposal or bid; and that the bidder or agents, officer, or employees have not, either directly or indirectly, entered into any agreement, participated in any collusion, or otherwise taken any action in restraint of free competitive bidding in connection with this proposal bid.

Do not sign, notarize, or submit this Highway Work Proposal when submitting an electronic bid on the Internet.

Subscribed and sworn to before me this date _____

 (Signature, Notary Public, State of Wisconsin)

 (Bidder Signature)

 (Print or Type Name, Notary Public, State Wisconsin)

 (Print or Type Bidder Name)

 (Date Commission Expires)

 (Bidder Title)

Notary Seal

For Department Use Only

Type of Work	
Mill and relay, common excavation, base aggregate dense, concrete pavement, HMA pavement, curb and gutter, storm sewer, lighting, signing, marking.	
Notice of Award Dated	Date Guaranty Returned

**PLEASE ATTACH
PROPOSAL GUARANTY HERE**

Effective with November 2007 Letting

PROPOSAL REQUIREMENTS AND CONDITIONS

The bidder, signing and submitting this proposal, agrees and declares as a condition thereof, to be bound by the following conditions and requirements.

If the bidder has a corporate relationship with the proposal design engineering company, the bidder declares that it did not obtain any facts, data, or other information related to this proposal from the design engineering company that was not available to all bidders.

The bidder declares that they have carefully examined the site of, and the proposal, plans, specifications and contract forms for the work contemplated, and it is assumed that the bidder has investigated and is satisfied as to the conditions to be encountered, as to the character, quality, and quantities of work to be performed and materials to be furnished, and as to the requirements of the specifications, special provisions and contract. It is mutually agreed that submission of a proposal shall be considered conclusive evidence that the bidder has made such examination.

The bidder submits herewith a proposal guaranty in proper form and amount payable to the party as designated in the advertisement inviting proposals, to be retained by and become the property of the owner of the work in the event the undersigned shall fail to execute the contract and contract bond and return the same to the office of the engineer within fourteen (14) days after having been notified in writing to do so; otherwise to be returned.

The bidder declares that they understand that the estimate of quantities in the attached schedule is approximate only and that the attached quantities may be greater or less in accordance with the specifications.

The bidder agrees to perform the said work, for and in consideration of the payment of the amount becoming due on account of work performed, according to the unit prices bid in the following schedule, and to accept such amounts in full payment of said work.

The bidder declares that all of the said work will be performed at their own proper cost and expense, that they will furnish all necessary materials, labor, tools, machinery, apparatus, and other means of construction in the manner provided in the applicable specifications and the approved plans for the work together with all standard and special designs that may be designed on such plans, and the special provisions in the contract of which this proposal will become a part, if and when accepted. The bidder further agrees that the applicable specifications and all plans and working drawings are made a part hereof, as fully and completely as if attached hereto.

The bidder, if awarded the contract, agrees to begin the work not later than ten (10) days after the date of written notification from the engineer to do so, unless otherwise stipulated in the special provisions.

The bidder declares that if they are awarded the contract, they will execute the contract agreement and begin and complete the work within the time named herein, and they will file a good and sufficient surety bond for the amount of the contract for performance and also for the full amount of the contract for payment.

The bidder, if awarded the contract, shall pay all claims as required by Section 779.14, Statutes of Wisconsin, and shall be subject to and discharge all liabilities for injuries pursuant to Chapter 102 of the Statutes of Wisconsin, and all acts amendatory thereto. They shall further be responsible for any damages to property or injury to persons occurring through their own negligence or that of their employees or agents, incident to the performance of work under this contract, pursuant to the Standard Specifications for Road and Bridge Construction applicable to this contract.

In connection with the performance of work under this contract, the contractor agrees to comply with all applicable state and federal statutes relating to non-discrimination in employment. No otherwise qualified person shall be excluded from employment or otherwise be subject to discrimination in employment in any manner on the basis of age, race, religion, color, gender, national origin or ancestry, disability, arrest or conviction record (in keeping with s.111.32), sexual orientation, marital status, membership in the military reserve, honesty testing, genetic testing, and outside use of lawful products. This provision shall include, but not be limited to the following: employment, upgrading, demotion or transfer; recruitment or recruitment advertising; layoff or termination; rates of pay or other forms of compensation, and selection for training, including apprenticeship. The contractor further agrees to ensure equal opportunity in employment to all applicants and employees and to take affirmative action to attain a representative workforce.

The contractor agrees to post notices and posters setting forth the provisions of the nondiscrimination clause, in a conspicuous and easily accessible place, available for employees and applicants for employment.

If a state public official (section 19.42, Stats.) or an organization in which a state public official holds at least a 10% interest is a party to this agreement, this contract is voidable by the state unless appropriate disclosure is made to the State of Wisconsin Ethics Board.

Effective with August 2007 Letting

BID PREPARATION

Preparing the Proposal Schedule of Items

A General

- (1) Obtain bidding proposals as specified in [section 102](#) of the standard specifications prior to 11:45 AM of the last business day preceding the letting. Submit bidding proposals using one of the following methods:
 1. Electronic bid on the internet.
 2. Electronic bid on a printout with accompanying diskette or CD ROM.
 3. Paper bid under a waiver of the electronic submittal requirements.
- (2) Bids submitted on a printout with accompanying diskette or CD ROM or paper bids submitted under a waiver of the electronic submittal requirements govern over bids submitted on the internet.
- (3) The department will provide bidding information through the department's web site at <http://www.dot.wisconsin.gov/business/engrserv/bid-letting-information.htm>. The contractor is responsible for reviewing this web site for general notices as well as information regarding proposals in each letting. The department will also post special notices of all addenda to each proposal through this web site no later than 4:00 P.M. local time on the Thursday before the letting. Check the department's web site after 5:00 P.M. local time on the Thursday before the letting to ensure all addenda have been accounted for before preparing the bid. When bidding using methods 1 and 2 above, check the Bid Express™ on-line bidding exchange at <http://www.bidx.com/> after 5:00 P.M. local time on the Thursday before the letting to ensure that the latest schedule of items Expedite file (*.ebs or *.00x) is used to submit the final bid.
- (4) Interested parties can subscribe to the Bid Express™ on-line bidding exchange by following the instructions provided at the www.bidx.com web site or by contacting:

Info Tech Inc.
5700 SW 34th Street, Suite 1235
Gainesville, FL 32608-5371
email: <mailto:customer.support@bidx.com>

- (5) The department will address equipment and process failures, if the bidder can demonstrate that those failures were beyond their control.
- (6) Contractors are responsible for checking on the issuance of addenda and for obtaining the addenda. Notice of issuance of addenda is posted on the department's web site at <http://www.dot.wisconsin.gov/business/engrserv/bid-letting-information.htm> or by calling the department at (608) 266-1631. Addenda can ONLY be obtained from the departments web site listed above or by picking up the addenda at the Bureau of Highway Construction, Room 601, 4802 Sheboygan Avenue, Madison, WI, during regular business hours.

B Submitting Electronic Bids

B.1 On the Internet

- (1) Do the following before submitting the bid:
 1. Have a properly executed annual bid bond on file with the department.
 2. Have a digital ID on file with and enabled by Info Tech Inc. Using this digital ID will constitute the bidder's signature for proper execution of the bidding proposal.
- (2) In lieu of preparing, delivering, and submitting the proposal as specified in [102.6](#) and [102.9](#) of the standard specifications, submit the proposal on the internet as follows:

1. Download the latest schedule of items reflecting all addenda from the Bid Express™ web site.
 2. Use Expedite™ software to enter a unit price for every item in the schedule of items.
 3. Submit the bid according to the requirements of Expedite™ software and the Bid Express™ web site. Do not submit a bid on a printout with accompanying diskette or CD ROM or a paper bid. If the bidder does submit a bid on a printout with accompanying diskette or a paper bid in addition to the internet submittal, the department will disregard the internet bid.
 4. Submit the bid before the hour and date the Notice to Contractors designates.
 5. Do not sign, notarize, and return the bidding proposal described in 102.2 of the standard specifications.
- (3) The department will not consider the bid accepted until the hour and date the Notice to Contractors designates.

B.2 On a Printout with Accompanying Diskette or CD ROM

- (1) Download the latest schedule of items from the Wisconsin pages of the Bid Express™ web site reflecting the latest addenda posted on the department's web site at <http://www.dot.wisconsin.gov/business/engrserv/bid-letting-information.htm>. Use Expedite™ software to prepare and print the schedule of items. Provide a valid amount for all price fields. Follow instructions and review the help screens provided on the Bid Express™ web site to assure that the schedule of items is prepared properly.
- (2) Staple an 8 1/2 by 11 inch printout of the Expedite™ generated schedule of items to the other proposal documents submitted to the department as a part of the bidder's sealed bid. As a separate submittal not in the sealed bid envelop but due at the same time and place as the sealed bid, also provide the Expedite™ generated schedule of items on a 3 1/2 inch computer diskette or CD ROM. Label each diskette or CD ROM with the bidder's name, the 4 character department-assigned bidder identification code from the top of the bidding proposal, and a list of the proposal numbers included on that diskette or CD ROM as indicated in the following example:

Bidder Name

BN00

Proposals: 1, 12, 14, & 22

- (3) If bidding on more than one proposal in the letting, the bidder may include all proposals for that letting on one diskette or CD ROM. Include only submitted proposals with no incomplete or other files on the diskette or CD ROM.
- (4) The bidder-submitted printout of the Expedite™ generated schedule of items is the governing contract document and must conform to the requirements of section 102 of the standard specifications. If a printout needs to be altered, cross out the printed information with ink or typewriter and enter the new information and initial it in ink. If there is a discrepancy between the printout and the diskette or CD ROM, the department will analyze the bid using the printout information.
- (5) In addition to the reasons specified in section 102 of the standard specifications, proposals are irregular and the department may reject them for one or more of the following:
 1. The check code printed on the bottom of the printout of the Expedite™ generated schedule of items is not the same on each page.
 2. The check code printed on the printout of the Expedite™ generated schedule of items is not the same as the check code for that proposal provided on the diskette or CD ROM.

3. The diskette or CD ROM is not submitted at the time and place the department designates.

C Waiver of Electronic Submittal

- (1) The bidder may request a waiver of the electronic submittal requirements. Submit a written request for a waiver in lieu of bids submitted on the internet or on a printout with accompanying diskette or CD ROM. Use the waiver that was included with the paper bid document sent to the bidder or type up a waiver on the bidder's letterhead. The department will waive the electronic submittal requirements for a bidding entity (individual, partnership, joint venture, corporation, or limited liability company) for up to 4 individual proposals in a calendar year. The department may allow additional waivers for equipment malfunctions.
- (2) Submit a schedule of items on paper conforming to [section 102](#) of the standard specifications. The department charges the bidder a \$75 administrative fee per proposal, payable at the time and place the department designates for receiving bids, to cover the costs of data entry. The department will accept a check or money order payable to: "Wisconsin, Dept. of Transportation."
- (3) In addition to the reasons specified in [section 102](#) of the standard specifications, proposals are irregular and the department may reject them for one or more of the following:
 1. The bidder fails to provide the written request for waiver of the electronic submittal requirements.
 2. The bidder fails to pay the \$75 administrative fee before the time the department designates for the opening of bids unless the bidder requests on the waiver that they be billed for the \$75.
 3. The bidder exceeds 4 waivers of electronic submittal requirements within a calendar year.
- (4) In addition to the reasons specified in [section 102](#) of the standard specifications, the department may refuse to issue bidding proposals for future contracts to a bidding entity that owes the department administrative fees for a waiver of electronic submittal requirements.

PROPOSAL BID BOND

DT1303 1/2006

Wisconsin Department of Transportation

Proposal Number	Project Number	Letting Date
Name of Principal		
Name of Surety	State in Which Surety is Organized	

We, the above-named Principal and the above-named Surety, are held and firmly bound unto the State of Wisconsin in the sum equal to the Proposal Guaranty for the total bid submitted for the payment to be made; we jointly and severally bind ourselves, our heirs, executors, administrators, successors and assigns. The condition of this obligation is that the Principal has submitted a bid proposal to the State of Wisconsin acting through the Department of Transportation for the improvement designated by the Proposal Number and Letting Date indicated above.

If the Principal is awarded the contract and, within the time and manner required by law after the prescribed forms are presented for signature, enters into a written contract in accordance with the bid, and files the bond with the Department of Transportation to guarantee faithful performance and payment for labor and materials, as required by law, or if the Department of Transportation shall reject all bids for the work described, then this obligation shall be null and void; otherwise, it shall be and remain in full force and effect. In the event of failure of the Principal to enter into the contract or give the specified bond, the Principal shall pay to the Department of Transportation **within 10 business days of demand** a total equal to the Proposal Guaranty as liquidated damages; the liability of the Surety continues for the full amount of the obligation as stated until the obligation is paid in full.

The Surety, for value received, agrees that the obligations of it and its bond shall not be impaired or affected by any extension of time within which the Department of Transportation may accept the bid; and the Surety does waive notice of any such extension.

IN WITNESS, the Principal and Surety have agreed and have signed by their proper officers and have caused their corporate seals to be affixed this date: **(DATE MUST BE ENTERED)**

PRINCIPAL

(Company Name) **(Affix Corporate Seal)**

(Signature and Title)

(Company Name)

(Signature and Title)

(Company Name)

(Signature and Title)

(Company Name)

(Signature and Title)

(Name of Surety) **(Affix Seal)**

(Signature of Attorney-in-Fact)

NOTARY FOR PRINCIPAL

(Date)

State of Wisconsin)
) ss.
_____ County)

On the above date, this instrument was acknowledged before me by the named person(s).

(Signature, Notary Public, State of Wisconsin)

(Print or Type Name, Notary Public, State of Wisconsin)

(Date Commission Expires)

Notary Seal

NOTARY FOR SURETY

(Date)

State of Wisconsin)
) ss.
_____ County)

On the above date, this instrument was acknowledged before me by the named person(s).

(Signature, Notary Public, State of Wisconsin)

(Print or Type Name, Notary Public, State of Wisconsin)

(Date Commission Expires)

Notary Seal

IMPORTANT: A certified copy of Power of Attorney of the signatory agent must be attached to the bid bond.

CERTIFICATE OF ANNUAL BID BOND

DT1305 8/2003

Wisconsin Department of Transportation

Time Period Valid (From/To)
Name of Surety
Name of Contractor
Certificate Holder Wisconsin Department of Transportation

This is to certify that an annual bid bond issued by the above-named Surety is currently on file with the Wisconsin Department of Transportation.

This certificate is issued as a matter of information and conveys no rights upon the certificate holder and does not amend, extend or alter the coverage of the annual bid bond.

Cancellation: Should the above policy be cancelled before the expiration date, the issuing surety will give thirty (30) days written notice to the certificate holder indicated above.

(Signature of Authorized Contractor Representative)

(Date)

DECEMBER 2000

**CERTIFICATION REGARDING DEBARMENT, SUSPENSION, AND OTHER
RESPONSIBILITY MATTERS - PRIMARY COVERED TRANSACTIONS**

Instructions for Certification

1. By signing and submitting this proposal, the prospective contractor is providing the certification set out below.
2. The inability of a person to provide the certification required below will not necessarily result in denial of participation in this covered transaction. The prospective contractor shall submit an explanation of why it cannot provide the certification set out below. The certification or explanation will be considered in connection with the department or agency's determination whether to enter into this transaction. However, failure of the prospective contractor to furnish a certification or an explanation shall disqualify such person from participation in this transaction.
3. The certification in this clause is a material representation of fact upon which reliance was placed when the department determined to enter into this transaction. If it is later determined that the contractor knowingly rendered an erroneous certification in addition to other remedies available to the Federal Government the department may terminate this transaction for cause or default.
4. The prospective contractor shall provide immediate written notice to the department to whom this proposal is submitted if at any time the prospective contractor learns that its certification was erroneous when submitted or has become erroneous by reason of changed circumstances.
5. The terms "covered transaction," "debarred," "suspended," "ineligible," "lower tier covered transaction," "participant," "person," "primary covered transaction," "principal," "proposal," and "voluntarily excluded," as used in this clause, have the meanings set out in the Definitions and Coverage sections of the rules implementing Executive Order 12549. You may contact the department to which this proposal is being submitted for assistance in obtaining a copy of those regulations.
6. The prospective contractor agrees by submitting this proposal that, should this contract be entered into, it shall not knowingly enter into any lower tier covered transaction with a person who is debarred, suspended, declared ineligible, or voluntarily excluded from participation in this covered transaction, unless authorized by the department entering into this transaction.
7. The prospective contractor further agrees by submitting this proposal that it will include the clause titled "Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion-Lower Tier Covered Transaction," which is included as an addendum to PR-1273 - "Required Contract Provisions Federal Aid Construction Contracts," without

modification, in all lower tier covered transactions and in all solicitations for lower tier covered transactions.

8. The contractor may rely upon a certification of a prospective subcontractor/materials supplier that it is not debarred, suspended, ineligible, or voluntarily excluded from the covered transaction, unless it knows that the certification is erroneous. A contractor may decide the method and frequency by which it determines the eligibility of its principals. Each contractor may, but is not required to, check the Disapproval List (telephone # 608/266/1631).
9. Nothing contained in the foregoing shall be construed to require establishment of a system of records in order to render in good faith the certification required by this clause. The knowledge and information of a contractor is not required to exceed that which is normally possessed by a prudent person in the ordinary course of business dealings.
10. Except for transactions authorized under paragraph 6 of these instructions, if a contractor in a covered transaction knowingly enters into a lower tier covered transaction with a person who is suspended, debarred, ineligible or voluntarily excluded from participation in this transaction, in addition to other remedies available to the Federal Government, the department may terminate this transaction for cause or default.

Certification Regarding Debarment, Suspension, and Other Responsibility Matters - Primary Covered Transactions

- (1) The prospective contractor certifies to the best of its knowledge and belief, that it and its principals:
 - (a) Are not presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from covered transactions by any Federal department or agency;
 - (b) Have not within a three-year period preceding this proposal been convicted of or had a civil judgment rendered against them for commission of fraud or a criminal offense in connection with obtaining, attempting to obtain, or performing a public (Federal, State or local) transaction or contract under a public transaction; violation of Federal or State antitrust statutes or commission of embezzlement, theft, forgery, bribery, falsification or destruction of records, making false statements or receiving stolen property;
 - (c) Are not presently indicted for or otherwise criminally or civilly charged by a governmental entity (Federal, State or local) with commission of any of the offense enumerated in paragraph (1)(b) of this certification; and
 - (d) Have not within a three-year period preceding this proposal had one or more public transactions (Federal, State or local) terminated for cause or default.
- (2) Where the prospective contractor is unable to certify to any of the statements in this certification, such prospective contractor shall attach an explanation to this proposal.

Special Provisions

Table of Contents

Article	Description	Page #
1.	General.....	2
2.	Scope of Work.....	2
3.	Prosecution and Progress.....	2
4.	Traffic.....	3
5.	Holiday Work Restrictions.....	3
6.	Utilities.....	4
7.	Erosion Control.....	5
8.	Coordination with Businesses.....	5
9.	QMP Base Aggregate.....	6
10.	Mill and Relay.....	14
11.	Freeway Lighting Systems.....	14
12.	Temporary Sidewalk, Item SPV.0045.01.....	15
13.	Adjusting Sanitary Sewer Manhole Covers, Item SPV.0060.01.....	16
14.	Internal/External Sanitary Manhole Seals, Item SPV.0060.02.....	16
15.	Connecting Pipe Underdrain 4-Inch to Existing Inlet, Item SPV.0060.03.....	17
16.	Construction Staking Curb Ramp Layout, Item SPV.0060.04.....	18
17.	Removing Luminaires, Item SPV.0060.05.....	19
18.	Lamp Disposal High Intensity Discharge, Item SPV.0060.06.....	19
19.	Sawing Curb Head, Item SPV.0090.01.....	20
20.	Concrete Curb and Gutter 18-Inch, Item SPV.0090.02.....	21
21.	Removing Electrical Wires from Conduit, Item SPV.0090.03.....	21
22.	Fence Safety Modified, Item SPV.0090.04.....	22
23.	Salvaging Bus Shelter, Item SPV.0105.01.....	23
24.	Salvaging Bicycle Rack, Item SPV.0105.02.....	23
25.	Lighting System Survey, Item SPV.0105.03.....	24
26.	Construction Staking Parking Lots Subgrade, Item SPV.0180.01.....	25
27.	Construction Staking Parking Lots Base, Item SPV.0180.02.....	25
28.	Construction Staking Parking Lots Concrete Pavement, Driveways and Sidewalk, Item SPV.0180.03.....	26

SPECIAL PROVISIONS

1. General.

Perform the work under this construction contract for Project 2707-03-71, USH 45 to West Bend, Paradise Drive Park and Ride Lot 66-55, Washington County, Wisconsin as the plans show and execute the work as specified in the State of Wisconsin, Department of Transportation, Standard Specifications for Highway and Structure Construction, 2014 Edition, as published by the department, and these special provisions.

If all or a portion of the plans and special provisions are developed in the SI metric system and the schedule of prices is developed in the US standard measure system, the department will pay for the work as bid in the US standard system.

100-005 (20130615)

2. Scope of Work.

The work under this contract shall consist of grading, storm sewer, base aggregate dense placement, asphaltic milling and relay, HMA pavement, concrete curb and gutter, pavement marking and signing and all incidental items necessary to complete the work as shown on the plans and included in the proposal and contract.

104-005 (20090901)

3. Prosecution and Progress.

Begin work within ten calendar days after the engineer issues a written notice to do so.

Provide the time frame for construction of the project within the 2014 construction season to the engineer in writing within a month after executing the contract but at least 14 calendar days before the preconstruction conference. Assure that the time frame is consistent with the contract completion time. Upon approval, the engineer will issue the notice to proceed within ten calendar days before the beginning of the approved time frame.

To revise the time frame, submit a written request to the engineer at least two weeks before the beginning of the intended time frame. The engineer will approve or deny that request based on the conditions cited in the request and its effect on the department's scheduled resources.

Contact James Weiglein, WisDOT Washington and Ozaukee County Highway Maintenance Coordinator, 14 calendar days prior to construction at (414) 750-1406 or james.weiglein@dot.wi.gov, to coordinate the removal and storage of project trash receptacles.

4. Traffic.

The project site will be closed to traffic during construction. During construction operations, maintain pedestrian access along Parkway Drive, across construction entrances to site at all times in accordance with the Americans with Disabilities Act (ADA) Accessibility Guidelines (ADAAG).

Install a Traffic Control Sign PMCS on the project site 14 calendar days prior to the start of construction. The location and message shall be determined by the engineer.

Designate an individual responsible for traffic control maintenance including access of local traffic, and 24-hour emergency traffic control repair. Provide the name and telephone number of this individual to the engineer at the preconstruction conference.

The contractor shall conduct operations in a manner that will cause the least interference to traffic movements and adjacent business and residential access within the construction areas.

Fill drop-offs as described below and anticipated to exist for more than three continuous days and nights and that have a continuous length of 50 feet or more with aggregates or other approved temporary fill material to provide at minimum a 3:1 slope.

- Drop-offs greater than 6 inches but less than 12 inches less than 2 feet from the travel lane.
- Drop-offs greater than 12 inches but less than 24 inches less than 4 feet from the travel lane.

The parking and storage of construction vehicles, equipment and material shall be outside the clear zone of any roadway carrying traffic during non-working hours except at locations and periods approved by the engineer and shall be restricted to the minimum area required and the minimum time necessary at the work site to prosecute the work. At such location the material and equipment involved shall not constitute a hazard to the traveling public. At no time shall vehicles, equipment or materials be parked or stored in a wetland or other environmentally sensitive area.

5. Holiday Work Restrictions.

Do not perform work on, nor haul materials of any kind along or across any portion of the highway carrying USH 45 traffic, and entirely clear the traveled way and shoulders of such portions of the highway of equipment, barricades, signs, lights, and any other material that might impede the free flow of traffic during the following holiday periods:

- From noon Friday, August 29, 2014 to 6:00 AM Tuesday, September 2, 2014 for Labor Day;
- From noon Wednesday, November 26, 2014 to 6:00 AM Monday, December 1, 2014 for Thanksgiving.

107-005 (20050502)

6. Utilities.

This contract comes under the provision of Administrative Rule Trans 220.107-065 (20080501)

Underground utility facilities are located within the project limits. Utility adjustments are required for this construction project as noted below. Coordinate construction activities with a call to Diggers Hotline or a direct call to the utilities that have facilities in the area as required per statutes. Use caution to ensure the integrity of underground facilities and maintain code clearances from overhead facilities at all times.

Contact each utility company listed in the plans, prior to preparing bids, to obtain current information on the status of existing and any new utility relocation work.

AT&T Wisconsin

Has existing underground facilities located within the project limits. No conflicts are anticipated.

Charter Communications

Has existing underground facilities located within the project limits. No conflicts are anticipated.

City of West Bend

Has existing underground facilities located within the project limits. A sanitary manhole located at Station 2+90, 67' LT will be adjusted as part of project according to plans and specifications under this contract.

Time Warner Telecom

Has existing underground facilities located within the project limits. No conflicts are anticipated.

We Energies-Electric

Has existing poles and overhead line. These facilities will remain in place. No conflicts are anticipated.

We Energies-Gas Ops

Has an existing gas. No conflicts are anticipated.

WisDOT Traffic Lighting

Have existing lighting facilities within the project limits to be modified according to plans and specifications under this contract.

7. Erosion Control.

Replace standard spec. 107.20(3) with the following:

The contractor shall prepare and submit an erosion control implementation plan (ECIP) for the project including borrow sites, material disposal sites, dust control, and dewatering in accordance with Chapter TRANS 401 requirements. The erosion control implementation plan shall supplement information shown on the plans and shall not reproduce it. The erosion control implementation plan will identify how the contractor intends to implement the project's erosion control plan.

Provide the ECIP 14 calendar days prior to the pre-construction conference. Provide 1 copy of the ECIP to WisDOT and 1 copy of the ECIP to the WDNR Transportation Liaison specified in the contacts portion of this contract. Pursue operations in a timely and diligent manner, continuing all construction operations methodically from the initial removals and topsoil stripping operations through the subsequent grading, paving, and re-topsoiling to minimize the period of exposure to possible erosion. Do not implement the ECIP until it has been approved by the department.

Re-topsoil graded areas, as designated by the engineer, immediately after grading is completed within those areas. Seed, fertilizer, and mulch/erosion mat top-soiled areas, as designated by the engineer, within 5 calendar days after placement of topsoil. If graded areas are left exposed for more than 14 calendar days, seed those areas with temporary seed.

When performing roadway cleaning operations, the contractor shall use equipment having vacuum or water spray mechanism to eliminate the dispersion of dust. If vacuum equipment is employed, it shall have suitable self-contained particulate collectors to prevent discharge from the collection bin into the atmosphere.

Stockpile excess material or spoils on upland areas away from wetlands, floodplains and waterways. Stockpiled soil shall be protected against erosion. If stockpiled material is left for more than 14 calendar days, seed the stockpile with temporary seed.

Erosion control BMP's are at suggested locations. The actual locations will be determined by the contractors ECIP and by the engineer. Erosion Control BMP's shall be maintained until permanent vegetation is established or until the engineer determines that the BMP is no longer required.

8. Coordination with Businesses.

The contractor shall arrange and conduct a meeting between the contractor, the department, local officials and business people to discuss the project schedule of operations including vehicular and pedestrian access during construction operations. Hold the first meeting one week prior to the start of work under this contract and hold two meetings per month thereafter.

108-060 (20030820)

9. QMP Base Aggregate.

A Description

A.1 General

- (1) This special provision describes contractor quality control (QC) sampling and testing for base aggregates, documenting those test results, and documenting related production and placement process changes. This special provision also describes department quality verification (QV), independent assurance (IA), and dispute resolution.
- (2) Conform to standard spec 301, standard spec 305, and standard spec 310 as modified here in this special provision. Apply this special provision to material placed under all of the Base Aggregate Dense and Base Aggregate Open Graded bid items, except do not apply this special provision to material classified as reclaimed asphaltic pavement placed under the Base Aggregate Dense bid items.
- (3) Do not apply this special provision to material placed under the Aggregate Detours, Salvaged Asphaltic Pavement Base, Breaker Run, Select Crushed, Pit Run, Subbase, or Riprap bid items.
- (4) Provide and maintain a quality control program, defined as all activities related to and documentation of the following:
 1. Production and placement control and inspection.
 2. Material sampling and testing.
- (5) Chapter 8 of the department's construction and materials manual (CMM) provides additional detailed guidance for QMP work and describes required sampling and testing procedures. The contractor may obtain the CMM from the department's web site at:

<http://roadwaystandards.dot.wi.gov/standards/cmm/index.htm>

A.2 Contractor Testing for Small Quantities

- (1) The department defines a small quantity, for each individual Base Aggregate bid item, as a plan quantity of 9000 tons or less of material as shown in the schedule of items under that bid item.
- (2) The requirements under this special provision apply equally to a small quantity for an individual bid item except as follows:
 1. The contractor need not submit a full quality control plan but shall provide an organizational chart to the engineer including names, telephone numbers, and current certifications of all persons involved in the quality control program for material under affected bid items.

2. Divide the aggregate into uniformly sized sublots for testing as follows:

Plan Quantity	Minimum Required Testing
≤ 1500 tons	One test from production, load-out, or placement at the contractor's option ^[1]
> 1500 tons and ≤ 6000 tons	Two tests of the same type, either from production, load-out, or placement at the contractor's option ^[1]
> 6000 tons and ≤ 9000 tons	Three placement tests ^{[2][3]}

^[1] If using production tests for acceptance, submit test results to the engineer for review prior to incorporating the material into the work. Production test results are valid for a period of 3 years.

^[2] For 3-inch material, obtain samples at load-out.

^[3] If the actual quantity overruns 9000 tons, create overrun sublots to test at a rate of one additional placement test for each 3000 tons, or fraction of 3000 tons, of overrun.

3. No control charts are required. Submit aggregate load-out and placement test results to the engineer within one business day of obtaining the sample. Assure that all properties are within the limits specified for each test.

4. Department verification testing is optional for quantities of 6000 tons or less.

(3) Material represented by a subplot with any property outside the specification limits is nonconforming. The department may reject material or otherwise determine the final disposition of nonconforming material as specified in standard spec 106.5.

B Materials

B.1 Quality Control Plan

(1) Submit a comprehensive written quality control plan to the engineer at or before the pre-construction meeting. Do not place base before the engineer reviews and comments on the plan. Construct the project as that plan provides.

(2) Do not change the quality control plan without the engineer's review. Update the plan with changes as they become effective. Provide a current copy of the plan to the engineer and post in each of the contractor's laboratories as changes are adopted. Ensure that the plan provides the following elements:

1. An organizational chart with names, telephone numbers, current certifications and/or titles, and roles and responsibilities of QC personnel.

2. The process used to disseminate QC information and corrective action efforts to the appropriate persons. Include a list of recipients, the communication means that will be used, and action time frames.

3. A list of source and processing locations, section and quarter descriptions, for all aggregate materials requiring QC testing.

4. Test results for wear, sodium sulfate soundness, freeze/thaw soundness, and plasticity index of all aggregates requiring QC testing. Obtain this information from the region materials unit or from the engineer.

5. Descriptions of stockpiling and hauling methods.
6. Locations of the QC laboratory, retained sample storage, and where control charts and other documentation is posted.
7. An outline for resolving a process control problem. Include responsible personnel, required documentation, and appropriate communication steps.

B.2 Personnel

- (1) Have personnel certified under the department’s highway technician certification program (HTCP) perform sampling, testing, and documentation as follows:

Required Certification Level:	Sampling or Testing Roles:
Aggregate Technician IPP Aggregate Sampling Technician Aggregate Assistant Certified Technician (ACT-AGG)	Aggregate Sampling ^[1]
Aggregate Technician IPP Aggregate Assistant Certified Technician (ACT-AGG)	Aggregate Gradation Testing, Aggregate Fractured Particle Testing, Aggregate Liquid Limit and Plasticity Index Testing

^[1] Plant personnel under the direct observation of an aggregate technician certified at level one or higher may operate equipment to obtain samples.

- (2) A certified technician must coordinate and take responsibility for the work an ACT performs. Have a certified technician ensure that all sampling and testing is performed correctly, analyze test results, and post resulting data. No more than one ACT can work under a single certified technician.

B.3 Laboratory

- (1) Perform QC testing at a department-qualified laboratory. Obtain information on the Wisconsin laboratory qualification program from:

Materials Management Section
3502 Kinsman Blvd.
Madison, WI 53704
Telephone: (608) 246-5388

<http://www.dot.state.wi.us/business/engrserv/lab-qualification.htm>

B.4 Quality Control Documentation

B.4.1 General

- (1) Submit base aggregate placement documentation to the engineer within 10 business days after completing base placement. Ensure that the submittal is complete, neatly organized, and includes applicable project records and control charts.

B.4.2 Records

- (1) Document all placement observations, inspection records, and control adjustments daily in a permanent field record. Also include all test results in the project records. Provide test results to the engineer within 6 hours after obtaining a sample. For 3-inch

base, extend this 6-hour limit to 24 hours. Post or distribute tabulated results using a method mutually agreeable to the engineer and contractor.

B.4.3 Control Charts

- (1) Plot gradation and fracture on the appropriate control chart as soon as test results are available. Format control charts according to CMM 8.30. Include the project number on base placement control charts. Maintain separate control charts for each base aggregate size, source or classification, and type.
- (2) Provide control charts to the engineer within 6 hours after obtaining a sample. For 3-inch base, extend this 6-hour limit to 24 hours. Post or distribute charts using a method mutually agreeable to the engineer and contractor. Update control charts daily to include the following:
 1. Contractor individual QC tests.
 2. Department QV tests.
 3. Department IA tests.
 4. Four-point running average of the QC tests.
- (3) Except as specified under B.8.2.1 for nonconforming QV tests, include only QC tests in the running average. The contractor may plot process control or informational tests on control charts, but do not include these tests, conforming QV tests, or IA tests in the running average.

B.5 Contractor Testing

- (1) Test gradation, fracture, liquid limit and plasticity index during placement for each base aggregate size, source or classification, and type.
- (2) Test gradation once per 3000 tons of material placed. Determine random sample locations and provide those sample locations to the engineer. Obtain samples after the material has been bladed, mixed, and shaped but before compacting; except collect 3-inch samples from the stockpile at load-out. Do not sample from material used to maintain local traffic or from areas of temporary base that will not have an overlying pavement. On days when placing only material used to maintain local traffic or only temporary base that will not have an overlying pavement, no placement testing is required.
- (3) Split each contractor QC sample and identify it according to CMM 8.30. Retain the split for 7 calendar days in a dry, protected location. If requested for department comparison testing, deliver the split to the engineer within one business day.
- (4) The engineer may require additional sampling and testing to evaluate suspect material or the technician's sampling and testing procedures.
- (5) Test fracture for each gradation test until the fracture running average is above the lower warning limit. Subsequently, the contractor may reduce the frequency to one test per 10 gradation tests if the fracture running average remains above the warning limit.

- (6) Test the liquid limit and plasticity index for the first gradation test. Subsequently, test the liquid limit and plasticity index a minimum of once per 10 gradation tests.

B.6 Test Methods

B.6.1 Gradation

- (1) Test gradation using a washed analysis conforming to the following as modified in CMM 8.60:

Gradation.....	AASHTO T 27
Material finer than the No. 200 sieve.....	AASHTO T 11

- (2) For 3-inch base, if 3 consecutive running average points for the percent passing the No. 200 sieve are 8.5 percent or less, the contractor may use an unwashed analysis. Wash at least one sample out of 10. If a single running average for the percent passing the No. 200 sieve exceeds 8.5 percent, resume washed analyses until 3 consecutive running average points are again 8.5 percent passing or less.
- (3) Maintain a separate control chart for each sieve size specified in standard spec 305 or standard spec 310 for each base aggregate size, source or classification, and type. Set control and warning limits based on the standard specification gradation limits as follows:
 1. Control limits are at the upper and lower specification limits.
 2. There are no upper warning limits for sieves allowing 100 percent passing and no lower control limits for sieves allowing 0 percent passing.
 3. Dense graded warning limits, except for the No. 200 sieve, are 2 percent within the upper and lower control limits. Warning limits for the No. 200 sieve are set 0.5 percent within the upper and lower control limits.
 4. Open graded warning limits for the 1-inch, 3/8-inch, and No. 4 sieves are 2 percent within the upper and lower control limits. Upper warning limits for the No. 10, No. 40, and No. 200 sieves are 1 percent inside the upper control limit.

B.6.2 Fracture

- (1) Test fracture conforming to CMM 8.60. The engineer will waive fractured particle testing on quarried stone.
- (2) Maintain a separate fracture control chart for each base aggregate size, source or classification, and type. Set the lower control limit at the contract specification limit, either specified in another special provision or in table 301-2 of standard spec 301.2.4.5. Set the lower warning limit 2 percent above the lower control limit. There are no upper limits.

B.6.3 Liquid Limit and Plasticity

- (1) Test the liquid limit and plasticity according to AASHTO T 89 and T 90.
- (2) Ensure the material conforms to the limits specified in standard spec table 301-2.

B.7 Corrective Action

B.7.1 General

- (1) Consider corrective action when the running average trends toward a warning limit. Take corrective action if an individual test exceeds the contract specification limit. Document all corrective actions both in the project records and on the appropriate control chart.

B.7.2 Placement Corrective Action

- (1) Do not blend additional material on the roadbed to correct gradation problems.
- (2) Notify the engineer whenever the running average exceeds a warning limit. When 2 consecutive running averages exceed a warning limit, the engineer and contractor will discuss appropriate corrective action. Perform the engineer's recommended corrective action and increase the testing frequency as follows:
 1. For gradation, increase the QC testing frequency to at least one randomly sampled test per 1000 tons placed.
 2. For fracture, increase the QC testing frequency to at least one test per gradation test.
- (3) If corrective action improves the property in question such that the running average after 4 additional tests is within the warning limits, the contractor may return to the testing frequency specified in B.5.3. If corrective action does not improve the property in question such that the running average after 4 additional individual tests is still in the warning band, repeat the steps outlined above starting with engineer notification.
- (4) If the running average exceeds a control limit, material starting from the first running average exceeding the control limit and ending at the first subsequent running average inside the control limit is nonconforming and subject to pay reduction.
- (5) For individual test results significantly outside the control limits, notify the engineer, stop placing base, and suspend other activities that may affect the area in question. The engineer and contractor will jointly review data, data reduction, and data analysis; evaluate sampling and testing procedures; and perform additional testing as required to determine the extent of potentially unacceptable material. The engineer may direct the contractor to remove and replace that material. Individual test results are significantly outside the control limits if meeting one or more of the following criteria:
 1. A gradation control limit for the No. 200 sieve is exceeded by more than 3.0 percent.
 2. A gradation control limit for any sieve, except the No. 200, is exceeded by more than 5.0 percent.
 3. The fracture control limit is exceeded by more than 10.0 percent.

B.8 Department Testing

B.8.1 General

- (1) The department will conduct verification testing to validate the quality of the product and independent assurance testing to evaluate the sampling and testing. The

department will provide the contractor with a listing of names and telephone numbers of all QV and IA personnel for the project, and provide test results to the contractor within 2 business days after the department obtains the sample.

B.8.2 Verification Testing

B.8.2.1 General

- (1) The department will have an HTCP technician, or ACT working under a certified technician, perform QV sampling and testing. Department verification testing personnel must meet the same certification level requirements specified in B.2 for contractor testing personnel for each test result being verified. The department will notify the contractor before sampling so the contractor can observe QV sampling.
- (2) The department will conduct QV tests of each base aggregate size, source or classification, and type during placement conforming to the following:
 1. One non-random test on the first day of placement.
 2. At least one random test per 30,000 tons, or fraction of 30,000 tons, placed.
- (3) The department will sample randomly, at locations independent of the contractor's QC work, collecting one sample at each QV location. The department will collect QV samples after the material has been bladed, mixed, and shaped but before compacting; except, for 3-inch aggregates, the department will collect samples from the stockpile at load-out. The department will split each sample, test half for QV, and retain half.
- (4) The department will conduct QV tests in a separate laboratory and with separate equipment from the contractor's QC tests. The department will use the same methods specified for QC testing.
- (5) The department will assess QV results by comparing to the appropriate specification limits. If QV test results conform to the specification, the department will take no further action. If QV test results are nonconforming, add the QV to the QC test results as if it were an additional QC test.

B.8.3 Independent Assurance

- (1) Independence assurance is unbiased testing the department performs to evaluate the department's QV and the contractor's QC sampling and testing including personnel qualifications, procedures, and equipment. The department will perform an IA review according to the department's independent assurance program. That review may include one or more of the following:
 1. Split sample testing.
 2. Proficiency sample testing.
 3. Witnessing sampling and testing.
 4. Test equipment calibration checks.
 5. Reviewing required worksheets and control charts.
 6. Requesting that testing personnel perform additional sampling and testing.

- (2) If the department identifies a deficiency, and after further investigation confirms it, correct that deficiency. If the contractor does not correct or fails to cooperate in resolving identified deficiencies, the engineer may suspend placement until action is taken. Resolve disputes as specified in B.9.

B.9 Dispute Resolution

- (1) The engineer and contractor should make every effort to avoid conflict. If a dispute between some aspect of the contractor's and the engineer's testing program does occur, seek a solution mutually agreeable to the project personnel. The department and contractor may review the data, examine data reduction and analysis methods, evaluate sampling and testing procedures, and perform additional testing. Use ASTM E 178 to evaluate potential statistically outlying data.
- (2) Production test results, and results from other process control testing, may be considered when resolving a dispute.
- (3) If the project personnel cannot resolve a dispute, and the dispute affects payment or could result in incorporating non-conforming product, the department will use third party testing to resolve the dispute. The department's central office laboratory, or a mutually agreed on independent testing laboratory, will provide this testing. The engineer and contractor will abide by the results of the third party tests. The party in error will pay service charges incurred for testing by an independent laboratory. The department may use third party test results to evaluate the quality of questionable materials and determine the appropriate payment. The department may reject material or otherwise determine the final disposition of nonconforming material as specified in standard spec 106.5.

C (Vacant)

D (Vacant)

E Payment

- (1) Costs for all sampling, testing, and documentation required under this special provision are incidental to this work. If the contractor fails to perform the work required under this special provision, the department may reduce the contractor's pay. The department will administer pay reduction under the non-performance of QMP administrative item.
- (2) For material represented by a running average exceeding a control limit, the department will reduce pay by 10 percent of the contract price for the affected Base Aggregate bid items listed in subsection A. The department will administer pay reduction under the Nonconforming QMP Base Aggregate Gradation or Nonconforming QMP Base Aggregate Fracture Administrative items. The department will determine the quantity of nonconforming material as specified in B.7.2.

301-010 (20100709)

10. Mill and Relay.

Replace standard spec 330.3(2) with the following:

- (2) Immediately after milling, relay the material with a paver, grader, or both a paver and grader.
330-001 (20080902)

11. Freeway Lighting Systems.

General

Append standard specs 651, 652, 653, 654, 655, 656, 657 and 659 as follows.

Wet Location Splices

Modify standard spec 655.3.1 as follows:

Wet location splices are not anticipated on this project and not shown in the plans. In the event that the engineer allows wet location splices, make pull box splices with engineer approved epoxy kit.

Branch Circuit Tagouts

Any circuit that the contractor does not personally tag out at the disconnect shall be considered live, and will be subject to being activated by another person with no notice to the contractor. Make tagouts with manufactured tags, and endorse them with the date and the name of the contractor. Clear tagouts at the end of the workday.

Shop Locations

Materials indicated to be returned to the department shall be hauled to one of the following two locations:

- Milwaukee County Grounds, 10191 West Watertown Plank Road, Wauwatosa, as directed by Mr. Pat Stoetzel, (414) 750-5306.
- State Electrical Shop at 935 South 60th street, West Allis, as directed by Mr. Mike Prebish, (414) 266-1170.

Arrange pickups and deliveries three days in advance and during regular business hours (Monday – Thursday 7:00 AM to 3:45 PM).

Corrosion Protection

Corrosion protection measures described in standard specs 657.3.1 and 657.3.5 are invoked for breakaway transformer bases and aluminum light poles.

Wire Networks

Where two or more wire networks pass through a pull point, tag each circuit network (i.e. A/B/N and C/D/N) with approved all-weather tags.

At each pull point or access point, indicate the line side bundle with a lap of blue tape.

Lighting Pull Box Covers

This provision modifies the standard detail drawing for pull boxes and thereby both the standard items and SPV pay item for pull boxes. Lighting pull box covers shall read “LIGHTING”.

12. Temporary Sidewalk, Item SPV.0045.01.

A Description

This special provision describes maintaining accessible sidewalks crossing a construction zone. Maintaining accessible sidewalks consists of maintaining a sidewalk on temporary surface material.

B Materials

Furnish a hard temporary surface material consisting of asphaltic surface temporary in accordance to standard spec 465, any grade of concrete, skid resistant steel plating, or alternative material as approved by the engineer. Gravel or base course material is not acceptable.

C Construction

Install, maintain, move, and remove temporary surface material at temporary sidewalk locations as approved by the engineer. Level and compact the surface prior to placing temporary surface material. Provide a minimum clear width of 4 feet; be located outside the immediate work area, as approved by the engineer; meeting the requirements of the current Americans with Disabilities Act Accessibility Guidelines (ADAAG). Reconstruct or relay temporary sidewalk when disturbed by construction operations or utility trenches.

D Measurement

The department will measure Temporary Sidewalk by the day acceptably completed. The measured quantity will equal the number of calendar days a temporary sidewalk through the work area, is open to pedestrian traffic once placement of temporary sidewalk begins. Temporary sidewalk is defined as an accessible crossing covering both driveway entrances. Each day that the sidewalk is out of service for more than 2 hours will result in one day being deducted from the quantity measured for payment.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

Item Number	Description	Unit
SPV.0045.01	Temporary Sidewalk	Day

Payment is full compensation for furnishing, loading, hauling; for preparing the foundation; for furnishing, placing, maintaining, and removing temporary surface material; and for reconstructing or relaying the temporary surface material.

13. Adjusting Sanitary Sewer Manhole Covers, Item SPV.0060.01.

A Description

This work consists of adjusting sanitary sewer manhole covers to match the proposed finish grade.

B Material

Shall conform to section 405 of the City of West Bend Standard Specifications.

C Construction

Shall conform to section 405 of the City of West Bend Standard Specifications.

D Measurement

The department will measure Adjusting Sanitary Sewer Manhole Covers as each individual unit, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0060.01	Adjusting Sanitary Sewer Manhole Covers	Each

Payment is full compensation for furnishing all labor, tools and materials, exclusive of frames, grates or lids available and designated for adjusting; and for removing, reinstalling and adjusting the covers. The contractor shall replace all covers to be adjusted that are unusable due to the contractor's operations, at no expense to the department.

14. Internal/External Sanitary Manhole Seals, Item SPV.0060.02.

A Description

The work under this item consists of furnishing and installing internal/external manhole chimney seals.

B Material

Shall conform to section 405 of the City of West Bend Standard Specifications.

C Construction

Shall conform to Section 404 and Detail 402 of the City of West Bend Standard Specifications and the manufacturer's written instructions.

D Measurement

The department will measure Internal/External Manhole Seals as each individual unit, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid items:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0060.02	Internal/External Sanitary Manhole Seals	Each

Payment is full compensation for furnishing and installing internal/external rubber chimney seals and for furnishing all labor, tools, equipment and incidentals necessary to complete the work.

15. Connecting Pipe Underdrain 4-Inch to Existing Inlet, Item SPV.0060.03.

A Description

This special provision describes excavating, drilling/coring, removing debris from the work, installing pipe underdrain, and backfilling at inlets in locations where the engineer directs. The intent is to provide positive drainage in the proposed pipe underdrain between the inlet and the base of the EBS backfill or base aggregate beneath paved areas.

B Materials

Furnish mortar conforming to standard spec 501.

C Construction

Install in accordance with the plan details for the intended use, as directed by the engineer in the field. Connect new Pipe Underdrain 4-Inch to existing inlets as shown on the plan or as directed by the engineer.

Provide an excavation adjacent to existing inlet structure large enough to complete the required work.

Core or drill a hole in sidewall of the existing inlet structure, of sufficient diameter to accommodate Pipe Underdrain 4-Inch. Install Pipe Underdrain 4-Inch the full thickness of the concrete inlet wall, plus 4-inches extending into the inlet box. Mortar the space between the pipe underdrain and the inside of the hole in the inlet wall. Place the hole at the location shown on the plans or as directed by the engineer.

Backfill the excavation in lifts of 8 inches and compact each lift prior to placing the next lift, to prevent settlement of the material supporting the pipe underdrain, or settlement of the completed ground surface adjacent to the inlet.

Meet the pertinent requirements as set forth in standard spec 612.3.5 (2) amended as follows:

The contractor may backfill Pipe Underdrain 4-inch at the inlet and within the landscape area suitable material from the trench or roadway excavation. Beneath paved areas, backfill the pipe underdrain with base aggregate open graded.

D Measurement

The department will measure Connecting Pipe Underdrain 4-Inch to Existing Inlet by each individual unit, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0060.03	Connecting Pipe Underdrain 4-Inch to Existing Inlet	Each

Payment is full compensation for excavating at the inlet, coring or drilling, cleaning, including removal of the concrete core from hole drilled in the wall of the inlet; for any checking of elevations; for any associated dewatering; for providing and placing mortar, providing and placing all backfill; for maintaining temporary drainage; and for disposing of surplus material. The Pipe Underdrain 4-inch, Base Aggregate Open Graded, Base Aggregate Dense 1 1/4", Base Aggregate Dense 3/4", and/or Breaker Run items are paid separately as part of the roadway work and use of these materials for Connecting Pipe Underdrain 4-Inch to Existing Inlet are incidental to the Connecting Pipe Underdrain 4-Inch to Existing Inlet bid item.

16. Construction Staking Curb Ramp Layout, Item SPV.0060.04.

A Description

This work shall be in accordance with the applicable provisions of standard spec 650.

B (Vacant)

C Construction

Plan and layout all points necessary to establish horizontal and vertical position of the curb ramp in accordance with Americans with Disabilities Act (ADA) Accessibility Guidelines (ADAAG) and as detailed in the plans.

D Measurement

The department will measure Construction Staking Curb Ramp Layout as each individual curb ramp, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid items:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0060.04	Construction Staking Curb Ramp Layout	Each

Payment for Construction Staking Curb Ramp bid item is full compensation for planning and layout of curb ramps including setting lathe, stakes, pins, string line or other materials used to establish the horizontal and vertical position of the curb ramp; for resetting damaged or missing construction staking materials.

17. Removing Luminaires, Item SPV.0060.05.

A Description

The work under this item shall consist of removing existing luminaires from light poles intended to remain in service.

B (Vacant)

C Construction

Dispose of all materials off the site, except sodium vapor lamps. Lamps shall be disposed of under the requirements of a separate pay item.

D Measurement

The department will measure Removing Luminaires by each individual unit, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0060.05	Removing Luminaires	Each

Payment is full compensation for removing, hauling, and properly disposing of materials.

18. Lamp Disposal High Intensity Discharge, Item SPV.0060.06.

A Description

This special provision describes packaging, palletizing, and returning HID (metal halide; mercury vapor and high-pressure sodium) lamps removed under this contract to the department at the South 60th Street, West Allis, location.

B (Vacant)

C Construction

Lamps that the contractor turns in to the department will be considered the property of the department for proper future disposal. The contractor will have no further obligation for their disposal. The department will reject improperly packaged lamps.

Deliveries to the department shall be prearranged. Deliveries shall be consolidated into a truckload or more, except that where all the lamps removed under a contract measure less than a truckload, all shall be delivered as one load at one time.

Pack intact lamps in the packaging of the new lamps used to replace the old lamps, or packaging affording the equivalent protection. Deliver in full, closed, stackable cartons with the name of the contractor, the number and type/ wattage of lamps clearly written on each carton.

Pack broken lamps into minimum 6 mil plastic bags, which in turn shall be placed inside sturdy cardboard boxes or the equivalent, with the number of lamps clearly marked on each box. Mark the outer packaging "broken lamps". The department will reject metal containers.

Deliver all broken lamps, as noted above. The department will not pay broken lamps above a level of ten percent of the total number in the contract. Deliver broken lamps above the ten percent level to the department for no compensation.

If palletized, cartons shall be piled no more than two high and shall be secured with shrink-wrap to prevent shifting or falling loads. Label the pallets by the number and type/ wattage of lamps, and the name of the contractor.

The department will reject any lamps not removed as part of a contract pay item or otherwise required under this contract.

D Measurement

The department will measure Lamp Disposal High Intensity Discharge by each individual unit delivered to the department properly packaged, acceptably completed. This payment will be in addition to payment for the work under which the lamps are removed from service.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0060.06	Lamp Disposal High Intensity Discharge	Each

Payment is full compensation for packaging, palletizing and delivering lamps without breakage.

19. Sawing Curb Head, Item SPV.0090.01.

A Description

This special provision describes sawing curb head as shown on the plans and as hereinafter provided.

B (Vacant)

C Construction

Saw curb head in accordance with the applicable portions of standard spec 690. Remove leftover concrete curb head material debris in accordance with the applicable portions of standard spec 204.

D Measurement

The department will measure Sawing Curb Head by the linear foot, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid items:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0090.01	Sawing Curb Head	LF

Payment is full compensation for furnishing all sawing and sludge removal; and for disposal of leftover concrete curb head material debris.

20. Concrete Curb and Gutter 18-Inch, Item SPV.0090.02.

Construct the curb and gutter in accordance to standard spec 601 and in accordance to the plan details.

21. Removing Electrical Wires from Conduit, Item SPV.0090.03.

A Description

This special provision describes removing of electrical wires from existing conduits and disposal off of the project site.

B (Vacant)

C Construction

No removal work will be permitted without approval from the engineer. Removal shall start as soon as the temporary lighting or permanent lighting, as applicable, is placed in approved operation. An inspection and approval by the engineer will take place before any associated proposed permanent or temporary lighting is approved for operation.

All wires shall be removed from the existing embedded or underground conduits as shown on the plans and as directed by the engineer. Any necessary splices or disconnections shall be done as part of this pay items. Removed wires shall become property of the contractor and shall be disposed of off of the project site.

D Measurement

The department will measure Removing Electrical Wires from Conduit by linear feet of conduit from where wires shall be removed and disposed of, as directed by the engineer, acceptably completed. The vertical length and wire slack shall be incidental to this pay item.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0090.03	Removing Electrical Wires from Conduit	LF

Payment is full compensation for removing electrical wires from conduits; and for disposal of all removed materials.

22. Fence Safety Modified, Item SPV.0090.04.

A Description

This special provision describes furnishing and installing a plastic fence at locations shown on the plans and as hereinafter provided.

B Materials

Furnish fence fabric meeting the following requirements.

Color:	International orange (UV stabilized)
Roll Height:	4 feet
Mesh Opening:	1 inch min to 3 inch max
Resin/Construction:	High density polyethylene mesh
Service Temperature:	-60° F to 200° (ASTM D648)
Tensile Yield:	Avg. 2000 lb per 4 ft. width (ASTM D638)
Ultimate Tensile Strength:	Avg. 3000 lb per 4 ft. width (ASTM D638)
Elongation at Break (%):	Greater than 100% (ASTM D638)
Chemical Resistance:	Inert to most chemicals and acids

C Construction

Place temporary supports such that the gap between each support does not exceed 7 feet and as not to damage existing pavement. Weight each temporary support with sand bags or other engineer approved material to keep the fence in its intended location.

Use a minimum of three wire ties to secure the fence at each support. Weave tension wire through the top row of strands to provide a top stringer that prevents sagging.

Overlap two rolls at a temporary support and secure with wire ties.

D Measurement

The department will measure Fence Safety Modified by the linear foot along the base of the fence, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0090.04	Fence Safety Modified	LF

Payment is full compensation for furnishing and installing fence, temporary supports; maintaining the fence and supports in satisfactory condition; and for removing and disposing of fence and supports at project completion.

23. Salvaging Bus Shelter, Item SPV.0105.01.

A Description

Remove, handle, store, and re-erect the bus shelter and all appurtenant hardware without damaging the parts. Replace contractor-damaged parts and provide all other materials, required to re-erect the bus shelter. Dispose of all surplus materials.

B Material

Provide all new anchor bolts and anchor flanges.

Furnish anchor bolts and anchor flanges to the designated manufacturer’s specifications for Handi-Hut Shelters.

Handi-Hut, Inc.
3 Grunwald Street
Clifton, NJ 07013
(800) 603-6635

C Construction

Re-install Handi-Hut bus shelter at the location shown on the plan per the manufacturer’s requirements including new anchor bolts and anchor flanges. Provide the engineer with a copy of manufacturer’s instructions prior to any work.

In the event that damage does occur to any item that is designated for re-use in the new work, repair or replace the damaged item at no expense to the department.

D Measurement

The department will measure Salvaging Bus Shelter as a single lump sum unit of work, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0105.01	Salvaging Bus Shelter	LS

Payment is full compensation for removing the bus shelter and existing anchor flanges; properly storing the bus shelter, providing and installing new anchor bolts and new anchor flanges, replacing the bus shelter and all incidental work necessary to complete the contract work.

24. Salvaging Bicycle Rack, Item SPV.0105.02.

A Description

Remove, handle, store, and re-erect the bus shelter and all appurtenant hardware without damaging the parts. Replace contractor-damaged parts and provide all other materials, required to re-erect the bicycle rack. Dispose of all surplus materials.

B (Vacant)

C Construction

Remove the bicycle rack, clean concrete from bicycle rack supports, taking care not to damage them. Store the bicycle rack in an area away from construction activities to preclude damage to the bicycle rack.

In the event that damage does occur to any item that is designated for re-use in the new work, repair or replace the damaged item at no expense to the department.

D Measurement

The department will measure Salvaging Bicycle Rack as a single complete lump sum unit of work acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0105.02	Salvaging Bicycle Rack	LS

Payment is full compensation for removing the existing bicycle rack and supports; cleaning supports, properly storing the bicycle rack; and for reinstalling bicycle rack in new concrete sidewalk with proper hardware as detailed in the plan.

25. Lighting System Survey, Item SPV.0105.03.

A Description

These special provisions describe performing lighting system survey using Global Position System (GPS).

B (Vacant)

C Construction

Locate and survey using GPS all the lighting units and control cabinets. Maintain neat, orderly, and complete survey notes. Enter the coordinates into a Microsoft Excel 2007 spreadsheet along with other required fields as specified by WisDOT.

D Measurement

The department will measure Lighting System Survey for all lighting units and control cabinets as a single lump sum unit of work, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit prices under the following bid items:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0105.03	Lighting System Survey	LS

Payment is full compensation for locating and surveying all the lighting units and control cabinets.

26. Construction Staking Parking Lots Subgrade, Item SPV.0180.01.

A Description

Perform the work in accordance with the applicable provisions of standard spec 650.3.3 for subgrade; and standard spec 650.3.4 for base.

B (Vacant)

C Construction

Set additional construction stakes as necessary to establish location and grade of the parking lots including points of change in alignment and grade in accordance with the plans.

D Measurement

The department will measure Construction Staking Parking Lots Subgrade by the square yard, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid items:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0180.01	Construction Staking Parking Lots Subgrade	SY

Payment for Construction Staking Parking Lots Subgrade bid item is full compensation for locating and setting all construction stakes; for relocating and resetting damaged or missing construction stakes.

27. Construction Staking Parking Lots Base, Item SPV.0180.02.

A Description

Perform the work in accordance with the applicable provisions of standard spec 650.3.3, for subgrade, and standard spec 650.3.4 for base.

B (Vacant)

C Construction

Set additional construction stakes as necessary to establish location and grade of the parking lots including points of change in alignment and grade in accordance with the plans.

D Measurement

The department will measure Construction Staking Parking Lots Base by the square yard, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid items:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0180.02	Construction Staking Parking Lots Base	SY

Payment for Construction Staking Parking Lots Base bid item is full compensation for locating and setting all construction stakes; for relocating and resetting damaged or missing construction stakes.

28. Construction Staking Parking Lots Concrete Pavement, Driveways and Sidewalk, Item SPV.0180.03.

A Description

Perform the work in accordance with the applicable provisions of standard spec 650.3.8.

B (Vacant)

C Construction

Set additional construction stakes as necessary to establish location and grade of the parking lots including points of change in alignment and grade in accordance with the plans.

D Measurement

The department will measure Construction Staking Parking Lots Concrete Pavement, Driveways and Sidewalk by the square yard, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid items:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0180.03	Construction Staking Parking Lots Concrete Pavement, Driveways and Sidewalk	SY

Payment for Construction Staking Parking Lots Concrete Pavement, Driveways and Sidewalk bid item is full compensation for locating and setting all construction stakes; for relocating and resetting damaged or missing construction stakes.

ADDITIONAL SPECIAL PROVISION 4

Payment to First-Tier Subcontractors

Within 10 calendar days of receiving a progress payment for work completed by a subcontractor, pay the subcontractor for that work. The prime contractor may withhold payment to a subcontractor if, within 10 calendar days of receipt of that progress payment, the prime contractor provides written notification to the subcontractor and the department documenting "just cause" for withholding payment.

The prime contractor may also withhold routine retainage from payments due subcontractors.

Payment to Lower-Tier Subcontractors

Ensure that subcontracting agreements at all tiers provide prompt payment rights to lower-tier subcontractors that parallel those granted first-tier subcontractors in this provision.

Release of Routine Retainage

After granting substantial completion the department may reduce the routine retainage withheld from the prime contractor to 75 percent of the original total amount retained.

When the Department sends the semi-final estimate the department may reduce the routine retainage withheld from the prime contractor to 10 percent of the original total amount retained.

Within 30 calendar days of receiving the semi-final estimate from the department, submit written certification that subcontractors at all tiers are paid in full for acceptably completed work and that no routine retainage is being withheld. The department will pay the prime contractor in full and reduce the routine retainage withheld from the prime contractor to zero when the department approves the final estimate.

This special provision does not limit the right of the department, prime contractor, or subcontractors at any tier to withhold payment for work not acceptably completed or work subject to an unresolved contract dispute.

ADDITIONAL SPECIAL PROVISION 6**ASP 6 - Modifications to the standard specifications**

Make the following revisions to the 2014 edition of the standard specifications:

101.3 Definitions

Replace the definition of semi-final estimate with the following effective with the December 2013 letting:

Semi-final estimate An estimate indicating the engineer has measured and reported all contract quantities and materials requirements.

105.11.1 Partial Acceptance

Replace paragraph two with the following effective with the December 2013 letting:

- (2) Partial acceptance will relieve the contractor of maintenance responsibility for the designated portion of the work. By relieving the contractor of maintenance, the department does not relieve the contractor of responsibility for defective work or damages caused by the contractor's operations. Do not construe partial acceptance to be conditional final acceptance or final acceptance of any part of the project, or a waiver of any legal rights specified under 107.16.
-

105.11.2 Final Acceptance

Retitle and replace the entire text with the following effective with the December 2013 letting:

105.11.2 Project Acceptance**105.11.2.1 Inspection****105.11.2.1.1 General**

- (1) Notify the engineer when the project is substantially complete as defined in 105.11.2.1.3. As soon as it is practical, the engineer will inspect the work and categorize it as one of the following:
1. Unacceptable or not complete.
 2. Substantially complete.
 3. Complete.

105.11.2.1.2 Unacceptable or Not Complete

- (1) The engineer will identify, in writing, work that is unacceptable or not complete. Immediately correct or complete that work. The engineer will assess contract time until the work is corrected or completed.
- (2) Proceed as specified in 105.11.2.1.1 until the engineer determines that the work is complete.

105.11.2.1.3 Substantially Complete

- (1) The project is substantially complete and the engineer will no longer assess contract time if the contractor has completed all contract bid items and change order work, except for the punch-list. As applicable, the following must have occurred:
1. All lanes of traffic are open on a finished surface.
 2. All signage and traffic control devices are in place and operating.
 3. All drainage, erosion control, excavation, and embankments are completed.
 4. All safety appurtenances are completed.
- (2) The engineer will provide a written punch-list enumerating work the contractor must perform and documents the contractor must submit before the the engineer will categorize the work as complete.
1. Punch-list work includes uncompleted cleanup work required under 104.9 and minor corrective work. Immediately correct or complete the punch-list work. The engineer may restart contract time if the contractor does not complete the punch-list work within 5 business days after receiving the written punch-list. The engineer and contractor may mutually agree to extend this 5-day requirement.
 2. Punch-list documents include whatever contract required documentation is missing. The engineer may restart contract time if the contractor does not submit the punch-list documents within 15 business days after receiving the written punch-list. The engineer and contractor may mutually agree to extend this 15-day requirement.
- (3) Proceed as specified in 105.11.2.1.1 until the work is complete.

105.11.2.1.4 Complete

- (1) The project is complete when the contractor has completed all contract bid items, change order work, and punch-list work including the submission of all missing documentation.

105.11.2.2 Conditional Final Acceptance

- (1) When the engineer determines that the project is complete, the engineer will give the contractor written notice of conditional final acceptance relieving the contractor of maintenance responsibility for the completed work.

105.11.2.3 Final Acceptance

- (1) The engineer will grant final acceptance of the project after determining that all contract is work complete; all contract, materials, and payroll records are reviewed and approved; and the semi-final estimate quantities are final under 109.7.
- (2) Failure to discover defective work or materials before final acceptance does not prevent the department from rejecting that work or those materials later. The department may revoke final acceptance if the department discovers defective work or materials after it has accepted the work.

105.13.3 Submission of Claim

Replace paragraph one with the following effective with the December 2013 letting:

- (1) Submit the claim to the project engineer as promptly as possible following the submission of the Notice of Claim, but not later than final acceptance of the project as specified in 105.11.2.3. If the contractor does not submit the claim before final acceptance of the project, the department will deny the claim.

107.17.3 Railroad Insurance Requirements

Replace paragraph one with the following effective with the December 2013 letting:

- (1) If required by the special provisions, provide or arrange for a subcontractor to provide railroad protective liability insurance in addition to the types and limits of insurance required in 107.26. Keep railroad protective liability insurance coverage in force until completing all work, under or incidental to the contract, on the railroad right of way or premises of the railroad and until the engineer determines that the work is complete as specified in 105.11.2.1.4.

107.26 Standard Insurance Requirements

Replace paragraph one with the following effective with the December 2013 letting:

- (1) Maintain the following types and limits of commercial insurance in force until the engineer determines that the work is complete as specified in 105.11.2.1.4.

TABLE 107-1 REQUIRED INSURANCE AND MINIMUM COVERAGES

TYPE OF INSURANCE	MINIMUM LIMITS REQUIRED ^[1]
1. Commercial general liability insurance endorsed to include blanket contractual liability coverage. ^[2]	\$2 million combined single limits per occurrence with an annual aggregate limit of not less than \$4 million.
2. Workers' compensation.	Statutory limits
3. Employers' liability insurance.	Bodily injury by accident: \$100,000 each accident Bodily injury by disease: \$500,000 each accident \$100,000 each employee
4. Commercial automobile liability insurance covering all contractor-owned, non-owned, and hired vehicles used in carrying out the contract. ^[2]	\$1 million-combined single limits per occurrence.

^[1] The contractor may satisfy these requirements with primary insurance coverage or with excess/umbrella policies.

^[2] The Wisconsin Department of Transportation, its officers, agents, and employees shall be named as an additional insured under the general liability and automobile liability insurance.

108.14 Terminating the Contractor's Responsibility

Replace paragraph one with the following effective with the December 2013 letting:

- (1) The contractor's responsibilities are terminated, except as set forth in the contract bond and specified in 107.16, when the department grants final acceptance as specified in 105.11.2.3.
-

109.2 Scope of Payment

Replace paragraph two with the following effective with the December 2013 letting:

- (2) The department will pay for the quantity of work acceptably completed and measured for payment as the measurement subsection for each bid item specifies. Within the contract provide means to furnish and install the work complete and in-place. Payment is full compensation for everything required to perform the work under the applicable bid items including, but not limited to, the work elements listed in the payment subsection. Payment also includes all of the following not specifically excluded in that payment subsection:
 1. Furnishing and installing all materials as well as furnishing the labor, tools, supplies, equipment, and incidentals necessary to perform the work.
 2. All losses or damages, except as specified in 107.14, arising from one or more of the following:
 - The nature of the work.
 - The action of the elements.
 - Unforeseen difficulties encountered during prosecution of the work.
 3. All insurance costs, expenses, and risks connected with the prosecution of the work.
 4. All expenses incurred because of an engineer-ordered suspension, except as specified in 104.2.2.3.
 5. All infringements of patents, trademarks, or copyrights.
 6. All other expenses incurred to complete and protect the work under the contract.
-

109.6.1 General

Replace paragraphs three and four with the following effective with the December 2013 letting:

- (3) The department's payment of an estimate before conditional final acceptance of the work does not constitute the department's acceptance of the work, and does not relieve the contractor of responsibility for:
 1. Protecting, repairing, correcting, or renewing the work.
 2. Replacing all defects in the construction or in the materials used in the construction of the work under the contract, or responsibility for damage attributable to these defects.
 - (4) The contractor is responsible for all defects or damage that the engineer may discover on or before the engineer's conditional final acceptance of the work. The engineer is the sole judge of these defects or damage, and the contractor is liable to the department for not correcting all defects or damage.
-

109.7 Acceptance and Final Payment

Replace paragraphs one and two with the following effective with the December 2013 letting:

- (1) After the engineer grants conditional final acceptance of the work as specified in 105.11.2.2 and reviews required document submittals and materials test reports, the engineer will issue the semi-final estimate.
- (2) Within 30 calendar days after receiving the semi-final estimate, submit to the engineer a written statement of agreement or disagreement with the semi-final estimate. For an acceptable statement of disagreement, submit an item-by-item list with reasons for each disagreement. If the contractor does not submit this written statement within those 30 days, the engineer will process the final estimate for payment. The engineer and the contractor can mutually agree to extend this 30-day submission requirement.

450.3.3 Maintaining the Work

Replace paragraph one with the following effective with the December 2013 letting:

- (1) Protect and repair the prepared foundation, tack coat, base, paved traffic lanes, shoulders, and seal coat. Correct all rich or bleeding areas, breaks, raveled spots, or other nonconforming areas in the paved surface.

455.3.2.5 Maintaining Tack Coat

Replace paragraph one with the following effective with the December 2013 letting:

- (1) Protect and repair the existing surface and the tack coat. Correct areas with excess or deficient tack material and any breaks, raveled spots, or other areas where bond might be affected.

460.2.2.3 Aggregate Gradation Master Range

Replace paragraph one with the following effective with the January 2014 letting:

- (1) Ensure that the aggregate blend, including recycled material and mineral filler, conforms to the gradation requirements in table 460-1. The values listed are design limits; production values may exceed those limits.

TABLE 460-1 AGGREGATE GRADATION MASTER RANGE AND VMA REQUIREMENTS

SIEVE	PERCENTS PASSING DESIGNATED SIEVES						
	NOMINAL SIZE						
	37.5 mm	25.0 mm	19.0 mm	12.5 mm	9.5 mm	SMA 12.5 mm	SMA 9.5 mm
50.0-mm	100						
37.5-mm	90 – 100	100					
25.0-mm	90 max	90 - 100	100				
19.0-mm	___	90 max	90 - 100	100		100	
12.5-mm	___	___	90 max	90 - 100	100	90 - 97	100
9.5-mm	___	___	___	90 max	90 - 100	58 - 72	90 - 100
4.75-mm	___	___	___	___	90 max	25 - 35	35 - 45
2.36-mm	15 – 41	19 - 45	23 - 49	28 - 58	20 - 65	15 - 25	18 - 28
75-µm	0 – 6.0	1.0 - 7.0	2.0 - 8.0	2.0 - 10.0	2.0 - 10.0	8.0 - 12.0	10.0 - 14.0
% MINIMUM VMA	11.0	12.0	13.0	14.0 ^[1]	15.0 ^[2]	16.0	17.0

^[1] 14.5 for E-3 mixes.

^[2] 15.5 for E-3 mixes.

460.2.7 HMA Mixture Design

Replace paragraph one with the following effective with the January 2014 letting:

- (1) For each HMA mixture type used under the contract, develop and submit an asphaltic mixture design according to the department's test method number 1559 as described in CMM 8-66 and conforming to the requirements of table 460-1 and table 460-2. The values listed are design limits; production values may exceed those limits. The department will review mixture designs and report the results of that review to the designer according to the department's test method number 1559.

TABLE 460-2 MIXTURE REQUIREMENTS

Mixture type	E - 0.3	E - 1	E - 3	E - 10	E - 30	E - 30x	SMA
ESALs x 10 ⁶ (20 yr design life)	< 0.3	0.3 - < 1	1 - < 3	3 - < 10	10 - < 30	>= 30	—
LA Wear (AASHTO T96)							
100 revolutions(max % loss)	13	13	13	13	13	13	13
500 revolutions(max % loss)	50	50	45	45	45	45	40
Soundness (AASHTO T104) (sodium sulfate, max % loss)	12	12	12	12	12	12	12
Freeze/Thaw (AASHTO T103) (specified counties, max % loss)	18	18	18	18	18	18	18
Fractured Faces (ASTM 5821) (one face/2 face, % by count)	60 / —	65 / —	75 / 60	85 / 80	98 / 90	100/100	100/90
Flat & Elongated (ASTM D4791) (max %, by weight)	5 (5:1 ratio)	5 (5:1 ratio)	5 (5:1 ratio)	5 (5:1 ratio)	5 (5:1 ratio)	5 (5:1 ratio)	20 (3:1ratio)
Fine Aggregate Angularity (AASHTO T304, method A, min)	40	40	43	45	45	45	45
Sand Equivalency (AASHTO T176, min)	40	40	40	45	45	50	50
Gyratory Compaction							
Gyrations for N _{ini}	6	7	7	8	8	9	8
Gyrations for N _{des}	40	60	75	100	100	125	65
Gyrations for N _{max}	60	75	115	160	160	205	160
Air Voids, %V _a (%G _{mm} N _{des})	4.0 (96.0)	4.0 (96.0)	4.0 (96.0)	4.0 (96.0)	4.0 (96.0)	4.0 (96.0)	4.0 (96.0)
% G _{mm} N _{ini}	<= 91.5 ^[1]	<= 90.5 ^[1]	<= 89.0 ^[1]	<= 89.0	<= 89.0	<= 89.0	—
% G _{mm} N _{max}	<= 98.0	<= 98.0	<= 98.0	<= 98.0	<= 98.0	<= 98.0	—
Dust to Binder Ratio ^[2] (% passing 0.075/P _{be})	0.6 - 1.2	0.6 - 1.2	0.6 - 1.2	0.6 - 1.2	0.6 - 1.2	0.6 - 1.2	1.2 - 2.0
Voids filled with Binder (VFB or VFA, %)	68 - 80 ^{[4] [5]}	65 - 78 ^[4]	65 - 75 ^{[3] [4]}	65 - 75 ^{[3] [4]}	65 - 75 ^{[3] [4]}	65 - 75 ^{[3] [4]}	70 - 80
Tensile Strength Ratio (TSR) (ASTM 4867)							
no antistripping additive	0.70	0.70	0.70	0.70	0.70	0.70	0.70
with antistripping additive	0.75	0.75	0.75	0.75	0.75	0.75	0.75
Draindown at Production Temperature (%)	—	—	—	—	—	—	0.30

^[1] The percent maximum density at initial compaction is only a guideline.

^[2] For a gradation that passes below the boundaries of the caution zone(ref. AASHTO MP3), the dust to binder ratio limits are 0.6 - 1.6.

^[3] For 9.5mm and 12.5 mm nominal maximum size mixtures, the specified VFB range is 70 - 76%.

^[4] For 37.5mm nominal maximum size mixes, the specified VFB lower limit is 67%.

^[5] For 25.0mm nominal maximum size mixes, the specified VFB lower limit is 67%.

460.2.8.2.1.5 Control Limits

Replace paragraph one with the following effective with the January 2014 letting:

- (1) Conform to the following control limits for the JMF and warning limits based on a running average of the last 4 data points:

ITEM	JMF LIMITS	WARNING LIMITS
Percent passing given sieve:		
37.5-mm	+/- 6.0	+/- 4.5
25.0-mm	+/- 6.0	+/- 4.5
19.0-mm	+/- 5.5	+/- 4.0
12.5-mm	+/- 5.5	+/- 4.0
9.5-mm	+/- 5.5	+/- 4.0
2.36-mm	+/- 5.0	+/- 4.0
75-µm	+/- 2.0	+/- 1.5
Asphaltic content in percent	- 0.3	- 0.2
Air voids in percent	+/- 1.3	+/- 1.0
VMA in percent ^[1]	- 0.5	- 0.2

^[1] VMA limits based on minimum requirement for mix design nominal maximum aggregate size in Table 460-1.

- (2) Warning bands are defined as the area between the JMF limits and the warning limits.

460.2.8.2.1.6 Job Mix Formula Adjustment

Replace the entire text with the following effective with the January 2014 letting:

- (1) The contractor may request adjustment of the JMF according to the department's test method number 1559. Have an HTCP HMA technician certified at a level appropriate for process control and troubleshooting or mix design submit a written JMF adjustment request. Ensure that the resulting JMF is within specified master gradation bands. The department will have an HMA technician certified at level III review the proposed adjustment and, if acceptable, issue a revised JMF.
- (2) The department will not allow adjustments that do the following:
- Exceed specified JMF tolerance limits.
 - Reduce the JMF asphalt content unless the production VMA running average meets or exceeds the minimum VMA design requirement defined in table 460-1 for the mixture produced.
- (3) Have an HMA technician certified at level II make related process adjustments. If mixture redesign is necessary, submit a new JMF, subject to the same specification requirements as the original JMF.

520.3.8 Protection After Laying

Delete the entire subsection.

614.2.1 General

Replace paragraphs five and six with the following effective with the December 2013 letting:

- (5) Furnish zinc coated wire rope and fitting conforming to the plans and galvanized according to ASTM A741.
- (6) Before installation store galvanized components above ground level and away from surface run off. The department may reject material if the zinc coating is physically damaged or oxidized.
- (7) Provide manufacturer's drawings, and installation and maintenance instructions when providing proprietary systems.

614.2.3 Steel Rail and Fittings

Replace paragraph one with the following effective with the December 2013 letting:

- (1) Furnish galvanized steel rail conforming to AASHTO M180 class A, type II beam using the single-spot test coating requirements. Furnish plates, anchor plates, post mounting brackets, and other structural steel components conforming to 506.2.2.1 and hot-dip galvanized according to ASTM A123.
-

614.2.7 Crash Cushions

Replace paragraph one with the following effective with the December 2013 letting:

- (1) Furnish permanent and temporary crash cushions from the department's approved products list. Use cushions as wide or wider than the plan back-width. Furnish transitions conforming to the crash cushion manufacturer's design and specifications. Submit manufacturer crash cushion and transition design details to engineer before installing.
-

616.3.1 General

Replace paragraph six with the following effective with the December 2013 letting:

- (6) Remove and dispose of all excess excavation and surplus materials from the fence site.
-

618.3.3 Restoration

Replace paragraph one with the following effective with the December 2013 letting:

- (1) Upon termination of hauling operations and before conditional final acceptance, restore all haul roads, including drainage facilities and other components, to the equivalent of pre-hauling conditions.
-

627.3.1 General

Replace paragraph four with the following effective with the December 2013 letting:

- (4) Maintain the mulched areas and repair all areas damaged by wind, erosion, traffic, fire or other causes.
-

637.3.2.1 General

Delete paragraph three effective with the December 2013 letting.

670.3.4.2 Post-Construction Work

Replace paragraph one with the following effective with the December 2013 letting:

- (1) Submit 5 copies of ITS documentation including but not limited to the following:
 - Operator's manual: for contractor furnished equipment, submit a manual containing detailed operating instructions for each different type or model of equipment and or operation performed.
 - Maintenance procedures manuals: for contractor furnished equipment, submit a manual containing detailed preventive and corrective maintenance procedures for each type or model of equipment furnished.
 - Cabinet fiber optic wiring diagram: submit a cabinet wiring diagram, identified by location for each cabinet. Include both electrical wiring and fiber optic conductor and cable connections. Place one copy of the fiber optic wiring diagram in a weatherproof holder in the cabinet. Deliver the other copies to the engineer.
 - As-built drawings: submit final as-built drawings that detail the final placement of all conduit, cabling, equipment, and geometric modifications within the contract. Provide all documentation in an electronic format adhering to the region's ITS computer aided drafting standards and according to the department's as-built requirements. The department will review the as-built drawings for content and electronic format. Modify both the content and format of as-built drawings until meeting all requirements.
 - Equipment inventory list: submit an inventory list including serial number, make, model, date installed, and location installed of all equipment installed under the contract.

Errata

Make the following corrections to the 2014 edition of the standard specifications:

415.3.14 Protecting Concrete

Correct errata by referencing the opening to service specification.

- (1) Erect and maintain suitable barricades and, if necessary, provide personnel to keep traffic off the newly constructed pavement until it is opened for service as specified in 415.3.15. Conform to 104.6 for methods of handling and facilitating traffic.

501.2.9 Concrete Curing Materials

Correct errata by changing AASHTO M171 to ASTM C171.

- (2) Furnish sheeting conforming to ASTM C171 for white opaque polyethylene film, except that the contractor may use clear or black polyethylene for cold weather protection.

607.2 Materials

Correct errata by changing AASHTO M198 to ASTM C990.

- (1) Use materials conforming to the requirements for the class of material named and specified below.
 - Composite pipe, couplings, fittings and joint materials ASTM D2680
 - Annular rubber and plastic gaskets for flexible, watertight joints ASTM C990
 - External rubber gaskets, mastic, and protective film..... ASTM C877
 - Mortar519.2.3

637.2.1.3 Sheet Aluminum

Correct errata by changing ASTM B449 to B921 and eliminating the specification for coating thickness.

- (4) Degrease, etch, and coat the sign blank on both sides with a chromate treatment conforming to ASTM B921, class 2.

637.3.3.4 Performance

Correct errata to reference to 105.11.2.3 as revised to implement changes to the finals process.

- (1) Under 105.11.2.3 the department may revoke acceptance and direct the contractor to repair or replace previously accepted sign installations if the department subsequently discovers evidence of defective materials or improper installation. Deficiencies that warrant department action include but are not limited to the following:
 - Sign posts more than five degrees out of plumb.
 - Signs twisted by more than 5 degrees from plan orientation.
 - Signs with delaminated or warped plywood.
 - Signs with bubbling, fading, delaminating, or buckling sheeting.

646.3.3.4 Proving Period

Correct errata to reference to 105.11.2.3 as revised to implement changes to the finals process.

- (4) Replace all marking within sections with a percent failing more than 10% and repair or replace all markings that, in the engineer's assessment, show evidence of improper construction. If post-acceptance inspections uncover evidence of defective materials or improper construction, the department may revoke acceptance under 105.11.2.3.

ADDITIONAL SPECIAL PROVISION 7

- A. Reporting 1st Tier and DBE Payments During Construction
1. Comply with reporting requirements specified in the department's Civil Rights Compliance, Contractor's User Manual, Sublets and Payments.
 2. Report payments to all DBE firms within 10 calendar days of receipt of a progress payment by the department or a contractor for work performed, materials furnished, or materials stockpiled by a DBE firm. Report the payment as specified in A(1) for all work satisfactorily performed and for all materials furnished or stockpiled.
 3. Report payments to all first tier subcontractor relationships within 10 calendar days of receipt of a progress payment by the department for work performed. Report the payment as specified in A(1) for all work satisfactorily performed.
 4. All tiers shall report payments as necessary to comply with the DBE payment requirement as specified in A(2).
 5. Require all first tier relationships, DBE firms and all other tier relationships necessary to comply with the DBE payment requirement in receipt of a progress payment by contractor to acknowledge receipt of payment as specified in A(1), (2), (3) and (4).
 6. All agreements made by a contractor shall include the provisions in A(1), (2), (3), (4) and (5), and shall be binding on all first tier subcontractor relationships and all contractors and subcontractors utilizing DBE firms on the project.
- B. Costs for conforming to this special provision are incidental to the contract.

ADDITIONAL SPECIAL PROVISION 9 Electronic Certified Payroll Submittal

(1) Use the department's Civil Rights Compliance System (CRCS) to submit certified payrolls electronically. Details are available online through the department's highway construction contractor information (HCCI) site on the Labor, Wages, and EEO Information page at: <http://roadwaystandards.dot.wi.gov/hcci/labor-wages-eeo/index.shtm>

(2) Ensure that all tiers of subcontractors, as well as all trucking firms, submit their weekly certified payrolls electronically through CRCS. These payrolls are due within seven calendar days following the close of the payroll period. Every firm providing physical labor towards completing the project is a subcontractor under this special provision.

(3) Upon receipt of contract execution, promptly make all affected firms aware of the requirements under this special provision and arrange for them to receive CRCS training as they are about to begin payrolls. The department will provide training either in a classroom setting at one of our regional offices or by telephone. Contact Tess Mulrooney at 608-267-4489 to schedule the training.

(4) The department will reject all paper submittals of forms DT-1816 and DT-1929 for information required under this special provision. All costs for conforming to this special provision are incidental to the contract.

(5) Firms wishing to export payroll data from their computer system into CRCS should have their payroll coordinator send several sample electronic files to Tess two months before a payroll needs to be submitted. Not every contractor's payroll system is capable of producing export files. For details, see pages 17-22 of the CRCS System Background Information manual available online on the Labor, Wages, and EEO Information page at: <http://roadwaystandards.dot.wi.gov/hcci/labor-wages-eeo/crc-basic-info.pdf>

DECEMBER 2013

BUY AMERICA PROVISION

All steel and iron materials permanently incorporated in this project shall be domestic products and all manufacturing and coating processes for these materials from smelting forward in the manufacturing process must have occurred within the United States. Coating includes epoxy coating, galvanizing, painting and any other coating that protects or enhances the value of a material subject to the requirements of Buy America. The exemption of this requirement is the minimal use of foreign materials if the total cost of such material permanently incorporated in the product does not exceed one-tenth of one percent (1/10 of 1%) of the total contract cost or \$2,500.00, whichever is greater. For purposes of this paragraph, the cost is that shown to be the value of the subject products as they are delivered to the project. The contractor shall take actions and provide documentation conforming to CMM 2-28.5 to ensure compliance with this "Buy America" provision.

<http://roadwaystandards.dot.wi.gov/standards/cmm/cm-02-28.pdf#cm2-28.5>

Upon completion of the project certify to the engineer, in writing using department form WS4567, that all steel, iron, and coating processes for steel or iron incorporated into the contract work conform to these "Buy America" provisions. Attach a list of exemptions and their associated costs to the certification form. Department form WS4567 is available at:

<http://roadwaystandards.dot.wi.gov/standards/forms/ws4567.doc>

**WISCONSIN DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS AND TRANSPORTATION FACILITIES**

SUPPLEMENTAL REQUIRED CONTRACT PROVISIONS

- I. Wage Rates, Hours of labor and payment of Wages
- II. Payroll Requirements
- III. Postings at the Site of the Work
- IV. Affidavits
- V. Wage Rate Redistribution
- VI. Additional Classifications

I. WAGE RATES, HOURS OF LABOR AND PAYMENT OF WAGES

The schedule of "Minimum Wage Rates" attached hereto and made a part hereof furnishes the prevailing wage rates that have been determined pursuant to Section 103.50 of the Wisconsin Statutes. These wage rates are the minimum required to be paid to the various laborers, workers, mechanics and truck drivers employed by contractors and subcontractors on the construction work embraced by the contract and subject to prevailing hours and wages under Section 103.50, Stats. If necessary to employ laborers, workers, mechanics or truck drivers whose classification is not listed on the schedule, they shall be paid at rates conformable to those listed for similar classifications. Apprentices shall be paid at rates not less than those prescribed in their state indenture contracts.

While the wage rates shown are the minimum rates required by the contract to be paid during its life, this is not a representation that labor can be obtained at these rates. It is the responsibility of bidders to inform themselves as to the local labor conditions and prospective changes or adjustments of wage rates. No increase in the contract price shall be allowed or authorized on account of the payment of wage rates in excess of those listed herein.

Pursuant to Section 103.50 of the Wisconsin Statutes, the prevailing hours of labor have been determined to be up to 10 hours per day and 40 hours per calendar week Monday through Friday. If any laborer, worker, mechanic or truck driver is permitted or required to work more than the prevailing number of hours per day or per calendar week on this contract, they shall be paid for all hours in excess of the prevailing hours at a rate of at least one and one-half (1 1/2) times their hourly rate of pay. All work on Saturday, Sunday and the following holidays is to be paid at time and a half: (1) January 1, (2) the last Monday in May, (3) July 4, (4) the first Monday in September, (5) the fourth Thursday in November, (6) December 25, (7) the day before if January 1, July 4 or December 25 falls on a Saturday and (8) the day following if January 1, July 4 or December 25 falls on a Sunday.

All laborers, workers, mechanics and truck drivers shall be paid unconditionally not less often than once a week. Persons who own and operate their own trucks must receive the prevailing truck driver rate for the applicable type of truck (i.e. 2 axle, 3 or more axle, articulated, eculid or dumptor) he or she operates, plus an agreed upon amount for the use of his or her truck. Every owner-operator MUST be paid separately for their driving and for the use of their truck.

For those projects subject to the requirements of the Davis-Bacon Act, the Secretary of Labor will also have determined "Minimum Wage Rates" for work to be performed under the contract. These rates are, for all or most of the labor, worker, mechanic or truck driver classifications, identical to those established under Section 103.50 of the Wisconsin Statutes. In the event the rates are not identical, the higher of the two rates will govern.

II. PAYROLL REQUIREMENTS

All contractors and subcontractors must submit weekly Certified Payrolls and Compliance Statement verifying that all laborers, workers, mechanics and truck drivers working on the project have been paid the prevailing wage rates for all work performed under the contract required by Section 103.50 of the Wisconsin Statutes.

III. POSTINGS AT THE SITE OF THE WORK

In addition to the required postings furnished by the Department, the contractor shall post the following in at least one conspicuous place at the site of work:

- a. "NOTICE TO EMPLOYEES," which provides information required to be posted by the provisions of Section 103.50 of the Wisconsin Statutes.
- b. A copy of the State of Wisconsin Minimum Wages Rates. (Four pages.)
- c. A copy of the contractor's Equal Employment Opportunity Policy.
- d. On any project involving federal aid, in addition to the furnished postings, the contractor shall post a copy of the "Davis-Bacon Act, Minimum Wage Rates". (Three pages.)

IV. WAGE RATE REDISTRIBUTION

The amount specified as the hourly basic rate of pay and the amount(s) specified as the fringe benefit contribution(s), for all classes of laborers, workers, mechanics or truck drivers may be redistributed, when necessary, to conform to those specified in any applicable collective bargaining agreement, provided that both parties to such agreement

request and receive the approval for any such redistribution from both the Department of Transportation and the Department of Workforce Development prior to the implementation of such redistribution.

V. ADDITIONAL CLASSIFICATIONS

Any unlisted laborer or mechanic classification that is needed to perform work on this project, and is not included within the scope of any of the classifications listed in the application prevailing wage rate determination, may be added after award only if all of the following criteria have been met:

1. The affected employer(s) must make a written request to WisDOT Central Office to utilize the unlisted classification on this project.
2. The request must indicate the scope of the work to be performed by the unlisted classification and must indicate the proposed wage/fringe benefit package that the unlisted classification is to receive.
3. The work to be performed by the unlisted classification must not be performed by a classification that is included in the applicable prevailing wage rate determination.
4. The unlisted classification must be commonly employed in the area where the project is located.
5. The proposed wage/fringe benefit package must bear a reasonable relationship to those set forth in the applicable prevailing wage rate determination.
6. The request should be made prior to the actual performance of the work by the unlisted classification.
7. DWD must approve the use of the unlisted classification and the proposed wage/fringe benefit package. USDOL also must approve the use of the unlisted classification and the proposed wage/fringe benefit package on federal aid projects.
8. WisDOT and DWD may amend the proposed wage/fringe benefit package, as deemed necessary, and may set forth specific employment ratios and scope of work requirements in the approval document.

The approved wage/fringe benefit package shall be paid to all laborers, workers, mechanics or truck drivers performing work within the scope of that performed by the unlisted classification, from the first day on which such work is performed. In the event that work is performed by the unlisted classification prior to approval, the wage/fringe benefit package to be paid for such work must be in conformance with the wage/fringe

benefit package approved for such work. Under this arrangement a retroactive adjustment in wages and/or fringe benefits may be required to be made to the affected laborers, workers, mechanics or truck drivers by the affected employer(s).

**ANNUAL PREVAILING WAGE RATE DETERMINATION
FOR ALL STATE HIGHWAY PROJECTS
WASHINGTON COUNTY**

Compiled by the State of Wisconsin - Department of Workforce Development
for the Department of Transportation
Pursuant to s. 103.50, Stats.
Issued on May 1, 2014

CLASSIFICATION: Contractors are required to call the Department of Workforce Development if there are any questions regarding the proper trade or classification to be used for any worker on a public works project.

OVERTIME: Time and one-half must be paid for all hours worked over 10 hours per day and 40 hours per calendar week and for all hours worked on Saturday, Sunday and the following six (6) holidays: January 1; the last Monday in May; July 4; the 1st Monday in September; the 4th Thursday in November; December 25; the day before if January 1, July 4 or December 25 falls on a Saturday; the day following if January 1, July 4 or December 25 falls on a Sunday.

FUTURE INCREASE: If indicated for a specific trade or occupation, the full amount of such increase MUST be added to the "TOTAL" indicated for such trade or occupation on the date(s) such increase(s) becomes effective.

PREMIUM PAY: If indicated for a specific trade or occupation, the full amount of such pay MUST be added to the "HOURLY BASIC RATE OF PAY" indicated for such trade or occupation, whenever such pay is applicable.

SUBJOURNEY: Wage rates may be available for some of the classifications indicated below. Any employer that desires to use any subjourney classification on a project MUST request the applicable wage rate from the Department of Workforce Development PRIOR to the date such classification is used on such project. Form ERD-10880 is available for this purpose and can be obtained by writing to the Department of Workforce Development, Equal Rights Division, P.O. Box 8928, Madison, WI 53708.

<u>TRADE OR OCCUPATION</u>	<u>HOURLY BASIC RATE OF PAY</u>	<u>HOURLY FRINGE BENEFITS</u>	<u>TOTAL</u>
	\$	\$	\$
Bricklayer, Blocklayer or Stonemason	35.80	16.87	52.67
Carpenter	33.68	19.81	53.49
Future Increase(s): Add \$1.25/hr on 6/2/2014. Premium Pay: DOT PREMIUM: Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day.			
Cement Finisher	31.56	18.53	50.09
Future Increase(s): Add \$1.87 on 6/1/14; Add \$1.87 on 6/1/15; Add \$1.75 on 6/1/16. Premium Pay: DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.40/hr when the Wisconsin Department of Transportation or responsible governing agency requires that work be performed at night under artificial illumination with traffic control and the work is completed after sunset and before sunrise.			
Electrician	32.82	22.61	55.43
Premium Pay: DOT PREMIUM: Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day.			
Fence Erector	22.15	1.73	23.88
Ironworker	30.52	23.47	53.99
Future Increase(s): Add \$.80/hr on 6/1/2014. Premium Pay: DOT PREMIUM: Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day.			
Line Constructor (Electrical)	38.25	17.63	55.88
Painter	21.87	11.37	33.24
Pavement Marking Operator	30.00	0.00	30.00
Piledriver	29.06	25.53	54.59
Roofer or Waterproofer	29.40	13.71	43.11
Teledata Technician or Installer	24.75	16.08	40.83
Tuckpointer, Caulker or Cleaner	34.57	16.42	50.99

<u>TRADE OR OCCUPATION</u>	<u>HOURLY BASIC RATE OF PAY</u>	<u>HOURLY FRINGE BENEFITS</u>	<u>TOTAL</u>
	\$	\$	\$
Underwater Diver (Except on Great Lakes)	34.48	15.90	50.38
Heavy Equipment Operator - ELECTRICAL LINE CONSTRUCTION ONLY	34.43	15.24	49.67
Light Equipment Operator -ELECTRICAL LINE CONSTRUCTION ONLY	30.60	15.67	46.27
Heavy Truck Driver - ELECTRICAL LINE CONSTRUCTION ONLY	26.78	13.58	40.36
Light Truck Driver - ELECTRICAL LINE CONSTRUCTION ONLY	24.86	12.97	37.83
Groundman - ELECTRICAL LINE CONSTRUCTION ONLY	21.75	12.31	34.06

TRUCK DRIVERS

Single Axle or Two Axle	34.22	19.90	54.12
Three or More Axle	25.24	15.20	40.44
Articulated, Euclid, Dumptor, Off Road Material Hauler	29.27	20.40	49.67
Future Increase(s): Add \$1.75/hr on 6/1/14); Add \$1.25/hr on 6/1/15); Add \$1.30/hr on 6/1/16); Add \$1.25/hr on 6/ 1/ 17. Premium Pay: DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.50/hr night work premium. See DOT'S website for details about the applicability of this night work premium at: http:// www.dot.wi.gov/ business/ civilrights/ laborwages/ pwc. htm .			
Pavement Marking Vehicle	25.24	15.20	40.44
Shadow or Pilot Vehicle	34.22	19.90	54.12
Truck Mechanic	25.24	15.20	40.44

LABORERS

General Laborer	25.31	19.43	44.74
Future Increase(s): Add \$1.60/hr on 6/1/2014. Premium Pay: Add \$.10/hr for air tool operator, vibrator or tamper operator (mechanical hand operated), chain saw operator and demolition burning torch laborer; Add \$.15/hr for bituminous worker (raker and luteman), formsetter (curb, sidewalk and pavement) and strike off man; Add \$.20/hr for blaster and powderman; Add \$.35/hr for line and grade specialist; Add \$2.79/hr for topman; Add \$3.21/hr for bottomman; Add \$3.98/hr for pipelayer. DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.25/hr for work on projects involving temporary traffic control setup, for lane and shoulder closures, when work under artificial illumination conditions is necessary as required by the project provisions (including prep time prior to and/or cleanup after such time period).			
Asbestos Abatement Worker	19.00	0.00	19.00
Landscaper	25.31	19.43	44.74
Future Increase(s): Add \$1.60/hr on 6/1/14. Premium Pay: DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.25/hr for work on projects involving temporary traffic control setup, for lane and shoulder closures, when work under artificial illumination conditions is necessary as required by the project provisions (including prep time prior to and/or cleanup after such time period).			
Flagperson or Traffic Control Person	22.55	19.43	41.98
Future Increase(s): Add \$1.60/hr on 6/1/2014. Premium Pay: DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.25/hr when the Wisconsin Department of Transportation or responsible governing agency requires that work be performed at night under artificial illumination with traffic control and the work is completed after sunset and before sunrise.			

<u>TRADE OR OCCUPATION</u>	<u>HOURLY BASIC RATE OF PAY</u>	<u>HOURLY FRINGE BENEFITS</u>	<u>TOTAL</u>
	\$	\$	\$
Fiber Optic Laborer (Outside, Other Than Concrete Encased)	17.69	15.50	33.19
Railroad Track Laborer	13.50	8.92	22.42

HEAVY EQUIPMENT OPERATORS

Crane, Tower Crane, Pedestal Tower or Derrick, With Boom, Leads &/or Jib Lengths Measuring 176 Ft or Over; Crane, Tower Crane, Pedestal Tower or Derrick, With or Without Attachments, With a Lifting Capacity of Over 100 Tons, Self-Erecting Tower Crane With a Lifting Capacity Of Over 4,000 Lbs., Crane With Boom Dollies; Traveling Crane (Bridge Type).	36.72	20.40	57.12
--	-------	-------	-------

Future Increase(s): Add \$1.75/hr on 6/1/2014); Add \$1.25/hr on 6/1/2015); Add \$1.30/hr on 6/1/2016); Add \$1.25/hr on 6/ 1/ 2017.

Premium Pay: DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.50/hr night work premium. See DOT'S website for details about the applicability of this night work premium at: <http://www.dot.wi.gov/business/civilrights/laborwages/pwc.htm>.

Backhoe (Track Type) Having a Mfgr.'s Rated Capacity of 130,000 Lbs. or Over; Caisson Rig; Crane, Tower Crane, Portable Tower, Pedestal Tower or Derrick, With Boom, Leads &/or Jib Lengths Measuring 175 Ft or Under; Crane, Tower Crane, Portable Tower, Pedestal Tower or Derrick, With or Without Attachments, With a Lifting Capacity of 100 Tons or Under, Self-Erecting Tower Crane With A Lifting Capacity Of 4,000 Lbs., & Under; Dredge (NOT Performing Work on the Great Lakes); Licensed Boat Pilot (NOT Performing Work on the Great Lakes); Pile Driver.	36.22	20.40	56.62
--	-------	-------	-------

Future Increase(s): Add \$1.75/hr on 6/1/2014); Add \$1.25/hr on 6/1/2015); Add \$1.30/hr on 6/1/2016); Add \$1.25/hr on 6/ 1/ 2017.

Premium Pay: DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.50/hr night work premium. See DOT'S website for details about the applicability of this night work premium at: <http://www.dot.wi.gov/business/civilrights/laborwages/pwc.htm>.

Air Track, Rotary or Percussion Drilling Machine &/or Hammers, Blaster; Asphalt Heater, Planer & Scarifier; Asphalt Milling Machine; Asphalt Screed; Automatic Subgrader (Concrete); Backhoe (Track Type) Having a Mfgr.'s Rated Capacity of Under 130,000 Lbs., Backhoe (Mini, 15,000 Lbs. & Under); Bituminous (Asphalt) Plant & Paver, Screed; Boatmen (NOT Performing Work on the Great Lakes); Boring Machine (Directional, Horizontal or Vertical); Bridge (Bidwell) Paver; Bulldozer or Endloader; Concrete Batch Plant, Batch Hopper; Concrete Breaker (Large, Auto, Vibratory/Sonic, Manual or Remote); Concrete Bump Cutter, Grinder, Planing or Grooving Machine; Concrete Conveyor System; Concrete Laser/Screed; Concrete Paver (Slipform); Concrete Pump, Concrete Conveyor (Rotec or Bidwell Type); Concrete Slipform Placer Curb & Gutter Machine; Concrete Spreader & Distributor; Crane (Carry Deck, Mini) or Truck Mounted Hydraulic Crane (10 Tons or Under); Crane With a Lifting Capacity of 25 Tons or Under; Forestry Equipment, Timbco, Tree Shear, Tub Grinder, Processor; Gradall (Cruz-Aire Type); Grader or Motor Patrol; Grout Pump; Hydro-Blaster (10,000 PSI or Over); Loading Machine (Conveyor); Material or Stack Hoist; Mechanic or Welder; Milling Machine; Post Hole Digger or Driver; Roller (Over 5 Ton); Scraper (Self Propelled or Tractor Drawn) 5 cu yds or More Capacity; Shoulder Widener; Sideboom; Skid Rig; Stabilizing or Concrete Mixer (Self-Propelled or 14S or Over); Straddle	35.72	20.40	56.12
--	-------	-------	-------

<u>TRADE OR OCCUPATION</u>	<u>HOURLY BASIC RATE OF PAY</u>	<u>HOURLY FRINGE BENEFITS</u>	<u>TOTAL</u>
	\$	\$	\$
Carrier or Travel Lift; Tractor (Scraper, Dozer, Pusher, Loader); Tractor or Truck Mounted Hydraulic Backhoe; Trencher (Wheel Type or Chain Type); Tube Finisher; Tugger (NOT Performing Work on the Great Lakes); Winches & A- Frames. Future Increase(s): Add \$1.75/hr on 6/1/2014); Add \$1.25/hr on 6/1/2015); Add \$1.30/hr on 6/1/2016); Add \$1.25/hr on 6/ 1/ 2017. Premium Pay: DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.50/hr night work premium. See DOT'S website for details about the applicability of this night work premium at: http:// www.dot.wi.gov/business/ civilrights/ laborwages/ pwc. htm .	35.46	20.40	55.86
Belting, Burlap, Texturing Machine; Broom or Sweeper; Compactor (Self-Propelled or Tractor Mounted, Towed & Light Equipment); Concrete Finishing Machine (Road Type); Environmental Burner; Farm or Industrial Type Tractor; Fireman (Asphalt Plant, Pile Driver & Derrick NOT Performing Work on the Great Lakes); Forklift; Greaser; Hoist (Tugger, Automatic); Jeep Digger; Joint Sawyer (Multiple Blade); Launch (NOT Performing Work on the Great Lakes); Lift Slab Machine; Mechanical Float; Mulcher; Power Subgrader; Robotic Tool Carrier (With or Without Attachments); Roller (Rubber Tire, 5 Ton or Under); Self Propelled Chip Spreader; Shouldering Machine; Skid Steer Loader (With or Without Attachments); Telehandler; Tining or Curing Machine. Future Increase(s): Add \$1.75/hr on 6/1/2014); Add \$1.25/hr on 6/1/2015); Add \$1.30/hr on 6/1/2016); Add \$1.25/hr on 6/ 1/ 2017. Premium Pay: DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.50/hr night work premium. See DOT'S website for details about the applicability of this night work premium at: http:// www.dot.wi.gov/business/ civilrights/ laborwages/ pwc. htm .	35.17	20.40	55.57
Air Compressor (&/or 400 CFM or Over); Air, Electric or Hydraulic Jacking System; Augers (Vertical & Horizontal); Automatic Belt Conveyor & Surge Bin; Boiler (Temporary Heat); Concrete Proportioning Plant; Crusher, Screening or Wash Plant; Generator (&/or 150 KW or Over); Heaters (Mechanical); High Pressure Utility Locating Machine (Daylighting Machine); Mudjack; Oiler; Prestress Machine; Pug Mill; Pump (3 Inch or Over) or Well Points; Rock, Stone Breaker; Screed (Milling Machine); Stump Chipper; Tank Car Heaters; Vibratory Hammer or Extractor, Power Pack. Future Increase(s): Add \$1.75/hr on 6/1/2014); Add \$1.25/hr on 6/1/2015); Add \$1.30/hr on 6/1/2016); Add \$1.25/hr on 6/ 1/ 2017. Premium Pay: DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.50/hr night work premium. See DOT'S website for details about the applicability of this night work premium at: http:// www.dot.wi.gov/business/ civilrights/ laborwages/ pwc. htm .	26.69	16.65	43.34
Fiber Optic Cable Equipment.			

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20140708017

PROJECT(S):
2707-03-71

FEDERAL ID(S):
N/A

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS

SECTION 0001 ROADWAY ITEMS

0010	201.0105 CLEARING	4.000 STA
0020	201.0205 GRUBBING	4.000 STA
0030	204.0100 REMOVING PAVEMENT	176.000 SY
0040	204.0150 REMOVING CURB & GUTTER	265.000 LF
0050	204.0155 REMOVING CONCRETE SIDEWALK	62.000 SY
0060	205.0100 EXCAVATION COMMON ***	722.000 CY
0070	213.0100 FINISHING ROADWAY (PROJECT) 01. 2707-03-71	1.000 EACH
0080	305.0120 BASE AGGREGATE DENSE 1 1/4-INCH	1,107.000 TON
0090	310.0110 BASE AGGREGATE OPEN GRADED	195.000 TON
0100	311.0110 BREAKER RUN	300.000 TON

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20140708017

PROJECT(S):
2707-03-71

FEDERAL ID(S):
N/A

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	330.0100 MILL AND RELAY	3,139.000 SY	.		.	
0120	415.0080 CONCRETE PAVEMENT 8-INCH 01. DOWELLED	247.000 SY	.		.	
0130	415.0080 CONCRETE PAVEMENT 8-INCH 02. NON-DOWELLED	647.000 SY	.		.	
0140	416.0180 CONCRETE DRIVEWAY 8-INCH	153.000 SY	.		.	
0150	416.0610 DRILLED TIE BARS	30.000 EACH	.		.	
0160	416.1010 CONCRETE SURFACE DRAINS	9.000 CY	.		.	
0170	455.0105 ASPHALTIC MATERIAL PG58-28	43.000 TON	.		.	
0180	455.0605 TACK COAT	79.000 GAL	.		.	
0190	460.1101 HMA PAVEMENT TYPE E-1	705.000 TON	.		.	
0200	465.0105 ASPHALTIC SURFACE	61.000 TON	.		.	
0210	465.0315 ASPHALTIC FLUMES	17.000 SY	.		.	

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20140708017PROJECT(S):
2707-03-71FEDERAL ID(S):
N/A

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0220	601.0405 CONCRETE CURB & GUTTER 18-INCH TYPE A	57.000 LF
0230	601.0407 CONCRETE CURB & GUTTER 18-INCH TYPE D	556.000 LF
0240	601.0551 CONCRETE CURB AND GUTTER 4-INCH SLOPED 36-INCH TYPE A	53.000 LF
0250	601.0553 CONCRETE CURB AND GUTTER 4-INCH SLOPED 36-INCH TYPE D	236.000 LF
0260	602.0410 CONCRETE SIDEWALK 5-INCH	1,010.000 SF
0270	602.0505 CURB RAMP DETECTABLE WARNING FIELD YELLOW	32.000 SF
0280	606.0100 RIPRAP LIGHT	2.000 CY
0290	608.0312 STORM SEWER PIPE REINFORCED CONCRETE CLASS III 12-INCH	74.000 LF
0300	611.0642 INLET COVERS TYPE MS	1.000 EACH
0310	611.3901 INLETS MEDIAN 1 GRATE	1.000 EACH
0320	612.0104 PIPE UNDERDRAIN 4-INCH	1,000.000 LF

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20140708017PROJECT(S):
2707-03-71FEDERAL ID(S):
N/A

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0330	619.1000 MOBILIZATION	1.000 EACH	.		.	
0340	620.0300 CONCRETE MEDIAN SLOPED NOSE	53.000 SF	.		.	
0350	625.0100 TOPSOIL	557.000 SY	.		.	
0360	628.1504 SILT FENCE	350.000 LF	.		.	
0370	628.1520 SILT FENCE MAINTENANCE	150.000 LF	.		.	
0380	628.1905 MOBILIZATIONS EROSION CONTROL	2.000 EACH	.		.	
0390	628.1910 MOBILIZATIONS EMERGENCY EROSION CONTROL	2.000 EACH	.		.	
0400	628.2006 EROSION MAT URBAN CLASS I TYPE A	557.000 SY	.		.	
0410	628.7005 INLET PROTECTION TYPE A	2.000 EACH	.		.	
0420	628.7015 INLET PROTECTION TYPE C	1.000 EACH	.		.	
0430	628.7020 INLET PROTECTION TYPE D	4.000 EACH	.		.	

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20140708017PROJECT(S):
2707-03-71FEDERAL ID(S):
N/A

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0440	628.7570 ROCK BAGS	245.000 EACH	.		.	
0450	629.0210 FERTILIZER TYPE B	35.000 CWT	.		.	
0460	630.0130 SEEDING MIXTURE NO. 30	10.000 LB	.		.	
0470	630.0200 SEEDING TEMPORARY	5.000 LB	.		.	
0480	634.0616 POSTS WOOD 4X6-INCH X 16-FT	18.000 EACH	.		.	
0490	634.0816 POSTS TUBULAR STEEL 2X2-INCH X 16-FT	12.000 EACH	.		.	
0500	635.0200 SIGN SUPPORTS STRUCTURAL STEEL HS	1,200.000 LB	.		.	
0510	636.0100 SIGN SUPPORTS CONCRETE MASONRY **P**	2.400 CY	.		.	
0520	636.0500 SIGN SUPPORTS STEEL REINFORCEMENT	136.000 LB	.		.	
0530	637.1220 SIGNS TYPE I REFLECTIVE SH **P**	180.000 SF	.		.	
0540	637.2210 SIGNS TYPE II REFLECTIVE H	141.180 SF	.		.	

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20140708017PROJECT(S):
2707-03-71FEDERAL ID(S):
N/A

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0550	637.2230 SIGNS TYPE II REFLECTIVE F	66.000 SF	.		.	
0560	638.2102 MOVING SIGNS TYPE II	3.000 EACH	.		.	
0570	638.2602 REMOVING SIGNS TYPE II	15.000 EACH	.		.	
0580	638.3000 REMOVING SMALL SIGN SUPPORTS	13.000 EACH	.		.	
0590	642.5001 FIELD OFFICE TYPE B	1.000 EACH	.		.	
0600	643.0300 TRAFFIC CONTROL DRUMS	1,200.000 DAY	.		.	
0610	643.0410 TRAFFIC CONTROL BARRICADES TYPE II	150.000 DAY	.		.	
0620	643.0420 TRAFFIC CONTROL BARRICADES TYPE III	360.000 DAY	.		.	
0630	643.0705 TRAFFIC CONTROL WARNING LIGHTS TYPE A	720.000 DAY	.		.	
0640	643.0715 TRAFFIC CONTROL WARNING LIGHTS TYPE C	340.000 DAY	.		.	
0650	643.0800 TRAFFIC CONTROL ARROW BOARDS	8.000 DAY	.		.	

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20140708017PROJECT(S):
2707-03-71FEDERAL ID(S):
N/A

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0660	643.0900 TRAFFIC CONTROL SIGNS	904.000 DAY	.		.	
0670	643.0920 TRAFFIC CONTROL COVERING SIGNS TYPE II	2.000 EACH	.		.	
0680	643.1000 TRAFFIC CONTROL SIGNS FIXED MESSAGE	824.000 SF	.		.	
0690	643.1050 TRAFFIC CONTROL SIGNS PCMS	20.000 DAY	.		.	
0700	643.2000 TRAFFIC CONTROL DETOUR (PROJECT) 01. 2707-03-71	1.000 EACH	.		.	
0710	645.0120 GEOTEXTILE FABRIC TYPE HR	6.000 SY	.		.	
0720	647.0156 PAVEMENT MARKING ARROWS EPOXY TYPE 1	7.000 EACH	.		.	
0730	647.0256 PAVEMENT MARKING SYMBOLS EPOXY	6.000 EACH	.		.	
0740	647.0456 PAVEMENT MARKING CURB EPOXY	292.000 LF	.		.	
0750	647.0656 PAVEMENT MARKING PARKING STALL EPOXY	2,584.000 LF	.		.	
0760	647.0766 PAVEMENT MARKING CROSSWALK EPOXY 6-INCH	76.000 LF	.		.	

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20140708017PROJECT(S):
2707-03-71FEDERAL ID(S):
N/A

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0770	647.0796 PAVEMENT MARKING CROSSWALK EPOXY 24-INCH	54.000 LF	.		.	
0780	650.4000 CONSTRUCTION STAKING STORM SEWER	2.000 EACH	.		.	
0790	650.5500 CONSTRUCTION STAKING CURB GUTTER AND CURB & GUTTER	1,079.000 LF	.		.	
0800	650.8000 CONSTRUCTION STAKING RESURFACING REFERENCE	400.000 LF	.		.	
0810	650.9910 CONSTRUCTION STAKING SUPPLEMENTAL CONTROL (PROJECT) 01. 2707-03-71	LUMP	LUMP		.	
0820	652.0225 CONDUIT RIGID NONMETALLIC SCHEDULE 40 2-INCH	125.000 LF	.		.	
0830	655.0615 ELECTRICAL WIRE LIGHTING 10 AWG	340.000 LF	.		.	
0840	655.0620 ELECTRICAL WIRE LIGHTING 8 AWG	240.000 LF	.		.	
0850	659.1125 LUMINAIRES UTILITY LED C	8.000 EACH	.		.	
0860	690.0150 SAWING ASPHALT	340.000 LF	.		.	
0870	690.0250 SAWING CONCRETE	134.000 LF	.		.	

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20140708017PROJECT(S):
2707-03-71FEDERAL ID(S):
N/A

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0880	715.0415 INCENTIVE STRENGTH CONCRETE PAVEMENT	894.000 DOL	1.00000		894.00	
0890	SPV.0045 SPECIAL 01. TEMPORARY SIDEWALK	80.000 DAY	.		.	
0900	SPV.0060 SPECIAL 01. ADJUSTING SANITARY SEWER MANHOLE COVERS	1.000 EACH	.		.	
0910	SPV.0060 SPECIAL 02. INTERNAL/EXTERNAL SANITARY MANHOLE SEALS	1.000 EACH	.		.	
0920	SPV.0060 SPECIAL 03. CONNECTING PIPE UNDERDRAIN 4-INCH TO EXISTING INLET	2.000 EACH	.		.	
0930	SPV.0060 SPECIAL 04. CONSTRUCTION STAKING CURB RAMP LAYOUT	4.000 EACH	.		.	
0940	SPV.0060 SPECIAL 05. REMOVING LUMINAIRES	8.000 EACH	.		.	
0950	SPV.0060 SPECIAL 06. LAMP DISPOSAL HIGH INTENSITY DISCHARGE	8.000 EACH	.		.	
0960	SPV.0090 SPECIAL 01. SAWING CURB HEAD	29.000 LF	.		.	
0970	SPV.0090 SPECIAL 02. CONCRETE CURB & GUTTER 18-INCH	177.000 LF	.		.	

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20140708017

PROJECT(S):
2707-03-71

FEDERAL ID(S):
N/A

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0980	SPV.0090 SPECIAL 03. REMOVING ELECTRICAL WIRES FROM CONDUIT	135.000 LF	.		.	
0990	SPV.0090 SPECIAL 04. FENCE SAFETY MODIFIED	350.000 LF	.		.	
1000	SPV.0105 SPECIAL 01. SALVAGING BUS SHELTER	LUMP	LUMP		.	
1010	SPV.0105 SPECIAL 02. SALVAGING BICYCLE RACK	LUMP	LUMP		.	
1020	SPV.0105 SPECIAL 03. LIGHTING SYSTEM SURVEY	LUMP	LUMP		.	
1030	SPV.0180 SPECIAL 01. CONSTRUCTION STAKING PARKING LOTS SUBGRADE	894.000 SY	.		.	
1040	SPV.0180 SPECIAL 02. CONSTRUCTION STAKING PARKING LOTS BASE	4,033.000 SY	.		.	
1050	SPV.0180 SPECIAL 03. CONSTRUCTION STAKING PARKING LOTS CONCRETE PAVEMENT, DRIVEWAYS & SIDEWALK	1,159.000 SY	.		.	
	SECTION 0001 TOTAL				.	
	TOTAL BID				.	

PLEASE ATTACH SCHEDULE OF ITEMS HERE