#### **HIGHWAY WORK PROPOSAL**

Proposal Number:

Wisconsin Department of Transportation DT1502 10/2010 s.66.29(7) Wis. Stats.

COUNTY STATE PROJECT ID FEDERAL PROJECT ID

**PROJECT DESCRIPTION** 

**HIGHWAY** 

Dane 1009-00-76

Notice of Award Dated

Madison - Sun Prairie USH 151S - IH 39E Ramp **USH 151** 

This proposal, submitted by the undersigned bidder to the Wisconsin Department of Transportation, is in accordance with the advertised request for proposals. The bidder is to furnish and deliver all materials, and to perform all work for the improvement of the designated project in the time specified, in accordance with the appended Proposal Requirements and Conditions.

Proposal Guaranty Required, \$ 20,000.00	Attach Proposal Guaranty on back of this PAGE.
Payable to: Wisconsin Department of Transportation	
Bid Submittal Due	Firm Name, Address, City, State, Zip Code
Date: February 10, 2015 Time (Local Time): 9:00 AM	SAMPLE
Contract Completion Time	NOT FOR BIDDING PURPOSES
May 21, 2015	NOT FOR BIDDING FOR COLO
Assigned Disadvantaged Business Enterprise Goal  0%	This contract is exempt from federal oversight.

This certifies that the undersigned bidder, duly sworn, is an authorized representative of the firm named above; that the bidder has examined and carefully prepared the bid from the plans, Highway Work Proposal, and all addenda, and has checked the same in detail before submitting this proposal or bid; and that the bidder or agents, officer, or employees have not, either directly or indirectly, entered into any agreement, participated in any collusion, or otherwise taken any action in restraint of free competitive bidding in connection with this proposal bid.

Do not sign, notarize, or submit this Highway Work Proposal when s	submitting an electronic bid on the Internet.
Subscribed and sworn to before me this date	
(Signature, Notary Public, State of Wisconsin)	(Bidder Signature)
(Print or Type Name, Notary Public, State Wisconsin)	(Print or Type Bidder Name)
(Date Commission Expires)	(Bidder Title)
Notary Seal	
For Department U	se Only
ype of Work For Department U	se Only

Date Guaranty Returned

Grading, base course, concrete pavement, curb and gutter, beam guard, signing and pavement marking.

# PLEASE ATTACH PROPOSAL GUARANTY HERE

#### **Effective with November 2007 Letting**

#### PROPOSAL REQUIREMENTS AND CONDITIONS

The bidder, signing and submitting this proposal, agrees and declares as a condition thereof, to be bound by the following conditions and requirements.

If the bidder has a corporate relationship with the proposal design engineering company, the bidder declares that it did not obtain any facts, data, or other information related to this proposal from the design engineering company that was not available to all bidders.

The bidder declares that they have carefully examined the site of, and the proposal, plans, specifications and contract forms for the work contemplated, and it is assumed that the bidder has investigated and is satisfied as to the conditions to be encountered, as to the character, quality, and quantities of work to be performed and materials to be furnished, and as to the requirements of the specifications, special provisions and contract. It is mutually agreed that submission of a proposal shall be considered conclusive evidence that the bidder has made such examination.

The bidder submits herewith a proposal guaranty in proper form and amount payable to the party as designated in the advertisement inviting proposals, to be retained by and become the property of the owner of the work in the event the undersigned shall fail to execute the contract and contract bond and return the same to the office of the engineer within fourteen (14) days after having been notified in writing to do so; otherwise to be returned.

The bidder declares that they understand that the estimate of quantities in the attached schedule is approximate only and that the attached quantities may be greater or less in accordance with the specifications.

The bidder agrees to perform the said work, for and in consideration of the payment of the amount becoming due on account of work performed, according to the unit prices bid in the following schedule, and to accept such amounts in full payment of said work.

The bidder declares that all of the said work will be performed at their own proper cost and expense, that they will furnish all necessary materials, labor, tools, machinery, apparatus, and other means of construction in the manner provided in the applicable specifications and the approved plans for the work together with all standard and special designs that may be designed on such plans, and the special provisions in the contract of which this proposal will become a part, if and when accepted. The bidder further agrees that the applicable specifications and all plans and working drawings are made a part hereof, as fully and completely as if attached hereto.

The bidder, if awarded the contract, agrees to begin the work not later than ten (10) days after the date of written notification from the engineer to do so, unless otherwise stipulated in the special provisions.

The bidder declares that if they are awarded the contract, they will execute the contract agreement and begin and complete the work within the time named herein, and they will file a good and sufficient surety bond for the amount of the contract for performance and also for the full amount of the contract for payment.

The bidder, if awarded the contract, shall pay all claims as required by Section 779.14, Statutes of Wisconsin, and shall be subject to and discharge all liabilities for injuries pursuant to Chapter 102 of the Statutes of Wisconsin, and all acts amendatory thereto. They shall further be responsible for any damages to property or injury to persons occurring through their own negligence or that of their employees or agents, incident to the performance of work under this contract, pursuant to the Standard Specifications for Road and Bridge Construction applicable to this contract.

In connection with the performance of work under this contract, the contractor agrees to comply with all applicable state and federal statutes relating to non-discrimination in employment. No otherwise qualified person shall be excluded from employment or otherwise be subject to discrimination in employment in any manner on the basis of age, race, religion, color, gender, national origin or ancestry, disability, arrest or conviction record (in keeping with s.111.32), sexual orientation, marital status, membership in the military reserve, honesty testing, genetic testing, and outside use of lawful products. This provision shall include, but not be limited to the following: employment, upgrading, demotion or transfer; recruitment or recruitment advertising; layoff or termination; rates of pay or other forms of compensation, and selection for training, including apprenticeship. The contractor further agrees to ensure equal opportunity in employment to all applicants and employees and to take affirmative action to attain a representative workforce.

The contractor agrees to post notices and posters setting forth the provisions of the nondiscrimination clause, in a conspicuous and easily accessible place, available for employees and applicants for employment.

If a state public official (section 19.42, Stats.) or an organization in which a state public official holds at least a 10% interest is a party to this agreement, this contract is voidable by the state unless appropriate disclosure is made to the State of Wisconsin Ethics Board.

#### **Effective with August 2007 Letting**

#### **BID PREPARATION**

## Preparing the Proposal Schedule of Items

#### A General

- Obtain bidding proposals as specified in section 102 of the standard specifications prior to 11:45 AM of the last business day preceding the letting. Submit bidding proposals using one of the following methods:
  - 1. Electronic bid on the internet.
  - 2. Electronic bid on a printout with accompanying diskette or CD ROM.
  - 3. Paper bid under a waiver of the electronic submittal requirements.
- (2) Bids submitted on a printout with accompanying diskette or CD ROM or paper bids submitted under a waiver of the electronic submittal requirements govern over bids submitted on the internet.
- (3) The department will provide bidding information through the department's web site at <a href="http://www.dot.wisconsin.gov/business/engrserv/bid-letting-information.htm">http://www.dot.wisconsin.gov/business/engrserv/bid-letting-information.htm</a>. The contractor is responsible for reviewing this web site for general notices as well as information regarding proposals in each letting. The department will also post special notices of all addenda to each proposal through this web site no later than 4:00 P.M. local time on the Thursday before the letting. Check the department's web site after 5:00 P.M. local time on the Thursday before the letting to ensure all addenda have been accounted for before preparing the bid. When bidding using methods 1 and 2 above, check the Bid Express™ on-line bidding exchange at <a href="http://www.bidx.com/">http://www.bidx.com/</a> after 5:00 P.M. local time on the Thursday before the letting to ensure that the latest schedule of items Expedite file (\*.ebs or \*.00x) is used to submit the final bid.
- (4) Interested parties can subscribe to the Bid Express™ on-line bidding exchange by following the instructions provided at the www.bidx.com web site or by contacting:

Info Tech Inc. 5700 SW 34th Street, Suite 1235 Gainesville, FL 32608-5371

email: mailto:customer.support@bidx.com

- (5) The department will address equipment and process failures, if the bidder can demonstrate that those failures were beyond their control.
- (6) Contractors are responsible for checking on the issuance of addenda and for obtaining the addenda. Notice of issuance of addenda is posted on the department's web site at <a href="http://www.dot.wisconsin.gov/business/engrserv/bid-letting-information.htm">http://www.dot.wisconsin.gov/business/engrserv/bid-letting-information.htm</a> or by calling the department at (608) 266-1631. Addenda can ONLY be obtained from the departments web site listed above or by picking up the addenda at the Bureau of Highway Construction, Room 601, 4802 Sheboygan Avenue, Madison, WI, during regular business hours.

#### **B Submitting Electronic Bids**

#### **B.1** On the Internet

- (1) Do the following before submitting the bid:
  - 1. Have a properly executed annual bid bond on file with the department.
  - 2. Have a digital ID on file with and enabled by Info Tech Inc. Using this digital ID will constitute the bidder's signature for proper execution of the bidding proposal.
- (2) In lieu of preparing, delivering, and submitting the proposal as specified in 102.6 and 102.9 of the standard specifications, submit the proposal on the internet as follows:

- 1. Download the latest schedule of items reflecting all addenda from the Bid Express™ web site.
- 2. Use Expedite™ software to enter a unit price for every item in the schedule of items.
- 3. Submit the bid according to the requirements of Expedite<sup>™</sup> software and the Bid Express<sup>™</sup> web site. Do not submit a bid on a printout with accompanying diskette or CD ROM or a paper bid. If the bidder does submit a bid on a printout with accompanying diskette or a paper bid in addition to the internet submittal, the department will disregard the internet bid.
- 4. Submit the bid before the hour and date the Notice to Contractors designates.
- 5. Do not sign, notarize, and return the bidding proposal described in 102.2 of the standard specifications.
- (3) The department will not consider the bid accepted until the hour and date the Notice to Contractors designates.

#### B.2 On a Printout with Accompanying Diskette or CD ROM

- Ownload the latest schedule of items from the Wisconsin pages of the Bid Express™ web site reflecting the latest addenda posted on the department's web site at <a href="http://www.dot.wisconsin.gov/business/engrserv/bid-letting-information.htm">http://www.dot.wisconsin.gov/business/engrserv/bid-letting-information.htm</a>. Use Expedite ™ software to prepare and print the schedule of items. Provide a valid amount for all price fields. Follow instructions and review the help screens provided on the Bid Express™ web site to assure that the schedule of items is prepared properly.
- (2) Staple an 8 1/2 by 11 inch printout of the Expedite™ generated schedule of items to the other proposal documents submitted to the department as a part of the bidder's sealed bid. As a separate submittal not in the sealed bid envelop but due at the same time and place as the sealed bid, also provide the Expedite™ generated schedule of items on a 3 1/2 inch computer diskette or CD ROM. Label each diskette or CD ROM with the bidder's name, the 4 character department-assigned bidder identification code from the top of the bidding proposal, and a list of the proposal numbers included on that diskette or CD ROM as indicated in the following example:

**Bidder Name** 

**BN00** 

Proposals: 1, 12, 14, & 22

- (3) If bidding on more than one proposal in the letting, the bidder may include all proposals for that letting on one diskette or CD ROM. Include only submitted proposals with no incomplete or other files on the diskette or CD ROM.
- (4) The bidder-submitted printout of the Expedite™ generated schedule of items is the governing contract document and must conform to the requirements of section 102 of the standard specifications. If a printout needs to be altered, cross out the printed information with ink or typewriter and enter the new information and initial it in ink. If there is a discrepancy between the printout and the diskette or CD ROM, the department will analyze the bid using the printout information.
- (5) In addition to the reasons specified in section 102 of the standard specifications, proposals are irregular and the department may reject them for one or more of the following:
  - The check code printed on the bottom of the printout of the Expedite<sup>™</sup> generated schedule of items is not the same on each page.
  - 2. The check code printed on the printout of the Expedite™ generated schedule of items is not the same as the check code for that proposal provided on the diskette or CD ROM.

3. The diskette or CD ROM is not submitted at the time and place the department designates.

#### C Waiver of Electronic Submittal

- The bidder may request a waiver of the electronic submittal requirements. Submit a written request for a waiver in lieu of bids submitted on the internet or on a printout with accompanying diskette or CD ROM. Use the waiver that was included with the paper bid document sent to the bidder or type up a waiver on the bidder's letterhead. The department will waive the electronic submittal requirements for a bidding entity (individual, partnership, joint venture, corporation, or limited liability company) for up to 4 individual proposals in a calendar year. The department may allow additional waivers for equipment malfunctions.
- (2) Submit a schedule of items on paper conforming to section 102 of the standard specifications. The department charges the bidder a \$75 administrative fee per proposal, payable at the time and place the department designates for receiving bids, to cover the costs of data entry. The department will accept a check or money order payable to: "Wisconsin, Dept. of Transportation."
- (3) In addition to the reasons specified in section 102 of the standard specifications, proposals are irregular and the department may reject them for one or more of the following:
  - 1. The bidder fails to provide the written request for waiver of the electronic submittal requirements.
  - 2. The bidder fails to pay the \$75 administrative fee before the time the department designates for the opening of bids unless the bidder requests on the waiver that they be billed for the \$75.
  - 3. The bidder exceeds 4 waivers of electronic submittal requirements within a calendar year.
- (4) In addition to the reasons specified in section 102 of the standard specifications, the department may refuse to issue bidding proposals for future contracts to a bidding entity that owes the department administrative fees for a waiver of electronic submittal requirements.

#### PROPOSAL BID BOND

DT1303 1/2006

Wisconsin Department of Transportation

Proposal Number	Project Number		Letting Date
Name of Principal			
Name of Surety		State in Which Surety is	Organized

We, the above-named Principal and the above-named Surety, are held and firmly bound unto the State of Wisconsin in the sum equal to the Proposal Guaranty for the total bid submitted for the payment to be made; we jointly and severally bind ourselves, our heirs, executors, administrators, successors and assigns. The condition of this obligation is that the Principal has submitted a bid proposal to the State of Wisconsin acting through the Department of Transportation for the improvement designated by the Proposal Number and Letting Date indicated above.

If the Principal is awarded the contract and, within the time and manner required by law after the prescribed forms are presented for signature, enters into a written contract in accordance with the bid, and files the bond with the Department of Transportation to guarantee faithful performance and payment for labor and materials, as required by law, or if the Department of Transportation shall reject all bids for the work described, then this obligation shall be null and void; otherwise, it shall be and remain in full force and effect. In the event of failure of the Principal to enter into the contract or give the specified bond, the Principal shall pay to the Department of Transportation within 10 business days of demand a total equal to the Proposal Guaranty as liquidated damages; the liability of the Surety continues for the full amount of the obligation as stated until the obligation is paid in full.

The Surety, for value received, agrees that the obligations of it and its bond shall not be impaired or affected by any extension of time within which the Department of Transportation may accept the bid; and the Surety does waive notice of any such extension.

IN WITNESS, the Principal and Surety have agreed and have signed by their proper officers and have caused their corporate seals to be affixed this date: **(DATE MUST BE ENTERED)** 

#### **PRINCIPAL**

(Company Name) (Affix Corpora	te Seal)		
(Signature and Title)			
(Company Name)	_		
(Signature and Title)			
(Company Name)			
(Signature and Title)		(Name of Surety) (Affix Seal)	
(Company Name)		(Signature of Attorney-in-Fact)	
(Signature and Title)			
NOTARY FO	R PRINCIPAL	NOTARY FO	R SURETY
(Da	ate)	(Dat	e)
State of Wisconsin	)	State of Wisconsin	)
	) ss. _ County )		) ss. County )
On the above date, this instrument was acknowledged before me by the named person(s).		On the above date, this instrument w named person(s).	as acknowledged before me by the
(Signature, Notary Pub	lic, State of Wisconsin)	(Signature, Notary Publi	c, State of Wisconsin)
(Print or Type Name, Notary Public, State of Wisconsin)		(Print or Type Name, Notary	Public, State of Wisconsin)
(Date Commi	ssion Expires)	(Date Commiss	sion Expires)

Notary Seal Notary Seal

IMPORTANT: A certified copy of Power of Attorney of the signatory agent must be attached to the bid bond.

# **CERTIFICATE OF ANNUAL BID BOND**

DT1305 8/2003

Wisconsin Department of Transportation

(Date)

Time Period Valid (	From/To)
Name of Surety	
Name of Contracto	r
Certificate Holder	Wisconsin Department of Transportation
	y that an annual bid bond issued by the above-named Surety is currently on file with the partment of Transportation.
	is issued as a matter of information and conveys no rights upon the certificate holder mend, extend or alter the coverage of the annual bid bond.
Cancellation:	Should the above policy be cancelled before the expiration date, the issuing surety will give thirty (30) days written notice to the certificate holder indicated above.

(Signature of Authorized Contractor Representative)

#### March 2010

#### LIST OF SUBCONTRACTORS

Section 66.0901(7), Wisconsin Statutes, provides that as a part of the proposal, the bidder also shall submit a list of the subcontractors the bidder proposes to contract with and the class of work to be performed by each. In order to qualify for inclusion in the bidder's list a subcontractor shall first submit a bid in writing, to the general contractor at least 48 hours prior to the time of the bid closing. The list may not be added to or altered without the written consent of the municipality. A proposal of a bidder is not invalid if any subcontractor and the class of work to be performed by the subcontractor has been omitted from a proposal; the omission shall be considered inadvertent or the bidder will perform the work personally.

No subcontract, whether listed herein or later proposed, may be entered into without the written consent of the Engineer as provided in Subsection 108.1 of the Standard Specifications.

Name of Subcontractor	Class of Work	<b>Estimated Value</b>
-		

#### **DECEMBER 2000**

# CERTIFICATION REGARDING DEBARMENT, SUSPENSION, AND OTHER RESPONSIBILITY MATTERS - PRIMARY COVERED TRANSACTIONS

#### **Instructions for Certification**

- 1. By signing and submitting this proposal, the prospective contractor is providing the certification set out below.
- 2. The inability of a person to provide the certification required below will not necessarily result in denial of participation in this covered transaction. The prospective contractor shall submit an explanation of why it cannot provide the certification set out below. The certification or explanation will be considered in connection with the department or agency's determination whether to enter into this transaction. However, failure of the prospective contractor to furnish a certification or an explanation shall disqualify such person from participation in this transaction.
- 3. The certification in this clause is a material representation of fact upon which reliance was placed when the department determined to enter into this transaction. If it is later determined that the contractor knowingly rendered an erroneous certification in addition to other remedies available to the Federal Government the department may terminate this transaction for cause or default.
- 4. The prospective contractor shall provide immediate written notice to the department to whom this proposal is submitted if at any time the prospective contractor learns that its certification was erroneous when submitted or has become erroneous by reason of changed circumstances.
- 5. The terms "covered transaction," "debarred," "suspended," "ineligible," "lower tier covered transaction," "participant," "person," "primary covered transaction," "principal," "proposal," and "voluntarily excluded," as used in this clause, have the meanings set out in the Definitions and Coverage sections of the rules implementing Executive Order 12549. You may contact the department to which this proposal is being submitted for assistance in obtaining a copy of those regulations.
- 6. The prospective contractor agrees by submitting this proposal that, should this contract be entered into, it shall not knowingly enter into any lower tier covered transaction with a person who is debarred, suspended, declared ineligible, or voluntarily excluded from participation in this covered transaction, unless authorized by the department entering into this transaction.
- 7. The prospective contractor further agrees by submitting this proposal that it will include the clause titled "Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion-Lower Tier Covered Transaction," which is included as an addendum to PR-1273 "Required Contract Provisions Federal Aid Construction Contracts," without

modification, in all lower tier covered transactions and in all solicitations for lower tier covered transactions.

- 8. The contractor may rely upon a certification of a prospective subcontractor/materials supplier that it is not debarred, suspended, ineligible, or voluntarily excluded from the covered transaction, unless it knows that the certification is erroneous. A contractor may decide the method and frequency by which it determines the eligibility of its principals. Each contractor may, but is not required to, check the Disapproval List (telephone # 608/266/1631).
- 9. Nothing contained in the foregoing shall be construed to require establishment of a system of records in order to render in good faith the certification required by this clause. The knowledge and information of a contractor is not required to exceed that which is normally possessed by a prudent person in the ordinary course of business dealings.
- 10. Except for transactions authorized under paragraph 6 of these instructions, if a contractor in a covered transaction knowingly enters into a lower tier covered transaction with a person who is suspended, debarred, ineligible or voluntarily excluded from participation in this transaction, in addition to other remedies available to the Federal Government, the department may terminate this transaction for cause or default.

Certification Regarding Debarment, Suspension, and Other Responsibility Matters - Primary Covered Transactions

- (1) The prospective contractor certifies to the best of its knowledge and belief, that it and its principals:
  - (a) Are not presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from covered transactions by any Federal department or agency;
  - (b) Have not within a three-year period preceding this proposal been convicted of or had a civil judgment rendered against them for commission of fraud or a criminal offense in connection with obtaining, attempting to obtain, or performing a public (Federal, State or local) transaction or contract under a public transaction; violation of Federal or State antitrust statutes or commission of embezzlement, theft, forgery, bribery, falsification or destruction of records, making false statements or receiving stolen property;
  - (c) Are not presently indicted for or otherwise criminally or civilly charged by a governmental entity (Federal, State or local) with commission of any of the offense enumerated in paragraph (1)(b) of this certification; and
  - (d) Have not within a three-year period preceding this proposal had one or more public transactions (Federal, State or local) terminated for cause or default.
- (2) Where the prospective contractor is unable to certify to any of the statements in this certification, such prospective contractor shall attach an explanation to this proposal.

# **Special Provisions**

# **Table of Contents**

Articl	e Description	Page #
1.	General	2
2.	Scope of Work.	2
3.	Prosecution and Progress.	2
4.	Traffic.	3
5.	Holiday Work Restrictions.	
6.	Other Work Restrictions.	6
7.	Utilities	6
8.	Wisconsin Lane Closure System Advance Notification.	7
9.	Environmental Protection.	7
10.	QMP Base Aggregate.	
11.	Base Aggregate Dense ¾ Inch.	16
12.	Base Aggregate Dense 1 <sup>1</sup> / <sub>4</sub> Inch.	16
13.	Select Crushed Material	17
14.	Concrete Pavement 8-Inch.	17
15.	Protection of Concrete.	17
16.	Cover Plates Temporary, Item 611.8120.S.	17
17.	Salvage and Reinstall Ramp Gate Assembly, Item SPV.0060.01; Ramp Closure Gate Arms 30-FT, Item SPV.0060.02; Ramp Closure Gate Arms Stockpile 30-FT, Item CC2 2020 S	1.0
	Item 662.3030.S.	18

#### SPECIAL PROVISIONS

#### 1. General.

Perform the work under this construction contract for Project 1009-00-76, Madison – Sun Prairie, USH 151S – IH 39E Ramp, USH 151, Dane County, Wisconsin as the plans show and execute the work as specified in the State of Wisconsin, Department of Transportation, Standard Specifications for Highway and Structure Construction, 2015 Edition, as published by the department, and these special provisions.

If all or a portion of the plans and special provisions are developed in the SI metric system and the schedule of prices is developed in the US standard measure system, the department will pay for the work as bid in the US standard system. 100-005 (20140630)

# 2. Scope of Work.

The work under this contract shall consist of grading, base course, concrete pavement, curb and gutter, beam guard, signing, pavement marking, and all incidental items necessary to complete the work as shown on the plans and included in the proposal and contract.

104-005 (20090901)

# 3. Prosecution and Progress.

Begin work within ten calendar days after the engineer issues a written notice to do so.

Provide the start date to the engineer in writing within a month after executing the contract but at least 14 calendar days before the preconstruction conference. Upon approval, the engineer will issue the notice to proceed within ten calendar days before the approved start date.

To revise the start date, submit a written request to the engineer at least two weeks before the intended start date. The engineer will approve or deny that request based on the conditions cited in the request and its effect on the department's scheduled resources.

The contract time for completion is based on an expedited work schedule and may require extraordinary forces and equipment. Included in this "Prosecution and Progress" article and "Traffic" article are restrictions to working hours and lane closures. Work efforts will possibly require multiple or concurrent controlling operations to occur at the same time. This information is included to assist the contractor and its subcontractors and shall not be interpreted as a demonstration of specified means and methods.

The requirement of standard spec 107.8(6) is eliminated.

1009-00-76 2 of 20

No contractor equipment, including trucks, shall be allowed to use maintenance/emergency crossovers for changing their direction of travel.

Do not begin or continue any work that closes the NW loop ramp outside the allowed time periods specified in the Traffic article in these special provisions. If the contractor fails to open the ramp by the specified times, then the department will assess the contractor interim liquidated damages of \$4,000 per hour per traffic lane or ramp for each hour of lane or ramp closure violations. These damages shall be a quarterly fraction of the \$4,000 hourly interim liquidated damages for each 15-minute increment during which the lane or ramp closure violation occurs. The total interim liquidated damages shall be the summation of the separate interim liquidated damages for each lane or ramp closure violation. Hourly interim liquidated damages will be assessed using the Administrative bid item 801.0104 Failing to Open Road to Traffic.

Replace standard spec 108.11 paragraph (3) as follows:

The department will assess \$5,000 in daily liquidated damages. These liquidated damages reflect the cost of engineering, supervision, and a portion of road user costs.

Perform the work in the order shown on the Construction Staging plans and as hereinafter detailed. Changes to the construction staging will not be permitted unless approved by the engineer.

#### Stage 1 and 3, Cover and Uncover Type 1 Sign

An existing Type 1 sign on USH 151 southbound east of the project location requires a cover to shield a conflicting message.

#### Stage 2, Ramp Construction

This stage involves paving the right terrace of the northwest loop ramp and other incidental construction.

When the ramp is open, material and equipment delivery or removal are prohibited from entering and leaving the work zone into the live traffic lane.

#### 4. Traffic.

#### A General

Keep mainline IH 39/90/94 and mainline USH 151, on which this project is located, open to through traffic at all times throughout the project. Maintain all existing 12-foot wide lanes of traffic in each direction at all times on USH 151 and IH 39/90/94 except as allowed below. Keep all ramps open to traffic at all times except as allowed below.

All ramp closures are subject to the approval of the region traffic engineer. Times listed for ramp closure restrictions include setup and breakdown of any equipment and traffic control devices. Notify all local emergency services at least 24 hours prior to closing the NW loop ramp between IH 39/90/94 and USH 151. Provide the State Highway Patrol, the

1009-00-76 3 of 20

Dane County Sheriff's Department, and the engineer a current telephone number with which the contractor or his representative can be contacted during non-working hours in the event a safety hazard develops.

Do not park or store equipment, vehicles, or construction materials within the clear zone of any roadway carrying traffic during non-working hours except at locations and periods of time approved by the engineer. At such locations, the material and equipment involved shall not constitute a hazard to the traveling public.

During working hours, keep construction vehicles within the work zone to an absolute minimum.

Supplement standard spec 107.8 as follows:

Equip all contractors' vehicles and equipment operating in or near live traffic lanes with at least one hazard identification beacon (flashing amber light). The flashing amber light shall be activated when vehicles or equipment are operated on the roadway, parked in close proximity to the roadway, and when entering or exiting live lanes of traffic. The flashing amber light shall be mounted approximately midway between the transverse extremities of the vehicles or machinery and at the highest practicable point that provides visibility from all directions. The light shall be of the flashing strobe or revolving type meeting the following minimum requirements:

Flashing Strobe Type Light
360-degree lens
60 to 90 flashes per minute
5-inch minimum height
3-3/4 inch minimum diameter

Revolving Type Light
360-degree lens
45 to 90 flashes
4-5/8 inch minimum height
3-3/4 inch minimum diameter

The light shall be equipped with bulbs of 50 candlepower minimum. Mounting shall be either magnetic or permanent. No compensation for furnishing and installing the flashing amber light to contractor owned construction equipment or vehicles will be provided for in the contract.

The traffic requirements are subject to change at the direction of the engineer in the event of an emergency.

#### **B** Traffic Staging

# Stage 1 and 3, Cover and Uncover Type 1 Sign:

Advanced notification signage on USH 151 southbound describing the location of Exit 97A is located on a Type 1 sign on an overhead structure. Covering and uncovering the Type 1 sign with a fixed message sign will require closing multiple lanes to allow access without working over traffic. The sign shall be covered at the beginning of construction operations prior to any ramp closure. The sign may be uncovered only after completion of work requiring ramp closure.

1009-00-76 4 of 20

The mainline USH 151 lane closures required for covering and uncovering the Type 1 signs shall only occur on a Sunday through Thursday night between 11:00 PM and 4:00 AM.

# **Stage 2, Ramp Construction:**

This stage involves paving the right terrace of the northwest loop ramp. An intermittent closure of the northwest loop ramp (Exit 97A) will occur to construct the terrace paving and other associated improvements.

A detour shall be put in place using IH 39/90/94 northbound to the USH 51 interchange. The detour for USH 151 exiting traffic shall begin just east of the IH 39/90/94 and USH 151 interchange utilizing Exit 97B. Detoured traffic will proceed northbound onto IH 39/90/94 and then take Exit 132 to USH 51. At the USH 51 interchange, traffic will turn left onto USH 51 southbound at the signalized ramp terminal. After crossing under IH 39/90/94, detoured traffic will take the loop entrance ramp onto IH 39/90/94 and continue southbound to the end of the detour at USH 151. Detour signage will be placed along the detour route. The ramp may only be closed and detoured according to the schedule below:

NW Loop Ramp Closure Schedule							
	Sun PM Mon AM	Tues AM	Wed AM	Wed PM Thur AM	Fri PM	Sat PM	Sat AM Sun PM
Nighttime Closure	7:00 PM - 6:00 AM			7:00 PM - 6:00 AM			

Prior to reopening, ensure the ramp is free of all debris and construction materials. The ramp may not be opened if debris or construction materials are present within the traffic zone. Delays in opening the ramp associated with removal of debris or construction materials that conflict with the ramp closure schedule are the responsibility of the contractor and may be subject to damages as outlined in Section B above.

No detours are allowed for mainline USH 151 or mainline IH 39/90/94.

#### C Traffic Control Devices

Prior to any work being performed, place appropriate traffic control signing, devices and temporary and permanent pavement marking as detailed on the plans, in the Standard Detail Drawings and in conformance with the Manual of Uniform Traffic Control Devices (MUTCD). Do not proceed with any operation until all traffic control devices for such work are in the proper location, as approved by the engineer.

Place Traffic Control Signs Portable Changeable Message at the beginning of the project on IH 39/90/94 and USH 151 at least 14 calendar days prior to the beginning of construction as defined in the plans. Obtain approval from the department for all messages for the Traffic Control Signs Portable Changeable Message.

Do not proceed with any operation until all traffic control devices for such work are in the proper location.

1009-00-76 5 of 20

Place drums for shoulder closures one-foot minimum from edge of live traffic lane except as shown on the plans. Drums placed adjacent to the work areas shall be pulled back from the traveled lane when work is not in progress.

Have available at all times sufficient experienced personnel to promptly install, remove and reinstall the required traffic control devices to properly route traffic for work operations.

Do not disturb, remove or obliterate any permanent traffic control signs, advisory signs, shoulder delineators or beam guard in place along the traveled roadways not shown on the plans without the approval of the engineer.

# 5. Holiday Work Restrictions.

Do not perform work on, nor haul materials of any kind along or across any portion of the highway carrying USH 151 or IH 39/90/94 traffic, and entirely clear the traveled way and shoulders of such portions of the highway of equipment, barricades, signs, lights, and any other material that might impede the free flow of traffic during the following holiday periods:

- · From noon Friday, April 3, 2015 to 6:00 AM Monday, April 6, 2015 for Good Friday and Easter;
- From noon Friday, May 22, 2015 to 6:00 AM Tuesday, May 26, 2015 for Memorial Day;

107-005 (20050502)

#### 6. Other Work Restrictions.

USH 151, IH 39/90/94 and all ramps shall be kept fully open to traffic in each direction at all times during the following special event periods:

• Great Midwest Horse Fair – 6:00 AM Friday, April 17, 2015 to 7:00 PM Sunday, April 19, 2015.

#### 7. Utilities.

This contract does come under the provision of Administrative Rule Trans 220.

There are no known utility facilities within the project limits. 107-065 (20080501)

1009-00-76 6 of 20

# 8. Wisconsin Lane Closure System Advance Notification.

Provide the following minimum advance notification to the engineer for incorporation into the Wisconsin Lane Closure System (LCS). Advance notification is not required for closures and/restrictions on "ON" and "OFF" ramps from and to local streets.

New lane closures* 14 ca	alendar days
	alendar days
New system and service ramp restrictions* 14 ca	alendar days
System and service Ramp closures 14 ca	alendar days
Project start 14 ca	alendar days
Construction stage changes 14 ca	alendar days
Detours 14 ca	alendar days
Lane closures** 3 by	usiness days
System and Service Ramp closures** 3 by	usiness days
Extending all closure types 3 by	usiness days

<sup>\*</sup> With height, weight, or width restrictions (available width, all lanes in one direction <16')

Discuss LCS completion dates at weekly project meetings in order to manage closures nearing their completion date prior to the completion date. Enter changes in the schedule or completion date into LCS after the weekly project update meetings. For unexpected closure extension required due to weather, equipment malfunction, or other emergency situation, contact the regional work zone engineer in the region where the work will occur for additional guidance.

Enter the range of the project duration and utilize overrides when the closure is not in place for long term projects with sporadic restricted nighttime or daytime closures. Enter a note into LCS explaining that this approach is being utilized, so if a load needs to get through, permitting can double check to determine whether the closure is in place.

#### 9. Environmental Protection.

*Supplement standard spec 107.20 with the following:* 

Pursue operations in a timely and diligent manner, continuing all construction operations methodically from the initial topsoil stripping operation through the subsequent grading, re-topsoiling, and installation of erosion control devices in order to minimize the period of exposure to possible erosion.

WDNR mandates that appropriate erosion control measures be applied to borrow and waste areas during and following construction. Following completion of the project, restore borrow and waste areas and properly seed, mulch and protect them from the effects of erosion.

1009-00-76 7 of 20

<sup>\*\*</sup> Without height, weight, or width restrictions (available width, all lanes in one direction >16')

When engaged in roadway cleaning operations, the contractor shall use equipment having vacuum or water spray mechanisms to eliminate the dispersion of particulate matter into the atmosphere. If vacuum equipment is employed, it must have a suitable self-contained particulate collector to prevent discharge from the collector bin into the atmosphere. Payment for cleaning operations and equipment employed in cleaning operations is incidental to the contract.

Remove all temporary erosion control measures after disturbed areas are stabilized or at the direction of the engineer.

Provide the Erosion Control Implementation Plan (ECIP) 14 days prior to the preconstruction conference. The contractor shall prepare and submit an ECIP for the project, including borrow sites and material disposal sites, in accordance to Wis. Adm. Code Chapter TRANS 401 requirements. The erosion control implementation plan shall supplement information shown on the plans and shall not reproduce it. The erosion control implementation plan will identify how the contractor intends to implement the project's erosion control plan.

# 10. QMP Base Aggregate.

#### **A Description**

#### A.1 General

- (1) This special provision describes contractor quality control (QC) sampling and testing for base aggregates, documenting those test results, and documenting related production and placement process changes. This special provision also describes department quality verification (QV), independent assurance (IA), and dispute resolution.
- (2) Conform to standard spec 301, standard spec 305, and standard spec 310 as modified here in this special provision. Apply this special provision to material placed under all of the Base Aggregate Dense and Base Aggregate Open Graded bid items, except do not apply this special provision to material classified as reclaimed asphaltic pavement placed under the Base Aggregate Dense bid items.
- (3) Do not apply this special provision to material placed under the Aggregate Detours, Salvaged Asphaltic Pavement Base, Breaker Run, Select Crushed, Pit Run, Subbase, or Riprap bid items.
- (4) Provide and maintain a quality control program, defined as all activities related to and documentation of the following:
  - 1. Production and placement control and inspection.
  - 2. Material sampling and testing.

1009-00-76 8 of 20

(5) Chapter 8 of the department's construction and materials manual (CMM) provides additional detailed guidance for QMP work and describes required sampling and testing procedures. The contractor may obtain the CMM from the department's web site at:

http://roadwaystandards.dot.wi.gov/standards/cmm/index.htm

#### **A.2 Contractor Testing for Small Quantities**

- (1) The department defines a small quantity, for each individual Base Aggregate bid item, as a plan quantity of 9000 tons or less of material as shown in the schedule of items under that bid item.
- (2) The requirements under this special provision apply equally to a small quantity for an individual bid item except as follows:
  - 1. The contractor need not submit a full quality control plan but shall provide an organizational chart to the engineer including names, telephone numbers, and current certifications of all persons involved in the quality control program for material under affected bid items.

2. Divide the aggregate into uniformly sized sublots for testing as follows:

$\mathcal{E}\mathcal{E}$	,
Plan Quantity	Minimum Required Testing
≤ 1500 tons	One test from production, load-out, or
	placement at the contractor's option <sup>[1]</sup>
$> 1500$ tons and $\le 6000$ tons	Two tests of the same type, either from production, load-out, or placement at the contractor's option <sup>[1]</sup>
$>$ 6000 tons and $\leq$ 9000 tons	Three placement tests <sup>[2][3]</sup>

- If using production tests for acceptance, submit test results to the engineer for review prior to incorporating the material into the work. Production test results are valid for a period of 3 years.
- [2] For 3-inch material, obtain samples at load-out.
- [3] If the actual quantity overruns 9000 tons, create overrun sublots to test at a rate of one additional placement test for each 3000 tons, or fraction of 3000 tons, of overrun.
- 3. No control charts are required. Submit aggregate load-out and placement test results to the engineer within one business day of obtaining the sample. Assure that all properties are within the limits specified for each test.
- 4. Department verification testing is optional for quantities of 6000 tons or less.
- (3) Material represented by a sublot with any property outside the specification limits is nonconforming. The department may reject material or otherwise determine the final disposition of nonconforming material as specified in standard spec 106.5.

#### **B** Materials

#### **B.1 Quality Control Plan**

(1) Submit a comprehensive written quality control plan to the engineer at or before the pre-construction meeting. Do not place base before the engineer reviews and comments on the plan. Construct the project as that plan provides.

1009-00-76 9 of 20

- Do not change the quality control plan without the engineer's review. Update the plan with changes as they become effective. Provide a current copy of the plan to the engineer and post in each of the contractor's laboratories as changes are adopted. Ensure that the plan provides the following elements:
  - 1. An organizational chart with names, telephone numbers, current certifications and/or titles, and roles and responsibilities of QC personnel.
  - 2. The process used to disseminate QC information and corrective action efforts to the appropriate persons. Include a list of recipients, the communication means that will be used, and action time frames.
  - 3. A list of source and processing locations, section and quarter descriptions, for all aggregate materials requiring QC testing.
  - 4. Test results for wear, sodium sulfate soundness, freeze/thaw soundness, and plasticity index of all aggregates requiring QC testing. Obtain this information from the region materials unit or from the engineer.
  - 5. Descriptions of stockpiling and hauling methods.
  - 6. Locations of the QC laboratory, retained sample storage, and where control charts and other documentation is posted.
  - 7. An outline for resolving a process control problem. Include responsible personnel, required documentation, and appropriate communication steps.

#### **B.2** Personnel

(1) Have personnel certified under the department's highway technician certification program (HTCP) perform sampling, testing, and documentation as follows:

Required Certification Level:	Sampling or Testing Roles:
Aggregate Technician IPP	Aggregate Sampling <sup>[1]</sup>
Aggregate Sampling Technician	
Aggregate Assistant Certified Technician (ACT-AGG)	
Aggregate Technician IPP	Aggregate Gradation Testing,
Aggregate Assistant Certified Technician (ACT-AGG)	Aggregate Fractured Particle
	Testing, Aggregate Liquid
	Limit and Plasticity Index
	Testing

Plant personnel under the direct observation of an aggregate technician certified at level one or higher may operate equipment to obtain samples.

(2) A certified technician must coordinate and take responsibility for the work an ACT performs. Have a certified technician ensure that all sampling and testing is performed correctly, analyze test results, and post resulting data. No more than one ACT can work under a single certified technician.

#### **B.3** Laboratory

(1) Perform QC testing at a department-qualified laboratory. Obtain information on the Wisconsin laboratory qualification program from:

1009-00-76

Materials Management Section 3502 Kinsman Blvd. Madison, WI 53704 Telephone: (608) 246-5388

http://www.dot.state.wi.us/business/engrserv/lab-qualification.htm

## **B.4 Quality Control Documentation**

#### **B.4.1** General

(1) Submit base aggregate placement documentation to the engineer within 10 business days after completing base placement. Ensure that the submittal is complete, neatly organized, and includes applicable project records and control charts.

#### **B.4.2 Records**

(1) Document all placement observations, inspection records, and control adjustments daily in a permanent field record. Also include all test results in the project records. Provide test results to the engineer within 6 hours after obtaining a sample. For 3-inch base, extend this 6-hour limit to 24 hours. Post or distribute tabulated results using a method mutually agreeable to the engineer and contractor.

#### **B.4.3** Control Charts

- (1) Plot gradation and fracture on the appropriate control chart as soon as test results are available. Format control charts according to CMM 8.30. Include the project number on base placement control charts. Maintain separate control charts for each base aggregate size, source or classification, and type.
- Provide control charts to the engineer within 6 hours after obtaining a sample. For 3-inch base, extend this 6-hour limit to 24 hours. Post or distribute charts using a method mutually agreeable to the engineer and contractor. Update control charts daily to include the following:
  - 1. Contractor individual QC tests.
  - 2. Department OV tests.
  - 3. Department IA tests.
  - 4. Four-point running average of the QC tests.
- (3) Except as specified under B.8.2.1 for nonconforming QV tests, include only QC tests in the running average. The contractor may plot process control or informational tests on control charts, but do not include these tests, conforming QV tests, or IA tests in the running average.

#### **B.5** Contractor Testing

- (1) Test gradation, fracture, liquid limit and plasticity index during placement for each base aggregate size, source or classification, and type.
- (2) Test gradation once per 3000 tons of material placed. Determine random sample locations and provide those sample locations to the engineer. Obtain samples after the material has been bladed, mixed, and shaped but before compacting; except collect

1009-00-76

3-inch samples from the stockpile at load-out. Do not sample from material used to maintain local traffic or from areas of temporary base that will not have an overlying pavement. On days when placing only material used to maintain local traffic or only temporary base that will not have an overlying pavement, no placement testing is required.

- (3) Split each contractor QC sample and identify it according to CMM 8.30. Retain the split for 7 calendar days in a dry, protected location. If requested for department comparison testing, deliver the split to the engineer within one business day.
- (4) The engineer may require additional sampling and testing to evaluate suspect material or the technician's sampling and testing procedures.
- (5) Test fracture for each gradation test until the fracture running average is above the lower warning limit. Subsequently, the contractor may reduce the frequency to one test per 10 gradation tests if the fracture running average remains above the warning limit.
- (6) Test the liquid limit and plasticity index for the first gradation test. Subsequently, test the liquid limit and plasticity index a minimum of once per 10 gradation tests.

#### **B.6 Test Methods**

#### **B.6.1** Gradation

(1) Test gradation using a washed analysis conforming to the following as modified in CMM 8.60:

Gradation	AASHTO T 27
Material finer than the No. 200 sieve.	AASHTO T 11

- (2) For 3-inch base, if 3 consecutive running average points for the percent passing the No. 200 sieve are 8.5 percent or less, the contractor may use an unwashed analysis. Wash at least one sample out of 10. If a single running average for the percent passing the No. 200 sieve exceeds 8.5 percent, resume washed analyses until 3 consecutive running average points are again 8.5 percent passing or less.
- (3) Maintain a separate control chart for each sieve size specified in standard spec 305 or standard spec 310 for each base aggregate size, source or classification, and type. Set control and warning limits based on the standard specification gradation limits as follows:
  - 1. Control limits are at the upper and lower specification limits.
  - 2. There are no upper warning limits for sieves allowing 100 percent passing and no lower control limits for sieves allowing 0 percent passing.
  - 3. Dense graded warning limits, except for the No. 200 sieve, are 2 percent within the upper and lower control limits. Warning limits for the No. 200 sieve are set 0.5 percent within the upper and lower control limits.
  - 4. Open graded warning limits for the 1-inch, 3/8-inch, and No. 4 sieves are 2 percent within the upper and lower control limits. Upper warning limits for the No. 10, No. 40, and No. 200 sieves are 1 percent inside the upper control limit.

1009-00-76 12 of 20

#### **B.6.2** Fracture

- (1) Test fracture conforming to CMM 8.60. The engineer will waive fractured particle testing on quarried stone.
- (2) Maintain a separate fracture control chart for each base aggregate size, source or classification, and type. Set the lower control limit at the contract specification limit, either specified in another special provision or in table 301-2 of standard spec 301.2.4.5. Set the lower warning limit 2 percent above the lower control limit. There are no upper limits.

#### **B.6.3** Liquid Limit and Plasticity

- Test the liquid limit and plasticity according to AASHTO T 89 and T 90.
- Ensure the material conforms to the limits specified in standard spec table 301-2.

#### **B.7** Corrective Action

#### B.7.1 General

(1) Consider corrective action when the running average trends toward a warning limit. Take corrective action if an individual test exceeds the contract specification limit. Document all corrective actions both in the project records and on the appropriate control chart.

#### **B.7.2 Placement Corrective Action**

- (1) Do not blend additional material on the roadbed to correct gradation problems.
- (2) Notify the engineer whenever the running average exceeds a warning limit. When 2 consecutive running averages exceed a warning limit, the engineer and contractor will discuss appropriate corrective action. Perform the engineer's recommended corrective action and increase the testing frequency as follows:
  - 1. For gradation, increase the QC testing frequency to at least one randomly sampled test per 1000 tons placed.
  - 2. For fracture, increase the QC testing frequency to at least one test per gradation test
- (3) If corrective action improves the property in question such that the running average after 4 additional tests is within the warning limits, the contractor may return to the testing frequency specified in B.5.3. If corrective action does not improve the property in question such that the running average after 4 additional individual tests is still in the warning band, repeat the steps outlined above starting with engineer notification.
- (4) If the running average exceeds a control limit, material starting from the first running average exceeding the control limit and ending at the first subsequent running average inside the control limit is nonconforming and subject to pay reduction.

1009-00-76

- (5) For individual test results significantly outside the control limits, notify the engineer, stop placing base, and suspend other activities that may affect the area in question. The engineer and contractor will jointly review data, data reduction, and data analysis; evaluate sampling and testing procedures; and perform additional testing as required to determine the extent of potentially unacceptable material. The engineer may direct the contractor to remove and replace that material. Individual test results are significantly outside the control limits if meeting one or more of the following criteria:
  - 1. A gradation control limit for the No. 200 sieve is exceeded by more than 3.0 percent.
  - 2. A gradation control limit for any sieve, except the No. 200, is exceeded by more than 5.0 percent.
  - 3. The fracture control limit is exceeded by more than 10.0 percent.

#### **B.8 Department Testing**

#### **B.8.1** General

(1) The department will conduct verification testing to validate the quality of the product and independent assurance testing to evaluate the sampling and testing. The department will provide the contractor with a listing of names and telephone numbers of all QV and IA personnel for the project, and provide test results to the contractor within 2 business days after the department obtains the sample.

## **B.8.2** Verification Testing

#### B.8.2.1 General

- (1) The department will have an HTCP technician, or ACT working under a certified technician, perform QV sampling and testing. Department verification testing personnel must meet the same certification level requirements specified in B.2 for contractor testing personnel for each test result being verified. The department will notify the contractor before sampling so the contractor can observe QV sampling.
- (2) The department will conduct QV tests of each base aggregate size, source or classification, and type during placement conforming to the following:
  - 1. One non-random test on the first day of placement.
  - 2. At least one random test per 30,000 tons, or fraction of 30,000 tons, placed.
- (3) The department will sample randomly, at locations independent of the contractor's QC work, collecting one sample at each QV location. The department will collect QV samples after the material has been bladed, mixed, and shaped but before compacting; except, for 3-inch aggregates, the department will collect samples from the stockpile at load-out. The department will split each sample, test half for QV, and retain half.
- (4) The department will conduct QV tests in a separate laboratory and with separate equipment from the contractor's QC tests. The department will use the same methods specified for QC testing.

1009-00-76 14 of 20

(5) The department will assess QV results by comparing to the appropriate specification limits. If QV test results conform to the specification, the department will take no further action. If QV test results are nonconforming, add the QV to the QC test results as if it were an additional QC test.

#### **B.8.3** Independent Assurance

- (1) Independence assurance is unbiased testing the department performs to evaluate the department's QV and the contractor's QC sampling and testing including personnel qualifications, procedures, and equipment. The department will perform an IA review according to the department's independent assurance program. That review may include one or more of the following:
  - 1. Split sample testing.
  - 2. Proficiency sample testing.
  - 3. Witnessing sampling and testing.
  - 4. Test equipment calibration checks.
  - 5. Reviewing required worksheets and control charts.
  - 6. Requesting that testing personnel perform additional sampling and testing.
- (2) If the department identifies a deficiency, and after further investigation confirms it, correct that deficiency. If the contractor does not correct or fails to cooperate in resolving identified deficiencies, the engineer may suspend placement until action is taken. Resolve disputes as specified in B.9.

#### **B.9 Dispute Resolution**

- (1) The engineer and contractor should make every effort to avoid conflict. If a dispute between some aspect of the contractor's and the engineer's testing program does occur, seek a solution mutually agreeable to the project personnel. The department and contractor may review the data, examine data reduction and analysis methods, evaluate sampling and testing procedures, and perform additional testing. Use ASTM E 178 to evaluate potential statistically outlying data.
- (2) Production test results, and results from other process control testing, may be considered when resolving a dispute.
- (3) If the project personnel cannot resolve a dispute, and the dispute affects payment or could result in incorporating non-conforming product, the department will use third party testing to resolve the dispute. The department's central office laboratory, or a mutually agreed on independent testing laboratory, will provide this testing. The engineer and contractor will abide by the results of the third party tests. The party in error will pay service charges incurred for testing by an independent laboratory. The department may use third party test results to evaluate the quality of questionable materials and determine the appropriate payment. The department may reject material or otherwise determine the final disposition of nonconforming material as specified in standard spec 106.5.

#### C (Vacant)

1009-00-76 15 of 20

#### D (Vacant)

#### E Payment

- (1) Costs for all sampling, testing, and documentation required under this special provision are incidental to this work. If the contractor fails to perform the work required under this special provision, the department may reduce the contractor's pay. The department will administer pay reduction under the non-performance of QMP administrative item.
- (2) For material represented by a running average exceeding a control limit, the department will reduce pay by 10 percent of the contract price for the affected Base Aggregate bid items listed in subsection A. The department will administer pay reduction under the Nonconforming QMP Base Aggregate Gradation or Nonconforming QMP Base Aggregate Fracture Administrative items. The department will determine the quantity of nonconforming material as specified in B.7.2. 301-010 (20100709)

# 11. Base Aggregate Dense ¾ Inch.

This work shall be in accordance to the pertinent requirements of standard spec 305, except that the material used in the top 3 inches of all unpaved portions of shoulders, as shown in the plan, shall consist of crushed stone.

# 12. Base Aggregate Dense 1<sup>1</sup>/<sub>4</sub> Inch.

Revise standard spec 305.2.2.1 as follows:

Use 1½ inch base aggregate that conforms to the following gradation requirements:

Percentage by weight passing

Sieve Size	Percentage of Mass Passing
1 <sup>1</sup> / <sub>4</sub> inch	95 - 100
1 inch	
<sup>3</sup> / <sub>4</sub> inch	70 - 90
3/8 inch	45 - 75
No. 4	30 - 60
No. 10	20 - 40
No. 40	7 - 25
No. 200	2 - 12 [1], [3]

Limited to a maximum of eight percent for base placed between old and new pavement.

1009-00-76

<sup>&</sup>lt;sup>[3]</sup> 3 - 10 percent passing when base is  $\geq$  50% crushed gravel.

#### 13. Select Crushed Material.

Revise standard spec 312.2 as follows:

Use select crushed material that conforms to the following gradation requirements:

Sieve Size	Percentage of Mass Passing
5-inch	90 - 100
1 1/2-inch	0-30
No. 10	0 - 10

#### 14. Concrete Pavement 8-Inch.

The work shall be in accordance to standard spec 415, except that standard specs 415.3.6.1 (1) and (2) are deleted.

#### 15. Protection of Concrete.

Add the following to standard spec 415.3.16:

Provide for a minimum of one concrete finisher to remain on the project site after final finishing of all concrete surfaces until such time as the concrete has hardened sufficiently to resist surface scarring caused by footprints, handprints, or any other type of imprint, malicious or otherwise. The finisher shall actively and continuously patrol on foot the newly placed concrete and repair any damage to the surface that might be sustained as described above.

The cost for providing the finisher(s), the necessary equipment, and materials shall be construed to be included in the contract unit price for each concrete item.

# 16. Cover Plates Temporary, Item 611.8120.S.

#### **A Description**

This special provision describes furnishing, installing and removing a steel plate to cover and support asphaltic pavement and traffic loading at manholes, inlets and similar structures during milling and paving operations.

#### **B** Materials

Provide a 0.25-inch minimum thickness steel plate that extends to the outside edge of the existing masonry.

#### C (Vacant)

#### **D** Measurement

The department will measure Cover Plates Temporary as units, acceptably completed in place.

1009-00-76 17 of 20

#### **E** Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER DESCRIPTION UNIT 611.8120.S Cover Plates Temporary Each

Payment is full compensation for furnishing, installing, and removing the cover plates.

The steel plates shall become the property of the contractor when no longer needed in the contract work.

611-006 (20030820)

# 17. Salvage and Reinstall Ramp Gate Assembly, Item SPV.0060.01; Ramp Closure Gate Arms 30-FT, Item SPV.0060.02; Ramp Closure Gate Arms Stockpile 30-FT, Item 662.3030.S.

#### A Description

This special provision describes salvaging and reinstalling an existing ramp gate assembly, which includes removing the existing pole assembly; disconnecting wire; storing until it is installed on a new base and making all reconnections; furnishing and installing a new gate arm and making all connections; and furnishing and delivering a spare gate arm.

#### **B** Materials

#### Hardware

Furnish galvanized steel nuts and bolts conforming to ASTM A307 except where designated as high strength (HS), conform to ASTM A325.

#### Gate Arm

Provide aluminum/fiberglass gate arms of the nominal length the bid item indicates and conforming to plan dimensions. Cover gate arms on two sides with alternating red and white shop-applied type H reflective from the department's approved products list. Also provide a shear pin base that is the manufacturer's "permanent pivot" style. Obtain components from:

B&B Roadway 15191 Hwy 243 Russellville, AL 35654 Tel: (888) 560-2060

Gate arm: model MU605

1009-00-76 18 of 20

#### Gate Flashers

Furnish gate flasher assemblies conforming to the following:

- 1. A 2-conductor connector, rated 12 volts at 5 amps minimum.
- 2. A 2-amp weather resistant in-line fuse and fuse holder.
- 3. Wiring harness made from 6-conductor 14 AWG stranded insulated control cable.
- 4. A 12 V flasher controller, capable of providing LED flashers with 5% to 100% duty cycle at a one-second pulse repetition rate.
- 5. A 4-conductor male/female electrical connector pair, 10 amp capacity for each connection, weather resistant, and mounted to allow rapid gate arm replacement.
- 6. A 5-amp mercury switch with less than 3 ohms "on" resistance and a 20 to 30 degree activation angle. Mount the switch on the gate arm to activate the flashers when the gate arm is lowered more than 45 degrees from vertical.
- 7. Furnish red LED flashers meeting the requirements of the MUTCD and/or AREMA standards for hue and brightness.

Power consumption	0.45 amp @ 10.5 V
Life expectancy	100,000 hrs
Directionality	0-degree cone orthogonal to face of flasher
Compliance temperature	-40° C to +70° C

#### **C** Construction

Salvage, store, protect and reinstall the ramp closure gate at the location the plans show. Avoid damaging the gate pole assembly, as it will be reused. Do not use any equipment or devices that might damage structures, facilities, or property to be preserved and retained. Complete all operations necessary to remove ramp closure gates that might endanger the new construction before constructing new work.

Apply marine grade anti seize compound to all bolt threads and to the interface between the aluminum base and steel pole. The engineer may direct adjustment of the gate arm assembly to ensure the correct vertical and angular orientation of the completed closure gate.

Verify the attachment of the male side of the 4 conductor electrical connector, mercury switch, wiring harness, and the three LED flasher units to the portion of the flasher assembly mounted on the breakaway portion of the gate arm.

Adjust mercury switch so that as the gate arm is lowered to a maximum of 45 degrees from the vertical, the gate flasher assembly is energized, and the LEDs begin to flash. Ensure that when the gate arm is raised to a minimum of 15 degrees from vertical, the mercury switches the gate flasher assembly off.

1009-00-76

The engineer may allow alternates equal to specified manufactured components. The engineer may require plan detail modifications to accommodate alternates. The engineer may accept alternate arms or mounting adaptors only if the contractor can demonstrate that the department can easily remove and replace the arms.

#### **Furnishing Gate Arms**

Under the Ramp Closure Gate Arms Stockpile bid items, furnish and deliver spare arms of the nominal length the bid item indicates conforming to B Materials. Deliver spare gate arms to an address provided by:

Dena Dramm Phone (608) 246-5360

Deliver the existing gate arm and flashers removed from the ramp gate assembly to the above contact.

#### **D** Measurement

The department will measure Salvage and Reinstall Ramp Gate Assembly and Ramp Closure Gate Arms 30-FT by each individual unit, acceptably completed.

The department will measure the Ramp Closure Gate Arms Stockpile 30-FT bid item as each individual unit, acceptably furnished and delivered.

#### **E** Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0060.01	Salvage and Reinstall Ramp Gate Assembly	Each
SPV.0060.02	Ramp Closure Gate Arms 30-FT	Each
662.3030.S	Ramp Closure Gate Arms Stockpile 30-FT	Each

Payment is full compensation for disassembly of the existing unit as needed; for disconnecting wire, for storing of the unit, for reassembly on a new location; for providing all electrical connections and grounding; and for all testing. Base is paid for separately.

Payment for the Ramp Closure Gate Arms Stockpile is full compensation for furnishing and delivering spare ramp closure gate arms.

1009-00-76 20 of 20

November 2013 ASP-4

#### ADDITIONAL SPECIAL PROVISION 4

#### **Payment to First-Tier Subcontractors**

Within 10 calendar days of receiving a progress payment for work completed by a subcontractor, pay the subcontractor for that work. The prime contractor may withhold payment to a subcontractor if, within 10 calendar days of receipt of that progress payment, the prime contractor provides written notification to the subcontractor and the department documenting "just cause" for withholding payment.

The prime contractor may also withhold routine retainage from payments due subcontractors.

#### **Payment to Lower-Tier Subcontractors**

Ensure that subcontracting agreements at all tiers provide prompt payment rights to lower-tier subcontractors that parallel those granted first-tier subcontractors in this provision.

#### **Release of Routine Retainage**

After granting substantial completion the department may reduce the routine retainage withheld from the prime contractor to 75 percent of the original total amount retained.

When the Department sends the semi-final estimate the department may reduce the routine retainage withheld from the prime contractor to 10 percent of the original total amount retained.

Within 30 calendar days of receiving the semi-final estimate from the department, submit written certification that subcontractors at all tiers are paid in full for acceptably completed work and that no routine retainage is being withheld. The department will pay the prime contractor in full and reduce the routine retainage withheld from the prime contractor to zero when the department approves the final estimate.

This special provision does not limit the right of the department, prime contractor, or subcontractors at any tier to withhold payment for work not acceptably completed or work subject to an unresolved contract dispute.

## ADDITIONAL SPECIAL PROVISION 6 ASP 6 - Modifications to the standard specifications

Make the following revisions to the standard specifications:

#### 450.3.2.1 General

Replace the entire text with the following effective with the January 2015 letting:

- (1) Do not place asphaltic mixture when the air temperature approximately 3 feet above grade, in shade, and away from artificial heat sources is less than 36 F for upper layers or 32 F for lower layers unless the engineer allows in writing. The contractor should place HMA pavement for projects on or north of STH 29 between May 1 and October 15 inclusive and for projects south of STH 29 between April 15 and November 1 inclusive. Notify the engineer at least one business day before paving.
- (2) Unless the contract specifies otherwise, conform to the following:
  - Keep the road open to all traffic during construction.
  - Prepare the existing foundation for treatment as specified in 211.
  - Incorporate loose roadbed aggregate as a part of preparing the foundation, in shoulder construction, or dispose of as the engineer approves.
- (3) Place asphaltic mixture only on a prepared, firm, and compacted base, foundation layer, or existing pavement substantially surface-dry and free of loose and foreign material. Do not place over frozen subgrade or base, or where the roadbed is unstable.

### 450.5 Payment

Replace the entire text with the following effective with the January 2015 letting:

- (1) All costs of furnishing, maintaining, and operating the truck scale or other weighing equipment and furnishing the weigh tickets are incidental to the contract.
- (2) Nonconforming material allowed to remain in place is subject to price adjustment under 105.3.2.
- (3) Full-depth sawing to remove integrally placed safety edge where not required is incidental to the contract.
- (4) The contractor is responsible for pavement performance. If because of an excusable compensable delay under 108.10.3, the engineer directs the contractor to pave when the temperature is less than 36 F for the upper layer or less than 32 F for lower layers, the department:
  - Will relieve the contractor of responsibility for damage and defects the engineer attributes to cold weather paving.
  - Will not assess disincentives for density or ride.

#### 455.3.2.1 General

Replace paragraphs one and two with the following effective with the January 2015 letting:

- (1) Apply tack coat only when the air temperature is 32 F or more unless the engineer approves otherwise in writing. Before applying tack coat ensure that the surface is dry and reasonably free of loose dirt, dust, or other foreign matter. Do not apply if weather or surface conditions are unfavorable or before impending rains.
- (2) Use tack material of the type and grade the contract specifies. The contractor may, with the engineer's approval, dilute tack material as allowed under 455.2.4. Provide calculations using the asphalt content as-received from the supplier and subsequent contractor dilutions to show that as-placed material has 50 percent or more residual asphalt content. Apply at 0.050 to 0.070 gallons per square yard, after dilution, unless the contract designates otherwise. The engineer may adjust the application rate based on surface conditions. Limit application each day to the area the contractor expects to pave during that day.

### 460.2.2.3 Aggregate Gradation Master Range

Replace paragraph one with the following effective with the December 2014 letting:

(1) Ensure that the aggregate blend, including recycled material and mineral filler, conforms to the gradation requirements in table 460-1. The values listed are design limits; production values may exceed those limits.

TABLE 400.4	400DE04TE		DANGE AND WAA DECLUDENENTO
TABLE 460-1	$\Delta(i(iRF(i\Delta)F)$	GRADATION MASTER	RANGE AND VMA REQUIREMENTS

		Р	ERCENTS PA	SSING DESIG	NATED SIEVE	S	
SIEVE			1	NOMINAL SIZE			
	37.5 mm	25.0 mm	19.0 mm	12.5 mm	9.5 mm	SMA 12.5 mm	SMA 9.5 mm
50.0-mm	100						
37.5-mm	90 –100	100					
25.0-mm	90 max	90 -100	100				
19.0-mm		90 max	90 -100	100		100	
12.5-mm			90 max	90 -100	100	90 - 97	100
9.5-mm				90 max	90 -100	58 - 72	90 - 100
4.75-mm					90 max	25 - 35	35 - 45
2.36-mm	15 – 41	19 - 45	23 - 49	28 - 58	20 - 65	15 - 25	18 - 28
75-µm	0 - 6.0	1.0 - 7.0	2.0 - 8.0	2.0 - 10.0	2.0 - 10.0	8.0 - 12.0	10.0 - 14.0
% MINIMUM VMA	11.0	12.0	13.0	14.0 <sup>[1]</sup>	15.0 <sup>[2]</sup>	16.0	17.0

<sup>&</sup>lt;sup>[1]</sup> 14.5 for E-0.3 and E-3 mixes.

### 460.3.4 Cold Weather Paving

Add a new subsection as follows effective with the January 2015 letting:

#### 460.3.4 Cold Weather Paving

#### 460.3.4.1 Cold Weather Paving Plan

- (1) Submit a written cold weather paving plan to the engineer at the preconstruction meeting. In that plan outline material, operational, and equipment changes for paving when the air temperature approximately 3 feet above grade, in shade, and away from artificial heat sources is less than 40 F. Include the following:
  - Use a department-accepted HMA mix design that incorporates a warm mix additive from the department's approved products list. Do not use a foaming process.
  - Use additional rollers.
- (2) Engineer written acceptance is required for the cold weather paving plan. Engineer acceptance of the plan does not relieve the contractor of responsibility for pavement performance except as specified in 450.5(4).

#### 460.3.4.2 Cold Weather Paving Operations

- (1) Do not place asphaltic mixture when the air temperature approximately 3 feet above grade, in shade, and away from artificial heat sources is less than 40 F unless a valid engineer-accepted cold weather paving plan is in effect.
- (2) If the national weather service forecast for the construction area predicts ambient air temperature less than 40 F at the projected time of paving within the next 24 hours, confirm or submit revisions to a previously engineer-accepted cold weather paving plan for engineer validation. Upon validation of the plan, the engineer will allow paving for the next day. Once in effect, pave conforming to the engineeraccepted cold weather paving plan for the balance of that work day or shift regardless of the temperature at the time of paving.

<sup>[2] 15.5</sup> for E-0.3 and E-3 mixes.

#### 460.4 Measurement

Add paragraph two as follows effective with the January 2015 letting:

(2) The department will measure HMA Cold Weather Paving by the ton of HMA mixture for pavement placed conforming to an engineer-accepted cold weather paving plan.

#### 460.5.1 General

Revise paragraph one as follows effective with the January 2015 letting:

(1) The department will pay for measured quantities at the contract unit price under the following bid items:

ITEM NUMBER	DESCRIPTION	<u>UNIT</u>
460.1100	HMA Pavement Type E-0.3	TON
460.1101	HMA Pavement Type E-1	TON
460.1103	HMA Pavement Type E-3	TON
460.1110	HMA Pavement Type E-10	TON
460.1130	HMA Pavement Type E-30	TON
460.1132	HMA Pavement Type E-30X	TON
460.1700	HMA Pavement Type SMA	TON
460.2000	Incentive Density HMA Pavement	DOL
460.4000	HMA Cold Weather Paving	TON

#### 460.5.2.2 Disincentive for HMA Pavement Density

Revise paragraph two as follows effective with the January 2015 letting:

(2) The department will not assess density disincentives for pavement placed in cold weather because of a department-caused delay as specified in 450.5(4).

#### 460.5.2.4 Cold Weather Paving

Add a new subsection as follows effective with the January 2015 letting:

#### 460.5.2.4 Cold Weather Paving

- (1) Payment for HMA Cold Weather Paving is full compensation for additional materials and equipment specified for cold weather paving under 460.3.4 including costs for preparing, administering, and following the contractor's cold weather paving plan.
- (2) If HMA pavement is placed under 460.3.4 and the HMA Cold Weather Paving bid item is not in the contract, the department will pay for the additional costs specified in 460.5.2.4(1) as extra work. The department will pay separately for HMA pavement under the appropriate HMA Pavement bid items.

#### 465.2 Materials

Replace paragraph two with the following effective with the December 2014 letting:

(2) Under the other section 465 bid items, the contractor need not submit a mix design. Furnish aggregates mixed with a type AC asphaltic material, except under the Asphaltic Curb bid item furnish PG58-28 asphaltic material. Use coarse and fine mineral aggregates uniformly coated and mixed with the asphaltic material in an engineer-approved mixing plant. The contractor may include reclaimed asphaltic pavement materials in the mixture.

### **Bid Items Added**

Add the following new bid item effective with the January 2015 letting:

ITEM NUMBERDESCRIPTIONUNIT460.4000HMA Cold Weather PavingTON

#### **Errata**

Make the following corrections to the standard specifications:

#### 501.3.2.4.4 Water Reducer

Correct errata by deleting the reference to footnote 6 for grade D concrete.

(1) Add a water reducing admixture conforming to 501.2.3. Determine the specific type and rate of use based on the atmospheric conditions, the desired properties of the finished concrete and the manufacturer's recommended rate of use. The actual rate of use shall at least equal the manufacturer's recommended rate, and both the type and rate used require the engineer's approval before use.

### **ADDITIONAL SPECIAL PROVISION 7**

- A. Reporting 1<sup>st</sup> Tier and DBE Payments During Construction
  - 1. Comply with reporting requirements specified in the department's Civil Rights Compliance, Contractor's User Manual, Sublets and Payments.
  - 2. Report payments to all DBE firms within 10 calendar days of receipt of a progress payment by the department or a contractor for work performed, materials furnished, or materials stockpiled by a DBE firm. Report the payment as specified in A(1) for all work satisfactorily performed and for all materials furnished or stockpiled.
  - 3. Report payments to all first tier subcontractor relationships within 10 calendar days of receipt of a progress payment by the department for work performed. Report the payment as specified in A(1) for all work satisfactorily performed.
  - 4. All tiers shall report payments as necessary to comply with the DBE payment requirement as specified in A(2).
  - 5. Require all first tier relationships, DBE firms and all other tier relationships necessary to comply with the DBE payment requirement in receipt of a progress payment by contractor to acknowledge receipt of payment as specified in A(1), (2), (3) and (4).
  - 6. All agreements made by a contractor shall include the provisions in A(1), (2), (3), (4) and (5), and shall be binding on all first tier subcontractor relationships and all contractors and subcontractors utilizing DBE firms on the project.
- B. Costs for conforming to this special provision are incidental to the contract.

## **ADDITIONAL SPECIAL PROVISION 9 Electronic Certified Payroll Submittal**

- (1) Use the department's Civil Rights Compliance System (CRCS) to submit certified payrolls electronically. Details are available online through the department's highway construction contractor information (HCCI) site on the Labor, Wages, and EEO Information page at: http://www.dot.wi.gov/business/civilrights/laborwages/index.htm
- (2) Ensure that all tiers of subcontractors, as well as all trucking firms, submit their weekly certified payrolls electronically through CRCS. These payrolls are due within seven calendar days following the close of the payroll period. Every firm providing physical labor towards completing the project is a subcontractor under this special provision.
- (3) Upon receipt of contract execution, promptly make all affected firms aware of the requirements under this special provision and arrange for them to receive CRCS training as they are about to begin payrolls. The department will provide training either in a classroom setting at one of our regional offices or by telephone. Contact Tess Mulrooney at 608-267-4489 to schedule the training.
- (4) The department will reject all paper submittals of forms DT-1816 and DT-1929 for information required under this special provision. All costs for conforming to this special provision are incidental to the contract.
- (5) Firms wishing to export payroll data from their computer system into CRCS should have their payroll coordinator send several sample electronic files to Tess two months before a payroll needs to be submitted. Not every contractor's payroll system is capable of producing export files. For details, see pages 17-22 of the CRCS System Background Information manual available online on the Labor, Wages, and EEO Information page at: http://www.dot.wi.gov/business/civilrights/laborwages/docs/crc-payroll-manual.pdf

Page 1 of 1

#### **DECEMBER 2013**

#### **BUY AMERICA PROVISION**

All steel and iron materials permanently incorporated in this project shall be domestic products and all manufacturing and coating processes for these materials from smelting forward in the manufacturing process must have occurred within the United States. Coating includes epoxy coating, galvanizing, painting and any other coating that protects or enhances the value of a material subject to the requirements of Buy America. The exemption of this requirement is the minimal use of foreign materials if the total cost of such material permanently incorporated in the product does not exceed one-tenth of one percent (1/10 of 1%) of the total contract cost or \$2,500.00, whichever is greater. For purposes of this paragraph, the cost is that shown to be the value of the subject products as they are delivered to the project. The contractor shall take actions and provide documentation conforming to CMM 2-28.5 to ensure compliance with this "Buy America" provision.

http://roadwaystandards.dot.wi.gov/standards/cmm/cm-02-28.pdf#cm2-28.5

Upon completion of the project certify to the engineer, in writing using department form WS4567, that all steel, iron, and coating processes for steel or iron incorporated into the contract work conform to these "Buy America" provisions. Attach a list of exemptions and their associated costs to the certification form. Department form WS4567 is available at:

http://roadwaystandards.dot.wi.gov/standards/forms/ws4567.doc

1 of 1

## WISCONSIN DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS AND TRANSPORTATION FACILITIES

### SUPPLEMENTAL REQUIRED CONTRACT PROVISIONS

- I. Wage Rates, Hours of labor and payment of Wages
- II. Payroll Requirements
- III. Postings at the Site of the Work
- IV. Affidavits
- V. Wage Rate Redistribution
- VI. Additional Classifications

### I. WAGE RATES, HOURS OF LABOR AND PAYMENT OF WAGES

The schedule of "Minimum Wage Rates" attached hereto and made a part hereof furnishes the prevailing wage rates that have been determined pursuant to Section 103.50 of the Wisconsin Statutes. These wage rates are the minimum required to be paid to the various laborers, workers, mechanics and truck drivers employed by contractors and subcontractors on the construction work embraced by the contract and subject to prevailing hours and wages under Section 103.50, Stats. If necessary to employ laborers, workers, mechanics or truck drivers whose classification is not listed on the schedule, they shall be paid at rates conformable to those listed for similar classifications. Apprentices shall be paid at rates not less than those prescribed in their state indenture contacts.

While the wage rates shown are the minimum rates required by the contract to be paid during its life, this in not a representation that labor can be obtained at these rates. It is the responsibility of bidders to inform themselves as to the local labor conditions and prospective changes or adjustments of wage rates. No increase in the contract price shall be allowed or authorized on account of the payment of wage rates in excess of those listed herein.

Pursuant to Section 103.50 of the Wisconsin Statutes, the prevailing hours of labor have been determined to be up to 10 hours per day and 40 hours per calendar week Monday through Friday. If any laborer, worker, mechanic or truck driver is permitted or required to work more than the prevailing number of hours per day or per calendar week on this contract, they shall be paid for all hours in excess of the prevailing hours at a rate of at least one and one-half (1 1/2) times their hourly rate of pay. All work on Saturday, Sunday and the following holidays is to be paid at time and a half: (1) January 1, (2) the last Monday in May, (3) July 4, (4) the first Monday in September, (5) the fourth Thursday in November, (6) December 25, (7) the day before if January 1, July 4 or December 25 falls on a Saturday and (8) the day following if January 1, July 4 or December 25 falls on a Sunday.

All laborers, workers, mechanics and truck drivers shall be paid unconditionally not less often than once a week. Persons who own and operate their own trucks must receive the prevailing truck driver rate for the applicable type of truck (i.e. 2 axle, 3 or more axle, articulated, eculid or dumptor) he or she operates, plus an agreed upon amount for the use of his or her truck. Every owner-operator MUST be paid separately for their driving and for the use of their truck.

For those projects subject to the requirements of the Davis-Bacon Act, the Secretary of Labor will also have determined "Minimum Wage Rates" for work to be performed under the contract. These rates are, for all or most of the labor, worker, mechanic or truck driver classifications, identical to those established under Section 103.50 of the Wisconsin Statutes. In the event the rates are not identical, the higher of the two rates will govern.

### II. PAYROLL REQUIREMENTS

All contractors and subcontractors must submit weekly Certified Payrolls and Compliance Statement verifying that all laborers, workers, mechanics and truck drivers working on the project have been paid the prevailing wage rates for all work performed under the contract required by Section 103.50 of the Wisconsin Statutes.

#### III. POSTINGS AT THE SITE OF THE WORK

In addition to the required postings furnished by the Department, the contractor shall post the following in at least one conspicuous place at the site of work:

- a. "NOTICE TO EMPLOYEES," which provides information required to be posted by the provisions of Section 103.50 of the Wisconsin Statutes.
- b. A copy of the State of Wisconsin Minimum Wages Rates. (Four pages.)
- c. A copy of the contractor's Equal Employment Opportunity Policy.
- d. On any project involving federal aid, in addition to the furnished postings, the contractor shall post a copy of the "Davis-Bacon Act, Minimum Wage Rates". (Three pages.)

#### IV. WAGE RATE REDISTRIBUTION

The amount specified as the hourly basic rate of pay and the amount(s) specified as the fringe benefit contribution(s), for all classes of laborers, workers, mechanics or truck drivers may be redistributed, when necessary, to conform to those specified in any applicable collective bargaining agreement, provided that both parties to such agreement

request and receive the approval for any such redistribution from both the Department of Transportation and the Department of Workforce Development prior to the implementation of such redistribution.

#### V. ADDITIONAL CLASSIFICATIONS

Any unlisted laborer or mechanic classification that is needed to perform work on this project, and is not included within the scope of any of the classifications listed in the application prevailing wage rate determination, may be added after award only if all of the following criteria have been met:

- 1. The affected employer(s) must make a written request to WisDOT Central Office to utilize the unlisted classification on this project.
- 2. The request must indicate the scope of the work to be performed by the unlisted classification and must indicate the proposed wage/fringe benefit package that the unlisted classification is to receive.
- 3. The work to be performed by the unlisted classification must not be performed by a classification that is included in the applicable prevailing wage rate determination.
- 4. The unlisted classification must be commonly employed in the area where the project is located.
- 5. The proposed wage/fringe benefit package must bear a reasonable relationship to those set forth in the applicable prevailing wage rate determination.
- 6. The request should be made prior to the actual performance of the work by the unlisted classification.
- 7. DWD must approve the use of the unlisted classification and the proposed wage/fringe benefit package. USDOL also must approve the use of the unlisted classification and the proposed wage/fringe benefit package on federal aid projects.
- 8. WisDOT and DWD may amend the proposed wage/fringe benefit package, as deemed necessary, and may set forth specific employment ratios and scope of work requirements in the approval document.

The approved wage/fringe benefit package shall be paid to all laborers, workers, mechanics or truck drivers performing work within the scope of that performed by the unlisted classification, from the first day on which such work is performed. In the event that work is performed by the unlisted classification prior to approval, the wage/fringe benefit package to be paid for such work must be in conformance with the wage/fringe

benefit package approved for such work. Under this arrangement a retroactive adjustment in wages and/or fringe benefits may be required to be made to the affected laborers, workers, mechanics or truck drivers by the affected employer(s).

#### ANNUAL PREVAILING WAGE RATE DETERMINATION FOR ALL STATE HIGHWAY PROJECTS DANE COUNTY

Compiled by the State of Wisconsin - Department of Workforce Development for the Department of Transportation
Pursuant to s. 103.50, Stats.
Issued on May 1, 2014

**CLASSIFICATION:** Contractors are required to call the Department of Workforce Development if there are any questions regarding the proper trade or classification to be used for any worker on a public works project.

**OVERTIME:** Time and one-half must be paid for all hours worked over 10 hours per day and 40 hours per calendar week and for all hours worked on Saturday, Sunday and the following six (6) holidays: January 1; the last Monday in May; July 4; the 1st Monday in September; the 4th Thursday in November; December 25; the day before if January 1, July 4 or December 25 falls on a Saturday; the day following if January 1, July 4 or December 25 falls on a Sunday.

**FUTURE INCREASE:** If indicated for a specific trade or occupation, the full amount of such increase MUST be added to the "TOTAL" indicated for such trade or occupation on the date(s) such increase(s) becomes effective.

**PREMIUM PAY:** If indicated for a specific trade or occupation, the full amount of such pay MUST be added to the "HOURLY BASIC RATE OF PAY" indicated for such trade or occupation, whenever such pay is applicable.

**SUBJOURNEY:** Wage rates may be available for some of the classifications indicated below. Any employer that desires to use any subjourney classification on a project MUST request the applicable wage rate from the Department of Workforce Development PRIOR to the date such classification is used on such project. Form ERD-10880 is available for this purpose and can be obtained by writing to the Department of Workforce Development, Equal Rights Division, P.O. Box 8928, Madison, WI 53708.

TRADE OR OCCUPATION	HOURLY BASIC RATE OF PAY	HOURLY FRINGE BENEFITS \$	TOTAL
Bricklayer, Blocklayer or Stonemason		¥ 17.35	49.36
Carpenter	30.48	15.90	46.38
Cement Finisher	33.51	16.13	49.64
Future Increase(s): Add \$1.87 on 6/1/14; Add \$1.87 on 6/1/15; Add \$1 Premium Pay: DOT PREMIUMS: 1) Pay two times the hourly basic ra Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Department of Transportation or responsible governing agency requir artificial illumination with traffic control and the work is completed after	te on Sunday, Nev Day. 2) Add \$1.40/I es that work be pe	hr when the Wisc erformed at night	consin
Electrician	34.07	19.25	53.32
Premium Pay: DOT PREMIUM: Pay two times the hourly basic rate of Independence Day, Labor Day, Thanksgiving Day & Christmas Day.	n Sunday, New Ye	ar's Day, Memor	ial Day,
Fence Erector	24.72	0.00	24.72
Ironworker	31.25	19.46	50.71
Line Constructor (Electrical)	38.25	17.31	55.56
Painter	21.87	11.37	33.24
Pavement Marking Operator	30.00	0.00	30.00
Piledriver	30.98	15.90	46.88
Roofer or Waterproofer	29.40	6.25	35.65
Teledata Technician or Installer	21.89	11.85	33.74
Tuckpointer, Caulker or Cleaner	35.25	13.15	48.40
Underwater Diver (Except on Great Lakes)	34.48	15.90	50.38
Heavy Equipment Operator - ELECTRICAL LINE CONSTRUCTION ONL	Y 34.43	15.24	49.67
Light Equipment Operator -ELECTRICAL LINE CONSTRUCTION ONLY	35.50	15.89	51.39
Heavy Truck Driver - ELECTRICAL LINE CONSTRUCTION ONLY	26.78	13.63	40.41
Light Truck Driver - ELECTRICAL LINE CONSTRUCTION ONLY	24.86	12.97	37.83

DANE COUNTY Page 2

TRADE OR OCCUPATION	HOURLY BASIC RATE OF PAY	HOURLY FRINGE BENEFITS	TOTAL
	\$	\$	\$
Groundman - ELECTRICAL LINE CONSTRUCTION ONLY	21.75	12.70	34.45
TRUCK DRIVERS			
Single Axle or Two Axle	34.22	19.90	54.12
Three or More Axle	24.52	17.77	42.29
Future Increase(s): Add \$1.30/hr on 6/1/2014. Premium Pay: DOT PREMIUM: Pay two times the hourly basic rate of Independence Day, Labor Day, Thanksgiving Day & Christmas Day.		ar's Day, Memor	ial Day,
Articulated, Euclid, Dumptor, Off Road Material Hauler Future Increase(s): Add \$1.75/hr on 6/1/14); Add \$1.25/hr on 6/1/15) 6/1/17.	29.27 ; Add \$1.30/hr on 6	20.40 /1/16); Add \$1.2	49.67 5/hr on
Premium Pay: DOT PREMIUMS: 1) Pay two times the hourly basic rd Day, Independence Day, Labor Day, Thanksgiving Day & Christmas See DOT'S website for details about the applicability of this night wo business/ civilrights/ laborwages/ pwc. htm.	Day. 2) Add \$1.50/hrk premium at: http	nr night work pre	mium.
Pavement Marking Vehicle	23.31	17.13	40.44
Shadow or Pilot Vehicle	34.22	19.90	54.12
Truck Mechanic	23.31	17.13	40.44
LABORERS			
General Laborer Future Increase(s): Add \$1.60/hr on 6/1/2014. Premium Pay: Add \$.10/hr for topman, air tool operator, vibrator or ta operated), chain saw operator and demolition burning torch laborer; and luteman), formsetter (curb, sidewalk and pavement) and strike of powderman; Add \$.25/hr for bottomman; Add \$.35/hr for line and grad DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, Independence Day, Labor Day, Thanksgiving Day & Christmas Day, involving temporary traffic control setup, for lane and shoulder closur conditions is necessary as required by the project provisions (includit such time period).	Add \$.15/hr for bitu off man; Add \$.20/hr ide specialist; Add \$ New Year's Day, M 2) Add \$1.25/hr for res, when work und	minous worker ( for blaster and 5.45/hr for pipela lemorial Day, work on projects ler artificial illum	yer. / s ination
Asbestos Abatement Worker	24.36	14.44	38.80
Landscaper	29.32	14.63	43.95
Future Increase(s): Add \$1.60/hr on 6/1/14. Premium Pay: DOT PREMIUMS: 1) Pay two times the hourly basic red Day, Independence Day, Labor Day, Thanksgiving Day & Christmas involving temporary traffic control setup, for lane and shoulder closur conditions is necessary as required by the project provisions (includitions such time period).	Day. 2) Add \$1.25/hres, when work und	nr for work on pr ler artificial illum	ojects ination
Flagperson or Traffic Control Person	25.67	14.63	40.30
Future Increase(s): Add \$1.60/hr on 6/1/2014.  Premium Pay: DOT PREMIUMS: 1) Pay two times the hourly basic repay, Independence Day, Labor Day, Thanksgiving Day & Christmas Department of Transportation or responsible governing agency requiantificial illumination with traffic control and the work is completed after	Day. 2) Add \$1.25/hires that work be pe	nr when the Wise erformed at night	consin
Fiber Optic Laborer (Outside, Other Than Concrete Encased)	18.31	12.67	30.98
Railroad Track Laborer	23.46	3.30	26.76

	BENEFITS	TOTAL
<b>\$</b>	\$	\$
36.72 ): Add \$1.30/hr (	20.40 on 6/1/2016): Ac	57.12
on Sunday, New 2) Add \$1.50/h	Year's Day, Me r night work pre	morial mium.
•	,	
2) Add \$1.50/h	r night work pre	mium.
35.72	20.40	56.12
	on Sunday, New 2) Add \$1.30/hr of emium at: http:/ 36.22  or Sunday, New 2) Add \$1.50/hr emium at: http:/ 35.72	36.72 20.40  2); Add \$1.30/hr on 6/1/2016); Add \$1.50/hr night work preemium at: http://www.dot.wi.gd.  36.22 20.40  2); Add \$1.30/hr on 6/1/2016); Add \$1.30/hr night work preemium at: http://www.dot.wi.gd.  31.30/hr night work preemium at: http://www.dot.wi.gd.  32.72 20.40

TRADE OR OCCUPATION	HOURLY BASIC RATE OF PAY	HOURLY FRINGE BENEFITS	TOTAL
	\$	\$	\$
& A- Frames. Future Increase(s): Add \$1.75/hr on 6/1/2014); Add \$1.25/hr on 6/1/2 \$1.25/hr on 6/ 1/ 2017. Premium Pay: DOT PREMIUMS: 1) Pay two times the hourly basic range. Day, Independence Day, Labor Day, Thanksgiving Day & Christmas	ate on Sunday, Nev	v Year's Day, Me	emorial
See DOT'S website for details about the applicability of this night wo business/ civilrights/ laborwages/ pwc. htm.			
Belting, Burlap, Texturing Machine; Broom or Sweeper; Compactor (Self-Propelled or Tractor Mounted, Towed & Light Equipment); Concret Finishing Machine (Road Type); Environmental Burner; Farm or Industri Type Tractor; Fireman (Asphalt Plant, Pile Driver & Derrick NOT Perform Work on the Great Lakes); Forklift; Greaser; Hoist (Tugger, Automatic); Digger; Joint Sawer (Multiple Blade); Launch (NOT Performing Work on Great Lakes); Lift Slab Machine; Mechanical Float; Mulcher; Power Subgrader; Robotic Tool Carrier (With or Without Attachments); Roller (Rubber Tire, 5 Ton or Under); Self Propelled Chip Spreader; Shouldering Machine; Skid Steer Loader (With or Without Attachments); Telehandler Tining or Curing Machine.  Future Increase(s): Add \$1.75/hr on 6/1/2014); Add \$1.25/hr on 6/1/2 \$1.25/hr on 6/1/2017.  Premium Pay: DOT PREMIUMS: 1) Pay two times the hourly basic report Day, Independence Day, Labor Day, Thanksgiving Day & Christmas See DOT'S website for details about the applicability of this night wo business/ civilrights/ laborwages/ pwc. htm.	al ning Jeep the ng :; 2015); Add \$1.30/hr ate on Sunday, New Day. 2) Add \$1.50/h	v Year's Day, Me nr night work pre	emorial emium.
Air Compressor (&/or 400 CFM or Over); Air, Electric or Hydraulic Jackir System; Augers (Vertical & Horizontal); Automatic Belt Conveyor & Surg Bin; Boiler (Temporary Heat); Concrete Proportioning Plant; Crusher, Screening or Wash Plant; Generator (&/or 150 KW or Over); Heaters (Mechanical); High Pressure Utility Locating Machine (Daylighting Mach Mudjack; Oiler; Prestress Machine; Pug Mill; Pump (3 Inch or Over) or V Points; Rock, Stone Breaker; Screed (Milling Machine); Stump Chipper; Tank Car Heaters; Vibratory Hammer or Extractor, Power Pack.  Future Increase(s): Add \$1.75/hr on 6/1/2014); Add \$1.25/hr on 6/1/2 \$1.25/hr on 6/1/2017.  Premium Pay: DOT PREMIUMS: 1) Pay two times the hourly basic raday, Independence Day, Labor Day, Thanksgiving Day & Christmas See DOT'S website for details about the applicability of this night wo business/ civilrights/ laborwages/ pwc. htm.	ine); Vell 2015); Add \$1.30/hr ate on Sunday, Nev Day. 2) Add \$1.50/hrk premium at: http	v Year's Day, Me nr night work pre	emorial emium.
Fiber Optic Cable Equipment.		16.65	43.34
	<i></i>		

# Wisconsin Department of Transportation PAGE: 1 DATE: 12/15/14 SCHEDULE OF ITEMS REVISED:

LINE	TTEM DESCRIPTION	APPROX.		UNIT PR	BID AM	
NO	DESCRIPTION   	QUANTITY   AND UNITS			DOLLARS	CT
SECTI(	ON 0001 CONTRACT ITEMS					
	204.0150 REMOVING CURB & GUTTER	   1,506.00  LF	  00 			
	204.0165 REMOVING  GUARDRAIL 	   210.00  LF	  00 			
	204.0180 REMOVING  DELINEATORS AND MARKERS 	   3.00  EACH	  00 		   	
0040	204.0245 REMOVING STORM  SEWER (SIZE) 01.  12-INCH	   13.00  LF	  00 			
	205.0100 EXCAVATION  COMMON 	   2,813.00  CY	  00 			
0060	213.0100 FINISHING  ROADWAY (PROJECT) 01.  1009-00-76	   1.00  EACH	  00 			
	305.0110 BASE AGGREGATE  DENSE 3/4-INCH 	   250.00  TON	00			
	305.0120 BASE AGGREGATE  DENSE 1 1/4-INCH 	   1,345.00  TON	  00 			
	312.0110 SELECT CRUSHED  MATERIAL 	   1,110.00  TON	000	<b></b>	<del>_</del>	
	405.0100 COLORING  CONCRETE RED 	   370.00	    00 		   	

# Wisconsin Department of Transportation PAGE: 2 DATE: 12/15/14 SCHEDULE OF ITEMS REVISED:

LINE NO		APPROX.	UNIT PRICE	BID AMOUNT
INO	DESCRIPTION	QUANTITY   AND UNITS	DOLLARS CTS	DOLLARS   CTS
	415.0080 CONCRETE  PAVEMENT 8-INCH	   1,655.00  SY	) ) 	       .
	416.0610 DRILLED TIE  BARS 	   600.00  EACH	 0     .	       .
	520.8000 CONCRETE  COLLARS FOR PIPE 	   1.00  EACH	       	       .
0140	524.0612 APRON ENDWALLS  FOR CULVERT PIPE  SALVAGED 12-INCH	   1.00  EACH	) )   .	       .
0150	601.0580 CONCRETE CURB &  GUTTER 4-INCH SLOPED  36-INCH TYPE R	   1,506.00  LF	o  	       .
	611.0430 RECONSTRUCTING  INLETS	   6.00  EACH	   	       .
	611.0652 INLET COVERS  TYPE T 	   6.00  EACH	   	     
	611.8120.S COVER PLATES TEMPORARY	   6.00  EACH	     .	       .
	614.0380 STEEL PLATE BEAM GUARD ENERGY ABSORBING TERMINAL TEMPORARY	1.00		
0200	614.2300 MGS GUARDRAIL 3 	   113.00  LF	     .	       .
0210	614.2500 MGS THRIE BEAM  TRANSITION	   39.00  LF	    0    .	     

# Wisconsin Department of Transportation PAGE: 3 DATE: 12/15/14 SCHEDULE OF ITEMS REVISED:

LINE	ITEM   DESCRIPTION	APPROX.		UNIT PR		BID AM	
NO	DESCRIPTION	QUANTITY AND UNITS	- !	DOLLARS		DOLLARS	
0220	614.2610 MGS GUARDRAIL  TERMINAL EAT 	   1.00  EACH	    00		•	   	
0230	619.1000 MOBILIZATION   	   1.00  EACH	    00		•	     	
0240	624.0100 WATER   	   50.00  MGAL	00			   	
	625.0500 SALVAGED  TOPSOIL 	   4,050.00  SY	00			   	
0260	627.0200 MULCHING   	2,800.00	    00			   	
0270	628.1504 SILT FENCE   	   1,350.00  LF	    00			   	
	628.1520 SILT FENCE  MAINTENANCE 	   1,350.00  LF	00			   	
	628.1905 MOBILIZATIONS  EROSION CONTROL 	   2.00  EACH	00			   	
	628.1910 MOBILIZATIONS  EMERGENCY EROSION  CONTROL	   2.00  EACH	00			   	
0310	628.2002 EROSION MAT  CLASS I TYPE A 	   4,050.00  SY	    00		•	   	
	628.7015 INLET  PROTECTION TYPE C 	   4.00  EACH	    00			     	

## Wisconsin Department of Transportation PAGE: 4 DATE: 12/15/14

REVISED: SCHEDULE OF ITEMS

LINE		APPROX.	UNIT PRICE	BID AMOUNT	
NO	DESCRIPTION	QUANTITY AND UNITS	l	DOLLARS CTS	
	628.7020 INLET  PROTECTION TYPE D	   2.000  EACH		     	
	628.7504 TEMPORARY DITCH  CHECKS 	   20.000  LF	     	   	
	628.7555 CULVERT PIPE  CHECKS 	   5.000  EACH	   		
0360	628.7560 TRACKING PADS   	   1.000  EACH		     .	
0370	629.0210 FERTILIZER TYPE  B 	   4.300  CWT			
	630.0120 SEEDING MIXTURE  NO. 20	   75.000  LB	   		
	630.0130 SEEDING MIXTURE  NO. 30 	   75.000  LB		     	
	630.0200 SEEDING  TEMPORARY 	   190.000  LB		     	
	633.0100 DELINEATOR  POSTS STEEL 	   2.000  EACH		   	
	633.0500 DELINEATOR  REFLECTORS	   4.000  EACH		     	
0430	633.5200 MARKERS CULVERT  END 	   1.000  EACH		   	

# Wisconsin Department of Transportation PAGE: 5 DATE: 12/15/14 SCHEDULE OF ITEMS REVISED:

LINE	ITEM   DESCRIPTION 	APPROX.	UNIT PF	UNIT PRICE		BID AMOUNT	
NO		AND UNITS	DOLLARS		DOLLARS		
	634.0614 POSTS WOOD  4X6-INCH X 14-FT 	2.00	       				
0450	637.2210 SIGNS TYPE II  REFLECTIVE H 	9.000		   			
	637.2230 SIGNS TYPE II  REFLECTIVE F 	   6.75  SF	    0  		   		
	638.2602 REMOVING SIGNS  TYPE II 	   2.00  EACH	0		   		
	638.3000 REMOVING SMALL  SIGN SUPPORTS 	   2.00  EACH	0		   		
	642.5001 FIELD OFFICE  TYPE B 	   1.00  EACH	    0  		   		
0500	643.0100 TRAFFIC CONTROL  (PROJECT) 01.  1009-00-76	   1.00  EACH	   0   		   		
	643.0300 TRAFFIC CONTROL  DRUMS 	2,644.00	       		   		
	643.0420 TRAFFIC CONTROL  BARRICADES TYPE III 	   24.00  DAY	    0  		   		
	643.0705 TRAFFIC CONTROL  WARNING LIGHTS TYPE A 	   24.00  DAY	    0  		   		
	643.0715 TRAFFIC CONTROL  WARNING LIGHTS TYPE C 	   346.00  DAY	       		     		

# Wisconsin Department of Transportation PAGE: 6 DATE: 12/15/14 SCHEDULE OF ITEMS REVISED:

LINE	ITEM   DESCRIPTION 	APPROX.		UNIT PRICE		BID AMOUNT	
NO			:	DOLLARS		DOLLARS	CTS
	643.0800 TRAFFIC CONTROL  ARROW BOARDS 	   6.000  DAY					
	643.0900 TRAFFIC CONTROL  SIGNS 	   395.000  DAY				   	
	643.0910 TRAFFIC CONTROL  COVERING SIGNS TYPE I 	    EACH	1.000    			   	
	643.0920 TRAFFIC CONTROL  COVERING SIGNS TYPE II 	    EACH	20.000  				
	643.1000 TRAFFIC CONTROL  SIGNS FIXED MESSAGE 	    SF	71.000  				
	643.1050 TRAFFIC CONTROL  SIGNS PCMS 	    DAY	92.000  				
0610	643.2000 TRAFFIC CONTROL  DETOUR (PROJECT) 01.  1009-00-76	    EACH	1.000			   	
	643.3000 TRAFFIC CONTROL  DETOUR SIGNS 		3,549.000    3			   	
	646.0106 PAVEMENT  MARKING EPOXY 4-INCH 	    LF	2,690.000  				
	650.4000 CONSTRUCTION  STAKING STORM SEWER 	    EACH	1.000		•	   	
	650.4500 CONSTRUCTION  STAKING SUBGRADE 	      LF	1,506.000			     	

# Wisconsin Department of Transportation PAGE: 7 DATE: 12/15/14 SCHEDULE OF ITEMS REVISED:

LINE	:	APPROX.	UNIT PRICE	BID AMOUNT	
NO	DESCRIPTION 	QUANTITY AND UNITS		DOLLARS CTS	
0660	650.7000 CONSTRUCTION  STAKING CONCRETE  PAVEMENT	   1,506.000  LF	)     .	       .	
0670	650.8500 CONSTRUCTION  STAKING ELECTRICAL  INSTALLATIONS (PROJECT)  01. 1009-00-76	  LUMP 	LUMP		
0680	650.9910 CONSTRUCTION  STAKING SUPPLEMENTAL  CONTROL (PROJECT) 01.  1009-00-76	  LUMP 	  LUMP 	     	
0690	650.9920 CONSTRUCTION  STAKING SLOPE STAKES 	   1,575.000  LF	) ) 	       .	
	652.0225 CONDUIT RIGID  NONMETALLIC SCHEDULE 40  2-INCH	   400.000  LF	0		
	653.0140 PULL BOXES  STEEL 24X42-INCH 	   3.000  EACH	0		
	653.0905 REMOVING PULL  BOXES 	   3.000  EACH	)   .		
	654.0105 CONCRETE BASES  TYPE 5 	   1.000  EACH	         .	       .	
	655.0515 ELECTRICAL WIRE  TRAFFIC SIGNALS 10 AWG 	   1,800.000  LF	       	       .	
0750	657.0255 TRANSFORMER  BASES BREAKAWAY 11  1/2-INCH BOLT CIRCLE	   1.000  EACH	       .	       .	

## Wisconsin Department of Transportation PAGE: 8 DATE: 12/15/14

SCHEDULE OF ITEMS REVISED:

LINE	1	APPROX. QUANTITY AND UNITS		UNIT PRICE		BID AMOUNT	
NO	DESCRIPTION			DOLLARS	   CTS	DOLLARS	CTS
0760	662.3030.S RAMP CLOSURE  GATE ARMS STOCKPILE  30-FT	      EACH	1.000		.		
0770	674.0300 REMOVE CABLE   	   1,8  LF	00.000		.		
0780	690.0250 SAWING CONCRETE	   1,5  LF	06.000		.		
	715.0415 INCENTIVE  STRENGTH CONCRETE  PAVEMENT	   5  DOL	00.000	1	.00000	5	00.00
	SPV.0060 SPECIAL 01.  SALVAGE AND REINSTALL  RAMP GATE ASSEMBLY	    EACH	1.000		.		
	SPV.0060 SPECIAL 02.  RAMP CLOSURE GATE ARMS  30-FT	    EACH	1.000		.		
	   SECTION 0001 TOTAL						
	     TOTAL BID		   				

### PLEASE ATTACH SCHEDULE OF ITEMS HERE