

# HIGHWAY WORK PROPOSAL

Wisconsin Department of Transportation  
DT1502 10/2010 s.66.29(7) Wis. Stats.

Proposal Number:

22

COUNTY	STATE PROJECT ID	FEDERAL PROJECT ID	PROJECT DESCRIPTION	HIGHWAY
Milwaukee	2025-01-72		West Capitol Drive (STH 190) 12 Connecting Highway Intersections	Various Highways

This proposal, submitted by the undersigned bidder to the Wisconsin Department of Transportation, is in accordance with the advertised request for proposals. The bidder is to furnish and deliver all materials, and to perform all work for the improvement of the designated project in the time specified, in accordance with the appended Proposal Requirements and Conditions.

Proposal Guaranty Required, \$ 40,000.00 Payable to: Wisconsin Department of Transportation	Attach Proposal Guaranty on back of this PAGE.
Bid Submittal Due Date: May 12, 2015 Time (Local Time): 9:00 AM	Firm Name, Address, City, State, Zip Code
Contract Completion Time September 16, 2015	<b>SAMPLE NOT FOR BIDDING PURPOSES</b>
Assigned Disadvantaged Business Enterprise Goal 0 %	This contract is exempt from federal oversight.

This certifies that the undersigned bidder, duly sworn, is an authorized representative of the firm named above; that the bidder has examined and carefully prepared the bid from the plans, Highway Work Proposal, and all addenda, and has checked the same in detail before submitting this proposal or bid; and that the bidder or agents, officer, or employees have not, either directly or indirectly, entered into any agreement, participated in any collusion, or otherwise taken any action in restraint of free competitive bidding in connection with this proposal bid.

**Do not sign, notarize, or submit this Highway Work Proposal when submitting an electronic bid on the Internet.**

Subscribed and sworn to before me this date \_\_\_\_\_

\_\_\_\_\_  
(Signature, Notary Public, State of Wisconsin)

\_\_\_\_\_  
(Print or Type Name, Notary Public, State Wisconsin)

\_\_\_\_\_  
(Date Commission Expires)

Notary Seal

\_\_\_\_\_  
(Bidder Signature)

\_\_\_\_\_  
(Print or Type Bidder Name)

\_\_\_\_\_  
(Bidder Title)

## For Department Use Only

Type of Work Removal and replacement of concrete bases, monotube poles and mast arms, conduit, control vaults.	
Notice of Award Dated	Date Guaranty Returned

**PLEASE ATTACH  
PROPOSAL GUARANTY HERE**

**Effective with November 2007 Letting**

**PROPOSAL REQUIREMENTS AND CONDITIONS**

The bidder, signing and submitting this proposal, agrees and declares as a condition thereof, to be bound by the following conditions and requirements.

If the bidder has a corporate relationship with the proposal design engineering company, the bidder declares that it did not obtain any facts, data, or other information related to this proposal from the design engineering company that was not available to all bidders.

The bidder declares that they have carefully examined the site of, and the proposal, plans, specifications and contract forms for the work contemplated, and it is assumed that the bidder has investigated and is satisfied as to the conditions to be encountered, as to the character, quality, and quantities of work to be performed and materials to be furnished, and as to the requirements of the specifications, special provisions and contract. It is mutually agreed that submission of a proposal shall be considered conclusive evidence that the bidder has made such examination.

The bidder submits herewith a proposal guaranty in proper form and amount payable to the party as designated in the advertisement inviting proposals, to be retained by and become the property of the owner of the work in the event the undersigned shall fail to execute the contract and contract bond and return the same to the office of the engineer within fourteen (14) days after having been notified in writing to do so; otherwise to be returned.

The bidder declares that they understand that the estimate of quantities in the attached schedule is approximate only and that the attached quantities may be greater or less in accordance with the specifications.

The bidder agrees to perform the said work, for and in consideration of the payment of the amount becoming due on account of work performed, according to the unit prices bid in the following schedule, and to accept such amounts in full payment of said work.

The bidder declares that all of the said work will be performed at their own proper cost and expense, that they will furnish all necessary materials, labor, tools, machinery, apparatus, and other means of construction in the manner provided in the applicable specifications and the approved plans for the work together with all standard and special designs that may be designed on such plans, and the special provisions in the contract of which this proposal will become a part, if and when accepted. The bidder further agrees that the applicable specifications and all plans and working drawings are made a part hereof, as fully and completely as if attached hereto.

The bidder, if awarded the contract, agrees to begin the work not later than ten (10) days after the date of written notification from the engineer to do so, unless otherwise stipulated in the special provisions.

The bidder declares that if they are awarded the contract, they will execute the contract agreement and begin and complete the work within the time named herein, and they will file a good and sufficient surety bond for the amount of the contract for performance and also for the full amount of the contract for payment.

The bidder, if awarded the contract, shall pay all claims as required by Section 779.14, Statutes of Wisconsin, and shall be subject to and discharge all liabilities for injuries pursuant to Chapter 102 of the Statutes of Wisconsin, and all acts amendatory thereto. They shall further be responsible for any damages to property or injury to persons occurring through their own negligence or that of their employees or agents, incident to the performance of work under this contract, pursuant to the Standard Specifications for Road and Bridge Construction applicable to this contract.

In connection with the performance of work under this contract, the contractor agrees to comply with all applicable state and federal statutes relating to non-discrimination in employment. No otherwise qualified person shall be excluded from employment or otherwise be subject to discrimination in employment in any manner on the basis of age, race, religion, color, gender, national origin or ancestry, disability, arrest or conviction record (in keeping with s.111.32), sexual orientation, marital status, membership in the military reserve, honesty testing, genetic testing, and outside use of lawful products. This provision shall include, but not be limited to the following: employment, upgrading, demotion or transfer; recruitment or recruitment advertising; layoff or termination; rates of pay or other forms of compensation, and selection for training, including apprenticeship. The contractor further agrees to ensure equal opportunity in employment to all applicants and employees and to take affirmative action to attain a representative workforce.

The contractor agrees to post notices and posters setting forth the provisions of the nondiscrimination clause, in a conspicuous and easily accessible place, available for employees and applicants for employment.

If a state public official (section 19.42, Stats.) or an organization in which a state public official holds at least a 10% interest is a party to this agreement, this contract is voidable by the state unless appropriate disclosure is made to the State of Wisconsin Ethics Board.

## BID PREPARATION

### **Preparing the Proposal Schedule of Items**

#### **A General**

- (1) Obtain bidding proposals as specified in **section 102** of the standard specifications prior to 11:45 AM of the last business day preceding the letting. Submit bidding proposals using one of the following methods:
  1. Electronic bid on the internet.
  2. Electronic bid on a printout with accompanying diskette or CD ROM.
  3. Paper bid under a waiver of the electronic submittal requirements.
- (2) Bids submitted on a printout with accompanying diskette or CD ROM or paper bids submitted under a waiver of the electronic submittal requirements govern over bids submitted on the internet.
- (3) The department will provide bidding information through the department's web site at <http://www.dot.wisconsin.gov/business/engrserv/bid-letting-information.htm>. The contractor is responsible for reviewing this web site for general notices as well as information regarding proposals in each letting. The department will also post special notices of all addenda to each proposal through this web site no later than 4:00 P.M. local time on the Thursday before the letting. Check the department's web site after 5:00 P.M. local time on the Thursday before the letting to ensure all addenda have been accounted for before preparing the bid. When bidding using methods 1 and 2 above, check the Bid Express™ on-line bidding exchange at <http://www.bidx.com/> after 5:00 P.M. local time on the Thursday before the letting to ensure that the latest schedule of items Expedite file (\*.ebs or \*.00x) is used to submit the final bid.
- (4) Interested parties can subscribe to the Bid Express™ on-line bidding exchange by following the instructions provided at the [www.bidx.com](http://www.bidx.com) web site or by contacting:

Info Tech Inc.  
5700 SW 34th Street, Suite 1235  
Gainesville, FL 32608-5371  
email: <mailto:customer.support@bidx.com>

- (5) The department will address equipment and process failures, if the bidder can demonstrate that those failures were beyond their control.
- (6) Contractors are responsible for checking on the issuance of addenda and for obtaining the addenda. Notice of issuance of addenda is posted on the department's web site at <http://www.dot.wisconsin.gov/business/engrserv/bid-letting-information.htm> or by calling the department at (608) 266-1631. Addenda can ONLY be obtained from the departments web site listed above or by picking up the addenda at the Bureau of Highway Construction, Room 601, 4802 Sheboygan Avenue, Madison, WI, during regular business hours.

#### **B Submitting Electronic Bids**

##### **B.1 On the Internet**

- (1) Do the following before submitting the bid:
  1. Have a properly executed annual bid bond on file with the department.
  2. Have a digital ID on file with and enabled by Info Tech Inc. Using this digital ID will constitute the bidder's signature for proper execution of the bidding proposal.
- (2) In lieu of preparing, delivering, and submitting the proposal as specified in **102.6** and **102.9** of the standard specifications, submit the proposal on the internet as follows:

1. Download the latest schedule of items reflecting all addenda from the Bid Express™ web site.
  2. Use Expedite™ software to enter a unit price for every item in the schedule of items.
  3. Submit the bid according to the requirements of Expedite™ software and the Bid Express™ web site. Do not submit a bid on a printout with accompanying diskette or CD ROM or a paper bid. If the bidder does submit a bid on a printout with accompanying diskette or a paper bid in addition to the internet submittal, the department will disregard the internet bid.
  4. Submit the bid before the hour and date the Notice to Contractors designates.
  5. Do not sign, notarize, and return the bidding proposal described in 102.2 of the standard specifications.
- (3) The department will not consider the bid accepted until the hour and date the Notice to Contractors designates.

## **B.2 On a Printout with Accompanying Diskette or CD ROM**

- (1) Download the latest schedule of items from the Wisconsin pages of the Bid Express™ web site reflecting the latest addenda posted on the department's web site at <http://www.dot.wisconsin.gov/business/engrserv/bid-letting-information.htm>. Use Expedite™ software to prepare and print the schedule of items. Provide a valid amount for all price fields. Follow instructions and review the help screens provided on the Bid Express™ web site to assure that the schedule of items is prepared properly.
- (2) Staple an 8 1/2 by 11 inch printout of the Expedite™ generated schedule of items to the other proposal documents submitted to the department as a part of the bidder's sealed bid. As a separate submittal not in the sealed bid envelop but due at the same time and place as the sealed bid, also provide the Expedite™ generated schedule of items on a 3 1/2 inch computer diskette or CD ROM. Label each diskette or CD ROM with the bidder's name, the 4 character department-assigned bidder identification code from the top of the bidding proposal, and a list of the proposal numbers included on that diskette or CD ROM as indicated in the following example:

**Bidder Name**

**BN00**

**Proposals: 1, 12, 14, & 22**

- (3) If bidding on more than one proposal in the letting, the bidder may include all proposals for that letting on one diskette or CD ROM. Include only submitted proposals with no incomplete or other files on the diskette or CD ROM.
- (4) The bidder-submitted printout of the Expedite™ generated schedule of items is the governing contract document and must conform to the requirements of section 102 of the standard specifications. If a printout needs to be altered, cross out the printed information with ink or typewriter and enter the new information and initial it in ink. If there is a discrepancy between the printout and the diskette or CD ROM, the department will analyze the bid using the printout information.
- (5) In addition to the reasons specified in section 102 of the standard specifications, proposals are irregular and the department may reject them for one or more of the following:
  1. The check code printed on the bottom of the printout of the Expedite™ generated schedule of items is not the same on each page.
  2. The check code printed on the printout of the Expedite™ generated schedule of items is not the same as the check code for that proposal provided on the diskette or CD ROM.

3. The diskette or CD ROM is not submitted at the time and place the department designates.

### **C Waiver of Electronic Submittal**

- (1) The bidder may request a waiver of the electronic submittal requirements. Submit a written request for a waiver in lieu of bids submitted on the internet or on a printout with accompanying diskette or CD ROM. Use the waiver that was included with the paper bid document sent to the bidder or type up a waiver on the bidder's letterhead. The department will waive the electronic submittal requirements for a bidding entity (individual, partnership, joint venture, corporation, or limited liability company) for up to 4 individual proposals in a calendar year. The department may allow additional waivers for equipment malfunctions.
- (2) Submit a schedule of items on paper conforming to [section 102](#) of the standard specifications. The department charges the bidder a \$75 administrative fee per proposal, payable at the time and place the department designates for receiving bids, to cover the costs of data entry. The department will accept a check or money order payable to: "Wisconsin, Dept. of Transportation."
- (3) In addition to the reasons specified in [section 102](#) of the standard specifications, proposals are irregular and the department may reject them for one or more of the following:
  1. The bidder fails to provide the written request for waiver of the electronic submittal requirements.
  2. The bidder fails to pay the \$75 administrative fee before the time the department designates for the opening of bids unless the bidder requests on the waiver that they be billed for the \$75.
  3. The bidder exceeds 4 waivers of electronic submittal requirements within a calendar year.
- (4) In addition to the reasons specified in [section 102](#) of the standard specifications, the department may refuse to issue bidding proposals for future contracts to a bidding entity that owes the department administrative fees for a waiver of electronic submittal requirements.





# PROPOSAL BID BOND

DT1303 1/2006

Wisconsin Department of Transportation

Proposal Number	Project Number	Letting Date
Name of Principal		
Name of Surety	State in Which Surety is Organized	

We, the above-named Principal and the above-named Surety, are held and firmly bound unto the State of Wisconsin in the sum equal to the Proposal Guaranty for the total bid submitted for the payment to be made; we jointly and severally bind ourselves, our heirs, executors, administrators, successors and assigns. The condition of this obligation is that the Principal has submitted a bid proposal to the State of Wisconsin acting through the Department of Transportation for the improvement designated by the Proposal Number and Letting Date indicated above.

If the Principal is awarded the contract and, within the time and manner required by law after the prescribed forms are presented for signature, enters into a written contract in accordance with the bid, and files the bond with the Department of Transportation to guarantee faithful performance and payment for labor and materials, as required by law, or if the Department of Transportation shall reject all bids for the work described, then this obligation shall be null and void; otherwise, it shall be and remain in full force and effect. In the event of failure of the Principal to enter into the contract or give the specified bond, the Principal shall pay to the Department of Transportation **within 10 business days of demand** a total equal to the Proposal Guaranty as liquidated damages; the liability of the Surety continues for the full amount of the obligation as stated until the obligation is paid in full.

The Surety, for value received, agrees that the obligations of it and its bond shall not be impaired or affected by any extension of time within which the Department of Transportation may accept the bid; and the Surety does waive notice of any such extension.

IN WITNESS, the Principal and Surety have agreed and have signed by their proper officers and have caused their corporate seals to be affixed this date: **(DATE MUST BE ENTERED)**

## PRINCIPAL

\_\_\_\_\_  
(Company Name) **(Affix Corporate Seal)**

\_\_\_\_\_  
(Signature and Title)

\_\_\_\_\_  
(Company Name)

\_\_\_\_\_  
(Signature and Title)

\_\_\_\_\_  
(Company Name)

\_\_\_\_\_  
(Signature and Title)

\_\_\_\_\_  
(Company Name)

\_\_\_\_\_  
(Signature and Title)

## NOTARY FOR PRINCIPAL

\_\_\_\_\_  
(Date)

State of Wisconsin )  
 ) ss.  
\_\_\_\_\_ County )

On the above date, this instrument was acknowledged before me by the named person(s).

\_\_\_\_\_  
(Signature, Notary Public, State of Wisconsin)

\_\_\_\_\_  
(Print or Type Name, Notary Public, State of Wisconsin)

\_\_\_\_\_  
(Date Commission Expires)

**Notary Seal**

\_\_\_\_\_  
(Name of Surety) **(Affix Seal)**

\_\_\_\_\_  
(Signature of Attorney-in-Fact)

## NOTARY FOR SURETY

\_\_\_\_\_  
(Date)

State of Wisconsin )  
 ) ss.  
\_\_\_\_\_ County )

On the above date, this instrument was acknowledged before me by the named person(s).

\_\_\_\_\_  
(Signature, Notary Public, State of Wisconsin)

\_\_\_\_\_  
(Print or Type Name, Notary Public, State of Wisconsin)

\_\_\_\_\_  
(Date Commission Expires)

**Notary Seal**

**IMPORTANT: A certified copy of Power of Attorney of the signatory agent must be attached to the bid bond.**



# CERTIFICATE OF ANNUAL BID BOND

DT1305 8/2003

Wisconsin Department of Transportation

Time Period Valid (From/To)	
Name of Surety	
Name of Contractor	
Certificate Holder	Wisconsin Department of Transportation

This is to certify that an annual bid bond issued by the above-named Surety is currently on file with the Wisconsin Department of Transportation.

This certificate is issued as a matter of information and conveys no rights upon the certificate holder and does not amend, extend or alter the coverage of the annual bid bond.

**Cancellation:** Should the above policy be cancelled before the expiration date, the issuing surety will give thirty (30) days written notice to the certificate holder indicated above.

\_\_\_\_\_  
(Signature of Authorized Contractor Representative)

\_\_\_\_\_  
(Date)



## March 2010

## LIST OF SUBCONTRACTORS

Section 66.0901(7), Wisconsin Statutes, provides that as a part of the proposal, the bidder also shall submit a list of the subcontractors the bidder proposes to contract with and the class of work to be performed by each. In order to qualify for inclusion in the bidder's list a subcontractor shall first submit a bid in writing, to the general contractor at least 48 hours prior to the time of the bid closing. The list may not be added to or altered without the written consent of the municipality. A proposal of a bidder is not invalid if any subcontractor and the class of work to be performed by the subcontractor has been omitted from a proposal; the omission shall be considered inadvertent or the bidder will perform the work personally.

No subcontract, whether listed herein or later proposed, may be entered into without the written consent of the Engineer as provided in Subsection 108.1 of the Standard Specifications.

[illegible]

**DECEMBER 2000**

**CERTIFICATION REGARDING DEBARMENT, SUSPENSION, AND OTHER  
RESPONSIBILITY MATTERS - PRIMARY COVERED TRANSACTIONS**

Instructions for Certification

1. By signing and submitting this proposal, the prospective contractor is providing the certification set out below.
2. The inability of a person to provide the certification required below will not necessarily result in denial of participation in this covered transaction. The prospective contractor shall submit an explanation of why it cannot provide the certification set out below. The certification or explanation will be considered in connection with the department or agency's determination whether to enter into this transaction. However, failure of the prospective contractor to furnish a certification or an explanation shall disqualify such person from participation in this transaction.
3. The certification in this clause is a material representation of fact upon which reliance was placed when the department determined to enter into this transaction. If it is later determined that the contractor knowingly rendered an erroneous certification in addition to other remedies available to the Federal Government the department may terminate this transaction for cause or default.
4. The prospective contractor shall provide immediate written notice to the department to whom this proposal is submitted if at any time the prospective contractor learns that its certification was erroneous when submitted or has become erroneous by reason of changed circumstances.
5. The terms "covered transaction," "debarred," "suspended," "ineligible," "lower tier covered transaction," "participant," "person," "primary covered transaction," "principal," "proposal," and "voluntarily excluded," as used in this clause, have the meanings set out in the Definitions and Coverage sections of the rules implementing Executive Order 12549. You may contact the department to which this proposal is being submitted for assistance in obtaining a copy of those regulations.
6. The prospective contractor agrees by submitting this proposal that, should this contract be entered into, it shall not knowingly enter into any lower tier covered transaction with a person who is debarred, suspended, declared ineligible, or voluntarily excluded from participation in this covered transaction, unless authorized by the department entering into this transaction.
7. The prospective contractor further agrees by submitting this proposal that it will include the clause titled "Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion-Lower Tier Covered Transaction," which is included as an addendum to PR-1273 - "Required Contract Provisions Federal Aid Construction Contracts," without

modification, in all lower tier covered transactions and in all solicitations for lower tier covered transactions.

8. The contractor may rely upon a certification of a prospective subcontractor/materials supplier that it is not debarred, suspended, ineligible, or voluntarily excluded from the covered transaction, unless it knows that the certification is erroneous. A contractor may decide the method and frequency by which it determines the eligibility of its principals. Each contractor may, but is not required to, check the Disapproval List (telephone # 608/266/1631).
9. Nothing contained in the foregoing shall be construed to require establishment of a system of records in order to render in good faith the certification required by this clause. The knowledge and information of a contractor is not required to exceed that which is normally possessed by a prudent person in the ordinary course of business dealings.
10. Except for transactions authorized under paragraph 6 of these instructions, if a contractor in a covered transaction knowingly enters into a lower tier covered transaction with a person who is suspended, debarred, ineligible or voluntarily excluded from participation in this transaction, in addition to other remedies available to the Federal Government, the department may terminate this transaction for cause or default.

Certification Regarding Debarment, Suspension, and Other Responsibility Matters - Primary Covered Transactions

- (1) The prospective contractor certifies to the best of its knowledge and belief, that it and its principals:
  - (a) Are not presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from covered transactions by any Federal department or agency;
  - (b) Have not within a three-year period preceding this proposal been convicted of or had a civil judgment rendered against them for commission of fraud or a criminal offense in connection with obtaining, attempting to obtain, or performing a public (Federal, State or local) transaction or contract under a public transaction; violation of Federal or State antitrust statutes or commission of embezzlement, theft, forgery, bribery, falsification or destruction of records, making false statements or receiving stolen property;
  - (c) Are not presently indicted for or otherwise criminally or civilly charged by a governmental entity (Federal, State or local) with commission of any of the offense enumerated in paragraph (1)(b) of this certification; and
  - (d) Have not within a three-year period preceding this proposal had one or more public transactions (Federal, State or local) terminated for cause or default.
- (2) Where the prospective contractor is unable to certify to any of the statements in this certification, such prospective contractor shall attach an explanation to this proposal.

## Special Provisions

### Table of Contents

Article	Description	Page #
1.	General.....	2
2.	Scope of Work. ....	2
3.	Prosecution and Progress. ....	2
4.	Holiday Work Restrictions. ....	3
5.	Utilities.....	4
6.	Notice to Contractor – Survey. ....	6
7.	Tree and Planting Area Protection.....	7
8.	Erosion Control.....	7
9.	Excavation, Hauling, and Disposal of Petroleum Contaminated Soil, Item 205.0501.S. ....	8
10.	Construction Staking Electrical Installations 2025-01-72, Item 650.8500.01.....	12
11.	Conduit Rigid Nonmetallic Schedule 40 2 1/2-Inch, Item 652.0225; Conduit Rigid Nonmetallic Schedule 40 3-Inch, Item 652.0235. ....	13
12.	Concrete Bases Type 10, Item 654.0110; Concrete Base Type 13, Item 654.0113. ....	13
13.	Concrete Base Type 10 Special, Item SPV.0060.01.....	13
14.	Monotube Arms 20-FT, Item SPV.0060.02; 25-FT, Item SPV.0060.03; 30-FT, Item SPV.0060.04; 35-FT, Item SPV.0060.05; 40-FT, Item SPV.0060.06; 45-FT, Item SPV.0060.07; 50-FT, Item SPV.0060.08; 55-FT, Item SPV.0060.09. ....	14
15.	Poles Type 9, Item SPV.0060.10; Type 10, Item SPV.0060.11. ....	16
16.	Poles Type 12, Item SPV.0060.12; Type 12 Special, Item SPV.0060.13; Type 13 Special, Item SPV.0060.14. ....	18
17.	Rectangular Polymer Concrete Vault 13-Inch x 24-Inch x 18-Inch, Item SPV.0060.15 ; 17-Inch x 30-Inch x 18-Inch, Item SPV.0060.16. ....	19
18.	Utility Line Opening (ULO), Item SPV.0060.17. ....	21
19.	Colored Concrete Sidewalk 5-Inch, Item SPV.0165.01. ....	23



## **SPECIAL PROVISIONS**

### **1. General.**

Perform the work under this construction contract for Project 2025-01-72 West Capitol Drive (STH 190) 12 Connecting Highway Intersections, Various Highways, located in the City of Milwaukee, Milwaukee County, Wisconsin as the plans show and execute the work as specified in the State of Wisconsin, Department of Transportation, Standard Specifications for Highway and Structure Construction, 2015 Edition, as published by the department, and these special provisions.

If all or a portion of the plans and special provisions are developed in the SI metric system and the schedule of prices is developed in the US standard measure system, the department will pay for the work as bid in the US standard system.

100-005 (20141107)

### **2. Scope of Work.**

The work under this contract shall consist of removal and replacement of concrete bases, monotube poles and mast arms, conduit, control vaults and all incidental items necessary to complete the work as shown on the plans and included in the proposal and contract.

104-005 (20090901)

### **3. Prosecution and Progress.**

Begin work within ten calendar days after the engineer issues a written notice to do so.

Construct the project as to maintain a minimum of one lane of traffic in each direction as shown on the traffic control plan.

Maintain two lanes of traffic during the rush hour periods as indicated below:

- Eastbound West Capitol Drive between the morning rush hours of 6:30 AM and 8:30 AM, Monday through Friday.
- Westbound West Capitol Drive between the evening rush hours of 3:00 PM and 6:00 PM, Monday through Friday.

Provide the time frame for construction of all work on the project prior to the completion date. The time frame shall be provided to the engineer in writing within a month after executing the contract but at least 14 calendar days before the preconstruction meeting. Assure that the time frame is consistent with the contract completion time. Upon approval, the engineer will issue the notice to proceed within 10 calendar days before the beginning of the approved time frame.

To revise the time frame, submit a written request to the engineer at least two weeks before the beginning of the intended time frame. The engineer will approve or deny that request based on the conditions cited in the request and its effect on the department's scheduled resources.

No motorized construction equipment is allowed to operate between the hours of 9:00 PM and 7:00 AM without prior consent from the construction engineer.

If the contractor desires to work on Saturday, Sunday, or nationally recognized legal holidays, he must obtain approval from the engineer at least 24 hours in advance. If scheduling changes after approval has been obtained, notify the engineer as soon as possible, but not later than 3:00 PM of the prior day.

No extra cost will be allowed for "cold weather protection" as addressed in standard spec 415.3.13.

Except where noted, keep all intersections accessible at all times. Include any costs associated with staging operations at intersections that are to remain accessible at all times in the unit bid price for Traffic Control (Project).

Maintain or provide pedestrian access to adjacent properties, businesses, and at bus stops where necessary, as directed by the engineer. Provide adequate temporary sidewalk and bridging where the median or walk is impacted by construction activities or as directed by the engineer. The cost of bridging shall be included in the unit bid price for Concrete Sidewalk 5-Inch.

*Supplement standard spec 107.18 with the following:*

When performing the roadway cleaning operation, use equipment having vacuum or water-spray mechanisms to eliminate the dispersion of dust. If vacuum equipment is employed, it must have suitable, self-contained particulate collectors to prevent discharge from collection bin into the atmosphere.

Store drums, buckets and other containers related to construction operations in a secure area to prevent vandalism, spills, and unwanted dumping. If an abandoned container is discovered on the project site, notify the WDNR at (800) 943-0003.

#### **4. Holiday Work Restrictions.**

Do not perform work on, nor haul materials of any kind along or across any portion of the highway carrying West Capitol Drive (STH 190) traffic, and entirely clear the traveled way and shoulders of such portions of the highway of equipment, barricades, signs, lights, and any other material that might impede the free flow of traffic during the following holiday periods:

- From noon Friday, July 3, 2015 to 6:00 AM Monday, July 6, 2015 for Independence Day;
- From noon Friday, September 4, 2015 to 6:00 AM Tuesday, September 8, 2015 for Labor Day.

107-005 (20050502)

## **5. Utilities.**

This contract does not come under the provision of Administrative Rule Trans 220.

107-065 (20080501)

The City of Milwaukee has notified the department that the following operations necessary for the construction of new facilities and/or adjustment of existing facilities will be coordinated with the contractor's construction operations by each representative utility unless otherwise noted. Coordinate construction activities with a call to Digger's Hotline or a direct call to the utilities that have facilities in the area as required by statutes. Use caution to ensure the integrity of underground facilities and maintain code clearances from overhead facilities at all times.

Note: Bidders are advised to contact each utility company listed in the plans prior to preparing their bid to obtain current information on the status of each utility company's work required in association with the project. Existing trees, street light poles, hydrants and utility poles are to remain in place during construction unless noted on plans. Conduct an on-site visit prior to bidding to determine any special measures required for proper clearance between the trees, hydrants, poles, other utilities and any other physical structures and the construction equipment. During construction operations, keep all manholes accessible to utility companies for emergencies.

### **A City of Milwaukee**

#### **1. Water**

Milwaukee Water Works has large size water mains and other facilities within the limits of the project. Take extreme caution when placing the monotube bases near these water mains. No Water service boxes work is anticipated as part of this project. Contact Mr. Musa Abu-Khader of the City of Milwaukee at (414) 286-2432 for concerns or questions.

#### **2. Sewer**

The City of Milwaukee has storm sewer facilities within the limits of the project. No manholes and inlets work is anticipated as part of this project. Take extreme caution when placing the monotube bases near sewer mains. Contact Mr. Musa Abu-Khader of the City of Milwaukee at (414) 286-2432 for concerns or questions.

#### **3. Street Lighting**

The City of Milwaukee has street lighting facilities within the limits of the project. No work is anticipated on the street lighting facilities. Contact Mr. Denis Kozelek of the City of Milwaukee at (414) 286-3252 for concerns or questions..

#### **4. Underground Conduits and Communications (TES)**

The City of Milwaukee has communications cables in underground conduit located within the project limits. These cables will be kept in operation during construction. Take precaution when working near these facilities to prevent damage. Contact Ms. Karen Rogney, [Karen.rogney@milwaukee.gov](mailto:Karen.rogney@milwaukee.gov) of the City of Milwaukee at (414) 286-3243 for concerns or questions.

#### **5. Traffic Signals and Signs**

City of Milwaukee Traffic Signals and Signs has facilities located within the limits of the project. Specified PVC Conduits, vaults, bases, and monotube mast arm structures are to be installed by contractor as part of this project. Prior to construction, any needed pole, signal standard, and control cabinet relocations; and temporary traffic signal work will be completed by City of Milwaukee forces. Coordinate all traffic control staging with the City of Milwaukee.

In coordination with contractor installed facilities, cable and signal hardware will be installed, modified, upgraded, and replaced by City of Milwaukee forces as part of a Local Force Account (LFA) contract that is related to the project.

Provide a 10-working day advance notice to Mr. Al Nichols of the City of Milwaukee's Traffic Signal Field Operations at (414) 286-3687 office or (414) 708-5148 mobile, to coordinate the installation of traffic signal materials. Coordinate all Traffic Signal Operation with Mr. Joseph Blakeman of the City of Milwaukee's Traffic Engineering at (414) 286-8070 as well as any city traffic signal concerns.

#### **6. Forestry**

City of Milwaukee Forestry has irrigation system within the limits of the project. Forestry forces will shut off the water and replace impacted PVC pipes and connections of the sprinkler systems at the following median locations in coordination with construction operations:

- N Sherman Boulevard and W Capitol Drive – northerly and southerly medians.
- W Roosevelt Road and W Capitol Drive – westerly median on W Roosevelt Road
- N 34<sup>th</sup> Street and W Capitol Drive – westerly median
- M 20<sup>th</sup> Street and W Capitol Drive – westerly median
- N Green Bay Avenue and W Capitol Drive – northerly median
- N Dr. Martin Luther King Drive and W Capitol Drive – easterly median

Contact Mr. James Kringer of the City of Milwaukee at (414) 708-2428 for coordination of this work.

#### **B. WE Energies - Gas**

WE Energies – Gas has facilities within the limits of the project. No work and or adjustments of We Energies – Gas facilities are anticipated in conjunction with this project. Contact Mr. Mitch Braverman of the WE Energies – at (414) 540 5709 office or (414) 507-8127 cell, for coordination of this work.

### **C. WE Energies – Electric**

WE Energies - Electric has underground and overhead facilities within the limits of the project. No work and or adjustments of We Energies - Electric facilities are anticipated in conjunction with this project.

Contact Mr. Leonard Wilson of the WE Energies – at (414) 944 5690, [leonard.wilson@we-energies.com](mailto:leonard.wilson@we-energies.com) for concerns or questions.

### **D. AT&T (TCG) Wisconsin**

AT&T (Wisconsin local) has underground facilities consisting of conduits and vaults throughout the project limits. No work and or adjustments of AT&T facilities are anticipated in conjunction with this project.

Contact Mr. Jay Bulanel at (262) 896-7669, [Jb5175@att.com](mailto:Jb5175@att.com) for concerns or questions.

### **E. Time Warner Cable (TWC)**

TWC has overhead cables located throughout the project limits. No work and or adjustments of TWC facilities are anticipated in conjunction with this project.

Contact Mr. Steve Cramer at (414) 277-4045 or (414) 688-2385 cell, for concerns or questions.

### **F. American Transmission Company (ATC)**

ATC has underground high voltage facilities crossing W Capitol Drive at the east side of North 20<sup>th</sup> Street. No conflicts are anticipated during construction of this project at this location.

Contact Kim Hackelberg of the ATC at (920) 338-6556 or 920-680-6322 cell, for concerns or questions.

### **G. Milwaukee Metropolitan Sewerage District (MMSD)**

MMSD has numerous facilities located on West Capitol Drive between N 35<sup>th</sup> Street and N 27<sup>th</sup> Street. No work and or adjustments of MMSD facilities are anticipated in conjunction with this project.

Contact Mr. Larry Anderson at (414) 225-2241, [landerson@mmsd.com](mailto:landerson@mmsd.com) for concerns or questions.

## **6. Notice to Contractor – Survey.**

Digital design file information/existing surface data, including design surface DTMs and/or coordinate system GPS information will not be available for this project.

## **7. Tree and Planting Area Protection.**

Remove one tree located at the south east corner of West Capitol Drive and North 7<sup>th</sup> Street.

### **A Sidewalk Construction**

Sidewalks are to be removed, and roots cut, by use of hand implements only, to be incidental to the cost of Removing Concrete Sidewalk.

### **General**

All cutting for the removal of sod and soil in order to establish a finished grade with 4 feet of existing trees must be done manually if necessary.

No construction equipment, cars trucks, materials shall be parked or stored on any median or tree borders on this project or adjacent roadways.

Root foundations must remain adequate to withstand heavy windstorms.

Root system of street trees shall not be cut for the installation of any type of cable by the contractor. Contact the City Forestry Division at 414-708-2428 for directional boring specifications.

Caution shall be used during the construction process to avoid damage to the roots, trunks, and branches of all street trees. Damage caused to any street tree or irrigation system will be repaired by the City of Milwaukee's Forestry Division and the costs of repair, rejuvenation, and/or value lost will be billed to the contractor or credited against the contract at the option of the city.

At locations where the contractor has not complied with the forestry special requirements stated in the special provisions above, and the maximum clearance was exceeded or a thin form was not used, a minimum penalty from the city of \$50.00 per location will be taken. The penalty will increase in proportion to the excess distance beyond clearance allowed. The penalty will be \$50.00 for each 2-inch increment or part thereof in excess of the initial clearance allowed. Any damage to the tree's structure totaling 15 percent of the trees value will be billed on a prorata basis. If, in the opinion of the City of Milwaukee's Forestry Division, the tree has been damaged to the point that it warrants removal, the penalty will be equal to \$100.00 per inch diameter of the tree. A field measurement will be taken to determine the tree size.

## **8. Erosion Control.**

Perform this work in accordance to the requirements of standard spec 107.20 and as hereinafter supplemented.

Take adequate precautions to install and maintain necessary erosion and sediment control during grading and construction operations at curbs and gutters, and at other locations determined by the engineer. Protect storm drain inlets and manholes, as determined by the

engineer, with a filter fabric meeting accepted design criteria, standards, and specifications. Maintain all erosion control measures until such time that the engineer determines the measures are no longer necessary.

Submit the Erosion Control Implementation Plan (ECIP) a minimum of 14 days prior to the preconstruction meeting for approval by the department and concurrence by the Wisconsin Department of Natural Resources (DNR). Contractor will not be allowed to start until written approval has been received from the department.

## **9. Excavation, Hauling, and Disposal of Petroleum Contaminated Soil, Item 205.0501.S.**

### **A Description**

#### **A.1 General**

This special provision describes excavating, loading, hauling, and disposing of petroleum contaminated soil at a DNR approved bioremediation facility. The closest DNR approved bioremediation facilities are:

Waste Management Orchard Ridge Landfill  
N96 W13503 County Line Road  
Menomonee Falls, WI 53051  
(262) 532-6200

Advanced Disposal Emerald Park Landfill  
W124 S10629 South 124<sup>th</sup> Street  
Muskego, WI 53150  
(414) 529-1360

Perform this work in accordance to standard spec 205 and with pertinent parts of Chapters NR 700-754 of the Wisconsin Administrative Code, as supplemented herein. Per NR 718.07, a solid waste collection and transportation service-operating license is required under NR 502.06 for each vehicle used to transport contaminated soil.

#### **A.2 Notice to the Contractor – Contaminated Soil and Groundwater Location**

The department completed testing for soil and groundwater contamination for locations within this project where excavation is required. Testing indicated that petroleum-contaminated soil and groundwater is present at the following location as shown on the plans:

1. Northwest corner of STH 190 (W. Capitol Dr.) and N. 35<sup>th</sup> St. at the proposed monotube mast arm traffic signal location at 10.0' south of right-of-way and 16.5' west of right-of-way, from approximately 0 to 16+ feet below ground surface. Soil and groundwater at this location is contaminated with petroleum. Approximately 40 cubic yards (approximately 68 tons at an estimated 1.7 tons per cubic yard) of contaminated soil will be excavated here for traffic light monotube installation. Groundwater at this

location has elevated concentrations of petroleum compounds and metals. See Section C below for management of water from dewatering activities.

Directly load contaminated soil into trucks that will transport the soil to a WDNR-licensed bioremediation facility.

If contaminated soils are encountered elsewhere on the project, terminate excavation activities in the area and notify the engineer.

### **A.3 Protection of Groundwater Monitoring Wells**

Active groundwater monitoring wells are present within the construction limits at the following locations as shown on the plans:

1. In the median on the north side of the intersection of W. Capitol Dr. and N. Sherman Blvd. near the proposed monotube location 15.0' north of right-of-way and 55.0' west of right-of-way.
2. In the median on the east side of the intersection of W. Capitol Dr. and N. Sherman Blvd. near the proposed monotube location 57.0' north of right-of-way and 16.0' east of right-of-way.

If groundwater monitoring wells are encountered elsewhere during construction, notify the engineer and protect the wells to maintain their integrity. If required by the environmental consultant, adjust wells that do not conflict with utilities, structures, curb and gutter, etc. to be flush with the final grade. For wells that conflict with the previously mentioned items, notify the environmental consultant, and coordinate with the environmental consultant, or for wells that require abandonment, the abandonment or adjustment of the wells by others. The environmental consultant will provide maps indicating the locations of all known monitoring wells, if requested by the contractor.

Coordinate with the environmental consultant to ensure that the environmental consultant is present to abandon and/or document the location of the groundwater monitoring well during excavation activities.

The excavation management plan for this project has been designed to minimize the offsite disposal of contaminated material. The excavation management plan, including these special provisions, has been developed in cooperation with the WDNR. The WDNR concurrence letter is on file at the Wisconsin Department of Transportation. For further information regarding previous investigation and remediation activities at this site contact:

Name:	Andrew Malsom, HAZMAT and Environmental Engineer
Address:	WisDOT SE region, 141 NW Barstow St., Waukesha WI 53187
Phone:	(262) 548-6705
Fax:	(262) 548-6891
E-mail:	<a href="mailto:Andrew.Malsom@dot.wi.gov">Andrew.Malsom@dot.wi.gov</a>



#### **A.4 Coordination**

Coordinate work under this contract with the environment consultant:

Consultant: TRC Environmental Corporation  
Address: 150 N. Patrick Blvd., Suite 180, Brookfield, WI 53045  
Contact: Bryan Bergmann, P.G.  
Phone: (262) 901-2126  
Fax: (262) 879-1220  
E-mail: [bbergmann@trcsolutions.com](mailto:bbergmann@trcsolutions.com)

The role of the environmental consultant will be limited to:

1. Determining the location and limits of contaminated soil to be excavated based on soil analytical results from previous investigations, visual observations, and field screening of soil that is excavated;
2. Identifying contaminated soils to be hauled to the bioremediation facility;
3. Documenting that activities associated with management of contaminated soil are in conformance with the contaminated soil management methods for this project as specified herein; and
4. Obtaining the necessary approvals for disposal of contaminated soil from the bioremediation facility.

Provide at least a 14-calendar day notice of the preconstruction conference date to the environmental consultant. At the preconstruction conference, provide a schedule for all excavation activities in the area of contamination to the environmental consultant. Also notify the environmental consultant at least three calendar days prior to commencement of excavation activities in the contaminated area.

Coordinate with the environmental consultant to ensure that the environmental consultant is present during excavation activities in the contaminated area. Perform excavation work in the contaminated area on a continuous basis until excavation work is completed.

Identify the DNR approved bioremediation facility that will be used for disposal of contaminated soils, and provide this information to the environmental consultant no later than 30 calendar days prior to commencement of excavation activities in the contaminated area or at the preconstruction conference, whichever comes first. The environmental consultant will be responsible for obtaining the necessary approvals for disposal of contaminated soils from the bioremediation facility. Do not transport contaminated soil offsite without prior approval from the environmental consultant.

## **A.5 Health and Safety Requirements**

*Supplement standard spec 107.1 with the following:*

During excavation activities, expect to encounter soil contaminated with gasoline, diesel fuel, fuel oil, or other petroleum related products. Site workers taking part in activities that will result in the reasonable probability of exposure to safety and health hazards associated with hazardous materials shall have completed health and safety training that meets the Occupational Safety and Health Administration (OSHA) requirements for Hazardous Waste Operations and Emergency Response (HAZWOPER), as provided in 29 CFR 1910.120.

Prepare a site-specific Health and Safety Plan, and develop, delineate and enforce the health and safety exclusion zones for each contaminated site location as required by 29 CFR 1910.120. Submit the site-specific health and safety plan and written documentation of up-to-date OSHA training to the engineer prior to the start of work.

## **B (Vacant)**

## **C Construction**

*Supplement standard spec 205.3 with the following:*

Control operations in the contaminated areas to minimize the quantity of contaminated soil excavated.

The environmental consultant will periodically evaluate soil excavated from the contaminated areas to determine if the soil will require offsite bioremediation. The environmental consultant will evaluate excavated soil based on field screening results, visual observations, and soil analytical results from previous environmental investigations. Assist the environmental consultant in collecting soil samples for evaluation using excavation equipment. The sampling frequency shall be a maximum of one sample for every 20 cubic yards excavated.

Directly load and haul soils designated by the environmental consultant for offsite bioremediation to the DNR approved bioremediation facility. Use loading and hauling practices that are appropriate to prevent any spills or releases of petroleum-contaminated soils or residues. Prior to transport, sufficiently dewater soils designated for off-site bioremediation so as not to contain free liquids.

Verify that the vehicles used to transport material are licensed for such activity in accordance to applicable state and federal regulations. Do not transport regulated solid waste off-site without obtaining the approval of the environmental consultant and engineer and notifying the disposal facility.

If dewatering is required in an area of known contamination, water generated from dewatering activities may contain petroleum VOCs and metals. Such water may, with approval of the Milwaukee Metropolitan Sewerage District (MMSD), be discharged to the sanitary sewer as follows:

- Meet all applicable requirements of the MMSD including the control of suspended solids. Perform all necessary monitoring to document compliance with MMSD's requirements. Furnish, install, operate, maintain, disassemble, and remove treatment equipment necessary to comply with MMSD's requirements.
- Ensure continuous dewatering and excavation safety at all times. Provide, operate, and maintain adequate pumping equipment and drainage and disposal facilities. Notify the engineer of any dewatering activities, and obtain any permits necessary to discharge water. Provide copies of such permits to the engineer. Meet any requirements and pay any costs for obtaining and complying with such permit use. Follow all applicable legislative statutes, judiciary decisions, and regulations of the State of Wisconsin.

Costs associated with excavation dewatering in the contaminated area are considered incidental to this pay item. The Wisconsin Department of Transportation will be the generator of regulated solid waste from this construction project.

#### **D Measurement**

The department will measure Excavation, Hauling, and Disposal of Petroleum Contaminated Soil in tons of contaminated soil accepted by the bioremediation facility as documented by weight tickets generated by the bioremediation facility.

#### **E Payment**

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
205.0501.S	Excavation, Hauling, and Disposal of Petroleum Contaminated Soil	Ton

Payment is full compensation for excavating, segregating, loading, hauling, and treatment via bioremediation of contaminated soil; obtaining solid waste collection and transportation service operating licenses; assisting in the collection soil samples for field evaluation; dewatering of soils prior to transport, if necessary; and for furnishing all labor, tools, equipment, and incidentals necessary to complete the work.

205-003 (20080902)

### **10. Construction Staking Electrical Installations 2025-01-72, Item 650.8500.01.**

The work under this item shall be performed in accordance to the requirements of standard spec 650, and as shown in the plans.

The traffic poles, bases and vaults are referenced from the right-of-way line to the center. See drawing details for any additional information.

**11. Conduit Rigid Nonmetallic Schedule 40 2 1/2-Inch, Item 652.0225; Conduit Rigid Nonmetallic Schedule 40 3-Inch, Item 652.0235.**

*Supplement standard spec 652, with the following:*

Locations of the conduits where they are required are identified in the plans. However, installation will require integration with existing field conditions. Appropriate adjustment on conduit locations may be made if the field conditions are such that the pipes cannot be installed at the specified locations. Any relocation of greater than 5 feet must be approved by the engineer.

Plan changes must be approved by the City of Milwaukee's electric services supervisor or traffic engineer. The primary contacts are Mr. Dennis Miller, Street Lighting Operations supervisor (414) 286-5942 office, (414) 708-4251 mobile; or Mr. Joseph Blakeman, traffic control engineer (414) 286-8070.

Provide three sets of as-built plans to City of Milwaukee electric services supervisor or engineer upon completion of conduit installation. The plan sets are incidental to the conduit installation, and no extra payment will be made by the department.

**12. Concrete Bases Type 10, Item 654.0110; Concrete Base Type 13, Item 654.0113.**

Contact the City of Milwaukee sewer engineering five working days prior to excavating any concrete bases at (414) 286-2467 to confirm lateral clearance with sewer facilities.

*Modify standard spec 654.2 as follows:*

Furnish templates, anchor rods, nuts, and washers for installation as shown on the plans.

*Add the following to standard spec 654.3:*

Contact City of Milwaukee Sewer Engineering five working days prior to excavation for any concrete bases. Contact Bob Brooks at (414) 286-3241 or Nancy Alvarado at (414) 286-2013 to confirm lateral clearance with sewer facilities.

**13. Concrete Base Type 10 Special, Item SPV.0060.01.**

**A Description**

This special provision describes constructing Concrete Base Type 10 Special with a 36-inch diameter for monotube mast arm structures. All work shall conform with standard spec 654 with modifications as shown on the plans, and as hereinafter provided.

**B Materials**

*Modify standard spec 654.2 as follows:*

Furnish templates, anchor rods, nuts, and washers for installation as shown on the plans.

**C Construction**

Construction of this item shall conform with standard spec 654.

The contractor shall contact City of Milwaukee Sewer Engineering five working days prior to excavation for any concrete bases. Contact Bob Brooks at (414) 286-3241 or Nancy Alvarado at (414) 286-2013 to confirm lateral clearance with sewer facilities.

**D Measurement**

The department will measure Concrete Base Type 10 Special as each individual concrete base, acceptably completed.

**E Payment**

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0060.01	Concrete Base Type 10 Special	Each

Payment is full compensation for providing all labor and materials, including hardware and fittings necessary for constructing concrete bases.

- 14. Monotube Arms 20-FT, Item SPV.0060.02; 25-FT, Item SPV.0060.03; 30-FT, Item SPV.0060.04; 35-FT, Item SPV.0060.05; 40-FT, Item SPV.0060.06; 45-FT, Item SPV.0060.07; 50-FT, Item SPV.0060.08; 55-FT, Item SPV.0060.09.**

**A Description**

Work under this item consists of furnishing and installing monotube arms.

**B Materials**

Design support structures conforming to the minimum wall thickness the plan details show and to AASHTO design and fabrication standards for structural supports for highway signs, luminaries, and traffic signals. Use a design life of 50 years. Design to withstand a 3 second gust wind speed of 90 mph (145 km/h). Do not use the methods of appendix C of those AASHTO standards.

Use category III criteria for 15 to 30-foot arms. Use category II criteria for 35 to 55-foot arms.

For structures requiring a fatigue analysis, use 45 mph (72 km/h) for truck-induced gusts.

Base the designs on the completed maximum loading configuration the standard detail drawing shows. Along with the materials list, submit a certificate of compliance certifying that the arms as furnished conform to the above structural performance requirements. Ensure that the certificate of compliance is on the manufacturer's letterhead, signed by an authorized company officer, and notarized. Send a copy of the certificate and a copy of the monotube arm shop drawings to the department electrical engineer.

Furnish monotube arms conforming to the following:

1. Consist of zinc coated steel round or oval members.
2. Have a mounting device welded to the pole end of the monotube arm that allows the attachment of the arm to a pole as the plans show.
3. Have stiffeners or gussets if required between the arm tube and the arm mounting device to provide adequate strength to resist side loads.
4. Have a clean, uniform natural finish. No paint or other corrosion preventive maintenance coating is required.

After welding and before zinc coating, clean exterior surfaces of each arm free of all loose rust and mill scale, dirt, oil or grease, and other foreign substances.

Apply zinc coating as specified for sign bridge components in standard spec 641.2.8. Ensure that the zinc coating is tight, free from rough areas or slag, and presents a uniform appearance.

After manufacturing is complete, clean the exterior surfaces of each pole free of all loose scale, dirt, oil, or grease, and other foreign substances.

### **C Construction**

Install monotube arms as specified in the plan details and using appropriate contractor-furnished hardware.

Prior to installation of each monotube arm, a 1 1/4-inch hole shall be drilled into the bottom of the arm approximately centered over each driving lane as shown on the plans. Where emergency vehicle pre-emption (EVP) is installed, a separate 1 1/4-inch hole shall be drilled in the bottom of the arm approximately centered over the roadway approach, but a minimum of 4-feet from the nearest drilled hole.

The contractor shall provide 9-14 AWG traffic signal cable spooled 5 feet outside the arm from each drilled hole in the arm, including the hole for EVP if applicable, to the base of the pole below the hand hole. A separate nylon pull rope shall also be provided for the EVP hole to the base of the pole below the hand hole where applicable.

**D Measurement**

The department will measure Monotube Arms (Length) as each individual arm, acceptably completed.

**E Payment**

The department will pay for measured quantity at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0060.02	Monotube Arms 20-FT	Each
SPV.0060.03	Monotube Arms 25-FT	Each
SPV.0060.04	Monotube Arms 30-FT	Each
SPV.0060.05	Monotube Arms 35-FT	Each
SPV.0060.06	Monotube Arms 40-FT	Each
SPV.0060.07	Monotube Arms 45-FT	Each
SPV.0060.08	Monotube Arms 50-FT	Each
SPV.0060.09	Monotube Arms 55-FT	Each

Payment is full compensation for providing and installing all materials, including all hardware, fittings, mounting devices, shims, and attachments necessary to completely install the arms.

**15. Poles Type 9, Item SPV.0060.10; Type 10, Item SPV.0060.11.****A Description**

Work under this item consists of furnishing and installing monotube poles.

**B Materials**

Design support structures conforming to the minimum wall thickness the plan details show and to AASHTO design and fabrication standards for structural supports for highway signs, luminaries, and traffic signals. Use a design life of 50 years. Design to withstand a 3 second gust wind speed of 90 mph (145 km/h). Do not use the methods of Appendix C of those AASHTO standards.

Use category III criteria for 15 to 30-foot arms.

For structures requiring a fatigue analysis, use 45 mph (72 km/h) for truck-induced gusts.

After welding and before zinc coating, clean the exterior surface of each steel pole free of all loose rust and mill scale, dirt, oil or grease, and other foreign substances.

Apply a zinc coating conforming to the process specified for steel sign bridges in standard spec 641.2.8. Ensure that the zinc coating is tight, free from rough areas or slag, and presents a uniform appearance.

After completing manufacturing, clean the exterior surfaces of each pole free of all loose scale, dirt, oil or grease, and other foreign substances.

Provide a reinforced hand hold measuring 4 inches by 6 inches (100 mm by 150 mm) as the plans show. Locate the hand hole 18 inches (450 mm) from the bottom of the pole base to the center of the door.

For the hand hole, include an access cover mounted to the pole by two ¼” -20 x ¾” (m6 x 1.00 x 19 mm) hex-head stainless steel bolts.

Provide a grounding lug complete with mounting hardware, as required, inside the pole as the plans show.

Provide access to the grounding lug from the hand hole. Weld the ground lug directly opposite the hand hole on the inside wall of the pole.

Equip the top of the shaft with a removable, ventilated cap held securely in place by at least three ¼” -20 x ¾” (m6 x 1.00 x 19 mm) hex-head stainless steel set screws.

Ensure that all castings are clean, smooth, and with all details well defined and true to pattern.

Attach base plates firmly to the pole shaft by welding or other approved method.

Include anchor bolts meeting AASHTO standards applicable to the pole type and loading. Provide a mounting template that ensures correct installation of anchor bolts in foundation.

### **C Construction**

Install poles as specified in the plan details and using appropriate contractor-furnished anchor bolts and hardware. Use the appropriate anchor bolt template to ensure correct installation. Secure pole to anchor assembly and document tensioning procedures conforming to 657.3.2 and provide completed copies of form DT2321 for each structure to the engineer for inclusion in the permanent record.

After completing erection using normal pole shaft raking techniques, ensure the centerline of the shaft appears vertical.

### **D Measurement**

The department will measure each Pole (Type) as each individual pole, acceptably completed.

### **E Payment**

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0060.10	Pole Type 9	Each
SPV.0060.11	Pole Type 10	Each



Payment is full compensation for providing and installing poles including all hardware and fittings necessary to install the poles, and for installing identification plaques, if required.

**16. Poles Type 12, Item SPV.0060.12; Type 12 Special, Item SPV.0060.13; Type 13 Special, Item SPV.0060.14.**

**A Description**

Work under this item consists of furnishing and installing monotube poles as shown on the plans and specified below.

**B Materials**

Design support structures conforming to the minimum wall thickness the plan details show and to AASHTO design and fabrication standards for structural supports for highway signs, luminaries, and traffic signals. Use a design life of 50 years. Design to withstand a 3 second gust wind speed of 90 mph (145 km/h). Do not use the methods of Appendix C of those AASHTO standards.

Use category II criteria for 35 to 55-foot arms.

For structures requiring a fatigue analysis, use 45 mph (72 km/h) for truck-induced gusts.

After welding and before zinc coating, clean the exterior surface of each steel pole free of all loose rust and mill scale, dirt, oil or grease, and other foreign substances.

Apply a zinc coating conforming to the process specified for steel sign bridges in standard spec 641.2.8. Ensure that the zinc coating is tight, free from rough areas or slag, and presents a uniform appearance.

After completing manufacturing, clean the exterior surfaces of each pole free of all loose scale, dirt, oil or grease, and other foreign substances.

Provide a reinforced hand hole measuring 4 inches by 6 inches (100 mm by 150 mm) as the plans show. Locate the hand hole 18 inches (450 mm) from the bottom of the pole base to the center of the door.

For the hand hole, include an access cover mounted to the pole by two ¼"-20 x ¾" (m6 x 1.00 x 19 mm) hex-head stainless steel bolts.

Provide a grounding lug complete with mounting hardware, as required, inside the pole as the plans show.

Provide access to the grounding lug from the hand hole. Weld the ground lug directly opposite the hand hole on the inside wall of the pole.

Equip the top of the shaft with a removable, ventilated cap held securely in place by at least three ¼" -20 x ¾" (m6 x 1.00 x 19 mm) hex-head stainless steel set screws.

Ensure that all castings are clean, smooth, and with all details well defined and true to pattern.

Attach base plates firmly to the pole shaft by welding or other approved method.

Include anchor bolts meeting AASHTO standards applicable to the pole type and loading.

Provide a mounting template that ensures correct installation of anchor bolts in foundation.

### **C Construction**

Install poles as specified in the plan details and using appropriate contractor-furnished anchor bolts and hardware. Use the appropriate anchor bolt template to ensure correct installation. Secure pole to anchor assembly and document tensioning procedures conforming to standard spec 657.3.2 and provide completed copies of form DT2321 for each structure to the engineer for inclusion in the permanent record.

After completing erection using normal pole shaft raking techniques, ensure the centerline of the shaft appears vertical.

### **D Measurement**

The department will measure Poles (Type) and Poles (Type) Special as each individual pole, acceptably completed.

### **E Payment**

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0060.12	Poles Type 12	Each
SPV.0060.13	Poles Type 12 Special	Each
SPV.0060.14	Poles Type 13 Special	Each

Payment is full compensation for providing and installing poles including all hardware and fittings necessary to install the poles.

## **17. Rectangular Polymer Concrete Vault 13-Inch x 24-Inch x 18-Inch, Item SPV.0060.15; 17-Inch x 30-Inch x 18-Inch, Item SPV.0060.16.**

### **A Description**

This special provision describes furnishing and installing Polymer Concrete Vaults in accordance to current City of Milwaukee methods. All work shall be in accordance to standard spec 651.

## **B Materials**

Polymer Concrete shall be manufactured from one of the general types and grades defined in polymers in concrete structural applications state of the art report, ACI 548.6R-96 for structural uses. Thermoplastics will not be acceptable.

Enclosure walls shall be made from pattern cut structural fiberglass cloths to assure uniform, pre-measurable fiberglass content on all areas. Chopper gun fiberglass construction is not acceptable.

Binding polymers used in the manufacture of the polymer concrete and the fiber reinforced polyester shall be of the same formulation or from formulations with demonstrated chemical compatibility to assure complete chemical bonding of all components. Fiber reinforced polyester wall sections must be cast integrally into and chemically bonded within the upper polymer concrete casting.

### **1. Testing**

Meet ANSI/SCTE 77 2010 (Tier 15 or greater), ASTM C 857, and WUC 3.6 structural requirements.

Compressive Modulus of Elasticity (fiberglass reinforced polymer):  $5.6 \times 10^6$  PSI tested in accordance to procedures outlined in ASTM D-695

Comprehensive Strength (fiberglass reinforced polymer): 24,300 PSI tested in accordance to ASTM D-695

Flexural Strength (fiberglass reinforced polymer): 18,700 PSI tested in accordance to ASTM D-790

Tensile Strength (fiberglass reinforced polymer): 12,100 PSI tested in accordance to procedures outlined in ASTM D-638

Tensile Modulus of Elasticity (fiberglass reinforced polymer):  $8.6 \times 10^5$  PSI tested in accordance to procedures outlined in ASTM D-638

Splitting Tensile Strength (polymer concrete): Tested in accordance to procedures outlined in ASTM C-496

Accelerated Service: Tested in accordance to procedure E outlined in ASTM D-756

Water Absorption: Tested in accordance to ASTM D-570 outlined in sections 6.1 and 6.5

Impact Resistance (fiberglass reinforced polymer concrete): 72 foot pounds in accordance to ASTM D-2444 administered with a "C" tup

Skid Resistance: 0.60 coefficient of friction in accordance to ASTM C-1028

Flammability Test: Tested in accordance to ASTM D-635

Ultraviolet Exposure: Tested in accordance to ASTM test method G-53

#### Chemical Resistance

1. Sodium Chloride 5%
2. Sodium Carbonate 0.1 N
3. Hydrochloric Acid 0.2 N
4. Acetic Acid 5%
5. Sulfuric Acid 0.1N
6. Sodium Sulfate 0.1 N
7. Sodium Hydroxide 0.1N
8. Kerosene Oil per ASTM D-543
9. Transformer Oil per ASTM D-543

The street lighting vaults and covers shall be gray in color and shall be flared wall indicated on the Drawings. Covers shall be provided with 2 stainless steel bolts. Each cover shall have the words "TRAFFIC" cast into its surface along the longest dimension. The words shall be permanently recessed into the surface.

#### C Construction

Install rectangular flared wall vaults according to current City of Milwaukee standards. Provisions for inserting conduit into any side or the bottom of the vault shall be included.

#### D Measurement

The department will measure Rectangular Polymer Concrete Vault (Size) by each individual unit, acceptably completed.

#### E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0060.15	Rectangular Polymer Concrete Vault 13-Inch x 24-Inch x 18-Inch	Each
SPV.0060.16	Rectangular Polymer Concrete Vault 17-Inch x 30-Inch x 18-Inch	Each

Payment is full compensation for furnishing labor, equipment, coordination and all materials and incidentals necessary to complete the work.

### 18. Utility Line Opening (ULO), Item SPV.0060.17.

#### A Description

This special provision describes excavating to uncover utilities for the purpose of determining elevation or location and potential conflicts as shown on the plans or as directed by the engineer.

**B (Vacant)****C Construction**

Perform the excavation in such a manner that the utility in question is not damaged and the safety of the workers is not compromised.

Perform the utility line openings as soon as possible and at least 10 days in advance of proposed utility construction to allow any conflicts to be resolved with minimal disruption. Give the engineer a minimum of three working days once utility line opening information is received to review all relevant design information prior to proposed utility construction. Where utilities are within 6 feet of each other at a potential conflict location, only one utility line opening will be called for. In these cases, a single utility line opening will be considered full payment to locate multiple utilities. Utility line openings include a trench up to 10 feet long as measured at the trench bottom, and of any depth required to locate the intended utility.

Approve and coordinate all utility line openings with the engineer. Notify the utility engineers or their agents of this work a minimum of 3 days prior to the work so they may be present when the work is completed.

Replace pavement over utility line opening trenches which are within the staged traffic area as directed by the engineer. Replace pavement and open to traffic within 24 hours of the excavation.

**D Measurement**

The department will measure Utility Line Opening (ULO) by each individual unit, acceptably completed.

**E. Payment**

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0060.17	Utility Line Opening (ULO)	Each

Payment is full compensation for the excavation required to expose the utility line; backfilling with existing material removed from the excavation; compacting the backfill; restoring the site; and for cleanup.

Existing pavement, concrete curb, gutter, and sidewalk removals necessary to facilitate utility line openings are not considered part of or paid for under Utility Line Openings, but are considered separate and measured and paid for separately as removal items. Pavement replacement material, concrete curb, gutter, and sidewalk items will also be considered separate from Utility Line Openings and will be measured and paid for separately.

## **19. Colored Concrete Sidewalk 5-Inch, Item SPV.0165.01.**

### **A Description**

This special provision describes the construction of colored concrete sidewalk. Perform work conforming to standard spec 405, standard spec 602 and as hereinafter provided.

### **B Materials**

Furnish one sample of the colored concrete; one for each color, at least 15 working days prior to the start of colored concrete sidewalk construction. The specified color is “brick red”, as specified in the plan, with a clear liquid release agent. For final approval call Mr. Robert Viktora of the City of Milwaukee at (414) 286-3896.

Use grade A2 or grade A-FA concrete as specified in standard spec 501.2. All colored concrete must originate from the same batch plant.

### **C Construction**

Pour concrete in one layer with full-depth integral color.

Colored concrete shall be installed by an experienced contractor who has installed a minimum of 30,000 square feet of colored concrete. Submit written documentation of colored concrete work to the engineer prior to the start of construction.

Use 1 to 4 mil. Polyethylene (plastic) for protection of all adjoining areas for Integral Color concrete.

Apply liquid color releases sparingly to colored surface.

Allow 24 hours before removing excess release from the slab with garden hose.

Apply Decorative Sealer to completely dry slab or as per manufacturer’s methods. Apply two coats.

### **D Measurement**

The department will measure Colored Concrete Sidewalk 5-Inch by the square foot, acceptably completed.

### **E Payment**

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0165.01	Colored Concrete Sidewalk 5-Inch	SF

Payment is full compensation for furnishing and constructing colored concrete sidewalk.



## **ADDITIONAL SPECIAL PROVISION 4**

### **Payment to First-Tier Subcontractors**

Within 10 calendar days of receiving a progress payment for work completed by a subcontractor, pay the subcontractor for that work. The prime contractor may withhold payment to a subcontractor if, within 10 calendar days of receipt of that progress payment, the prime contractor provides written notification to the subcontractor and the department documenting "just cause" for withholding payment.

The prime contractor may also withhold routine retainage from payments due subcontractors.

### **Payment to Lower-Tier Subcontractors**

Ensure that subcontracting agreements at all tiers provide prompt payment rights to lower-tier subcontractors that parallel those granted first-tier subcontractors in this provision.

### **Release of Routine Retainage**

After granting substantial completion the department may reduce the routine retainage withheld from the prime contractor to 75 percent of the original total amount retained.

When the Department sends the semi-final estimate the department may reduce the routine retainage withheld from the prime contractor to 10 percent of the original total amount retained.

Within 30 calendar days of receiving the semi-final estimate from the department, submit written certification that subcontractors at all tiers are paid in full for acceptably completed work and that no routine retainage is being withheld. The department will pay the prime contractor in full and reduce the routine retainage withheld from the prime contractor to zero when the department approves the final estimate.

This special provision does not limit the right of the department, prime contractor, or subcontractors at any tier to withhold payment for work not acceptably completed or work subject to an unresolved contract dispute.



**ADDITIONAL SPECIAL PROVISION 6****ASP 6 - Modifications to the standard specifications**

Make the following revisions to the standard specifications:

---

**450.3.2.1 General**

Replace the entire text with the following effective with the January 2015 letting:

- (1) Do not place asphaltic mixture when the air temperature approximately 3 feet above grade, in shade, and away from artificial heat sources is less than 36 F for upper layers or 32 F for lower layers unless the engineer allows in writing. The contractor should place HMA pavement for projects on or north of STH 29 between May 1 and October 15 inclusive and for projects south of STH 29 between April 15 and November 1 inclusive. Notify the engineer at least one business day before paving.
  - (2) Unless the contract specifies otherwise, conform to the following:
    - Keep the road open to all traffic during construction.
    - Prepare the existing foundation for treatment as specified in 211.
    - Incorporate loose roadbed aggregate as a part of preparing the foundation, in shoulder construction, or dispose of as the engineer approves.
  - (3) Place asphaltic mixture only on a prepared, firm, and compacted base, foundation layer, or existing pavement substantially surface-dry and free of loose and foreign material. Do not place over frozen subgrade or base, or where the roadbed is unstable.
- 

**450.5 Payment**

Replace the entire text with the following effective with the May 2015 letting:

- (1) All costs of furnishing, maintaining, and operating the truck scale or other weighing equipment and furnishing the weigh tickets are incidental to the contract.
  - (2) Nonconforming material allowed to remain in place is subject to price adjustment under 105.3.2.
  - (3) Full-depth sawing to remove integrally placed safety edge where not required is incidental to the contract.
  - (4) The contractor is responsible for the quality of HMA pavement placed in cold weather. If because of an excusable compensable delay under 108.10.3, the engineer directs the contractor to pave when the temperature is less than 36 F for the upper layer or less than 32 F for lower layers, the department:
    - Will relieve the contractor of responsibility for damage and defects the engineer attributes to cold weather paving.
    - Will not assess disincentives for density or ride.
- 

**455.3.2.1 General**

Replace the paragraphs one and two with the following effective with the January 2015 letting:

- (1) Apply tack coat only when the air temperature is 32 F or more unless the engineer approves otherwise in writing. Before applying tack coat ensure that the surface is dry and reasonably free of loose dirt, dust, or other foreign matter. Do not apply if weather or surface conditions are unfavorable or before impending rains.
- (2) Use tack material of the type and grade the contract specifies. The contractor may, with the engineer's approval, dilute tack material as allowed under 455.2.4. Provide calculations using the asphalt content as-received from the supplier and subsequent contractor dilutions to show that as-placed material has 50 percent or more residual asphalt content. Apply at 0.050 to 0.070 gallons per square yard, after dilution, unless the contract designates otherwise. The engineer may adjust the application rate based on surface conditions. Limit application each day to the area the contractor expects to pave during that day.

**460.2.2.3 Aggregate Gradation Master Range**

*Replace paragraph one with the following effective with the December 2014 letting:*

- (1) Ensure that the aggregate blend, including recycled material and mineral filler, conforms to the gradation requirements in table 460-1. The values listed are design limits; production values may exceed those limits.

**TABLE 460-1 AGGREGATE GRADATION MASTER RANGE AND VMA REQUIREMENTS**

SIEVE	PERCENTS PASSING DESIGNATED SIEVES						
	NOMINAL SIZE						
	37.5 mm	25.0 mm	19.0 mm	12.5 mm	9.5 mm	SMA 12.5 mm	SMA 9.5 mm
50.0-mm	100						
37.5-mm	90 – 100	100					
25.0-mm	90 max	90 - 100	100				
19.0-mm	—	90 max	90 - 100	100		100	
12.5-mm	—	—	90 max	90 - 100	100	90 - 97	100
9.5-mm	—	—	—	90 max	90 - 100	58 - 72	90 - 100
4.75-mm	—	—	—	—	90 max	25 - 35	35 - 45
2.36-mm	15 – 41	19 - 45	23 - 49	28 - 58	20 - 65	15 - 25	18 - 28
75-µm	0 – 6.0	1.0 - 7.0	2.0 - 8.0	2.0 - 10.0	2.0 - 10.0	8.0 - 12.0	10.0 - 14.0
% MINIMUM VMA	11.0	12.0	13.0	14.0 <sup>[1]</sup>	15.0 <sup>[2]</sup>	16.0	17.0

<sup>[1]</sup> 14.5 for E-0.3 and E-3 mixes.

<sup>[2]</sup> 15.5 for E-0.3 and E-3 mixes.

**460.3.4 Cold Weather Paving**

*Add a new subsection as follows effective with the May 2015 letting:*

**460.3.4 Cold Weather Paving****460.3.4.1 Cold Weather Paving Plan**

- (1) Submit a written cold weather paving plan to the engineer at the preconstruction meeting. In that plan outline material, operational, and equipment changes for paving when the air temperature approximately 3 feet above grade, in shade, and away from artificial heat sources is less than 40 F. Include the following:
- Use a department-accepted HMA mix design that incorporates a warm mix additive from the department's approved products list. Do not use a foaming process that introduces water into the mix.
  - Use additional rollers.

- (2) Engineer written acceptance is required for the cold weather paving plan. Engineer acceptance of the plan does not relieve the contractor of responsibility for pavement performance except as specified in 450.5(4).

**460.3.4.2 Cold Weather Paving Operations**

- (1) Do not place asphaltic mixture when the air temperature approximately 3 feet above grade, in shade, and away from artificial heat sources is less than 40 F unless a valid engineer-accepted cold weather paving plan is in effect.
- (2) If the national weather service forecast for the construction area predicts ambient air temperature less than 40 F at the projected time of paving within the next 24 hours, confirm or submit revisions to a previously engineer-accepted cold weather paving plan for engineer validation. Upon validation of the plan, the engineer will allow paving for the next day. Once in effect, pave conforming to the engineer-accepted cold weather paving plan for the balance of that work day or shift regardless of the temperature at the time of paving.

**460.4 Measurement**

*Add paragraph two as follows effective with the January 2015 letting:*

- (2) The department will measure HMA Cold Weather Paving by the ton of HMA mixture for pavement placed conforming to an engineer-accepted cold weather paving plan.

**460.5.1 General**

*Revise paragraph one as follows effective with the January 2015 letting:*

- (1) The department will pay for measured quantities at the contract unit price under the following bid items:

<u>ITEM NUMBER</u>	<u>DESCRIPTION</u>	<u>UNIT</u>
460.1100	HMA Pavement Type E-0.3	TON
460.1101	HMA Pavement Type E-1	TON
460.1103	HMA Pavement Type E-3	TON
460.1110	HMA Pavement Type E-10	TON
460.1130	HMA Pavement Type E-30	TON
460.1132	HMA Pavement Type E-30X	TON
460.1700	HMA Pavement Type SMA	TON
460.2000	Incentive Density HMA Pavement	DOL
460.4000	HMA Cold Weather Paving	TON

**460.5.2.2 Disincentive for HMA Pavement Density**

*Revise paragraph two as follows effective with the January 2015 letting:*

- (2) The department will not assess density disincentives for pavement placed in cold weather because of a department-caused delay as specified in 450.5(4).

**460.5.2.4 Cold Weather Paving**

*Add a new subsection as follows effective with the May 2015 letting:*

**460.5.2.4 Cold Weather Paving**

- (1) Payment for HMA Cold Weather Paving is full compensation for additional materials and equipment specified for cold weather paving under 460.3.4 including costs for preparing, administering, and following the contractor's cold weather paving plan. The department will not pay for HMA Cold Weather Paving for HMA placed on days when the department is assessing liquidated damages.
- (2) If HMA pavement is placed under 460.3.4 and the HMA Cold Weather Paving bid item is not in the contract, the department will pay for the additional costs specified in 460.5.2.4(1) as extra work. The department will pay separately for HMA pavement under the appropriate HMA Pavement bid items.

**465.2 Materials**

*Replace paragraph two with the following effective with the December 2014 letting:*

- (2) Under the other 465 bid items, the contractor need not submit a mix design. Furnish aggregates mixed with a type AC asphaltic material, except under the Asphaltic Curb bid item furnish PG58-28 asphaltic material. Use coarse and fine mineral aggregates uniformly coated and mixed with the asphaltic material in an engineer-approved mixing plant. The contractor may include reclaimed asphaltic pavement materials in the mixture.

**506.3.2 Shop Drawings**

Replace the entire text with the following effective with the May 2015 letting:

- (1) Ensure that shop drawings conform to the contract plans and provide additional details, dimensions, computations, and other information necessary for completely fabricating and erecting the work. Include project and structure numbers on each shop drawing sheet.
- (2) Check shop drawings and submit electronically to the department for review before beginning fabrication. For primary fabrication items, also certify that shop drawings conform to quality control standards by submitting department form DT2333. Department review does not relieve the contractor from responsibility for errors or omissions on shop drawings.
- (3) Shop drawings are part of the contract. The department must approve differences between shop drawings and contract plans. The contractor bears the costs of department-approved substitutions. Do not deviate from or revise drawings without notifying the department and resubmitting revised drawings.
- (4) Ensure that the fabricator delivers 3 sets of shop drawings for railroad structures to the railroad company upon contract completion.

---

**Bid Items Added**

Add the following new bid item effective with the January 2015 letting:

<u>ITEM NUMBER</u>	<u>DESCRIPTION</u>	<u>UNIT</u>
460.4000	HMA Cold Weather Paving	TON

---

**Errata**

Make the following corrections to the standard specifications:

**501.3.2.4.4 Water Reducer**

Correct errata by deleting the reference to footnote 6 for grade D concrete.

- (1) Add a water reducing admixture conforming to 501.2.3. Determine the specific type and rate of use based on the atmospheric conditions, the desired properties of the finished concrete and the manufacturer's recommended rate of use. The actual rate of use shall at least equal the manufacturer's recommended rate, and both the type and rate used require the engineer's approval before use.

---

**506.5 Payment**

Correct errata by changing the reference to 506.3.22.

- (9) The department will limit costs for inspections conducted under 506.3.22 to \$0.05 per pound of material and deduct costs in excess of that amount from payment due the contractor. The department will determine costs for in-house inspections based on hourly rates for department staff plus overhead and use invoiced costs for contracted-out inspections. The department will administer deductions for the contractor's share of the total inspection cost under the Excess Costs For Fabrication Shop Inspection administrative item.

**ADDITIONAL SPECIAL PROVISION 7**

- A. Reporting 1<sup>st</sup> Tier and DBE Payments During Construction
1. Comply with reporting requirements specified in the department's Civil Rights Compliance, Contractor's User Manual, Sublets and Payments.
  2. Report payments to all DBE firms within 10 calendar days of receipt of a progress payment by the department or a contractor for work performed, materials furnished, or materials stockpiled by a DBE firm. Report the payment as specified in A(1) for all work satisfactorily performed and for all materials furnished or stockpiled.
  3. Report payments to all first tier subcontractor relationships within 10 calendar days of receipt of a progress payment by the department for work performed. Report the payment as specified in A(1) for all work satisfactorily performed.
  4. All tiers shall report payments as necessary to comply with the DBE payment requirement as specified in A(2).
  5. Require all first tier relationships, DBE firms and all other tier relationships necessary to comply with the DBE payment requirement in receipt of a progress payment by contractor to acknowledge receipt of payment as specified in A(1), (2), (3) and (4).
  6. All agreements made by a contractor shall include the provisions in A(1), (2), (3), (4) and (5), and shall be binding on all first tier subcontractor relationships and all contractors and subcontractors utilizing DBE firms on the project.
- B. Costs for conforming to this special provision are incidental to the contract.



**ADDITIONAL SPECIAL PROVISION 9**  
**Electronic Certified Payroll Submittal**

(1) Use the department's Civil Rights Compliance System (CRCS) to submit certified payrolls electronically. Details are available online through the department's highway construction contractor information (HCCI) site on the Labor, Wages, and EEO Information page at:

<http://www.dot.wi.gov/business/civilrights/laborwages/index.htm>

(2) Ensure that all tiers of subcontractors, as well as all trucking firms, submit their weekly certified payrolls electronically through CRCS. These payrolls are due within seven calendar days following the close of the payroll period. Every firm providing physical labor towards completing the project is a subcontractor under this special provision.

(3) Upon receipt of contract execution, promptly make all affected firms aware of the requirements under this special provision and arrange for them to receive CRCS training as they are about to begin payrolls. The department will provide training either in a classroom setting at one of our regional offices or by telephone. Contact Tess Mulrooney at 608-267-4489 to schedule the training.

(4) The department will reject all paper submittals of forms DT-1816 and DT-1929 for information required under this special provision. All costs for conforming to this special provision are incidental to the contract.

(5) Firms wishing to export payroll data from their computer system into CRCS should have their payroll coordinator send several sample electronic files to Tess two months before a payroll needs to be submitted. Not every contractor's payroll system is capable of producing export files. For details, see pages 17-22 of the CRCS System Background Information manual available online on the Labor, Wages, and EEO Information page at:

<http://www.dot.wi.gov/business/civilrights/laborwages/docs/crc-payroll-manual.pdf>

**DECEMBER 2013**

**BUY AMERICA PROVISION**

All steel and iron materials permanently incorporated in this project shall be domestic products and all manufacturing and coating processes for these materials from smelting forward in the manufacturing process must have occurred within the United States. Coating includes epoxy coating, galvanizing, painting and any other coating that protects or enhances the value of a material subject to the requirements of Buy America. The exemption of this requirement is the minimal use of foreign materials if the total cost of such material permanently incorporated in the product does not exceed one-tenth of one percent (1/10 of 1%) of the total contract cost or \$2,500.00, whichever is greater. For purposes of this paragraph, the cost is that shown to be the value of the subject products as they are delivered to the project. The contractor shall take actions and provide documentation conforming to CMM 2-28.5 to ensure compliance with this "Buy America" provision.

<http://roadwaystandards.dot.wi.gov/standards/cmm/cm-02-28.pdf#cm2-28.5>

Upon completion of the project certify to the engineer, in writing using department form WS4567, that all steel, iron, and coating processes for steel or iron incorporated into the contract work conform to these "Buy America" provisions. Attach a list of exemptions and their associated costs to the certification form. Department form WS4567 is available at:

<http://roadwaystandards.dot.wi.gov/standards/forms/ws4567.doc>



**Effective with September 2004 Letting**

**WISCONSIN DEPARTMENT OF TRANSPORTATION  
DIVISION OF HIGHWAYS AND TRANSPORTATION FACILITIES**

**SUPPLEMENTAL REQUIRED CONTRACT PROVISIONS**

- I. Wage Rates, Hours of labor and payment of Wages
- II. Payroll Requirements
- III. Postings at the Site of the Work
- IV. Affidavits
- V. Wage Rate Redistribution
- VI. Additional Classifications

**I. WAGE RATES, HOURS OF LABOR AND PAYMENT OF WAGES**

The schedule of "Minimum Wage Rates" attached hereto and made a part hereof furnishes the prevailing wage rates that have been determined pursuant to Section 103.50 of the Wisconsin Statutes. These wage rates are the minimum required to be paid to the various laborers, workers, mechanics and truck drivers employed by contractors and subcontractors on the construction work embraced by the contract and subject to prevailing hours and wages under Section 103.50, Stats. If necessary to employ laborers, workers, mechanics or truck drivers whose classification is not listed on the schedule, they shall be paid at rates conformable to those listed for similar classifications. Apprentices shall be paid at rates not less than those prescribed in their state indenture contracts.

While the wage rates shown are the minimum rates required by the contract to be paid during its life, this is not a representation that labor can be obtained at these rates. It is the responsibility of bidders to inform themselves as to the local labor conditions and prospective changes or adjustments of wage rates. No increase in the contract price shall be allowed or authorized on account of the payment of wage rates in excess of those listed herein.

Pursuant to Section 103.50 of the Wisconsin Statutes, the prevailing hours of labor have been determined to be up to 10 hours per day and 40 hours per calendar week Monday through Friday. If any laborer, worker, mechanic or truck driver is permitted or required to work more than the prevailing number of hours per day or per calendar week on this contract, they shall be paid for all hours in excess of the prevailing hours at a rate of at least one and one-half (1 1/2) times their hourly rate of pay. All work on Saturday, Sunday and the following holidays is to be paid at time and a half: (1) January 1, (2) the last Monday in May, (3) July 4, (4) the first Monday in September, (5) the fourth Thursday in November, (6) December 25, (7) the day before if January 1, July 4 or December 25 falls on a Saturday and (8) the day following if January 1, July 4 or December 25 falls on a Sunday.

All laborers, workers, mechanics and truck drivers shall be paid unconditionally not less often than once a week. Persons who own and operate their own trucks must receive the prevailing truck driver rate for the applicable type of truck (i.e. 2 axle, 3 or more axle, articulated, eculid or dumptor) he or she operates, plus an agreed upon amount for the use of his or her truck. Every owner-operator MUST be paid separately for their driving and for the use of their truck.

For those projects subject to the requirements of the Davis-Bacon Act, the Secretary of Labor will also have determined "Minimum Wage Rates" for work to be performed under the contract. These rates are, for all or most of the labor, worker, mechanic or truck driver classifications, identical to those established under Section 103.50 of the Wisconsin Statutes. In the event the rates are not identical, the higher of the two rates will govern.

## **II. PAYROLL REQUIREMENTS**

All contractors and subcontractors must submit weekly Certified Payrolls and Compliance Statement verifying that all laborers, workers, mechanics and truck drivers working on the project have been paid the prevailing wage rates for all work performed under the contract required by Section 103.50 of the Wisconsin Statutes.

## **III. POSTINGS AT THE SITE OF THE WORK**

In addition to the required postings furnished by the Department, the contractor shall post the following in at least one conspicuous place at the site of work:

- a. "NOTICE TO EMPLOYEES," which provides information required to be posted by the provisions of Section 103.50 of the Wisconsin Statutes.
- b. A copy of the State of Wisconsin Minimum Wages Rates. (Four pages.)
- c. A copy of the contractor's Equal Employment Opportunity Policy.
- d. On any project involving federal aid, in addition to the furnished postings, the contractor shall post a copy of the "Davis-Bacon Act, Minimum Wage Rates". (Three pages.)

## **IV. WAGE RATE REDISTRIBUTION**

The amount specified as the hourly basic rate of pay and the amount(s) specified as the fringe benefit contribution(s), for all classes of laborers, workers, mechanics or truck drivers may be redistributed, when necessary, to conform to those specified in any applicable collective bargaining agreement, provided that both parties to such agreement

request and receive the approval for any such redistribution from both the Department of Transportation and the Department of Workforce Development prior to the implementation of such redistribution.

## **V. ADDITIONAL CLASSIFICATIONS**

Any unlisted laborer or mechanic classification that is needed to perform work on this project, and is not included within the scope of any of the classifications listed in the application prevailing wage rate determination, may be added after award only if all of the following criteria have been met:

1. The affected employer(s) must make a written request to WisDOT Central Office to utilize the unlisted classification on this project.
2. The request must indicate the scope of the work to be performed by the unlisted classification and must indicate the proposed wage/fringe benefit package that the unlisted classification is to receive.
3. The work to be performed by the unlisted classification must not be performed by a classification that is included in the applicable prevailing wage rate determination.
4. The unlisted classification must be commonly employed in the area where the project is located.
5. The proposed wage/fringe benefit package must bear a reasonable relationship to those set forth in the applicable prevailing wage rate determination.
6. The request should be made prior to the actual performance of the work by the unlisted classification.
7. DWD must approve the use of the unlisted classification and the proposed wage/fringe benefit package. USDOL also must approve the use of the unlisted classification and the proposed wage/fringe benefit package on federal aid projects.
8. WisDOT and DWD may amend the proposed wage/fringe benefit package, as deemed necessary, and may set forth specific employment ratios and scope of work requirements in the approval document.

The approved wage/fringe benefit package shall be paid to all laborers, workers, mechanics or truck drivers performing work within the scope of that performed by the unlisted classification, from the first day on which such work is performed. In the event that work is performed by the unlisted classification prior to approval, the wage/fringe benefit package to be paid for such work must be in conformance with the wage/fringe

benefit package approved for such work. Under this arrangement a retroactive adjustment in wages and/or fringe benefits may be required to be made to the affected laborers, workers, mechanics or truck drivers by the affected employer(s).

**ANNUAL PREVAILING WAGE RATE DETERMINATION  
FOR ALL STATE HIGHWAY PROJECTS  
MILWAUKEE COUNTY**

Compiled by the State of Wisconsin - Department of Workforce Development  
for the Department of Transportation  
Pursuant to s. 103.50, Stats.  
Issued on May 1, 2015

**CLASSIFICATION:** Contractors are required to call the Department of Workforce Development if there are any questions regarding the proper trade or classification to be used for any worker on a public works project.

**OVERTIME:** Time and one-half must be paid for all hours worked over 10 hours per day and 40 hours per calendar week and for all hours worked on Saturday, Sunday and the following six (6) holidays: January 1; the last Monday in May; July 4; the 1st Monday in September; the 4th Thursday in November; December 25; the day before if January 1, July 4 or December 25 falls on a Saturday; the day following if January 1, July 4 or December 25 falls on a Sunday.

**FUTURE INCREASE:** If indicated for a specific trade or occupation, the full amount of such increase MUST be added to the "TOTAL" indicated for such trade or occupation on the date(s) such increase(s) becomes effective.

**PREMIUM PAY:** If indicated for a specific trade or occupation, the full amount of such pay MUST be added to the "HOURLY BASIC RATE OF PAY" indicated for such trade or occupation, whenever such pay is applicable.

**SUBJOURNEY:** Wage rates may be available for some of the classifications indicated below. Any employer that desires to use any subjourney classification on a project MUST request the applicable wage rate from the Department of Workforce Development PRIOR to the date such classification is used on such project. Form ERD-10880 is available for this purpose and can be obtained by writing to the Department of Workforce Development, Equal Rights Division, P.O. Box 8928, Madison, WI 53708.

<u>TRADE OR OCCUPATION</u>	<u>HOURLY BASIC RATE OF PAY</u>	<u>HOURLY FRINGE BENEFITS</u>	<u>TOTAL</u>
	\$	\$	\$
Bricklayer, Blocklayer or Stonemason	35.37	17.99	53.36
Carpenter	33.68	19.99	53.67
Cement Finisher	32.75	19.21	51.96
Future Increase(s): Add \$1.87 on 6/1/15; Add \$1.75 on 6/1/16.			
Premium Pay: DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.40/hr when the Wisconsin Department of Transportation or responsible governing agency requires that work be performed at night under artificial illumination with traffic control and the work is completed after sunset and before sunrise.			
Electrician	33.93	22.77	56.70
Premium Pay: DOT PREMIUM: Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day.			
Fence Erector	23.73	19.09	42.82
Ironworker	30.77	23.97	54.74
Premium Pay: DOT PREMIUM: Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day.			
Line Constructor (Electrical)	37.43	18.19	55.62
Painter	29.22	16.69	45.91
Pavement Marking Operator	30.27	18.79	49.06
Piledriver	30.11	26.51	56.62
Future Increase(s): Add \$1.50/hr on 6/1/2015; Add \$1.60/hr on 6/1/2016.			
Premium Pay: Add \$.65/hr for Piledriver Loftsmen; Add \$.75/hr for Sheet Piling Loftsmen. DOT PREMIUM: Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day.			
Roofer or Waterproofing	29.40	17.05	46.45
Teledata Technician or Installer	24.89	17.15	42.04
Tuckpointer, Caulker or Cleaner	33.76	17.82	51.58

<b>TRADE OR OCCUPATION</b>	<b>HOURLY BASIC RATE OF PAY</b>	<b>HOURLY FRINGE BENEFITS</b>	<b>TOTAL</b>
	<b>\$</b>	<b>\$</b>	<b>\$</b>
Underwater Diver (Except on Great Lakes)	35.40	15.90	51.30
Heavy Equipment Operator - ELECTRICAL LINE CONSTRUCTION ONLY	35.55	15.57	51.12
Light Equipment Operator -ELECTRICAL LINE CONSTRUCTION ONLY	31.60	14.64	46.24
Heavy Truck Driver - ELECTRICAL LINE CONSTRUCTION ONLY	27.65	13.44	41.09
Light Truck Driver - ELECTRICAL LINE CONSTRUCTION ONLY	25.68	12.83	38.51
Groundman - ELECTRICAL LINE CONSTRUCTION ONLY	21.75	11.63	33.38

**TRUCK DRIVERS**

Single Axle or Two Axle	25.18	18.31	43.49
Future Increase(s): Add \$1.15/hr on 6/1/2015. Premium Pay: DOT PREMIUM: Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day.			
Three or More Axle	25.28	18.31	43.59
Future Increase(s): Add \$1.15/hr on 6/1/2015. Premium Pay: DOT PREMIUM: Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day.			
Articulated, Euclid, Dumptor, Off Road Material Hauler	30.27	21.15	51.42
Future Increase(s): Add \$1.25/hr on 6/1/2015; Add \$1.30/hr on 6/1/2016; Add \$1.25/hr on 6/1/2017. Premium Pay: DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.50/hr night work premium. See DOT'S website for details about the applicability of this night work premium at: <a href="http://www.dot.wi.gov/business/civilrights/laborwages/pwc.htm">http://www.dot.wi.gov/business/civilrights/laborwages/pwc.htm</a> .			
Pavement Marking Vehicle	23.16	17.13	40.29
Shadow or Pilot Vehicle	24.37	17.77	42.14
Truck Mechanic	24.52	17.77	42.29

**LABORERS**

General Laborer	27.06	20.03	47.09
Future Increase(s): Add \$1.05/hr eff. 06/01/2015; Add \$1.00/hr eff. 06/01/2016; Add \$1.00/hr eff. 06/01/2017 Premium Pay: Add \$.15/hr for air tool operator, joint sawer and filler (pavement), vibrator or tamper operator (mechanical hand operated), chain saw operator and demolition burning torch laborer; Add \$.35/hr for bituminous worker (raker and luteman), formsetter (curb, sidewalk and pavement) and strike off man; Add \$.50/hr for line and grade specialist; Add \$.65/hr for blaster and powderman; Add \$2.01/hr for topman; Add \$2.46/hr for bottomman; Add \$3.23/hr for pipelayer. / DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.25/hr for work on projects involving temporary traffic control setup, for lane and shoulder closures, when work under artificial illumination conditions is necessary as required by the project provisions (including prep time prior to and/or cleanup after such time period).			
Asbestos Abatement Worker	22.05	18.41	40.46
Landscaper	27.06	20.03	47.09
Future Increase(s): Add \$1.05/hr eff. 06/01/2015; Add \$1.00/hr eff. 06/01/2016; Add \$1.00/hr eff. 06/01/2017 Premium Pay: DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.25/hr for work on projects involving temporary traffic control setup, for lane and shoulder closures, when work under artificial illumination conditions is necessary as required by the project provisions (including prep time prior to and/or cleanup after such time period).			
Flagperson or Traffic Control Person	22.55	19.37	41.92

<b>TRADE OR OCCUPATION</b>	<b>HOURLY BASIC RATE OF PAY</b>	<b>HOURLY FRINGE BENEFITS</b>	<b>TOTAL</b>
	<b>\$</b>	<b>\$</b>	<b>\$</b>
Fiber Optic Laborer (Outside, Other Than Concrete Encased)	17.71	16.01	33.72
Railroad Track Laborer	14.50	4.39	18.89

### HEAVY EQUIPMENT OPERATORS

Crane, Tower Crane, Pedestal Tower or Derrick, With Boom, Leads &/or Jib Lengths Measuring 176 Ft or Over; Crane, Tower Crane, Pedestal Tower or Derrick, With or Without Attachments, With a Lifting Capacity of Over 100 Tons, Self-Erecting Tower Crane With a Lifting Capacity Of Over 4,000 Lbs., Crane With Boom Dollies; Traveling Crane (Bridge Type).	37.72	21.15	58.87
--	-------	-------	-------

Future Increase(s): Add \$1.25/hr on 6/1/2015; Add \$1.30/hr on 6/1/2016; Add \$1.25/hr on 6/1/2017.

Premium Pay: DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.50/hr night work premium.

See DOT'S website for details about the applicability of this night work premium at: <http://www.dot.wi.gov/business/civilrights/laborwages/pwc.htm>.

Backhoe (Track Type) Having a Mfr.'s Rated Capacity of 130,000 Lbs. or Over; Caisson Rig; Crane, Tower Crane, Portable Tower, Pedestal Tower or Derrick, With Boom, Leads &/or Jib Lengths Measuring 175 Ft or Under; Crane, Tower Crane, Portable Tower, Pedestal Tower or Derrick, With or Without Attachments, With a Lifting Capacity of 100 Tons or Under, Self-Erecting Tower Crane With A Lifting Capacity Of 4,000 Lbs., & Under; Dredge (NOT Performing Work on the Great Lakes); Licensed Boat Pilot (NOT Performing Work on the Great Lakes); Pile Driver.	37.22	21.15	58.37
---	-------	-------	-------

Future Increase(s): Add \$1.25/hr on 6/1/2015; Add \$1.30/hr on 6/1/2016; Add \$1.25/hr on 6/1/2017.

Premium Pay: DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.50/hr night work premium.

See DOT'S website for details about the applicability of this night work premium at: <http://www.dot.wi.gov/business/civilrights/laborwages/pwc.htm>.

Air Track, Rotary or Percussion Drilling Machine &/or Hammers, Blaster; Asphalt Heater, Planer & Scarifier; Asphalt Milling Machine; Asphalt Screed; Automatic Subgrader (Concrete); Backhoe (Track Type) Having a Mfr.'s Rated Capacity of Under 130,000 Lbs., Backhoe (Mini, 15,000 Lbs. & Under); Bituminous (Asphalt) Plant & Paver, Screed; Boatmen (NOT Performing Work on the Great Lakes); Boring Machine (Directional, Horizontal or Vertical); Bridge (Bidwell) Paver; Bulldozer or Endloader; Concrete Batch Plant, Batch Hopper; Concrete Breaker (Large, Auto, Vibratory/Sonic, Manual or Remote); Concrete Bump Cutter, Grinder, Planing or Grooving Machine; Concrete Conveyor System; Concrete Laser/Screed; Concrete Paver (Slipform); Concrete Pump, Concrete Conveyor (Rotec or Bidwell Type); Concrete Slipform Placer Curb & Gutter Machine; Concrete Spreader & Distributor; Crane (Carry Deck, Mini) or Truck Mounted Hydraulic Crane (10 Tons or Under); Crane With a Lifting Capacity of 25 Tons or Under; Forestry Equipment, Timbco, Tree Shear, Tub Grinder, Processor; Gradall (Cruz-Aire Type); Grader or Motor Patrol; Grout Pump; Hydro-Blaster (10,000 PSI or Over); Loading Machine (Conveyor); Material or Stack Hoist; Mechanic or Welder; Milling Machine; Post Hole Digger or Driver; Roller (Over 5 Ton); Scraper (Self Propelled or Tractor Drawn) 5 cu yds or More Capacity; Shoulder Widener; Sideboom; Skid Rig; Stabilizing or Concrete Mixer (Self-Propelled or 14S or Over); Straddle Carrier or Travel Lift; Tractor (Scraper, Dozer, Pusher, Loader); Tractor or Truck Mounted Hydraulic Backhoe; Trencher (Wheel Type or Chain Type);	36.72	21.15	57.87
--	-------	-------	-------

<b>TRADE OR OCCUPATION</b>	<b>HOURLY BASIC RATE OF PAY</b>	<b>HOURLY FRINGE BENEFITS</b>	<b>TOTAL</b>
	<b>\$</b>	<b>\$</b>	<b>\$</b>
Tube Finisher; Tugger (NOT Performing Work on the Great Lakes); Winches & A- Frames. Future Increase(s): Add \$1.25/hr on 6/1/2015; Add \$1.30/hr on 6/1/2016; Add \$1.25/hr on 6/1/2017. Premium Pay: DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.50/hr night work premium. See DOT'S website for details about the applicability of this night work premium at: <a href="http://www.dot.wi.gov/business/civilrights/laborwages/pwc.htm">http://www.dot.wi.gov/business/civilrights/laborwages/pwc.htm</a> .			
Belting, Burlap, Texturing Machine; Broom or Sweeper; Compactor (Self-Propelled or Tractor Mounted, Towed & Light Equipment); Concrete Finishing Machine (Road Type); Environmental Burner; Farm or Industrial Type Tractor; Fireman (Asphalt Plant, Pile Driver & Derrick NOT Performing Work on the Great Lakes); Forklift; Greaser; Hoist (Tugger, Automatic); Jeep Digger; Joint Sawyer (Multiple Blade); Launch (NOT Performing Work on the Great Lakes); Lift Slab Machine; Mechanical Float; Mulcher; Power Subgrader; Robotic Tool Carrier (With or Without Attachments); Roller (Rubber Tire, 5 Ton or Under); Self Propelled Chip Spreader; Shouldering Machine; Skid Steer Loader (With or Without Attachments); Telehandler; Tining or Curing Machine. Future Increase(s): Add \$1.25/hr on 6/1/2015; Add \$1.30/hr on 6/1/2016; Add \$1.25/hr on 6/1/2017. Premium Pay: DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.50/hr night work premium. See DOT'S website for details about the applicability of this night work premium at: <a href="http://www.dot.wi.gov/business/civilrights/laborwages/pwc.htm">http://www.dot.wi.gov/business/civilrights/laborwages/pwc.htm</a> .	36.46	21.15	57.61
Air Compressor (&/or 400 CFM or Over); Air, Electric or Hydraulic Jacking System; Augers (Vertical & Horizontal); Automatic Belt Conveyor & Surge Bin; Boiler (Temporary Heat); Concrete Proportioning Plant; Crusher, Screening or Wash Plant; Generator (&/or 150 KW or Over); Heaters (Mechanical); High Pressure Utility Locating Machine (Daylighting Machine); Mudjack; Oiler; Prestress Machine; Pug Mill; Pump (3 Inch or Over) or Well Points; Rock, Stone Breaker; Screed (Milling Machine); Stump Chipper; Tank Car Heaters; Vibratory Hammer or Extractor, Power Pack. Future Increase(s): Add \$1.25/hr on 6/1/2015; Add \$1.30/hr on 6/1/2016; Add \$1.25/hr on 6/1/2017. Premium Pay: DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.50/hr night work premium. See DOT'S website for details about the applicability of this night work premium at: <a href="http://www.dot.wi.gov/business/civilrights/laborwages/pwc.htm">http://www.dot.wi.gov/business/civilrights/laborwages/pwc.htm</a> .	36.17	21.15	57.32
Fiber Optic Cable Equipment.	28.89	17.95	46.84
Work Performed on the Great Lakes Including Diver; Wet Tender or Hydraulic Dredge Engineer.	41.65	21.71	63.36
Work Performed on the Great Lakes Including 70 Ton & Over Tug Operator; Assistant Hydraulic Dredge Engineer; Crane or Backhoe Operator; Hydraulic Dredge Leverman or Diver's Tender; Mechanic or Welder.	41.65	21.71	63.36
Work Performed on the Great Lakes Including Deck Equipment Operator or Machineryman (Maintains Cranes Over 50 Tons or Backhoes 115,000 Lbs. or More); Tug, Launch or Loader, Dozer or Like Equipment When Operated on a Barge, Breakwater Wall, Slip, Dock or Scow, Deck Machinery.	35.72	17.85	53.57
Work Performed on the Great Lakes Including Deck Equipment Operator, Machineryman or Fireman (Operates 4 Units or More or Maintains Cranes 50 Tons or Under or Backhoes 115,000 Lbs. or Under); Deck Hand, Deck Engineer or Assistant Tug Operator; Off Road Trucks-Great Lakes ONLY.	35.46	20.40	55.86



## SCHEDULE OF ITEMS

REVISED:

CONTRACT:  
20150512022PROJECT(S):  
2025-01-72FEDERAL ID(S):  
N/A

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS

## SECTION 0001 Participating Items

0010	201.0120 Clearing	14.000 ID	.		.	
0020	201.0220 Grubbing	14.000 ID	.		.	
0030	204.0155 Removing Concrete Sidewalk	170.000 SY	.		.	
0040	205.0501.S Excavation, Hauling, and Disposal of Petroleum Contaminated Soil	68.000 TON	.		.	
0050	213.0100 Finishing Roadway (project) 01. 2025-01-72	1.000 EACH	.		.	
0060	602.0410 Concrete Sidewalk 5-Inch	738.000 SF	.		.	
0070	619.1000 Mobilization	1.000 EACH	.		.	
0080	625.0100 Topsoil	100.000 SY	.		.	
0090	631.1000 Sod Lawn	100.000 SY	.		.	

## SCHEDULE OF ITEMS

REVISED:

CONTRACT:  
20150512022PROJECT(S):  
2025-01-72FEDERAL ID(S):  
N/A

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0100	641.8100 Overhead Sign Support (structure) 01. W Capitol Dr & N 35th St / Roosevelt Dr	LUMP	LUMP			.
0110	641.8100 Overhead Sign Support (structure) 02. W Capitol Dr & N 31st St	LUMP	LUMP			.
0120	641.8100 Overhead Sign Support (structure) 03. W Capitol Dr & N Green Bay Ave	LUMP	LUMP			.
0130	643.0100 Traffic Control (project) 01. 2025-01-72	1.000 EACH	.			.
0140	643.0300 Traffic Control Drums	22,513.000 DAY	.			.
0150	643.0420 Traffic Control Barricades Type III	9,353.000 DAY	.			.
0160	643.0705 Traffic Control Warning Lights Type A	22,513.000 DAY	.			.
0170	643.0715 Traffic Control Warning Lights Type C	14,006.000 DAY	.			.
0180	643.0900 Traffic Control Signs	8,319.000 DAY	.			.
0190	650.8500 Construction Staking Electrical Installations (project) 01. 2025-01-72	LUMP	LUMP			.

## SCHEDULE OF ITEMS

REVISED:

CONTRACT:  
20150512022PROJECT(S):  
2025-01-72FEDERAL ID(S):  
N/A

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0200	650.9910 Construction Staking Supplemental Control (project) 01. 2025-01-72	LUMP	LUMP		.	
0210	652.0230 Conduit Rigid Nonmetallic Schedule 40 2 1/2-Inch	80.000 LF	.		.	
0220	652.0235 Conduit Rigid Nonmetallic Schedule 40 3-Inch	400.000 LF	.		.	
0230	654.0110 Concrete Bases Type 10	10.000 EACH	.		.	
0240	654.0113 Concrete Bases Type 13	6.000 EACH	.		.	
0250	SPV.0060 Special 01. Concrete Bases Type 10 Special	29.000 EACH	.		.	
0260	SPV.0060 Special 02. Monotube Arms 20-Ft	1.000 EACH	.		.	
0270	SPV.0060 Special 03. Monotube Arms 25-Ft	3.000 EACH	.		.	
0280	SPV.0060 Special 04. Monotube Arms 30-Ft	6.000 EACH	.		.	
0290	SPV.0060 Special 05. Monotube Arms 35-Ft	19.000 EACH	.		.	
0300	SPV.0060 Special 06. Monotube Arms 40-Ft	10.000 EACH	.		.	

## SCHEDULE OF ITEMS

REVISED:

CONTRACT:  
20150512022PROJECT(S):  
2025-01-72FEDERAL ID(S):  
N/A

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0310	SPV.0060 Special 07. Monotube Arms 45-Ft	1.000 EACH	.		.	
0320	SPV.0060 Special 08. Monotube Arms 50-Ft	2.000 EACH	.		.	
0330	SPV.0060 Special 09. Monotube Arms 55-Ft	2.000 EACH	.		.	
0340	SPV.0060 Special 10. Poles Type 9	6.000 EACH	.		.	
0350	SPV.0060 Special 11. Poles Type 10	4.000 EACH	.		.	
0360	SPV.0060 Special 12. Poles Type 12	5.000 EACH	.		.	
0370	SPV.0060 Special 13. Poles Type 12 Special	23.000 EACH	.		.	
0380	SPV.0060 Special 14. Poles Type 13 Special	6.000 EACH	.		.	
0390	SPV.0060 Special 15. Rectangular Polymer Concrete Vault 13"X 24"X 18"	29.000 EACH	.		.	
0400	SPV.0060 Special 16. Rectangular Polymer Concrete Vault 17"X 30"X 18"	5.000 EACH	.		.	

## SCHEDULE OF ITEMS

REVISED:

CONTRACT:  
20150512022PROJECT(S):  
2025-01-72FEDERAL ID(S):  
N/A

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0410	SPV.0060 Special 17. Utility Line Opening (Ulo)	4.000 EACH	.		.	
0420	SPV.0165 Special 01. Colored Concrete Sidewalk 5-Inch	792.000 SF	.		.	
	SECTION 0001 TOTAL				.	
	TOTAL BID				.	



**PLEASE ATTACH SCHEDULE OF ITEMS HERE**