MAY 2015

ORDER OF SHEETS

Typical Sections and Details (Includes Erosion Control Plans)

Estimate of Quantitles

Miscellaneous Quantities

Standard Detail Drawings

Computer Earthwork Data

END PROJECT 3700-20-71

BEGIN PROJECT 3700-20-71

ROCK

LABEL

0 🗆

X

ò

Ø

STA 605+88.00 = 133,150.21

X = 511,642.11

PROFILE GRADE LINE

ORIGINAL GROUND

SPECIAL DITCH

UTILITIES

ELECTRIC

GAS

FIBER OPTIC

SANITARY SEWER

UTILITY PEDESTAL

TELEPHONE POLE

STORM SEWER

TELEPHONE

POWER POLE

WATER

GRADE ELEVATION

MARSH OR ROCK PROFILE

CULVERT (Profile View)

(To be noted as such)

STA 621+15.00

Sign Plates

Cross Sections

STH 50

= 60 MPH 40 MPH

2,400 (2002)

= 14,200

= __

= __

20__

Section No. 1

Section No. 2

Section No. 3 \$ D Section No. 3 Section No. 4 Right of Way Plat Section No. 5 Plan and Profile Section No. 6 Section No. 7 -Section No. 8 Structure Plans Section No. 9 Section No. 9 TOTAL SHEETS = _128 DESIGN DESIGNATION A.A.D.T. A.A.D.T. 20__ D.H.V. D.D. DESIGN SPEED **ESALS** KENOSHA CONVENTIONAL SYMBOLS CORPORATE LIMITS PROPERTY LINE LOT LINE LIMITED HIGHWAY EASEMENT EXISTING RIGHT OF WAY PROPOSED OR NEW R/W LINE SLOPE INTERCEPT REFERENCE LINE EXISTING CULVERT PROPOSED CULVERT (Box or Pipe) COMBUSTIBLE FLUIDS MARSH AREA WOODED OR SHRUB AREA

STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION

PLAN OF PROPOSED IMPROVEMENT

STH 50

NEW SIGNAL, STH 50 & CTH O

STH 50

KENOSHA COUNTY

STATE PROJECT NUMBER 3700-20-71

Klondike EM

> LAYOUT SCALE 1 1 Ml.

R-19-E

TOTAL NET LENGTH OF CENTERLINE = 0.000 MI.

HORIZONTAL POSITIONS SHOWN ON THIS PLAN ARE WISCONSIN COUNTY COORDINATES, KENOSHA COUNTY, NADB3 (2007), IN U.S. SURVEY FEET. VALUES ARE GRID COORDINATES, GRID BEARINGS, AND GRID DISTANCES. GRID DISTANCES MAY BE USED AS GROUND DISTANCES. VERTICAL DATUM BASED ON USGS (NAVD 88)

LAYOUT NAME : 010101_TI

FEDERAL PROJECT STATE PROJECT PROJECT CONTRACT 3700-20-71

> ORIGINAL PLANS PREPARED BY Short Elliott Hendrickson Inc. SEH 6808 Odana Road, Suite 200 Madison, WI 53719-1137 Madison, WI 53719-1137

for All of Us® 800.732.4362 toll free | www.sehinc.com SCONS BEAVEN WISCONS.

Building a Better World 608.620.6199 main | 888,908,8166 fax

STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION

PREPARED BY M SQUARED ENGINEERING Surveyor Designer Project Manager

Regional Examiner Regional Supervisor.

APPROVED FOR THE DEPARTMENT

PLOT BY : SEH INC

R-20-E

SEH

JUSTIN EFFINGER

UTILITY CONTACT LIST: AT&T WISCONSIN - COMMUNICATION LINE 2005 PEWAUKEE RD WAUKESHA, WI 53188 PH: (262) 896-7434 ATTENTION: MARK EDER EMAIL: ME1754@ATT.COM

TDS TELECOM - COMMUNICATION LINE 20875 CROSSROADS CIR - SUITE 800 WAUKESHA, WI 53186 PH: (262) 754-3052 ATTENTION: MICHAEL JOHNSON EMAIL: MICHAEL.JOHNSON@TDSTELECOM.COM

TIME WARNER CABLE, A DELAWARE LIMITED PARTNERSHIP - COMMUNICATION LINE 1320 N DR MARTIN LUTHER KING JR DR MILWAUKEE, WI 53212-4002 PH: (414) 277-4045 ATTENTION: STEVEN CRAMER EMAIL: WIS.ENGINEERING@TWCABLE.COM

WISCONSIN DEPARTMENT OF TRANSPORTATION -<u>WISCONSIN SIGNALS</u> 141 NW BARSTOW ST WAUKESHA, WI 53187-0798 PH: (414) 750-260

WE ENERGIES - ELECTRICITY SEND ALL CORRESPONDENCE TO:

LATROY BRUMFIELD 333 WEST EVERETT ST - A299 MILWAUKEE, WI 53203 PH: (414) 221-5617 EMAIL: LATROY.BRUMFIELD@WE-ENERGIES.COM

CONSTRUCTION FIELD CONTACT:

FRANCISCO CHAVEZ 500 S 116TH ST WEST ALLIS, WI 53214 PH: (414) 944-5540 EMAIL: FRANCISCO, CHAVEZ@WE-ENERGIES, COM

WE ENERGIES - GAS SEND ALL CORRESPONDENCE TO:

LATROY BRUMFIELD 333 WEST EVERETT ST - A299 MILWAUKEE, WI 53203 PH: (414) 221-5617 EMAIL: LATROY.BRUMFIELD@WE-ENERGIES.COM

CONSTRUCTION FIELD CONTACT:

SCOTT HOLSTEIN 700 S KANE ST BURLINGTION, WI 53105 PH: (262) 763-1084 EMAIL: SCOTT.HOLSTEIN@WE-ENERGIES.COM TO OBTAIN LOCATION OF PARTICIPANTS' UNDERGROUND FACILITIES BEFORE YOU DIG IN WISCONSIN



NOTE: WIS. STATUTE 182.0175 (1974) REQUIRES MIN. OF 3 WORK DAYS NOTICE BEFORE YOU EXCAVATE.

WISDOT REGION CONTACT:

JUSTIN EFFINGER WISDOT SOUTHEAST REGION WAUKESHA OFFICE 141 NW BARSTOW ST WAUKESHA, WI 53187 PH: (262) 548-5676 EMAIL: JUSTIN.EFFINGER@DOT.WI.GOV

DESIGN CONTACT:

JILL FEHRMAN 6808 ODANA ROAD SUITE 200 MADISON, WI 53719 PH: (608) 620-6183 EMAIL: JFEHRMAN@SEHINC.COM

WI DNR CONTACT:

CRAIG WEBSTER WI DEPARTMENT OF NATURAL RESOURCES 141 NW BARSTOW **ROOM 180** WAUKESHA, WI 53188 PH: (262) 574-2141 EMAIL: CRAIG.WEBSTER@WISCONSIN.GOV

ORDER OF SHEETS - SECTION 2:

PROJECT OVERVIEW TYPICAL SECTIONS CONSTRUCTION DETAILS PLAN DETAILS EROSION CONTROL STORM SEWER SIGNING TRAFFIC SIGNALS PAVEMENT MARKING TRAFFIC CONTROL ALIGNMENT

STANDARD ABBREVIATIONS:

ABUT **ABUTMENT** HYD AC ACRE ΙD AGG AGGREGATE TNV APRON ENDWALL FOR CULVERT PIPE **AECPRC** TP REINFORCED CONCRETE LHF **AECPCS** APRON ENDWALL FOR CULVERT PIPE CORRUGATED STEEL ĹF **ASPH** ASPHALTIC LC **AVERAGE** AVG LS AVERAGE DAILY TRAFFIC ADT MH BACK FACE MOR ВМ BENCH MARK MCE BR BRIDGE NC COMMERCIAL ENTRANCE NΩ CL OR C/L OR & CENTER LINE OBLIT CENTRAL ANGLE OR DELTA PAVT CONC CONCRETE **CPRC** CULVERT PIPE REINFORCED CONCRETE PVRC CULVERT PIPE CORRUGATED STEEL CPCS QOR CR CREEK REQ'D CUBIC YARD CURB AND GUTTER RES DEGREE OF CURVE RHF DHV DESIGN HOUR VOLUME R/W DISCH DISCHARGE RDWY DITCH GRADE DWY DRIVEWAY R/L OR R EAST GRID COORDINATE SALV STEEL PLATE BEAM GUARD EAT SAN ENERGY ABSORBING TERMINAL SF END POINT OF RADIUS E0R SY ELEVATION SDD ENT **ENTRANCE** STA EQUIVALENT SINGLE AXLE LOADS **ESALS** SS EXCAVATION EXC **SSPRC** EXCAVATION BELOW SUBGRADE EBS SE EXIST EXISTING FC FACE OF CURB TC FF FACE TO FACE T OR TN FERT FERTILIZE FIELD ENTRANCE TYP FE FLOW LINE VAR

HYDRANT INSIDE DIAMETER TNVFRT IRON PIPE OR PIN LEFT-HAND FORWARD LENGTH OF CURVE LINEAR FOOT LONG CHORD OF CURVE LUMP SUM MANHOLE MID POINT OF RADIUS MARKERS CULVERT END NORMAL CROWN NUMBER OBLITERATE PAVEMENT PRIVATE ENTRANCE POINT OF VERTICAL REVERSE CURVE QUARTER POINT OF RADIUS RADIUS REQUIRED RESIDENCE OR RESIDENTIAL RIGHT-HAND FORWARD RIGHT-OF-WAY RIVER ROADWAY REFERENCE LINE SALVAGED SANITARY SEWER SQUARE FEET SQUARE YARD STANDARD DETAIL DRAWINGS STATION STORM SEWER STORM SEWER PIPE REINFORCED CONCRETE SUPERELEVATION RATE TOP OF CURB TRUCKS (PERCENT OF) TYPICAL VARIABLE VERTICAL CURVE NORTH GRID COORDINATE

GENERAL NOTES:

- NO TREES OR SHRUBS SHALL BE REMOVED WITHOUT APPROVAL OF THE ENGINEER.
- 2. THE LOCATIONS OF EXISTING AND PROPOSED UTILITY INSTALLATIONS AS SHOWN ON THE PLANS ARE APPROXIMATE. THERE MAY BE OTHER UTILITY INSTALLATIONS WITHIN THE PROJECT AREA THAT ARE NOT SHOWN.
- 3. THE CONTRACTOR SHALL NOTIFY DIGGERS HOTLINE AND AFFECTED UTILITIES PRIOR TO THE START OF WORK. ANY LOCAL MUNICIPAL UTILITY WHICH IS NOT A MEMBER OF THE DIGGERS HOTLINE MUST BE CONTACTED SEPARATELY.
- PRIOR TO ORDERING DRAINAGE PIPES AND STRUCTURES. THE CONTRACTOR SHALL VERIFY RELATED DRAINAGE INFORMATION IN THE PLANS WITH THE ENGINEER.
- 5. INLET AND DISCHARGE ELEVATIONS FOR DRAINAGE STRUCTURES SHOWN ON THE PLAN MAY BE ADJUSTED BY THE ENGINEER TO FIT FIELD CONDITIONS.
- 6. WETLANDS, WATERWAYS, AND OTHER ENVIRONMENTALLY SENSITIVE AREAS SHALL BE PROTECTED AT ALL TIMES. DO NOT STORE EQUIPMENT OR MATERIALS NEAR THESE SITES UNLESS APPROVED BY THE ENGINEER.
- 7. BROKEN CONCRETE CONTAINING RE-BAR SHALL NOT BE USED AS RIPRAP.
- CROSS SECTIONS SHOWN INCLUDE THE THICKNESS OF TOPSOIL WHERE REQUIRED. TOPSOIL SHALL BE REPLACED WITH 4-INCH
- 9. TRAFFIC CONTROL DEVICES SHALL BE ADJUSTED TO FIT FIELD CONDITIONS AS DIRECTED BY THE ENGINEER.
- 10. RE-TOPSOIL OF GRADED AREAS, AS DESIGNATED BY THE ENGINEER, IMMEDIATELY AFTER GRADING IS COMPLETED WITHIN THOSE AREAS. SEED, FERTILIZE, AND EROSION MAT TOP-SOILED AREAS, AS DESIGNATED BY THE ENGINEER, WITHIN FIVE (5) CALENDAR DAYS AFTER PLACEMENT OF TOPSOIL. GRADED AREAS ARE LEFT EXPOSED FOR MORE THAN FOURTEEN (14) CALENDAR DAYS, SEED THOSE AREAS WITH TEMPORARY SEED.

- 11. STOCKPILE EXCESS MATERIAL OR SPOILS ON UPLAND AREAS AWAY FROM WETLANDS, FLOODPLAINS AND WATERWAYS. STOCKPILED SOIL SHALL BE PROTECTED AGAINST EROSION. IF STOCKPILED MATERIAL IS LEFT FOR MORE THAN FOURTEEN (14) CALENDAR DAYS, SEED THE STOCKPILE WITH TEMPORARY
- 12. EROSION CONTROL BMP'S ARE AT SUGGESTED LOCATIONS. THE ACTUAL LOCATIONS WILL BE DETERMINED BY THE CONTRACTORS ECIP AND BY THE ENGINEER. EROSION CONTROL BMP'S SHALL BE MAINTAINED UNTIL PERMANENT VEGETATION IS ESTABLISHED OR UNTIL THE ENGINEER DETERMINES THAT THE BMP IS NO LONGER REQUIRED.
- 13. REMOVAL OF EROSION CONTROL DEVICES IS INCLUDED IN THE COST OF THEIR RESPECTIVE BID ITEMS.
- 14. ASPHALTIC AND CONCRETE SURFACES SHALL BE SAWCUT AT THE MATCH LINE AS SHOWN ON THE PLAN OR AS DIRECTED BY THE ENGINEER.
- 15. DISTURBED AREAS AMOUNTING TO GREATER THAN 25 SQUARE FEET WILL BE PROTECTED WITH SILT FENCE ON THE DOWN SLOPE AND SHALL BE TOPSOILED, FERTILIZED, SEEDED AND HAVE EROSION MAT PLACED ON THE AREA.
- 16. FERTILIZER SHALL NOT BE USED NEAR NAVIGABLE WATERWAYS OR WETLANDS.
- 17. A CONVERSION FACTOR OF 2.0 TONS/CY IS USED TO ESTIMATE QUANTITIES FOR BASE AGGREGATE DENSE.
- 18. A CONVERSION FACTOR OF 1.75 TONS/CY IS USED TO ESTIMATE QUANTITIES FOR BASE COURSE, OPEN GRADED.
- 19. A CONVERSION FACTOR OF 112 LBS/IN/SY IS USED TO ESTIMATE QUANTITIES FOR HMA PAVEMENT.

PROJECT NO:3700-20-71

FIBER OPTIC

HUNDREDWEIGHT

FL

F0

CWT

HWY: STH 50

۷C

ΥD

COUNTY: KENOSHA

GENERAL NOTES

SHEET

Ε

FILE NAME : 020101_GN (GEN NOTES).DWG PLOT DATE: 1/29/2015 11:25 AM LAYOUT NAME : 020101_GN PLOT SCALE : NTS PLOT BY : SEH INC WISDOT/CADDS SHEET 42

R STH 50

LAYOUT NAME : 020301_TS

30.01

8.6' 10.0' 4.0'

CLEAR ZONE

10.0'

SHOULDER


4%


PLOT SCALE : 1 IN:20 FT

WISDOT/CADDS SHEET 42


SHEET

Ε





TYPICAL FINISHED SECTION - STH 50 STA 607+18.74 TO STA 611+75.00 STA 615+25.00 TO STA 619+82.89



WISDOT/CADDS SHEET 42


HWY:STH 50 Ε PROJECT NO:3700-20-71 COUNTY: KENOSHA TYPICAL SECTIONS SHEET FILE NAME : 020301_TS (TYP SECTIONS).DWG LAYOUT NAME : 020302_TS PLOT DATE: 1/27/2015 7:05 PM PLOT BY : SEH INC PLOT SCALE : 1 IN:20 FT

GENERAL NOTES:


GRANULAR BACKFILL REQUIRED AROUND INLET (INCIDENTAL TO CONSTRUCTION OF INLET)

DETAILS OF CONSTRUCTION, MATERIALS, AND WORKMANSHIP NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS, APPLICABLE SPECIAL PROVISIONS, S.D.D. FOR INLETS TYPE 1, 2, 3 & 4 AND UNDERDRAIN PIPE DETAIL.

CONNECT PIPE UNDERDRAIN TO INLETS. SEE S.D.D. "EDGEDRAIN OUTLET & OUTFALL MARKERS" FOR DETAILS.




DETAIL OF INLET W/CASTING




SIDE VIEW

CULVERT DITCH CHECKS





DETAIL OF CURB & GUTTER TERMINI

COUNTY: KENOSHA Ε PROJECT NO: 3700-20-71 HWY: STH 50 CONSTRUCTION DETAILS PAGE 01 OF 01 SHEET



ELEVATION VIEW AT FLAG LINE (GRATE AND CURB DETAILS OMITTED FOR DRAWING CLARITY)








DETAIL OF CURB AND GUTTER AT INLETS


(TYPE HM INLET SHOWN)


PROJECT NO: 3700-20-71 HWY: STH 50 COUNTY: KENOSHA CONSTRUCTION DETAILS PAGE 02 OF 01 SHEET E




































DETECTOR INPUT 3

3700-20-71

PLAN LOOP DETECTOR*(S) 11

PROJECT NO:



CONTROLLER LOGIC

PHASE NUMBER	PHASE LOCKING	DUAL ENTRY W / Ø	PHASE RECALL	PHASE ACTIVE
1		6		Х
2	Х	6	MIN	х
3				
4		8		х
5		2		х
6	Х	2	MIN	Х
7				
8		4		Х

TYPE OF INTERCONNECT/COMI	MUNICATION
NONE	
CLOSED LOOP	
TWISTED PAIR	
FIBER OPTIC*	
FIBER OPTIC (ETHERNET)	
RADIO	
CELL MODEM	Х

TYPE OF COORDINATION						
NONE		Х				
ТВС						
TRAFFIC RESPONSIVE						
ADAPTIVE						
*LOCATION OF MASTER						
CONTROLLER NO:	S-					
SIGNAL SYSTEM NO:	SS-					

TYPE OF LIGHTING						
BY OTHER AGENCY						
IN TRAFFIC CABINET	Х					
IN SEPARATE DOT LIGHTING CABINET						

TYPE OF PRE-EMPT						
NONE	Х					
RAILROAD						
EMERGENCY VEHICLE						
GTT						
TOMAR						
HARDWIRE						
OTHER						
LIFT BRIDGE						
QUEUE DETECTION						

DETECTOR LOGIC

COUNTY:

CALLED PHASE	1	4	5	8				
CALL OPTION	Х		X					
DELAY TIME								
EXTENTION OPTION	X	Х	X	Х				
EXTEND TIME		Х		Х				
USE ADDED INITIAL								
CROSS SWITCH PHASE	2		6					
DETECTOR INPUT	4	2	8	6	12	10	16	14
PLAN LOOP DETECTOR*(S)	21	42	61	82				
CALLED PHASE	2		,	•				
CALLED I HASE	2	4	6	8				
CALL OPTION	X	X X	X	X				
CALL OPTION								
CALL OPTION DELAY TIME	Х	Х	X	Х				
CALL OPTION DELAY TIME EXTENTION OPTION	Х	Х	X	Х				

51

81

41

11

HWY: STH 50

15

13

19	17	23	21	27	25	31	29	DETECTOR INPUT
								PLAN LOOP DETECTOR*(S)
								CALLED PHASE
								CALL OPTION
								DELAY TIME
								EXTENTION OPTION
								EXTEND TIME
								USE ADDED INITIAL
								CROSS SWITCH PHASE

20	18	24	22	28	26	32	30	DETECTOR INPUT
								PLAN LOOP DETECTOR*(S)
								CALLED PHASE
								CALL OPTION
								DELAY TIME
								EXTENTION OPTION
								EXTEND TIME
								USE ADDED INITIAL
								CROSS SWITCH PHASE

SEQUENCE OF OPERATIONS

STH 50 & CTH O (368TH AVENUE) TOWN OF WHEATLAND KENOSHA COUNTY CABINET TYPE: TS2 SIGNAL NO: \$30-1419 CONTROLLER TYPE: ECONOLITE DATE: 01/15 PAGE NO. 3 OF 3

SHEET NO:

KENOSHA COUNTY PLOT DATE : 1/29/2015 PLOT NAME : 024009_sp_ph FILE NAME: 024009_sp_ph.ppt PLOT BY : SEH INC PLOT SCALE: 1:1

2

Ŋ
4ILS
Ę
뭏
Ω
á
⊢
SEC
뒥
PIC
Ξ
02
O
Š
Ź
움
ETS
黑
Z
8
0020
370
ĕ
- 1
ΙM
Ę
15
99
128766
乊
Ś
WITS
\leq
Ŕ
?
±
ΨŦ
<u>م</u>
ĸ

PROJECTID:	3700-20-71
INTERSECTION:	STH 50 & CTH O (368TH AVENUE)

	BLK - BLACK	RED - RED	GRN - GREEN
SIGNAL WIRE COLOR CODING	WHT - WHITE	BLU - BLUE	ORG - ORANGE

	AWG 14 # OF					SIGNAL	INDICATION WIRE	COLOR				
св_то		HEAD NO.	RED	YELLOW	GREEN	<red></red>	<yellow></yellow>	<green></green>	<flashing> <yellow></yellow></flashing>	D/WALK	WALK	PED BUTTON
SB1	12	1	RED	ORG	GRN							
		9				RED/BLK	ORG/BLK	GRN/BLK	BLU/BLK	-		
SB2	7	10				RED	ORG	GRN	BLU/BLK			
SB7	12	7	RED	ORG	GRN							
		8	RED	ORG	GRN							
SB8	12	12	RED	ORG	GRN					annon condition of the risk — set frameworks and through the first state of		
		14	RED/BLK	ORG/BLK	GRN/BLK							
SB9	12	13	RED	ORG	GRN							
SB10	12	4				RED	ORG	GRN	BLU/BLK			
		6	RED/BLK	ORG/BLK	GRN/BLK							
SB11	7	5				RED	ORG	GRN	BLU/BLK			
SB15	12	2	RED	ORG	GRN		-					
		3	RED	ORG	GRN	-						
SB16	12	11	RED	ORG	GRN							-
		15	RED/BLK	ORG/BLK	GRN/BLK							
SB17	7	16	RED	ORG	GRN							

EQUIPMENT GROUNDING CONDUCTOR 10 AWG GREEN XLP								
FROM	то							
CB1	SB1							
SB1	SB2							
SB2	SB7							
SB7	SB8							
SB8	SB8							
SB9	SB10							
SB10	SB11							
SB11	SB15							
SB15	SB16							
SB16	SB17							
SB17	CB1							

PULL BOX BOND	
FROM	то
PB1	CB1
PB2	SB1
PB3	SB2
PB4	SB2
PB5	SB7
PB6	SB8
PB7	SB9
PB8	SB10
PB9	SB11
PB10	SB11
PB11	SB15
PB12	SB16
PB13	SB17
PB14	CB1

LIGH TING U	F 2-10 AWGW/									
GR	GROUND									
FROM	TO									
CB1	SB3									
SB3	SB4									
SB3	SB9									
SB4	SB5									
SB5	SB6									
CB1	SB17									
SB17	SB11									
SB11	SB12									
SB12	SB13									
SB13	SB14									

RADAR DET	RADAR DETECTION CABLE									
FROM	TO									
CB1	RA1 (SB11)									
CB1	RA2 (SB3)									
CB1	RA3 (SB9)									
CB1	RA4 (SB17)									
CB1	RM1 (SB15)									
CB1	RM2 (SB7)									
CB1	RM3 (SB9)									
CB1	RM4 (SB1)									

*USE THE WHITE CONDUCTOR IN THE CABLE ASSEMBLY AS THE GROUNDED CONDUCTOR FOR ALL TRAFFIC SIGNAL INDICATIONS

*ENSURE THE GROUNDED CONDUCTOR IN THE FEEDER CABLE AND THE POLE CABLES ARE BOTH 12" LONGER THAN THE UNGROUNDED CONDUCTORS.
*AT THE SIGNAL BASES, CONNECT ONE TERMINAL FROM THE PEDESTRIAN PUSH BUTTONS TO THE COLOR INDICATED IN THE CHART. CONNECT THE OTHER TERMINAL TO THE GROUNDED CONDUCTOR

"OTHER" COLUMN MAY INCLUDE SHADOW BOX SIGN



PROJECT NO:3700-20-71

HWY:STH 50

COUNTY: KENOSHA

CABLE ROUTING


PLOT SCALE : 1 IN:100 FT


E


FILE NAME: 024030_CR (CABLE ROUTING).DWG LAYOUT NAME - 024010_CR (CABLE ROUTING)


PLOT DATE : 1/29/2015 9:01 AM


LAYOUT NAME : 024010_CR











FILE NAME : 025000_TC.DWG

AND


PLOT DATE: 1/27/2015 7:09 PM

LAYOUT NAME : 025001_SP


PLOT SCALE : 1 IN:200 FT

WISDOT/CADDS SHEET 42

FOLDER PATH:P:\UZ\W\WITSE\128766\15-CIVIL 3D\37002001\SHEETSPLAN\SEC 02



FOLDER PATH:P:\UZ\W\WITSE\128766\15-CIVIL 3D\37002001\SHETSPLAN\SEC 02



DATE 25 LINE	MAR15	EST	IMATE	OFQUAN	T I T I E S 3700-20-71	
NUMBER	ITEM	ITEM DESCRIPTION	UNI T	TOTAL	QUANTI TY	
0010	204.0100	Removing Pavement	SY	1, 157. 000	1, 157. 000	
0020	204. 0220	Removing Inlets	EACH	2.000	2.000	
0030	204. 0245	Removing Storm Sewer (size) 01. 18-Inch	LF	29. 000	29. 000	
0040	205. 0100	Excavation Common	CY	1, 829. 000	1, 829. 000	
0040	213. 0100	Finishing Roadway (project) 01.	EACH	1, 829, 000	1, 829. 000	
0030	213.0100	3700-20-71	EACH	1.000	1.000	
0060	305. 0110	Base Aggregate Dense 3/4-Inch	TON	26. 000	26. 000	
0070	305. 0120	Base Aggregate Dense 1 1/4-Inch	TON	1, 251. 000	1, 251. 000	
0800	310. 0110		TON	1, 227. 000		
		Base Aggregate Open Graded			1, 227. 000	
0090	415. 0090	Concrete Pavement 9-Inch	SY	3, 195. 000	3, 195. 000	
0100	416. 0610	Drilled Tie Bars	EACH	1, 010. 000	1, 010. 000	
0110	416. 0620	Drilled Dowel Bars	EACH	100.000	100.000	
0120	520. 8000	Concrete Collars for Pipe	EACH	1.000	1.000	
0130	522. 1015	Apron Endwalls for Culvert Pipe Reinforced Concrete 15-Inch	EACH	1. 000	1. 000	
0140	601. 0551	Concrete Curb & Gutter 4-Inch Sloped	LF	2, 590. 000	2, 590. 000	
0150	602. 0410	36-Inch Type A Concrete Sidewalk 5-Inch	SF	3, 755. 000	3, 755. 000	
				· 		
0160	608. 0312	Storm Sewer Pipe Reinforced Concrete Class III 12-Inch	LF	613. 000	613. 000	
0170	608. 0315	Storm Sewer Pipe Reinforced Concrete	LF	474. 000	474. 000	
0190	600 0210	Class III 15-Inch	LF	20,000	20,000	
0180	608. 0318	Storm Sewer Pipe Reinforced Concrete Class III 18-Inch	LF	29. 000	29. 000	
0190	611. 0627	Inlet Covers Type HM	EACH	18. 000	18. 000	
0200	611. 0636	Inlet Covers Type HM-S	EACH	2. 000	2. 000	
0210	611. 1005	Catch Basins 5-FT Diameter	EACH	1. 000	1. 000	
0220	611. 3004	Inlets 4-FT Diameter	EACH	2. 000	2. 000	
0230	611. 3230	Inlets 2x3-FT	EACH	17. 000	17.000	
0240	612. 0106	Pipe Underdrain 6-Inch	LF	1, 800. 000	1, 800. 000	
0250	619. 1000	Mobilization	EACH	1. 000	1. 000	
0260	620. 0300	Concrete Median Sloped Nose	SF	216. 000	216. 000	
0270	625.0500	Sal vaged Topsoi I	SY	3, 490. 000	3, 490. 000	
0280	628. 1504	Silt Fence	LF	560. 000	560. 000	
0290	628. 1520	Silt Fence Maintenance	LF	560. 000	560. 000	
0300	628. 1905	Mobilizations Erosion Control	EACH	2. 000	2. 000	
0310	628. 1910	Mobilizations Emergency Erosion Control	EACH	2. 000	2. 000	
0320	628. 2002	Erosion Mat Class I Type A	SY	3, 490. 000	3, 490. 000	
0330	628. 7005	Inlet Protection Type A	EACH	20.000	20.000	
0340	628. 7015	Inlet Protection Type C	EACH	20. 000	20. 000	
0350	628. 7555	Culvert Pipe Checks	EACH	50. 000	50. 000	
0360	629. 0210	Fertilizer Type B	CWT	2.000	2.000	
0370	630. 0130	Seeding Mixture No. 30	LB	64.000	64.000	
0380	630. 0200	Seeding Temporary	LB	128. 000	128. 000	
0390	634. 0616	Posts Wood 4x6-Inch X 16-FT	EACH	3. 000	3. 000	
0400	634. 0618	Posts Wood 4x6-Inch X 18-FT	EACH	12. 000	12. 000	
0410	427 2210	Signs Type II Reflective H	CE CE	272 500	272 500	
0410	637. 2210		SF	272. 500	272. 500	
0420	637. 2215	Signs Type II Reflective H Folding	SF	59. 680	59. 680	
0430	638. 2102	Moving Signs Type II	EACH	1. 000	1. 000	
0440	638. 2602	Removing Signs Type II	EACH	12. 000	12. 000	
0450	638. 3000	Removing Small Sign Supports	EACH	11. 000	11. 000	
0460	642. 5001	Field Office Type B	EACH	1. 000	1. 000	
0470	643. 0100	Traffic Control (project) 01. 3700-20-71		1. 000	1. 000	
0480	643. 0300	Traffic Control Drums	DAY	5, 333. 000	5, 333. 000	
0490	643. 0420	Traffic Control Barricades Type III	DAY	76. 000	76. 000	
20	3.3.3.20	The source sall rodges type till	2	. 5. 666	. 0. 000	

DATE 25	MAR15	E S ⁻	TIMAT	E OF QUANT		
LI NE NUMBER	LTEM	LTEM DECCRIPTION	LINII T	TOTAL	3700-20-71	
0500	I TEM 643.0715	ITEM DESCRIPTION Traffic Control Warning Lights Type C	UNI T DAY	TOTAL 5, 333. 000	QUANTI TY 5, 333. 000	
0510	643. 0800	Traffic Control Arrow Boards	DAY	76. 000	76. 000	
0520	643.0900	Traffic Control Signs	DAY	608.000	608.000	
0530	643. 2000	Traffic Control Detour (project) 01. 3700-20-71	EACH	1. 000	1. 000	
0540	643.3000	Traffic Control Detour Signs	DAY	2, 432. 000	2, 432. 000	
0550	645. 0111	Geotextile Fabric Type DF Schedule A	SY	1, 200. 000	1, 200. 000	
0560	646. 0106	Pavement Marking Epoxy 4-Inch	LF	7, 798. 000	7, 798. 000	
0570 0580	646.0600	Removing Pavement Markings Pavement Marking Grooved Wet Reflective	LF LF	1, 691. 000 1, 063. 000	1, 691. 000 1, 063. 000	
0360	040.0041.3	Contrast Tape 4-Inch	LI	1,003.000	1,003.000	
0590	646. 0843. S	Pavement Marking Grooved Wet Reflective Contrast Tape 8-Inch	LF	1, 708. 000	1, 708. 000	
0600	647. 0456	Pavement Marking Curb Epoxy	LF	20.000	20.000	
0610	647. 0606	Pavement Marking Island Nose Epoxy	EACH	2. 000	2. 000	
0620	647.0726	Pavement Marking Diagonal Epoxy 12-Inch	LF LF	360. 000	360. 000	
0630	652. 0225	Conduit Rigid Nonmetallic Schedule 40	LF	988. 000	988. 000	
0640	652. 0235	2-Inch Conduit Rigid Nonmetallic Schedule 40	LF	555. 000	555. 000	
	/ED 0/15	3-Inch	1.5			
0650	652. 0615	Conduit Special 3-Inch	LF 	752. 000	752. 000	
0660	653. 0140	Pull Boxes Steel 24x42-Inch	EACH	14. 000	14.000	
0670	654. 0101	Concrete Bases Type 1	EACH	4. 000	4. 000	
0680	654. 0102	Concrete Bases Type 2	EACH	2. 000	2.000	
0690	654. 0105	Concrete Bases Type 5	EACH	7. 000	7. 000	
0700	654. 0110	Concrete Bases Type 10	EACH	2. 000	2. 000	
0710	654. 0113	Concrete Bases Type 13	EACH	2. 000	2.000	
0720	654. 0217	Concrete Control Cabinet Bases Type 9	EACH	1. 000	1. 000	
0730	655. 0230	Special Cable Traffic Signal 5-14 AWG	LF	441. 000	441. 000	
0730	655. 0240	Cable Traffic Signal 7-14 AWG	LF LF	778. 000	778. 000	
0750	655. 0260	Cable Traffic Signal 12-14 AWG	LF	2,001.000	2, 001. 000	
0760	655. 0320	Cable Type UF 2-10 AWG Grounded	LF	1, 845. 000	1, 845. 000	
0770	655. 0515	Electrical Wire Traffic Signals 10 AWG	LF	1, 968. 000	1, 968. 000	
0780	655. 0615	Electrical Wire Lighting 10 AWG	LF	1, 512. 000	1, 512. 000	
0790	656. 0200	Electrical Service Meter Breaker Pedestal (Lecation) 01 Sth 50 % Cth 0	LS	1. 000	1. 000	
0800	657. 0100	Pedestal (location) 01. Sth 50 & Cth 0 Pedestal Bases	EACH	4. 000	4. 000	
0810	657. 0255	Transformer Bases Breakaway 11 1/2-Inch	EACH	9. 000	9. 000	
0820	657. 0305	Bolt Circle Poles Type 2	EACH	1. 000	1. 000	
0830	657. 0305	Polles Type 3	EACH	1. 000	1. 000	
0840	657. 0310	Poles Type 5 Poles Type 5-Alumi num	EACH	7. 000	7. 000	
0850	657. 0420	Traffic Signal Standards Aluminum 13-FT	EACH	2. 000	2. 000	
0860	657. 0425	Traffic Signal Standards Aluminum 15-FT	EACH	2. 000	2. 000	
0870	657. 0425	Luminaire Arms Single Member 4-Inch	EACH	2. 000	2.000	
		Clamp 6-FT				
0880	657. 0610	Luminaire Arms Single Member 4 1/2-Inch	EACH	8. 000	8. 000	
0890	657. 1350	Clamp 6-FT Install Poles Type 10	EACH	2. 000	2. 000	
0900	657. 1355	Install Poles Type 10	EACH	2. 000	2.000	
0910	657. 1520	Install Monotube Arms 20-FT	EACH	2. 000	2.000	
0920	657. 1540	Install Monotube Arms 40-FT	EACH	2.000	2.000	
0930	657. 1808	Install Luminaire Arms Steel 8-FT	EACH	2.000	2.000	
0940	658. 0110	Traffic Signal Face 3-12 Inch Vertical	EACH	12. 000	12. 000	

_

				E	ARTHWORK DATA SU	JMMARY TABLE						
DIVISION	STAGE	CATEGORY CODE	FROM/TO STATION	LOCATION	205.0100 COMMON EXCAVATION (1)	SALVAGED/ UNUSABLE PAVEMENT MATERIAL (4)	AVAILABLE MATERIAL (2)	UNEXPANDED FILL	EXPANDED FILL (3)	MASS ORDINATE +/- (4)	DIVISION WASTE	208.0100 DIVISION BORROW
					сит				FACTOR 1.25			
1	1	0010 0010	605+88 - 613+30 613+72 - 621+15	STH 50 STH 50	815 1014	184 177	631 837	453 399	566 499	65 338	65 338	
	STAGE 1 SUBTO	TAL			1829	361	1468	852	1065	403	403	0
IVISION 1 SUBT	OTAL				1829	361	1468	852	1065	403	403	0
					1829	361	1468	852	1065	403	403	0
ITEM TOTALS			<u>-</u>		TOTAL COMMON EXC		1829	CY				

COUNTY: KENOSHA Ε PROJECT NO:3700-20-71 HWY:STH 50 MISCELLANEOUS QUANTITIES SHEET

¹⁾ COMMON EXCAVATION IS THE SUM OF THE CUT, ITEM NUMBER 205.0100. 2) AVAILABLE MATERIAL = CUT - SALVAGED/UNUSABLE PAVEMENT MATERIAL

³⁾ EXPANDED FILL. FACTOR = 1.25

⁴⁾ THE MASS ORDINATE + OR - QUANTITY CALCULATED FOR THE STAGE. PLUS QUANTITY INDICATES EXCESS OF MATERIAL WITHIN THE STAGE AND IS CATEGORIZED AT DIVISION WASTE. MINUS INDICATES A SHORTAGE OF MATERIAL WITHIN THE STAGE AND IS CATEGORIZED AS DIVISION BORROW, ITEM NUMBER 208.0100.

STATION	LOCATION	REMOVING PAVEMENT 204.0100 SY	REMOVING INLETS 204.0220 EACH	REMOVING STORM STORM SEWER 18-INCH 204.0245 LF
609+27 - 613+30	LT & RT	593	1	
612+00	4.5' LT		1	15
613+72 - 617+72	LT & RT	564		
615+00	4.8' RT			14
Kara Line	TOTAL	1157	2	20

BASE AGGREGATES

STATION - STATION	LOCATION	305.0110 BASE AGGREGATES 3/4-INCH TON	305.0120 BASE AGGREGATES 1 1/4-INCH TON	310.0110 BASE AGGREGATES OPEN GRADED TON	REMARKS
STH 50					
605+88 - 607+18	RT	11	11	20	EB SHOULDER
605+88 - 613+30	LT/RT		405	363	EB TURN LANE
607+72 - 613+08	LT		148	112	WB SHOULDER
611+75 - 613+01	LT		26	64	EBMEDIAN
612+30 - 613+23	RT		19	46	EB SPLITTER ISLAND
613+72 - 621+15	LT/RT		405	363	WB TURN LANE
613+79 - 614+73	LT		19	46	WB SPLITTER ISLAND
613+93 - 619+90	RT		178	121	EB SHOULDER
614+00 - 615+25	RT		26	63	WB MEDIAN
619+83 - 621+15	LT	15	15	28	WB SHOULDER
	TOTALS	26	1251	1227	

PAVING ITEMS

STATION - STATION	LOCATION	415.0090 CONCRETE PAVEMENT 9-INCH SY	416.0610 DRILLED TIE BARS EACH	416.0620 DRILLED DOWEL BARS EACH	601.0551 CONCRETE CURB & GUTTER 4-NCH SLOPED 36-NCH TYPE A LF	602.0410 CONCRETE SIDEWALK 5-INCH SF	620.0300 CONCRETE MEDIAN SLOPED NOSE SF
STH 50							
605+88 - 613+30		1343	303	25	584		
607+72 - 613+08	LT	240	202	25	500	1075	28
612+21 - 613+30	RT				190	810	80
613+72 - 614+80	LT				190	810	
613+72 - 621+15		1341	303	25	584		80
613+93 - 619+50	RT	271	202	25	542	1060	28
ITEM TOTALS		3195	1010	100	2590	3755	216

STORM SEWER STRUCTURE ITEMS

522.1015 APRON ENDWALLS

			FOR CULVERT PIPE	CATH BASINS	INLET	S	NLET	COVERS
STRUCTURE NUMBER	STATION	LOCATION	REINFORCED CONCRETE 15-INCH EACH	611.1005 5-FT DIAMETER EACH.1005	611.3004 4-FT DIAMETER EACH	611.3230 2x3-FT EACH	611.0627 TYPE HM EACH	611.0636 TYPE HM-S EACH
						-		
1	607+35.16	1.3' RT	1	-		-		-
2	609+00.00	7.8' RT	•		-	1	1	•
3	611+25.00	3.4' LT	~			1	1	-
4	611+99.78	7.1' LT			1			1
5	611+99.67	19.6' LT	27			1	1	2
6	612+78.74	8.5 LT	0.0		1-4	1	1	(-
7	612+78.74	19.5' LT	(4)	-	1.9	1	1	
8	612+85.85	8.09 RT	o¥0	1		1000	1	-
9	613+20.29	8.49 RT	(2)		1.2	1	1	-
10	613+20.29	19.50 RT				1	1.	- 2
11	614+12.28	18.9' RT			49.1	1	1	-
12	614+12.36	8.5' RT		0.00		1	1	-
13	614+12.50	8.5' LT			16	1	1	U.S.
14	614+12.50	19.5' LT			11.4	1	1	2
15	614+70.54	8.5' RT	0.0		1.4	1	1	
16	614+70.36	8.6' LT			1940	1	1	
17	614+70.24	19.5' LT		-		1	1	
18	615+00.05	7.3' RT	1.00		1	1.51	4	1
19	615+00.15	19.5' RT				1	1	
20	615+75.30	3.4' RT			10.4	1	1	9-
21	618+24.00	8.9' LT				1	1	•
TEM TOTALS			1	1	2	17	18	2

STORM SEWER PIPE REINFORCED CONCRETE CLASS III

520.8000

					520.0000			
					CONCRETE	608.0312	608.0315	608.0318
PIPE		INLET	OUTLET	SLOPE	COLLAR	12-INCH	15-INCH	18-INCH
NUMBER	STATION - STATION	ELEV	ELEV	FT/FT	EACH	LF	LF	LF
P-1	607+39 - 609+00	805.50	803.22	0.014		-	161	
P-2	609+00 - 611+25	803.12	799.10	0.018	4		225	
P-3	611+25 - 612+00	799.00	797.40	0.021			75	-
P-4	612+00	797.05	796.81	0.020		-		12
P-5	612+00 - 612+79	798.60	797.65	0.012		79		
P-6	612+79	798.85	798.70	0.014		11	-	-
P-7	612+86 - 613+20	796.85	796.47	0.012		33	1.9	
P-8	613+20	797.10	796.95	0.014	140	11	-	1.2
P-9	614+12	798.05	797.90	0.015	3.1	10	4.1	
P-10	614+12	798.10	797.90	0.012		17	-	-
P-11	614+13	798.35	798.20	0.014		11		- 2
P-12	614+13 - 614+71	797.80	797.17	0.011		58		1.
P-13	614+71	797.35	797.17	0.011	4	17		0.2
P-14	614+71	797.50	797.36	0.013		11	-	1.5
P-15	614+77 - 615+00	797.07	796.74	0.011		30		
P-16	615+00	796.63	796.49	0.011			13	-
P-17	615+00	796.14	795.83	0.018	1			17
P-18	615+00 - 615+75	797.80	796.74	0.014	-	75		
P-19	615+75 - 618+25	800.20	797.90	0.009	•	250		
M TOTALS					1	613	474	29

PIPE UNDER DRAIN

645.0111 612.0106 GEOTEXTILE FABRIC 6-INCH TYPE DE SCHEDIJI E A

STATION - STATION	LOCATION	6-INCH LF	TYPE DF SCHEDULE A SY	REMARKS
STH 50 605+88 - 613+08	LT/RT	720	500	ALONG TURN LANE
610+00 611+88 - 612+00 613+93 - 620+74 615+00 - 615+15	LT LT LT/RT RT	10 20 725 25	7 14 503 17	CONNECT EXISTING TO PROPOSED INLET ALONG TURN LANE TO PROPOSED INLET
UNDISTRIBUTED		300	158	
	TOTAL	1800	1200	

PROJECT NO:3700-20-71 HWY:STH 50

COUNTY: KENOSHA

MISCELLANEOUS QUANTITIES

LAYOUT NAME : 030202_MQ

PLOT SCALE : NTS

WISDOT/CADDS SHEET 42

SHEET

Ε

FILE NAME : P:\UZ\W\WITSE\128766\15-CIVIL 3D\37002001\SHEETSPLAN\SEC 03 MISCELLANEOUS QTY\030200_MQ (ROADWAY).DWG

PLOT DATE: 1/29/2015 10:37 AM

PLOT BY : SEH INC

							EF	ROSION CONTR	OL ITEMS					
		RESTORATION	ITEMS			LOCATION	628.1504 SILT FENCE LF	628.1520 SILT FENCE MAINTENANCE LF	628.7005 INLET PROTECTION TYPE A EACH	628.7015 NLET PROTECTION TYPE C EACH	628.7555 N CULVERT DITCH CHECKS EACH	EPOSI	ON CONTROL MOBILIZA	ATIONS
LOCATION	625.0500 SALVAGED TOPSOIL SY	628.2002 EROSION MAT CLASS I TYPE A SY	629.0210 FERTILIZER TYPE B CWT	630.0130 SEEDING MIXTURE NO. 30 LB	630.0200 SEEDING TEMPORARY LB	STH 50 & CTH O INTERSECTION NW QUADRANT NE QUADRANT SW QUADRANT SE QUADRANT	102 100 175 88	102 100 175 88		EACH	- - 10 20	LOCATION	628.1905 MOBILIZATIONS EROSION CONTROL EACH	628.1910 MOBILIZATIONS EMERGENCY EROSION CONTR
STH 50 605+88 - 611+75	1221	1221	0.77	22.0	44.0	STH 50						PROJECT (3700-20-71)		2
615+25 - 621+15	1237	1237	0.78	22.3	44.5	607+35					10			
NW QUADRANT	70	70	0.04	1.3	2.5	609+00	-		1	1	-	ITEM TOTALS	2	2
SW QUADRANT	257	257	0.16	4.6	9.2	611+25			1	1		77 22 22 27 24 27 22 27		
SE QUADRANT	59	59	0.04	1.1	2.1	612+00	0.00	2.	2	2	-			
NE QUADRANT	64	64	0.04	1.2	2.3	612+79			2	2	-			
	511	234	12.22	35.2	22.7	612+86	-		1	1				
UNDISTRIBUTED	582	582	0.37	11.5	22.9	613+20			2	2	-			
						614+12	-	1.5	4	4	-			
ITEM TOTALS	3490	3490	2	64	128	614+70		-	3	3	-			
						615+00			2	2	-			
						615+75		(3)	1	1	C-			
						618+24			1	1	-			
						UNDISTRIBUTED	95	95	1.		10			
						ITEM TOTALS	560	560	20	20	50			
					·								SAWING	Like Street
STATION	N. STATION		643.0300 BA	643.0420 ARRICADES TYPE III	643.0715 WARNING 643.0800 LIGHTS ARROW 643.0900 TYPE C BOARDS SIGNS DAYS DAYS DAYS		SIGN		CONTROL UR SIGNS	643.3000 TOTAL			690.0150 ASPHALT CATION LF	690.0250 CONCRETE LF
STATION STH 50	N - STATION	LOCATION DAY	643.0300 BA	643.0420 ARRICADES	WARNING 643.0800 LIGHTS ARROW 643.0900		SIGN CODE			TOTAL		STATION LC STH 50 605+88 607+72	ASPHALT	CONCRETE
			643.0300 BA DRUMS /S DAYS	643.0420 ARRICADES TYPE III DAYS	WARNING 643.0800 LIGHTS ARROW 643.0900 TYPE C BOARDS SIGNS		CODE M4-8	MESSAGE "DETOUR"	EACH DA	TOTAL YS DAYS		STH 50 605+88	ASPHALT OCATION LF	CONCRETE
STH 50	15	LOCATION DAY	643.0300 BA DRUMS YS DAYS	643.0420 ARRICADES TYPE III	WARNING 643.0800 LIGHTS ARROW 643.0900 TYPE C BOARDS SIGNS DAYS DAYS DAYS		M4-8 M3-1	MESSAGE "DETOUR" "NORTH"	EACH DA' 18 31 7 31	TOTAL DAYS B 684 B 266		STH 50 605+88 607+72	ASPHALT DCATION LF RT 3 LT 3	CONCRETE LF
STH 50 605+88 - 621+ 605+88 - 621+	15 15	LOCATION DAY	643.0300 BA DRUMS YS DAYS	643.0420 ARRICADES TYPE III DAYS	WARNING 643.0800 LIGHTS ARROW 643.0900 TYPE C BOARDS SIGNS DAYS DAYS DAYS 2297 38 304		M4-8 M3-1 M3-3	MESSAGE "DETOUR" "NORTH" "SOUTH"	EACH DA 18 3: 7 3: 11 3:	TOTAL YS DAYS 3 684 3 266 3 418		STH 50 605+88 607+72 609+27 - 613+30	ASPHALT CATION LF RT 3 LT 3 RT LT CL	428 114 22
STH 50 605+88 - 621+7 605+88 - 621+7 STH 50 & CTH C	15 15 O INTERSECTION	LOCATION DAY LT 38 RT 38	643.0300 BA DRUMS VS DAYS 2297 2297	643.0420 ARRICADES TYPE III DAYS	WARNING LIGHTS ARROW 643.0900 643.00000		M4-8 M3-1 M3-3 M1-5A	MESSAGE "DETOUR" "NORTH"	EACH DA 18 31 7 31 11 31 18 31	TOTAL YS DAYS 3 684 3 266 3 418 3 684		STH 50 605+88 607+72 609+27 - 613+30 612+20 - 613+08	ASPHALT CATION LF RT 3 LT 3 RT LT LT	CONCRETE LF 428 114
STH 50 605+88 - 621+7 605+88 - 621+7 STH 50 & CTH C	15 15 O INTERSECTION T	LOCATION DAY	643.0300 BA DRUMS VS DAYS 2297 2297	643.0420 ARRICADES TYPE III DAYS	WARNING LIGHTS ARROW 643.0900 643.00000		M4-8 M3-1 M3-3 M1-5A MO6-1	MESSAGE "DETOUR" "NORTH" "SOUTH"	EACH DA 18 3: 7 3: 11 3: 18 3: 6 3:	TOTAL DAYS 3 684 3 266 3 418 3 684 3 228		STH 50 605+88 607+72 609+27 - 613+30 612+20 - 613+08 613+08 - 613+30	RT 3 LT 3 RT LT CL LT CL	428 114 22
STH 50 605+88 - 621+' 605+88 - 621+' STH 50 & CTH C NW QUADRANT NE QUADRANT	15 15 O INTERSECTION T	LOCATION DAY LT 38 RT 38	643.0300 BADRUMS //S DAYS 2297 2297 152 218	643.0420 ARRICADES TYPE III DAYS	WARNING LIGHTS ARROW 643.0900 ARROW 643.0900 BOARDS SIGNS DAYS DAYS 2297 38 304 2297 38 304 152 218		M4-8 M3-1 M3-3 M1-5A M06-1 M05-1L	MESSAGE "DETOUR" "NORTH" "SOUTH"	### BACH DA 18 33 7 33 11 33 18 33 6 33 3 33	TOTAL DAYS 3 684 3 266 3 418 3 684 3 228 3 114		STH 50 605+88 607+72 609+27 - 613+30 612+20 - 613+08 613+08 - 613+30 613+72 - 617+76 613+72 - 613+93 613+93 - 614+72	ASPHALT CATION LF RT 3 LT 3 RT LT CL LT CL RT	428 114 22 430
STH 50 605+88 - 621+' 605+88 - 621+' STH 50 & CTH C NW QUADRANT NE QUADRANT SW QUADRANT	15 15 O INTERSECTION T T	LOCATION DAY LT 38 RT 38 N 38 38	643.0300 BADRUMS VS DAYS 2297 2297 152 218 218	643.0420 ARRICADES TYPE III DAYS	WARNING LIGHTS TYPE C DAYS DAYS BOARDS SIGNS DAYS DAYS DAYS 2297 38 304 152 218 218		M4-8 M3-1 M3-3 M1-5A MO6-1	MESSAGE "DETOUR" "NORTH" "SOUTH"	EACH DA 18 3: 7 3: 11 3: 18 3: 6 3:	TOTAL DAYS 3 684 3 266 3 418 3 684 3 228 3 114		STH 50 605+88 607+72 609+27 - 613+30 612+20 - 613+08 613+08 - 613+30 613+72 - 617+76 613+72 - 613+93 613+93 - 614+72 619+90	RT 3 LT 3 RT LT CL LT CL RT RT RT S	428 114 22 430 22
STH 50 605+88 - 621+' 605+88 - 621+' STH 50 & CTH C NW QUADRANT NE QUADRANT	15 15 O INTERSECTION T T	LOCATION DAY LT 38 RT 38	643.0300 BADRUMS VS DAYS 2297 2297 152 218 218	643.0420 ARRICADES TYPE III DAYS	WARNING LIGHTS ARROW 643.0900 ARROW 643.0900 BOARDS SIGNS DAYS DAYS 2297 38 304 2297 38 304 152 218		M4-8 M3-1 M3-3 M1-5A M06-1 M05-1L	MESSAGE "DETOUR" "NORTH" "SOUTH"	### BACH DA 18 33 7 33 11 33 18 33 6 33 3 33	TOTAL DAYS 8 684 8 266 8 418 8 684 8 228 8 114 8 38		STH 50 605+88 607+72 609+27 - 613+30 612+20 - 613+08 613+08 - 613+30 613+72 - 617+76 613+72 - 613+93 613+93 - 614+72	ASPHALT CATION LF RT 3 LT 3 RT LT CL LT CL RT	428 114 22 430 22

							PAVE	MENTMAR	KING							
STATION - STATION	LOCATION	EPOXY		646,0600 REMOVING PAVEMENT MARKINGS LF	646.0841.S GROOVED WET REFLECTIVE CONTRAST TAPE 4-INCH LF	646.0 GROOVI REFLE CONTRAST	CTVE	647.0456 CURB EPOXY LF		646.0726 PAVEMENT MARKING DIAGONAL EPOXY 12-INCH LF	SPV.0060.01 GROOVED CONTRAST PREFORMED THERMOPLASTIC ARROWS TYPE 2 EACH	SPV.0060.02 GROOVED CONTRAST PREFORMED THERMOPLASTIC WORDS EACH	SPV.0090.01 GROOVED CONTRAST PREFORMED THERMOPLASTIC STOP LINE 18-INCH LF	REMARKS	INCENTIVE STRENG	TH CONCRETE PAVEMEN 715.0415 DOL
STH 50 604+25 - 625+00	RT & LT	4220	3578	1518	1062.5	1624	84	20	2	360	2	2	141	"ONLY"	STH 50 605+88 - 621+15	500
CTH O/368TH AVE 45+90'O' - 47+70'O'	CL		16	173		¥			i Vi				-			500
BID ITEM TOTAL		4,220	3,578	-		1624	84									

COUNTY: KENOSHA

FILE NAME : P:\UZ\W\WITSE\128766\15-CIVIL 3D\37002001\SHEETSPLAN\SEC 03 MISCELLANEOUS QTY\030200_MQ (ROADWAY).DWG

HWY:STH 50

PROJECT NO:3700-20-71

PLOT DATE : 3/5/2015 2:28 PM

PLOT BY : SEH INC

MISCELLANEOUS QUANTITIES

LAYOUT NAME : 030203_MQ

PLOT SCALE : NTS

SHEET

3	
J	3
	J

	II PERMANENT SI	<u></u>		637.2210	637.2215	634.0616	634.0618	638.2602	638.3000	638.2102		CATEGORY CODE 1000
			TYPE II			POSTS	POSTS		REMOVING	MOVING		
			SIGN	SIGNS	SIGNS	WOOD	WOOD	REMOVING	SMALL	SIGNS	MOUNT	
SIGN	SIGN	SIGN	SIZE	TYPE II	TYPE II	4X6-INCH	4X6-INCH	SIGNS	SIGN	TYPE II	ON SAME	
NO.	CODE	MESSAGE	W x H		REFLECTIVE H	X 16-FT	X 18-FT	TYPE II	SUPPORTS		POST AS	REMARKS
			[IN.] x [IN.]	[SF]	FOLDING	[EA]	[EA]	[EA]	[EA]	[EA]	SIGN#	NEW SIGN LOCATION
	Do 001 (0)			10.50	[SF]		,					
100	R3-20L(3)		36 x 54	13.50			1					
101	J12-1(3)		36 x 66	16.50			1	1	1			
	M1-5A	CTH O	36 x 36									
	M5-1L		30 x 30									
102	R5-1A(3)		42 x 30	8.75		1		1	1			
103	M1-94H	368TH AVE	60 x 18	7.50								ON SIGNAL MAST ARM
104	J13-1(3)		36 x 66	16.50			1	1	1			
	M1-5A	CTH O	36 x 36									
	M6-1		30 x 30									
105	R1-1F(3)		36 x 36		7.46		1				106	
106	R4-7(3)		36 x 48	12.00				1	1		105	
107	R1-1F(3)		36 x 36		7.46							ON SIGNAL POLE
108	R5-1(3)		36 x 36	9.00								ON SIGNAL POLE
109	R1-1F(3)		36 x 36		7.46							ON SIGNAL POLE
110	R5-1(3)		36 x 36	9.00								ON SIGNAL POLE
111	J4-1(3)		36 x 54	13.50			1					
	M3-4		36 x 18									
	M1-6	STH 50	36 x 36									
112	J1-1(2S)		24 x 39	6.50			1					
	M2-1		21 x 15									
	M1-6	STH 50	24 x 24									
113	R5-1		X					1	1			
114	J3-2(2S)		48 x 57	19.00			1	1	1			
	M3-2	 	24 x 12									
	M1-6	STH 50	24 x 24									
	M6-1		21 x 21									
	M3-4		24 x 12									
	M1-6	STH 50	24 x 24									
	M1-6		21 x 21									
115	R1-1F(3)		36 x 36		7.46							ON SIGNAL POLE
115A	R6-3		X		7.40					1		ON SIGNAL POLE
116	R1-1F(3)		36 x 36		7.46							ON SIGNAL POLE
117	R1-1F(3)		36 x 36		7.46		1				125	
118	R1-1F(3)		36 x 36		7.46							ON SIGNAL POLE
119	J13-1(3)		36 x 66	16.50			1				129	
	M1-5A	CTH O	36 x 36									
	M6-1		30 x 30									
120	R3-20L(3)		36 x 54	13.50			1					
121	R5-1(3)		36 x 36	9.00								ON SIGNAL POLE
122	R5-1(3)		36 x 36	9.00								ON SIGNAL POLE

SHEET 1 OF 2

MISCELLANEOUS QUANTITIES - PERMANENT SIGNING HWY: STH 50 @ CTH 0 COUNTY: KENOSHA SHEET: PROJECT NO: 3700-20-71

CATEGORY CODE 1000	

					637.2210	637.2215	634.0616	634.0618	638.2602	638.3000	638.2102		
				TYPE II			POSTS	POSTS		REMOVING	MOVING		
				SIGN	SIGNS	SIGNS	WOOD	WOOD	REMOVING	SMALL	SIGNS	MOUNT	
	SIGN	SIGN	SIGN	SIZE	TYPE II	TYPE II	4X6-INCH	4X6-INCH	SIGNS	SIGN	TYPE II	ON SAME	
1	NO.	CODE	MESSAGE	W x H	REFLECTIVE H	REFLECTIVE H	X 16-FT	X 18-FT	TYPE II	SUPPORTS		POST AS	REMARKS
				[IN.] x [IN.]	[SF]	FOLDING	[EA]	[EA]	[EA]	[EA]	[EA]	SIGN#	NEW SIGN LOCATION
						[SF]							
	123	R1-1F(3)		36 x 36		7.46			1	1			ON SIGNAL POLE
	123A	R6-3(2S)		30 x 24	5.00								
	124	J3-2(2S)		48 x 57	19.00			1	1	1			
		M3-4		24 x 12									
1 [M1-6	STH 50	24 x 24									
		M6-1		21 x 21									
		M3-3		24 x 12									
		M1-6	STH 50	24 x 24									
		M6-1		21 x 21									
	125	R4-7(3)		36 x 48	12.00				1	1		117	
	126	R5-1		x					1	1			
	127	J13-1		x					1				
	128	J4-1(3)		36 x 54	13.50			1					
		M3-2		36 x 18									
		M1-6	STH 50	36 x 36									
	129	R5-1A(3)		42 x 30	8.75				1	1		119	
	130	R3-20LL(2S)		24 x 36	6.00		1						
	131	R6-2L(2M)		30 x 36	7.50								ON SIGNAL POLE
	132	M1-94H	368TH AVE	60 x 18	7.50								ON SIGNAL MAST ARM
	133	R6-2L(2M)		30 x 36	7.50								ON SIGNAL POLE
	134	R3-20LL(2S)		24 x 36	6.00		1						
				Х									
													_
		TOTALS			272.50	59.68	3	12	12	11	1		

SHEET 2 OF 2

PLOT SCALE : 1:1

PROJECT NO: 3700-20-71 HWY: STH 50 @ CTH 0 COUNTY: KENOSHA MISCELLANEOUS QUANTITIES – PERMANENT SIGNING SHEET: **E**

FILE NAME N:\PDS\C3D\CAD\37002071\SIGNING\QUANTITIES\STH50_CTHO_MQ.PPT PLOT DATE : 1/13/2015 2:41:05 PM PLOT BY : MSCKVW PLOT NAME : 030214_mq_fm2

TYPE I & II PERMANENT SIGNING

|3

	TOVITIO OR		NO. 14 (ABOVE GROUN 655.0230 CABLE	655.0240 CABLE	
			TRAFFIC SIGNAL	TRAFFIC SIGNAL	
			5 - 14 AWG	7 - 14 AWG	
3.0140	FROM	TO	LF	LF	1
LBOXES	004	11545.4	24		
TEEL 42 - INCH	SB1 SB1	HEAD 1 HEAD 9	21	22	<u> </u>
EACH		HEAD			ļ
	SB2	10		22	j
1	SB7	HEAD 7	64		
1	SB7	HEAD 8	51		
1	0.00	HEAD	19		Ī
1	SB8	12 HEAD	19		
1	SB8	14	19		
1		HEAD			
1	SB9	13	47		
1	SB10	HEAD 4	0.4	22	
1	SB10 SB11	HEAD 6 HEAD 5	21	22	1
1	SB15	HEAD 2	64	22	
<u></u>	SB15	HEAD 3	52		
1		HEAD			
	SB16	11	19		
14		HEAD	4.0		
	SB16	16 HEAD	19		
	SB17	15	45		
		TOTAL	441	88	
	ADDITIONA	L QUANTITIES	SHOWN ELSEWHERE		

SUMMARYO	F STATE F	URNISHED MATERIALS - FOR INFORMATION ONLY
QUANTITY	UNIT	DESCRIPTION
1	EACH	TRAFFIC SIGNAL CONTROLLER AND CABINET
2	EACH	POLES, TYPE 10
2	EACH	POLES, TYPE 12
2	EACH	MONOTUBE ARMS, 20-FOOT
2	EACH	MONOTUBE ARMS, 40-FOOT
2	FACH	STEEL LUMINAIRE ARMS 8-FOOT

RADAR DETECTION SYSTEM

CONDUIT

00110011				
FROM	то	652.0225 CONDUIT RIGID NONMETALLIC SCHEDULE 40 2-INCH LF	652.0235 CONDUIT RIGID NONMETALLIC SCHEDULE 40 3-INCH LF	652.0615 CONDUIT SPECIAL 3-INCH LF
004	DD4		40	
CB1	PB1	***	18	
PB1	PB2	-	106	400
PB2	PB3	-		108
PB3	PB4	-		54
PB4	PB5			104
PB5 PB6	PB6		68	400
PB6 PB7	PB7 PB8	_	108	102
PB/ PB8	PB9	_	108	104
PB9	PB9 PB10	-	***	56
PB9 PB10	PB10 PB11		Accorded to	104
			72	104
PB11 PB12	PB12 PB13	***	12	120
PB12 PB13	PB13		106	120
PB13	CB1	-	15	
PD 14	СВТ	-	15	
PB2	SB1	5		
PB3	SB2	19		_
PB3	SB3	19		
PB4	SB4	143		
PB5	SB7		25	
PB6	SB8	5		
PB7	SB9		5	
PB8	SB10	13	-	
PB9	SB11	32		
PB10	SB12	136		
PB11	SB15		7	
PB12	SB16	8	<u></u>	
PB13	SB17	-	25	***
SB4	SB5	152		
SB5	SB6	152		
SB12	SB13	152	***	_
SB13	SB14	152		
TO	TAL	988	555	752

D WOLLER E-42424- FITCHBUR	NEER	TOTAL	14		SB SB SB ADDII	HEAD 16 16 HEAD	19 19 45 441 OWN ELSEWHERE	88
IN STONAL	≣	LOCATION	654.0101 CONCRETE BASES TYPE 1 EACH	654.0102 CONCRETE BASES TYPE 2 EACH	654.0105 CONCRETE BASES TYPE 5 EACH	654.0110 CONCRETE BASES TYPE 10 EACH	654.0113 CONCRETE BASES TYPE 13 EACH	654.0217 CONCRETE CONTROL CABINET BASES TYPE 9 SPECIAL EACH
SB S	1 612+97.1 2 613+16.0 3 612+79.1 4 611+52.9 5 610+03.0 6 608+52.8 7 612+67.2 8 613+18.9 9 613+68.2 10 613+85.1 11 615+48.4 13 616+98.4 14 618+48.6 15 614+24.7 16 613+82.0 17 613+85.0	67.2' RT 14.0' RT 13.6' RT 9.2' LT 1.8' LT 2.2' RT 67.4' LT 90.6' LT 94.1' LT 10.3' RT 2.9' RT 4.7' LT 67.0' RT 86.6' RT 105.2' RT 122.8' RT	1	1	- - 1 1 1 1 1 - - - 1 1 1 1 - - - 7	 1 1 1		

ALL ITEMS ON THIS SHEET ARE CATEGORY 0010 SIGNAL NO. S30-1419 STH 50 & CTH O PAGE 01 OF 03

SHEET

PROJECT NO:3700-20-71 HWY: STH 50

PLOT DATE : 1/27/2015 7:11 PM

COUNTY: KENOSHA

PULL BOXES STEEL

NUMBER STATION LOCATION

118.6' RT

67.9' RT

13.9' RT

13.0' LT

65.1' LT

89.7' LT

65.6' LT

14.0' LT

13.8' RT

65.6' RT

79.4' RT

83.6' RT

612+86.0

613+01.6

612+97.7

612+95.7

612+92.0

613+18.1 613+69.5

614+16.1

614+16.6

614+16.9

614+17.5

613+84.7

PB13 613+24.7

PULL

BOX

PB1

PB2

PB3

PB4 PB5

PB8

PB9

PB11

PB12

PLOT BY : SEH INC

MISCELLANEOUS QUANTITIES

LAYOUT NAME : 030201_MQ

PLOT SCALE : NTS

WISDOT/CADDS SHEET 42

E

CB1 CB1 CB1 CB1 CB1 CB1 CB1 CB1 CB1 CB1	SB1 SB2 SB7 SB8 SB9 SB10 SB11 SB15 SB15	373 	NAL TRAF G 12-	55.0260 CABLE FIC SIGNAL - 14 AWG LF 107 308 338 405 422 236 185			FROM TO CB1 SB3 SB3 LUMI SB3 SB4 SB4 LUMI SB3 SB10 LUMI SB4 SB5	230 N O 276 N	G WIRE LIGHTIN			_	FROM TO CB1 SB1 SB1 SB2 SB2 SB7 SB7 SB8 SB8 SB9 SB9 SB10 SB10 SB11 SB11 SB15 SB15 SB16 SB16 SB17	655.0515 ELECTRICAL TRAFFIC SIGN 10 AWG LF 107 118 179 104 101 112 137 175 91	WIRE NALS
	L SERVICE METER	690 S SHOWN ELSEWHERE BREAKER PEDESTAL		SERVICE R PEDESTAL	_		SB5 LUMI SB5 SB6 SB6 LUMI CB1 SB17 SB17 LUMI SB11 LUMI SB12 LUMI SB12 SB13 SB13 LUMI SB13 SB14 SB14 LUMI	N 160 N 126 N 337 N 2 236 N 3 160 N 4 160 N	117 — 117 — 117 — 288 — 117 — 117 — 117 — 117 — 117 — 117			_	SB17 CB1 PB1 CB1 PB2 SB1 PB3 SB2 PB4 SB2 PB5 SB7 PB6 SB8 PB7 SB9 PB8 SB10 PB9 SB11 PB10 SB11 PB11 SB15 PB12 SB16 PB13 SB17 PB14 CB1 TOTAL	126 29 40 39 82 45 25 25 24 52 96 27 28 45 28	
BASES, POLES SIGNAL BASE NUMBER		MS, PUSH BUTTONS, AND 657.0255 TRANSFORMER BASES BREAKAWAY 11 1/2 INCH BOLT CIRCLE EACH	0 LUMINAIRES 657.0305 POLES TYPE 2 EACH	657.0310 POLES TYPE 3 EACH	657.0322 POLES TYPE 5 ALUMINUM EACH	657.0420 TRAFFIC SIGNAL STANDARDS ALUMINUM 13 - FT EACH	657.0425 TRAFFIC SIGNAL STANDARDS ALUMINUM 15 - FT EACH	SINGLE MEMBER 4 -INCH CLAMP	657.0610 LUMINAIRE ARMS SINGLE MEMBER 4 1/2-INCH CLAMP 6-FOOT EACH	657.1350 INSTALL POLES TYPE 10 EACH	657.1355 INSTALL POLES TYPE 12 EACH	657.1520 INSTALL MONOTUBE ARM 20-FT EACH	657.1540 INSTALL IS MONOTUBE ARMS 40-FT EACH	657.1808 INSTALL LUMINAIRE ARMS 8-FT EACH	659.1125 LUMINAIRES UTILITY LED C EACH
SB1		1	1												
SB2	1	 1					1		 2						
SB3 SB4		1			1				1						1
SB5		1		_	1				1		_			_	1
SB6 SB7		1 			1 				<u> </u>				<u></u> 1		1
SB8	1					1									
SB9 SB10	1						1			1		<u> </u>		<u> </u>	1
SB10		 1		1				2			_				2
SB12		1			1				1						1
SB13		1			1				1						1
SB14 SB15		1 			1				1 		 1		 1		1
SB16	1					1									
			_							1		1		1	1
SB17		9	1	1	7	2	2	2	8	2	2	2	2	2	12

HWY:STH 50

PROJECT NO:3700-20-71

COUNTY: KENOSHA

MISCELLANEOUS QUANTITIES

SHEET

TRAFFIC SIGNAL AND PEDESTRIAN FACES, AND BACKPLATES

SIGNAL HEAD NUMBER	SIGNAL BASE NUMBER	658.0110 TRAFFIC SIGNAL FACE 3-12 INCH VERTICAL EACH	658.0115 TRAFFIC SIGNAL FACE 4-12 INCH VERTICAL EACH	658.0215 BACKPLATES SIGNAL FACE 3 SECTION 12-INCH EACH	658.0220 BACKPLATES SIGNAL FACE 4 SECTION 12-INCH EACH	658.0600 LED MODULES 12-INCH RED BALL EACH	658.0605 LED MODULES 12-INCH YELLOW BALL EACH	658.0610 LED MODULES 12-INCH GREEN BALL EACH	658.0615 LED MODULES 12-INCH RED ARROW EACH	658.0620 LED MODULES 12-INCH YELLOW ARROW EACH	658.0625 LED MODULES 12-INCH GREEN ARROW EACH
1	SB1	1		1		1	1	1			
2	SB15	1		1		1	1	1			
3	SB15	1		1		1	1	1			
4	SB10		1		1				1	2	1
5	SB11		1		1				1	2	1
6	SB10	1		1		1	1	1			
7	SB7	1		1		1	1	1			
8	SB7	1		1		1	1	1			
9	SB1		1		1				1	2	1
10	SB2		1		1				1	2	1
11	SB16	1		1		1	1	1			
12	SB8	1		1		1	1	1			
13	SB9	1		1		1	1	1			
14	SB8	1		1		1	1	1			
15	SB16	1		1		1	1	1			
16	SB17	1		1		1	1	1			
	TOTAL	12	4	12	4	12	12	12	4	8	4

COCATION LS STH 50 & CTHO 1 TOTAL 1 TOTA	SIGNAL MOUNTING HARDWARE STH 50 & CTH O	658.5069.01 SIGNAL MOUNTING HARDWARE		INSTALL W STH 50 & 0	VIRELESS MODEM CTH O	SPV.0060.03 INSTALL WIRELESS	
SPV.0105.01	STH 50 & CTH O	LS	_			1 1	
STH 50 & CTH O		TRANSPORTING SIGNAL AND LIGHTING MATERIALS		SPV.0105.02 INSTALL STATE FURNISHED TRAFFIC SIGNAL CABINET			SPV.0105.03 TRANSPORTING AND INSTALLING STATE FURNISHED RADAR DETECTION SYSTEM
SIGNAL NO. S30-1419		1		1	_		1
PAGE 03 OF 03							SIGNAL NO. S30-1419 STH 50 & CTH O

FILE NAME: P:\UZ\W\WITSE\128766\15-CIVIL 3D\37002001\SHEETSPLAN\SEC 03 MISCELLANEOUS QTY\030200_MQ (SIGNALS).DWG

PLOT DATE : 1/27/2015 7:11 PM

PLOT BY : SEH INC

LAYOUT NAME : 030203_MQ


PLOT SCALE : NTS

WISDOT/CADDS SHEET 42

Standard Detail Drawing List

08A05-19C	INLET COVERS TYPE F, HM, HM-S, S, T, V, HM-GJ, & HM-GJ-S
08A08-01	CATCH BASINS 3-FT, 4-FT, 5-FT AND 6-FT DIAMETER
08C06-01	INLETS 3-FT AND 4-FT DIAMETER
08C07-01	INLETS 2X2-FT, 2X2.5-FT, 2X3-FT AND 2.5X3-FT
08D01-17	CONCRETE CURB, CONCRETE CURB AND GUTTER AND TIES
08D15-04A	EDGEDRAIN OUTLET AND OUTFALL MARKERS
08D15-04B	EDGEDRAIN AND BASE AGGREGATE OPEN GRADED
08D15-04C	EDGEDRAIN AND BASE AGGREGATE OPEN GRADED
08E09-06	SILT FENCE
08E10-02	INLET PROTECTION TYPE A, B, C AND D
08F01-11	APRON ENDWALLS FOR CULVERT PIPE
08F04-07	JOINT TIES FOR CONCRETE PIPE AND CONCRETE COLLAR DETAIL
09B02-08	CONDUIT UNDER PAVED HIGHWAYS
09B04-11	PULL BOX
09C02-07	CONCRETE BASES, TYPES 1, 2, 5, & 6
09C03-04	TRANSFORMER/PEDESTAL BASES
09C06-07	CONCRETE CONTROL CABINET BASE, TYPE 9, SPECIAL
09C11-05	CONCRETE BASE TYPE 10
09C12-05A	CONCRETE BASE TYPE 13
09C12-05B	CONCRETE BASE TYPE 13
09D01-05	CABINET SERVICE INSTALLATION (METER BREAKER PEDESTAL)
09D02-03	SI GNAL CONTROL CABI NET
09E01-13A	POLE MOUNTINGS FOR TRAFFIC SIGNALS TYPE 2
09E01-13B	POLE MOUNTINGS FOR TRAFFIC SIGNALS AND LIGHTING UNITS, TYPE 3 (HEAVY DUTY)
09E01-13D	POLE MOUNTINGS FOR LIGHTING UNITS, TYPE 5 (30 FEET)
09E01-13G	HARDWARE DETAILS FOR POLE MOUNTINGS
09E03-05	NON-FREEWAY LIGHTING UNIT POLE WIRING
09E06-05	TRAFFIC SIGNAL STANDARD POLY BRACKET MOUNTINGS (TYPICAL) 13 FT. OR 15 FT.
09E08-06B	TYPE 10 POLE 15'-30' MONOTUBE ARM
09E08-06C	TYPE 12 POLE 35' -55' MONOTUBE ARM
09E08-06E	GENERAL NOTES AND HARDWARE DETAILS FOR TYPE 9, 10, 12 & 13 POLES WITH MONOTUBE ARMS
11B02-02	CONCRETE MEDIAN NOSE
13C01-17	CONCRETE PAVEMENT LONGITUDINAL JOINTS AND TIES
13C11-11A	RURAL DOWELED CONCRETE PAVEMENT
13C11-11B	RURAL DOWELED CONCRETE PAVEMENT
13C18-02A	CONCRETE PAVEMENT JOINTING
13C18-02B	CONCRETE PAVEMENT STEEL REINFORCEMENT
13C18-02C	CONCRETE PAVEMENT JOINT TIES
13C18-02D	CONCRETE PAVEMENT JOINTING AT UTILITY FIXTURES
15C02-05C	DETOUR SIGNING FOR MAINLINE CLOSURES
15C02-03C 15C07-12B	PAVEMENT MARKING WORDS
15C07-12C	PAVEMENT MARKING ARROWS
15C08-16A	PAVEMENT MARKING (MAINLINE)
15C08-16B	PAVEMENT MARKING (INTERSECTIONS)
15C08-16E	PAVEMENT MARKING (LEFT TURN LANE)
15C08-16F	PAVEMENT MARKING (ISLANDS)
15C18-03	MEDIAN ISLAND MARKING
15C33-01	STOP LINE AND CROSSWALK PAVEMENT MARKING
15D20-02	TRAFFIC CONTROL, SINGLE LANE CLOSURE, NON-FREEWAY/EXPRESSWAY
15D21-03	TRAFFIC CONTROL, INTERSECTION WITHIN SINGLE LANE CLOSURE
15D27-02	TRAFFIC CONTROL, SHOULDER CLOSURE ON DIVIDED ROADWAY, SPEEDS GREATER THAN 40 MPH


6



TYPE "F"

USE WITH TYPES A & D CONCRETE CURB & GUTTER, 36 INCH.


25 ½" 23 ½" 23 ½" 23 ½" 23 ½" 23 ½" 23 ½" 23 ½" 23 ½" 25 ½" 23 ½" 25 ½" 25 ½" 26 ½" 27 ½" 28 ½" 28 ½" 29 ½" 20 ½"



GENERAL NOTES

DETAILS OF CONSTRUCTION, MATERIALS AND WORKMANSHIP NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS AND THE APPLICABLE SPECIAL PROVISIONS.


DETAIL DRAWINGS FOR PROPOSED ALTERNATE DESIGNS FOR INLET COVERS SHALL BE SUBMITTED TO THE ENGINEER FOR APPROVAL PROVIDING THAT SUCH ALTERNATE DESIGNS MAKE PROVISION FOR EQUIVALENT CAPACITY AND STRENGTH.



ALTERNATIVE CURB BOX FOR TYPE "HM" COVER

USE WITH TYPES G & J CONCRETE CURB & GUTTER, 30 INCH NOTED AS TYPE HM-GJ ON DRAINAGE TABLE


NOIE:
SPECIAL GRATE FOR THE
TYPE "H" COVER MAY ALSO BE
USED FOR THE TYPE "HM-GJ" COVER
NOTED AS TYPE HM-GJ-S ON DRAINAGE TABLE



TYPE "HM"

USE WITH TYPES A & D CONCRETE CURB & GUTTER, 36 INCH.

NOTE:
SPECIAL GRATE FOR THE
TYPE "H" COVER MAY ALSO BE
USED FOR THE TYPE "HM" COVER
NOTED AS TYPE HM-S ON DRAINAGE TABLE



TYPE "T"

USE WITH TYPES R & T CONCRETE CURB & GUTTER, 36 INCH.



STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED

II/27/2013
DATE / /S/ Jerry H. Zogg
ROADWAY STANDARDS DEVELOPMENT ENGINEER

A 5-19


D.D. 8






Ω









SEPARATE PRECAST REINFORCED CONCRETE BASE OPTION DETAIL "A"

CONTRACTOR TO PROVIDE DRAWING(S) STAMPED BY A PROFESSIONAL ENGINEER FOR STEEL REINFORCING DESIGN FOR CAST-IN-PLACE STRUCTURES

SECTION A-A


(4)

PRECAST REINFORCED CONCRETE WITH MONOLITHIC BASE


SEE DETAIL "A"

CONCRETE BLOCK WITH CAST-IN-PLACE OR PRECAST REINFORCED CONCRETE BASE ②


OVER 12' 25' DEP



TOP WITH PLAIN END JOINT




TOP WITH TONGUE AND GROOVE JOINT



RISER WITH TONGUE AND GROOVE JOINT

DETAIL "B"



DETAIL "C"

GENERAL NOTES

DETAILS OF CONSTRUCTION, MATERIALS AND WORKMANSHIP NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS AND THE APPLICABLE SPECIAL PROVISIONS.

UNLESS OTHERWISE AUTHORIZED IN WRITING BY THE ENGINEER, THE CONTRACTOR SHALL NOT ORDER AND DELIVER PRECAST CATCH BASIN UNITS REQUIRED FOR THE PROJECT UNTIL A LIST OF SIZES IS FURNISHED BY THE ENGINEER.

DETAILED DRAWINGS FOR PROPOSED ALTERNATE DESIGNS FOR UNDERGROUND DRAINAGE STRUCTURES SHALL BE SUBMITTED TO THE ENGINEER FOR APPROVAL PROVIDING THAT SUCH ALTERNATE DESIGNS MAKE PROVISION FOR EQUIVALENT CAPACITY AND STRENGTH.

ALL DRAINAGE STRUCTURES ARE DESIGNATED ON THE PLANS AS "MANHOLES 3X3-L", "CATCH BASINS 4-B", "INLETS 2X3-H", ETC. THE FIRST NUMBERS DESIGNATE THE SIZE OF THE STRUCTURE, AND THE FOLLOWING LETTER DESIGNATES THE TYPE OF COVER TO BE USED TO COMPRISE THE COMPLETE UNIT.

BASES SHALL BE PLACED ON A BED OF MATERIAL AT LEAST 6 INCHES IN DEPTH, WHICH MEETS THE REQUIREMENTS OF GRANULAR BACKFILL. THIS BEDDING SHALL BE COMPACTED AND PROVIDE UNIFORM SUPPORT FOR THE ENTIRE AREA OF THE BASE.

PRECAST REINFORCED CONCRETE CONE TOPS (ECCENTRIC OR CONCENTRIC) OR PRECAST REINFORCED CONCRETE FLAT SLAB TOPS MAY BE USED ON CONCRETE BLOCK STRUCTURES. THE TOPS SHALL BE INSTALLED ON

ECCENTRIC CONE TOPS MAY BE USED ON ALL STRUCTURES, AND CONCENTRIC CONE TOPS SHALL BE USED ONLY ON STRUCTURES 5 FEET OR LESS IN DEPTH, UNLESS OTHERWISE DIRECTED BY THE ENGINEER.

STEPS MEETING AASHTO M199 AND THE FOLLOWING REQUIREMENTS SHALL BE INSTALLED IN ALL STRUCTURES OVER 5 FEET IN DEPTH: 16 INCH C-C MAXIMUM SPACING; PROJECT A MINIMUM CLEAR DISTANCE OF 4 INCHES FROM THE WALL AT THE POINT OF EMBEDMENT; MINIMUM LENGTH OF 10 INCHES; MINIMUM WALL EMBEDMENT OF 3 INCHES, FERROUS METAL STEPS NOT PAINTED OR TREATED TO RESIST CORROSION SHALL HAVE A MINIMUM CROSS SECTIONAL DIMENSION OF 1 INCH.

STEPS OF APPROVED POLYPROPYLENE PLASTIC COATED REINFORCEMENT BAR ARE ACCEPTABLE. REINFORCING BAR MUST BE A MINIMUM OF $\crit{1/2}$ INCH AND MEET THE REQUIREMENTS OF ASTM A615.

CERTIFICATION SHALL BE PROVIDED THAT INSTALLED STEPS WHEN TESTED IN ACCORDANCE WITH SECTION 10 OF AASHTO T280 CAN WITHSTAND A VERTICAL LOAD OF 800 LBS. AND A HORIZONTAL LOAD OF 400 LBS.

ALL BAR STEEL REINFORCEMENT SHALL BE EMBEDDED 2 INCHES CLEAR UNLESS OTHERWISE SHOWN OR NOTED.

ALL PRECAST INLET UNITS SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF AASHTO DESIGNATION M199.

PRECAST REINFORCED RISERS SHALL HAVE A TONGUE AND GROOVE JOINT WITH TONGUE UP OR DOWN.

CONCRETE BLOCK WILL NOT BE PERMITED FOR STRUCTURES GREATER THAN 4 FEET IN DIAMETER.

4" OVERHANGING BASES ARE REQUIRED FOR ALL CONCRETE BLOCK INSTALLATIONS. 4" OVERHANG IS REQUIRED WHEN SEPARATE PRECAST BASE IS PROVIDED. OVERHANG IS NOT REQUIRED ON PRECAST STRUCTURES WITH AN INTEGRAL OR MONOLITHIC BASE.

FOR ADDITIONAL CONFIGURATIONS, MAINTAIN A MINIMUM OF 12 INCHES AS MEASURED FROM THE INSIDE OF THE STRUCTURE WALL BETWEEN THE OUTSIDE PIPE WALLS OF ADJACENT PIPES. SEE DETAIL "C".

- MINIMUM WALL THICKNESS SHALL BE 4 INCHES FOR 3-FT, 5 INCHES FOR 4-FT, 6 INCHES FOR 5-FT AND 7 INCHES MINIMUM WALL INICINESS STALL DE FOR 6-FT DIAMETER PRECAST CATCH BASINS.
- (2) FOR PRECAST CATCH BASINS PROVIDE REINFORCING STEEL IN ACCORDANCE TO AASHTO M199.
- (3) PRECAST FLAT SLAB TOPS AND BASES WITH A DIAMETER OF 48" AND LESS SHALL HAVE A MINIMUM THICKNESS OF 6". PRECAST FLAT SLAB TOPS AND BASES WITH A DIAMETER LARGER THAN 48" SHALL HAVE A MINIMUM THICKNESS
- 4 1" CONCRETE KEY POURED AFTER INSTALLATION. 2' SUMP MEASURED FROM TOP OF KEY.

CATCH BASIN COVER OPENING MATRIX

CATCH BASIN	INLET COVER TYPE	ALL A'S	ALL B'S	BW	С	F	ALL H'S	S	Т	٧	WM	Z
SIZE	OPENING SIZE (FT)											
3-FT	2X2	Х	Х					Х		Х		
	2 DIA.				Х							Х
	2X2	×	X					Х		Х		
4-FT-	2X2.5			Х				Х	Х	Х	Х	
6-FT	2 DIA.				Х							Х
	2X3						x					
	2.5X3					X						

PIPE MATRIX

CATCH BASIN		MAXIMUM INSIDE PIPE DIAMETER FOR TWO PIPES									
SIZE	180° SEPARATION (IN)	90° SEPARATION (IN)									
3-FT	15	12									
4-FT	24	18									
5-FT	36	24									
6-FT	42	30									


CATCH BASINS 3-FT, 4-FT, 5-FT AND 6-FT DIAMETER

STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION

PPROVED	

/S/ Jerry H. Zogg 6/5/2012 DATE ROADWAY STANDARDS DEVELOPMENT ENGINEER FHWA


CATCH BASINS 3-FT, 4-FT, 5-FT AND 6-FT DIAMETER



PLAN VIEW CIRCULAR OPENING

JOINTS TO BE SEALED WITH

A BUTYL RUBBER SEAL PER SEALANT MANUFACTURERS RECOMMENDATIONS CONFORMING TO ASTM C990 (TYP) PRECAST DISCHARGE WALL TOP WITH PLAIN END JOINT



1/2" CEMENT

CONCRETE

(MIN. SLOPE 1 IN. /FT.)


CONCRETE BLOCK


OR PRECAST REINFORCED


CONCRETE BASE 2

WITH CAST-IN-PLACE

PLASTER COAT







RISER WITH TONGUE AND GROOVE JOINT

DETAIL "A"

DETAIL "B"

INLETS 3-FT AND 4-FT DIAMETER

GENERAL NOTES

DETAILS OF CONSTRUCTION, MATERIALS AND WORKMANSHIP NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS AND THE APPLICABLE SPECIAL PROVISIONS.

UNLESS OTHERWISE AUTHORIZED IN WRITING BY THE ENGINEER, THE CONTRACTOR SHALL NOT ORDER AND DELIVER PRECAST INLET UNITS REQUIRED FOR THE PROJECT UNTIL A LIST OF SIZES IS FURNISHED BY THE ENGINEER.

DETAILED DRAWINGS FOR PROPOSED ALTERNATE DESIGNS FOR UNDERGROUND DRAINAGE STRUCTURES SHALL BE SUBMITTED TO THE ENGINEER FOR APPROVAL PROVIDING THAT SUCH ALTERNATE DESIGNS MAKE PROVISION FOR EQUIVALENT CAPACITY AND

ALL DRAINAGE STRUCTURES ARE DESIGNATED ON THE PLANS AS "MANHOLES 3X3-L", "CATCH BASINS 4-B", "INLETS 2X3-H", ETC. THE FIRST NUMBERS DESIGNATE THE SIZE OF THE STRUCTURE, AND THE FOLLOWING LETTER DESIGNATES THE TYPE OF COVER TO BE USED TO COMPRISE THE COMPLETE UNIT.

BASES SHALL BE PLACED ON A BED OF MATERIAL AT LEAST 6 INCHES IN DEPTH, WHICH MEETS THE REQUIREMENTS OF GRANULAR BACKFILL. THIS BEDDING SHALL BE COMPACTED AND PROVIDE UNIFORM SUPPORT FOR THE ENTIRE AREA OF THE BASE.

ALL BAR STEEL REINFORCEMENT SHALL BE EMBEDDED 2 INCHES CLEAR UNLESS OTHERWISE SHOWN OR NOTED.

ALL PRECAST INLET UNITS SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF AASHTO DESIGNATION M199.

PRECAST REINFORCED RISERS SHALL HAVE A TONGUE AND GROOVE JOINT WITH TONGUE UP OR DOWN.


4" OVERHANGING BASES ARE REQUIRED FOR ALL CONCRETE BLOCK INSTALLATIONS. 4" OVERHANG IS REQUIRED WHEN SEPARATE PRECAST BASE IS PROVIDED. OVERHANG IS NOT REQUIRED ON PRECAST STRUCTURES WITH AN INTEGRAL OR MONOLITHIC BASE.

FOR ADDITIONAL CONFIGURATIONS, MAINTAIN A MINIMUM OF 12 INCHES AS MEASURED FROM THE INSIDE OF THE STRUCTURE WALL BETWEEN THE OUTSIDE PIPE WALLS OF ADJACENT PIPES. SEE DETAIL "C".

- (1) MINIMUM WALL THICKNESS SHALL BE 4-IN FOR 3-FT DIAMETER AND 5-IN FOR 4-FT DIAMETER PRECAST INLETS.
- (2) FOR PRECAST CATCH BASINS PROVIDE REINFORCING STEEL IN ACCORDANCE TO AASHTO M199.

INLET COVER OPENING MATRIX

	INLET COVER TYPE	ALL A'S	ALL B'S	BW	С	F	ALL H'S	S	T	٧	WM	Z
INLET SIZE	OPENING SIZE (FT)											
3-FT	2 DIA.				×							х
	2X2	х	х					х		Х		
4-FT	2 DIA.				х							Х
	2X2	х	x					х		х		
	2X2.5			Х				х	х	Х	Х	
	2X3						х					
	2.5X3					х						



DETAIL "C"

PIPE MATRIX

INLET		MAXIMUM INSIDE PIPE DIAMETER FOR TWO PIPES								
SIZE	180° SEPARATION (IN)	90° SEPARATION (IN)								
3-FT	15	12								
4-FT	24	18								

INLETS 3-FT AND 4-FT DIAMETER

STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION

APPROVED

6/5/2012 /S/ Jerry H. Zogg DATE ROADWAY STANDARDS DEVELOPMENT ENGINEER FHW4

Ö

 ∞

C

SEE DETAIL "A"

2

PRECAST REINFORCED

MONOLITHIC BASE

CONCRETE WITH

8 (1)

> DISCHARGE PIPE

SECTION A-A


CIRCULAR INLETS W/ FLAT TOP

MORTAR

ထ

C ω Δ

Ω



GENERAL NOTES

DETAILS OF CONSTRUCTION, MATERIALS AND WORKMANSHIP NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS AND THE APPLICABLE SPECIAL PROVISIONS.

UNLESS OTHERWISE AUTHORIZED IN WRITING BY THE ENGINEER, THE CONTRACTOR SHALL NOT ORDER AND DELIVER PRECAST INLET UNITS REQUIRED FOR THE PROJECT UNTIL A LIST OF SIZES IS FURNISHED BY THE ENGINEER.

DETAILED DRAWINGS FOR PROPOSED ALTERNATE DESIGNS FOR UNDERGROUND DRAINAGE STRUCTURES SHALL BE SUBMITTED TO THE ENGINEER FOR APPROVAL PROVIDING THAT SUCH ALTERNATE DESIGNS MAKE PROVISION FOR EQUIVALENT CAPACITY AND STRENGTH.

ALL PRECAST INLET UNITS SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF ASTM C 913.

ALL DRAINAGE STRUCTURES ARE DESIGNATED ON THE PLANS AS "MANHOLES 3X3-L", "CATCH BASINS 4-B", "INLETS 2X3-H", ETC. THE FIRST NUMBERS DESIGNATES THE SIZE OF THE STRUCTURE, AND THE FOLLOWING LETTER DESIGNATES THE TYPE OF COVER TO BE USED TO COMPRISE THE COMPLETE UNIT.

BASES SHALL BE PLACED ON A BED OF MATERIAL AT LEAST 6 INCHES IN DEPTH, WHICH MEETS THE REQUIREMENTS OF GRANULAR BACKFILL. THIS BEDDING SHALL BE COMPACTED AND PROVIDE UNIFORM SUPPORT FOR THE ENTIRE AREA OF THE BASE.

ALL BAR STEEL REINFORCEMENT SHALL BE EMBEDDED 2 INCHES CLEAR UNLESS OTHERWISE SHOWN OR NOTED.

PRECAST REINFORCED RISERS SHALL HAVE A TONGUE AND GROOVE JOINT WITH TONGUE UP OR DOWN.

- 4" OVERHANGING BASES ARE REQUIRED FOR CAST-IN-PLACE REINFORCED CONCRETE AND CONCRETE BLOCK INSTALLATIONS.
- 4" OVERHANG IS REQUIRED WHEN SEPARATE PRECAST BASE IS PROVIDED.
- OVERHANG IS NOT REQUIRED ON PRECAST STRUCTURES WITH AN INTEGRAL OR MONOLITHIC BASE.

MAXIMUM INSIDE PIPE DIAMETER DETERMINED BY 3 INCH CLEARANCE ON EACH SIDE OF THE OUTSIDE WALL OF THE PIPE. SEE DETAIL "A". ASSUMES PIPE ENTERS PERPENDICULAR TO THE STRUCTURE.


- 1) FOR PRECAST INLETS PROVIDE REINFORCING STEEL IN ACCORDANCE TO ASTM C 913.
- (2) CONTRACTOR TO PROVIDE DRAWING(S) STAMPED BY A PROFESSIONAL ENGINEER FOR STEEL REINFORCING DESIGN FOR CAST-IN-PLACE STRUCTURES.

INLET COVER MATRIX

	INLET SIZE		INLET COVER TYPE	ALL A'S	ALL B'S	BW	F	ALL H'S	s	т	v	WM
		WIDTH (W) (FT)	LENGTH (L) (FT)									
	2X2-FT	2	2	X	х				Х		Х	
ſ	2X2.5-FT	2	2.5			Х			Х	Х	Х	Х
[2X3-FT	2	3					Х				
	2.5X3-FT	2.5	3				Х					

PIPE MATRIX

	MAXIMUM II Dian	NSIDE PIPE IETER		
INLET SIZE	WIDTH (IN)	LENGTH (IN)		
2X2-FT	12	12		
2X2.5-FT	12	18		
2X3-FT	12	24		
2.5X3-FT	18	24		



DETAIL "A"

INLETS 2X2-FT, 2X2.5-FT, 2X3-FT AND 2.5X3-FT

STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION

APPROVED 6/5/2012 DATE

FHWA


/S/ Jerry H. Zogg ROADWAY STANDARDS DEVELOPMENT


ENGINEER


INLETS 2X2-FT, 2X2.5-FT, 2X3-FT AND 2.5X3-FT

SEPARATE PRECAST REINFORCED

CONCRETE BASE OPTION







RURAL CROSS SECTION

SHOULDER


TRAVELED

GENERAL NOTES


THE DIMENSIONS SHOWN ON THE TYPICAL CROSS SECTIONS WILL GOVERN IN THE EVENT THERE IS A CONFLICT WITH THE DETAILS SHOWN ON THIS DRAWING.

PIPE UNDERDRAIN SHALL BE LAID PARALLEL TO THE GRADE OF THE ROADWAY.

1 TRENCH BACKFILL WILL BE PAID FOR AS BASE AGGREGATE OPEN GRADED.



EDGEDRAIN IN URBAN ROADWAY



POST PAVING INSTALLATION (QUANTITIES ARE BASED ON THIS DETAIL)

PRE-PAVING INSTALLATION ALTERNATIVE

EDGEDRAIN IN RURAL ROADWAY

EDGEDRAIN AND BASE AGGREGATE OPEN GRADED

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED

3/21/07
DATE / /S/ Steven W. Krebs
CHIEF MATERIALS MANAGEMENT ENGINEER

S.D.D. 8 D 15

6

D.D. 8 D

15

TYPICAL APPLICATION OF SILT FENCE

6

b

Ō

Ш





PLAN VIEW SILT FENCE AT MEDIAN SURFACE DRAINS



GENERAL NOTES

DETAILS OF CONSTRUCTION NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS AND APPLICABLE SPECIAL PROVISIONS.

- ① HORIZONTAL BRACE REQUIRED WITH 2" X 4" WOODEN FRAME OR EQUIVALENT AT TOP OF POSTS.
- 2 FOR MANUAL INSTALLATIONS THE TRENCH SHALL BE A MINIMUM OF 4" WIDE & 6" DEEP TO BURY AND ANCHOR THE GEOTEXTILE FABRIC. FOLD MATERIAL TO FIT TRENCH AND BACKFILL & COMPACT TRENCH WITH EXCAVATED SOIL.
- 3 WOOD POSTS SHALL BE A MINIMUM SIZE OF 11/8" X 11/8" OF OAK OR HICKORY.
- 4) SILT FENCE TO EXTEND ACROSS THE TOP OF THE PIPE.
- (5) CONSTRUCT SILT FENCE FROM A CONTINUOUS ROLL IF POSSIBLE BY CUTTING LENGTHS TO AVOID JOINTS. IF A JOINT IS NECESSARY USE ONE OF THE FOLLOWING TWO METHODS; A) OVERLAP THE END POSTS AND TWIST, OR ROTATE, AT LEAST 180 DEGREES, B) HOOK THE END OF EACH SILT FENCE LENGTH.



TRENCH DETAIL



SILT FENCE TIE BACK

(WHEN REQUIRED BY THE ENGINEER)



SILT FENCE

တ ∞





INLET PROTECTION, TYPE A

GENERAL NOTES

INLET PROTECTION DEVICES SHALL BE MAINTAINED OR REPLACED AT THE DIRECTION OF THE ENGINEER.

MANUFACTURED ALTERNATIVES APPROVED AND LISTED ON THE DEPARTMENT'S EROSION CONTROL PRODUCT ACCEPTABILITY LIST MAY BE

WHEN REMOVING OR MAINTAINING INLET PROTECTION, CARE SHALL BE TAKEN SO THAT THE SEDIMENT TRAPPED ON THE GEOTEXTILE FABRIC DOES NOT FALL INTO THE INLET. ANY MATERIAL FALLING INTO THE INLET SHALL BE REMOVED IMMEDIATELY.

- 1) FINISHED SIZE, INCLUDING FLAP POCKETS WHERE REQUIRED, SHALL EXTEND A MINIMUM OF 10" AROUND THE PERIMETER TO FACILITATE MAINTENANCE OR REMOVAL.
- (2) FOR INLET PROTECTION, TYPE C (WITH CURB BOX), AN ADDITIONAL 18" OF FABRIC IS WRAPPED AROUND THE WOOD AND SECURED WITH STAPLES. THE WOOD SHALL NOT BLOCK THE ENTIRE HEIGHT OF THE CURB BOX OPENING.
- (3) FLAP POCKETS SHALL BE LARGE ENOUGH TO ACCEPT WOOD 2X4.



INLET PROTECTION, TYPE C (WITH CURB BOX)

INSTALLATION NOTES

TYPE B & C

TRIM EXCESS FABRIC IN THE FLOW LINE TO WITHIN 3" OF THE GRATE.

THE CONTRACTOR SHALL DEMONSTRATE A METHOD OF MAINTENANCE, USING A SEWN FLAP, HAND HOLDS OR OTHER METHOD TO PREVENT ACCUMULATED SEDIMENT FROM ENTERING THE INLET.

TYPE D

DO NOT INSTALL INLET PROTECTION TYPE D IN INLETS SHALLOWER THAN 30", MEASURED FROM THE BOTTOM OF THE INLET TO THE TOP OF THE GRATE.

TRIM EXCESS FABRIC IN THE FLOW LINE TO WITHIN 3" OF THE GRATE.

THE INSTALLED BAG SHALL HAVE A MINIMUM SIDE CLEARANCE, BETWEEN THE INLET WALLS AND THE BAG, MEASURED AT THE BOTTOM OF THE OVERFLOW HOLES, OF 3". WHERE NECESSARY THE CONTRACTOR SHALL CINCH THE BAG, USING PLASTIC ZIP TIES, TO ACHIEVE THE 3" CLEARANCE, THE TIES SHALL BE PLACED AT A MAXIMUM OF 4" FROM THE BOTTOM OF THE BAG.

INLET PROTECTION TYPE A, B, C, AND D

STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION

APPROVED

10/16/02

/S/ Beth Cannestra CHIEF ROADWAY DEVELOPMENT ENGINEER 6

0

ш

 ∞

 ∞

Δ

	METAL APRON ENDWALLS														
PIPE	MIN. 1	THICK.			DIMENS	SIONS (II	nches)			APPROX.					
DIA.				В	Н	L	և կ		W	SLOPE	BODY				
(IN.)	STEEL	ALUM.	(±]")	(MAX.)	(±]")	(±1½")	①	0	(±2")						
12	.064	.060	6	6	6	21	12	171/2	24	21/2+o 1	1Pc.				
15	.064	.060	7	8	6	26	14	213/4	30	2½+o 1	1Pc.				
18	.064	.060	8	10	6	31	15	281/4	36	2½+o 1	1Pc.				
21	.064	.060	9	12	6	36	18	29%	42	$2\frac{1}{2}$ to 1	1Pc.				
24	.064	. 075	10	13	6	41	18	371/4	48	$2\frac{1}{2}$ to 1	1Pc.				
30	.079	. 075	12	16	8	51	18	521/4	60	$2\frac{1}{2}$ to 1	1Pc.				
36	.079	. 105	14	19	9	60	24	59¾	72	$2\frac{1}{2}$ to 1	2 Pc.				
42	.109	. 105	16	22	11	69	24	75%	84	$2\frac{1}{2}$ to 1	2 Pc.				
48	.109	.105	18	27	12	78	24	81	90	2 ¹ / ₄ +o 1	3 Pc.				
54	.109	. 105	18	30	12	84	30	851/2	102	21/4+0 1	3 Pc.				
60	.109×	.105×	18	33	12	87	_		114	2 to 1	3 Pc.				
66	.109×	.105×	18	36	12	87	_	_	120	2 to 1	3 Pc.				
72	.109×	.105×	18	39	12	87	_	_	126	2 to 1	3 Pc.				
78	.109×	.105×	18	42	12	87	_	_	132	11/2+0 1	3 Pc.				
84	.109×		18	45	12	87	_	_	138	1/2+0 1	3 Pc.				
90	.109×	.105×	18	37	12	87	_	_	144	1/2+0 1	3 Pc.				
96	.109×	.105×	18	35	12	87	_		150	11/2+0 1	3 Pc.				

* EXCEPT CENTER PANEL

SEE GENERAL NOTES

PLAN VIEW

END VIEW

SIDE ELEVATION

METAL ENDWALLS

SHOULDER

SLOPE

	RE	INFORC	ED C	ONCRE T	E APRO	N E	NDWAL	.LS
PIPE			DIM	ENSIONS	(Inches)			APPROX.
DIA.	Т	A	В	С	D	E	G	SLOPE
12	2	4	24	48 1/8	721/8	24	2	3 to 1
15	21/4	6	27	46	73	30	21/4	3 to 1
18	21/2	9	27	46	73	36	21/2	3 to 1
21	23/4	9	36	371/2	731/2	42	23/4	3 to 1
24	3	91/2	431/2	30	731/2	48	3	3 to 1
27	31/4	101/2	$49^{1}/_{2}$	24	731/2	54	31/4	3 to 1
30	$3\frac{1}{2}$	12	54	193⁄4	731/2	60	31/2	3 to 1
36	4	15	63	34¾	97¾	72	4	3 to 1
42	$4\frac{1}{2}$	21	63	35	98	78	41/2	3 to 1
48	5	24	72	26	98	84	5	3 to 1
54	51/2		65	* ** 33 ¹ / ₄ -35	* 98 ¹ / ₄ - 100	90	51/2	2% to 1
60	6	* ** 30-35	60	39	99	96	5	2 to 1
66	61/2		* ** 72-78	* * * 21-27	99	102	51/2	2 to 1
72	7	* ** 24-36	78	21	99	108	6	2 to 1
78	71/2	* ** 24-36	78	21	99	114	61/2	2 to 1
84	8	36	901/2	21	1111/2	120	61/2	11/2+0 1
90	81/2	41	871/2	24	1111/2	132	61/2	11/2+0 1

*MINIMUM

PLAN

END VIEW

END SECTION

GROOVED END ON OUTLET END SECTION TONGUE END ON INLET END SECTION

BAR OR STEEL FABRIC

REINFORCEMENT

LONGITUDINAL SECTION

CONCRETE ENDWALLS

OPTIONAL

1 1/2" R

CULVERT

MEASURED LENGTH

OF CULVERT (TO-

NEAREST FOOT)

DESIGN

REINFORCED

SECTION A-A)

END CORNER PLATES MAY

BE FASTENED TO APRON

THE SURFACES TIGHTLY

TOGETHER

PROPER BY BOLTS, RIVETS, OR RESISTANCE SPOT WELDS WHICH WILL HOLD

TOE PLATE (SAME THICKNESS

AND METAL AS APRON) SHALL

BE FURNISHED WHEN CALLED

FOR ON THE PLANS

FDGE (SFE


END SECTION CONNECTOR STRAP LUG


1" WIDE, 12 GA. (0.109"


THICK) GALVANIZED STRAP

WITH STANDARD 6" X 1/2" BAND BOLT AND NUT

TYPE 1 FOR 12" THRU 24" CORR. PIPE









ALTERNATE FOR: ALL SIZES CORRUGATED CIRCULAR PIPE


NOTE: DIMPLED BAND FITS OVER OUTSIDE OF ENDWALL. AND CORRUGATED BAND FITS INSIDE ENDWALL. DIMPLED BAND MAY BE USED WITH HELICALLY CORRUGATED PIPE.


CONNECTION DETAILS 1, 2 OR 5.

ALTERNATE FOR TYPE 1 CONNECTION










FOR CIRCUMFERENTIALLY CORRUGATED PIPE USE ENDWALL CONNECTION DETAILS 1, 2, 3 OR 5

FOR HELICALLY CORRUGATED PIPE USE ENDWALL

FOR HELICALLY CORRUGATED PIPES WITH TWO CIRCUMFERENTIAL CORRUGATIONS AT EACH END USE ENDWALL CONNECTION DETAILS 1, 2 OR 3.

CONNECTION DETAILS



GENERAL NOTES

DETAILS OF CONSTRUCTION, MATERIALS AND WORKMANSHIP NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS AND THE APPLICABLE SPECIAL PROVISIONS.

CONCRETE CULVERT ENDWALLS MAY NOT BE USED WITH GALVANIZED STEEL OR ALUMINUM CULVERT PIPE OR VISE VERSA, GALVANIZED STEEL OR ALUMINUM ENDWALLS SHALL NORMALLY BE INSTALLED ON CULVERT PIPE OF THE SAME METAL.

ALL THREE PIECE STEEL APRON ENDWALLS FOR 60" DIAMETER PIPE AND LARGER SHALL HAVE 0.109" SIDES AND 0.138" CENTER PANELS. ALL THREE PIECE ALUMINUM APRON ENDWALLS FOR 60" DIAMETER PIPE AND LARGER SHALL HAVE 0.105" SIDES AND 0.134" CENTER PANELS. THE WIDTH OF CENTER PANELS SHALL BE GREATER THAN 20 PERCENT OF THE PIPE

LAP SEAMS SHALL BE TIGHTLY JOINED BY GALVANIZED RIVETS OR BOLTS FOR STEEL UNITS AND ALUMINUM RIVETS AND BOLTS FOR ALUMINUM UNITS. FOR THE 60" THROUGH 96" DIAMETER APRON ENDWALL SIZES. THE REINFORCED EDGES AND CENTER PANEL SEAMS SHALL BE FURTHER REINFORCED WITH GALVANIZED STEEL OR ALUMINUM STIFFENER ANGLES. THE ANGLES SHALL BE ATTACHED BY GALVANIZED NUTS AND BOLTS FOR STEEL UNITS AND ALUMINUM NUTS AND BOLTS FOR ALUMINUM UNITS.

WHERE TWO OR MORE PIPES WITH APRON ENDWALLS ARE LAID ADJACENT TO EACH OTHER, THEY SHALL BE SEPARATED BY A DISTANCE SUFFICIENT TO PROVIDE A MINIMUM CLEARANCE OF 6 INCHES BETWEEN APRON ENDWALLS.

(1) FOR PIPE SIZES UP TO 60" DIAMETER, A 180° ROLLED EDGE MAY BE USED INSTEAD OF STEEL ROD REINFORCEMENT. SEE SECTION A-A.

APRON ENDWALLS FOR CULVERT PIPE

STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION


11/30/94 /S/ Rory L. Rhinesmith CHIEF ROADWAY DEVELOPMENT ENGINEER

END CORNER

1/16" DIA. HOLES FOR

BOLTS OR RIVETS -

12" C-C MAX. SPACING



GENERAL NOTES


DETAILS OF CONSTRUCTION, MATERIALS, AND WORKMANSHIP NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS AND APPLICABLE SPECIAL PROVISIONS.

CONCRETE CULVERT AND STORM SEWER PIPE SHALL BE TIED TOGETHER IN THE MANNER ILLUSTRATED BY THIS DETAIL AT LOCATIONS DESIGNATED IN THE STANDARD SPECIFICATIONS AND THE PLAN. THE CONTRACTOR MAY USE EITHER ALTERNATE 1, 2 OR 3 FOR DRAINAGE STRUCTURES, ONLY ALTERNATE 1 AND 3 MAY BE USED FOR CATTLE PASSES, UNLESS OTHERWISE STATED IN THE CONTRACT. THE MATERIALS, FABRICATION AND WORK NECESSARY TO TIE THE PIPE BY THIS DETAIL WILL BE CONSIDERED INCIDENTAL TO THE PIPE AND APRON ENDWALLS IF REQUIRED.

DETAILED DRAWINGS FOR PROPOSED ALTERNATE DESIGNS FOR JOINT TIES SHALL BE SUBMITTED TO THE ENGINEER FOR APPROVAL.


JOINT TIES TO BE HOT-DIP GALVANIZED PER ASTM A 153.

- (1) & OF TONGUE AND GROOVE OR BELL AND SPIGOT JOINTS.
- THE INSIDE OF THE THREADED INSERTS SHALL BE CLEAN TO ALLOW THE INSERTION OF THREADED EYE
- ${\mathfrak S}$ HOLES SHALL BE CAST-IN-PLACE OR DRILLED 12 INCHES FROM ${\mathfrak L}$ OF TONGUE AND GROOVE.
- 4 BOLT PROJECTION INSIDE OF PIPE SHALL NOT EXCEED 2 INCHES.
- (5) OPENING TO BE ROD DIAMETER PLUS 1 INCH.
- ⑥ LENGTH ADEQUATE TO EXTEND TO WITHIN $rac{1}{2}$ INCH OF THE INNER SURFACE OF THE PIPE.




D

ADJUSTABLE TIE ROD TABLE 5/8 5 12-60 3/4 5 1/2 3/4 90-108 DIMENSIONS SHOWN ARE IN INCHES **TAPERED** PLAIN RIGHT AND LEFT THREADS **SLEEVE NUTS** 2 1/2" MIN. THREADED




ADJUSTABLE TIE ROD (ALTERNATE NO. 3)



FOR PIPE SECTIONS REQUIRING TIE RODS

TRANSVERSE SECTION



SECTION A-A

CONCRETE COLLAR DETAIL


JOINT TIES FOR CONCRETE PIPE AND CONCRETE COLLAR DETAIL

STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION

6/5/2012 /S/ Jerry H. Zogg DATE ROADWAY STANDARDS DEVELOPMENT ENGINEER

 ∞

Ω



GENERAL NOTES

DETAILS OF CONSTRUCTION, MATERIALS AND WORKMANSHIP NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE CONTRACT.

METALLIC (STANDARD SPECIFICATION 652.2.2) OR NONMETALLIC (STANDARD SPECIFICATION 652.2.3) CONDUIT SHALL BE FURNISHED AND PLACED AS SHOWN.

DEPTH OF CONDUIT INSTALLED BELOW THE TRAVELED WAY SHALL BE 24 INCHES MINIMUM AND 36 INCHES MAXIMUM.

DEPTH OF CONDUIT INSTALLED THAT IS NOT BELOW THE TRAVELED WAY SHALL BE 18 INCHES MINIMUM AND 36 INCHES MAXIMUM.

ANY EXCEPTION TO THE MAXIMUM DEPTH SHALL BE ONLY WITH THE WRITTEN APPROVAL OF THE ENGINEER.

THE TRENCH SHALL NOT BE BACKFILLED PRIOR TO INSPECTION OF THE CONDUIT.

ALL METALLIC CONDUIT RACEWAY ENDS SHALL BE REAMED AND THREADED.

ALL METALLIC CONDUIT IN WHICH WIRE OR CABLE IS TO BE INSTALLED SHALL BE BUSHED WITH APPROVED THREADED BUSHINGS BEFORE INSTALLATION OF THE WIRE OR CABLE.

ALL METALLIC CONDUITS IN WHICH WIRE OR CABLE IS NOT TO BE INSTALLED SHALL BE CAPPED WITH THREADED PROTECTIVE CAPS, AS APPROVED BY THE ENGINEER.

ALL NONMETALLIC CONDUIT SHALL BE CAPPED OR PLUGGED IMMEDIATELY AFTER INSTALLATION AND SHALL REMAIN CAPPED OR PLUGGED UNTIL WIRE/CABLES ARE INSTALLED.

NONMETALLIC CONDUITS IN WHICH WIRE OR CABLE IS NOT BEING INSTALLED SHALL REMAIN CAPPED OR PLUGGED.

BENDING OF PVC ELECTRICAL CONDUIT SHALL BE ACCOMPLISHED BY USING A BLANKET OR EMERSION TYPE TANK DESIGNED FOR THE PURPOSE OF BENDING PVC ELECTRICAL CONDUIT.

ALL CUT ENDS SHALL BE TRIMMED INSIDE AND OUTSIDE TO REMOVE ALL ROUGH EDGES ON NONMETALLIC CONDUIT. (SEE NEC 347.5)

WHEN REQUIRED TO CONNECT NONMETALLIC CONDUIT TO METALLIC CONDUIT, ONLY U.L. LISTED ADAPTER FITTINGS SHALL BE USED.

PRIOR TO CONDUIT ACCEPTANCE, CONDUIT CAPS OR PLUGS SHALL BE REMOVED, AND THE CAPS, PLUGS AND CONDUIT ENDS SHALL BE THOROUGHLY CLEANED AND THEN THE CAPS OR PLUGS REIN-STALLED TO ENSURE THAT THE CAPS OR PLUGS CAN BE EASILY REMOVED IN THE FUTURE.

ALL CONDUIT BEING FURNISHED AND INSTALLED SHALL HAVE THE U.L. LABEL FIRMLY

CONDUIT RUNS SHALL BE THE SAME SIZE OF CONDUIT FROM ONE END TO THE OTHER (FROM PULL BOX TO PULL BOX-OR-JUNCTION BOX TO JUNCTION BOX-OR-BASE TO BASE. ETC.).

POLY ROPE OR A PULL WIRE SHALL BE INSTALLED AS STATED IN THE STANDARD SPECIFICATION, ITEM 652.3.1.1.

ALL CONDUIT RUNS SHALL BE STRAIGHT (WITHOUT BENDS) FROM PULL BOX TO PULL BOX, PULL BOX TO BASE AND BASE TO BASE AS SHOWN ON THE PLANS.

BOTTOM OF ¼" HOLE PVC CONDUIT-CONDUIT TRENCH BOTTOM OF METALLIC CONDUIT-FOR DRAINAGE CONDUIT TRENCH 1" DIA. X 6" NIPPLE NO. 2 COARSE NO. 2 COARSE AGGREGATE FILL AGGREGATE FILL I'-0" DIA. OR SQUARE → —1'-0" DIA. OR SQUARE —>

NOTE: INSTALL AT LOCATIONS WHERE METALLIC CONDUITS

CANNOT BE PITCHED TO DRAIN INTO A PULL BOX.

DRAIN SUMP FOR METALLIC CONDUIT DRAIN SUMP FOR PVC CONDUIT

NOTE: INSTALL AT LOCATIONS WHERE PVC CONDUITS

CANNOT BE PITCHED TO DRAIN INTO A PULL BOX.

ARROW MARK INSCRIBED IN PAVEMENT SURFACE OVER € OF CONDUIT (BOTH ENDS) — 2'-0"*—* — 2'-0" NORMAL PAVEMENT EDGE OF PAVEMENT THICKNESS PAVEMENT OR BACK OF CURB BASE COURSE BACKFILL SLOPE 1/8"/FT. EITHER DIRECTION *DEPTH OF CONDUIT AND LENGTH OF PULL BOX VARIES CONDUIT, PITCH TO DRAIN WITH HEIGHT OF CURB USED. ALSO SEE PULL BOX S.D.D. 9B4

SIDE ELEVATION DETAIL FOR CONDUIT UNDER PAVED HIGHWAYS

CONDUIT UNDER PAVED HIGHWAYS

STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION

 $\mathbf{\omega}$

Ω

APPROVED Sept. 2014 /S/ Ahmet Demirbilek DATE STATE ELECTRICAL ENGINEER FHWA

6

ARROW MARK SHALL BE INSCRIBED IN PAVEMENT SURFACE 1/4" TO 3/8"

DEEP AT EACH LOCATION WHERE CONDUITS ARE PLACED UNDER

PLAN VIEW

ARROW MARK

CONDUIT

THE PAVEMENT

EDGE OF

PAVEMENT OR BACK

OF CURB

DIMENSION IN INCHES		CORRUGATED STEEL PIPE									
PIPE DIAMETER (INSIDE)	Α	12	12	12	18	18	18	24	24	24	
PIPE LENGTH **	В	24	30	36	24	30	36	36	42	48	
WALL THICKNESS	С	0.064	0.064	0.064	0.064	0.064	0.064	0.064	0.064	0.064	
COVER	D	10 1/4	10 1/4	10 1/4	16 1/4	16 1/4	16 1/4	22 1/4	22 1/4	22 1/4	
FRAME	Ε	14 1/2	14 1/2	14 1/2	20 ½	20 ½	20 ½	26 ½	26 ½	26 ½	
FRAME	F	8 1/2	8 1/2	8 1/2	14 1/2	14 ½	14 1/2	20 ½	20 ½	20 ½	
FRAME	G	11 1/2	11 1/2	11 1/2	17 1/2	17 1/2	17 1/2	23 ½	23 ½	23 ½	
WEIGHT IN POUNDS *											
FRAME AND COVER		60	60	60	110	110	110	155	155	155	

- * THE ACTUAL WEIGHT OF THE MANHOLE FRAME AND COVER MAY VARY WITHIN 5 PERCENT PLUS OR MINUS OF THE WEIGHTS SHOWN.
- NORMALLY USED LENGTHS. THE PROJECT ENGINEER SHALL DETERMINE IF PIPE LENGTHS, OTHER THAN THOSE SPECIFIED, SHALL BE USED, TO A MAXIMUM OF 48" (CONTINUOUS LENGTH, NON-SPLICED). THE ADDITIONAL LENGTH SHALL BE INCIDENTAL TO THE PULL BOX BID PRICE.

6" MAX. **EXTENSION** TOP OF ORIGINAL CORRUGATED PIPE (3) BOLTS, NUTS & LOCKWASHERS REQUIRED

ELECTRIC

FINAL GRADE

ALL METALLIC CONDUIT

AND THREADED

CUT OPENINGS

THE FIELD

2" PVC PIPE CAP ON BOTH ENDS

WITH 7, 8 1/4" HOLES DRILLED

IN EACH END.

PULL BOX

AS REQUIRED IN

ENDS SHALL BE REAMED

ALL CONDUIT PITCHED

4 TO 8 BRICKS

EQUALLY SPACED

TO DRAIN TO PULL BOXES

2" DRAIN DUCT TO

DITCH OR SEWER

WHEN SPECIFIED

CORRUGATED PIPE EXTENDER

HEAVY DUTY FRAME -

6" MIN.

(TYP.)

AND COVER

WHEN A PULL BOX IS INSTALLED IN CRUSHED

AGGREGATE SHOULDERS, PLACE IT 2-3

2-3 INCHES OF CRUSHED AGGREGATE

NO. 2 COARSE

(SEE SECTION 501

OF THE STANDARD

WIRE AND/OR CABLE.

INSTALL END BELLS (U.L. LISTED FOR


CONDUIT BEFORE INSTALLATION OF

ELECTRICAL USE) ON ALL NONMETALLIC


SPECIFICATIONS)

AGGREGATE

INCHES BELOW GRADE AND COVER IT WITH




воттом




ALTERNATE COVER (LOCKING)

TIGHTENING BAR TYPE



EQUIPMENT GROUNDING LUG AND LOCATION IN STEEL PULL BOXES



EQUIPMENT GROUNDING LUG AND LOCATION IN STEEL PULL BOXES

PULL BOX TO NEAREST BASE DISTANCE MORE THAN 20 FEET. PULL BOX GROUND WIRE SHALL CONNECT AT SYSTEM GROUNDING WIRE. USE DEPARTMENT APPROVED TAP CONNECTOR.

PULL BOX

STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION

APPROVED

Sept. 2014 /S/ Ahmet Demirbilek DATE STATE ELECTRICAL ENGINEER FHWA

GENERAL NOTES

DETAILS OF CONSTRUCTION, MATERIALS AND WORKMANSHIP NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE CONTRACT.

ALL FRAMES AND COVERS SHALL BE HEAVY DUTY TYPE, SUITABLE FOR VEHICULAR

PULL BOXES LOCATED IN THE ROADWAYS SHALL HAVE LOCKING COVERS.

ENTRANCE HOLES INTO PULL BOXES SHALL BE CUT WITH A CIRCULAR HOLE SAW OR HYDRAULIC CONDUIT PUNCH. HOLE SIZE SHALL BE THE OUTSIDE DIAMETER OF THE CONDUIT THAT IS TO FIT IN THE OPENING PLUS NO MORE THAN 1/4".

THE CONTRACTOR SHALL NOT INSTALL WIRE IN ANY PULL BOX UNTIL ITS INSTALLATION HAS BEEN INSPECTED AND ACCEPTED BY THE ENGINEER.

GROUNDING LUGS (MECHANICAL CONNECTORS) SHALL BE U.L. LISTED AND APPROVED

ALL METALLIC CONDUIT IN WHICH WIRE AND/OR CABLE IS TO BE INSTALLED. SHALL BE BUSHED BEFORE INSTALLATION OF THE WIRE AND/OR CABLE.

WHEN PULL BOXES ARE INSTALLED FOR FUTURE USE, DO NOT INSTALL THE EQUIPMENT GROUNDING LUG. THE EQUIPMENT GROUNDING LUG, THE EQUIPMENT GROUNDING ELECTRODE AND THE EQUIPMENT GROUNDING CONDUCTOR SHALL BE REQUIRED AND INSTALLED UNDER A FUTURE WIRING CONTRACT.

TRAFFIC LOADS.

6


D

D 9 \Box

Ω

တ

Ω



IF A BASE REQUIRES A DEEP FORM BECAUSE OF LOOSE DIRT OR FILL. THE FORM SHALL BE REMOVED BEFORE BACKFILLING AROUND THE BASE.
BACKFILL SHALL BE TAMPED TIGHT AGAINST THE BARE CONCRETE BASE IN LAYERS OF 1FOOT OR LESS. A NO. 4 AWG, STRANDED COPPER EQUIPMENT GROUNDING CONDUCTOR SHALL

BE EXOTHERMICALLY WELDED TO THE EQUIPMENT GROUNDING ELECTRODE

(GROUND ROD) FOR TYPE 1. TYPE 2. TYPE 5. AND TYPE 6 BASES.

GENERAL NOTES (CONTINUED)

ENDS OF CONDUIT INSTALLED BELOW GRADE FOR FUTURE USE SHALL BE

OF CONCRETE BASES BEFORE INSTALLATION OF CABLE OR WIRE.

CAPPED IF METALLIC OR PLUGGED IF NONMETALLIC.

BELL ENDS SHALL BE INSTALLED ON ALL PVC CONDUIT EXPOSED AT THE TOP

THE EQUIPMENT GROUNDING CONDUCTOR SHALL BE FURNISHED AND INSTALLED TO ENTER THE BASE OF THE TYPE 2 AND TYPE 5 BASES THROUGH A LINCH CONDUIT INSTALLED FOR GROUNDING PURPOSES, LEAVING A 4 FOOT COIL OF WIRE ABOVE THE CONCRETE BASE. THE EQUIPMENT GROUNDING CONDUCTOR SHALL BE NEATLY COILED AND THE COILS TIED TOGETHER.

ANCHOR RODS SHALL BE THREADED 12" IN LENGTH ON EACH END OF THE ROD, ANCHOR RODS SHALL BE MANUFACTURED IN ACCORDANCE WITH SECTION 654.2.1 OF THE STANDARD SPECIFICATIONS.

WASHERS AND LOCK WASHERS ARE REQUIRED ON ALL ANCHOR RODS.

WHEN ANCHOR RODS USING THE ALTERNATE "L" BEND ARE FURNISHED. THE 4" "L" BEND SHALL BE IN ADDITION TO THE SPECIFIED ANCHOR ROD BAR LENGTH. THE "L" BEND END SHALL NOT BE THREADED.

ANCHOR RODS SHALL BE INSTALLED WITH MISALIGNMENTS OF LESS THAN 1:40 FROM VERTICAL.

WELDING OF THE ANCHOR RODS TO THE CAGE IS UNACCEPTABLE. TIE WIRES SHALL BE USED.

BAR STEEL REINFORCEMENT SHALL BE COATED WITH POWDERED EPOXY RESIN IN ACCORDANCE WITH SECTION 505 OF THE STANDARD SPECIFICATIONS (LATEST EDITION).

- 1) THE MINIMUM DEPTH OF CONDUIT EXITING THE CONCRETE BASE AND INSTALLED BELOW THE TRAVELED WAY SHALL BE 24 INCHES. THE MINIMUM DEPTH OF CONDUIT EXITING THE CONCRETE BASE THAT IS NOT INSTALLED BELOW THE TRAVELED WAY SHALL BE 18 INCHES. THE MAXIMUM DEPTH OF ALL CONDUIT SHALL BE 36 INCHES EXCEPT WITH WRITTEN APPROVAL BY THE ENGINEER.
- (2) (4) 1" DIA. X 3'-6" ANCHOR RODS.
- (3) (4) 1" DIA. X 5'-0" ANCHOR RODS.
- (4) (6) NO. 6 X 6'-8" BAR STEEL REINFORCEMENT.
- (5) (7) NO. 4 X 5'-1" BAR STEEL REINFORCEMENT @ 1'-0" C-C.
- (6) (4) 1" DIA. X 3'-6" ANCHOR RODS.
- (7) (6) NO.4 X 4'-8" BAR STEEL REINFORCEMENT.
- (8) (5) NO. 4 X 5'-1" BAR STEEL REINFORCEMENT @ 1'-0" C-C.

FHWA

GENERAL NOTES

DETAILS OF CONSTRUCTION, MATERIALS AND WORKMANSHIP NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE CONTRACT

BASES SHALL BE EXCAVATED BY USE OF A CIRCULAR AUGER.

TOP SURFACES OF CONCRETE BASES SHALL BE TROWEL FINISHED SMOOTH AND LEVEL.

CONDUIT SIZES AND LOCATIONS SHALL BE AS SHOWN ON THE PLANS.

THE FINAL OR TERMINATING CONCRETE BASE IN A CONDUIT RUN SHALL HAVE A 6" EXIT STUB INSTALLED FOR FUTURE CABLING USE. THE EXIT STUB SHALL BE SIZED AS USED THROUGHOUT THE CONDUIT RUN AS SHOWN AT THE ENTRANCE OF THE BASE.

MINIMUM BENDING RADIUS OF CONDUIT IS EQUAL TO 6 X THE DIAMETER.

CONDUIT HEIGHT ABOVE CONCRETE BASES SHALL BE 1 INCH. ALL METALLIC CONDUIT ENDS SHALL BE REAMED AND THREADED.

ALL CONDUIT ENDS AT THE TOP OF CONCRETE BASES SHALL BE CAPPED IF METALLIC OR PLUGGED IF NONMETALLIC IMMEDIATELY AFTER PLACEMENT AND BEFORE CONCRETE IS POURED. CONDUITS IN WHICH WIRE OR CABLE IS NOT INSTALLED SHALL REMAIN CAPPED OR PLUGGED.

FORMING DETAIL

1'-8"

a)

- FORM

FORMING SHALL BE

CONCRETE HAS SET

REMOVED AFTER

FORM DEPTH SHALL BE

GRADE ON THE LOWER

SIDE OF BASE

4" MAX.

CONDUIT WITHIN

6" DIA.

ANCHOR RODS SHALL BE

ORIENTED PARALLEL TO

1" CHAMFER ALL AROUND

FORM ALL EXPOSED

CONCRETE, PROVIDE


6

Ö

ဖ

C

NO MORE THAN 6" BELOW



QUANTITY

REQUIREMENTS

ARDS OF CONCRETE

APPROX. CUBIC

LBS. OF HOOP

LBS. OF VERTICAL

BAR STEEL

BAR STEEL

CONCRETE BASE TYPE

0.57

23

60

0.40

NONE


NONE


5 & 6

0.40

16

18





CONCRETE BASES

* ANY ANCHOR ROD PROJECTION SHORTER THAN 2¾" OR LONGER THAN 31/4" SHALL REQUIRE THE BASE TO BE REMOVED AND REPLACED AT THE CONTRACTORS EXPENSE.

** FOR NONBREAKAWAY INSTALLATIONS, 41/2" ± ANCHOR ROD PROJECTION WITH THE USE OF LEVELING NUTS. RODENT SCREEN REQUIRED.

CONCRETE BASES, TYPES 1, 2, 5, & 6


STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION


APPROVED Sept. 2014 /S/ Ahmet Demirbilek STATE ELECTRICAL ENGINEER 2

6

ပ Ω

Δ





BASES SHALL BE EXCAVATED BY USE OF A CIRCULAR AUGER.

TOP SURFACES OF CONCRETE BASES SHALL BE TROWEL FINISHED AND LEVEL.

CONDUIT SIZES AND LOCATIONS SHALL BE AS SHOWN ON THE PLANS.

THE FINAL OR TERMINATING CONCRETE BASE IN A CONDUIT RUN SHALL HAVE A 6" EXIT STUB INSTALLED FOR FUTURE CABLING USE. THE EXIT STUB SHALL BE SIZED AS USED THROUGHOUT THE CONDUIT RUN AS SHOWN AT THE ENTRANCE OF THE BASE.

MINIMUM BENDING RADIUS OF CONDUIT IS EQUAL TO 6 X THE DIAMETER.

CONDUIT HEIGHT ABOVE CONCRETE BASES SHALL BE 4 INCHES. ALL METALLIC CONDUIT ENDS SHALL BE REAMED AND THREADED. NONMETALLIC CONDUIT SHALL HAVE BELL END INSTALLED. ALL CONDUIT SHALL BE SLOPED TO PULL BOX.

ALL CONDUIT ENDS AT THE TOP OF CONCRETE BASES SHALL BE CAPPED IF METALLIC OR PLUGGED IF NONMETALLIC IMMEDIATELY AFTER PLACEMENT AND BEFORE CONCRETE IS POURED. CONDUIT IN WHICH WIRE OR CABLE IS NOT INSTALLED SHALL REMAIN CAPPED OR PLUGGED.

BELL ENDS SHALL BE INSTALLED ON ALL PVC CONDUIT EXPOSED AT THE TOP OF CONCRETE BASES BEFORE INSTALLATION OF CABLE OR WIRE.

ENDS OF CONDUIT INSTALLED BELOW GRADE FOR FUTURE USE SHALL BE CAPPED IF METALLIC OR PLUGGED IF NONMETALLIC.

WHEN REQUIRED TO CONNECT NONMETALLIC CONDUIT TO METALLIC CONDUIT, ONLY ADAPTER FITTINGS, U.L.LISTED FOR ELECTRICAL USE. SHALL BE USED.

IF A BASE REQUIRES A DEEP FORM BECAUSE OF LOOSE DIRT OR FILL. THE FORM SHALL BE REMOVED BEFORE BACKFILLING AROUND THE BASE. BACKFILL SHALL BE TAMPED TIGHT AGAINST THE BARE CONCRETE BASE IN LAYERS OF 1 FOOT OR LESS.

A NO. 4 AWG, STRANDED COPPER EQUIPMENT GROUNDING CONDUCTOR SHALL BE EXOTHERMICALLY WELDED TO THE EQUIPMENT GROUNDING ELECTRODE (GROUND ROD).

THE EQUIPMENT GROUNDING CONDUCTOR SHALL ENTER THE BASE THROUGH A 1 INCH CONDUIT INSTALLED FOR GROUNDING PURPOSES, LEAVING A 4 FOOT COIL OF WIRE ABOVE THE CONCRETE BASE. THE EQUIPMENT GROUNDING CONDUCTOR SHALL BE NEATLY COILED AND THE COILS TIED TOGETHER.


WELDING OF THE ANCHOR RODS TO THE CAGE IS UNACCEPTABLE. TEMPLATES SHALL BE USED.

BAR STEEL REINFORCEMENT SHALL BE COATED WITH POWDERED EPOXY RESIN IN ACCORDANCE WITH SECTION 505 OF THE STANDARD SPECIFICATIONS

ANCHOR RODS SHALL BE INSTALLED WITH MISALIGNMENTS OF LESS THAN 1:40 FROM VERTICAL.

- 1 THE MINIMUM DEPTH OF CONDUIT EXITING THE CONCRETE BASE AND INSTALLED BELOW THE TRAVELED WAY SHALL BE 24 INCHES. THE MINIMUM DEPTH OF CONDUIT EXITING THE CONCRETE BASE THAT IS NOT INSTALLED BELOW THE TRAVELED WAY SHALL BE 18 INCHES. THE MAXIMUM DEPTH OF ALL CONDUIT SHALL BE 36 INCHES, (GREATER THAN 36 INCHES IF INSTALLED IN BREAKER-RUN), EXCEPT WITH WRITTEN APPROVAL BY THE ENGINEER.
- (2) (6) NO. 6 X 13'-7" BAR STEEL REINFORCEMENT.
- (3) (15) NO. 4 X 7'-4" BAR STEEL REINFORCEMENT @ 1'-0" C-C.

CONCRETE MASONRY	fc=3,500 p).S.i.
HIGH STRENGTH BAR STEEL REINFORCEMENT, GRADE 60	fy=60,000	p.s.i.
ANCHOR RODS, AASHTO M314 GRADE 55	fy=55,000	p.s.i.
TEMPLATES, ASTM, A709 GRADE 36	fy=36,000	p.s.i.



CONCRETE BASE TYPE 10 (FOR TYPE 9 & 10 POLES)

TO BE USED WHEN GROUND ELEVATION AT BASE EQUALS OR IS GREATER THAN HIGH POINT OF ROADWAY ELEVATION. SEE S.D.D. 9C13-2 WHEN GROUND ELEVATION AT BASE IS LOWER THAN HIGH POINT OF ROADWAY ELEVATION.

€ FOOTING PARALLEL TO-1/2" THICK TEMPLATES ROADWAY 11/2" ANCHOR RODS DIRECTION TOP AND BOTTOM TEMPLATES TOP TEMPLATE REMOVED AFTER CONCRETE SET TOP OF CONCRETE THREAD TOP 81/2" OF ANCHOR ROD FOR 3 NUTS AND 2 WASHERS AND BOTTOM 51/2" FOR 2 NUTS PER ANCHOR ROD. HOT-DIP GALVANIZE THE ENTIRE LENGTH OF THE ANCHOR RODS (AASHTO M111) AND HOT-DIP NUTS AND WASHERS (AASHTO M232). USE ZINC COATED NUTS MANUFACTURED WITH (6) - 1¹/₂" X 50" SUFFICIENT ALLOWANCE TO ALLOW NUTS ANCHOR RODS TO RUN FREELY ON THE THREADS. BOTTOM TEMPLATE LEFT IN PLACE THREAD BOTTOM OF ANCHOR ROD 51/2" ANCHOR BOLT ASSEMBLY DETAIL

CONCRETE BASE TYPE 10

ANCHOR ASSEMBLY

NO MORE THAN 4" BELOW

GRADE ON THE LOWER

SIDE OF BASE

4" MAX.

ANCHOR ROD CIRCLE

DIAMETER = 15"

APPROX. CUBIC YARDS OF CONCRETE 2.5

VARDS OF CONCRETE

LBS. OF HOOP
BAR STEEL

LBS. OF VERTICAL
BAR STEEL

122

CONCRETE BASE TYPE 10

TROWEL FINISH

OF CONCRETE

2" MAX.-

- FORM

4" MAX.

FORMING DETAIL

AND LEVEL TOP

FORMING SHALL BE REMOVED AFTER

CONCRETE HAS SET

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

ပ

တ


Δ

APPROVED

FHWA

DATE STATE ELECTRICAL ENGINEER

D.D. 9 C 11-5



H.S. REINFORCEMENT = 433 LBS.

SEE S.D.D. 9C13-2 WHEN GROUND ELEVATION AT BASE IS LOWER THAN HIGH POINT OF ROADWAY ELEVATION.

TO BE USED WHEN GROUND ELEVATION AT BASE EQUALS OR IS GREATER THAN HIGH POINT OF ROADWAY ELEVATION.

6

D

D

9

C

2

0


Δ

Ω


STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION








TOP AND BOTTOM TEMPLATES



ANCHOR BOLT ASSEMBLY DETAIL

CONCRETE BASE TYPE 13 ANCHOR ASSEMBLY



CONCRETE BASE TYPE 13

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

6

5b

12

ပ

Ω

APPROVED

DATE
STATE ELECTRICAL ENGINEER
FHWA

D D

9

D

Ω

တ

Ω


/S/ Ahmet Demirbilek


STATE ELECTRICAL ENGINEER

Sept. 2014

DATE

FHWA





6

D

D

9

Ш


ယ

က ш တ Ω

Ω

STATE OF WISCONSIN

DEPARTMENT OF TRANSPORTATION



Ö

ဖ

Ш

13b 6 Ω

6

D

D

9

Ш

DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE CONTRACT.

TYPE 5 ALUMINUM POLES SHALL BE CONSTRUCTED OF 6063-T6 ALUMINUM ALLOY.

THE TYPE 5 ALUMINUM POLES SHALL HAVE A MINIMUM WALL THICKNESS OF 0.188".

TYPE 5 STEEL POLES SHALL HAVE A MINIMUM WALL THICKNESS OF U.S. STANDARD

2% INCHES IN OUTSIDE DIAMETER. THE STRAIGHT PORTION OF THE SLIPFITTER

WHEN TRANSFORMER BASES ARE USED, WIRE CONEECTIONS SHALL BE MADE IN THE


- 4" x 6" REINFORCED HANDHOLE & COVER ASSEMBLY WITH 2 (TWO) 1/4" X 3/4" 20
- GROMMETS, 1" CHASE NIPPLES OR 1" CLOSE CONDUIT NIPPLES WITH BUSHINGS
- FURNISH AND INSTALL VENTILATED, CAST, METALLIC (ALUMINUM ALLOY) CAPS.
- SHIMMING, IF NEEDED, SHALL BE LOCATED BETWEEN THE CONCRETE FOUNDATION

POLE MONTINGS FOR LIGHTING UNITS, TYPE 5 (30 FEET)

STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION 6

-13 Ш

6 Ω Ω



BE STAINLESS STEEL

BASE PLATE

13


S.D.D. 9 E 1-13g


Sept. 2014


FHWA


/S/ Ahmet Demirbilek

STATE ELECTRICAL ENGINEER









POLE TYPES 9 AND 10 ARE FOR ARM LENGTHS 15-FOOT TO 30-FOOT.

POLE TYPES 12 AND 13 ARE FOR ARM LENGTHS 35-FOOT TO 55-FOOT.

MONOTUBE POLE AND ARM SHALL BE GALVANIZED STEEL.

RING-STIFFENED BUILT-UP BOX TYPE OF ATTACHMENT FOR TRAFFIC SIGNAL ARM.

ONE (1) PIECE POLE CONSTRUCTION (NO WELDED POLE SECTIONS).

STANDARD STRAIGHT ARM DESIGN (3 % ± RISE).

SECTION 657, POLES OF THE STANDARD SPECIFICATIONS SHALL APPLY TO THIS DRAWING.

PROVIDE WIREWAY THRU POLE WALL AND ARM CONNECTION PLATES. PROVIDE ROUND, SMOOTH INSIDE SURFACE.

MANUFACTURER'S SUBMITTED POLE DESIGNS AND DRAWINGS SHALL BE SIGNED AND STAMPED BY A REGISTERED PROFESSIONAL ENGINEER AND CERTIFIED AS BEING IN COMPLIANCE WITH THE AASHTO 2013 6TH EDITION AND ALL PERTINENT WISDOT SPECIFICATIONS AND DRAWINGS FOR TRAFFIC AND LIGHTING STRUCTURES AND AS FOLLOWS:

- CATEGORY I FATIGUE LOADS OF GALLOPING, TRUCK GUSTS (AT 45 MPH VEHICLE VELOCITY) AND NATURAL WIND GUSTS FOR DESIGN OF TYPE 9 AND TYPE 10 STRUCTURES.
- CATEGORY I FATIGUE LOADS OF GALLOPING, TRUCK GUSTS (AT 45 MPH VEHICLE VELOCITY) AND NATURAL WIND GUSTS FOR DESIGN OF TYPE 12 AND TYPE 13 STRUCTURES.
- 90 MPH (3-SECOND GUST) WIND SPEED AND A 50 YEAR DESIGN LIFE.

SECURE THE OPENING BELOW THE BASE PLATE WITH STAINLESS STEEL OR GALVANIZED STEEL MESH AND SECURE THE MESH WITH $\frac{3}{4}$ " S.S. BANDING AROUND THE LEVELING NUTS.

INDENT PRINT (NOMINAL $\frac{1}{2}$ " HIGH) THE POLE LENGTH AND FIRST TWO LETTERS OF THE MANUFACTURERS NAME ON TWO SIDES OF THE BASE PLATE 180 DEGREES APART, BEFORE GALVANIZING. THE ARM SHALL BE IDENTIFIED WITH THE SAME INFORMATION BY INDENT PRINT.

SIGNAL FACE SHALL BE MOUNTED 6 INCHES (NOMINAL) FROM THE END OF THE MONOTUBE ARM OR AS SHOWN ON THE PLAN CONSTRUCTION DETAIL OR AS DIRECTED BY THE PROJECT ENGINEER/ELECTRICAL OPERATIONS PERSONNEL. MOUNT ALL LIKE HEADS AT SAME ELEVATION.


SIGN MOUNTING BRACKETS SHALL BE FURNISHED IN ACCORDANCE WITH SECTION 637 OF THE STANDARD SPECIFICATIONS FOR HIGHWAY AND STRUCTURE CONSTRUCTION.

- DESIGN FOR MAXIMUM ALLOWABLE HANDHOLE WITH COVER ASSEMBLY WITH TWO 1/4" X 3/4" 20 TPI STAINLESS STEEL HEX HEAD BOLTS.
- 2) SIGNAL MOUNTING BRACKETS FOR POLE MOUNTING, MOUNT WITH CAP SCREW AND BANDING, (SEE SPECIFICATIONS SEC. 658).
- 3 SECURELY MOUNT BACKPLATES, PROJECTING 5" BEYOND ALL SIDES OF THE SIGNAL FACE HOUSING, PER MANUFACTURERS RECOMMENDATIONS.
- 4 THE TOP OF THE POLE SHAFT AND THE END OF THE MONOTUBE ARM SHALL BE EQUIPPED WITH A REMOVABLE, VENTILATED CAP HELD SECURELY IN PLACE WITH SET SCREWS.
- (5) FACTORY-WELDED BRACKET FOR GROUNDING LUG, OPPOSITE HANDHOLE, (LUG AND HARDWARE PAID UNDER SEPARATE ITEM), PROVIDE HOLE IN BRACKET FOR 1/4" x 3/4" 20 TPI STAINLESS STEEL HEX HEAD BOLT.
- 6 FACTORY-WELDED "J" HOOK FOR STRAIN RELIEF FOR POLE LUMINAIRE WIRE.
- (7) INSTALL DEPARTMENT PROVIDED STRUCTURAL IDENTIFICATION PLAQUES.

STRUCTURAL IDENTIFICATION PLAQUES SHALL BE PLACED ON THE POLES IN THE SAME DIRECTION AS THE ARM.


MOUNTING HEIGHT SHALL BE 5'-0" ABOVE THE CURB OR SHOULDER .ADJUST IF IT IS KNOWN THAT REQUIRED TRAFFIC SIGNS WILL BE OBSTRUCTED.

8 FACTORY DRILLED 1/2" DRAIN HOLE 2" FROM FLANGE CONNECTION PLATE.




SIGNAL FACE MOUNTING BRACKET DETAIL FOR MONOTUBE ARM

(MOUNT PER MANUFACTURER'S RECOMMENDATION)




TYPICAL GROUNDING CONNECTIONS

NUT, BOLT AND WASHERS SHALL
BE STAINLESS STEEL



PINNACI F

VERTICAL MOUNTING DETAIL



"J" HOOK WIRE SUPPORT

GENERAL NOTES AND HARDWARE DETAILS FOR TYPE 9, 10, 12 & 13 POLES WITH MONOTUBE ARMS

6

ထ


ш


Δ

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

5'-0"

APPROVED
Sept. 2014
DATE
STATE ELECTRICAL ENGINEER
FHWA





CONTRACTION JOINTS

CONSTRUCT TRANSVERSE CONTRACTION JOINTS NORMAL TO THE CENTERLINE. SHOW THE LOCATION OF CONTRACTION JOINTS THROUGH INTERSECTIONS ON THE PLANS OR AS DIRECTED BY THE ENGINEER.

DO NOT SEAL OR FILL CONTRACTION JOINTS.

INSTALL DOWEL BARS PARALLEL TO THE PAVEMENT CENTERLINE AND PAVEMENT

FOR PAVEMENT SLABS OF VARYING WIDTHS, LOCATE THE OUTER MOST DOWEL BAR SO THAT THE CENTER OF THE BAR IS A MINIMUM OF 6 INCHES AND A MAXIMUM OF 18 INCHES FROM THE FREE EDGE OF PAVEMENT.


CONSTRUCTION JOINTS

LOCATE CONSTRUCTION JOINTS A MINIMUM OF 6 FEET FROM THE NEAREST CONTRACTION JOINT AND ALIGN PARALLEL TO CONTRACTION JOINTS.

- 1 REFER TO TYPICAL CROSS SECTIONS FOR ADDITIONAL DETAILS.
- 2 MEASURE THE ENTIRE PAVED WIDTH INCLUDING THE PORTION(S) LABELED PAVED SHOULDER AS CONCRETE PAVEMENT.

PAVEMENT DEPTH, DOWEL BAR SIZE AND JOINT SPACING TABLE

PAVEMENT DEPTH (D)	DOWEL BAR DIAMETER	CONTRACTION JOINT SPACING
5 ½", 6",6 ½"	NONE	12'
7",7 1/2"	1"	14'
8" , 8 ¹ / ₂ "	1 1/4"	15'
9",9 1/2"	1 1/4"	15'
10" & ABOVE	1 1/2"	15'




D

D

13

C

CONTRACTION JOINT LAYOUT FOR TWO-LANE TWO-WAY HIGHWAY



PAVED

- 2'-0" PAVED

SHOULDER


SHOULDER

CONTRACTION JOINT LAYOUT FOR DIVIDED HIGHWAY

RURAL DOWELED **CONCRETE PAVEMENT**

STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION 6

ပ 13 Ω



6

Ö

D

13

C

GENERAL NOTES

- (1) OBTAIN THE ENGINEER'S APPROVAL FOR THE USE OF ALTERNATIVE DESIGNS OF THE DOWEL ASSEMBLY. USE MECHANICAL DOWEL BAR INSERTERS OR DOWEL ASSEMBLIES WHEN CONSTRUCTING CONTRACTION JOINTS.
- ② SECURE BASKETS WITH ANCHORS TO HOLD DOWEL BARS IN THE CORRECT POSITION AND ALIGNMENT. TYPE, LOCATION, NUMBER AND LENGTH OF ANCHORS ARE DEPENDENT UPON FIELD CONDITIONS.
- 3 FORM OR SAW CONSTRUCTION JOINTS. PROVIDE A 1/4-INCH RADIUS AT FORMED JOINTS.
- 4 PROVIDE A SMOOTH VERTICAL FACE FOR THE ENTIRE DEPTH OF THE PAVEMENT WHEN FORMING CONSTRUCTION JOINTS.
- (5) INSTALL DOWEL BARS AT CONSTRUCTION JOINTS BY FORMING OR DRILLING. INSTALL FORMED DOWEL BARS 12 INCHES C-C AND 12 INCHES FROM PAVEMENT EDGE. REMOVE EXCESS CONCRETE FROM THE FREE END OF THE DOWEL BAR IF DOWEL BARS ARE FORMED THROUGH A HEADER BOARD. INSTALL DRILLED DOWEL BARS ACCORDING TO DRILLED DOWEL BAR CONSTRUCTION JOINT DETAIL.
- (6) APPLY A THIN UNIFORM COATING OF SURFACE TREATMENT TO THE FREE END OF DOWEL BARS TO PREVENT BONDING.
- 7 ANCHOR DOWEL BARS INTO DRILLED HOLES WITH AN EPOXY. MAXIMUM DRILLED HOLE SIZE IS 1/8-INCH GREATER THAN DOWEL BAR DIAMETER, 9 INCHES IN LENGTH.

RURAL DOWELED CONCRETE PAVEMENT


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION


APPROVED


DATE PAVEMENT POLICY & DESIGN ENGINEER


FHWA

S.D.D. 13 C 11












DIAGONAL MANHOLE BOXOUT FOR CONSTRUCTION JOINTS




MANHOLE WITH LONGITUDINAL JOINT




MANHOLE WITH DIVERTED LONGITUDINAL CONTRACTION JOINT



INLET WITH TRANSVERSE JOINT



MANHOLE WITH TRANSVERSE JOINT



MANHOLE WITH DIVERTED TRANSVERSE CONTRACTION JOINT

- ① USE BOXOUTS WHEN UTILITY STRUCTURE IS IN THE PATH OF CONSTRUCTION JOINTS. PROVIDE A 1-FOOT MINIMUM CLEARANCE BETWEEN THE EXTERIOR LIMIT OF THE STRUCTURE TO THE DIAMOND BOXOUT.
- 2 ADJUST TRANSVERSE JOINT TO INTERSECT MANHOLE IF POSSIBLE.
- (3) IF DISTANCE BETWEEN THE LONGITUDINAL JOINT AND THE EDGE OF MANHOLE IS 2 FEET OR LESS, DIVERT THE LONGITUDIAL JOINT AT A 2:1 TAPER RATE TO THE CENTER OF THE MANHOLE. IF THE DISTANCE IS GREATER THAN 2 FEET, DO NOT DIVERT THE JOINT AND SAW AS NORMAL. PLACE REBAR REINFORCEMENT AROUND THE MANHOLE.
- (4) IF DISTANCE FROM THE EDGE OF THE MANHOLE TO THE NEAREST TRANSVERSE JOINT IS 4 FEET OR LESS, REDIRECT JOINT TO INTERSECT THE CENTER OF THE MANHOLE. IF DISTANCE IS GREATER THAN 4 FEET, DO NOT DIVERT THE JOINT AND SAW AS NORMAL. PLACE REBAR REINFORCEMENT AROUND THE MANHOLE.
- (5) ALIGN TRANSVERSE JOINT WITH ONE EDGE OF INLET WHEN PRACTICAL.

CONCRETE PAVEMENT
JOINTING AT UTILITY FIXTURES

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED


5-3-2013
DATE


/S/ Deb Bischoff
PAVEMENT POLICY & DESIGN ENGINEER


، [

6

<u>∞</u>



























TYPICAL STOP LINE PAVEMENT MARKING FOR SIDEROADS WITH CROSSWALK MARKING



TYPICAL STOP LINE PAVEMENT MARKING WITHOUT CURB AND GUTTER

GENERAL NOTES

- 1 18-INCH STOP LINES MAY BE DELETED OR ADDED BY THE PROJECT ENGINEER BASED ON VISIBILITY AND SIGHT LINES.
- 2 IF STOP SIGN IS LESS THAN OR EQUAL TO 40 FEET FROM THE EDGELINE THAN NO STOP LINE IS REQUIRED.
- (3) IF STOP SIGN IS LESS THAN OR EQUAL TO 30 FEET FROM THE FLANGELINE EXTENSION THAN NO STOP LINE IS REQUIRED.
- MOVE CLOSER TO EDGE OF TRAVEL LANE AS NEEDED FOR VISIBILITY AND SIGHT LINES.

STOP LINE AND CROSSWALK **PAVEMENT MARKING**

STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION

APPROVED	
4/30/2013	/S/ Travis Feltes
DATE	STATE TRAFFIC ENGINEER
FHWA	


Ē D 15 C

6

33

Ω





THIS LANE CLOSURE DETAIL IS TYPICAL FOR CLOSING THE LEFT LANE, FOR A RIGHT LANE CLOSURE, REVERSE THE TRAFFIC CONTROL.

THIS DETAIL MAY BE USED FOR ROADWAYS WITH EITHER TWO OR THREE LANES IN EACH DIRECTION.

THE EXACT NUMBER, LOCATION, AND SPACING OF ALL SIGNS AND DEVICES SHALL BE ADJUSTED TO FIT FIELD CONDITIONS AS APPROVED BY THE ENGINEER.

THE SPACING BETWEEN TRAFFIC CONTROL SIGNS SHOULD BE ADJUSTED TO NOT CONFLICT WITH AND SHOULD PROVIDE A DESIRABLE MINIMUM OF 200 FEET CLEARANCE TO EXISTING SIGNS THAT WILL REMAIN IN PLACE.

ALL SIGNS ARE 48"×48" UNLESS OTHERWISE NOTED. IF NECESSARY DUE TO SPACE CONSTRAINTS IN URBAN AREAS, 36" X 36" SIGNS MAY BE USED IF APPROVED BY DISTRICT TRAFFIC UNIT.

"WO" SIGNS ARE THE SAME AS "W" SIGNS EXCEPT THE BACKGROUND IS ORANGE.

SIGNS THAT WILL BE IN PLACE LESS THAN 7 CONTINUOUS DAYS AND NIGHTS, OR THAT WILL BE PLACED IN A CLOSED LANE, MAY BE MOUNTED ON PORTABLE SUPPORTS.

ANY SIGNS TEMPORARY OR EXISTING, WHICH CONFLICT WITH TRAFFIC CONTROL "IN USE" SHALL BE REMOVED OR COVERED AS NEEDED AND AS APPROVED BY THE ENGINEER.

REMOVE PAVEMENT MARKINGS AND PLACE TEMPORARY PAVEMENT MARKING, REMOVABLE TAPE IF LANE CLOSURE IS TO BE IN PLACE FOR 4 OR MORE CONTINUOUS DAYS AND NIGHTS.

ON UNDIVIDED ROADWAYS, OMIT THE SIGNS SHOWN ON LEFT SIDE OF ROAD.

W2O-1, G2O-1 AND G2O-2A SIGNS ARE NOT REQUIRED IF THE LANE CLOSURE IS WITHIN A LARGER WORK ZONE WHERE THESE SIGNS ARE ALREADY PRESENT.

OMIT G20-1 SIGNS IF LENGTH OF WORK AREA IS 2 MILES OR LESS.

CONSIDER GEOMETRICS WHEN LOCATING SIGNS AND ARROWBOARDS SO THE APPROACHING DRIVER HAS A CLEAR VIEW OF THE ARROWBOARDS AND LANE CLOSURE DRUMS.

PLACE THE ARROWBOARD AS CLOSE AS POSSIBLE TO THE BEGINNING OF THE LANE CLOSURE TAPER, PREFERABLY ON THE SHOULDER OR TERRACE.

CHANNELIZING DEVICES PLACED ADJACENT TO WORK AREA SHALL BE PULLED BACK FROM THE TRAVEL LANE WHEN WORK IS NOT IN PROGRESS.

BARRICADES IN A CLOSED LANE THAT MUST BE MOVED FOR A WORK OPERATION SHALL BE IMMEDIATELY RE-ESTABLISHED UPON COMPLETION OF THE OPERATION OR, FOR CONTINUING OPERATIONS, AT THE END OF EACH WORKING DAY.

WARNING LIGHTS ARE NOT REQUIRED IF THE LANE CLOSURE IS A DAYTIME ONLY OPERATION.

TRAFFIC CONTROL, SINGLE LANE CLOSURE, NON-FREEWAY/EXPRESSWAY

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION


APPROVED


8/2013 /S/ Travis Feltes

DATE STATE TRAFFIC ENGINEER OF DESIGN


FHWA

S.D.D. 15 D





- 1. DETAILS OF CONSTRUCTION, MATERIALS, AND WORKMANSHIP NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS, THE SPECIAL REPORTS OF THE STANDARD SPECIFICATIONS, THE SPECIAL PROVISIONS, AND THE PLANS.
- 2. UNLESS OTHERWISE NOTED, ALL SIGNS SHOWN ON THIS SHEET ARE "SIGNS, TYPE II".
- 3. UNLESS OTHERWISE NOTED, TYPE II SIGNS ON THIS SHEET SHALL HAVE "TYPE H REFLECTIVE SHEETING" AND "TYPE H MESSAGE MATERIAL". TYPE I SIGNS SHALL HAVE "TYPE SH REFLECTIVE
- 4. UNLESS OTHERWISE NOTED, ALL SIGNS SHOWN ON THIS SHEET SHALL HAVE A GREEN BACKGROUND AND WHITE MESSAGE.
- 5. TYPE II SIGNS ALL UPPERCASE MESSAGE (EXCEPT ON SHIELDS OR WHERE OTHERWISE NOTED) SHALL BE "SERIES E". ALL LOWERCASE MESSAGE WITH AN INITIAL UPPERCASE LETTER SHALL BE "SERIES E".
- 6. TYPE I SIGNS ALL UPPERCASE MESSAGE (EXCEPT ON SHIELDS OR WHERE OTHERWISE NOTED) SHALL BE "SERIES E MODIFIED". ALL LOWER CASE MESSAGE WITH AN INITIAL UPPERCASE LETTER SHALL BE "SERIES E MODIFIED". ALL CAP WORDS ARE "SERIES E".
- 7. UNLESS OTHERWISE NOTED, ALL SIGNS SHOWN ON THIS SHEET SHALL HAVE "TYPE A" OR "TYPE C" ARROWS AS SHOWN. SEE THE STANDARD SIGN PLATES FOR FURTHER DETAILS.
- 8. SEE THE STANDARD SIGN PLATES FOR FURTHER DETAILS ON ROUTE MARKER SHIELDS.
- 9. THE SIGN NUMBER IS DENOTED IN THE CIRCLE NEAR EACH DETAIL.
- 10. NUMBER FRACTIONS FOR INTERCHANGE SEQUENCE SIGNS SHALL BE "SERIES E" PER PLATES A11-7 AND A11-10.
- 11. DO NOT SCALE.



SHEET 1 OF 1

PROJECT NO:3700-20-71 HWY:STH 50 COUNTY: KENOSHA SCALE: E SIGNING DETAIL - TYPE II SIGNS SHEET

FILE NAME: N:\PDS\C3D\CAD\37002071\SIGNING\070101_MS.DWG

PLOT DATE: 9/23/2013 4:47 PM

PLOT BY : LAROSA, PHILIP P PLOT NAME : _____PLOT SCALE : *******

WISDOT/CADDS SHEET 47

1. Signs are Type II - Type H Reflective - reference WIS DOT Standard

areater than 48 inches (both vertical and horizontal) shall have one horizontal splice between the arrows and route shields. Vertical splices shall not be used on route assemblies with a horizontal dimension of 144 inches or less. The contractor shall not use more than one vertical joint per sign and the joint shall be between route shields.



PROJECT NO:

J32-1

J22-1

J23-1

J33-1

PLOT BY: mscsja

PLATE NO. __A2-15.8

DATE 2/06/14


SHEET NO:




URBAN ARFA

2' Min - 4' Max (See Note 6) 7'-3"(士) ** Curb Flowline. White Edgeline Location

RURAL AREA (See Note 2)



2' Min - 4' Max (See Note 6)



5'-3"(生) A POLICE AND A POL D^{-1} Outside Edae of Gravel

White Edgeline Location

** The existence of curb and gutter does not in itself mandate the vertical clearance illustrated.

HWY:

That height is typically measured where there is sidewalk adjacent to the roadway or parking is permitted. In the absence of sidewalk vertical clearance is measured from the top of the curb. Offset of signs is measured from the flow line.

* 6 feet from edge of a paved shoulder or 12 feet from the edge of pavement (edge line location) or 2 feet from outside edge of gravel, whichever is greater unless directed by project engineer.

PLOT DATE: 12-NOV-2014 14:03

GENERAL NOTES

- 1. Signs wider than 4 feet, 20 sq.ft or larger, shall be mounted on multiple posts. Refer to plate A4-4.
- 2. If signs are mounted on barrier wall, see A4-10 sign plate.
- 3. For expressways and freeways, mounting height is $7'-3''(\pm)$ or 6'-3" (±) depending upon existence of a sub-sign.
- 4. Minimum mounting height for J assemblies (A2-1S) is $7'-3''(\pm)$ or $6'-3''(\pm)$ per urban or rural detail respectively.
- 5. Minimum mounting height for signs mounted on traffic signal poles is $5' - 3'' (\pm)$.
- 6. Offset distance shall be consistent with existing signs or consistent throughout length of project.
- 7. The (+) tolerance for mounting height is 3 inches.
- 8. Folding signs shall be mounted at a height of 5'-3'' (\pm) or as directd by the Engineer.
- 9. The Double Arrow sign (W12-1) shall be mounted at a height of 2'-3" (\pm) . The Chevron sign (W1-8), Roundabout Chevron panel (R6-4B), Enhanced Reference Markers, Clearance Markers (W5-52), Mile Markers (D10 series), In Road Object Markers (W5-54) & End of Road Markers (W5-56) shall be mounted at a height of 4'-3'' (\pm).

POST EMBEDMENT DEPTH

D
(Min)
4'
5'

TYPICAL INSTALLATION OF PERMANENT TYPE II SIGNS ON SINGLE POSTS

WISCONSIN DEPT OF TRANSPORTATION

SHEET NO:

APPROVED

for State Traffic Engineer

DATE 11/12/14

PROJECT NO: FILE NAME : C:\CAEFiles\Projects\tr_stdplate\A43.DGN COUNTY:

PLOT BY: mscsja

PLOT NAME :

WISDOT/CADDS SHEET 42

PLOT SCALE: 99.237937:1.000000



NOTES: 1. ALL MATERIAL TO BE APPROVED

BY ENGINEER PRIOR TO INSTALLATION

- 2. SEE SIGN PLATE A4-8 FOR SIGN HARDWARE REQUIREMENTS
- 3. 18 INCH X 18 INCH SQUARE BOX-OUTS MAY BE USED FOR INSTALLATIONS IN EXISTING CONCRETE OR ASPHALT LOCATIONS.



ELEVATION VIEW

DETAIL OF STEEL 2 X 2 SIGN POST IN BOX-OUT



DETAIL OF WOOD 4 X 6 SIGN POST IN BOX-OUT

HWY:



PLAN VIEW

COUNTY:

FOR NEW CONCRETE/ASPHALT INSTALLATIONS

SIGN POST BOX-OUTS A4-3B

WISCONSIN DEPT OF TRANSPORTATION

For State Traffic Engineer

DATE 1/27/14 PLATE NO. A4-3B.1

SHEET NO:

FILE NAME : C:\CAEFiles\Projects\tr_stdplate\A43B.DGN

PROJECT NO:

PLOT DATE: 27-JAN-2014 09:48

PLOT NAME :

PLOT BY: mscsja

PLOT SCALE: 13.659812:1.000000

APPROVED


WISDOT/CADDS SHEET 42

- 1. For 3 or 4 post installations, individual post spacing shall be greater than 3'-6".
- 2. See tables below for required number of posts.
- 3. For expressways and freeways. mounting height is 7'-3'' (±) or 6'-3'' (±) depending upon existence of sub-sign.
- 4. The (±) tolerance for mounting height is 3 inches.
- 5. Minimum mounting height for J assemblies (A2-1S) is 7'-3'' (±) or 6'-3'' (±) per urban or rural detail respectively.
- 6. Offset distance shall be consistent with existing signs or consistent throughout length of project.
- 7. Folding signs shall be mounted at a height of 5'-3" (±) or as directed by the engineer.
- 8. The Double Arrow sign (W12-1) shall be mounted at a height of 2'-3" (±). The Chevron sign (W1-8). Roundabout Chevron panel (R6-4B), Clearance Markers (W5-52), Mile Markers (D10 series), In Road Object Markers (W5-54) & End of Road Markers (W5-56) shall be mounted at a height of 4"-3" (±).
- * 6 feet from edge of a paved shoulder or 12 feet from the edge of pavement (edge line location) or 2 feet from outside edge of gravel, whichever is greater unless directed by project engineer.
- ** The existence of curb and gutter does not in itself mandate the vertical clearance illustrated. That height is typically measured where there is sidewalk adjacent to the roadway or parking is permitted. In the absence of sidewalk vertical clearance is measured from the top of the curb. Offset of signs is measured from the flow line.
- *** See A4-3 sign plate for signs 4' or less in width or less than 20 S.F. in area.

URBAN AREA RURAL AREA (See Note 3) 2'Min - 4'Max (See Note 6) ₩E# FF# 6'-3"(±) 6'-3"(±) 7'-3"(±) ** Curb ****\ Flowline D **7000** White Edgeline

2'Min - 4'Max (See Note 6) 6'-3"(±) Curb Flowline. 48" DIAMOND WARNING SIGN

D 11



COUNTY:

Outside Edge

of Gravel

	SIGN SHAPE OTHER THAN (TWO POSTS REQUIRED	
	L	E
* * *	Greater than 48" Less than 60"	12"
	60" to 120"	L/5

SIGN SHAPE OTHER THAN (THREE POSTS REQUIR	
L	E
Greater than 120" less than 168"	12"

HWY:

White Edgeline,

Location

SIGN SHAPE OTHER THAN (FOUR POSTS REQUIRE	
L	E
168" and greater	12"

Location

Outside Edae

of Gravel

POST EMBEDMENT DEPTH

Area of Sign	
Installation	D
(Sq. Ft.)	(Min)
20 or Less	4'
Greater than 20	5'

TYPICAL INSTALLATION OF TYPE II SIGNS ON MULTIPLE POSTS

Matther

PLATE NO. A4-4.13

FILE NAME : C:\CAEFiles\Projects\tr_stdplate\A44.DGN

PROJECT NO:

PLOT DATE: 12-NOV-2014 14:01

PLOT NAME :

PLOT BY: mscsja

PLOT SCALE: 107.021305:1.000000

WISDOT/CADDS SHEET 42


SHEET NO:

WISCONSIN DEPT OF TRANSPORTATION

APPROVED

For State Traffic Engineer

DATE 11/12/14






PROJECT NO: HWY: COUNTY: SHEET NO: FILE NAME : C:\CAEFiles\Projects\tr_stdplate\A49.DGN PLOT DATE: 05-FEB-2015 17:09 PLOT BY: mscsja PLOT NAME : PLOT SCALE: 13.659812:1.000000

DATE 2/05/15

PLATE NO. <u>A4-9.9</u>

For State Traffic Engineer




- 1. WOOD 4"X6" POST MATERIAL SHALL CONFORM TO 507.2.2 OF THE WISDOT STANDARD SPECIFICATIONS
- 2. BLOCK BANDING AND CLIPS SHALL BE STAINLESS STEEL, 3/4" WIDTH AND 0.025" THICKNESS
- 3. SIGNS 3' OR GREATER IN HEIGHT SHALL UTILIZE 3 BLOCK BANDS. SIGNS UNDER 3' IN HEIGHT SHALL UTILIZE 2 BLOCK BANDS
- 4. ACTUAL NUMBER OF FASTENERS PER SIGN VARIES WITH THE SIGN AREA, BUT NORNALLY THERE ARE TWO. FOR SIGNS GREATER THAN 9 S.F. 3 FASTENERS SHALL BE USED.
- 5. ALL SIGN MOUNTING BOLTS AND WASHERS SHALL BE EITHER:
 - a. Hot dip or mechanically galvanized in accordance with ASTM Designation: A 153, Class D, or
 - b. Cadmium plated in accordance with ASTM Designation: B 766 TYPE 3, Class 12, or
 - c. Electro-galvanized in accordance with ASTM Designation: B 633, TYPE III, SC 3.
- 6. ALL BOLTS SHALL HAVE HEXAGONAL HEADS.
- 7. STEEL WASHERS SHALL BE 11/4" O.D. X 3/8" I.D. X 1/16"
- 8. NYLON WASHERS SHALL BE $1^{1}/_{4}$ " O.D. X $\frac{3}{8}$ " I.D. X .080 FOR TYPE H OR TYPE F FACE SIGN


X LAG BOLTS SHALL BE 3/8" X 21/2"

BLOCK BANDING DETAIL (V-BLOCK OPTION) WISCONSIN DEPT OF TRANSPORTATION APPROVED For State Traffic Engineer PLATE NO. <u>A5-10.1</u>


DATE 7/12/07

SHEET NO:





- 2. Signs 3 feet or greater in height shall have three bracket bands installed. Signs less than 3 feet in height shall have two bracket bands installed.
- 3. Banding and assembly bracket shall be stainless steel. All bands shall be $\frac{3}{4}$ " in width and 0.025" thickness.



WASHERS (ALL POSTS) -

COUNTY:

1-1/4" O.D. X3/8" I.D. X1/16" STEEL 1-1/4" O.D. X3/8" I.D. X .080 NYLON FOR ALL TYPE H SIGNS

STANDARD SIGN SIGN BANDING DETAILS

WISCONSIN DEPT OF TRANSPORTATION

APPROVED

State Traffic Engineer DATE 8/16/13

SHEET NO:

FILE NAME : C:\CAEFiles\Projects\tr_stdplate\A59.DGN

PLOT DATE: 16-AUG-2013 13:27

PLOT BY: mscsja

PLOT NAME :

PLOT SCALE: 33.740899:1.000000

WISDOT/CADDS SHEET 42

PLATE NO. A5-9.3

- Sign is Type II see Note 7 reference WIS DOT Standard Specification for HIGHWAY and STRUCTURE CONSTRUCTION latest edition.
- 2. Color:


Background - White & Black - See Note 7 Message - Black


- 3. Message Series see Note 5
- 4. Corners may be square or rounded when base material is plywood but borders shall be rounded as shown. When base material is metal, the corners and borders shall be rounded.
- 5. Message Series E for 1 letter.


 Message Series D for 2 letters unless
 message is too big then Series C.

 Message Series C for 3 letters unless
 message is too big then Series B.
- 6. Substitute appropriate letters & optically center to achieve proper balance.
- 7. Permanent Signs

Background - Type H Reflective Detour or temporary Signs Background - Reflective







PLOT NAME :

SIZE	Α	В	С	D	E	F	G	Н	I	J	К	L	М	N	0	Р	0	R	S	Т	U	V	W	Х	Y	Z	Area sq. ft.
1																											
2	24		1 1/2			10	3	5 1/8	4 1/8	9 1/4	9 5/8	2	11 1/2	10 1/8	9 3/8	2 1/4		6 %									4.0
3	36		2 1/4			16	4	7 %	5 %	12 1/4	12 1/8	3	17 1/8	15 1/4	14	3 3/8		10									9.0
4	36		2 1/4			16	4	7 %	5 %	12 1/4	12 1/8	3	17 1/8	15 1/4	14	3 %		10									9.0
5	36		2 1/4			16	4	7 5/8	5 %	12 1/4	12 1/8	3	17 1/8	15 1/4	14	3 3/8		10									9.0
DDO	IECT	NO.					111	/V.					COUN	TV.													
FRU	JECT	NO.					HV	V I .						I I .					I								

CTH MARKER
M1-5A FOR ASSEMBLIES

WISCONSIN DEPT OF TRANSPORTATION

APPROVED

PROVED

Matthew Rauch

Forstate Traffic Engineer

NATE 9/27/11 PLATE NO. M1-5A.8

DATE 9/27/11

SHEET NO:

BLACK

M1-5A

- 1. Sign is Type II See Note 6 reference WIS DOT Standard Specification for HIGHWAY and STRUCTURE CONSTRUCTION latest edition.
- 2. Color:

Background - White & Black - See Note 6 Message - Black

- 3. Message Series See note 5
- 4. Corners may be square or rounded when base material is plywood but borders shall be rounded as shown. When base material is metal, the corners and borders shall be rounded.
- 5. Substitute appropriate Series numerals and adjust spacing as per plate A10-1.
- 6. Permanent Signs
 Background Type H Reflective
 Detour or temporary Signs
 Background Reflective

BLACK	↑ G → ↑ F → → ↑ → → → → → → → → → →
Metric equivalent for this sign is:	

HWY:

900 mm X 900 mm

5 900 mm X 900 mm

PROJECT NO:

SIZE	Α	В	С	D	E	F	G	Н	I	J	К	L	М	N	0	Р	Q	R	S	Т	U	٧	W	Х	Y	Z	Area sq. ft.	Area m2
1																												
2	24		1 1/2			12	5 1/2	6 1/2	10 1/4	2 1/2	8 %	11 1/2	1	1 1/8	11 1/4	21 1/8											4.0	. 36
3	36		2 1/4			18	8 3/4	9 1/4	15 3/8	5 3/8	12 5/8	17 1/8	1 1/2	2 1/8	16 1/8	33											9.0	. 81
4	36		2 1/4			18	8 3/4	9 1/4	15 3/8	5 3/8	12 5/8	17 1/8	1 1/2	2 1/8	16 1/8	33											9.0	.81
5	36		2 1/4			18	8 3/4	9 1/4	15 3/8	5 3/8	12 5/8	17 1/8	1 1/2	2 1/8	16 1/8	33											9.0	.81
ט ן	26		2 /4			10	0 74	J /4	12 78	3 78	12 78	11 /8	1 /2	² /8	10 /8	33		<u> </u>										9.0

COUNTY:

STATE ROUTE MARKER
M1-6 FOR ASSEMBLIES

WISCONSIN DEPT OF TRANSPORTATION


APPROVED

The state Traffic Engineer

DATE 3/20/02 PLATE NO. M1-6.9

SHEET NO:

PLOT NAME :



- 1. All Signs Type II Type H
- 2. Color:

Background - See note 5 Message - See note 5

- 3. Message Series C
- 4. Corners may be square or rounded when base material is plywood but borders shall be rounded as shown. When base material is metal, the corners and borders shall be rounded.
- 5. M3-1 thru M3-4 Background White

Message - Black

MB3-1 thru MB3-4 Background - Blue

Message - White

MK3-1 thru MK3-4 Background - Green

Message - White

MM3-1 thru MM3-4 Background - White

Message - Green

MN3-1 thru MN3-4 Background - Brown

Message - White

6. Note the first letter of each direction is larger than the remainder of the message.

					MN3-4																					
SIZE	Α	В	С	D	E	F	G	Н	I	J K	L	М	N	0	Р	0	R	S	T	U	v	W	Х	Y	Z	Areq sq. ft.
SIZE 1																										
2	24	12	1 1/8	3/8	3/8	6	7	2 1/4	2 3/4	10 1/4 7 1/8	8 3/8	10 1/4	9 3/4	8 3/4			1 1/2									2.00
3	36	18	1 1/8	3/8	1/2	9	10	3 3/4	4 1/4	14 3/8 12	12 1/8	14	14 1/8	13			1 1/2									4.5
4	36	18	1 1/8	3/8	1/2	9	10	3 3/4	4 1/4	14 3/8 12	12 1/8	14	14 1/8	13			1 1/2									4.5
5	36	18	1 1/8	3/8	1/2	9	10	3 3/4	4 1/4	14 3/8 12	12 1/8	14	14 1/8	13			1 1/2									4.5

COUNTY:

STANDARD SIGNS M3-1 thur M3-4 SERIES

WISCONSIN DEPT OF TRANSPORTATION

APPROVED

Matther & Rauch

For State Traffic Engineer

DATE 6/30/14 PLATE NO. M3-1.13

SHEET NO:

07.001/5...14.675054.4.000000

FILE NAME : C:\CAEFiles\Projects\tr_stdplate\M31.DGN

HWY:

PROJECT NO:

PLOT DATE: 30-JUN-2014 12:53

PLOT NAME :

PLOT BY: mscsja

PLOT SCALE: 11.675051:1.000000

- 1. Sign is Type II Type F Reflective reference WIS DOT Standard Specification for HIGHWAY and STRUCTURE CONSTRUCTION latest edition.
- 2. Color:

Background - Orange Message - Black

- 3. Message Series B
- 4. Corners may be square or rounded when base material is plywood but borders shall be rounded as shown. When base material is metal, the corners and borders shall be rounded.

D E		;
	F	↑ :
✓ A ———————————————————————————————————	1	

Α С E F G H I J S Х Z D 0 10 10 1/4 1 1/8 3/8 3/8 24 2.0 3 36 1 1/8 3/8 1/2 4 1/2 14 5/8 14 1/2 4.5 4 5

COUNTY:

STANDARD SIGN M4-8

WISCONSIN DEPT OF TRANSPORTATION

APPROVED

For State Traffic Engineer

DATE 11/10/10 PLATE NO. M4-8.2

SHEET NO:

FILE NAME : C:\Users\PROJECTS\tr_stdplate\M48.DGN

PROJECT NO:

HWY:

PLOT DATE: 10-NOV-2010 13:18

PLOT BY : ditjph

PLOT NAME: PLOT SCALE: 4

PLOT SCALE: 4.767233:1.000000

WISDOT/CADDS SHEET 42

- Signs are Type II See Note 4 reference WIS DOT Standard Specification for HIGHWAY and STRUCTURE CONSTRUCTION latest edition.
- 2. Color:

Background - See note 4 Message - See note 4

- 3. Corners may be square or rounded when base material is plywood but borders shall be rounded as shown. When base material is metal, the corners and borders shall be rounded.
- 4. M5-1 and M5-2 Background White Type H Reflective Message Black
 - MB5-1 and MB5-2 Background Blue

 Message White Type H Reflective
 - MG5-1 and MG5-2 Background Green

 Message White Type H Reflective
 - MK5-1 and MK5-2 Background Green
 - Message White Type H Reflective
 - MM5-1 and MM5-2 Background White Type H Reflective Message Green
- MN5-1 and MN5-2 Background Brown


Message - White - Type H Reflective

- M05-1 and M05-2 Background Orange Type F Reflective Message - Black
- MP5-1 and MP5-2 Background White Type H Reflective Message Blue
- MR5-1 and MR5-2 Background Brown
 - Message Yellow Type H Reflective
- 5. M5-1R same as M5-1L except arrow points right.
- 6. M5-2R same as M5-2L except arrow tilts right.

c —	
D → E →	
Į.	←
·	M5-2L
	MK5-2L


MK5-1L MM5-1L MO5-1L MP5-1L MR5-1L

M5-1L



MB5-1L MG5-1L MN5-1L

HWY:



MG5-2L

MN5-2L

MM5-2L

M05-2L

MP5-2L

MR5-2L

T A S

SIZE	Α	В	С	D	E	F	G	Н	I	J	K	L	M	N	0	Р	0	R	S	T	U	٧	₩	Х	Y	Z	Areo sq. fi
1																											
2	21		1 1/8	3%	3/8		7	3 3/8	5/8		2 1/8	4 1/2	6 %	5 1/4	5	2 1/2		1/2	2 %	3	1 1/2	1/2					3.06
3	30		1 3/8	1/2	5/8		10 1/8	4 1/8	7 /8		3	6 1/2	9 1/8	7 1/2	7 1/4	3 1/2		3/4	3 3/4	4 1/4	1 1/8	1/2					6.25
4	30		1 3/8	1/2	5/8		10 1/8	4 1/8	7 /8		3	6 1/2	9 1/8	7 1/2	7 1/4	3 1/2		3/4	3 3/4	4 1/4	1 1/8	1/2					6.25
5	30		1 3/8	1/2	5/8		10 1/8	4 1/8	½		3	6 1/2	9 1/8	7 1/2	7 1/4	3 1/2		3/4	3 3/4	4 1/4	1 1/8	1/2					6.25

COUNTY:

STANDARD SIGN M5-1 & M5-2

WISCONSIN DEPT OF TRANSPORTATION

APPROVED

For State Traffic Engineer
DATE 7/29/13 PLATE NO. M5-1.12

SHEET NO:

PROJECT NO:

- 1. Signs are Type II Type H except as Shown
- 2. Color:

Background - See note 4 Message - See note 4

- 3. Corners may be square or rounded when base material is plywood but borders shall be rounded as shown. When base material is metal, the corners and borders shall be rounded.
- 4. M6-1 and M6-2 Background White

Message - Black

MB6-1 and MB6-2 Background - Blue

Message - White

MG6-1 and MG6-2 Background - Green

Message - White

MK6-1 and MK6-2 Background - Green

Message - White

MM6-1 and MM6-2 Background - White

Message - Green

MN6-1 and MN6-2 Background - Brown

Message - White

M06-1 and M06-2 Background - Orange - Type F Reflective

Message - Black

MP6-1 and MP6-2 Background - White

Message - Blue


MR6-1 and MR6-2 Background - Brown

Message - Yellow

c —	
D ->	
	A
	M6 - 2
	MK 6 - 2



- MM6-2 MN6 - 2
- MO6-2
- MP6-2
- MR6-2



HWY:

M6 - 1

MK6-1


MM6 - 1


MN6-1

MO6 - 1

MP6-1

MR6-1





SIZE	Α	В	С	D	Е	F	G	Н	I	J	K	L	М	N	0	Р	0	R	S	Т	U	٧	W	X	Y	Z	Area sq. ft.
1																											
2	21		1 1/8	3/8	3/8		7 1/2	7 1/8	5 %	5	4 1/4	5 1/4	3	2 %	1/2						1 1/2	1/2					3.06
3	30		1 3/8	1/2	5/8		10 3/4	10 1/4	8	7 1/4	6	7 1/2	4 1/4	3 3/4	3/4						1 1/8	1/2					6.25
4	30		1 3/8	1/2	5/8		10 3/4	10 1/4	8	7 1/4	6	7 1/2	4 1/4	3 3/4	3/4						1 %	1/2					6.25
5	30		1 3/8	1/2	5/8		10 3/4	10 1/4	8	7 1/4	6	7 1/2	4 1/4	3 3/4	3/4						1 1/8	1/2					6.25

COUNTY:

STANDARD SIGN M6-1 & M6-2**SERIES**

WISCONSIN DEPT OF TRANSPORTATION

APPROVED

DATE 7/03/14 PLATE NO. M6-1.14

SHEET NO:

FILE NAME : C:\CAEFiles\Projects\tr_stdplate\M61.DGN


PROJECT NO:

PLOT DATE: 03-JUL-2014 14:28

PLOT NAME :

PLOT BY: mscsja

PLOT SCALE: 11.675051:1.000000





<u>NOTES</u>

- 1. Sign is Type II Type H Reflective reference WIS DOT Standard Specification for HIGHWAY and STRUCTURE CONSTRUCTION latest edition.
- 2. Color:

Background - White Message - Black

- 3. Message Series D
- 4. Corners may be square or rounded when base material is plywood but borders shall be rounded as shown. When base material is metal, the corners and borders shall be rounded.
- 5. Modify the message as required.





SIZE	A	В	С	D	E	F	G	Н	I	J	K	L	M	N	0	Ρ	0	R	S	T	U	V	W	X	Y	Z	Area sq. ft.
1																											
2S	48	30	1 3/8	1/2	5/8	8	5	4	13 1/4	13 1/2	19	14	15	13													10.0
2M	48	30	1 3/8	1/2	5/8	8	5	4	13 1/4	13 1/2	19	14	15	13													10.0
3	48	30	1 3/8	1/2	5/8	8	5	4	13 1/4	13 1/2	19	14	15	13													10.0
4	48	30	1 3/8	1/2	5/8	8	5	4	13 1/4	13 1/2	19	14	15	13													10.0
5	48	30	1 3/8	1/2	5/8	8	5	4	13 1/4	13 1/2	19	14	15	13													10.0
PRO	DJECT	NO:						HWY:					С	OUNTY	':												


STANDARD SIGN R11-2


WISCONSIN DEPT OF TRANSPORTATION

DATE 4/1/11 PLATE NO. R11-2.10

SHEET NO:

PLOT BY: mscj9h






<u>NOTES</u>

- 1. Sign is Type II Type H Reflective reference WIS DOT Standard Specification for HIGHWAY and STRUCTURE CONSTRUCTION latest edition.
- 2. Color:

Background - White Message - See note 4

- 3. Corners may be square or rounded when base material is plywood but borders shall be rounded as shown. When base material is metal, the corners and borders shall be rounded.
- 4. Border & Arrow are non reflective black, the circle with diagonal bar is reflective red.



ARROW DETAIL

SIZE	Α	В	C	D	E	F	G	н	I	J	K	L	M	N	0	Р	0	R	S	T	U	٧	₩	×	Y	Z	Area sq. ft
1	24		1 1/8	3/8	1/2	10 1/2	4	7 1/2	2	1 1/2	2 1/2	45°	8 1/2	5	6	1/2											4.0
25	24		1 1/8	3/8	1/2	10 1/2	4	7 1/2	2	1 1/2	2 1/2	45°	8 1/2	5	6	1/2											4.0
2M	36		1 %	5/8	3/4	15 ¾	6	11 1/4	3	2 1/4	3 3/4	45°	12 3/4	7 1/2	9	3/4											9.0
3	36		1 5/8	5/8	3/4	15 3/4	6	11 1/4	3	2 1/4	3 3/4	45°	12 3/4	7 1/2	9	3/4											9.0
4	36		1 %	5/8	3/4	15 ¾	6	11 1/4	3	2 1/4	3 3/4	45°	12 3/4	7 1/2	9	3/4											9.0
5	48		2 1/4	3/4	1	21	8	15	4	3	5	45°	17	10	12	1											16.0

COUNTY:

STANDARD SIGN R3-2

WISCONSIN DEPT OF TRANSPORTATION

APPROVED Mat

For State Traffic Engineer

DATE 12/08/10 PLATE NO. R3-2.10

SHEET NO:


HWY:

PROJECT NO:

- 1. Sign is Type II Type H Reflective reference WIS DOT Standard Specification for HIGHWAY and STRUCTURE CONSTRUCTION latest edition.
- 2. Color:

Background - White Message - Black

- 3. Message Series E
- 4. Corners may be square or rounded when base material is plywood but borders shall be rounded as shown. When base material is metal, the corners and borders shall be rounded.



ARROW DETAIL

SIZE	Α	В	С	D	Ε	F	G	Н	I	J	K	L	M	N	0	Р	0	R	S	T	U	V	W	X	Y	Z	Area sq. ft.
1																											
25	24	36	1 1/8	3/8	1/2	4	1/4	2 1/2	1	2 1/8	2 5/8	3 1/4	2	1 1/2	7 1/4	7 1/2		8 1/8	7 5/8	8	22°	1/2	9 1/2				6.0
2M	24	36	1 1/8	3/8	1/2	4	1/4	2 1/2	1	2 1/8	2 %	3 1/4	2	1 1/2	7 1/4	7 1/2		8 1/8	7 %	8	22°	1/2	9 1/2				6.0
3	36	54	1 3/4	1/2	5/8	6	3/8	3 3/4	1 1/2	4 1/4	4	4 %	3	2 1/4	10 %	11 1/4		12 1/4	11 1/2	12	22°	3/4	13 1/4				13.5
4																											
5																											

COUNTY:

R3-20L

HWY:

М

М

0

STANDARD SIGN R3-20L

WISCONSIN DEPT OF TRANSPORTATION

APPROVED For State Traffic Engineer PLATE NO. R3-20L.7

DATE 10/18/10

SHEET NO:

FILE NAME : C:\Users\PROJECTS\tr_stdplate\R320L.DGN

PROJECT NO:


PLOT DATE: 15-OCT-2010 14:45

PLOT NAME :

PLOT BY: dotsja

PLOT SCALE: 5.959043:1.000000


WISDOT/CADDS SHEET 42



- 1. Sign is Type II Type H Reflective reference WIS DOT Standard Specification for HIGHWAY and STRUCTURE CONSTRUCTION latest edition.
- 2. Color:

Background - White Message - Black

- 3. Message Series E
- 4. Corners may be square or rounded when base material is plywood but borders shall be rounded as shown. When base material is metal, the corners and borders shall be rounded.



ARROW DETAIL

PLOT NAME :

SIZE	Α	В		С	D	E	F	G	Н	I	J	K	L	M	N	0	Р	0	R	S	T	U	٧	W	X	Y	Z	Area sq. ft.
1																												
25	24	36	5 1	l 1/8	3/8	1/2	4	1/4	2 1/2	1	2 1/8	2 5/8	3 1/4	2	1 1/2	7 1/4	7 1/2		8 1/8	7 %	8	22°	1/2	9 1/2				6.0
2M	24	36	5 1	l 1/8	3/8	1/2	4	1/4	2 1/2	1	2 1/8	2 %	3 1/4	2	1 1/2	7 1/4	7 1/2		8 1/8	7	8	22°	1/2	9 1/2				6.0
3	36	54	1	1 3/4	1/2	5/8	6	3/8	3 3/4	1 1/2	4 1/4	4	4 1/8	3	2 1/4	10 %	11 1/4		12 1/4	11 1/2	12	22°	3/4	13 1/4				13.5
4																												
5																												

COUNTY:

STANDARD SIGN R3-20LL

WISCONSIN DEPT OF TRANSPORTATION

APPROVED Matthew & Rawh

for State Traffic Engineer

DATE 10/18/10 PLATE NO. R3-20LL.1

SHEET NO:

FILE NAME : C:\Users\PROJECTS\tr_stdplate\R320LL.DGN

HWY:

PROJECT NO:

PLOT DATE: 15-OCT-2010 14:38


PLOT BY : dotsja

PLOT SCALE: 5.959043:1.000000

- 1. Sign is Type II Type H Reflective reference WIS DOT Standard Specification for HIGHWAY and STRUCTURE CONSTRUCTION latest edition. material is plywood but borders shall be rounded
- 2. Color:

Background - White Message - Black

- 3. Corners may be square or rounded when base as shown. When base material is metal, the corners and borders shall be rounded.
- 4. R4-8 is the same as R4-7 except Legend is reversed.



ARROW DETAIL

																							\rightarrow	ŊΙ	N 		
SIZE	Α .	В	С	D	E	F	G	Н	I	J	K	L	М	N	0	Р	0	R	S	Т	U	٧	₩	X	Y	Z	Areg sq. ft.
1	18	24	1 1/8	3∕8	1/2	3 %	4 3/4	5 1/2	1 3/8	2 1/4	6	3	9 3/8	1 1/2 22	1/2	3 1/2	6 1/8	5/8	1 1/8	3 1/4	6 3/4	1/2	20 ¾				3.0
25	24	30	1 1/8	3/8	1/2	4 1/2	6 1/4	7 3/8	1 %	3	8	4	12 1/2	2 3	30	4 %	8 1/8	7 ⁄8	2 1/2	4 3/8	9	5/8	25 1/8				5.0
21	24	30	1 1/8	3/8	1/2	4 1/2	6 1/4	7 3/8	1 %	3	8	4	12 1/2	2 3	30	4 %	8 1/8	7 ⁄8	2 1/2	4 3/8	9	5/8	25 1/8				5.0
3	36	48	1 3/4	1/2	5/8	6 3/4	9 3/8	11 1/8	2 1/8	4 1/2	12	6	18 3/4	3 4	15	6 %	12 1/4	1 1/4	3 3/4	6 %	13 1/2	1	40 ¾				12.0
4	36	48	1 3/4	1/2	5/8	6 3/4	9 3/8	11 1/8	2 1/8	4 1/2	12	6	18 ¾	3 4	45	6 %	12 1/4	1 1/4	3 3/4	6 %	13 1/2	1	40 3/4				12.0
5	48	60	2 1/4	3/4	1	9	12 1/2	14 3/4	3 3/4	6	16	8	25	4	60	9 1/4	16 1/4	1 %	5	8 ¾	18	1 1/4	50 1/4				20.0

COUNTY:

R4-7

STANDARD SIGN R4-7 & R4-8

WISCONSIN DEPT OF TRANSPORTATION

SHEET NO:

For State Traffic Engineer DATE 3/25/2011

PLATE NO. R4-7.8

FILE NAME : C:\Users\PROJECTS\tr_stdplate\R47.DGN

PROJECT NO:

D→

HWY:

PLOT DATE: 25-MAR-2011 14:10

PLOT NAME :

PLOT BY: mscsja

PLOT SCALE: 5.462457:1.000000

WISDOT/CADDS SHEET 42

<u>NOTES</u>

- 1. Sign is Type II Type H Reflective reference WIS DOT Standard Specification for HIGHWAY and STRUCTURE CONSTRUCTION latest edition.
- 2. Color:

Background - See detail Message - White - Type H Reflective

- 3. Message Series D
- 4. Corners may be square or rounded when base material is plywood but when base material is metal, the cornors shall be rounded.

Whi te Red White R5-1

SIZE	Α	В	С	D	Е	F	G	Н	I	J	K	L	М	N	0	Р	0	R	S	Т	U	V	W	Х	Y	Z	Area sq. ft.
1																											
2S	30		1 1/8		5	4	6 1/2	2	3/8	6 1/2	2 3/8	9 %	14 1/2	12 1/2	8 1/2	8 %											6.26
2M	36		2 1/4		6	5	7 1/2	2 1/2	1/2	8 1/8	3	12 1/8	17 1/2	15	10 %	10 ¾											9.0
3	36		2 1/4		6	5	7 1/2	2 ½	1/2	8 1/8	3	12 1/8	17 1/2	15	10 %	10 3/4											9.0
4	36		2 1/4		6	5	7 1/2	2 1/2	1/2	8 1/8	3	12 1/8	17 1/2	15	10 %	10 3/4											9.0
5	48		3		8	6	11	3	5/8	9 3/4	3 %	14 1/2	23 ½	20	12 3/4	12 1/8											16.0

COUNTY:

STANDARD SIGN R5-1

WISCONSIN DEPT OF TRANSPORTATION

APPROVED


For State Traffic Engineer

DATE 12/17/10 PLATE NO. R5-1.15

SHEET NO:

PROJECT NO:


HWY:



- 1. Sign is Type II Type H Reflective reference WIS DOT Standard Specification for HIGHWAY and STRUCTURE CONSTRUCTION latest edition.
- 2. Color:

Background - Red Message - White

- 3. Message Series D
- 4. Corners may be square or rounded when base material is plywood but borders shall be rounded as shown. When base material is metal, the corners and borders shall be rounded.



STANDARD SIGN R5-1A

WISCONSIN DEPT OF TRANSPORTATION

APPROVED


Matther R Raud

For State Traffic Engineer PLATE NO. R5-1A.2

DATE 12/17/10

SHEET NO:


PROJECT NO:



- 1. Sign is Type II Type H Reflective reference WIS DOT Standard Specification for HIGHWAY and STRUCTURE CONSTRUCTION latest edition.
- 2. Color:

Background - White Message - Black

- 3. Message Series D
- 4. Corners may be square or rounded when base material is plywood but borders shall be rounded as shown. When base material is metal, the corners and borders shall be rounded.
- 5. R6-2L same as R6-2R except arrow points to the left.



SIZE	Α	В	С	D	E	F	G	Η	I	J	K	L	М	N	0	Р	0	R	S	Т	J	٧	W	Х	Y	Z
1	18	24	1 1/8	3/8	1/2	5	2 1/2	1 1/2	4 1/2	5 ½	6 %	6 1/2	6 %	6 ¾	11 %	2 %	1/4	3∕8	2 1/4	1 1/2	4 1/2					
2S	24	30	1 1/8	3/8	1/2	6	3	2 1/2	5 ½	7	8 1/8	8 1/8	8 1/2	8 %	16	3 ½	3/8	1/2	3	2	6					
2M	30	36	1 3/8	1/2	5/8	8	2 1/2	2 5/8	6 %	8	10 1/2	10 1/2	11 1/4	11 1/4	20	4 3/8	1/2	5/8	3 3/4	2 1/2	7 1/2					
3	36	48	1 %	1/2	5/8	10	5 1/4	3 1/4	9	10 1/2	12 3/4	12 3/4	13 1/4	13 1/2	24	5 %	1/2	3/4	4 3/4	3	9					
4	36	48	1 %	1/2	5/8	10	5 1/4	3 1/4	9	10 1/2	12 3/4	12 3/4	13 1/4	13 ½	24	5 %	1/2	3/4	4 3/4	3	9					
5	·										·									·				·		
1																										

COUNTY:

STANDARD SIGN R6-2 R&L

WISCONSIN DEPT OF TRANSPORTATION

APPROVED

Matthe R Rauch

For State Traffic Engineer

DATE 11/2/10

PLATE NO. R6-2.8

SHEET NO:

FILE NAME : C:\Users\PROJECTS\tr_stdplate\R62.DGN

HWY:

PROJECT NO:

PLOT DATE: 02-NOV-2010 15:25

PLOT NAME :

PLOT BY: ditjph

PLOT SCALE: 4.469282:1.000000

WISDOT/CADDS SHEET 42

STH 50 KENOSHA COUNTY

STATION	CUT (SF)	FILL (SF)	CUT (CY)	*FILL (CY)	CUMULATIVE VOLUME		MASS HAUL
					CUT (CY)	FILL (CY)	(CY)
605+88.000	13.68	0.00	0.00	0.00	0.00	0.00	0.00
606+00.000	10.48	1.15	5.28	0.31	5.28	0.31	4.97
606+50.000	11.89	2.39	20.72	4.10	26.00	4.41	21.59
607+00.000	11.49	1.48	21.65	4.48	47.65	8.89	38.76
607+50,000	13.52	11.32	23.16	14.81	70.81	23.70	47.11
608+00.000	25.99	12.11	36.58	27.11	107.39	50.81	56.58
608+50.000	25.76	52.02	47.92	74.23	155.31	125.04	30.27
609+00.000	26.08	46.14	48.00	113.61	203.31	238.65	-35.34
609+50.000	29.40	37.06	51.37	96.30	254.68	334.95	-80.27
610+00.000	33.04	27.37	57.82	74.58	312.50	409.53	-97.03
610+50.000	34.71	24.20	62.73	59.70	375.23	469.23	-94.00
611+00.000	37.42	1 6.75	66.79	47.40	442.02	516.63	-74.61
611+50.000	39.01	10.58	70.77	31.64	512.79	548.26	-35.47
612+00.000	42.42	2.28	75.40	14.89	588.19	563.15	25.04
612+50.000	63.89	0.00	98.44	2.64	686.63	565.79	120.84
613+00.000	69.23	0.00	128.20	0.00	814.83	565.79	249.04
613+50.000	0.00	0.00	0.00	0.00	814.83	565.79	249.04
614+00,000	69.56	0.00	128.81	0.00	943.64	565.79	377.85
614+50.000	63.86	0.00	123.54	0.00	1067.18	565.79	501.39
615+00.000	48.95	1 .51	104.46	1.74	1171.64	567.53	604.12
615+50.000	38.56	11.46	81.03	15.01	1252.67	582.54	670.13
616+00.000	37.39	14.08	70.32	29.56	1322.99	612.10	710.89
616+50.000	35.66	19.08	67.64	38.38	1390.63	650.48	740.16
617+00.000	33.00	24.22	63.58	50.11	1454.21	700.59	753.62
617+50.000	29.31	32.02	57.70	65.09	1511.91	765.68	746.24
618+00.000	29.89	31.62	54.81	73.65	1566.72	839.33	727.40
618+50.000	29.38	37.48	54.88	79.98	1621.60	919.30	702.30
619+00.000	28.22	40.71	53.33	90.50	1674.93	1009.80	665.13
619+50.000	26.90	3.15	51.04	50.76	1725.97	1060.56	665.41
620+00.000	16.06	0.00	39.78	3.65	1765.75	1064.21	701.54
620+50.000	13.95	0.06	27.78	0.06	1793.53	1064.28	729.26
621+00.000	14.74	0.00	26.56	0.06	1820.09	1064.34	755.75
621+15.000	15.37	0.00	8.31	0.00	1828.40	1064.34	764.06

*EXPANDED 25%

20 FT SHEET Ε

FILE NAME : P:\UZ\W\WITSE\128766\15-CIVIL 3D\37002001\SHEETSPLAN\SEC 09 CROSS SECTIONS\EW DATA.DWG LAYOUT NAME - EW DATA - 090101_EW

PROJECT NO:3700-20-71

PLOT DATE: 1/27/2015 7:11 PM


COUNTY: KENOSHA


PLOT BY: SAVANNAH HALLOCK PLOT NAME:


CROSS SECTIONS: EARTHWORK DATA TABLE


PLOT SCALE : 1 IN:20 FT


HWY:STH 50














Notes



Wisconsin Department of Transportation

Dedicated people creating transportation solutions through innovation and exceptional service.

http://www.dot.wisconsin.gov