

# HIGHWAY WORK PROPOSAL

Wisconsin Department of Transportation  
DT1502 10/2010 s.66.29(7) Wis. Stats.

Proposal Number:

14

COUNTY	STATE PROJECT ID	FEDERAL PROJECT ID	PROJECT DESCRIPTION	HIGHWAY
Iron	9240-09-70		Park Falls - Manitowish Bear River Bridge, B-26-0039	STH 182
Iron	9240-09-80		Park Falls - Manitowish Price County Line - STH 47	STH 182

This proposal, submitted by the undersigned bidder to the Wisconsin Department of Transportation, is in accordance with the advertised request for proposals. The bidder is to furnish and deliver all materials, and to perform all work for the improvement of the designated project in the time specified, in accordance with the appended Proposal Requirements and Conditions.

Proposal Guaranty Required, \$ 75,000.00 Payable to: Wisconsin Department of Transportation	Attach Proposal Guaranty on back of this PAGE.
Bid Submittal Due Date: June 9, 2015 Time (Local Time): 9:00 AM	Firm Name, Address, City, State, Zip Code
Contract Completion Time Fifty-Five (55) Working Days	<b>SAMPLE NOT FOR BIDDING PURPOSES</b>
Assigned Disadvantaged Business Enterprise Goal 0 %	This contract is exempt from federal oversight.

This certifies that the undersigned bidder, duly sworn, is an authorized representative of the firm named above; that the bidder has examined and carefully prepared the bid from the plans, Highway Work Proposal, and all addenda, and has checked the same in detail before submitting this proposal or bid; and that the bidder or agents, officer, or employees have not, either directly or indirectly, entered into any agreement, participated in any collusion, or otherwise taken any action in restraint of free competitive bidding in connection with this proposal bid.

**Do not sign, notarize, or submit this Highway Work Proposal when submitting an electronic bid on the Internet.**

Subscribed and sworn to before me this date \_\_\_\_\_

\_\_\_\_\_  
(Signature, Notary Public, State of Wisconsin)

\_\_\_\_\_  
(Print or Type Name, Notary Public, State Wisconsin)

\_\_\_\_\_  
(Date Commission Expires)

Notary Seal

\_\_\_\_\_  
(Bidder Signature)

\_\_\_\_\_  
(Print or Type Bidder Name)

\_\_\_\_\_  
(Bidder Title)

## For Department Use Only

Type of Work Bear River Bridge, B-26-0039, temporary signals and related traffic control items, HMA pavement Type E-0.3, removing asphaltic surface milling, preparation of asphaltic shoulders, base aggregate dense, culvert pipe replacements, centerline rumble strips, epoxy pavement marking, excavation common, guard rail, and permanent signing.	Notice of Award Dated	Date Guaranty Returned
--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	-----------------------	------------------------

**PLEASE ATTACH  
PROPOSAL GUARANTY HERE**

## **Effective with November 2007 Letting**

### **PROPOSAL REQUIREMENTS AND CONDITIONS**

The bidder, signing and submitting this proposal, agrees and declares as a condition thereof, to be bound by the following conditions and requirements.

If the bidder has a corporate relationship with the proposal design engineering company, the bidder declares that it did not obtain any facts, data, or other information related to this proposal from the design engineering company that was not available to all bidders.

The bidder declares that they have carefully examined the site of, and the proposal, plans, specifications and contract forms for the work contemplated, and it is assumed that the bidder has investigated and is satisfied as to the conditions to be encountered, as to the character, quality, and quantities of work to be performed and materials to be furnished, and as to the requirements of the specifications, special provisions and contract. It is mutually agreed that submission of a proposal shall be considered conclusive evidence that the bidder has made such examination.

The bidder submits herewith a proposal guaranty in proper form and amount payable to the party as designated in the advertisement inviting proposals, to be retained by and become the property of the owner of the work in the event the undersigned shall fail to execute the contract and contract bond and return the same to the office of the engineer within fourteen (14) days after having been notified in writing to do so; otherwise to be returned.

The bidder declares that they understand that the estimate of quantities in the attached schedule is approximate only and that the attached quantities may be greater or less in accordance with the specifications.

The bidder agrees to perform the said work, for and in consideration of the payment of the amount becoming due on account of work performed, according to the unit prices bid in the following schedule, and to accept such amounts in full payment of said work.

The bidder declares that all of the said work will be performed at their own proper cost and expense, that they will furnish all necessary materials, labor, tools, machinery, apparatus, and other means of construction in the manner provided in the applicable specifications and the approved plans for the work together with all standard and special designs that may be designed on such plans, and the special provisions in the contract of which this proposal will become a part, if and when accepted. The bidder further agrees that the applicable specifications and all plans and working drawings are made a part hereof, as fully and completely as if attached hereto.

The bidder, if awarded the contract, agrees to begin the work not later than ten (10) days after the date of written notification from the engineer to do so, unless otherwise stipulated in the special provisions.

The bidder declares that if they are awarded the contract, they will execute the contract agreement and begin and complete the work within the time named herein, and they will file a good and sufficient surety bond for the amount of the contract for performance and also for the full amount of the contract for payment.

The bidder, if awarded the contract, shall pay all claims as required by Section 779.14, Statutes of Wisconsin, and shall be subject to and discharge all liabilities for injuries pursuant to Chapter 102 of the Statutes of Wisconsin, and all acts amendatory thereto. They shall further be responsible for any damages to property or injury to persons occurring through their own negligence or that of their employees or agents, incident to the performance of work under this contract, pursuant to the Standard Specifications for Road and Bridge Construction applicable to this contract.

In connection with the performance of work under this contract, the contractor agrees to comply with all applicable state and federal statutes relating to non-discrimination in employment. No otherwise qualified person shall be excluded from employment or otherwise be subject to discrimination in employment in any manner on the basis of age, race, religion, color, gender, national origin or ancestry, disability, arrest or conviction record (in keeping with s.111.32), sexual orientation, marital status, membership in the military reserve, honesty testing, genetic testing, and outside use of lawful products. This provision shall include, but not be limited to the following: employment, upgrading, demotion or transfer; recruitment or recruitment advertising; layoff or termination; rates of pay or other forms of compensation, and selection for training, including apprenticeship. The contractor further agrees to ensure equal opportunity in employment to all applicants and employees and to take affirmative action to attain a representative workforce.

The contractor agrees to post notices and posters setting forth the provisions of the nondiscrimination clause, in a conspicuous and easily accessible place, available for employees and applicants for employment.

If a state public official (section 19.42, Stats.) or an organization in which a state public official holds at least a 10% interest is a party to this agreement, this contract is voidable by the state unless appropriate disclosure is made to the State of Wisconsin Ethics Board.

## Effective with June 2015 Letting

### BID PREPARATION

#### **Preparing the Proposal Schedule of Items**

##### **A General**

- (1) Obtain bidding proposals as specified in **section 102** of the standard specifications prior to 11:45 AM of the last business day preceding the letting. Submit bidding proposals using one of the following methods:
  1. Electronic bid on the internet.
  2. Electronic bid on a printout with accompanying diskette or CD ROM.
  3. Paper bid under a waiver of the electronic submittal requirements.
- (2) Bids submitted on a printout with accompanying diskette or CD ROM or paper bids submitted under a waiver of the electronic submittal requirements govern over bids submitted on the internet.
- (3) The department will provide bidding information through the department's web site at:

Use the following link prior to June 19, 2015:

<http://roadwaystandards.dot.wi.gov/hcci/>

Use the following link beginning June 19, 2015:

<http://wisconsindot.gov/Pages/doing-bus/contractors/hcci/bid-let.aspx>

The contractor is responsible for reviewing this web site for general notices as well as information regarding proposals in each letting. The department will also post special notices of all addenda to each proposal through this web site no later than 4:00 P.M. local time on the Thursday before the letting. Check the department's web site after 5:00 P.M. local time on the Thursday before the letting to ensure all addenda have been accounted for before preparing the bid. When bidding using methods 1 and 2 above, check the Bid Express™ on-line bidding exchange at <http://www.bidx.com/> after 5:00 P.M. local time on the Thursday before the letting to ensure that the latest schedule of items Expedite file (\*.ebs or \*.00x) is used to submit the final bid.

- (4) Interested parties can subscribe to the Bid Express™ on-line bidding exchange by following the instructions provided at the [www.bidx.com](http://www.bidx.com) web site or by contacting:

Info Tech Inc.

5700 SW 34th Street, Suite 1235

Gainesville, FL 32608-5371

email: <mailto:customer.support@bidx.com>

- (5) The department will address equipment and process failures, if the bidder can demonstrate that those failures were beyond their control.
- (6) Contractors are responsible for checking on the issuance of addenda and for obtaining the addenda. Notice of issuance of addenda is posted on the department's web site at:

Use the following link prior to June 19, 2015:

<http://roadwaystandards.dot.wi.gov/hcci/>

Use the following link beginning June 19, 2015:

<http://wisconsindot.gov/Pages/doing-bus/contractors/hcci/bid-let.aspx>

or by calling the department at (608) 266-1631. Addenda can ONLY be obtained from the departments web site listed above or by picking up the addenda at the Bureau of Highway Construction, Room 601, 4802 Sheboygan Avenue, Madison, WI, during regular business hours.

## **B Submitting Electronic Bids**

### **B.1 On the Internet**

- (1) Do the following before submitting the bid:
  1. Have a properly executed annual bid bond on file with the department.
  2. Have a digital ID on file with and enabled by Info Tech Inc. Using this digital ID will constitute the bidder's signature for proper execution of the bidding proposal.
- (2) In lieu of preparing, delivering, and submitting the proposal as specified in 102.6 and 102.9 of the standard specifications, submit the proposal on the internet as follows:
  1. Download the latest schedule of items reflecting all addenda from the Bid Express<sup>TM</sup> web site.
  2. Use Expedite<sup>TM</sup> software to enter a unit price for every item in the schedule of items.
  3. Submit the bid according to the requirements of Expedite<sup>TM</sup> software and the Bid Express<sup>TM</sup> web site. Do not submit a bid on a printout with accompanying diskette or CD ROM or a paper bid. If the bidder does submit a bid on a printout with accompanying diskette or a paper bid in addition to the internet submittal, the department will disregard the internet bid.
  4. Submit the bid before the hour and date the Notice to Contractors designates.
  5. Do not sign, notarize, and return the bidding proposal described in 102.2 of the standard specifications.
- (3) The department will not consider the bid accepted until the hour and date the Notice to Contractors designates.

### **B.2 On a Printout with Accompanying Diskette or CD ROM**

- (1) Download the latest schedule of items from the Wisconsin pages of the Bid Express<sup>TM</sup> web site reflecting the latest addenda posted on the department's web site at:

Use the following link prior to June 19, 2015:

<http://roadwaystandards.dot.wi.gov/hcci/>

Use the following link beginning June 19, 2015:

<http://wisconsin.dot.gov/Pages/doing-bus/contractors/hcci/bid-let.aspx>

Use Expedite<sup>TM</sup> software to prepare and print the schedule of items. Provide a valid amount for all price fields. Follow instructions and review the help screens provided on the Bid Express<sup>TM</sup> web site to assure that the schedule of items is prepared properly.

- (2) Staple an 8 1/2 by 11 inch printout of the Expedite<sup>TM</sup> generated schedule of items to the other proposal documents submitted to the department as a part of the bidder's sealed bid. As a separate submittal not in the sealed bid envelop but due at the same time and place as the sealed bid, also provide the Expedite<sup>TM</sup> generated schedule of items on a 3 1/2 inch computer diskette or CD ROM. Label each diskette or CD ROM with the bidder's name, the 4 character department-assigned bidder identification code from the top of the bidding proposal, and a list of the proposal numbers included on that diskette or CD ROM as indicated in the following example:

**Bidder**

**Name**

**BN00**

**Proposals: 1, 12, 14, & 22**

- (3) If bidding on more than one proposal in the letting, the bidder may include all proposals for that letting on one diskette or CD ROM. Include only submitted proposals with no incomplete or other files on the diskette or CD ROM.

- (4) The bidder-submitted printout of the Expedite<sup>TM</sup> generated schedule of items is the governing contract document and must conform to the requirements of [section 102](#) of the standard specifications. If a printout needs to be altered, cross out the printed information with ink or typewriter and enter the new information and initial it in ink. If there is a discrepancy between the printout and the diskette or CD ROM, the department will analyze the bid using the printout information.
- (5) In addition to the reasons specified in [section 102](#) of the standard specifications, proposals are irregular and the department may reject them for one or more of the following:
  - 1. The check code printed on the bottom of the printout of the Expedite<sup>TM</sup> generated schedule of items is not the same on each page.
  - 2. The check code printed on the printout of the Expedite<sup>TM</sup> generated schedule of items is not the same as the check code for that proposal provided on the diskette or CD ROM.
  - 3. The diskette or CD ROM is not submitted at the time and place the department designates.

### **C Waiver of Electronic Submittal**

- (1) The bidder may request a waiver of the electronic submittal requirements. Submit a written request for a waiver in lieu of bids submitted on the internet or on a printout with accompanying diskette or CD ROM. Use the waiver that was included with the paper bid document sent to the bidder or type up a waiver on the bidder's letterhead. The department will waive the electronic submittal requirements for a bidding entity (individual, partnership, joint venture, corporation, or limited liability company) for up to 4 individual proposals in a calendar year. The department may allow additional waivers for equipment malfunctions.
- (2) Submit a schedule of items on paper conforming to [section 102](#) of the standard specifications. The department charges the bidder a \$75 administrative fee per proposal, payable at the time and place the department designates for receiving bids, to cover the costs of data entry. The department will accept a check or money order payable to: "Wisconsin, Dept. of Transportation."
- (3) In addition to the reasons specified in [section 102](#) of the standard specifications, proposals are irregular and the department may reject them for one or more of the following:
  - 1. The bidder fails to provide the written request for waiver of the electronic submittal requirements.
  - 2. The bidder fails to pay the \$75 administrative fee before the time the department designates for the opening of bids unless the bidder requests on the waiver that they be billed for the \$75.
  - 3. The bidder exceeds 4 waivers of electronic submittal requirements within a calendar year.
- (4) In addition to the reasons specified in [section 102](#) of the standard specifications, the department may refuse to issue bidding proposals for future contracts to a bidding entity that owes the department administrative fees for a waiver of electronic submittal requirements.

# PROPOSAL BID BOND

DT1303 1/2006

Wisconsin Department of Transportation

Proposal Number	Project Number	Letting Date
Name of Principal		
Name of Surety	State in Which Surety is Organized	

We, the above-named Principal and the above-named Surety, are held and firmly bound unto the State of Wisconsin in the sum equal to the Proposal Guaranty for the total bid submitted for the payment to be made; we jointly and severally bind ourselves, our heirs, executors, administrators, successors and assigns. The condition of this obligation is that the Principal has submitted a bid proposal to the State of Wisconsin acting through the Department of Transportation for the improvement designated by the Proposal Number and Letting Date indicated above.

If the Principal is awarded the contract and, within the time and manner required by law after the prescribed forms are presented for signature, enters into a written contract in accordance with the bid, and files the bond with the Department of Transportation to guarantee faithful performance and payment for labor and materials, as required by law, or if the Department of Transportation shall reject all bids for the work described, then this obligation shall be null and void; otherwise, it shall be and remain in full force and effect. In the event of failure of the Principal to enter into the contract or give the specified bond, the Principal shall pay to the Department of Transportation **within 10 business days of demand** a total equal to the Proposal Guaranty as liquidated damages; the liability of the Surety continues for the full amount of the obligation as stated until the obligation is paid in full.

The Surety, for value received, agrees that the obligations of it and its bond shall not be impaired or affected by any extension of time within which the Department of Transportation may accept the bid; and the Surety does waive notice of any such extension.

IN WITNESS, the Principal and Surety have agreed and have signed by their proper officers and have caused their corporate seals to be affixed this date: **(DATE MUST BE ENTERED)**

## PRINCIPAL

\_\_\_\_\_  
(Company Name) **(Affix Corporate Seal)**

\_\_\_\_\_  
(Signature and Title)

\_\_\_\_\_  
(Company Name)

\_\_\_\_\_  
(Signature and Title)

\_\_\_\_\_  
(Company Name)

\_\_\_\_\_  
(Signature and Title)

\_\_\_\_\_  
(Company Name)

\_\_\_\_\_  
(Signature and Title)

## NOTARY FOR PRINCIPAL

\_\_\_\_\_  
(Date)

State of Wisconsin )  
 ) ss.  
\_\_\_\_\_ County )

On the above date, this instrument was acknowledged before me by the named person(s).

\_\_\_\_\_  
(Signature, Notary Public, State of Wisconsin)

\_\_\_\_\_  
(Print or Type Name, Notary Public, State of Wisconsin)

\_\_\_\_\_  
(Date Commission Expires)

**Notary Seal**

\_\_\_\_\_  
(Name of Surety) **(Affix Seal)**

\_\_\_\_\_  
(Signature of Attorney-in-Fact)

## NOTARY FOR SURETY

\_\_\_\_\_  
(Date)

State of Wisconsin )  
 ) ss.  
\_\_\_\_\_ County )

On the above date, this instrument was acknowledged before me by the named person(s).

\_\_\_\_\_  
(Signature, Notary Public, State of Wisconsin)

\_\_\_\_\_  
(Print or Type Name, Notary Public, State of Wisconsin)

\_\_\_\_\_  
(Date Commission Expires)

**Notary Seal**

**IMPORTANT: A certified copy of Power of Attorney of the signatory agent must be attached to the bid bond.**





# CERTIFICATE OF ANNUAL BID BOND

DT1305 8/2003

Wisconsin Department of Transportation

Time Period Valid (From/To)	
Name of Surety	
Name of Contractor	
Certificate Holder	Wisconsin Department of Transportation

This is to certify that an annual bid bond issued by the above-named Surety is currently on file with the Wisconsin Department of Transportation.

This certificate is issued as a matter of information and conveys no rights upon the certificate holder and does not amend, extend or alter the coverage of the annual bid bond.

**Cancellation:** Should the above policy be cancelled before the expiration date, the issuing surety will give thirty (30) days written notice to the certificate holder indicated above.

\_\_\_\_\_  
(Signature of Authorized Contractor Representative)

\_\_\_\_\_  
(Date)



## March 2010

## LIST OF SUBCONTRACTORS

Section 66.0901(7), Wisconsin Statutes, provides that as a part of the proposal, the bidder also shall submit a list of the subcontractors the bidder proposes to contract with and the class of work to be performed by each. In order to qualify for inclusion in the bidder's list a subcontractor shall first submit a bid in writing, to the general contractor at least 48 hours prior to the time of the bid closing. The list may not be added to or altered without the written consent of the municipality. A proposal of a bidder is not invalid if any subcontractor and the class of work to be performed by the subcontractor has been omitted from a proposal; the omission shall be considered inadvertent or the bidder will perform the work personally.

No subcontract, whether listed herein or later proposed, may be entered into without the written consent of the Engineer as provided in Subsection 108.1 of the Standard Specifications.

[illegible]

**DECEMBER 2000**

**CERTIFICATION REGARDING DEBARMENT, SUSPENSION, AND OTHER  
RESPONSIBILITY MATTERS - PRIMARY COVERED TRANSACTIONS**

Instructions for Certification

1. By signing and submitting this proposal, the prospective contractor is providing the certification set out below.
2. The inability of a person to provide the certification required below will not necessarily result in denial of participation in this covered transaction. The prospective contractor shall submit an explanation of why it cannot provide the certification set out below. The certification or explanation will be considered in connection with the department or agency's determination whether to enter into this transaction. However, failure of the prospective contractor to furnish a certification or an explanation shall disqualify such person from participation in this transaction.
3. The certification in this clause is a material representation of fact upon which reliance was placed when the department determined to enter into this transaction. If it is later determined that the contractor knowingly rendered an erroneous certification in addition to other remedies available to the Federal Government the department may terminate this transaction for cause or default.
4. The prospective contractor shall provide immediate written notice to the department to whom this proposal is submitted if at any time the prospective contractor learns that its certification was erroneous when submitted or has become erroneous by reason of changed circumstances.
5. The terms "covered transaction," "debarred," "suspended," "ineligible," "lower tier covered transaction," "participant," "person," "primary covered transaction," "principal," "proposal," and "voluntarily excluded," as used in this clause, have the meanings set out in the Definitions and Coverage sections of the rules implementing Executive Order 12549. You may contact the department to which this proposal is being submitted for assistance in obtaining a copy of those regulations.
6. The prospective contractor agrees by submitting this proposal that, should this contract be entered into, it shall not knowingly enter into any lower tier covered transaction with a person who is debarred, suspended, declared ineligible, or voluntarily excluded from participation in this covered transaction, unless authorized by the department entering into this transaction.
7. The prospective contractor further agrees by submitting this proposal that it will include the clause titled "Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion-Lower Tier Covered Transaction," which is included as an addendum to PR-1273 - "Required Contract Provisions Federal Aid Construction Contracts," without

modification, in all lower tier covered transactions and in all solicitations for lower tier covered transactions.

8. The contractor may rely upon a certification of a prospective subcontractor/materials supplier that it is not debarred, suspended, ineligible, or voluntarily excluded from the covered transaction, unless it knows that the certification is erroneous. A contractor may decide the method and frequency by which it determines the eligibility of its principals. Each contractor may, but is not required to, check the Disapproval List (telephone # 608/266/1631).
9. Nothing contained in the foregoing shall be construed to require establishment of a system of records in order to render in good faith the certification required by this clause. The knowledge and information of a contractor is not required to exceed that which is normally possessed by a prudent person in the ordinary course of business dealings.
10. Except for transactions authorized under paragraph 6 of these instructions, if a contractor in a covered transaction knowingly enters into a lower tier covered transaction with a person who is suspended, debarred, ineligible or voluntarily excluded from participation in this transaction, in addition to other remedies available to the Federal Government, the department may terminate this transaction for cause or default.

Certification Regarding Debarment, Suspension, and Other Responsibility Matters - Primary Covered Transactions

- (1) The prospective contractor certifies to the best of its knowledge and belief, that it and its principals:
  - (a) Are not presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from covered transactions by any Federal department or agency;
  - (b) Have not within a three-year period preceding this proposal been convicted of or had a civil judgment rendered against them for commission of fraud or a criminal offense in connection with obtaining, attempting to obtain, or performing a public (Federal, State or local) transaction or contract under a public transaction; violation of Federal or State antitrust statutes or commission of embezzlement, theft, forgery, bribery, falsification or destruction of records, making false statements or receiving stolen property;
  - (c) Are not presently indicted for or otherwise criminally or civilly charged by a governmental entity (Federal, State or local) with commission of any of the offense enumerated in paragraph (1)(b) of this certification; and
  - (d) Have not within a three-year period preceding this proposal had one or more public transactions (Federal, State or local) terminated for cause or default.
- (2) Where the prospective contractor is unable to certify to any of the statements in this certification, such prospective contractor shall attach an explanation to this proposal.

## Special Provisions

### Table of Contents

Article	Description	Page #
1.	General.....	2
2.	Scope of Work. ....	2
3.	Prosecution and Progress. ....	2
4.	Traffic. ....	3
5.	Holiday Work Restrictions. ....	4
6.	Utilities.....	4
7.	Public Convenience and Safety. ....	5
8.	Environmental Protection, Aquatic Exotic Species Control.....	6
9.	Erosion Control Structures.....	7
10.	Erosion Control.....	7
11.	Environmental Protection - Dewatering. ....	8
12.	Information to Bidders - U.S. Army Corps of Engineers Section 404 Permit.....	8
13.	Notice to Contractor, Notification of Demolition and/or Renovation No Asbestos Found. ....	9
14.	Removing Old Structure Over Waterway With Debris Capture System Station 34”BR”+49.00, Item 203.0700.S.01.....	9
15.	QMP Base Aggregate. ....	10
16.	QMP Ride; Incentive IRI Ride, Item 440.4410.S.....	18
17.	QMP HMA Pavement Nuclear Density.....	25
18.	Reheating HMA Pavement Longitudinal Joints, Item 460.4110.S.....	33
19.	Concrete Staining Multi-Color B-26-39, Item 517.1015.S.....	34
20.	Architectural Surface Treatment B-26-39, Item 517.1050.S.....	36
21.	Removing Signs Type II. ....	37
22.	Field Facilities.....	37
23.	Pavement Marking Epoxy.....	37
24.	Locating No-Passing Zones, Item 648.0100.....	38
25.	Culvert Pipe Transitions, Item SPV.0060.01.....	38
26.	Reestablish Section Corner Monuments, Item SPV.0060.02. ....	39
27.	Lane Shift, Item SPV.0060.03. ....	40

## **SPECIAL PROVISIONS**

### **1. General.**

Perform the work under this construction contract for Project 9240-09-70, Park Falls – Manitowish, Bear River Bridge B-26-0039, STH 182, and Project 9240-09-80, Park Falls – Manitowish, Price County Line – STH 47, STH 182, both projects in Iron County, Wisconsin as the plans show and execute the work as specified in the State of Wisconsin, Department of Transportation, Standard Specifications for Highway and Structure Construction, 2015 Edition, as published by the department, and these special provisions.

If all or a portion of the plans and special provisions are developed in the SI metric system and the schedule of prices is developed in the US standard measure system, the department will pay for the work as bid in the US standard system.

100-005 (20141107)

### **2. Scope of Work.**

The work under this contract shall consist of Bear River Bridge, B-26-39, temporary signals and related traffic control items, excavation common, guard rail, removing asphaltic surface milling, HMA pavement 0.3, preparation of asphaltic shoulders, base aggregate dense, culvert pipe replacements, permanent signing, centerline rumbles and epoxy pavement marking and all incidental items necessary to complete the work as shown on the plans and included in the proposal and contract.

104-05 0090901)

### **3. Prosecution and Progress.**

Begin work within ten calendar days after the engineer issues a written notice to do so.  
(20090901)

Install silt fence adjacent to wetlands prior to operating heavy equipment in these areas to prevent debris from entering into wetlands.

#### **Fish Spawning**

There shall be no instream disturbance of Bear River as a result of construction activity under or for this contract, from October 15 to June 15 both dates inclusive, in order to avoid adverse impacts upon the spawning of all fish.

Any change to this limitation will require submitting a written request by the contractor to the engineer, subsequent review and concurrence by the Department of Natural Resources in the request, and final approval by the engineer. The approval will include all conditions to the request as mutually agreed upon by WisDOT and DNR.



**Asphaltic Surface Patching**

Place Asphaltic Surface Patching before areas are opened up to traffic or when flagmen are present to direct traffic through the work areas.

**Milling and Overlay**

Do not allow the exposed milled surface to remain open to traffic for a period greater than 48 hours.

**Migratory Birds**

Swallow and other migratory birds' nests have been observed on or under the existing bridge. All active nests (when eggs or young are present) of migratory birds are protected under the federal Migratory Bird Treaty Act.

The nesting season for swallows and other birds is usually between May 1 and August 30. Either prevent active nests from becoming established, or apply for a depredation permit from the US Fish and Wildlife Service for work that may disturb or destroy active nests. The need for a permit may be avoided by removing the existing bridge structure prior to nest occupation by birds, or clearing nests from all structures before the nests become active in early spring. As a last resort, prevent birds from nesting by installing a suitable netting device on the remaining structure prior to nesting activity. Include the cost for preventing nesting in the cost of Removing Old Structure Over Waterway with Debris Capture System.

**Construction Over or Adjacent to Navigable Waters**

*Add the following to standard spec 107.19(3):*

A waterway marker permit is required for placing advanced warning signs in Bear River as shown in the plans. Additional information on waterway markers can be found on the Wisconsin DNR website: <http://dnr.wi.gov/topic/boat/ordinances.html>. (NCR 107.01-10152014)

**4. Traffic.**

The project will be constructed under traffic and as described below. Traffic flow and access will be maintained for the duration of the construction project. Construction will occur during daylight hours on weekdays. Traffic may be restricted to a single lane within the area of construction operations during daylight hours utilizing flag persons as shown in the Traffic Control for Lane Closure (Suitable for Moving Operations) standard detail drawing. This lane restriction shall not exceed one mile in length. This single lane restriction shall apply to any work performed on STH 182 and all intersecting roads under this contract.

Maintain access to all businesses and residences at all times. Do not close any driveways without permission of the engineer and provide a minimum of 48 hours advance notice to the property owner. Do not close entrances longer than ½ day unless other arrangements are made with the property owners affected.

Maintain access through work zones to local streets and residences at all times. Any disruptions to access shall be controlled at all times by the use of proper traffic control measures, including flaggers, and must have the prior approval of the engineer. Necessary marking and signing of the roadway within the construction shall be the responsibility of the contractor.

Do not park equipment or materials within 10 feet of the edge of the shoulder unless approved by the engineer. Do not park or store equipment or material not being used during actual performance of work within 30 feet of the edge of traveled way.

Restore HMA pavement after each culvert pipe has been completely replaced by the weekend or 72 hours, whichever is sooner. Remove the temporary widening at the shoulders as a result of the lane shift after each pipe is completely installed and restore the shoulders will be restored to their original dimensions and condition.

Traffic will be restricted to a single lane within the area of construction operations. This single lane restriction for work performed on the Bear River Bridge, B-26-39, which shall be constructed in halves managed by temporary traffic signals. The spacing between stop bars shall be 500 feet during temporary traffic signal operation, with the exception of a maximum time period of two weeks, at which the spacing may be lengthened to 1900 feet, with an approved schedule from the engineer, 10 days prior. This spacing will address the grade difference from existing to proposed roadways, and will accommodate paving of the binder course, transitioning from Stage 1 to Stage 2.

After the culvert pipe has been completely replaced the roadway surface shall be restored to HMA pavement by the weekend or 72 hours, whichever is sooner, as shown in the Culvert Pipe Transition construction detail at all pipe replacement location within the project limits.

## **5. Holiday Work Restrictions.**

Do not perform work on, nor haul materials of any kind along or across any portion of the highway carrying STH 182 traffic, and entirely clear the traveled way and shoulders of such portions of the highway of equipment, barricades, signs, lights, and any other material that might impede the free flow of traffic during the following holiday periods:

- From noon Friday, July 3, 2015, to 6:00 AM Monday July 6, 2015 for Independence Day;
- From noon Friday, September 4, 2015 to 6:00 AM Tuesday, September 8, 2015 for Labor Day.

107-005 (20050502)

## **6. Utilities.**

### **Utilities 9240-09-70.**

This contract comes under the provision of Administrative Rule Trans 220.

107-065 (20080501)

There are utility facilities within the construction limits of this project. Additional detailed information regarding the location of discontinued, relocated, and/or removed utility facilities is available in the work plan provided by each utility company or on the permits issued to them.

View these documents at the Regional Office during normal working hours.

The following utilities are located within or near the project limits and no conflicts are anticipated:

**CenturyLink**  
**Price Electric Cooperative Inc.**

**Utilities 9240-09-80.**

This contract comes under the provision of Administrative Rule Trans 220.  
107-065 (20080501)

There are utility facilities within the construction limits of this project. Additional detailed information regarding the location of discontinued, relocated, and/or removed utility facilities is available in the work plan provided by each utility company or on the permits issued to them. View these documents at the Regional Office during normal working hours.

**CenturyLink** has underground communication facilities along the left side of STH 182 near culvert 26-182-03.

Prior to construction CenturyLink plans to discontinue this facility in place.

Prior to construction CenturyLink plans to install a new facility along the left side of STH 182 beyond the endwall of culvert 26-182-03. No conflicts are anticipated.

CenturyLink has other facilities throughout project limits. No conflicts are anticipated.

The following utilities are located within or near the project limits and no conflicts are anticipated:

**Price Electric Cooperative Inc.**

**7. Public Convenience and Safety.**

*Replace standard spec 107.8 (4) with the following:*

Notify the following organizations and departments at least 2 business days before, lane closures are put into effect:

Wisconsin State Patrol  
Iron County Sheriff's Department  
Iron County Highway Departments  
Town of Sherman  
Town of Sherman Fire Department  
Town of Sherman First Responders  
School District of Park Falls  
School District of Mercer

## **8. Environmental Protection, Aquatic Exotic Species Control.**

Exotic invasive organisms such as VHS, zebra mussels, purple loosestrife, and Eurasian water milfoil are becoming more prolific in Wisconsin and pose adverse effects to waters of the state. Wisconsin State Statutes 30.07, "Transportation of Aquatic Plants and Animals; Placement of Objects in Navigable Waters", details the state law that requires the removal of aquatic plants and zebra mussels each time equipment is put into state waters.

At construction sites that involve navigable water or wetlands, use the follow cleaning procedures to minimize the chance of exotic invasive species infestation. Use these procedures for all equipment that comes in contact with waters of the state and/or infested water or potentially infested water in other states.

Ensure that all equipment that has been in contact with waters of the state, or with infested or potentially infested waters, has been decontaminated for aquatic plant materials and zebra mussels prior to being used in other waters of the state. Before using equipment on this project, thoroughly disinfect all equipment that has come into contact with potentially infested waters. Use the following inspection and removal procedures (guidelines from the Wisconsin Department of Natural Resources [http://dnr.wi.gov/topic/fishing/documents/vhs/disinfection\\_protocols.pdf](http://dnr.wi.gov/topic/fishing/documents/vhs/disinfection_protocols.pdf) for disinfection:

1. Prior to leaving the contaminated site, wash machinery and ensure that the machinery is free of all soil and other substances that could possibly contain exotic invasive species;
2. Drain all water from boats, trailers, bilges, live wells, coolers, bait buckets, engine compartments, and any other area where water may be trapped;
3. Inspect boat hulls, propellers, trailers and other surfaces. Scrape off any attached mussels, remove any aquatic plant materials (fragments, stems, leaves, seeds, or roots), and dispose of removed mussels and plant materials in a garbage can prior to leaving the area or invested waters; and
4. Disinfect your boat, equipment and gear by either:
  - a. Washing with ~212° F water (steam clean), or
  - b. Drying thoroughly for five days after cleaning with soap and water and/or high pressure water, or

- c. Disinfecting with either 200 ppm (0.5 oz per gallon or 1 Tablespoon per gallon) Chlorine for 10-minute contact time or 1:100 solution (38 grams per gallon) of Virkon Aquatic for 20- to 30-minute contact time. Note: Virkon is not registered to kill zebra mussel veligers nor invertebrates like spiny water flea. Therefore this disinfect should be used in conjunction with a hot water (>104° F) application.

Complete the inspection and removal procedure before equipment is brought to the project site and before the equipment leaves the project site.

107-055 (20130615)

## **9. Erosion Control Structures.**

Within seven calendar days after the commencement of work on the bridge superstructure, place all permanent erosion control devices, including riprap, erosion mat, ditch checks, seed, fertilizer, mulch, soil stabilizer, or any other item required by the contract or deemed necessary by the engineer. These devices shall be in place in the area under the bridge and on both sides of the roadway, from the waterway to a point 100-feet behind the backwall of the abutment. Within said limits, place these devices to a height equivalent to the calculated water elevation resulting from a storm that occurs on the average of once every two years (Q2) as shown on the plan, or as directed by the engineer. Prior to initial construction operations, place turbidity barriers, silt screens, and other temporary erosion control measures as shown on the plans, and remove them after the permanent erosion control devices are in place unless directed otherwise by the engineer.

In the event that construction activity does not disturb the existing ground below the Q2 elevation, the above timing requirements for permanent erosion control shall be waived.

107-070 (20030820)

## **10. Erosion Control.**

*Add the following to standard spec 107.20:*

Perform construction operations in a timely and diligent manner, continuing all construction operations methodically from the initial topsoil stripping operation through the subsequent grading and finishing to minimize the period of exposure to erosion.

Replace topsoil on disturbed areas, including spot locations such as cross drains, driveways, guardrail and terminals, and intersections, immediately after grading is completed within those areas. Complete finishing operations, which includes seed, fertilizer, mulch and any other permanent erosion control measures required, within seven calendar days after the placement of topsoil.

(NCR 107.03-10152014)

## **11. Environmental Protection - Dewatering.**

*Add the following to standard spec 107.18:*

If dewatering is required, treat the water to remove suspended solids before allowing it to enter any waterway or wetland. Provide a settling basin, or other suitable means approved by the engineer, with sufficient capacity and size to provide an efficient means to filter the water from the dewatering operation before it is discharged back into the wetland or waterway as provided in the standard specifications and these special provisions. Treatment practices may include the use of natural polyacrylamide such as chitosan, as approved by the engineer.

Conform to dewatering guidelines of WisDNR Storm Water Construction Technical Standards, Code #1061, "Dewatering". This document can be found at the WisDNR website: [http://dnr.wi.gov/topic/stormwater/standards/const\\_standards.html](http://dnr.wi.gov/topic/stormwater/standards/const_standards.html). Include dewatering plans in the Erosion Control Implementation Plan (ECIP) for the project.

Include the cost of all work and materials associated with water treatment and/or dewatering in the unit bid price for culvert pipe replacement items. Work includes furnishing all materials, excavation, maintenance, cleaning, disposal of surplus material, removal of the basin after completion of dewatering operations.  
(NCR 107.13-10152014)

## **12. Information to Bidders - U.S. Army Corps of Engineers Section 404 Permit.**

The department has obtained a US Army Corps of Engineers Section 404 Permit. Comply with the requirements of the permit in addition to requirements of the special provisions. A copy of the permit is available from the region office by contacting Jim Volkmann at (715) 365-5773, methods of operations, including preparatory work, staging, site clean-up or storing materials, causing impacts to other wetlands or waters are not permitted.

If the contractor chooses a method of construction that is not covered by the department's 404 Permit, obtain the proper additional permits required from the US Army Corps of Engineers. It is the contractor's responsibility to determine if additional permits are required. Obtain the additional permits prior to beginning construction operations requiring the permits. No time extensions as discussed in standard spec 108.10 will be granted for the time required to apply for and obtain the additional permits. The contractor must be aware that the US Army Corps of Engineers may not grant the additional permits.  
(NCR 107.07-10052011)

### **13. Notice to Contractor, Notification of Demolition and/or Renovation No Asbestos Found.**

James Gondek, License Number 108099, inspected Structure B-26-0002 for asbestos on July 22, 2014. No regulated Asbestos Containing Material (RACM) was found on this structure. A copy of the inspection report is available from: Dave Kircher at (715) 365-5769.

In accordance with NR447 and DHS159, ensure that DNR or DHS receives a completed Notification of Demolition and/or Renovation (DNR Form 4500-113 (R 4/11), or subsequent revision) via U.S. mail, hand-delivery, or using the online notification system at least 10 working days prior to beginning any construction or demolition. Pay all associated fees. Provide a copy of the completed 4500-113 form to Jim Volkmann at (715) 365-5773 and DOT BTS-ESS attn: Hazardous Materials Specialist PO Box 7965, Madison, WI 53707-7965. In addition, comply with all local or municipal asbestos requirements.

Use the following information to complete WisDNR form 4500-113 :

- Site Name: Structure B-26-0002, STH 182 over Bear River
- Site Address: 46.4'40.25" N / 90.0'54.08"W T 42 N R 4E Sec 32, Town of Sherman
- Ownership Information: Wis DOT NCR Rhinelander, 510 Hanson Lake Rd, Rhinelander WI 54501
- Contact: Jim Volkmann
- Phone: (715) 365-5773
- Age: 67 years old. This structure was constructed in 1948.
- Area: 1560 SF of deck
  
- If asbestos not previously identified is found or previously non-friable asbestos becomes crumbled, pulverized, or reduced to a powder, stop work immediately, notify the engineer, and the engineer will notify the department's Bureau of Technical Services at (608) 266-1476 for an emergency response in accordance to standard spec 107.24. Keep material wet until it is abated or until it is determined to be non-asbestos containing material.

107-125 (20120615)

### **14. Removing Old Structure Over Waterway With Debris Capture System Station 34"BR"+49.00, Item 203.0700.S.01.**

Conform to standard spec 203 as modified in this special provision.

*Add the following to standard spec 203:*

#### **203.3.6 Removals Over Waterways and Wetlands**

##### **203.3.6.3 Removing Old Structure Over Waterway with Debris Capture System**

- (1) Remove the existing Structure B-26-02 over the Bear River in large sections and conforming to the contractor's approved structure removal plan. Due to the very

sensitive nature of the Bear River, provide a debris capture and containment system for superstructure removal that prevents all large pieces and virtually all other debris, including fine particles and slurry, from entering the waterway or wetland.

- (2) Submit a structure removal plan as part of the erosion control implementation plan required under standard spec 107.20. Do not start work under the structure removal plan without the department's written approval of the plan. Include the following information in the structure removal plan:
  - Methods and schedule to remove the structure.
  - Methods to control potentially harmful environmental impacts.
  - Methods to avoid or minimize the discharge of any pollutant to the waterway or wetland during superstructure removal.
  - Details of the debris capture and containment system for superstructure removal including contingency plans to deal with potential failures.
  - Methods to control dust and contain slurry.
  - Methods for removing piers and abutments. If blasting in water, include restrictions that regulatory agencies and the contract require.
- (3) If stockpiling spoil material, place it on an upland site an adequate distance from the waterway, wetland, or any open water created by excavation. Install silt fence between the spoil pile and the waterway, wetland, or excavation site.

*Add the following Removing Old Structure bid item to standard spec 203.5.1 of the standard specifications:*

ITEM NUMBER	DESCRIPTION	UNIT
203.0700.S.01	Removing Old Structure Over Waterway With Debris Capture System Station 34"BR"+49.00	LS
203-025 (20080902)		

## **15. QMP Base Aggregate.**

### **A Description**

#### **A.1 General**

- (1) This special provision describes contractor quality control (QC) sampling and testing for base aggregates, documenting those test results, and documenting related production and placement process changes. This special provision also describes department quality verification (QV), independent assurance (IA), and dispute resolution.
- (2) Conform to standard spec 301, standard spec 305, and standard spec 310 as modified here in this special provision. Apply this special provision to material placed under all of the Base Aggregate Dense and Base Aggregate Open Graded bid items, except do not apply this special provision to material classified as reclaimed asphaltic pavement placed under the Base Aggregate Dense bid items.



- (3) Do not apply this special provision to material placed under the Aggregate Detours, Salvaged Asphaltic Pavement Base, Breaker Run, Select Crushed, Pit Run, Subbase, or Riprap bid items.
- (4) Provide and maintain a quality control program, defined as all activities related to and documentation of the following:
  1. Production and placement control and inspection.
  2. Material sampling and testing.
- (5) Chapter 8 of the department's construction and materials manual (CMM) provides additional detailed guidance for QMP work and describes required sampling and testing procedures. The contractor may obtain the CMM from the department's web site at:

<http://roadwaystandards.dot.wi.gov/standards/cmm/index.htm>

## **A.2 Contractor Testing for Small Quantities**

- (1) The department defines a small quantity, for each individual Base Aggregate bid item, as a plan quantity of 9000 tons or less of material as shown in the schedule of items under that bid item.
- (2) The requirements under this special provision apply equally to a small quantity for an individual bid item except as follows:
  1. The contractor need not submit a full quality control plan but shall provide an organizational chart to the engineer including names, telephone numbers, and current certifications of all persons involved in the quality control program for material under affected bid items.
  2. Divide the aggregate into uniformly sized sublots for testing as follows:

<b>Plan Quantity</b>	<b>Minimum Required Testing</b>
$\leq 1500$ tons	One test from production, load-out, or placement at the contractor's option <sup>[1]</sup>
$> 1500$ tons and $\leq 6000$ tons	Two tests of the same type, either from production, load-out, or placement at the contractor's option <sup>[1]</sup>
$> 6000$ tons and $\leq 9000$ tons	Three placement tests <sup>[2][3]</sup>

<sup>[1]</sup> If using production tests for acceptance, submit test results to the engineer for review prior to incorporating the material into the work. Production test results are valid for a period of 3 years.

<sup>[2]</sup> For 3-inch material, obtain samples at load-out.

<sup>[3]</sup> If the actual quantity overruns 9000 tons, create overrun sublots to test at a rate of one additional placement test for each 3000 tons, or fraction of 3000 tons, of overrun.

3. No control charts are required. Submit aggregate load-out and placement test results to the engineer within one business day of obtaining the sample. Assure that all properties are within the limits specified for each test.

4. Department verification testing is optional for quantities of 6000 tons or less.

- (3) Material represented by a subplot with any property outside the specification limits is nonconforming. The department may reject material or otherwise determine the final disposition of nonconforming material as specified in standard spec 106.5.

## **B Materials**

### **B.1 Quality Control Plan**

- (1) Submit a comprehensive written quality control plan to the engineer at or before the pre-construction meeting. Do not place base before the engineer reviews and comments on the plan. Construct the project as that plan provides.
- (2) Do not change the quality control plan without the engineer's review. Update the plan with changes as they become effective. Provide a current copy of the plan to the engineer and post in each of the contractor's laboratories as changes are adopted. Ensure that the plan provides the following elements:
1. An organizational chart with names, telephone numbers, current certifications and/or titles, and roles and responsibilities of QC personnel.
  2. The process used to disseminate QC information and corrective action efforts to the appropriate persons. Include a list of recipients, the communication means that will be used, and action time frames.
  3. A list of source and processing locations, section and quarter descriptions, for all aggregate materials requiring QC testing.
  4. Test results for wear, sodium sulfate soundness, freeze/thaw soundness, and plasticity index of all aggregates requiring QC testing. Obtain this information from the region materials unit or from the engineer.
  5. Descriptions of stockpiling and hauling methods.
  6. Locations of the QC laboratory, retained sample storage, and where control charts and other documentation is posted.
  7. An outline for resolving a process control problem. Include responsible personnel, required documentation, and appropriate communication steps.

### **B.2 Personnel**

- (1) Have personnel certified under the department's highway technician certification program (HTCP) perform sampling, testing, and documentation as follows:

<b>Required Certification Level:</b>	<b>Sampling or Testing Roles:</b>
Aggregate Technician IPP Aggregate Sampling Technician Aggregate Assistant Certified Technician (ACT-AGG)	Aggregate Sampling <sup>[1]</sup>
Aggregate Technician IPP Aggregate Assistant Certified Technician (ACT-AGG)	Aggregate Gradation Testing, Aggregate Fractured Particle Testing, Aggregate Liquid Limit and Plasticity Index Testing

<sup>[1]</sup> Plant personnel under the direct observation of an aggregate technician certified at level one or higher may operate equipment to obtain samples.

- (2) A certified technician must coordinate and take responsibility for the work an ACT performs. Have a certified technician ensure that all sampling and testing is performed correctly, analyze test results, and post resulting data. No more than one ACT can work under a single certified technician.

### **B.3 Laboratory**

- (1) Perform QC testing at a department-qualified laboratory. Obtain information on the Wisconsin laboratory qualification program from:  
Materials Management Section  
3502 Kinsman Blvd.  
Madison, WI 53704  
Telephone: (608) 246-5388  
<http://www.dot.state.wi.us/business/engrserv/lab-qualification.htm>

### **B.4 Quality Control Documentation**

#### **B.4.1 General**

- (1) Submit base aggregate placement documentation to the engineer within 10 business days after completing base placement. Ensure that the submittal is complete, neatly organized, and includes applicable project records and control charts.

#### **B.4.2 Records**

- (1) Document all placement observations, inspection records, and control adjustments daily in a permanent field record. Also include all test results in the project records. Provide test results to the engineer within 6 hours after obtaining a sample. For 3-inch base, extend this 6-hour limit to 24 hours. Post or distribute tabulated results using a method mutually agreeable to the engineer and contractor.

#### **B.4.3 Control Charts**

- (1) Plot gradation and fracture on the appropriate control chart as soon as test results are available. Format control charts according to CMM 8.30. Include the project number on base placement control charts. Maintain separate control charts for each base aggregate size, source or classification, and type.
- (2) Provide control charts to the engineer within 6 hours after obtaining a sample. For 3-inch base, extend this 6-hour limit to 24 hours. Post or distribute charts using a method mutually agreeable to the engineer and contractor. Update control charts daily to include the following:
  1. Contractor individual QC tests.
  2. Department QV tests.
  3. Department IA tests.
  4. Four-point running average of the QC tests.
- (3) Except as specified under B.8.2.1 for nonconforming QV tests, include only QC tests in the running average. The contractor may plot process control or informational tests on control charts, but do not include these tests, conforming QV tests, or IA tests in the running average.

## **B.5 Contractor Testing**

- (1) Test gradation, fracture, liquid limit and plasticity index during placement for each base aggregate size, source or classification, and type.
- (2) Test gradation once per 3000 tons of material placed. Determine random sample locations and provide those sample locations to the engineer. Obtain samples after the material has been bladed, mixed, and shaped but before compacting; except collect 3-inch samples from the stockpile at load-out. Do not sample from material used to maintain local traffic or from areas of temporary base that will not have an overlying pavement. On days when placing only material used to maintain local traffic or only temporary base that will not have an overlying pavement, no placement testing is required.
- (3) Split each contractor QC sample and identify it according to CMM 8.30. Retain the split for 7 calendar days in a dry, protected location. If requested for department comparison testing, deliver the split to the engineer within one business day.
- (4) The engineer may require additional sampling and testing to evaluate suspect material or the technician's sampling and testing procedures.
- (5) Test fracture for each gradation test until the fracture running average is above the lower warning limit. Subsequently, the contractor may reduce the frequency to one test per 10 gradation tests if the fracture running average remains above the warning limit.
- (6) Test the liquid limit and plasticity index for the first gradation test. Subsequently, test the liquid limit and plasticity index a minimum of once per 10 gradation tests.

## **B.6 Test Methods**

### **B.6.1 Gradation**

- (1) Test gradation using a washed analysis conforming to the following as modified in CMM 8.60:  
Gradation..... AASHTO T 27  
Material finer than the No. 200 sieve..... AASHTO T 11
- (2) For 3-inch base, if 3 consecutive running average points for the percent passing the No. 200 sieve are 8.5 percent or less, the contractor may use an unwashed analysis. Wash at least one sample out of 10. If a single running average for the percent passing the No. 200 sieve exceeds 8.5 percent, resume washed analyses until 3 consecutive running average points are again 8.5 percent passing or less.
- (3) Maintain a separate control chart for each sieve size specified in standard spec 305 or standard spec 310 for each base aggregate size, source or classification, and type. Set control and warning limits based on the standard specification gradation limits as follows:

1. Control limits are at the upper and lower specification limits.
2. There are no upper warning limits for sieves allowing 100 percent passing and no lower control limits for sieves allowing 0 percent passing.
3. Dense graded warning limits, except for the No. 200 sieve, are 2 percent within the upper and lower control limits. Warning limits for the No. 200 sieve are set 0.5 percent within the upper and lower control limits.
4. Open graded warning limits for the 1-inch, 3/8-inch, and No. 4 sieves are 2 percent within the upper and lower control limits. Upper warning limits for the No. 10, No. 40, and No. 200 sieves are 1 percent inside the upper control limit.

### **B.6.2 Fracture**

- (1) Test fracture conforming to CMM 8.60. The engineer will waive fractured particle testing on quarried stone.
- (2) Maintain a separate fracture control chart for each base aggregate size, source or classification, and type. Set the lower control limit at the contract specification limit, either specified in another special provision or in table 301-2 of standard spec 301.2.4.5. Set the lower warning limit 2 percent above the lower control limit. There are no upper limits.

### **B.6.3 Liquid Limit and Plasticity**

- (1) Test the liquid limit and plasticity according to AASHTO T 89 and T 90.
- (2) Ensure the material conforms to the limits specified in standard spec table 301-2.

## **B.7 Corrective Action**

### **B.7.1 General**

- (1) Consider corrective action when the running average trends toward a warning limit. Take corrective action if an individual test exceeds the contract specification limit. Document all corrective actions both in the project records and on the appropriate control chart.

### **B.7.2 Placement Corrective Action**

- (1) Do not blend additional material on the roadbed to correct gradation problems.
- (2) Notify the engineer whenever the running average exceeds a warning limit. When 2 consecutive running averages exceed a warning limit, the engineer and contractor will discuss appropriate corrective action. Perform the engineer's recommended corrective action and increase the testing frequency as follows:
  1. For gradation, increase the QC testing frequency to at least one randomly sampled test per 1000 tons placed.
  2. For fracture, increase the QC testing frequency to at least one test per gradation test.

- (3) If corrective action improves the property in question such that the running average after 4 additional tests is within the warning limits, the contractor may return to the testing frequency specified in B.5.3. If corrective action does not improve the property in question such that the running average after 4 additional individual tests is still in the warning band, repeat the steps outlined above starting with engineer notification.
- (4) If the running average exceeds a control limit, material starting from the first running average exceeding the control limit and ending at the first subsequent running average inside the control limit is nonconforming and subject to pay reduction.
- (5) For individual test results significantly outside the control limits, notify the engineer, stop placing base, and suspend other activities that may affect the area in question. The engineer and contractor will jointly review data, data reduction, and data analysis; evaluate sampling and testing procedures; and perform additional testing as required to determine the extent of potentially unacceptable material. The engineer may direct the contractor to remove and replace that material. Individual test results are significantly outside the control limits if meeting one or more of the following criteria:
  - 1. A gradation control limit for the No. 200 sieve is exceeded by more than 3.0 percent.
  - 2. A gradation control limit for any sieve, except the No. 200, is exceeded by more than 5.0 percent.
  - 3. The fracture control limit is exceeded by more than 10.0 percent.

## **B.8 Department Testing**

### **B.8.1 General**

- (1) The department will conduct verification testing to validate the quality of the product and independent assurance testing to evaluate the sampling and testing. The department will provide the contractor with a listing of names and telephone numbers of all QV and IA personnel for the project, and provide test results to the contractor within 2 business days after the department obtains the sample.

### **B.8.2 Verification Testing**

#### **B.8.2.1 General**

- (1) The department will have an HTCP technician, or ACT working under a certified technician, perform QV sampling and testing. Department verification testing personnel must meet the same certification level requirements specified in B.2 for contractor testing personnel for each test result being verified. The department will notify the contractor before sampling so the contractor can observe QV sampling.
- (2) The department will conduct QV tests of each base aggregate size, source or classification, and type during placement conforming to the following:
  - 1. One non-random test on the first day of placement.
  - 2. At least one random test per 30,000 tons, or fraction of 30,000 tons, placed.

- (3) The department will sample randomly, at locations independent of the contractor's QC work, collecting one sample at each QV location. The department will collect QV samples after the material has been bladed, mixed, and shaped but before compacting; except, for 3-inch aggregates, the department will collect samples from the stockpile at load-out. The department will split each sample, test half for QV, and retain half.
- (4) The department will conduct QV tests in a separate laboratory and with separate equipment from the contractor's QC tests. The department will use the same methods specified for QC testing.
- (5) The department will assess QV results by comparing to the appropriate specification limits. If QV test results conform to the specification, the department will take no further action. If QV test results are nonconforming, add the QV to the QC test results as if it were an additional QC test.

### **B.8.3 Independent Assurance**

- (1) Independence assurance is unbiased testing the department performs to evaluate the department's QV and the contractor's QC sampling and testing including personnel qualifications, procedures, and equipment. The department will perform an IA review according to the department's independent assurance program. That review may include one or more of the following:
  1. Split sample testing.
  2. Proficiency sample testing.
  3. Witnessing sampling and testing.
  4. Test equipment calibration checks.
  5. Reviewing required worksheets and control charts.
  6. Requesting that testing personnel perform additional sampling and testing.
- (2) If the department identifies a deficiency, and after further investigation confirms it, correct that deficiency. If the contractor does not correct or fails to cooperate in resolving identified deficiencies, the engineer may suspend placement until action is taken. Resolve disputes as specified in B.9.

### **B.9 Dispute Resolution**

- (1) The engineer and contractor should make every effort to avoid conflict. If a dispute between some aspect of the contractor's and the engineer's testing program does occur, seek a solution mutually agreeable to the project personnel. The department and contractor may review the data, examine data reduction and analysis methods, evaluate sampling and testing procedures, and perform additional testing. Use ASTM E 178 to evaluate potential statistically outlying data.
- (2) Production test results, and results from other process control testing, may be considered when resolving a dispute.

- (3) If the project personnel cannot resolve a dispute, and the dispute affects payment or could result in incorporating non-conforming product, the department will use third party testing to resolve the dispute. The department's central office laboratory, or a mutually agreed on independent testing laboratory, will provide this testing. The engineer and contractor will abide by the results of the third party tests. The party in error will pay service charges incurred for testing by an independent laboratory. The department may use third party test results to evaluate the quality of questionable materials and determine the appropriate payment. The department may reject material or otherwise determine the final disposition of nonconforming material as specified in standard spec 106.5.

**C (Vacant)**

**D (Vacant)**

**E Payment**

- (1) Costs for all sampling, testing, and documentation required under this special provision are incidental to this work. If the contractor fails to perform the work required under this special provision, the department may reduce the contractor's pay. The department will administer pay reduction under the non-performance of QMP administrative item.
- (2) For material represented by a running average exceeding a control limit, the department will reduce pay by 10 percent of the contract price for the affected Base Aggregate bid items listed in subsection A. The department will administer pay reduction under the Nonconforming QMP Base Aggregate Gradation or Nonconforming QMP Base Aggregate Fracture Administrative items. The department will determine the quantity of nonconforming material as specified in B.7.2.

301-010 (20100709)

**16. QMP Ride; Incentive IRI Ride, Item 440.4410.S.**

**A Description**

- (1) This special provision describes profiling pavements with a non-contact profiler, locating areas of localized roughness, and determining the International Roughness Index (IRI) for each wheel path segment.
- (2) Profile the final riding surface of all mainline pavements. Include auxiliary lanes in Category I and II segments; crossroads with county, state or U.S. highway designations greater than 1500 feet in continuous length; bridges, bridge approaches; and railroad crossings. Exclude roundabouts and pavements within 150 feet of the points of curvature of roundabout intersections.
- (3) The engineer may direct straightedging under standard spec 415.3.10 for pavement excluded from localized roughness under C.5.2 (1); for bridges; and for roundabouts and pavements within 150 feet of the points of curvature of roundabout intersections. Other surfaces being tested under this provision are exempt from straightedging requirements.



## **B (Vacant)**

## **C Construction**

### **C.1 Quality Control Plan**

- (1) Submit a written quality control plan to the engineer at or before the pre-pave meeting. Ensure that the plan provides the following elements:
  1. An organizational chart with names, telephone numbers, current certifications and/or titles, and roles and responsibilities of all quality control personnel.
  2. The process by which quality control information and corrective action efforts will be disseminated to the appropriate persons. Include a list of recipients, the communication means that will be used, and action time frames.
  3. The methods and timing used for monitoring and/or testing ride quality throughout the paving process. Also indicate the approximate timing of acceptance testing in relation to the paving operations.
  4. The segment locations of each profile run used for acceptance testing.
  5. Traffic Control Plan

### **C.2 Personnel**

- (1) Have a profiler operator, certified under the department's highway technician certification program (HTCP), operate the equipment, collect the required data, and analyze the results using the methods taught in the HTCP profiling course. Ensure that an HTCP-certified profiler operator supervises data entry into the material records system (MRS).

### **C.3 Equipment**

- (1) Furnish a profile-measuring device capable of measuring IRI from the list of department-approved devices published on the department's web site:  
<http://roadwaystandards.dot.wi.gov/standards/qmp/index.htm>
- (2) Unless the engineer and contractor mutually agree otherwise, arrange to have a calibrated profiler available when paving the final riding surface.
- (3) Perform daily calibration verification of the profiler using test methods according to the manufacturer's recommendations. Notify the engineer before performing the calibration verification. If the engineer requests, arrange to have the engineer observe the calibration verification and operation. Maintain records of the calibration verification activities, and provide the records to the engineer upon request.

### **C.4 Testing**

#### **C.4.1 Run and Reduction Parameters**

- (1) Enter the equipment-specific department-approved filter settings and parameters given in the approved profilers list on the department's QMP ride web site.  
<http://roadwaystandards.dot.wi.gov/standards/qmp/profilers.pdf>

### C.4.2 Contractor Testing

- (1) Operate profilers within the manufacturer's recommended speed tolerances. Perform all profile runs in the direction of travel. Measure the longitudinal profile of each wheel track of each lane. The wheel tracks are 6.0 feet apart and centered in the traveled way of the lane.
- (2) Coordinate with the engineer to schedule profile runs for acceptance. The department may require testing to accommodate staged construction or if corrective action may be required.
- (3) Measure the profiles of each standard or partial segment. Define primary segments starting at a project terminus and running contiguously along the mainline to the other project terminus. Field-locate the beginning and ending points for each profile run. When applicable, align segment limits with the subplot limits used for testing under the QMP Concrete Pavement specification. Define segments one wheel path wide and distinguished by length as follows:
  1. Standard segments are 500 feet long.
  2. Partial segments are less than 500 feet long.
- (4) Treat partial segments as independent segments.

The department will categorize each standard or partial segment as follows:

<b>Segments with a Posted Speed Limit of 55 MPH or Greater</b>	
<b>Category</b>	<b>Description</b>
HMA I	Asphalt pavement with multiple opportunities to achieve a smooth ride. The following operations performed under this contract are considered as opportunities: a layer of HMA, a leveling or wedging layer of HMA, and diamond grinding or partial depth milling of the underlying pavement surface.
HMA II	Asphalt pavement with a single opportunity to achieve a smooth ride.
HMA III	Asphalt pavement segments containing any portion of a bridge, bridge approach, railroad crossing, or intersection. An intersection is defined as the area within the points of curvature of the intersection radii.
PCC II	Concrete pavement.
PCC III	Concrete pavement segments containing any portion of a bridge, bridge approach, railroad crossing, intersection or gap. An intersection is defined as the area within the points of curvature of the intersection radii.

<b>Segments with Any Portion Having a Posted Speed Limit Less Than 55 MPH</b>	
<b>Category</b>	<b>Description</b>
HMA IV	Asphalt pavement including intersections, bridges, approaches, and railroad crossings.
PCC IV	Concrete pavement including gaps, intersections, bridges, approaches, and railroad crossings.

### C.4.3 Verification Testing

- (1) The department may conduct verification testing (QV) to validate the quality of the product. A HTCP certified profiler operator will perform the QV testing. The department will provide the contractor with a listing of the names and telephone numbers of all verification personnel for the project.
- (2) The department will notify the contractor before testing so the contractor can observe the QV testing. Verification testing will be performed independent of the contractor's QC work using separate equipment from the contractor's QC tests. The department will provide test results to the contractor within 1 business day after the department completes the testing.
- (3) The engineer and contractor will jointly investigate any testing discrepancies. The investigation may include additional testing as well as review and observation of both the department's and contractor's testing procedures and equipment. Both parties will document all investigative work.
- (4) If the contractor does not respond to an engineer request to resolve a testing discrepancy, the engineer may suspend production until action is taken. Resolve disputes as specified in C.6.

### C.4.4 Documenting Profile Runs

- (1) Compute the IRI for each segment and analyze areas of localized roughness using the ProVAL software. Also, the contractor shall prepare the ProVAL Ride Quality Module Reports, showing the IRI for each segment and the areas of localized roughness exceeding an IRI of 200 in/mile. Use ride quality module report as follows:

	<u>Fixed Interval</u>	<u>Continuous (Localized Roughness)</u>
Base-length	500'	25'
Threshold	140"/Mile	200"/Mile

The ProVAL software is available for download at:

<http://www.roadprofile.com>.

- (2) As part of the profiler software outputs and ProVAL reports, document the areas of localized roughness. Field-locate the areas of localized roughness prior to the engineer's assessment for corrective actions. Document the reasons for areas excluded and submit to the engineer.
- (3) Within 5 business days after completing profiling of the pavement covered under this special provision, unless the engineer and contractor mutually agree to a different timeline, submit the electronic ProVAL project file containing the .ppf files for each profiler acceptance run data and Ride Quality Module Reports, in .pdf format using the department's Materials Reporting System (MRS) software available on the department's web site:

<http://www.atwoodsystems.com/mrs>

Notify the engineer when the Profiler Acceptance Run data and the Ride Quality Report have been submitted to the MRS system.

## **C.5 Corrective Actions**

### **C.5.1 General**

- (1) Analyze the data from the PROVAL reports and make corrective action recommendations to the department. The department will independently assess whether a repair will help or hurt the long-term pavement performance before deciding on corrective action. Correct the ride as the engineer directs in writing.

### **C.5.2 Corrective Actions for Localized Roughness**

- (1) Apply localized roughness requirements to all pavements, including HMA III, PCC III, HMA IV, and PCC IV; except localized roughness requirements will not be applied to pavements within 25 feet of the following surfaces if they are not constructed under this contract: bridges, bridge approaches, or railroad crossings. The department may direct the contractor to make corrections to the pavement within the 25-foot exclusionary zones.
- (2) The engineer will review each individual wheel track for areas of localized roughness. The engineer will assess areas of localized roughness within 5 business days of receiving notification that the reports were uploaded. The engineer will analyze the report documenting areas that exceed an IRI of 200 in/mile and do one of the following for each location:
  1. Direct the contractor to correct the area to minimize the effect on the ride.
  2. Leave the area of localized roughness in place with no pay reduction.
  3. Except for HMA IV and PCC IV segments, assess a pay reduction as follows for each location in each wheel path:

<b>Localized Roughness IRI (in/mile)</b>	<b>Pay Reduction<sup>[1]</sup> (dollars)</b>
> 200	(Length in Feet) x (IRI – 200)

<sup>[1]</sup> A maximum \$250 pay reduction may be assessed for locations of localized roughness that are less than or equal to 25 feet long. Locations longer than 25 feet may be assessed a maximum pay reduction of \$10 per foot.

- (3) The engineer will not direct corrective action or assess a pay reduction for an area of localized roughness without independent identification of that area as determined by physically riding the pavement. For corrections, use only techniques the engineer approves.
- (4) Re-profile corrected areas to verify that the IRI is less than 140 in/mile after correction. Submit a revised ProVAL ride quality module report to the reference documents section of the MRS for the corrected areas to validate the results.

### **C.5.3 Corrective Actions for Excessive IRI**

- (1) If an individual segment IRI exceeds 140 in/mile for HMA I, HMA II, and PCC II pavements after correction for localized roughness, the engineer may require the contractor to correct that segment. Correct the segment final surface as follows:

HMA I: Correct to an IRI of 60 in/mile using whichever of the following methods as approved by the engineer:  
Mill and replace the full lane width of the riding surface excluding the paved shoulder.  
Continuous diamond grinding or fine-tooth milling the full lane width, if required, of the riding surface including adjustment of the paved shoulders.

HMA II: Correct to an IRI of 85 in/mile using whichever of the following methods as approved by the engineer:  
Mill and replace the full lane width of the riding surface excluding the paved shoulder.  
Continuous diamond grinding or fine-tooth milling of the full lane width, if required, of the riding surface including adjustment of the paved shoulders

PCC II: Correct to an IRI of 85 in/mile using whichever of the following methods as approved by the engineer:  
Continuous diamond grinding of the full lane width, if required, of the riding surface including adjustment of the paved shoulders. Conform to sections C.1 through C.4 of Concrete Pavement Continuous Diamond Grinding Special provision contained elsewhere in the contract.  
Remove and replace the full lane width of the riding surface.

- (2) Re-profile corrected segments to verify that the final IRI meets the above correction limits and there are no areas of localized roughness. Enter a revised ProVAL ride quality module report for the corrected areas to the reference documents section of the MRS. Segments failing these criteria after correction are subject to the engineer's right to adjust pay for non-conforming work under standard spec 105.3.

### **C.6 Dispute Resolution**

- (1) The engineer and contractor should make every effort to avoid conflict. If a dispute between some aspect of the contractor's and the engineer's testing program does occur, seek a solution mutually agreeable to the project personnel. The department and contractor may review the data, examine data reduction and analysis methods, evaluate testing procedures, and perform additional testing.

- (2) If the project personnel cannot resolve a dispute and the dispute affects payment or could result in incorporating nonconforming pavement, the department will use third party testing to resolve the dispute. The department's Quality Assurance Unit, or a mutually agreed on independent testing company, will provide this testing. The engineer and contractor will abide by the results of the third party tests. The party in error will pay service charges incurred for testing by an independent tester. The department may use third party tests to evaluate the quality of questionable pavement and determine the appropriate payment.

## **D Measurement**

- (1) The department will measure Incentive IRI Ride by the dollar, adjusted as specified in E.2.

## **E Payment**

### **E.1 Payment for Profiling**

- (1) Costs for furnishing and operating the profiler, documenting profile results, and correcting the final pavement surface are incidental to the contract. The department will pay separately for engineer-directed corrective action performed within the 25-foot exclusionary zones under C.5.2 as extra work.

### **E.2 Pay Adjustment**

- (1) The department will pay incentive for ride under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
440.4410.S	Incentive IRI Ride	DOL

- (2) Incentive payment is not limited, either up or down, to the amount the schedule of items shows.
- (3) The department will administer disincentives for ride under the Disincentive IRI Ride administrative item.
- (4) The department will not assess disincentive on HMA III or PCC III segments. Incentive pay for HMA III and PCC III segments will be according to the requirements for the category of the adjoining segments.
- (5) The department will adjust pay for each segment based on the initial IRI for that segment. If corrective action is required, the department will base disincentives on the IRI after correction for pavement meeting the following conditions:

All Pavement:	The corrective work is performed in a contiguous, full lane width section 500 feet long, or a length as agreed with the engineer.
HMA Pavements:	The corrective work is a mill and inlay or full depth replacement and the inlay or replacement layer thickness conforms to standard spec 460.3.2.
Concrete Pavements:	The corrective work is a full depth replacement and conforms to standard spec 415.

- (6) The department will adjust pay for 500-foot long standard segments nominally one wheel path wide using equation “QMP 1.04” as follows:

<b>HMA I</b>	
<b>Initial IRI (inches/mile)</b>	<b>Pay Adjustment<sup>[1]</sup> (dollars per standard segment)</b>
< 30	250
≥ 30 to < 35	1750 – (50 x IRI)
≥ 35 to < 60	0
≥ 60 to < 75	1000 – (50/3 x IRI)
≥ 75	-250

<b>HMA II and PCC II</b>	
<b>Initial IRI (inches/mile)</b>	<b>Pay Adjustment<sup>[1][2]</sup> (dollars per standard segment)</b>
< 50	250
≥ 50 to < 55	2750 – (50 x IRI)
≥ 55 to < 85	0
≥ 85 to < 100	(4250/3) – (50/3 x IRI)
≥ 100	-250

<b>HMA IV and PCC IV</b>	
<b>Initial IRI (inches/mile)</b>	<b>Pay Adjustment<sup>[1][2]</sup> (dollars per standard segment)</b>
< 35	250
≥ 35 to < 45	1125-(25xIRI)
≥ 45	0

<sup>[1]</sup> The department will not assess a ride disincentive for HMA pavement placed in cold weather because of a department-caused delay as specified in 450.5(4) of the contract additional special provisions (ASP 6).

<sup>[2]</sup> If the engineer directs placing concrete pavement for department convenience, the department will not adjust pay for ride on pavement the department orders the contractor to place when the air temperature falls below 35 F.

- (7) The department will prorate the pay adjustment for partial segments based on their length.

## **17. QMP HMA Pavement Nuclear Density.**

### **A Description**

Replace standard spec 460.3.3.2 (1) and standard spec 460.3.3.2 (4) with the following:

- (1) This special provision describes density testing of in-place HMA pavement with the use of nuclear density gauges. Conform to standard spec 460 as modified in this special provision.
- (2) Provide and maintain a quality control program defined as all activities and documentation of the following:
  1. Selection of test sites.
  2. Testing.
  3. Necessary adjustments in the process.
  4. Process control inspection.
- (3) Chapter 8 of the department's construction and materials manual (CMM) provides additional detailed guidance for QMP work and describes required procedures. Obtain the CMM from the department's web site at:  
<http://roadwaystandards.dot.wi.gov/standards/cmm/index.htm>
- (4) The department's Materials Reporting System (MRS) software allows contractors to submit data to the department electronically, estimate pay adjustments, and print selected reports. Qualified personnel may obtain MRS software from the department's web site at:

<http://www.atwoodsystems.com/mrs>

## **B Materials**

### **B.1 Personnel**

- (1) Perform HMA pavement density (QC, QV) testing using a HTCP certified nuclear technician I, or a nuclear assistant certified technician (ACT-NUC) working under a certified technician.
- (2) If an ACT is performing sampling or testing, a certified technician must coordinate and take responsibility for the work an ACT performs. Have a certified technician ensure that all sampling and testing is performed correctly, analyze test results, and post resulting data. No more than one ACT can work under a single certified technician.

### **B.2 Testing**

- (1) Conform to ASTM D2950 and CMM 8.15 for density testing and gauge monitoring methods. Perform nuclear gauge measurements using gamma radiation in the backscatter position. Perform each test for 4 minutes of nuclear gauge count time.

### **B.3 Equipment**

#### **B.3.1 General**

- (1) Furnish nuclear gauges from the department's approved product list at  
<http://www.dot.wisconsin.gov/business/engrserv/approvedprod.htm>.
- (2) Have the gauge calibrated by the manufacturer or an approved calibration service within 12 months of its use on the project. Retain a copy of the manufacturer's calibration certificate with the gauge.



- (3) Prior to each construction season, and following any calibration of the gauge, the contractor must perform calibration verification for each gauge using the reference blocks located in the department's central office materials laboratory. To obtain information or schedule a time to perform calibration verification, contact the department's Radiation Safety Officer at:

Materials Management Section  
3502 Kinsman Blvd.  
Madison, Wisconsin 53704  
Telephone: (608) 243-5998

### **B.3.2 Correlation of Nuclear Gauges**

#### **B.3.2.1 Correlation of QC and QV Nuclear Gauges**

- (1) Select a representative section of the compacted pavement prior to or on the first day of paving for the correlation process. The section does not have to be the same mix design.
- (2) Correlate the 2 or more gauges used for density measurement (QC, QV). The QC and QV gauge operators will perform the correlation on 5 test sites jointly located. Record each density measurement of each test site for the QC, QV and back up gauges.
- (3) Calculate the average of the difference in density of the 5 test sites between the QC and QV gauges. Locate an additional 5 test sites if the average difference exceeds 1.0 lb/ft<sup>3</sup>. Measure and record the density on the 5 additional test sites for each gauge.
- (4) Calculate the average of the difference in density of the 10 test sites between the QC and QV gauges. Replace one or both gauges if the average difference of the 10 tests exceeds 1.0 lb/ft<sup>3</sup> and repeat correlation process from B.3.2.1 (2).
- (5) Furnish one of the QC gauges passing the allowable correlation tolerances to perform density testing on the project.

#### **B.3.2.2 Correlation Monitoring**

- (1) After performing the gauge correlation specified in B.3.2.1, establish a project reference site approved by the department. Clearly mark a flat surface of concrete or asphalt or other material that will not be disturbed during the duration of the project. Perform correlation monitoring of the QC, QV, and all back-up gauges at the project reference site.
- (2) Conduct an initial 10 density tests with each gauge on the project reference site and calculate the average value for each gauge to establish the gauge's reference value. Use the gauge's reference value as a control to monitor the calibration of the gauge for the duration of the project.

- (3) Check each gauge on the project reference site a minimum of one test per day if paving on the project. Calculate the difference between the gauge's daily test result and its reference value. Investigate if a daily test result is not within 1.5 lb/ft<sup>3</sup> of its reference value. Conduct 5 additional tests at the reference site once the cause of deviation is corrected. Calculate and record the average of the 5 additional tests. Remove the gauge from the project if the 5-test average is not within 1.5 lb/ft<sup>3</sup> of its reference value established in B.3.2.2(2).
- (4) Maintain the reference site test data for each gauge at an agreed location.

## **B.4 Quality Control Testing and Documentation**

### **B.4.1 Lot and Sublot Requirements**

#### **B.4.1.1 Mainline Traffic Lanes, Shoulders, and Appurtenances**

- (1) A lot consists of the tonnage placed each day for each layer and target density specified in standard spec 460.3.3.1. A lot may include partial sublots.
- (2) Divide the roadway into sublots. A sublot is 1500 lane feet for each layer and target density.
- (3) A sublot may include HMA placed on more than one day of paving. Test sublots at the pre-determined random locations regardless of when the HMA is placed. No additional testing is required for partial sublots at the beginning or end of a day's paving.
- (4) If a resulting partial quantity at the end of the project is less than 750 lane feet, include that partial quantity with the last full sublot of the lane. If a resulting partial quantity at the end of the project is 750 lane feet or more, create a separate sublot for that partial quantity.
- (5) Randomly select test locations for each sublot as specified in CMM 8.15 prior to paving and provide a copy to the engineer. Locate and mark QC density test sites when performing the tests. Perform density tests prior to opening the roadway to traffic.
- (6) Use Table 1 to determine the number of tests required at each station, depending on the width of the lane being tested. When more than one test is required at a station, offset the tests 10 feet longitudinally from one another to form a diagonal testing row across the lane.

<b>Lane Width</b>	<b>No. of Tests</b>	<b>Transverse Location</b>
5 ft or less	1	Random
Greater than 5 ft to 9 ft	2	Random within 2 equal widths
Greater than 9 ft	3	Random within 3 equal widths

**Table 1**

#### **B.4.1.2 Side Roads, Crossovers, Turn Lanes, Ramps, and Roundabouts**

- (1) A lot represents a combination of the total daily tonnage for each layer and target density.

- (2) Each side road, crossover, turn lane, ramp, and roundabout must contain at least one subplot for each layer.
- (3) If a side road, crossover, turn lane, or ramp is 1500 feet or longer, determine sublots and random test locations as specified in B.4.1.1.
- (4) If a side road, crossover, turn lane, or ramp is less than 1500 feet long, determine sublots using a maximum of 750 tons per subplot and perform the number of random tests as specified in Table 2.

<b>Side Roads, Turn Lanes, Crossovers, Ramps, Roundabouts: Sublot/Layer tonnage</b>	<b>Minimum Number of Tests Required</b>
25 to 100 tons	1
101 to 250 tons	3
251 to 500 tons	5
501 to 750 tons	7

**Table 2**

## **B.4.2 Pavement Density Determination**

### **B.4.2.1 Mainline Traffic Lanes and Appurtenances**

- (1) Calculate the average subplot densities using the individual test results in each subplot.
- (2) If all subplot averages are no more than one percent below the target density, calculate the daily lot density by averaging the results of each random QC test taken on that day's material.
- (3) If any subplot average is more than one percent below the target density, do not include the individual test results from that subplot when computing the lot average density and remove that subplot's tonnage from the daily quantity for incentive. The tonnage from any such subplot is subject to disincentive pay according to standard spec 460.5.2.2.

### **B.4.2.2 Mainline Shoulders**

#### **B.4.2.2.1 Width Greater Than 5 Feet**

- (1) Determine the pavement density as specified in B.4.2.1.

#### **B.4.2.2.2 Width of 5 Feet or Less**

- (1) If all subplot test results are no more than 3.0 percent below the minimum target density, calculate the daily lot density by averaging all individual test results for the day.
- (2) If a subplot test result is more than 3.0 percent below the target density, the engineer may require the unacceptable material to be removed and replaced with acceptable material or allow the nonconforming material to remain in place with a 50 percent pay reduction. Determine the limits of the unacceptable material according to B.4.3.

### **B.4.2.3 Side Roads, Crossovers, Turn Lanes, Ramps, and Roundabouts**

- (1) Determine the pavement density as specified in B.4.2.1.

#### **B.4.2.4 Documentation**

- (1) Document QC density test data as specified in CMM 8.15. Provide the engineer with the data for each lot within 24 hours of completing the QC testing for the lot.

#### **B.4.3 Corrective Action**

- (1) Notify the engineer immediately when an individual test is more than 3.0 percent below the specified minimum in standard spec 460.3.3.1. Investigate and determine the cause of the unacceptable test result.
- (2) The engineer may require unacceptable material specified in B.4.3(1) to be removed and replaced with acceptable material or allow the nonconforming material to remain in place with a 50 percent pay reduction. Determine limits of the unacceptable area by measuring density of the layer at 50-foot increments both ahead and behind the point of unacceptable density and at the same offset as the original test site. Continue testing at 50-foot increments until a point of acceptable density is found as specified in standard spec 460.5.2.2(1). Removal and replacement of material may be required if extended testing is in a previously accepted subplot. Testing in a previously accepted subplot will not be used to recalculate a new lot density.
- (3) Compute unacceptable pavement area using the product of the longitudinal limits of the unacceptable density and the full subplot width within the traffic lanes or shoulders.
- (4) Retesting and acceptance of replaced pavement will be according to standard spec 105.3.
- (5) Tests indicating density more than 3.0 percent below the specified minimum, and further tests taken to determine the limits of unacceptable area, are excluded from the computations of the subplot and lot densities.
- (6) If 2 consecutive subplot averages within the same paving pass and same target density are more than one percent below the specified target density, notify the engineer and take necessary corrective action. Document the locations of such sublots and the corrective action that was taken.

### **B.5 Department Testing**

#### **B.5.1 Verification Testing**

- (1) The department will have a HTCP certified technician, or ACT working under a certified technician, perform verification testing. The department will test randomly at locations independent of the contractor's QC work. The department will perform verification testing at a minimum frequency of 10 percent of the sublots and a minimum of one subplot per mix design. The sublots selected will be within the active work zone. The contractor will supply the necessary traffic control for the department's testing activities.

- (2) The QV tester will test each selected subplot using the same testing requirements and frequencies as the QC tester.
- (3) If the verification subplot average is not more than one percent below the specified minimum target density, use the QC tests for acceptance.
- (4) If the verification subplot average is more than one percent below the specified target density, compare the QC and QV subplot averages. If the QV subplot average is within  $1.0 \text{ lb/ft}^3$  of the QC subplot average, use the QC tests for acceptance.
- (5) If the first QV/QC subplot average comparison shows a difference of more than  $1.0 \text{ lb/ft}^3$  each tester will perform an additional set of tests within that subplot. Combine the additional tests with the original set of tests to compute a new subplot average for each tester. If the new QV and QC subplot averages compare to within  $1.0 \text{ lb/ft}^3$ , use the original QC tests for acceptance.
- (6) If the QV and QC subplot averages differ by more than  $1.0 \text{ lb/ft}^3$  after a second set of tests, resolve the difference with dispute resolution specified in B.6. The engineer will notify the contractor immediately when density deficiencies or testing precision exceeding the allowable differences are observed.

#### **B.5.2 Independent Assurance Testing**

- (1) Independent assurance is unbiased testing the department performs to evaluate the department's verification and the contractor's QC sampling and testing including personnel qualifications, procedures, and equipment. The department will perform the independent assurance review according to the department's independent assurance program.

#### **B.6 Dispute Resolution**

- (1) The testers may perform investigation in the work zone by analyzing the testing, calculation, and documentation procedures. The testers may perform gauge correlation according to B.3.2.1.
- (2) The testers may use correlation monitoring according to B.3.2.2 to determine if one of the gauges is out of tolerance. If a gauge is found to be out of tolerance with its reference value, remove the gauge from the project and use the other gauge's test results for acceptance.
- (3) If the testing discrepancy cannot be identified, the contractor may elect to accept the QV subplot density test results or retesting of the subplot in dispute within 48 hours of paving. Traffic control costs will be split between the department and the contractor.
- (4) If investigation finds that both gauges are in error, the contractor and engineer will reach a decision on resolution through mutual agreement.

## **B.7 Acceptance**

- (1) The department will not accept QMP HMA Pavement Nuclear Density if a non-correlated gauge is used for contractor QC tests.

## **C (Vacant)**

## **D (Vacant)**

## **E Payment**

### **E.1 QMP Testing**

- (1) Costs for all sampling, testing, and documentation required under this special provision are incidental to the work. If the contractor fails to perform the work required under this special provision, the department may reduce the contractor's pay. The department will administer pay reduction under the Non-performance of QMP administrative item.

### **E.2 Disincentive for HMA Pavement Density**

- (1) The department will administer density disincentives according to standard spec 460.5.2.2.

### **E.3 Incentive for HMA Pavement Density**

- (1) Delete standard spec 460.5.2.3.
- (2) If the lot density is greater than the minimum specified in standard spec table 460-3 and all individual air voids test results for that mixture are within +1.0 percent or -0.5 percent of the design target in standard spec table 460-2, the department will adjust pay for that lot as follows:

<b>Percent Lot Density Above Minimum</b>	<b>Pay Adjustment Per Ton</b>
From -0.4 to 1.0 inclusive	\$0
From 1.1 to 1.8 inclusive	\$0.40
More than 1.8	\$0.80

- (3) The department will adjust pay under the Incentive Density HMA Pavement bid item. Adjustment under this item is not limited, either up or down, to the bid amount shown on the schedule of items.
- (4) If a traffic lane meets the requirements for disincentive, the department will not pay incentive on the integrally paved shoulder.
- (5) Submit density results to the department electronically using the MRS software. The department will validate all contractor data before determining pay adjustments.

460-020 (20100709)

## **18. Reheating HMA Pavement Longitudinal Joints, Item 460.4110.S.**

### **A Description**

This special provision describes reheating the abutting edge of the previously compacted layer in the adjacent lane while paving mainline asphalt pavements.

### **B (Vacant)**

### **C Construction**

#### **C.1 Equipment**

Provide a self-contained heating unit that heats by convection only. Do not use forced air to enhance the flame. Provide a fireproof barrier between the flame and the heater's fuel source. The heater must produce a uniform distribution of heat within the heat box. Provide automatic controls to regulate the heater output and shutoff the heater when the paver stops or the heater control system loses power.

Mount the heater on the paver inside the paver's automatic leveling device.

#### **C.2 Reheating Joints**

Evenly reheat at least an 8 inch (200 mm) wide strip of the previously compacted layer in the adjacent lane as follows:

- Reheat the joint to within 60 degrees F (15 degrees C) of the mix temperature at the paver auger. Measure joint temperature immediately behind the heater.

The engineer may allow the required joint reheat temperatures to be cooler than specified to adjust for weather, wind, and other field conditions. Coordinate the heater output and paver speed to achieve the required joint reheat temperature without visible smoke emission.

### **D Measurement**

The department will measure Reheating HMA Pavement Longitudinal Joints by the linear foot, acceptably completed, as measured along each joint for each layer of asphalt placed.

### **E Payment**

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
460.4110.S	Reheating HMA Pavement Longitudinal Joints	LF

Payment is full compensation for furnishing all the work required under this bid item.  
460-015 (20140630)

## **19. Concrete Staining Multi-Color B-26-39, Item 517.1015.S.01.**

### **A Description**

Furnish and apply a multi-color concrete stain to the exposed concrete surfaces of the structure, as detailed in the plans and as hereinafter provided.

### **B Materials**

#### **B.1 Mortar**

Use mortar for sack rubbing the concrete surfaces as given in standard spec 502.3.7.5 or use one of the following products:

Preblended, Packaged Type II Cement:      Tri-Mix by TK Products  
                                                                                 Thoroseal Pearl Gray by Thoro Products

The mortar shall contain one of the following acrylic bonding admixtures mixed and applied in accordance to manufacturer's recommendations:

Acrylic Bonding Admixture:      TK-225 by TK Products  
                                                                                 Achro 60 by Thoro Products  
                                                                                 Achro Set by Master Builders

#### **B.2 Concrete Stain**

Use concrete stain manufactured for use on exterior concrete surfaces. Use the following products, or equal as approved by the department:

Tri-Sheen Concrete Surfacers, Smooth by TK Products  
Tri-Sheen Acrylic by TK Products  
TK-1450 Natural Look Urethane Anti-Graffiti Primers by TK Products  
Safe-Cure & Seal EPX by Chem Masters  
H&C Concrete Stain Solid Color Water Based by Sherwin-Williams

### **C Construction**

#### **C.1 General**

Furnish, prepare, apply, cure, and store all materials in accordance to the product manufacturer's specifications for the type and condition of application required.

Match or exceed the stain manufacturer's minimum recommended curing time of the concrete or 28 days, whichever is greater, prior to staining.

#### **C.2 Preparation of Concrete Surfaces**

Provide a sack rubbed finish in accordance to standard spec 502.3.7.5, using mortar as indicated above on concrete surfaces with open voids or honeycombing.

Following the sack rubbing, clean all concrete surfaces that are to be coated to ensure that the surface is free of all laitance, dirt, dust, grease, efflorescence, and any foreign material and that the surface will accept the coating material according to product requirements. As



a minimum, clean the surface using a 3000-psi water blast. Hold the nozzle of the water blaster approximately 6 inches from the concrete surface and move it continuously in a sweeping motion. Give special attention to smooth concrete surfaces to produce an acceptable surface texture. Correct any surface problems resulting from the surface preparation methods. Grit blasting of the concrete surface is not allowed.

### **C.3 Staining Concrete Surfaces**

Apply the concrete stain in accordance to the manufacturer's recommendations.

Apply the concrete stain when the temperature of the concrete surface is 45° F or higher, or as given by the manufacturer.

The color of the staining shall produce a multi-color effect that consists of multiple colors replicating varying natural stone coloration. Stain the joints between stones produced by the form liner to create the appearance of grouted joints.

Do not begin staining the structure until earthwork operations are completed to a point where this work can begin without receiving damage. Where this work is adjacent to exposed soil or pavement areas, provide temporary covering protection from overspray or splatter.

### **C.4 Test Areas**

Prior to applying stain to the structure, apply the stain to sample panels measuring a minimum of 48-inches x 48-inches and constructed to demonstrate workmanship in the use of the form liner specified on the structure if applicable. Match or exceed the stain manufacturer's minimum recommended curing time of the concrete or 28 days, whichever is greater, prior to staining. Submit color samples to the department prior to staining the sample panels. Prepare the concrete surfaces of the sample panels and apply stain using the same materials and in the same manner as proposed for the structure, including staining of the joints between stones produced by the form liner. Do not apply stain to the structure until the department approves the test panels.

### **C.5 Surfaces to be Coated.**

Apply concrete stain to the surfaces in accordance to the plan.

## **D Measurement**

The department will measure Concrete Staining Multi-Color (Structure) in area by the square foot of surface, acceptably prepared and stained.

## **E Payment**

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
517.1015.S.01	Concrete Staining Multi-Color B-26-39	SF

Payment is full compensation for furnishing and applying the coloring system; for preparing the concrete surface; and for constructing and staining the sample panels.  
517-115 (20140630)

## **20. Architectural Surface Treatment B-26-39, Item 517.1050.S.01.**

### **A Description**

Construct a concrete masonry architectural surface treatment on the exposed concrete surfaces of the structure, as detailed in the plans and as hereinafter provided.

### **B Materials**

Use form liners that attach easily to the forming system, and do not compress more than ¼-inch when poured at a rate of 10 vertical feet/hour.

Use a release agent that is compatible with the form liner and coloring materials.

Wall ties shall have set “break-backs” at a minimum of ¾-inches from the finished concrete surface.

### **C Construction**

#### **C.1 Equipment**

Equipment and tools necessary for performing all parts of the work shall be satisfactory as to design, capacity, and mechanical condition for the purposes intended. Repair, improve, replace, or supplement all equipment that is not maintained in full working order, or which is proven inadequate to obtain the results prescribed.

#### **C.2 Form Liner Preparation**

Clean the form liner prior to each pour and ensure that it is free of any build-up. Visually inspect each liner for blemishes or tears, and repair if necessary per manufacturer’s recommendations.

Apply form release per manufacturer’s recommendations.

#### **C.3 Form Liner Attachment**

Place adjacent liners less than ¼-inch from each other, attach liner securely to forms in accordance to the manufacturer’s recommendations, and coordinate wall ties with form liner and form manufacturer, e.g., diameter, size, and frequency.

#### **C.4 Surface Finishing**

Ensure that the textured surface is free of laitance; sandblasting is not permitted.

Grind or fill pouring blemishes.

### **D Measurement**

The department will measure Architectural Surface Treatment (Structure) in area by the square foot of architectural surface acceptably completed.

## **E Payment**

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
517.1050.S.01	Architectural Surface Treatment B-26-39	SF

Payment is full compensation for producing the proposed architectural surface treatment including: preparing the foundation; finishing and protecting the surface treatment; and for properly disposing of surplus material.

517-150 (20110615)

## **21. Removing Signs Type II.**

*Add the following to standard spec 638.3.4 (2):*

Return aluminum Type II signs to either one of the department's North Central Region Office Sign Shops located at 2841 Industrial Street, Wisconsin Rapids or 501 North Hanson Lake Road, Rhinelander. Contact the Signing Lead Worker at (715) 421-8006. (NCR 638.01-10152014)

## **22. Field Facilities.**

*Add the following to standard spec 642.2.1(3):*

Provide a water cooler to dispense the bottled drinking water.

*Add the following to standard spec 642.3:*

Set up the field office within seven days after notice from the engineer.

Provide a parking area large enough to park a minimum of six cars directly adjacent to the field office. The parking area and approach to the field office shall be well drained and consist of a crushed base aggregate or an existing paved surface and shall be ready for use within seven days after the field office is set up. (NCR 642.02-10152014)

## **23. Pavement Marking Epoxy.**

Apply Pavement Marking Same Day Epoxy 4-Inch no-passing zone and centerline permanent pavement markings in accordance to standard spec 646.3.1.3.

Apply Pavement Marking Epoxy 4-Inch no-passing zone and centerline permanent pavement markings to the upper layer of pavements within seven calendar days after installing the centerline rumble strips. (NCR 646.03-10152014)

## **24. Locating No-Passing Zones, Item 648.0100.**

For this project, the spotting sight distance in areas with a 55 mph posted speed limit is 0.21 miles (1108 feet).

648-005 (20060512)

## **25. Culvert Pipe Transitions, Item SPV.0060.01.**

### **A Description**

This special provision describes laying out transition limits, saw cutting and removing pavement as necessary, excavating, backfilling, and compacting in order to construct 10:1 cut transitions at culvert pipes.

### **B Materials**

Furnish fill material that is in accordance to the pertinent requirements of standard spec 207. Backfill with native material, unless native material is determined to be unsuitable in which case granular material shall be used.

### **C Construction**

Complete pavement removal, excavation and backfilling for Culvert Pipe Transitions in accordance to the standard specifications.

Layout the limits of the transition area as determined by contractor (see construction detail).

Complete saw cutting necessary for construction of Culvert Pipe Transitions in accordance to standard spec 690.

Cover each area disturbed by construction Culvert Pipe Transitions with base aggregate dense as shown on the construction detail upon completion of Culvert Pipe Transition work and asphaltic surface patch as shown on the Culvert Pipe Transition construction detail before 6:00 PM the Friday after base aggregate dense is placed. If base aggregate dense is placed on a Friday, cover with the asphaltic surface patch by the end of the workday.

Complete patching in accordance to standard spec 465.

Dispose of unused material as specified in standard spec 465.

### **D Measurement**

The department will measure Culvert Pipe Transitions as a unit per each pipe location, acceptably completed.

## **E Payment**

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0060.01	Culvert Pipe Transitions	Each

Payment is full compensation for laying out transition limits, sawing existing pavement and removing existing pavement as necessary; excavating, backfilling, and compacting native material; and for disposing of surplus or unsuitable excavated materials. Granular material, if required, will be paid for as Granular Backfill. Asphaltic patching will be measured and paid as Asphaltic Surface.

## **26. Reestablish Section Corner Monuments, Item SPV.0060.02.**

### **A Description**

This special provision describes reestablishing section corner monuments as shown in the plan details, as directed by the engineer and as hereinafter provided.

### **B Materials**

Provide one of the following survey monuments for each location: A Berntsen Steel Nail Marker, for placement in asphalt pavement; a Berntsen BP1 Brass Marker with anchoring plug for placement in concrete pavement; or a Berntsen Aluminum Break-Off Monument for placement in locations outside the pavement area.

### **C Construction**

#### **C.1 General**

All survey work required to reestablish the survey monument from the reference monuments shall be performed by, or under the direction of, a registered land surveyor. Provide an updated county specified tie sheet(s) to the County Surveyor and the engineer. Provide county coordinates for all ties and monuments shown on the tie sheet(s). Obtain an example of the specified tie sheet(s) from the corresponding County Surveyor.

#### **C.2 Berntsen Steel Nail Marker**

Locate the exact position for the monument on the asphalt pavement. Drive the Berntsen Steel Nail Marker into the pavement until the top of the Steel Nail Marker is countersunk below the surrounding finished asphalt pavement as shown on the plan details.

#### **C.3 Berntsen BP1 Brass Marker**

Drill a hole in the finished concrete pavement using a Berntsen "Survey Marker Countersink Drill Bit", Item # BPMDDL. Insert the ribbed plastic expansion plug into the drilled hole. Tap the brass marker stem into the expansion plug until the top of the brass marker is countersunk below the surrounding finished concrete pavement as shown on the plan details.

#### **C.4 Berntsen Aluminum Break-off Monument**

Install according to the pertinent provisions of standard spec 621.3 for Non-Driven Aluminum Monuments and the plan details.

#### **D Measurement**

The department will measure Reestablish Section Corner Monuments by each individual section corner monument, acceptably completed.

#### **E Payment**

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0060.02	Reestablish Section Corner Monuments	Each

Payment is full compensation for furnishing all excavation, backfilling, and drilling necessary to place section corner monuments; providing and placing survey monuments; furnishing a registered land surveyor and all survey work; preparing and delivering tie sheets.

(NCR 650.03-01272014)

### **27. Lane Shift, Item SPV.0060.03.**

#### **A Description**

Lane Shift will consist of constructing a temporary one-lane roadway to permit the installation of culvert pipes with fill greater than 4 feet.

#### **B Materials**

Furnish fill that is according to the pertinent requirements of standard spec 208. Furnish Base Aggregate Dense that is according to the pertinent requirements of standard spec 305. Furnish Asphaltic Surface Temporary that is according to the pertinent requirements of standard spec 465.

#### **C Construction**

Place fill on existing slopes in accordance to standard spec 208. Place Base Aggregate Dense in accordance to standard spec 305. Place Asphaltic Surface Temporary in accordance to standard spec 465. Remove fill, Base Aggregate Dense, and Asphaltic Surface Temporary in accordance to standard spec 205.

#### **D Measurement**

The department will measure Lane Shift as each individual unit, acceptably completed.

**E Payment**

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0060.03	Lane Shift	Each

Payment is full compensation for placing, removing and disposal of fill material, Base Aggregate Dense, and Asphaltic Surface Temporary.

Traffic control and landscaping items will be measured and paid separately.  
(NCR 208.02-10152014)





## **ADDITIONAL SPECIAL PROVISION 4**

### **Payment to First-Tier Subcontractors**

Within 10 calendar days of receiving a progress payment for work completed by a subcontractor, pay the subcontractor for that work. The prime contractor may withhold payment to a subcontractor if, within 10 calendar days of receipt of that progress payment, the prime contractor provides written notification to the subcontractor and the department documenting "just cause" for withholding payment.

The prime contractor may also withhold routine retainage from payments due subcontractors.

### **Payment to Lower-Tier Subcontractors**

Ensure that subcontracting agreements at all tiers provide prompt payment rights to lower-tier subcontractors that parallel those granted first-tier subcontractors in this provision.

### **Release of Routine Retainage**

After granting substantial completion the department may reduce the routine retainage withheld from the prime contractor to 75 percent of the original total amount retained.

When the Department sends the semi-final estimate the department may reduce the routine retainage withheld from the prime contractor to 10 percent of the original total amount retained.

Within 30 calendar days of receiving the semi-final estimate from the department, submit written certification that subcontractors at all tiers are paid in full for acceptably completed work and that no routine retainage is being withheld. The department will pay the prime contractor in full and reduce the routine retainage withheld from the prime contractor to zero when the department approves the final estimate.

This special provision does not limit the right of the department, prime contractor, or subcontractors at any tier to withhold payment for work not acceptably completed or work subject to an unresolved contract dispute.

**ADDITIONAL SPECIAL PROVISION 6****ASP 6 - Modifications to the standard specifications**

Make the following revisions to the standard specifications:

---

**450.3.2.1 General**

Replace the entire text with the following effective with the January 2015 letting:

- (1) Do not place asphaltic mixture when the air temperature approximately 3 feet above grade, in shade, and away from artificial heat sources is less than 36 F for upper layers or 32 F for lower layers unless the engineer allows in writing. The contractor should place HMA pavement for projects on or north of STH 29 between May 1 and October 15 inclusive and for projects south of STH 29 between April 15 and November 1 inclusive. Notify the engineer at least one business day before paving.
  - (2) Unless the contract specifies otherwise, conform to the following:
    - Keep the road open to all traffic during construction.
    - Prepare the existing foundation for treatment as specified in 211.
    - Incorporate loose roadbed aggregate as a part of preparing the foundation, in shoulder construction, or dispose of as the engineer approves.
  - (3) Place asphaltic mixture only on a prepared, firm, and compacted base, foundation layer, or existing pavement substantially surface-dry and free of loose and foreign material. Do not place over frozen subgrade or base, or where the roadbed is unstable.
- 

**450.5 Payment**

Replace the entire text with the following effective with the May 2015 letting:

- (1) All costs of furnishing, maintaining, and operating the truck scale or other weighing equipment and furnishing the weigh tickets are incidental to the contract.
  - (2) Nonconforming material allowed to remain in place is subject to price adjustment under 105.3.2.
  - (3) Full-depth sawing to remove integrally placed safety edge where not required is incidental to the contract.
  - (4) The contractor is responsible for the quality of HMA pavement placed in cold weather. If because of an excusable compensable delay under 108.10.3, the engineer directs the contractor to pave when the temperature is less than 36 F for the upper layer or less than 32 F for lower layers, the department:
    - Will relieve the contractor of responsibility for damage and defects the engineer attributes to cold weather paving.
    - Will not assess disincentives for density or ride.
- 

**455.3.2.1 General**

Replace the paragraphs one and two with the following effective with the January 2015 letting:

- (1) Apply tack coat only when the air temperature is 32 F or more unless the engineer approves otherwise in writing. Before applying tack coat ensure that the surface is dry and reasonably free of loose dirt, dust, or other foreign matter. Do not apply if weather or surface conditions are unfavorable or before impending rains.
- (2) Use tack material of the type and grade the contract specifies. The contractor may, with the engineer's approval, dilute tack material as allowed under 455.2.4. Provide calculations using the asphalt content as-received from the supplier and subsequent contractor dilutions to show that as-placed material has 50 percent or more residual asphalt content. Apply at 0.050 to 0.070 gallons per square yard, after dilution, unless the contract designates otherwise. The engineer may adjust the application rate based on surface conditions. Limit application each day to the area the contractor expects to pave during that day.

**460.2.2.3 Aggregate Gradation Master Range**

*Replace paragraph one with the following effective with the December 2014 letting:*

- (1) Ensure that the aggregate blend, including recycled material and mineral filler, conforms to the gradation requirements in table 460-1. The values listed are design limits; production values may exceed those limits.

**TABLE 460-1 AGGREGATE GRADATION MASTER RANGE AND VMA REQUIREMENTS**

SIEVE	PERCENTS PASSING DESIGNATED SIEVES						
	NOMINAL SIZE						
	37.5 mm	25.0 mm	19.0 mm	12.5 mm	9.5 mm	SMA 12.5 mm	SMA 9.5 mm
50.0-mm	100						
37.5-mm	90 – 100	100					
25.0-mm	90 max	90 - 100	100				
19.0-mm	—	90 max	90 - 100	100		100	
12.5-mm	—	—	90 max	90 - 100	100	90 - 97	100
9.5-mm	—	—	—	90 max	90 - 100	58 - 72	90 - 100
4.75-mm	—	—	—	—	90 max	25 - 35	35 - 45
2.36-mm	15 – 41	19 - 45	23 - 49	28 - 58	20 - 65	15 - 25	18 - 28
75-µm	0 – 6.0	1.0 - 7.0	2.0 - 8.0	2.0 - 10.0	2.0 - 10.0	8.0 - 12.0	10.0 - 14.0
% MINIMUM VMA	11.0	12.0	13.0	14.0 <sup>[1]</sup>	15.0 <sup>[2]</sup>	16.0	17.0

<sup>[1]</sup> 14.5 for E-0.3 and E-3 mixes.

<sup>[2]</sup> 15.5 for E-0.3 and E-3 mixes.

**460.3.4 Cold Weather Paving**

*Add a new subsection as follows effective with the May 2015 letting:*

**460.3.4 Cold Weather Paving****460.3.4.1 Cold Weather Paving Plan**

- (1) Submit a written cold weather paving plan to the engineer at the preconstruction meeting. In that plan outline material, operational, and equipment changes for paving when the air temperature approximately 3 feet above grade, in shade, and away from artificial heat sources is less than 40 F. Include the following:
- Use a department-accepted HMA mix design that incorporates a warm mix additive from the department's approved products list. Do not use a foaming process that introduces water into the mix.
  - Use additional rollers.

- (2) Engineer written acceptance is required for the cold weather paving plan. Engineer acceptance of the plan does not relieve the contractor of responsibility for pavement performance except as specified in 450.5(4).

**460.3.4.2 Cold Weather Paving Operations**

- (1) Do not place asphaltic mixture when the air temperature approximately 3 feet above grade, in shade, and away from artificial heat sources is less than 40 F unless a valid engineer-accepted cold weather paving plan is in effect.
- (2) If the national weather service forecast for the construction area predicts ambient air temperature less than 40 F at the projected time of paving within the next 24 hours, confirm or submit revisions to a previously engineer-accepted cold weather paving plan for engineer validation. Upon validation of the plan, the engineer will allow paving for the next day. Once in effect, pave conforming to the engineer-accepted cold weather paving plan for the balance of that work day or shift regardless of the temperature at the time of paving.

**460.4 Measurement**

Add paragraph two as follows effective with the January 2015 letting:

- (2) The department will measure HMA Cold Weather Paving by the ton of HMA mixture for pavement placed conforming to an engineer-accepted cold weather paving plan.

**460.5.1 General**

Revise paragraph one as follows effective with the January 2015 letting:

- (1) The department will pay for measured quantities at the contract unit price under the following bid items:

<u>ITEM NUMBER</u>	<u>DESCRIPTION</u>	<u>UNIT</u>
460.1100	HMA Pavement Type E-0.3	TON
460.1101	HMA Pavement Type E-1	TON
460.1103	HMA Pavement Type E-3	TON
460.1110	HMA Pavement Type E-10	TON
460.1130	HMA Pavement Type E-30	TON
460.1132	HMA Pavement Type E-30X	TON
460.1700	HMA Pavement Type SMA	TON
460.2000	Incentive Density HMA Pavement	DOL
460.4000	HMA Cold Weather Paving	TON

**460.5.2.2 Disincentive for HMA Pavement Density**

Revise paragraph two as follows effective with the January 2015 letting:

- (2) The department will not assess density disincentives for pavement placed in cold weather because of a department-caused delay as specified in 450.5(4).

**460.5.2.4 Cold Weather Paving**

Add a new subsection as follows effective with the May 2015 letting:

**460.5.2.4 Cold Weather Paving**

- (1) Payment for HMA Cold Weather Paving is full compensation for additional materials and equipment specified for cold weather paving under 460.3.4 including costs for preparing, administering, and following the contractor's cold weather paving plan. The department will not pay for HMA Cold Weather Paving for HMA placed on days when the department is assessing liquidated damages.
- (2) If HMA pavement is placed under 460.3.4 and the HMA Cold Weather Paving bid item is not in the contract, the department will pay for the additional costs specified in 460.5.2.4(1) as extra work. The department will pay separately for HMA pavement under the appropriate HMA Pavement bid items.

**465.2 Materials**

Replace paragraph two with the following effective with the December 2014 letting:

- (2) Under the other 465 bid items, the contractor need not submit a mix design. Furnish aggregates mixed with a type AC asphaltic material, except under the Asphaltic Curb bid item furnish PG58-28 asphaltic material. Use coarse and fine mineral aggregates uniformly coated and mixed with the asphaltic material in an engineer-approved mixing plant. The contractor may include reclaimed asphaltic pavement materials in the mixture.

**506.3.2 Shop Drawings**

Replace the entire text with the following effective with the May 2015 letting:

- (1) Ensure that shop drawings conform to the contract plans and provide additional details, dimensions, computations, and other information necessary for completely fabricating and erecting the work. Include project and structure numbers on each shop drawing sheet.
- (2) Check shop drawings and submit electronically to the department for review before beginning fabrication. For primary fabrication items, also certify that shop drawings conform to quality control standards by submitting department form DT2333. Department review does not relieve the contractor from responsibility for errors or omissions on shop drawings.
- (3) Shop drawings are part of the contract. The department must approve differences between shop drawings and contract plans. The contractor bears the costs of department-approved substitutions. Do not deviate from or revise drawings without notifying the department and resubmitting revised drawings.
- (4) Ensure that the fabricator delivers 3 sets of shop drawings for railroad structures to the railroad company upon contract completion.

---

**Bid Items Added**


---

Add the following new bid item effective with the January 2015 letting:

<u>ITEM NUMBER</u>	<u>DESCRIPTION</u>	<u>UNIT</u>
460.4000	HMA Cold Weather Paving	TON

---

**Errata**


---

Make the following corrections to the standard specifications:

---

**501.3.2.4.4 Water Reducer**

Correct errata by deleting the reference to footnote 6 for grade D concrete.

- (1) Add a water reducing admixture conforming to 501.2.3. Determine the specific type and rate of use based on the atmospheric conditions, the desired properties of the finished concrete and the manufacturer's recommended rate of use. The actual rate of use shall at least equal the manufacturer's recommended rate, and both the type and rate used require the engineer's approval before use.
- 

**506.5 Payment**

Correct errata by changing the reference to 506.3.22.

- (9) The department will limit costs for inspections conducted under 506.3.22 to \$0.05 per pound of material and deduct costs in excess of that amount from payment due the contractor. The department will determine costs for in-house inspections based on hourly rates for department staff plus overhead and use invoiced costs for contracted-out inspections. The department will administer deductions for the contractor's share of the total inspection cost under the Excess Costs For Fabrication Shop Inspection administrative item.

**ADDITIONAL SPECIAL PROVISION 7**

- A. Reporting 1<sup>st</sup> Tier and DBE Payments During Construction
1. Comply with reporting requirements specified in the department's Civil Rights Compliance, Contractor's User Manual, Sublets and Payments.
  2. Report payments to all DBE firms within 10 calendar days of receipt of a progress payment by the department or a contractor for work performed, materials furnished, or materials stockpiled by a DBE firm. Report the payment as specified in A(1) for all work satisfactorily performed and for all materials furnished or stockpiled.
  3. Report payments to all first tier subcontractor relationships within 10 calendar days of receipt of a progress payment by the department for work performed. Report the payment as specified in A(1) for all work satisfactorily performed.
  4. All tiers shall report payments as necessary to comply with the DBE payment requirement as specified in A(2).
  5. Require all first tier relationships, DBE firms and all other tier relationships necessary to comply with the DBE payment requirement in receipt of a progress payment by contractor to acknowledge receipt of payment as specified in A(1), (2), (3) and (4).
  6. All agreements made by a contractor shall include the provisions in A(1), (2), (3), (4) and (5), and shall be binding on all first tier subcontractor relationships and all contractors and subcontractors utilizing DBE firms on the project.
- B. Costs for conforming to this special provision are incidental to the contract.



## **ADDITIONAL SPECIAL PROVISION 9 Electronic Certified Payroll Submittal**

(1) Use the department's Civil Rights Compliance System (CRCS) to submit certified payrolls electronically. Details are available online through the department's highway construction contractor information (HCCI) site on the Labor, Wages, and EEO Information page at:

Use the following link prior to June 19, 2015:

<http://www.dot.wi.gov/business/civilrights/laborwages/index.htm>

Use the following link beginning June 19, 2015:

<http://wisconsin.gov/Pages/doing-bus/civil-rights/labornwage/default.aspx>

(2) Ensure that all tiers of subcontractors, as well as all trucking firms, submit their weekly certified payrolls electronically through CRCS. These payrolls are due within seven calendar days following the close of the payroll period. Every firm providing physical labor towards completing the project is a subcontractor under this special provision.

(3) Upon receipt of contract execution, promptly make all affected firms aware of the requirements under this special provision and arrange for them to receive CRCS training as they are about to begin payrolls. The department will provide training either in a classroom setting at one of our regional offices or by telephone. Contact Tess Mulrooney at 608-267-4489 to schedule the training.

(4) The department will reject all paper submittals of forms DT-1816 and DT-1929 for information required under this special provision. All costs for conforming to this special provision are incidental to the contract.

(5) Firms wishing to export payroll data from their computer system into CRCS should have their payroll coordinator send several sample electronic files to Tess two months before a payroll needs to be submitted. Not every contractor's payroll system is capable of producing export files. For details, see pages 17-22 of the CRCS System Background Information manual available online on the Labor, Wages, and EEO Information page at:

Use the following link prior to June 19, 2015:

<http://www.dot.wi.gov/business/civilrights/laborwages/docs/crc-payroll-manual.pdf>

Use the following link beginning June 19, 2015:

<http://wisconsin.gov/Documents/doing-bus/civil-rights/labornwage/crcs-payroll-manual.pdf>



## **Effective June 2015 letting**

### **BUY AMERICA PROVISION**

All steel and iron materials permanently incorporated in this project shall be domestic products and all manufacturing and coating processes for these materials from smelting forward in the manufacturing process must have occurred within the United States. Coating includes epoxy coating, galvanizing, painting and any other coating that protects or enhances the value of a material subject to the requirements of Buy America. The exemption of this requirement is the minimal use of foreign materials if the total cost of such material permanently incorporated in the product does not exceed one-tenth of one percent (1/10 of 1%) of the total contract cost or \$2,500.00, whichever is greater. For purposes of this paragraph, the cost is that shown to be the value of the subject products as they are delivered to the project. The contractor shall take actions and provide documentation conforming to CMM 2-28.5 to ensure compliance with this "Buy America" provision.

Use the following link prior to June 19, 2015:

<http://roadwaystandards.dot.wi.gov/standards/cmm/cm-02-28.pdf#cm2-28.5>

Use the following link beginning June 19, 2015:

<http://wisconsindot.gov/rdwy/cmm/cm-02-28.pdf>

Upon completion of the project certify to the engineer, in writing using department form WS4567, that all steel, iron, and coating processes for steel or iron incorporated into the contract work conform to these "Buy America" provisions. Attach a list of exemptions and their associated costs to the certification form. Department form WS4567 is available at:

Use the following link prior to June 19, 2015:

<http://roadwaystandards.dot.wi.gov/standards/forms/ws4567.doc>

Use the following link beginning June 19, 2015:

<http://wisconsindot.gov/rdwy/worksheets/ws4567.doc>

**Effective with September 2004 Letting**

**WISCONSIN DEPARTMENT OF TRANSPORTATION  
DIVISION OF HIGHWAYS AND TRANSPORTATION FACILITIES**

**SUPPLEMENTAL REQUIRED CONTRACT PROVISIONS**

- I. Wage Rates, Hours of labor and payment of Wages
- II. Payroll Requirements
- III. Postings at the Site of the Work
- IV. Affidavits
- V. Wage Rate Redistribution
- VI. Additional Classifications

**I. WAGE RATES, HOURS OF LABOR AND PAYMENT OF WAGES**

The schedule of "Minimum Wage Rates" attached hereto and made a part hereof furnishes the prevailing wage rates that have been determined pursuant to Section 103.50 of the Wisconsin Statutes. These wage rates are the minimum required to be paid to the various laborers, workers, mechanics and truck drivers employed by contractors and subcontractors on the construction work embraced by the contract and subject to prevailing hours and wages under Section 103.50, Stats. If necessary to employ laborers, workers, mechanics or truck drivers whose classification is not listed on the schedule, they shall be paid at rates conformable to those listed for similar classifications. Apprentices shall be paid at rates not less than those prescribed in their state indenture contracts.

While the wage rates shown are the minimum rates required by the contract to be paid during its life, this is not a representation that labor can be obtained at these rates. It is the responsibility of bidders to inform themselves as to the local labor conditions and prospective changes or adjustments of wage rates. No increase in the contract price shall be allowed or authorized on account of the payment of wage rates in excess of those listed herein.

Pursuant to Section 103.50 of the Wisconsin Statutes, the prevailing hours of labor have been determined to be up to 10 hours per day and 40 hours per calendar week Monday through Friday. If any laborer, worker, mechanic or truck driver is permitted or required to work more than the prevailing number of hours per day or per calendar week on this contract, they shall be paid for all hours in excess of the prevailing hours at a rate of at least one and one-half (1 1/2) times their hourly rate of pay. All work on Saturday, Sunday and the following holidays is to be paid at time and a half: (1) January 1, (2) the last Monday in May, (3) July 4, (4) the first Monday in September, (5) the fourth Thursday in November, (6) December 25, (7) the day before if January 1, July 4 or December 25 falls on a Saturday and (8) the day following if January 1, July 4 or December 25 falls on a Sunday.

All laborers, workers, mechanics and truck drivers shall be paid unconditionally not less often than once a week. Persons who own and operate their own trucks must receive the prevailing truck driver rate for the applicable type of truck (i.e. 2 axle, 3 or more axle, articulated, eculid or dumptor) he or she operates, plus an agreed upon amount for the use of his or her truck. Every owner-operator MUST be paid separately for their driving and for the use of their truck.

For those projects subject to the requirements of the Davis-Bacon Act, the Secretary of Labor will also have determined "Minimum Wage Rates" for work to be performed under the contract. These rates are, for all or most of the labor, worker, mechanic or truck driver classifications, identical to those established under Section 103.50 of the Wisconsin Statutes. In the event the rates are not identical, the higher of the two rates will govern.

## **II. PAYROLL REQUIREMENTS**

All contractors and subcontractors must submit weekly Certified Payrolls and Compliance Statement verifying that all laborers, workers, mechanics and truck drivers working on the project have been paid the prevailing wage rates for all work performed under the contract required by Section 103.50 of the Wisconsin Statutes.

## **III. POSTINGS AT THE SITE OF THE WORK**

In addition to the required postings furnished by the Department, the contractor shall post the following in at least one conspicuous place at the site of work:

- a. "NOTICE TO EMPLOYEES," which provides information required to be posted by the provisions of Section 103.50 of the Wisconsin Statutes.
- b. A copy of the State of Wisconsin Minimum Wages Rates. (Four pages.)
- c. A copy of the contractor's Equal Employment Opportunity Policy.
- d. On any project involving federal aid, in addition to the furnished postings, the contractor shall post a copy of the "Davis-Bacon Act, Minimum Wage Rates". (Three pages.)

## **IV. WAGE RATE REDISTRIBUTION**

The amount specified as the hourly basic rate of pay and the amount(s) specified as the fringe benefit contribution(s), for all classes of laborers, workers, mechanics or truck drivers may be redistributed, when necessary, to conform to those specified in any applicable collective bargaining agreement, provided that both parties to such agreement

request and receive the approval for any such redistribution from both the Department of Transportation and the Department of Workforce Development prior to the implementation of such redistribution.

## **V. ADDITIONAL CLASSIFICATIONS**

Any unlisted laborer or mechanic classification that is needed to perform work on this project, and is not included within the scope of any of the classifications listed in the application prevailing wage rate determination, may be added after award only if all of the following criteria have been met:

1. The affected employer(s) must make a written request to WisDOT Central Office to utilize the unlisted classification on this project.
2. The request must indicate the scope of the work to be performed by the unlisted classification and must indicate the proposed wage/fringe benefit package that the unlisted classification is to receive.
3. The work to be performed by the unlisted classification must not be performed by a classification that is included in the applicable prevailing wage rate determination.
4. The unlisted classification must be commonly employed in the area where the project is located.
5. The proposed wage/fringe benefit package must bear a reasonable relationship to those set forth in the applicable prevailing wage rate determination.
6. The request should be made prior to the actual performance of the work by the unlisted classification.
7. DWD must approve the use of the unlisted classification and the proposed wage/fringe benefit package. USDOL also must approve the use of the unlisted classification and the proposed wage/fringe benefit package on federal aid projects.
8. WisDOT and DWD may amend the proposed wage/fringe benefit package, as deemed necessary, and may set forth specific employment ratios and scope of work requirements in the approval document.

The approved wage/fringe benefit package shall be paid to all laborers, workers, mechanics or truck drivers performing work within the scope of that performed by the unlisted classification, from the first day on which such work is performed. In the event that work is performed by the unlisted classification prior to approval, the wage/fringe benefit package to be paid for such work must be in conformance with the wage/fringe

benefit package approved for such work. Under this arrangement a retroactive adjustment in wages and/or fringe benefits may be required to be made to the affected laborers, workers, mechanics or truck drivers by the affected employer(s).

**ANNUAL PREVAILING WAGE RATE DETERMINATION  
FOR ALL STATE HIGHWAY PROJECTS  
IRON COUNTY**

Compiled by the State of Wisconsin - Department of Workforce Development  
for the Department of Transportation  
Pursuant to s. 103.50, Stats.  
Issued on May 1, 2015

**CLASSIFICATION:** Contractors are required to call the Department of Workforce Development if there are any questions regarding the proper trade or classification to be used for any worker on a public works project.

**OVERTIME:** Time and one-half must be paid for all hours worked over 10 hours per day and 40 hours per calendar week and for all hours worked on Saturday, Sunday and the following six (6) holidays: January 1; the last Monday in May; July 4; the 1st Monday in September; the 4th Thursday in November; December 25; the day before if January 1, July 4 or December 25 falls on a Saturday; the day following if January 1, July 4 or December 25 falls on a Sunday.

**FUTURE INCREASE:** If indicated for a specific trade or occupation, the full amount of such increase MUST be added to the "TOTAL" indicated for such trade or occupation on the date(s) such increase(s) becomes effective.

**PREMIUM PAY:** If indicated for a specific trade or occupation, the full amount of such pay MUST be added to the "HOURLY BASIC RATE OF PAY" indicated for such trade or occupation, whenever such pay is applicable.

**SUBJOURNEY:** Wage rates may be available for some of the classifications indicated below. Any employer that desires to use any subjourney classification on a project MUST request the applicable wage rate from the Department of Workforce Development PRIOR to the date such classification is used on such project. Form ERD-10880 is available for this purpose and can be obtained by writing to the Department of Workforce Development, Equal Rights Division, P.O. Box 8928, Madison, WI 53708.

<u>TRADE OR OCCUPATION</u>	<u>HOURLY BASIC RATE OF PAY</u>	<u>HOURLY FRINGE BENEFITS</u>	<u>TOTAL</u>
	\$	\$	\$
Bricklayer, Blocklayer or Stonemason	35.94	16.91	52.85
Carpenter	32.72	16.00	48.72
Future Increase(s): Add \$1.42/hr on 6/1/2015; Add \$1.42/hr on 6/1/2016. Premium Pay: DOT PREMIUM: Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day.			
Cement Finisher	32.75	19.21	51.96
Future Increase(s): Add \$1.87 on 6/1/15; Add \$1.75 on 6/1/16. Premium Pay: DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.40/hr when the Wisconsin Department of Transportation or responsible governing agency requires that work be performed at night under artificial illumination with traffic control and the work is completed after sunset and before sunrise.			
Electrician	29.20	17.42	46.62
Future Increase(s): Add \$.75/hr on 6/1/2015. Premium Pay: DOT PREMIUM: Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day.			
Fence Erector	23.73	19.09	42.82
Ironworker	28.72	29.36	58.08
Line Constructor (Electrical)	39.50	17.73	57.23
Painter	26.65	16.09	42.74
Pavement Marking Operator	26.52	20.15	46.67
Piledriver	30.11	26.51	56.62
Future Increase(s): Add \$1.50/hr on 6/1/2015; Add \$1.60/hr on 6/1/2016. Premium Pay: Add \$.65/hr for Piledriver Loftsman; Add \$.75/hr for Sheet Piling Loftsman. DOT PREMIUM: Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day.			
Roofer or Waterproofer	21.20	6.44	27.64

<b>TRADE OR OCCUPATION</b>	<b>HOURLY BASIC RATE OF PAY</b>	<b>HOURLY FRINGE BENEFITS</b>	<b>TOTAL</b>
	<b>\$</b>	<b>\$</b>	<b>\$</b>
Teledata Technician or Installer	22.25	12.24	34.49
Tuckpointer, Caulker or Cleaner	33.76	17.82	51.58
Underwater Diver (Except on Great Lakes)	35.40	15.90	51.30
Heavy Equipment Operator - ELECTRICAL LINE CONSTRUCTION ONLY	35.55	15.57	51.12
Light Equipment Operator -ELECTRICAL LINE CONSTRUCTION ONLY	31.60	14.98	46.58
Heavy Truck Driver - ELECTRICAL LINE CONSTRUCTION ONLY	27.65	13.44	41.09
Light Truck Driver - ELECTRICAL LINE CONSTRUCTION ONLY	25.68	12.83	38.51
Groundman - ELECTRICAL LINE CONSTRUCTION ONLY	21.75	11.63	33.38

**TRUCK DRIVERS**

Single Axle or Two Axle	25.18	18.31	43.49
Future Increase(s): Add \$1.15/hr on 6/1/2015. Premium Pay: DOT PREMIUM: Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day.			
Three or More Axle	24.50	17.79	42.29
Articulated, Euclid, Dumptr, Off Road Material Hauler	25.28	18.31	43.59
Future Increase(s): Add \$1.15/hr on 6/1/2015. Premium Pay: DOT PREMIUM: Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day.			
Pavement Marking Vehicle	23.16	20.01	43.17
Shadow or Pilot Vehicle	24.37	17.77	42.14
Truck Mechanic	24.50	17.79	42.29

**LABORERS**

General Laborer	30.13	15.14	45.27
Future Increase(s): Add \$1.05/hr eff. 06/01/2015; Add \$1.00/hr eff. 06/01/2016; Add \$1.00/hr eff. 06/01/2017 Premium Pay: Add \$.10/hr for topman, air tool operator, vibrator or tamper operator (mechanical hand operated), chain saw operator and demolition burning torch laborer; Add \$.15/hr for bituminous worker (raker and luteman), formsetter (curb, sidewalk and pavement) and strike off man; Add \$.20/hr for blaster and powderman; Add \$.25/hr for bottomman; Add \$.35/hr for line and grade specialist; Add \$.45/hr for pipelayer. DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.25/hr for work on projects involving temporary traffic control setup, for lane and shoulder closures, when work under artificial illumination conditions is necessary as required by the project provisions (including prep time prior to and/or cleanup after such time period).			
Asbestos Abatement Worker	24.13	14.61	38.74
Landscaper	30.13	15.14	45.27
Future Increase(s): Add \$1.05/hr eff. 06/01/2015; Add \$1.00/hr eff. 06/01/2016; Add \$1.00/hr eff. 06/01/2017 Premium Pay: DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.25/hr for work on projects involving temporary traffic control setup, for lane and shoulder closures, when work under artificial illumination conditions is necessary as required by the project provisions (including prep time prior to and/or cleanup after such time period).			
Flagperson or Traffic Control Person	26.76	15.14	41.90
Future Increase(s): Add \$1.05/hr eff. 06/01/2015; Add \$1.00/hr eff. 06/01/2016; Add \$1.00/hr eff. 06/01/2017 Premium Pay: DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.25/hr when the Wisconsin			

<b>TRADE OR OCCUPATION</b>	<b>HOURLY BASIC RATE OF PAY</b>	<b>HOURLY FRINGE BENEFITS</b>	<b>TOTAL</b>
	<b>\$</b>	<b>\$</b>	<b>\$</b>
Department of Transportation or responsible governing agency requires that work be performed at night under artificial illumination with traffic control and the work is completed after sunset and before sunrise.			
Fiber Optic Laborer (Outside, Other Than Concrete Encased)	18.33	13.65	31.98
Railroad Track Laborer	17.00	2.96	19.96

### HEAVY EQUIPMENT OPERATORS

Crane, Tower Crane, Pedestal Tower or Derrick, With Boom, Leads &/or Jib Lengths Measuring 176 Ft or Over; Crane, Tower Crane, Pedestal Tower or Derrick, With or Without Attachments, With a Lifting Capacity of Over 100 Tons, Self-Erecting Tower Crane With a Lifting Capacity Of Over 4,000 Lbs., Crane With Boom Dollies; Traveling Crane (Bridge Type).	37.72	21.15	58.87
Future Increase(s): Add \$1.25/hr on 6/1/2015; Add \$1.30/hr on 6/1/2016; Add \$1.25/hr on 6/1/2017. Premium Pay: DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.50/hr night work premium. See DOT'S website for details about the applicability of this night work premium at: <a href="http://www.dot.wi.gov/business/civilrights/laborwages/pwc.htm">http://www.dot.wi.gov/business/civilrights/laborwages/pwc.htm</a> .			
Backhoe (Track Type) Having a Mfr.'s Rated Capacity of 130,000 Lbs. or Over; Caisson Rig; Crane, Tower Crane, Portable Tower, Pedestal Tower or Derrick, With Boom, Leads &/or Jib Lengths Measuring 175 Ft or Under; Crane, Tower Crane, Portable Tower, Pedestal Tower or Derrick, With or Without Attachments, With a Lifting Capacity of 100 Tons or Under, Self-Erecting Tower Crane With A Lifting Capacity Of 4,000 Lbs., & Under; Dredge (NOT Performing Work on the Great Lakes); Licensed Boat Pilot (NOT Performing Work on the Great Lakes); Pile Driver.	37.22	21.15	58.37
Future Increase(s): Add \$1.25/hr on 6/1/2015; Add \$1.30/hr on 6/1/2016; Add \$1.25/hr on 6/1/2017. Premium Pay: DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.50/hr night work premium. See DOT'S website for details about the applicability of this night work premium at: <a href="http://www.dot.wi.gov/business/civilrights/laborwages/pwc.htm">http://www.dot.wi.gov/business/civilrights/laborwages/pwc.htm</a> .			
Air Track, Rotary or Percussion Drilling Machine &/or Hammers, Blaster; Asphalt Heater, Planer & Scarifier; Asphalt Milling Machine; Asphalt Screed; Automatic Subgrader (Concrete); Backhoe (Track Type) Having a Mfr.'s Rated Capacity of Under 130,000 Lbs., Backhoe (Mini, 15,000 Lbs. & Under); Bituminous (Asphalt) Plant & Paver, Screed; Boatmen (NOT Performing Work on the Great Lakes); Boring Machine (Directional, Horizontal or Vertical); Bridge (Bidwell) Paver; Bulldozer or Endloader; Concrete Batch Plant, Batch Hopper; Concrete Breaker (Large, Auto, Vibratory/Sonic, Manual or Remote); Concrete Bump Cutter, Grinder, Planing or Grooving Machine; Concrete Conveyor System; Concrete Laser/Screed; Concrete Paver (Slipform); Concrete Pump, Concrete Conveyor (Rotec or Bidwell Type); Concrete Slipform Placer Curb & Gutter Machine; Concrete Spreader & Distributor; Crane (Carry Deck, Mini) or Truck Mounted Hydraulic Crane (10 Tons or Under); Crane With a Lifting Capacity of 25 Tons or Under; Forestry Equipment, Timbco, Tree Shear, Tub Grinder, Processor; Gradall (Cruz-Aire Type); Grader or Motor Patrol; Grout Pump; Hydro-Blaster (10,000 PSI or Over); Loading Machine (Conveyor); Material or Stack Hoist; Mechanic or Welder; Milling Machine; Post Hole Digger or Driver; Roller (Over 5 Ton); Scraper (Self Propelled or Tractor Drawn) 5 cu yds or More Capacity; Shoulder Widener; Sideboom; Skid Rig; Stabilizing or Concrete Mixer (Self-Propelled or 14S or Over); Straddle	36.72	21.15	57.87



<b>TRADE OR OCCUPATION</b>	<b>HOURLY BASIC RATE OF PAY</b>	<b>HOURLY FRINGE BENEFITS</b>	<b>TOTAL</b>
	\$	\$	\$
Carrier or Travel Lift; Tractor (Scraper, Dozer, Pusher, Loader); Tractor or Truck Mounted Hydraulic Backhoe; Trencher (Wheel Type or Chain Type); Tube Finisher; Tugger (NOT Performing Work on the Great Lakes); Winches & A- Frames. Future Increase(s): Add \$1.25/hr on 6/1/2015; Add \$1.30/hr on 6/1/2016; Add \$1.25/hr on 6/1/2017. Premium Pay: DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.50/hr night work premium. See DOT'S website for details about the applicability of this night work premium at: <a href="http://www.dot.wi.gov/business/civilrights/laborwages/pwc.htm">http://www.dot.wi.gov/business/civilrights/laborwages/pwc.htm</a> .			
Belting, Burlap, Texturing Machine; Broom or Sweeper; Compactor (Self-Propelled or Tractor Mounted, Towed & Light Equipment); Concrete Finishing Machine (Road Type); Environmental Burner; Farm or Industrial Type Tractor; Fireman (Asphalt Plant, Pile Driver & Derrick NOT Performing Work on the Great Lakes); Forklift; Greaser; Hoist (Tugger, Automatic); Jeep Digger; Joint Sawyer (Multiple Blade); Launch (NOT Performing Work on the Great Lakes); Lift Slab Machine; Mechanical Float; Mulcher; Power Subgrader; Robotic Tool Carrier (With or Without Attachments); Roller (Rubber Tire, 5 Ton or Under); Self Propelled Chip Spreader; Shouldering Machine; Skid Steer Loader (With or Without Attachments); Telehandler; Tining or Curing Machine. Future Increase(s): Add \$1.25/hr on 6/1/2015; Add \$1.30/hr on 6/1/2016; Add \$1.25/hr on 6/1/2017. Premium Pay: DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.50/hr night work premium. See DOT'S website for details about the applicability of this night work premium at: <a href="http://www.dot.wi.gov/business/civilrights/laborwages/pwc.htm">http://www.dot.wi.gov/business/civilrights/laborwages/pwc.htm</a> .	36.46	21.15	57.61
Air Compressor (&/or 400 CFM or Over); Air, Electric or Hydraulic Jacking System; Augers (Vertical & Horizontal); Automatic Belt Conveyor & Surge Bin; Boiler (Temporary Heat); Concrete Proportioning Plant; Crusher, Screening or Wash Plant; Generator (&/or 150 KW or Over); Heaters (Mechanical); High Pressure Utility Locating Machine (Daylighting Machine); Mudjack; Oiler; Prestress Machine; Pug Mill; Pump (3 Inch or Over) or Well Points; Rock, Stone Breaker; Screed (Milling Machine); Stump Chipper; Tank Car Heaters; Vibratory Hammer or Extractor, Power Pack. Future Increase(s): Add \$1.25/hr on 6/1/2015; Add \$1.30/hr on 6/1/2016; Add \$1.25/hr on 6/1/2017. Premium Pay: DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.50/hr night work premium. See DOT'S website for details about the applicability of this night work premium at: <a href="http://www.dot.wi.gov/business/civilrights/laborwages/pwc.htm">http://www.dot.wi.gov/business/civilrights/laborwages/pwc.htm</a> .	36.17	21.15	57.32
Fiber Optic Cable Equipment.	28.89	17.95	46.84
Work Performed on the Great Lakes Including Diver; Wet Tender or Hydraulic Dredge Engineer.	41.65	21.71	63.36
Work Performed on the Great Lakes Including 70 Ton & Over Tug Operator; Assistant Hydraulic Dredge Engineer; Crane or Backhoe Operator; Hydraulic Dredge Leverman or Diver's Tender; Mechanic or Welder.	41.65	21.71	63.36
Work Performed on the Great Lakes Including Deck Equipment Operator or Machineryman (Maintains Cranes Over 50 Tons or Backhoes 115,000 Lbs. or More); Tug, Launch or Loader, Dozer or Like Equipment When Operated on a Barge, Breakwater Wall, Slip, Dock or Scow, Deck Machinery.	35.72	17.85	53.57
Work Performed on the Great Lakes Including Deck Equipment Operator, Machineryman or Fireman (Operates 4 Units or More or Maintains Cranes 50 Tons or Under or Backhoes 115,000 Lbs. or Under); Deck Hand, Deck Engineer or Assistant Tug Operator; Off Road Trucks-Great Lakes ONLY.	35.46	20.40	55.86

<u>TRADE OR OCCUPATION</u>	<u>HOURLY BASIC RATE OF PAY</u>	<u>HOURLY FRINGE BENEFITS</u>	<u>TOTAL</u>
-----	\$-----	\$-----	\$-----

## SCHEDULE OF ITEMS

REVISED:

CONTRACT:  
20150609014PROJECT(S):  
9240-09-70  
9240-09-80FEDERAL ID(S):  
N/A  
N/A

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS

## SECTION 0001 Contract Items

0010	201.0105 Clearing	13.000 STA	.	.	.	.
0020	201.0205 Grubbing	13.000 STA	.	.	.	.
0030	202.0105 Roadside Clearing	8.000 STA	.	.	.	.
0040	203.0100 Removing Small Pipe Culverts	18.000 EACH	.	.	.	.
0050	203.0700.S Removing Old Structure Over Waterway With Debris Capture System (station) 01. 34"BR"+49.00	LUMP	LUMP	.	.	.
0060	204.0110 Removing Asphaltic Surface	325.000 SY	.	.	.	.
0070	204.0115 Removing Asphaltic Surface Butt Joints	540.000 SY	.	.	.	.
0080	204.0120 Removing Asphaltic Surface Milling	197,320.000 SY	.	.	.	.
0090	204.0165 Removing Guardrail	446.000 LF	.	.	.	.

## Wisconsin Department of Transportation

PAGE: 2

DATE: 04/13/15

## SCHEDULE OF ITEMS

REVISED:

CONTRACT:  
20150609014PROJECT(S):  
9240-09-70  
9240-09-80FEDERAL ID(S):  
N/A  
N/A

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0100	204.0180 Removing Delineators and Markers	34.000 EACH	.		.	
0110	205.0100 Excavation Common	4,225.000 CY	.		.	
0120	206.1000 Excavation for Structures Bridges (structure) 01. B-26-39	LUMP	LUMP		.	
0130	208.0100 Borrow	950.000 CY	.		.	
0140	209.0100 Backfill Granular	1,680.000 CY	.		.	
0150	210.0100 Backfill Structure	255.000 CY	.		.	
0160	211.0400 Prepare Foundation for Asphaltic Shoulders	1,462.000 STA	.		.	
0170	213.0100 Finishing Roadway (project) 01. 9240-09-70	1.000 EACH	.		.	
0180	213.0100 Finishing Roadway (project) 02. 9240-09-80	1.000 EACH	.		.	
0190	305.0110 Base Aggregate Dense 3/4-Inch	3,370.000 TON	.		.	

## SCHEDULE OF ITEMS

REVISED:

CONTRACT:  
20150609014PROJECT(S):  
9240-09-70  
9240-09-80FEDERAL ID(S):  
N/A  
N/A

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0200	305.0120 Base Aggregate Dense 1 1/4-Inch	8,950.000 TON	.		.	
0210	305.0500 Shaping Shoulders	1,462.000 STA	.		.	
0220	440.4410.S Incentive IRI Ride	57,200.000 DOL	1.00000		57200.00	
0230	455.0105 Asphaltic Material PG58-28	2,135.000 TON	.		.	
0240	455.0605 Tack Coat	17,030.000 GAL	.		.	
0250	460.1100 HMA Pavement Type E-0.3	36,845.000 TON	.		.	
0260	460.2000 Incentive Density HMA Pavement	23,580.000 DOL	1.00000		23580.00	
0270	460.4000 HMA Cold Weather Paving	9,000.000 TON	.		.	
0280	460.4110.S Reheating HMA Pavement Longitudinal Joints	75,071.000 LF	.		.	
0290	465.0105 Asphaltic Surface	615.000 TON	.		.	

## SCHEDULE OF ITEMS

REVISED:

CONTRACT:  
20150609014PROJECT(S):  
9240-09-70  
9240-09-80FEDERAL ID(S):  
N/A  
N/A

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0300	465.0120 Asphaltic Surface Driveways and Field Entrances	200.000 TON	.		.	
0310	465.0125 Asphaltic Surface Temporary	230.000 TON	.		.	
0320	465.0450 Asphaltic Intersection Rumble Strips	85.000 SY	.		.	
0330	465.0475 Asphalt Center Line Rumble Strips 2-Lane Rural	64,790.000 LF	.		.	
0340	502.0100 Concrete Masonry Bridges	225.000 CY	.		.	
0350	502.3200 Protective Surface Treatment	390.000 SY	.		.	
0360	503.0137 Prestressed Girder Type I 36W-Inch	450.000 LF	.		.	
0370	505.0405 Bar Steel Reinforcement HS Bridges	4,740.000 LB	.		.	
0380	505.0605 Bar Steel Reinforcement HS Coated Bridges	24,710.000 LB	.		.	
0390	506.2605 Bearing Pads Elastomeric Non-Laminated	12.000 EACH	.		.	

## SCHEDULE OF ITEMS

REVISED:

CONTRACT:  
20150609014PROJECT(S):  
9240-09-70  
9240-09-80FEDERAL ID(S):  
N/A  
N/A

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0400	506.4000 Steel Diaphragms (structure) 01. B-26-39	5.000 EACH	.		.	
0410	511.1200 Temporary Shoring (structure) 01. B-26-39	230.000 SF	.		.	
0420	516.0500 Rubberized Membrane Waterproofing	26.000 SY	.		.	
0430	517.1015.S Concrete Staining Multi-Color (structure) 01. B-26-39	230.000 SF	.		.	
0440	517.1050.S Architectural Surface Treatment (structure) 01. B-26-39	230.000 SF	.		.	
0450	522.0124 Culvert Pipe Reinforced Concrete Class III 24-Inch	736.000 LF	.		.	
0460	522.0130 Culvert Pipe Reinforced Concrete Class III 30-Inch	812.000 LF	.		.	
0470	522.1024 Apron Endwalls for Culvert Pipe Reinforced Concrete 24-Inch	20.000 EACH	.		.	
0480	522.1030 Apron Endwalls for Culvert Pipe Reinforced Concrete 30-Inch	16.000 EACH	.		.	
0490	550.1100 Piling Steel HP 10-Inch X 42 Lb	700.000 LF	.		.	

## SCHEDULE OF ITEMS

REVISED:

CONTRACT:  
20150609014PROJECT(S):  
9240-09-70  
9240-09-80FEDERAL ID(S):  
N/A  
N/A

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0500	603.8000 Concrete Barrier Temporary Precast Delivered	600.000 LF	.		.	
0510	603.8125 Concrete Barrier Temporary Precast Installed	1,000.000 LF	.		.	
0520	606.0300 Riprap Heavy	298.000 CY	.		.	
0530	612.0406 Pipe Underdrain Wrapped 6-Inch	140.000 LF	.		.	
0540	614.0150 Anchor Assemblies for Steel Plate Beam Guard	4.000 EACH	.		.	
0550	614.2300 MGS Guardrail 3	125.000 LF	.		.	
0560	614.2500 MGS Thrie Beam Transition	158.000 LF	.		.	
0570	614.2610 MGS Guardrail Terminal EAT	4.000 EACH	.		.	
0580	618.0100 Maintenance And Repair of Haul Roads (project) 01. 9240-09-70	1.000 EACH	.		.	
0590	618.0100 Maintenance And Repair of Haul Roads (project) 02. 9240-09-80	1.000 EACH	.		.	



## Wisconsin Department of Transportation

PAGE: 7

DATE: 04/13/15

REVISED:

## SCHEDULE OF ITEMS

CONTRACT:  
20150609014PROJECT(S):  
9240-09-70  
9240-09-80FEDERAL ID(S):  
N/A  
N/A

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0600	619.1000 Mobilization	1.000 EACH	.		.	
0610	624.0100 Water	110.000 MGAL	.		.	
0620	625.0100 Topsoil	14,600.000 SY	.		.	
0630	627.0200 Mulching	3,500.000 SY	.		.	
0640	628.1504 Silt Fence	4,300.000 LF	.		.	
0650	628.1520 Silt Fence Maintenance	1,260.000 LF	.		.	
0660	628.1905 Mobilizations Erosion Control	6.000 EACH	.		.	
0670	628.1910 Mobilizations Emergency Erosion Control	4.000 EACH	.		.	
0680	628.2006 Erosion Mat Urban Class I Type A	9,600.000 SY	.		.	
0690	628.5505 Polyethylene Sheeting	2,745.000 SY	.		.	
0700	628.6005 Turbidity Barriers	180.000 SY	.		.	

## SCHEDULE OF ITEMS

CONTRACT:  
20150609014PROJECT(S):  
9240-09-70  
9240-09-80FEDERAL ID(S):  
N/A  
N/A

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0710	628.7504 Temporary Ditch Checks	40.000 LF	.		.	
0720	628.7555 Culvert Pipe Checks	68.000 EACH	.		.	
0730	628.7570 Rock Bags	84.000 EACH	.		.	
0740	629.0210 Fertilizer Type B	10.000 CWT	.		.	
0750	630.0130 Seeding Mixture No. 30	352.000 LB	.		.	
0760	633.1100 Delineators Temporary	50.000 EACH	.		.	
0770	633.5200 Markers Culvert End	98.000 EACH	.		.	
0780	634.0612 Posts Wood 4x6-Inch X 12-FT	4.000 EACH	.		.	
0790	634.0616 Posts Wood 4x6-Inch X 16-FT	91.000 EACH	.		.	
0800	634.0618 Posts Wood 4x6-Inch X 18-FT	1.000 EACH	.		.	
0810	637.2210 Signs Type II Reflective H	349.000 SF	.		.	

## SCHEDULE OF ITEMS

REVISED:

CONTRACT:  
20150609014PROJECT(S):  
9240-09-70  
9240-09-80FEDERAL ID(S):  
N/A  
N/A

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0820	637.2230 Signs Type II Reflective F	216.000 SF	.		.	
0830	638.2602 Removing Signs Type II	100.000 EACH	.		.	
0840	638.3000 Removing Small Sign Supports	99.000 EACH	.		.	
0850	642.5201 Field Office Type C	1.000 EACH	.		.	
0860	643.0100 Traffic Control (project) 01. 9240-09-70	1.000 EACH	.		.	
0870	643.0100 Traffic Control (project) 02. 9240-09-80	1.000 EACH	.		.	
0880	643.0300 Traffic Control Drums	2,640.000 DAY	.		.	
0890	643.0420 Traffic Control Barricades Type III	90.000 DAY	.		.	
0900	643.0715 Traffic Control Warning Lights Type C	1,200.000 DAY	.		.	
0910	643.0900 Traffic Control Signs	3,950.000 DAY	.		.	
0920	645.0120 Geotextile Fabric Type HR	530.000 SY	.		.	

## SCHEDULE OF ITEMS

REVISED:

CONTRACT:  
20150609014PROJECT(S):  
9240-09-70  
9240-09-80FEDERAL ID(S):  
N/A  
N/A

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0930	646.0106 Pavement Marking Epoxy 4-Inch	250,925.000 LF	.		.	
0940	646.0406 Pavement Marking Same Day Epoxy 4-Inch	94,890.000 LF	.		.	
0950	646.0600 Removing Pavement Markings	400.000 LF	.		.	
0960	648.0100 Locating No-Passing Zones	14.300 MI	.		.	
0970	649.0100 Temporary Pavement Marking 4-Inch	76,905.000 LF	.		.	
0980	649.0400 Temporary Pavement Marking Removable Tape 4-Inch	2,300.000 LF	.		.	
0990	649.1400 Temporary Pavement Marking Stop Line Removable Tape 24-Inch	24.000 LF	.		.	
1000	650.4500 Construction Staking Subgrade	1,800.000 LF	.		.	
1010	650.5000 Construction Staking Base	1,800.000 LF	.		.	
1020	650.6000 Construction Staking Pipe Culverts	18.000 EACH	.		.	

## SCHEDULE OF ITEMS

REVISED:

CONTRACT:  
20150609014PROJECT(S):  
9240-09-70  
9240-09-80FEDERAL ID(S):  
N/A  
N/A

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
1030	650.6500 Construction Staking Structure Layout (structure) 01. B-26-39	LUMP	LUMP			.
1040	650.8000 Construction Staking Resurfacing Reference	73,105.000 LF	.		.	.
1050	650.9910 Construction Staking Supplemental Control (project) 01. 9240-09-70	LUMP	LUMP			.
1060	650.9910 Construction Staking Supplemental Control (project) 02. 9240-09-80	LUMP	LUMP			.
1070	650.9920 Construction Staking Slope Stakes	3,000.000 LF	.		.	.
1080	661.0100 Temporary Traffic Signals for Bridges (structure) 01. B-26-39	LUMP	LUMP			.
1090	690.0150 Sawing Asphalt	473.000 LF	.		.	.
1100	715.0502 Incentive Strength Concrete Structures	2,100.000 DOL	1.00000		2100.00	
1110	SPV.0060 Special 01. Culvert Pipe Transitions	18.000 EACH	.		.	.

## SCHEDULE OF ITEMS

REVISED:

CONTRACT:  
20150609014PROJECT(S):  
9240-09-70  
9240-09-80FEDERAL ID(S):  
N/A  
N/A

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
1120	SPV.0060 Special 02. Reestablish Section Corner Monuments	2.000 EACH	.		.	
1130	SPV.0060 Special 03. Lane Shift	7.000 EACH	.		.	
	SECTION 0001 TOTAL				.	
	TOTAL BID				.	

**PLEASE ATTACH SCHEDULE OF ITEMS HERE**