

# HIGHWAY WORK PROPOSAL

Wisconsin Department of Transportation  
DT1502 10/2010 s.66.29(7) Wis. Stats.

Proposal Number:

Ø 2

<u>COUNTY</u>	<u>STATE PROJECT ID</u>	<u>FEDERAL PROJECT ID</u>	<u>PROJECT DESCRIPTION</u>	<u>HIGHWAY</u>
Dane	1206-04-68		C Madison, South Madison Beltline WSOR Bridge B-13-0192	USH 12

This proposal, submitted by the undersigned bidder to the Wisconsin Department of Transportation, is in accordance with the advertised request for proposals. The bidder is to furnish and deliver all materials, and to perform all work for the improvement of the designated project in the time specified, in accordance with the appended Proposal Requirements and Conditions.

Proposal Guaranty Required, \$ 20,000.00 Payable to: Wisconsin Department of Transportation	Attach Proposal Guaranty on back of this PAGE.
Bid Submittal Due  Date: November 10, 2015 Time (Local Time): 9:00 AM	Firm Name, Address, City, State, Zip Code
Contract Completion Time  Thirty-Five (35) Calendar Days	<b>SAMPLE</b> <b>NOT FOR BIDDING PURPOSES</b>
Assigned Disadvantaged Business Enterprise Goal  0%	This contract is exempt from federal oversight.

This certifies that the undersigned bidder, duly sworn, is an authorized representative of the firm named above; that the bidder has examined and carefully prepared the bid from the plans, Highway Work Proposal, and all addenda, and has checked the same in detail before submitting this proposal or bid; and that the bidder or agents, officer, or employees have not, either directly or indirectly, entered into any agreement, participated in any collusion, or otherwise taken any action in restraint of free competitive bidding in connection with this proposal bid.

**Do not sign, notarize, or submit this Highway Work Proposal when submitting an electronic bid on the Internet.**

Subscribed and sworn to before me this date \_\_\_\_\_

\_\_\_\_\_  
(Signature, Notary Public, State of Wisconsin)

\_\_\_\_\_  
(Print or Type Name, Notary Public, State Wisconsin)

\_\_\_\_\_  
(Date Commission Expires)

Notary Seal

\_\_\_\_\_  
(Bidder Signature)

\_\_\_\_\_  
(Print or Type Bidder Name)

\_\_\_\_\_  
(Bidder Title)

## For Department Use Only

Type of Work  Abutment repairs to the WB US 12 structure of the WSOR railroad, replacing concrete approach slabs, pavement marking, and concrete rumble strips.	Date Guaranty Returned
Notice of Award Dated	

**PLEASE ATTACH  
PROPOSAL GUARANTY HERE**

**Effective with November 2007 Letting**

**PROPOSAL REQUIREMENTS AND CONDITIONS**

The bidder, signing and submitting this proposal, agrees and declares as a condition thereof, to be bound by the following conditions and requirements.

If the bidder has a corporate relationship with the proposal design engineering company, the bidder declares that it did not obtain any facts, data, or other information related to this proposal from the design engineering company that was not available to all bidders.

The bidder declares that they have carefully examined the site of, and the proposal, plans, specifications and contract forms for the work contemplated, and it is assumed that the bidder has investigated and is satisfied as to the conditions to be encountered, as to the character, quality, and quantities of work to be performed and materials to be furnished, and as to the requirements of the specifications, special provisions and contract. It is mutually agreed that submission of a proposal shall be considered conclusive evidence that the bidder has made such examination.

The bidder submits herewith a proposal guaranty in proper form and amount payable to the party as designated in the advertisement inviting proposals, to be retained by and become the property of the owner of the work in the event the undersigned shall fail to execute the contract and contract bond and return the same to the office of the engineer within fourteen (14) days after having been notified in writing to do so; otherwise to be returned.

The bidder declares that they understand that the estimate of quantities in the attached schedule is approximate only and that the attached quantities may be greater or less in accordance with the specifications.

The bidder agrees to perform the said work, for and in consideration of the payment of the amount becoming due on account of work performed, according to the unit prices bid in the following schedule, and to accept such amounts in full payment of said work.

The bidder declares that all of the said work will be performed at their own proper cost and expense, that they will furnish all necessary materials, labor, tools, machinery, apparatus, and other means of construction in the manner provided in the applicable specifications and the approved plans for the work together with all standard and special designs that may be designed on such plans, and the special provisions in the contract of which this proposal will become a part, if and when accepted. The bidder further agrees that the applicable specifications and all plans and working drawings are made a part hereof, as fully and completely as if attached hereto.

The bidder, if awarded the contract, agrees to begin the work not later than ten (10) days after the date of written notification from the engineer to do so, unless otherwise stipulated in the special provisions.

The bidder declares that if they are awarded the contract, they will execute the contract agreement and begin and complete the work within the time named herein, and they will file a good and sufficient surety bond for the amount of the contract for performance and also for the full amount of the contract for payment.

The bidder, if awarded the contract, shall pay all claims as required by Section 779.14, Statutes of Wisconsin, and shall be subject to and discharge all liabilities for injuries pursuant to Chapter 102 of the Statutes of Wisconsin, and all acts amendatory thereto. They shall further be responsible for any damages to property or injury to persons occurring through their own negligence or that of their employees or agents, incident to the performance of work under this contract, pursuant to the Standard Specifications for Road and Bridge Construction applicable to this contract.

In connection with the performance of work under this contract, the contractor agrees to comply with all applicable state and federal statutes relating to non-discrimination in employment. No otherwise qualified person shall be excluded from employment or otherwise be subject to discrimination in employment in any manner on the basis of age, race, religion, color, gender, national origin or ancestry, disability, arrest or conviction record (in keeping with s.111.32), sexual orientation, marital status, membership in the military reserve, honesty testing, genetic testing, and outside use of lawful products. This provision shall include, but not be limited to the following: employment, upgrading, demotion or transfer; recruitment or recruitment advertising; layoff or termination; rates of pay or other forms of compensation, and selection for training, including apprenticeship. The contractor further agrees to ensure equal opportunity in employment to all applicants and employees and to take affirmative action to attain a representative workforce.

The contractor agrees to post notices and posters setting forth the provisions of the nondiscrimination clause, in a conspicuous and easily accessible place, available for employees and applicants for employment.

If a state public official (section 19.42, Stats.) or an organization in which a state public official holds at least a 10% interest is a party to this agreement, this contract is voidable by the state unless appropriate disclosure is made to the State of Wisconsin Ethics Board.

## Effective with August 2015 Letting

### BID PREPARATION

#### **Preparing the Proposal Schedule of Items**

##### **A General**

- (1) Obtain bidding proposals as specified in **section 102** of the standard specifications prior to 11:45 AM of the last business day preceding the letting. Submit bidding proposals using one of the following methods:
  1. Electronic bid on the internet.
  2. Electronic bid on a printout with accompanying diskette or CD ROM.
  3. Paper bid under a waiver of the electronic submittal requirements.
- (2) Bids submitted on a printout with accompanying diskette or CD ROM or paper bids submitted under a waiver of the electronic submittal requirements govern over bids submitted on the internet.

- (3) The department will provide bidding information through the department's web site at:  
<http://wisconsindot.gov/Pages/doing-bus/contractors/hcci/bid-let.aspx>

The contractor is responsible for reviewing this web site for general notices as well as information regarding proposals in each letting. The department will also post special notices of all addenda to each proposal through this web site no later than 4:00 P.M. local time on the Thursday before the letting. Check the department's web site after 5:00 P.M. local time on the Thursday before the letting to ensure all addenda have been accounted for before preparing the bid. When bidding using methods 1 and 2 above, check the Bid Express™ on-line bidding exchange at <http://www.bidx.com/> after 5:00 P.M. local time on the Thursday before the letting to ensure that the latest schedule of items Expedite file (\*.ebs or \*.00x) is used to submit the final bid.

- (4) Interested parties can subscribe to the Bid Express™ on-line bidding exchange by following the instructions provided at the [www.bidx.com](http://www.bidx.com) web site or by contacting:

Info Tech Inc.  
5700 SW 34th Street, Suite 1235  
Gainesville, FL 32608-5371  
email: <mailto:customer.support@bidx.com>

- (5) The department will address equipment and process failures, if the bidder can demonstrate that those failures were beyond their control.
- (6) Contractors are responsible for checking on the issuance of addenda and for obtaining the addenda. Notice of issuance of addenda is posted on the department's web site at:  
<http://wisconsindot.gov/Pages/doing-bus/contractors/hcci/bid-let.aspx>

or by calling the department at (608) 266-1631. Addenda can ONLY be obtained from the departments web site listed above or by picking up the addenda at the Bureau of Highway Construction, Room 601, 4802 Sheboygan Avenue, Madison, WI, during regular business hours.

- (7) Addenda posted after 5:00 PM on the Thursday before the letting will be emailed to the eligible bidders for that proposal. All eligible bidders shall acknowledge receipt of the addenda whether they are bidding on the proposal or not. Not acknowledging receipt may jeopardize the awarding of the project.

## **B Submitting Electronic Bids**

### **B.1 On the Internet**

- (1) Do the following before submitting the bid:
  1. Have a properly executed annual bid bond on file with the department.
  2. Have a digital ID on file with and enabled by Info Tech Inc. Using this digital ID will constitute the bidder's signature for proper execution of the bidding proposal.
- (2) In lieu of preparing, delivering, and submitting the proposal as specified in 102.6 and 102.9 of the standard specifications, submit the proposal on the internet as follows:
  1. Download the latest schedule of items reflecting all addenda from the Bid Express<sup>TM</sup> web site.
  2. Use Expedite<sup>TM</sup> software to enter a unit price for every item in the schedule of items.
  3. Submit the bid according to the requirements of Expedite<sup>TM</sup> software and the Bid Express<sup>TM</sup> web site. Do not submit a bid on a printout with accompanying diskette or CD ROM or a paper bid. If the bidder does submit a bid on a printout with accompanying diskette or a paper bid in addition to the internet submittal, the department will disregard the internet bid.
  4. Submit the bid before the hour and date the Notice to Contractors designates.
  5. Do not sign, notarize, and return the bidding proposal described in 102.2 of the standard specifications.
- (3) The department will not consider the bid accepted until the hour and date the Notice to Contractors designates.

### **B.2 On a Printout with Accompanying Diskette or CD ROM**

- (1) Download the latest schedule of items from the Wisconsin pages of the Bid Express<sup>TM</sup> web site reflecting the latest addenda posted on the department's web site at:  
<http://wisconsindot.gov/Pages/doing-bus/contractors/hcci/bid-let.aspx>

Use Expedite<sup>TM</sup> software to prepare and print the schedule of items. Provide a valid amount for all price fields. Follow instructions and review the help screens provided on the Bid Express<sup>TM</sup> web site to assure that the schedule of items is prepared properly.

- (2) Staple an 8 1/2 by 11 inch printout of the Expedite<sup>TM</sup> generated schedule of items to the other proposal documents submitted to the department as a part of the bidder's sealed bid. As a separate submittal not in the sealed bid envelop but due at the same time and place as the sealed bid, also provide the Expedite<sup>TM</sup> generated schedule of items on a 3 1/2 inch computer diskette or CD ROM. Label each diskette or CD ROM with the bidder's name, the 4 character department-assigned bidder identification code from the top of the bidding proposal, and a list of the proposal numbers included on that diskette or CD ROM as indicated in the following example:

**Bidder**

**Name**

**BN00**

**Proposals: 1, 12, 14, & 22**

- (3) If bidding on more than one proposal in the letting, the bidder may include all proposals for that letting on one diskette or CD ROM. Include only submitted proposals with no incomplete or other files on the diskette or CD ROM.
- (4) The bidder-submitted printout of the Expedite<sup>TM</sup> generated schedule of items is the governing contract document and must conform to the requirements of section 102 of the standard specifications. If a printout needs to be altered, cross out the printed information with ink or typewriter and enter the new information and initial it in ink. If there is a discrepancy between the printout and the diskette or CD ROM, the department will analyze the bid using the printout information.

- (5) In addition to the reasons specified in [section 102](#) of the standard specifications, proposals are irregular and the department may reject them for one or more of the following:
1. The check code printed on the bottom of the printout of the Expedite<sup>TM</sup> generated schedule of items is not the same on each page.
  2. The check code printed on the printout of the Expedite<sup>TM</sup> generated schedule of items is not the same as the check code for that proposal provided on the diskette or CD ROM.
  3. The diskette or CD ROM is not submitted at the time and place the department designates.

### **C Waiver of Electronic Submittal**

- (1) The bidder may request a waiver of the electronic submittal requirements. Submit a written request for a waiver in lieu of bids submitted on the internet or on a printout with accompanying diskette or CD ROM. Use the waiver that was included with the paper bid document sent to the bidder or type up a waiver on the bidder's letterhead. The department will waive the electronic submittal requirements for a bidding entity (individual, partnership, joint venture, corporation, or limited liability company) for up to 4 individual proposals in a calendar year. The department may allow additional waivers for equipment malfunctions.
- (2) Submit a schedule of items on paper conforming to [section 102](#) of the standard specifications. The department charges the bidder a \$75 administrative fee per proposal, payable at the time and place the department designates for receiving bids, to cover the costs of data entry. The department will accept a check or money order payable to: "Wisconsin, Dept. of Transportation."
- (3) In addition to the reasons specified in [section 102](#) of the standard specifications, proposals are irregular and the department may reject them for one or more of the following:
  1. The bidder fails to provide the written request for waiver of the electronic submittal requirements.
  2. The bidder fails to pay the \$75 administrative fee before the time the department designates for the opening of bids unless the bidder requests on the waiver that they be billed for the \$75.
  3. The bidder exceeds 4 waivers of electronic submittal requirements within a calendar year.
- (4) In addition to the reasons specified in [section 102](#) of the standard specifications, the department may refuse to issue bidding proposals for future contracts to a bidding entity that owes the department administrative fees for a waiver of electronic submittal requirements.

# PROPOSAL BID BOND

DT1303 1/2006

Wisconsin Department of Transportation

Proposal Number	Project Number	Letting Date
Name of Principal		
Name of Surety	State in Which Surety is Organized	

We, the above-named Principal and the above-named Surety, are held and firmly bound unto the State of Wisconsin in the sum equal to the Proposal Guaranty for the total bid submitted for the payment to be made; we jointly and severally bind ourselves, our heirs, executors, administrators, successors and assigns. The condition of this obligation is that the Principal has submitted a bid proposal to the State of Wisconsin acting through the Department of Transportation for the improvement designated by the Proposal Number and Letting Date indicated above.

If the Principal is awarded the contract and, within the time and manner required by law after the prescribed forms are presented for signature, enters into a written contract in accordance with the bid, and files the bond with the Department of Transportation to guarantee faithful performance and payment for labor and materials, as required by law, or if the Department of Transportation shall reject all bids for the work described, then this obligation shall be null and void; otherwise, it shall be and remain in full force and effect. In the event of failure of the Principal to enter into the contract or give the specified bond, the Principal shall pay to the Department of Transportation **within 10 business days of demand** a total equal to the Proposal Guaranty as liquidated damages; the liability of the Surety continues for the full amount of the obligation as stated until the obligation is paid in full.

The Surety, for value received, agrees that the obligations of it and its bond shall not be impaired or affected by any extension of time within which the Department of Transportation may accept the bid; and the Surety does waive notice of any such extension.

IN WITNESS, the Principal and Surety have agreed and have signed by their proper officers and have caused their corporate seals to be affixed this date: **(DATE MUST BE ENTERED)**

## PRINCIPAL

\_\_\_\_\_  
(Company Name) **(Affix Corporate Seal)**

\_\_\_\_\_  
(Signature and Title)

\_\_\_\_\_  
(Company Name)

\_\_\_\_\_  
(Signature and Title)

\_\_\_\_\_  
(Company Name)

\_\_\_\_\_  
(Signature and Title)

\_\_\_\_\_  
(Company Name)

\_\_\_\_\_  
(Signature and Title)

## NOTARY FOR PRINCIPAL

\_\_\_\_\_  
(Date)

State of Wisconsin )  
 ) ss.  
\_\_\_\_\_ County )

On the above date, this instrument was acknowledged before me by the named person(s).

\_\_\_\_\_  
(Signature, Notary Public, State of Wisconsin)

\_\_\_\_\_  
(Print or Type Name, Notary Public, State of Wisconsin)

\_\_\_\_\_  
(Date Commission Expires)

**Notary Seal**

\_\_\_\_\_  
(Name of Surety) **(Affix Seal)**

\_\_\_\_\_  
(Signature of Attorney-in-Fact)

## NOTARY FOR SURETY

\_\_\_\_\_  
(Date)

State of Wisconsin )  
 ) ss.  
\_\_\_\_\_ County )

On the above date, this instrument was acknowledged before me by the named person(s).

\_\_\_\_\_  
(Signature, Notary Public, State of Wisconsin)

\_\_\_\_\_  
(Print or Type Name, Notary Public, State of Wisconsin)

\_\_\_\_\_  
(Date Commission Expires)

**Notary Seal**

**IMPORTANT: A certified copy of Power of Attorney of the signatory agent must be attached to the bid bond.**





# CERTIFICATE OF ANNUAL BID BOND

DT1305 8/2003

Wisconsin Department of Transportation

Time Period Valid (From/To)	
Name of Surety	
Name of Contractor	
Certificate Holder	Wisconsin Department of Transportation

This is to certify that an annual bid bond issued by the above-named Surety is currently on file with the Wisconsin Department of Transportation.

This certificate is issued as a matter of information and conveys no rights upon the certificate holder and does not amend, extend or alter the coverage of the annual bid bond.

**Cancellation:** Should the above policy be cancelled before the expiration date, the issuing surety will give thirty (30) days written notice to the certificate holder indicated above.

\_\_\_\_\_  
(Signature of Authorized Contractor Representative)

\_\_\_\_\_  
(Date)



## March 2010

## LIST OF SUBCONTRACTORS

Section 66.0901(7), Wisconsin Statutes, provides that as a part of the proposal, the bidder also shall submit a list of the subcontractors the bidder proposes to contract with and the class of work to be performed by each. In order to qualify for inclusion in the bidder's list a subcontractor shall first submit a bid in writing, to the general contractor at least 48 hours prior to the time of the bid closing. The list may not be added to or altered without the written consent of the municipality. A proposal of a bidder is not invalid if any subcontractor and the class of work to be performed by the subcontractor has been omitted from a proposal; the omission shall be considered inadvertent or the bidder will perform the work personally.

No subcontract, whether listed herein or later proposed, may be entered into without the written consent of the Engineer as provided in Subsection 108.1 of the Standard Specifications.

[illegible]

**DECEMBER 2000**

**CERTIFICATION REGARDING DEBARMENT, SUSPENSION, AND OTHER  
RESPONSIBILITY MATTERS - PRIMARY COVERED TRANSACTIONS**

Instructions for Certification

1. By signing and submitting this proposal, the prospective contractor is providing the certification set out below.
2. The inability of a person to provide the certification required below will not necessarily result in denial of participation in this covered transaction. The prospective contractor shall submit an explanation of why it cannot provide the certification set out below. The certification or explanation will be considered in connection with the department or agency's determination whether to enter into this transaction. However, failure of the prospective contractor to furnish a certification or an explanation shall disqualify such person from participation in this transaction.
3. The certification in this clause is a material representation of fact upon which reliance was placed when the department determined to enter into this transaction. If it is later determined that the contractor knowingly rendered an erroneous certification in addition to other remedies available to the Federal Government the department may terminate this transaction for cause or default.
4. The prospective contractor shall provide immediate written notice to the department to whom this proposal is submitted if at any time the prospective contractor learns that its certification was erroneous when submitted or has become erroneous by reason of changed circumstances.
5. The terms "covered transaction," "debarred," "suspended," "ineligible," "lower tier covered transaction," "participant," "person," "primary covered transaction," "principal," "proposal," and "voluntarily excluded," as used in this clause, have the meanings set out in the Definitions and Coverage sections of the rules implementing Executive Order 12549. You may contact the department to which this proposal is being submitted for assistance in obtaining a copy of those regulations.
6. The prospective contractor agrees by submitting this proposal that, should this contract be entered into, it shall not knowingly enter into any lower tier covered transaction with a person who is debarred, suspended, declared ineligible, or voluntarily excluded from participation in this covered transaction, unless authorized by the department entering into this transaction.
7. The prospective contractor further agrees by submitting this proposal that it will include the clause titled "Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion-Lower Tier Covered Transaction," which is included as an addendum to PR-1273 - "Required Contract Provisions Federal Aid Construction Contracts," without

modification, in all lower tier covered transactions and in all solicitations for lower tier covered transactions.

8. The contractor may rely upon a certification of a prospective subcontractor/materials supplier that it is not debarred, suspended, ineligible, or voluntarily excluded from the covered transaction, unless it knows that the certification is erroneous. A contractor may decide the method and frequency by which it determines the eligibility of its principals. Each contractor may, but is not required to, check the Disapproval List (telephone # 608/266/1631).
9. Nothing contained in the foregoing shall be construed to require establishment of a system of records in order to render in good faith the certification required by this clause. The knowledge and information of a contractor is not required to exceed that which is normally possessed by a prudent person in the ordinary course of business dealings.
10. Except for transactions authorized under paragraph 6 of these instructions, if a contractor in a covered transaction knowingly enters into a lower tier covered transaction with a person who is suspended, debarred, ineligible or voluntarily excluded from participation in this transaction, in addition to other remedies available to the Federal Government, the department may terminate this transaction for cause or default.

Certification Regarding Debarment, Suspension, and Other Responsibility Matters - Primary Covered Transactions

- (1) The prospective contractor certifies to the best of its knowledge and belief, that it and its principals:
  - (a) Are not presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from covered transactions by any Federal department or agency;
  - (b) Have not within a three-year period preceding this proposal been convicted of or had a civil judgment rendered against them for commission of fraud or a criminal offense in connection with obtaining, attempting to obtain, or performing a public (Federal, State or local) transaction or contract under a public transaction; violation of Federal or State antitrust statutes or commission of embezzlement, theft, forgery, bribery, falsification or destruction of records, making false statements or receiving stolen property;
  - (c) Are not presently indicted for or otherwise criminally or civilly charged by a governmental entity (Federal, State or local) with commission of any of the offense enumerated in paragraph (1)(b) of this certification; and
  - (d) Have not within a three-year period preceding this proposal had one or more public transactions (Federal, State or local) terminated for cause or default.
- (2) Where the prospective contractor is unable to certify to any of the statements in this certification, such prospective contractor shall attach an explanation to this proposal.

## Special Provisions

### Table of Contents

Article	Description	Page #
1.	General.....	2
2.	Scope of Work. ....	2
3.	Prosecution and Progress. ....	2
4.	Traffic. ....	5
5.	Lane Rental Fee Assessment. ....	7
6.	Utilities.....	9
7.	Other Contracts. ....	9
8.	Railroad Insurance and Coordination. ....	9
9.	Notice to Contractor, Notification of Demolition and/or Renovation No Asbestos Found. ....	10
10.	Public Convenience and Safety. ....	11
11.	Project Communication Enhancement Effort. ....	11
12.	Incentive/Disincentive for Interim Completion of Work Rimrock Road WB Beltline Entrance Closure, Item 108.3100.S.01.....	12
13.	QMP Base Aggregate. ....	13
14.	Nighttime Work Lighting-Stationary.....	21
15.	Pavement Marking Grooved Wet Reflective Contrast Tape 8-Inch, Item 646.0843.S. ....	23
16.	Temporary Thrie Beam Connection, SPV.0060.001.....	25
17.	Repositioning Traffic Control Devices for Mainline Closures, Item SPV.0060.002. ....	26
18.	Traffic Channelizing Curb System Furnished, Item SPV.0090.001, Installed, Item SPV.0090.002. ....	27
19.	Temporary Pavement Marking Wet Reflective Contrast Removable Tape 4-Inch, Item SPV.0090.003; 8-Inch, Item SPV.0090.004.....	29
20.	Traffic Control Gawk Screen Furnished, Item SPV.0090.005; Installed, Item SPV.0090.006. ....	30
21.	Removing Pavement Markings Water Blasting, Item SPV.0090.007.....	31
22.	Concrete Pavement Approach Slab HES Special, Item SPV.0180.001. ....	32

## **SPECIAL PROVISIONS**

### **1. General.**

Perform the work under this construction contract for Project 1206-04-68, City of Madison, South Madison Beltline, WSOR Bridge B-13-0192, USH 12, Dane County, Wisconsin as the plans show and execute the work as specified in the State of Wisconsin, Department of Transportation, Standard Specifications for Highway and Structure Construction, 2015 Edition, as published by the department, and these special provisions.

If all or a portion of the plans and special provisions are developed in the SI metric system and the schedule of prices is developed in the US standard measure system, the department will pay for the work as bid in the US standard system.

100-005 (20130615)

### **2. Scope of Work.**

The work under this contract shall consist of concrete pavement approach slab, shoulder rumble strips, traffic control, structure rehab to B-13-192, pavement marking, and all incidental items necessary to complete the work as shown on the plans and included in the proposal and contract.

104-005 (20090901)

### **3. Prosecution and Progress.**

#### **A Notice to Proceed**

Begin work within ten calendar days after the engineer issues a written notice to do so.

Provide the time frame for construction of the project within the 2016 construction season to the engineer in writing within a month after executing the contract but at least 14 calendar days before the preconstruction conference. Assure that the time frame is consistent with the contract completion time. Upon approval, the engineer will issue the notice to proceed within ten calendar days before the beginning of the approved time frame.

To revise the time frame, submit a written request to the engineer at least two weeks before the beginning of the intended time frame. The engineer will approve or deny that request based on the conditions cited in the request and its effect on the department's scheduled resources.



Provide a work schedule that complies with either of the following timeframes:

- Start no earlier than May 31, 2016 with completion by July 8, 2016.
- Start no earlier than July 20, 2016 with completion by October 3, 2016.

## **B General**

The contract time for completion is based on an expedited work schedule and may require extraordinary forces and equipment. The use of special high early concrete mixes to expedite cure times is prohibited and will not be an approved method to compress the construction schedule.

Indicate on the proposed schedule of operations that a large force and adequate equipment will be needed to assure that the work will be completed within the established contract time.

## **C Construction Overview**

The schedule of operations shall conform to the construction staging as shown in the plans and hereafter described unless the engineer approves modifications to the schedule in writing.

### Stage 1

- Construct first half of the bridge repair and concrete approach slab.

### Stage 2

- Construct remainder of the bridge repair and concrete approach slab.
- Complete all work for Stage 1 and 2 within 25 calendar days as specified in the article Incentive / Disincentive for Interim Completion of Work.

### Stage 3

- Install shoulder rumble strips and remaining pavement marking.

## **D Contractor Coordination**

Hold prosecution and progress meetings once a week. The contractor's superintendent or designated representative and subcontractor's representatives for ongoing subcontract work or subcontractor work expected to begin within the next two weeks shall attend and provide a written schedule of the next week(s)' operations.

The written schedule shall include begin and end dates of specific prime and subcontractor work operations. Invite City of Madison traffic engineering staff, City of Fitchburg and Town of Madison. Agenda items at the meeting will include review of the contractor's schedule and subcontractors' schedule, evaluation of progress and pay items, and making revisions if necessary. Plans and specifications for upcoming work will be reviewed to prevent potential problems or conflicts between contractors.

Based on the progress meeting, if the engineer requests a revised schedule, submit it within three calendar days. Failure to submit a new schedule within three days shall result in the engineer holding pay requests until received.

#### **E Workzone Access and Work Hours**

Work on USH 12 not protected by concrete barrier is prohibited outside of allowable lane closure hours specified in Traffic article. Access between live traffic lanes and work zones protected by concrete barrier is restricted as follows:

- No access is allowed during peak hours of 6:00 AM – 9:00 AM and 3:00 PM – 7:00 PM Monday through Friday.
- Access for contractor personnel utilizing small work vehicles is allowed during non-peak hours.
- Hauling of materials, equipment, and other large truck ingress/egress is to be completed during nighttime lane closures or, if approved by the engineer, with the assistance of a safety vehicle during daytime non-peak hours using the single lane of the traffic split for access to and from the downstream end of the workzone. Utilize the safety vehicle to create a suitable gap in traffic in order to assist trucks entering or exiting the work zone. The safety vehicle is not allowed to leave the traffic lane and enter the work zone. Costs associated with use of a safety vehicle are incidental to the contract.

#### **F Clear Zone Working Restrictions**

Do not leave any longitudinal drop offs within 4 feet of the edge of the traveled way greater than 3 inches unless protected by temporary precast barrier. Do not leave any transverse drop offs within 30 feet of the edge of the traveled way greater than 2 inches unless protected by temporary precast barrier.

Store materials or park equipment a minimum of 30-feet from the edge of the USH 12 mainline or ramp traveled way unless protected by concrete barrier.

If the contractor is unsure whether an individual work operation will meet the safety requirements for working within the clear zone, review the proposed work operation with the engineer before proceeding with the work.

#### **G Migratory Birds**

Swallow and other migratory birds' nests have been observed on or under the existing bridge. All active nests (when eggs or young are present) of migratory birds are protected under the federal Migratory Bird Treaty Act.

The nesting season for swallows and other birds is usually between May 1 and August 30. Either prevent active nests from becoming established, or apply for a depredation permit from the US Fish and Wildlife Service for work that may disturb or destroy active nests. The need for a permit may be avoided by removing the existing bridge structure prior to nest occupation by birds, or clearing nests from all structures before the nests become active in early spring. As a last resort, prevent birds from nesting

by installing a suitable netting device on the remaining structure prior to nesting activity. Include the cost for preventing nesting in the cost of Excavation for Structure B-13-192.

#### **4. Traffic.**

##### **A General**

Accomplish the construction sequence, including the associated traffic control as detailed in the Construction Staging section of the plans, and as described in this article.

Do not begin or continue any work that closes traffic lanes outside the allowed time periods specified in this article.

##### **B Traffic Operations**

###### All Stages

- Maintain a minimum lane width of 11-feet for USH 12 mainline and ramps.
- Maintain a minimum 1-foot shy distance from travel way to concrete barrier (temporary and permanent) or guardrail.
- Maintain a minimum 16-feet clear width for oversize / overweigh (OSOW) vehicles at all times.

###### Stage 1

- Westbound USH 12/18 traffic will be split around the workzone with two lanes north of the workzone and one lane south of the workzone.
- The contractor will be allowed to close down the single westbound USH 12/18 lane south of the split during allowed lane closure hours.

###### Stage 2

- Westbound USH 12/18 traffic will be split around the workzone with one lane north of the workzone and two lanes south of the workzone.
- The contractor will be allowed to close down both westbound USH 12/18 lanes south of the split during allowed lane closure hours.

###### Stage 3

- WB USH 12/18 traffic will be restored to original lane locations.

##### **C Lane/Ramp Night Closures**

Do not close traffic lanes (including ramps) outside the allowed time periods.

Request approval from the engineer for all lane closures at least three working days in advance of requested closure. A request does not constitute approval. Failure to obtain approval or reopen closed lanes at the required time shall be subject to lane rental charges specified in the Lane Rental Fee Assessment article.

No lane or shoulder closures will be permitted during events listed under article Holiday Work Restrictions.

Allowable lane closure hours are as follows:

Description			Direction	Lanes	Start	End
Monday Night	To	Friday Morning	EB/WB	Single	8:00 PM	6:00 AM
			EB/WB	Dual	10:00 PM	5:00 AM
Friday Night	To	Saturday Morning	EB/WB	Single	8:00 PM	8:00 AM
			EB/WB	Dual	11:00 PM	6:00 AM
Saturday Night	To	Sunday Morning	EB/WB	Single	8:00 PM	10:00 AM
			EB/WB	Dual	11:00 PM	8:00 AM
Sunday Night	To	Monday Morning	EB/WB	Single	7:00 PM	6:00 AM
			EB/WB	Dual	10:00 PM	5:00 AM

Nighttime closure to the westbound offramp to Park Street is allowed to occur concurrent with single lane closures.

#### **D Special Event Restrictions**

Shake the Lake, June 25 or July 2, 2016

- USH 12 Off Peak lane closures are restricted from Noon the day of the event to 5:00 AM the morning after the event.
- Maintain full access to the Rimrock Road and Park Street interchanges from Noon the day of the event to 5:00 AM the morning after the event.

University of Wisconsin home football games

- Off peak lane closures will not be permitted from five hours prior to game until five hours after the game.
- Maintain full access to the Rimrock Road and Park Street interchanges from five hours prior to game until five hours after the game.

#### **E Advance Notification**

Notify the Dane County EMS; Police and Fire for the City of Madison, City of Fitchburg and Town of Madison; City of Madison Traffic Engineering; Dane County Sheriff's Department and Dane County Highway Commissioner 48 hours in advance of all switchovers of traffic lanes and closures of existing ramps. Notifications must be given by 4:00 PM on Thursday for any such work to be done on the following Monday.

All entrance and exit ramps shall be posted seven calendar days in advance of their closure with dates and time of closure with a Portable Changeable Message Sign.

#### **Wisconsin Lane Closure System Advance Notification**

Provide the following advance notification to the engineer for incorporation into the Wisconsin Lane Closure System (LCS).

**TABLE 108-1 CLOSURE TYPE AND REQUIRED MINIMUM ADVANCE NOTIFICATION**

Closure type with height, weight, or width restrictions (available width, all lanes in one direction $\leq 16'$ )	MINIMUM NOTIFICATION
Lane and shoulder closures	14 calendar days
Full roadway closures	14 calendar days
System and service ramp closures	14 calendar days
Full system and service ramp closures	14 calendar days
Detours	14 calendar days
Closure type without height, weight, or width restrictions (available width, all lanes in one direction $> 16'$ )	MINIMUM NOTIFICATION
Lane and shoulder closures	3 business days
System and service ramp closures	3 business days
Modifying all closure types	3 business days

Discuss LCS completion dates and provide changes in the schedule to the engineer at weekly project meetings in order to manage closures nearing their completion date.  
108-057 (20150630)

## **F Traffic Control Signs**

*Add the following to standard spec 643.3.8.1:*

For signs mounted on portable sign supports, use supports that provide a minimum of 5 feet from the bottom of the sign to the pavement.

## **5. Lane Rental Fee Assessment.**

### **A General**

The contract designates some lane closures to perform the work. No Lane Rental Fee Assessments will be charged for closing lanes during the allowable lane closure hours. If a lane is closed outside of the allowable lane closure hours, the contractor will be subject to Lane Rental Fee Assessments. If a lane is obstructed at any time due to contractor operations, it is considered a closure. The purpose of lane rental is to enforce compliance of lane restrictions and discourage unnecessary closures.

The allowable lane closure hours are shown in the Traffic article.

Submit the dates of the proposed lane, ramp, and roadway restrictions to the engineer as part of the progress schedule. The contractor will coordinate lane, ramp, and roadway closures with any concurrent operations on adjacent roadways within 3 miles of the project.

If other projects are in the vicinity of this project, coordinate lane closures to run concurrent with lane closures on adjacent projects when possible. When lane closures on adjacent projects extend into the limits of this project, Lane Rental Fee Assessments will only occur if the closure facilitates work under this contract.

#### **A.1 Lane Rental Fee Assessment**

The Lane Rental Fee Assessment incurred for each lane closure, each ramp closure, and each full closure of a roadway, per direction of travel, is as follows:

<b>Time Period in excess of specified time</b>	<b>15 minute Lane Rental Charge (per lane)</b>	<b>Cumulative Lane Rental Charge (per lane)</b>
0 - 15 minutes	\$750	\$750
15 - 30 minutes	\$1,500	\$2,250
30 - 45 minutes	\$2,250	\$4,500
>45 minutes	\$3,000	\$7,500 and up

If the contractor fails to open lanes of traffic after 60 minutes from the specified times, a constant reduction of \$3,000 for each additional 15 minute increment, for each lane and each direction of traffic will be assessed until lanes are open to traffic.

The Lane Rental Fee Assessment represents the average cost of the interference and inconvenience to the road users for each closure. The Lane Rental Fee Assessment will be measured in 15-minute increments. All lane, roadway, or ramp closure event increments less than 15 minutes will be assessed as a 15-minute increment.

Lane Rental Fee Assessments will be made based on the applicable rate for any and all closures whether work is being performed or not. The engineer, or designated representative, will be the sole authority in determining time period length for the Lane Rental Fee Assessment.

Lane Rental Fee Assessments will not be assessed for closures due to crashes, accidents or emergencies not initiated by the contractor.

#### **B (Vacant)**

#### **C (Vacant)**

#### **D Measurement**

The department will assess Lane Rental Fee Assessment by the dollar under the administrative item Failing to Open Road to Traffic. The total dollar amount of Lane Rental Fee Assessment will be computed by multiplying the Lane Rental Assessment Rate by the number of 15-minute increments of each lane closure event as described above.

Lane Rental Fee Assessment will be in effect from the time of the Notice to Proceed until the department issues final acceptance.

**E (Vacant)**

**6. Utilities.**

This contract comes under the provision of Administrative Rule Trans 220.  
107-065 (20080501)

There are underground and overhead facilities located within the project limits. Coordinate construction activities with a call to Digger's Hotline or a direct call to the utilities that have facilities in the area as required per statutes. Use caution to ensure the integrity of underground facilities and maintain code clearances from overhead facilities at all times.

The following utility companies have facilities within the project; however, no adjustments are anticipated:

AT&T Electric Transmission  
City of Madison – Street Lighting  
City of Madison – Sewer  
MG&E – Electric  
MG&E – Gas  
Madison Water Utility – Water

**7. Other Contracts.**

The following projects will be under construction concurrently with the work under this contract:

Verona Road Interchange

Ongoing construction will be occurring on or near the USH 12/14 (Beltline) and USH 18/151 (Verona Road) interchange. Coordinate lane closures and traffic control sign placement with this project.

**8. Railroad Insurance and Coordination.**

**A Description**

Comply with standard spec 107.17 for all work affecting Wisconsin and Southern Railroad Company property and any existing tracks.

**A.1 Railroad Insurance Requirements**

In addition to standard spec 107.26, provide railroad protective liability insurance coverage as specified in standard spec 107.17.3. Insurance is filed in the name of Wisconsin and Southern Railroad Company.

Notify evidence of the required coverage, and duration to Ms. Jamie Wilson, Watco Companies, 315 W. 3<sup>rd</sup> Street, Pittsburg, KS 66762, TELEPHONE (620) 231-2230, email [jmwilson@watcocompanies.com](mailto:jmwilson@watcocompanies.com). Include the following information on the insurance document:

Project 1206-04-68  
Route Name USH 12, Dane County  
Crossing ID 177871Y  
Railroad Subdivision Evansville  
Railroad Milepost 135.57

#### **A.2 Work by Railroad**

The railroad will perform the work described in this section, except for work described in other special provisions and will be accomplished without cost to the contractor.

#### **A.3 Names and addresses of Railroad Representatives for Consultation and Coordination**

Contact Jamie Wilson, Watco Companies, 315 W. 3<sup>rd</sup> Street, Pittsburg, KS 66762, TELEPHONE (620) 231-2230, email [jmwilson@watcocompanies.com](mailto:jmwilson@watcocompanies.com), for consultation on railroad requirements during construction.

Amend standard spec 108.4 to include the railroad in the distribution of the initial bar chart, and monthly schedule updates. The bar chart shall specifically show work involving coordination with the railroad.

#### **A.4 Temporary Grade Crossing**

If a temporary grade crossing is desired, submit a written request to the railroad representative named in A.3 several weeks prior to the time needed. Approval is subject to the discretion of the railroad. The department has made no arrangements for a temporary grade crossing.

#### **A.5 Train Operation**

Approximately 2-4 through freight trains operate daily through the construction site. Through freight trains operate at up to 25 mph. No switching movements occur at this location.

### **9. Notice to Contractor, Notification of Demolition and/or Renovation No Asbestos Found.**

John Roelke, License Number AII-119523, inspected Structure B-13-192 for asbestos on August 21, 2013. Additional inspection of the concrete was completed by James Gondek, License Number AII-108099 on June 18, 2015. No regulated Asbestos Containing Material (RACM) was found on this structures. Copies of the inspection reports are available from: David Layton at [david.layton@dot.wi.gov](mailto:david.layton@dot.wi.gov) or (608) 246-3821.



In accordance with NR447 and DHS159, ensure that DNR or DHS receives a completed Notification of Demolition and/or Renovation (DNR Form 4500-113 (R 4/11), or subsequent revision) via U.S. mail, hand-delivery, or using the online notification system at least 10 working days prior to beginning any construction or demolition. Pay all associated fees. Provide a copy of the completed 4500-113 form to the engineer and DOT BTS-ESS attn: Hazardous Materials Specialist PO Box 7965, Madison, WI, 53707-7965. In addition, comply with all local or municipal asbestos requirements.

Use the following information to complete WisDNR form 4500-113:

- Site Name: Structure B-13-192, USH 12/18 Westbound (W Beltline) over WSOR
- Site Address: Section 35, Town 7N, Range 9E, Lat 43°02'15.26"N, Long 89°23'21.23"W, Town of Madison
- Ownership Information: WisDOT Division of Transportation System Development, Southwest Region, 2101 Wright St, Madison WI 53704-2583
- Contact: Greg Brecka
- Phone: (608) 246-2671
- Age: 54 years old. This structure was constructed in 1961.
- Area: 6,735 SF of deck

Insert the following paragraph in Section 6.g.:

- If asbestos not previously identified is found or previously non-friable asbestos becomes crumbled, pulverized, or reduced to a powder, stop work immediately, notify the engineer, and the engineer will notify the department's Bureau of Technical Services at (608) 266-1476 for an emergency response in accordance to standard spec 107.24. Keep material wet until it is abated or until it is determined to be non-asbestos containing material.

## **10. Public Convenience and Safety.**

*Revise standard spec 107.8(6) as follows:*

Operations are allowed for 24 hours a day.

## **11. Project Communication Enhancement Effort.**

Use the Project Communication Enhancement Effort (PCEE) tools on this contract. Coordinate with the department to modify the various published tools as necessary to meet the particular project needs and determine how to implement those tools under the contract. Ensure the full participation of the contractor and its principal subcontractors throughout the term of the contract.

Forms and associated guidance are published in the PCEE Manual available at the department's Highway Construction Contract Information (HCCI) web site at:

<http://roadwaystandards.dot.wi.gov/standards/admin/pcee-user-manual.doc>

105-005 (20090901)

**12. Incentive/Disincentive for Interim Completion of Work Rimrock Road WB Beltline Entrance Closure, Item 108.3100.S.01.**

**A General**

This item shall consist of either an incentive payment or a disincentive pay reduction as specified below.

The contractor shall complete all of the work necessary to complete Stage 1, Stage 2, and restore traffic on the Rimrock WB Beltline onramp within 25 calendar days.

Under this Incentive/Disincentive plan, no time extensions will be granted for adverse weather conditions; for delays in material deliveries; or for labor disputes unless it can be shown that such disputes are industry wide.

Each day shall be defined as a 24 hour period beginning at 12:01 AM.

The maximum incentive payment, as shown on the Schedule of Items, is for department accounting purposes. The actual incentive payment the contractor may receive shall be in accordance to section B of this provision.

Incentive payments will not be considered as part of the money value of the work completed for computing time extensions.

**B Incentive Payment**

The contractor shall be entitled to an incentive payment for completion of all of the work necessary to restore westbound beltline traffic to their normal lanes and reopen the westbound Beltline onramp from Rimrock Road, including all structure work and concrete pavement approach slabs within the project limits, on this contract within 25 calendar days or such extended time as may be allowed.

The incentive payment shall be paid at the rate of \$5,000 per calendar day for each day or portion thereof, of completion prior to 12:01 AM on the 26th calendar day of closure. The maximum amount of incentive payment shall not exceed \$40,000.

**C Disincentive Pay Reduction**

Should the contractor fail to complete all of the work and coordination measures necessary to restore westbound beltline traffic to their normal lanes and reopen the westbound Beltline onramp from Rimrock Road within 25 calendar days of closure, the contractor shall be liable to the department for a pay reduction in the amount of \$5,000 per day or portion thereof, for each calendar day the contract work remains incomplete beyond 25 calendar days. An entire calendar day will be charged for any period of time within a calendar day that the work remains incomplete beyond 12:01 AM.

If contract time expires before completing all work specified in the contract, additional liquidated damages according to standard spec 108.11 will be affixed in addition to the disincentive pay reduction.

#### **D Measurement and Payment**

Incentive/Disincentive for interim Completion of Work will be measured by the calendar day and will be paid for at the contract unit price per calendar day.

The unit price per day based on the incentive pay adjustment shall be compensation in full for completing the work as hereinbefore specified.

The unit price per day based on the disincentive pay reduction shall be assessed for failing to complete all the work as hereinbefore specified.

### **13. QMP Base Aggregate.**

#### **A Description**

##### **A.1 General**

- (1) This special provision describes contractor quality control (QC) sampling and testing for base aggregates, documenting those test results, and documenting related production and placement process changes. This special provision also describes department quality verification (QV), independent assurance (IA), and dispute resolution.
- (2) Conform to standard spec 301, standard spec 305, and standard spec 310 as modified here in this special provision. Apply this special provision to material placed under all of the Base Aggregate Dense and Base Aggregate Open Graded bid items, except do not apply this special provision to material classified as reclaimed asphaltic pavement placed under the Base Aggregate Dense bid items.
- (3) Do not apply this special provision to material placed under the Aggregate Detours, Salvaged Asphaltic Pavement Base, Breaker Run, Select Crushed, Pit Run, Subbase, or Riprap bid items.
- (4) Provide and maintain a quality control program, defined as all activities related to and documentation of the following:
  1. Production and placement control and inspection.
  2. Material sampling and testing.
- (5) Chapter 8 of the department's construction and materials manual (CMM) provides additional detailed guidance for QMP work and describes required sampling and testing procedures. The contractor may obtain the CMM from the department's web site at:

<http://roadwaystandards.dot.wi.gov/standards/cmm/index.htm>

##### **A.2 Contractor Testing for Small Quantities**

- (1) The department defines a small quantity, for each individual Base Aggregate bid item, as a plan quantity of 9000 tons or less of material as shown in the schedule of items under that bid item.

- (2) The requirements under this special provision apply equally to a small quantity for an individual bid item except as follows:

1. The contractor need not submit a full quality control plan but shall provide an organizational chart to the engineer including names, telephone numbers, and current certifications of all persons involved in the quality control program for material under affected bid items.
2. Divide the aggregate into uniformly sized sublots for testing as follows:

Plan Quantity	Minimum Required Testing
$\leq 1500$ tons	One test from production, load-out, or placement at the contractor's option <sup>[1]</sup>
$> 1500$ tons and $\leq 6000$ tons	Two tests of the same type, either from production, load-out, or placement at the contractor's option <sup>[1]</sup>
$> 6000$ tons and $\leq 9000$ tons	Three placement tests <sup>[2][3]</sup>

<sup>[1]</sup> If using production tests for acceptance, submit test results to the engineer for review prior to incorporating the material into the work. Production test results are valid for a period of 3 years.

<sup>[2]</sup> For 3-inch material, obtain samples at load-out.

<sup>[3]</sup> If the actual quantity overruns 9000 tons, create overrun sublots to test at a rate of one additional placement test for each 3000 tons, or fraction of 3000 tons, of overrun.

3. No control charts are required. Submit aggregate load-out and placement test results to the engineer within one business day of obtaining the sample. Assure that all properties are within the limits specified for each test.

4. Department verification testing is optional for quantities of 6000 tons or less.

- (3) Material represented by a subplot with any property outside the specification limits is nonconforming. The department may reject material or otherwise determine the final disposition of nonconforming material as specified in standard spec 106.5.

## **B Materials**

### **B.1 Quality Control Plan**

- (1) Submit a comprehensive written quality control plan to the engineer at or before the pre-construction meeting. Do not place base before the engineer reviews and comments on the plan. Construct the project as that plan provides.

- (2) Do not change the quality control plan without the engineer's review. Update the plan with changes as they become effective. Provide a current copy of the plan to the engineer and post in each of the contractor's laboratories as changes are adopted. Ensure that the plan provides the following elements:

1. An organizational chart with names, telephone numbers, current certifications and/or titles, and roles and responsibilities of QC personnel.
2. The process used to disseminate QC information and corrective action efforts to the appropriate persons. Include a list of recipients, the communication means that will be used, and action time frames.

3. A list of source and processing locations, section and quarter descriptions, for all aggregate materials requiring QC testing.
4. Test results for wear, sodium sulfate soundness, freeze/thaw soundness, and plasticity index of all aggregates requiring QC testing. Obtain this information from the region materials unit or from the engineer.
5. Descriptions of stockpiling and hauling methods.
6. Locations of the QC laboratory, retained sample storage, and where control charts and other documentation is posted.
7. An outline for resolving a process control problem. Include responsible personnel, required documentation, and appropriate communication steps.

## **B.2 Personnel**

- (1) Have personnel certified under the department's highway technician certification program (HTCP) perform sampling, testing, and documentation as follows:

<b>Required Certification Level:</b>	<b>Sampling or Testing Roles:</b>
Aggregate Technician IPP Aggregate Sampling Technician Aggregate Assistant Certified Technician (ACT-AGG)	Aggregate Sampling <sup>[1]</sup>
Aggregate Technician IPP Aggregate Assistant Certified Technician (ACT-AGG)	Aggregate Gradation Testing, Aggregate Fractured Particle Testing, Aggregate Liquid Limit and Plasticity Index Testing

<sup>[1]</sup> Plant personnel under the direct observation of an aggregate technician certified at level one or higher may operate equipment to obtain samples.

- (2) A certified technician must coordinate and take responsibility for the work an ACT performs. Have a certified technician ensure that all sampling and testing is performed correctly, analyze test results, and post resulting data. No more than one ACT can work under a single certified technician.

## **B.3 Laboratory**

- (1) Perform QC testing at a department-qualified laboratory. Obtain information on the Wisconsin laboratory qualification program from:

Materials Management Section  
3502 Kinsman Blvd.  
Madison, WI 53704  
Telephone: (608) 246-5388

<http://www.dot.state.wi.us/business/engrserv/lab-qualification.htm>

## **B.4 Quality Control Documentation**

### **B.4.1 General**

- (1) Submit base aggregate placement documentation to the engineer within 10 business days after completing base placement. Ensure that the submittal is complete, neatly organized, and includes applicable project records and control charts.

#### **B.4.2 Records**

- (1) Document all placement observations, inspection records, and control adjustments daily in a permanent field record. Also include all test results in the project records. Provide test results to the engineer within 6 hours after obtaining a sample. For 3-inch base, extend this 6-hour limit to 24 hours. Post or distribute tabulated results using a method mutually agreeable to the engineer and contractor.

#### **B.4.3 Control Charts**

- (1) Plot gradation and fracture on the appropriate control chart as soon as test results are available. Format control charts according to CMM 8.30. Include the project number on base placement control charts. Maintain separate control charts for each base aggregate size, source or classification, and type.
- (2) Provide control charts to the engineer within 6 hours after obtaining a sample. For 3-inch base, extend this 6-hour limit to 24 hours. Post or distribute charts using a method mutually agreeable to the engineer and contractor. Update control charts daily to include the following:
  1. Contractor individual QC tests.
  2. Department QV tests.
  3. Department IA tests.
  4. Four-point running average of the QC tests.
- (3) Except as specified under B.8.2.1 for nonconforming QV tests, include only QC tests in the running average. The contractor may plot process control or informational tests on control charts, but do not include these tests, conforming QV tests, or IA tests in the running average.

#### **B.5 Contractor Testing**

- (1) Test gradation, fracture, liquid limit and plasticity index during placement for each base aggregate size, source or classification, and type.
- (2) Test gradation once per 3000 tons of material placed. Determine random sample locations and provide those sample locations to the engineer. Obtain samples after the material has been bladed, mixed, and shaped but before compacting; except collect 3-inch samples from the stockpile at load-out. Do not sample from material used to maintain local traffic or from areas of temporary base that will not have an overlying pavement. On days when placing only material used to maintain local traffic or only temporary base that will not have an overlying pavement, no placement testing is required.
- (3) Split each contractor QC sample and identify it according to CMM 8.30. Retain the split for 7 calendar days in a dry, protected location. If requested for department comparison testing, deliver the split to the engineer within one business day.

- (4) The engineer may require additional sampling and testing to evaluate suspect material or the technician's sampling and testing procedures.
- (5) Test fracture for each gradation test until the fracture running average is above the lower warning limit. Subsequently, the contractor may reduce the frequency to one test per 10 gradation tests if the fracture running average remains above the warning limit.
- (6) Test the liquid limit and plasticity index for the first gradation test. Subsequently, test the liquid limit and plasticity index a minimum of once per 10 gradation tests.

## **B.6 Test Methods**

### **B.6.1 Gradation**

- (1) Test gradation using a washed analysis conforming to the following as modified in CMM 8.60:  
 Gradation..... AASHTO T 27  
 Material finer than the No. 200 sieve..... AASHTO T 11
- (2) For 3-inch base, if 3 consecutive running average points for the percent passing the No. 200 sieve are 8.5 percent or less, the contractor may use an unwashed analysis. Wash at least one sample out of 10. If a single running average for the percent passing the No. 200 sieve exceeds 8.5 percent, resume washed analyses until 3 consecutive running average points are again 8.5 percent passing or less.
- (3) Maintain a separate control chart for each sieve size specified in standard spec 305 or standard spec 310 for each base aggregate size, source or classification, and type. Set control and warning limits based on the standard specification gradation limits as follows:
  1. Control limits are at the upper and lower specification limits.
  2. There are no upper warning limits for sieves allowing 100 percent passing and no lower control limits for sieves allowing 0 percent passing.
  3. Dense graded warning limits, except for the No. 200 sieve, are 2 percent within the upper and lower control limits. Warning limits for the No. 200 sieve are set 0.5 percent within the upper and lower control limits.
  4. Open graded warning limits for the 1-inch, 3/8-inch, and No. 4 sieves are 2 percent within the upper and lower control limits. Upper warning limits for the No. 10, No. 40, and No. 200 sieves are 1 percent inside the upper control limit.

### **B.6.2 Fracture**

- (1) Test fracture conforming to CMM 8.60. The engineer will waive fractured particle testing on quarried stone.
- (2) Maintain a separate fracture control chart for each base aggregate size, source or classification, and type. Set the lower control limit at the contract specification limit, either specified in another special provision or in table 301-2 of standard spec

301.2.4.5. Set the lower warning limit 2 percent above the lower control limit. There are no upper limits.

### **B.6.3 Liquid Limit and Plasticity**

- (1) Test the liquid limit and plasticity according to AASHTO T 89 and T 90.
- (2) Ensure the material conforms to the limits specified in standard spec table 301-2.

## **B.7 Corrective Action**

### **B.7.1 General**

- (1) Consider corrective action when the running average trends toward a warning limit. Take corrective action if an individual test exceeds the contract specification limit. Document all corrective actions both in the project records and on the appropriate control chart.

### **B.7.2 Placement Corrective Action**

- (1) Do not blend additional material on the roadbed to correct gradation problems.
- (2) Notify the engineer whenever the running average exceeds a warning limit. When 2 consecutive running averages exceed a warning limit, the engineer and contractor will discuss appropriate corrective action. Perform the engineer's recommended corrective action and increase the testing frequency as follows:
  1. For gradation, increase the QC testing frequency to at least one randomly sampled test per 1000 tons placed.
  2. For fracture, increase the QC testing frequency to at least one test per gradation test.
- (3) If corrective action improves the property in question such that the running average after 4 additional tests is within the warning limits, the contractor may return to the testing frequency specified in B.5.3. If corrective action does not improve the property in question such that the running average after 4 additional individual tests is still in the warning band, repeat the steps outlined above starting with engineer notification.
- (4) If the running average exceeds a control limit, material starting from the first running average exceeding the control limit and ending at the first subsequent running average inside the control limit is nonconforming and subject to pay reduction.
- (5) For individual test results significantly outside the control limits, notify the engineer, stop placing base, and suspend other activities that may affect the area in question. The engineer and contractor will jointly review data, data reduction, and data analysis; evaluate sampling and testing procedures; and perform additional testing as required to determine the extent of potentially unacceptable material. The engineer may direct the contractor to remove and replace that material. Individual test results are significantly outside the control limits if meeting one or more of the following criteria:



1. A gradation control limit for the No. 200 sieve is exceeded by more than 3.0 percent.
2. A gradation control limit for any sieve, except the No. 200, is exceeded by more than 5.0 percent.
3. The fracture control limit is exceeded by more than 10.0 percent.

## **B.8 Department Testing**

### **B.8.1 General**

- (1) The department will conduct verification testing to validate the quality of the product and independent assurance testing to evaluate the sampling and testing. The department will provide the contractor with a listing of names and telephone numbers of all QV and IA personnel for the project, and provide test results to the contractor within 2 business days after the department obtains the sample.

### **B.8.2 Verification Testing**

#### **B.8.2.1 General**

- (1) The department will have an HTCP technician, or ACT working under a certified technician, perform QV sampling and testing. Department verification testing personnel must meet the same certification level requirements specified in B.2 for contractor testing personnel for each test result being verified. The department will notify the contractor before sampling so the contractor can observe QV sampling.
- (2) The department will conduct QV tests of each base aggregate size, source or classification, and type during placement conforming to the following:
  1. One non-random test on the first day of placement.
  2. At least one random test per 30,000 tons, or fraction of 30,000 tons, placed.
- (3) The department will sample randomly, at locations independent of the contractor's QC work, collecting one sample at each QV location. The department will collect QV samples after the material has been bladed, mixed, and shaped but before compacting; except, for 3-inch aggregates, the department will collect samples from the stockpile at load-out. The department will split each sample, test half for QV, and retain half.
- (4) The department will conduct QV tests in a separate laboratory and with separate equipment from the contractor's QC tests. The department will use the same methods specified for QC testing.
- (5) The department will assess QV results by comparing to the appropriate specification limits. If QV test results conform to the specification, the department will take no further action. If QV test results are nonconforming, add the QV to the QC test results as if it were an additional QC test.

#### **B.8.3 Independent Assurance**

- (1) Independence assurance is unbiased testing the department performs to evaluate the department's QV and the contractor's QC sampling and testing including personnel qualifications, procedures, and equipment. The department will perform an IA review

according to the department's independent assurance program. That review may include one or more of the following:

1. Split sample testing.
  2. Proficiency sample testing.
  3. Witnessing sampling and testing.
  4. Test equipment calibration checks.
  5. Reviewing required worksheets and control charts.
  6. Requesting that testing personnel perform additional sampling and testing.
- (2) If the department identifies a deficiency, and after further investigation confirms it, correct that deficiency. If the contractor does not correct or fails to cooperate in resolving identified deficiencies, the engineer may suspend placement until action is taken. Resolve disputes as specified in B.9.

### **B.9 Dispute Resolution**

- (1) The engineer and contractor should make every effort to avoid conflict. If a dispute between some aspect of the contractor's and the engineer's testing program does occur, seek a solution mutually agreeable to the project personnel. The department and contractor may review the data, examine data reduction and analysis methods, evaluate sampling and testing procedures, and perform additional testing. Use ASTM E 178 to evaluate potential statistically outlying data.
- (2) Production test results, and results from other process control testing, may be considered when resolving a dispute.
- (3) If the project personnel cannot resolve a dispute, and the dispute affects payment or could result in incorporating non-conforming product, the department will use third party testing to resolve the dispute. The department's central office laboratory, or a mutually agreed on independent testing laboratory, will provide this testing. The engineer and contractor will abide by the results of the third party tests. The party in error will pay service charges incurred for testing by an independent laboratory. The department may use third party test results to evaluate the quality of questionable materials and determine the appropriate payment. The department may reject material or otherwise determine the final disposition of nonconforming material as specified in standard spec 106.5.

### **C (Vacant)**

### **D (Vacant)**

### **E Payment**

- (1) Costs for all sampling, testing, and documentation required under this special provision are incidental to this work. If the contractor fails to perform the work required under this special provision, the department may reduce the contractor's pay. The department will administer pay reduction under the non-performance of QMP administrative item.

- (2) For material represented by a running average exceeding a control limit, the department will reduce pay by 10 percent of the contract price for the affected Base Aggregate bid items listed in subsection A. The department will administer pay reduction under the Nonconforming QMP Base Aggregate Gradation or Nonconforming QMP Base Aggregate Fracture Administrative items. The department will determine the quantity of nonconforming material as specified in B.7.2.

301-010 (20100709)

## **14. Nighttime Work Lighting-Stationary.**

### **A Description**

Provide portable lighting as necessary to complete nighttime work. Nighttime operations consist of work specifically scheduled to occur after sunset and before sunrise.

### **B (Vacant)**

### **C Construction**

#### **C.1 General**

This provision shall apply when providing, maintaining, moving, and removing portable light towers and equipment-mounted lighting fixtures for nighttime stationary work operations, for the duration of nighttime work on the contract.

At least 14 days prior to the nighttime work, furnish a lighting plan to the engineer for review and acceptance. Address the following in the plan:

- Layout, including location of portable lighting – lateral placement, height, and spacing. Clearly show on the layout the location of all lights necessary for every aspect of work to be done at night.
- Specifications, brochures, and technical data of all lighting equipment to be used.
- The details on how the luminaires will be attached.
- Electrical power source information.
- Details on the louvers, shields, or methods to be employed to reduce glare.
- Lighting calculations. Provide illumination with average to minimum uniformity ratio of 5:1 or less throughout the work area.
- Detail information on any other auxiliary equipment.

#### **C.2 Portable Lighting**

Provide portable lighting that is sturdy and free standing and does not require any guy wires, braces, or any other attachments. Furnish portable lighting capable of being moved as necessary to keep up with the construction project. Position the portable lighting and trailers to minimize the risk of being impacted by traffic on the roadway or by construction traffic or equipment. Provide lightning protection for the portable lighting. Portable lighting shall withstand up to 60 mph wind velocity. If portable generators are used as a power source, furnish adequate power to operate all required lighting equipment without any interruption during the nighttime work. Provide wiring that is weatherproof

and installed according to local, state, federal (NECA and OSHA) requirements. Equip all power sources with a ground-fault circuit interrupter to prevent electrical shock.

### **C.3 Light Level and Uniformity**

Position (spacing and mounting height) the luminaires to provide illumination with an average to minimum uniformity ratio of 5:1 or less throughout the work area. Illuminate the area as necessary to incorporate construction vehicles, equipment, and personnel activities.

### **C.4 Glare Control**

Design, install, and operate all lighting supplied under these specifications to minimize or avoid glare that interferes with all traffic on the roadway or that causes annoyance or discomfort for properties adjoining the roadway. Locate, aim, and adjust the luminaires to provide the adequate level of illumination and the specified uniformity in the work area without the creation of objectionable glare.

Provide louvers, shields, or visors, as needed, to reduce any objectionable levels of glare. As a minimum, ensure the following requirements are met to avoid objectionable glare on the roadways open to traffic in either direction or for adjoining properties:

Aim tower-mounted luminaires, either parallel or perpendicular to the roadway, so as to minimize light aimed toward approaching traffic.

Aim all luminaires such that the center of beam axis is no greater than 60 degrees above vertical (straight down).

If lighting does not meet above-mentioned criteria, adjust the lighting within 24 hours.

### **C.5 Continuous Operation**

Provide and have available sufficient fuel, spare lamps, generators, and qualified personnel to ensure that the lights will operate continuously during nighttime operation. In the event of any failure of the lighting system, discontinue the operation until the adequate level of illumination is restored. Move and remove lighting as necessary.

## **D (Vacant)**

## **E Payment**

Costs for furnishing a lighting plan, and for providing, maintaining, moving, and removing portable lighting, tower mounted lighting, and equipment-mounted lighting required under this special provision are incidental to the contract.

**15. Pavement Marking Grooved Wet Reflective Contrast Tape 8-Inch, Item 646.0843.S.**

**A Description**

This special provision describes furnishing, grooving and installing preformed wet reflective pavement marking contrast tape for grooved applications as shown on the plans, according to standard spec 646, and as hereinafter provided.

**B Materials**

Furnish wet reflective pavement marking contrast tape and adhesive material, per manufacturer's recommendation if required, from the department's approved products list.

Furnish a copy of the manufacturer's recommendations to the engineer before preparing the pavement marking grooves.

**C Construction**

**C.1 General**

For quality assurance, provide the engineer and the region's Marking Section evidence of manufacturer training in the proper placement and installation of pavement marking contrast tape.

Plane the grooved lines according to details in the plan and per manufacturer's recommendations. Use grooving equipment with a free-floating, independent cutting head. Plane a minimum number of passes to create a grooved surface per manufacturer's recommendations.

**C.2 Groove Depth**

Cut the groove to a depth of 120 mils  $\pm$  10 mils from the pavement surface or, if tined, from the high point of the tined surface. To measure the depth, the contractor may use a depth plate placed in the groove and a straightedge placed across the plate and groove, or the contractor may use a straightedge placed perpendicular to the groove. The department may periodically check groove depths.

**C.3 Groove Width – Longitudinal Markings**

Cut the groove one-inch wider than the width of the tape.

**C.4 Groove Position**

Position the groove edge according to plan details. Groove a minimum of 4 inches, but not greater than, 12 inches from both ends of the tape segment. Achieve straight alignment with the grooving equipment.

## **C.5 Groove Cleaning**

### **C.5.1 Concrete**

Cooling the cutting head with water may be necessary for some applications and equipment. If cooling water is necessary, flush the groove immediately with high-pressure water after cutting to remove any build-up of cement dust and water slurry. If this is not done, the slurry may harden in the groove.

If water is used in the grooving process, allow the groove to dry a minimum of 24 hours after groove cleaning, and prior to pavement marking application. The groove surface shall be clean and dry before applying the adhesive, and the pavement marking tape. Use a high-pressure air blower with at least 185 ft<sup>3</sup>/min air flow and 120 psi air pressure to clean the groove; use of the air blower does not decrease the amount of time required for the groove to dry.

### **C.5.2 New Asphalt**

Groove pavement five or more days after paving.

Use a high-pressure air blower with at least 185 ft<sup>3</sup>/min air flow and 90 psi air pressure to clean the groove.

### **C.5.3 Existing Asphalt**

Check for structural integrity in supporting grooving operations. If the structural integrity of the asphalt pavement is inadequate to support grooving operations, immediately notify the engineer.

Use a high-pressure air blower with at least 185 ft<sup>3</sup>/min air flow and 90 psi air pressure to clean the groove.

## **C.6 Tape Application**

Apply the tape when both the air and surface temperature are 40 degrees F and rising.

Apply tape in the groove as per manufacturer's recommendations. If manufacturer's recommendations require surface preparation adhesive

- For the Southeast Region and the ozone non-attainment Northeast Region counties of Sheboygan, Manitowoc, and Kewaunee:
- Apply SPA-60 during May 1 to September 30, both dates inclusive due to Volatile Organic Compound Limitations..
- Apply P-50 during October 1 to April 30, both dates inclusive. –
- For the remainder counties:
- Apply either adhesive.

Refer to the manufacturer's instructions for determining when the surface preparation adhesive is set.

Tamp the wet reflective pavement marking contrast tape with a tamper cart roller, with a minimum of a 200-lb load, cut to fit the groove. Tamp a minimum of three complete cycles (6 passes) with grooved modified tamper roller cart.

#### **D Measurement**

The department will measure Pavement Marking Grooved Wet Reflective Contrast Tape 8-inch for grooved applications in length by the linear foot of tape placed according to the contract and accepted.

#### **E Payment**

The department will pay for measured quantities at the contract unit price under the following bid items:

ITEM NUMBER	DESCRIPTION	UNIT
646.0843.S	Pavement Marking Grooved Wet Reflective Contrast Tape 8-Inch	LF

Payment is full compensation for cleaning and preparing the pavement surface; furnishing and installing the material; and for removing temporary pavement marking, if necessary.

646-022 (20120615)

### **16. Temporary Thrie Beam Connection, SPV.0060.001.**

#### **A Description**

This special provision describes providing Temporary Thrie Beam Connection and angle plate at the gaps or connection locations in Concrete Barrier Temporary Precast in conforming to standard spec 506 and standard spec 614 with the connection locations detailed in the plans.

#### **B Materials**

Furnish and install Temporary Thrie Beam Connection, angle plate, mechanical anchors, and thrie beam terminal connectors according to the pertinent requirements of standard spec 506 and standard spec 614.

#### **C Construction**

Construct Temporary Thrie Beam Connection as indicated on the plan or required by the engineer.

#### **D Measurement**

The department will measure Temporary Thrie Beam Connection as each individual unit, acceptably completed.

**E Payment**

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0060.001	Temporary Thrie Beam Connection	Each

Payment is full compensation for providing Temporary Thrie Beam Connection, including mechanical anchors, thrie beam terminal connectors, angle plate, and removal upon completion.

**17. Repositioning Traffic Control Devices for Mainline Closures, Item SPV.0060.002.****A Description**

This special provision describes repositioning traffic control devices as required to close mainline lanes to traffic.

**B Materials**

Use traffic control devices conforming to standard spec 643 that have been delivered and placed within the project limits under other contract bid items.

**C Construction**

Reposition traffic control devices as required to close one or more lanes to public traffic along the mainline roadway. Monitor and maintain the traffic control device configuration for the duration of the closure. Upon conclusion of the allowable lane closure timeframes, return the devices to their previous configuration or an engineer-approved position within the project limits.

**D Measurement**

The department will measure Repositioning Traffic Control Devices for Mainline Closures as each individual reposition/return cycle acceptably completed, measured as the number of reposition/return cycles the engineer deems necessary to conform to the traffic control plan, contract staging plan, and other contract requirements. The department will not measure additional moves or configuration changes as might be required solely to accommodate the contractor's operations.

The department will measure each change in configuration on a nightly basis regardless of the overall duration of the interruption to traffic at that location. Each direction of travel will be measured separately.

Changes between single and double lane closures during the same night are incidental to the contract. Longitudinal gaps in lane closures shall not constitute measurement of multiple closures, and are incidental to the contract.



## **E Payment**

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0060.002	Repositioning Traffic Control Devices for Mainline Closures	Each

Payment is full compensation for providing the required closure including placing and maintaining the required closure configuration as well as returning the traffic control devices to their previous or other engineer-approved location when the closure is no longer required. The department will pay separately for furnishing, and maintaining the condition of, required traffic control devices under other contract bid items.

## **18. Traffic Channelizing Curb System Furnished, Item SPV.0090.001, Installed, Item SPV.0090.002.**

### **A Description**

This special provision describes providing, maintaining and removing temporary traffic channelizing curb system at locations the plans show or the engineer directs.

### **B Materials**

#### **B.1 General**

Furnish a temporary traffic channelizing curb system with a base component consisting of interlocking units and flexible vertical component. The system shall be constructed of material resistant to ultraviolet light, ozone, and hydrocarbons. The units shall interface with each other to form a temporary continuous longitudinal lane channelizing system separating traffic lanes. Provide a system that is fastened to or placed on the underlying pavement surface according to the manufacturer's recommendations. The system shall be continuous interlocking modules and allow for cross drainage under or around the curb modules.

The channelizing system shall meet the requirement of National Cooperative Highway Research Program (NCHRP) Report 350 or the Manual for Assessing Safety Hardware (MASH). Submit a copy of the FHWA approval letter to the engineer.

#### **B.2 Curb Unit**

The curb sections shall be approximately 12" wide and shall not exceed 4" in height. Curb sides shall be sloped to allow crossover by emergency vehicles. Normal curb sections shall be a minimum of 40 inches and a maximum of 48 inches long. The transition sections shall be 18 inches long and shall not exceed 2 inches in height at the exposed nose. The units shall be yellow if used in a work zone installation or a permanent installation adjacent to yellow pavement markings, and white if used in a permanent installation adjacent to white pavement markings.

### **B.3 Vertical Component**

Provide at least one vertical component for every four modular curb units or 12 feet to 14 feet uniformly spaced along the channelizing system. The vertical component shall be orange in color if used in a work zone installation. The component shall be yellow if used in a permanent installation adjacent to yellow pavement markings, and white if used in a permanent location adjacent to white pavement markings.

The vertical component shall be a minimum of 36 inches and a maximum of 48 inches in height measured from the pavement surface. The width should be approximately 8 to 9 inches for elliptical designs and 4 to 6 inches for round (tubular) designs.

The vertical component shall be equipped with reflective sheeting or with reflective stripes conforming to standard spec 637.2.2.2. Where stripes are used, the stripes shall consist of two 3-inch wide bands placed a maximum of 2 inches from the top with a maximum of 4 inches between the bands. The base component shall be equipped with reflectors.

## **C Construction**

### **C.1 Installation**

Install the channelizing system according to the manufacturer's recommendations. Remove all conflicting pavement marking, raised pavement marker and delineator posts in the location where the channelizing system is to be installed. Follow manufacturer's installation procedures regarding anchoring systems into the various types of roadway surfaces. Only use anchors and hardware provided by the manufacturer.

### **C.2 Relocate**

Relocate the channelizing system at locations the plans show or the engineer directs.

### **C.3 Maintenance**

Replace damaged retroreflecting sheeting, misaligned curb units, damaged vertical components, and anchorbolts within 24 hours after the damage is reported to the contractor.

### **C.4 Removal**

Repair all holes left in pavement when the temporary traffic channelizing curb system is removed. Holes shall be filled with an engineer-approved non-shrink grout.

Upon completion of the project, remove the channelizing system. The temporary channelizing system shall remain the property of the contractor for systems used in temporary traffic control applications.

## **D Measurement**

The department will measure Traffic Channelizing Curb System Furnished by linear foot, acceptably completed, measured as the maximum linear footage of Traffic Control Channelizing Curb System required on the project site at any one time.

The department will measure Traffic Control Channelizing Curb System Installed by the linear foot, acceptably completed, measured along the base of the curb after each installation for each contract-identified or engineer-directed initial installation. The department will also measure subsequent contract-identified or engineer-directed reinstallations. The department will not measure installations made solely to accommodate the contractor's means and methods.

#### **E Payment**

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0090.001	Traffic Channelizing Curb System Furnished	LF
SPV.0090.002	Traffic Channelizing Curb System Installed	LF

Payment is full compensation for delivering, installing, maintaining, and removing the channelizing systems.

### **19. Temporary Pavement Marking Wet Reflective Contrast Removable Tape 4-Inch, Item SPV.0090.003; 8-Inch, Item SPV.0090.004.**

#### **A Description**

This special provision describes furnishing, and installing preformed wet reflective pavement marking contrast removable tape for applications as shown on the plans, according to standard spec 649, and as hereinafter provided.

#### **B Materials**

Furnish wet reflective pavement marking contrast removable tape and adhesive material, per manufacturer's recommendation if required, from the department's approved products list and according to standard spec 649.

#### **C Construction**

##### **C.1 General**

For quality assurance, provide the engineer and the region's Marking Section evidence of manufacturer training in the proper placement and installation of pavement marking contrast tape.

##### **C.6 Tape Application**

Apply the tape when both the air and surface temperature are 40 degrees F and rising.

Apply tape per manufacturer's recommendations and according to standard spec 649. Refer to the manufacturer's instructions for determining when the surface preparation adhesive is set.

**D Measurement**

The department will measure Temporary Pavement Marking Wet Reflective Contrast Removable Tape (Width) for applications in length by the linear foot of tape placed, acceptably completed.

**E Payment**

The department will pay for measured quantities at the contract unit price under the following bid items:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0090.003	Temporary Pavement Marking Wet Reflective Contrast Removable Tape 4-In	LF
SPV.0090.004	Temporary Pavement Marking Wet Reflective Contrast Removable Tape 8-In	LF

Payment is full compensation for cleaning and preparing the pavement surface; furnishing and installing the material; and for removing temporary pavement marking, if necessary.

**20. Traffic Control Gawk Screen Furnished, Item SPV.0090.005; Installed, Item SPV.0090.006.**

**A Description**

This special provision describes furnishing and installing gawk screen on concrete barrier and removal upon completion of the project.

**B Materials**

Furnish polymer concrete colored Armocast Guardian Gawk-Glare Screen and all necessary hardware and materials to install the glare screen.

**C Construction**

Furnish and deliver gawk screen to worksites within the project.

Install the screen in accordance to the manufacturer's recommendations at contract-identified locations or as the engineer directs. Maintain the screen during construction. Repair or replace any portion of the screen that is damaged during construction as directed by the engineer.

Remove screen upon project completion. If attached to permanent concrete barrier or concrete parapet, fill all anchor holes with an epoxy from the departments approved products list.

**D Measurement**

The department will measure Traffic Control Gawk Screen Furnished by the linear foot, acceptably completed, measured as the maximum linear footage of gawk screen required on the project site at any one time.

The department will measure Traffic Control Gawk Screen Installed by the linear foot, acceptably completed, measured along the base of the screen after each installation for each contract-identified or engineer-directed initial installation. The department will also measure subsequent contract-identified or engineer-directed reinstallations. The department will not measure installations made solely to accommodate the contractor's means and methods.

#### **E Payment**

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0090.005	Traffic Control Gawk Screen Furnished	LF
SPV.0090.006	Traffic Control Gawk Screen Installed	LF

Payment is full compensation for providing gawk screen, initial delivery, trucking between worksites, each installation, and removing after contract completion; and for furnishing all hardware necessary to install the screen.

### **21. Removing Pavement Markings Water Blasting, Item SPV.0090.007.**

#### **A Description**

This special provision describes removing pavement markings by water blasting. Conform to standard spec 646 as modified in this special provision.

#### **B (Vacant)**

#### **C Construction**

Use water blasting to remove the following, as shown on the plan and directed by the engineer:

- Markings in areas of temporary traffic shifts.
- Markings on bridge decks.
- Temporary markings on the final pavement surface.

Completely remove pavement marking using a truck mounted ultra high pressure pump and water tank capable of delivering a minimum of 30,000 psi and up to 40,000 psi to waterjet nozzles.. Use equipment with a vacuum recovery system that contains wastewater and debris to provide a clean, damp-dry surface, without a secondary cleanup operation. Do not scar or damage the pavement during the removal process. Limit water blasting to when the ambient temperature is at least 36 F and rising.

Properly dispose of the accumulated material off site.

#### **D Measurement**

The department will measure Removing Pavement Markings Water Blasting by the linear foot, up to a single 8-inch wide line, acceptably completed.

**E Payment**

The department will pay for measured quantities at the contract unit price under the following bid items:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0090.007	Removing Pavement Markings Water Blasting	LF

Payment is full compensation for removal and disposal of all materials.

**22. Concrete Pavement Approach Slab HES Special, Item SPV.0180.001.****A Description**

Furnish and install Concrete Pavement Approach Slab HES Special in accordance to the pertinent provisions of standard spec 415, as shown on the plans, construction details and as hereinafter provided.

**B Materials**

Conform to standard spec 415.

**C Construction**

Conform to standard spec 415. Conform to the construction detail, Concrete Pavement Approach Slab HES Special, for Reinforcement Positioning Detail of Section A-A and Bend Detail Bottom Reinforcement for Section B-B. All other construction shall conform to the standard detail drawings.

**D Measurement**

The department will measure Concrete Pavement Approach Slab HES Special as each square yard, acceptably completed.

**E Payment**

The department will pay for measured quantities at the contract unit price under the following bid items:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0180.001	Concrete Pavement Approach Slab HES Special	SY

Payment is full compensation for furnishing all requirements as specified in standard spec 415.

## **ADDITIONAL SPECIAL PROVISION 4**

### **Payment to First-Tier Subcontractors**

Within 10 calendar days of receiving a progress payment for work completed by a subcontractor, pay the subcontractor for that work. The prime contractor may withhold payment to a subcontractor if, within 10 calendar days of receipt of that progress payment, the prime contractor provides written notification to the subcontractor and the department documenting "just cause" for withholding payment.

The prime contractor may also withhold routine retainage from payments due subcontractors.

### **Payment to Lower-Tier Subcontractors**

Ensure that subcontracting agreements at all tiers provide prompt payment rights to lower-tier subcontractors that parallel those granted first-tier subcontractors in this provision.

### **Release of Routine Retainage**

After granting substantial completion the department may reduce the routine retainage withheld from the prime contractor to 75 percent of the original total amount retained.

When the Department sends the semi-final estimate the department may reduce the routine retainage withheld from the prime contractor to 10 percent of the original total amount retained.

Within 30 calendar days of receiving the semi-final estimate from the department, submit written certification that subcontractors at all tiers are paid in full for acceptably completed work and that no routine retainage is being withheld. The department will pay the prime contractor in full and reduce the routine retainage withheld from the prime contractor to zero when the department approves the final estimate.

This special provision does not limit the right of the department, prime contractor, or subcontractors at any tier to withhold payment for work not acceptably completed or work subject to an unresolved contract dispute.





**ADDITIONAL SPECIAL PROVISION 6****ASP 6 - Modifications to the standard specifications**

Make the following revisions to the standard specifications:

---

**450.3.2.1 General**

Replace the entire text with the following effective with the January 2015 letting:

- (1) Do not place asphaltic mixture when the air temperature approximately 3 feet above grade, in shade, and away from artificial heat sources is less than 36 F for upper layers or 32 F for lower layers unless the engineer allows in writing. The contractor should place HMA pavement for projects on or north of STH 29 between May 1 and October 15 inclusive and for projects south of STH 29 between April 15 and November 1 inclusive. Notify the engineer at least one business day before paving.
  - (2) Unless the contract specifies otherwise, conform to the following:
    - Keep the road open to all traffic during construction.
    - Prepare the existing foundation for treatment as specified in 211.
    - Incorporate loose roadbed aggregate as a part of preparing the foundation, in shoulder construction, or dispose of as the engineer approves.
  - (3) Place asphaltic mixture only on a prepared, firm, and compacted base, foundation layer, or existing pavement substantially surface-dry and free of loose and foreign material. Do not place over frozen subgrade or base, or where the roadbed is unstable.
- 

**450.5 Payment**

Replace the entire text with the following effective with the May 2015 letting:

- (1) All costs of furnishing, maintaining, and operating the truck scale or other weighing equipment and furnishing the weigh tickets are incidental to the contract.
  - (2) Nonconforming material allowed to remain in place is subject to price adjustment under 105.3.2.
  - (3) Full-depth sawing to remove integrally placed safety edge where not required is incidental to the contract.
  - (4) The contractor is responsible for the quality of HMA pavement placed in cold weather. If because of an excusable compensable delay under 108.10.3, the engineer directs the contractor to pave when the temperature is less than 36 F for the upper layer or less than 32 F for lower layers, the department:
    - Will relieve the contractor of responsibility for damage and defects the engineer attributes to cold weather paving.
    - Will not assess disincentives for density or ride.
- 

**455.3.2.1 General**

Replace the paragraphs one and two with the following effective with the January 2015 letting:

- (1) Apply tack coat only when the air temperature is 32 F or more unless the engineer approves otherwise in writing. Before applying tack coat ensure that the surface is dry and reasonably free of loose dirt, dust, or other foreign matter. Do not apply if weather or surface conditions are unfavorable or before impending rains.
- (2) Use tack material of the type and grade the contract specifies. The contractor may, with the engineer's approval, dilute tack material as allowed under 455.2.4. Provide calculations using the asphalt content as-received from the supplier and subsequent contractor dilutions to show that as-placed material has 50 percent or more residual asphalt content. Apply at 0.050 to 0.070 gallons per square yard, after dilution, unless the contract designates otherwise. The engineer may adjust the application rate based on surface conditions. Limit application each day to the area the contractor expects to pave during that day.

**460.2.2.3 Aggregate Gradation Master Range**

*Replace paragraph one with the following effective with the December 2014 letting:*

- (1) Ensure that the aggregate blend, including recycled material and mineral filler, conforms to the gradation requirements in table 460-1. The values listed are design limits; production values may exceed those limits.

**TABLE 460-1 AGGREGATE GRADATION MASTER RANGE AND VMA REQUIREMENTS**

SIEVE	PERCENTS PASSING DESIGNATED SIEVES						
	NOMINAL SIZE						
	37.5 mm	25.0 mm	19.0 mm	12.5 mm	9.5 mm	SMA 12.5 mm	SMA 9.5 mm
50.0-mm	100						
37.5-mm	90 – 100	100					
25.0-mm	90 max	90 - 100	100				
19.0-mm	—	90 max	90 - 100	100		100	
12.5-mm	—	—	90 max	90 - 100	100	90 - 97	100
9.5-mm	—	—	—	90 max	90 - 100	58 - 72	90 - 100
4.75-mm	—	—	—	—	90 max	25 - 35	35 - 45
2.36-mm	15 – 41	19 - 45	23 - 49	28 - 58	20 - 65	15 - 25	18 - 28
75-µm	0 – 6.0	1.0 - 7.0	2.0 - 8.0	2.0 - 10.0	2.0 - 10.0	8.0 - 12.0	10.0 - 14.0
% MINIMUM VMA	11.0	12.0	13.0	14.0 <sup>[1]</sup>	15.0 <sup>[2]</sup>	16.0	17.0

<sup>[1]</sup> 14.5 for E-0.3 and E-3 mixes.

<sup>[2]</sup> 15.5 for E-0.3 and E-3 mixes.

**460.3.4 Cold Weather Paving**

*Add a new subsection as follows effective with the May 2015 letting:*

**460.3.4 Cold Weather Paving****460.3.4.1 Cold Weather Paving Plan**

- (1) Submit a written cold weather paving plan to the engineer at the preconstruction meeting. In that plan outline material, operational, and equipment changes for paving when the air temperature approximately 3 feet above grade, in shade, and away from artificial heat sources is less than 40 F. Include the following:
- Use a department-accepted HMA mix design that incorporates a warm mix additive from the department's approved products list. Do not use a foaming process that introduces water into the mix.
  - Use additional rollers.

- (2) Engineer written acceptance is required for the cold weather paving plan. Engineer acceptance of the plan does not relieve the contractor of responsibility for pavement performance except as specified in 450.5(4).

**460.3.4.2 Cold Weather Paving Operations**

- (1) Do not place asphaltic mixture when the air temperature approximately 3 feet above grade, in shade, and away from artificial heat sources is less than 40 F unless a valid engineer-accepted cold weather paving plan is in effect.
- (2) If the national weather service forecast for the construction area predicts ambient air temperature less than 40 F at the projected time of paving within the next 24 hours, confirm or submit revisions to a previously engineer-accepted cold weather paving plan for engineer validation. Upon validation of the plan, the engineer will allow paving for the next day. Once in effect, pave conforming to the engineer-accepted cold weather paving plan for the balance of that work day or shift regardless of the temperature at the time of paving.

**460.4 Measurement**

*Add paragraph two as follows effective with the January 2015 letting:*

- (2) The department will measure HMA Cold Weather Paving by the ton of HMA mixture for pavement placed conforming to an engineer-accepted cold weather paving plan.

**460.5.1 General**

*Revise paragraph one as follows effective with the January 2015 letting:*

- (1) The department will pay for measured quantities at the contract unit price under the following bid items:

<u>ITEM NUMBER</u>	<u>DESCRIPTION</u>	<u>UNIT</u>
460.1100	HMA Pavement Type E-0.3	TON
460.1101	HMA Pavement Type E-1	TON
460.1103	HMA Pavement Type E-3	TON
460.1110	HMA Pavement Type E-10	TON
460.1130	HMA Pavement Type E-30	TON
460.1132	HMA Pavement Type E-30X	TON
460.1700	HMA Pavement Type SMA	TON
460.2000	Incentive Density HMA Pavement	DOL
460.4000	HMA Cold Weather Paving	TON

**460.5.2.2 Disincentive for HMA Pavement Density**

*Revise paragraph two as follows effective with the January 2015 letting:*

- (2) The department will not assess density disincentives for pavement placed in cold weather because of a department-caused delay as specified in 450.5(4).

**460.5.2.4 Cold Weather Paving**

*Add a new subsection as follows effective with the May 2015 letting:*

**460.5.2.4 Cold Weather Paving**

- (1) Payment for HMA Cold Weather Paving is full compensation for additional materials and equipment specified for cold weather paving under 460.3.4 including costs for preparing, administering, and following the contractor's cold weather paving plan. The department will not pay for HMA Cold Weather Paving for HMA placed on days when the department is assessing liquidated damages.
- (2) If HMA pavement is placed under 460.3.4 and the HMA Cold Weather Paving bid item is not in the contract, the department will pay for the additional costs specified in 460.5.2.4(1) as extra work. The department will pay separately for HMA pavement under the appropriate HMA Pavement bid items.

**465.2 Materials**

*Replace paragraph two with the following effective with the December 2014 letting:*

- (2) Under the other 465 bid items, the contractor need not submit a mix design. Furnish aggregates mixed with a type AC asphaltic material, except under the Asphaltic Curb bid item furnish PG58-28 asphaltic material. Use coarse and fine mineral aggregates uniformly coated and mixed with the asphaltic material in an engineer-approved mixing plant. The contractor may include reclaimed asphaltic pavement materials in the mixture.

**506.3.2 Shop Drawings**

Replace the entire text with the following effective with the May 2015 letting:

- (1) Ensure that shop drawings conform to the contract plans and provide additional details, dimensions, computations, and other information necessary for completely fabricating and erecting the work. Include project and structure numbers on each shop drawing sheet.
- (2) Check shop drawings and submit electronically to the department for review before beginning fabrication. For primary fabrication items, also certify that shop drawings conform to quality control standards by submitting department form DT2333. Department review does not relieve the contractor from responsibility for errors or omissions on shop drawings.
- (3) Shop drawings are part of the contract. The department must approve differences between shop drawings and contract plans. The contractor bears the costs of department-approved substitutions. Do not deviate from or revise drawings without notifying the department and resubmitting revised drawings.
- (4) Ensure that the fabricator delivers 3 sets of shop drawings for railroad structures to the railroad company upon contract completion.

---

**Bid Items Added**


---

Add the following new bid item effective with the January 2015 letting:

<u>ITEM NUMBER</u>	<u>DESCRIPTION</u>	<u>UNIT</u>
460.4000	HMA Cold Weather Paving	TON

---

**Errata**


---

Make the following corrections to the standard specifications:

---

**501.3.2.4.4 Water Reducer**

Correct errata by deleting the reference to footnote 6 for grade D concrete.

- (1) Add a water reducing admixture conforming to 501.2.3. Determine the specific type and rate of use based on the atmospheric conditions, the desired properties of the finished concrete and the manufacturer's recommended rate of use. The actual rate of use shall at least equal the manufacturer's recommended rate, and both the type and rate used require the engineer's approval before use.
- 

**506.5 Payment**

Correct errata by changing the reference to 506.3.22.

- (9) The department will limit costs for inspections conducted under 506.3.22 to \$0.05 per pound of material and deduct costs in excess of that amount from payment due the contractor. The department will determine costs for in-house inspections based on hourly rates for department staff plus overhead and use invoiced costs for contracted-out inspections. The department will administer deductions for the contractor's share of the total inspection cost under the Excess Costs For Fabrication Shop Inspection administrative item.

**ADDITIONAL SPECIAL PROVISION 7**

- A. Reporting 1<sup>st</sup> Tier and DBE Payments During Construction
1. Comply with reporting requirements specified in the department's Civil Rights Compliance, Contractor's User Manual, Sublets and Payments.
  2. Report payments to all DBE firms within 10 calendar days of receipt of a progress payment by the department or a contractor for work performed, materials furnished, or materials stockpiled by a DBE firm. Report the payment as specified in A(1) for all work satisfactorily performed and for all materials furnished or stockpiled.
  3. Report payments to all first tier subcontractor relationships within 10 calendar days of receipt of a progress payment by the department for work performed. Report the payment as specified in A(1) for all work satisfactorily performed.
  4. All tiers shall report payments as necessary to comply with the DBE payment requirement as specified in A(2).
  5. Require all first tier relationships, DBE firms and all other tier relationships necessary to comply with the DBE payment requirement in receipt of a progress payment by contractor to acknowledge receipt of payment as specified in A(1), (2), (3) and (4).
  6. All agreements made by a contractor shall include the provisions in A(1), (2), (3), (4) and (5), and shall be binding on all first tier subcontractor relationships and all contractors and subcontractors utilizing DBE firms on the project.
- B. Costs for conforming to this special provision are incidental to the contract.



## **ADDITIONAL SPECIAL PROVISION 9**

### **Electronic Certified Payroll Submittal**

(1) Use the department's Civil Rights Compliance System (CRCS) to submit certified payrolls electronically. Details are available online through the department's highway construction contractor information (HCCI) site on the Labor, Wages, and EEO Information page at:

<http://wisconsindot.gov/Pages/doing-bus/civil-rights/labornwage/default.aspx>

(2) Ensure that all tiers of subcontractors, as well as all trucking firms, submit their weekly certified payrolls electronically through CRCS. These payrolls are due within seven calendar days following the close of the payroll period. Every firm providing physical labor towards completing the project is a subcontractor under this special provision.

(3) Upon receipt of contract execution, promptly make all affected firms aware of the requirements under this special provision and arrange for them to receive CRCS training as they are about to begin payrolls. The department will provide training either in a classroom setting at one of our regional offices or by telephone. Contact Tess Mulrooney at 608-267-4489 to schedule the training.

(4) The department will reject all paper submittals of forms DT-1816 and DT-1929 for information required under this special provision. All costs for conforming to this special provision are incidental to the contract.

(5) Firms wishing to export payroll data from their computer system into CRCS should have their payroll coordinator send several sample electronic files to Tess two months before a payroll needs to be submitted. Not every contractor's payroll system is capable of producing export files. For details, see pages 17-22 of the CRCS System Background Information manual available online on the Labor, Wages, and EEO Information page at:

<http://wisconsindot.gov/Documents/doing-bus/civil-rights/labornwage/crcs-payroll-manual.pdf>

**Effective August 2015 letting**

**BUY AMERICA PROVISION**

All steel and iron materials permanently incorporated in this project shall be domestic products and all manufacturing and coating processes for these materials from smelting forward in the manufacturing process must have occurred within the United States. Coating includes epoxy coating, galvanizing, painting and any other coating that protects or enhances the value of a material subject to the requirements of Buy America. The exemption of this requirement is the minimal use of foreign materials if the total cost of such material permanently incorporated in the product does not exceed one-tenth of one percent (1/10 of 1%) of the total contract cost or \$2,500.00, whichever is greater. For purposes of this paragraph, the cost is that shown to be the value of the subject products as they are delivered to the project. The contractor shall take actions and provide documentation conforming to CMM 2-28.5 to ensure compliance with this "Buy America" provision.

<http://wisconsindot.gov/rdwy/cmm/cm-02-28.pdf>

Upon completion of the project certify to the engineer, in writing using department form WS4567, that all steel, iron, and coating processes for steel or iron incorporated into the contract work conform to these "Buy America" provisions. Attach a list of exemptions and their associated costs to the certification form. Department form WS4567 is available at:

<http://wisconsindot.gov/rdwy/worksheets/ws4567.doc>



**Effective with September 2004 Letting**

**WISCONSIN DEPARTMENT OF TRANSPORTATION  
DIVISION OF HIGHWAYS AND TRANSPORTATION FACILITIES**

**SUPPLEMENTAL REQUIRED CONTRACT PROVISIONS**

- I. Wage Rates, Hours of labor and payment of Wages
- II. Payroll Requirements
- III. Postings at the Site of the Work
- IV. Affidavits
- V. Wage Rate Redistribution
- VI. Additional Classifications

**I. WAGE RATES, HOURS OF LABOR AND PAYMENT OF WAGES**

The schedule of "Minimum Wage Rates" attached hereto and made a part hereof furnishes the prevailing wage rates that have been determined pursuant to Section 103.50 of the Wisconsin Statutes. These wage rates are the minimum required to be paid to the various laborers, workers, mechanics and truck drivers employed by contractors and subcontractors on the construction work embraced by the contract and subject to prevailing hours and wages under Section 103.50, Stats. If necessary to employ laborers, workers, mechanics or truck drivers whose classification is not listed on the schedule, they shall be paid at rates conformable to those listed for similar classifications. Apprentices shall be paid at rates not less than those prescribed in their state indenture contracts.

While the wage rates shown are the minimum rates required by the contract to be paid during its life, this is not a representation that labor can be obtained at these rates. It is the responsibility of bidders to inform themselves as to the local labor conditions and prospective changes or adjustments of wage rates. No increase in the contract price shall be allowed or authorized on account of the payment of wage rates in excess of those listed herein.

Pursuant to Section 103.50 of the Wisconsin Statutes, the prevailing hours of labor have been determined to be up to 10 hours per day and 40 hours per calendar week Monday through Friday. If any laborer, worker, mechanic or truck driver is permitted or required to work more than the prevailing number of hours per day or per calendar week on this contract, they shall be paid for all hours in excess of the prevailing hours at a rate of at least one and one-half (1 1/2) times their hourly rate of pay. All work on Saturday, Sunday and the following holidays is to be paid at time and a half: (1) January 1, (2) the last Monday in May, (3) July 4, (4) the first Monday in September, (5) the fourth Thursday in November, (6) December 25, (7) the day before if January 1, July 4 or December 25 falls on a Saturday and (8) the day following if January 1, July 4 or December 25 falls on a Sunday.

All laborers, workers, mechanics and truck drivers shall be paid unconditionally not less often than once a week. Persons who own and operate their own trucks must receive the prevailing truck driver rate for the applicable type of truck (i.e. 2 axle, 3 or more axle, articulated, eculid or dumptor) he or she operates, plus an agreed upon amount for the use of his or her truck. Every owner-operator **MUST** be paid separately for their driving and for the use of their truck.

For those projects subject to the requirements of the Davis-Bacon Act, the Secretary of Labor will also have determined "Minimum Wage Rates" for work to be performed under the contract. These rates are, for all or most of the labor, worker, mechanic or truck driver classifications, identical to those established under Section 103.50 of the Wisconsin Statutes. In the event the rates are not identical, the higher of the two rates will govern.

## **II. PAYROLL REQUIREMENTS**

All contractors and subcontractors must submit weekly Certified Payrolls and Compliance Statement verifying that all laborers, workers, mechanics and truck drivers working on the project have been paid the prevailing wage rates for all work performed under the contract required by Section 103.50 of the Wisconsin Statutes.

## **III. POSTINGS AT THE SITE OF THE WORK**

In addition to the required postings furnished by the Department, the contractor shall post the following in at least one conspicuous place at the site of work:

- a. "NOTICE TO EMPLOYEES," which provides information required to be posted by the provisions of Section 103.50 of the Wisconsin Statutes.
- b. A copy of the State of Wisconsin Minimum Wages Rates. (Four pages.)
- c. A copy of the contractor's Equal Employment Opportunity Policy.
- d. On any project involving federal aid, in addition to the furnished postings, the contractor shall post a copy of the "Davis-Bacon Act, Minimum Wage Rates". (Three pages.)

## **IV. WAGE RATE REDISTRIBUTION**

The amount specified as the hourly basic rate of pay and the amount(s) specified as the fringe benefit contribution(s), for all classes of laborers, workers, mechanics or truck drivers may be redistributed, when necessary, to conform to those specified in any applicable collective bargaining agreement, provided that both parties to such agreement

request and receive the approval for any such redistribution from both the Department of Transportation and the Department of Workforce Development prior to the implementation of such redistribution.

## **V. ADDITIONAL CLASSIFICATIONS**

Any unlisted laborer or mechanic classification that is needed to perform work on this project, and is not included within the scope of any of the classifications listed in the application prevailing wage rate determination, may be added after award only if all of the following criteria have been met:

1. The affected employer(s) must make a written request to WisDOT Central Office to utilize the unlisted classification on this project.
2. The request must indicate the scope of the work to be performed by the unlisted classification and must indicate the proposed wage/fringe benefit package that the unlisted classification is to receive.
3. The work to be performed by the unlisted classification must not be performed by a classification that is included in the applicable prevailing wage rate determination.
4. The unlisted classification must be commonly employed in the area where the project is located.
5. The proposed wage/fringe benefit package must bear a reasonable relationship to those set forth in the applicable prevailing wage rate determination.
6. The request should be made prior to the actual performance of the work by the unlisted classification.
7. DWD must approve the use of the unlisted classification and the proposed wage/fringe benefit package. USDOL also must approve the use of the unlisted classification and the proposed wage/fringe benefit package on federal aid projects.
8. WisDOT and DWD may amend the proposed wage/fringe benefit package, as deemed necessary, and may set forth specific employment ratios and scope of work requirements in the approval document.

The approved wage/fringe benefit package shall be paid to all laborers, workers, mechanics or truck drivers performing work within the scope of that performed by the unlisted classification, from the first day on which such work is performed. In the event that work is performed by the unlisted classification prior to approval, the wage/fringe benefit package to be paid for such work must be in conformance with the wage/fringe

benefit package approved for such work. Under this arrangement a retroactive adjustment in wages and/or fringe benefits may be required to be made to the affected laborers, workers, mechanics or truck drivers by the affected employer(s).

**ANNUAL PREVAILING WAGE RATE DETERMINATION  
FOR ALL STATE HIGHWAY PROJECTS  
DANE COUNTY**

Compiled by the State of Wisconsin - Department of Workforce Development  
for the Department of Transportation  
Pursuant to s. 103.50, Stats.  
Issued on May 1, 2015

**CLASSIFICATION:** Contractors are required to call the Department of Workforce Development if there are any questions regarding the proper trade or classification to be used for any worker on a public works project.

**OVERTIME:** Time and one-half must be paid for all hours worked over 10 hours per day and 40 hours per calendar week and for all hours worked on Saturday, Sunday and the following six (6) holidays: January 1; the last Monday in May; July 4; the 1st Monday in September; the 4th Thursday in November; December 25; the day before if January 1, July 4 or December 25 falls on a Saturday; the day following if January 1, July 4 or December 25 falls on a Sunday.

**FUTURE INCREASE:** If indicated for a specific trade or occupation, the full amount of such increase MUST be added to the "TOTAL" indicated for such trade or occupation on the date(s) such increase(s) becomes effective.

**PREMIUM PAY:** If indicated for a specific trade or occupation, the full amount of such pay MUST be added to the "HOURLY BASIC RATE OF PAY" indicated for such trade or occupation, whenever such pay is applicable.

**SUBJOURNEY:** Wage rates may be available for some of the classifications indicated below. Any employer that desires to use any subjourney classification on a project MUST request the applicable wage rate from the Department of Workforce Development PRIOR to the date such classification is used on such project. Form ERD-10880 is available for this purpose and can be obtained by writing to the Department of Workforce Development, Equal Rights Division, P.O. Box 8928, Madison, WI 53708.

<u>TRADE OR OCCUPATION</u>	<u>HOURLY BASIC RATE OF PAY</u>	<u>HOURLY FRINGE BENEFITS</u>	<u>TOTAL</u>
	\$	\$	\$
Bricklayer, Blocklayer or Stonemason	32.09	18.04	50.13
Carpenter	32.72	16.00	48.72
Future Increase(s): Add \$1.42/hr on 6/1/2015; Add \$1.42/hr on 6/1/2016. Premium Pay: DOT PREMIUM: Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day.			
Cement Finisher	35.18	16.78	51.96
Future Increase(s): Add \$1.87 on 6/1/15; Add \$1.75 on 6/1/16. Premium Pay: DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.40/hr when the Wisconsin Department of Transportation or responsible governing agency requires that work be performed at night under artificial illumination with traffic control and the work is completed after sunset and before sunrise.			
Electrician	33.93	22.77	56.70
Premium Pay: DOT PREMIUM: Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day.			
Fence Erector	18.00	6.09	24.09
Ironworker	31.50	20.01	51.51
Line Constructor (Electrical)	39.50	17.73	57.23
Painter	26.65	13.10	39.75
Pavement Marking Operator	29.22	25.90	55.12
Piledriver	33.24	16.00	49.24
Future Increase(s): Add \$1.44/hr on 6/1/2015; Add \$1.44/hr on 6/1/2016. Premium Pay: DOT PREMIUM: Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day.			
Roofer or Waterproofer	29.40	11.31	40.71
Teledata Technician or Installer	22.25	12.24	34.49
Tuckpointer, Caulker or Cleaner	23.60	7.10	30.70

<b>TRADE OR OCCUPATION</b>	<b>HOURLY BASIC RATE OF PAY</b>	<b>HOURLY FRINGE BENEFITS</b>	<b>TOTAL</b>
	<b>\$</b>	<b>\$</b>	<b>\$</b>
Underwater Diver (Except on Great Lakes)	35.40	15.90	51.30
Heavy Equipment Operator - ELECTRICAL LINE CONSTRUCTION ONLY	35.55	15.57	51.12
Light Equipment Operator -ELECTRICAL LINE CONSTRUCTION ONLY	31.60	15.29	46.89
Heavy Truck Driver - ELECTRICAL LINE CONSTRUCTION ONLY	27.65	13.44	41.09
Light Truck Driver - ELECTRICAL LINE CONSTRUCTION ONLY	25.68	12.83	38.51
Groundman - ELECTRICAL LINE CONSTRUCTION ONLY	21.73	12.17	33.90

**TRUCK DRIVERS**

Single Axle or Two Axle	25.18	18.31	43.49
Future Increase(s): Add \$1.15/hr on 6/1/2015. Premium Pay: DOT PREMIUM: Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day.			
Three or More Axle	25.28	18.31	43.59
Future Increase(s): Add \$1.15/hr on 6/1/2015. Premium Pay: DOT PREMIUM: Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day.			
Articulated, Euclid, Dumptor, Off Road Material Hauler	30.27	21.15	51.42
Future Increase(s): Add \$1.25/hr on 6/1/2015; Add \$1.30/hr on 6/1/2016; Add \$1.25/hr on 6/1/2017. Premium Pay: DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.50/hr night work premium. See DOT'S website for details about the applicability of this night work premium at: <a href="http://www.dot.wi.gov/business/civilrights/laborwages/pwc.htm">http://www.dot.wi.gov/business/civilrights/laborwages/pwc.htm</a> .			
Pavement Marking Vehicle	23.16	21.13	44.29
Shadow or Pilot Vehicle	24.37	17.77	42.14
Truck Mechanic	24.52	17.77	42.29

**LABORERS**

General Laborer	30.41	15.14	45.55
Future Increase(s): Add \$1.05/hr eff. 06/01/2015; Add \$1.00/hr eff. 06/01/2016; Add \$1.00/hr eff. 06/01/2017 Premium Pay: Add \$.10/hr for topman, air tool operator, vibrator or tamper operator (mechanical hand operated), chain saw operator and demolition burning torch laborer; Add \$.15/hr for bituminous worker (raker and luteman), formsetter (curb, sidewalk and pavement) and strike off man; Add \$.20/hr for blaster and powderman; Add \$.25/hr for bottomman; Add \$.35/hr for line and grade specialist; Add \$.45/hr for pipelayer. / DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.25/hr for work on projects involving temporary traffic control setup, for lane and shoulder closures, when work under artificial illumination conditions is necessary as required by the project provisions (including prep time prior to and/or cleanup after such time period).			
Asbestos Abatement Worker	18.00	9.58	27.58
Landscaper	30.41	15.14	45.55
Future Increase(s): Add \$1.05/hr eff. 06/01/2015; Add \$1.00/hr eff. 06/01/2016; Add \$1.00/hr eff. 06/01/2017 Premium Pay: DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.25/hr for work on projects involving temporary traffic control setup, for lane and shoulder closures, when work under artificial illumination conditions is necessary as required by the project provisions (including prep time prior to and/or cleanup after such time period).			
Flagperson or Traffic Control Person	26.76	15.14	41.90

<b>TRADE OR OCCUPATION</b>	<b>HOURLY BASIC RATE OF PAY</b>	<b>HOURLY FRINGE BENEFITS</b>	<b>TOTAL</b>
	<b>\$</b>	<b>\$</b>	<b>\$</b>
Future Increase(s): Add \$1.05/hr eff. 06/01/2015; Add \$1.00/hr eff. 06/01/2016; Add \$1.00/hr eff. 06/01/2017 Premium Pay: DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.25/hr when the Wisconsin Department of Transportation or responsible governing agency requires that work be performed at night under artificial illumination with traffic control and the work is completed after sunset and before sunrise.			
Fiber Optic Laborer (Outside, Other Than Concrete Encased)	18.33	13.65	31.98
Railroad Track Laborer	14.50	5.29	19.79

### HEAVY EQUIPMENT OPERATORS

Crane, Tower Crane, Pedestal Tower or Derrick, With Boom, Leads &/or Jib Lengths Measuring 176 Ft or Over; Crane, Tower Crane, Pedestal Tower or Derrick, With or Without Attachments, With a Lifting Capacity of Over 100 Tons, Self-Erecting Tower Crane With a Lifting Capacity Of Over 4,000 Lbs., Crane With Boom Dollies; Traveling Crane (Bridge Type). Future Increase(s): Add \$1.25/hr on 6/1/2015; Add \$1.30/hr on 6/1/2016; Add \$1.25/hr on 6/1/2017. Premium Pay: DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.50/hr night work premium. See DOT'S website for details about the applicability of this night work premium at: <a href="http://www.dot.wi.gov/business/civilrights/laborwages/pwc.htm">http://www.dot.wi.gov/business/civilrights/laborwages/pwc.htm</a> .	37.72	21.15	58.87
Backhoe (Track Type) Having a Mfgr.'s Rated Capacity of 130,000 Lbs. or Over; Caisson Rig; Crane, Tower Crane, Portable Tower, Pedestal Tower or Derrick, With Boom, Leads &/or Jib Lengths Measuring 175 Ft or Under; Crane, Tower Crane, Portable Tower, Pedestal Tower or Derrick, With or Without Attachments, With a Lifting Capacity of 100 Tons or Under, Self-Erecting Tower Crane With A Lifting Capacity Of 4,000 Lbs., & Under; Dredge (NOT Performing Work on the Great Lakes); Licensed Boat Pilot (NOT Performing Work on the Great Lakes); Pile Driver. Future Increase(s): Add \$1.25/hr on 6/1/2015; Add \$1.30/hr on 6/1/2016; Add \$1.25/hr on 6/1/2017. Premium Pay: DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.50/hr night work premium. See DOT'S website for details about the applicability of this night work premium at: <a href="http://www.dot.wi.gov/business/civilrights/laborwages/pwc.htm">http://www.dot.wi.gov/business/civilrights/laborwages/pwc.htm</a> .	37.22	21.15	58.37
Air Track, Rotary or Percussion Drilling Machine &/or Hammers, Blaster; Asphalt Heater, Planer & Scarifier; Asphalt Milling Machine; Asphalt Screed; Automatic Subgrader (Concrete); Backhoe (Track Type) Having a Mfgr.'s Rated Capacity of Under 130,000 Lbs., Backhoe (Mini, 15,000 Lbs. & Under); Bituminous (Asphalt) Plant & Paver, Screed; Boatmen (NOT Performing Work on the Great Lakes); Boring Machine (Directional, Horizontal or Vertical); Bridge (Bidwell) Paver; Bulldozer or Endloader; Concrete Batch Plant, Batch Hopper; Concrete Breaker (Large, Auto, Vibratory/Sonic, Manual or Remote); Concrete Bump Cutter, Grinder, Planing or Grooving Machine; Concrete Conveyor System; Concrete Laser/Screed; Concrete Paver (Slipform); Concrete Pump, Concrete Conveyor (Rotec or Bidwell Type); Concrete Slipform Placer Curb & Gutter Machine; Concrete Spreader & Distributor; Crane (Carry Deck, Mini) or Truck Mounted Hydraulic Crane (10 Tons or Under); Crane With a Lifting Capacity of 25 Tons or Under; Forestry Equipment, Timbco, Tree Shear, Tub Grinder, Processor; Gradall (Cruz-Aire Type); Grader or Motor Patrol; Grout Pump; Hydro-Blaster (10,000 PSI or Over); Loading Machine (Conveyor); Material or Stack Hoist; Mechanic or Welder; Milling Machine; Post Hole	36.72	21.15	57.87

<u>TRADE OR OCCUPATION</u>	<u>HOURLY BASIC RATE OF PAY</u>	<u>HOURLY FRINGE BENEFITS</u>	<u>TOTAL</u>
	\$	\$	\$
Digger or Driver; Roller (Over 5 Ton); Scraper (Self Propelled or Tractor Drawn) 5 cu yds or More Capacity; Shoulder Widener; Sideboom; Skid Rig; Stabilizing or Concrete Mixer (Self-Propelled or 14S or Over); Straddle Carrier or Travel Lift; Tractor (Scraper, Dozer, Pusher, Loader); Tractor or Truck Mounted Hydraulic Backhoe; Trencher (Wheel Type or Chain Type); Tube Finisher; Tugger (NOT Performing Work on the Great Lakes); Winches & A- Frames. Future Increase(s): Add \$1.25/hr on 6/1/2015; Add \$1.30/hr on 6/1/2016; Add \$1.25/hr on 6/1/2017. Premium Pay: DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.50/hr night work premium. See DOT'S website for details about the applicability of this night work premium at: <a href="http://www.dot.wi.gov/business/civilrights/laborwages/pwc.htm">http://www.dot.wi.gov/business/civilrights/laborwages/pwc.htm</a> .			
Belting, Burlap, Texturing Machine; Broom or Sweeper; Compactor (Self-Propelled or Tractor Mounted, Towed & Light Equipment); Concrete Finishing Machine (Road Type); Environmental Burner; Farm or Industrial Type Tractor; Fireman (Asphalt Plant, Pile Driver & Derrick NOT Performing Work on the Great Lakes); Forklift; Greaser; Hoist (Tugger, Automatic); Jeep Digger; Joint Sawyer (Multiple Blade); Launch (NOT Performing Work on the Great Lakes); Lift Slab Machine; Mechanical Float; Mulcher; Power Subgrader; Robotic Tool Carrier (With or Without Attachments); Roller (Rubber Tire, 5 Ton or Under); Self Propelled Chip Spreader; Shouldering Machine; Skid Steer Loader (With or Without Attachments); Telehandler; Tining or Curing Machine. Future Increase(s): Add \$1.25/hr on 6/1/2015; Add \$1.30/hr on 6/1/2016; Add \$1.25/hr on 6/1/2017. Premium Pay: DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.50/hr night work premium. See DOT'S website for details about the applicability of this night work premium at: <a href="http://www.dot.wi.gov/business/civilrights/laborwages/pwc.htm">http://www.dot.wi.gov/business/civilrights/laborwages/pwc.htm</a> .	36.46	21.15	57.61
Air Compressor (&/or 400 CFM or Over); Air, Electric or Hydraulic Jacking System; Augers (Vertical & Horizontal); Automatic Belt Conveyor & Surge Bin; Boiler (Temporary Heat); Concrete Proportioning Plant; Crusher, Screening or Wash Plant; Generator (&/or 150 KW or Over); Heaters (Mechanical); High Pressure Utility Locating Machine (Daylighting Machine); Mudjack; Oiler; Prestress Machine; Pug Mill; Pump (3 Inch or Over) or Well Points; Rock, Stone Breaker; Screed (Milling Machine); Stump Chipper; Tank Car Heaters; Vibratory Hammer or Extractor, Power Pack. Future Increase(s): Add \$1.25/hr on 6/1/2015; Add \$1.30/hr on 6/1/2016; Add \$1.25/hr on 6/1/2017. Premium Pay: DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.50/hr night work premium. See DOT'S website for details about the applicability of this night work premium at: <a href="http://www.dot.wi.gov/business/civilrights/laborwages/pwc.htm">http://www.dot.wi.gov/business/civilrights/laborwages/pwc.htm</a> .	36.17	21.15	57.32
Fiber Optic Cable Equipment.	28.89	17.95	46.84



## SCHEDULE OF ITEMS

REVISED:

CONTRACT:  
20151110002PROJECT(S):  
1206-04-68FEDERAL ID(S):  
N/A

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS

## SECTION 0001 Contract Items

0010	108.3100.S Incentive/Disincentive for Interim Completion of Work 001. Rimrock Road WB Beltline Entrance Closure	CD	8.000	5000.00000	40000.00	
0020	204.0100 Removing Pavement	SY	105.000	.	.	
0030	206.1000 Excavation for Structures Bridges (structure) 001. B-13-192	LUMP		LUMP		.
0040	210.0100 Backfill Structure	CY	80.000	.	.	
0050	213.0100 Finishing Roadway (project) 001. 1206-04-68	EACH	1.000	.	.	
0060	305.0120 Base Aggregate Dense 1 1/4-Inch	TON	47.000	.	.	
0070	416.1110 Concrete Shoulder Rumble Strips	LF	2,717.000	.	.	
0080	502.0100 Concrete Masonry Bridges	CY	15.000	.	.	
0090	502.5005 Masonry Anchors Type L No. 5 Bars	EACH	84.000	.	.	

## SCHEDULE OF ITEMS

REVISED:

CONTRACT:  
20151110002PROJECT(S):  
1206-04-68FEDERAL ID(S):  
N/A

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0100	505.0605 Bar Steel Reinforcement HS Coated Bridges	1,310.000 LB	.		.	
0110	511.1200 Temporary Shoring (structure) 001. B-13-192	285.000 SF	.		.	
0120	516.0500 Rubberized Membrane Waterproofing	6.000 SY	.		.	
0130	603.8000 Concrete Barrier Temporary Precast Delivered	1,025.000 LF	.		.	
0140	603.8125 Concrete Barrier Temporary Precast Installed	1,738.000 LF	.		.	
0150	614.0905 Crash Cushions Temporary	1.000 EACH	.		.	
0160	619.1000 Mobilization	1.000 EACH	.		.	
0170	628.7020 Inlet Protection Type D	1.000 EACH	.		.	
0180	643.0200 Traffic Control Surveillance and Maintenance (project) 001. 1206-04-68	35.000 DAY	.		.	
0190	643.0300 Traffic Control Drums	4,054.000 DAY	.		.	
0200	643.0420 Traffic Control Barricades Type III	394.000 DAY	.		.	

## SCHEDULE OF ITEMS

REVISED:

CONTRACT:  
20151110002PROJECT(S):  
1206-04-68FEDERAL ID(S):  
N/A

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0210	643.0705 Traffic Control Warning Lights Type A	788.000 DAY	.		.	
0220	643.0715 Traffic Control Warning Lights Type C	1,068.000 DAY	.		.	
0230	643.0800 Traffic Control Arrow Boards	82.000 DAY	.		.	
0240	643.0900 Traffic Control Signs	1,613.000 DAY	.		.	
0250	643.0920 Traffic Control Covering Signs Type II	7.000 EACH	.		.	
0260	643.1050 Traffic Control Signs PCMS	222.000 DAY	.		.	
0270	643.2000 Traffic Control Detour (project) 001. 1206-04-68	1.000 EACH	.		.	
0280	643.3000 Traffic Control Detour Signs	3,025.000 DAY	.		.	
0290	646.0106 Pavement Marking Epoxy 4-Inch	2,667.000 LF	.		.	
0300	646.0126 Pavement Marking Epoxy 8-Inch	125.000 LF	.		.	
0310	646.0843.S Pavement Marking Grooved Wet Reflective Contrast Tape 8-Inch	986.000 LF	.		.	

## SCHEDULE OF ITEMS

REVISED:

CONTRACT:  
20151110002PROJECT(S):  
1206-04-68FEDERAL ID(S):  
N/A

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0320	647.0746 Pavement Marking Diagonal Epoxy 24-Inch	256.000 LF	.		.	
0330	649.0400 Temporary Pavement Marking Removable Tape 4-Inch	1,946.000 LF	.		.	
0340	649.2100 Temporary Raised Pavement Markers	102.000 EACH	.		.	
0350	690.0250 Sawing Concrete	115.000 LF	.		.	
0360	SPV.0060 Special 001. Temporary Thrie Beam Connection	2.000 EACH	.		.	
0370	SPV.0060 Special 002. Repositioning Traffic Control Devices For Mainline Closures	10.000 EACH	.		.	
0380	SPV.0090 Special 001. Traffic Channelizing Curb System Furnished	457.000 LF	.		.	
0390	SPV.0090 Special 002. Traffic Channelizing Curb System Installed	909.000 LF	.		.	
0400	SPV.0090 Special 003. Temporary Pavement Marking Wet Reflective Cntrst Removable Tape 4-Inch	6,057.000 LF	.		.	
0410	SPV.0090 Special 004. Temporary Pavement Marking Wet Reflective Cntrst Removable Tape 8-Inch	610.000 LF	.		.	

## SCHEDULE OF ITEMS

REVISED:

CONTRACT:  
20151110002PROJECT(S):  
1206-04-68FEDERAL ID(S):  
N/A

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0420	SPV.0090 Special 005. Traffic Control Gawk Screen Furnished	775.000 LF	.		.	
0430	SPV.0090 Special 006. Traffic Control Gawk Screen Installed	1,488.000 LF	.		.	
0440	SPV.0090 Special 007. Removing Pavement Markings Water Blasting	3,342.000 LF	.		.	
0450	SPV.0180 Special 001. Concrete Pavement Approach Slab HES Special	105.000 SY	.		.	
	SECTION 0001 TOTAL				.	
	TOTAL BID				.	



**PLEASE ATTACH SCHEDULE OF ITEMS HERE**