

# HIGHWAY WORK PROPOSAL

Wisconsin Department of Transportation  
DT1502 10/2010 s.66.29(7) Wis. Stats.

Proposal Number:

Ø 5

| COUNTY | STATE PROJECT ID | FEDERAL PROJECT ID | PROJECT DESCRIPTION                          | HIGHWAY |
|--------|------------------|--------------------|----------------------------------------------|---------|
| Monroe | 1071-02-60       |                    | La Crosse - Tomah<br>W County Line to USH 12 | IH 90   |

This proposal, submitted by the undersigned bidder to the Wisconsin Department of Transportation, is in accordance with the advertised request for proposals. The bidder is to furnish and deliver all materials, and to perform all work for the improvement of the designated project in the time specified, in accordance with the appended Proposal Requirements and Conditions.

|                                                                                                |                                                  |
|------------------------------------------------------------------------------------------------|--------------------------------------------------|
| Proposal Guaranty Required, \$ 75,000.00<br>Payable to: Wisconsin Department of Transportation | Attach Proposal Guaranty on back of this PAGE.   |
| Bid Submittal Due<br>Date: February 9, 2016<br>Time (Local Time): 9:00 AM                      | Firm Name, Address, City, State, Zip Code        |
| Contract Completion Time<br>Sixty (60) Working Days                                            | <b>SAMPLE</b><br><b>NOT FOR BIDDING PURPOSES</b> |
| Assigned Disadvantaged Business Enterprise Goal<br>0%                                          | This contract is exempt federal oversight.       |

This certifies that the undersigned bidder, duly sworn, is an authorized representative of the firm named above; that the bidder has examined and carefully prepared the bid from the plans, Highway Work Proposal, and all addenda, and has checked the same in detail before submitting this proposal or bid; and that the bidder or agents, officer, or employees have not, either directly or indirectly, entered into any agreement, participated in any collusion, or otherwise taken any action in restraint of free competitive bidding in connection with this proposal bid.

**Do not sign, notarize, or submit this Highway Work Proposal when submitting an electronic bid on the Internet.**

Subscribed and sworn to before me this date \_\_\_\_\_

\_\_\_\_\_  
(Signature, Notary Public, State of Wisconsin)

\_\_\_\_\_  
(Print or Type Name, Notary Public, State Wisconsin)

\_\_\_\_\_  
(Date Commission Expires)

Notary Seal

\_\_\_\_\_  
(Bidder Signature)

\_\_\_\_\_  
(Print or Type Bidder Name)

\_\_\_\_\_  
(Bidder Title)

## For Department Use Only

|                                                                                                                                                                                        |                        |
|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------|
| Type of Work<br>Pavement removal, concrete pavement repair and replacement, HMA pavement shoulders, earthwork, culvert repair and maintenance, permanent signing and pavement marking. |                        |
| Notice of Award Dated                                                                                                                                                                  | Date Guaranty Returned |

**PLEASE ATTACH  
PROPOSAL GUARANTY HERE**

## **Effective with November 2007 Letting**

### **PROPOSAL REQUIREMENTS AND CONDITIONS**

The bidder, signing and submitting this proposal, agrees and declares as a condition thereof, to be bound by the following conditions and requirements.

If the bidder has a corporate relationship with the proposal design engineering company, the bidder declares that it did not obtain any facts, data, or other information related to this proposal from the design engineering company that was not available to all bidders.

The bidder declares that they have carefully examined the site of, and the proposal, plans, specifications and contract forms for the work contemplated, and it is assumed that the bidder has investigated and is satisfied as to the conditions to be encountered, as to the character, quality, and quantities of work to be performed and materials to be furnished, and as to the requirements of the specifications, special provisions and contract. It is mutually agreed that submission of a proposal shall be considered conclusive evidence that the bidder has made such examination.

The bidder submits herewith a proposal guaranty in proper form and amount payable to the party as designated in the advertisement inviting proposals, to be retained by and become the property of the owner of the work in the event the undersigned shall fail to execute the contract and contract bond and return the same to the office of the engineer within fourteen (14) days after having been notified in writing to do so; otherwise to be returned.

The bidder declares that they understand that the estimate of quantities in the attached schedule is approximate only and that the attached quantities may be greater or less in accordance with the specifications.

The bidder agrees to perform the said work, for and in consideration of the payment of the amount becoming due on account of work performed, according to the unit prices bid in the following schedule, and to accept such amounts in full payment of said work.

The bidder declares that all of the said work will be performed at their own proper cost and expense, that they will furnish all necessary materials, labor, tools, machinery, apparatus, and other means of construction in the manner provided in the applicable specifications and the approved plans for the work together with all standard and special designs that may be designed on such plans, and the special provisions in the contract of which this proposal will become a part, if and when accepted. The bidder further agrees that the applicable specifications and all plans and working drawings are made a part hereof, as fully and completely as if attached hereto.

The bidder, if awarded the contract, agrees to begin the work not later than ten (10) days after the date of written notification from the engineer to do so, unless otherwise stipulated in the special provisions.

The bidder declares that if they are awarded the contract, they will execute the contract agreement and begin and complete the work within the time named herein, and they will file a good and sufficient surety bond for the amount of the contract for performance and also for the full amount of the contract for payment.

The bidder, if awarded the contract, shall pay all claims as required by Section 779.14, Statutes of Wisconsin, and shall be subject to and discharge all liabilities for injuries pursuant to Chapter 102 of the Statutes of Wisconsin, and all acts amendatory thereto. They shall further be responsible for any damages to property or injury to persons occurring through their own negligence or that of their employees or agents, incident to the performance of work under this contract, pursuant to the Standard Specifications for Road and Bridge Construction applicable to this contract.

In connection with the performance of work under this contract, the contractor agrees to comply with all applicable state and federal statutes relating to non-discrimination in employment. No otherwise qualified person shall be excluded from employment or otherwise be subject to discrimination in employment in any manner on the basis of age, race, religion, color, gender, national origin or ancestry, disability, arrest or conviction record (in keeping with s.111.32), sexual orientation, marital status, membership in the military reserve, honesty testing, genetic testing, and outside use of lawful products. This provision shall include, but not be limited to the following: employment, upgrading, demotion or transfer; recruitment or recruitment advertising; layoff or termination; rates of pay or other forms of compensation, and selection for training, including apprenticeship. The contractor further agrees to ensure equal opportunity in employment to all applicants and employees and to take affirmative action to attain a representative workforce.

The contractor agrees to post notices and posters setting forth the provisions of the nondiscrimination clause, in a conspicuous and easily accessible place, available for employees and applicants for employment.

If a state public official (section 19.42, Stats.) or an organization in which a state public official holds at least a 10% interest is a party to this agreement, this contract is voidable by the state unless appropriate disclosure is made to the State of Wisconsin Ethics Board.

## Effective with August 2015 Letting

### BID PREPARATION

#### **Preparing the Proposal Schedule of Items**

##### **A General**

- (1) Obtain bidding proposals as specified in **section 102** of the standard specifications prior to 11:45 AM of the last business day preceding the letting. Submit bidding proposals using one of the following methods:
  1. Electronic bid on the internet.
  2. Electronic bid on a printout with accompanying diskette or CD ROM.
  3. Paper bid under a waiver of the electronic submittal requirements.
- (2) Bids submitted on a printout with accompanying diskette or CD ROM or paper bids submitted under a waiver of the electronic submittal requirements govern over bids submitted on the internet.

- (3) The department will provide bidding information through the department's web site at:  
<http://wisconsindot.gov/Pages/doing-bus/contractors/hcci/bid-let.aspx>

The contractor is responsible for reviewing this web site for general notices as well as information regarding proposals in each letting. The department will also post special notices of all addenda to each proposal through this web site no later than 4:00 P.M. local time on the Thursday before the letting. Check the department's web site after 5:00 P.M. local time on the Thursday before the letting to ensure all addenda have been accounted for before preparing the bid. When bidding using methods 1 and 2 above, check the Bid Express™ on-line bidding exchange at <http://www.bidx.com/> after 5:00 P.M. local time on the Thursday before the letting to ensure that the latest schedule of items Expedite file (\*.ebs or \*.00x) is used to submit the final bid.

- (4) Interested parties can subscribe to the Bid Express™ on-line bidding exchange by following the instructions provided at the [www.bidx.com](http://www.bidx.com) web site or by contacting:

Info Tech Inc.  
5700 SW 34th Street, Suite 1235  
Gainesville, FL 32608-5371  
email: <mailto:customer.support@bidx.com>

- (5) The department will address equipment and process failures, if the bidder can demonstrate that those failures were beyond their control.
- (6) Contractors are responsible for checking on the issuance of addenda and for obtaining the addenda. Notice of issuance of addenda is posted on the department's web site at:  
<http://wisconsindot.gov/Pages/doing-bus/contractors/hcci/bid-let.aspx>

or by calling the department at (608) 266-1631. Addenda can ONLY be obtained from the departments web site listed above or by picking up the addenda at the Bureau of Highway Construction, Room 601, 4802 Sheboygan Avenue, Madison, WI, during regular business hours.

- (7) Addenda posted after 5:00 PM on the Thursday before the letting will be emailed to the eligible bidders for that proposal. All eligible bidders shall acknowledge receipt of the addenda whether they are bidding on the proposal or not. Not acknowledging receipt may jeopardize the awarding of the project.

## **B Submitting Electronic Bids**

### **B.1 On the Internet**

- (1) Do the following before submitting the bid:
  1. Have a properly executed annual bid bond on file with the department.
  2. Have a digital ID on file with and enabled by Info Tech Inc. Using this digital ID will constitute the bidder's signature for proper execution of the bidding proposal.
- (2) In lieu of preparing, delivering, and submitting the proposal as specified in 102.6 and 102.9 of the standard specifications, submit the proposal on the internet as follows:
  1. Download the latest schedule of items reflecting all addenda from the Bid Express<sup>TM</sup> web site.
  2. Use Expedite<sup>TM</sup> software to enter a unit price for every item in the schedule of items.
  3. Submit the bid according to the requirements of Expedite<sup>TM</sup> software and the Bid Express<sup>TM</sup> web site. Do not submit a bid on a printout with accompanying diskette or CD ROM or a paper bid. If the bidder does submit a bid on a printout with accompanying diskette or a paper bid in addition to the internet submittal, the department will disregard the internet bid.
  4. Submit the bid before the hour and date the Notice to Contractors designates.
  5. Do not sign, notarize, and return the bidding proposal described in 102.2 of the standard specifications.
- (3) The department will not consider the bid accepted until the hour and date the Notice to Contractors designates.

### **B.2 On a Printout with Accompanying Diskette or CD ROM**

- (1) Download the latest schedule of items from the Wisconsin pages of the Bid Express<sup>TM</sup> web site reflecting the latest addenda posted on the department's web site at:  
<http://wisconsindot.gov/Pages/doing-bus/contractors/hcci/bid-let.aspx>

Use Expedite<sup>TM</sup> software to prepare and print the schedule of items. Provide a valid amount for all price fields. Follow instructions and review the help screens provided on the Bid Express<sup>TM</sup> web site to assure that the schedule of items is prepared properly.

- (2) Staple an 8 1/2 by 11 inch printout of the Expedite<sup>TM</sup> generated schedule of items to the other proposal documents submitted to the department as a part of the bidder's sealed bid. As a separate submittal not in the sealed bid envelop but due at the same time and place as the sealed bid, also provide the Expedite<sup>TM</sup> generated schedule of items on a 3 1/2 inch computer diskette or CD ROM. Label each diskette or CD ROM with the bidder's name, the 4 character department-assigned bidder identification code from the top of the bidding proposal, and a list of the proposal numbers included on that diskette or CD ROM as indicated in the following example:

**Bidder**

**Name**

**BN00**

**Proposals: 1, 12, 14, & 22**

- (3) If bidding on more than one proposal in the letting, the bidder may include all proposals for that letting on one diskette or CD ROM. Include only submitted proposals with no incomplete or other files on the diskette or CD ROM.
- (4) The bidder-submitted printout of the Expedite<sup>TM</sup> generated schedule of items is the governing contract document and must conform to the requirements of section 102 of the standard specifications. If a printout needs to be altered, cross out the printed information with ink or typewriter and enter the new information and initial it in ink. If there is a discrepancy between the printout and the diskette or CD ROM, the department will analyze the bid using the printout information.

- (5) In addition to the reasons specified in [section 102](#) of the standard specifications, proposals are irregular and the department may reject them for one or more of the following:
1. The check code printed on the bottom of the printout of the Expedite<sup>TM</sup> generated schedule of items is not the same on each page.
  2. The check code printed on the printout of the Expedite<sup>TM</sup> generated schedule of items is not the same as the check code for that proposal provided on the diskette or CD ROM.
  3. The diskette or CD ROM is not submitted at the time and place the department designates.

### **C Waiver of Electronic Submittal**

- (1) The bidder may request a waiver of the electronic submittal requirements. Submit a written request for a waiver in lieu of bids submitted on the internet or on a printout with accompanying diskette or CD ROM. Use the waiver that was included with the paper bid document sent to the bidder or type up a waiver on the bidder's letterhead. The department will waive the electronic submittal requirements for a bidding entity (individual, partnership, joint venture, corporation, or limited liability company) for up to 4 individual proposals in a calendar year. The department may allow additional waivers for equipment malfunctions.
- (2) Submit a schedule of items on paper conforming to [section 102](#) of the standard specifications. The department charges the bidder a \$75 administrative fee per proposal, payable at the time and place the department designates for receiving bids, to cover the costs of data entry. The department will accept a check or money order payable to: "Wisconsin, Dept. of Transportation."
- (3) In addition to the reasons specified in [section 102](#) of the standard specifications, proposals are irregular and the department may reject them for one or more of the following:
  1. The bidder fails to provide the written request for waiver of the electronic submittal requirements.
  2. The bidder fails to pay the \$75 administrative fee before the time the department designates for the opening of bids unless the bidder requests on the waiver that they be billed for the \$75.
  3. The bidder exceeds 4 waivers of electronic submittal requirements within a calendar year.
- (4) In addition to the reasons specified in [section 102](#) of the standard specifications, the department may refuse to issue bidding proposals for future contracts to a bidding entity that owes the department administrative fees for a waiver of electronic submittal requirements.

# PROPOSAL BID BOND

DT1303 1/2006

Wisconsin Department of Transportation

|                   |                                    |              |
|-------------------|------------------------------------|--------------|
| Proposal Number   | Project Number                     | Letting Date |
| Name of Principal |                                    |              |
| Name of Surety    | State in Which Surety is Organized |              |

We, the above-named Principal and the above-named Surety, are held and firmly bound unto the State of Wisconsin in the sum equal to the Proposal Guaranty for the total bid submitted for the payment to be made; we jointly and severally bind ourselves, our heirs, executors, administrators, successors and assigns. The condition of this obligation is that the Principal has submitted a bid proposal to the State of Wisconsin acting through the Department of Transportation for the improvement designated by the Proposal Number and Letting Date indicated above.

If the Principal is awarded the contract and, within the time and manner required by law after the prescribed forms are presented for signature, enters into a written contract in accordance with the bid, and files the bond with the Department of Transportation to guarantee faithful performance and payment for labor and materials, as required by law, or if the Department of Transportation shall reject all bids for the work described, then this obligation shall be null and void; otherwise, it shall be and remain in full force and effect. In the event of failure of the Principal to enter into the contract or give the specified bond, the Principal shall pay to the Department of Transportation **within 10 business days of demand** a total equal to the Proposal Guaranty as liquidated damages; the liability of the Surety continues for the full amount of the obligation as stated until the obligation is paid in full.

The Surety, for value received, agrees that the obligations of it and its bond shall not be impaired or affected by any extension of time within which the Department of Transportation may accept the bid; and the Surety does waive notice of any such extension.

IN WITNESS, the Principal and Surety have agreed and have signed by their proper officers and have caused their corporate seals to be affixed this date: **(DATE MUST BE ENTERED)**

## PRINCIPAL

\_\_\_\_\_  
(Company Name) **(Affix Corporate Seal)**

\_\_\_\_\_  
(Signature and Title)

\_\_\_\_\_  
(Company Name)

\_\_\_\_\_  
(Signature and Title)

\_\_\_\_\_  
(Company Name)

\_\_\_\_\_  
(Signature and Title)

\_\_\_\_\_  
(Company Name)

\_\_\_\_\_  
(Signature and Title)

## NOTARY FOR PRINCIPAL

\_\_\_\_\_  
(Date)

State of Wisconsin )  
 ) ss.  
\_\_\_\_\_ County )

On the above date, this instrument was acknowledged before me by the named person(s).

\_\_\_\_\_  
(Signature, Notary Public, State of Wisconsin)

\_\_\_\_\_  
(Print or Type Name, Notary Public, State of Wisconsin)

\_\_\_\_\_  
(Date Commission Expires)

**Notary Seal**

\_\_\_\_\_  
(Name of Surety) **(Affix Seal)**

\_\_\_\_\_  
(Signature of Attorney-in-Fact)

## NOTARY FOR SURETY

\_\_\_\_\_  
(Date)

State of Wisconsin )  
 ) ss.  
\_\_\_\_\_ County )

On the above date, this instrument was acknowledged before me by the named person(s).

\_\_\_\_\_  
(Signature, Notary Public, State of Wisconsin)

\_\_\_\_\_  
(Print or Type Name, Notary Public, State of Wisconsin)

\_\_\_\_\_  
(Date Commission Expires)

**Notary Seal**

**IMPORTANT: A certified copy of Power of Attorney of the signatory agent must be attached to the bid bond.**



# CERTIFICATE OF ANNUAL BID BOND

DT1305 8/2003

Wisconsin Department of Transportation

|                             |                                        |
|-----------------------------|----------------------------------------|
| Time Period Valid (From/To) |                                        |
| Name of Surety              |                                        |
| Name of Contractor          |                                        |
| Certificate Holder          | Wisconsin Department of Transportation |

This is to certify that an annual bid bond issued by the above-named Surety is currently on file with the Wisconsin Department of Transportation.

This certificate is issued as a matter of information and conveys no rights upon the certificate holder and does not amend, extend or alter the coverage of the annual bid bond.

**Cancellation:** Should the above policy be cancelled before the expiration date, the issuing surety will give thirty (30) days written notice to the certificate holder indicated above.

\_\_\_\_\_  
(Signature of Authorized Contractor Representative)

\_\_\_\_\_  
(Date)



## March 2010

## LIST OF SUBCONTRACTORS

Section 66.0901(7), Wisconsin Statutes, provides that as a part of the proposal, the bidder also shall submit a list of the subcontractors the bidder proposes to contract with and the class of work to be performed by each. In order to qualify for inclusion in the bidder's list a subcontractor shall first submit a bid in writing, to the general contractor at least 48 hours prior to the time of the bid closing. The list may not be added to or altered without the written consent of the municipality. A proposal of a bidder is not invalid if any subcontractor and the class of work to be performed by the subcontractor has been omitted from a proposal; the omission shall be considered inadvertent or the bidder will perform the work personally.

No subcontract, whether listed herein or later proposed, may be entered into without the written consent of the Engineer as provided in Subsection 108.1 of the Standard Specifications.

[illegible]

**DECEMBER 2000**

**CERTIFICATION REGARDING DEBARMENT, SUSPENSION, AND OTHER  
RESPONSIBILITY MATTERS - PRIMARY COVERED TRANSACTIONS**

Instructions for Certification

1. By signing and submitting this proposal, the prospective contractor is providing the certification set out below.
2. The inability of a person to provide the certification required below will not necessarily result in denial of participation in this covered transaction. The prospective contractor shall submit an explanation of why it cannot provide the certification set out below. The certification or explanation will be considered in connection with the department or agency's determination whether to enter into this transaction. However, failure of the prospective contractor to furnish a certification or an explanation shall disqualify such person from participation in this transaction.
3. The certification in this clause is a material representation of fact upon which reliance was placed when the department determined to enter into this transaction. If it is later determined that the contractor knowingly rendered an erroneous certification in addition to other remedies available to the Federal Government the department may terminate this transaction for cause or default.
4. The prospective contractor shall provide immediate written notice to the department to whom this proposal is submitted if at any time the prospective contractor learns that its certification was erroneous when submitted or has become erroneous by reason of changed circumstances.
5. The terms "covered transaction," "debarred," "suspended," "ineligible," "lower tier covered transaction," "participant," "person," "primary covered transaction," "principal," "proposal," and "voluntarily excluded," as used in this clause, have the meanings set out in the Definitions and Coverage sections of the rules implementing Executive Order 12549. You may contact the department to which this proposal is being submitted for assistance in obtaining a copy of those regulations.
6. The prospective contractor agrees by submitting this proposal that, should this contract be entered into, it shall not knowingly enter into any lower tier covered transaction with a person who is debarred, suspended, declared ineligible, or voluntarily excluded from participation in this covered transaction, unless authorized by the department entering into this transaction.
7. The prospective contractor further agrees by submitting this proposal that it will include the clause titled "Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion-Lower Tier Covered Transaction," which is included as an addendum to PR-1273 - "Required Contract Provisions Federal Aid Construction Contracts," without

modification, in all lower tier covered transactions and in all solicitations for lower tier covered transactions.

8. The contractor may rely upon a certification of a prospective subcontractor/materials supplier that it is not debarred, suspended, ineligible, or voluntarily excluded from the covered transaction, unless it knows that the certification is erroneous. A contractor may decide the method and frequency by which it determines the eligibility of its principals. Each contractor may, but is not required to, check the Disapproval List (telephone # 608/266/1631).
9. Nothing contained in the foregoing shall be construed to require establishment of a system of records in order to render in good faith the certification required by this clause. The knowledge and information of a contractor is not required to exceed that which is normally possessed by a prudent person in the ordinary course of business dealings.
10. Except for transactions authorized under paragraph 6 of these instructions, if a contractor in a covered transaction knowingly enters into a lower tier covered transaction with a person who is suspended, debarred, ineligible or voluntarily excluded from participation in this transaction, in addition to other remedies available to the Federal Government, the department may terminate this transaction for cause or default.

Certification Regarding Debarment, Suspension, and Other Responsibility Matters - Primary Covered Transactions

- (1) The prospective contractor certifies to the best of its knowledge and belief, that it and its principals:
  - (a) Are not presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from covered transactions by any Federal department or agency;
  - (b) Have not within a three-year period preceding this proposal been convicted of or had a civil judgment rendered against them for commission of fraud or a criminal offense in connection with obtaining, attempting to obtain, or performing a public (Federal, State or local) transaction or contract under a public transaction; violation of Federal or State antitrust statutes or commission of embezzlement, theft, forgery, bribery, falsification or destruction of records, making false statements or receiving stolen property;
  - (c) Are not presently indicted for or otherwise criminally or civilly charged by a governmental entity (Federal, State or local) with commission of any of the offense enumerated in paragraph (1)(b) of this certification; and
  - (d) Have not within a three-year period preceding this proposal had one or more public transactions (Federal, State or local) terminated for cause or default.
- (2) Where the prospective contractor is unable to certify to any of the statements in this certification, such prospective contractor shall attach an explanation to this proposal.

## Special Provisions

### Table of Contents

| Article | Description                                                                                                                                                                                                                   | Page # |
|---------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------|
| 1.      | General.....                                                                                                                                                                                                                  | 2      |
| 2.      | Scope of Work. ....                                                                                                                                                                                                           | 2      |
| 3.      | Prosecution and Progress. ....                                                                                                                                                                                                | 2      |
| 4.      | Traffic. ....                                                                                                                                                                                                                 | 3      |
| 5.      | Holiday Work Restrictions. ....                                                                                                                                                                                               | 5      |
| 6.      | Utilities.....                                                                                                                                                                                                                | 6      |
| 7.      | Archaeological Site Protection. ....                                                                                                                                                                                          | 7      |
| 8.      | QMP Base Aggregate. ....                                                                                                                                                                                                      | 8      |
| 9.      | Rout and Seal, Item 415.6000.S.....                                                                                                                                                                                           | 16     |
| 10.     | Culvert Pipe Liners, 18 -Inch, Item 520.9700.S.01; Culvert Pipe Liners, 24-Inch, Item 520.9700.S.02; Culvert Pipe Liners, 30-Inch, Item 520.9700.S.03; Cleaning Culvert Pipes for Liner Verification, Item 520.9750.S.01..... | 18     |

## **SPECIAL PROVISIONS**

### **1. General.**

Perform the work under this construction contract for Project 1071-02-60, La Crosse - Tomah, W County Line to USH 12, IH 90, Monroe County, Wisconsin as the plans show and execute the work as specified in the State of Wisconsin, Department of Transportation, Standard Specifications for Highway and Structure Construction, 2016 Edition, as published by the department, and these special provisions.

If all or a portion of the plans and special provisions are developed in the SI metric system and the schedule of prices is developed in the US standard measure system, the department will pay for the work as bid in the US standard system.

100-005 (20150630)

### **2. Scope of Work.**

The work under this contract shall consist of pavement removal, concrete repair and replacement, HMA pavement shoulders, culvert repair and maintenance, permanent signing, pavement marking and all incidental items necessary to complete the work as shown on the plans and included in the proposal and contract.

104-005 (20090901)

### **3. Prosecution and Progress.**

Begin work within ten calendar days after the engineer issues a written notice to do so.

Provide the time frame for construction of the project within the 2016 construction season to the engineer in writing within a month after executing the contract but at least 14 calendar days before the preconstruction conference. Assure that the time frame is consistent with the contract completion time. Upon approval, the engineer will issue the notice to proceed within ten calendar days before the beginning of the approved time frame.

To revise the time frame, submit a written request to the engineer at least two weeks before the beginning of the intended time frame. The engineer will approve or deny that request based on the conditions cited in the request and its effect on the department's scheduled resources.

Standard spec 108.4.2.2 is modified to include weekly progress meetings and bar chart progress schedule updates.

**Northern Long-eared Bat (*Myotis septentrionalis*)**

Northern Long-eared Bats (NLEB) have the potential to inhabit the project limits because they roost in trees and structures (bridges, culverts, buildings). Roosts may not have been observed on this project, but conditions to support the species exist. The species and all active roosts are protected by the Federal Endangered Species Act.

In order to avoid adverse impacts upon the NLEBs, no vegetation clearing and grubbing within the identified clearing and grubbing limits will be allowed from June 1 to July 31, both dates inclusive.

If the required clearing and removal is not completed by May 31, the department will suspend all clearing and associated work directly impacted by clearing. The department will issue a notice to proceed with clearing and associated work directly impacted by clearing after consulting with the United States Fish and Wildlife Service (USFWS).

Submit a schedule and description of Clearing and/or Grubbing operations with the ECIP 14 days prior to any Clearing operations. The department will determine, based on schedule and scope of work, what additional erosion control measures shall be implemented prior to the start of Clearing operations, and list those additional measures in the ECIP.

**4. Traffic.**

The requirements of standard spec 643 are supplemented as follows:

**Wisconsin Lane Closure System Advance Notification**

Provide the following advance notification to the engineer for incorporation into the Wisconsin Lane Closure System (LCS).

**TABLE 108-1 CLOSURE TYPE AND REQUIRED MINIMUM ADVANCE NOTIFICATION**

| Closure type with height, weight, or width restrictions (available width, all lanes in one direction $\leq 16'$ ) | MINIMUM NOTIFICATION |
|-------------------------------------------------------------------------------------------------------------------|----------------------|
| Lane and shoulder closures                                                                                        | 14 calendar days     |
| Full roadway closures                                                                                             | 14 calendar days     |
| System and service ramp closures                                                                                  | 14 calendar days     |
| Full system and service ramp closures                                                                             | 14 calendar days     |
| Detours                                                                                                           | 14 calendar days     |
|                                                                                                                   |                      |

| Closure type without height, weight, or width restrictions (available width, all lanes in one direction >16') | MINIMUM NOTIFICATION |
|---------------------------------------------------------------------------------------------------------------|----------------------|
| Lane and shoulder closures                                                                                    | 3 business days      |
| System and service ramp closures                                                                              | 3 business days      |
| Modifying all closure types                                                                                   | 3 business days      |

Discuss LCS completion dates and provide changes in the schedule to the engineer at weekly project meetings in order to manage closures nearing their completion date.  
108-057 (20150630)

Notify the engineer if there are any changes in the schedule, early completions, or cancellations of scheduled work. Failure to provide advance notification may result in non-compensable delays to the contractor. No time extensions will be granted for these delays.

Coordinate all arrangements for handling traffic with the engineer before work is started on a new stage of construction that will change the traffic pattern existing at the time. Ensure that all traffic control devices are in place and approved by the engineer before beginning each stage.

Maintain one lane of IH90 traffic in each direction at all times. The contractor must limit mainline closure lengths to a maximum of eight miles, with a minimum gap of three miles between closures if necessary. Lane closures in a series, in either direction, must occupy the same lane. Lane closures shall be no longer than necessary to complete the work at hand.

During every stage of construction, lane closures will have to be pulled every Friday at noon. The contractor may reestablish the lane closures after 6:00pm on Sunday night.

Keep all entrance and exit ramps open to traffic at all times. All concrete ramp patching shall be performed half at a time. Diverting traffic entirely to the shoulder will not be permitted.

Conduct construction and hauling operations in such a manner that minimizes the duration and intensity of interference to the free flow of vehicles on IH 90. This includes the following:

- A. Do not park or store any equipment, vehicles, or construction materials within the right-of-way of IH 90 traveled roadways.
- B. No vehicle or piece of equipment will be permitted to directly cross live traffic lanes.

- C. Equip all vehicles and machines used to transport materials or supplies to the work site which are operated on the traveled roadway, with hazard identification beam (flashing yellow signal) 5-1/2 inch minimum diameter. The beam shall be visible from 360 degrees and shall be in operation when the vehicle is within the roadway or shoulder area.
- D. Have available at all times, sufficient experienced personnel to promptly install, remove, and reinstall the required traffic control devices to route traffic according to the plans, these special provisions, and as directed by the engineer.
- E. Do not use existing median crossovers for storage of equipment or materials.
- F. Do not use any maintenance crossovers or any other median crossovers unless a left lane closure is in place for entry and exit. Violators will be restricted from working on the project for the remainder of the contract time and any material they are hauling will not be paid.
- G. Interstate access control shall remain intact during construction.
- H. Immediately clean up all debris falling onto the roadway.

Access to and from the roadway shall be at the existing interchange ramps.

Construction vehicles shall move with traffic and shall be able to accelerate with IH 90 traffic prior to merging with it.

Do not disturb, remove, or obliterate any traffic control signs, advisory signs, shoulder delineators, or beam guard, in place along the traveled roadways without the approval of the engineer.

Reinstall or replace any signs damaged during construction operations at contractor expense.

Coordination may be required with state project 1017-01-60 if 1017-01-60 is built concurrently. The limits for 1017-01-60 include IH 90 Eastbound starting at Exit 43 (USH 12) heading east.

## **5. Holiday Work Restrictions.**

Do not perform work on, nor haul materials of any kind along or across any portion of the highway carrying IH 90 traffic, and entirely clear the traveled way and shoulders of such portions of the highway of equipment, barricades, signs, lights, and any other material that might impede the free flow of traffic during the following holiday periods:

- From noon Friday, May 27, 2016 to 6:00 AM Tuesday, May 31, 2016 for Memorial Day;
- From noon Wednesday, June 22, 2016 to 6:00 AM Monday, June 27, 2016 for Tomah Tractor Pull;
- From noon Friday, July 1, 2016 to 6:00 AM Tuesday, July 5, 2016 for Independence Day;
- From noon Friday, September 2, 2016 to 6:00 AM Tuesday, September 6, 2016 for Labor Day;
- From noon Thursday, September 22, 2016 to 6:00 AM Monday, September 26, 2016 for Cranberry Festival Weekend.

Both lanes in each direction shall be open for traffic with no obstructions during the aforementioned holiday weekends.

107-005 (20050502)

## **6. Utilities**

This contract does come under the provision of Administrative Rule Trans 220.

The following utility companies have facilities within the project area; however, no adjustments are anticipated:

Alliant Energy  
 AT&T Legacy  
 ATC  
 Charter Communications  
 Dairyland Power Cooperative  
 Mediacom  
 Oakdale Electric Cooperative  
 City of Sparta Water and Sewer  
 We Energies  
 WisDOT  
 WisDOT RWIS  
 Xcel Energy

If utility conflicts occur, they will be adjusted during construction in coordination with the contractor.

107-065 (20080501)

## **7. Archaeological Site Protection.**

The department has identified archeological sites within the project limits. The sites are:

- Area-47MO-69 located between Station 1188+00 and Station 1194.80
- Area-47MO-68 located between Station 1190+00A, It and Station 1195+00A, LT
- Area-47MO-70 located between Station 1202+00 and Station 1206+50
- Area-47MO-72 located between Station 1319+00 and Station 1333+00
- Area-47MO-79 located between Station 1381+50 and Station 1387+00
- Area-47MO-66 located between Station 1394+00 and Station 1400+00
- Area-47MO-71 located between Station 1429+00 and Station 1444+00
- Area-47MO-293 located between Station 1655+50, rt and Station 1658+50, RT
- Area-47MO-04 located between Station 1721+00A, It to Station 1725+50a, LT
- Area-47MO-03 located between Station 1726+25A to Station 1730+00A
- Area-47MO-01 located between Station 1758+00 and Station 1762+50
- Area-47MO-02 located between Station 1764+00 and Station 1768+50
- Area-47MO-05 located between Station 1768+00 and Station 1773+00
- Area BMO-59 located between Station 2137+20 and 2150+00

The State Historic Preservation Office, (SHPO), has granted concurrence for construction in the areas, provided the following stipulations are strictly enforced:

When equipment needs to be staged, mobilized, or moved in a commitment area in any manner that extends beyond the roadway, clearance shall be obtained by contacting Jim Becker at (608) 261-0137 or Lynn Cloud at (608) 266-0099 14 days prior to construction. The notice is required in order for SHPO to schedule an on-site archeologist. The roadway is defined as both eastbound and westbound traveled lanes and shoulder.

The contractor shall not use these sites for borrow or waste disposal.

The contractor shall not allow any equipment, construction vehicles or personal vehicles to leave the roadway in these designated areas unless they are actively engaged in construction activities.

When construction activities have been concluded for the day, all construction equipment, construction vehicles or personal vehicles shall be parked in areas suitable for commercial parking and shall not be parked on any agricultural lands or lawns within the designated areas.

## **8. QMP Base Aggregate.**

### **A Description**

#### **A.1 General**

- (1) This special provision describes contractor quality control (QC) sampling and testing for base aggregates, documenting those test results, and documenting related production and placement process changes. This special provision also describes department quality verification (QV), independent assurance (IA), and dispute resolution.
- (2) Conform to standard spec 301, standard spec 305, and standard spec 310 as modified here in this special provision. Apply this special provision to material placed under all of the Base Aggregate Dense and Base Aggregate Open Graded bid items, except do not apply this special provision to material classified as reclaimed asphaltic pavement placed under the Base Aggregate Dense bid items.
- (3) Do not apply this special provision to material placed under the Aggregate Detours, Salvaged Asphaltic Pavement Base, Breaker Run, Select Crushed, Pit Run, Subbase, or Riprap bid items.
- (4) Provide and maintain a quality control program, defined as all activities related to and documentation of the following:
  1. Production and placement control and inspection.
  2. Material sampling and testing.
- (5) Chapter 8 of the department's construction and materials manual (CMM) provides additional detailed guidance for QMP work and describes required sampling and testing procedures. The contractor may obtain the CMM from the department's web site at:

<http://roadwaystandards.dot.wi.gov/standards/cmm/index.htm>

#### **A.2 Contractor Testing for Small Quantities**

- (1) The department defines a small quantity, for each individual Base Aggregate bid item, as a plan quantity of 9000 tons or less of material as shown in the schedule of items under that bid item.
- (2) The requirements under this special provision apply equally to a small quantity for an individual bid item except as follows:
  1. The contractor need not submit a full quality control plan but shall provide an organizational chart to the engineer including names, telephone numbers, and current certifications of all persons involved in the quality control program for material under affected bid items.

2. Divide the aggregate into uniformly sized sublots for testing as follows:

| <b>Plan Quantity</b>               | <b>Minimum Required Testing</b>                                                                                      |
|------------------------------------|----------------------------------------------------------------------------------------------------------------------|
| $\leq 1500$ tons                   | One test from production, load-out, or placement at the contractor's option <sup>[1]</sup>                           |
| $> 1500$ tons and $\leq 6000$ tons | Two tests of the same type, either from production, load-out, or placement at the contractor's option <sup>[1]</sup> |
| $> 6000$ tons and $\leq 9000$ tons | Three placement tests <sup>[2] [3]</sup>                                                                             |

- <sup>[1]</sup> If using production tests for acceptance, submit test results to the engineer for review prior to incorporating the material into the work. Production test results are valid for a period of 3 years.
- <sup>[2]</sup> For 3-inch material, obtain samples at load-out.
- <sup>[3]</sup> If the actual quantity overruns 9000 tons, create overrun sublots to test at a rate of one additional placement test for each 3000 tons, or fraction of 3000 tons, of overrun.
3. No control charts are required. Submit aggregate load-out and placement test results to the engineer within one business day of obtaining the sample. Assure that all properties are within the limits specified for each test.
4. Department verification testing is optional for quantities of 6000 tons or less.
- (3) Material represented by a subplot with any property outside the specification limits is nonconforming. The department may reject material or otherwise determine the final disposition of nonconforming material as specified in standard spec 106.5.

## **B Materials**

### **B.1 Quality Control Plan**

- (1) Submit a comprehensive written quality control plan to the engineer at or before the pre-construction meeting. Do not place base before the engineer reviews and comments on the plan. Construct the project as that plan provides.
- (2) Do not change the quality control plan without the engineer's review. Update the plan with changes as they become effective. Provide a current copy of the plan to the engineer and post in each of the contractor's laboratories as changes are adopted. Ensure that the plan provides the following elements:
1. An organizational chart with names, telephone numbers, current certifications and/or titles, and roles and responsibilities of QC personnel.
  2. The process used to disseminate QC information and corrective action efforts to the appropriate persons. Include a list of recipients, the communication means that will be used, and action time frames.
  3. A list of source and processing locations, section and quarter descriptions, for all aggregate materials requiring QC testing.
  4. Test results for wear, sodium sulfate soundness, freeze/thaw soundness, and plasticity index of all aggregates requiring QC testing. Obtain this information from the region materials unit or from the engineer.
  5. Descriptions of stockpiling and hauling methods.

6. Locations of the QC laboratory, retained sample storage, and where control charts and other documentation is posted.
7. An outline for resolving a process control problem. Include responsible personnel, required documentation, and appropriate communication steps.

## B.2 Personnel

- (1) Have personnel certified under the department's highway technician certification program (HTCP) perform sampling, testing, and documentation as follows:

| Required Certification Level:                                                                                   | Sampling or Testing Roles:                                                                                                         |
|-----------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------|
| Aggregate Technician IPP<br>Aggregate Sampling Technician<br>Aggregate Assistant Certified Technician (ACT-AGG) | Aggregate Sampling <sup>[1]</sup>                                                                                                  |
| Aggregate Technician IPP<br>Aggregate Assistant Certified Technician (ACT-AGG)                                  | Aggregate Gradation Testing,<br>Aggregate Fractured Particle<br>Testing, Aggregate Liquid<br>Limit and Plasticity Index<br>Testing |

<sup>[1]</sup> Plant personnel under the direct observation of an aggregate technician certified at level one or higher may operate equipment to obtain samples.

- (2) A certified technician must coordinate and take responsibility for the work an ACT performs. Have a certified technician ensure that all sampling and testing is performed correctly, analyze test results, and post resulting data. No more than one ACT can work under a single certified technician.

## B.3 Laboratory

- (1) Perform QC testing at a department-qualified laboratory. Obtain information on the Wisconsin laboratory qualification program from:  
Materials Management Section  
3502 Kinsman Blvd.  
Madison, WI 53704  
Telephone: (608) 246-5388  
<http://www.dot.state.wi.us/business/engrserv/lab-qualification.htm>

## B.4 Quality Control Documentation

### B.4.1 General

- (1) Submit base aggregate placement documentation to the engineer within 10 business days after completing base placement. Ensure that the submittal is complete, neatly organized, and includes applicable project records and control charts.

### B.4.2 Records

- (1) Document all placement observations, inspection records, and control adjustments daily in a permanent field record. Also include all test results in the project records. Provide test results to the engineer within 6 hours after obtaining a sample. For 3-inch

base, extend this 6-hour limit to 24 hours. Post or distribute tabulated results using a method mutually agreeable to the engineer and contractor.

#### **B.4.3 Control Charts**

- (1) Plot gradation and fracture on the appropriate control chart as soon as test results are available. Format control charts according to CMM 8.30. Include the project number on base placement control charts. Maintain separate control charts for each base aggregate size, source or classification, and type.
- (2) Provide control charts to the engineer within 6 hours after obtaining a sample. For 3-inch base, extend this 6-hour limit to 24 hours. Post or distribute charts using a method mutually agreeable to the engineer and contractor. Update control charts daily to include the following:
  1. Contractor individual QC tests.
  2. Department QV tests.
  3. Department IA tests.
  4. Four-point running average of the QC tests.
- (3) Except as specified under B.8.2.1 for nonconforming QV tests, include only QC tests in the running average. The contractor may plot process control or informational tests on control charts, but do not include these tests, conforming QV tests, or IA tests in the running average.

#### **B.5 Contractor Testing**

- (1) Test gradation, fracture, liquid limit and plasticity index during placement for each base aggregate size, source or classification, and type.
- (2) Test gradation once per 3000 tons of material placed. Determine random sample locations and provide those sample locations to the engineer. Obtain samples after the material has been bladed, mixed, and shaped but before compacting; except collect 3-inch samples from the stockpile at load-out. Do not sample from material used to maintain local traffic or from areas of temporary base that will not have an overlying pavement. On days when placing only material used to maintain local traffic or only temporary base that will not have an overlying pavement, no placement testing is required.
- (3) Split each contractor QC sample and identify it according to CMM 8.30. Retain the split for 7 calendar days in a dry, protected location. If requested for department comparison testing, deliver the split to the engineer within one business day.
- (4) The engineer may require additional sampling and testing to evaluate suspect material or the technician's sampling and testing procedures.
- (5) Test fracture for each gradation test until the fracture running average is above the lower warning limit. Subsequently, the contractor may reduce the frequency to one test per 10 gradation tests if the fracture running average remains above the warning limit.

- (6) Test the liquid limit and plasticity index for the first gradation test. Subsequently, test the liquid limit and plasticity index a minimum of once per 10 gradation tests.

## **B.6 Test Methods**

### **B.6.1 Gradation**

- (1) Test gradation using a washed analysis conforming to the following as modified in CMM 8.60:  
Gradation..... AASHTO T 27  
Material finer than the No. 200 sieve..... AASHTO T 11
- (2) For 3-inch base, if 3 consecutive running average points for the percent passing the No. 200 sieve are 8.5 percent or less, the contractor may use an unwashed analysis. Wash at least one sample out of 10. If a single running average for the percent passing the No. 200 sieve exceeds 8.5 percent, resume washed analyses until 3 consecutive running average points are again 8.5 percent passing or less.
- (3) Maintain a separate control chart for each sieve size specified in standard spec 305 or standard spec 310 for each base aggregate size, source or classification, and type. Set control and warning limits based on the standard specification gradation limits as follows:
  1. Control limits are at the upper and lower specification limits.
  2. There are no upper warning limits for sieves allowing 100 percent passing and no lower control limits for sieves allowing 0 percent passing.
  3. Dense graded warning limits, except for the No. 200 sieve, are 2 percent within the upper and lower control limits. Warning limits for the No. 200 sieve are set 0.5 percent within the upper and lower control limits.
  4. Open graded warning limits for the 1-inch, 3/8-inch, and No. 4 sieves are 2 percent within the upper and lower control limits. Upper warning limits for the No. 10, No. 40, and No. 200 sieves are 1 percent inside the upper control limit.

### **B.6.2 Fracture**

- (1) Test fracture conforming to CMM 8.60. The engineer will waive fractured particle testing on quarried stone.
- (2) Maintain a separate fracture control chart for each base aggregate size, source or classification, and type. Set the lower control limit at the contract specification limit, either specified in another special provision or in table 301-2 of standard spec 301.2.4.5. Set the lower warning limit 2 percent above the lower control limit. There are no upper limits.

### **B.6.3 Liquid Limit and Plasticity**

- (1) Test the liquid limit and plasticity according to AASHTO T 89 and T 90.
- (2) Ensure the material conforms to the limits specified in standard spec table 301-2.

## **B.7 Corrective Action**

### **B.7.1 General**

- (1) Consider corrective action when the running average trends toward a warning limit. Take corrective action if an individual test exceeds the contract specification limit. Document all corrective actions both in the project records and on the appropriate control chart.

### **B.7.2 Placement Corrective Action**

- (1) Do not blend additional material on the roadbed to correct gradation problems.
- (2) Notify the engineer whenever the running average exceeds a warning limit. When 2 consecutive running averages exceed a warning limit, the engineer and contractor will discuss appropriate corrective action. Perform the engineer's recommended corrective action and increase the testing frequency as follows:
  1. For gradation, increase the QC testing frequency to at least one randomly sampled test per 1000 tons placed.
  2. For fracture, increase the QC testing frequency to at least one test per gradation test.
- (3) If corrective action improves the property in question such that the running average after 4 additional tests is within the warning limits, the contractor may return to the testing frequency specified in B.5.3. If corrective action does not improve the property in question such that the running average after 4 additional individual tests is still in the warning band, repeat the steps outlined above starting with engineer notification.
- (4) If the running average exceeds a control limit, material starting from the first running average exceeding the control limit and ending at the first subsequent running average inside the control limit is nonconforming and subject to pay reduction.
- (5) For individual test results significantly outside the control limits, notify the engineer, stop placing base, and suspend other activities that may affect the area in question. The engineer and contractor will jointly review data, data reduction, and data analysis; evaluate sampling and testing procedures; and perform additional testing as required to determine the extent of potentially unacceptable material. The engineer may direct the contractor to remove and replace that material. Individual test results are significantly outside the control limits if meeting one or more of the following criteria:
  1. A gradation control limit for the No. 200 sieve is exceeded by more than 3.0 percent.
  2. A gradation control limit for any sieve, except the No. 200, is exceeded by more than 5.0 percent.
  3. The fracture control limit is exceeded by more than 10.0 percent.

## **B.8 Department Testing**

### **B.8.1 General**

- (1) The department will conduct verification testing to validate the quality of the product and independent assurance testing to evaluate the sampling and testing. The department will provide the contractor with a listing of names and telephone numbers of all QV and IA personnel for the project, and provide test results to the contractor within 2 business days after the department obtains the sample.

### **B.8.2 Verification Testing**

#### **B.8.2.1 General**

- (1) The department will have an HTCP technician, or ACT working under a certified technician, perform QV sampling and testing. Department verification testing personnel must meet the same certification level requirements specified in B.2 for contractor testing personnel for each test result being verified. The department will notify the contractor before sampling so the contractor can observe QV sampling.
- (2) The department will conduct QV tests of each base aggregate size, source or classification, and type during placement conforming to the following:
  1. One non-random test on the first day of placement.
  2. At least one random test per 30,000 tons, or fraction of 30,000 tons, placed.
- (3) The department will sample randomly, at locations independent of the contractor's QC work, collecting one sample at each QV location. The department will collect QV samples after the material has been bladed, mixed, and shaped but before compacting; except, for 3-inch aggregates, the department will collect samples from the stockpile at load-out. The department will split each sample, test half for QV, and retain half.
- (4) The department will conduct QV tests in a separate laboratory and with separate equipment from the contractor's QC tests. The department will use the same methods specified for QC testing.
- (5) The department will assess QV results by comparing to the appropriate specification limits. If QV test results conform to the specification, the department will take no further action. If QV test results are nonconforming, add the QV to the QC test results as if it were an additional QC test.

#### **B.8.3 Independent Assurance**

- (1) Independence assurance is unbiased testing the department performs to evaluate the department's QV and the contractor's QC sampling and testing including personnel qualifications, procedures, and equipment. The department will perform an IA review according to the department's independent assurance program. That review may include one or more of the following:

1. Split sample testing.
  2. Proficiency sample testing.
  3. Witnessing sampling and testing.
  4. Test equipment calibration checks.
  5. Reviewing required worksheets and control charts.
  6. Requesting that testing personnel perform additional sampling and testing.
- (2) If the department identifies a deficiency, and after further investigation confirms it, correct that deficiency. If the contractor does not correct or fails to cooperate in resolving identified deficiencies, the engineer may suspend placement until action is taken. Resolve disputes as specified in B.9.

### **B.9 Dispute Resolution**

- (1) The engineer and contractor should make every effort to avoid conflict. If a dispute between some aspect of the contractor's and the engineer's testing program does occur, seek a solution mutually agreeable to the project personnel. The department and contractor may review the data, examine data reduction and analysis methods, evaluate sampling and testing procedures, and perform additional testing. Use ASTM E 178 to evaluate potential statistically outlying data.
- (2) Production test results, and results from other process control testing, may be considered when resolving a dispute.
- (3) If the project personnel cannot resolve a dispute, and the dispute affects payment or could result in incorporating non-conforming product, the department will use third party testing to resolve the dispute. The department's central office laboratory, or a mutually agreed on independent testing laboratory, will provide this testing. The engineer and contractor will abide by the results of the third party tests. The party in error will pay service charges incurred for testing by an independent laboratory. The department may use third party test results to evaluate the quality of questionable materials and determine the appropriate payment. The department may reject material or otherwise determine the final disposition of nonconforming material as specified in standard spec 106.5.

### **C (Vacant)**

### **D (Vacant)**

### **E Payment**

- (1) Costs for all sampling, testing, and documentation required under this special provision are incidental to this work. If the contractor fails to perform the work required under this special provision, the department may reduce the contractor's pay. The department will administer pay reduction under the non-performance of QMP administrative item.

- (2) For material represented by a running average exceeding a control limit, the department will reduce pay by 10 percent of the contract price for the affected Base Aggregate bid items listed in subsection A. The department will administer pay reduction under the Nonconforming QMP Base Aggregate Gradation or Nonconforming QMP Base Aggregate Fracture Administrative items. The department will determine the quantity of nonconforming material as specified in B.7.2.

301-010 (20100709)

## **9. Rout and Seal, Item 415.6000.S.**

### **A Description**

This special provision describes routing, cleaning, drying, and sealing the longitudinal edge of pavement joints in new asphaltic pavement shoulders immediately adjacent to the edge of the concrete mainline pavement. The work shall conform to the plan details and as hereinafter provided.

### **B Materials**

Furnish material that conforms to the requirements of the Specifications for Joint Sealants, Hot-Poured, for Concrete and Asphalt Pavements, ASTM Designation: D 6690, Type II, modified to require that the bond strength test be run at -20 degrees F. (The unmodified ASTM D 6690, Type II allows this test to be run at either 0 degrees F or -20 degrees F.)

Deliver each lot or batch of sealing compound to the jobsite in the manufacturer's original sealed container. Mark each container with the manufacturer's name, batch or lot number, and the safe heating temperature. Present the manufacturer's certification stating that the compound meets the requirements of this specification. Prior to applying the sealant, furnish to the engineer a certificate of compliance and a copy of the manufacturer's recommendations on heating and applying the sealant.

### **C Construction**

#### **C.1 Equipment**

Heat the sealing compound to the pouring temperature recommended by the manufacturer in an approved kettle or tank, constructed as a double boiler, with the space between the inner and outer shells filled with oil or other satisfactory heat transfer medium. If and when using the heating kettle on concrete or asphaltic pavement, properly insulate the heating kettle to ensure heat is not radiated to the pavement surface.

Make rout cuts in a single pass. Two-pass cutting will not be allowed. Use a self-propelled mechanical router capable of routing the bituminous pavement to provide a 1.0:1.0 depth to width ratio of all routed cracks. The router blade or blades shall be of such size and configuration to cut the desired joint reservoir in one pass. No spacers between blades shall be allowed unless the contractor can demonstrate to the engineer that the desired reservoir and rout cut can be obtained with them. Either wet or dry routing will be permitted provided the above conditions are met. Use a pressure distributor for applying sealing material through a hand-operated wand or nozzle according to sealant manufacturer's instructions.

## **C.2 Methods**

Conduct the operation so that the routing, cleaning, and sealing are continuous operations. Traffic shall not be allowed to knead together or damage the routed joints. Rerout, if necessary, routed joints not sealed before traffic is allowed on the pavement when routing and sealing operations resume at no additional cost to the department. Do not perform rout cutting, cleaning, and sealing, within 48 hours of the placement of the shoulder's surface course.

Rout the longitudinal joint to a minimum width of  $\frac{3}{4}$ -inches and a minimum depth of  $\frac{3}{4}$ -inches. Use a power vacuum or equivalent to immediately remove any routing slurry, dirt, or deleterious matter adhering to the joint walls or remaining in the joint cavity, or both. Prior to sealing, dry the cleaned joints either by air-drying or by using a high capacity torch. Immediately prior to sealing, blow out the dried crack with a blast of compressed air, 80-psi minimum. Continue cleaning until the joint is dry, and until all dirt, dust, or deleterious matter is removed from the joint and adjacent pavement to the satisfaction of the engineer. If the air compressor produces dirt or other residue in the joint cavity, the contractor shall be required to clean the joint again.

If cleaning operations could cause damage to, or interfere with, traffic in adjacent lanes, or both, provide protective screening that is subject to the approval of the engineer to the cleaning operation.

Following cleaning, dry the routed joints and warm them with a hot air lance. Take care not to burn the pavement surface. Under no circumstances shall more than two minutes elapse between the time the hot air lance is used and the sealant is placed.

Provide positive temperature control and mechanical agitation. Do not heat the sealant to more than 20 degrees F below the safe heating temperature. The safe heating temperature can be obtained from the manufacturer's shipping container. Provide a direct connecting pressure type extruding device with nozzles shaped for insertion into the joint. Immediately remove sealant spilled on the surface of the pavement.

Seal the joints when the sealant material is at the pouring temperature recommended by the manufacturer. Fill the joint such that after cooling, the sealant is flush with the adjacent pavement surface. Do not overfill the joint; the engineer may allow a very slight overband. Sand shall not be spread on the sealed joints to allow for opening to traffic. Before opening to traffic, the sealant shall be tack free.

## **D Measurement**

The department will measure Rout and Seal in length by the linear foot, completed according to the contract and accepted.

## **E Payment**

The department will pay for measured quantities at the contract unit price under the following bid item:

| ITEM NUMBER | DESCRIPTION   | UNIT |
|-------------|---------------|------|
| 415.6000.S  | Rout and Seal | LF   |

Payment is full compensation for rout cutting; cleaning the joint; furnishing and installing all materials, including sealant.

415-100 (20140630)

## **10. Culvert Pipe Liners, 18 -Inch, Item 520.9700.S.01; Culvert Pipe Liners, 24-Inch, Item 520.9700.S.02; Culvert Pipe Liners, 30-Inch, Item 520.9700.S.03; Cleaning Culvert Pipes for Liner Verification, Item 520.9750.S.01.**

### **A Description**

This special provision describes providing and pressure grouting culvert pipe liners for circular culverts.

### **B Materials**

#### **B.1 General**

Provide flow calculations at the preconstruction conference. Use contractor-proposed liner properties, the Manning's coefficients listed on the department's approved products list, and base calculations on existing culvert sizes and liner sizes the plans show. Ensure that pipes when lined have a capacity within  $\pm 5\%$  of the original full flow capacity of the pipe.

#### **B.2 Flexible Pipe Liner**

Use liners with a Manning's coefficient value published on the department's approved products list. Upon delivery provide manufacturer certificates of compliance certifying that the liners conform to the following:

| Pipe Type                               | ASTM Designation | ASTM D3350 Resin |
|-----------------------------------------|------------------|------------------|
| <b>High Density Polyethylene (HDPE)</b> |                  |                  |
| Profile Wall Pipe                       | F894             | 345463C          |
| Solid Wall Pipe                         | F714             | 345463C          |
| <b>Polyvinylchloride (PVC)</b>          | F949             | ---              |

#### **B.3 Grout**

Provide grout consisting of:

- One part of type I or II portland cement
- Three parts sand conforming to standard spec 501.2.5.
- Water to achieve required fluidity.

Alternatively the contractor may use an engineer-approved commercial cellular concrete grout conforming to the following:

|                      |                            |                                             |
|----------------------|----------------------------|---------------------------------------------|
| Cement               | ASTM C150                  | Type I or II                                |
| Density              | ASTM C495 (no oven drying) | 50 pcf min                                  |
| Compressive Strength | ASTM C495                  | 300 psi @ 28 day min<br>100 psi in 24 hours |
| Shrinkage            | ASTM                       | 1% by volume                                |
| Flow                 | ASTM C939                  | 35 sec max                                  |

## **C Construction**

### **C.1 General**

As soon as possible after contract execution, survey existing culvert pipes to determine which culverts need cleaning in order to verify the required liner diameter and length. Notify the engineer before cleaning to confirm payment under the Cleaning Culvert Pipes for Liner Verification bid item.

Coordinate with the engineer to field verify culvert diameter and length, shape, material, and condition before ordering the liners.

Obtain easements if necessary for installing long sections of pipe.

### **C.2 Excavating and Cleaning**

Before inserting the liner, clean and dry the pipe. Excavate and pump as required to remove debris and other materials that would interfere with the placement or support of the inserted liner. Dispose of and replace unserviceable endwalls as the engineer directs.

### **C.3 Placing Liners**

Unload liners using slings and boom-type trucks or equivalents. Do not use chains or wire rope to handle liners and do not dump liners from the trucks when unloading.

Connect joints conforming to the manufacturer's recommendations.

### **C.4 Pressure Grouting**

After the liner is in place, fill the area between the original pipe and the liner completely with grout to provide uniform space between the liner and the original pipe. Block, grout in lifts, or otherwise secure liners to prevent floatation associated while grouting.

Use a grout plant that is capable of accurately measuring, proportioning, mixing, and discharging by volume and at discharge pressures the liner manufacturer recommends. Do not exceed manufacturer-specified maximum pressures. The contractor may place grout in lifts to prevent exceeding maximum allowable pressures.

#### **C.4 Site Restoration**

Replace pipe sections damaged or collapsed during installation or grouting operations. Restore the grade to its original or improved cross section. Dispose of waste material.

#### **D Measurement**

The department will measure the Culvert Pipe Liners bid items by the linear foot measured in place for each culvert location, acceptably completed.

The department will measure Cleaning Culvert Pipes for Liner Verification as each culvert, acceptably cleaned. The department will only measure culverts the engineer approves for payment.

#### **E Payment**

The department will pay for measured quantities at the contract unit price under the following bid item:

| ITEM NUMBER   | DESCRIPTION                                   | UNIT |
|---------------|-----------------------------------------------|------|
| 520.9700.S.01 | Culvert Pipe Liners 18-Inch                   | LF   |
| 520.9700.S.02 | Culvert Pipe Liners 24-Inch                   | LF   |
| 520.9700.S.03 | Culvert Pipe Liners 30-Inch                   | LF   |
| 520.9750.S.01 | Cleaning Culvert Pipes for Liner Verification | Each |

Payment for the Culvert Pipe Liners bid items is full compensation for providing pipe liners; obtaining easements; for excavation and pumping; for cleaning the existing pipe before liner installation; for pressure grouting; for replacing contractor-damaged pipe and endwalls; and for restoring the grade and disposing of waste materials.

The department will pay the contractor \$150 per cubic yard for grout required in excess of 110 percent of the theoretical quantity required to fill the space between the inside diameter of the existing pipe and the outside diameter of the liner.

Payment for Cleaning Culvert Pipes for Liner Verification is full compensation for cleaning required to verify liner length and diameter; for excavation and pumping; and for disposing of waste material.

The department will pay separately for replacing unserviceable endwalls not rendered unserviceable by contractor operations under the appropriate contract endwall bid item, or absent the appropriate item as extra work.

520-015 (20140630)

**ADDITIONAL SPECIAL PROVISION 4**

**Payment to First-Tier Subcontractors**

Within 10 calendar days of receiving a progress payment for work completed by a subcontractor, pay the subcontractor for that work. The prime contractor may withhold payment to a subcontractor if, within 10 calendar days of receipt of that progress payment, the prime contractor provides written notification to the subcontractor and the department documenting "just cause" for withholding payment.

The prime contractor may also withhold routine retainage from payments due subcontractors.

**Payment to Lower-Tier Subcontractors**

Ensure that subcontracting agreements at all tiers provide prompt payment rights to lower-tier subcontractors that parallel those granted first-tier subcontractors in this provision.

**Release of Routine Retainage**

After granting substantial completion the department may reduce the routine retainage withheld from the prime contractor to 75 percent of the original total amount retained.

When the Department sends the semi-final estimate the department may reduce the routine retainage withheld from the prime contractor to 10 percent of the original total amount retained.

Within 30 calendar days of receiving the semi-final estimate from the department, submit written certification that subcontractors at all tiers are paid in full for acceptably completed work and that no routine retainage is being withheld. The department will pay the prime contractor in full and reduce the routine retainage withheld from the prime contractor to zero when the department approves the final estimate.

This special provision does not limit the right of the department, prime contractor, or subcontractors at any tier to withhold payment for work not acceptably completed or work subject to an unresolved contract dispute.

## ADDITIONAL SPECIAL PROVISION 6

### ASP 6 - Modifications to the standard specifications

*Make the following revisions to the standard specifications:*

---

#### 550.5.2 Piling

*Add the following as paragraph three effective with the December 2015 letting:*

- (3) The department will not entertain a change order request for a differing site condition under 104.2.2.2 or for a quantity change under 104.2.2.4.3 for the Piling bid items. Instead the department will adjust pay under the Piling Quantity Variation administrative item if the total driven length of each size is less than 85 percent of, or more than 115 percent of the contract quantity as follows:
- | Percent of Contract Length Driven | Pay Adjustment                                           |
|-----------------------------------|----------------------------------------------------------|
| < 85                              | ( 85% contract length - driven length ) x 20% unit price |
| > 115                             | (driven length - 115% contract length) x 5% unit price   |
- 

#### 643.2.1 General

*Replace paragraph two with the following effective with the December 2015 letting:*

- (2) Use reflective sheeting from the department's approved products list on barricades, drums, and flexible tubular marker posts.

## Errata

---

*Make the following corrections to the standard specifications:*

---

#### 641.2.9 Overhead Sign Supports

*Correct errata adding back accidentally deleted paragraphs one through three.*

- (1) Provide commercially fabricated overhead sign supports conforming to AASHTO design and fabrication standards for structural supports for highway signs, luminaires, and traffic signals. Use a design life of 50 years with a wind importance factor of 1.00. Design to withstand a 3 second gust wind speed of 90 mph. Do not use the methods of appendix C of those AASHTO standards.
- (2) Design structures, listed as applicable structure types in the AASHTO standards, to the fatigue category criteria as follows:
  1. Structures carrying variable message signs:
    - Category I criteria for structures over all roadway types.
  2. Structures carrying type II or III signs:
    - Category I criteria for structures used over highways and free flow ramps.
    - Category II criteria for structures with arms greater than 30 feet used over local roads and city streets.
    - Category III criteria for structures with arms 30 feet or less used over local roads and city streets.
- (3) Use the posted speed limit of the roadway beneath the structure for truck-induced gusts.
- (4) Submit shop drawings identified by structure number, design computations, and material specifications, to the engineer before erecting sign supports. Provide tightening procedures for mast arm or luminaire arm to pole shaft connections on the shop drawings. Have a professional engineer registered in the state of Wisconsin sign, seal, and date the shop drawings and certify that the design conforms to AASHTO standards and the contract.
- (5) Provide steel pole shafts and mast arms zinc coated according to ASTM A123. Provide tapered pole and arm shafts with a minimum taper of 0.14 inch per foot for single-member vertical and single-member horizontal structure components. Provide bolts and other hardware conforming to 641.2.2.

**ADDITIONAL SPECIAL PROVISION 7**

- A. Reporting 1<sup>st</sup> Tier and DBE Payments During Construction
1. Comply with reporting requirements specified in the department's Civil Rights Compliance, Contractor's User Manual, Sublets and Payments.
  2. Report payments to all DBE firms within 10 calendar days of receipt of a progress payment by the department or a contractor for work performed, materials furnished, or materials stockpiled by a DBE firm. Report the payment as specified in A(1) for all work satisfactorily performed and for all materials furnished or stockpiled.
  3. Report payments to all first tier subcontractor relationships within 10 calendar days of receipt of a progress payment by the department for work performed. Report the payment as specified in A(1) for all work satisfactorily performed.
  4. All tiers shall report payments as necessary to comply with the DBE payment requirement as specified in A(2).
  5. Require all first tier relationships, DBE firms and all other tier relationships necessary to comply with the DBE payment requirement in receipt of a progress payment by contractor to acknowledge receipt of payment as specified in A(1), (2), (3) and (4).
  6. All agreements made by a contractor shall include the provisions in A(1), (2), (3), (4) and (5), and shall be binding on all first tier subcontractor relationships and all contractors and subcontractors utilizing DBE firms on the project.
- B. Costs for conforming to this special provision are incidental to the contract.



## **ADDITIONAL SPECIAL PROVISION 9**

### **Electronic Certified Payroll Submittal**

(1) Use the department's Civil Rights Compliance System (CRCS) to submit certified payrolls electronically. Details are available online through the department's highway construction contractor information (HCCI) site on the Labor, Wages, and EEO Information page at:

<http://wisconsindot.gov/Pages/doing-bus/civil-rights/labornwage/default.aspx>

(2) Ensure that all tiers of subcontractors, as well as all trucking firms, submit their weekly certified payrolls electronically through CRCS. These payrolls are due within seven calendar days following the close of the payroll period. Every firm providing physical labor towards completing the project is a subcontractor under this special provision.

(3) Upon receipt of contract execution, promptly make all affected firms aware of the requirements under this special provision and arrange for them to receive CRCS training as they are about to begin payrolls. The department will provide training either in a classroom setting at one of our regional offices or by telephone. Contact Tess Mulrooney at 608-267-4489 to schedule the training.

(4) The department will reject all paper submittals of forms DT-1816 and DT-1929 for information required under this special provision. All costs for conforming to this special provision are incidental to the contract.

(5) Firms wishing to export payroll data from their computer system into CRCS should have their payroll coordinator send several sample electronic files to Tess two months before a payroll needs to be submitted. Not every contractor's payroll system is capable of producing export files. For details, see pages 17-22 of the CRCS System Background Information manual available online on the Labor, Wages, and EEO Information page at:

<http://wisconsindot.gov/Documents/doing-bus/civil-rights/labornwage/crcs-payroll-manual.pdf>

**Effective August 2015 letting**

**BUY AMERICA PROVISION**

All steel and iron materials permanently incorporated in this project shall be domestic products and all manufacturing and coating processes for these materials from smelting forward in the manufacturing process must have occurred within the United States. Coating includes epoxy coating, galvanizing, painting and any other coating that protects or enhances the value of a material subject to the requirements of Buy America. The exemption of this requirement is the minimal use of foreign materials if the total cost of such material permanently incorporated in the product does not exceed one-tenth of one percent (1/10 of 1%) of the total contract cost or \$2,500.00, whichever is greater. For purposes of this paragraph, the cost is that shown to be the value of the subject products as they are delivered to the project. The contractor shall take actions and provide documentation conforming to CMM 2-28.5 to ensure compliance with this "Buy America" provision.

<http://wisconsindot.gov/rdwy/cmm/cm-02-28.pdf>

Upon completion of the project certify to the engineer, in writing using department form WS4567, that all steel, iron, and coating processes for steel or iron incorporated into the contract work conform to these "Buy America" provisions. Attach a list of exemptions and their associated costs to the certification form. Department form WS4567 is available at:

<http://wisconsindot.gov/rdwy/worksheets/ws4567.doc>

**Effective with September 2004 Letting**

**WISCONSIN DEPARTMENT OF TRANSPORTATION  
DIVISION OF HIGHWAYS AND TRANSPORTATION FACILITIES**

**SUPPLEMENTAL REQUIRED CONTRACT PROVISIONS**

- I. Wage Rates, Hours of labor and payment of Wages
- II. Payroll Requirements
- III. Postings at the Site of the Work
- IV. Affidavits
- V. Wage Rate Redistribution
- VI. Additional Classifications

**I. WAGE RATES, HOURS OF LABOR AND PAYMENT OF WAGES**

The schedule of "Minimum Wage Rates" attached hereto and made a part hereof furnishes the prevailing wage rates that have been determined pursuant to Section 103.50 of the Wisconsin Statutes. These wage rates are the minimum required to be paid to the various laborers, workers, mechanics and truck drivers employed by contractors and subcontractors on the construction work embraced by the contract and subject to prevailing hours and wages under Section 103.50, Stats. If necessary to employ laborers, workers, mechanics or truck drivers whose classification is not listed on the schedule, they shall be paid at rates conformable to those listed for similar classifications. Apprentices shall be paid at rates not less than those prescribed in their state indenture contracts.

While the wage rates shown are the minimum rates required by the contract to be paid during its life, this is not a representation that labor can be obtained at these rates. It is the responsibility of bidders to inform themselves as to the local labor conditions and prospective changes or adjustments of wage rates. No increase in the contract price shall be allowed or authorized on account of the payment of wage rates in excess of those listed herein.

Pursuant to Section 103.50 of the Wisconsin Statutes, the prevailing hours of labor have been determined to be up to 10 hours per day and 40 hours per calendar week Monday through Friday. If any laborer, worker, mechanic or truck driver is permitted or required to work more than the prevailing number of hours per day or per calendar week on this contract, they shall be paid for all hours in excess of the prevailing hours at a rate of at least one and one-half (1 1/2) times their hourly rate of pay. All work on Saturday, Sunday and the following holidays is to be paid at time and a half: (1) January 1, (2) the last Monday in May, (3) July 4, (4) the first Monday in September, (5) the fourth Thursday in November, (6) December 25, (7) the day before if January 1, July 4 or December 25 falls on a Saturday and (8) the day following if January 1, July 4 or December 25 falls on a Sunday.

All laborers, workers, mechanics and truck drivers shall be paid unconditionally not less often than once a week. Persons who own and operate their own trucks must receive the prevailing truck driver rate for the applicable type of truck (i.e. 2 axle, 3 or more axle, articulated, eculid or dumptor) he or she operates, plus an agreed upon amount for the use of his or her truck. Every owner-operator MUST be paid separately for their driving and for the use of their truck.

For those projects subject to the requirements of the Davis-Bacon Act, the Secretary of Labor will also have determined "Minimum Wage Rates" for work to be performed under the contract. These rates are, for all or most of the labor, worker, mechanic or truck driver classifications, identical to those established under Section 103.50 of the Wisconsin Statutes. In the event the rates are not identical, the higher of the two rates will govern.

## **II. PAYROLL REQUIREMENTS**

All contractors and subcontractors must submit weekly Certified Payrolls and Compliance Statement verifying that all laborers, workers, mechanics and truck drivers working on the project have been paid the prevailing wage rates for all work performed under the contract required by Section 103.50 of the Wisconsin Statutes.

## **III. POSTINGS AT THE SITE OF THE WORK**

In addition to the required postings furnished by the Department, the contractor shall post the following in at least one conspicuous place at the site of work:

- a. "NOTICE TO EMPLOYEES," which provides information required to be posted by the provisions of Section 103.50 of the Wisconsin Statutes.
- b. A copy of the State of Wisconsin Minimum Wages Rates. (Four pages.)
- c. A copy of the contractor's Equal Employment Opportunity Policy.
- d. On any project involving federal aid, in addition to the furnished postings, the contractor shall post a copy of the "Davis-Bacon Act, Minimum Wage Rates". (Three pages.)

## **IV. WAGE RATE REDISTRIBUTION**

The amount specified as the hourly basic rate of pay and the amount(s) specified as the fringe benefit contribution(s), for all classes of laborers, workers, mechanics or truck drivers may be redistributed, when necessary, to conform to those specified in any applicable collective bargaining agreement, provided that both parties to such agreement

request and receive the approval for any such redistribution from both the Department of Transportation and the Department of Workforce Development prior to the implementation of such redistribution.

## **V. ADDITIONAL CLASSIFICATIONS**

Any unlisted laborer or mechanic classification that is needed to perform work on this project, and is not included within the scope of any of the classifications listed in the application prevailing wage rate determination, may be added after award only if all of the following criteria have been met:

1. The affected employer(s) must make a written request to WisDOT Central Office to utilize the unlisted classification on this project.
2. The request must indicate the scope of the work to be performed by the unlisted classification and must indicate the proposed wage/fringe benefit package that the unlisted classification is to receive.
3. The work to be performed by the unlisted classification must not be performed by a classification that is included in the applicable prevailing wage rate determination.
4. The unlisted classification must be commonly employed in the area where the project is located.
5. The proposed wage/fringe benefit package must bear a reasonable relationship to those set forth in the applicable prevailing wage rate determination.
6. The request should be made prior to the actual performance of the work by the unlisted classification.
7. DWD must approve the use of the unlisted classification and the proposed wage/fringe benefit package. USDOL also must approve the use of the unlisted classification and the proposed wage/fringe benefit package on federal aid projects.
8. WisDOT and DWD may amend the proposed wage/fringe benefit package, as deemed necessary, and may set forth specific employment ratios and scope of work requirements in the approval document.

The approved wage/fringe benefit package shall be paid to all laborers, workers, mechanics or truck drivers performing work within the scope of that performed by the unlisted classification, from the first day on which such work is performed. In the event that work is performed by the unlisted classification prior to approval, the wage/fringe benefit package to be paid for such work must be in conformance with the wage/fringe

benefit package approved for such work. Under this arrangement a retroactive adjustment in wages and/or fringe benefits may be required to be made to the affected laborers, workers, mechanics or truck drivers by the affected employer(s).

**ANNUAL PREVAILING WAGE RATE DETERMINATION  
FOR ALL STATE HIGHWAY PROJECTS  
MONROE COUNTY**

Compiled by the State of Wisconsin - Department of Workforce Development  
for the Department of Transportation  
Pursuant to s. 103.50, Stats.  
Issued on May 1, 2015

**CLASSIFICATION:** Contractors are required to call the Department of Workforce Development if there are any questions regarding the proper trade or classification to be used for any worker on a public works project.

**OVERTIME:** Time and one-half must be paid for all hours worked over 10 hours per day and 40 hours per calendar week and for all hours worked on Saturday, Sunday and the following six (6) holidays: January 1; the last Monday in May; July 4; the 1st Monday in September; the 4th Thursday in November; December 25; the day before if January 1, July 4 or December 25 falls on a Saturday; the day following if January 1, July 4 or December 25 falls on a Sunday.

**FUTURE INCREASE:** If indicated for a specific trade or occupation, the full amount of such increase MUST be added to the "TOTAL" indicated for such trade or occupation on the date(s) such increase(s) becomes effective.

**PREMIUM PAY:** If indicated for a specific trade or occupation, the full amount of such pay MUST be added to the "HOURLY BASIC RATE OF PAY" indicated for such trade or occupation, whenever such pay is applicable.

**SUBJOURNEY:** Wage rates may be available for some of the classifications indicated below. Any employer that desires to use any subjourney classification on a project MUST request the applicable wage rate from the Department of Workforce Development PRIOR to the date such classification is used on such project. Form ERD-10880 is available for this purpose and can be obtained by writing to the Department of Workforce Development, Equal Rights Division, P.O. Box 8928, Madison, WI 53708.

| <u>TRADE OR OCCUPATION</u>                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | <u>HOURLY<br/>BASIC RATE<br/>OF PAY</u> | <u>HOURLY<br/>FRINGE<br/>BENEFITS</u> | <u>TOTAL</u> |
|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------|---------------------------------------|--------------|
|                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | \$                                      | \$                                    | \$           |
| Bricklayer, Blocklayer or Stonemason                                                                                                                                                                                                                                                                                                                                                                                                                                                                 | 30.28                                   | 18.18                                 | 48.46        |
| Carpenter                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            | 32.72                                   | 16.00                                 | 48.72        |
| Future Increase(s): Add \$1.42/hr on 6/1/2015; Add \$1.42/hr on 6/1/2016.<br>Premium Pay: DOT PREMIUM: Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day.                                                                                                                                                                                                                                                   |                                         |                                       |              |
| Cement Finisher                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | 33.95                                   | 18.01                                 | 51.96        |
| Future Increase(s): Add \$1.87 on 6/1/15; Add \$1.75 on 6/1/16.<br>Premium Pay: DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.40/hr when the Wisconsin Department of Transportation or responsible governing agency requires that work be performed at night under artificial illumination with traffic control and the work is completed after sunset and before sunrise. |                                         |                                       |              |
| Electrician                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          | 30.59                                   | 18.37                                 | 48.96        |
| Premium Pay: DOT PREMIUM: Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day.                                                                                                                                                                                                                                                                                                                                |                                         |                                       |              |
| Fence Erector                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | 18.50                                   | 10.14                                 | 28.64        |
| Ironworker                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | 31.50                                   | 20.01                                 | 51.51        |
| Line Constructor (Electrical)                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | 39.50                                   | 18.54                                 | 58.04        |
| Painter                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              | 26.65                                   | 13.10                                 | 39.75        |
| Pavement Marking Operator                                                                                                                                                                                                                                                                                                                                                                                                                                                                            | 26.04                                   | 20.63                                 | 46.67        |
| Piledriver                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | 30.11                                   | 26.51                                 | 56.62        |
| Future Increase(s): Add \$1.50/hr on 6/1/2015; Add \$1.60/hr on 6/1/2016.<br>Premium Pay: Add \$.65/hr for Piledriver Loftsmen; Add \$.75/hr for Sheet Piling Loftsmen. DOT PREMIUM: Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day.                                                                                                                                                                     |                                         |                                       |              |
| Roofer or Waterproofer                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | 26.25                                   | 4.21                                  | 30.46        |
| Teledata Technician or Installer                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | 22.25                                   | 12.24                                 | 34.49        |

| <b>TRADE OR OCCUPATION</b>                                   | <b>HOURLY<br/>BASIC RATE<br/>OF PAY</b> | <b>HOURLY<br/>FRINGE<br/>BENEFITS</b> | <b>TOTAL</b> |
|--------------------------------------------------------------|-----------------------------------------|---------------------------------------|--------------|
|                                                              | <b>\$</b>                               | <b>\$</b>                             | <b>\$</b>    |
| Tuckpointer, Caulker or Cleaner                              | 23.60                                   | 7.10                                  | 30.70        |
| Underwater Diver (Except on Great Lakes)                     | 35.40                                   | 15.90                                 | 51.30        |
| Heavy Equipment Operator - ELECTRICAL LINE CONSTRUCTION ONLY | 35.55                                   | 15.57                                 | 51.12        |
| Light Equipment Operator -ELECTRICAL LINE CONSTRUCTION ONLY  | 31.60                                   | 14.98                                 | 46.58        |
| Heavy Truck Driver - ELECTRICAL LINE CONSTRUCTION ONLY       | 27.65                                   | 13.44                                 | 41.09        |
| Light Truck Driver - ELECTRICAL LINE CONSTRUCTION ONLY       | 25.68                                   | 12.83                                 | 38.51        |
| Groundman - ELECTRICAL LINE CONSTRUCTION ONLY                | 21.75                                   | 11.63                                 | 33.38        |

**TRUCK DRIVERS**

|                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |       |       |       |
|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|-------|-------|
| Single Axle or Two Axle                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | 25.18 | 18.31 | 43.49 |
| Future Increase(s): Add \$1.15/hr on 6/1/2015.<br>Premium Pay: DOT PREMIUM: Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day.                                                                                                                                                                                                                                                                                                                                    |       |       |       |
| Three or More Axle                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | 25.28 | 18.31 | 43.59 |
| Future Increase(s): Add \$1.15/hr on 6/1/2015.<br>Premium Pay: DOT PREMIUM: Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day.                                                                                                                                                                                                                                                                                                                                    |       |       |       |
| Articulated, Euclid, Dumptor, Off Road Material Hauler                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | 30.27 | 21.15 | 51.42 |
| Future Increase(s): Add \$1.25/hr on 6/1/2015; Add \$1.30/hr on 6/1/2016; Add \$1.25/hr on 6/1/2017.<br>Premium Pay: DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.50/hr night work premium.<br>See DOT'S website for details about the applicability of this night work premium at: <a href="http://www.dot.wi.gov/business/civilrights/laborwages/pwc.htm">http://www.dot.wi.gov/business/civilrights/laborwages/pwc.htm</a> . |       |       |       |
| Pavement Marking Vehicle                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   | 23.16 | 20.01 | 43.17 |
| Shadow or Pilot Vehicle                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | 24.37 | 17.77 | 42.14 |
| Truck Mechanic                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             | 24.52 | 17.77 | 42.29 |

**LABORERS**

|                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |       |       |       |
|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|-------|-------|
| General Laborer                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            | 30.13 | 15.14 | 45.27 |
| Future Increase(s): Add \$1.05/hr eff. 06/01/2015; Add \$1.00/hr eff. 06/01/2016; Add \$1.00/hr eff. 06/01/2017<br>Premium Pay: Add \$.10/hr for topman, air tool operator, vibrator or tamper operator (mechanical hand operated), chain saw operator and demolition burning torch laborer; Add \$.15/hr for bituminous worker (raker and luteman), formsetter (curb, sidewalk and pavement) and strike off man; Add \$.20/hr for blaster and powderman; Add \$.25/hr for bottomman; Add \$.35/hr for line and grade specialist; Add \$.45/hr for pipelayer.<br>DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.25/hr for work on projects involving temporary traffic control setup, for lane and shoulder closures, when work under artificial illumination conditions is necessary as required by the project provisions (including prep time prior to and/or cleanup after such time period). |       |       |       |
| Asbestos Abatement Worker                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | 24.58 | 14.61 | 39.19 |
| Landscaper                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 | 30.13 | 15.14 | 45.27 |
| Future Increase(s): Add \$1.05/hr eff. 06/01/2015; Add \$1.00/hr eff. 06/01/2016; Add \$1.00/hr eff. 06/01/2017<br>Premium Pay: DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.25/hr for work on projects involving temporary traffic control setup, for lane and shoulder closures, when work under artificial illumination conditions is necessary as required by the project provisions (including prep time prior to and/or cleanup after such time period).                                                                                                                                                                                                                                                                                                                                                                                                                                  |       |       |       |

| <b>TRADE OR OCCUPATION</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | <b>HOURLY<br/>BASIC RATE<br/>OF PAY</b> | <b>HOURLY<br/>FRINGE<br/>BENEFITS</b> | <b>TOTAL</b> |
|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------|---------------------------------------|--------------|
|                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | <b>\$</b>                               | <b>\$</b>                             | <b>\$</b>    |
| Flagperson or Traffic Control Person                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 | 26.76                                   | 15.14                                 | 41.90        |
| Future Increase(s): Add \$1.05/hr eff. 06/01/2015; Add \$1.00/hr eff. 06/01/2016; Add \$1.00/hr eff. 06/01/2017<br>Premium Pay: DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.25/hr when the Wisconsin Department of Transportation or responsible governing agency requires that work be performed at night under artificial illumination with traffic control and the work is completed after sunset and before sunrise. |                                         |                                       |              |
| Fiber Optic Laborer (Outside, Other Than Concrete Encased)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | 18.33                                   | 13.65                                 | 31.98        |
| Railroad Track Laborer                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | 14.50                                   | 3.71                                  | 18.21        |

### HEAVY EQUIPMENT OPERATORS

|                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |       |       |       |
|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|-------|-------|
| Crane, Tower Crane, Pedestal Tower or Derrick, With Boom, Leads &/or Jib Lengths Measuring 176 Ft or Over; Crane, Tower Crane, Pedestal Tower or Derrick, With or Without Attachments, With a Lifting Capacity of Over 100 Tons, Self-Erecting Tower Crane With a Lifting Capacity Of Over 4,000 Lbs., Crane With Boom Dollies; Traveling Crane (Bridge Type).                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | 37.72 | 21.15 | 58.87 |
| Future Increase(s): Add \$1.25/hr on 6/1/2015; Add \$1.30/hr on 6/1/2016; Add \$1.25/hr on 6/1/2017.<br>Premium Pay: DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.50/hr night work premium.<br>See DOT'S website for details about the applicability of this night work premium at: <a href="http://www.dot.wi.gov/business/civilrights/laborwages/pwc.htm">http://www.dot.wi.gov/business/civilrights/laborwages/pwc.htm</a> .                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |       |       |       |
| Backhoe (Track Type) Having a Mfr.'s Rated Capacity of 130,000 Lbs. or Over; Caisson Rig; Crane, Tower Crane, Portable Tower, Pedestal Tower or Derrick, With Boom, Leads &/or Jib Lengths Measuring 175 Ft or Under; Crane, Tower Crane, Portable Tower, Pedestal Tower or Derrick, With or Without Attachments, With a Lifting Capacity of 100 Tons or Under, Self-Erecting Tower Crane With A Lifting Capacity Of 4,000 Lbs., & Under; Dredge (NOT Performing Work on the Great Lakes); Licensed Boat Pilot (NOT Performing Work on the Great Lakes); Pile Driver.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             | 37.22 | 21.15 | 58.37 |
| Future Increase(s): Add \$1.25/hr on 6/1/2015; Add \$1.30/hr on 6/1/2016; Add \$1.25/hr on 6/1/2017.<br>Premium Pay: DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.50/hr night work premium.<br>See DOT'S website for details about the applicability of this night work premium at: <a href="http://www.dot.wi.gov/business/civilrights/laborwages/pwc.htm">http://www.dot.wi.gov/business/civilrights/laborwages/pwc.htm</a> .                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |       |       |       |
| Air Track, Rotary or Percussion Drilling Machine &/or Hammers, Blaster; Asphalt Heater, Planer & Scarifier; Asphalt Milling Machine; Asphalt Screed; Automatic Subgrader (Concrete); Backhoe (Track Type) Having a Mfr.'s Rated Capacity of Under 130,000 Lbs., Backhoe (Mini, 15,000 Lbs. & Under); Bituminous (Asphalt) Plant & Paver, Screed; Boatmen (NOT Performing Work on the Great Lakes); Boring Machine (Directional, Horizontal or Vertical); Bridge (Bidwell) Paver; Bulldozer or Endloader; Concrete Batch Plant, Batch Hopper; Concrete Breaker (Large, Auto, Vibratory/Sonic, Manual or Remote); Concrete Bump Cutter, Grinder, Planing or Grooving Machine; Concrete Conveyor System; Concrete Laser/Screed; Concrete Paver (Slipform); Concrete Pump, Concrete Conveyor (Rotec or Bidwell Type); Concrete Slipform Placer Curb & Gutter Machine; Concrete Spreader & Distributor; Crane (Carry Deck, Mini) or Truck Mounted Hydraulic Crane (10 Tons or Under); Crane With a Lifting Capacity of 25 Tons or Under; Forestry Equipment, Timbco, Tree Shear, Tub Grinder, Processor; Gradall (Cruz-Aire Type); Grader or Motor Patrol; Grout Pump; Hydro-Blaster (10,000 PSI or Over); Loading Machine (Conveyor); | 36.72 | 21.15 | 57.87 |

| <u>TRADE OR OCCUPATION</u>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | <u>HOURLY<br/>BASIC RATE<br/>OF PAY</u> | <u>HOURLY<br/>FRINGE<br/>BENEFITS</u> | <u>TOTAL</u> |
|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------|---------------------------------------|--------------|
|                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | \$                                      | \$                                    | \$           |
| Material or Stack Hoist; Mechanic or Welder; Milling Machine; Post Hole Digger or Driver; Roller (Over 5 Ton); Scraper (Self Propelled or Tractor Drawn) 5 cu yds or More Capacity; Shoulder Widener; Sideboom; Skid Rig; Stabilizing or Concrete Mixer (Self-Propelled or 14S or Over); Straddle Carrier or Travel Lift; Tractor (Scraper, Dozer, Pusher, Loader); Tractor or Truck Mounted Hydraulic Backhoe; Trencher (Wheel Type or Chain Type); Tube Finisher; Tugger (NOT Performing Work on the Great Lakes); Winches & A- Frames.<br>Future Increase(s): Add \$1.25/hr on 6/1/2015; Add \$1.30/hr on 6/1/2016; Add \$1.25/hr on 6/1/2017.<br>Premium Pay: DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.50/hr night work premium.<br>See DOT'S website for details about the applicability of this night work premium at: <a href="http://www.dot.wi.gov/business/civilrights/laborwages/pwc.htm">http://www.dot.wi.gov/business/civilrights/laborwages/pwc.htm</a> .                                                                                                                                                                                                                          |                                         |                                       |              |
| Belting, Burlap, Texturing Machine; Broom or Sweeper; Compactor (Self-Propelled or Tractor Mounted, Towed & Light Equipment); Concrete Finishing Machine (Road Type); Environmental Burner; Farm or Industrial Type Tractor; Fireman (Asphalt Plant, Pile Driver & Derrick NOT Performing Work on the Great Lakes); Forklift; Greaser; Hoist (Tugger, Automatic); Jeep Digger; Joint Sawyer (Multiple Blade); Launch (NOT Performing Work on the Great Lakes); Lift Slab Machine; Mechanical Float; Mulcher; Power Subgrader; Robotic Tool Carrier (With or Without Attachments); Roller (Rubber Tire, 5 Ton or Under); Self Propelled Chip Spreader; Shouldering Machine; Skid Steer Loader (With or Without Attachments); Telehandler; Tining or Curing Machine.<br>Future Increase(s): Add \$1.25/hr on 6/1/2015; Add \$1.30/hr on 6/1/2016; Add \$1.25/hr on 6/1/2017.<br>Premium Pay: DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.50/hr night work premium.<br>See DOT'S website for details about the applicability of this night work premium at: <a href="http://www.dot.wi.gov/business/civilrights/laborwages/pwc.htm">http://www.dot.wi.gov/business/civilrights/laborwages/pwc.htm</a> . | 36.46                                   | 21.15                                 | 57.61        |
| Air Compressor (&/or 400 CFM or Over); Air, Electric or Hydraulic Jacking System; Augers (Vertical & Horizontal); Automatic Belt Conveyor & Surge Bin; Boiler (Temporary Heat); Concrete Proportioning Plant; Crusher, Screening or Wash Plant; Generator (&/or 150 KW or Over); Heaters (Mechanical); High Pressure Utility Locating Machine (Daylighting Machine); Mudjack; Oiler; Prestress Machine; Pug Mill; Pump (3 Inch or Over) or Well Points; Rock, Stone Breaker; Screed (Milling Machine); Stump Chipper; Tank Car Heaters; Vibratory Hammer or Extractor, Power Pack.<br>Future Increase(s): Add \$1.25/hr on 6/1/2015; Add \$1.30/hr on 6/1/2016; Add \$1.25/hr on 6/1/2017.<br>Premium Pay: DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.50/hr night work premium.<br>See DOT'S website for details about the applicability of this night work premium at: <a href="http://www.dot.wi.gov/business/civilrights/laborwages/pwc.htm">http://www.dot.wi.gov/business/civilrights/laborwages/pwc.htm</a> .                                                                                                                                                                                 | 36.17                                   | 21.15                                 | 57.32        |
| Fiber Optic Cable Equipment.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | 28.89                                   | 17.95                                 | 46.84        |

## Wisconsin Department of Transportation

PAGE: 1

DATE: 12/08/15

REVISED:

## SCHEDULE OF ITEMS

CONTRACT:  
20160209005PROJECT(S):  
1071-02-60FEDERAL ID(S):  
N/A

CONTRACTOR : \_\_\_\_\_

| LINE<br>NO | ITEM<br>DESCRIPTION | APPROX.<br>QUANTITY<br>AND UNITS | UNIT PRICE |     | BID AMOUNT |     |
|------------|---------------------|----------------------------------|------------|-----|------------|-----|
|            |                     |                                  | DOLLARS    | CTS | DOLLARS    | CTS |

## SECTION 0001 Contract Items

|      |                                                           |            |   |  |   |  |
|------|-----------------------------------------------------------|------------|---|--|---|--|
| 0010 | 201.0105 Clearing                                         | 95.000     |   |  |   |  |
|      |                                                           | STA        | . |  | . |  |
| 0020 | 201.0205 Grubbing                                         | 30.000     |   |  |   |  |
|      |                                                           | STA        | . |  | . |  |
| 0030 | 203.0100 Removing Small<br>Pipe Culverts                  | 12.000     |   |  |   |  |
|      |                                                           | EACH       | . |  | . |  |
| 0040 | 204.0100 Removing<br>Pavement                             | 71,525.000 |   |  |   |  |
|      |                                                           | SY         | . |  | . |  |
| 0050 | 205.0100 Excavation<br>Common                             | 10.000     |   |  |   |  |
|      |                                                           | CY         | . |  | . |  |
| 0060 | 208.0100 Borrow                                           | 2,250.000  |   |  |   |  |
|      |                                                           | CY         | . |  | . |  |
| 0070 | 211.0400 Prepare<br>Foundation for Asphaltic<br>Shoulders | 924.000    |   |  |   |  |
|      |                                                           | STA        | . |  | . |  |
| 0080 | 213.0100 Finishing<br>Roadway (project) 01.<br>1071-02-60 | 1.000      |   |  |   |  |
|      |                                                           | EACH       | . |  | . |  |
| 0090 | 305.0110 Base Aggregate<br>Dense 3/4-Inch                 | 5,750.000  |   |  |   |  |
|      |                                                           | TON        | . |  | . |  |
| 0100 | 305.0120 Base Aggregate<br>Dense 1 1/4-Inch               | 95.000     |   |  |   |  |
|      |                                                           | TON        | . |  | . |  |

## Wisconsin Department of Transportation

PAGE: 2

DATE: 12/08/15

REVISED:

## SCHEDULE OF ITEMS

CONTRACT:  
20160209005PROJECT(S):  
1071-02-60FEDERAL ID(S):  
N/A

CONTRACTOR : \_\_\_\_\_

| LINE<br>NO | ITEM<br>DESCRIPTION                               | APPROX.<br>QUANTITY<br>AND UNITS | UNIT PRICE |     | BID AMOUNT |     |
|------------|---------------------------------------------------|----------------------------------|------------|-----|------------|-----|
|            |                                                   |                                  | DOLLARS    | CTS | DOLLARS    | CTS |
| 0110       | 390.0403 Base Patching<br>Concrete Shes           | 545.000<br>SY                    | .          |     | .          |     |
| 0120       | 415.6000 S Rout and Seal                          | 100,070.000<br>LF                | .          |     | .          |     |
| 0130       | 416.0610 Drilled Tie<br>Bars                      | 50.000<br>EACH                   | .          |     | .          |     |
| 0140       | 416.0620 Drilled Dowel<br>Bars                    | 3,760.000<br>EACH                | .          |     | .          |     |
| 0150       | 416.1715 Concrete<br>Pavement Repair SHES         | 1,560.000<br>SY                  | .          |     | .          |     |
| 0160       | 416.1725 Concrete<br>Pavement Replacement<br>SHES | 295.000<br>SY                    | .          |     | .          |     |
| 0170       | 455.0105 Asphaltic<br>Material PG58-28            | 900.000<br>TON                   | .          |     | .          |     |
| 0180       | 455.0605 Tack Coat                                | 190.000<br>GAL                   | .          |     | .          |     |
| 0190       | 460.1100 HMA Pavement<br>Type E-0.3               | 16,100.000<br>TON                | .          |     | .          |     |
| 0200       | 460.1110 HMA Pavement<br>Type E-10                | 120.000<br>TON                   | .          |     | .          |     |
| 0210       | 465.0400 Asphaltic<br>Shoulder Rumble Strips      | 97,000.000<br>LF                 | .          |     | .          |     |

## Wisconsin Department of Transportation

PAGE: 3

DATE: 12/08/15

REVISED:

## SCHEDULE OF ITEMS

CONTRACT:  
20160209005PROJECT(S):  
1071-02-60FEDERAL ID(S):  
N/A

CONTRACTOR : \_\_\_\_\_

| LINE<br>NO | ITEM<br>DESCRIPTION                                                           | APPROX.<br>QUANTITY<br>AND UNITS | UNIT PRICE |     | BID AMOUNT |     |
|------------|-------------------------------------------------------------------------------|----------------------------------|------------|-----|------------|-----|
|            |                                                                               |                                  | DOLLARS    | CTS | DOLLARS    | CTS |
| 0220       | 520.8000 Concrete<br>Collars for Pipe                                         | 249.000<br>EACH                  | .          |     | .          |     |
| 0230       | 520.8700 Cleaning<br>Culvert Pipes                                            | 154.000<br>EACH                  | .          |     | .          |     |
| 0240       | 520.9700.S Culvert Pipe<br>Liners (size) 01.<br>18-Inch                       | 472.000<br>LF                    | .          |     | .          |     |
| 0250       | 520.9700.S Culvert Pipe<br>Liners (size) 02.<br>24-Inch                       | 158.000<br>LF                    | .          |     | .          |     |
| 0260       | 520.9700.S Culvert Pipe<br>Liners (size) 03.<br>30-Inch                       | 80.000<br>LF                     | .          |     | .          |     |
| 0270       | 520.9750.S Cleaning<br>Culvert Pipes for Liner<br>Verification                | 7.000<br>EACH                    | .          |     | .          |     |
| 0280       | 522.0118 Culvert Pipe<br>Reinforced Concrete<br>Class III 18-Inch             | 84.000<br>LF                     | .          |     | .          |     |
| 0290       | 522.0154 Culvert Pipe<br>Reinforced Concrete<br>Class III 54-Inch             | 14.000<br>LF                     | .          |     | .          |     |
| 0300       | 522.1018 Apron Endwalls<br>for Culvert Pipe<br>Reinforced Concrete<br>18-Inch | 5.000<br>EACH                    | .          |     | .          |     |
| 0310       | 522.1024 Apron Endwalls<br>for Culvert Pipe<br>Reinforced Concrete<br>24-Inch | 3.000<br>EACH                    | .          |     | .          |     |

## Wisconsin Department of Transportation

PAGE: 4

DATE: 12/08/15

REVISED:

## SCHEDULE OF ITEMS

CONTRACT:  
20160209005PROJECT(S):  
1071-02-60FEDERAL ID(S):  
N/A

CONTRACTOR : \_\_\_\_\_

| LINE<br>NO | ITEM<br>DESCRIPTION                                                           | APPROX.<br>QUANTITY<br>AND UNITS | UNIT PRICE |     | BID AMOUNT |     |
|------------|-------------------------------------------------------------------------------|----------------------------------|------------|-----|------------|-----|
|            |                                                                               |                                  | DOLLARS    | CTS | DOLLARS    | CTS |
| 0320       | 522.1030 Apron Endwalls<br>for Culvert Pipe<br>Reinforced Concrete<br>30-Inch | EACH 3.000                       | .          |     | .          |     |
| 0330       | 522.1054 Apron Endwalls<br>for Culvert Pipe<br>Reinforced Concrete<br>54-Inch | EACH 1.000                       | .          |     | .          |     |
| 0340       | 524.0118 Culvert Pipe<br>Salvaged 18-Inch                                     | LF 104.000                       | .          |     | .          |     |
| 0350       | 524.0124 Culvert Pipe<br>Salvaged 24-Inch                                     | LF 280.000                       | .          |     | .          |     |
| 0360       | 524.0130 Culvert Pipe<br>Salvaged 30-Inch                                     | LF 81.000                        | .          |     | .          |     |
| 0370       | 524.0136 Culvert Pipe<br>Salvaged 36-Inch                                     | LF 32.000                        | .          |     | .          |     |
| 0380       | 524.0148 Culvert Pipe<br>Salvaged 48-Inch                                     | LF 128.000                       | .          |     | .          |     |
| 0390       | 524.0154 Culvert Pipe<br>Salvaged 54-Inch                                     | LF 36.000                        | .          |     | .          |     |
| 0400       | 524.0160 Culvert Pipe<br>Salvaged 60-Inch                                     | LF 18.000                        | .          |     | .          |     |
| 0410       | 524.0618 Apron Endwalls<br>for Culvert Pipe<br>Salvaged 18-Inch               | EACH 31.000                      | .          |     | .          |     |

## SCHEDULE OF ITEMS

REVISED:

CONTRACT:  
20160209005PROJECT(S):  
1071-02-60FEDERAL ID(S):  
N/A

CONTRACTOR : \_\_\_\_\_

| LINE<br>NO | ITEM<br>DESCRIPTION                                             | APPROX.<br>QUANTITY<br>AND UNITS | UNIT PRICE |     | BID AMOUNT |     |
|------------|-----------------------------------------------------------------|----------------------------------|------------|-----|------------|-----|
|            |                                                                 |                                  | DOLLARS    | CTS | DOLLARS    | CTS |
| 0420       | 524.0624 Apron Endwalls<br>for Culvert Pipe<br>Salvaged 24-Inch | 29.000<br>EACH                   | .          |     | .          |     |
| 0430       | 524.0630 Apron Endwalls<br>for Culvert Pipe<br>Salvaged 30-Inch | 23.000<br>EACH                   | .          |     | .          |     |
| 0440       | 524.0636 Apron Endwalls<br>for Culvert Pipe<br>Salvaged 36-Inch | 20.000<br>EACH                   | .          |     | .          |     |
| 0450       | 524.0642 Apron Endwalls<br>for Culvert Pipe<br>Salvaged 42-Inch | 8.000<br>EACH                    | .          |     | .          |     |
| 0460       | 524.0648 Apron Endwalls<br>for Culvert Pipe<br>Salvaged 48-Inch | 20.000<br>EACH                   | .          |     | .          |     |
| 0470       | 524.0654 Apron Endwalls<br>for Culvert Pipe<br>Salvaged 54-Inch | 9.000<br>EACH                    | .          |     | .          |     |
| 0480       | 524.0660 Apron Endwalls<br>for Culvert Pipe<br>Salvaged 60-Inch | 5.000<br>EACH                    | .          |     | .          |     |
| 0490       | 606.0300 Riprap Heavy                                           | 50.000<br>CY                     | .          |     | .          |     |
| 0500       | 611.0430 Reconstructing<br>Inlets                               | 5.000<br>EACH                    | .          |     | .          |     |
| 0510       | 611.0642 Inlet Covers<br>Type MS                                | 9.000<br>EACH                    | .          |     | .          |     |
| 0520       | 611.3901 Inlets Median 1<br>Grate                               | 5.000<br>EACH                    | .          |     | .          |     |

## SCHEDULE OF ITEMS

REVISED:

CONTRACT:  
20160209005PROJECT(S):  
1071-02-60FEDERAL ID(S):  
N/A

CONTRACTOR : \_\_\_\_\_

| LINE<br>NO | ITEM<br>DESCRIPTION                                                             | APPROX.<br>QUANTITY<br>AND UNITS | UNIT PRICE |     | BID AMOUNT |     |
|------------|---------------------------------------------------------------------------------|----------------------------------|------------|-----|------------|-----|
|            |                                                                                 |                                  | DOLLARS    | CTS | DOLLARS    | CTS |
| 0530       | 611.3904 Inlets Median 4<br>Grate                                               | 1.000<br>EACH                    | .          |     | .          |     |
| 0540       | 618.0100 Maintenance And<br>Repair of Haul Roads<br>(project) 01.<br>1071-02-60 | 1.000<br>EACH                    | .          |     | .          |     |
| 0550       | 619.1000 Mobilization                                                           | 1.000<br>EACH                    | .          |     | .          |     |
| 0560       | 624.0100 Water                                                                  | 23.410<br>MGAL                   | .          |     | .          |     |
| 0570       | 625.0500 Salvaged<br>Topsoil                                                    | 35,500.000<br>SY                 | .          |     | .          |     |
| 0580       | 627.0200 Mulching                                                               | 35,500.000<br>SY                 | .          |     | .          |     |
| 0590       | 628.1504 Silt Fence                                                             | 1,400.000<br>LF                  | .          |     | .          |     |
| 0600       | 628.1520 Silt Fence<br>Maintenance                                              | 1,400.000<br>LF                  | .          |     | .          |     |
| 0610       | 628.1905 Mobilizations<br>Erosion Control                                       | 6.000<br>EACH                    | .          |     | .          |     |
| 0620       | 628.1910 Mobilizations<br>Emergency Erosion<br>Control                          | 5.000<br>EACH                    | .          |     | .          |     |
| 0630       | 628.7005 Inlet<br>Protection Type A                                             | 27.000<br>EACH                   | .          |     | .          |     |

## Wisconsin Department of Transportation

PAGE: 7

DATE: 12/08/15

REVISED:

## SCHEDULE OF ITEMS

CONTRACT:  
20160209005PROJECT(S):  
1071-02-60FEDERAL ID(S):  
N/A

CONTRACTOR : \_\_\_\_\_

| LINE<br>NO | ITEM<br>DESCRIPTION                     | APPROX.<br>QUANTITY<br>AND UNITS | UNIT PRICE |     | BID AMOUNT |     |
|------------|-----------------------------------------|----------------------------------|------------|-----|------------|-----|
|            |                                         |                                  | DOLLARS    | CTS | DOLLARS    | CTS |
| 0640       | 628.7504 Temporary Ditch<br>Checks      | 165.000<br>LF                    | .          |     | .          |     |
| 0650       | 628.7555 Culvert Pipe<br>Checks         | 325.000<br>EACH                  | .          |     | .          |     |
| 0660       | 629.0210 Fertilizer Type<br>B           | 26.000<br>CWT                    | .          |     | .          |     |
| 0670       | 630.0130 Seeding Mixture<br>No. 30      | 750.000<br>LB                    | .          |     | .          |     |
| 0680       | 630.0200 Seeding<br>Temporary           | 1,100.000<br>LB                  | .          |     | .          |     |
| 0690       | 633.5200 Markers Culvert<br>End         | 325.000<br>EACH                  | .          |     | .          |     |
| 0700       | 634.0612 Posts Wood<br>4x6-Inch X 12-FT | 6.000<br>EACH                    | .          |     | .          |     |
| 0710       | 634.0614 Posts Wood<br>4x6-Inch X 14-FT | 105.000<br>EACH                  | .          |     | .          |     |
| 0720       | 634.0616 Posts Wood<br>4x6-Inch X 16-FT | 97.000<br>EACH                   | .          |     | .          |     |
| 0730       | 634.0618 Posts Wood<br>4x6-Inch X 18-FT | 56.000<br>EACH                   | .          |     | .          |     |
| 0740       | 634.0620 Posts Wood<br>4x6-Inch X 20-FT | 11.000<br>EACH                   | .          |     | .          |     |

## SCHEDULE OF ITEMS

DATE: 12/08/15

REVISED:

CONTRACT:  
20160209005PROJECT(S):  
1071-02-60FEDERAL ID(S):  
N/A

CONTRACTOR : \_\_\_\_\_

| LINE<br>NO | ITEM<br>DESCRIPTION                                          | APPROX.<br>QUANTITY<br>AND UNITS | UNIT PRICE |     | BID AMOUNT |     |
|------------|--------------------------------------------------------------|----------------------------------|------------|-----|------------|-----|
|            |                                                              |                                  | DOLLARS    | CTS | DOLLARS    | CTS |
| 0750       | 635.0200 Sign Supports<br>Structural Steel HS                | 8,620.200<br>LB                  | .          |     | .          |     |
| 0760       | 635.0300 Sign Supports<br>Replacing Base<br>Connection Bolts | 34.000<br>EACH                   | .          |     | .          |     |
| 0770       | 636.0100 Sign Supports<br>Concrete Masonry                   | 16.000<br>CY                     | .          |     | .          |     |
| 0780       | 636.0500 Sign Supports<br>Steel Reinforcement                | 958.000<br>LB                    | .          |     | .          |     |
| 0790       | 637.1220 Signs Type I<br>Reflective SH                       | 3,829.830<br>SF                  | .          |     | .          |     |
| 0800       | 637.2210 Signs Type II<br>Reflective H                       | 2,219.420<br>SF                  | .          |     | .          |     |
| 0810       | 637.2215 Signs Type II<br>Reflective H Folding               | 81.000<br>SF                     | .          |     | .          |     |
| 0820       | 637.2230 Signs Type II<br>Reflective F                       | 242.000<br>SF                    | .          |     | .          |     |
| 0830       | 638.2601 Removing Signs<br>Type I                            | 29.000<br>EACH                   | .          |     | .          |     |
| 0840       | 638.2602 Removing Signs<br>Type II                           | 214.000<br>EACH                  | .          |     | .          |     |
| 0850       | 638.3000 Removing Small<br>Sign Supports                     | 255.000<br>EACH                  | .          |     | .          |     |

## SCHEDULE OF ITEMS

REVISED:

CONTRACT:  
20160209005PROJECT(S):  
1071-02-60FEDERAL ID(S):  
N/A

CONTRACTOR : \_\_\_\_\_

| LINE<br>NO | ITEM<br>DESCRIPTION                                                                     | APPROX.<br>QUANTITY<br>AND UNITS | UNIT PRICE |     | BID AMOUNT |     |
|------------|-----------------------------------------------------------------------------------------|----------------------------------|------------|-----|------------|-----|
|            |                                                                                         |                                  | DOLLARS    | CTS | DOLLARS    | CTS |
| 0860       | 638.3100 Removing<br>Structural Steel Sign<br>Supports                                  | 24.000<br>EACH                   | .          |     | .          |     |
| 0870       | 642.5201 Field Office<br>Type C                                                         | 1.000<br>EACH                    | .          |     | .          |     |
| 0880       | 643.0200 Traffic Control<br>Surveillance and<br>Maintenance (project) 01.<br>1071-02-60 | 60.000<br>DAY                    | .          |     | .          |     |
| 0890       | 643.0300 Traffic Control<br>Drums                                                       | 32,000.000<br>DAY                | .          |     | .          |     |
| 0900       | 643.0420 Traffic Control<br>Barricades Type III                                         | 2,050.000<br>DAY                 | .          |     | .          |     |
| 0910       | 643.0705 Traffic Control<br>Warning Lights Type A                                       | 4,050.000<br>DAY                 | .          |     | .          |     |
| 0920       | 643.0715 Traffic Control<br>Warning Lights Type C                                       | 2,050.000<br>DAY                 | .          |     | .          |     |
| 0930       | 643.0800 Traffic Control<br>Arrow Boards                                                | 120.000<br>DAY                   | .          |     | .          |     |
| 0940       | 643.0900 Traffic Control<br>Signs                                                       | 3,800.000<br>DAY                 | .          |     | .          |     |
| 0950       | 643.1050 Traffic Control<br>Signs PCMS                                                  | 120.000<br>DAY                   | .          |     | .          |     |
| 0960       | 645.0120 Geotextile<br>Fabric Type HR                                                   | 100.000<br>SY                    | .          |     | .          |     |

## SCHEDULE OF ITEMS

CONTRACT:  
20160209005PROJECT(S):  
1071-02-60FEDERAL ID(S):  
N/A

CONTRACTOR : \_\_\_\_\_

| LINE<br>NO | ITEM<br>DESCRIPTION                                                                  | APPROX.<br>QUANTITY<br>AND UNITS | UNIT PRICE |     | BID AMOUNT |     |
|------------|--------------------------------------------------------------------------------------|----------------------------------|------------|-----|------------|-----|
|            |                                                                                      |                                  | DOLLARS    | CTS | DOLLARS    | CTS |
| 0970       | 646.0106 Pavement<br>Marking Epoxy 4-Inch                                            | 572,746.000<br>LF                | .          |     | .          |     |
| 0980       | 646.0126 Pavement<br>Marking Epoxy 8-Inch                                            | 16,536.000<br>LF                 | .          |     | .          |     |
| 0990       | 647.0566 Pavement<br>Marking Stop Line Epoxy<br>18-Inch                              | 361.000<br>LF                    | .          |     | .          |     |
| 1000       | 647.0746 Pavement<br>Marking Diagonal Epoxy<br>24-Inch                               | 1,123.000<br>LF                  | .          |     | .          |     |
| 1010       | 650.8000 Construction<br>Staking Resurfacing<br>Reference                            | 242,771.000<br>LF                | .          |     | .          |     |
| 1020       | 650.9910 Construction<br>Staking Supplemental<br>Control (project) 01.<br>1071-02-60 | LUMP                             | LUMP       |     | .          |     |
| 1030       | 650.9920 Construction<br>Staking Slope Stakes                                        | 2,529.000<br>LF                  | .          |     | .          |     |
| 1040       | 690.0150 Sawing Asphalt                                                              | 373.000<br>LF                    | .          |     | .          |     |
| 1050       | 690.0250 Sawing Concrete                                                             | 18,057.000<br>LF                 | .          |     | .          |     |
|            | SECTION 0001 TOTAL                                                                   |                                  |            |     | .          |     |
|            | TOTAL BID                                                                            |                                  |            |     | .          |     |

**PLEASE ATTACH SCHEDULE OF ITEMS HERE**