

HIGHWAY WORK PROPOSAL

Wisconsin Department of Transportation
06/2017 s.66.0901(7) Wis. Stats

Proposal Number: **006**

<u>COUNTY</u>	<u>STATE PROJECT</u>	<u>FEDERAL</u>	<u>PROJECT DESCRIPTION</u>	<u>HIGHWAY</u>
Winnebago	1517-75-77	WISC 2019120	Ush 10 - Ush 10/Sth 441; County Cb - Oneida Street	USH 010

ADDENDUM REQUIRED ATTACHED AT BACK

This proposal, submitted by the undersigned bidder to the Wisconsin Department of Transportation, is in accordance with the advertised request for proposals. The bidder is to furnish and deliver all materials, and to perform all work for the improvement of the designated project in the time specified, in accordance with the appended Proposal Requirements and Conditions.

Proposal Guaranty Required: \$75,000.00 Payable to: Wisconsin Department of Transportation	Attach Proposal Guaranty on back of this PAGE.
Bid Submittal Date: February 12, 2019 Time (Local Time): 9:00 am	Firm Name, Address, City, State, Zip Code
Contract Completion Time October 11, 2019	SAMPLE NOT FOR BIDDING PURPOSES
Assigned Disadvantaged Business Enterprise Goal 7%	This contract is exempt from federal oversight.

This certifies that the undersigned bidder, duly sworn, is an authorized representative of the firm named above; that the bidder has examined and carefully prepared the bid from the plans, Highway Work Proposal, and all addenda, and has checked the same in detail before submitting this proposal or bid; and that the bidder or agents, officer, or employees have not, either directly or indirectly, entered into any agreement, participated in any collusion, or otherwise taken any action in restraint of free competitive bidding in connection with this proposal bid.

Do not sign, notarize, or submit this Highway Work Proposal when submitting an electronic bid on the Internet.

Subscribed and sworn to before me this date _____

(Signature, Notary Public, State of Wisconsin)

(Bidder Signature)

(Print or Type Name, Notary Public, State Wisconsin)

(Print or Type Bidder Name)

(Date Commission Expires)

(Bidder Title)

Notary Seal

Type of Work: Grading, Base, Concrete Pavement, Asphalt Pavement, Storm Sewer, Curb and Gutter, Sidewalk, Concrete Driveway, Concrete Barrier, Slope Paving, Signs, Pavement Markings	For Department Use Only
Notice of Award Dated	Date Guaranty Returned

**PLEASE ATTACH
PROPOSAL GUARANTY HERE**

Effective with November 2007 Letting

PROPOSAL REQUIREMENTS AND CONDITIONS

The bidder, signing and submitting this proposal, agrees and declares as a condition thereof, to be bound by the following conditions and requirements.

If the bidder has a corporate relationship with the proposal design engineering company, the bidder declares that it did not obtain any facts, data, or other information related to this proposal from the design engineering company that was not available to all bidders.

The bidder declares that they have carefully examined the site of, and the proposal, plans, specifications and contract forms for the work contemplated, and it is assumed that the bidder has investigated and is satisfied as to the conditions to be encountered, as to the character, quality, and quantities of work to be performed and materials to be furnished, and as to the requirements of the specifications, special provisions and contract. It is mutually agreed that submission of a proposal shall be considered conclusive evidence that the bidder has made such examination.

The bidder submits herewith a proposal guaranty in proper form and amount payable to the party as designated in the advertisement inviting proposals, to be retained by and become the property of the owner of the work in the event the undersigned shall fail to execute the contract and contract bond and return the same to the office of the engineer within fourteen (14) days after having been notified in writing to do so; otherwise to be returned.

The bidder declares that they understand that the estimate of quantities in the attached schedule is approximate only and that the attached quantities may be greater or less in accordance with the specifications.

The bidder agrees to perform the said work, for and in consideration of the payment of the amount becoming due on account of work performed, according to the unit prices bid in the following schedule, and to accept such amounts in full payment of said work.

The bidder declares that all of the said work will be performed at their own proper cost and expense, that they will furnish all necessary materials, labor, tools, machinery, apparatus, and other means of construction in the manner provided in the applicable specifications and the approved plans for the work together with all standard and special designs that may be designed on such plans, and the special provisions in the contract of which this proposal will become a part, if and when accepted. The bidder further agrees that the applicable specifications and all plans and working drawings are made a part hereof, as fully and completely as if attached hereto.

The bidder, if awarded the contract, agrees to begin the work not later than ten (10) days after the date of written notification from the engineer to do so, unless otherwise stipulated in the special provisions.

The bidder declares that if they are awarded the contract, they will execute the contract agreement and begin and complete the work within the time named herein, and they will file a good and sufficient surety bond for the amount of the contract for performance and also for the full amount of the contract for payment.

The bidder, if awarded the contract, shall pay all claims as required by Section 779.14, Statutes of Wisconsin, and shall be subject to and discharge all liabilities for injuries pursuant to Chapter 102 of the Statutes of Wisconsin, and all acts amendatory thereto. They shall further be responsible for any damages to property or injury to persons occurring through their own negligence or that of their employees or agents, incident to the performance of work under this contract, pursuant to the Standard Specifications for Road and Bridge Construction applicable to this contract.

In connection with the performance of work under this contract, the contractor agrees to comply with all applicable state and federal statutes relating to non-discrimination in employment. No otherwise qualified person shall be excluded from employment or otherwise be subject to discrimination in employment in any manner on the basis of age, race, religion, color, gender, national origin or ancestry, disability, arrest or conviction record (in keeping with s.111.32), sexual orientation, marital status, membership in the military reserve, honesty testing, genetic testing, and outside use of lawful products. This provision shall include, but not be limited to the following: employment, upgrading, demotion or transfer; recruitment or recruitment advertising; layoff or termination; rates of pay or other forms of compensation, and selection for training, including apprenticeship. The contractor further agrees to ensure equal opportunity in employment to all applicants and employees and to take affirmative action to attain a representative workforce.

The contractor agrees to post notices and posters setting forth the provisions of the nondiscrimination clause, in a conspicuous and easily accessible place, available for employees and applicants for employment.

If a state public official (section 19.42, Stats.) or an organization in which a state public official holds at least a 10% interest is a party to this agreement, this contract is voidable by the state unless appropriate disclosure is made to the State of Wisconsin Ethics Board.

Effective with August 2015 Letting

BID PREPARATION

Preparing the Proposal Schedule of Items

A General

- (1) Obtain bidding proposals as specified in section 102 of the standard specifications prior to 11:45 AM of the last business day preceding the letting. Submit bidding proposals using one of the following methods:
 1. Electronic bid on the internet.
 2. Electronic bid on a printout with accompanying diskette or CD ROM.
 3. Paper bid under a waiver of the electronic submittal requirements.
- (2) Bids submitted on a printout with accompanying diskette or CD ROM or paper bids submitted under a waiver of the electronic submittal requirements govern over bids submitted on the internet.

- (3) The department will provide bidding information through the department's web site at:
<https://wisconsindot.gov/Pages/doing-bus/contractors/hcci/bid-let.aspx>

The contractor is responsible for reviewing this web site for general notices as well as information regarding proposals in each letting. The department will also post special notices of all addenda to each proposal through this web site no later than 4:00 PM local time on the Thursday before the letting. Check the department's web site after 5:00 PM local time on the Thursday before the letting to ensure all addenda have been accounted for before preparing the bid. When bidding using methods 1 and 2 above, check the Bid Express™ on-line bidding exchange at <http://www.bidx.com/> after 5:00 PM local time on the Thursday before the letting to ensure that the latest schedule of items Expedite file (*.ebs or *.00x) is used to submit the final bid.

- (4) Interested parties can subscribe to the Bid Express™ on-line bidding exchange by following the instructions provided at the www.bidx.com web site or by contacting:

Info Tech Inc.
5700 SW 34th Street, Suite 1235
Gainesville, FL 32608-5371
email: <mailto:customer.support@bidx.com>

- (5) The department will address equipment and process failures, if the bidder can demonstrate that those failures were beyond their control.
- (6) Contractors are responsible for checking on the issuance of addenda and for obtaining the addenda. Notice of issuance of addenda is posted on the department's web site at:
<https://wisconsindot.gov/Pages/doing-bus/contractors/hcci/bid-let.aspx>

or by calling the department at (608) 266-1631. Addenda can ONLY be obtained from the department's web site listed above or by picking up the addenda at the Bureau of Highway Construction, 4th floor, 4822 Madison Yards Way, Madison, WI, during regular business hours.

- (7) Addenda posted after 5:00 PM on the Thursday before the letting will be emailed to the eligible bidders for that proposal. All eligible bidders shall acknowledge receipt of the addenda whether they are bidding on the proposal or not. Not acknowledging receipt may jeopardize the awarding of the project.

B Submitting Electronic Bids

B.1 On the Internet

- (1) Do the following before submitting the bid:
 1. Have a properly executed annual bid bond on file with the department.

2. Have a digital ID on file with and enabled by Info Tech Inc. Using this digital ID will constitute the bidder's signature for proper execution of the bidding proposal.
- (2) In lieu of preparing, delivering, and submitting the proposal as specified in 102.6 and 102.9 of the standard specifications, submit the proposal on the internet as follows:
 1. Download the latest schedule of items reflecting all addenda from the Bid Express™ web site.
 2. Use Expedite™ software to enter a unit price for every item in the schedule of items.
 3. Submit the bid according to the requirements of Expedite™ software and the Bid Express™ web site. Do not submit a bid on a printout with accompanying diskette or CD ROM or a paper bid. If the bidder does submit a bid on a printout with accompanying diskette or a paper bid in addition to the internet submittal, the department will disregard the internet bid.
 4. Submit the bid before the hour and date the Notice to Contractors designates.
 5. Do not sign, notarize, and return the bidding proposal described in 102.2 of the standard specifications.
- (3) The department will not consider the bid accepted until the hour and date the Notice to Contractors designates.

B.2 On a Printout with Accompanying Diskette or CD ROM

- (1) Download the latest schedule of items from the Wisconsin pages of the Bid Express™ web site reflecting the latest addenda posted on the department's web site at:
<https://wisconsindot.gov/Pages/doing-bus/contractors/hcci/bid-let.aspx>
Use Expedite™ software to prepare and print the schedule of items. Provide a valid amount for all price fields. Follow instructions and review the help screens provided on the Bid Express™ web site to assure that the schedule of items is prepared properly.
- (2) Staple an 8 1/2 by 11 inch printout of the Expedite™ generated schedule of items to the other proposal documents submitted to the department as a part of the bidder's sealed bid. As a separate submittal, not in the sealed bid envelop but due at the same time and place as the sealed bid, also provide the Expedite™ generated schedule of items on a 3 1/2 inch computer diskette or CD ROM. Label each diskette or CD ROM with the bidder's name, the 4 character department-assigned bidder identification code from the top of the bidding proposal, and a list of the proposal numbers included on that diskette or CD ROM as indicated in the following example:

Bidder Name

BN00

Proposals: 1, 12, 14, & 22

- (3) If bidding on more than one proposal in the letting, the bidder may include all proposals for that letting on one diskette or CD ROM. Include only submitted proposals with no incomplete or other files on the diskette or CD ROM.
- (4) The bidder-submitted printout of the Expedite™ generated schedule of items is the governing contract document and must conform to the requirements of section 102 of the standard specifications. If a printout needs to be altered, cross out the printed information with ink or typewriter and enter the new information and initial it in ink. If there is a discrepancy between the printout and the diskette or CD ROM, the department will analyze the bid using the printout information.
- (5) In addition to the reasons specified in section 102 of the standard specifications, proposals are irregular and the department may reject them for one or more of the following:
 1. The check code printed on the bottom of the printout of the Expedite™ generated schedule of items is not the same on each page.
 2. The check code printed on the printout of the Expedite™ generated schedule of items is not the same as the check code for that proposal provided on the diskette or CD ROM.

3. The diskette or CD ROM is not submitted at the time and place the department designates.

C Waiver of Electronic Submittal

- (1) The bidder may request a waiver of the electronic submittal requirements. Submit a written request for a waiver in lieu of bids submitted on the internet or on a printout with accompanying diskette or CD ROM. Use the waiver that was included with the paper bid document sent to the bidder or type up a waiver on the bidder's letterhead. The department will waive the electronic submittal requirements for a bidding entity (individual, partnership, joint venture, corporation, or limited liability company) for up to 4 individual proposals in a calendar year. The department may allow additional waivers for equipment malfunctions.
- (2) Submit a schedule of items on paper conforming to section 102 of the standard specifications. The department charges the bidder a \$75 administrative fee per proposal, payable at the time and place the department designates for receiving bids, to cover the costs of data entry. The department will accept a check or money order payable to: "Wisconsin, Dept. of Transportation."
- (3) In addition to the reasons specified in section 102 of the standard specifications, proposals are irregular and the department may reject them for one or more of the following:
 1. The bidder fails to provide the written request for waiver of the electronic submittal requirements.
 2. The bidder fails to pay the \$75 administrative fee before the time the department designates for the opening of bids unless the bidder requests on the waiver that they be billed for the \$75.
 3. The bidder exceeds 4 waivers of electronic submittal requirements within a calendar year.
- (4) In addition to the reasons specified in section 102 of the standard specifications, the department may refuse to issue bidding proposals for future contracts to a bidding entity that owes the department administrative fees for a waiver of electronic submittal requirements.

PROPOSAL BID BOND

DT1303 1/2006

Wisconsin Department of Transportation

Proposal Number	Project Number	Letting Date
Name of Principal		
Name of Surety	State in Which Surety is Organized	

We, the above-named Principal and the above-named Surety, are held and firmly bound unto the State of Wisconsin in the sum equal to the Proposal Guaranty for the total bid submitted for the payment to be made; we jointly and severally bind ourselves, our heirs, executors, administrators, successors and assigns. The condition of this obligation is that the Principal has submitted a bid proposal to the State of Wisconsin acting through the Department of Transportation for the improvement designated by the Proposal Number and Letting Date indicated above.

If the Principal is awarded the contract and, within the time and manner required by law after the prescribed forms are presented for signature, enters into a written contract in accordance with the bid, and files the bond with the Department of Transportation to guarantee faithful performance and payment for labor and materials, as required by law, or if the Department of Transportation shall reject all bids for the work described, then this obligation shall be null and void; otherwise, it shall be and remain in full force and effect. In the event of failure of the Principal to enter into the contract or give the specified bond, the Principal shall pay to the Department of Transportation **within 10 business days of demand** a total equal to the Proposal Guaranty as liquidated damages; the liability of the Surety continues for the full amount of the obligation as stated until the obligation is paid in full.

The Surety, for value received, agrees that the obligations of it and its bond shall not be impaired or affected by any extension of time within which the Department of Transportation may accept the bid; and the Surety does waive notice of any such extension.

IN WITNESS, the Principal and Surety have agreed and have signed by their proper officers and have caused their corporate seals to be affixed this date: **(DATE MUST BE ENTERED)**

PRINCIPAL

(Company Name) **(Affix Corporate Seal)**

(Signature and Title)

(Company Name)

(Signature and Title)

(Company Name)

(Signature and Title)

(Company Name)

(Signature and Title)

NOTARY FOR PRINCIPAL

(Date)

State of Wisconsin)
) ss.
_____ County)

On the above date, this instrument was acknowledged before me by the named person(s).

(Signature, Notary Public, State of Wisconsin)

(Print or Type Name, Notary Public, State of Wisconsin)

(Date Commission Expires)

Notary Seal

(Name of Surety) **(Affix Seal)**

(Signature of Attorney-in-Fact)

NOTARY FOR SURETY

(Date)

State of Wisconsin)
) ss.
_____ County)

On the above date, this instrument was acknowledged before me by the named person(s).

(Signature, Notary Public, State of Wisconsin)

(Print or Type Name, Notary Public, State of Wisconsin)

(Date Commission Expires)

Notary Seal

IMPORTANT: A certified copy of Power of Attorney of the signatory agent must be attached to the bid bond.

CERTIFICATE OF ANNUAL BID BOND

DT1305 8/2003

Wisconsin Department of Transportation

Time Period Valid (From/To)	
Name of Surety	
Name of Contractor	
Certificate Holder	Wisconsin Department of Transportation

This is to certify that an annual bid bond issued by the above-named Surety is currently on file with the Wisconsin Department of Transportation.

This certificate is issued as a matter of information and conveys no rights upon the certificate holder and does not amend, extend or alter the coverage of the annual bid bond.

Cancellation: Should the above policy be cancelled before the expiration date, the issuing surety will give thirty (30) days written notice to the certificate holder indicated above.

(Signature of Authorized Contractor Representative)

(Date)

March 2010

LIST OF SUBCONTRACTORS

Section 66.0901(7), Wisconsin Statutes, provides that as a part of the proposal, the bidder also shall submit a list of the subcontractors the bidder proposes to contract with and the class of work to be performed by each. In order to qualify for inclusion in the bidder's list a subcontractor shall first submit a bid in writing, to the general contractor at least 48 hours prior to the time of the bid closing. The list may not be added to or altered without the written consent of the municipality. A proposal of a bidder is not invalid if any subcontractor and the class of work to be performed by the subcontractor has been omitted from a proposal; the omission shall be considered inadvertent or the bidder will perform the work personally.

No subcontract, whether listed herein or later proposed, may be entered into without the written consent of the Engineer as provided in Subsection 108.1 of the Standard Specifications.

[illegible]

DECEMBER 2000

**CERTIFICATION REGARDING DEBARMENT, SUSPENSION, AND OTHER
RESPONSIBILITY MATTERS - PRIMARY COVERED TRANSACTIONS**

Instructions for Certification

1. By signing and submitting this proposal, the prospective contractor is providing the certification set out below.
2. The inability of a person to provide the certification required below will not necessarily result in denial of participation in this covered transaction. The prospective contractor shall submit an explanation of why it cannot provide the certification set out below. The certification or explanation will be considered in connection with the department or agency's determination whether to enter into this transaction. However, failure of the prospective contractor to furnish a certification or an explanation shall disqualify such person from participation in this transaction.
3. The certification in this clause is a material representation of fact upon which reliance was placed when the department determined to enter into this transaction. If it is later determined that the contractor knowingly rendered an erroneous certification in addition to other remedies available to the Federal Government the department may terminate this transaction for cause or default.
4. The prospective contractor shall provide immediate written notice to the department to whom this proposal is submitted if at any time the prospective contractor learns that its certification was erroneous when submitted or has become erroneous by reason of changed circumstances.
5. The terms "covered transaction," "debarred," "suspended," "ineligible," "lower tier covered transaction," "participant," "person," "primary covered transaction," "principal," "proposal," and "voluntarily excluded," as used in this clause, have the meanings set out in the Definitions and Coverage sections of the rules implementing Executive Order 12549. You may contact the department to which this proposal is being submitted for assistance in obtaining a copy of those regulations.
6. The prospective contractor agrees by submitting this proposal that, should this contract be entered into, it shall not knowingly enter into any lower tier covered transaction with a person who is debarred, suspended, declared ineligible, or voluntarily excluded from participation in this covered transaction, unless authorized by the department entering into this transaction.
7. The prospective contractor further agrees by submitting this proposal that it will include the clause titled "Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion-Lower Tier Covered Transaction," which is included as an addendum to PR-1273 - "Required Contract Provisions Federal Aid Construction Contracts," without

modification, in all lower tier covered transactions and in all solicitations for lower tier covered transactions.

8. The contractor may rely upon a certification of a prospective subcontractor/materials supplier that it is not debarred, suspended, ineligible, or voluntarily excluded from the covered transaction, unless it knows that the certification is erroneous. A contractor may decide the method and frequency by which it determines the eligibility of its principals. Each contractor may, but is not required to, check the Disapproval List (telephone # 608/266/1631).
9. Nothing contained in the foregoing shall be construed to require establishment of a system of records in order to render in good faith the certification required by this clause. The knowledge and information of a contractor is not required to exceed that which is normally possessed by a prudent person in the ordinary course of business dealings.
10. Except for transactions authorized under paragraph 6 of these instructions, if a contractor in a covered transaction knowingly enters into a lower tier covered transaction with a person who is suspended, debarred, ineligible or voluntarily excluded from participation in this transaction, in addition to other remedies available to the Federal Government, the department may terminate this transaction for cause or default.

Certification Regarding Debarment, Suspension, and Other Responsibility Matters - Primary Covered Transactions

- (1) The prospective contractor certifies to the best of its knowledge and belief, that it and its principals:
 - (a) Are not presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from covered transactions by any Federal department or agency;
 - (b) Have not within a three-year period preceding this proposal been convicted of or had a civil judgment rendered against them for commission of fraud or a criminal offense in connection with obtaining, attempting to obtain, or performing a public (Federal, State or local) transaction or contract under a public transaction; violation of Federal or State antitrust statutes or commission of embezzlement, theft, forgery, bribery, falsification or destruction of records, making false statements or receiving stolen property;
 - (c) Are not presently indicted for or otherwise criminally or civilly charged by a governmental entity (Federal, State or local) with commission of any of the offense enumerated in paragraph (1)(b) of this certification; and
 - (d) Have not within a three-year period preceding this proposal had one or more public transactions (Federal, State or local) terminated for cause or default.
- (2) Where the prospective contractor is unable to certify to any of the statements in this certification, such prospective contractor shall attach an explanation to this proposal.

Special Provisions

Table of Contents

Article	Description	Page #
1.	Administrative.....	3
1.1	General.....	3
1.2	Scope of Work.	3
1.3	Other Contracts.	3
1.4	Notice to Contractor – Street Sweeping.....	4
1.5	Notice to Contractor-Maintain Access.....	4
1.6	Notice to Contractor - Right-of-Way Fencing.	4
1.7	Notice to Contractor- Work by Railroad.	4
2.	Prosecution and Progress.	4
2.1	Prosecution and Progress.	4
2.2	Bar Chart Progress Schedule	6
3.	Meetings.....	7
3.1	Timely Decision Making Manual.	7
3.2	Coordination with Businesses.....	8
4.	Alternative Dispute Resolution (Vacant).....	8
5.	Insurance.....	8
5.1	Railroad Insurance and Coordination - Wisconsin Central Ltd (CN).....	8
6.	Environmental.....	10
6.1	Information to Bidders, WPDES General Consturction Storm Water Discharge Permit.....	10
6.2	Environmental Protection.	10
6.3	Notice to Contractor – Archaeological Survey Coordination.....	11
6.4	Environmental Protection, Dewatering.....	11
6.5	Information to Bidders, U.S. Army Corps of Engineers Section 404 Permit.....	12
7.	Traffic and Restrictions to Work.	12
7.1	Traffic.	12
7.2	Holiday and Other Work Restrictions.....	15
7.3	Ingress and Egress.....	15
7.4	Public Convenience and Safety.	15
7.5	Traffic Control.	16
7.6	Temporary Portable Rumble Strips, Item 643.0310.S.....	18
8.	Utilities.....	19
8.1	Utilities.....	19
8.2	Municipality Acceptance of Sanitary Sewer.....	20
9.	Clear – Demolition – Removal.	20
9.1	Clearing and Grubbing.....	20
10.	Earthwork.....	21
10.1	Embankment Construction.....	21
10.2	Roadway Embankment, Item SPV.0035.001.	21
11.	Bases, Subbases, and Pavements.	22

11.1	Coloring Concrete Custom, Item 405.0200.	22
11.2	Aggregate Quality Testing for Modified High-Performance Concrete (HPC) Mixes.....	23
11.3	QMP HMA Pavement Nuclear Density.....	25
11.4	Concrete Pavement Joint Layout, Item 415.5110.S.....	31
11.5	Optimized Aggregate Gradation Incentive, Item 715.0710.....	32
11.6	Flexural Strength for Concrete Mix Design.....	36
11.7	Modified High Performance Concrete (HPC) Pavement 9-Inch, Item SPV.0180.001;	36
12.	Bridges.	39
12.1	Removing Crushed Aggregate Slope Paving, Item SPV.0180.002.	39
13.	Retaining Walls, Ground Support. (Vacant).....	39
14.	Drainage and Erosion Control.	40
14.1	Erosion Control.....	40
14.2	Maintaining Drainage.	40
14.3	Storm Sewer Backfill.....	41
14.4	Backfill Controlled Low Strength, Item 209.0200.S.	41
14.5	Temporary Ditch Checks.	42
14.6	Manholes 10-Ft Diameter, Item SPV.0060.100.....	43
14.7	Street Sweeping, Item SPV.0075.001.....	43
14.8	Water for Seeded Areas, Item SPV.0120.150.....	44
15.	Miscellaneous Concrete. (Vacant).....	45
16.	Signing and Marking.....	45
16.1	Remove Commercial Sign, Item SPV.0060.250.	45
17.	Lighting/Electrical.	45
17.1	General Requirements for Electrical Work.....	45
17.2	Lighting Control Cabinets 6240/480 30-Inch 659.2230.....	46
18.	Intelligent Transportation Systems.	46
18.1	Intelligent Transportation Systems	46
19.	Landscaping. (Vacant)	49
20.	Miscellaneous – Incidental Construction.....	49
20.1	Survey Monument Coordination.....	49
20.2	Adjusting Sanitary Manhole Covers, Item SPV.0060.650.	49
20.3	Sanitary Lateral 4-Inch, Item SPV.0090.651.....	50
20.4	Referenced Construction Specifications.	51
20.5	Survey Project 1517-75-77, Item SPV.0105.002.....	51

SPECIAL PROVISIONS

1. Administrative.

1.1 General.

Perform the work under this construction contract for Project 1517-75-77, USH 10 – USH 10/STH 441, County CB - Oneida Street, USH 10, Winnebago County, Wisconsin as the plans show and execute the work as specified in the State of Wisconsin, Department of Transportation, Standard Specifications for Highway and Structure Construction, 2019 Edition, as published by the department, and these special provisions.

If all or a portion of the plans and special provisions are developed in the SI metric system and the schedule of prices is developed in the US standard measure system, the department will pay for the work as bid in the US standard system.

100-005 (20180628)

1.2 Scope of Work.

The work under this contract consists of removals, grading, breaker run, base aggregate dense, concrete pavement, concrete curb and gutter, HMA pavement, mill and overlay, storm sewer, erosion control, pavement marking, permanent signing, and all incidental items necessary to complete the work as shown on the plans and included in the proposal and contract.

104-005 (20090901)

1.3 Other Contracts.

The following project will be under construction concurrently with the work under this contract. Coordinate trucking activities, detours, work zone traffic control, roadway and lane closures, and other work items as required with other contracts.

Project 1517-75-73, USH 10 – USH 10/STH 441, County CB - Oneida Street, USH 10, STH 441 SB Mainline (Midway Road – East Project Limits), Winnebago and Calumet Counties, Wisconsin under a department contract. Work under this contract (LET date of March 13, 2018) is anticipated to be completed in November of 2019. The work under this contract consists of common excavation, roadway embankment, base aggregate, concrete pavement, HMA pavement, storm sewer, retaining walls, sign structures, erosion control, signing, pavement marking, and lighting. The work under this contract has schedule and work zone overlap for 1517-75-77.

1.4 Notice to Contractor – Street Sweeping.

All street sweeping due to contractors hauling operations is considered incidental to the contract. The contractor is responsible for keeping all public roadways clean and free from dirt and debris at all times. For this work provide a self-contained mechanical or air conveyance street sweeper and dispose the accumulated material.

Cleaning of the roadway before traffic switches or cleaning of roadways from non-contractor vehicle traffic will be paid for under the contract item Street Sweeping.
(NER441-20150117)

1.5 Notice to Contractor-Maintain Access.

The contractor must maintain access to the residents and businesses during the duration of Midway and Racine Road closures.
(NER441-20150117)

1.6 Notice to Contractor - Right-of-Way Fencing.

Maintain all existing freeway right-of-way fencing or temporary fencing that is disturbed by your operations. At no time leave a site where the fencing is inadequate to protect the general public.
(NER441-20150117)

1.7 Notice to Contractor- Work by Railroad.

Wisconsin Central Ltd. will be performing crossing work concurrently with this project as outlined in 5.1 Railroad Insurance and Coordination and shown on Railroad Crossing Details in the plan. Coordination with the railroad work is required.

2. Prosecution and Progress.

2.1 Prosecution and Progress.

Begin work within ten calendar days after the engineer issues a written notice to do so.

Provide the start date to the engineer in writing within a month after executing the contract but at least 14 calendar days before the preconstruction conference. Assure that the time frame is consistent with the contract completion time. Upon approval, the engineer will issue the notice to proceed within ten calendar days before the beginning of the approved time frame.

To revise the time frame, submit a written request to the engineer at least two weeks before the beginning of the intended time frame. The engineer will approve or deny that request based on the conditions cited in the request and its effect on the department's scheduled resources.

When engaged in roadway cleaning operations, use equipment having vacuum or water spray mechanisms to eliminate the dispersion of particulate matter into the atmosphere. If vacuum equipment is employed, it must have suitable self-contained particulate collectors to prevent discharge from the collection bin into the atmosphere.

Excess fill material and cleared and grubbed material shall be stockpiled on upland areas an adequate distance away from wetlands, storm sewer inlets, floodplains, and the waterways. Provide erosion control devices for stockpiled soil to avoid erosion and nuisance dust emissions.

The contractor is advised that there may be multiple mobilizations for such items as erosion control, traffic control, detours, signing items, temporary pavement markings and other incidental items related to the staging. The department will make no additional payment for said mobilizations.

Cost for dewatering is considered incidental to construction

An assumed duration of specific traffic control set up and related construction activities have been included for information only. The contractor can elect to complete individual construction stages and traffic phases any time during the project contract, provided the prerequisites have been met and interim and final completion dates are met.

After written notice to proceed, and prior to Final Acceptance of the work, assist with maintenance of existing roadways and bridges as specified in standard spec 104.6.1. This assistance may include performance of work covered under pay items or accommodating local repair forces within the work zones. Maintain all newly constructed work as specified in standard spec 104.6.1. Various pay items may be required to maintain the freeway and local streets during construction.

Notify the local municipalities 10 calendar days in advance of the adjustment of sanitary manholes and water valves.

Do not place curb and gutter or pavement on Midway Road prior to July 2, 2019 prior to engineer approval.

Traffic/Construction Overview

Follow the construction operations as outlined in the staging overview sheets and other plan details. Items listed below are not limited to, but only highlight construction activities, that are subject to interim completion dates, liquidated damages, or penalties.

Do not begin work until June 12, 2019.

Stage 1

- Reconstruct Racine Road (CTH AP) from Olde Miday Road to North Project limits.
- Begin reconstruction of Midway Road (CTH AP) and ramp connections (Midway Road from Mission Street west to Racine Road.)

- Do not place curb and gutter or pavement on Midway Road prior to July 2, 2019 without engineer approval.
- Contractor to coordinate work on Midway Road with project 1517-75-73 contractor to avoid conflicts.

Stage 2

- Continue and Complete Construction of Midway Road and USH 10/STH 441 ramp connections.
- Contactor shall coordinate railroad work with Wisconsin Central LTD railroad.
- Contractor shall not place pavement within 200 feet of railroad crossing prior to the railroad completing crossing.
- Coordinate Midway Road interchange ramp opening with contractor for 1517-75-73. Workzone and signing overlap, coordinate with 1517-75-73 contractor.
- Racine Road open to traffic.

Stage 3

- Resurface Racine Road (CTH P) from Olde Midway Road south to south project limits.
- This work to be done under a flagging operation.
- Racine Road and Midway Road to remain open to traffic.

Interim Completion Date for Opening Racine Road

Complete all contract work necessary to re-open Racine Road to through traffic prior to 12:01 AM August 23, 2019.

If the contractor fails to complete the work necessary to reopen Racine Road to through traffic prior to 12:01 AM August 23, 2019, the department will assess the contractor \$2070 in interim liquidated damages for each calendar day that the roadway remains closed after 12:01 AM, August 23, 2019. An entire calendar day will be charged for any period of time within a calendar day that the road remains closed beyond 12:01 AM.

If contract time expires prior to completing all work specified in the contract, additional liquidated damages will be affixed according to standard spec 108.11.

2.2 Bar Chart Progress Schedule

Complete a Bar Chart Progress Schedule in accordance with standard spec 108.4 and herein provided:

Replace standard spec 108.4.2.2 with the following:

Weekly Progress Meetings and Bar Chart Progress Updates

The contractor and the engineer will meet weekly to assess progress schedule and jointly update information to the initial schedule. At a minimum, updates will include the actual

start and finish of each activity, percentage complete, and remaining durations of activities started but not yet completed.

At each weekly progress meeting, submit a Three-Week Look-Ahead Schedule. The Three-Week Look-Ahead schedules can be hand drawn or generated by computer. With each Three-Week Look-Ahead include:

1. Activities underway and as-built dates for the past week.
2. Planned work for the upcoming two-week period.
3. Include in the Three-Week Look-Ahead schedule the activities underway and critical RFIs and submittals, based on the schedule. The Three-Week Look-Ahead may also include details on other activities not individually represented in the schedule.
4. On a weekly basis, the department and the contractor shall agree on the as-built dates depicted in the Three-Week Look-Ahead schedule or document any disagreements. Use the as-built dates from the Three-Week Look-Ahead schedules for the month when updating the schedule.

Replace standard spec 108.4.2.5 with the following:

Bar Chart Progress Schedule Measurement and Payment

Include the cost for the schedule, weekly progress meetings, and Three-Week Look-Ahead schedules in the total bid. The schedule, weekly progress meetings, and Three-Week Look-Ahead schedules are incidental to the contract.

3. Meetings.

3.1 Timely Decision Making Manual.

Use the Timely Decision Making Manual (TDM) on this contract. Coordinate with the department to modify the various published tools as necessary to meet the particular project needs and determine how to implement those tools under the contract. Ensure the full participation of the contractor and its principal subcontractors throughout the term of the contract.

Forms and associated guidance are published in the TDM available at the department's Highway Construction Contract Information (HCCI) web site at:

[Timely Decision Making Manual \(TDM\)](#)

stp-105-005 (20151210)

3.2 Coordination with Businesses.

The contractor will arrange and conduct meetings between the department, local officials and business people to discuss the project schedule of operations including vehicular and pedestrian access during construction operations. The first meeting shall be held prior to the start of work under this contract and as needed or directed by the engineer.
(NER441-20141017)

4. Alternative Dispute Resolution (Vacant).

5. Insurance.

5.1 Railroad Insurance and Coordination - Wisconsin Central Ltd (CN).

A Description

Comply with standard spec 107.17 for all work affecting Wisconsin Central Ltd (CN) property and any existing tracks

A.1 Railroad Insurance Requirements

In addition to standard spec 107.26, provide railroad protective liability insurance coverage as specified in standard spec 107.17.3. Insurance is filed in the name of Wisconsin Central Ltd and Its Parents (CN).

Notify evidence of the required coverage, and duration to Jackie Macewicz, Manager Public Works; 1625 Depot Street, Stevens Point, WI 54481; Telephone (715) 345-2503; E-mail: Jackie.macewicz@cn.ca.

Also send a copy to the following: Jared Kinziger, NE Region Railroad Coordinator; 944 Vanderperren Way, Green Bay, WI 54304; Telephone (920) 492-7713; E-mail: jared.kinziger@dot.wi.gov.

Include the following information on the insurance document:

- Project ID: 1517-75-77
- Work Performed: Reconstruct and widen CTH AP Midway Road and resurface up to the railroad crossing on CTH P Racine Road.

#	Route Name	City/County	Crossing ID	RR Subdivision	RR Milepost
1	CTH AP, Midway Road	Menasha/Winnebago	386624H	Manitowoc Banta Spur	187.54
2	CTH P, Racine Road	Menasha/Winnebago	386626W	Manitowoc Banta Spur	187.03

A.2 Train Operation

#	Passenger Train Volume	Passenger Train Speed	Freight Train Volume	Freight Train Speed	Frequency	Switch Train Comment*
1	0	0	0	10	Daily	There are switch trains in addition to through trains
2	0	0	2	10	Daily	No switch trains

* Switch trains are in addition to freight and passenger trains.

A.3 Names and Addresses of Railroad Representatives for Consultation and Coordination Construction Contact

Construction Contact

Jackie Macewicz, Manager Public Works; 1625 Depot St., Stevens Point, WI 54481; Telephone (715) 345-2503; E-mail jackie.macewicz@cn.ca for consultation on railroad requirements during construction.

Amend standard spec 108.4 to include the railroad in the distribution of the initial bar chart, and monthly schedule updates. The bar chart shall specifically show work involving coordination with the railroad.

Flagging Contact

Submit by US Mail a "Request for Flagging Services and Cable Location" form with prepayment to: Mary Ellen Carmody, CN, 24002 Vreeland Road, Flat Rock, MI 48134; Telephone (734) 783-4533. The form can be obtained at:

<https://www.cn.ca/en/safety/employees/contractors-erailsafe/utility-installations/>

Requests for flagging and cable locates can take up to five business days after the railroad receives the paperwork. Reference the Wisconsin Milepost and Subdivision located in A.1. Advise Ms. Carmody that the flagging services are to be billed at the rate for a public highway project.

Cable Locate Contact

In addition to contacting Diggers Hotline, follow the procedure listed under Flagging Contact. Wisconsin Central Ltd (CN) will only locate railroad owned facilities buried in the railroad right-of-way. The railroad does not locate any other utilities.

A.4 Work by Railroad

The railroad will perform the work described in this section, except for work described in other special provisions, and will be accomplished without cost to the contractor. Replace and lengthen the crossing surface and remove and install new railroad crossing signals.

A.5 Temporary Grade Crossing

If a temporary grade crossing is desired, submit a written request to the railroad representative named in A.3 at least 40 days prior to the time needed. Approval is subject to the discretion of the railroad. The department has made no arrangements for a temporary grade crossing.

A.6 Rail Security Awareness and Contractor Orientation

All employees of contractors who work on CN properties are required to have minimum CN Safety and Security Awareness training. This training can be obtained by registering and following the CN link through www.contractororientation.com. This training is good for a period of one year.

- a. Exception: CN has exempted from this training those it classifies as "Delivery Persons". Delivery Persons include contractors such as UPS, FedEx, trucking companies, etc. who merely access the property to supply materials or equipment.

The security awareness and contractor orientation certification must be renewed for projects that will carry over beyond the one year period. Contractor and subcontractor employees shall wear the identification badge issued by www.contractororientation.com when on railroad right-of-way. Costs associated with training and registration are incidental to other items in the contract.

stp-107-026 (20170615)

6. Environmental.

6.1 Information to Bidders, WPDES General Consturction Storm Water Discharge Permit.

The department has obtained coverage through the Wisconsin Department of Natural Resources to discharge storm water associated with land disturbing construction activities of this contract under the Wisconsin Pollutant Discharge Elimination System General Construction Storm Water Discharge Permit (WPDES Permit No. WI-S066796-1). A certificate of permit coverage is available from the regional office by contacting Scott Ebel at 920-5676 Post the permit in a conspicuous place at the construction site.

stp-107-056 (20180628)

6.2 Environmental Protection.

Supplement standard spec 107.18 as follows:

Wetlands

Do not disturb nor store materials or topsoil within the nearby wetlands as shown on the erosion control sheets unless areas are designated to be filled or impacted as permitted in the project's U.S. Army Corps of Engineers Section 404 Permit. The work area shall be separated from the wetlands by silt fence, as shown on the plans, to avoid siltation and inadvertent fill into the wetland areas.

Invasive Plant Species

Phragmites and Loosestrife, invasive species plants, exist within the USH 41/USH 10 corridor. All soils outside of the median areas along USH 41/USH 10 containing plant or root fragments that will be disturbed as part of the work within the contract shall be incorporated into the salvaged topsoil within the immediate area of the work. Excavation and waste of Phragmites and Loosestrife infested soil from the median areas, other areas shown on the plans, and any other areas that may be approved by the engineer will be paid for under the Common Excavation item. Waste material shall be placed in upland locations in the general area where the plant currently exists. All other areas where Phragmites and Loosestrife soil is left on site will be paid for as Salvaged Topsoil.

For all equipment that comes into contact with Phragmites and Loosestrife infested areas, follow the guidelines established under the Environmental Protection, Aquatic Exotic Species Control section of this special provision for inspection and cleaning of equipment prior to leaving the project site. Additional information on this plant can be found at the following website: www.dnr.wi.gov/invasives/plants.asp.
(NER441-20150117)

6.3 Notice to Contractor – Archaeological Survey Coordination.

The department will conduct archaeological surveys for borrow sites, batch plants, waste sites, and staging areas to be used for the project. If significant discoveries of non-burial related archaeological properties are discovered, Section 106 procedures pursuant to 36 CFR 800 will be followed or another area shall be obtained for borrow, batch plants, waste sites, and staging areas.

Notify the department as soon as possible to allow time for archaeological surveys to be completed in advance of your work.
(NER441-20141017)

6.4 Environmental Protection, Dewatering.

Supplement standard spec 107.18 as follows:

If dewatering is required, treat the water to remove suspended sediments by filtration, settlement or other appropriate best management practice prior to discharge. The means and methods proposed to be used during construction shall be submitted for approval as part of the Erosion Control Implementation Plan for dewatering at each location it is required. The submittal shall also include the details of how the intake will be managed to not cause an increase in the background level turbidity prior to treatment and any additional erosion controls necessary to prevent sediments from reaching the project limits or wetlands and waterways. Guidance on dewatering can be found on the Wisconsin Department of Natural Resources website located in the Storm Water Construction Technical Standards, Dewatering Code #1061, “Dewatering”. This document can be found at the WisDNR website:

http://dnr.wi.gov/topic/stormwater/standards/const_standards.html

The cost of all work and materials associated with water treatment and/or dewatering is incidental to the bid items the work is associated.
(NER12-1010)

6.5 Information to Bidders, U.S. Army Corps of Engineers Section 404 Permit.

The department obtained the U.S. Army Corps of Engineers Section 404 Permit. Comply with the requirements of the permit in addition to requirements of the special provisions. A copy of the permit is available from the regional office by contacting Scott Ebel at (920) 492-5676.

7. Traffic and Restrictions to Work.

7.1 Traffic.

Traffic Overview

Stage 1

- Racine Road closed from Olde Midway Road to North Project limits.
- Access to residents on Racine Road must be maintained.
- Midway Road (CTH AP) and ramp connections (Midway Road from Mission Street west to Racine Road) are closed.
- Traffic will need to use local alternative routes and adjacent Racine Road (CTH P) and Appleton Road (STH 47) and Racine Road Interchange (CTH P) for mainline access USH 10/STH 441 access.

Stage 2

- Midway Road and all USH 10/STH 441 ramps are closed.
- Racine Road is open to traffic.
- Traffic will need to use local alternative routes and adjacent Racine Road (CTH P) and Appleton Road (STH 47) and Racine Road Interchange (CTH P) for mainline access USH 10/STH 441 access.

Stage 3

- Racine Road (CTH P) will be down to one lane during flagging operation
- Midway Road is open.
- Full closure on Racine Road at railroad crossing for railroad work. Contractor shall coordinate closure for railroad work with railroad.
- Midway Road interchange ramps to be opened under mainline project 1517-75-73. Workzone and signing overlap, coordinate with 1517-75-73 contractor.

Clear Zone Working Restrictions

Do not store materials or equipment within the clear zone of traffic lanes which are not protected by temporary precast barrier. Remove materials from the clear zone prior to opening lane closures. Do not leave any slopes steeper than 3:1 or any drop offs at the edge

of the traveled way greater than 2 inches within the clear zone which are not protected by temporary precast barrier prior to opening lane closures.

Park equipment a minimum of 30-feet from the edge of the traveled way. Equipment may be parked in the median if it meets the minimum distance requirement from both traveled ways or if it is protected by concrete barrier.

If the contractor is unsure whether an individual work operation will meet the safety requirements for working within the clear zone, review the proposed work operation with the engineer before proceeding with the work.
(NER441-20141017)

Expressway / Freeway Traffic Control Meeting

Conduct a traffic control meeting prior to:

1. Initial traffic control set up.
2. Intermediate traffic switches
3. Reopening of the highway to traffic

Notify Susan Paulus at (414) 460-3409 seven business days prior to setting up the meeting.
(NER441-20141017)

Wisconsin Lane Closure System Advance Notification

Provide the following advance notification to the engineer for incorporation into the Wisconsin Lane Closure System (LCS).

TABLE 108-1 CLOSURE TYPE AND REQUIRED MINIMUM ADVANCE NOTIFICATION

Closure type with height, weight, or width restrictions (available width, all lanes in one direction < 16')	MINIMUM NOTIFICATION
Lane and shoulder closures	7 calendar days
Full roadway closures	7 calendar days
Ramp closures	7 calendar days
Detours	7 calendar days
Closure type without height, weight, or width restrictions (available width, all lanes in one direction $\geq 16'$)	MINIMUM NOTIFICATION
Lane and shoulder closures	3 business days
Ramp closures	3 business days
Modifying all closure types	3 business days

Discuss LCS completion dates and provide changes in the schedule to the engineer at weekly project meetings in order to manage closures nearing their completion date.
stp-108-057 (20161130)

Portable Changeable Message Signs – Message Prior Approval

After coordinating with department construction field staff, notify Susan Paulus at (414) 460-3409, three business days prior to deploying or changing a message on a PCMS to obtain approval of the proposed message.
(NER441-20141017)

Traffic Impact Response Time

Provide a preferred method of notification and a designated person that is available 24 hours per day, seven days per week, to respond to any event that impacts the free flow of traffic during non-working hours. The designated person shall respond within 2 hours of being notified by the engineer. Notification is defined as the first phone call/voice message, text message or e-mail. Impacts to traffic may include, but are not limited to, temporary barrier wall that has been moved from its original position, water ponding on the travel lanes, or temporary pavement deterioration. The contractor designated person needs to be able to promptly address the issues impacting traffic once notified by the engineer.

Failure to respond onsite and start implementation of corrective actions within 2 hours will result in the department issuing a deduction of \$500 per hour at the start of the third hour beyond the initial notification by the engineer. The department will administer the deduction for the road, or portion thereof, not being open to traffic under the Failing to Open Road to Traffic administrative item.

Private Driveways

Maintain access to all business driveways and private residence driveways on a minimum of crushed aggregate base course surface at all times except as follows. Close driveways for a maximum of seven calendar days for grading and placement of base aggregate and concrete paving for each driveway (includes placement of storm sewer pipes). Notify each business and/or each residence on the property a minimum of seven days prior to any driveway closures. A business with multiple driveways shall have one driveway open at all times.
(NER441-20141017)

Local Street Work Restrictions

Existing trees, street light poles, hydrants and other utility poles are to remain in place during construction unless otherwise noted in the plan. Conduct an on-site visit prior to bidding to determine any special measures required for proper clearance between the trees, hydrants and poles and the paving equipment.

Provide adequate temporary sidewalk and bridging between the curb and right-of-way line over freshly paved concrete or other obstructions in the sidewalk area, as directed by the engineer.

Inform property owners and tenants at least seven days prior to removing a driveway approach that serves that property. Schedule sidewalk and driveway approach removal and replacement so that the time lapse between removal and replacement is minimal.

Do not close residential approaches or remove from service without at least seven days prior notice given to the occupants of the premises to remove their vehicles prior to driveway removal or closing of the driveway approach access. If necessary, make other access arrangements, agreed to in writing and signed by the contractor and the property owner serviced by the driveway. Obtain approval from the engineer prior to alternating construction sequencing.

(NER441-20150117)

7.2 Holiday and Other Work Restrictions.

Do not perform work on, nor haul materials of any kind along or across any portion of the highway carrying USH 10/STH 441 and System Interchange ramp traffic, and entirely clear the traveled way and shoulders of such portions of the highway of equipment, barricades, signs, lights and any other material that might impede the free flow of traffic during the following holiday periods:

- From noon Wednesday, July 3, 2019 to 5:00 AM Monday, July 8, 2019 for Independence Day;
- From noon Friday, August 30, 2019 to 5:00 AM Tuesday, September 3, 2019 for Labor Day.

(NER441-20141017)

7.3 Ingress and Egress.

Supplement standard spec 107.9 with the following:

Provide and maintain safe and adequate ingress and egress to and from local streets, private points of access, and other establishment at existing or new access points.

Provide signs, barricades, flaggers, and/or other appurtenances for the maintenance and protection of traffic. Construction operations shall be conducted to ensure a minimum of delay to traffic.

Stopping or slowing traffic on the freeway shall not be permitted.

(NER10/441-20130117)

7.4 Public Convenience and Safety.

Revise standard spec 107.8(6) as follows:

Check for and comply with local ordinances governing the hours of operation of construction equipment.

Contact Randy Gallow, (920) 720-7110, at the Village of Fox Crossing to request a written waiver for hours of operation of construction equipment. Provide the approved waiver request to the engineer.

Contact Tim Montour, (920) 967-3612, at the City of Menasha to request a written waiver for hours of operation of construction equipment. Provide the approved waiver request to the engineer.

Delete standard spec 107.8 (4) and replace with the following:

Notify the following organizations and departments at least 72 hours before road closures or detours are put into effect:

Wisconsin State Patrol	(920) 929-3700
Calumet County Sheriff's Department	(920) 849-2335
Winnebago County Sheriff's Department	(920) 236-7334
Village of Fox Crossing Fire Department	(920) 720-7125
Village of Fox Crossing Police Department	(920) 720-7109
Village of Fox Crossing School District	(920) 967-1400
City of Menasha Fire Department	(920) 967-5125
City of Menasha Police Department	(920) 967-3500
City of Menasha School District	(920) 967-1400

The Winnebago County Sheriff's Department 911 dispatches all area police, fire and ambulance services, and will relay any notification given by the contractor in the event of an emergency.
(NER441-20141017)

7.5 Traffic Control.

After written notice to proceed, and prior to Final Acceptance of the work, assist with maintenance of existing roadways and bridges as specified in standard spec 104.6.1. This assistance may include performance of work covered under pay items or accommodating local repair forces within the work zones. Maintain all newly constructed work as specified in standard spec 104.6.1. Various pay items may be required to maintain the freeway and local streets during construction.

Perform this work according to the requirements of standard spec 643, and as shown on the plans or as approved by the engineer, except as hereinafter modified.

Submit to engineer for approval a detailed traffic control plan for any changes to the proposed traffic control detail as shown on the plans. Submit this plan ten days prior to the preconstruction conference.

Provide 24 hours-a-day availability of equipment and forces to expeditiously restore lights, signs, or other traffic control devices that are damaged or disturbed. The cost to maintain and restore the above items shall be considered incidental to the item as bid and no additional payment will be made therefore.

Supply the name and telephone number of a local contact person for traffic control repair before starting work.

Have available at all times sufficient experienced personnel to promptly install, remove and reinstall the required traffic control devices to route traffic during the construction operations.

The turning of traffic control devices when not in use to obscure the message will not be allowed under this contract.

Obtain prior approval from the engineer for the location of egress and ingress for construction vehicles to prosecute the work.

Cover existing signs which conflict with traffic control as directed by the engineer.

Conduct operations in such a manner that causes the least interference and inconvenience to the free flow of vehicles on the roadways. This includes the following:

- a. Do not park or store any vehicle, piece of equipment, or construction materials on the right-of-way without approval of the engineer.
- b. All construction vehicles and equipment entering or leaving live traffic lanes shall yield to through traffic and shall enter live traffic within 10 mph of the posted speed limit.
- c. Equip all vehicles and equipment entering or leaving the live traffic lanes with a hazard identification beam (flashing yellow signal) capable of being visible on a sunny day when viewed without the sun directly on or behind the device from a distance of 1000 feet. Activate the beam when merging into or exiting a live traffic lane.
- d. Provide a minimum seven working day notice to the business management personnel prior to entering or working within the TLE area.

Do not disturb, remove or obliterate any traffic control signs, advisory signs, shoulder delineators or beam guard in place along the traveled roadways without the approval of the engineer. Immediately repair or replace any damage done to the above during the construction operations at contractor expense.

The traffic requirements are subject to change at the direction of the engineer in the event of an emergency.
(NER441-20141017)

7.6 Temporary Portable Rumble Strips, Item 643.0310.S.

A Description

This special provision describes providing, relocating, maintaining, and removing temporary portable rumble strips.

B Materials

Furnish RoadQuake2 or Roadquake2F temporary portable rumble strips, by Plastic Safety Systems. Do not use alternate products or methods without preapproval by the Bureau of Traffic Operations.

C Construction

C.1 Placement

Provide rumble strips where the plans show or the engineer directs as follows:

1. Before placing rumble strips, clean the roadway of sand and other materials that may cause slippage.
2. Place one end of the rumble strips 6 inches from the roadway centerline. Extend the strips perpendicular to the direction of travel. Ensure strips lay flat on the roadway surface.
3. Only one series of rumble strips, placed before the first work zone, is required per direction of travel for multiple work zones spaced 1 mile or less apart. Work zones spaced greater than 1 mile apart require a separate series of rumble strips.

C.2 Maintenance

Maintain rumble strips as follows:

1. If rumble strips slide, become out of alignment, or are no longer in the wheel path of approaching vehicles during the work period, thoroughly clean both sides of the rumble strips and reset on a clean roadway.
2. Repair or replace damaged rumble strips immediately.

D Measurement

The department will measure temporary portable rumble strips as a single lump sum unit of work, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
643.0310.S	Temporary Portable Rumble Strips	LS

Payment is full compensation for providing, relocating, maintaining or replacing, and removing temporary portable rumble strips.

stp-643-020 (20161130)

8. Utilities.

8.1 Utilities

- (1) This contract comes under the provision of Administrative Code Chapter Trans 220. 107-65 0080501)
- (2) Some of the utility work described below is dependent on prior work being performed by the contractor at a specific site. In such situations, provide the engineer and the affected utility a good faith notice of when the utility is to start work at the site. Provide this notice 14 to 16 calendar days in advance of when the prior work will be completed, and the site will be available to the utility owner. Follow-up with a confirmation notice to the engineer and the utility owner not less than three working days before the site will be ready for the utility owner to begin its work.
- (3) Additional detailed information regarding the location of vacated, relocated, and/or removed utility facilities is available in the work plan provided by each utility company or on the permits issued to them. View these documents at the region WisDOT office during normal working hours.
- (4) **AT&T Wisconsin** maintains a **communication** line along Midway Road and Racine Road within the project limits. AT&T Wisconsin has a crossing at STA 27+50 MWB and STA 28+40 MWB that need to be adjusted during construction so they are not in conflict with the storm sewer. Notify AT&T Wisconsin at least 7 days prior to when in the schedule the pavement and curb & gutter will be removed to coordinate when AT&T Wisconsin can adjust their lines. AT&T Wisconsin requires 4-days to complete the adjustment of both crossings.
- (5) **Fox Crossing Utilities** maintains a **sanitary sewer** facility along Midway Road and Racine Road within the project limits. Adjust sanitary manholes to match the new finished pavement elevations in accordance with the requirements of the bid item: Adjusting Sanitary Manhole Covers. Notify Fox Crossing Utilities at least 3-days prior to adjusting the manholes so they can be on site to inspect the adjustment.
- (6) Fox Crossing Utilities also maintains a sanitary sewer lateral along Racine Road at STA 45R+50 that is in conflict with the storm sewer. Adjust sanitary sewer lateral in accordance with the requirements of the bid item: Sanitary Lateral 4-Inch. Notify Fox Crossing Utilities 3-days prior to exposing the sanitary sewer lateral so they can be on site to inspect the adjustment.
- (7) **Fox Crossing Utilities** maintains a **watermain** facility along Midway Road and Racine Road within the project limits. Fox Crossing Utilities will relocate one hydrant along Racine Road prior to construction and will adjust eight water valves during construction. Notify Fox Crossing Utilities 3-days prior to the necessary water valve adjustment; and anticipate 4 hours to adjust each water valve.

- (8) Fox Crossing Utilities will be discontinuing the existing 12-inch watermain and installing a new 12-inch watermain facility along Midway Road from Racine Road to Earl Street. The watermain will be installed behind the north sidewalk from Racine Road to the WIS 441 structures, then within the terrace area until they end their work at approximately STA 24+75 MWB. This work is scheduled to be completed prior to construction.
- (9) **Menasha Utilities** maintains an **electric** facility along Midway Road and Racine Road within the project limits. Menasha Utilities has an underground electrical facility along the west side of Racine Road that has been previously relocated outside of the slope intercept and is not anticipated to be in conflict.
- (10) Menasha Utilities also updating their service to a customer at the intersection of Earl Street and Midway Road, this update will require Menasha Utilities to install a new underground electric line that will cross Midway Road at approximately STA 26+50 MWB. No conflicts are anticipated with this new facility, and the work will be completed prior to construction.
- (11) The following utility owners have facilities within the project area; however, no adjustments are anticipated:
 - a. **ATC Management, Inc.**
 - b. **Charter Communications**
 - c. **Menasha Utilities – Water**
 - d. **TDS Metrocom LLC**
 - e. **WE Energies – Electric**
 - f. **WE Energies – Gas**

8.2 Municipality Acceptance of Sanitary Sewer.

Both the department and Fox Crossing Utilities personnel will inspect construction of sanitary sewer under this contract. However, construction staking, testing, and acceptance of the sanitary sewer construction will be by the Fox Crossing Utilities.
stp-105-001 (20140630)

9. Clear – Demolition – Removal.

9.1 Clearing and Grubbing.

Complete work according to standard spec 201 and as herein provided.

Revise standard spec 201.3 as follows:

Burning of stumps, roots, brush, waste logs and limbs, timber tops, and debris resulting from clearing and grubbing is not allowed.
(NER41-20100201)

10. Earthwork.

10.1 Embankment Construction.

Replace standard spec 205.3.2(4) with the following:

If placing embankment on side slopes 10 feet high or higher and steeper than one vertical to 3 horizontal, provide vertically-faced, horizontal benches at least 2 feet wide into the existing embankment slope every 2-foot of vertical height.

If constructing embankment on only one side of abutments, wing walls, piers, or culvert headwalls, construct the embankment so that the area immediately adjacent to the structure is not compacted in a manner that causes overturning of or excessive pressure against the structure. If constructing embankment on both sides of a concrete wall, pipe, or box type structure, construct the embankment so that the elevation on both sides of the structure is always approximately the same.

(NER441-20150117)

10.2 Roadway Embankment, Item SPV.0035.001.

Conform to standard spec 207 and as follows:

Replace standard spec 207.1(1) with the following:

This section describes placing in embankments and in miscellaneous backfills, material obtained under the bid items in the roadway and drainage excavation or excavation for structure sections.

Supplement standard spec 207.2(1) with the following:

The contractor may not place excess topsoil or other unstable soil in embankments when the embankment fill height exceeds 10 feet.

Replace standard spec 207.4(1) with the following:

The department will measure Roadway Embankment by the cubic yard acceptably completed in its final location using the method of average end areas, with no correction for curvature or settlement, except as follows:

- a) The engineer and contractor mutually agree to an alternative volume calculation method;
- b) The method of average end areas is not feasible;
- c) Other methods are specified herein standard spec 207.4.

If it is not possible to compute volumes of the various classes of roadway and drainage embankment by the method of average end areas due to erratic location of isolated deposits, the department may compute the volumes by alternative methods involving three-dimensional measurements.

The department will not measure embankment material beyond the limits of the required slopes.

Replace standard spec 207.5(1) with the following:

The department will pay for measured quantities at the contract unit price under the following bid items:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0035.001	Roadway Embankment	CY

Payment is full compensation for forming, compacting, shaping, sloping, trimming, finishing, maintaining the embankments, and all other incidental work required under this section.

(NER441-20150117)

11. Bases, Subbases, and Pavements.

11.1 Coloring Concrete Custom, Item 405.0200.

This special provision describes coloring concrete Red-Brown for incorporation full-depth in work constructed under other contract bid items. Conform to standard spec 405 as modified in this special provision.

Replace standard spec 405.2.1.1(1) with the following:

- (1) Integrally color concrete using non-fading pigments conforming to ASTM C979.
 - For Red-Brown: use synthetic iron oxides at a loading of 6 percent or more by weight of total cementitious material in the mix. Match the concrete color in reasonably close conformance with Red-Brown color, which is similar to Federal Standard 595 - FS 10076.

Replace standard spec 405.2.1.1(3) with the following:

- (3) The department will accept the color based on comparison to color samples available for viewing at WIS 441 Field Office at W6214 Aerotech Drive, Appleton, WI 54914.

stp-405-020 (20160607)

11.2 Aggregate Quality Testing for Modified High-Performance Concrete (HPC) Mixes.

A Description

- (1) This provision describes additional requirements for testing the quality of coarse aggregates being used in modified high-performance concrete mixes for structures and pavements.
- (2) Conform to the standard specifications and modified high-performance concrete provisions contained within the contract, as modified in this provision.

B Materials

B.1 Personnel

- (1) Have personnel certified under the department's highway technician certification program (HTCP) perform sampling, testing, and documentation.

B.2 Laboratory

- (1) Perform testing at a department-qualified laboratory. Obtain information on the Wisconsin laboratory qualification program from:

Materials Management Section
3502 Kinsman Blvd.
Madison, Wisconsin 53704
Telephone: 608-246-5388

<https://www.dot.state.wi.us/business/engrserv/lab-qualification.htm>

B.3 Equipment

- (1) Furnish the necessary equipment and supplies for performing quality control testing. The engineer may inspect the measuring and testing devices to confirm both calibration and condition. Calibrate all testing equipment according to the CMM and maintain a calibration record at the laboratory.

B.4 Records

- (1) Document all observations, inspection records, and test results. Submit testing records to the engineer.

B.5 Contractor Testing

- (1) Perform all quality control tests necessary to control the production processes applicable to this special provision. Use the test methods identified below, or other methods the engineer approves, to perform the following tests:

LA Wear (100 and 500 revolutions)	AASHTO T 96
Sodium Sulfate Soundness (R-4, 5 cycles)	AASHTO T 104
Freeze-Thaw Soundness	AASHTO T 103
Chert ^[1]	AASHTO T 113

^[1]Material classified lithologically as chert and having a bulk specific gravity (saturated surface-dry basis) of less than 2.45. Determine the percentage of chert by dividing the weight of chert in the sample retained on the 3/8-inch sieve by the weight of the total sample.

- (2) The department may periodically observe contractor sampling and testing, and direct additional contractor sampling and testing for department evaluation. Ensure that all test results are available for the engineer's review at any time during normal working hours.
- (3) In addition to the requirements of standard spec 106.3.4.2.2, perform tests for LA wear, sodium sulfate soundness, freeze-thaw soundness and chert at least once per calendar year when producing coarse aggregates for use in modified high-performance concrete mixes.
- (4) Randomly test the percentage of chert at least once per 10,000 tons during production of coarse aggregates to be used in modified high-performance concrete mixes.

B.6 Department Testing

- (1) The department will have a HTCP certified technician, or ACT working under a certified technician, perform verification testing. The department will sample randomly at locations independent of the contractor's QC work. In all cases, the department will conduct the verification tests with separate personnel and equipment from the contractor's QC tests. The department will perform verification testing of chert at a frequency of 10 percent of the random quality control tests or a minimum of once per project, or at greater frequency if determined to be necessary by the engineer.

C (Vacant)

D (Vacant)

E Payment

- (1) Costs for all sampling, testing, and documentation required under this special provision are incidental to the work. If the contractor fails to perform the work required under this special provision, the department may reduce the contractor's pay.
(NER441-20141217)

11.3 QMP HMA Pavement Nuclear Density.

A Description

Replace standard spec 460.3.3.2 (1) and standard spec 460.3.3.2 (4) with the following:

- (1) This special provision describes density testing of in-place HMA pavement with the use of nuclear density gauges. Conform to standard spec 460 as modified in this special provision.
- (2) Provide and maintain a quality control program defined as all activities and documentation of the following:
 1. Selection of test sites.
 2. Testing.
 3. Necessary adjustments in the process.
 4. Process control inspection.
- (3) Chapter 8 of the department's construction and materials manual (CMM) provides additional detailed guidance for QMP work and describes required procedures. Obtain the CMM from the department's web site at:
<https://roadwaystandards.dot.wi.gov/standards/cmm/index.htm>
- (4) The department's Materials Reporting System (MRS) software allows contractors to submit data to the department electronically, estimate pay adjustments, and print selected reports. Qualified personnel may obtain MRS software from the department's web site at:

<http://www.atwoodsystems.com/mrs>

B Materials

B.1 Personnel

- (1) Perform HMA pavement density (QC, QV) testing using a HTCP certified nuclear technician I, or a nuclear assistant certified technician (ACT-NUC) working under a certified technician.
- (2) If an ACT is performing sampling or testing, a certified technician must coordinate and take responsibility for the work an ACT performs. Have a certified technician ensure that all sampling and testing is performed correctly, analyze test results, and post resulting data. No more than one ACT can work under a single certified technician.

B.2 Testing

- (1) Conform to ASTM D2950 and CMM 8.15 for density testing and gauge monitoring methods. Perform nuclear gauge measurements using gamma radiation in the backscatter position. Perform each test for 4 minutes of nuclear gauge count time.

B.3 Equipment

B.3.1 General

- (1) Furnish nuclear gauges from the department's approved product list at
<https://www.dot.wisconsin.gov/business/engrserv/approvedprod.htm>.

- (2) Have the gauge calibrated by the manufacturer or an approved calibration service within 12 months of its use on the project. Retain a copy of the manufacturer's calibration certificate with the gauge.
- (3) Prior to each construction season, and following any calibration of the gauge, the contractor must perform calibration verification for each gauge using the reference blocks located in the department's central office materials laboratory. To obtain information or schedule a time to perform calibration verification, contact the department's Radiation Safety Officer at:
Materials Management Section
3502 Kinsman Blvd.
Madison, Wisconsin 53704
Telephone: (608) 243-5998

B.3.2 Comparison of Nuclear Gauges

B.3.2.1 Comparison of QC and QV Nuclear Gauges

- (1) Select a representative section of the compacted pavement prior to or on the first day of paving for the comparison process. The section does not have to be the same mix design.
- (2) Compare the 2 or more gauges used for density measurement (QC, QV). The QC and QV gauge operators will perform the comparison on 5 test sites jointly located. Record each density measurement of each test site for the QC, QV and back up gauges.
- (3) Calculate the average of the difference in density of the 5 test sites between the QC and QV gauges. Locate an additional 5 test sites if the average difference exceeds 1.0 lb/ft^3 . Measure and record the density on the 5 additional test sites for each gauge.
- (4) Calculate the average of the difference in density of the 10 test sites between the QC and QV gauges. Replace one or both gauges if the average difference of the 10 tests exceeds 1.0 lb/ft^3 and repeat comparison process from B.3.2.1 (2).
- (5) Furnish one of the QC gauges passing the allowable comparison tolerances to perform density testing on the project.

B.3.2.2 Comparison Monitoring

- (1) After performing the gauge comparison specified in B.3.2.1, establish a project reference site approved by the department. Clearly mark a flat surface of concrete or asphalt or other material that will not be disturbed during the duration of the project. Perform comparison monitoring of the QC, QV, and all back-up gauges at the project reference site.

- (2) Conduct an initial 10 density tests with each gauge on the project reference site and calculate the average value for each gauge to establish the gauge's reference value. Use the gauge's reference value as a control to monitor the calibration of the gauge for the duration of the project.
- (3) Check each gauge on the project reference site a minimum of one test per day if paving on the project. Calculate the difference between the gauge's daily test result and its reference value. Investigate if a daily test result is not within 1.5 lb/ft³ of its reference value. Conduct 5 additional tests at the reference site once the cause of deviation is corrected. Calculate and record the average of the 5 additional tests. Remove the gauge from the project if the 5-test average is not within 1.5 lb/ft³ of its reference value established in B.3.2.2(2).
- (4) Maintain the reference site test data for each gauge at an agreed location.

B.4 Quality Control Testing and Documentation

B.4.1 Lot and Sublot Requirements

B.4.1.1 Mainline Traffic Lanes, Shoulders, and Appurtenances

- (1) A lot consists of the tonnage placed each day for each layer and target density specified in standard spec 460.3.3.1. A lot may include partial sublots.
- (2) Divide the roadway into sublots. A sublot is 1500 lane feet for each layer and target density.
- (3) A sublot may include HMA placed on more than one day of paving. Test sublots at the pre-determined random locations regardless of when the HMA is placed. No additional testing is required for partial sublots at the beginning or end of a day's paving.
- (4) If a resulting partial quantity at the end of the project is less than 750 lane feet, include that partial quantity with the last full sublot of the lane. If a resulting partial quantity at the end of the project is 750 lane feet or more, create a separate sublot for that partial quantity.
- (5) Randomly select test locations for each sublot as specified in CMM 8.15 prior to paving and provide a copy to the engineer. Locate and mark QC density test sites when performing the tests. Perform density tests prior to opening the roadway to traffic.
- (6) Use Table 1 to determine the number of tests required at each station, depending on the width of the lane being tested. When more than one test is required at a station, offset the tests 10 feet longitudinally from one another to form a diagonal testing row across the lane.

Lane Width	No. of Tests	Transverse Location
5 ft or less	1	Random
Greater than 5 ft to 9 ft	2	Random within 2 equal widths
Greater than 9 ft	3	Random within 3 equal widths

Table 1

B.4.1.2 Side Roads, Crossovers, Turn Lanes, Ramps, and Roundabouts

- (1) A lot represents a combination of the total daily tonnage for each layer and target density.
- (2) Each side road, crossover, turn lane, ramp, and roundabout must contain at least one subplot for each layer.
- (3) If a side road, crossover, turn lane, or ramp is 1500 feet or longer, determine sublots and random test locations as specified in B.4.1.1.
- (4) If a side road, crossover, turn lane, or ramp is less than 1500 feet long, determine sublots using a maximum of 750 tons per subplot and perform the number of random tests as specified in Table 2.

Side Roads, Turn Lanes, Crossovers, Ramps, Roundabouts: Sublot/Layer tonnage	Minimum Number of Tests Required
25 to 100 tons	1
101 to 250 tons	3
251 to 500 tons	5
501 to 750 tons	7

Table 2

B.4.2 Pavement Density Determination

B.4.2.1 Mainline Traffic Lanes and Appurtenances

- (1) Calculate the average subplot densities using the individual test results in each subplot.
- (2) If all subplot averages are no more than one percent below the target density, calculate the daily lot density by averaging the results of each random QC test taken on that day's material.
- (3) If any subplot average is more than one percent below the target density, do not include the individual test results from that subplot when computing the lot average density and remove that subplot's tonnage from the daily quantity for incentive. The tonnage from any such subplot is subject to disincentive pay according to standard spec 460.5.2.2.

B.4.2.2 Mainline Shoulders

B.4.2.2.1 Width Greater Than 5 Feet

- (1) Determine the pavement density as specified in B.4.2.1.

B.4.2.2.2 Width of 5 Feet or Less

- (1) If all subplot test results are no more than 3.0 percent below the minimum target density, calculate the daily lot density by averaging all individual test results for the day.

- (2) If a subplot test result is more than 3.0 percent below the target density, the engineer may require the unacceptable material to be removed and replaced with acceptable material or allow the nonconforming material to remain in place with a 50 percent pay reduction. Determine the limits of the unacceptable material according to B.4.3.

B.4.2.3 Side Roads, Crossovers, Turn Lanes, Ramps, and Roundabouts

- (1) Determine the pavement density as specified in B.4.2.1.

B.4.2.4 Documentation

- (1) Document QC density test data as specified in CMM 8.15. Provide the engineer with the data for each lot within 24 hours of completing the QC testing for the lot.

B.4.3 Corrective Action

- (1) Notify the engineer immediately when an individual test is more than 3.0 percent below the specified minimum in standard spec 460.3.3.1. Investigate and determine the cause of the unacceptable test result.
- (2) The engineer may require unacceptable material specified in B.4.3(1) to be removed and replaced with acceptable material or allow the nonconforming material to remain in place with a 50 percent pay reduction. Determine limits of the unacceptable area by measuring density of the layer at 50-foot increments both ahead and behind the point of unacceptable density and at the same offset as the original test site. Continue testing at 50-foot increments until a point of acceptable density is found as specified in standard spec 460.5.2.2(1). Removal and replacement of material may be required if extended testing is in a previously accepted subplot. Testing in a previously accepted subplot will not be used to recalculate a new lot density.
- (3) Compute unacceptable pavement area using the product of the longitudinal limits of the unacceptable density and the full subplot width within the traffic lanes or shoulders.
- (4) Retesting and acceptance of replaced pavement will be according to standard spec 105.3.
- (5) Tests indicating density more than 3.0 percent below the specified minimum, and further tests taken to determine the limits of unacceptable area, are excluded from the computations of the subplot and lot densities.
- (6) If 2 consecutive subplot averages within the same paving pass and same target density are more than one percent below the specified target density, notify the engineer and take necessary corrective action. Document the locations of such sublots and the corrective action that was taken.

B.5 Department Testing

B.5.1 Verification Testing

- (1) The department will have a HTCP certified technician, or ACT working under a certified technician, perform verification testing. The department will test randomly at locations independent of the contractor's QC work. The department will perform verification testing at a minimum frequency of 10 percent of the sublots and a minimum of one subplot per mix design. The sublots selected will be within the active work zone. The contractor will supply the necessary traffic control for the department's testing activities.
- (2) The QV tester will test each selected subplot using the same testing requirements and frequencies as the QC tester.
- (3) If the verification subplot average is not more than one percent below the specified minimum target density, use the QC tests for acceptance.
- (4) If the verification subplot average is more than one percent below the specified target density, compare the QC and QV subplot averages. If the QV subplot average is within 1.0 lb/ft³ of the QC subplot average, use the QC tests for acceptance.
- (5) If the first QV/QC subplot average comparison shows a difference of more than 1.0 lb/ft³ each tester will perform an additional set of tests within that subplot. Combine the additional tests with the original set of tests to compute a new subplot average for each tester. If the new QV and QC subplot averages compare to within 1.0 lb/ft³, use the original QC tests for acceptance.
- (6) If the QV and QC subplot averages differ by more than 1.0 lb/ft³ after a second set of tests, resolve the difference with dispute resolution specified in B.6. The engineer will notify the contractor immediately when density deficiencies or testing precision exceeding the allowable differences are observed.

B.5.2 Independent Assurance Testing

- (1) Independent assurance is unbiased testing the department performs to evaluate the department's verification and the contractor's QC sampling and testing including personnel qualifications, procedures, and equipment. The department will perform the independent assurance review according to the department's independent assurance program.

B.6 Dispute Resolution

- (1) The testers may perform investigation in the work zone by analyzing the testing, calculation, and documentation procedures. The testers may perform gauge comparison according to B.3.2.1.

- (2) The testers may use comparison monitoring according to B.3.2.2 to determine if one of the gauges is out of tolerance. If a gauge is found to be out of tolerance with its reference value, remove the gauge from the project and use the other gauge's test results for acceptance.
- (3) If the testing discrepancy cannot be identified, the contractor may elect to accept the QV subplot density test results or retesting of the subplot in dispute within 48 hours of paving. Traffic control costs will be split between the department and the contractor.
- (4) If investigation finds that both gauges are in error, the contractor and engineer will reach a decision on resolution through mutual agreement.

B.7 Acceptance

- (1) The department will not accept QMP HMA Pavement Nuclear Density if a non-compared gauge is used for contractor QC tests.

C (Vacant)

D (Vacant)

E Payment

E.1 QMP Testing

- (1) Costs for all sampling, testing, and documentation required under this special provision are incidental to the work. If the contractor fails to perform the work required under this special provision, the department may reduce the contractor's pay. The department will administer pay reduction under the Non-performance of QMP administrative item.

E.2 Disincentive for HMA Pavement Density

- (1) The department will administer density disincentives according to standard spec 460.5.2.2.

E.3 Incentive for HMA Pavement Density

- (1) The department will administer density incentives according to standard spec 460.5.2.3.

stp-460-020 (20161130)

11.4 Concrete Pavement Joint Layout, Item 415.5110.S.

A Description

This special provision describes providing a concrete pavement or concrete base joint layout design for intersections and marking the location of all joints in the field

B (Vacant)

C Construction

Plan and locate all points necessary to establish the horizontal position of the transverse and longitudinal joints in the concrete to prevent uncontrolled cracking. Submit a joint layout design to the engineer at least 7 calendar days before paving each intersection. Do not lay out joints until the engineer has reviewed the joint layout design. Mark the location of all concrete joints in the field. Follow the plan details for joints in concrete making adjustments as required to fit field conditions.

D Measurement

The department will measure Concrete Pavement Joint Layout as a single lump sum unit for all joint layout designs and marking acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
415.5110.S	Concrete Pavement Joint Layout	LS

Payment is full compensation for providing the intersection joint layout designs and marking all joints in the field.

The department will adjust pay for crack repairs as specified in standard spec 415.5.3 stp-415-020 (20170615)

11.5. Optimized Aggregate Gradation Incentive, Item 715.0710.

Description

This special provision describes optional contractor optimized aggregate gradation, optional optimized mixture designs, and associated additional requirements for class 1 concrete used in concrete pavements. Conform to standard specification part 7 and as follows:

Optimized Aggregate Gradation

A Job Mix Formula (JMF) contains all of the following:

Proportions for each aggregate fraction conforming to table 1.

Individual gradations for each aggregate fraction.

Composite gradation of the combined aggregates including working ranges on each sieve in accordance with table 2.

Submit the target JMF and aggregate production gradation test results to the engineer for review 10 business days before initial concrete placement.

TABLE 1 TARANTULA CURVE GRADATION BAND

SIEVE SIZES	PERCENT RETAINED
2 in.	0
1 1/2 in.	≤5
1 in.	≤16
3/4 in.	≤20
1/2 in.	4-20
3/8 in.	4-20
No. 4	4-20
No. 8 ^[1]	≤12
No. 16 ^[1]	≤12
No. 30 ^{[1] [2]}	4-20
No. 50 ^[2]	4-20
No. 100 ^[2]	≤10
No. 200 ^[2]	≤2.3

^[1] Minimum of 15% retained on the sum of the #8, #16, and #30 sieves.

^[2] Conform to 24-34% retained of fine sand on the #30-200 sieves.

TABLE 2 JMF WORKING RANGE

SIEVE SIZES	WORKING RANGE ^[1] (PERCENT)
2 in.	+/- 5
1 1/2 in.	+/- 5
1 in.	+/- 5
3/4 in.	+/- 5
1/2 in.	+/- 5
3/8 in.	+/- 5
No. 4	+/- 5
No. 8	+/- 4
No. 16	+/- 4
No. 30	+/- 4
No. 50	+/- 3
No. 100	+/- 2
No. 200	≤ 2.3

^[1] Working range limits of composite gradation based on moving average of 4 tests.

Test each component aggregate once per 1,500 cubic yards during concrete production. Take samples by one of the following sampling methods:

1. At the belt leading to the weigh hopper.
2. Working face of the stock piles at the concrete plant if approved by the engineer.

The department will take independent QV samples using the same sampling method the contractor uses for QC sampling. QV samples may be taken by the contractor's QC personnel if witnessed by the department's QV personnel. The department will split each QV sample and retain half for all dispute resolutions. If QV test results conform to the specification, the department will take no further action. If QV test results are nonconforming, add the QV to the QC test results as if it were an additional QC test.

If, during concrete production, the moving average of four for any sieve fall outside the allowable JMF working range do the following:

1. Notify the engineer of the test results within 1 business day from the time of sampling.
2. Make immediate adjustments to the JMF, within the limits specified in Table 3;
3. Review JMF adjustments with the engineer. Both the contractor and engineer will sign the adjusted JMF if the adjustments comply with Table 3.
4. If the moving average of four falls outside the adjusted allowable working range, stop production and provide a new mix design including JMF to the engineer.

TABLE 3 ALLOWABLE JMF ADJUSTMENTS

SIEVE SIZES	ALLOWABLE ADJUSTMENT (PERCENT)
$\geq$ No. 4	+/- 5
No. 8 – No. 30	+/- 4
No. 50	+/- 3
No. 100	+/- 2

Dispute Resolution

The department will resolve disputes as specified in standard spec 106.3.4.3.5 using QV split samples.

Sublot and Lot Size

A sublot consists of up to 1,500 cubic yards. A lot consists of two sublots.

Optimized Concrete Mixtures

The contractor may use a reduced cementitious content for concrete pavement placed if the contractor does the following:

1. Use an optimized aggregate gradation as defined in this special provision.
2. Conform to the additional testing requirements for flexural strength as specified in the contract special provisions.
3. Submit aggregate gradation result records no more than 2 years old when developing the mix design.
4. Determine the volume of voids in the optimized aggregates using ASTM C29.

5. Download and follow the instructions tab of the Optimized Gradation and Mix Design Spreadsheet located at:
<http://wisconsindot.gov/Pages/doing-bus/eng-consultants/cnslt-rsrcs/qmp/default.aspx>
6. Design an appropriate paste content based upon the Performance-based PCC Mix Design Guide located at:
<http://wisconsindot.gov/Pages/doing-bus/eng-consultants/cnslt-rsrcs/qmp/default.aspx>
7. Provide a minimum V_{paste}/V_{voids} of 1.25. (Paste/Void ratio equals the volume of paste divided by the volume of voids.).
8. Evaluate workability of trial batches by following section 6.8 of AASHTO Draft Performance Engineered Concrete Pavement Mixtures Specifications located at:
<http://wisconsindot.gov/Pages/doing-bus/eng-consultants/cnslt-rsrcs/qmp/default.aspx>
9. Submit trial batch workability results when submitting the mix design.
10. Submit the CP Tech center computer spreadsheet concrete mix design to the engineer for review at least 3 business days before producing concrete.
11. Provide a minimum cement content of 520 pounds per cubic yard, except if using type I, IL, or III cement in a mix where the geologic composition of the coarse aggregate is primarily igneous or metamorphic materials, provide a minimum cement content of 660 pounds per cubic yard.
12. The contractor may use class C fly ash or grade 100 or 120 slag as a partial replacement for cement. For binary mixes use up to 30% fly ash or slag. For ternary mixes use up to 30% fly ash plus slag in combination. Replacement values are in percent by weight of the total cementitious material in the mix.
13. See CMM 8-70.2.2.3 for additional guidance.

Measurement

The department will measure Optimized Aggregate Gradation Incentive by the dollar, for each combined averaged lot of QC test results meeting Table 1.

Payment

The department will pay incentive of 3 percent of the contract unit price for concrete pavement under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
715.0710	Optimized Aggregate Gradation Incentive	DOL
stp-715-005 (20180628)		

11.6 Flexural Strength for Concrete Mix Design.

This special provision describes optional testing requirements for flexural strength during the mix design process. Conform to standard spec part 7 as modified in this special provision.

Add the following to standard spec table 701-2:

TEST	TEST STANDARD
Flexural Strength of Concrete	AASHTO T97

Replace standard spec 715.2.3.1(1) with the following:

- (1) Provide both compressive and flexural strength information to demonstrate the strength of the proposed mix design. Use either laboratory strength data for new mixes or field strength data for established mixes as follows:
 1. Use at least 5 pairs of cylinders for compressive strength. Demonstrate that the 28-day compressive strength will equal or exceed the 85 percent within limits criterion specified in 715.5.2.
 2. Use at least 5 pairs of beams for flexural strength. Demonstrate that the 28-day flexural strength will equal or exceed 650 psi.

stp-715-010 (20170615)

11.7 Modified High Performance Concrete (HPC) Pavement 9-Inch, Item SPV.0180.001;

This special provision describes specialized material and construction requirements to be utilized on all concrete pavement and shoulders. Conform to standard spec 415 and 501, as modified in this special provision. Conform to section 715 for QMP, as modified in this special provision.

MODIFY STANDARD SPEC SECTION 415 AS FOLLOWS:

415.5.1 General

Replace 415.5.1(1) with the following:

- (1) The department will pay for measured quantities at the contract unit price and incidentals necessary to complete the work under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0180.001	Modified High Performance Concrete (HPC) Pavement 9-Inch	SY

MODIFY STANDARD SPEC SECTION 501 AS FOLLOWS:

501.2.5.4.1 General

Replace the entire text with the following:

- (1) Use clean, hard, durable crushed limestone with 100% fractured surfaces and free of an excess of thin or elongated pieces, frozen lumps, vegetation, deleterious substances or adherent coatings considered injurious.
- (2) Use virgin aggregates only.

501.2.5.4.2 Deleterious Substances

Replace standard spec 501.2.5.4.2(1) with the following:

- (1) The amount of deleterious substances must not exceed the following percentages:

DELETERIOUS SUBSTANCE	PERCENT BY WEIGHT
Shale.....	1.0
Coal.....	1.0
Clay lumps	0.3
Soft fragments.....	5.0
Any combination of above.....	5.0
Flat or elongated pieces based on a 3:1 ratio	15.0
Materials passing the No. 200 sieve	1.5
Chert.....	3.0

501.2.5.4.3 Physical Properties

Replace standard spec 501.2.5.4.3(1) with the following:

- (1) The percent wear shall not exceed 30, the weighted soundness loss shall not exceed 6 percent, and the weighted freeze-thaw average loss shall not exceed 15 percent.

501.3.5.1 General

Replace standard spec 501.3.5.1(1) with the following:

- (1) Use central-mixed concrete as defined in 501.3.5.1(2) for all work under this special provision.

501.3.8.2.1 General

Replace the entire text with the following:

- (1) The contractor is responsible for the quality of the concrete placed in hot weather. For concrete placed under this special provision, submit a written temperature control plan at or before the pre-pour meeting. In that plan, outline the actions the contractor will take to control concrete temperature if the concrete temperature at the point of placement exceeds 80 F. Do not place concrete under the items in this special provision

without the engineer's written acceptance of that temperature control plan. Perform work as outlined in the temperature control plan.

- (2) If the concrete temperature at the point of placement exceeds 90 F, do not place concrete under this special provision.
- (3) Notify the engineer whenever conditions exist that might cause the concrete temperature at the point of placement to exceed 80 F. If project information is not available, the contractor should obtain information from similar mixes placed for other nearby work.

501.5 Payment

Replace standard spec 501.5(3) with the following:

- (3) Ice, additives, or other actions the contractor takes to control the temperature of concrete are incidental to this item.

Add the following as standard spec 501.5(4):

- (4) Water used to wet the base material is incidental to this item.

MODIFY STANDARD SPEC SECTION 715 AS FOLLOWS:

715.3.2.2.1 Pavement

Replace the entire section with:

- (1) If a subplot strength is less than 3000 psi, the department may direct the contractor to core that subplot to determine its structural adequacy and whether to direct removal. Cut and test cores according to AASHTO T 24 and as where the engineer directs. Have an HTCP certified PCC technician I perform or observe the coring.
- (2) The subplot pavement is conforming if the compressive strengths of all cores from the subplot are 3000 psi or greater or the engineer does not require coring.
- (3) The subplot pavement is nonconforming if the compressive strengths of any core from the subplot is less than 3000 psi. The department may direct removal and replacement or otherwise determine the final disposition of nonconforming material as specified in 106.5.

715.5.1 General

Replace standard spec 715.5.1(4) with the following:

- (4) The department will adjust pay for each lot using PWL of the 28-day subplot average strengths for that lot. The department will measure PWL relative to the lower specification limit of 4500 psi for pavements. The department will not pay a strength incentive for concrete that is nonconforming in another specified property.

715.5.2 Pavements

Replace standard spec 715.5.2(3) with the following:

- (3) For lots with a full battery of QC tests at less than 4 locations, there is no incentive but the department will assess a disincentive based on the individual subplot average strengths. The department will reduce pay for sublots with an average strength below 4500 psi by \$1.50 per square yard.
(NER441-20141217)

12. Bridges.

12.1 Removing Crushed Aggregate Slope Paving, Item SPV.0180.002.

A Description

This special provision describes removing and disposing of asphaltic-coated crushed aggregate slope paving as shown in the plans, in accordance with section 204 of the standard specifications, and as hereinafter provided.

B (Vacant)

C Construction

Remove crushed aggregate slope paving in accordance with the pertinent provisions of section 204 of the standard specifications. After removing the existing slope paving material, restore the slope in front of the abutments to a smooth surface.

D Measurement

The department will measure Removing Crushed Aggregate Slope Paving by the square yard, acceptably completed.

E Payment

The department will pay for the measured quantity at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0180.002	Removing Crushed Aggregate Slope Paving	SY

Payment is full compensation for removing the slope paving material; restoring the slope to a smooth surface; and for properly disposing of all material removed.

13. Retaining Walls, Ground Support. (Vacant)

14. Drainage and Erosion Control.

14.1 Erosion Control.

Supplement standard spec 107.20 as follows:

Perform construction operations in a timely and diligent manner, continuing all construction operations methodically from the initial topsoil stripping operation through the subsequent grading and finishing to minimize the period of exposure to erosion.

Immediately re-topsoil graded areas, as designated by the engineer, after grading is completed within those areas. Seed, fertilizer, and mulch or erosion mat all topsoiled areas as per ECIP after placement of topsoil.

Restore as much disturbed area as possible or as directed by the engineer with topsoil, seeding, fertilizer, and mulching or erosion mat at the end of each construction season to minimize erosion due to spring melt. As directed by the engineer, stabilize areas that cannot be restored with permanent measures at the end of each construction season with the soil stabilizer item provided in the plan.

Prepare an Erosion Control Implementation Plan (ECIP) amendment detailing an over-winter erosion control plan for 2018/2019. Present this ECIP amendment at a pre-winter shut down meeting with DNR and DEPARTMENT staff prior to October 15th.
(NER441-20141017)

14.2 Maintaining Drainage.

Maintain drainage at and through worksite during construction according to standard spec 107.22, standard spec 204, and standard spec 520.

Use existing culvert pipes and existing drainage channels to maintain existing surface drainage.

Dewatering

If dewatering or pumping is required, treat the water to remove suspended solids before allowing it to enter any waterway or wetland. Filter pumped water through a media such as washed stone or allow settling in a sedimentation basin with sufficient capacity and size to provide an efficient means to filter the water from the dewatering operation before it is discharged back into the waterway or wetland. As part of the Erosion Control Implementation Plan (ECIP) submittal, supply all pertinent information and calculations used to determine the best management practice for dewatering at each location it is required.

Refer to the dewatering guidelines of WisDNR Storm Water Management Technical Standards, Code #1061, "Dewatering". This document can be found at the WisDNR website: <http://dnr.wi.gov/runoff/stormwater/techstds.htm>

The cost of all work and materials associated with water treatment and/or dewatering is incidental to the project.
(NER441-20150125)

14.3 Storm Sewer Backfill.

Replace standard spec 608.5.2 (1) with the following:

- (1) Payment for the Storm Sewer Pipe bid items is full compensation for providing all materials, including all special Y's, mitered sections, elbows and connections required; for excavating and wasting excess material, except rock excavation; for providing and removing sheeting and shoring; for forming foundation; for laying pipe; for sealing joints and making connections to new or existing features; for providing foundation and trench backfill material; for backfilling; for cleaning out; and absent the pertinent contract bid items, for restoring the work site.

(NER441-20170420)

14.4 Backfill Controlled Low Strength, Item 209.0200.S.

A Description

This special provision describes furnishing and placing a controlled low strength material designed for use as backfill in trenches for culverts, sewers, utilities, or similar structures, as backfill behind bridges abutments, or as fill for the abandonment of culverts, pipes, or tanks.

B Materials

Provide controlled low strength backfill that consists of a designed cementitious mixture of natural or processed materials. Allowable materials include natural sand, natural gravel, produced sand, foundry sand, produced gravel, fly ash, Portland cement, and other broken or fragmented mineral materials. The designed mixture shall be self-leveling and shall be free of shrinkage after hardening. Design the mixture to reach a state of hardening such that it can support foot traffic in no more than 24 hours. Provide a mixture that also meets the following requirements.

Test	Method	Value
Flow (inch)	ASTM D-6103	9 min
Compressive Strength (psi)	ASTM D-6024	20-40 @ 14 days 40-80 @ 28 days 80-120 @ 90 days

Chemical admixtures to control air content and setting time are allowable. Ten days prior to placement, furnish the engineer with a design mix detailing all components and their proportions in the mix. Also, provide documentation from the supplier of the industrial byproducts that the foundry sand and fly ash used in the mixture meet the requirements for Industrial Byproducts Categories 1, 2, 3, or 4 in NR 538 of the Wisconsin Administrative Code for use as a confined geotechnical fill.

C Construction

Place controlled low strength backfill at the locations and to the lines and grades as shown on the plan. Proportion and mix materials to produce a product of consistent texture and flow characteristics. The engineer may reject any materials exhibiting a substantial change in properties, appearance, or composition.

If the official Weather Bureau forecast for the construction site predicts temperatures at or below freezing within the next 24 hours after placement of controlled low strength backfill, protect the placed materials from freezing during that time period. If the temperature is not forecast to rise above 40° F for 72 hours after placement, the engineer may require protection from freezing for up to 72 hours.

No controlled low strength backfill shall be allowed to enter any stream, lake, or sewer system. The contractor shall be responsible for any clean up or remediation costs resulting from such occurrences.

D Measurement

The department will measure Backfill Controlled Low Strength in volume by the cubic yard of material placed and accepted. Such volume shall be computed from actual measurements of the dimensions of the area to be backfilled. In irregular or inaccessible areas, the engineer may allow volume to be determined by other appropriate methods.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
209.0200.S	Backfill Controlled Low Strength	CY

Payment is full compensation for designing the mix; supplying all materials; preparing the proportioned mix; hauling it to the construction site; placing the material; and protecting it from freezing.

stp-209-010 (20090901)

14.5 Temporary Ditch Checks.

Complete work according to standard spec 628 and as herein provided. Erosion bales will not be allowed for construction of temporary ditch checks.

Delete standard spec 628.3.14(2) and replace it with the following:

- (2) Construct temporary ditch checks using a manufactured alternative from the PAL. Place temporary ditch checks across ditches at locations the plans show or as the engineer directs immediately after shaping the ditches or slopes. Excavate upstream sumps as the engineer directs.

Delete standard spec 628.4.17 and replace it with the following:

- (1) The department will measure Temporary Ditch Checks by the linear foot, acceptably completed.
(NER441-20141017)

14.6 Manholes 10-Ft Diameter, Item SPV.0060.100.

A Description

Perform the work according to the applicable provisions of standard spec 611 and as detailed in the plans.

B Materials

Conform to standard spec 611.2 and the plan details.

C Construction

Conform to standard spec 611.3 and the plan details.

D Measurement

The department will measure Manholes 10-Ft Diameter as each individual unit acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid items:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0060.100	Manholes 10-Ft Diameter	EACH

Payment is full compensation for providing all materials, including all masonry, conduit and sewer connections, steps and other fittings; for all excavating, backfilling, disposing of surplus material, and for cleaning out and restoring the work site; except that the department will pay for covers, including frames, grates and lids separately.

14.7 Street Sweeping, Item SPV.0075.001.

A Description

Remove small dirt and dust particles from the roadway using a street sweeper for cleaning the roadway before traffic switches or cleaning of roadways from non-contractor vehicle traffic.

B (Vacant)

C Construction

Provide a self-contained mechanical or air conveyance street sweeper and dispose the accumulated material.

D Measurement

The department will measure Street Sweeping by the hour that the street sweeper is on the project picking up and removing debris from the roadway, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0075.001	Street Sweeping	HRS

Payment is full compensation for furnishing all labor, tools, equipment, and incidentals necessary to complete the contract work.

All street sweeping due to the contractors hauling operations is considered incidental to the contract.

(NER441-20150117)

14.8 Water for Seeded Areas, Item SPV.0120.150.**A Description**

This special provision describes furnishing, hauling and applying water to seeded areas as directed by the engineer, and as hereinafter provided.

B Materials

When watering seeded areas, use clean water, free of impurities or substances that might injure the seed.

C Construction

If rainfall is not sufficient, keep all seeded areas thoroughly moist by watering or sprinkling. Water for 30 days after seed placement or as the engineer directs. Apply water in a manner to preclude washing or erosion. The topsoil shall not be left un-watered for more than 3 days during this 30-day period unless the engineer determines that it is excessively wet and does not require watering. The equivalent of one inch of rainfall per week shall be considered the minimum.

D Measurement

The department will measure Water for Seeded Areas by volume by the thousand gallon units (MGAL), acceptably completed. The department will determine volume by engineer-approved meters or from tanks of known capacity.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0120.150	Water for Seeded Areas	MGAL

Payment is full compensation for furnishing, hauling, and applying the water.

(NER12-1010)

15. Miscellaneous Concrete. (Vacant)

16. Signing and Marking.

16.1 Remove Commercial Sign, Item SPV.0060.250.

A Description

This work shall consist of removing commercial signs, supports, and foundation as shown in the plans and according to the pertinent requirements of standard spec 204, and as hereinafter provided.

B (Vacant)

C Construction

Ensure that the engineer has reviewed and has approved all sign removals before beginning removal work. Coordinate with the property owner and electrical utility to disconnect power to the commercial sign before removing signs. Remove conduit from the existing sign to the easement line and place a temporary marker at the end of the remaining conduit. Remove the wire from the building to the removed sign. Sign supports, sign assemblies, and wiring shall become property of the contractor. Transport all removed items from the project site. The contractor is responsible for legal hauling and disposal of removed items.

D Measurement

The department will measure Remove Commercial Sign bid item as an each unit, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0060.250	Remove Commercial Sign	EACH

Payment is full compensation for disconnecting power; removing sign supports, removing masonry foundation, sign assemblies, conduit and wiring; and for hauling and properly disposing of items.

17. Lighting/Electrical.

17.1 General Requirements for Electrical Work.

Add the following to standard spec 651.2, Materials:

(7) The approved products lists located at:

<https://www.dot.state.wi.us/business/engrserv/electric/index.htm>

Contact information for the Wisconsin Department of Transportation Northeast Region
Electrical Unit: Randy Asman, (920) 360-3107, Randy.Asman@dot.wi.gov

17.2 Lighting Control Cabinets 6240/480 30-Inch 659.2230.

Replace standard spec 659.2, Materials, with the following:

Provide a 3.0kVA control power transformer.

18. Intelligent Transportation Systems.

18.1 Intelligent Transportation Systems

Supplement standard spec 106.3 with the following:

Design/Shop Drawings

Prior to the purchase and/or fabrication of any of the components listed herein, and for any non-catalog item, and no more than 30 days after notice to proceed, submit five copies of design drawings and shop drawings, as required, to the department for review. The items and the drawings that represent them shall meet the requirements of the standard specifications.

Design drawing submissions shall consist of signed and certified designs, design drawings, calculations, and material specifications for required items.

The department will complete its review of the material within 30 days from the date of receipt of the submission, unless otherwise specified. The department will advise the contractor, in writing, as to the acceptability of the material submitted. The department may determine that if no exceptions were taken for the item, it is approved, and no further action is required by the contractor; or the item may be partially or totally rejected, in which case modify and/or amend the submittal as required by the department and resubmit the item within 14 days. At this time, the review and approval cycle described above will begin again.

Supplement standard spec 671.2 with the following:

671.2.4 Locate Wire

Furnish and install a No. 14 AWG stranded copper wire for future locate purposes through each conduit run. Connect the locate wire by using a wire nut at each pull box, manhole, or other access point. Alternatively, use a single wire through the access points. All material furnished under this item shall meet the requirements of standard spec 655.

671-05 0100630)

18.2 Ramp Closure Gates 26-FT, Item 662.1026.S; Ramp Closure Gates 40-FT, Item 662.1040.S;

A Description

This special provision describes providing freeway on-ramp closure gates on type 5 steel luminaire poles. This special provision also describes furnishing and delivering spare gate arms.

B Materials

B.1 General

Provide five user manuals and a listing of vendors and contact information for each manufactured component including flasher electrical components.

The engineer may allow alternates equal to specified manufactured components. The engineer may require plan detail modifications to accommodate alternates. The engineer may accept alternate arms or mounting adaptors only if the contractor can demonstrate that the department can easily remove and replace the arms.

B.2 Components

Furnish type 5 steel poles designed to carry twin 15-foot luminaire arms and conforming to standard spec 657 and with dimensions for acceptable installation of the ramp gate hardware as shown on the detail. Ensure a contiguous pole by eliminating the hand hole near base of pole, thus allowing uninhibited mounting of the gate pivot assembly.

Furnish galvanized steel nuts and bolts conforming to ASTM A307 except where designated as high strength (HS), conform to ASTM F3125. For the ramp closure gate locking mechanism, furnish a 3/4-inch handle nut.

Furnish grade A36 steel for the gate supports, gate pivot assembly, and associated hardware galvanized after fabrication by either a mechanical or hot-dip process. Grind welded connections, rough edges, and burrs smooth before galvanizing to ensure a finished appearance. Ensure that the galvanized coating conforms to ASTM A 153.

Provide aluminum/fiberglass gate arms of the nominal length the bid item indicates and conforming to plan dimensions. Cover gate arms on two sides with alternating red and white shop-applied type H reflective from the department's approved products list. Also provide a shear pin base that is the manufacturer's "permanent pivot" style. Obtain components from:

1. B&B Roadway
2. 15191 Hwy 243
3. Russellville, AL 35654
4. Tel: (888) 560-2060
5. Gate arm: model MU605

Furnish a worm gear winch with a single line vertical lift capacity of 2000 lbs. Ensure that the winch has hardened steel gears, a handgrip, permanently lubricated bearings, a reinforced arc-welded reel assembly, and mounting plate. Ensure that the winch can be mounted to the winch mount plate shown on the construction details and the handgrip can be operated without conflict with the pole or ramp gate assembly. Furnish a 2-inch outdoor rated, rot resistant polyester strap for the connection between the worm gear winch and the gate arm pivot assembly.

C Construction

C.1 Ramp Closure Gates

Under the Ramp Closure Gates bid items, provide ramp closure gate at the locations the plans show. Apply marine grade anti seize compound compound to all bolt threads and to the interface between the aluminum base and steel pole. The engineer may direct adjustment of the gate arm assembly to ensure the correct vertical and angular orientation of the completed closure gate.

Install structure identification plaques in the location the plan details show.

Randy Asman, (920) 360-3107

C.2 Furnishing Gate Arms

Under the Ramp Closure Gate Arms Stockpile bid items, furnish and deliver spare arms of the nominal length the bid item indicates conforming to B.2. Deliver spare gate arms to an address provided by:

Randy Asman, (920) 360-3107

D Measurement

The department will measure the Ramp Closure Gates bid items as each individual installation, acceptably completed.

The department will measure the Ramp Closure Gate Arms Stockpile bid items as each individual unit, acceptably furnished and delivered.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
662.1026.S	Ramp Closure Gates 26-FT	EACH
662.1040.S	Ramp Closure Gates 40-FT	EACH

Payment for the Ramp Closure Gate bid items is full compensation for providing ramp closure gates including support poles; for gate arm assemblies including guides, collars, and gate arms; and for structure identification plaques. Payment for the Ramp Closure Gate Arms Stockpile is full compensation for furnishing and delivering spare ramp closure gate arms.

stp-662-005 (20180628)

19. Landscaping. (Vacant)

20. Miscellaneous – Incidental Construction.

20.1 Survey Monument Coordination.

The monument disturbance is anticipated at the intersection of Oneida Street and Valley Road.

The contractor is to notify the Northeast Regional Survey Coordinator, Cormac McInnis, (920) 492-5638, at least 30 days prior to the beginning of construction activities. The Regional Survey Coordinator will then make the arrangements to have the Public Land Survey Monument and Landmark Reference Monuments tied out.

After the majority of construction is complete (prior to restoration) the contractor is again to notify the Survey Coordinator that the site is ready for the replacement of the monuments. The Survey Coordinator will then make arrangements to have the Public Land Survey Monument and Landmark Reference Monuments reset.
(NER14-0429)

20.2 Adjusting Sanitary Manhole Covers, Item SPV.0060.650.

A Description

This special provision describes adjusting sanitary manhole covers and castings to match into new pavement surface.

B Materials

Conform to standard spec 611.2.

New casting and cover will be supplied by the Village of Fox Crossing Utility District.

Contact David Tracey at the Village of Fox Crossing at (920) 720-7175 to arrange to pick up castings and covers.

C Construction

Conform to standard spec 611.3.7.

Remove and reinstall existing chimney seals, as necessary to adjust manhole cover.

Remove existing castings and covers and contact David Tracey at the Village of Fox Crossing Utility District withing two days to arrange pickup of material.

D Measurement

The department will measure Adjusting Sanitary Manhole Covers as each individual unit, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0060.650	Adjusting Sanitary Manhole Covers	EACH

Payment for Adjusting Sanitary Manhole Covers is full compensation for providing all required materials, exclusive of frames, grates, or lids; and for removing, reinstalling and adjusting the covers, and castings including removing and reinstalling the existing chimney seal.

(NER441-20141017)

20.3Sanitary Lateral 4-Inch, Item SPV.0090.651.**A Description**

This special provision describes Sanitary Lateral 4-Inch PVC, as shown on the plans, conforming to the requirements in the separate specification titled "Village of Fox Crossing Standard Specifications and Special Provisions per S-2017-0167". Contact Jeff Roth at Village of Fox Crossing (920) 720-7175 to obtain a copy.

B Materials

Furnish the following pipe and lateral material: Polyvinyl chloride (PVC) Schedule 40, ASTM Specification D-3034, SDR 35.

C Construction

Conforming to the requirements in the separate specification titled "Village of Fox Crossing Standard Specifications and Special Provisions per S-2017-0167".

D Measurement

The department will measure Sanitary Lateral 4-Inch, in length by the linear foot in place, and the quantity measured for payment shall be the horizontal distance measured along the centerline of the pipe from the inlet to the upstream end.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0090.651	Sanitary Lateral 4-Inch	LF

Payment is full compensation for furnishing all material including elbows, connections and cleanouts; for laying pipe; for connecting to inlets; for backfilling; and for furnishing granular backfill material.

20.4 Referenced Construction Specifications.

Construct the sanitary sewer work conforming to the Village of Fox Crossing Standard Specifications and Special Provisions per S-2017-0167. If there is a discrepancy or conflict between the referenced specification and the standard specifications regarding contract administration, part 1 of the standard specifications governs.
stp-105-002 (20130615)

20.5 Survey Project 1517-75-77, Item SPV.0105.002.

A Description

Standard spec 105.6 and 650 are modified to define the requirements for construction staking for this contract.

Replace standard spec 105.6.2 with the following:

The department will not perform any construction staking for this contract. Perform all survey required to layout and construct the work under this contract, subject to engineer's approval.

The survey includes establishing horizontal and vertical position for all aspects of construction including but not limited to storm sewer, subgrade, base, curb, gutter, curb and gutter, pipe culverts, structure layout, pavement, barriers (temporary and permanent), electrical installations, supplemental control, slope stakes, ponds, ITS, FTMS, ramp gates, parking lots, utilities, landscaping elements, irrigation system layout, installation of community sensitive design elements, traffic control items, fencing, etc.

The department may choose to perform quality assurance survey during construction. This quality assurance survey does not relieve the contractor of the responsibility for furnishing all survey work required under this contract.

Delete standard spec 650.1.

B (Vacant)

C Construction

Survey required under this item shall be according to all pertinent requirements of standard spec 650 and shall include all other miscellaneous survey required to layout and construct all work under this contract.

D Measurement

The department will measure Survey Project (ID) as a single lump sum unit of work, acceptably completed.

E Payment

Replace standard spec 650.5 with the following:

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0105.002	Survey Project 1517-75-77	LS

Payment is full compensation for performing all survey work required to layout and construct all work under this contract. No additional payments will be made for re-staking due to construction disturbance and knock-outs.

(NER441-20150117)

**ADDITIONAL SPECIAL PROVISION 1 (ASP 1)
FOR TRANSPORTATION ALLIANCE FOR NEW SOLUTIONS (TrANS)
PROGRAM EMPLOYMENT PLACEMENTS AND APPRENTICESHIPS**

The Safe, Accountable, Flexible, Efficient Transportation Equity Act: A Legacy for Users (SAFETEA-LU), Section 5204(e) – Surface Transportation Workforce Development Training and Education, provides for 100 percent Federal funding if the core program funds are used for training, education, or workforce development purposes, including “pipeline” activities. The core programs includes: Congestion Mitigation and Air Quality Improvement (CMAQ) Program, Highway Bridge Program (HBP), Interstate Maintenance (IM), National Highway System (NHS), and Surface Transportation Program (STP). These workforce development activities cover surface transportation workers, including OJT/SS programs for women and minorities as authorized in 23 U.S.C. §140(b).

TrANS is an employment program originally established in 1995 in Southeastern Wisconsin. Currently TrANS has expanded to include TrANS program locations to serve contractors in Southeast (Milwaukee and surrounding counties), Southcentral (Dane County and surrounding counties including Rock County), and most Northeastern Wisconsin counties from locations in Keshena, Rhinelander and surrounding far Northern areas. TrANS attempts to meet contractor’s needs in other geographic locations as possible. It is an industry driven plan of services to address the outreach, preparation, placement and retention of women, minorities and non-minorities as laborers and apprentices in the highway skilled trades. These candidate preparation and contractor coordination services are provided by community based organizations. For a list of the TrANS Coordinators contact the Disadvantaged Business Enterprise Office at (414) 438-4583 in Milwaukee or (608) 266-6961 in Madison. These services are provided to you at no cost.

I. BASIC CONCEPTS

Training reimbursements to employing contractors for new placements, rehires or promotions to apprentice of TrANS Program graduates will be made as follows:

- 1) **On-the-Job Training, Item ASP.1T0G, ASP 1 Graduate.** At the rate of \$5.00 per hour on federal aid projects when TrANS graduates are initially hired, or seasonally rehired, as unskilled laborers or the equivalent.

Eligibility and Duration: To the employing contractor, for up to 2000 hours from the point of initial hire as a TrANS program placement.

Contract Goal: To maintain the intent of the Equal Employment Opportunity program, it is a goal that 12 (number) TrANS Graduate(s) be utilized on this contract.

- 2) **On-the-Job Training, Item ASP.1T0A, ASP 1 Apprentice.** At the rate of \$5.00 per hour on federal aid projects at the point when an employee who came out of the TrANS Program is subsequently entered into an apprenticeship contract in an underutilized skilled trade (this will include the Skilled Laborer Apprenticeship when that standard is implemented).

Eligibility and Duration: To the employing contractor, for the length of time the TrANS graduate is in apprentice status.

Contract Goal: To maintain the intent of the Equal Employment Opportunity program, it is a goal that 7 (number) TrANS Apprentice(s) be utilized on this contract.

- 3) The maximum duration of reimbursement is two years as a TrANS graduate plus time in apprentice status.
- 4) If a TrANS program is not available in the contractor's area and another training program is utilized, payment of On-the-Job Training hours may be approved by the Wisconsin Department of Transportation (WisDOT) if the training program meets the established acceptance criteria. Only On-the-Job Training Hours accumulated after WisDOT approval will be reimbursed as specified under Items ASP.1T0G and ASP.1T0A. For more information, contact the Disadvantaged Business Enterprise Office at the phone numbers listed above.
- 5) WisDOT reserves the right to deny payments under items ASP.1T0G and ASP.1T0A if the contractor either fails to provide training or there is evidence of a lack of good faith in meeting the requirements of this training special provision.

I. RATIONALE AND SPECIAL NOTE

The \$5.00 per hour now being paid for TrANS placements is intended to cover the duration of two years to allow for reaching entry-level laborer status. An additional incentive, the \$5.00 rate, would promote movement into the underutilized skilled trades' apprenticeships and applies until the individual completes their apprenticeship. These incentives benefit TrANS candidates by giving them a better opportunity to enter a skilled trade; benefits contractors who will be assisted in meeting their EEO profiles and goals; and benefits the public who will see the program reinforce larger public-private employment reform in Wisconsin. The pool of TrANS graduates was created for the purpose of addressing underutilization in the skilled trades, an objective that is further reinforced by a parallel retention pilot program, known as the Companywide Reporting. *Whether or not reimbursement is involved, the WisDOT reassures contractors who are in the Companywide Program that TrANS placements still contribute toward fulfilling the new hire goal of 50% women and minorities.* Based on data administered by United States Department of Labor (US DOL), the highway skilled trades remain underutilized for women statewide (less than 6.9%); and for minorities in all counties (% varies by county).

NOTE: *Unless using other advancement strategies, contractors are encouraged to use some or all of this monetary incentive to offset the cut in hourly wages an individual may incur when entering an apprenticeship if the full general laborer hourly rate has been previously paid. No special accounting measures are required.*

II. IMPLEMENTATION

The implementation of ASP 1 is intended to cover only the amount of time it takes for underutilization to be resolved across the trades. This will be measured annually at the county and/or state levels using data administered by WisDWD in relation to goals set by the USDOL-

OFCCP. With appropriate state and federal approvals, we may also do some measurement at the company level.

It is the contractor's responsibility to note on their Certified Payrolls if their employee is a TrANS graduate or a TrANS apprentice. The District EEO Coordinators utilize the information on the Certified Payrolls to track the hours accumulated by TrANS Graduates and TrANS apprentices on WisDOT contracts. Payment under this ASP 1 is made based on the hours recorded off of the Certified Payrolls. Tracking may eventually include improved linkages with the WisDWD apprentice database, information from company and committee level sources.

TrANS is nondiscriminatory by regulation, and is a tool for optional use by contractors to address the underutilization of women and minorities as laborers and apprentices in our industry's skilled trades.

IV. TRANS TRAINING

As part of the contractor's equal employment opportunity affirmative action program, training shall be provided to employees enrolled in apprenticeship and on-the-job training programs as follows:

The contractor shall provide on-the-job training aimed at developing full journey workers in the type of trade or job classifications involved. In the event the contractor subcontracts a portion of the contract work, the contractor shall determine how many, if any, of the trainees are to be trained by the subcontractor provided, however, that the contractor shall retain the primary responsibility for meeting the training requirements imposed by this special provision. The contractor shall also insure that this training special provision is made applicable to such subcontract.

Training and upgrading of minorities and women toward journey workers status is a primary objective of this training special provision. Accordingly, the contractor shall make every effort to enroll minority trainees and women (e.g., by conducting systematic and direct recruitment through public and private sources likely to yield minority trainees and women trainees); to the extent such persons are available within a reasonable area of recruitment. The contractor will be given an opportunity and will be responsible for demonstrating the steps that they have taken in pursuance thereof, prior to determination as to whether the contractor is in compliance with this training special provision. This training commitment is not intended, and shall not be used, to discriminate against any applicant for training, whether a member of a minority group or not.

No employee shall be employed as a trainee in any classification in which they have successfully completed a training course leading to journey workers status or in which they have been employed as a journey worker. The contractor should satisfy this requirement by including appropriate questions in the employee application or by other suitable means. Regardless of the method used, the contractor's records should document the findings in each case.

V. APPRENTICESHIP TRAINING

The Federal Highway Administration's (FHWA) policy is to require full use of all available training and skill improvement opportunities to assure increased participation of minority groups, disadvantaged persons and women in all phases of the highway construction industry. The FHWA On-the-Job Training (OJT) Program requires the State transportation agencies (STAs) to establish apprenticeships and training programs targeted to move women, minorities, and disadvantaged individuals into journey-level positions to ensure that a competent workforce is available to meet highway construction hiring needs, and to address the historical underrepresentation of members of these groups in highway construction skilled crafts.

The OJT Supportive Services (OJT/SS) Program was established in Title 23 Code of Federal Regulations (CFR), Part 230) to supplement the OJT program and support STA training programs by providing services to highway construction contractors and assistance to highway construction apprentices and trainees. The primary objectives of OJT/SS are:

- (1) To increase the overall effectiveness of the State highway agencies' approved training programs.
- (2) To seek other ways to increase the training opportunities for women, minorities, and disadvantaged individuals.

The STAs are responsible for establishing procedures, subject to the availability of Surface Transportation and Bridge Funds under 23 U.S.C. §140(b) (Nondiscrimination), for the provision of supportive services with respect to training programs approved under 23 CFR, Part 230(a) (Equal Employment Opportunity on Federal and Federal-aid Construction Contracts – including Supportive Services).

The contractor and subcontractor shall maintain records to demonstrate compliance with these apprenticeship requirements. Reasonable exemptions and modifications to and from any or all of these requirements will be determined by the Wisconsin Department of Transportation-Civil Rights Office. A request for an exemption or modification, with justification, shall be made in writing, addressed to WisDOT Civil Rights Office, 4802 Sheboygan Avenue, P.O. Box 7965, Rm. 451, Madison, WI 53707.

ADDITIONAL SPECIAL PROVISION 3

DISADVANTAGED BUSINESS ENTERPRISE [DBE] PROGRAM IMPLEMENTATION

1. Description

- a. The federal DBE program requirements outlined in the Code of Federal Regulations at 49 CFR Part 26 apply to this Wisconsin Department of Transportation contract. WisDOT is a recipient of federal funds and this contract includes federal funds. United States Department of Transportation Federal DBE Program requires the following provisions:
 - (1) Pursuant to the federal DBE program regulation at 49 CFR Part 26, a contractor's failure to comply with any provision of the DBE regulations will be considered a material breach of contract. This is non-negotiable. If a contractor fails to carry out the DBE program and Title VI nondiscrimination requirements of its contracts, the following sanctions will be assessed depending upon the facts, reasoning, severity and remedial efforts of the contractor: termination of contract, withholding payment, assessment of monetary sanctions, assessment of liquidated damages and/or suspension/debarment proceedings that may result in the disqualification of the contractor from bidding for a designated period of time.
 - (2) The contractor shall utilize the specific DBEs listed to perform the work and supply the materials for which each is listed unless the contractor obtains the federal fund recipient's [DOT] written consent. Unless [WisDOT] consent is provided, the contractor shall not be entitled to any payment for work or material unless it is performed or supplied by the listed DBE.
- b. The Wisconsin Department of Transportation [WisDOT] is committed to the compliant administration of the DBE Program. Each WisDOT Secretary affirms this commitment with his/her signed assurance.
<https://wisconsindot.gov/Documents/doing-bus/civil-rights/dbe/policy-statement.pdf>
 - (1) The department encourages the contractor to assist and develop DBE firms to become fully knowledgeable contractors to successfully perform on its contracts. Under the contract, the contractor agrees to provide the assistance to participating DBE's in the following areas:
 - i. Produce accurate and complete quotes.
 - ii. Understand highway plans applicable to their work.
 - iii. Understand specifications and contract requirements applicable to their work.
 - iv. Understand contracting reporting requirements.
 - (2) Wisconsin DOT identifies the assigned DBE goal in its contract advertisements and posts the contract DBE goal on the cover of the bidding proposal. The contractor can meet the assigned, specified contract DBE goal by subcontracting work to a DBE or by procuring services or materials from a DBE. The department calculates the DBE participation as the dollar value of DBE participation included in the bid expressed as a percentage of the total contract bid amount.
 - (3) For more comprehensive information on the disadvantaged business program, visit the department's Civil Rights and Compliance Section website at:
<https://wisconsindot.gov/Pages/doing-bus/civil-rights/dbe/default.aspx>

2. Definitions

Interpret these terms, used throughout this additional special provision, as follows:

- a. **Bid Percentage:** The DBE percentage indicated in the bidding proposal at the time of bid.
- b. **DBE:** A small business certified as disadvantaged business enterprise (DBE) under the federal DBE program and included on the Wisconsin UCP DBE Directory deemed ready, willing and able.
- c. **DBE goal:** The amount of DBE participation expected in the contract as shown on the cover of the Highway Work Proposal.
- d. **Manufacturer:** A firm that operates or maintains a factory or establishment that produces, on the premises, the materials, supplies, articles, or equipment required under the contract.
- e. **Supplier:** A firm that owns, operates, or maintains a store, warehouse, or other establishment in which the materials, supplies, articles or equipment required under the contract are bought, kept in stock, and regularly sold or leased to the public.
- f. **Voluntary Achievement:** The amount of DBE participation achieved and reported in the contract in excess of the assigned goal.

3. DBE Percentage Required at Bid Submission

Indicate the bid percentage (i.e. 0% through 100%) of DBE participation on the completed bidding proposal. For electronic submittals, show the percentage in the miscellaneous data folder, Item 3, DBE Percent. For paper submittals, show the percentage on the sheet included after the schedule of items. By submission of the bid, the bidder contractually commits to DBE participation at or above the bid percentage, or certifies that they have utilized comprehensive good faith efforts to solicit and utilize DBE firms to meet the DBE participation requirements of this contract proposal, and that the bid percentage is reflective of these good faith efforts. The bid percentage should demonstrate the efforts of the prime contractor prior to bid. If the bidder does not indicate the bid percentage of DBE participation on the completed bidding proposal, the department will consider the bid irregular and may reject the bid.

4. WisDOT Interpretation of Federal DBE Program Provision

Prime contractors must utilize the specific DBEs listed to perform the work and/or supply the materials for which each is listed on the Commitment to Subcontract to DBE Form [DT1506] and approved by WisDOT's DBE office to execute its contract. The approved Commitment to Subcontract to DBE Form [DT1506] becomes a contract document/record.

a. Department's DBE Evaluation Process

WisDOT evaluates DBE using the Commitment to Subcontract to DBE, payments to subcontractors and contract documentation. The prime contractor shall list the specific DBE certified firms and items of work s/he intends to use toward the fulfillment of the assigned DBE contract goal. The prime contractor receives DBE credit for payments made to the DBE firms performing the work listed on the approved Form DT1506.

b. Documentation Submittal

The contractor is to identify, by name, the DBE firms whose utilization is intended to satisfy this provision, the items of work of the DBE subcontract or supply agreement and the dollar value of those items of work by completing the Commitment to Subcontract to DBE Form [DT1506]. Effective January 1, 2017, the contractor will be required to submit the documentation within 5 business days after bid opening. All necessary supporting documentation including Attachment 'A' forms and/or Good Faith Efforts Form

[DT1202] must be submitted no later than 2 business days from contractor's initial submission of the DT 1506. The contractor must provide a signed Attachment 'A' form to the DBE office within the time limit in order to receive authorization for contract execution; the DBE office reserves the right accept alternate documentation in lieu of the signed form in extenuating circumstances. Documentation must be submitted to the DBE Office by email at DBE_Alert@dot.wi.gov (DBE_Alert@dot.wi.gov) or by postal mail ATTN: DBE Office, PO Box 7965, Madison, WI 53707-7965.

(1) **Bidder Meets DBE Goal**

If the bidder indicates that the contract DBE goal is met, after award and before execution, the department will evaluate the Commitment to Subcontract to DBE Form DT1506 and attachment A(s) to verify the actual DBE percentage calculation. If the DBE commitment is verified, the contract is eligible for execution with respect to the DBE commitment.

(2) **Bidder Does Not Meet DBE Goal**

- i. If the bidder indicates a bid percentage on the Commitment to Subcontract to DBE Form [DT1506] that does not meet the contract DBE goal, the bidder must submit a Good Faith Efforts Form [DT1202] and supporting documentation. After award and before execution, the department will evaluate the bidder's DBE commitment and consider the bidder's good faith efforts submission.
- ii. The department will evaluate the bidder's good faith effort request and notify the bidder of one of the following:
 - (a) If the department grants a good faith efforts, the bid is eligible for contract execution with respect to DBE commitment.
 - (b) If the department rejects the good faith efforts request, the department may declare the bid ineligible for execution. The department will provide a written explanation of why the good faith efforts request was rejected. The bidder may appeal the department's rejection as allowed under 7 a. & b.

c. **Bidder Fails to Submit Documentation**

If the contractor fails to furnish the Commitment to Subcontract to DBE Form [DT1506] within the specified time, the department may cancel the award. Delay in fulfilling this requirement is not a cause for extension of the contract time and shall not be used as a tool to delay execution.

5. Department's Criteria for Good Faith Effort

Appendix A of 49 CFR Part 26, is the guiding regulation concerning good faith efforts. However, the federal regulations do not explicitly define "good faith" but states that bidder must actively and aggressively attempt to meet the goal. The federal regulations are general and do not include every factor or effort that can be considered. As a result, each state must establish its own processes and consider the factors established in its own practices to create a process for making a determination of adequate good faith. WisDOT evaluates good faith on a contract basis just as each contract award is evaluated individually.

The department will only approve a contractor's good faith efforts if the bidder has made the effort, given the relevant circumstances under the contract that a bidder actively and aggressively seeking to meet the goal would make. The department will evaluate the bidder's good faith effort to determine whether a good faith efforts will be granted. The bidder must demonstrate, on the DT1202 that they have aggressively solicited DBE participation in an attempt to meet the contract DBE goal and attaining the stated DBE goal is not feasible.

- a. The department, in conjunction with industry stakeholders, has developed the following guidance for contractor good faith effort. The guidance and the attached appendices provide a framework for the actions required by all parties in the processing and evaluation of bidder's total efforts to achieve the project specific DBE goal prior to the bid letting date.

b. Prime Contractors should:

- (1) Document all efforts and decisions made toward achieving the DBE goal on the contract. The bidder should use the Civil Rights & Compliance System [CRCS] and related WisDOT- approved DBE outreach tools, including the Bid Express Small Business Network, to foster DBE participation on all applicable contracts.
- (2) Prime contractors may request assistance with DBE outreach and follow-up by contacting the department's DBE Support Services Office by phone or email request at least 14 days prior to the bid letting date. Requesting assistance with outreach is not a decisive factor in the review Good faith effort evaluation. Phone numbers are 414-438-4584 and/or 414-659-0487; Fax: 414-438-5392; E-mail: DOTDBESupportServices@dot.wi.gov.
- (3) Request quotes by identifying potential items to subcontract and solicit. Prime contractors are strongly encouraged to include in their initial contacts a single page including a detailed list of items for which they are accepting quotes, by project, within a letting. *See attached sample entitled "Sample Contractor Solicitation Letter" in Appendix A.* Prime contractors should also indicate a willingness to accept quotes in areas they are planning to perform themselves, as required by federal rules. In some cases, it might be appropriate to use DBE's to do work in a prime contractor's area of specialization.
 - i. Solicit quotes from certified DBE firms who match 'possible items to subcontract' using all reasonable and available means. Additionally, forward copies of solicitations highlighting the work areas for which you are seeking quotes to DOTDBESupportServices@dot.wi.gov.
 - ii. SBN is the preferred outreach tool. <https://www.bidx.com/wi/main>. Other acceptable means include postal mail, email, fax, phone call.
 - (a) Primes must ask DBE firms for a response in their solicitations. See *Sample Contractors Solicitation Letter* in Appendix. This letter can be included as an attachment to the SBN sub-quote request.
 - (b) Solicit quotes at least 10 calendar days prior to the letting date, at least two Fridays before the letting, to allow DBE firms sufficient time to respond. Prime contractors should contact DBE firms early, asking if they need help organizing their quote, assistance confirming equipment needs, or other assistance supporting their submission of a competitive quote for their services.
 - (c) Second solicitation should take place within 5 calendar days. Email and SBN are the preferred delivery of the follow-up solicitation.
 - iii. Upon request, provide interested DBE firms with adequate information about plans, specifications and the requirements of the contract by letter, information session, email, phone call and/or referral.
 - iv. When potential exists, the contractor should advise interested DBE firms on how to obtain bonding, line of credit or insurance if requested.
 - v. Document DBE firm's interest in quoting by taking appropriate steps to follow up initial solicitation with:
 - (a) Email to all prospective DBE firms in relevant work areas.
 - (b) Phone call log to DBE firms who express interest via written response or call.
 - (c) Fax/letter confirmation
 - (d) Signed copy of Bid Express SBN Record of Subcontractor Outreach Effort.

c. Evaluate DBE quotes Documentation is critical if a prime does not utilize the DBE firm's quote for any reason.

- (1) Evaluate DBE firm's capability to perform 'possible items to subcontract' using legitimate reasons, including but not limited to, **a discussion with the DBE firm** regarding its capabilities prior to the bid letting. If lack of capacity is your reason for not utilizing the DBE quote, you are required to contact the DBE by phone and email regarding their ability to perform the work indicated in the UCP directory listed as their work area by NAICS code. Only the work area and/or NAICS code listed in the UCP directory can be counted toward DBE credit. Documentation of the conversation is required.
- (2) In striving to meet an assigned DBE contract goal, prime contractors are expected to use DBE quotes that are responsive and reasonable. This includes DBE quotes that are not the low quote.

- (3) **Special Circumstance** - Evaluation of DBE quotes with tied bid items. "Tied quotes are the condition in which a subcontractor submits quotes including multiple areas of expertise across multiple work areas noting that the items and price are tied. Typically this type of quoting represents a cost saving to the prime but is not clearly stated as a discount; tied quotes are usually presented as 'all or none' quote to the prime." When non-DBE subcontractors submit tied bid items in their quotes to the prime, the DBE firms' quote may seem not competitive. In such a case, the following steps are taken in comparing the relevant quotes. These are qualitative examples.
- i. Compare bid items common to both quotes, noting the reasonableness in the price comparison.
 - ii. Review quotes from other firms for the bid items not quoted by the DBE firm to see if combining both can provide the same competitive advantage that the tied bid items offered.
- d. Immediately after notification of contract award, the prime submits all '**Commitment to Subcontract**' forms to the DBE Office. Prime contractor has 5 days to submit the completed form for the DBE firms it intends to use on the contract for DBE credit. If the goal is not met in full, the prime contractor must provide the following information along with WisDOT form DT1202: Certificate of Good Faith Efforts.
- (1) The names, addresses, e-mail addresses, telephone numbers of DBE's contacted. The dates of both initial and follow-up contact.
 - (2) A description of information provided to the DBE's regarding the plans, specifications, and estimated quantities for portions of the work to be performed by that DBE.
 - (3) Photocopies or electronic copies of all written solicitations to DBE's. A printed copy of SBN solicitation is acceptable.
 - (4) Documentation of each quote received from a DBE and, if rejected, the reason for that rejection.
 - (5) Bidder attendance at any pre-solicitation or pre-bid meetings the department held to inform DBE's of participation opportunities available on the project.

The prime contractor must obtain written consent from the DBE Office to change or replace any DBE firm listed on the approved Commitment to Subcontract to DBE Form [DT1506]. If the prime contractor utilizes another contractor, including the use of its own workforce, to perform the work assigned to a DBE on the approved DT1506, the prime contractor will not be entitled to payment for that work. Any changes to DBE after the approval of the DT1506 must be reviewed and approved by the DBE office prior to the change.

6. Use of Joint Checks

The use of joint checks is allowable if it is a commonly recognized business practice in the material industry. A joint check is defined as a two-party check between a DBE, a prime contractor and the regular dealer of materials supplier who is neither the prime nor an affiliate of the prime. Typically, the prime contractor issues one check as payor to the DBE subcontractor and to the supplier jointly (to guarantee payment to the supplier) as payment for the material/supplies used by the DBE in cases where the prime has submitted the DBE and material for DBE credit. The DBE subcontractor gains the opportunity to establish a direct contracting relationship with the supplier to potentially facilitate a business rapport that results in a line of credit or increased partnering opportunities.

The cost of material and supplies purchased by the DBE is part of the value of work performed by the DBE to be counted toward the goal. To receive credit, the DBE must be responsible for negotiating price, determining quality and quantity, ordering the materials, and installing (where applicable) and "paying for the material itself." See 49 CFR 26.55(c)(1).

The approval to use joint checks constitutes a commitment to provide further information to WisDOT, upon request by staff. WisDOT will allow the use of joint checks when the following conditions are met:

- a. The Prime must request permission to use joint checks from the DBE Office by submitting the Application to Use Joint Checks.
 - (1) Request should be made when the DBE Commitment form or Request to Sublet is submitted; the request will not be considered if submitted after the DBE Subcontractor starts its work.
 - (2) Approval/Permission must be granted prior to the issuance of any joint checks.
 - (3) The payment schedule for the supplier must be presented to the DBE office before the first check is issued.
 - (4) The joint check for supplies must be strictly for the cost of supplies.
- b. DBE subcontractor is responsible to furnish and/or install the material/work item. The DBE subcontractor shall not be an 'extra participant' in the transaction; the DBE's role in the transaction cannot be limited solely to signing the check(s) to release payment to the material supplier. At a minimum, the DBE subcontractor's tasks should include the following.
 - (1) The DBE subcontractor (not the prime/payor) negotiates the quantities, price and delivery of materials;
 - (2) The DBE subcontractor consents to sign/release the check to the supplier by signing the Application to Use Joint Checks after establishing the conditions and documentation of payment within the subcontract terms or in a separate written document.
- c. The Prime contractor/payor acts solely as a guarantor,
 - (1) The prime agrees to furnish the check used for the payment of materials/supplies under the contract.
 - (2) The prime contractor/payor cannot require the subcontractor to use a specific supplier or the prime contractors negotiated unit price.

7. Bidder's Appeal Process

- a. A bidder can appeal the department's decision to deny the bidder's good faith effort submission. The bidder must provide written documentation refuting the specific reasons for rejection as stated in the department's rejection notice. The bidder may meet in person with the department if so requested. Failure to appeal within 7 calendar days after receiving the department's written denial notice of a good faith effort evaluation constitutes a forfeiture of the bidder's right of appeal. A contract cannot be executed without documentation that the DBE provisions have been fulfilled.
- b. The department will appoint a representative, who did not participate in the original determination, to assess the bidder's appeal. The department will issue a written decision within 5 calendar days after the bidder presents all written and oral testimony. In that written decision, the department will explain the basis for finding that the bidder did or did not meet the contract DBE goal or make an adequate good faith effort to meet the contract DBE goal. The department's decision is final. If the department finds that the bidder did not meet the contract DBE goal or did not make adequate efforts to meet the DBE goal, the department may declare the bid ineligible for execution.

8. Department's Criteria for DBE Participation

Directory of DBE firms

- a. The only resource for DBE certified firms certified in the state of Wisconsin is the Wisconsin Unified Certification Program [UCP] DBE List. Wisconsin Department of Transportation maintains a current list of certified DBE firms titled Wisconsin UCP DBE Directory on the website at:
<https://wisconsin.gov/Documents/doing-business/civil-rights/dbe/dbe-ucp-directory.xlsx>
- b. The DBE office is also available to assist at 414-438-4583 or 608-267-3849.

9. Counting DBE Participation

Assessing DBE Work

- a. The department will only count the DBE usage towards the contract DBE goal if the DBE firm is certified as a DBE by one of the unified certification program agencies. If a firm becomes DBE certified before entering into a subcontract, the department may consider that DBE usage towards the contract goal. The department only counts the value of the work a DBE actually performs towards the DBE goal. The department assesses the DBE work as follows:
- b. The department counts work performed by the DBE's own resources. The department includes the cost of materials and supplies the DBE obtains for the work. The department also includes the cost of equipment the DBE leases for the work. The department will not include the cost of materials, supplies, or equipment the DBE purchases or leases from the prime contractor or its affiliate, except the department will count non-project specific leases the DBE has in place before the work is advertised.
- c. The department counts fees and commissions the DBE charges for providing a bona fide professional, technical, consultant, or managerial services. The department also counts fees and commissions the DBE charges for providing bonds or insurance. The department will only count costs the engineer deems reasonable based on experience or prevailing market rates.
- d. If a DBE subcontracts work, the department counts the value of the subcontracted work only if the DBE's subcontractor is also a DBE.
- e. The contractor shall maintain records and may be required to furnish periodic reports documenting its performance under this item.
- f. It is the prime contractor's responsibility to determine whether the work that is committed and/or contracted to a DBE certified firm can be counted for DBE credit by referencing the work type and NAICS code listed for the DBE firm on the Wisconsin UCP DBE Directory.
- g. It is the prime contractor's responsibility to assess the DBE firm's ability to perform the work for which s/he is committing/contracting the DBE to do. Note that the department encourages the prime contractor to assist and develop DBE firms to become fully knowledgeable contractors to successfully perform on its contracts.

10. Commercially Useful Function

- a. Commercially useful function is evaluated after the contract has been executed, while the DBE certified firm is performing its work items. A DBE performs a commercially useful function when it is responsible for execution of the work of the contract and is carrying out its responsibilities by actually performing, managing, and supervising the work involved.
- b. The department uses Form DT1011: DBE Commercially Useful Function Review and Certification to evaluate whether the DBE is performing a commercially useful function. WisDOT counts expenditures of a DBE toward the DBE goal only if the DBE is performing a commercially useful function on that contract.
- c. A DBE is performing a commercially useful function if the following conditions are met:
 - (1) For contract work, the DBE is responsible for executing a distinct portion of the contract work and it is carrying out its responsibilities by actually performing, managing, and supervising that work.
 - (2) For materials and supplies, the DBE is responsible for negotiating price, determining quality and quantity, ordering, and paying for those materials and supplies.

11. Credit Evaluation for Trucking

All bidders are expected to adhere to the department's current trucking policy posted on the HCCI website at <https://wisconsindot.gov/Documents/doing-bus/civil-rights/dbe/trucking-utilization-policy.pdf>

12. Credit Evaluation for Manufacturers, Suppliers, Brokers

The department will calculate the amount of DBE credit awarded to a prime using a DBE firm for the provisions of materials and supplies on a contract-by-contract basis. The department will count the material and supplies that a DBE provides under the contract for DBE credit based on whether the DBE is a manufacturer, supplier or broker. Generally, DBE crediting measures and evaluates the DBE owner's role, responsibility and contribution to the transaction: maximum DBE credit when the DBE manufactures materials or supplies; DBE credit decreases when the DBE solely supplies material and minimal credit is allotted when the DBE's role is administrative or transactional.

It is the bidder's responsibility to find out if the DBE is considered a supplier or a manufacturer before listing them on Commitment to Subcontract to DBE form DT1506.

a. Manufacturers

- (1) A manufacturer is a firm that operates or maintains a factory or establishment that produces, on the premises, the materials, supplies, articles, or equipment required under the contract and of the general character described by the specifications.
- (2) If the materials or supplies are obtained from a DBE manufacturer, count **100%** percent of the cost of the materials or supplies toward DBE goals.

b. Regular Dealers of Material and/or Supplies

- (1) A regular dealer is a firm that owns, operates, or maintains a store, warehouse, or other establishment in which the materials, supplies, articles or equipment of the general character described by the specifications and required under the contract are bought, kept in stock, and regularly sold or leased to the public in the usual course of business.
- (2) If the materials or supplies are purchased from a DBE regular dealer, count **60%** percent of the cost of the materials or supplies toward DBE goals.
- (3) At a minimum, a regular dealer must meet the following criteria to be counted for DBE credit:
 - i. The DBE firm must be an established, regular business that engages, as its principal business and under its own name, in the purchase and sale or lease of the products in question.
 - ii. The DBE firm must both own and operate distribution equipment for the product--bulk items such as petroleum products, steel, cement, gravel, stone, or asphalt. If some of the distribution equipment is leased, the lease agreement must accompany the DBE Commitment form for evaluation of the dealer's control before the DBE office approves the DBE credit.

c. Brokers, Transaction Expeditors, Packagers, Manufacturers Representatives

- (1) No portion of the cost of the materials, supplies, services themselves will count for DBE credit; however, WisDOT will evaluate the fees or commissions charged when a prime purchases materials, supplies or services from a DBE certified firm which is neither a manufacturer nor a regular dealer, namely: brokers, packagers, manufacturers' representatives or other persons who arrange or expedite transactions.
- (2) Brokerage fees have historically been calculated as **10%** of the purchase amount.
- (3) WisDOT may count the amount of fees or commissions charged for assistance in the procurement of the materials and supplies, or fees or transportation charges for the delivery of materials or supplies required on a job site.
- (4) The evaluation will review the contract need for the item/service, review the sub-contract or invoice for the item/service, compare the fees customarily allowed for similar services to determine whether they are reasonable.

When DBE suppliers are contracted, additional documentation must accompany the DT1506 and Attachment 'A' forms. An invoice or bill-of-sale that includes the company names of the bidder and the DBE supplier and documentation of the calculations used as the basis for the purchase agreement, subcontract or invoice.

WisDOT recognizes that the amount on the Attachment 'A' form may be more or less than the amount on the invoice. Please respond to the following questions and submit with your DBE Commitment Form.

1. What is the product or material?
2. Is this item in the prime's inventory or was the item purchased when contract was awarded?
3. Which contract line items were referenced to develop this quote?
4. What is the amount of material or product used on the project?

13. Credit Evaluation for DBE Primes

Wisconsin DOT calculates DBE credit based on the amount and type of work performed by DBE certified firms. If the prime contractor is a DBE certified firm, the department will only count the work that DBE prime contractor performs with its own forces for DBE credit. We will also calculate DBE credit for the work performed by any other DBE certified subcontractor, DBE certified supplier, DBE certified manufacturer on that contract in that DBE's approved work areas/NAICS code. Crediting for manufacturers and suppliers is calculated consistent with paragraph 12 of this document and 49 CFR Part 26.

14. Joint Venture

If a DBE performs as a participant in a joint venture, the department will only count that portion of the total dollar value of the contract equal to that portion of the work that the DBE performs with its own forces for DBE credit.

15. Mentor Protégé

- a. If a DBE performs as a participant in a mentor protégé agreement, the department will count for credit the portion of the work performed by the DBE protégé firm.
- b. DBE credit will be evaluated and confirmed by the DBE Office for any contracts on which the mentor protégé team identifies itself to the DBE Office as a current participant of the Mentor Protégé Program.
- c. Refer to WisDOT's Mentor Protégé guidelines for guidance on the number of contracts and amount of DBE credit that can be counted on any WisDOT project.

16. DBE Replacement or Termination

Contractual Requirement

The contractor shall utilize the specific DBEs listed to perform the work and supply the materials for which each is listed unless the contractor obtains written consent from the Department's DBE Office. If the Department does not provide consent to replace or terminate a DBE firm, the prime contractor shall not be entitled to any payment for work or material unless it is performed or supplied by the listed DBE.

Contractor Considerations

- a. A prime contractor cannot terminate and/or replace a DBE subcontractor listed on the approved Commitment to Subcontract to DBE Form [DT1506] without prior written consent from the DBE Office. This includes, but is not limited to, instances in which a prime contractor seeks to perform work originally designated for a DBE subcontractor with its own forces or those of an affiliate, a non-DBE firm, or with another DBE firm.

- b. If a prime contractor feels it is necessary to replace or terminate a DBE firm that has been approved for DBE credit toward its contract, s/he will be required to provide reasons and documentation to support why the prime cannot fulfill the contractual commitment that it made to the Department regarding the DBE utilization.
- c. Prime contractor is required to make affirmative efforts to find another DBE subcontractor to perform at least the same amount of work under the contract as the DBE that was terminated, to the extent needed to meet the assigned DBE contract goal.
- d. In circumstances when a DBE subcontractor fails to complete its work on the contract for any reason or is terminated from a contract, the prime contractor is expected to make affirmative efforts to maintain its commitment to the assigned DBE goal.
- e. The DBE firm should communicate with the prime contractor regarding its schedule and capacity in the context of the contract. If the DBE anticipates that it cannot fulfill its subcontract, s/he shall advise the prime contractor and suggest a DBE that may replace their services or provide written consent to be released from its subcontract.
 - (1) Before the prime contractor can request to terminate or substitute a DBE firm; s/he must:
 - i. Make every effort to fulfill the DBE commitment by working with the listed DBE to ensure that they are fully knowledgeable of your expectations for successful performance on the contract. Document these efforts in writing.
 - ii. If those efforts fail, provide written notice to the DBE subcontractor of your *intent* to request to terminate and/or replace the firm including the reason(s) you want to pursue this action.
 - iii. Copy the DBE Office on all correspondence related to changing a DBE firm who has been approved for DBE credit on a contract including the preparation and coordination efforts with the DBE on the contract.
 - iv. Clearly state the amount of time the DBE firm has to remedy and/or respond to your notice of intent to replace/terminate their firm from the contract. The DBE shall be allowed five days to respond, in writing. **EXCEPTION:** The prime contractor must provide a verifiable reason for a response period shorter than five days. For example a WisDOT project manager must verify that waiting 5 days for a DBE performing traffic control work to respond would affect the public safety.
 - v. The DBE subcontractor must forward a written response to the prime contractor and copy the DBE Office. The written response must outline why it objects to the proposed termination of its subcontract and list the reasons that WisDOT should not approve the request for their firm to be replaced or removed from the contract.

The Request to Replace or Terminate a DBE

The prime contractor must provide a written request to replace or terminate a DBE firm that has been approved for DBE credit on a WisDOT contract. The written request can be an email or printed document delivered by email or fax; at minimum, the request must contain the following:

1. Contract ID number.
2. Wisconsin DOT Contract Project Manager name and contact information.
3. DBE name and work type and/or NAICS code.
4. Contract's progress schedule.
5. Reason(s) for requesting that the DBE be replaced or terminated.
6. Attach/include all communication with the DBE to deploy/address/resolve work completion,

WisDOT will review your request and any supporting documentation that you submit to evaluate whether the circumstance and the reasons constitute a good cause for replacing or terminating the DBE that was approved for DBE credit on that contract.

Examples of Good Causes to Replace a DBE according to the federal DBE program guidelines {49 CFR part 26.53}

- The listed DBE subcontractor fails or refuses to execute a written contract.
- The listed DBE subcontractor fails or refuses to perform the work of its subcontract in a way consistent with normal industry standards. Provided, however, that good cause does not exist if the failure or refusal of the DBE subcontractor to perform its work on the subcontract results from the bad faith or discriminatory action of the prime contractor.
- The listed DBE subcontractor fails or refuses to meet the prime contractor's reasonable, nondiscriminatory bond requirements.
- The listed DBE subcontractor becomes bankrupt, insolvent, or exhibits credit unworthiness.
- The listed DBE subcontractor is ineligible to work on public works projects because of suspension and debarment proceedings pursuant 2 CFR Parts 180, 215 and 1,200 or applicable state law.
- You have determined that the listed DBE subcontractor is not a responsible contractor.
- The listed DBE subcontractor voluntarily withdraws from the project and provides to you written notice of its withdrawal.
- The listed DBE is ineligible to receive DBE credit for the type of work required.
- A DBE owner dies or becomes disabled with the result that the listed DBE contractor is unable to complete its work on the contract.

Evaluation and Response to the Request

If WisDOT determines that your reasons comply with the good cause standards; the DBE office will send the prime contractor and the WisDOT project manager an email stating that we concur with the reasons and approve the replacement or termination.

If WisDOT determines that your reasons do not comply with the good cause standards of the federal DBE program, the DBE Office will send the prime contractor an email that includes *the requirement* to utilize the committed DBE, *remedial actions* to support the completion of the contractual commitment, a list of available WisDOT support services *and administrative remedies that may be invoked* for failure to comply with federal DBE guidelines for DBE replacement.

The Wisconsin Department of transportation contact for all actions related to replacing a DBE is the DBE Program Chief and/or the DBE Program Engineer which can be reached at DBE_Alert@dot.wi.gov or by calling 608-267-3849.

17. DBE Utilization beyond the approved DBE Commitment Form DT1506

If the Prime/subcontractor increases the scope of work for a participating DBE or adds a DBE subcontractor that was not on the approved Form DT1506 at any time after contract award, s/he should follow these steps so that the participation can be accurately credited toward the DBE goal.

- a. Send an email to the DBE Engineer at DBE_Alert@dot.wi.gov describing the work to be performed by the new DBE including the proposed schedule or duration, DBE name and contact information. You may also call the DBE Engineer at 414-659-0487 to notify him of the change verbally.

If the scope change added work for a participating DBE; list the date and reason for the scope change.

- b. Forward a complete, signed Attachment 'A' form to the DBE Office at DBE_Alert@dot.wi.gov. A complete Attachment A includes DBE contact information, signature, subcontract value and proper description of the work areas to be performed by the DBE.

The DBE office will confirm the DBE participation and revise the DT1506 based on the email/discussion and attach the new/revised Attachment A to the Contract record/documentation.

18. Contract Modifications

When additional opportunity is available by contract modifications, the Prime Contractor shall utilize DBE Subcontractors that were committed to equal work items, in the original contract.

19. Payment

Costs for conforming to this Additional Special Provision (ASP) and any associated DBE requirements are incidental to the contract.

APPENDIX A

Sample Contractor Solicitation Letter Page 1

This sample is provided as a guide not a requirement

GFW SAMPLE MEMORANDUM

TO: DBE FIRMS
 FROM: POTENTIAL PRIME CONTRACTOR OR MAJOR SUBCONTRACTOR
 SUBJECT: REQUEST FOR DBE QUOTES
 LET DATE & TIME
 DATE: MONTH DAY YEAR
 CC: DBE OFFICE ENGINEER

Our company is considering bidding on the projects indicated on the next page, as a prime and/or a subcontractor for the Wisconsin Department of Transportation Month- date -year Letting. Page 2 lists the projects and work items that we may subcontract for this letting. We are interested in obtaining subcontractor quotes for these projects and work categories. Also note that we are willing to accept quotes in areas we may be planning to perform ourselves as required by federal rules.

Please review page 2, respond whether you plan to quote, highlight the projects and work items you are interested in performing and return it via fax or email within 3 days. Plans, specifications and addenda are available through WisDOT at the DBE Support Services office or at the Highway Construction Contract Information (HCCI) site at <https://wisconsindot.gov/Pages/doing-bus/contractors/hcci/default.aspx>

Your quote should include all of the costs required to complete the items you propose to perform including labor, equipment, material, and related bonding or insurance. The quote should note items that you are DBE certified to perform, tied items, and any special terms. Page 2, with the indicated projects and items you plan to quote, should be used as a cover sheet for your quote.

Please make every effort to have your quotes into our office by time deadline the prior to the letting date. **Make sure the correct letting date, project ID and proposal number, unit price and extension are included in your quote.** We prefer quotes be sent via SBN but prime's alternatives are acceptable. Our office hours are include hours and days. Please call our office as soon as possible prior to the letting if you need information/clarification to prepare your quote at contact number.

If you wish to discuss or evaluate your quote in more detail, contact us after the contract is awarded. Status of the contract can be checked at WisDOT's HCCI site at <https://wisconsindot.gov/Pages/doing-bus/contractors/hcci/default.aspx>

All questions should be directed to:

Project Manager, John Doe,

Phone: (000) 123-4567

Email: Joe@joetheplumber.com

Fax: (000) 123- 4657

Sample Contractor Solicitation Letter Page 2

This sample is provided as a guide not a requirement

REQUEST FOR QUOTATION

Prime's Name: _____
 Letting Date: _____
 Project ID: _____

Please check all that apply

- “ Yes, we will be quoting on the projects and items listed below
- “ No, we are not interested in quoting on the letting or its items referenced below
- “ Please take our name off your monthly DBE contact list
- “ We have questions about quoting this letting. Please have someone contact me at this number

Prime Contractor 's Contact Person

 Phone: _____
 Fax: _____
 Email: _____

DBE Contractor Contact Person

 Phone _____
 Fax _____
 Email _____

Please circle the jobs and items you will be quoting below

Proposal No.	1	2	3	4	5	6	7
County							

WORK DESCRIPTION:

Clear and Grub	X		X	X		X	X
Dump Truck Hauling	X		X	X		X	X
Curb & Gutter/Sidewalk, Etc.	X		X	X		X	X
Erosion Control Items	X		X	X		X	X
Signs and Posts/Markers	X		X	X		X	X
Traffic Control		X	X	X		X	X
Electrical Work/Traffic Signals		X	X	X		X	
Pavement Marking		X	X	X	X	X	X
Sawing Pavement		X	X	X	X	X	X
QMP, Base	X	X		X	X	X	X
Pipe Underdrain	X			X			
Beam Guard				X	X	X	X
Concrete Staining							X
Trees/Shrubs	X						X

Again please make every effort to have your quotes into our office by time deadline prior to the letting date.

We prefer quotes be sent via SBN but prime's preferred alternatives are acceptable.

If there are further questions please direct them to the prime contractor's contact person at phone number.

APPENDIX B

BEST PRACTICES FOR PRIME CONTRACTOR & DBE SUBCONTRACTOR GOOD FAITH EFFORT

This list is not a set of requirements; it is a list of potential strategies

Primes

- Ø Prime contractor open houses inviting DBE firms to see the bid “war room” or providing technical assistance.
- Ø Participate in speed networking and mosaic exercises as arranged by DBE office.
- Ø Host information sessions not directly associated with a bid letting.
- Ø Participate in a formal mentor protégé or joint venture with a DBE firm.
- Ø Participate in WisDOT advisory committees i.e. TRANSAC, or Mega Project committee meetings.
- Ø Facilitate a small group DBE ‘training session’ Clarifying how your firm prepares for bid letting, evaluates subcontractors, preferred qualifications and communication methods.
- Ø Encourage subcontractors to solicit and highlight DBE participation in their quotes to you.
- Ø Quality of communication, not quantity creates the best results. Contractors should do as thorough a job as possible in communicating with DBE firms before the bid and provide any assistance requested to assure best possible bid.

DBE

- Ø DBE firms should contact primes as soon as possible with questions regarding their quotes or bid; seven days prior is optimal.
- Ø Continually check for contract addendums on the HCCI website through the Thursday prior to letting to stay abreast of changes.
- Ø Review the status of contracts on the HCCI website reviewing the ‘apparent low bidder’ list, and bid tabs at a minimum.
- Ø Prepare a portfolio or list of related projects and prime and supplier references; be sure to note transportation-related projects of similar size and scope, firm expertise and staffing.
- Ø Participate in DBE office assessment programs.
- Ø Participate on advisory and mega-project committees.
- Ø Sign up to receive the DBE Contracting Update.
- Ø Consider membership in relevant industry or contractor organizations.
- Ø Active participation is a must. Quote as many projects as you can reasonably work on; quoting the primes and bidding as a prime with the department are the only ways to get work.

APPENDIX C

Types of Efforts considered in determining GFE

This list represents concepts being assessed; analysis requires additional steps

1. Whether the contractor attended any pre-solicitation or pre-bid meetings that were scheduled by WisDOT to inform DBEs of contracting and subcontracting opportunities.
2. Whether the contractor provided written notice to a reasonable number of specific DBEs that their interest in the contract was being solicited, in sufficient time to allow the DBEs to participate effectively.
3. Whether the contractor followed up initial solicitations of interest by contacting DBEs to determine if the DBEs were interested; returned the phone calls of interested DBE firms.
4. Whether the contractor selected portions of the work to be performed by DBEs in order to increase the likelihood of meeting the DBE goal.
5. Whether the contractor provided interested DBEs with adequate information about the plans, specifications and requirements of the contract.
6. Whether the contractor negotiated in good faith with interested DBEs, not rejected DBEs as unqualified without sound reasons based on a thorough investigation of their capabilities.
7. Whether the contractor made efforts to assist interested DBEs in being more competitive.
8. Whether the contractor effectively used the services of available minority community organizations: minority contractors groups, local, state, and Federal minority business assistance offices, and other organizations that provide assistance to small businesses and DBE firms.
9. Whether Prime used CRCS to identify DBE who specialize in relevant work areas.
10. Whether the contractor used available resources including contacting the DBE office, using WisDOT's website
11. Whether the contractor returned calls of firms expressing interest in a timely manner.

APPENDIX D
Good Faith Effort Evaluation Guidance
Excerpt from Appendix A of 49 CFR Part 26

APPENDIX A TO PART 26 -- GUIDANCE CONCERNING GOOD FAITH EFFORTS

- I. When, as a recipient, you establish a contract goal on a DOT assisted contract, a bidder must, in order to be responsible and/or responsive, make good faith efforts to meet the goal. The bidder can meet this requirement in either of two ways. First, the bidder can meet the goal, documenting commitments for participation by DBE firms sufficient for this purpose. Second, even if it doesn't meet the goal, the bidder can document adequate good faith efforts. This means that the bidder must show that it took all necessary and reasonable steps to achieve a DBE goal or other requirement of this part which, by their scope, intensity, and appropriateness to the objective, could reasonably be expected to obtain sufficient DBE participation, even if they were not fully successful.
- II. In any situation in which you have established a contract goal, part 26 requires you to use the good faith efforts mechanism of this part. As a recipient, it is up to you to make a fair and reasonable judgment whether a bidder that did not meet the goal made adequate good faith efforts. It is important for you to consider the quality, quantity, and intensity of the different kinds of efforts that the bidder has made. The efforts employed by the bidder should be those that one could reasonably expect a bidder to take if the bidder were actively and aggressively trying to obtain DBE participation sufficient to meet the DBE contract goal. Mere pro forma efforts are not good faith efforts to meet the DBE contract requirements. We emphasize, however, that your determination concerning the sufficiency of the firm's good faith efforts is a judgment call: meeting quantitative formulas is not required.
- III. The Department also strongly cautions you against requiring that a bidder meet a contract goal (i.e., obtain a specified amount of DBE participation) in order to be awarded a contract, even though the bidder makes an adequate good faith efforts showing. This rule specifically prohibits you from ignoring bona fide good faith efforts.
- IV. The following is a list of types of actions which you should consider as part of the bidder's good faith efforts to obtain DBE participation. It is not intended to be a mandatory checklist, nor is it intended to be exclusive or exhaustive. Other factors or types of efforts may be relevant in appropriate cases.
 - A. Soliciting through all reasonable and available means (e.g. attendance at pre-bid meetings, advertising and/or written notices) the interest of all certified DBEs who have the capability to perform the work of the contract. The bidder must solicit this interest within sufficient time to allow the DBEs to respond to the solicitation. The bidder must determine with certainty if the DBEs are interested by taking appropriate steps to follow up initial solicitations.
 - B. Selecting portions of the work to be performed by DBEs in order to increase the likelihood that the DBE goals will be achieved. This includes, where appropriate, breaking out contract work items into economically feasible units to facilitate DBE participation, even when the prime contractor might otherwise prefer to perform these work items with its own forces.
 - C. Providing interested DBEs with adequate information about the plans, specifications, and requirements of the contract in a timely manner to assist them in responding to a solicitation.
 - D.
 - (1) Negotiating in good faith with interested DBEs. It is the bidder's responsibility to make a portion of the work available to DBE subcontractors and suppliers and to select those portions of the work or material needs consistent with the available DBE subcontractors and suppliers, so as to facilitate DBE participation. Evidence of such negotiation includes the names, addresses, and telephone numbers of DBEs that were considered; a description of the information provided regarding the plans and specifications for the work selected for subcontracting; and evidence as to why additional agreements could not be reached for DBEs to perform the work.
 - (2) A bidder using good business judgment would consider a number of factors in negotiating with subcontractors, including DBE subcontractors, and would take a firm's price and capabilities as well as contract goals into consideration. However, the fact that there may be some additional costs involved in finding and using DBEs is not in itself sufficient reason for a bidder's failure to meet the contract DBE goal, as long as such costs are reasonable. Also, the ability or desire of a prime contractor to perform the work of a

contract with its own organization does not relieve the bidder of the responsibility to make good faith efforts. Prime contractors are not, however, required to accept higher quotes from DBEs if the price difference is excessive or unreasonable.

- E. Not rejecting DBEs as being unqualified without sound reasons based on a thorough investigation of their capabilities. The contractor's standing within its industry, membership in specific groups, organizations, or associations and political or social affiliations (for example union vs. non-union employee status) are not legitimate causes for the rejection or non solicitation of bids in the contractor's efforts to meet the project goal.
 - F. Making efforts to assist interested DBEs in obtaining bonding, lines of credit, or insurance as required by the recipient or contractor.
 - G. Making efforts to assist interested DBEs in obtaining necessary equipment, supplies, materials, or related assistance or services.
 - H. Effectively using the services of available minority/women community organizations; minority/women contractors' groups; local, state, and Federal minority/women business assistance offices; and other organizations as allowed on a case-by-case basis to provide assistance in the recruitment and placement of DBEs.
- V. In determining whether a bidder has made good faith efforts, you may take into account the performance of other bidders in meeting the contract. For example, when the apparent successful bidder fails to meet the contract goal, but others meet it, you may reasonably raise the question of whether, with additional reasonable efforts, the apparent successful bidder could have met the goal. If the apparent successful bidder fails to meet the goal, but meets or exceeds the average DBE participation obtained by other bidders, you may view this, in conjunction with other factors, as evidence of the apparent successful bidder having made good faith efforts.

Appendix E

Small Business Network [SBN] Overview

The Small Business Network is a part of the Bid Express® service that was created to ensure that prime bidders have a centralized online location to find subs - including small and disadvantaged business enterprises (DBEs). It is available for prime bidders to use as part of their Basic Service subscription.

Within the Small Business Network, Prime Contractors can:

1. Easily select proposals, work types and items:
 - a. After adding applicable work types, select items that you wish to quote. Enter the sub-quote quantities and add comments, if desired. Adding or removing items and work types can be done quickly. If needed, you can save the sub-quote for completion at a later time.
2. Create sub-quotes for the subcontracting community:
 - a. Create sub-quotes with ease using the intuitive sub-quote creator. In seven short steps, you can rapidly create a custom sub-quote directed to all subcontractors that bid on the applicable work types. Steps include: provide contact information and sub-quote expiration date, select letting and proposal, add work types and items, specify terms and conditions, upload attachments, and select vendors.
 - b. Create a sub-quote to send to subcontractors or suppliers that lists the items in a proposal that you want quoted
 - c. Create an unlimited number of sub-quotes for items you want quoted, and optionally mark them as a DBE-preferred request.
 - d. Add attachments to sub-quotes.
3. View sub-quote requests & responses:
 - a. After logging into the Bid Express service, you can quickly review all of your sub-quote requests and all unsolicited sub-quote requests from subcontractors. To simplify the Small Business Network home screen, sub-quote requests can be hidden with one click if they are not applicable.
 - b. View or receive unsolicited sub-quotes that subcontractors have posted, complete with terms, conditions and pricing.
4. View Record of Subcontractor Outreach Effort:
 - a. For each sub-quote produced, a *Record of Subcontractor Outreach Effort* is generated that shows the response statistics for a particular sub-quote. If accepted by the letting agency, this report may serve as proof of a “Good Faith” effort in reaching out to the DBE community.
 - b. Easily locate pre-qualified and certified small and disadvantaged businesses.
 - c. Advertise to small and disadvantaged businesses more efficiently and cost effectively.
 - d. Document your interactions with subs/DBEs by producing an Outreach Report (may be accepted as proof of DBE outreach at the discretion of each agency).

The Small Business Network is a part of the Bid Express® service that was created to ensure that small businesses have a centralized area to access information about upcoming projects. It can help small businesses learn more about opportunities, compete more effectively, network with other contractors and subcontractors, and win more jobs.

1. View and reply to sub-quote requests from primes:
 - a. After logging into the Bid Express service, you can quickly review all incoming sub-quote requests and all unsolicited sub-quotes created by your company. Receive notifications by selected work type. To simplify on the Small Business Network home screen, sub-quote requests can be filtered by work types relevant to your interests, or hidden with one click if they are not applicable.
2. Select items when responding to sub-quote requests from primes:
 - a. You have the freedom to choose and price any number of items when responding to a sub-quote request. Quantities can be modified, and per-item comments are also available.
 - b. View requests for sub-quotes for work that primes have posted for projects they are bidding, add your pricing, terms, and conditions, and submit completed sub-quotes to the requesting primes.
 - c. Add attachments to a sub-quote.
3. Create and send unsolicited sub-quotes to specific contractors:
 - a. Create unsolicited sub-quotes with ease using the intuitive sub-quote creator. In eight short steps, you can rapidly create a custom sub-quote directed at any number of specific vendors of your choosing. Steps include: provide contact information and sub-quote expiration date, select letting and proposal, add work types and items, specify terms and conditions, upload attachments, and select vendors.
4. Easily select and price items for unsolicited sub-quotes:
 - a. After adding applicable work types, select items that you wish to quote. The extended price calculates automatically, cutting out costly calculation errors. Comments can be provided on a per-item basis as well.
 - b. Create an unsolicited sub-quote that lists the items from a proposal that you want to quote, include pricing, terms and conditions, and send it to selected prime/plan holder.
 - c. Add attachments to a sub-quote.
 - d. Add unsolicited work items to sub-quotes that you are responding to.
5. Easy Access to Valuable Information
 - a. Receive a confirmation that your sub-quote was opened by a prime.
 - b. View Bid Tab Analysis data from past bids, including the high, average and low prices of items.
 - c. View important notices and publications from DOT targeted to small and disadvantaged businesses.
6. Accessing Small Business Network for WisDOT contracting opportunities
 - a. If you are a contractor not yet subscribing to the Bid Express service, go to www.bidx.com and select "Order Bid Express." The Small Business Network is a part of the Bid Express Basic Service.
 - b. DBE firms can request a Bid Express Small Business Network Account at no cost by calling 414-438-4588.

ADDITIONAL SPECIAL PROVISION 4

Payment to First-Tier Subcontractors

Within 10 calendar days of receiving a progress payment for work completed by a subcontractor, pay the subcontractor for that work. The prime contractor may withhold payment to a subcontractor if, within 10 calendar days of receipt of that progress payment, the prime contractor provides written notification to the subcontractor and the department documenting "just cause" for withholding payment.

The prime contractor may also withhold routine retainage from payments due subcontractors.

Payment to Lower-Tier Subcontractors

Ensure that subcontracting agreements at all tiers provide prompt payment rights to lower-tier subcontractors that parallel those granted first-tier subcontractors in this provision.

Release of Routine Retainage

After granting substantial completion the department may reduce the routine retainage withheld from the prime contractor to 75 percent of the original total amount retained.

When the Department sends the semi-final estimate the department may reduce the routine retainage withheld from the prime contractor to 10 percent of the original total amount retained.

Within 30 calendar days of receiving the semi-final estimate from the department, submit written certification that subcontractors at all tiers are paid in full for acceptably completed work and that no routine retainage is being withheld. The department will pay the prime contractor in full and reduce the routine retainage withheld from the prime contractor to zero when the department approves the final estimate.

This special provision does not limit the right of the department, prime contractor, or subcontractors at any tier to withhold payment for work not acceptably completed or work subject to an unresolved contract dispute.

ADDITIONAL SPECIAL PROVISION 6**ASP 6 - Modifications to the standard specifications**

Make the following revisions to the standard specifications:

107.17.1 General

Replace paragraph seven with the following effective with the December 2018 letting:

- (7) Have a professional engineer registered in the state of Wisconsin sign and seal the shop drawings. At least 30 calendar days before starting falsework, form, or shoring construction; submit a PDF file of shop drawings to the railroad's chief engineering officer and to the engineer. The engineer and the railroad may review the shop drawings. If the engineer or the railroad finds the shop drawings unsatisfactory, the contractor shall make the required changes. A satisfactory shop drawing review does not relieve the contractor of responsibility and liability for the structural integrity and proper functioning of the falsework, forms, or shoring.
-

109.1.1 General

Replace the entire text with the following effective with the January 2019 letting:

- (1) The engineer will use the US standard system to measure all work completed under the contract. The engineer will determine quantities of materials the contractor furnishes and work the contractor performs using measurement methods and computations conforming to standard engineering practice, modified to meet department requirements. The engineer will document these measurements using department procedures.
 - (2) The engineer will measure the work as the contract measurement subsection for individual items specifies. The department will measure the actual quantities of work the contractor acceptably completes and make final payment based on those actual measured quantities except as follows:
 1. If the measurement subsection for a bid item specifically restricts the quantity measured for payment or allows for use of conversion factors.
 2. If the engineer executes a contract change order modifying the method of measurement for specific bid items, the engineer will measure the quantities of applicable bid items for payment using the change order methods.
 3. If the engineer, under 105.3.1(2), approves a contractor-requested plan dimension change between US standard and SI metric dimensions, the engineer will measure whichever of the following is less:
 - Actual quantities constructed.
 - Quantities derived from the original plan dimensions.
 4. For substitutions made under 106.2.3 between US standard and SI metric products, the engineer will measure the actual quantities of the substitute products using the original contract measuring system.
-

305.2.1 General

Replace paragraph two with the following effective with the December 2018 letting:

- (2) Where the contract specifies or allows 1 1/4-inch base, do not place reclaimed asphalt, reprocessed material, or blended materials below virgin aggregate materials unless the contract specifies or the engineer allows in writing. The department will allow virgin aggregate above reclaimed asphalt, reprocessed material, or blended materials in shoulder areas adjacent to concrete pavement.
-

420.3.2.1 General

Replace paragraph one with the following effective with the December 2018 letting:

- (1) Use self-propelled grinding machines with depth, grade, and slope controls designed for grinding and texturing concrete. Equip grinding machines with diamond blades and a vacuuming system capable of removing liquid and solid residue from the ground surface. Shroud the machine to prevent discharging loosened material into adjacent work areas or live traffic lanes. Provide the specified effective wheelbase, defined as the center of the front to center of the rear main support wheels.

420.3.2.2 Continuous Grinding

Replace paragraph one with the following effective with the December 2018 letting:

- (1) Under the Continuous Diamond Grinding Concrete Pavement bid item, ensure that the grinding machine, including the grinding head, weighs 35,000 pounds or more, will grind a strip at least 4 feet wide, and has an effective wheel base of 25 feet or more. For pavements with a design speed less than 40 miles per hour and areas difficult to access, the contractor may use equipment with an effective wheel base of 12 feet or more.
-

450.3.2.8 Jointing

Replace paragraphs three through five with the following effective with the December 2018 letting:

- (3) Construct notched wedge longitudinal joints for mainline paving if the pavement thickness conforms to the minimums specified in 460.3.2, unless the engineer directs or allows an alternate joint. Construct the wedge using a slope no steeper than 3:1. Extend the wedge 12 inches beyond the normal lane width, or as the engineer directs. Ensure that the wedge for all layers directly overlaps and slopes in the same direction.
 - (4) Locate the joint at the pavement centerline for 2-lane roadways, or at lane lines if the roadway has more than 2 lanes. Construct a vertical notch 1/2-inch to 3/4-inch high on the centerline or lane line at the top of each wedge. Place a 1/2-inch to 3/4-inch notch at the outside bottom edge of the wedge after compacting each layer. Align the finished longitudinal joint line of the upper layer with the centerline or lane line.
 - (5) Construct the wedge for each layer using an engineer-approved strike-off device that will provide a uniform slope and will not restrict the main screed. Shape and compact the wedge with a weighted steel side roller wheel the same width as the wedge. Apply a tack coat to the wedge surface and both notches before placing the adjacent lane.
-

455.2.4.3 Emulsified Asphalts

Replace paragraph two with the following effective with the December 2018 letting:

- (2) The bill of lading for emulsified asphalts shall indicate the asphalt content of the original emulsion and dilution rate of the additional water added to the original emulsion. If undiluted samples are not available, test the diluted material and modify AASHTO M140, M208, or M316 to reflect properties resulting from dilution of the asphalt.
-

460.2.8.3.1.4 Department Verification Testing Requirements

Replace paragraph three with the following effective with the December 2018 letting:

- (3) The department will perform testing conforming to the following standards:
 - Bulk specific gravity (G_{mb}) of the compacted mixture according to AASHTO T166.
 - Maximum specific gravity (G_{mm}) according to AASHTO T209.
 - Air voids (V_a) by calculation according to AASHTO T269.
 - VMA by calculation according to AASHTO R35.
 - Asphalt content by ignition oven according to AASHTO T308 as modified in CMM 8-36.6.3.6, chemical extraction according to AASHTO T-164, or Asphalt Analyzer™ according to manufacturer recommendations.
-

460.2.8.3.1.6 Acceptable Verification Parameters

Replace paragraph one with the following effective with the December 2018 letting:

- (1) The engineer will provide test results to the contractor within 2 mixture-production days after obtaining the sample. The quality of the product is acceptably verified if it meets the following limits:
 - V_a is within a range of 2.0 to 4.3 percent. For SMA, V_a is within a range of 2.7 to 5.3 percent.
 - VMA is within minus 0.5 of the minimum requirement for the mix design nominal maximum aggregate size.
 - Asphalt content is within minus 0.3 percent of the JMF.

460.2.8.3.1.7 Dispute Resolution

Replace paragraph one with the following effective with the December 2018 letting:

- (1) When QV test results do not meet the specified limits for 100 percent pay, the bureau's AASHTO accredited laboratory and certified personnel will referee test the retained portion of the QV sample and the retained portion of the required forward and backward QC retained samples according to CMM 8-36.

460.5.2.1 General

Replace paragraphs five and six with the following effective with the December 2018 letting:

- (5) The department will reduce pay for nonconforming QMP HMA mixtures as specified in 460.2.8.2.1.7, starting from the stop point to the point when the running average of 4 is back inside the warning limits. The engineer will determine the quantity of material subject to pay reduction based on the testing data and an inspection of the completed pavement. The department will reduce pay as follows:

PAYMENT FOR MIXTURE^{[1] [2] [3]}

ITEM	PRODUCED WITHIN WARNING BANDS	PRODUCED OUTSIDE JMF LIMITS
Gradation	90%	75%
Asphalt Content ^[4]	—	—
Air Voids	70%	50%
VMA	90%	75%

^[1] For projects or plants where the total production of each mixture design requires less than 4 tests refer to CMM 8-36.

^[2] Payment is in percent of the contract unit price for the HMA Pavement bid item. The department will reduce pay based on the nonconforming property with lowest percent pay. If the quantity of material subject to pay adjustment based on the running average of 4 is also subject to pay adjustment resulting from dispute resolution in accordance with 460.2.8.3.1.7, the department will apply the single pay adjustment resulting in the lowest percent pay.

^[3] In addition to any pay adjustment listed in the table above, the department will adjust pay for nonconforming binder under the Nonconforming QMP Asphaltic Material administrative item. The department will deduct 25 percent of the contract unit price of the HMA Pavement bid item per ton of pavement placed with nonconforming PG binder the engineer allows to remain in place.

^[4] The department will not adjust pay based on a running average of 4 asphalt content tests; however, corrective action will be applied to nonconforming material according to 460.2.8.2.1.7.

- (6) If during a QV dispute resolution investigation the department discovers unacceptable mixture defined by one or more of the following:
- Va greater than 5.0 or less than 1.5.
 - VMA more than 1.0 below the minimum allowed in table 460-1.
 - AC more than 0.5 % below the JMF target.

Remove and replace the material, or if the engineer allows the mixture to remain in place, the department will pay for the quantity of affected material at 50 percent of the contract price.

506.3.2 Shop Drawings

Replace paragraph four with the following effective with the December 2018 letting:

- (4) Ensure that the fabricator submits a PDF file of shop drawings for railroad structures to the railroad company's chief engineering officer upon contract completion.

646.3.1.2 Liquid Marking

Replace paragraph five with the following effective with the January 2019 letting:

- (5) Apply liquid marking and glass beads across the line at or exceeding the following:

LIQUID MARKING	PAVEMENT TYPE	THICKNESS (mils)	BEAD APPLICATION (pounds per gallon)
Paint	all	16	8
Epoxy	SMA, seal coats, and polymer overlays	25	25
Epoxy	all other	20	22.5
Wet Reflective Epoxy	all	20	18

646.3.2.3.2 Wet Reflective Epoxy

Replace paragraph five with the following effective with the January 2019 letting:

- (1) Apply wet reflective epoxy binder in a grooved slot. and provide a double drop bead system as follows:
 - First: wet reflective/recoverable elements at the application rate specified for the product chosen from the department's APL.
 - Second: glass beads at the application rate specified in 646.3.1.2(5).

650.3.1 General

Replace the entire text with the following effective with the December 2018 letting:

- (1) Department and contractor responsibilities for construction staking are specified in 105.6. Conform to 105.6 and the additional requirements specified here in 650.3 for the individual contractor-staking bid items the contract includes.
- (2) Protect and preserve known property and survey marks and land monuments as specified in 107.11.3. The contract may require related work under the 621 bid items.
- (3) Obtain or calculate benchmark data, grades, and alignment from plan information. The engineer will furnish data for the horizontal and vertical control points, control point ties, horizontal alignments, profiles, and elevations. Reestablish, set additional, and maintain the horizontal and vertical control points and control point ties, as needed for bid items.
- (4) Check horizontal and vertical information including but not limited to alignments, locations, elevations, and dimensions, that either the plans show or the engineer provides, for compatibility with existing field conditions. Conduct similar compatibility checks and accuracy checks of horizontal and vertical positions either the department or the contractor establishes in the field.
- (5) Perform survey work using conventional methods, or AMG methods capable of achieving the lines and grades the plans show for the work in question. Establish additional benchmarks and control points as necessary to support the method of operation.

650.3.1.1 Staking

- (1) Furnish, set, reference, and maintain stakes and markings necessary to establish the alignment, location, benchmarks, elevations, and continuous profile-grades for road and structure work as needed for bid items. Supervise and coordinate construction staking.
- (2) Maintain neat, orderly, and complete survey notes, drawings, and computations used in establishing the lines and grades. Make the survey notes and computations available to the engineer within 24 hours, upon request, as the work progresses.
- (3) Furnish surveying equipment, stakes, flags, pins, lath, whiskers, and other materials necessary to perform this work, subject to the engineer's approval.

650.3.1.2 Automated Machine Guidance**650.3.1.2.1 General**

- (1) The contractor may substitute AMG for conventional staking on all or part of the work under the individual staking bid items. Coordinate with the engineer throughout the course of construction to ensure that work performed using AMG conforms to the contract tolerances and that the methods employed conform to the contractor's AMG work plan and accepted industry standards. Revert to conventional staking methods for all or part of the work at any point during construction if AMG is producing unacceptable results.

650.3.1.2.2 AMG Work Plan

- (1) Submit a comprehensive written AMG work plan for department review at least 5 business days before the preconstruction conference. In that plan discuss how AMG technology will be integrated into other

technologies employed on the project. List the staking bid items that will have work performed using AMG and, for each bid item listed, include the following:

1. Designate which portions of the contract will be done using AMG and which portions will be done using conventional staking.
 2. Designate a single staff person as the primary contact for AMG technology issues.
 3. List and map the primary and secondary control points required under 105.6.2 enveloping the site.
 4. Describe the contractor's quality control procedures. Include the frequency and type of checks performed to ensure that the work conforms to the contract plans.
- (2) The engineer will review the plan to determine if it conforms to the contract. Do not perform AMG work until the engineer approves the governing portion of the AMG workplan. Perform the work as the contractor's AMG work plan provides. Update the plan as necessary.

650.3.1.2.3 Geometric and Surface Information

650.3.1.2.3.1 Department Responsibilities

- (1) At any time after the contract is awarded the contractor may request the contractor data packet. The department will provide the packet within 5 business days of receiving the contractor's request.

650.3.1.2.3.2 Contractor Responsibilities

- (1) Develop and maintain a contractor construction model for areas of the project employing AMG. Confirm that the resulting model agrees with the contract plans.
- (2) If the engineer requests, provide the construction model to the department in LandXML or other engineer-approved format.

650.3.1.2.4 Managing and Updating Information

- (1) Notify the department of any errors or discrepancies in department-provided information. The department will determine what revisions may be required. The department will revise the contract plans, if necessary, to address errors or discrepancies that the contractor identifies. The department will provide the best available information related to those contract plan revisions.
- (2) Revise the construction model as required to support construction operations and to reflect any contract plan revisions the department makes. Perform checks to confirm that the revised construction model agrees with the contract plan revisions. If the engineer requests, provide construction model updates to the engineer. The department will pay for costs incurred to incorporate contract plan revisions as extra work.

650.3.1.2.5 Construction Checks

- (1) Check the work against the plan elevation at randomly selected points on cross-sections located at stations evenly divisible by 100 at the frequency the engineer approved as a part of the AMG work plan. Submit the results of these random checks to the engineer daily. Notify the engineer immediately if a check exceeds the tolerances specified in 650.3.1.2.6 below.
- (2) Check the work at additional points as the engineer directs. The department may conduct periodic independent checks.

650.3.1.2.6 Construction Tolerances

- (1) Ensure that the finished work vertically matches existing or other completed features. Ensure that the work conforms to revised plan elevations as follows:
- Subgrade : +/- 0.10 feet.
 - Base : within the tolerance specified in 301.3.4.1(2).

650.3.3 Subgrade

Retitle and replace the entire text with the following effective with the December 2018 letting:

650.3.3 Subgrade Staking

- (1) Set construction stakes or marks at intervals of 100 feet, or more frequently, for rural sections and at intervals of 50 feet, or more frequently, for urban sections. Include additional stakes at each cross-section as necessary to match the plan cross-section, achieve the required accuracy, and to support construction operations. Also set and maintain stakes as necessary to establish the horizontal and vertical positions of intersecting road radii, auxiliary lanes, horizontal and vertical curves, and curve

transitions. Locate stakes to within 0.25 feet horizontally and establish the grade elevation to within 0.03 feet vertically.

Errata

520.3.3 Laying Pipe

Correct errata by replacing "sections" with "joints" to clarify the intent that the last 3 joints need ties.

- (5) Provide joint ties on the upstream and downstream ends of circular and horizontal elliptical concrete culvert and concrete cattle pass installations. Tie the next 3 pipe joints or, if using apron endwalls, the endwall joint and the last 2 pipe joints. Ties are not required on culverts with masonry endwalls unless the plans show otherwise.
-

608.3.3 Laying Pipe

Correct errata by replacing "sections" with "joints" to clarify the intent that the last 3 joints need ties.

- (5) Provide joint ties on concrete storm sewer system infall and outfall pipes. Tie the last 3 pipe joints or, if using apron endwalls, the endwall joint and the next 2 pipe joints. Ties are not required on installations with masonry endwalls unless the plans show otherwise.

ADDITIONAL SPECIAL PROVISION 7

- A. Reporting 1st Tier and DBE Payments During Construction
1. Comply with reporting requirements specified in the department's Civil Rights Compliance, Contractor's User Manual, Sublets and Payments.
 2. Report payments to all DBE firms within 10 calendar days of receipt of a progress payment by the department or a contractor for work performed, materials furnished, or materials stockpiled by a DBE firm. Report the payment as specified in A(1) for all work satisfactorily performed and for all materials furnished or stockpiled.
 3. Report payments to all first tier subcontractor relationships within 10 calendar days of receipt of a progress payment by the department for work performed. Report the payment as specified in A(1) for all work satisfactorily performed.
 4. All tiers shall report payments as necessary to comply with the DBE payment requirement as specified in A(2).
 5. Require all first tier relationships, DBE firms and all other tier relationships necessary to comply with the DBE payment requirement in receipt of a progress payment by contractor to acknowledge receipt of payment as specified in A(1), (2), (3) and (4).
 6. All agreements made by a contractor shall include the provisions in A(1), (2), (3), (4) and (5), and shall be binding on all first tier subcontractor relationships and all contractors and subcontractors utilizing DBE firms on the project.
- B. Costs for conforming to this special provision are incidental to the contract.

NOTE: CRCS Prime Contractor payment is currently not automated and will need to be manually loaded into the Civil Rights Compliance System. Copies of prime contractor payments received (check or ACH) will have to be forwarded to paul.ndon@dot.wi.gov within 5 days of payment receipt to be logged manually.

***Additionally, for information on Subcontractor Sublet assignments, Subcontractor Payments and Payment Tracking, please refer to the CRCS Payment and Sublets manual at:

<https://wisconsindot.gov/Documents/doing-bus/civil-rights/labornwage/crcs-payments-sublets-manual.pdf>

ADDITIONAL SPECIAL PROVISION 9

Electronic Certified Payroll or Labor Data Submittal

(1) Use the department's Civil Rights Compliance System (CRCS) to electronically submit certified payroll reports for contracts with federal funds and labor data for contracts with state funds only. Details are available online through the department's highway construction contractor information (HCCI) site on the Labor, Wages, and EEO Information page at:

<https://wisconsindot.gov/Pages/doing-bus/civil-rights/labornwage/default.aspx>

(2) Ensure that all tiers of subcontractors, including all trucking firms, either submit their weekly certified payroll reports (contracts with federal funds) or labor data (contracts with state funds only) electronically through CRCS. These payrolls or labor data are due within seven calendar days following the close of the payroll period. Every firm providing physical labor towards completing the project is a subcontractor under this special provision.

(3) Upon receipt of contract execution, promptly make all affected firms aware of the requirements under this special provision and arrange for them to receive CRCS training as they are about to begin their submittals. The department will provide training either in a classroom setting at one of our regional offices or by telephone. Contact Paul Ndon at (414) 438-4584 to schedule the training.

(4) The department will reject all paper submittals for information required under this special provision. All costs for conforming to this special provision are incidental to the contract.

(5) Firms wishing to export payroll/labor data from their computer system into CRCS should have their payroll coordinator contact Paul Ndon at paul.ndon@dot.wi.gov. Not every contractor's payroll system is capable of producing export files. For details, see Section 4.8 CPR Auto Submit (Data Mapping) on pages 49-50; 66-71 of the CRCS Payroll Manual at:

<https://wisconsindot.gov/Documents/doing-bus/civil-rights/labornwage/crcs-payroll-manual.pdf>

REQUIRED CONTRACT PROVISIONS FEDERAL-AID CONSTRUCTION CONTRACTS

- I. General
- II. Nondiscrimination
- III. Nonsegregated Facilities
- IV. Davis-Bacon and Related Act Provisions
- V. Contract Work Hours and Safety Standards Act Provisions
- VI. Subletting or Assigning the Contract
- VII. Safety: Accident Prevention
- VIII. False Statements Concerning Highway Projects
- IX. Implementation of Clean Air Act and Federal Water Pollution Control Act
- X. Compliance with Governmentwide Suspension and Debarment Requirements
- XI. Certification Regarding Use of Contract Funds for Lobbying

ATTACHMENTS

A. Employment and Materials Preference for Appalachian Development Highway System or Appalachian Local Access Road Contracts (included in Appalachian contracts only)

I. GENERAL

1. Form FHWA-1273 must be physically incorporated in each construction contract funded under Title 23 (excluding emergency contracts solely intended for debris removal). The contractor (or subcontractor) must insert this form in each subcontract and further require its inclusion in all lower tier subcontracts (excluding purchase orders, rental agreements and other agreements for supplies or services).

The applicable requirements of Form FHWA-1273 are incorporated by reference for work done under any purchase order, rental agreement or agreement for other services. The prime contractor shall be responsible for compliance by any subcontractor, lower-tier subcontractor or service provider.

Form FHWA-1273 must be included in all Federal-aid design-build contracts, in all subcontracts and in lower tier subcontracts (excluding subcontracts for design services, purchase orders, rental agreements and other agreements for supplies or services). The design-builder shall be responsible for compliance by any subcontractor, lower-tier subcontractor or service provider.

Contracting agencies may reference Form FHWA-1273 in bid proposal or request for proposal documents, however, the Form FHWA-1273 must be physically incorporated (not referenced) in all contracts, subcontracts and lower-tier subcontracts (excluding purchase orders, rental agreements and other agreements for supplies or services related to a construction contract).

2. Subject to the applicability criteria noted in the following sections, these contract provisions shall apply to all work performed on the contract by the contractor's own organization and with the assistance of workers under the contractor's immediate superintendence and to all work performed on the contract by piecework, station work, or by subcontract.

3. A breach of any of the stipulations contained in these Required Contract Provisions may be sufficient grounds for withholding of progress payments, withholding of final payment, termination of the contract, suspension / debarment or any other action determined to be appropriate by the contracting agency and FHWA.

4. Selection of Labor: During the performance of this contract, the contractor shall not use convict labor for any purpose within the limits of a construction project on a Federal-aid highway unless it is labor performed by convicts who are on parole, supervised release, or probation. The term Federal-aid highway does not include roadways functionally classified as local roads or rural minor collectors.

II. NONDISCRIMINATION

The provisions of this section related to 23 CFR Part 230 are applicable to all Federal-aid construction contracts and to all related construction subcontracts of \$10,000 or more. The provisions of 23 CFR Part 230 are not applicable to material supply, engineering, or architectural service contracts.

In addition, the contractor and all subcontractors must comply with the following policies: Executive Order 11246, 41 CFR 60, 29 CFR 1625-1627, Title 23 USC Section 140, the Rehabilitation Act of 1973, as amended (29 USC 794), Title VI of the Civil Rights Act of 1964, as amended, and related regulations including 49 CFR Parts 21, 26 and 27; and 23 CFR Parts 200, 230, and 633.

The contractor and all subcontractors must comply with: the requirements of the Equal Opportunity Clause in 41 CFR 60-1.4(b) and, for all construction contracts exceeding \$10,000, the Standard Federal Equal Employment Opportunity Construction Contract Specifications in 41 CFR 60-4.3.

Note: The U.S. Department of Labor has exclusive authority to determine compliance with Executive Order 11246 and the policies of the Secretary of Labor including 41 CFR 60, and 29 CFR 1625-1627. The contracting agency and the FHWA have the authority and the responsibility to ensure compliance with Title 23 USC Section 140, the Rehabilitation Act of 1973, as amended (29 USC 794), and Title VI of the Civil Rights Act of 1964, as amended, and related regulations including 49 CFR Parts 21, 26 and 27; and 23 CFR Parts 200, 230, and 633.

The following provision is adopted from 23 CFR 230, Appendix A, with appropriate revisions to conform to the U.S. Department of Labor (US DOL) and FHWA requirements.

1. Equal Employment Opportunity: Equal employment opportunity (EEO) requirements not to discriminate and to take affirmative action to assure equal opportunity as set forth under laws, executive orders, rules, regulations (28 CFR 35, 29 CFR 1630, 29 CFR 1625-1627, 41 CFR 60 and 49 CFR 27) and orders of the Secretary of Labor as modified by the provisions prescribed herein, and imposed pursuant to 23 U.S.C. 140 shall constitute the EEO and specific affirmative action standards for the contractor's project activities under

this contract. The provisions of the Americans with Disabilities Act of 1990 (42 U.S.C. 12101 et seq.) set forth under 28 CFR 35 and 29 CFR 1630 are incorporated by reference in this contract. In the execution of this contract, the contractor agrees to comply with the following minimum specific requirement activities of EEO:

a. The contractor will work with the contracting agency and the Federal Government to ensure that it has made every good faith effort to provide equal opportunity with respect to all of its terms and conditions of employment and in their review of activities under the contract.

b. The contractor will accept as its operating policy the following statement:

"It is the policy of this Company to assure that applicants are employed, and that employees are treated during employment, without regard to their race, religion, sex, color, national origin, age or disability. Such action shall include: employment, upgrading, demotion, or transfer; recruitment or recruitment advertising; layoff or termination; rates of pay or other forms of compensation; and selection for training, including apprenticeship, pre-apprenticeship, and/or on-the-job training."

2. EEO Officer: The contractor will designate and make known to the contracting officers an EEO Officer who will have the responsibility for and must be capable of effectively administering and promoting an active EEO program and who must be assigned adequate authority and responsibility to do so.

3. Dissemination of Policy: All members of the contractor's staff who are authorized to hire, supervise, promote, and discharge employees, or who recommend such action, or who are substantially involved in such action, will be made fully cognizant of, and will implement, the contractor's EEO policy and contractual responsibilities to provide EEO in each grade and classification of employment. To ensure that the above agreement will be met, the following actions will be taken as a minimum:

a. Periodic meetings of supervisory and personnel office employees will be conducted before the start of work and then not less often than once every six months, at which time the contractor's EEO policy and its implementation will be reviewed and explained. The meetings will be conducted by the EEO Officer.

b. All new supervisory or personnel office employees will be given a thorough indoctrination by the EEO Officer, covering all major aspects of the contractor's EEO obligations within thirty days following their reporting for duty with the contractor.

c. All personnel who are engaged in direct recruitment for the project will be instructed by the EEO Officer in the contractor's procedures for locating and hiring minorities and women.

d. Notices and posters setting forth the contractor's EEO policy will be placed in areas readily accessible to employees, applicants for employment and potential employees.

e. The contractor's EEO policy and the procedures to implement such policy will be brought to the attention of employees by means of meetings, employee handbooks, or other appropriate means.

4. Recruitment: When advertising for employees, the contractor will include in all advertisements for employees the notation: "An Equal Opportunity Employer." All such advertisements will be placed in publications having a large circulation among minorities and women in the area from which the project work force would normally be derived.

a. The contractor will, unless precluded by a valid bargaining agreement, conduct systematic and direct recruitment through public and private employee referral sources likely to yield qualified minorities and women. To meet this requirement, the contractor will identify sources of potential minority group employees, and establish with such identified sources procedures whereby minority and women applicants may be referred to the contractor for employment consideration.

b. In the event the contractor has a valid bargaining agreement providing for exclusive hiring hall referrals, the contractor is expected to observe the provisions of that agreement to the extent that the system meets the contractor's compliance with EEO contract provisions. Where implementation of such an agreement has the effect of discriminating against minorities or women, or obligates the contractor to do the same, such implementation violates Federal nondiscrimination provisions.

c. The contractor will encourage its present employees to refer minorities and women as applicants for employment. Information and procedures with regard to referring such applicants will be discussed with employees.

5. Personnel Actions: Wages, working conditions, and employee benefits shall be established and administered, and personnel actions of every type, including hiring, upgrading, promotion, transfer, demotion, layoff, and termination, shall be taken without regard to race, color, religion, sex, national origin, age or disability. The following procedures shall be followed:

a. The contractor will conduct periodic inspections of project sites to insure that working conditions and employee facilities do not indicate discriminatory treatment of project site personnel.

b. The contractor will periodically evaluate the spread of wages paid within each classification to determine any evidence of discriminatory wage practices.

c. The contractor will periodically review selected personnel actions in depth to determine whether there is evidence of discrimination. Where evidence is found, the contractor will promptly take corrective action. If the review indicates that the discrimination may extend beyond the actions reviewed, such corrective action shall include all affected persons.

d. The contractor will promptly investigate all complaints of alleged discrimination made to the contractor in connection with its obligations under this contract, will attempt to resolve such complaints, and will take appropriate corrective action within a reasonable time. If the investigation indicates that the discrimination may affect persons other than the complainant, such corrective action shall include such other persons. Upon completion of each investigation, the contractor will inform every complainant of all of their avenues of appeal.

6. Training and Promotion:

a. The contractor will assist in locating, qualifying, and increasing the skills of minorities and women who are

applicants for employment or current employees. Such efforts should be aimed at developing full journey level status employees in the type of trade or job classification involved.

b. Consistent with the contractor's work force requirements and as permissible under Federal and State regulations, the contractor shall make full use of training programs, i.e., apprenticeship, and on-the-job training programs for the geographical area of contract performance. In the event a special provision for training is provided under this contract, this subparagraph will be superseded as indicated in the special provision. The contracting agency may reserve training positions for persons who receive welfare assistance in accordance with 23 U.S.C. 140(a).

c. The contractor will advise employees and applicants for employment of available training programs and entrance requirements for each.

d. The contractor will periodically review the training and promotion potential of employees who are minorities and women and will encourage eligible employees to apply for such training and promotion.

7. Unions: If the contractor relies in whole or in part upon unions as a source of employees, the contractor will use good faith efforts to obtain the cooperation of such unions to increase opportunities for minorities and women. Actions by the contractor, either directly or through a contractor's association acting as agent, will include the procedures set forth below:

a. The contractor will use good faith efforts to develop, in cooperation with the unions, joint training programs aimed toward qualifying more minorities and women for membership in the unions and increasing the skills of minorities and women so that they may qualify for higher paying employment.

b. The contractor will use good faith efforts to incorporate an EEO clause into each union agreement to the end that such union will be contractually bound to refer applicants without regard to their race, color, religion, sex, national origin, age or disability.

c. The contractor is to obtain information as to the referral practices and policies of the labor union except that to the extent such information is within the exclusive possession of the labor union and such labor union refuses to furnish such information to the contractor, the contractor shall so certify to the contracting agency and shall set forth what efforts have been made to obtain such information.

d. In the event the union is unable to provide the contractor with a reasonable flow of referrals within the time limit set forth in the collective bargaining agreement, the contractor will, through independent recruitment efforts, fill the employment vacancies without regard to race, color, religion, sex, national origin, age or disability; making full efforts to obtain qualified and/or qualifiable minorities and women. The failure of a union to provide sufficient referrals (even though it is obligated to provide exclusive referrals under the terms of a collective bargaining agreement) does not relieve the contractor from the requirements of this paragraph. In the event the union referral practice prevents the contractor from meeting the obligations pursuant to Executive Order 11246, as amended, and these special provisions, such contractor shall immediately notify the contracting agency.

8. Reasonable Accommodation for Applicants / Employees with Disabilities: The contractor must be familiar

with the requirements for and comply with the Americans with Disabilities Act and all rules and regulations established there under. Employers must provide reasonable accommodation in all employment activities unless to do so would cause an undue hardship.

9. Selection of Subcontractors, Procurement of Materials and Leasing of Equipment: The contractor shall not discriminate on the grounds of race, color, religion, sex, national origin, age or disability in the selection and retention of subcontractors, including procurement of materials and leases of equipment. The contractor shall take all necessary and reasonable steps to ensure nondiscrimination in the administration of this contract.

a. The contractor shall notify all potential subcontractors and suppliers and lessors of their EEO obligations under this contract.

b. The contractor will use good faith efforts to ensure subcontractor compliance with their EEO obligations.

10. Assurance Required by 49 CFR 26.13(b):

a. The requirements of 49 CFR Part 26 and the State DOT's U.S. DOT-approved DBE program are incorporated by reference.

b. The contractor or subcontractor shall not discriminate on the basis of race, color, national origin, or sex in the performance of this contract. The contractor shall carry out applicable requirements of 49 CFR Part 26 in the award and administration of DOT-assisted contracts. Failure by the contractor to carry out these requirements is a material breach of this contract, which may result in the termination of this contract or such other remedy as the contracting agency deems appropriate.

11. Records and Reports: The contractor shall keep such records as necessary to document compliance with the EEO requirements. Such records shall be retained for a period of three years following the date of the final payment to the contractor for all contract work and shall be available at reasonable times and places for inspection by authorized representatives of the contracting agency and the FHWA.

a. The records kept by the contractor shall document the following:

(1) The number and work hours of minority and non-minority group members and women employed in each work classification on the project;

(2) The progress and efforts being made in cooperation with unions, when applicable, to increase employment opportunities for minorities and women; and

(3) The progress and efforts being made in locating, hiring, training, qualifying, and upgrading minorities and women;

b. The contractors and subcontractors will submit an annual report to the contracting agency each July for the duration of the project, indicating the number of minority, women, and non-minority group employees currently engaged in each work classification required by the contract work. This information is to be reported on [Form FHWA-1391](#). The staffing data should represent the project work force on board in all or any part of the last payroll period preceding the end of July. If on-the-job training is being required by special provision, the contractor

will be required to collect and report training data. The employment data should reflect the work force on board during all or any part of the last payroll period preceding the end of July.

III. NONSEGREGATED FACILITIES

This provision is applicable to all Federal-aid construction contracts and to all related construction subcontracts of \$10,000 or more.

The contractor must ensure that facilities provided for employees are provided in such a manner that segregation on the basis of race, color, religion, sex, or national origin cannot result. The contractor may neither require such segregated use by written or oral policies nor tolerate such use by employee custom. The contractor's obligation extends further to ensure that its employees are not assigned to perform their services at any location, under the contractor's control, where the facilities are segregated. The term "facilities" includes waiting rooms, work areas, restaurants and other eating areas, time clocks, restrooms, washrooms, locker rooms, and other storage or dressing areas, parking lots, drinking fountains, recreation or entertainment areas, transportation, and housing provided for employees. The contractor shall provide separate or single-user restrooms and necessary dressing or sleeping areas to assure privacy between sexes.

IV. DAVIS-BACON AND RELATED ACT PROVISIONS

This section is applicable to all Federal-aid construction projects exceeding \$2,000 and to all related subcontracts and lower-tier subcontracts (regardless of subcontract size). The requirements apply to all projects located within the right-of-way of a roadway that is functionally classified as Federal-aid highway. This excludes roadways functionally classified as local roads or rural minor collectors, which are exempt. Contracting agencies may elect to apply these requirements to other projects.

The following provisions are from the U.S. Department of Labor regulations in 29 CFR 5.5 "Contract provisions and related matters" with minor revisions to conform to the FHWA-1273 format and FHWA program requirements.

1. Minimum wages

a. All laborers and mechanics employed or working upon the site of the work, will be paid unconditionally and not less often than once a week, and without subsequent deduction or rebate on any account (except such payroll deductions as are permitted by regulations issued by the Secretary of Labor under the Copeland Act (29 CFR part 3)), the full amount of wages and bona fide fringe benefits (or cash equivalents thereof) due at time of payment computed at rates not less than those contained in the wage determination of the Secretary of Labor which is attached hereto and made a part hereof, regardless of any contractual relationship which may be alleged to exist between the contractor and such laborers and mechanics.

Contributions made or costs reasonably anticipated for bona fide fringe benefits under section 1(b)(2) of the Davis-Bacon Act on behalf of laborers or mechanics are considered wages paid to such laborers or mechanics, subject to the provisions

of paragraph 1.d. of this section; also, regular contributions made or costs incurred for more than a weekly period (but not less often than quarterly) under plans, funds, or programs which cover the particular weekly period, are deemed to be constructively made or incurred during such weekly period. Such laborers and mechanics shall be paid the appropriate wage rate and fringe benefits on the wage determination for the classification of work actually performed, without regard to skill, except as provided in 29 CFR 5.5(a)(4). Laborers or mechanics performing work in more than one classification may be compensated at the rate specified for each classification for the time actually worked therein: Provided, That the employer's payroll records accurately set forth the time spent in each classification in which work is performed. The wage determination (including any additional classification and wage rates conformed under paragraph 1.b. of this section) and the Davis-Bacon poster (WH-1321) shall be posted at all times by the contractor and its subcontractors at the site of the work in a prominent and accessible place where it can be easily seen by the workers.

b.(1) The contracting officer shall require that any class of laborers or mechanics, including helpers, which is not listed in the wage determination and which is to be employed under the contract shall be classified in conformance with the wage determination. The contracting officer shall approve an additional classification and wage rate and fringe benefits therefore only when the following criteria have been met:

(i) The work to be performed by the classification requested is not performed by a classification in the wage determination; and

(ii) The classification is utilized in the area by the construction industry; and

(iii) The proposed wage rate, including any bona fide fringe benefits, bears a reasonable relationship to the wage rates contained in the wage determination.

(2) If the contractor and the laborers and mechanics to be employed in the classification (if known), or their representatives, and the contracting officer agree on the classification and wage rate (including the amount designated for fringe benefits where appropriate), a report of the action taken shall be sent by the contracting officer to the Administrator of the Wage and Hour Division, Employment Standards Administration, U.S. Department of Labor, Washington, DC 20210. The Administrator, or an authorized representative, will approve, modify, or disapprove every additional classification action within 30 days of receipt and so advise the contracting officer or will notify the contracting officer within the 30-day period that additional time is necessary.

(3) In the event the contractor, the laborers or mechanics to be employed in the classification or their representatives, and the contracting officer do not agree on the proposed classification and wage rate (including the amount designated for fringe benefits, where appropriate), the contracting officer shall refer the questions, including the views of all interested parties and the recommendation of the contracting officer, to the Wage and Hour Administrator for determination. The Wage and Hour Administrator, or an authorized representative, will issue a determination within 30 days of receipt and so advise the contracting officer or

will notify the contracting officer within the 30-day period that additional time is necessary.

(4) The wage rate (including fringe benefits where appropriate) determined pursuant to paragraphs 1.b.(2) or 1.b.(3) of this section, shall be paid to all workers performing work in the classification under this contract from the first day on which work is performed in the classification.

c. Whenever the minimum wage rate prescribed in the contract for a class of laborers or mechanics includes a fringe benefit which is not expressed as an hourly rate, the contractor shall either pay the benefit as stated in the wage determination or shall pay another bona fide fringe benefit or an hourly cash equivalent thereof.

d. If the contractor does not make payments to a trustee or other third person, the contractor may consider as part of the wages of any laborer or mechanic the amount of any costs reasonably anticipated in providing bona fide fringe benefits under a plan or program. Provided, That the Secretary of Labor has found, upon the written request of the contractor, that the applicable standards of the Davis-Bacon Act have been met. The Secretary of Labor may require the contractor to set aside in a separate account assets for the meeting of obligations under the plan or program.

2. Withholding

The contracting agency shall upon its own action or upon written request of an authorized representative of the Department of Labor, withhold or cause to be withheld from the contractor under this contract, or any other Federal contract with the same prime contractor, or any other federally-assisted contract subject to Davis-Bacon prevailing wage requirements, which is held by the same prime contractor, so much of the accrued payments or advances as may be considered necessary to pay laborers and mechanics, including apprentices, trainees, and helpers, employed by the contractor or any subcontractor the full amount of wages required by the contract. In the event of failure to pay any laborer or mechanic, including any apprentice, trainee, or helper, employed or working on the site of the work, all or part of the wages required by the contract, the contracting agency may, after written notice to the contractor, take such action as may be necessary to cause the suspension of any further payment, advance, or guarantee of funds until such violations have ceased.

3. Payrolls and basic records

a. Payrolls and basic records relating thereto shall be maintained by the contractor during the course of the work and preserved for a period of three years thereafter for all laborers and mechanics working at the site of the work. Such records shall contain the name, address, and social security number of each such worker, his or her correct classification, hourly rates of wages paid (including rates of contributions or costs anticipated for bona fide fringe benefits or cash equivalents thereof of the types described in section 1(b)(2)(B) of the Davis-Bacon Act), daily and weekly number of hours worked, deductions made and actual wages paid. Whenever the Secretary of Labor has found under 29 CFR 5.5(a)(1)(iv) that the wages of any laborer or mechanic include the amount of any costs reasonably anticipated in providing benefits under a plan or program described in section 1(b)(2)(B) of the Davis-

Bacon Act, the contractor shall maintain records which show that the commitment to provide such benefits is enforceable, that the plan or program is financially responsible, and that the plan or program has been communicated in writing to the laborers or mechanics affected, and records which show the costs anticipated or the actual cost incurred in providing such benefits. Contractors employing apprentices or trainees under approved programs shall maintain written evidence of the registration of apprenticeship programs and certification of trainee programs, the registration of the apprentices and trainees, and the ratios and wage rates prescribed in the applicable programs.

b. (1) The contractor shall submit weekly for each week in which any contract work is performed a copy of all payrolls to the contracting agency. The payrolls submitted shall set out accurately and completely all of the information required to be maintained under 29 CFR 5.5(a)(3)(i), except that full social security numbers and home addresses shall not be included on weekly transmittals. Instead the payrolls shall only need to include an individually identifying number for each employee (e.g., the last four digits of the employee's social security number). The required weekly payroll information may be submitted in any form desired. Optional Form WH-347 is available for this purpose from the Wage and Hour Division Web site at <http://www.dol.gov/esa/whd/forms/wh347instr.htm> or its successor site. The prime contractor is responsible for the submission of copies of payrolls by all subcontractors. Contractors and subcontractors shall maintain the full social security number and current address of each covered worker, and shall provide them upon request to the contracting agency for transmission to the State DOT, the FHWA or the Wage and Hour Division of the Department of Labor for purposes of an investigation or audit of compliance with prevailing wage requirements. It is not a violation of this section for a prime contractor to require a subcontractor to provide addresses and social security numbers to the prime contractor for its own records, without weekly submission to the contracting agency..

(2) Each payroll submitted shall be accompanied by a "Statement of Compliance," signed by the contractor or subcontractor or his or her agent who pays or supervises the payment of the persons employed under the contract and shall certify the following:

(i) That the payroll for the payroll period contains the information required to be provided under §5.5 (a)(3)(ii) of Regulations, 29 CFR part 5, the appropriate information is being maintained under §5.5 (a)(3)(i) of Regulations, 29 CFR part 5, and that such information is correct and complete;

(ii) That each laborer or mechanic (including each helper, apprentice, and trainee) employed on the contract during the payroll period has been paid the full weekly wages earned, without rebate, either directly or indirectly, and that no deductions have been made either directly or indirectly from the full wages earned, other than permissible deductions as set forth in Regulations, 29 CFR part 3;

(iii) That each laborer or mechanic has been paid not less than the applicable wage rates and fringe benefits or cash equivalents for the classification of work performed, as specified in the applicable wage determination incorporated into the contract.

(3) The weekly submission of a properly executed certification set forth on the reverse side of Optional Form WH-347 shall satisfy the requirement for submission of the "Statement of Compliance" required by paragraph 3.b.(2) of this section.

(4) The falsification of any of the above certifications may subject the contractor or subcontractor to civil or criminal prosecution under section 1001 of title 18 and section 231 of title 31 of the United States Code.

c. The contractor or subcontractor shall make the records required under paragraph 3.a. of this section available for inspection, copying, or transcription by authorized representatives of the contracting agency, the State DOT, the FHWA, or the Department of Labor, and shall permit such representatives to interview employees during working hours on the job. If the contractor or subcontractor fails to submit the required records or to make them available, the FHWA may, after written notice to the contractor, the contracting agency or the State DOT, take such action as may be necessary to cause the suspension of any further payment, advance, or guarantee of funds. Furthermore, failure to submit the required records upon request or to make such records available may be grounds for debarment action pursuant to 29 CFR 5.12.

4. Apprentices and trainees

a. Apprentices (programs of the USDOL).

Apprentices will be permitted to work at less than the predetermined rate for the work they performed when they are employed pursuant to and individually registered in a bona fide apprenticeship program registered with the U.S. Department of Labor, Employment and Training Administration, Office of Apprenticeship Training, Employer and Labor Services, or with a State Apprenticeship Agency recognized by the Office, or if a person is employed in his or her first 90 days of probationary employment as an apprentice in such an apprenticeship program, who is not individually registered in the program, but who has been certified by the Office of Apprenticeship Training, Employer and Labor Services or a State Apprenticeship Agency (where appropriate) to be eligible for probationary employment as an apprentice.

The allowable ratio of apprentices to journeymen on the job site in any craft classification shall not be greater than the ratio permitted to the contractor as to the entire work force under the registered program. Any worker listed on a payroll at an apprentice wage rate, who is not registered or otherwise employed as stated above, shall be paid not less than the applicable wage rate on the wage determination for the classification of work actually performed. In addition, any apprentice performing work on the job site in excess of the ratio permitted under the registered program shall be paid not less than the applicable wage rate on the wage determination for the work actually performed. Where a contractor is performing construction on a project in a locality other than that in which its program is registered, the ratios and wage rates (expressed in percentages of the journeyman's hourly rate) specified in the contractor's or subcontractor's registered program shall be observed.

Every apprentice must be paid at not less than the rate specified in the registered program for the apprentice's level of progress, expressed as a percentage of the journeymen hourly

rate specified in the applicable wage determination. Apprentices shall be paid fringe benefits in accordance with the provisions of the apprenticeship program. If the apprenticeship program does not specify fringe benefits, apprentices must be paid the full amount of fringe benefits listed on the wage determination for the applicable classification. If the Administrator determines that a different practice prevails for the applicable apprentice classification, fringes shall be paid in accordance with that determination.

In the event the Office of Apprenticeship Training, Employer and Labor Services, or a State Apprenticeship Agency recognized by the Office, withdraws approval of an apprenticeship program, the contractor will no longer be permitted to utilize apprentices at less than the applicable predetermined rate for the work performed until an acceptable program is approved.

b. Trainees (programs of the USDOL).

Except as provided in 29 CFR 5.16, trainees will not be permitted to work at less than the predetermined rate for the work performed unless they are employed pursuant to and individually registered in a program which has received prior approval, evidenced by formal certification by the U.S. Department of Labor, Employment and Training Administration.

The ratio of trainees to journeymen on the job site shall not be greater than permitted under the plan approved by the Employment and Training Administration.

Every trainee must be paid at not less than the rate specified in the approved program for the trainee's level of progress, expressed as a percentage of the journeyman hourly rate specified in the applicable wage determination. Trainees shall be paid fringe benefits in accordance with the provisions of the trainee program. If the trainee program does not mention fringe benefits, trainees shall be paid the full amount of fringe benefits listed on the wage determination unless the Administrator of the Wage and Hour Division determines that there is an apprenticeship program associated with the corresponding journeyman wage rate on the wage determination which provides for less than full fringe benefits for apprentices. Any employee listed on the payroll at a trainee rate who is not registered and participating in a training plan approved by the Employment and Training Administration shall be paid not less than the applicable wage rate on the wage determination for the classification of work actually performed. In addition, any trainee performing work on the job site in excess of the ratio permitted under the registered program shall be paid not less than the applicable wage rate on the wage determination for the work actually performed.

In the event the Employment and Training Administration withdraws approval of a training program, the contractor will no longer be permitted to utilize trainees at less than the applicable predetermined rate for the work performed until an acceptable program is approved.

c. Equal employment opportunity. The utilization of apprentices, trainees and journeymen under this part shall be in conformity with the equal employment opportunity requirements of Executive Order 11246, as amended, and 29 CFR part 30.

d. Apprentices and Trainees (programs of the U.S. DOT).

Apprentices and trainees working under apprenticeship and skill training programs which have been certified by the Secretary of Transportation as promoting EEO in connection with Federal-aid highway construction programs are not subject to the requirements of paragraph 4 of this Section IV. The straight time hourly wage rates for apprentices and trainees under such programs will be established by the particular programs. The ratio of apprentices and trainees to journeymen shall not be greater than permitted by the terms of the particular program.

5. Compliance with Copeland Act requirements. The contractor shall comply with the requirements of 29 CFR part 3, which are incorporated by reference in this contract.

6. Subcontracts. The contractor or subcontractor shall insert Form FHWA-1273 in any subcontracts and also require the subcontractors to include Form FHWA-1273 in any lower tier subcontracts. The prime contractor shall be responsible for the compliance by any subcontractor or lower tier subcontractor with all the contract clauses in 29 CFR 5.5.

7. Contract termination: debarment. A breach of the contract clauses in 29 CFR 5.5 may be grounds for termination of the contract, and for debarment as a contractor and a subcontractor as provided in 29 CFR 5.12.

8. Compliance with Davis-Bacon and Related Act requirements. All rulings and interpretations of the Davis-Bacon and Related Acts contained in 29 CFR parts 1, 3, and 5 are herein incorporated by reference in this contract.

9. Disputes concerning labor standards. Disputes arising out of the labor standards provisions of this contract shall not be subject to the general disputes clause of this contract. Such disputes shall be resolved in accordance with the procedures of the Department of Labor set forth in 29 CFR parts 5, 6, and 7. Disputes within the meaning of this clause include disputes between the contractor (or any of its subcontractors) and the contracting agency, the U.S. Department of Labor, or the employees or their representatives.

10. Certification of eligibility.

a. By entering into this contract, the contractor certifies that neither it (nor he or she) nor any person or firm who has an interest in the contractor's firm is a person or firm ineligible to be awarded Government contracts by virtue of section 3(a) of the Davis-Bacon Act or 29 CFR 5.12(a)(1).

b. No part of this contract shall be subcontracted to any person or firm ineligible for award of a Government contract by virtue of section 3(a) of the Davis-Bacon Act or 29 CFR 5.12(a)(1).

c. The penalty for making false statements is prescribed in the U.S. Criminal Code, 18 U.S.C. 1001.

V. CONTRACT WORK HOURS AND SAFETY STANDARDS ACT

The following clauses apply to any Federal-aid construction contract in an amount in excess of \$100,000 and subject to the overtime provisions of the Contract Work Hours and Safety Standards Act. These clauses shall be inserted in addition to the clauses required by 29 CFR 5.5(a) or 29 CFR 4.6. As used in this paragraph, the terms laborers and mechanics include watchmen and guards.

1. Overtime requirements. No contractor or subcontractor contracting for any part of the contract work which may require or involve the employment of laborers or mechanics shall require or permit any such laborer or mechanic in any workweek in which he or she is employed on such work to work in excess of forty hours in such workweek unless such laborer or mechanic receives compensation at a rate not less than one and one-half times the basic rate of pay for all hours worked in excess of forty hours in such workweek.

2. Violation; liability for unpaid wages; liquidated damages. In the event of any violation of the clause set forth in paragraph (1.) of this section, the contractor and any subcontractor responsible therefor shall be liable for the unpaid wages. In addition, such contractor and subcontractor shall be liable to the United States (in the case of work done under contract for the District of Columbia or a territory, to such District or to such territory), for liquidated damages. Such liquidated damages shall be computed with respect to each individual laborer or mechanic, including watchmen and guards, employed in violation of the clause set forth in paragraph (1.) of this section, in the sum of \$10 for each calendar day on which such individual was required or permitted to work in excess of the standard workweek of forty hours without payment of the overtime wages required by the clause set forth in paragraph (1.) of this section.

3. Withholding for unpaid wages and liquidated damages. The FHWA or the contracting agency shall upon its own action or upon written request of an authorized representative of the Department of Labor withhold or cause to be withheld, from any moneys payable on account of work performed by the contractor or subcontractor under any such contract or any other Federal contract with the same prime contractor, or any other federally-assisted contract subject to the Contract Work Hours and Safety Standards Act, which is held by the same prime contractor, such sums as may be determined to be necessary to satisfy any liabilities of such contractor or subcontractor for unpaid wages and liquidated damages as provided in the clause set forth in paragraph (2.) of this section.

4. Subcontracts. The contractor or subcontractor shall insert in any subcontracts the clauses set forth in paragraph (1.) through (4.) of this section and also a clause requiring the subcontractors to include these clauses in any lower tier subcontracts. The prime contractor shall be responsible for compliance by any subcontractor or lower tier subcontractor with the clauses set forth in paragraphs (1.) through (4.) of this section.

VI. SUBLETTING OR ASSIGNING THE CONTRACT

This provision is applicable to all Federal-aid construction contracts on the National Highway System.

1. The contractor shall perform with its own organization contract work amounting to not less than 30 percent (or a greater percentage if specified elsewhere in the contract) of the total original contract price, excluding any specialty items designated by the contracting agency. Specialty items may be performed by subcontract and the amount of any such specialty items performed may be deducted from the total original contract price before computing the amount of work required to be performed by the contractor's own organization (23 CFR 635.116).

a. The term "perform work with its own organization" refers to workers employed or leased by the prime contractor, and equipment owned or rented by the prime contractor, with or without operators. Such term does not include employees or equipment of a subcontractor or lower tier subcontractor, agents of the prime contractor, or any other assignees. The term may include payments for the costs of hiring leased employees from an employee leasing firm meeting all relevant Federal and State regulatory requirements. Leased employees may only be included in this term if the prime contractor meets all of the following conditions:

(1) the prime contractor maintains control over the supervision of the day-to-day activities of the leased employees;

(2) the prime contractor remains responsible for the quality of the work of the leased employees;

(3) the prime contractor retains all power to accept or exclude individual employees from work on the project; and

(4) the prime contractor remains ultimately responsible for the payment of predetermined minimum wages, the submission of payrolls, statements of compliance and all other Federal regulatory requirements.

b. "Specialty Items" shall be construed to be limited to work that requires highly specialized knowledge, abilities, or equipment not ordinarily available in the type of contracting organizations qualified and expected to bid or propose on the contract as a whole and in general are to be limited to minor components of the overall contract.

2. The contract amount upon which the requirements set forth in paragraph (1) of Section VI is computed includes the cost of material and manufactured products which are to be purchased or produced by the contractor under the contract provisions.

3. The contractor shall furnish (a) a competent superintendent or supervisor who is employed by the firm, has full authority to direct performance of the work in accordance with the contract requirements, and is in charge of all construction operations (regardless of who performs the work) and (b) such other of its own organizational resources (supervision, management, and engineering services) as the contracting officer determines is necessary to assure the performance of the contract.

4. No portion of the contract shall be sublet, assigned or otherwise disposed of except with the written consent of the contracting officer, or authorized representative, and such consent when given shall not be construed to relieve the contractor of any responsibility for the fulfillment of the contract. Written consent will be given only after the contracting agency has assured that each subcontract is

evidenced in writing and that it contains all pertinent provisions and requirements of the prime contract.

5. The 30% self-performance requirement of paragraph (1) is not applicable to design-build contracts; however, contracting agencies may establish their own self-performance requirements.

VII. SAFETY: ACCIDENT PREVENTION

This provision is applicable to all Federal-aid construction contracts and to all related subcontracts.

1. In the performance of this contract the contractor shall comply with all applicable Federal, State, and local laws governing safety, health, and sanitation (23 CFR 635). The contractor shall provide all safeguards, safety devices and protective equipment and take any other needed actions as it determines, or as the contracting officer may determine, to be reasonably necessary to protect the life and health of employees on the job and the safety of the public and to protect property in connection with the performance of the work covered by the contract.

2. It is a condition of this contract, and shall be made a condition of each subcontract, which the contractor enters into pursuant to this contract, that the contractor and any subcontractor shall not permit any employee, in performance of the contract, to work in surroundings or under conditions which are unsanitary, hazardous or dangerous to his/her health or safety, as determined under construction safety and health standards (29 CFR 1926) promulgated by the Secretary of Labor, in accordance with Section 107 of the Contract Work Hours and Safety Standards Act (40 U.S.C. 3704).

3. Pursuant to 29 CFR 1926.3, it is a condition of this contract that the Secretary of Labor or authorized representative thereof, shall have right of entry to any site of contract performance to inspect or investigate the matter of compliance with the construction safety and health standards and to carry out the duties of the Secretary under Section 107 of the Contract Work Hours and Safety Standards Act (40 U.S.C.3704).

VIII. FALSE STATEMENTS CONCERNING HIGHWAY PROJECTS

This provision is applicable to all Federal-aid construction contracts and to all related subcontracts.

In order to assure high quality and durable construction in conformity with approved plans and specifications and a high degree of reliability on statements and representations made by engineers, contractors, suppliers, and workers on Federal-aid highway projects, it is essential that all persons concerned with the project perform their functions as carefully, thoroughly, and honestly as possible. Willful falsification, distortion, or misrepresentation with respect to any facts related to the project is a violation of Federal law. To prevent any misunderstanding regarding the seriousness of these and similar acts, Form FHWA-1022 shall be posted on each Federal-aid highway project (23 CFR 635) in one or more places where it is readily available to all persons concerned with the project:

18 U.S.C. 1020 reads as follows:

"Whoever, being an officer, agent, or employee of the United States, or of any State or Territory, or whoever, whether a person, association, firm, or corporation, knowingly makes any false statement, false representation, or false report as to the character, quality, quantity, or cost of the material used or to be used, or the quantity or quality of the work performed or to be performed, or the cost thereof in connection with the submission of plans, maps, specifications, contracts, or costs of construction on any highway or related project submitted for approval to the Secretary of Transportation; or

Whoever knowingly makes any false statement, false representation, false report or false claim with respect to the character, quality, quantity, or cost of any work performed or to be performed, or materials furnished or to be furnished, in connection with the construction of any highway or related project approved by the Secretary of Transportation; or

Whoever knowingly makes any false statement or false representation as to material fact in any statement, certificate, or report submitted pursuant to provisions of the Federal-aid Roads Act approved July 1, 1916, (39 Stat. 355), as amended and supplemented;

Shall be fined under this title or imprisoned not more than 5 years or both."

IX. IMPLEMENTATION OF CLEAN AIR ACT AND FEDERAL WATER POLLUTION CONTROL ACT

This provision is applicable to all Federal-aid construction contracts and to all related subcontracts.

By submission of this bid/proposal or the execution of this contract, or subcontract, as appropriate, the bidder, proposer, Federal-aid construction contractor, or subcontractor, as appropriate, will be deemed to have stipulated as follows:

1. That any person who is or will be utilized in the performance of this contract is not prohibited from receiving an award due to a violation of Section 508 of the Clean Water Act or Section 306 of the Clean Air Act.

2. That the contractor agrees to include or cause to be included the requirements of paragraph (1) of this Section X in every subcontract, and further agrees to take such action as the contracting agency may direct as a means of enforcing such requirements.

X. CERTIFICATION REGARDING DEBARMENT, SUSPENSION, INELIGIBILITY AND VOLUNTARY EXCLUSION

This provision is applicable to all Federal-aid construction contracts, design-build contracts, subcontracts, lower-tier subcontracts, purchase orders, lease agreements, consultant contracts or any other covered transaction requiring FHWA approval or that is estimated to cost \$25,000 or more – as defined in 2 CFR Parts 180 and 1200.

1. Instructions for Certification – First Tier Participants:

a. By signing and submitting this proposal, the prospective first tier participant is providing the certification set out below.

b. The inability of a person to provide the certification set out below will not necessarily result in denial of participation in this

covered transaction. The prospective first tier participant shall submit an explanation of why it cannot provide the certification set out below. The certification or explanation will be considered in connection with the department or agency's determination whether to enter into this transaction. However, failure of the prospective first tier participant to furnish a certification or an explanation shall disqualify such a person from participation in this transaction.

c. The certification in this clause is a material representation of fact upon which reliance was placed when the contracting agency determined to enter into this transaction. If it is later determined that the prospective participant knowingly rendered an erroneous certification, in addition to other remedies available to the Federal Government, the contracting agency may terminate this transaction for cause of default.

d. The prospective first tier participant shall provide immediate written notice to the contracting agency to whom this proposal is submitted if any time the prospective first tier participant learns that its certification was erroneous when submitted or has become erroneous by reason of changed circumstances.

e. The terms "covered transaction," "debarred," "suspended," "ineligible," "participant," "person," "principal," and "voluntarily excluded," as used in this clause, are defined in 2 CFR Parts 180 and 1200. "First Tier Covered Transactions" refers to any covered transaction between a grantee or subgrantee of Federal funds and a participant (such as the prime or general contract). "Lower Tier Covered Transactions" refers to any covered transaction under a First Tier Covered Transaction (such as subcontracts). "First Tier Participant" refers to the participant who has entered into a covered transaction with a grantee or subgrantee of Federal funds (such as the prime or general contractor). "Lower Tier Participant" refers any participant who has entered into a covered transaction with a First Tier Participant or other Lower Tier Participants (such as subcontractors and suppliers).

f. The prospective first tier participant agrees by submitting this proposal that, should the proposed covered transaction be entered into, it shall not knowingly enter into any lower tier covered transaction with a person who is debarred, suspended, declared ineligible, or voluntarily excluded from participation in this covered transaction, unless authorized by the department or agency entering into this transaction.

g. The prospective first tier participant further agrees by submitting this proposal that it will include the clause titled "Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion-Lower Tier Covered Transactions," provided by the department or contracting agency, entering into this covered transaction, without modification, in all lower tier covered transactions and in all solicitations for lower tier covered transactions exceeding the \$25,000 threshold.

h. A participant in a covered transaction may rely upon a certification of a prospective participant in a lower tier covered transaction that is not debarred, suspended, ineligible, or voluntarily excluded from the covered transaction, unless it knows that the certification is erroneous. A participant is responsible for ensuring that its principals are not suspended, debarred, or otherwise ineligible to participate in covered transactions. To verify the eligibility of its principals, as well as the eligibility of any lower tier prospective participants, each participant may, but is not required to, check the Excluded Parties List System website (<https://www.epls.gov/>), which is compiled by the General Services Administration.

i. Nothing contained in the foregoing shall be construed to require the establishment of a system of records in order to render in good faith the certification required by this clause. The knowledge and information of the prospective participant is not required to exceed that which is normally possessed by a prudent person in the ordinary course of business dealings.

j. Except for transactions authorized under paragraph (f) of these instructions, if a participant in a covered transaction knowingly enters into a lower tier covered transaction with a person who is suspended, debarred, ineligible, or voluntarily excluded from participation in this transaction, in addition to other remedies available to the Federal Government, the department or agency may terminate this transaction for cause or default.

* * * * *

2. Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion – First Tier Participants:

a. The prospective first tier participant certifies to the best of its knowledge and belief, that it and its principals:

(1) Are not presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from participating in covered transactions by any Federal department or agency;

(2) Have not within a three-year period preceding this proposal been convicted of or had a civil judgment rendered against them for commission of fraud or a criminal offense in connection with obtaining, attempting to obtain, or performing a public (Federal, State or local) transaction or contract under a public transaction; violation of Federal or State antitrust statutes or commission of embezzlement, theft, forgery, bribery, falsification or destruction of records, making false statements, or receiving stolen property;

(3) Are not presently indicted for or otherwise criminally or civilly charged by a governmental entity (Federal, State or local) with commission of any of the offenses enumerated in paragraph (a)(2) of this certification; and

(4) Have not within a three-year period preceding this application/proposal had one or more public transactions (Federal, State or local) terminated for cause or default.

b. Where the prospective participant is unable to certify to any of the statements in this certification, such prospective participant shall attach an explanation to this proposal.

2. Instructions for Certification - Lower Tier Participants:

(Applicable to all subcontracts, purchase orders and other lower tier transactions requiring prior FHWA approval or estimated to cost \$25,000 or more - 2 CFR Parts 180 and 1200)

a. By signing and submitting this proposal, the prospective lower tier is providing the certification set out below.

b. The certification in this clause is a material representation of fact upon which reliance was placed when this transaction was entered into. If it is later determined that the prospective lower tier participant knowingly rendered an erroneous certification, in addition to other remedies available to the Federal Government, the department, or agency with which

this transaction originated may pursue available remedies, including suspension and/or debarment.

c. The prospective lower tier participant shall provide immediate written notice to the person to which this proposal is submitted if at any time the prospective lower tier participant learns that its certification was erroneous by reason of changed circumstances.

d. The terms "covered transaction," "debarred," "suspended," "ineligible," "participant," "person," "principal," and "voluntarily excluded," as used in this clause, are defined in 2 CFR Parts 180 and 1200. You may contact the person to which this proposal is submitted for assistance in obtaining a copy of those regulations. "First Tier Covered Transactions" refers to any covered transaction between a grantee or subgrantee of Federal funds and a participant (such as the prime or general contract). "Lower Tier Covered Transactions" refers to any covered transaction under a First Tier Covered Transaction (such as subcontracts). "First Tier Participant" refers to the participant who has entered into a covered transaction with a grantee or subgrantee of Federal funds (such as the prime or general contractor). "Lower Tier Participant" refers any participant who has entered into a covered transaction with a First Tier Participant or other Lower Tier Participants (such as subcontractors and suppliers).

e. The prospective lower tier participant agrees by submitting this proposal that, should the proposed covered transaction be entered into, it shall not knowingly enter into any lower tier covered transaction with a person who is debarred, suspended, declared ineligible, or voluntarily excluded from participation in this covered transaction, unless authorized by the department or agency with which this transaction originated.

f. The prospective lower tier participant further agrees by submitting this proposal that it will include this clause titled "Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion-Lower Tier Covered Transaction," without modification, in all lower tier covered transactions and in all solicitations for lower tier covered transactions exceeding the \$25,000 threshold.

g. A participant in a covered transaction may rely upon a certification of a prospective participant in a lower tier covered transaction that is not debarred, suspended, ineligible, or voluntarily excluded from the covered transaction, unless it knows that the certification is erroneous. A participant is responsible for ensuring that its principals are not suspended, debarred, or otherwise ineligible to participate in covered transactions. To verify the eligibility of its principals, as well as the eligibility of any lower tier prospective participants, each participant may, but is not required to, check the Excluded Parties List System website (<https://www.epls.gov/>), which is compiled by the General Services Administration.

h. Nothing contained in the foregoing shall be construed to require establishment of a system of records in order to render in good faith the certification required by this clause. The knowledge and information of participant is not required to exceed that which is normally possessed by a prudent person in the ordinary course of business dealings.

i. Except for transactions authorized under paragraph e of these instructions, if a participant in a covered transaction knowingly enters into a lower tier covered transaction with a person who is suspended, debarred, ineligible, or voluntarily excluded from participation in this transaction, in addition to other remedies available to the Federal Government, the

department or agency with which this transaction originated may pursue available remedies, including suspension and/or debarment.

* * * * *

Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion--Lower Tier Participants:

1. The prospective lower tier participant certifies, by submission of this proposal, that neither it nor its principals is presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from participating in covered transactions by any Federal department or agency.

2. Where the prospective lower tier participant is unable to certify to any of the statements in this certification, such prospective participant shall attach an explanation to this proposal.

* * * * *

XI. CERTIFICATION REGARDING USE OF CONTRACT FUNDS FOR LOBBYING

This provision is applicable to all Federal-aid construction contracts and to all related subcontracts which exceed \$100,000 (49 CFR 20).

1. The prospective participant certifies, by signing and submitting this bid or proposal, to the best of his or her knowledge and belief, that:

a. No Federal appropriated funds have been paid or will be paid, by or on behalf of the undersigned, to any person for influencing or attempting to influence an officer or employee of any Federal agency, a Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress in connection with the awarding of any Federal contract, the making of any Federal grant, the making of any Federal loan, the entering into of any cooperative agreement, and the extension, continuation, renewal, amendment, or modification of any Federal contract, grant, loan, or cooperative agreement.

b. If any funds other than Federal appropriated funds have been paid or will be paid to any person for influencing or attempting to influence an officer or employee of any Federal agency, a Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress in connection with this Federal contract, grant, loan, or cooperative agreement, the undersigned shall complete and submit Standard Form-LLL, "Disclosure Form to Report Lobbying," in accordance with its instructions.

2. This certification is a material representation of fact upon which reliance was placed when this transaction was made or entered into. Submission of this certification is a prerequisite for making or entering into this transaction imposed by 31 U.S.C. 1352. Any person who fails to file the required certification shall be subject to a civil penalty of not less than \$10,000 and not more than \$100,000 for each such failure.

3. The prospective participant also agrees by submitting its bid or proposal that the participant shall require that the language of this certification be included in all lower tier subcontracts, which exceed \$100,000 and that all such recipients shall certify and disclose accordingly.

**ATTACHMENT A - EMPLOYMENT AND MATERIALS
PREFERENCE FOR APPALACHIAN DEVELOPMENT
HIGHWAY SYSTEM OR APPALACHIAN LOCAL ACCESS
ROAD CONTRACTS**

This provision is applicable to all Federal-aid projects funded under the Appalachian Regional Development Act of 1965.

1. During the performance of this contract, the contractor undertaking to do work which is, or reasonably may be, done as on-site work, shall give preference to qualified persons who regularly reside in the labor area as designated by the DOL wherein the contract work is situated, or the subregion, or the Appalachian counties of the State wherein the contract work is situated, except:

a. To the extent that qualified persons regularly residing in the area are not available.

b. For the reasonable needs of the contractor to employ supervisory or specially experienced personnel necessary to assure an efficient execution of the contract work.

c. For the obligation of the contractor to offer employment to present or former employees as the result of a lawful collective bargaining contract, provided that the number of nonresident persons employed under this subparagraph (1c) shall not exceed 20 percent of the total number of employees employed by the contractor on the contract work, except as provided in subparagraph (4) below.

2. The contractor shall place a job order with the State Employment Service indicating (a) the classifications of the laborers, mechanics and other employees required to perform the contract work, (b) the number of employees required in each classification, (c) the date on which the participant estimates such employees will be required, and (d) any other pertinent information required by the State Employment Service to complete the job order form. The job order may be placed with the State Employment Service in writing or by telephone. If during the course of the contract work, the information submitted by the contractor in the original job order is substantially modified, the participant shall promptly notify the State Employment Service.

3. The contractor shall give full consideration to all qualified job applicants referred to him by the State Employment Service. The contractor is not required to grant employment to any job applicants who, in his opinion, are not qualified to perform the classification of work required.

4. If, within one week following the placing of a job order by the contractor with the State Employment Service, the State Employment Service is unable to refer any qualified job applicants to the contractor, or less than the number requested, the State Employment Service will forward a certificate to the contractor indicating the unavailability of applicants. Such certificate shall be made a part of the contractor's permanent project records. Upon receipt of this certificate, the contractor may employ persons who do not normally reside in the labor area to fill positions covered by the certificate, notwithstanding the provisions of subparagraph (1c) above.

5. The provisions of 23 CFR 633.207(e) allow the contracting agency to provide a contractual preference for the use of mineral resource materials native to the Appalachian region.

6. The contractor shall include the provisions of Sections 1 through 4 of this Attachment A in every subcontract for work which is, or reasonably may be, done as on-site work.

Non-discrimination Provisions

During the performance of this contract, the contractor, for itself, its assignees, and successors in interest (hereinafter referred to as the "contractor") agrees as follows:

1. Compliance with Regulations: The contractor (hereinafter includes consultants) will comply with the Acts and the Regulations relative to Non-discrimination in Federally-assisted programs of the U.S. Department of Transportation, Federal Highway Administration, as they may be amended from time to time, which are herein incorporated by reference and made a part of this contract.

2. Non-discrimination: The contractor, with regard to the work performed by it during the contract, will not discriminate on the grounds of race, color, or national origin in the selection and retention of subcontractors, including procurements of materials and leases of equipment. The contractor will not participate directly or indirectly in the discrimination prohibited by the Acts and the Regulations, including employment practices when the contract covers any activity, project, or program set forth in Appendix B of 49 CFR Part 21.

3. Solicitations for Subcontracts, Including Procurements of Materials and Equipment: In all solicitations, either by competitive bidding, or negotiation made by the contractor for work to be performed under a subcontract, including procurements of materials, or leases of equipment, each potential subcontractor or supplier will be notified by the contractor of the contractor's obligations under this contract and the Acts and the Regulations relative to Non-discrimination on the grounds of race, color, or national origin.

4. Information and Reports: The contractor will provide all information and reports required by the Acts, the Regulations, and directives issued pursuant thereto and will permit access to its books, records, accounts, other sources of information, and its facilities as may be determined by the Recipient or the Federal Highway Administration to be pertinent to ascertain compliance with such Acts, Regulations, and instructions. Where any information required of a contractor is in the exclusive possession of another who fails or refuses to furnish the information, the contractor will so certify to the Recipient or the Federal Highway Administration, as appropriate, and will set forth what efforts it has made to obtain the information.

5. Sanctions for Noncompliance: In the event of a contractor's noncompliance with the Non-discrimination provisions of this contract, the Recipient will impose such contract sanctions as it or the Federal Highway Administration may determine to be appropriate, including, but not limited to:

- a. Withholding payments to the contractor under the contract until the contractor complies; and/or
- b. Cancelling, terminating, or suspending a contract, in whole or in part.

6. Incorporation of Provisions: The contractor will include the provisions of paragraphs one through six in every subcontract, including procurements of materials and leases of equipment, unless exempt by the Acts, the Regulations and directives issued pursuant thereto. The contractor will take action with respect to any subcontract or procurement as the Recipient or the Federal Highway Administration may direct as a means of enforcing such provisions including sanctions for noncompliance. Provided, that if the contractor becomes involved in, or is threatened with litigation by a subcontractor, or supplier because of such direction, the contractor may request the Recipient to enter into any litigation to protect the interests of the Recipient. In addition, the contractor may request the United States to enter into the litigation to protect the interests of the United States.

During the performance of this contract, the contractor, for itself, its assignees, and successors in interest (hereinafter referred to as the "contractor") agrees to comply with the following non-discrimination statutes and authorities; including but not limited to:

Pertinent Non-Discrimination Authorities:

- Title VI of the Civil Rights Act of 1964 (42 U.S.C. § 2000d et seq., 78 stat. 252), (prohibits discrimination on the basis of race, color, national origin); and 49 CFR Part 21.
- The Uniform Relocation Assistance and Real Property Acquisition Policies Act of 1970, (42 U.S.C. § 4601), (prohibits unfair treatment of persons displaced or whose property has been acquired because of Federal or Federal-aid programs and projects);
- Federal-Aid Highway Act of 1973, (23 U.S.C. § 324 et seq.), (prohibits discrimination on the basis of sex);
- Section 504 of the Rehabilitation Act of 1973, (29 U.S.C. § 794 et seq.), as amended, (prohibits discrimination on the basis of disability); and 49 CFR Part 27;
- The Age Discrimination Act of 1975, as amended, (42 U.S.C. § 6101 et seq.), (prohibits discrimination on the basis of age);
- Airport and Airway Improvement Act of 1982, (49 USC § 471, Section 47123), as amended, (prohibits discrimination based on race, creed, color, national origin, or sex);
- The Civil Rights Restoration Act of 1987, (PL 100-209), (Broadened the scope, coverage and applicability of Title VI of the Civil Rights Act of 1964, The Age Discrimination Act of 1975 and Section 504 of the Rehabilitation Act of 1973, by expanding the definition of the terms "programs or activities" to include all of the programs or activities of the Federal-aid recipients, sub-recipients and contractors, whether such programs or activities are Federally funded or not);
- Titles II and III of the Americans with Disabilities Act, which prohibit discrimination on the basis of disability in the operation of public entities, public and private transportation systems, places of public accommodation, and certain testing entities (42 U.S.C. §§ 12131-12189) as implemented by Department of Transportation regulations at 49 C.F.R. parts 37 and 38;
- The Federal Aviation Administration's Non-discrimination statute (49 U.S.C. § 47123) (prohibits discrimination on the basis of race, color, national origin, and sex);

- Executive Order 12898, Federal Actions to Address Environmental Justice in Minority Populations and Low-Income Populations, which ensures Non-discrimination against minority populations by discouraging programs, policies, and activities with disproportionately high and adverse human health or environmental effects on minority and low-income populations;
- Executive Order 13166, Improving Access to Services for Persons with Limited English Proficiency, and resulting agency guidance, national origin discrimination includes discrimination because of Limited English proficiency (LEP). To ensure compliance with Title VI, you must take reasonable steps to ensure that LEP persons have meaningful access to your programs (70 Fed. Reg. at 74087 to 74100);
- Title IX of the Education Amendments of 1972, as amended, which prohibits you from discriminating because of sex in education programs or activities (20 U.S.C. 1681 et seq).

SEPTEMBER 2002

**NOTICE OF REQUIREMENT FOR AFFIRMATIVE ACTION TO ENSURE
EQUAL EMPLOYMENT OPPORTUNITY (EXECUTIVE ORDER 11246)**

1. The Offeror's or Bidder's attention is called to the "Employment Practices" and "Equal Opportunity Clause" set forth in the Required Contract Provisions, FHWA 1273.
2. The goals and timetables for minority and female participation expressed in percentage terms for the contractor's aggregate work force in each trade, on all construction work in the covered area, are as follows:

Goals for Minority Participation for Each Trade:

<u>County</u>	<u>%</u>	<u>County</u>	<u>%</u>	<u>County</u>	<u>%</u>
Adams	1.7	Iowa	1.7	Polk	2.2
Ashland	1.2	Iron	1.2	Portage	0.6
Barron	0.6	Jackson	0.6	Price	0.6
Bayfield	1.2	Jefferson	7.0	Racine	8.4
Brown	1.3	Juneau	0.6	Richland	1.7
Buffalo	0.6	Kenosha	3.0	Rock	3.1
Burnett	2.2	Kewaunee	1.0	Rusk	0.6
Calumet	0.9	La Crosse	0.9	St. Croix	2.9
Chippewa	0.5	Lafayette	0.5	Sauk	1.7
Clark	0.6	Langlade	0.6	Sawyer	0.6
Columbia	1.7	Lincoln	0.6	Shawano	1.0
Crawford	0.5	Manitowoc	1.0	Sheboygan	7.0
Dane	2.2	Marathon	0.6	Taylor	0.6
Dodge	7.0	Marinette	1.0	Trempealeau	0.6
Door	1.0	Marquette	1.7	Vernon	0.6
Douglas	1.0	Menominee	1.0	Vilas	0.6
Dunn	0.6	Milwaukee	8.0	Walworth	7.0
Eau Claire	0.5	Monroe	0.6	Washburn	0.6
Florence	1.0	Oconto	1.0	Washington	8.0
Fond du Lac	1.0	Oneida	0.6	Waukesha	8.0
Forest	1.0	Outagamie	0.9	Waupaca	1.0
Grant	0.5	Ozaukee	8.0	Waushara	1.0
Green	1.7	Pepin	0.6	Winnebago	0.9
Green Lake	1.0	Pierce	2.2	Wood	0.6

Goals for female participation for each trade: 6.9%

These goals are applicable to all the contractor's construction work, (whether or not it is federal or federally assisted), performed in the covered area. If the contractor performs construction work in the geographical area located outside of the covered area, it shall apply the goals established for such geographical area where the work is actually performed. With regard to this second area, the contractor also is subject to the goals for both its federally involved and nonfederally involved construction.

The contractor's compliance with the Executive Order and the Regulations in 41 CFR Part 60-4 shall be based on its implementation of the Equal Opportunity Clause, specific affirmative action obligations required by the specifications set forth in 41 CFR 60-4.3(a), and its efforts to meet the goals. The hours of minority and female employment and training must be substantially uniform throughout the length of the contract, and in each trade, and the contractor shall make a good faith effort to employ minorities and women evenly on each of its projects. The transfer of minority or female employees or trainees from contractor to contractor or from project to project for the sole purpose of meeting the contractor's goals shall be a violation of the contract, the Executive Order and the Regulations in 41 CFR Part 60-4. Compliance with the goals will be measured against the total work hours performed.

3. The contractor shall provide written notification to the Director of the Office of Federal Contract Compliance Programs within ten (10) working days of award of any construction subcontract in excess of \$10,000.00 at any tier for construction work under the contract resulting from this solicitation. The notification shall list the name, address and telephone number of the subcontractor, employer identification number of the subcontractor; estimated dollar amount of the subcontract; estimated starting and completion dates of the subcontract; and the geographical area in which the subcontract is to be performed.

As referred to in this section, the Director means:

Director
Office of Federal Contract Compliance Programs
Ruess Federal Plaza
310 W. Wisconsin Ave., Suite 1115
Milwaukee, WI 53202

The "Employer Identification Number" means the Federal Social Security number used on the Employer's Quarterly Federal Tax Return, U.S. Treasury Department Form 941.

4. As used in this notice, and in the contract resulting from solicitation, the "covered area" is the county(ies) in Wisconsin to which this proposal applies.

APRIL 2013

ADDITIONAL FEDERAL-AID PROVISIONS

NOTICE TO ALL BIDDERS

To report bid rigging activities call:

1-800-424-9071

The U.S. Department of Transportation (DOT) operates the above toll-free "hotline" Monday through Friday, 8:00 a.m. to 5:00 p.m., Eastern Time. Anyone with knowledge of possible bid rigging, bidding collusion, or other fraudulent activities should use the "hotline" to report such activities.

The "hotline" is part of the DOT's continuing effort to identify and investigate highway construction contract fraud and abuse and is operated under the direction of the DOT Inspector General. All information will be treated confidentially and caller anonymity will be respected.

Effective August 2015 letting

BUY AMERICA PROVISION

All steel and iron materials permanently incorporated in this project shall be domestic products and all manufacturing and coating processes for these materials from smelting forward in the manufacturing process must have occurred within the United States. Coating includes epoxy coating, galvanizing, painting and any other coating that protects or enhances the value of a material subject to the requirements of Buy America. The exemption of this requirement is the minimal use of foreign materials if the total cost of such material permanently incorporated in the product does not exceed one-tenth of one percent (1/10 of 1%) of the total contract cost or \$2,500.00, whichever is greater. For purposes of this paragraph, the cost is that shown to be the value of the subject products as they are delivered to the project. The contractor shall take actions and provide documentation conforming to CMM 2-28.5 to ensure compliance with this "Buy America" provision.

<https://wisconsindot.gov/rdwy/cmm/cm-02-28.pdf>

Upon completion of the project certify to the engineer, in writing using department form WS4567, that all steel, iron, and coating processes for steel or iron incorporated into the contract work conform to these "Buy America" provisions. Attach a list of exemptions and their associated costs to the certification form. Department form WS4567 is available at:

<https://wisconsindot.gov/hcciDocs/contracting-info/ws4567.doc>

Cargo Preference Act Requirement

All Federal-aid projects shall comply with 46 CFR 381.7 (a) – (b) as follows:

(a) *Agreement Clauses*. “Use of United States-flag vessels:”

(1) Pursuant to Pub. L. 664 (43 U.S.C. 1241(b)) at least 50 percent of any equipment, materials or commodities procured, contracted for or otherwise obtained with funds granted, guaranteed, loaned, or advanced by the U.S. Government under this agreement, and which may be transported by ocean vessel, shall be transported on privately owned United States-flag commercial vessels, if available.

(2) Within 20 days following the date of loading for shipments originating within the United States or within 30 working days following the date of loading for shipments originating outside the United States, a legible copy of a rated, ‘on-board’ commercial ocean bill-of-lading in English for each shipment of cargo described in paragraph (a)(1) of this section shall be furnished to both the Contracting Officer (through the prime contractor in the case of subcontractor bills-of-lading) and to the Division of National Cargo, Office of Market Development, Maritime Administration, Washington, DC 20590.”

(b) *Contractor and Subcontractor Clauses*. “Use of United States-flag vessels: The contractor agrees—”

(1) To utilize privately owned United States-flag commercial vessels to ship at least 50 percent of the gross tonnage (computed separately for dry bulk carriers, dry cargo liners, and tankers) involved, whenever shipping any equipment, material, or commodities pursuant to this contract, to the extent such vessels are available at fair and reasonable rates for United States-flag commercial vessels.

(2) To furnish within 20 days following the date of loading for shipments originating within the United States or within 30 working days following the date of loading for shipments originating outside the United States, a legible copy of a rated, ‘on-board’ commercial ocean bill-of-lading in English for each shipment of cargo described in paragraph (b) (1) of this section to both the Contracting Officer (through the prime contractor in the case of subcontractor bills-of-lading) and to the Division of National Cargo, Office of Market Development, Maritime Administration, Washington, DC 20590.

(3) To insert the substance of the provisions of this clause in all subcontracts issued pursuant to this contract.

**WISCONSIN DEPARTMENT OF TRANSPORTATION
DIVISION OF TRANSPORTATION AND SYSTEM DEVELOPMENT**

**SUPPLEMENTAL REQUIRED CONTRACT PROVISIONS
FOR PROJECTS WITH FEDERAL AID**

I. PREVAILING WAGE RATES

The attached U.S. Department of Labor (Davis-Bacon Minimum Wage Rates) furnishes the minimum prevailing wage rates pursuant to the Davis-Bacon and Related Acts. The wage rates shown are the minimum rates required by the contract to be paid during its life, however this is not a representation that labor can be obtained at these rates. It is the responsibility of bidders to inform themselves as to the local labor conditions and prospective changes or adjustments of wage rates. No increase in the contract price will be allowed or authorized on account of the payment of wage rates in excess of those listed herein.

II. COVERAGE OF TRUCK DRIVERS

Truck drivers are covered by Davis-Bacon Minimum Wage Rates in the following circumstances:

- Drivers of a contractor or subcontractor for time spent working on the site of the work.
- Drivers of a contractor or subcontractor for time spent loading and/or unloading materials and supplies on the site of the work, if such time is not de minimis. https://www.dol.gov/whd/FOH/FOH_Ch15.pdf
- Truck drivers transporting materials or supplies between a facility that is deemed part of the site of the work and the actual construction site.
- Truck drivers transporting portions of the building or work between a site established specifically for the performance of the contract where a significant portion of such building or work is constructed and the physical place where the building or work called for in the contract will remain.

Truck drivers are not covered by Davis-Bacon Minimum Wage Rates in the following circumstances:

- Material delivery truck drivers while off the site of the work.
- Drivers of a contractor or subcontractor traveling between a Davis-Bacon job and a commercial supply facility while they are off the site of the work."
- Truck drivers whose time spent on the site of the work is de minimis, such as only a few minutes at a time merely to pick up or drop off materials or supplies.

Details are available online at:

<https://www.dol.gov/whd/recovery/pwrb/Tab9.pdf>

<https://wisconsindot.gov/Pages/doing-bus/civil-rights/labornwage/trckng.aspx>

III. POSTINGS AT THE SITE OF THE WORK

In addition to the required postings furnished by the department, the contractor shall post the following in at least one conspicuous and accessible place at the site of work:

- a. A copy of the contractor's Equal Employment Opportunity Policy.

All required documents shall be posted by the first day of work and be accurate and complete. Postings must be readable, in an area where they will be noticed, and maintained until the last day of work.

IV. RESOURCES

Required information regarding compliance with federal provisions is found in the following resources:

- FHWA-1273 included in this contract
- U.S. Department of Labor Prevailing Wage Resource Book
- U.S. Department of Labor Field Operations Handbook
- U.S. Code of Federal Regulations
- Any applicable law, Act, or Executive Order enacted by the federal government at the time of the letting of this contract

General Decision Number: WI180010 12/28/2018 WI10

Superseded General Decision Number: WI20170010

State: Wisconsin

Construction Type: Highway

Counties: Wisconsin Statewide.

HIGHWAY, AIRPORT RUNWAY & TAXIWAY CONSTRUCTION PROJECTS (does not include bridges over navigable waters; tunnels; buildings in highway rest areas; and railroad construction)

Note: Under Executive Order (EO) 13658, an hourly minimum wage of \$10.35 for calendar year 2018 applies to all contracts subject to the Davis-Bacon Act for which the contract is awarded (and any solicitation was issued) on or after January 1, 2015. If this contract is covered by the EO, the contractor must pay all workers in any classification listed on this wage determination at least \$10.35 per hour (or the applicable wage rate listed on this wage determination, if it is higher) for all hours spent performing on the contract in calendar year 2018. The EO minimum wage rate will be adjusted annually. Please note that this EO applies to the above-mentioned types of contracts entered into by the federal government that are subject to the Davis-Bacon Act itself, but it does not apply to contracts subject only to the Davis-Bacon Related Acts, including those set forth at 29 CFR 5.1(a)(2)-(60). Additional information on contractor requirements and worker protections under the EO is available at www.dol.gov/whd/govcontracts.

Modification Number	Publication Date
0	01/05/2018
1	05/18/2018
2	05/25/2018
3	06/15/2018
4	06/22/2018
5	07/20/2018
6	08/03/2018
7	08/31/2018
8	09/28/2018
9	10/12/2018
10	11/30/2018
11	12/07/2018
12	12/28/2018

* BRWI0001-002 06/01/2018

CRAWFORD, JACKSON, JUNEAU, LA CROSSE, MONROE, TREMPLEAU, AND VERNON COUNTIES

	Rates	Fringes
BRICKLAYER.....	\$ 33.06	22.65

* BRWI0002-002 06/01/2018

ASHLAND, BAYFIELD, DOUGLAS, AND IRON COUNTIES

	Rates	Fringes
BRICKLAYER.....	\$ 38.87	21.26

* BRWI0002-005 06/01/2018

ADAMS, ASHLAND, BARRON, BROWN, BURNETT, CALUMET, CHIPPEWA, CLARK, COLUMBIA, DODGE, DOOR, DUNN, FLORENCE, FOND DU LAC, FOREST, GREEN LAKE, IRON, JEFFERSON, KEWAUNEE, LANGLADE, LINCOLN, MANITOWOC, MARATHON, MARINETTE, MARQUETTE, MENOMINEE, OCONTO, ONEIDA, OUTAGAMIE, POLK, PORTAGE, RUSK, ST CROIX, SAUK, SHAWANO, SHEBOYGAN, TAYLOR, VILAS, WALWORTH, WAUPACA, WAUSHARA, WINNEBAGO, AND WOOD COUNTIES

	Rates	Fringes
CEMENT MASON/CONCRETE FINISHER...	\$ 35.39	21.46

* BRWI0003-002 06/01/2018

BROWN, DOOR, FLORENCE, KEWAUNEE, MARINETTE, AND OCONTO COUNTIES

	Rates	Fringes
BRICKLAYER.....	\$ 33.44	22.27

* BRWI0004-002 06/01/2018

KENOSHA, RACINE, AND WALWORTH COUNTIES

	Rates	Fringes
BRICKLAYER.....	\$ 37.66	23.35

* BRWI0006-002 06/01/2018

ADAMS, CLARK, FOREST, LANGLADE, LINCOLN, MARATHON, MENOMINEE,
ONEIDA, PORTAGE, PRICE, TAYLOR, VILAS AND WOOD COUNTIES

	Rates	Fringes
BRICKLAYER.....	\$ 34.30	21.41

* BRWI0007-002 06/01/2018

GREEN, LAFAYETTE, AND ROCK COUNTIES

	Rates	Fringes
BRICKLAYER.....	\$ 34.82	22.59

* BRWI0008-002 06/01/2018

MILWAUKEE, OZAUKEE, WASHINGTON, AND WAUKESHA COUNTIES

	Rates	Fringes
BRICKLAYER.....	\$ 38.03	22.55

BRWI0011-002 06/01/2016

CALUMET, FOND DU LAC, MANITOWOC, AND SHEBOYGAN COUNTIES

	Rates	Fringes
BRICKLAYER.....	\$ 32.22	20.57

* BRWI0019-002 06/01/2018

BARRON, BUFFALO, BURNETT, CHIPPEWA, DUNN, EAU CLAIRE, PEPIN,
PIERCE, POLK, RUSK, ST. CROIX, SAWYER AND WASHBURN COUNTIES

	Rates	Fringes
BRICKLAYER.....	\$ 32.97	22.74

* BRWI0034-002 06/01/2018

COLUMBIA AND SAUK COUNTIES

	Rates	Fringes
BRICKLAYER.....	\$ 34.80	22.61

CARP0087-001 05/01/2016

BURNETT (W. of Hwy 48), PIERCE (W. of Hwy 29), POLK (W. of Hwys
35, 48 & 65), AND ST. CROIX (W. of Hwy 65) COUNTIES

	Rates	Fringes
Carpenter & Piledrivermen.....	\$ 36.85	18.39

CARP0252-002 06/01/2016

ADAMS, BARRON, BAYFIELD (Eastern 2/3), BROWN, BUFFALO, BURNETT (E. of Hwy 48), CALUMET, CHIPPEWA, CLARK, COLUMBIA, CRAWFORD, DANE, DODGE, DOOR, DUNN, EAU CLAIRE, FLORENCE (except area bordering Michigan State Line), FOND DU LAC, FOREST, GRANT, GREEN, GREEN LAKE, IOWA, IRON, JACKSON, JEFFERSON, JUNEAU, KEWAUNEE, LA CROSSE, LAFAYETTE, LANGLADE, LINCOLN, MANITOWOC, MARATHON, MARINETTE (except N.E. corner), MARQUETTE, MENOMINEE, MONROE, OCONTO, ONEIDA, OUTAGAMIE, PEPIN, PIERCE (E. of Hwys 29 & 65), POLK (E. of Hwys 35, 48 & 65), PORTAGE, PRICE, RICHLAND, ROCK, RUSK, SAUK, SAWYER, SHAWANO, SHEBOYGAN, ST CROIX (E. of Hwy 65), TAYLOR, TREMPLEAU, VERNON, VILAS, WALWORTH, WASHBURN, WAUPACA, WAUSHARA, WINNEBAGO, AND WOOD COUNTIES

	Rates	Fringes
CARPENTER		
CARPENTER.....	\$ 33.56	18.00
MILLWRIGHT.....	\$ 35.08	18.35
PILEDRIIVER.....	\$ 34.12	18.00

 CARP0252-010 06/01/2016

ASHLAND COUNTY

	Rates	Fringes
Carpenters		
Carpenter.....	\$ 33.56	18.00
Millwright.....	\$ 35.08	18.35
File Driver.....	\$ 34.12	18.00

 CARP0264-003 06/01/2016

KENOSHA, MILWAUKEE, OZAUCREE, RACINE, WAUKESHA, AND WASHINGTON COUNTIES

	Rates	Fringes
CARPENTER.....	\$ 35.78	22.11

 CARP0361-004 05/01/2018

BAYFIELD (West of Hwy 63) AND DOUGLAS COUNTIES

	Rates	Fringes
CARPENTER.....	\$ 36.15	20.43

 CARP2337-001 06/01/2016

ZONE A: MILWAUKEE, OZAUCREE, WAUKESHA AND WASHINGTON

ZONE B: KENOSHA & RACINE

	Rates	Fringes
PILEDRIIVERMAN		
Zone A.....	\$ 31.03	22.69
Zone B.....	\$ 31.03	22.69

 ELEC0014-002 06/04/2018

ASHLAND, BARRON, BAYFIELD, BUFFALO, BURNETT, CHIPPEWA, CLARK (except Maryville, Colby, Unity, Sherman, Fremont, Lynn & Sherwood), CRAWFORD, DUNN, EAU CLAIRE, GRANT, IRON, JACKSON, LA CROSSE, MONROE, PEPIN, PIERCE, POLK, PRICE, RICHLAND, RUSK, ST CROIX, SAWYER, TAYLOR, TREMPLEAU, VERNON, AND WASHBURN COUNTIES

	Rates	Fringes
Electricians:.....	\$ 34.21	20.46

 ELEC0014-007 06/05/2018

REMAINING COUNTIES

	Rates	Fringes
Teledata System Installer Installer/Technician.....	\$ 26.25	13.92
Low voltage construction, installation, maintenance and removal of teledata facilities (voice, data, and video) including outside plant, telephone and data inside wire, interconnect, terminal equipment, central offices, PABX, fiber optic cable and equipment, micro waves, V-SAT, bypass, CATV, WAN (wide area networks), LAN (local area networks), and ISDN (integrated systems digital network).		

ELEC0127-002 06/01/2017

KENOSHA COUNTY

	Rates	Fringes
Electricians:.....	\$ 38.50	30%+10.57

ELEC0158-002 06/04/2018

BROWN, DOOR, KEWAUNEE, MANITOWOC (except Schleswig), MARINETTE (Wausaukee and area South thereof), OCONTO, MENOMINEE (East of a line 6 miles West of the West boundary of Oconto County), SHAWANO (Except Area North of Townships of Aniwa and Hutchins) COUNTIES

	Rates	Fringes
Electricians:.....	\$ 32.50	19.68

ELEC0159-003 06/01/2018

COLUMBIA, DANE, DODGE (Area West of Hwy 26, except Chester and Emmet Townships), GREEN, LAKE (except Townships of Berlin, Seneca, and St. Marie), IOWA, MARQUETTE (except Townships of Neshkoka, Crystal Lake, Newton, and Springfield), and SAUK COUNTIES

	Rates	Fringes
Electricians:.....	\$ 39.04	21.56

ELEC0219-004 06/01/2016

FLORENCE COUNTY (Townships of Aurora, Commonwealth, Fern, Florence and Homestead) AND MARINETTE COUNTY (Township of Niagara)

	Rates	Fringes
Electricians:		
Electrical contracts over \$180,000.....	\$ 32.38	18.63
Electrical contracts under \$180,000.....	\$ 30.18	18.42

ELEC0242-005 05/16/2018

DOUGLAS COUNTY

	Rates	Fringes
Electricians:.....	\$ 36.85	26.17

ELEC0388-002 06/03/2018

ADAMS, CLARK (Colby, Freemont, Lynn, Mayville, Sherman, Sherwood, Unity), FOREST, JUNEAU, LANGLADE, LINCOLN, MARATHON, MARINETTE (Beecher, Dunbar, Goodman & Pembine), MENOMINEE (Area West of a line 6 miles West of the West boundary of Oconto County), ONEIDA, PORTAGE, SHAWANO (Aniwa and Hutchins), VILAS AND WOOD COUNTIES

	Rates	Fringes
Electricians:.....	\$ 32.55	19.02

ELEC0430-002 06/01/2018		
RACINE COUNTY (Except Burlington Township)		
	Rates	Fringes
Electricians:.....	\$ 38.78	21.49

ELEC0494-005 06/01/2018		
MILWAUKEE, OZAUKEE, WASHINGTON, AND WAUKESHA COUNTIES		
	Rates	Fringes
Electricians:.....	\$ 39.31	24.69

ELEC0494-006 06/01/2018		
CALUMET (Township of New Holstein), DODGE (East of Hwy 26 including Chester Township), FOND DU LAC, MANITOWOC (Schleswig), and SHEBOYGAN COUNTIES		
	Rates	Fringes
Electricians:.....	\$ 33.40	22.08

ELEC0494-013 06/01/2018		
DODGE (East of Hwy 26 including Chester Twp, excluding Emmet Twp), FOND DU LAC (Except Waupuin), MILWAUKEE, OZAUKEE, MANITOWOC (Schleswig), WASHINGTON, AND WAUKESHA COUNTIES		
	Rates	Fringes
Sound & Communications		
Installer.....	\$ 19.56	15.78
Technician.....	\$ 28.99	16.25
Installation, testing, maintenance, operation and servicing of all sound, intercom, telephone interconnect, closed circuit TV systems, radio systems, background music systems, language laboratories, electronic carillon, antenna distribution systems, clock and program systems and low-voltage systems such as visual nurse call, audio/visual nurse call systems, doctors entrance register systems. Includes all wire and cable carrying audio, visual, data, light and radio frequency signals. Includes the installation of conduit, wiremold, or raceways in existing structures that have been occupied for six months or more where required for the protection of the wire or cable, but does not mean a complete conduit or raceway system. work covered does not include the installation of conduit, wiremold or any raceways in any new construction, or the installation of power supply outlets by means of which external electric power is supplied to any of the foregoing equipment or products		

ELEC0577-003 06/01/2018		
CALUMET (except Township of New Holstein), GREEN LAKE (N. part including Townships of Berlin, St Marie, and Seneca), MARQUETTE (N. part including Townships of Crystal Lake, Neshkoro, Newton, and Springfield), OUTAGAMIE, WAUPACA, WAUSHARA, AND WINNEBAGO COUNTIES		
	Rates	Fringes
Electricians:.....	\$ 32.18	18.59

ELEC0890-003 06/01/2018		
DODGE (Emmet Township only), GREEN, JEFFERSON, LAFAYETTE,		

RACINE (Burlington Township), ROCK AND WALWORTH COUNTIES

	Rates	Fringes
Electricians:.....	\$ 34.15	19.63

ELEC0953-001 07/01/2015		

	Rates	Fringes
Line Construction:		
(1) Lineman.....	\$ 42.14	32% + 5.00
(2) Heavy Equipment Operator.....	\$ 40.03	32% + 5.00
(3) Equipment Operator.....	\$ 33.71	32% + 5.00
(4) Heavy Groundman Driver..	\$ 26.78	14.11
(5) Light Groundman Driver..	\$ 24.86	13.45
(6) Groundsman.....	\$ 23.18	32% + 5.00

ENGI0139-005 06/04/2018		

	Rates	Fringes
Power Equipment Operator		
Group 1.....	\$ 40.72	22.10
Group 2.....	\$ 40.22	22.10
Group 3.....	\$ 39.72	22.10
Group 4.....	\$ 39.46	22.10
Group 5.....	\$ 39.17	22.10
Group 6.....	\$ 33.27	22.10

HAZARDOUS WASTE PREMIUMS:

EPA Level "A" protection - \$3.00 per hour
 EPA Level "B" protection - \$2.00 per hour
 EPA Level "C" protection - \$1.00 per hour

POWER EQUIPMENT OPERATORS CLASSIFICATIONS

GROUP 1: Cranes, tower cranes, and derricks with or without attachments with a lifting capacity of over 100 tons; or cranes, tower cranes, and derricks with boom, leads and/or jib lengths measuring 176 feet or longer.

GROUP 2: Cranes, tower cranes and derricks with or without attachments with a lifting capacity of 100 tons or less; or cranes, tower cranes, and derricks with boom, leads, and/or jibs lengths measuring 175 feet or under and Backhoes (excavators) weighing 130,000 lbs and over; caisson rigs; pile driver; dredge operator; dredge engineer; Boat Pilot.

GROUP 3: Mechanic or welder - Heavy duty equipment; cranes with a lifting capacity of 25 tons or under; concrete breaker (manual or remote); vibratory/sonic concrete breaker; concrete laser screed; concrete slipform paver; concrete batch plant operator; concrete pvt. spreader - heavy duty (rubber tired); concrete spreader & distributor; automatic subgrader (concrete); concrete grinder & planing machine; concrete slipform curb & gutter machine; slipform concrete placer; tube finisher; hydro blaster (10,000 psi & over); bridge paver; concrete conveyor system; concrete pump; Rotec type Conveyor; stabilizing mixer (self-propelled); shoulder widener; asphalt plant engineer; bituminous paver; bump cutter & grooving machine; milling machine; screed (bituminous paver); asphalt heater, planer & scarifier; Backhoes (excavators) weighing under 130,000 lbs; grader or motor patrol; tractor (scraper, dozer, pusher, loader); scraper - rubber tired (single or twin engine); endloader; hydraulic backhoe (tractor type); trenching machine; skid rigs; tractor, side boom (heavy); drilling or boring machine (mechanical heavy); roller over 5 tons; percussion or rotary drilling machine; air track; blaster; loading machine (conveyor); tugger; boatmen; winches & A-frames; post driver; material hoist.

GROUP 4: Greaser, roller steel (5 tons or less); roller (pneumatic tired) - self propelled; tractor (mounted or towed compactors & light equipment); shouldering machine; self-propelled chip spreader; concrete spreader; finishing machine; mechanical float; curing machine; power subgrader; joint sawer (multiple blade) belting machine; burlap

machine; texturing machine; tractor endloader (rubber tired) - light; jeep digger; forklift; mulcher; launch operator; fireman, environmental burner

GROUP 5: Air compressor; power pack; vibrator hammer and extractor; heavy equipment, leadman; tank car heaters; stump chipper; curb machine operator; Concrete proportioning plants; generators; mudjack operator; rock breaker; crusher or screening plant; screed (milling machine); automatic belt conveyor and surge bin; pug mill operator; Oiler, pump (over 3 inches); Drilling Machine Tender.

GROUP 6: Off-road material hauler with or without ejector.

IRON0008-002 06/01/2017

BROWN, CALUMET, DOOR, FOND DU LAC, KEWAUNEE, MANITOWOC, MARINETTE, OCONTO, OUTAGAMI, SHAWANO, SHEBOYGAN, AND WINNEBAGO COUNTIES:

	Rates	Fringes
IRONWORKER.....	\$ 31.24	26.97
Paid Holidays: New Year's Day, Memorial Day, July 4th, Labor Day, Thanksgiving Day & Christmas Day.		

IRON0008-003 06/01/2017

KENOSHA, MILWAUKEE, OZAUKEE, RACINE, WALWORTH (N.E. 2/3), WASHINGTON, AND WAUKESHA COUNTIES

	Rates	Fringes
IRONWORKER.....	\$ 33.19	26.97
Paid Holidays: New Year's Day, Memorial Day, July 4th, Labor Day, Thanksgiving Day & Christmas Day.		

IRON0383-001 06/01/2017

ADAMS, COLUMBIA, CRAWFORD, DANE, DODGE, FLORENCE, FOREST, GRANT, GREENE, (Excluding S.E. tip), GREEN LAKE, IOWA, JEFFERSON, JUNEAU, LA CROSSE, LAFAYETTE, LANGLADE, MARATHON, MARQUETTE, MENOMINEE, MONROE, PORTAGE, RICHLAND, ROCK (Northern area, vicinity of Edgerton and Milton), SAUK, VERNON, WAUPACA, WAUSHARA, AND WOOD COUNTIES

	Rates	Fringes
IRONWORKER.....	\$ 34.50	23.82

IRON0498-005 06/01/2016

GREEN (S.E. 1/3), ROCK (South of Edgerton and Milton), and WALWORTH (S.W. 1/3) COUNTIES:

	Rates	Fringes
IRONWORKER.....	\$ 36.29	30.77

IRON0512-008 05/01/2017

BARRON, BUFFALO, CHIPPEWA, CLARK, DUNN, EAU CLAIRE, JACKSON, PEPIN, PIERCE, POLK, RUSK, ST CROIX, TAYLOR, AND TREMPLEAU COUNTIES

	Rates	Fringes
IRONWORKER.....	\$ 36.50	26.45

IRON0512-021 05/01/2017

ASHLAND, BAYFIELD, BURNETT, DOUGLAS, IRON, LINCOLN, ONEIDA,
PRICE, SAWYER, VILAS AND WASHBURN COUNTIES

	Rates	Fringes
IRONWORKER.....	\$ 32.04	26.45

LABO0113-002 06/04/2018		

MILWAUKEE AND WAUKESHA COUNTIES

	Rates	Fringes
LABORER		
Group 1.....	\$ 27.88	21.76
Group 2.....	\$ 28.03	21.76
Group 3.....	\$ 28.23	21.76
Group 4.....	\$ 28.38	21.76
Group 5.....	\$ 28.53	21.76
Group 6.....	\$ 24.37	21.76

LABORERS CLASSIFICATIONS

GROUP 1: General Laborer; Tree Trimmer; Conduit Layer;
Demolition and Wrecking Laborer; Guard Rail, Fence, and
Bridge Builder; Landscaper; Multiplate Culvert Assembler;
Stone Handler; Bituminous Worker (Shoveler, Loader, and
Utility Man); Batch Truck Dumper or Cement Handler;
Bituminous Worker (Dumper, Ironer, Smoother, and Tamper);
Concrete Handler

GROUP 2: Air Tool Operator; Joint Sawyer and Filler
(Pavement); Vibrator or Tamper Operator (Mechanical Hand
Operated); Chain Saw Operator; Demolition Burning Torch
Laborer

GROUP 3: Bituminous Worker (Raker and Luteman); Formsetter
(Curb, Sidewalk, and Pavement); Strike Off Man

GROUP 4: Line and Grade Specialist

GROUP 5: Blaster and Powderman

GROUP 6: Flagperson; traffic control person

LABO0113-003 06/04/2018

OZAUKEE AND WASHINGTON COUNTIES

	Rates	Fringes
LABORER		
Group 1.....	\$ 27.13	21.76
Group 2.....	\$ 27.23	21.76
Group 3.....	\$ 27.28	21.76
Group 4.....	\$ 27.48	21.76
Group 5.....	\$ 27.33	21.76
Group 6.....	\$ 24.22	21.76

LABORERS CLASSIFICATIONS

GROUP 1: General Laborer; Tree Trimmer; Conduit Layer;
Demolition and Wrecking Laborer; Guard Rail, Fence, and
Bridge Builder; Landscaper; Multiplate Culvert Assembler;
Stone Handler; Bituminous Worker (Shoveler, Loader, and
Utility Man); Batch Truck Dumper or Cement Handler;
Bituminous Worker (Dumper, Ironer, Smoother, and Tamper);
Concrete Handler

GROUP 2: Air Tool Operator; Joint Sawyer and Filler
(Pavement); Vibrator or Tamper Operator (Mechanical Hand
Operated);

GROUP 3: Bituminous Worker (Raker and Luteman); Formsetter
(Curb, Sidewalk, and Pavement); Strike Off Man

GROUP 4: Line and Grade Specialist

GROUP 5: Blaster; powderman

GROUP 6: Flagperson and Traffic Control Person

LABO0113-011 06/04/2018

KENOSHA AND RACINE COUNTIES

	Rates	Fringes
LABORER		
Group 1.....	\$ 26.94	21.76
Group 2.....	\$ 27.09	21.76
Group 3.....	\$ 27.29	21.76
Group 4.....	\$ 27.26	21.76
Group 5.....	\$ 27.59	21.76
Group 6.....	\$ 24.08	21.76

LABORERS CLASSIFICATIONS:

GROUP 1: General laborer; Tree Trimmer; Conduit Layer; Demolition and Wrecking Laborer; Guard Rail, Fence, and Bridge Builder; Landscaper; Multiplate Culvert Assembler; Stone Handler; Bituminous Worker (Shoveler, Loader, and Utility Man); Batch Truck Dumper or Cement Handler; Bituminous worker (Dumper, Ironer, Smoother, and Tamper); Concrete Handler

GROUP 2: Air Tool Operator; Joint Sawyer and Filler (Pavement); Vibrator or Tamper Operator (Mechanical Hand Operated); Chain Saw Operator; Demolition Burning Torch Laborer

GROUP 3: Bituminous Worker (Raker and Luteman); Formsetter (Curb, Sidewalk, and Pavement); Strike Off Man

GROUP 4: Line and Grade Specialist

GROUP 5: Blaster and Powderman

GROUP 6: Flagman; traffic control person

LABO0140-002 06/04/2018

ADAMS, ASHLAND, BARRON, BAYFIELD, BROWN, BUFFALO, BURNETT, CALUMET, CHIPPEWA, CLARK, COLUMBIA, CRAWFORD, DODGE, DOOR, DOUGLAS, DUNN, EAU CLAIRE, FLORENCE, FOND DU LAC, FOREST, GRANT, GREEN, GREEN LAKE, IRON, JACKSON, JUNEAU, IOWA, JEFFERSON, KEWAUNEE, LA CROSSE, LAFAYETTE, LANGLADE, LINCOLN, MANITOWOC, MARATHON, MARINETTE, MARQUETTE, MENOMINEE, MONROE, OCONTO, ONEIDA, OUTAGAMIE, PEPIN, PIERCE, POLK, PORTAGE, PRICE, RICHLAND, ROCK, RUSK, SAUK, SAWYER, SHAWANO, SHEBOYGAN, ST. CROIX, TAYLOR, TREMPLEAU, VERNON, VILLAS, WALWORTH, WASHBURN, WAUPACA, WAUSHARA, WINNEBAGO, AND WOOD COUNTIES

	Rates	Fringes
LABORER		
Group 1.....	\$ 31.80	17.20
Group 2.....	\$ 31.90	17.20
Group 3.....	\$ 31.95	17.20
Group 4.....	\$ 32.15	17.20
Group 5.....	\$ 32.00	17.20
Group 6.....	\$ 28.43	17.20

LABORER CLASSIFICATIONS

GROUP 1: General Laborer; Tree Trimmer; Conduit Layer; Demolition and Wrecking Laborer; Guard Rail, Fence, and Bridge Builder; Landscaper; Multiplate Culvert Assembler; Stone Handler; Bituminous Worker (Shoveler, Loader, and Utility Man); Batch Truck Dumper or Cement Handler; Bituminous Worker (Dumper, Ironer, Smoother and Tamper); Concrete Handler

GROUP 2: Air Tool Operator; Joint Sawyer and Filler (Pavement); Vibrator or Tamper Operator (Mechanical Hand Operated); Chain Saw Operator; Demolition Burning Torch

Laborer

GROUP 3: Bituminous Worker (Raker and Luteman); Formsetter
(Curb, Sidewalk and Pavement); Strike Off Man

GROUP 4: Line and Grade Specialist

GROUP 5: Blaster; powderman

GROUP 6: Flagperson; Traffic Control

LABO0464-003 06/04/2018

DANE COUNTY

	Rates	Fringes
LABORER		
Group 1.....	\$ 32.08	17..20
Group 2.....	\$ 32.18	17..20
Group 3.....	\$ 32.23	17..20
Group 4.....	\$ 32.43	17..20
Group 5.....	\$ 32.28	17..20
Group 6.....	\$ 28.43	17..20

LABORERS CLASSIFICATIONS:

GROUP 1: General Laborer; Tree Trimmer; Conduit Layer;
Demolition and Wrecking Laborer; Guard Rail, Fence, and
Bridge Builder; Landscaper; Multiplate Culvert Assembler;
Stone Handler; Bituminous Worker (Shoveler, Loader, and
Utility Man); Batch Truck Dumper or Cement Handler;
Bituminous Worker (Dumper, Ironer, Smoother, and Tamper);
Concrete Handler

GROUP 2: Air Tool Operator; Joint Sawyer and Filler
(Pavement); Vibrator or Tamper Operator (Mechanical Hand
Operated); Chain Saw Operator; Demolition Burning Torch
Laborer

GROUP 3: Bituminous Worker (Raker and Luteman); Formsetter
(Curb, Sidewalk, and Pavement); Strike Off Man

GROUP 4: Line and Grade Specialist

GROUP 5: Blaster; Powderman

GROUP 6: Flagperson and Traffic Control Person

PAIN0106-008 05/01/2017

ASHLAND, BAYFIELD, BURNETT, AND DOUGLAS COUNTIES

	Rates	Fringes
Painters:		
New:		
Brush, Roller.....	\$ 30.33	17.27
Spray, Sandblast, Steel....	\$ 30.93	17.27
Repaint:		
Brush, Roller.....	\$ 28.83	17.27
Spray, Sandblast, Steel....	\$ 29.43	17.27

PAIN0108-002 06/01/2017

RACINE COUNTY

	Rates	Fringes
Painters:		
Brush, Roller.....	\$ 33.74	18.95
Spray & Sandblast.....	\$ 34.74	18.95

PAIN0259-002 05/01/2008

BARRON, CHIPPEWA, DUNN, EAU CLAIRE, PEPIN, PIERCE, POLK, RUSK,
SAWYER, ST. CROIX, AND WASHBURN COUNTIES

	Rates	Fringes
PAINTER.....	\$ 24.11	12.15

PAIN0259-004 05/01/2015

BUFFALO, CRAWFORD, JACKSON, LA CROSSE, MONROE, TREMPPEALEAU, AND
VERNON COUNTIES

	Rates	Fringes
PAINTER.....	\$ 22.03	12.45

PAIN0781-002 06/01/2018

JEFFERSON, MILWAUKEE, OZAUKEE, WASHINGTON, AND WAUKESHA COUNTIES

	Rates	Fringes
Painters:		
Bridge.....	\$ 31.60	23.51
Brush.....	\$ 31.55	23.51
Spray & Sandblast.....	\$ 32.30	23.51

PAIN0802-002 06/01/2017

COLUMBIA, DANE, DODGE, GRANT, GREEN, IOWA, LAFAYETTE, RICHLAND,
ROCK, AND SAUK COUNTIES

	Rates	Fringes
PAINTER		
Brush.....	\$ 28.25	17.72

PREMIUM PAY:
 Structural Steel, Spray, Bridges = \$1.00 additional per
 hour.

PAIN0802-003 06/01/2017

ADAMS, BROWN, CALUMET, CLARK, DOOR, FOND DU LAC, FOREST, GREEN
LAKE, IRON, JUNEAU, KEWAUNEE, LANGLADE, LINCOLN, MANITOWOC,
MARATHON, MARINETTE, MARQUETTE, MENOMINEE, OCONTO, ONEIDA,
OUTAGAMIE, PORTAGE, PRICE, SHAWANO, SHEBOYGAN, TAYLOR, VILAS,
WAUSHARA, WAUPACA, WINNEBAGO, AND WOOD COUNTIES

	Rates	Fringes
PAINTER.....	\$ 24.89	12.05

PAIN0934-001 06/01/2017

KENOSHA AND WALWORTH COUNTIES

	Rates	Fringes
Painters:		
Brush.....	\$ 33.74	18.95
Spray.....	\$ 34.74	18.95
Structural Steel.....	\$ 33.89	18.95

PAIN1011-002 06/01/2017

FLORENCE COUNTY

	Rates	Fringes
Painters:.....	\$ 24.86	12.23

PLAS0599-010 06/01/2017

	Rates	Fringes
CEMENT MASON/CONCRETE FINISHER		
Area 1.....	\$ 39.46	17.17
Area 2 (BAC).....	\$ 35.07	19.75
Area 3.....	\$ 35.61	19.40

Area 4.....	\$ 34.70	20.51
Area 5.....	\$ 36.27	18.73
Area 6.....	\$ 32.02	22.99

AREA DESCRIPTIONS

AREA 1: BAYFIELD, DOUGLAS, PRICE, SAWYER, AND WASHBURN COUNTIES

AREA 2: ADAMS, ASHLAND, BARRON, BROWN, BURNETT, CALUMET, CHIPPEWA, CLARK, COLUMBIA, DODGE, DOOR, DUNN, FLORENCE, FOND DU LAC, FOREST, GREEN LAKE, IRON, JEFFERSON, KEWAUNEE, LANGLADE, LINCOLN, MANITOWOC, MARATHON, MARINETTE, MARQUETTE, MENOMINEE, OCONTO, ONEIDA, OUTAGAMIE, POLK, PORTAGE, RUSK, ST CROIX, SAUK, SHAWANO, SHEBOYGAN, TAYLOR, VILAS, WALWORTH, WAUPACA, WAUSHARA, WINNEBAGO, AND WOOD COUNTIES

AREA 3: BUFFALO, CRAWFORD, EAU CLAIRE, JACKSON, JUNEAU, LA CROSSE MONROE, PEPIN, PIERCE, RICHLAND, TREMPLEAU, AND VERNON COUNTIES

AREA 4: MILWAUKEE, OZAUKEE, WASHINGTON, AND WAUKESHA COUNTIES

AREA 5: DANE, GRANT, GREEN, IOWA, LAFAYETTE, AND ROCK COUNTIES

AREA 6: KENOSHA AND RACINE COUNTIES

TEAM0039-001 06/01/2018

	Rates	Fringes
TRUCK DRIVER		
1 & 2 Axles.....	\$ 28.12	21.20
3 or more Axles; Euclids Dumptor & Articulated, Truck Mechanic.....	\$ 28.27	21.20

WELL DRILLER.....	\$ 16.52	3.70

WELDERS - Receive rate prescribed for craft performing operation to which welding is incidental.

=====

Note: Executive Order (EO) 13706, Establishing Paid Sick Leave for Federal Contractors applies to all contracts subject to the Davis-Bacon Act for which the contract is awarded (and any solicitation was issued) on or after January 1, 2017. If this contract is covered by the EO, the contractor must provide employees with 1 hour of paid sick leave for every 30 hours they work, up to 56 hours of paid sick leave each year. Employees must be permitted to use paid sick leave for their own illness, injury or other health-related needs, including preventive care; to assist a family member (or person who is like family to the employee) who is ill, injured, or has other health-related needs, including preventive care; or for reasons resulting from, or to assist a family member (or person who is like family to the employee) who is a victim of, domestic violence, sexual assault, or stalking. Additional information on contractor requirements and worker protections under the EO is available at www.dol.gov/whd/govcontracts.

Unlisted classifications needed for work not included within the scope of the classifications listed may be added after award only as provided in the labor standards contract clauses (29CFR 5.5 (a) (1) (ii)).

The body of each wage determination lists the classification and wage rates that have been found to be prevailing for the cited type(s) of construction in the area covered by the wage determination. The classifications are listed in alphabetical order of "identifiers" that indicate whether the particular

rate is a union rate (current union negotiated rate for local), a survey rate (weighted average rate) or a union average rate (weighted union average rate).

Union Rate Identifiers

A four letter classification abbreviation identifier enclosed in dotted lines beginning with characters other than "SU" or "UAVG" denotes that the union classification and rate were prevailing for that classification in the survey. Example: PLUM0198-005 07/01/2014. PLUM is an abbreviation identifier of the union which prevailed in the survey for this classification, which in this example would be Plumbers. 0198 indicates the local union number or district council number where applicable, i.e., Plumbers Local 0198. The next number, 005 in the example, is an internal number used in processing the wage determination. 07/01/2014 is the effective date of the most current negotiated rate, which in this example is July 1, 2014.

Union prevailing wage rates are updated to reflect all rate changes in the collective bargaining agreement (CBA) governing this classification and rate.

Survey Rate Identifiers

Classifications listed under the "SU" identifier indicate that no one rate prevailed for this classification in the survey and the published rate is derived by computing a weighted average rate based on all the rates reported in the survey for that classification. As this weighted average rate includes all rates reported in the survey, it may include both union and non-union rates. Example: SULA2012-007 5/13/2014. SU indicates the rates are survey rates based on a weighted average calculation of rates and are not majority rates. LA indicates the State of Louisiana. 2012 is the year of survey on which these classifications and rates are based. The next number, 007 in the example, is an internal number used in producing the wage determination. 5/13/2014 indicates the survey completion date for the classifications and rates under that identifier.

Survey wage rates are not updated and remain in effect until a new survey is conducted.

Union Average Rate Identifiers

Classification(s) listed under the UAVG identifier indicate that no single majority rate prevailed for those classifications; however, 100% of the data reported for the classifications was union data. EXAMPLE: UAVG-OH-0010 08/29/2014. UAVG indicates that the rate is a weighted union average rate. OH indicates the state. The next number, 0010 in the example, is an internal number used in producing the wage determination. 08/29/2014 indicates the survey completion date for the classifications and rates under that identifier.

A UAVG rate will be updated once a year, usually in January of each year, to reflect a weighted average of the current negotiated/CBA rate of the union locals from which the rate is based.

WAGE DETERMINATION APPEALS PROCESS

1.) Has there been an initial decision in the matter? This can be:

- * an existing published wage determination
- * a survey underlying a wage determination
- * a Wage and Hour Division letter setting forth a position on a wage determination matter
- * a conformance (additional classification and rate) ruling

On survey related matters, initial contact, including requests for summaries of surveys, should be with the Wage and Hour Regional Office for the area in which the survey was conducted because those Regional Offices have responsibility for the Davis-Bacon survey program. If the response from this initial

contact is not satisfactory, then the process described in 2.) and 3.) should be followed.

With regard to any other matter not yet ripe for the formal process described here, initial contact should be with the Branch of Construction Wage Determinations. Write to:

Branch of Construction Wage Determinations
Wage and Hour Division
U.S. Department of Labor
200 Constitution Avenue, N.W.
Washington, DC 20210

2.) If the answer to the question in 1.) is yes, then an interested party (those affected by the action) can request review and reconsideration from the Wage and Hour Administrator (See 29 CFR Part 1.8 and 29 CFR Part 7). Write to:

Wage and Hour Administrator
U.S. Department of Labor
200 Constitution Avenue, N.W.
Washington, DC 20210

The request should be accompanied by a full statement of the interested party's position and by any information (wage payment data, project description, area practice material, etc.) that the requestor considers relevant to the issue.

3.) If the decision of the Administrator is not favorable, an interested party may appeal directly to the Administrative Review Board (formerly the Wage Appeals Board). Write to:

Administrative Review Board
U.S. Department of Labor
200 Constitution Avenue, N.W.
Washington, DC 20210

4.) All decisions by the Administrative Review Board are final.

=====

END OF GENERAL DECISION

August 2018

NOTICE TO BIDDERS WAGE RATE DECISION

The wage rate decision of the Department of Labor which has been incorporated in these advertised specifications is incomplete in that the classifications may be omitted from the Department of Labor's decision.

Since the bidder is responsible, independently, for ascertaining area practice with respect to the necessity, or lack of necessity, for the use of these classifications in the prosecution of the work contemplated by this project, no inference may be drawn from the omission of these classifications concerning prevailing area practices relative to their use. Further, this omission will not, per se, be construed as establishing any governmental liability for increased labor cost if it is subsequently determined that such classifications are required.

There may be omissions and/or errors in the federal wage rates. The bidder is responsible for evaluating and determining the correct applicable rate.

If a project includes multiple types of construction (highway, bridge over navigable water, sanitary sewer and water main, building) and there is not a separate wage determination for this type of work included in the proposal, use the wage determination that is in the proposal.

If a project includes multiple types of construction, different wage rate determinations may be inserted into the contract (WI10/Highway = in all WisDOT highway contracts, WI15/Heavy = bridge over navigable water per USDOL and US Coast Guard designation, WI8/Heavy (Sewer & Water Line & Tunnel) = sanitary sewer and water main if the cost is more than 20% of the contract and/or at least \$1,000,000, and Building). If multiple wage rate determinations are inserted into the contract, use the classification in the wage determination for the work being done. Use WI15 wage rates when working on the bridge and/or structure from bank to bank. Use WI8 wage rates when working on any sanitary sewer or water main work. Use Building wage rates for all work done within the footprint of the building. Use WI10 wage rates for all other highway work in the contract and approaches to structures. For example, if a laborer is working within the footprint of a building, use the Laborer rate in the Building wage determination inserted in the contract. If a laborer is working on a bridge/structure within the banks, use the Laborer rate in the WI15/Heavy wage determination if inserted in the contract. If the laborer is working on the highway, use the Laborer rate in the WI10/Highway wage determination.



Proposal Schedule of Items

Page 1 of 11

Proposal ID: 20190212006 Project(s): 1517-75-77

Federal ID(s): WISC 2019120

SECTION: 0001

Contact Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0002	201.0105 Clearing	3.000 STA	_____.	_____.
0004	201.0120 Clearing	126.000 ID	_____.	_____.
0006	201.0205 Grubbing	3.000 STA	_____.	_____.
0008	201.0220 Grubbing	126.000 ID	_____.	_____.
0010	203.0100 Removing Small Pipe Culverts	1.000 EACH	_____.	_____.
0012	204.0100 Removing Pavement	15,591.000 SY	_____.	_____.
0014	204.0115 Removing Asphaltic Surface Butt Joints	143.000 SY	_____.	_____.
0016	204.0120 Removing Asphaltic Surface Milling	13,479.000 SY	_____.	_____.
0018	204.0150 Removing Curb & Gutter	262.000 LF	_____.	_____.
0020	204.0165 Removing Guardrail	257.000 LF	_____.	_____.
0022	204.0185 Removing Masonry	11.000 CY	_____.	_____.
0024	204.0190 Removing Surface Drains	4.000 EACH	_____.	_____.
0026	204.0210 Removing Manholes	8.000 EACH	_____.	_____.
0028	204.0220 Removing Inlets	22.000 EACH	_____.	_____.
0030	204.0245 Removing Storm Sewer (size) 001. 6-15 Inches	472.000 LF	_____.	_____.
0032	204.0245 Removing Storm Sewer (size) 002. 18-21 Inches	196.000 LF	_____.	_____.



Proposal Schedule of Items

Page 2 of 11

Proposal ID: 20190212006 Project(s): 1517-75-77

Federal ID(s): WISC 2019120

SECTION: 0001

Contact Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0034	204.0245 Removing Storm Sewer (size) 003. 24-30 Inches	667.000 LF	_____.	_____.
0036	204.0245 Removing Storm Sewer (size) 004. 36-42 Inches	1,573.000 LF	_____.	_____.
0038	205.0100 Excavation Common	35,922.000 CY	_____.	_____.
0040	209.0200.S Backfill Controlled Low Strength	30.000 CY	_____.	_____.
0042	210.1100 Backfill Structure Type A	56.000 CY	_____.	_____.
0044	213.0100 Finishing Roadway (project) 001. 1517-75-77	1.000 EACH	_____.	_____.
0046	305.0110 Base Aggregate Dense 3/4-Inch	157.000 TON	_____.	_____.
0048	305.0120 Base Aggregate Dense 1 1/4-Inch	9,728.000 TON	_____.	_____.
0050	311.0110 Breaker Run	16,275.000 TON	_____.	_____.
0052	405.0200 Coloring Concrete Custom 001. Color 10076	153.000 CY	_____.	_____.
0054	415.4100 Concrete Pavement Joint Filling	24,167.000 SY	_____.	_____.
0056	415.5110.S Concrete Pavement Joint Layout	1.000 LS	_____.	_____.
0058	416.0160 Concrete Driveway 6-Inch	56.000 SY	_____.	_____.
0060	416.0170 Concrete Driveway 7-Inch	64.000 SY	_____.	_____.
0062	416.0610 Drilled Tie Bars	10.000 EACH	_____.	_____.
0064	416.0620 Drilled Dowel Bars	113.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 3 of 11

Proposal ID: 20190212006 Project(s): 1517-75-77

Federal ID(s): WISC 2019120

SECTION: 0001

Contact Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0066	455.0605 Tack Coat	1,029.000 GAL	_____.	_____.
0068	460.2000 Incentive Density HMA Pavement	1,470.000 DOL	1.00000	1,470.00
0070	460.6223 HMA Pavement 3 MT 58-28 S	94.000 TON	_____.	_____.
0072	460.6424 HMA Pavement 4 MT 58-28 H	2,250.000 TON	_____.	_____.
0074	465.0120 Asphaltic Surface Driveways and Field Entrances	40.000 TON	_____.	_____.
0076	465.0315 Asphaltic Flumes	39.000 SY	_____.	_____.
0078	520.8000 Concrete Collars for Pipe	2.000 EACH	_____.	_____.
0080	522.1012 Apron Endwalls for Culvert Pipe Reinforced Concrete 12-Inch	1.000 EACH	_____.	_____.
0082	522.1018 Apron Endwalls for Culvert Pipe Reinforced Concrete 18-Inch	2.000 EACH	_____.	_____.
0084	522.1024 Apron Endwalls for Culvert Pipe Reinforced Concrete 24-Inch	2.000 EACH	_____.	_____.
0086	601.0409 Concrete Curb & Gutter 30-Inch Type A	2,688.000 LF	_____.	_____.
0088	601.0411 Concrete Curb & Gutter 30-Inch Type D	121.000 LF	_____.	_____.
0090	601.0452 Concrete Curb & Gutter Integral 30-Inch Type D	7,175.000 LF	_____.	_____.
0092	601.0600 Concrete Curb Pedestrian	80.000 LF	_____.	_____.
0094	602.0410 Concrete Sidewalk 5-Inch	28,961.000 SF	_____.	_____.



Proposal Schedule of Items

Page 4 of 11

Proposal ID: 20190212006 Project(s): 1517-75-77

Federal ID(s): WISC 2019120

SECTION: 0001

Contact Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0096	602.0515 Curb Ramp Detectable Warning Field Natural Patina	160.000 SF	_____.	_____.
0098	602.0615 Curb Ramp Detectable Warning Field Radial Natural Patina	76.000 SF	_____.	_____.
0100	603.1442 Concrete Barrier Type S42C	150.000 LF	_____.	_____.
0102	603.3513 Concrete Barrier Transition Type S32 to S36	2.000 EACH	_____.	_____.
0104	603.3535 Concrete Barrier Transition Type S36 to S42	2.000 EACH	_____.	_____.
0106	604.0400 Slope Paving Concrete	945.000 SY	_____.	_____.
0108	608.0312 Storm Sewer Pipe Reinforced Concrete Class III 12-Inch	80.000 LF	_____.	_____.
0110	608.0318 Storm Sewer Pipe Reinforced Concrete Class III 18-Inch	702.000 LF	_____.	_____.
0112	608.0324 Storm Sewer Pipe Reinforced Concrete Class III 24-Inch	1,489.000 LF	_____.	_____.
0114	608.0336 Storm Sewer Pipe Reinforced Concrete Class III 36-Inch	743.000 LF	_____.	_____.
0116	608.0342 Storm Sewer Pipe Reinforced Concrete Class III 42-Inch	1,006.000 LF	_____.	_____.
0118	608.0412 Storm Sewer Pipe Reinforced Concrete Class IV 12-Inch	100.000 LF	_____.	_____.
0120	608.0418 Storm Sewer Pipe Reinforced Concrete Class IV 18-Inch	21.000 LF	_____.	_____.



Proposal Schedule of Items

Page 5 of 11

Proposal ID: 20190212006 Project(s): 1517-75-77

Federal ID(s): WISC 2019120

SECTION: 0001

Contact Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0122	608.2329 Storm Sewer Pipe Reinforced Concrete Horizontal Elliptical Class HE-III 29x45-Inch	86.000 LF	_____.	_____.
0124	608.2334 Storm Sewer Pipe Reinforced Concrete Horizontal Elliptical Class HE-III 34x53-Inch	28.000 LF	_____.	_____.
0126	611.0420 Reconstructing Manholes	2.000 EACH	_____.	_____.
0128	611.0530 Manhole Covers Type J	6.000 EACH	_____.	_____.
0130	611.0535 Manhole Covers Type J-Special	6.000 EACH	_____.	_____.
0132	611.0612 Inlet Covers Type C	1.000 EACH	_____.	_____.
0134	611.0624 Inlet Covers Type H	39.000 EACH	_____.	_____.
0136	611.0639 Inlet Covers Type H-S	20.000 EACH	_____.	_____.
0138	611.0642 Inlet Covers Type MS	20.000 EACH	_____.	_____.
0140	611.1005 Catch Basins 5-FT Diameter	5.000 EACH	_____.	_____.
0142	611.1006 Catch Basins 6-FT Diameter	5.000 EACH	_____.	_____.
0144	611.2006 Manholes 6-FT Diameter	7.000 EACH	_____.	_____.
0146	611.2008 Manholes 8-FT Diameter	4.000 EACH	_____.	_____.
0148	611.3004 Inlets 4-FT Diameter	22.000 EACH	_____.	_____.
0150	611.3230 Inlets 2x3-FT	26.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 6 of 11

Proposal ID: 20190212006 Project(s): 1517-75-77

Federal ID(s): WISC 2019120

SECTION: 0001

Contact Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0152	611.3901 Inlets Median 1 Grate	4.000 EACH	_____.	_____.
0154	611.3902 Inlets Median 2 Grate	8.000 EACH	_____.	_____.
0156	611.8115 Adjusting Inlet Covers	2.000 EACH	_____.	_____.
0158	612.0406 Pipe Underdrain Wrapped 6-Inch	1,840.000 LF	_____.	_____.
0160	618.0100 Maintenance And Repair of Haul Roads (project) 001. 1517-75-77	1.000 EACH	_____.	_____.
0162	619.1000 Mobilization	1.000 EACH	_____.	_____.
0164	620.0200 Concrete Median Blunt Nose	454.000 SF	_____.	_____.
0166	620.0300 Concrete Median Sloped Nose	117.000 SF	_____.	_____.
0168	624.0100 Water	139.000 MGAL	_____.	_____.
0170	625.0100 Topsoil	17,261.000 SY	_____.	_____.
0172	628.1504 Silt Fence	550.000 LF	_____.	_____.
0174	628.1520 Silt Fence Maintenance	550.000 LF	_____.	_____.
0176	628.1905 Mobilizations Erosion Control	6.000 EACH	_____.	_____.
0178	628.1910 Mobilizations Emergency Erosion Control	4.000 EACH	_____.	_____.
0180	628.2006 Erosion Mat Urban Class I Type A	17,262.000 SY	_____.	_____.
0182	628.7005 Inlet Protection Type A	13.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 7 of 11

Proposal ID: 20190212006 Project(s): 1517-75-77

Federal ID(s): WISC 2019120

SECTION: 0001

Contact Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0184	628.7010 Inlet Protection Type B	6.000 EACH	_____.	_____.
0186	628.7015 Inlet Protection Type C	120.000 EACH	_____.	_____.
0188	628.7020 Inlet Protection Type D	14.000 EACH	_____.	_____.
0190	628.7504 Temporary Ditch Checks	46.000 LF	_____.	_____.
0192	628.7555 Culvert Pipe Checks	10.000 EACH	_____.	_____.
0194	628.7560 Tracking Pads	4.000 EACH	_____.	_____.
0196	628.7570 Rock Bags	100.000 EACH	_____.	_____.
0198	629.0210 Fertilizer Type B	12.000 CWT	_____.	_____.
0200	630.0140 Seeding Mixture No. 40	318.000 LB	_____.	_____.
0202	630.0200 Seeding Temporary	476.000 LB	_____.	_____.
0204	634.0614 Posts Wood 4x6-Inch X 14-FT	29.000 EACH	_____.	_____.
0206	634.0616 Posts Wood 4x6-Inch X 16-FT	18.000 EACH	_____.	_____.
0208	634.0618 Posts Wood 4x6-Inch X 18-FT	8.000 EACH	_____.	_____.
0210	634.0620 Posts Wood 4x6-Inch X 20-FT	6.000 EACH	_____.	_____.
0212	637.2210 Signs Type II Reflective H	674.000 SF	_____.	_____.
0214	637.2215 Signs Type II Reflective H Folding	20.000 SF	_____.	_____.
0216	637.2230 Signs Type II Reflective F	44.000 SF	_____.	_____.



Proposal Schedule of Items

Page 8 of 11

Proposal ID: 20190212006 Project(s): 1517-75-77

Federal ID(s): WISC 2019120

SECTION: 0001

Contact Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0218	638.2602 Removing Signs Type II	37.000 EACH	_____.	_____.
0220	638.3000 Removing Small Sign Supports	38.000 EACH	_____.	_____.
0222	642.5201 Field Office Type C	1.000 EACH	_____.	_____.
0224	643.0310.S Temporary Portable Rumble Strips	1.000 LS	_____.	_____.
0226	643.0410 Traffic Control Barricades Type II	272.000 DAY	_____.	_____.
0228	643.0420 Traffic Control Barricades Type III	2,658.000 DAY	_____.	_____.
0230	643.0705 Traffic Control Warning Lights Type A	3,668.000 DAY	_____.	_____.
0232	643.0900 Traffic Control Signs	3,458.000 DAY	_____.	_____.
0234	643.0910 Traffic Control Covering Signs Type I	8.000 EACH	_____.	_____.
0236	643.0920 Traffic Control Covering Signs Type II	4.000 EACH	_____.	_____.
0238	643.1050 Traffic Control Signs PCMS	28.000 DAY	_____.	_____.
0240	643.5000 Traffic Control	1.000 EACH	_____.	_____.
0242	646.1020 Marking Line Epoxy 4-Inch	22,647.000 LF	_____.	_____.
0244	646.3020 Marking Line Epoxy 8-Inch	922.000 LF	_____.	_____.
0246	646.5020 Marking Arrow Epoxy	10.000 EACH	_____.	_____.
0248	646.5120 Marking Word Epoxy	3.000 EACH	_____.	_____.
0250	646.5320 Marking Railroad Crossings Epoxy	4.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 9 of 11

Proposal ID: 20190212006 Project(s): 1517-75-77

Federal ID(s): WISC 2019120

SECTION: 0001

Contact Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0252	646.7120 Marking Diagonal Epoxy 12-Inch	291.000 LF	_____.	_____.
0254	646.7420 Marking Crosswalk Epoxy Transverse Line 6-Inch	517.000 LF	_____.	_____.
0256	646.8120 Marking Curb Epoxy	243.000 LF	_____.	_____.
0258	646.8220 Marking Island Nose Epoxy	6.000 EACH	_____.	_____.
0260	652.0225 Conduit Rigid Nonmetallic Schedule 40 2-Inch	1,868.000 LF	_____.	_____.
0262	653.0164 Pull Boxes Non-Conductive 24x42-Inch	7.000 EACH	_____.	_____.
0264	653.0905 Removing Pull Boxes	2.000 EACH	_____.	_____.
0266	654.0105 Concrete Bases Type 5	3.000 EACH	_____.	_____.
0268	654.0107 Concrete Bases Type 7	6.000 EACH	_____.	_____.
0270	654.0230 Concrete Control Cabinet Bases Type L30	1.000 EACH	_____.	_____.
0272	655.0610 Electrical Wire Lighting 12 AWG	1,320.000 LF	_____.	_____.
0274	655.0615 Electrical Wire Lighting 10 AWG	2,129.000 LF	_____.	_____.
0276	655.0620 Electrical Wire Lighting 8 AWG	7,984.000 LF	_____.	_____.
0278	656.0400 Electrical Service Main Lugs Only Meter Pedestal (location) 001.CB-200	LS	LUMP SUM	_____.
0280	657.0210 Transformer Bases Breakaway 15-17 Inch Bolt Circle	6.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 10 of 11

Proposal ID: 20190212006 Project(s): 1517-75-77

Federal ID(s): WISC 2019120

SECTION: 0001

Contact Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0282	657.0255 Transformer Bases Breakaway 11 1/2-Inch Bolt Circle	3.000 EACH	_____.	_____.
0284	657.0337 Poles Type 17-Aluminum	7.000 EACH	_____.	_____.
0286	657.0730 Luminaire Arms Truss Type 6-Inch Clamp 12-FT	8.000 EACH	_____.	_____.
0288	659.1125 Luminaires Utility LED C	8.000 EACH	_____.	_____.
0290	659.2230 Lighting Control Cabinets 240/480 30-Inch	1.000 EACH	_____.	_____.
0292	662.1026.S Ramp Closure Gates Hardwired 26-FT	2.000 EACH	_____.	_____.
0294	662.1040.S Ramp Closure Gates Hardwired 40-FT	1.000 EACH	_____.	_____.
0296	690.0150 Sawing Asphalt	695.000 LF	_____.	_____.
0298	690.0250 Sawing Concrete	127.000 LF	_____.	_____.
0300	715.0415 Incentive Strength Concrete Pavement	6,440.000 DOL	1.00000	6,440.00
0302	715.0710 Optimized Aggregate Gradation Incentive	12,871.800 DOL	1.00000	12,871.80
0304	740.0440 Incentive IRI Ride	2,950.000 DOL	1.00000	2,950.00
0306	ASP.1T0A On-the-Job Training Apprentice at \$5.00/HR	2,000.000 HRS	5.00000	10,000.00
0308	ASP.1T0G On-the-Job Training Graduate at \$5.00/HR	1,320.000 HRS	5.00000	6,600.00
0310	SPV.0035 Special 001. Roadway Embankment	1,241.000 CY	_____.	_____.



Proposal Schedule of Items

Page 11 of 11

Proposal ID: 20190212006 Project(s): 1517-75-77

Federal ID(s): WISC 2019120

SECTION: 0001

Contact Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0312	SPV.0060 Special 100. Manhole 10-FT Diameter	1.000 EACH	_____.	_____.
0314	SPV.0060 Special 250. Remove Commerical Sign	1.000 EACH	_____.	_____.
0316	SPV.0060 Special 650. Adjusting Sanitary Manhole Covers	10.000 EACH	_____.	_____.
0318	SPV.0075 Special 001. Street Sweeping	34.000 HRS	_____.	_____.
0320	SPV.0090 Special 651. Sanitary Lateral 4-Inch	50.000 LF	_____.	_____.
0322	SPV.0105 Special 002. Survey Project 1517-75-77	LS	LUMP SUM	_____.
0324	SPV.0120 Special 150. Water for Seeded Areas	396.000 MGAL	_____.	_____.
0326	SPV.0180 Special 001. Modified High Performance Concrete (HPC) Pavement 9-Inch	21,453.000 SY	_____.	_____.
0328	SPV.0180 Special 002. Removing Crushed Aggregate Slope Paving	705.000 SY	_____.	_____.

Section: 0001

Total:

_____.

Total Bid:

_____.

PLEASE ATTACH SCHEDULE OF ITEMS HERE



Wisconsin Department of Transportation

February 4, 2019

**Division of Transportation Systems
Development**

Bureau of Project Development
4802 Sheboygan Avenue, Rm 601
P O Box 7916
Madison, WI 53707-7916

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

Federal Wage Rate Addendum #01

Letting of February 12, 2019

Attached is a copy of the revised WI 10 Highway Davis Bacon Prevailing Wage Rates that are included in proposals 01 – 03, 05 – 08, 10 – 12, 14, 15, 19, 20, 24, and 26 - 28; and WI 15 Heavy Davis Bacon Prevailing Wage Rates that are included in proposal 28. These wage rates are effective for all proposals they are included in in the February 12, 2019 letting. The updated wage rates are dated January 4, 2019 and are effective on or after January 14, 2019.

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractors.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

General Decision Number: WI190010 01/04/2019 WI10

Superseded General Decision Number: WI20180010

State: Wisconsin

Construction Type: Highway

Counties: Wisconsin Statewide.

HIGHWAY, AIRPORT RUNWAY & TAXIWAY CONSTRUCTION PROJECTS (does not include bridges over navigable waters; tunnels; buildings in highway rest areas; and railroad construction)

Note: Under Executive Order (EO) 13658, an hourly minimum wage of \$10.60 for calendar year 2019 applies to all contracts subject to the Davis-Bacon Act for which the contract is awarded (and any solicitation was issued) on or after January 1, 2015. If this contract is covered by the EO, the contractor must pay all workers in any classification listed on this wage determination at least \$10.60 per hour (or the applicable wage rate listed on this wage determination, if it is higher) for all hours spent performing on the contract in calendar year 2019. If this contract is covered by the EO and a classification considered necessary for performance of work on the contract does not appear on this wage determination, the contractor must pay workers in that classification at least the wage rate determined through the conformance process set forth in 29 CFR 5.5(a)(1)(ii) (or the EO minimum wage rate, if it is higher than the conformed wage rate). The EO minimum wage rate will be adjusted annually. Please note that this EO applies to the above-mentioned types of contracts entered into by the federal government that are subject to the Davis-Bacon Act itself, but it does not apply to contracts subject only to the Davis-Bacon Related Acts, including those set forth at 29 CFR 5.1(a)(2)-(60). Additional information on contractor requirements and worker protections under the EO is available at www.dol.gov/whd/govcontracts.

Modification Number	Publication Date
0	01/04/2019

* BRWI0001-002 06/01/2018

CRAWFORD, JACKSON, JUNEAU, LA CROSSE, MONROE, TREMPLEAU, AND VERNON COUNTIES

	Rates	Fringes
BRICKLAYER.....	\$ 33.06	22.65

* BRWI0002-002 06/01/2018

ASHLAND, BAYFIELD, DOUGLAS, AND IRON COUNTIES

	Rates	Fringes
BRICKLAYER.....	\$ 38.87	21.26

* BRWI0002-005 06/01/2018

ADAMS, ASHLAND, BARRON, BROWN, BURNETT, CALUMET, CHIPPEWA, CLARK, COLUMBIA, DODGE, DOOR, DUNN, FLORENCE, FOND DU LAC, FOREST, GREEN LAKE, IRON, JEFFERSON, KEWAUNEE, LANGLADE, LINCOLN, MANITOWOC, MARATHON, MARINETTE, MARQUETTE, MENOMINEE, OCONTO, ONEIDA, OUTAGAMIE, POLK, PORTAGE, RUSK, ST CROIX, SAUK, SHAWANO, SHEBOYGAN, TAYLOR, VILAS, WALWORTH, WAUPACA, WAUSHARA, WINNEBAGO, AND WOOD COUNTIES

	Rates	Fringes
CEMENT MASON/CONCRETE FINISHER...	\$ 35.39	21.46

* BRWI0003-002 06/01/2018

BROWN, DOOR, FLORENCE, KEWAUNEE, MARINETTE, AND OCONTO COUNTIES

	Rates	Fringes
BRICKLAYER.....	\$ 33.44	22.27

* BRWI0004-002 06/01/2018		

KENOSHA, RACINE, AND WALWORTH COUNTIES

	Rates	Fringes
BRICKLAYER.....	\$ 37.66	23.35

* BRWI0006-002 06/01/2018		

ADAMS, CLARK, FOREST, LANGLADE, LINCOLN, MARATHON, MENOMINEE, ONEIDA, PORTAGE, PRICE, TAYLOR, VILAS AND WOOD COUNTIES

	Rates	Fringes
BRICKLAYER.....	\$ 34.30	21.41

* BRWI0007-002 06/01/2018		

GREEN, LAFAYETTE, AND ROCK COUNTIES

	Rates	Fringes
BRICKLAYER.....	\$ 34.82	22.59

* BRWI0008-002 06/01/2018		

MILWAUKEE, OZAUKEE, WASHINGTON, AND WAUKESHA COUNTIES

	Rates	Fringes
BRICKLAYER.....	\$ 38.03	22.55

BRWI0011-002 06/01/2016		

CALUMET, FOND DU LAC, MANITOWOC, AND SHEBOYGAN COUNTIES

	Rates	Fringes
BRICKLAYER.....	\$ 32.22	20.57

* BRWI0019-002 06/01/2018		

BARRON, BUFFALO, BURNETT, CHIPPEWA, DUNN, EAU CLAIRE, PEPIN, PIERCE, POLK, RUSK, ST. CROIX, SAWYER AND WASHBURN COUNTIES

	Rates	Fringes
BRICKLAYER.....	\$ 32.97	22.74

* BRWI0034-002 06/01/2018		

COLUMBIA AND SAUK COUNTIES

	Rates	Fringes
BRICKLAYER.....	\$ 34.80	22.61

CARP0087-001 05/01/2016		

BURNETT (W. of Hwy 48), PIERCE (W. of Hwy 29), POLK (W. of Hwys 35, 48 & 65), AND ST. CROIX (W. of Hwy 65) COUNTIES

	Rates	Fringes
Carpenter & Piledrivermen.....	\$ 36.85	18.39

CARP0252-002 06/01/2016		

ADAMS, BARRON, BAYFIELD (Eastern 2/3), BROWN, BUFFALO, BURNETT (E. of Hwy 48), CALUMET, CHIPPEWA, CLARK, COLUMBIA, CRAWFORD, DANE, DODGE, DOOR, DUNN, EAU CLAIRE, FLORENCE (except

area bordering Michigan State Line), FOND DU LAC, FOREST, GRANT, GREEN, GREEN LAKE, IOWA, IRON, JACKSON, JEFFERSON, JUNEAU, KEWAUNEE, LA CROSSE, LAFAYETTE, LANGLADE, LINCOLN, MANITOWOC, MARATHON, MARINETTE (except N.E. corner), MARQUETTE, MENOMINEE, MONROE, OCONTO, ONEIDA, OUTAGAMIE, PEPIN, PIERCE (E. of Hwys 29 & 65), POLK (E. of Hwys 35, 48 & 65), PORTAGE, PRICE, RICHLAND, ROCK, RUSK, SAUK, SAWYER, SHAWANO, SHEBOYGAN, ST CROIX (E. of Hwy 65), TAYLOR, TREMPLEALEAU, VERNON, VILAS, WALWORTH, WASHBURN, WAUPACA, WAUSHARA, WINNEBAGO, AND WOOD COUNTIES

	Rates	Fringes
CARPENTER		
CARPENTER.....	\$ 33.56	18.00
MILLWRIGHT.....	\$ 35.08	18.35
PILEDRIIVER.....	\$ 34.12	18.00

CARP0252-010 06/01/2016		

ASHLAND COUNTY

	Rates	Fringes
Carpenters		
Carpenter.....	\$ 33.56	18.00
Millwright.....	\$ 35.08	18.35
File Driver.....	\$ 34.12	18.00

CARP0264-003 06/01/2016		

KENOSHA, MILWAUKEE, OZAUKEE, RACINE, WAUKESHA, AND WASHINGTON COUNTIES

	Rates	Fringes
CARPENTER.....	\$ 35.78	22.11

CARP0361-004 05/01/2018		

BAYFIELD (West of Hwy 63) AND DOUGLAS COUNTIES

	Rates	Fringes
CARPENTER.....	\$ 36.15	20.43

CARP2337-001 06/01/2016		

ZONE A: MILWAUKEE, OZAUKEE, WAUKESHA AND WASHINGTON

ZONE B: KENOSHA & RACINE

	Rates	Fringes
PILEDRIIVERMAN		
Zone A.....	\$ 31.03	22.69
Zone B.....	\$ 31.03	22.69

ELEC0014-002 06/04/2018		

ASHLAND, BARRON, BAYFIELD, BUFFALO, BURNETT, CHIPPEWA, CLARK (except Maryville, Colby, Unity, Sherman, Fremont, Lynn & Sherwood), CRAWFORD, DUNN, EAU CLAIRE, GRANT, IRON, JACKSON, LA CROSSE, MONROE, PEPIN, PIERCE, POLK, PRICE, RICHLAND, RUSK, ST CROIX, SAWYER, TAYLOR, TREMPLEALEAU, VERNON, AND WASHBURN COUNTIES

	Rates	Fringes
Electricians:.....	\$ 34.21	20.46

ELEC0014-007 06/05/2018		

REMAINING COUNTIES

Rates	Fringes
-------	---------

Teledata System Installer
Installer/Technician.....\$ 26.25 13.92

Low voltage construction, installation, maintenance and removal of teledata facilities (voice, data, and video) including outside plant, telephone and data inside wire, interconnect, terminal equipment, central offices, PABX, fiber optic cable and equipment, micro waves, V-SAT, bypass, CATV, WAN (wide area networks), LAN (local area networks), and ISDN (integrated systems digital network).

ELEC0127-002 06/01/2017

KENOSHA COUNTY

	Rates	Fringes
Electricians:.....	\$ 38.50	30%+10.57

ELEC0158-002 06/04/2018

BROWN, DOOR, KEWAUNEE, MANITOWOC (except Schleswig), MARINETTE (Wausaukee and area South thereof), OCONTO, MENOMINEE (East of a line 6 miles West of the West boundary of Oconto County), SHAWANO (Except Area North of Townships of Aniwa and Hutchins) COUNTIES

	Rates	Fringes
Electricians:.....	\$ 32.50	19.68

ELEC0159-003 06/01/2018

COLUMBIA, DANE, DODGE (Area West of Hwy 26, except Chester and Emmet Townships), GREEN, LAKE (except Townships of Berlin, Seneca, and St. Marie), IOWA, MARQUETTE (except Townships of Neshkoka, Crystal Lake, Newton, and Springfield), and SAUK COUNTIES

	Rates	Fringes
Electricians:.....	\$ 39.04	21.56

ELEC0219-004 06/01/2016

FLORENCE COUNTY (Townships of Aurora, Commonwealth, Fern, Florence and Homestead) AND MARINETTE COUNTY (Township of Niagara)

	Rates	Fringes
Electricians:		
Electrical contracts over \$180,000.....	\$ 32.38	18.63
Electrical contracts under \$180,000.....	\$ 30.18	18.42

ELEC0242-005 05/16/2018

DOUGLAS COUNTY

	Rates	Fringes
Electricians:.....	\$ 36.85	26.17

ELEC0388-002 06/03/2018

ADAMS, CLARK (Colby, Freemont, Lynn, Mayville, Sherman, Sherwood, Unity), FOREST, JUNEAU, LANGLADE, LINCOLN, MARATHON, MARINETTE (Beecher, Dunbar, Goodman & Pembine), MENOMINEE (Area West of a line 6 miles West of the West boundary of Oconto County), ONEIDA, PORTAGE, SHAWANO (Aniwa and Hutchins), VILAS AND WOOD COUNTIES

	Rates	Fringes
--	-------	---------

Electricians:.....	\$ 32.55	19.02

ELEC0430-002 06/01/2018		
RACINE COUNTY (Except Burlington Township)		
	Rates	Fringes
Electricians:.....	\$ 38.78	21.49

ELEC0494-005 06/01/2018		
MILWAUKEE, OZAUKEE, WASHINGTON, AND WAUKESHA COUNTIES		
	Rates	Fringes
Electricians:.....	\$ 39.31	24.69

ELEC0494-006 06/01/2018		
CALUMET (Township of New Holstein), DODGE (East of Hwy 26 including Chester Township), FOND DU LAC, MANITOWOC (Schleswig), and SHEBOYGAN COUNTIES		
	Rates	Fringes
Electricians:.....	\$ 33.40	22.08

ELEC0494-013 06/01/2018		
DODGE (East of Hwy 26 including Chester Twp, excluding Emmet Twp), FOND DU LAC (Except Waupuin), MILWAUKEE, OZAUKEE, MANITOWOC (Schleswig), WASHINGTON, AND WAUKESHA COUNTIES		
	Rates	Fringes
Sound & Communications		
Installer.....	\$ 19.56	15.78
Technician.....	\$ 28.99	16.25
Installation, testing, maintenance, operation and servicing of all sound, intercom, telephone interconnect, closed circuit TV systems, radio systems, background music systems, language laboratories, electronic carillon, antenna distribution systems, clock and program systems and low-voltage systems such as visual nurse call, audio/visual nurse call systems, doctors entrance register systems. Includes all wire and cable carrying audio, visual, data, light and radio frequency signals. Includes the installation of conduit, wiremold, or raceways in existing structures that have been occupied for six months or more where required for the protection of the wire or cable, but does not mean a complete conduit or raceway system. work covered does not include the installation of conduit, wiremold or any raceways in any new construction, or the installation of power supply outlets by means of which external electric power is supplied to any of the foregoing equipment or products		

ELEC0577-003 06/01/2018		
CALUMET (except Township of New Holstein), GREEN LAKE (N. part including Townships of Berlin, St Marie, and Seneca), MARQUETTE (N. part including Townships of Crystal Lake, Neshkoro, Newton, and Springfield), OUTAGAMIE, WAUPACA, WAUSHARA, AND WINNEBAGO COUNTIES		
	Rates	Fringes
Electricians:.....	\$ 32.18	18.59

ELEC0890-003 06/01/2018		
DODGE (Emmet Township only), GREEN, JEFFERSON, LAFAYETTE, RACINE (Burlington Township), ROCK AND WALWORTH COUNTIES		

	Rates	Fringes
Electricians:.....	\$ 34.15	19.63

ELEC0953-001 07/01/2015

	Rates	Fringes
Line Construction:		
(1) Lineman.....	\$ 42.14	32% + 5.00
(2) Heavy Equipment Operator.....	\$ 40.03	32% + 5.00
(3) Equipment Operator.....	\$ 33.71	32% + 5.00
(4) Heavy Groundman Driver..	\$ 26.78	14.11
(5) Light Groundman Driver..	\$ 24.86	13.45
(6) Groundsman.....	\$ 23.18	32% + 5.00

ENGI0139-005 06/04/2018

	Rates	Fringes
Power Equipment Operator		
Group 1.....	\$ 40.72	22.10
Group 2.....	\$ 40.22	22.10
Group 3.....	\$ 39.72	22.10
Group 4.....	\$ 39.46	22.10
Group 5.....	\$ 39.17	22.10
Group 6.....	\$ 33.27	22.10

HAZARDOUS WASTE PREMIUMS:

EPA Level "A" protection - \$3.00 per hour
EPA Level "B" protection - \$2.00 per hour
EPA Level "C" protection - \$1.00 per hour

POWER EQUIPMENT OPERATORS CLASSIFICATIONS

GROUP 1: Cranes, tower cranes, and derricks with or without attachments with a lifting capacity of over 100 tons; or cranes, tower cranes, and derricks with boom, leads and/or jib lengths measuring 176 feet or longer.

GROUP 2: Cranes, tower cranes and derricks with or without attachments with a lifting capacity of 100 tons or less; or cranes, tower cranes, and derricks with boom, leads, and/or jibs lengths measuring 175 feet or under and Backhoes (excavators) weighing 130,000 lbs and over; caisson rigs; pile driver; dredge operator; dredge engineer; Boat Pilot.

GROUP 3: Mechanic or welder - Heavy duty equipment; cranes with a lifting capacity of 25 tons or under; concrete breaker (manual or remote); vibratory/sonic concrete breaker; concrete laser screed; concrete slipform paver; concrete batch plant operator; concrete pvt. spreader - heavy duty (rubber tired); concrete spreader & distributor; automatic subgrader (concrete); concrete grinder & planing machine; concrete slipform curb & gutter machine; slipform concrete placer; tube finisher; hydro blaster (10,000 psi & over); bridge paver; concrete conveyor system; concrete pump; Rotec type Conveyor; stabilizing mixer (self-propelled); shoulder widener; asphalt plant engineer; bituminous paver; bump cutter & grooving machine; milling machine; screed (bituminous paver); asphalt heater, planer & scarifier; Backhoes (excavators) weighing under 130,000 lbs; grader or motor patrol; tractor (scraper, dozer, pusher, loader); scraper - rubber tired (single or twin engine); endloader; hydraulic backhoe (tractor type); trenching machine; skid rigs; tractor, side boom (heavy); drilling or boring machine (mechanical heavy); roller over 5 tons; percussion or rotary drilling machine; air track; blaster; loading machine (conveyor); tugger; boatmen; winches & A-frames; post driver; material hoist.

GROUP 4: Greaser, roller steel (5 tons or less); roller (pneumatic tired) - self propelled; tractor (mounted or towed compactors & light equipment); shouldering machine; self-propelled chip spreader; concrete spreader; finishing machine; mechanical float; curing machine; power subgrader; joint sawer (multiple blade) belting machine; burlap machine; texturing machine; tractor endloader (rubber tired) - light; jeep digger; forklift; mulcher; launch operator; fireman, environmental burner

GROUP 5: Air compressor; power pack; vibrator hammer and
extractor; heavy equipment, leadman; tank car heaters;
stump chipper; curb machine operator; Concrete
proportioning plants; generators; mudjack operator; rock
breaker; crusher or screening plant; screed (milling
machine); automatic belt conveyor and surge bin; pug mill
operator; Oiler, pump (over 3 inches); Drilling Machine
Tender.

GROUP 6: Off-road material hauler with or without ejector.

IRON0008-002 06/01/2017

BROWN, CALUMET, DOOR, FOND DU LAC, KEWAUNEE, MANITOWOC,
MARINETTE, OCONTO, OUTAGAMI, SHAWANO, SHEBOYGAN, AND WINNEBAGO
COUNTIES:

	Rates	Fringes
IRONWORKER.....	\$ 31.24	26.97

Paid Holidays: New Year's Day, Memorial Day, July 4th, Labor
Day, Thanksgiving Day & Christmas Day.

IRON0008-003 06/01/2017

KENOSHA, MILWAUKEE, OZAUCKEE, RACINE, WALWORTH (N.E. 2/3),
WASHINGTON, AND WAUKESHA COUNTIES

	Rates	Fringes
IRONWORKER.....	\$ 33.19	26.97

Paid Holidays: New Year's Day, Memorial Day, July 4th, Labor
Day, Thanksgiving Day & Christmas Day.

IRON0383-001 06/01/2017

ADAMS, COLUMBIA, CRAWFORD, DANE, DODGE, FLORENCE, FOREST,
GRANT, GREENE, (Excluding S.E. tip), GREEN LAKE, IOWA,
JEFFERSON, JUNEAU, LA CROSSE, LAFAYETTE, LANGLADE, MARATHON,
MARQUETTE, MENOMINEE, MONROE, PORTAGE, RICHLAND, ROCK (Northern
area, vicinity of Edgerton and Milton), SAUK, VERNON, WAUPACA,
WAUSHARA, AND WOOD COUNTIES

	Rates	Fringes
IRONWORKER.....	\$ 34.50	23.82

IRON0498-005 06/01/2016

GREEN (S.E. 1/3), ROCK (South of Edgerton and Milton), and
WALWORTH (S.W. 1/3) COUNTIES:

	Rates	Fringes
IRONWORKER.....	\$ 36.29	30.77

IRON0512-008 05/01/2017

BARRON, BUFFALO, CHIPPEWA, CLARK, DUNN, EAU CLAIRE, JACKSON,
PEPIN, PIERCE, POLK, RUSK, ST CROIX, TAYLOR, AND TREMPLEAU
COUNTIES

	Rates	Fringes
IRONWORKER.....	\$ 36.50	26.45

IRON0512-021 05/01/2017

ASHLAND, BAYFIELD, BURNETT, DOUGLAS, IRON, LINCOLN, ONEIDA,
PRICE, SAWYER, VILAS AND WASHBURN COUNTIES

	Rates	Fringes
IRONWORKER.....	\$ 32.04	26.45

LABO0113-002 06/04/2018

MILWAUKEE AND WAUKESHA COUNTIES

	Rates	Fringes
LABORER		
Group 1.....	\$ 27.88	21.76
Group 2.....	\$ 28.03	21.76
Group 3.....	\$ 28.23	21.76
Group 4.....	\$ 28.38	21.76
Group 5.....	\$ 28.53	21.76
Group 6.....	\$ 24.37	21.76

LABORERS CLASSIFICATIONS

GROUP 1: General Laborer; Tree Trimmer; Conduit Layer; Demolition and Wrecking Laborer; Guard Rail, Fence, and Bridge Builder; Landscaper; Multiplate Culvert Assembler; Stone Handler; Bituminous Worker (Shoveler, Loader, and Utility Man); Batch Truck Dumper or Cement Handler; Bituminous Worker (Dumper, Ironer, Smoother, and Tamper); Concrete Handler

GROUP 2: Air Tool Operator; Joint Sawyer and Filler (Pavement); Vibrator or Tamper Operator (Mechanical Hand Operated); Chain Saw Operator; Demolition Burning Torch Laborer

GROUP 3: Bituminous Worker (Raker and Luteman); Formsetter (Curb, Sidewalk, and Pavement); Strike Off Man

GROUP 4: Line and Grade Specialist

GROUP 5: Blaster and Powderman

GROUP 6: Flagperson; traffic control person

LABO0113-003 06/04/2018

OZAUKEE AND WASHINGTON COUNTIES

	Rates	Fringes
LABORER		
Group 1.....	\$ 27.13	21.76
Group 2.....	\$ 27.23	21.76
Group 3.....	\$ 27.28	21.76
Group 4.....	\$ 27.48	21.76
Group 5.....	\$ 27.33	21.76
Group 6.....	\$ 24.22	21.76

LABORERS CLASSIFICATIONS

GROUP 1: General Laborer; Tree Trimmer; Conduit Layer; Demolition and Wrecking Laborer; Guard Rail, Fence, and Bridge Builder; Landscaper; Multiplate Culvert Assembler; Stone Handler; Bituminous Worker (Shoveler, Loader, and Utility Man); Batch Truck Dumper or Cement Handler; Bituminous Worker (Dumper, Ironer, Smoother, and Tamper); Concrete Handler

GROUP 2: Air Tool Operator; Joint Sawyer and Filler (Pavement); Vibrator or Tamper Operator (Mechanical Hand Operated);

GROUP 3: Bituminous Worker (Raker and Luteman); Formsetter (Curb, Sidewalk, and Pavement); Strike Off Man

GROUP 4: Line and Grade Specialist

GROUP 5: Blaster; powderman

GROUP 6: Flagperson and Traffic Control Person

LABO0113-011 06/04/2018

KENOSHA AND RACINE COUNTIES

	Rates	Fringes
LABORER		
Group 1.....	\$ 26.94	21.76
Group 2.....	\$ 27.09	21.76
Group 3.....	\$ 27.29	21.76
Group 4.....	\$ 27.26	21.76
Group 5.....	\$ 27.59	21.76
Group 6.....	\$ 24.08	21.76

LABORERS CLASSIFICATIONS:

GROUP 1: General laborer; Tree Trimmer; Conduit Layer; Demolition and Wrecking Laborer; Guard Rail, Fence, and Bridge Builder; Landscaper; Multiplate Culvert Assembler; Stone Handler; Bituminous Worker (Shoveler, Loader, and Utility Man); Batch Truck Dumper or Cement Handler; Bituminous worker (Dumper, Ironer, Smoother, and Tamper); Concrete Handler

GROUP 2: Air Tool Operator; Joint Sawyer and Filler (Pavement); Vibrator or Tamper Operator (Mechanical Hand Operated); Chain Saw Operator; Demolition Burning Torch Laborer

GROUP 3: Bituminous Worker (Raker and Luteman); Formsetter (Curb, Sidewalk, and Pavement); Strike Off Man

GROUP 4: Line and Grade Specialist

GROUP 5: Blaster and Powderman

GROUP 6: Flagman; traffic control person

LABO0140-002 06/04/2018

ADAMS, ASHLAND, BARRON, BAYFIELD, BROWN, BUFFALO, BURNETT, CALUMET, CHIPPEWA, CLARK, COLUMBIA, CRAWFORD, DODGE, DOOR, DOUGLAS, DUNN, EAU CLAIRE, FLORENCE, FOND DU LAC, FOREST, GRANT, GREEN, GREEN LAKE, IRON, JACKSON, JUNEAU, IOWA, JEFFERSON, KEWAUNEE, LA CROSSE, LAFAYETTE, LANGLADE, LINCOLN, MANITOWOC, MARATHON, MARINETTE, MARQUETTE, MENOMINEE, MONROE, OCONTO, ONEIDA, OUTAGAMIE, PEPIN, PIERCE, POLK, PORTAGE, PRICE, RICHLAND, ROCK, RUSK, SAUK, SAWYER, SHAWANO, SHEBOYGAN, ST. CROIX, TAYLOR, TREMPLEAU, VERNON, VILLAS, WALWORTH, WASHBURN, WAUPACA, WAUSHARA, WINNEBAGO, AND WOOD COUNTIES

	Rates	Fringes
LABORER		
Group 1.....	\$ 31.80	17.20
Group 2.....	\$ 31.90	17.20
Group 3.....	\$ 31.95	17.20
Group 4.....	\$ 32.15	17.20
Group 5.....	\$ 32.00	17.20
Group 6.....	\$ 28.43	17.20

LABORER CLASSIFICATIONS

GROUP 1: General Laborer; Tree Trimmer; Conduit Layer; Demolition and Wrecking Laborer; Guard Rail, Fence, and Bridge Builder; Landscaper; Multiplate Culvert Assembler; Stone Handler; Bituminous Worker (Shoveler, Loader, and Utility Man); Batch Truck Dumper or Cement Handler; Bituminous Worker (Dumper, Ironer, Smoother and Tamper); Concrete Handler

GROUP 2: Air Tool Operator; Joint Sawyer and Filler (Pavement); Vibrator or Tamper Operator (Mechanical Hand Operated); Chain Saw Operator; Demolition Burning Torch Laborer

GROUP 3: Bituminous Worker (Raker and Luteman); Formsetter

(Curb, Sidewalk and Pavement); Strike Off Man

GROUP 4: Line and Grade Specialist

GROUP 5: Blaster; powderman

GROUP 6: Flagperson; Traffic Control

LABO0464-003 06/04/2018

DANE COUNTY

	Rates	Fringes
LABORER		
Group 1.....	\$ 32.08	17..20
Group 2.....	\$ 32.18	17..20
Group 3.....	\$ 32.23	17..20
Group 4.....	\$ 32.43	17..20
Group 5.....	\$ 32.28	17..20
Group 6.....	\$ 28.43	17..20

LABORERS CLASSIFICATIONS:

GROUP 1: General Laborer; Tree Trimmer; Conduit Layer;
Demolition and Wrecking Laborer; Guard Rail, Fence, and
Bridge Builder; Landscaper; Multiplate Culvert Assembler;
Stone Handler; Bituminous Worker (Shoveler, Loader, and
Utility Man); Batch Truck Dumper or Cement Handler;
Bituminous Worker (Dumper, Ironer, Smoother, and Tamper);
Concrete Handler

GROUP 2: Air Tool Operator; Joint Sawyer and Filler
(Pavement); Vibrator or Tamper Operator (Mechanical Hand
Operated); Chain Saw Operator; Demolition Burning Torch
Laborer

GROUP 3: Bituminous Worker (Raker and Luteman); Formsetter
(Curb, Sidewalk, and Pavement); Strike Off Man

GROUP 4: Line and Grade Specialist

GROUP 5: Blaster; Powderman

GROUP 6: Flagperson and Traffic Control Person

PAIN0106-008 05/01/2017

ASHLAND, BAYFIELD, BURNETT, AND DOUGLAS COUNTIES

	Rates	Fringes
Painters:		
New:		
Brush, Roller.....	\$ 30.33	17.27
Spray, Sandblast, Steel....	\$ 30.93	17.27
Repaint:		
Brush, Roller.....	\$ 28.83	17.27
Spray, Sandblast, Steel....	\$ 29.43	17.27

PAIN0108-002 06/01/2017

RACINE COUNTY

	Rates	Fringes
Painters:		
Brush, Roller.....	\$ 33.74	18.95
Spray & Sandblast.....	\$ 34.74	18.95

PAIN0259-002 05/01/2008

BARRON, CHIPPEWA, DUNN, EAU CLAIRE, PEPIN, PIERCE, POLK, RUSK,
SAWYER, ST. CROIX, AND WASHBURN COUNTIES

	Rates	Fringes
PAINTER.....	\$ 24.11	12.15

PAIN0259-004 05/01/2015

BUFFALO, CRAWFORD, JACKSON, LA CROSSE, MONROE, TREMPLEAU, AND
VERNON COUNTIES

	Rates	Fringes
PAINTER.....	\$ 22.03	12.45

PAIN0781-002 06/01/2018

JEFFERSON, MILWAUKEE, OZAUKEE, WASHINGTON, AND WAUKESHA COUNTIES

	Rates	Fringes
Painters:		
Bridge.....	\$ 31.60	23.51
Brush.....	\$ 31.55	23.51
Spray & Sandblast.....	\$ 32.30	23.51

PAIN0802-002 06/01/2017

COLUMBIA, DANE, DODGE, GRANT, GREEN, IOWA, LAFAYETTE, RICHLAND,
ROCK, AND SAUK COUNTIES

	Rates	Fringes
PAINTER		
Brush.....	\$ 28.25	17.72

PREMIUM PAY:
Structural Steel, Spray, Bridges = \$1.00 additional per
hour.

PAIN0802-003 06/01/2017

ADAMS, BROWN, CALUMET, CLARK, DOOR, FOND DU LAC, FOREST, GREEN
LAKE, IRON, JUNEAU, KEWAUNEE, LANGLADE, LINCOLN, MANITOWOC,
MARATHON, MARINETTE, MARQUETTE, MENOMINEE, OCONTO, ONEIDA,
OUTAGAMIE, PORTAGE, PRICE, SHAWANO, SHEBOYGAN, TAYLOR, VILAS,
WAUSHARA, WAUPACA, WINNEBAGO, AND WOOD COUNTIES

	Rates	Fringes
PAINTER.....	\$ 24.89	12.05

PAIN0934-001 06/01/2017

KENOSHA AND WALWORTH COUNTIES

	Rates	Fringes
Painters:		
Brush.....	\$ 33.74	18.95
Spray.....	\$ 34.74	18.95
Structural Steel.....	\$ 33.89	18.95

PAIN1011-002 06/01/2017

FLORENCE COUNTY

	Rates	Fringes
Painters:.....	\$ 24.86	12.23

PLAS0599-010 06/01/2017

	Rates	Fringes
CEMENT MASON/CONCRETE FINISHER		
Area 1.....	\$ 39.46	17.17
Area 2 (BAC).....	\$ 35.07	19.75
Area 3.....	\$ 35.61	19.40
Area 4.....	\$ 34.70	20.51
Area 5.....	\$ 36.27	18.73
Area 6.....	\$ 32.02	22.99

AREA DESCRIPTIONS

- AREA 1: BAYFIELD, DOUGLAS, PRICE, SAWYER, AND WASHBURN COUNTIES
- AREA 2: ADAMS, ASHLAND, BARRON, BROWN, BURNETT, CALUMET, CHIPPEWA, CLARK, COLUMBIA, DODGE, DOOR, DUNN, FLORENCE, FOND DU LAC, FOREST, GREEN LAKE, IRON, JEFFERSON, KEWAUNEE, LANGLADE, LINCOLN, MANITOWOC, MARATHON, MARINETTE, MARQUETTE, MENOMINEE, OCONTO, ONEIDA, OUTAGAMIE, POLK, PORTAGE, RUSK, ST CROIX, SAUK, SHAWANO, SHEBOYGAN, TAYLOR, VILAS, WALWORTH, WAUPACA, WAUSHARA, WINNEBAGO, AND WOOD COUNTIES
- AREA 3: BUFFALO, CRAWFORD, EAU CLAIRE, JACKSON, JUNEAU, LA CROSSE MONROE, PEPIN, PIERCE, RICHLAND, TREMPPEALEAU, AND VERNON COUNTIES
- AREA 4: MILWAUKEE, OZAUKEE, WASHINGTON, AND WAUKESHA COUNTIES
- AREA 5: DANE, GRANT, GREEN, IOWA, LAFAYETTE, AND ROCK COUNTIES
- AREA 6: KENOSHA AND RACINE COUNTIES

TEAM0039-001 06/01/2018		
	Rates	Fringes
TRUCK DRIVER		
1 & 2 Axles.....	\$ 28.12	21.20
3 or more Axles; Euclids		
Dumptor & Articulated,		
Truck Mechanic.....	\$ 28.27	21.20

WELL DRILLER.....	\$ 16.52	3.70

WELDERS - Receive rate prescribed for craft performing operation to which welding is incidental.

=====

Note: Executive Order (EO) 13706, Establishing Paid Sick Leave for Federal Contractors applies to all contracts subject to the Davis-Bacon Act for which the contract is awarded (and any solicitation was issued) on or after January 1, 2017. If this contract is covered by the EO, the contractor must provide employees with 1 hour of paid sick leave for every 30 hours they work, up to 56 hours of paid sick leave each year. Employees must be permitted to use paid sick leave for their own illness, injury or other health-related needs, including preventive care; to assist a family member (or person who is like family to the employee) who is ill, injured, or has other health-related needs, including preventive care; or for reasons resulting from, or to assist a family member (or person who is like family to the employee) who is a victim of, domestic violence, sexual assault, or stalking. Additional information on contractor requirements and worker protections under the EO is available at www.dol.gov/whd/govcontracts.

Unlisted classifications needed for work not included within the scope of the classifications listed may be added after award only as provided in the labor standards contract clauses (29CFR 5.5 (a) (1) (ii)).

The body of each wage determination lists the classification and wage rates that have been found to be prevailing for the cited type(s) of construction in the area covered by the wage determination. The classifications are listed in alphabetical order of "identifiers" that indicate whether the particular rate is a union rate (current union negotiated rate for local), a survey rate (weighted average rate) or a union average rate (weighted union average rate).

Union Rate Identifiers

A four letter classification abbreviation identifier enclosed in dotted lines beginning with characters other than "SU" or "UAVG" denotes that the union classification and rate were prevailing for that classification in the survey. Example: PLUM0198-005 07/01/2014. PLUM is an abbreviation identifier of the union which prevailed in the survey for this classification, which in this example would be Plumbers. 0198 indicates the local union number or district council number where applicable, i.e., Plumbers Local 0198. The next number, 005 in the example, is an internal number used in processing the wage determination. 07/01/2014 is the effective date of the most current negotiated rate, which in this example is July 1, 2014.

Union prevailing wage rates are updated to reflect all rate changes in the collective bargaining agreement (CBA) governing this classification and rate.

Survey Rate Identifiers

Classifications listed under the "SU" identifier indicate that no one rate prevailed for this classification in the survey and the published rate is derived by computing a weighted average rate based on all the rates reported in the survey for that classification. As this weighted average rate includes all rates reported in the survey, it may include both union and non-union rates. Example: SULA2012-007 5/13/2014. SU indicates the rates are survey rates based on a weighted average calculation of rates and are not majority rates. LA indicates the State of Louisiana. 2012 is the year of survey on which these classifications and rates are based. The next number, 007 in the example, is an internal number used in producing the wage determination. 5/13/2014 indicates the survey completion date for the classifications and rates under that identifier.

Survey wage rates are not updated and remain in effect until a new survey is conducted.

Union Average Rate Identifiers

Classification(s) listed under the UAVG identifier indicate that no single majority rate prevailed for those classifications; however, 100% of the data reported for the classifications was union data. EXAMPLE: UAVG-OH-0010 08/29/2014. UAVG indicates that the rate is a weighted union average rate. OH indicates the state. The next number, 0010 in the example, is an internal number used in producing the wage determination. 08/29/2014 indicates the survey completion date for the classifications and rates under that identifier.

A UAVG rate will be updated once a year, usually in January of each year, to reflect a weighted average of the current negotiated/CBA rate of the union locals from which the rate is based.

WAGE DETERMINATION APPEALS PROCESS

1.) Has there been an initial decision in the matter? This can be:

- * an existing published wage determination
- * a survey underlying a wage determination
- * a Wage and Hour Division letter setting forth a position on a wage determination matter
- * a conformance (additional classification and rate) ruling

On survey related matters, initial contact, including requests for summaries of surveys, should be with the Wage and Hour Regional Office for the area in which the survey was conducted because those Regional Offices have responsibility for the Davis-Bacon survey program. If the response from this initial contact is not satisfactory, then the process described in 2.) and 3.) should be followed.

With regard to any other matter not yet ripe for the formal process described here, initial contact should be with the Branch of Construction Wage Determinations. Write to:

Branch of Construction Wage Determinations
Wage and Hour Division
U.S. Department of Labor
200 Constitution Avenue, N.W.
Washington, DC 20210

2.) If the answer to the question in 1.) is yes, then an interested party (those affected by the action) can request review and reconsideration from the Wage and Hour Administrator (See 29 CFR Part 1.8 and 29 CFR Part 7). Write to:

Wage and Hour Administrator
U.S. Department of Labor
200 Constitution Avenue, N.W.
Washington, DC 20210

The request should be accompanied by a full statement of the interested party's position and by any information (wage payment data, project description, area practice material, etc.) that the requestor considers relevant to the issue.

3.) If the decision of the Administrator is not favorable, an interested party may appeal directly to the Administrative Review Board (formerly the Wage Appeals Board). Write to:

Administrative Review Board
U.S. Department of Labor
200 Constitution Avenue, N.W.
Washington, DC 20210

4.) All decisions by the Administrative Review Board are final.

=====
END OF GENERAL DECISION

General Decision Number: WI190015 01/04/2019 WI15

Superseded General Decision Number: WI20180015

State: Wisconsin

Construction Type: Heavy

Counties: Wisconsin Statewide.

HEAVY CONSTRUCTION PROJECTS (Excluding Tunnel, Sewer, and Water Lines).

Note: Under Executive Order (EO) 13658, an hourly minimum wage of \$10.60 for calendar year 2019 applies to all contracts subject to the Davis-Bacon Act for which the contract is awarded (and any solicitation was issued) on or after January 1, 2015. If this contract is covered by the EO, the contractor must pay all workers in any classification listed on this wage determination at least \$10.60 per hour (or the applicable wage rate listed on this wage determination, if it is higher) for all hours spent performing on the contract in calendar year 2019. If this contract is covered by the EO and a classification considered necessary for performance of work on the contract does not appear on this wage determination, the contractor must pay workers in that classification at least the wage rate determined through the conformance process set forth in 29 CFR 5.5(a)(1)(ii) (or the EO minimum wage rate, if it is higher than the conformed wage rate). The EO minimum wage rate will be adjusted annually. Please note that this EO applies to the above-mentioned types of contracts entered into by the federal government that are subject to the Davis-Bacon Act itself, but it does not apply to contracts subject only to the Davis-Bacon Related Acts, including those set forth at 29 CFR 5.1(a)(2)-(60). Additional information on contractor requirements and worker protections under the EO is available at www.dol.gov/whd/govcontracts.

Modification Number Publication Date
0 01/04/2019

BOIL0107-001 01/01/2017

	Rates	Fringes
BOILERMAKER		
Boilermaker.....	\$ 35.65	29.89
Small Boiler Repair (under 25,000 lbs/hr).....	\$ 26.91	16.00

* BRWI0001-002 06/01/2018

CRAWFORD, JACKSON, JUNEAU, LA CROSSE, MONROE, TREMPLEAU, AND
VERNON COUNTIES

	Rates	Fringes
BRICKLAYER.....	\$ 33.06	22.65

* BRWI0002-002 06/01/2018

ASHLAND, BAYFIELD, DOUGLAS, AND IRON COUNTIES

	Rates	Fringes
BRICKLAYER.....	\$ 38.87	21.26

* BRWI0002-005 06/01/2018

ADAMS, ASHLAND, BARRON, BROWN, BURNETT, CALUMET, CHIPPEWA,
CLARK, COLUMBIA, DODGE, DOOR, DUNN, FLORENCE, FOND DU LAC,
FOREST, GREEN LAKE, IRON, JEFFERSON, KEWAUNEE, LANGLADE,
LINCOLN, MANITOWOC, MARATHON, MARINETTE, MARQUETTE, MENOMINEE,
OCONTO, ONEIDA, OUTAGAMIE, POLK, PORTAGE, RUSK, ST CROIX, SAUK,
SHAWANO, SHEBOYGAN, TAYLOR, VILAS, WALWORTH, WAUPACA, WAUSHARA,
WINNEBAGO, AND WOOD COUNTIES

	Rates	Fringes
CEMENT MASON/CONCRETE FINISHER...	\$ 35.39	21.46

* BRWI0003-002 06/01/2018		
BROWN, DOOR, FLORENCE, KEWAUNEE, MARINETTE, AND OCONTO COUNTIES		
	Rates	Fringes
BRICKLAYER.....	\$ 33.44	22.27

* BRWI0004-002 06/01/2018		
KENOSHA, RACINE, AND WALWORTH COUNTIES		
	Rates	Fringes
BRICKLAYER.....	\$ 37.66	23.35

* BRWI0006-002 06/01/2018		
ADAMS, CLARK, FOREST, LANGLADE, LINCOLN, MARATHON, MENOMINEE, ONEIDA, PORTAGE, PRICE, TAYLOR, VILAS AND WOOD COUNTIES		
	Rates	Fringes
BRICKLAYER.....	\$ 34.30	21.41

* BRWI0007-002 06/01/2018		
GREEN, LAFAYETTE, AND ROCK COUNTIES		
	Rates	Fringes
BRICKLAYER.....	\$ 34.82	22.59

* BRWI0008-002 06/01/2018		
MILWAUKEE, OZAUKEE, WASHINGTON, AND WAUKESHA COUNTIES		
	Rates	Fringes
BRICKLAYER.....	\$ 38.03	22.55

* BRWI0009-001 06/01/2018		
GREEN LAKE, MARQUETTE, OUTAGAMIE, SHAWANO, WAUPACA, WASHARA, AND WINNEBAGO COUNTIES		
	Rates	Fringes
BRICKLAYER.....	\$ 33.44	22.27

BRWI0011-002 06/01/2016		
CALUMET, FOND DU LAC, MANITOWOC, AND SHEBOYGAN COUNTIES		
	Rates	Fringes
BRICKLAYER.....	\$ 32.22	20.57

* BRWI0013-002 06/01/2018		
DANE, GRANT, IOWA, AND RICHLAND COUNTIES		
	Rates	Fringes
BRICKLAYER.....	\$ 34.80	22.61

* BRWI0019-002 06/01/2018		
BARRON, BUFFALO, BURNETT, CHIPPEWA, DUNN, EAU CLAIRE, PEPIN, PIERCE, POLK, RUSK, ST. CROIX, SAWYER AND WASHBURN COUNTIES		
	Rates	Fringes

BRICKLAYER.....	\$ 32.97	22.74
-----------------	----------	-------

* BRWI0021-002 06/01/2018

DODGE AND JEFFERSON COUNTIES

	Rates	Fringes
BRICKLAYER.....	\$ 35.24	22.15

* BRWI0034-002 06/01/2018

COLUMBIA AND SAUK COUNTIES

	Rates	Fringes
BRICKLAYER.....	\$ 34.80	22.61

CARP0087-001 05/01/2016

BURNETT (W. of Hwy 48), PIERCE (W. of Hwy 29), POLK (W. of Hwys 35, 48 & 65), AND ST. CROIX (W. of Hwy 65) COUNTIES

	Rates	Fringes
Carpenter & Piledrivermen.....	\$ 36.85	18.39

CARP0252-002 06/01/2016

ADAMS, BARRON, BAYFIELD (Eastern 2/3), BROWN, BUFFALO, BURNETT (E. of Hwy 48), CALUMET, CHIPPEWA, CLARK, COLUMBIA, CRAWFORD, DANE, DODGE, DOOR, DUNN, EAU CLAIRE, FLORENCE (except area bordering Michigan State Line), FOND DU LAC, FOREST, GRANT, GREEN, GREEN LAKE, IOWA, IRON, JACKSON, JEFFERSON, JUNEAU, KEWAUNEE, LA CROSSE, LAFAYETTE, LANGLADE, LINCOLN, MANITOWOC, MARATHON, MARINETTE (except N.E. corner), MARQUETTE, MENOMINEE, MONROE, OCONTO, ONEIDA, OUTAGAMIE, PEPIN, PIERCE (E. of Hwys 29 & 65), POLK (E. of Hwys 35, 48 & 65), PORTAGE, PRICE, RICHLAND, ROCK, RUSK, SAUK, SAWYER, SHAWANO, SHEBOYGAN, ST CROIX (E. of Hwy 65), TAYLOR, TREMPPEALEAU, VERNON, VILAS, WALWORTH, WASHBURN, WAUPACA, WAUSHARA, WINNEBAGO, AND WOOD COUNTIES

	Rates	Fringes
CARPENTER		
CARPENTER.....	\$ 33.56	18.00
MILLWRIGHT.....	\$ 35.08	18.35
PILEDRIIVER.....	\$ 34.12	18.00

CARP0252-010 06/01/2016

ASHLAND COUNTY

	Rates	Fringes
Carpenters		
Carpenter.....	\$ 33.56	18.00
Millwright.....	\$ 35.08	18.35
Pile Driver.....	\$ 34.12	18.00

CARP0264-003 06/01/2016

KENOSHA, MILWAUKEE, OZAUKEE, RACINE, WAUKESHA, AND WASHINGTON COUNTIES

	Rates	Fringes
CARPENTER.....	\$ 35.78	22.11

CARP0361-004 05/01/2018

BAYFIELD (West of Hwy 63) AND DOUGLAS COUNTIES

	Rates	Fringes
CARPENTER.....	\$ 36.15	20.43

CARP2337-001 06/01/2016

ZONE A: MILWAUKEE, OZAUKEE, WAUKESHA AND WASHINGTON

ZONE B: KENOSHA & RACINE

	Rates	Fringes
PILEDRIVERMAN		
Zone A.....	\$ 31.03	22.69
Zone B.....	\$ 31.03	22.69

CARP2337-003 06/01/2016

	Rates	Fringes
MILLWRIGHT		
Zone A.....	\$ 29.98	21.53
Zone B.....	\$ 29.98	21.53

ZONE DEFINITIONS

ZONE A: MILWAUKEE, OZAUKEE, WAUKESHA AND WASHINGTON COUNTIES

ZONE B: KENOSHA & RACINE COUNTIES

ELEC0014-002 06/04/2018

ASHLAND, BARRON, BAYFIELD, BUFFALO, BURNETT, CHIPPEWA, CLARK
(except Maryville, Colby, Unity, Sherman, Fremont, Lynn &
Sherwood), CRAWFORD, DUNN, EAU CLAIRE, GRANT, IRON, JACKSON, LA
CROSSE, MONROE, PEPIN, PIERCE, POLK, PRICE, RICHLAND, RUSK, ST
CROIX, SAWYER, TAYLOR, TREMPPEALEAU, VERNON, AND WASHBURN
COUNTIES

	Rates	Fringes
Electricians:.....	\$ 34.21	20.46

ELEC0014-007 06/05/2018

REMAINING COUNTIES

	Rates	Fringes
Teledata System Installer		
Installer/Technician.....	\$ 26.25	13.92

Low voltage construction, installation, maintenance and
removal of teledata facilities (voice, data, and video)
including outside plant, telephone and data inside wire,
interconnect, terminal equipment, central offices, PABX,
fiber optic cable and equipment, micro waves, V-SAT,
bypass, CATV, WAN (wide area networks), LAN (local area
networks), and ISDN (integrated systems digital network).

ELEC0127-002 06/01/2017

KENOSHA COUNTY

	Rates	Fringes
Electricians:.....	\$ 38.50	30%+10.57

ELEC0158-002 06/04/2018

BROWN, DOOR, KEWAUNEE, MANITOWOC (except Schleswig),
MARINETTE (Wausaukee and area South thereof), OCONTO, MENOMINEE
(East of a line 6 miles West of the West boundary of Oconto
County), SHAWANO (Except Area North of Townships of Aniwa and
Hutchins) COUNTIES

	Rates	Fringes
Electricians:.....	\$ 32.50	19.68

ELEC0159-003 06/01/2018

COLUMBIA, DANE, DODGE (Area West of Hwy 26, except Chester and Emmet Townships), GREEN, LAKE (except Townships of Berlin, Seneca, and St. Marie), IOWA, MARQUETTE (except Townships of Neshkoka, Crystal Lake, Newton, and Springfield), and SAUK COUNTIES

	Rates	Fringes
Electricians:.....	\$ 39.04	21.56

ELEC0219-004 06/01/2016

FLORENCE COUNTY (Townships of Aurora, Commonwealth, Fern, Florence and Homestead) AND MARINETTE COUNTY (Township of Niagara)

	Rates	Fringes
Electricians:		
Electrical contracts over \$180,000.....	\$ 32.38	18.63
Electrical contracts under \$180,000.....	\$ 30.18	18.42

ELEC0242-005 05/16/2018

DOUGLAS COUNTY

	Rates	Fringes
Electricians:.....	\$ 36.85	26.17

ELEC0388-002 06/03/2018

ADAMS, CLARK (Colby, Freemont, Lynn, Mayville, Sherman, Sherwood, Unity), FOREST, JUNEAU, LANGLADE, LINCOLN, MARATHON, MARINETTE (Beecher, Dunbar, Goodman & Pembine), MENOMINEE (Area West of a line 6 miles West of the West boundary of Oconto County), ONEIDA, PORTAGE, SHAWANO (Aniwa and Hutchins), VILAS AND WOOD COUNTIES

	Rates	Fringes
Electricians:.....	\$ 32.55	19.02

ELEC0430-002 06/01/2018

RACINE COUNTY (Except Burlington Township)

	Rates	Fringes
Electricians:.....	\$ 38.78	21.49

ELEC0494-005 06/01/2018

MILWAUKEE, OZAUKEE, WASHINGTON, AND WAUKESHA COUNTIES

	Rates	Fringes
Electricians:.....	\$ 39.31	24.69

ELEC0494-006 06/01/2018

CALUMET (Township of New Holstein), DODGE (East of Hwy 26 including Chester Township), FOND DU LAC, MANITOWOC (Schleswig), and SHEBOYGAN COUNTIES

	Rates	Fringes
Electricians:.....	\$ 33.40	22.08

ELEC0494-013 06/01/2018

DODGE (East of Hwy 26 including Chester Twp, excluding Emmet

Twp), FOND DU LAC (Except Waupuin), MILWAUKEE, OZAUKEE,
MANITOWOC (Schleswig), WASHINGTON, AND WAUKESHA COUNTIES

	Rates	Fringes
Sound & Communications		
Installer.....	\$ 19.56	15.78
Technician.....	\$ 28.99	16.25

Installation, testing, maintenance, operation and servicing of all sound, intercom, telephone interconnect, closed circuit TV systems, radio systems, background music systems, language laboratories, electronic carillon, antenna distribution systems, clock and program systems and low-voltage systems such as visual nurse call, audio/visual nurse call systems, doctors entrance register systems. Includes all wire and cable carrying audio, visual, data, light and radio frequency signals. Includes the installation of conduit, wiremold, or raceways in existing structures that have been occupied for six months or more where required for the protection of the wire or cable, but does not mean a complete conduit or raceway system. work covered does not include the installation of conduit, wiremold or any raceways in any new construction, or the installation of power supply outlets by means of which external electric power is supplied to any of the foregoing equipment or products

ELEC0577-003 06/01/2018

CALUMET (except Township of New Holstein), GREEN LAKE (N. part including Townships of Berlin, St Marie, and Seneca), MARQUETTE (N. part including Townships of Crystal Lake, Neshkoro, Newton, and Springfield), OUTAGAMIE, WAUPACA, WAUSHARA, AND WINNEBAGO COUNTIES

	Rates	Fringes
Electricians:.....	\$ 32.18	18.59

ELEC0890-003 06/01/2018

DODGE (Emmet Township only), GREEN, JEFFERSON, LAFAYETTE, RACINE (Burlington Township), ROCK AND WALWORTH COUNTIES

	Rates	Fringes
Electricians:.....	\$ 34.15	19.63

ELEC0953-001 07/01/2015

	Rates	Fringes
Line Construction:		
(1) Lineman.....	\$ 42.14	32% + 5.00
(2) Heavy Equipment Operator.....	\$ 40.03	32% + 5.00
(3) Equipment Operator.....	\$ 33.71	32% + 5.00
(4) Heavy Groundman Driver..	\$ 26.78	14.11
(5) Light Groundman Driver..	\$ 24.86	13.45
(6) Groundsman.....	\$ 23.18	32% + 5.00

ENGI0139-001 06/01/2018

KENOSHA, MILWAUKEE, OZAUKEE, RACINE, WASHINGTON, AND WAUKESHA COUNTIES

	Rates	Fringes
Power Equipment Operator		
Group 1.....	\$ 45.61	21.40
Group 2.....	\$ 45.11	21.40
Group 3.....	\$ 44.61	21.40
Group 4.....	\$ 43.92	21.40
Group 5.....	\$ 41.14	21.40
Group 6.....	\$ 35.99	21.40

HAZARDOUS WASTE PREMIUMS:

EPA Level "A" Protection: \$3.00 per hour

EPA Level "B" Protection: \$2.00 per hour

EPA Level "C" Protection: \$1.00 per hour

POWER EQUIPMENT OPERATORS CLASSIFICATIONS

GROUP 1: Cranes, Tower Cranes, Pedestal Tower Cranes and Derricks with or w/o attachments with a lifting capacity of over 100 tons; or Cranes, Tower Cranes, Pedestal Tower Cranes and Derricks with boom, leads, and/or jib lengths measuring 176 feet or longer; Self-Erecting Tower Cranes over 4000 lbs lifting capacity; All Cranes with Boom Dollies; Boring Machines (directional); Master Mechanic. \$0.50 additional per hour per 100 tons or 100 ft of boom over 200 ft or lifting capacity of crane over 200 tons to a maximum of 300 tons or 300 ft. Thereafter an increase of \$0.01 per ft or ton, whichever is greater.

GROUP 2: Cranes, Tower Cranes, Pedestal Tower Cranes and Derricks with or without attachments with a lifting capacity of 100 tons or less; or Cranes, Tower Cranes Portable Tower Cranes, Pedestal Tower Cranes and Derricks with boom, leads and/or jib lengths measuring 175 feet or less; Backhoes (excavators) 130,000 lbs and over; Caisson Rigs; Pile Drivers; Boring Machines (vertical or horizontal), Versi-Lift, Tri-Lift, Gantry 20,000 lbs & over.

GROUP 3: Backhoe (excavator) under 130,000 lbs; Self-erecting Tower Crane 4000 lbs & under lifting capacity; Traveling Crane (bridge type); Skid Rigs; Dredge Operator; Mechanic; Concrete Paver (over 27E); Concrete Spreader and Distributor; Forklift/ Telehandler (machinery- moving / steel erection); Hydro Blaster, 10,000 psi and over

GROUP 4: Material Hoists; Stack Hoists; Hydraulic Backhoe (tractor or truck mounted); Hydraulic Crane, 5 tons or under (tractor or truck mounted); Hoist (tuggers 5 tons & over); Hydro-Excavators/Daylighters; Concrete Pumps Rotec type Conveyors; Tractor/Bulldozer/End Loader (over 40 hp); Motor Patrol; Scraper Operator; Sideboom; Straddle Carrier; Welder; Bituminous Plant and Paver Operator; Roller over 5 tons; Rail Leveling Machine (Railroad); Tie Placer; Tie Extractor; Tie Tamper; Stone Leveler; Rotary Drill Operator and Blaster; Percussion Drill Operator; Air Track Drill and/or Hammers; Gantrys (under 20,000 lbs); Trencher (wheel type or chain type having 8 inch or larger bucket); Milling Machine; Off-Road Material Haulers.

GROUP 5: Backfiller; Concrete Auto Breaker (large); Concrete Finishing Machines (road type); Rubber Tired Roller; Concrete Batch Hopper; Concrete Conveyor Systems; Grout Pumps; Concrete Mixers (14S or over); Screw Type Pumps and Gypsum Pumps; Tractor, Bulldozer, End Loader (under 40 hp); Trencher (chain type, bucket under 8 inch); Industrial Locomotives; Rollers under 5 tons; Stump Grinder/Chipper (Large); Timber Equipment; Firemen (pile drivers and derricks); Personnel Hoist, Telehandler over 8000 lbs; Robotic Tool Carrier with or without attachments

GROUP 6: Tampers - Compactors (riding type); Assistant Engineer; A-Frames and Winch Trucks; Concrete Auto Breaker; Hydrohammers (small); Brooms and Sweepers; Hoist (tuggers under 5 tons); Boats (Tug, Safety, Work Barges, Launch); Shouldering Machine Operator; Prestress Machines; Screed Operator; Stone Crushers and Screening Plants; Screed Operators (milling machine), Farm or Industrial Tractor Mounted Equipment; Post Hole Digger; Fireman (asphalt plants); Air Compressors over 400 CFM; Generators, over 150 KW; Augers (vertical and horizontal); Air, Electric, Hydraulic Jacks (slipform); Skid Steer Loaders (with or without attachments); Boiler Operators (temporary heat); Refrigeration Plant/Freeze Machines; Power Pack Vibratory/Ultra Sound Drivers and Extractors; Welding Machines; Heaters (mechanical); Pumps; Winches (small electric); Oiler and Greaser; Rotary Drill Tender; Conveyor; Forklifts/Telehandler 8000 lbs & under; Elevators; Automatic Hoists; Pumps (well points); Combination Small Equipment Operators

REMAINING COUNTIES

	Rates	Fringes
Power Equipment Operator		
Group 1.....	\$ 40.72	21.60
Group 2.....	\$ 39.47	21.60
Group 3.....	\$ 38.17	21.60
Group 4.....	\$ 37.64	21.60
Group 5.....	\$ 35.57	21.60
Group 6.....	\$ 34.04	21.60

HAZARDOUS WASTE PREMIUMS:

EPA Level "A" Protection: \$3.00 per hour
 EPA Level "B" Protection: \$2.00 per hour
 EPA Level "C" Protection: \$1.00 per hour

POWER EQUIPMENT OPERATORS CLASSIFICATIONS

GROUP 1: Cranes, Tower Cranes and Derricks with or without attachments with a lifting capacity of over 100 tons; Cranes, Tower Cranes, and Derricks with boom, leads and/or jib lengths 176 ft or longer.

GROUP 2: Backhoes (Excavators) weighing 130,00 lbs and over; Cranes, Tower Cranes and Derricks with or without attachments with a lifting capacity of 100 tons or less; Cranes, Tower Cranes, and Derricks with boom, leads, and/or jib lengths 175 ft or less; Caisson Rigs; Pile Driver

GROUP 3: Backhoes (Excavators) weighing under 130,000 lbs; Travelling Crane (bridge type); Milling Machine; Concrete Paver over 27 E; Concrete Spreader and Distributor; Concrete Laser Screed; Concrete Grinder and Planing Machine; Slipform Curb and Gutter Machine; Boring Machine (Directional); Dredge Operator; Skid Rigs; over 46 meter Concrete Pump.

GROUP 4: Hydraulic Backhoe (tractor or truck mounted); Hydraulic Crane, 10 tons or less; Tractor, Bulldozer, or End Loader (over 40 hp); Motor Patrol; Scraper Operator; Bituminous Plant and Paver Operator; Screed-Milling Machine; Roller over 5 tons; Concrete pumps 46 meter and under; Grout Pumps; Rotec type machine; Hydro Blaster, 10,000 psi and over; Rotary Drill Operator; Percussion Drilling Machine; Air Track Drill with or without integral hammer; Blaster; Boring Machine (vertical or horizontal); Side Boom; Trencher, wheel type or chain type having 8 inch or larger bucket; Rail Leveling Machine (Railroad); Tie Placer; Tie Extractor; Tie Tamper; Stone Leveler; Straddle Carrier; Material Hoists; Stack Hoist; Man Hoists; Mechanic and Welder; Off Road Material Haulers.

GROUP 5: Tractor, Bulldozer, or Endloader (under 40 hp); Tampers -Compactors, riding type; Stump Chipper, large; Roller, Rubber Tire; Backfiller; Trencher, chain type (bucket under 8 inch); Concrete Auto Breaker, large; Concrete Finishing Machine (road type); Concrete Batch Hopper; Concrete Conveyor Systems; Concrete Mixers, 14S or over; Pumps, Screw Type and Gypsum); Hydrohammers, small; Brooms and Sweepers; Lift Slab Machine; Roller under 5 tons; Industrial Locomotives; Fireman (Pile Drivers and Derricks); Pumps (well points); Hoists, automatic; A-Frames and Winch Trucks; Hoists (tuggers); Boats (Tug, Safety, Work Barges and Launches); Assistant Engineer

GROUP 6: Shouldering Machine Operator; Farm or Industrial Tractor mounted equipment; Post Hole Digger; Auger (vertical and horizontal); Skid Steer Loader with or without attachments; Robotic Tool Carrier with or without attachments; Power Pack Vibratory/Ultra Sound Driver and Extractor; Fireman (Asphalt Plants); Screed Operator; Stone Crushers and Screening Plants; Air, Electric, Hydraulic Jacks (Slip Form); Prestress Machines; Air Compressor, 400 CFM or over; Refrigeration Plant/Freeze Machine; Boiler Operators (temporary heat); Forklifts; Welding Machines; Generators; Pumps over 3"; Heaters, Mechanical; Combination small equipment operator; Winches, small electric; Oiler;

Greaser; Rotary Drill Tender; Conveyor; Elevator Operator

IRON0008-002 06/01/2017

BROWN, CALUMET, DOOR, FOND DU LAC, KEWAUNEE, MANITOWOC,
MARINETTE, OCONTO, OUTAGAMI, SHAWANO, SHEBOYGAN, AND WINNEBAGO
COUNTIES:

	Rates	Fringes
IRONWORKER.....	\$ 31.24	26.97

Paid Holidays: New Year's Day, Memorial Day, July 4th, Labor
Day, Thanksgiving Day & Christmas Day.

IRON0008-003 06/01/2017

KENOSHA, MILWAUKEE, OZAUKEE, RACINE, WALWORTH (N.E. 2/3),
WASHINGTON, AND WAUKESHA COUNTIES

	Rates	Fringes
IRONWORKER.....	\$ 33.19	26.97

Paid Holidays: New Year's Day, Memorial Day, July 4th, Labor
Day, Thanksgiving Day & Christmas Day.

IRON0383-001 06/01/2017

ADAMS, COLUMBIA, CRAWFORD, DANE, DODGE, FLORENCE, FOREST,
GRANT, GREENE, (Excluding S.E. tip), GREEN LAKE, IOWA,
JEFFERSON, JUNEAU, LA CROSSE, LAFAYETTE, LANGLADE, MARATHON,
MARQUETTE, MENOMINEE, MONROE, PORTAGE, RICHLAND, ROCK (Northern
area, vicinity of Edgerton and Milton), SAUK, VERNON, WAUPACA,
WAUSHARA, AND WOOD COUNTIES

	Rates	Fringes
IRONWORKER.....	\$ 34.50	23.82

IRON0512-008 05/01/2017

BARRON, BUFFALO, CHIPPEWA, CLARK, DUNN, EAU CLAIRE, JACKSON,
PEPIN, PIERCE, POLK, RUSK, ST CROIX, TAYLOR, AND TREMPLEAU
COUNTIES

	Rates	Fringes
IRONWORKER.....	\$ 36.50	26.45

IRON0512-021 05/01/2017

ASHLAND, BAYFIELD, BURNETT, DOUGLAS, IRON, LINCOLN, ONEIDA,
PRICE, SAWYER, VILAS AND WASHBURN COUNTIES

	Rates	Fringes
IRONWORKER.....	\$ 32.04	26.45

LABO0113-002 06/04/2018

MILWAUKEE AND WAUKESHA COUNTIES

	Rates	Fringes
LABORER		
Group 1.....	\$ 27.88	21.76
Group 2.....	\$ 28.03	21.76
Group 3.....	\$ 28.23	21.76
Group 4.....	\$ 28.38	21.76
Group 5.....	\$ 28.53	21.76
Group 6.....	\$ 24.37	21.76

LABORERS CLASSIFICATIONS

GROUP 1: General Laborer; Tree Trimmer; Conduit Layer; Demolition and Wrecking Laborer; Guard Rail, Fence, and Bridge Builder; Landscaper; Multiplate Culvert Assembler; Stone Handler; Bituminous Worker (Shoveler, Loader, and Utility Man); Batch Truck Dumper or Cement Handler; Bituminous Worker (Dumper, Ironer, Smoother, and Tamper); Concrete Handler

GROUP 2: Air Tool Operator; Joint Sawyer and Filler (Pavement); Vibrator or Tamper Operator (Mechanical Hand Operated); Chain Saw Operator; Demolition Burning Torch Laborer

GROUP 3: Bituminous Worker (Raker and Luteman); Formsetter (Curb, Sidewalk, and Pavement); Strike Off Man

GROUP 4: Line and Grade Specialist

GROUP 5: Blaster and Powderman

GROUP 6: Flagperson; traffic control person

LABO0113-003 06/04/2018

OZAUKEE AND WASHINGTON COUNTIES

	Rates	Fringes
LABORER		
Group 1.....	\$ 27.13	21.76
Group 2.....	\$ 27.23	21.76
Group 3.....	\$ 27.28	21.76
Group 4.....	\$ 27.48	21.76
Group 5.....	\$ 27.33	21.76
Group 6.....	\$ 24.22	21.76

LABORERS CLASSIFICATIONS

GROUP 1: General Laborer; Tree Trimmer; Conduit Layer; Demolition and Wrecking Laborer; Guard Rail, Fence, and Bridge Builder; Landscaper; Multiplate Culvert Assembler; Stone Handler; Bituminous Worker (Shoveler, Loader, and Utility Man); Batch Truck Dumper or Cement Handler; Bituminous Worker (Dumper, Ironer, Smoother, and Tamper); Concrete Handler

GROUP 2: Air Tool Operator; Joint Sawyer and Filler (Pavement); Vibrator or Tamper Operator (Mechanical Hand Operated);

GROUP 3: Bituminous Worker (Raker and Luteman); Formsetter (Curb, Sidewalk, and Pavement); Strike Off Man

GROUP 4: Line and Grade Specialist

GROUP 5: Blaster; powderman

GROUP 6: Flagperson and Traffic Control Person

LABO0113-011 06/04/2018

KENOSHA AND RACINE COUNTIES

	Rates	Fringes
LABORER		
Group 1.....	\$ 26.94	21.76
Group 2.....	\$ 27.09	21.76
Group 3.....	\$ 27.29	21.76
Group 4.....	\$ 27.26	21.76
Group 5.....	\$ 27.59	21.76
Group 6.....	\$ 24.08	21.76

LABORERS CLASSIFICATIONS:

GROUP 1: General laborer; Tree Trimmer; Conduit Layer; Demolition and Wrecking Laborer; Guard Rail, Fence, and

Bridge Builder; Landscaper; Multiplate Culvert Assembler;
Stone Handler; Bituminous Worker (Shoveler, Loader, and
Utility Man); Batch Truck Dumper or Cement Handler;
Bituminous worker (Dumper, Ironer, Smoother, and Tamper);
Concrete Handler

GROUP 2: Air Tool Operator; Joint Sawyer and Filler
(Pavement); Vibrator or Tamper Operator (Mechanical Hand
Operated); Chain Saw Operator; Demolition Burning Torch
Laborer

GROUP 3: Bituminous Worker (Raker and Luteman); Formsetter
(Curb, Sidewalk, and Pavement); Strike Off Man

GROUP 4: Line and Grade Specialist

GROUP 5: Blaster and Powderman

GROUP 6: Flagman; traffic control person

LABO0140-002 06/04/2018

ADAMS, ASHLAND, BARRON, BAYFIELD, BROWN, BUFFALO, BURNETT,
CALUMET, CHIPPEWA, CLARK, COLUMBIA, CRAWFORD, DODGE, DOOR,
DOUGLAS, DUNN, EAU CLAIRE, FLORENCE, FOND DU LAC, FOREST,
GRANT, GREEN, GREEN LAKE, IRON, JACKSON, JUNEAU, IOWA,
JEFFERSON, KEWAUNEE, LA CROSSE, LAFAYETTE, LANGLADE, LINCOLN,
MANITOWOC, MARATHON, MARINETTE, MARQUETTE, MENOMINEE, MONROE,
OCONTO, ONEIDA, OUTAGAMIE, PEPIN, PIERCE, POLK, PORTAGE, PRICE,
RICHLAND, ROCK, RUSK, SAUK, SAWYER, SHAWANO, SHEBOYGAN, ST.
CROIX, TAYLOR, TREMPERALEAU, VERNON, VILLAS, WALWORTH, WASHBURN,
WAUPACA, WAUSHARA, WINNEBAGO, AND WOOD COUNTIES

	Rates	Fringes
LABORER		
Group 1.....	\$ 31.80	17.20
Group 2.....	\$ 31.90	17.20
Group 3.....	\$ 31.95	17.20
Group 4.....	\$ 32.15	17.20
Group 5.....	\$ 32.00	17.20
Group 6.....	\$ 28.43	17.20

LABORER CLASSIFICATIONS

GROUP 1: General Laborer; Tree Trimmer; Conduit Layer;
Demolition and Wrecking Laborer; Guard Rail, Fence, and
Bridge Builder; Landscaper; Multiplate Culvert Assembler;
Stone Handler; Bituminous Worker (Shoveler, Loader, and
Utility Man); Batch Truck Dumper or Cement Handler;
Bituminous Worker (Dumper, Ironer, Smoother and Tamper);
Concrete Handler

GROUP 2: Air Tool Operator; Joint Sawyer and Filler
(Pavement); Vibrator or Tamper Operator (Mechanical Hand
Operated); Chain Saw Operator, Demolition Burning Torch
Laborer

GROUP 3: Bituminous Worker (Raker and Luteman); Formsetter
(Curb, Sidewalk and Pavement); Strike Off Man

GROUP 4: Line and Grade Specialist

GROUP 5: Blaster; powderman

GROUP 6: Flagperson; Traffic Control

LABO0464-003 06/04/2018

DANE COUNTY

	Rates	Fringes
LABORER		
Group 1.....	\$ 32.08	17..20
Group 2.....	\$ 32.18	17..20
Group 3.....	\$ 32.23	17..20
Group 4.....	\$ 32.43	17..20

Group 5.....	\$ 32.28	17..20
Group 6.....	\$ 28.43	17..20

LABORERS CLASSIFICATIONS:

GROUP 1: General Laborer; Tree Trimmer; Conduit Layer; Demolition and Wrecking Laborer; Guard Rail, Fence, and Bridge Builder; Landscaper; Multiplate Culvert Assembler; Stone Handler; Bituminous Worker (Shoveler, Loader, and Utility Man); Batch Truck Dumper or Cement Handler; Bituminous Worker (Dumper, Ironer, Smoother, and Tamper); Concrete Handler

GROUP 2: Air Tool Operator; Joint Sawyer and Filler (Pavement); Vibrator or Tamper Operator (Mechanical Hand Operated); Chain Saw Operator; Demolition Burning Torch Laborer

GROUP 3: Bituminous Worker (Raker and Luteman); Formsetter (Curb, Sidewalk, and Pavement); Strike Off Man

GROUP 4: Line and Grade Specialist

GROUP 5: Blaster; Powderman

GROUP 6: Flagperson and Traffic Control Person

PAIN0106-008 05/01/2017

ASHLAND, BAYFIELD, BURNETT, AND DOUGLAS COUNTIES

	Rates	Fringes
Painters:		
New:		
Brush, Roller.....	\$ 30.33	17.27
Spray, Sandblast, Steel....	\$ 30.93	17.27
Repaint:		
Brush, Roller.....	\$ 28.83	17.27
Spray, Sandblast, Steel....	\$ 29.43	17.27

PAIN0108-002 06/01/2017

RACINE COUNTY

	Rates	Fringes
Painters:		
Brush, Roller.....	\$ 33.74	18.95
Spray & Sandblast.....	\$ 34.74	18.95

PAIN0259-002 05/01/2008

BARRON, CHIPPEWA, DUNN, EAU CLAIRE, PEPIN, PIERCE, POLK, RUSK, SAWYER, ST. CROIX, AND WASHBURN COUNTIES

	Rates	Fringes
PAINTER.....	\$ 24.11	12.15

PAIN0259-004 05/01/2015

BUFFALO, CRAWFORD, JACKSON, LA CROSSE, MONROE, TREMPPEALEAU, AND VERNON COUNTIES

	Rates	Fringes
PAINTER.....	\$ 22.03	12.45

PAIN0781-002 06/01/2018

JEFFERSON, MILWAUKEE, OZAUKEE, WASHINGTON, AND WAUKESHA COUNTIES

	Rates	Fringes
Painters:		
Bridge.....	\$ 31.60	23.51
Brush.....	\$ 31.55	23.51

Spray & Sandblast.....	\$ 32.30	23.51
------------------------	----------	-------

PAIN0802-002 06/01/2017

COLUMBIA, DANE, DODGE, GRANT, GREEN, IOWA, LAFAYETTE, RICHLAND,
ROCK, AND SAUK COUNTIES

	Rates	Fringes
PAINTER		
Brush.....	\$ 28.25	17.72

PREMIUM PAY:
Structural Steel, Spray, Bridges = \$1.00 additional per
hour.

PAIN0802-003 06/01/2017

ADAMS, BROWN, CALUMET, CLARK, DOOR, FOND DU LAC, FOREST, GREEN
LAKE, IRON, JUNEAU, KEWAUNEE, LANGLADE, LINCOLN, MANITOWOC,
MARATHON, MARINETTE, MARQUETTE, MENOMINEE, OCONTO, ONEIDA,
OUTAGAMIE, PORTAGE, PRICE, SHAWANO, SHEBOYGAN, TAYLOR, VILAS,
WAUSHARA, WAUPACA, WINNEBAGO, AND WOOD COUNTIES

	Rates	Fringes
PAINTER.....	\$ 24.89	12.05

PAIN0934-001 06/01/2017

KENOSHA AND WALWORTH COUNTIES

	Rates	Fringes
Painters:		
Brush.....	\$ 33.74	18.95
Spray.....	\$ 34.74	18.95
Structural Steel.....	\$ 33.89	18.95

PAIN1011-002 06/01/2017

FLORENCE COUNTY

	Rates	Fringes
Painters:.....	\$ 24.86	12.23

PLAS0599-010 06/01/2017

	Rates	Fringes
CEMENT MASON/CONCRETE FINISHER		
Area 1.....	\$ 39.46	17.17
Area 2 (BAC).....	\$ 35.07	19.75
Area 3.....	\$ 35.61	19.40
Area 4.....	\$ 34.70	20.51
Area 5.....	\$ 36.27	18.73
Area 6.....	\$ 32.02	22.99

AREA DESCRIPTIONS

AREA 1: BAYFIELD, DOUGLAS, PRICE, SAWYER, AND WASHBURN
COUNTIES

AREA 2: ADAMS, ASHLAND, BARRON, BROWN, BURNETT, CALUMET,
CHIPPEWA, CLARK, COLUMBIA, DODGE, DOOR, DUNN, FLORENCE,
FOND DU LAC, FOREST, GREEN LAKE, IRON, JEFFERSON, KEWAUNEE,
LANGLADE, LINCOLN, MANITOWOC, MARATHON, MARINETTE,
MARQUETTE, MENOMINEE, OCONTO, ONEIDA, OUTAGAMIE, POLK,
PORTAGE, RUSK, ST CROIX, SAUK, SHAWANO, SHEBOYGAN, TAYLOR,
VILAS, WALWORTH, WAUPACA, WAUSHARA, WINNEBAGO, AND WOOD
COUNTIES

AREA 3: BUFFALO, CRAWFORD, EAU CLAIRE, JACKSON, JUNEAU, LA
CROSSE MONROE, PEPIN, PIERCE, RICHLAND, TREMPLEAU, AND
VERNON COUNTIES

AREA 4: MILWAUKEE, OZAUKEE, WASHINGTON, AND WAUKESHA COUNTIES

AREA 5: DANE, GRANT, GREEN, IOWA, LAFAYETTE, AND ROCK
COUNTIES

AREA 6: KENOSHA AND RACINE COUNTIES

PLUM0011-003 05/07/2018

ASHLAND, BAYFIELD, BURNETT, DOUGLAS, IRON, SAWYER, AND WASHBURN
COUNTIES

	Rates	Fringes
PLUMBER.....	\$ 40.63	20.72

PLUM0075-002 06/01/2016

MILWAUKEE, OZAUKEE, WASHINGTON, AND WAUKESHA COUNTIES

	Rates	Fringes
PLUMBER.....	\$ 40.27	21.47

PLUM0075-004 06/01/2016

DODGE (Watertown), GREEN, JEFFERSON, LAFAYETTE, AND ROCK
COUNTIES

	Rates	Fringes
PLUMBER.....	\$ 40.52	21.47

PLUM0075-009 06/01/2016

COLUMBIA, DANE, IOWA, MARQUETTE, RICHLAND AND SAUK COUNTIES

	Rates	Fringes
PLUMBER.....	\$ 38.82	20.12

PLUM0111-007 05/28/2018

MARINETTE COUNTY (Niagara only)

	Rates	Fringes
PLUMBER/PIPEFITTER.....	\$ 33.33	24.48

PLUM0118-002 06/01/2018

KENOSHA, RACINE, AND WALWORTH COUNTIES

	Rates	Fringes
Plumber and Steamfitter.....	\$ 44.95	20.95

PLUM0400-003 06/04/2018

ADAMS, BROWN, CALUMET, DODGE (except Watertown), DOOR, FOND DU
LAC, GREEN LAKE, KEWAUNEE, MANITOWOC, MARINETTE (except
Niagara), MENOMINEE, OCONTO, OUTAGAMIE, SHAWANO, SHEBOYGAN,
WAUPACA, WAUSHARA, AND WINNEBAGO COUNTIES

	Rates	Fringes
PLUMBER/PIPEFITTER.....	\$ 36.74	19.06

PLUM0434-002 06/03/2018

BARON, BUFFALO, CHIPPEWA, CLARK, CRAWFORD, DUNN, EAU CLAIRE,
FLORENCE, FOREST, GRANT, JACKSON, JUNEAU, LA CROSSE, LANGLADE,
LINCOLN, MARATHON, MONROE, ONEIDA, PEPIN, PIERCE, POLK,
PORTAGE, PRICE, RUSK, ST. CROIX, TAYLOR, TREMPEREAU, VERNON,
VILAS, AND WOOD COUNTIES

	Rates	Fringes
PIPEFITTER.....	\$ 40.15	18.57

 PLUM0601-003 06/04/2018

DODGE (Watertown), GREEN, JEFFERSON, LAFAYETTE, MILWAUKEE,
 OZAUKEE, ROCK, WASHINGTON AND WAUKESHA COUNTIES

	Rates	Fringes
PIPEFITTER.....	\$ 45.52	24.54

 PLUM0601-009 06/04/2017

COLUMBIA, DANE, IOWA, MARQUETTE, RICHLAND AND SAUK COUNTIES

	Rates	Fringes
PIPEFITTER.....	\$ 47.08	20.89

 TEAM0039-002 06/01/2018

	Rates	Fringes
TRUCK DRIVER		
1 & 2 Axle Trucks.....	\$ 28.12	21.20
3 or more axles; Euclids or Dumptor, Articulated Truck, Mechanic.....	\$ 28.27	21.20

 SUWI2011-001 11/16/2011

	Rates	Fringes
WELL DRILLER.....	\$ 16.52	

 WELDERS - Receive rate prescribed for craft performing
 operation to which welding is incidental.

=====

Note: Executive Order (EO) 13706, Establishing Paid Sick Leave for Federal Contractors applies to all contracts subject to the Davis-Bacon Act for which the contract is awarded (and any solicitation was issued) on or after January 1, 2017. If this contract is covered by the EO, the contractor must provide employees with 1 hour of paid sick leave for every 30 hours they work, up to 56 hours of paid sick leave each year. Employees must be permitted to use paid sick leave for their own illness, injury or other health-related needs, including preventive care; to assist a family member (or person who is like family to the employee) who is ill, injured, or has other health-related needs, including preventive care; or for reasons resulting from, or to assist a family member (or person who is like family to the employee) who is a victim of, domestic violence, sexual assault, or stalking. Additional information on contractor requirements and worker protections under the EO is available at www.dol.gov/whd/govcontracts.

Unlisted classifications needed for work not included within the scope of the classifications listed may be added after award only as provided in the labor standards contract clauses (29CFR 5.5 (a) (1) (ii)).

The body of each wage determination lists the classification and wage rates that have been found to be prevailing for the cited type(s) of construction in the area covered by the wage determination. The classifications are listed in alphabetical order of "identifiers" that indicate whether the particular rate is a union rate (current union negotiated rate for local), a survey rate (weighted average rate) or a union average rate (weighted union average rate).

Union Rate Identifiers

A four letter classification abbreviation identifier enclosed in dotted lines beginning with characters other than "SU" or "UAVG" denotes that the union classification and rate were prevailing for that classification in the survey. Example: PLUM0198-005 07/01/2014. PLUM is an abbreviation identifier of the union which prevailed in the survey for this classification, which in this example would be Plumbers. 0198 indicates the local union number or district council number where applicable, i.e., Plumbers Local 0198. The next number, 005 in the example, is an internal number used in processing the wage determination. 07/01/2014 is the effective date of the most current negotiated rate, which in this example is July 1, 2014.

Union prevailing wage rates are updated to reflect all rate changes in the collective bargaining agreement (CBA) governing this classification and rate.

Survey Rate Identifiers

Classifications listed under the "SU" identifier indicate that no one rate prevailed for this classification in the survey and the published rate is derived by computing a weighted average rate based on all the rates reported in the survey for that classification. As this weighted average rate includes all rates reported in the survey, it may include both union and non-union rates. Example: SULA2012-007 5/13/2014. SU indicates the rates are survey rates based on a weighted average calculation of rates and are not majority rates. LA indicates the State of Louisiana. 2012 is the year of survey on which these classifications and rates are based. The next number, 007 in the example, is an internal number used in producing the wage determination. 5/13/2014 indicates the survey completion date for the classifications and rates under that identifier.

Survey wage rates are not updated and remain in effect until a new survey is conducted.

Union Average Rate Identifiers

Classification(s) listed under the UAVG identifier indicate that no single majority rate prevailed for those classifications; however, 100% of the data reported for the classifications was union data. EXAMPLE: UAVG-OH-0010 08/29/2014. UAVG indicates that the rate is a weighted union average rate. OH indicates the state. The next number, 0010 in the example, is an internal number used in producing the wage determination. 08/29/2014 indicates the survey completion date for the classifications and rates under that identifier.

A UAVG rate will be updated once a year, usually in January of each year, to reflect a weighted average of the current negotiated/CBA rate of the union locals from which the rate is based.

WAGE DETERMINATION APPEALS PROCESS

1.) Has there been an initial decision in the matter? This can be:

- * an existing published wage determination
- * a survey underlying a wage determination
- * a Wage and Hour Division letter setting forth a position on a wage determination matter
- * a conformance (additional classification and rate) ruling

On survey related matters, initial contact, including requests for summaries of surveys, should be with the Wage and Hour Regional Office for the area in which the survey was conducted because those Regional Offices have responsibility for the Davis-Bacon survey program. If the response from this initial contact is not satisfactory, then the process described in 2.) and 3.) should be followed.

With regard to any other matter not yet ripe for the formal process described here, initial contact should be with the

Branch of Construction Wage Determinations. Write to:

Branch of Construction Wage Determinations
Wage and Hour Division
U.S. Department of Labor
200 Constitution Avenue, N.W.
Washington, DC 20210

2.) If the answer to the question in 1.) is yes, then an interested party (those affected by the action) can request review and reconsideration from the Wage and Hour Administrator (See 29 CFR Part 1.8 and 29 CFR Part 7). Write to:

Wage and Hour Administrator
U.S. Department of Labor
200 Constitution Avenue, N.W.
Washington, DC 20210

The request should be accompanied by a full statement of the interested party's position and by any information (wage payment data, project description, area practice material, etc.) that the requestor considers relevant to the issue.

3.) If the decision of the Administrator is not favorable, an interested party may appeal directly to the Administrative Review Board (formerly the Wage Appeals Board). Write to:

Administrative Review Board
U.S. Department of Labor
200 Constitution Avenue, N.W.
Washington, DC 20210

4.) All decisions by the Administrative Review Board are final.

=====

END OF GENERAL DECISION



Wisconsin Department of Transportation

February 5, 2019

Division of Transportation Systems Development

Bureau of Project Development
4822 Madison Yards Way, 4th Floor South
Madison, WI 53705

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

Proposal #06: 1517-75-77, WISC 2019 120
USH 10 – USH 10/STH 441
County CB – Oneida St
USH 10
Winnebago County

Letting of February 12, 2019

This is Addendum No. 01, which provides for the following:

Schedule of Items:

Revised Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
204.0100	Removing Pavement	SY	15,591	-1,349	14,242
205.0100	Common Excavation	CY	35,922	-5,874	30,048
465.0120	Asphaltic Surface Driveways and Field Entrances	Ton	40	39	79
465.0315	Asphaltic Flume	SY	39	-21	18
608.0324	Storm Sewer Pipe Reinforced Concrete Class III 24-Inch	LF	1,489	27	1,516
SPV.0035.001	Roadway Embankment	CY	1,241	391	1,632

Added Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
643.0300	Traffic Control Drums	Day	0	340	340
643.0715	Traffic Control Warning Lights Type C	Day	0	340	340

Deleted Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
415.4100	Concrete Pavement Joint Filling	SY	24,167	-24,167	0

Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
34	Removal Plan- Added Removing Grass (Paid As Common Excavation)
35	Removal Plan- Added Removing Grass (Paid As Common Excavation) and Updated Removing Asphaltic Surface
36	Removal Plan – Updated Removing Asphaltic Surface
71	Storm Sewer- Extended pipe 108G to 108H
117-120	Alignment Details – Midway Rd (CTH AP) Added in PI's
122, 126-128,	Alignment Details – Racine Rd- Added in PI's
130-131	Alignment Details- Midway Road Ramps- Added PI's
137	Miscellaneous Quantities- Updated
140	Miscellaneous Quantities – Updated
143	Miscellaneous Quantities- Updated
146	Miscellaneous Quantities - Updated
148	Miscellaneous Quantities- Updated
150	Miscellaneous Quantities – Updated
169	Miscellaneous Quantities – Updated
319-328	Earthwork Quantities
329-353	Cross Sections: Midway Road (CTH AP)
377-379	Cross Sections: Midway Road Northwest Ramp
380-382	Cross Sections: Midway Road Northeast Ramp
383-385	Cross Sections: Midway Road Southeast Ramp
386-390	Cross Sections: Midway Road Southwest Ramp
391-392	Cross Sections: Midway Road Northwest Bypass Ramp
393-394	Cross Sections: Midway Road Southeast Bypass Ramp

Added Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of why sheet was added)
206A	Plan- Racine Rd- Was not included in LET Plan

Schedule of Items

Attached, dated February 5, 2019, are the revised Schedule of Items Pages 1 – 11.

Plan Sheets

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:

Revised: 34 – 36, 71, 117 – 120, 122, 126 – 128, 130, 131, 137, 140, 143, 146, 148, 150, 169, 319 – 353, and 377 – 394.

Added: 206A

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman


Proposal Development Specialist
Proposal Management Section

END OF ADDENDUM

LEGEND

	REMOVING PAVEMENT		PAVEMENT REMOVED UNDER PREVIOUS CONTRACT
	REMOVING GRASS (PAID AS COMMON EXCAVATION)		REMOVING ASPHALTIC SURFACE (PAID AS COMMON EXCAVATION)
	REMOVING SMALL PIPE CULVERT		REMOVING STORM SEWER
	SAMCUT		REMOVING INLETS
	REMOVING SURFACE DRAINS		REMOVING MANHOLES

Addendum No. 01
ID 1517-75-77
Revised Sheet 34
February 5, 2019



NOTE: SEE SIGNING PLAN FOR SIGN REMOVALS

PROJECT NO: 1517-75-77

HWY: STH 441/USH 10

COUNTY: WINNEBAGO

REMOVAL PLAN

SHEET 34

E

FILE NAME : S:\NPS\CD\WIS441\151775-77\021100-RWNE-15177577-021100-RW.DWG


LAYOUT NAME - NE-15177577-021100-RW - NE-15177577-021102-RW

PLOT BY : MARTENS, JOHN M

PLOT SCALE : 1 IN:40 FT

WISDOT/CADDs SHEET 42

Addendum No. 01
ID 1517-75-77
Revised Sheet 35
February 5, 2019



LEGEND

- | | |
|--|--|
| REMOVING PAVEMENT | PAVEMENT REMOVED UNDER PREVIOUS CONTRACT |
| REMOVING GRASS (PAID AS COMMON EXCAVATION) | REMOVING ASPHALTIC SURFACE (PAID AS COMMON EXCAVATION) |
| REMOVING SMALL PIPE CULVERT | REMOVING STORM SEWER |
| SAWCUT | REMOVING INLETS |
| REMOVING SURFACE DRAINS | REMOVING MANHOLES |

NOTE: SEE SIGNING PLAN FOR SIGN REMOVALS


REMOVAL PLAN

COUNTY: WINNEBAGO

HWY: STH 441/USH 10

PROJECT NO: 1517-75-77

SHEET 35





Addendum No. 01
ID 1517-75-77
Revised Sheet 36
February 5, 2019


NOTE: SEE SIGNING PLAN FOR SIGN REMOVALS

LEGEND

- | | | | |
|--|-----------------------------|--|---|
| | REMOVING PAVEMENT | | REMOVING ASPHALTIC SURFACE
(PAID AS COMMON EXCAVATION) |
| | REMOVING SMALL PIPE CULVERT | | REMOVING STORM SEWER |
| | SAWCUT | | REMOVING INLETS |
| | REMOVING SURFACE DRAINS | | REMOVING MANHOLES |





Addendum No. 01
ID 1517-75-77
Revised Sheet 71
February 5, 2019




Addendum No. 01
 ID 1517-75-77
 Revised Sheet 117
 February 5, 2019

PROJECT NO: 1517-75-77	HWY: STH 441/USH 10	COUNTY: WINNEBAGO	ALIGNMENT DETAILS - MIDWAY RD (CTH AP)	SHEET 117	E
FILE NAME : S:\NPOS\330\WIS441\1517750-72-77-85\SHEETS\PLAN\1517-75-77\027200-AD\NE-15177577-027200-AD.DWG					WISDOT/CADD SHEET 42
LAYOUT NAME : NE-15177577-027200-AD - NE-15177577-027201-AD					
PLOT DATE : 1/25/2019 10:29 AM					
PLOT BY : SLEZAK, KIMBERLY A					
PLOT NAME :					
PLOT SCALE : 1 IN:40 FT					








Addendum No. 01
ID 1517-75-77
Revised Sheet 120
February 5, 2019


PROJECT NO: 1517-75-77	HWY: STH 441/USH 10	COUNTY: WINNEBAGO	ALIGNMENT DETAILS - MIDWAY RD (CTH AP)	SHEET 120	E
------------------------	---------------------	-------------------	--	-----------	---

FILE NAME : S:\NPD\3D\WIS441\151775-75-77\027200-AD\NE-15177577-027200-AD.DWG
LAYOUT NAME : NE-15177577-027200-AD - NE-15177577-027200-AD
PLOT DATE : 1/25/2019 10:29 AM
PLOT BY : SLEZAK, KIMBERLY A
PLOT NAME :
PLOT SCALE : 1 IN=40 FT
WISDOT/CADDs SHEET 42




Addendum No. 01
ID 1517-75-77
Revised Sheet 122
February 5, 2019

PROJECT NO: 1517-75-77	HWY: STH 441/USH 10	COUNTY: WINNEBAGO	ALIGNMENT DETAILS - RACINE RD	SHEET 122	E
FILE NAME : S:\NPOS\G3D\WIS441\15177570-72-77-85\SHEETS\PLAN\1517-75-77\027200-AD\NE-15177577-027200-AD.DWG					WISDOT/CADDs SHEET 42
LAYOUT NAME - NE-15177577-027200-AD - NE-15177577-027200-AD					
PLOT DATE : 1/25/2019 10:29 AM					
PLOT BY : SLEZAK, KIMBERLY A					
PLOT NAME :					
PLOT SCALE : 1 IN:40 FT					




Addendum No. 01
ID 1517-75-77
Revised Sheet 126
February 5, 2019



PROJECT NO: 1517-75-77	HWY: STH 441/USH 10	COUNTY: WINNEBAGO	ALIGNMENT DETAILS - RACINE RD	SHEET 127	E
FILE NAME : S:\NPOS\G30\WIS441\15177570-72-77-85\SHEETS\PLAN\1517-75-77\027200-AD\NE-15177577-027212-AD.DWG					WISDOT/CADD'S SHEET 42
LAYOUT NAME - NE-15177577-027200-AD - NE-15177577-027212-AD					
PLOT DATE : 1/25/2019 10:29 AM					
PLOT BY : SLEZAK, KIMBERLY A					
PLOT NAME :					
PLOT SCALE : 1 IN=40 FT					

44+79.34 MATCH LINE



44R+00

N0° 09' 11"E

43R+

1

42R+00

11R+00

11"E

NO


R+00

MAT

PROJECT NO: 1517-75-77	HWY: STH 441/USH 10	COUNTY: WINNEBAGO	ALIGNMENT DETAILS - RACINE RD	SHEET 128
FILE NAME : S:\PROJ\GIS\WIS441\1517-75-77_85\SHEETS\PLAN\1517-75-77_027200-AD.DWG LAYOUT NAME : NE-15177577-027200-AD - NE-15177577-027200-AD PLOT DATE : 1/25/2019 10:29 AM PLOT BY : SLEZAK, KIMBERLY A PLOT SCALE : 1 IN=40 FT WISDOT/CADDIS SHEET 42				


2

2



Addendum No. 01
ID 1517-75-77
Revised Sheet 130
February 5, 2019

PROJECT NO: 1517-75-77	HWY: STH 441/USH 10	COUNTY: WINNEBAGO	ALIGNMENT DETAILS - MIDWAY ROAD NE RAMP	SHEET 130	E
FILE NAME : S:\NPOS\330\WIS441\151775-77\027200-AD\NE-15177577-027200-AD.DWG					WISDOT/CADD SHEET 42
LAYOUT NAME : NE-15177577-027200-AD - NE-15177577-027215-AD					
PLOT DATE : 1/25/2019 10:29 AM					PLOT BY : SLEZAK, KIMBERLY A
PLOT SCALE : 1 IN:40 FT					



Addendum No. 01
 ID 1517-75-77
 Revised Sheet 131
 February 5, 2019

PROJECT NO: 1517-75-77

HWY: STH 441/USH 10

COUNTY: WINNEBAGO

ALIGNMENT DETAILS - MIDWAY ROAD SE RAMP

SHEET 131

E

FILE NAME : S:\NPOS\3D\WIS441\1517750-72-77-85\SHEETS\PLAN\1517-75-77\027200-AD\NE-15177577-027216-AD

PLOT DATE : 1/25/2019 10:29 AM

PLOT BY : SLEZAK, KIMBERLY A

PLOT NAME :

PLOT SCALE : 1 IN=40 FT

WISDOT/CADD SHEET 42

CLEARING AND GRUBBING

CATEGORY	STATION	OFFSET	LOCATION	201.0105 CLEARING	201.0205 GRUBBING	201.0120 CLEARING	201.0220 GRUBBING	REMARKS
1000	38R+00 TO 39R+00	LT	RACINE RD	1	1	-	-	
	39R+00 TO 40R+00	LT	RACINE RD	1	1	-	-	
	47R+00 TO 48R+00	LT	RACINE RD	1	1	-	-	
	RACINE SUBTOTAL			3	3	0	0	
	12MEB+87	LT	MIDWAY RD	-	-	3	3	
	12MEB+87	LT	MIDWAY RD	-	-	4	4	
	12MEB+87	LT	MIDWAY RD	-	-	6	6	
	12MEB+87	LT	MIDWAY RD	-	-	2	2	
	12MEB+87	LT	MIDWAY RD	-	-	5	5	
	12MEB+87	LT	MIDWAY RD	-	-	5	5	
	13MEB+25	LT	MIDWAY RD	-	-	6	6	
	15MEB+08	RT	MIDWAY RD	-	-	5	5	
	15MEB+69	RT	MIDWAY RD	-	-	18	18	
	15MEB+88	RT	MIDWAY RD	-	-	19	19	
	16MEB+13	RT	MIDWAY RD	-	-	16	16	
	16MEB+35	RT	MIDWAY RD	-	-	16	16	
	28MEB+86	RT	MIDWAY RD	-	-	9	9	
	29MEB+47	RT	MIDWAY RD	-	-	12	12	
	MIDWAY SUBTOTAL			0	0	126	126	
	PROJECT TOTAL			3	3	126	126	

REMOVALS PAVEMENT

CATEGORY	STATION	OFFSET	LOCATION	204.0100 REMOVING PAVEMENT	204.0120* REMOVING ASPHALTIC SURFACE MILLING	204.0150 REMOVING CURB AND GUTTER	REMARKS
1000	2R+39 - 14R+39	R/L	RACINE RD	-	4,094	-	MILLING
	13R+54 - 14R+49	R/L	RACINE RD	-	52	-	MILLING BETWEEN RAIL
	13R+63 - 19R+16	R/L	RACINE RD	-	2,361	-	MILLING
	21R+57 - 36R+63	R/L	RACINE RD	-	5,897	-	MILLING
	36R+63 - 37R+59	R/L	RACINE RD	-	746	-	MILLING
	37R+59 - 50R+01	R/L	RACINE RD	2,761	-	-	OLD CONCRETE ROADWAY
	RACINE SUBTOTAL			2,761	13,150	0	
	11MEB+50 - 25MEB+21	R/L	MIDWAY RD	8,756	-	-	
	25MEB+21 - 25MEB+77	R/L	MIDWAY RD	2,725	-	-	
	10MEB+36 - 11MEB+51	RT	MIDWAY RD	-	-	115	
	10MEB+23 - 11MEB+50	LT	MIDWAY RD	-	-	146	
	MIDWAY SUBTOTAL			11,481	0	262	
	TOTAL			14,242	13,150	262	

* QUANTITIES SHOWN ELSEWHERE ON PLAN

PROJECT NO: 1517-75-77

HWY: STH 441/USH 10

COUNTY: WINNEBAGO

MISCELLANEOUS QUANTITIES

SHEET 137

E

FILE NAME : S:\NPD\3030\WIS441\151775-77-85 SHEETS\PLAN\1517-75-77-030200-MO\030201.DWG

LAYOUT NAME - 030201 - 030201.MO

PLOT DATE : 1/15/2019 3:15 PM

PLOT BY : SLEZAK, KIMBERLY A PLOT NAME :

PLOT SCALE : *****

WISDOT/CADDs SHEET 42

REMOVE COMMERCIAL SIGN

CATEGORY	STATION	OFFSET	LOCATION	EACH	REMARKS
1000	25MEB+92	RT	MIDWAY RD	1	EARL LUTHO SIGN
	PROJECT TOTAL			1	

REMOVING GUARDRAIL

CATEGORY	STATION	OFFSET	LOCATION	LF
1000	45R+35 to 47R+92	LT	RACINE RD	257
	PROJECT TOTAL			257

Addendum No. 01
ID 1517-75-77
Revised Sheet 137
February 5, 2019

Addendum No. 01
ID 1517-75-77
Revised Sheet 140
February 5, 2019

EARTHWORK QUANTITIES

Division	From/To Station	Location	205.0100* Common Excavation (1)		Salvaged/Unusable Pavement Material (CY) (3)	Available Material (CY) (4)	Fill (CY)	Mass Ordinate +/- (5)	SPV.0035.001 Roadway Embankment (CY)
			Cut (CY) (2)	EBS (CY)					
Division 1									
Midway Road MEB	10+78.23/29+76		19,597	0	2,763	16,844	760	16,844	760
Division 1 Subtotal			19,597	0	2,763	16,844	760	16,844	760
Division 2									
Racine Road	10+78.23/52+75		6,436	0	1,724	4,712	623	4,712	623
Division 2 Subtotal			6,436	0	1,724	4,712	623	4,712	623
Division 3									
Midway NE Ramp	37+35.61/244+50		869	0	77	791	21	791	21
Division 3 Subtotal			869	0	77	791	21	791	21
Division 4									
Midway NW Ramp	242+50/241+96.79		763	0	0	763	108	763	108
Division 4 Subtotal			763	0	0	763	108	763	108
Division 5									
Midway SE Ramp	240+59.13/241+00		789	0	0	789	0	789	0
Division 5 Subtotal			789	0	0	789	0	789	0
Division 6									
Midway SW Ramp	239+25/241+12.07		348	0	0	348	120	348	120
Division 6 Subtotal			348	0	0	348	120	348	120
Division 7									
Midway NWB Bypass Ramp	240+11.83/01+48.34		850	0	0	850	0	850	0
Division 7 Subtotal			850	0	0	850	0	850	0
Division 8									
Midway SEB Bypass Ramp	00+49.43/01+00		297	0	0	297	0	297	0
Division 8 Subtotal			297	0	0	297	0	297	0
PROJECT 1517-75-77 Totals			29,948	0	4,554	25,394	1,632	25,394	1,632
Total Common Exc			29,948				Total Roadway Embankment		1,632

*. Additional Quantities Shown Elsewhere on Plan

Notes:

- (1) Common Excavation is the sum of the Cut and EBS Excavation columns. Item number 205.0100
- (2) Salvaged/Unusable Pavement Material is included in Cut
- (3) Salvaged/Unusable Pavement Material is the Volume of All Existing Pavement. Concrete Pavement for Ramps are included in Midway Road Salvage Value.
- (4) Available Material = Cut - Salvaged/Unusable Pavement Material
- (5) The Mass Ordinate +/- or - Qty calculated for the Division. Plus quantity indicates an excess of material within the Division. Minus indicates a shortage of material within the Division.

PROJECT NO: 1517-75-77

HWY: STH 441/USH 10

COUNTY: WINNEBAGO

MISCELLANEOUS QUANTITIES

SHEET 140

E

FILE NAME : S:\NPS\G30\WIS441\1517\75-77-85\SHEETS\PLAN\1517-75-77\030200-MO\030201.DWG

LAYOUT NAME - 030201 - 030204.MO

PLOT DATE : 1/30/2019 3:35 PM

PLOT BY : SLEZAK, KIMBERLY A

PLOT NAME :

PLOT SCALE : *****

WISDOT/CADDs SHEET 42

Addendum No. 01
ID 1517-75-77
Revised Sheet 143
February 5, 2019

01
143
19

PAVEMENT ITEMS

CATEGORY	STATION	OFFSET	LOCATION	SPV.0180.001 MODIFIED HIGH PERFORMANCE CONCRETE (HPC) PAVEMENT 9-INCH	455.0605* TACK COAT	HMA PAVEMENT 3 MT 58-28 S	HMA PAVEMENT 4 MT 58-28 H	REMARKS
1000	2R+39	-	14R+39	-	-	-	604	HAUL ROAD
	10R+45	-	10R+81	RT	-	-	12	AIRPORT RD, OVERLAYED CONC.
	13R+54	-	14R+49	R/L	-	4	8	HAUL ROAD BETWEEN RAILS
	13R+63	-	19R+16	R/L	-	165	348	HAUL ROAD
	21R+57	-	36R+63	R/L	-	413	870	HAUL ROAD
	36R+63	-	37R+59	R/L	-	52	110	HAUL ROAD
	37R+59	-	49R+57	RT	1,598	-	-	TRAVEL LANE
	37R+59	-	49R+57	LT	2,132	-	-	TRAVEL LANE AND BIKE LANE
	38R+79	-	49R+52	LT	1,054	-	-	LEFT TURN LANE
	37R+59	-	40R+03	RT	109	-	-	BIKE LANE
	40R+03	-	44R+74	RT	1,138	-	-	RIGHT TURN LANE AND MIDWAY RD INT
	44R+75	-	49R+57	RT	214	-	-	BIKE LANE
	49R+57	-	50R+01	R/L	-	15	16	38
	RACINE SUBTOTAL				6,244	935	16	1,990
10MEB+77	-	24MEB+46	RT	MIDWAY RD	-	-	-	
10MWB+77	-	24MWB+74	LT	MIDWAY RD	-	-	-	
11MEB+10	-	12MEB+28	R/L	MIDWAY RD	-	-	-	
18MEB+61	-	24MEB+07	R/L	MIDWAY RD	-	-	-	
25MEB+24	-	29MEB+77	RT	MIDWAY RD	-	-	-	
25MWB+61	-	29MWB+77	LT	MIDWAY RD	-	-	-	
26MEB+65	-	28MEB+97	R/L	MIDWAY RD	-	-	-	
24MEB+46	-	25MEB+62	R/L	MIDWAY RD	-	-	-	
24MEB+46	-	25MEB+62	R/L	MIDWAY RD	-	-	-	
240MNB+50	-	242MNB+00	R/L	MNBW	-	-	-	
240MSW+00	-	240MSW+12	R/L	MSW	-	-	-	
240MSW+12	-	241MSW+16	R/L	MSW	-	-	-	
242MNE+48	-	244MNE+50	R/L	MNE	-	-	-	
239MSE+25	-	241MSE+18	R/L	MSE	-	-	-	
81EARL+59	-	81EARL+92	R/L	EARL ST	-	-	-	
81EARL+39	-	81EARL+59	R/L	EARL ST	-	7	7	17
MIDWAY SUBTOTAL				15,209	66	79	261	
PROJECT TOTAL				21,453	1,002	94	2,250	

*QUANTITIES SHOWN ELSEWHERE ON PLAN

CONCRETE PAVEMENT JOINT FILLING

CATEGORY	STATION	OFFSET	LOCATION	CONCRETE PAVEMENT JOINT FILLING
1000	37R+58 - 49R+57	R/L	RACINE RD	6,902
	RACINE SUBTOTAL			6,902
	10MEB+77 - 29MEB+77	R/L	MIDWAY RD	17,265
MIDWAY SUBTOTAL				17,265

BACKFILL CONTROLLED LOW STRENGTH

CATEGORY	STATION	OFFSET	LOCATION	BACKFILL CONTROLLED LOW STRENGTH
1000	38+87		RACINE RD	209,020.5
	PROJECT TOTAL			30

ASPHALTIC FLUME

CATEGORY	STATION	OFFSET	LOCATION	465.0315 ASPHALTIC FLUMES	REMARKS
	49R+61	RT	RACINE RD	6	
	49R+61	LT	RACINE RD	8	
	RACINE SUBTOTAL			14	
1000	81EARL+55	RT	EARL ST	2	
	81EARL+55	LT	EARL ST	2	
	MIDWAY SUBTOTAL			4	

Addendum No. 01
ID 1517-75-77
Revised Sheet 146
February 5, 2019

DRIVEWAYS

CATEGORY	STATION	OFFSET	LOCATION	204.0120* REMOVING ASPHALTIC SURFACE MILLING	205.0100* EXCAVATION COMMON (DRIVEWAY)	305.0110* BASE AGGREGATE DENSE		416.0160 CONCRETE DRIVEWAY (APRON) (SIDEWALK)	416.0170 CONCRETE DRIVEWAY 7-INCH (APRON) (SIDEWALK)		455.0605* TACK COAT	465.0120 ASPHALTIC SURFACE DRIVEWAYS AND FIELD ENTRANCES	REMARKS
						3/4-INCH (BACK OF SIDEWALK)	1-1/4-INCH (DRIVEWAY)	SY	SY	SY	GAL	TON	
1000	4R+09 - 4R+46	RT	RACINE RD	27	-	-	-	-	-	-	1.90	3.26	
	4R+70 - 5R+07	LT	RACINE RD	22	-	-	-	-	-	-	1.54	2.64	
	8R+74 - 9R+27	RT	RACINE RD	28	-	-	-	-	-	-	1.93	3.30	
	10R+34 - 10R+78	LT	RACINE RD	58	-	-	-	-	-	-	4.04	6.92	
	27R+44 - 27R+67	LT	RACINE RD	11	-	-	-	-	-	-	0.74	1.26	
	27R+79 - 28R+05	LT	RACINE RD	10	-	-	-	-	-	-	0.69	1.18	
	29R+71 - 30R+01	LT	RACINE RD	13	-	-	-	-	-	-	0.91	1.56	
	30R+64 - 30R+98	RT	RACINE RD	20	-	-	-	-	-	-	1.42	2.44	
	31R+07 - 31R+33	RT	RACINE RD	17	-	-	-	-	-	-	1.17	2.00	
	31R+80 - 32R+10	RT	RACINE RD	19	-	-	-	-	-	-	1.31	2.24	
	32R+34 - 32R+62	LT	RACINE RD	13	-	-	-	-	-	-	0.94	1.60	
	33R+68 - 33R+94	LT	RACINE RD	7	-	-	-	-	-	-	0.49	0.83	
	34R+22 - 34R+53	RT	RACINE RD	27	-	-	-	-	-	-	1.89	3.24	
	34R+87 - 35R+11	RT	RACINE RD	19	-	-	-	-	-	-	1.35	2.31	
	35R+55 - 35R+93	RT	RACINE RD	39	-	-	-	-	-	-	2.73	4.68	
	37R+31 - 37R+59	RT	RACINE RD	-	2	-	11	-	-	-	-	6	INCLUDES ASPHALT SIDEWALK
	40R+69 - 40R+91	RT	RACINE RD	-	4	5	5	8	7	-	-	-	
	44R+94 - 45R+16	RT	RACINE RD	-	8	5	5	8	7	-	-	-	
	46R+33 - 46R+65	RT	RACINE RD	-	20	-	24	13	12	-	-	8	
RACINE SUBTOTAL				329	35	10	45	30	26	0	23	53	
26MW/B+76 - 27MW/B+38				-	66	-	51	-	-	35	29	25	
MIDWAY SUBTOTAL				0	66	0	51	0	0	35	4	25	
PROJECT TOTAL				329	100	10	96	56	64	0	27	79	

*QUANTITIES SHOWN ELSEWHERE ON PLAN

PROJECT NO: 1517-75-77

HWY: STH 441/USH 10

COUNTY: WINNEBAGO

MISCELLANEOUS QUANTITIES

SHEET 146

E

FILE NAME : S:\NPS\CD\WIS441\15177570-72-77-85 SHEETS\PLAN\1517-75-77\030200-MW\030201.DWG
LAYOUT NAME - 030201 - 030210.MW

PLOT DATE : 1/30/2019 10:18 AM

PLOT BY : SLEZAK, KIMBERLY A

PLOT NAME :

PLOT SCALE : *****

WISDOT/CADD SHEET 42

Addendum No. 01
ID 1517-75-77
Revised Sheet 148
February 5, 2019

STORM SEWER-STRUCTURES-RECONSTRUCT & ADJUSTMENT

CATEGORY	STRUCTURE NUMBER	STATION	OFFSET	611.0420 RECONSTRUCTING MANHOLES	611.8115 ADJUSTING INLET COVERS	REMARKS
1000	STAGE 2					
	201	24MWB+66	40.1 LT	1	-	
	300	25MWB+69	35.5 LT	1	-	
	200E	243MNE+34	1.5 LT	-	1	
	200G	243MNE+40	21.5 RT	-	1	
STAGE 2 SUBTOTAL				2	2	
PROJECT TOTAL				2	2	

APRON ENDWALLS

CATEGORY	STRUCTURE NUMBER	STATION	OFFSET	INVERT ELEVATION (FT)	522.1012 APRON ENDWALLS FOR CULVERT PIPE REINFORCED CONCRETE 12-INCH	522.1018 APRON ENDWALLS FOR CULVERT PIPE REINFORCED CONCRETE 18-INCH	522.1024 APRON ENDWALLS FOR CULVERT PIPE REINFORCED CONCRETE 24-INCH
1000	STAGE 1						
	103E	46R+69	30.7 RT	760.69	1	-	-
	STAGE 1 SUBTOTAL				1	0	0
	STAGE 2						
	108G	19MWB+71	50.9 LT	754.20	-	-	1
STAGE 2 SUBTOTAL				754.98	0	2	2
PROJECT TOTAL					1	2	2

PIPE UNDERDRAIN WRAPPED 6-INCH

CATEGORY	STATION	TO	STATION	OFFSET	LOCATION	LF	REMARKS
1000	40R+21	-	40R+71	RT	RACINE RD	50	CONNECT TO INLET 101C
	40R+22	-	40R+72	LT	RACINE RD	50	CONNECT TO INLET 101A
	47R+28	-	47R+78	RT	RACINE RD	50	CONNECT TO INLET 104C
	47R+28	-	47R+78	LT	RACINE RD	50	CONNECT TO INLET 104B
	RACINE SUBTOTAL					200	
	15MEB+67	-	16MEB+15	LT	MIDWAY RD	50	CONNECT TO INLET 107A
	15MEB+71	-	16MEB+18	LT	MIDWAY RD	50	CONNECT TO INLET 107B
	15MEB+81	-	16MEB+33	RT	MIDWAY RD	50	CONNECT TO INLET 107F
	15MEB+82	-	16MEB+32	LT	MIDWAY RD	50	CONNECT TO INLET 107E
	240MNV+77	-	241MNV+25	LT	MNV	50	CONNECT TO INLET 108B
	240MNV+85	-	241MNV+05	LT	MNV	23	CONNECT TO INLET 108E
	241MNV+05	-	241MNV+29	LT	MNV	25	CONNECT TO INLET 108E
	241MNV+03	-	241MNV+53	RT	MNV	50	CONNECT TO INLET 108D
	240MSW+25	-	240MSW+75	RT	MSW	50	CONNECT TO INLET 108M
	240MSW+27	-	240MSW+73	LT	MSW	50	CONNECT TO INLET 108N
	243MNE+05	-	243MNE+55	LT	MNE	50	CONNECT TO INLET 200E
	243MNE+17	-	243MNE+67	RT	MNE	50	CONNECT TO INLET 200G
	240MSE+22	-	240MSE+71	RT	MSE	50	CONNECT TO INLET 200N
	240MSE+24	-	240MSE+74	LT	MSE	50	CONNECT TO INLET 200L
	24MEB+42	-	25MEB+57	R/L	MIDWAY RD	182	DAYLIGHT INTO RR DITCH
	24MEB+85	-	25MEB+68	R/L	MIDWAY RD	170	DAYLIGHT INTO RR DITCH
	28MEB+53	-	29MEB+03	RT	MIDWAY RD	50	CONNECT TO INLET 500D
	28MEB+53	-	29MEB+03	LT	MIDWAY RD	50	CONNECT TO INLET 500B
MIDWAY SUBTOTAL						1,100	
PROJECT TOTAL						1,300	

PROJECT NO:1517-75-77

HWY: STH 441/USH 10

COUNTY: WINNEBAGO

MISCELLANEOUS QUANTITIES

SHEET 148

E

FILE NAME : S:\NPOS\G30\N15177570-72-77-85\SHEETS\PLAN\1517-75-77\030201-MO\030201.DWG

PLOT DATE : 1/15/2019 3:15 PM

PLOT SCALE : *****

WISDOT/CADDs SHEET 42

Addendum No. 01
ID 1517-75-77
Revised Sheet 150
February 5, 2019

STORM SEWER-PIPE

CATEGORY	FROM STRUCTURE	TO STRUCTURE	START INVERT ELEVATION (FT)	END INVERT ELEVATION (FT)	SLOPE	STORM SEWER-PIPE							
						608.0312	608.0318	608.0324	608.0412	608.0418	608.0336	608.0342	608.2329
						STORM SEWER PIPE REINFORCED CONCRETE CLASS III 12-INCH	STORM SEWER PIPE REINFORCED CONCRETE CLASS III 18-INCH	STORM SEWER PIPE REINFORCED CONCRETE CLASS III 24-INCH	STORM SEWER PIPE REINFORCED CONCRETE CLASS IV 12 INCH	STORM SEWER PIPE REINFORCED CONCRETE CLASS IV 18-INCH	STORM SEWER PIPE REINFORCED CONCRETE CLASS III 36-INCH	STORM SEWER PIPE REINFORCED CONCRETE CLASS III 42-INCH	STORM SEWER PIPE REINFORCED CONCRETE HORIZONTAL ELLIPTICAL CLASS HE-III 29X45-INCH
1000	STAGE 2												
	107	106	751.60	750.70	0.38%	-	-	-	-	-	-	237	-
	106	106B	750.69	750.30	0.40%	-	-	-	-	-	-	96	-
	106B	105	750.30	749.56	0.40%	-	-	-	-	-	-	185	-
	106A	106B	753.86	753.66	0.56%	-	36	-	-	-	-	-	-
	106C	106B	753.87	753.71	0.47%	-	34	-	-	-	-	-	-
	108I	108	753.56	753.20	0.40%	-	-	89	-	-	-	-	-
	108	107	753.12	751.70	0.50%	-	-	-	-	-	287	-	-
	107D	107B	752.36	751.95	1.02%	-	-	-	-	-	-	-	40
	107C	107B	752.65	752.40	1.02%	-	25	-	-	-	-	-	-
	107B	107A	751.92	751.70	0.70%	-	-	-	-	-	-	-	31
	107A	107	751.70	751.60	0.67%	-	-	-	-	-	-	-	15
	107H	107F	753.17	752.35	2.02%	-	-	41	-	-	-	-	-
	107G	107F	752.59	752.36	0.94%	-	25	-	-	-	-	-	-
	107F	107E	752.22	752.10	0.39%	-	-	31	-	-	-	-	-
	107E	107	752.80	752.00	0.40%	-	-	25	-	-	-	-	-
	108G	108H	754.20	753.90	0.63%	-	-	48	-	-	-	-	-
	108H	108I	753.86	753.56	0.51%	-	-	47	-	-	-	-	-
	108M	108K	754.35	754.02	0.40%	-	-	63	-	-	-	-	-
	108K	108J	754.02	753.75	0.51%	-	-	43	-	-	-	-	-
	108J	108I	753.75	753.66	0.96%	-	-	9	-	-	-	-	-
	109	108F	755.50	754.93	2.07%	-	28	-	-	-	-	-	-
	108F	108E	753.93	753.75	0.46%	-	-	39	-	-	-	-	-
	108E	108B	753.75	753.65	0.46%	-	-	22	-	-	-	-	-
	108B	108A	753.65	753.43	0.50%	-	-	44	-	-	-	-	-
	108A	108	753.43	753.20	0.50%	-	-	46	-	-	-	-	-
	108D	108C	754.40	754.19	0.92%	-	23	-	-	-	-	-	-
	108C	108B	754.19	754.00	1.00%	-	19	-	-	-	-	-	-
	108N	108M	754.60	754.40	0.94%	-	21	-	-	-	-	-	-
	108O	108N	755.80	755.00	3.55%	-	23	-	-	-	-	-	-
	108L	108M	754.98	754.61	2.46%	-	-	15	-	-	-	-	-

PROJECT NO: 1517-75-77

HWY: STH 441/USH 10

COUNTY: WINNEBAGO

MISCELLANEOUS QUANTITIES

PLOT SCALE : *****

SHEET 150

E

FILE NAME : S:\NPOS\G30\WIS441\15177570-72-77-85\SHEETS\PLAN\1517-75-77\030200-MO\030201.DWG

LAYOUT NAME - 030201 - 030214.MO

PLOT DATE : 1/15/2019 3:15 PM

PLOT BY : SLEZAK, KIMBERLY A

PLOT NAME :

WISDOT/CADDs SHEET 42

Addendum No. 01
ID 1517-75-77
Revised Sheet 169
February 5, 2019

TRAFFIC CONTROL 1517-75-77

CATEGORY	STATION	LOCATION	643.5000	REMARKS
1000	VARIES	MIDWAY AND RACINE	1	
PROJECT TOTAL			1	

TRAFFIC CONTROL

DESCRIPTION OF WORK	DAYS	643.0300	643.0310.S	643.0410	643.0420	643.0705	643.0715	643.0900	643.0910	643.0920	643.1050
		TRAFFIC CONTROL DRUMS	TEMPORARY PORTABLE RUMBLE STRIPS	TRAFFIC CONTROL BARRICADES TYPE II	TRAFFIC CONTROL BARRICADES TYPE III	TRAFFIC CONTROL WARNING LIGHTS TYPE A	TRAFFIC CONTROL WARNING LIGHTS TYPE C	TRAFFIC CONTROL SIGNS	TRAFFIC CONTROL COVERING SIGNS TYPE I	TRAFFIC CONTROL COVERING SIGNS TYPE II	TRAFFIC CONTROL CONTROL SIGNS PCMS
		EACH	LS	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH
		DAY		DAY	DAY	DAY	DAY	DAY	DAY	DAY	DAY
RACINE RD STAGE 1											
TRAFFIC CONTROL ADVANCE WARNING	7	-	-	-	-	-	-	-	-	-	28
MAINLINE CLOSURE	45	-	-	26	1,170	36	1,620	34	1,530	-	-
MIDWAY RD STAGE 2											
MAINLINE CLOSURE	68	5	-	272	19	1,292	26	23	1,564	-	-
HAUL ROAD REPAIR STAGE 3											
LANE CLOSURE WITH FLAGGING OPERATION	14	-	1	-	14	196	20	26	364	-	-
UNDISTRIBUTED	-	-	-	-	-	-	-	-	8	4	-
PROJECT TOTAL	134	340	1	272	2,658	3,668	340	3,458	8	4	28

PROJECT NO: 1517-75-77

HWY: STH 441/USH 10

COUNTY: WINNEBAGO

MISCELLANEOUS QUANTITIES

SHEET 169

E


FILE NAME : S:\NPD\3030200\151775-77\3030200-MO\3030201.DWG
LAYOUT NAME - 030201 - 030225.MO

PLOT DATE : 1/25/2019 12:25 PM
PLOT BY : SLEZAK, KIMBERLY A
PLOT NAME :

PLOT SCALE : *****

WISDOT/CADD SHEET 42

Addendum No. 01
ID 1517-75-77
Added Sheet 206A
February 5, 2019



Division 1 - Midway Road (MEB)

			AREA (SF)		Incremental Vol (CY) (Unadjusted)			Cumulative Vol (CY)			
STATION	Real Station	Distance	Cut	Salvaged/Unusable Pavement Material	Fill	Cut	Salvaged/Unusable Pavement Material	Fill	Cut	Expanded Fill 1.00	Mass Ordinate
						Note 1	Note 2	Note 3	Note 1		Note 8
10+78.23	1078.23	0.00	250.33	33.33	0.00	0	0	0	0	0	0
11+00	1100.00	21.77	229.21	33.33	0.00	193	27	0	193	0	166
11+25	1125.00	25.00	225.92	33.33	0.00	211	31	0	404	0	346
11+50	1150.00	25.00	217.10	33.33	0.00	205	31	0	609	0	521
11+75	1175.00	25.00	214.46	33.33	0.00	200	31	0	809	0	689
12+00	1200.00	25.00	214.94	33.33	0.00	199	31	0	1,008	0	857
12+25	1225.00	25.00	227.60	33.33	0.01	205	31	0	1,213	0	1,031
12+50	1250.00	25.00	0.00	33.33	0.00	105	31	0	1,318	0	1,106
12+75	1275.00	25.00	285.49	33.33	0.00	132	31	0	1,450	0	1,207
13+00	1300.00	25.00	317.00	33.33	0.00	279	31	0	1,729	0	1,455
13+25	1325.00	25.00	341.26	33.33	0.00	305	31	0	2,034	0	1,729
13+50	1350.00	25.00	341.61	33.33	0.33	316	31	0	2,350	0	2,014
13+75	1375.00	25.00	354.46	33.33	0.00	322	31	0	2,672	0	2,306
14+00	1400.00	25.00	369.42	33.33	0.00	335	31	0	3,007	0	2,610
14+25	1425.00	25.00	392.91	33.33	0.00	353	31	0	3,360	0	2,932
14+50	1450.00	25.00	428.70	33.33	0.00	380	31	0	3,741	0	3,281
14+75	1475.00	25.00	464.18	33.33	0.00	413	31	0	4,154	0	3,664
15+00	1500.00	25.00	492.52	33.33	0.00	443	31	0	4,597	0	4,076
15+25	1525.00	25.00	529.60	33.33	0.00	473	31	0	5,070	0	4,518
15+50	1550.00	25.00	558.28	33.33	0.00	504	31	0	5,574	0	4,991
15+75	1575.00	25.00	584.21	33.33	0.00	529	31	0	6,103	0	5,489
16+00	1600.00	25.00	609.30	33.33	0.01	553	31	0	6,655	0	6,011
16+25	1625.00	25.00	622.05	33.33	0.13	570	31	0	7,225	0	6,550
16+50	1650.00	25.00	618.07	74.67	0.00	574	50	0	7,799	0	7,074
16+75	1675.00	25.00	581.37	74.67	0.46	555	69	0	8,355	1	7,560
17+00	1700.00	25.00	547.01	74.67	0.00	522	69	0	8,877	1	8,013
17+25	1725.00	25.00	510.84	61.33	0.55	490	63	0	9,367	1	8,440
17+50	1750.00	25.00	455.32	61.33	0.00	447	57	0	9,814	1	8,830
17+75	1775.00	25.00	436.63	61.33	0.00	413	57	0	10,227	1	9,186
18+00	1800.00	25.00	454.96	61.33	47.98	413	57	22	10,640	24	9,520
18+25	1825.00	25.00	370.47	32.00	19.47	382	43	31	11,022	55	9,827
18+50	1850.00	25.00	391.60	32.00	0.27	353	30	9	11,375	64	10,141
18+75	1875.00	25.00	0.00	32.00	0.00	181	30	0	11,556	64	10,293
19+00	1900.00	25.00	0.00	32.00	0.00	0	30	0	11,556	64	10,263
19+25	1925.00	25.00	0.00	32.00	0.00	0	30	0	11,556	64	10,234
19+50	1950.00	25.00	0.00	32.00	0.00	0	30	0	11,556	64	10,204
19+75	1975.00	25.00	0.00	32.00	0.00	0	30	0	11,556	64	10,174
20+00	2000.00	25.00	382.00	32.00	36.74	177	30	17	11,733	81	10,305
20+25	2025.00	25.00	382.41	32.00	26.07	354	30	29	12,087	110	10,600

PROJECT NO:1517-75-77

HWY: STH 441/USH 10

COUNTY: WINNEBAGO

EARTHWORK QUANTITIES

PLOT BY : SLEZAK, KIMBERLY A

PLOT SCALE : 1 IN=40 FT

SHEET 319

FILE NAME : S:\NPOS\CDN\WIS441\151775-77-85 SHEET\PLAN\1517-75-77\090100-EN\090100-EN\UPDATED.DWG
LAYOUT NAME : 090100-EN\UPDATED - 090101

Addendum No. 01
ID 1517-75-77
Revised Sheet 319
February 5, 2019

Addendum No. 01
ID 1517-75-77
Revised Sheet 320
February 5, 2019

Division 1 - Midway Road (MEB) Continued									
STATION	Real Station	Distance	AREA (SF)		Incremental Vol (CY) (Unadjusted)			Cumulative Vol (CY)	
			Cut	Salvaged/Unusable Pavement Material	Fill	Cut	Salvaged/Unusable Pavement Material	Expanded Fill	Mass Ordinate
						Note 1	Note 2	Note 3	Note 8
20+50	2050.00	25.00	353.86	32.00	15.34	341	30	19	12,428
20+75	2075.00	25.00	331.71	25.33	41.37	317	27	26	12,745
21+00	2100.00	25.00	337.84	25.33	54.43	310	23	44	13,055
21+25	2125.00	25.00	466.91	25.33	37.89	373	23	43	13,428
21+50	2150.00	25.00	461.49	25.33	21.04	430	23	27	13,858
21+75	2175.00	25.00	456.44	25.33	34.62	425	23	26	14,283
22+00	2200.00	25.00	427.32	58.67	65.09	409	39	42	14,692
22+25	2225.00	25.00	387.55	58.67	77.36	377	54	66	15,069
22+50	2250.00	25.00	295.57	58.67	110.97	316	54	87	15,385
22+75	2275.00	25.00	314.82	58.67	44.84	283	54	72	15,668
23+00	2300.00	25.00	0.00	56.33	0.00	146	53	21	15,814
23+25	2325.00	25.00	0.00	56.33	0.00	0	52	0	15,814
23+48.91	2348.91	23.91	0.00	56.33	0.00	0	50	0	15,814
23+75	2375.00	26.09	0.00	26.67	0.00	0	40	0	15,814
24+00	2400.00	25.00	0.00	26.67	0.00	0	25	0	15,814
24+25	2425.00	25.00	157.47	26.67	38.84	73	25	18	15,886
24+50	2450.00	25.00	170.76	29.33	48.57	152	26	40	16,038
24+75	2475.00	25.00	172.49	53.33	29.99	159	38	36	16,197
25+00	2500.00	25.00	230.18	53.33	30.63	186	49	28	16,384
25+25	2525.00	25.00	251.35	53.33	11.45	223	49	19	16,607
25+50	2550.00	25.00	248.79	36.00	6.30	232	41	8	16,838
25+75	2575.00	25.00	218.96	36.00	11.72	217	33	8	17,055
26+00	2600.00	25.00	226.95	36.00	5.36	206	33	8	17,261
26+25	2625.00	25.00	0.00	36.00	0.00	105	33	2	17,366
26+50	2650.00	25.00	0.00	36.00	0.00	0	33	0	17,366
26+75	2675.00	25.00	0.00	36.00	0.00	0	33	0	17,366
27+00	2700.00	25.00	316.91	36.67	1.09	147	34	1	17,513
27+25	2725.00	25.00	231.52	36.67	0.00	254	34	1	17,767
27+50	2750.00	25.00	220.49	36.67	0.14	209	34	0	17,976
27+75	2775.00	25.00	223.27	36.67	0.03	205	34	0	18,182
28+00	2800.00	25.00	216.35	36.67	0.24	204	34	0	18,385
28+25	2825.00	25.00	207.28	36.67	0.20	196	34	0	18,581
28+50	2850.00	25.00	184.85	36.67	0.53	182	34	0	18,763
28+75	2875.00	25.00	180.09	36.67	0.84	169	34	1	18,932
29+00	2900.00	25.00	189.45	36.67	0.00	171	34	0	19,103
29+25	2925.00	25.00	180.51	36.67	0.00	171	34	0	19,274
29+50	2950.00	25.00	174.82	36.67	0.09	165	34	0	19,439
29+75	2975.00	25.00	154.12	36.67	0.00	152	34	0	19,591
29+76	2976.00	1.00	153.47	36.67	0.00	6	1	0	19,597
COLUMN TOTALS						19,597	2,753	760	

Notes

- 1- Cut includes Salvaged/Unusable Pavement material
- 2- Salvaged/Unusable Pavement Material is included in Cut
- 3- Fill Does not include Unusable Pavement Exc volume

Division 2 - Racine Road (R)

STATION	Real Station	Distance	AREA (SF)			Incremental Vol (CY) (Unadjusted)			Cumulative Vol (CY)		
			Cut	Salvaged/Unusable Pavement Material	Fill	Cut Note 1	Salvaged/Unusable Pavement Material	Fill Note 3	Cut Note 1	Expanded Fill 1.00	Mass Ordinate Note 8
37+35.61	3735.61	0.00	0.00	0.00	0.00	0	0	0	0	0	
37+50	3750.00	14.39	0.00	0.00	0.00	0	0	0	0	0	
37+75	3775.00	25.00	94.72	38.00	8.30	44	18	4	44	22	
38+00	3800.00	25.00	83.27	38.00	9.57	82	35	8	126	61	
38+25	3825.00	25.00	75.21	38.00	17.39	73	35	12	200	87	
38+50	3850.00	25.00	73.49	38.00	18.32	69	35	17	268	104	
38+75	3875.00	25.00	72.71	38.00	20.42	68	35	18	336	119	
39+00	3900.00	25.00	73.91	38.00	21.36	68	35	19	404	132	
39+25	3925.00	25.00	78.33	38.00	19.18	70	35	19	475	149	
39+50	3950.00	25.00	86.25	38.00	20.60	76	35	18	551	171	
39+75	3975.00	25.00	93.97	38.00	33.26	83	35	25	634	195	
40+00	4000.00	25.00	100.83	38.00	71.84	90	35	49	724	201	
40+25	4025.00	25.00	111.65	38.00	66.27	98	35	64	823	200	
40+50	4050.00	25.00	134.67	38.00	45.48	114	35	52	937	227	
40+75	4075.00	25.00	172.00	38.00	1.28	142	35	22	1,079	312	
41+00	4100.00	25.00	177.70	38.00	11.58	162	35	6	1,241	433	
41+25	4125.00	25.00	204.69	38.00	9.31	177	35	10	1,418	565	
41+50	4150.00	25.00	219.86	38.00	0.00	197	35	4	1,614	722	
41+75	4175.00	25.00	223.00	38.00	0.00	205	35	0	1,819	892	
42+00	4200.00	25.00	222.77	38.00	0.00	206	35	0	2,026	1,063	
42+25	4225.00	25.00	235.34	38.00	0.15	212	35	0	2,238	1,240	
42+50	4250.00	25.00	270.87	38.00	1.40	234	35	1	2,472	1,439	
42+75	4275.00	25.00	338.79	38.00	0.08	282	35	1	2,754	1,685	
43+00	4300.00	25.00	354.79	38.00	0.04	321	35	0	3,075	1,971	
43+25	4325.00	25.00	374.90	38.00	0.00	338	35	0	3,413	2,274	
43+50	4350.00	25.00	295.27	38.00	0.00	310	35	0	3,723	2,549	
43+75	4375.00	25.00	195.59	38.00	0.76	227	35	0	3,951	2,740	
44+00	4400.00	25.00	168.16	38.00	5.42	168	35	3	4,119	2,871	
44+25	4425.00	25.00	153.47	38.00	9.29	149	35	7	4,268	2,978	
44+50	4450.00	25.00	143.28	38.00	13.09	137	35	10	4,405	3,069	
44+75	4475.00	25.00	134.55	38.00	15.53	129	35	13	4,534	3,150	
45+00	4500.00	25.00	132.15	38.00	0.48	123	35	7	4,658	3,231	
45+25	4525.00	25.00	125.93	38.00	14.65	119	35	7	4,777	3,308	

Division 2 - Racine Road (R) Continued

STATION	Real Station	Distance	AREA (SF)		Incremental Vol (CY) (Unadjusted)			Cumulative Vol (CY)	
			Cut	Salvaged/Unusable Pavement Material	Fill	Cut	Salvaged/Unusable Pavement Material	Fill	Mass Ordinate
45+50	4550.00	25.00	120.76	38.00	12.18	114	35	12	4,891
45+75	4575.00	25.00	115.52	38.00	10.79	109	35	11	5,001
46+00	4600.00	25.00	114.00	38.00	13.40	106	35	11	5,107
46+25	4625.00	25.00	117.70	38.00	18.89	107	35	15	5,214
46+50	4650.00	25.00	117.75	38.00	0.49	109	35	9	5,323
46+75	4675.00	25.00	112.34	38.00	25.64	107	35	12	5,430
47+00	4700.00	25.00	107.74	38.00	34.13	102	35	28	5,532
47+25	4725.00	25.00	105.80	38.00	32.11	99	35	31	5,630
47+50	4750.00	25.00	113.32	38.00	12.98	101	35	21	5,732
47+75	4775.00	25.00	110.28	38.00	13.81	104	35	12	5,835
48+00	4800.00	25.00	109.66	38.00	15.10	102	35	13	5,937
48+25	4825.00	25.00	88.74	38.00	7.32	92	35	10	6,029
48+50	4850.00	25.00	84.10	38.00	8.39	80	35	7	6,109
48+75	4875.00	25.00	81.07	38.00	7.15	76	35	7	6,186
49+00	4900.00	25.00	78.90	38.00	8.23	74	35	7	6,260
49+25	4925.00	25.00	76.29	38.00	9.49	72	35	8	6,331
49+50	4950.00	25.00	74.87	38.00	7.40	70	35	8	6,401
49+75	4975.00	25.00	0.00	38.00	0.00	35	35	3	6,436
50+00	5000.00	25.00	0.00	0.00	0.00	0	18	0	6,436
50+25	5025.00	25.00	0.00	0.00	0.00	0	0	0	6,436
50+50	5050.00	25.00	0.00	0.00	0.00	0	0	0	6,436
50+75	5075.00	25.00	0.00	0.00	0.00	0	0	0	6,436
51+00	5100.00	25.00	0.00	0.00	0.00	0	0	0	6,436
51+25	5125.00	25.00	0.00	0.00	0.00	0	0	0	6,436
51+50	5150.00	25.00	0.00	0.00	0.00	0	0	0	6,436
51+75	5175.00	25.00	0.00	0.00	0.00	0	0	0	6,436
52+00	5200.00	25.00	0.00	0.00	0.00	0	0	0	6,436
52+25	5225.00	25.00	0.00	0.00	0.00	0	0	0	6,436
52+50	5250.00	25.00	0.00	0.00	0.00	0	0	0	6,436
52+75	5275.00	25.00	0.00	0.00	0.00	0	0	0	6,436
COLUMN TOTALS						6,436	1,724	623	

Notes

- 1- Cut includes Salvaged/Unusable Pavement material
- 2- Salvaged/Unusable Pavement Material is included in Cut
- 3- Fill Does not include Unusable Pavement Exc volume

Addendum No. 01
ID 1517-75-77
Revised Sheet 322
February 5, 2019

PROJECT NO: 1517-75-77

HWY: STH 441/USH 10

COUNTY: WINNEBAGO

EARTHWORK QUANTITIES

SHEET 322

FILE NAME : S:\NPOS\CDN\WIS441\151775-77-85 SHEET\PLAN\1517-75-77\090100-EW\UPDATED.DWG
LAYOUT NAME - 090100-EW-UPDATED - 090104
PLOT DATE : 1/30/2019 3:56 PM
PLOT BY : SLEZAK, KIMBERLY A
PLOT NAME :
PLOT SCALE : 1 IN=40 FT
WISDOT/CADDs SHEET 49

Addendum No. 01
ID 1517-75-77
Revised Sheet 323
February 5, 2019

Division 3 - Midway Road NE Ramp (MNE)

STATION	Real Station	Distance	AREA (SF)		Incremental Vol (CY) (Unadjusted)		Cumulative Vol (CY)	
			Cut	Salvaged/Unusable Pavement Material	Fill	Cut	Expanded Fill	Mass Ordinate
242+50	24250.00	0.00	202.55	10.42	0.00	0	0	0
242+75	24275.00	25.00	151.35	10.42	0.00	164	0	154
243+00	24300.00	25.00	118.43	10.42	0.00	125	0	269
243+25	24325.00	25.00	116.89	10.42	11.09	109	5	364
243+50	24350.00	25.00	118.69	10.42	0.10	109	10	458
243+75	24375.00	25.00	112.21	10.42	0.01	107	10	555
244+00	24400.00	25.00	100.29	10.42	0.21	98	10	644
244+25	24425.00	25.00	86.77	10.42	1.39	87	11	720
244+50	24450.00	25.00	64.47	10.42	19.18	70	21	771
			COLUMN TOTALS			869	77	21

Notes

- 1- Cut includes Salvaged/Unusable Pavement material
- 2- Salvaged/Unusable Pavement Material is included in Cut
- 3- Fill Does not include Unusable Pavement Exc volume

Addendum No. 01
ID 1517-75-77
Revised Sheet 324
February 5, 2019

Division 4 - Midway Road NW Ramp (MNV)

STATION	Real Station	Distance	AREA (SF)			Incremental Vol (CY) (Unadjusted)			Cumulative Vol (CY)		
			Cut	Salvaged/Unusable Pavement Material	Fill	Cut	Salvaged/Unusable Pavement Material	Fill	Cut	Expanded Fill 1.00	Mass Ordinate Note 8
240+59.13	24059.13	0.00	101.14	0.00	22.58	0	0	0	0	0	0
240+75	24075.00	15.87	68.90	0.00	38.69	50	0	18	50	18	32
241+00	24100.00	25.00	113.49	0.00	14.12	84	0	24	134	42	92
241+25	24125.00	25.00	201.03	0.00	18.38	146	0	15	280	57	223
241+49.97	24149.97	24.97	192.60	0.00	17.41	182	0	17	462	74	388
241+75	24175.00	25.03	189.04	0.00	12.67	177	0	14	639	88	551
241+96.79	24196.79	21.79	119.52	0.00	36.86	125	0	20	763	108	655
			COLUMN TOTALS			763	0	108			

Notes

- 1- Cut includes Salvaged/Unusable Pavement material
- 2- Salvaged/Unusable Pavement Material is included in Cut
- 3- Fill Does not include Unusable Pavement Exc volume

Addendum No. 01
ID 1517-75-77
Revised Sheet 325
February 5, 2019

Division 5 - Midway Road SE Ramp (MSE)

Division 5 - Highway Road & Ramp (M&E)

STATION	Real Station	Distance	AREA (SF)		Incremental Vol (CY) (Unadjusted)			Cumulative Vol (CY)		
			Cut	Salvaged/Unusable Pavement Material	Fill	Cut	Salvaged/Unusable Pavement Material	Fill	Cut 1.00	Expanded Fill 1.00
239+25	23925.00	0.00	99.58	0.00	0.01	0	0	0	0	Note 8
239+50	23950.00	25.00	118.57	0.00	0.00	101	0	0	101	0
239+75	23975.00	25.00	137.31	0.00	0.00	118	0	0	219	0
240+00	24000.00	25.00	100.01	0.00	0.00	110	0	0	329	0
240+25	24025.00	25.00	130.40	0.00	0.00	107	0	0	436	0
240+50	24050.00	25.00	158.91	0.00	0.00	134	0	0	570	0
240+75	24075.00	25.00	107.70	0.00	0.00	123	0	0	693	0
241+00	24100.00	25.00	98.11	0.00	0.00	95	0	0	789	0
			COLUMN TOTALS			789	0	0		

Notes

- 1- Cut includes Salvaged/Unusable Pavement material
- 2- Salvaged/Unusable Pavement Material is included in Cut
- 3- Fill Does not include Unusable Pavement Exc volume

PROJECT NO: 1517-75-77

FILE NAME : S:\NPOS\330\WIS441\15177570-72-77-85 SHEETS\PLAN\1517-75-77\090100-EW-UPDATED.DWG
LAYOUT NAME - 090100-EW - 090107

HWY: STH 441/USH 10

COUNTY: WINNEBAGO

EARTHWORK QUANTITIES

PLOT DATE : 1/24/2019 12:09 PM PLOT BY : COHEN, MICHAEL J PLOT NAME :

PLOT SCALE : 1 IN=40 FT

SHEET 325

E

Addendum No. 01
ID 1517-75-77
Revised Sheet 326
February 5, 2019

Division 6 - Midway Road SW Ramp (MSW)

STATION	Real Station	Distance	AREA (SF)		Incremental Vol (CY) (Unadjusted)			Cumulative Vol (CY)		
			Cut	Salvaged/Unusable Pavement Material	Fill	Cut	Salvaged/Unusable Pavement Material	Fill	Cut 1.00 Note 1	Expanded Fill 1.00 Note 8
240+11.83	24011.83	0.00	86.78	0.00	1.21	0	0	0	0	0
240+25	24025.00	13.17	76.86	0.00	53.51	40	0	13	40	13
240+50	24050.00	25.00	41.57	0.00	46.93	55	0	46	95	60
240+75	24075.00	25.00	53.16	0.00	41.67	44	0	41	139	101
241+00	24100.00	25.00	188.04	0.00	0.00	112	0	19	250	120
241+12.07	24112.07	12.07	247.20	0.00	0.00	97	0	0	348	120
COLUMN TOTALS						348	0	120		227

Notes

- 1- Cut includes Salvaged/Unusable Pavement material
- 2- Salvaged/Unusable Pavement Material is included in Cut
- 3- Fill Does not include Unusable Pavement Exc volume

Addendum No. 01
ID 1517-75-77
Revised Sheet 327
February 5, 2019

Division 7 - Midway Road NW Bypass Ramp (MNRWB)

STATION	Real Station	Distance	AREA (SF)		Incremental Vol (CY) (Unadjusted)		Cumulative Vol (CY)	
			Cut	Salvaged/Unusable Pavement Material	Fill	Cut	Expanded Fill	Mass Ordinate
00+49.43	49.43	0.00	107.75	0.00	0.17	Note 1 0	Note 3 0	Note 8 0
00+75	75.00	25.57	201.62	0.00	0.00	146	0	146
01+00	100.00	25.00	322.30	0.00	0.00	243	0	389
01+48.34	148.34	48.34	193.04	0.00	0.00	461	0	850
			COLUMN TOTALS			850	0	0

Notes

- 1- Cut includes Salvaged/Unusable Pavement material
- 2- Salvaged/Unusable Pavement Material is included in Cut
- 3- Fill Does not include Unusable Pavement Exc volume

PROJECT NO: 1517-75-77

HWY: STH 441/USH 10

COUNTY: WINNEBAGO

EARTHWORK QUANTITIES

SHEET 327

E

FILE NAME : S:\NPD\330\WIS441\15177570-72-77-85\SHEETS\PLAN\1517-75-77\090100-EN\090100-EN-UPDATED.DWG

LAYOUT NAME - 090100-EN - 090109

PLOT DATE : 1/24/2019 12:09 PM

PLOT BY : COHEN, MICHAEL J

PLOT NAME :

PLOT SCALE : 1 IN=40 FT

WISDOT/CADD SHEET 49

Division 8 - Midway Road SE Bypass Ramp (MSEB)

STATION	Real Station	Distance	AREA (SF)		Incremental Vol (CY) (Unadjusted)		Cumulative Vol (CY)	
			Cut	Salvaged/Unusable Pavement Material	Fill	Cut	Expanded Fill	Mass Ordinate
						Note 1	Note 1	Note 8
00+00	0.00	0.00	77.82	0.00	0.00	0	0	0
00+50	50.00	50.00	91.40	0.00	0.00	157	0	157
00+75	75.00	25.00	72.69	0.00	0.00	76	0	233
01+00	100.00	25.00	66.46	0.00	0.00	64	0	297
			COLUMN TOTALS			297	0	0

Notes

- 1- Cut includes Salvaged/Unusable Pavement material
- 2- Salvaged/Unusable Pavement Material is included in Cut
- 3- Fill Does not include Unusable Pavement Exc volume

Addendum No. 01
ID 1517-75-77
Revised Sheet 328
February 5, 2019

PROJECT NO: 1517-75-77

FILE NAME : S:\NPS\CD\WIS441\15177570-72-77-85 SHEETS\PLAN\1517-75-77\090100-EW.UPDATED.DWG
LAYOUT NAME - 090100-EW - 090110

HWY: STH 441/USH 10

COUNTY: WINNEBAGO

EARTHWORK QUANTITIES


PLOT DATE : 1/24/2019 12:09 PM PLOT BY : COHEN, MICHAEL J PLOT NAME :

PLOT SCALE : 1 IN:40 FT


SHEET 328

E


Addendum No. 01
ID 1517-75-77
Revised Sheet 329
February 5, 2019




Addendum No. 01
ID 1517-75-77
Revised Sheet 330
February 5, 2019




Addendum No. 01
ID 1517-75-77
Revised Sheet 331
February 5, 2019




Addendum No. 01
ID 1517-75-77
Revised Sheet 332
February 5, 2019



Addendum No. 01
ID 1517-75-77
Revised Sheet 333
February 5, 2019



Addendum No. 01
ID 1517-75-77
Revised Sheet 334
February 5, 2019



PROJECT NO: 1517-75-77

FILE NAME : S:\POS\C3D\WIS44\15177570_72.77_85\SHEETS\PLAN\1517-75-77\090200-XS-NE-15177577-090201-XS-WEB.DWG
LAYOUT NAME : NE-15177577-090206-XS-WEB

PLOT DATE : 1/23/2019 1:43 PM


PLOT BY : SLEZAK, KIMBERLY A PLOT NAME :

PLOT SCALE : 1 IN:20 FT


ET	334	E
----	-----	---

WISDOT/CADDs SHEET 49


Addendum No. 01
ID 1517-75-77
Revised Sheet 335
February 5, 2019



Addendum No. 01
ID 1517-75-77
Revised Sheet 336
February 5, 2019



Addendum No. 01
ID 1517-75-77
Revised Sheet 337
February 5, 2019



PROJECT NO: 1517-75-77

HWY: STH 441/USH 10


COUNTY: WINNEBAGO

CROSS SECTIONS: MIDWAY ROAD (CTH AP)


SHEET 337

FILE NAME : S:\NPOS\G30\WIS441\151775-77\090200-XS-NE-15177577-090201-XS-MEB.DWG
LAYOUT NAME : NE-15177577-090209-XS-MEB
PLOT DATE : 1/23/2019 1:43 PM
PLOT BY : SLEZAK, KIMBERLY A
PLOT NAME :
PLOT SCALE : 1 IN=20 FT
WISDOT/CADD SHEET 49


Addendum No. 01
ID 1517-75-77
Revised Sheet 338
February 5, 2019




Addendum No. 01
ID 1517-75-77
Revised Sheet 339
February 5, 2019




Addendum No. 01
ID 1517-75-77
Revised Sheet 340
February 5, 2019



Addendum No. 01
ID 1517-75-77
Revised Sheet 341
February 5, 2019




Addendum No. 01
ID 1517-75-77
Revised Sheet 342
February 5, 2019




PROJECT NO: 1517-75-77	HWY: STH 441/USH 10	COUNTY: WINNEBAGO	CROSS SECTIONS: MIDWAY ROAD (CTH AP)	SHEET 342	E
FILE NAME : S:\NPD\330\WIS441\151775-77\090200-XSNE-15177577-090201-XS-MEB.DWG					
LAYOUT NAME : NE-15177577-090214-XS-MEB					
PLOT DATE : 1/23/2019 1:44 PM					
PLOT BY : SLEZAK, KIMBERLY A					
PLOT NAME : CROSS SECTIONS: MIDWAY ROAD (CTH AP)					
PLOT SCALE : 1 IN:20 FT					
WISDOT/CADD SHEET 49					


Addendum No. 01
ID 1517-75-77
Revised Sheet 343
February 5, 2019



Addendum No. 01
ID 1517-75-77
Revised Sheet 344
February 5, 2019



Addendum No. 01
ID 1517-75-77
Revised Sheet 345
February 5, 2019



PROJECT NO: 1517-75-77

FILE NAME : S:\POS\C3D\WTS44\15177570_72_77_85\SHEETSPLAN\1517-75-77\090200-XS-NE-15177577-090201-XS-WEB.DWG
LAYOUT NAME : NE-15177577-090217-XS-WEB


PLOT DATE : 1/23/2019 1:45 PM

PLOT BY : SLEZAK, KIMBERLY A PLOT NAME :


PLOT SCALE : 1 IN:20 FT

WISDOT/CADD SHEET 49


Addendum No. 01
ID 1517-75-77
Revised Sheet 346
February 5, 2019




Addendum No. 01
ID 1517-75-77
Revised Sheet 347
February 5, 2019




Addendum No. 01
ID 1517-75-77
Revised Sheet 348
February 5, 2019



Addendum No. 01
ID 1517-75-77
Revised Sheet 349
February 5, 2019



Addendum No. 01
ID 1517-75-77
Revised Sheet 350
February 5, 2019



PROJECT NO: 1517-75-77

HWY: STH 441/USH 10

COUNTY: WINNEBAGO


CROSS SECTIONS: MIDWAY ROAD (CTH AP)

SHEET 350


WISDOT/CADD SHEET 49

FILE NAME : S:\NPOS\330\WIS441\151775-77\090200-XSNE-15177577-090201-XS-MEB.DWG
LAYOUT NAME - NE-15177577-090222-XS-MEB
PLOT DATE : 1/23/2019 1:45 PM
PLOT BY : SLEZAK, KIMBERLY A
PLOT NAME :
PLOT SCALE : 1 IN=20 FT


Addendum No. 01
ID 1517-75-77
Revised Sheet 351
February 5, 2019




Addendum No. 01
ID 1517-75-77
Revised Sheet 352
February 5, 2019




Addendum No. 01
ID 1517-75-77
Revised Sheet 353
February 5, 2019




Addendum No. 01
ID 1517-75-77
Revised Sheet 377
February 5, 2019




Addendum No. 01
ID 1517-75-77
Revised Sheet 378
February 5, 2019




Addendum No. 01
ID 1517-75-77
Revised Sheet 379
February 5, 2019




Addendum No. 01
ID 1517-75-77
Revised Sheet 380
February 5, 2019




Addendum No. 01
ID 1517-75-77
Revised Sheet 381
February 5, 2019




Addendum No. 01
 ID 1517-75-77
 Revised Sheet 382
 February 5, 2019




Addendum No. 01
ID 1517-75-77
Revised Sheet 383
February 5, 2019




Addendum No. 01
ID 1517-75-77
Revised Sheet 384
February 5, 2019




Addendum No. 01
ID 1517-75-77
Revised Sheet 385
February 5, 2019




Addendum No. 01
ID 1517-75-77
Revised Sheet 386
February 5, 2019




Addendum No. 01
ID 1517-75-77
Revised Sheet 387
February 5, 2019



Addendum No. 01
ID 1517-75-77
Revised Sheet 388
February 5, 2019




Addendum No. 01
ID 1517-75-77
Revised Sheet 389
February 5, 2019



PROJECT NO: 1517-75-77	HWY: STH 441/USH 10	COUNTY: WINNEBAGO	CROSS SECTIONS: MIDWAY ROAD SOUTHWEST RAMP	SHEET 389
FILE NAME : S:\PDS\CD\WIS1541\15177570_72_77_85\ASSETS\PLAN\15177570-090401-XS-RAMPS.DWG PLOT DATE : 1/24/2019 10:49 AM PLOT BY : SLEZAK, KIMBERLY A PLOT SCALE : 1 IN=10 FT LAYOUT NAME : NE-15177570-090401-XS-RAMPS - NEW RAMPS				
WISDOT/CADDIS SHEET 49				

Addendum No. 01
ID 1517-75-77
Revised Sheet 390
February 5, 2019



PROJECT NO: 1517-75-77

HWY: STH 441/USH 10

COUNTY: WINNEBAGO

CROSS SECTIONS: MIDWAY ROAD SOUTHWEST RAMP

SHEET 390

FILE NAME : S:\PDS\C3D\WIS441\15177570_72.77.85\SHEETSPLAN\1517-75-77\090200-XS\NE-15177577-090401-XS-RAMPS.DWG
LAYOUT NAME - NE-15177577-090401-XS-RAMPS
LAYOUT NAME - NE-15177577-090401-XS-RAMPS 5
LAYOUT NAME - MSW RAMPS 5

PLOT BY : SLEZAK, KIMBERLY A PLOT NAME :


PLOT SCALE : 1 IN:10 FT

WISDOT/CADDs SHEET 49


9

9


Addendum No. 01
ID 1517-75-77
Revised Sheet 391
February 5, 2019






Addendum No. 01
ID 1517-75-77
Revised Sheet 392
February 5, 2019



Addendum No. 01
ID 1517-75-77
Revised Sheet 393
February 5, 2019



Addendum No. 01
ID 1517-75-77
Revised Sheet 394
February 5, 2019





Proposal Schedule of Items

Page 1 of 11

Proposal ID: 20190212006 Project(s): 1517-75-77

Federal ID(s): WISC 2019120

SECTION: 0001

Contact Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0002	201.0105 Clearing	3.000 STA	_____.	_____.
0004	201.0120 Clearing	126.000 ID	_____.	_____.
0006	201.0205 Grubbing	3.000 STA	_____.	_____.
0008	201.0220 Grubbing	126.000 ID	_____.	_____.
0010	203.0100 Removing Small Pipe Culverts	1.000 EACH	_____.	_____.
0012	204.0100 Removing Pavement	14,242.000 SY	_____.	_____.
0014	204.0115 Removing Asphaltic Surface Butt Joints	143.000 SY	_____.	_____.
0016	204.0120 Removing Asphaltic Surface Milling	13,479.000 SY	_____.	_____.
0018	204.0150 Removing Curb & Gutter	262.000 LF	_____.	_____.
0020	204.0165 Removing Guardrail	257.000 LF	_____.	_____.
0022	204.0185 Removing Masonry	11.000 CY	_____.	_____.
0024	204.0190 Removing Surface Drains	4.000 EACH	_____.	_____.
0026	204.0210 Removing Manholes	8.000 EACH	_____.	_____.
0028	204.0220 Removing Inlets	22.000 EACH	_____.	_____.
0030	204.0245 Removing Storm Sewer (size) 001. 6-15 Inches	472.000 LF	_____.	_____.
0032	204.0245 Removing Storm Sewer (size) 002. 18-21 Inches	196.000 LF	_____.	_____.



Proposal Schedule of Items

Page 2 of 11

Proposal ID: 20190212006 Project(s): 1517-75-77

Federal ID(s): WISC 2019120

SECTION: 0001

Contact Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0034	204.0245 Removing Storm Sewer (size) 003. 24-30 Inches	667.000 LF	_____.	_____.
0036	204.0245 Removing Storm Sewer (size) 004. 36-42 Inches	1,573.000 LF	_____.	_____.
0038	205.0100 Excavation Common	30,048.000 CY	_____.	_____.
0040	209.0200.S Backfill Controlled Low Strength	30.000 CY	_____.	_____.
0042	210.1100 Backfill Structure Type A	56.000 CY	_____.	_____.
0044	213.0100 Finishing Roadway (project) 001. 1517-75-77	1.000 EACH	_____.	_____.
0046	305.0110 Base Aggregate Dense 3/4-Inch	157.000 TON	_____.	_____.
0048	305.0120 Base Aggregate Dense 1 1/4-Inch	9,728.000 TON	_____.	_____.
0050	311.0110 Breaker Run	16,275.000 TON	_____.	_____.
0052	405.0200 Coloring Concrete Custom 001. Color 10076	153.000 CY	_____.	_____.
0056	415.5110.S Concrete Pavement Joint Layout	1.000 LS	_____.	_____.
0058	416.0160 Concrete Driveway 6-Inch	56.000 SY	_____.	_____.
0060	416.0170 Concrete Driveway 7-Inch	64.000 SY	_____.	_____.
0062	416.0610 Drilled Tie Bars	10.000 EACH	_____.	_____.
0064	416.0620 Drilled Dowel Bars	113.000 EACH	_____.	_____.
0066	455.0605 Tack Coat	1,029.000 GAL	_____.	_____.



Proposal Schedule of Items

Page 3 of 11

Proposal ID: 20190212006 Project(s): 1517-75-77

Federal ID(s): WISC 2019120

SECTION: 0001

Contact Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0068	460.2000 Incentive Density HMA Pavement	1,470.000 DOL	1.00000	1,470.00
0070	460.6223 HMA Pavement 3 MT 58-28 S	94.000 TON	_____.	_____.
0072	460.6424 HMA Pavement 4 MT 58-28 H	2,250.000 TON	_____.	_____.
0074	465.0120 Asphaltic Surface Driveways and Field Entrances	79.000 TON	_____.	_____.
0076	465.0315 Asphaltic Flumes	18.000 SY	_____.	_____.
0078	520.8000 Concrete Collars for Pipe	2.000 EACH	_____.	_____.
0080	522.1012 Apron Endwalls for Culvert Pipe Reinforced Concrete 12-Inch	1.000 EACH	_____.	_____.
0082	522.1018 Apron Endwalls for Culvert Pipe Reinforced Concrete 18-Inch	2.000 EACH	_____.	_____.
0084	522.1024 Apron Endwalls for Culvert Pipe Reinforced Concrete 24-Inch	2.000 EACH	_____.	_____.
0086	601.0409 Concrete Curb & Gutter 30-Inch Type A	2,688.000 LF	_____.	_____.
0088	601.0411 Concrete Curb & Gutter 30-Inch Type D	121.000 LF	_____.	_____.
0090	601.0452 Concrete Curb & Gutter Integral 30-Inch Type D	7,175.000 LF	_____.	_____.
0092	601.0600 Concrete Curb Pedestrian	80.000 LF	_____.	_____.
0094	602.0410 Concrete Sidewalk 5-Inch	28,961.000 SF	_____.	_____.
0096	602.0515 Curb Ramp Detectable Warning Field Natural Patina	160.000 SF	_____.	_____.



Proposal Schedule of Items

Page 4 of 11

Proposal ID: 20190212006 Project(s): 1517-75-77

Federal ID(s): WISC 2019120

SECTION: 0001

Contact Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0098	602.0615 Curb Ramp Detectable Warning Field Radial Natural Patina	76.000 SF	_____.	_____.
0100	603.1442 Concrete Barrier Type S42C	150.000 LF	_____.	_____.
0102	603.3513 Concrete Barrier Transition Type S32 to S36	2.000 EACH	_____.	_____.
0104	603.3535 Concrete Barrier Transition Type S36 to S42	2.000 EACH	_____.	_____.
0106	604.0400 Slope Paving Concrete	945.000 SY	_____.	_____.
0108	608.0312 Storm Sewer Pipe Reinforced Concrete Class III 12-Inch	80.000 LF	_____.	_____.
0110	608.0318 Storm Sewer Pipe Reinforced Concrete Class III 18-Inch	702.000 LF	_____.	_____.
0112	608.0324 Storm Sewer Pipe Reinforced Concrete Class III 24-Inch	1,516.000 LF	_____.	_____.
0114	608.0336 Storm Sewer Pipe Reinforced Concrete Class III 36-Inch	743.000 LF	_____.	_____.
0116	608.0342 Storm Sewer Pipe Reinforced Concrete Class III 42-Inch	1,006.000 LF	_____.	_____.
0118	608.0412 Storm Sewer Pipe Reinforced Concrete Class IV 12-Inch	100.000 LF	_____.	_____.
0120	608.0418 Storm Sewer Pipe Reinforced Concrete Class IV 18-Inch	21.000 LF	_____.	_____.
0122	608.2329 Storm Sewer Pipe Reinforced Concrete Horizontal Elliptical Class HE-III 29x45- Inch	86.000 LF	_____.	_____.



Proposal Schedule of Items

Page 5 of 11

Proposal ID: 20190212006 Project(s): 1517-75-77

Federal ID(s): WISC 2019120

SECTION: 0001

Contact Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0124	608.2334 Storm Sewer Pipe Reinforced Concrete Horizontal Elliptical Class HE-III 34x53-Inch	28.000 LF	_____.	_____.
0126	611.0420 Reconstructing Manholes	2.000 EACH	_____.	_____.
0128	611.0530 Manhole Covers Type J	6.000 EACH	_____.	_____.
0130	611.0535 Manhole Covers Type J-Special	6.000 EACH	_____.	_____.
0132	611.0612 Inlet Covers Type C	1.000 EACH	_____.	_____.
0134	611.0624 Inlet Covers Type H	39.000 EACH	_____.	_____.
0136	611.0639 Inlet Covers Type H-S	20.000 EACH	_____.	_____.
0138	611.0642 Inlet Covers Type MS	20.000 EACH	_____.	_____.
0140	611.1005 Catch Basins 5-FT Diameter	5.000 EACH	_____.	_____.
0142	611.1006 Catch Basins 6-FT Diameter	5.000 EACH	_____.	_____.
0144	611.2006 Manholes 6-FT Diameter	7.000 EACH	_____.	_____.
0146	611.2008 Manholes 8-FT Diameter	4.000 EACH	_____.	_____.
0148	611.3004 Inlets 4-FT Diameter	22.000 EACH	_____.	_____.
0150	611.3230 Inlets 2x3-FT	26.000 EACH	_____.	_____.
0152	611.3901 Inlets Median 1 Grate	4.000 EACH	_____.	_____.
0154	611.3902 Inlets Median 2 Grate	8.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 6 of 11

Proposal ID: 20190212006 Project(s): 1517-75-77

Federal ID(s): WISC 2019120

SECTION: 0001

Contact Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0156	611.8115 Adjusting Inlet Covers	2.000 EACH	_____.	_____.
0158	612.0406 Pipe Underdrain Wrapped 6-Inch	1,840.000 LF	_____.	_____.
0160	618.0100 Maintenance And Repair of Haul Roads (project) 001. 1517-75-77	1.000 EACH	_____.	_____.
0162	619.1000 Mobilization	1.000 EACH	_____.	_____.
0164	620.0200 Concrete Median Blunt Nose	454.000 SF	_____.	_____.
0166	620.0300 Concrete Median Sloped Nose	117.000 SF	_____.	_____.
0168	624.0100 Water	139.000 MGAL	_____.	_____.
0170	625.0100 Topsoil	17,261.000 SY	_____.	_____.
0172	628.1504 Silt Fence	550.000 LF	_____.	_____.
0174	628.1520 Silt Fence Maintenance	550.000 LF	_____.	_____.
0176	628.1905 Mobilizations Erosion Control	6.000 EACH	_____.	_____.
0178	628.1910 Mobilizations Emergency Erosion Control	4.000 EACH	_____.	_____.
0180	628.2006 Erosion Mat Urban Class I Type A	17,262.000 SY	_____.	_____.
0182	628.7005 Inlet Protection Type A	13.000 EACH	_____.	_____.
0184	628.7010 Inlet Protection Type B	6.000 EACH	_____.	_____.
0186	628.7015 Inlet Protection Type C	120.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 7 of 11

Proposal ID: 20190212006 Project(s): 1517-75-77

Federal ID(s): WISC 2019120

SECTION: 0001

Contact Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0188	628.7020 Inlet Protection Type D	14.000 EACH	_____.	_____.
0190	628.7504 Temporary Ditch Checks	46.000 LF	_____.	_____.
0192	628.7555 Culvert Pipe Checks	10.000 EACH	_____.	_____.
0194	628.7560 Tracking Pads	4.000 EACH	_____.	_____.
0196	628.7570 Rock Bags	100.000 EACH	_____.	_____.
0198	629.0210 Fertilizer Type B	12.000 CWT	_____.	_____.
0200	630.0140 Seeding Mixture No. 40	318.000 LB	_____.	_____.
0202	630.0200 Seeding Temporary	476.000 LB	_____.	_____.
0204	634.0614 Posts Wood 4x6-Inch X 14-FT	29.000 EACH	_____.	_____.
0206	634.0616 Posts Wood 4x6-Inch X 16-FT	18.000 EACH	_____.	_____.
0208	634.0618 Posts Wood 4x6-Inch X 18-FT	8.000 EACH	_____.	_____.
0210	634.0620 Posts Wood 4x6-Inch X 20-FT	6.000 EACH	_____.	_____.
0212	637.2210 Signs Type II Reflective H	674.000 SF	_____.	_____.
0214	637.2215 Signs Type II Reflective H Folding	20.000 SF	_____.	_____.
0216	637.2230 Signs Type II Reflective F	44.000 SF	_____.	_____.
0218	638.2602 Removing Signs Type II	37.000 EACH	_____.	_____.
0220	638.3000 Removing Small Sign Supports	38.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 8 of 11

Proposal ID: 20190212006 Project(s): 1517-75-77

Federal ID(s): WISC 2019120

SECTION: 0001

Contact Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0222	642.5201 Field Office Type C	1.000 EACH	_____.	_____.
0224	643.0310.S Temporary Portable Rumble Strips	1.000 LS	_____.	_____.
0226	643.0410 Traffic Control Barricades Type II	272.000 DAY	_____.	_____.
0228	643.0420 Traffic Control Barricades Type III	2,658.000 DAY	_____.	_____.
0230	643.0705 Traffic Control Warning Lights Type A	3,668.000 DAY	_____.	_____.
0232	643.0900 Traffic Control Signs	3,458.000 DAY	_____.	_____.
0234	643.0910 Traffic Control Covering Signs Type I	8.000 EACH	_____.	_____.
0236	643.0920 Traffic Control Covering Signs Type II	4.000 EACH	_____.	_____.
0238	643.1050 Traffic Control Signs PCMS	28.000 DAY	_____.	_____.
0240	643.5000 Traffic Control	1.000 EACH	_____.	_____.
0242	646.1020 Marking Line Epoxy 4-Inch	22,647.000 LF	_____.	_____.
0244	646.3020 Marking Line Epoxy 8-Inch	922.000 LF	_____.	_____.
0246	646.5020 Marking Arrow Epoxy	10.000 EACH	_____.	_____.
0248	646.5120 Marking Word Epoxy	3.000 EACH	_____.	_____.
0250	646.5320 Marking Railroad Crossings Epoxy	4.000 EACH	_____.	_____.
0252	646.7120 Marking Diagonal Epoxy 12-Inch	291.000 LF	_____.	_____.



Proposal Schedule of Items

Page 9 of 11

Proposal ID: 20190212006 Project(s): 1517-75-77

Federal ID(s): WISC 2019120

SECTION: 0001

Contact Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0254	646.7420 Marking Crosswalk Epoxy Transverse Line 6-Inch	517.000 LF	_____.	_____.
0256	646.8120 Marking Curb Epoxy	243.000 LF	_____.	_____.
0258	646.8220 Marking Island Nose Epoxy	6.000 EACH	_____.	_____.
0260	652.0225 Conduit Rigid Nonmetallic Schedule 40 2-Inch	1,868.000 LF	_____.	_____.
0262	653.0164 Pull Boxes Non-Conductive 24x42-Inch	7.000 EACH	_____.	_____.
0264	653.0905 Removing Pull Boxes	2.000 EACH	_____.	_____.
0266	654.0105 Concrete Bases Type 5	3.000 EACH	_____.	_____.
0268	654.0107 Concrete Bases Type 7	6.000 EACH	_____.	_____.
0270	654.0230 Concrete Control Cabinet Bases Type L30	1.000 EACH	_____.	_____.
0272	655.0610 Electrical Wire Lighting 12 AWG	1,320.000 LF	_____.	_____.
0274	655.0615 Electrical Wire Lighting 10 AWG	2,129.000 LF	_____.	_____.
0276	655.0620 Electrical Wire Lighting 8 AWG	7,984.000 LF	_____.	_____.
0278	656.0400 Electrical Service Main Lugs Only Meter Pedestal (location) 001.CB-200	LS	LUMP SUM	_____.
0280	657.0210 Transformer Bases Breakaway 15-17 Inch Bolt Circle	6.000 EACH	_____.	_____.
0282	657.0255 Transformer Bases Breakaway 11 1/2-Inch Bolt Circle	3.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 10 of 11

Proposal ID: 20190212006 Project(s): 1517-75-77

Federal ID(s): WISC 2019120

SECTION: 0001

Contact Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0284	657.0337 Poles Type 17-Aluminum	7.000 EACH	_____.	_____.
0286	657.0730 Luminaire Arms Truss Type 6-Inch Clamp 12-FT	8.000 EACH	_____.	_____.
0288	659.1125 Luminaires Utility LED C	8.000 EACH	_____.	_____.
0290	659.2230 Lighting Control Cabinets 240/480 30-Inch	1.000 EACH	_____.	_____.
0292	662.1026.S Ramp Closure Gates Hardwired 26-FT	2.000 EACH	_____.	_____.
0294	662.1040.S Ramp Closure Gates Hardwired 40-FT	1.000 EACH	_____.	_____.
0296	690.0150 Sawing Asphalt	695.000 LF	_____.	_____.
0298	690.0250 Sawing Concrete	127.000 LF	_____.	_____.
0300	715.0415 Incentive Strength Concrete Pavement	6,440.000 DOL	1.00000	6,440.00
0302	715.0710 Optimized Aggregate Gradation Incentive	12,871.800 DOL	1.00000	12,871.80
0304	740.0440 Incentive IRI Ride	2,950.000 DOL	1.00000	2,950.00
0306	ASP.1T0A On-the-Job Training Apprentice at \$5.00/HR	2,000.000 HRS	5.00000	10,000.00
0308	ASP.1T0G On-the-Job Training Graduate at \$5.00/HR	1,320.000 HRS	5.00000	6,600.00
0310	SPV.0035 Special 001. Roadway Embankment	1,632.000 CY	_____.	_____.
0312	SPV.0060 Special 100. Manhole 10-FT Diameter	1.000 EACH	_____.	_____.
0314	SPV.0060 Special 250. Remove Commerical Sign	1.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 11 of 11

Proposal ID: 20190212006 Project(s): 1517-75-77

Federal ID(s): WISC 2019120

SECTION: 0001

Contact Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0316	SPV.0060 Special 650. Adjusting Sanitary Manhole Covers	10.000 EACH	_____.	_____.
0318	SPV.0075 Special 001. Street Sweeping	34.000 HRS	_____.	_____.
0320	SPV.0090 Special 651. Sanitary Lateral 4-Inch	50.000 LF	_____.	_____.
0322	SPV.0105 Special 002. Survey Project 1517-75-77	LS	LUMP SUM	_____.
0324	SPV.0120 Special 150. Water for Seeded Areas	396.000 MGAL	_____.	_____.
0326	SPV.0180 Special 001. Modified High Performance Concrete (HPC) Pavement 9-Inch	21,453.000 SY	_____.	_____.
0328	SPV.0180 Special 002. Removing Crushed Aggregate Slope Paving	705.000 SY	_____.	_____.
0330	643.0300 Traffic Control Drums	340.000 DAY	_____.	_____.
0332	643.0715 Traffic Control Warning Lights Type C	340.000 DAY	_____.	_____.
Section: 0001			Total:	_____.
			Total Bid:	_____.