HIGHWAY WORK PROPOSAL

Wisconsin Department of Transportation 06/2017 s.66.0901(7) Wis. Stats

STATE PROJECT

COUNTY

Notice of Award Dated

HIGHWAY

Proposal Number:

Pierce 7650-01-62 N/A Hager City - Prescott; Ush 63 To

FEDERAL

escott; Ush 63 To STH 035

Coulee Creek

PROJECT DESCRIPTION

ADDENDUM REQUIRED ATTACHED AT BACK

This proposal, submitted by the undersigned bidder to the Wisconsin Department of Transportation, is in accordance with the advertised request for proposals. The bidder is to furnish and deliver all materials, and to perform all work for the improvement of the designated project in the time specified, in accordance with the appended Proposal Requirements and Conditions.

Proposal Guaranty Required: \$100,000.00 Payable to: Wisconsin Department of Transportation		Attach Proposal Guaranty on back of this PAGE.
Bid Submittal		Firm Name, Address, City, State, Zip Code
Date: March 12, 2019 Time (Local Time): 9:00 am		SAMPLE
Contract Completion Time		NOT FOR BIDDING PURPOSES
65 Working Days		
Assigned Disadvantaged Business Enterprise Goal	0%	This contract is exempt from federal oversight.

This certifies that the undersigned bidder, duly sworn, is an authorized representative of the firm named above; that the bidder has examined and carefully prepared the bid from the plans, Highway Work Proposal, and all addenda, and has checked the same in detail before submitting this proposal or bid; and that the bidder or agents, officer, or employees have not, either directly or indirectly, entered into any agreement, participated in any collusion, or otherwise taken any action in restraint of free competitive bidding in connection with this proposal bid.

into any agreement, participated in any collusion, or otherwise taken any action in restraint of free competitive bidding in connection with this proposal bid.

Do not sign, notarize, or submit this Highway Work Proposal when submitting an electronic bid on the Internet.

Subscribed and sworn to before me this date ______

(Signature, Notary Public, State of Wisconsin)

(Print or Type Name, Notary Public, State Wisconsin)

(Print or Type Bidder Name)

(Date Commission Expires)

(Bidder Title)

Notary Seal

Type of Work:

For Department Use Only

Excavation, Base, HMA Pavement, Guard Rail, Pavement Marking

Date Guaranty Returned

PLEASE ATTACH PROPOSAL GUARANTY HERE

Effective with November 2007 Letting

PROPOSAL REQUIREMENTS AND CONDITIONS

The bidder, signing and submitting this proposal, agrees and declares as a condition thereof, to be bound by the following conditions and requirements.

If the bidder has a corporate relationship with the proposal design engineering company, the bidder declares that it did not obtain any facts, data, or other information related to this proposal from the design engineering company that was not available to all bidders.

The bidder declares that they have carefully examined the site of, and the proposal, plans, specifications and contract forms for the work contemplated, and it is assumed that the bidder has investigated and is satisfied as to the conditions to be encountered, as to the character, quality, and quantities of work to be performed and materials to be furnished, and as to the requirements of the specifications, special provisions and contract. It is mutually agreed that submission of a proposal shall be considered conclusive evidence that the bidder has made such examination.

The bidder submits herewith a proposal guaranty in proper form and amount payable to the party as designated in the advertisement inviting proposals, to be retained by and become the property of the owner of the work in the event the undersigned shall fail to execute the contract and contract bond and return the same to the office of the engineer within fourteen (14) days after having been notified in writing to do so; otherwise to be returned.

The bidder declares that they understand that the estimate of quantities in the attached schedule is approximate only and that the attached quantities may be greater or less in accordance with the specifications.

The bidder agrees to perform the said work, for and in consideration of the payment of the amount becoming due on account of work performed, according to the unit prices bid in the following schedule, and to accept such amounts in full payment of said work.

The bidder declares that all of the said work will be performed at their own proper cost and expense, that they will furnish all necessary materials, labor, tools, machinery, apparatus, and other means of construction in the manner provided in the applicable specifications and the approved plans for the work together with all standard and special designs that may be designed on such plans, and the special provisions in the contract of which this proposal will become a part, if and when accepted. The bidder further agrees that the applicable specifications and all plans and working drawings are made a part hereof, as fully and completely as if attached hereto.

The bidder, if awarded the contract, agrees to begin the work not later than ten (10) days after the date of written notification from the engineer to do so, unless otherwise stipulated in the special provisions.

The bidder declares that if they are awarded the contract, they will execute the contract agreement and begin and complete the work within the time named herein, and they will file a good and sufficient surety bond for the amount of the contract for performance and also for the full amount of the contract for payment.

The bidder, if awarded the contract, shall pay all claims as required by Section 779.14, Statutes of Wisconsin, and shall be subject to and discharge all liabilities for injuries pursuant to Chapter 102 of the Statutes of Wisconsin, and all acts amendatory thereto. They shall further be responsible for any damages to property or injury to persons occurring through their own negligence or that of their employees or agents, incident to the performance of work under this contract, pursuant to the Standard Specifications for Road and Bridge Construction applicable to this contract.

In connection with the performance of work under this contract, the contractor agrees to comply with all applicable state and federal statutes relating to non-discrimination in employment. No otherwise qualified person shall be excluded from employment or otherwise be subject to discrimination in employment in any manner on the basis of age, race, religion, color, gender, national origin or ancestry, disability, arrest or conviction record (in keeping with s.111.32), sexual orientation, marital status, membership in the military reserve, honesty testing, genetic testing, and outside use of lawful products. This provision shall include, but not be limited to the following: employment, upgrading, demotion or transfer; recruitment or recruitment advertising; layoff or termination; rates of pay or other forms of compensation, and selection for training, including apprenticeship. The contractor further agrees to ensure equal opportunity in employment to all applicants and employees and to take affirmative action to attain a representative workforce.

The contractor agrees to post notices and posters setting forth the provisions of the nondiscrimination clause, in a conspicuous and easily accessible place, available for employees and applicants for employment.

If a state public official (section 19.42, Stats.) or an organization in which a state public official holds at least a 10% interest is a party to this agreement, this contract is voidable by the state unless appropriate disclosure is made to the State of Wisconsin Ethics Board.

Effective with August 2015 Letting

BID PREPARATION

Preparing the Proposal Schedule of Items

A General

- (1) Obtain bidding proposals as specified in section 102 of the standard specifications prior to 11:45 AM of the last business day preceding the letting. Submit bidding proposals using one of the following methods:
 - 1. Electronic bid on theinternet.
 - 2. Electronic bid on a printout with accompanying diskette or CD ROM.
 - 3. Paper bid under a waiver of the electronic submittal requirements.
- (2) Bids submitted on a printout with accompanying diskette or CD ROM or paper bids submitted under a waiver of the electronic submittal requirements govern over bids submitted on the internet.
- (3) The department will provide bidding information through the department's web site at: https://wisconsindot.gov/Pages/doing-bus/contractors/hcci/bid-let.aspx

The contractor is responsible for reviewing this web site for general notices as well as information regarding proposals in each letting. The department will also post special notices of all addenda to each proposal through this web site no later than 4:00 PM local time on the Thursday before the letting. Check the department's web site after 5:00 PM local time on the Thursday before the letting to ensure all addenda have been accounted for before preparing the bid. When bidding using methods 1 and 2 above, check the Bid ExpressTM on-line bidding exchange at http://www.bidx.com/ after 5:00 PM local time on the Thursday before the letting to ensure that the latest schedule of items Expedite file (*.ebs or *.00x) is used to submit the final bid.

(4) Interested parties can subscribe to the Bid ExpressTM on-line bidding exchange by following the instructions provided at the www.bidx.com web site or by contacting:

Info Tech Inc. 5700 SW 34th Street, Suite 1235 Gainesville, FL 32608-5371 email: mailto:customer.support@bidx.com

- (5) The department will address equipment and process failures, if the bidder can demonstrate that those failures were beyond their control.
- (6) Contractors are responsible for checking on the issuance of addenda and for obtaining the addenda. Notice of issuance of addenda is posted on the department's web site at:

 https://wisconsindot.gov/Pages/doing-bus/contractors/hcci/bid-let.aspx

or by calling the department at (608) 266-1631. Addenda can ONLY be obtained from the departments web site listed above or by picking up the addenda at the Bureau of Highway Construction, 4th floor, 4822 Madison Yards Way, Madison, WI, during regular business hours

(7) Addenda posted after 5:00 PM on the Thursday before the letting will be emailed to the eligible bidders for that proposal. All eligible bidders shall acknowledge receipt of the addenda whether they are bidding on the proposal or not. Not acknowledging receipt may jeopardize the awarding of the project.

B Submitting Electronic Bids

B.1 On the Internet

- (1) Do the following before submitting the bid:
 - 1. Have a properly executed annual bid bond on file with the department.

- 2. Have a digital ID on file with and enabled by Info Tech Inc. Using this digital ID will constitute the bidder's signature for proper execution of the bidding proposal.
- (2) In lieu of preparing, delivering, and submitting the proposal as specified in 102.6 and 102.9 of the standard specifications, submit the proposal on the internet as follows:
 - 1. Download the latest schedule of items reflecting all addenda from the Bid Express TM web site.
 - 2. Use Expedite TM software to enter a unit price for every item in the schedule of items.
 - 3. Submit the bid according to the requirements of ExpediteTM software and the Bid ExpressTM web site. Do not submit a bid on a printout with accompanying diskette or CD ROM or a paper bid. If the bidder does submit a bid on a printout with accompanying diskette or a paper bid in addition to the internet submittal, the department will disregard the internet bid.
 - 4. Submit the bid before the hour and date the Notice to Contractors designates.
 - Do not sign, notarize, and return the bidding proposal described in 102.2 of the standard specifications.
- (3) The department will not consider the bid accepted until the hour and date the Notice to Contractors designates.

B.2 On a Printout with Accompanying Diskette or CD ROM

(1) Download the latest schedule of items from the Wisconsin pages of the Bid ExpressTM web site reflecting the latest addenda posted on the department's web site at:

https://wisconsindot.gov/Pages/doing-bus/contractors/hcci/bid-let.aspx

Use Expedite TM software to prepare and print the schedule of items. Provide a valid amount for all price fields. Follow instructions and review the help screens provided on the Bid Express Web site to assure that the schedule of items is prepared properly.

(2) Staple an 8 1/2 by 11 inch printout of the ExpediteTM generated schedule of items to the other proposal documents submitted to the department as a part of the bidder's sealed bid. As a separate submittal, not in the sealed bid envelop but due at the same time and place as the sealed bid, also provide the ExpediteTM generated schedule of items on a 3 1/2 inch computer diskette or CD ROM. Label each diskette or CD ROM with the bidder's name, the 4 character department-assigned bidder identification code from the top of the bidding proposal, and a list of the proposal numbers included on that diskette or CD ROM as indicated in the following example:

Bidder Name

BN00

Proposals: 1, 12, 14, & 22

- (3) If bidding on more than one proposal in the letting, the bidder may include all proposals for that letting on one diskette or CD ROM. Include only submitted proposals with no incomplete or other files on the diskette or CD ROM.
- (4) The bidder-submitted printout of the ExpediteTM generated schedule of items is the governing contract document and must conform to the requirements of section 102 of the standard specifications. If a printout needs to be altered, cross out the printed information with ink or typewriter and enter the new information and initial it in ink. If there is a discrepancy between the printout and the diskette or CD ROM, the department will analyze the bid using the printout information.
- (5) In addition to the reasons specified in section 102 of the standard specifications, proposals are irregular and the department may reject them for one or more of the following:
 - 1. The check code printed on the bottom of the printout of the ExpediteTM generated schedule of items is not the same on each page.
 - 2. The check code printed on the printout of the ExpediteTM generated schedule of items is not the same as the check code for that proposal provided on the diskette or CD ROM.

3. The diskette or CD ROM is not submitted at the time and place the department designates.

C Waiver of Electronic Submittal

- (1) The bidder may request a waiver of the electronic submittal requirements. Submit a written request for a waiver in lieu of bids submitted on the internet or on a printout with accompanying diskette or CD ROM. Use the waiver that was included with the paper bid document sent to the bidder or type up a waiver on the bidder's letterhead. The department will waive the electronic submittal requirements for a bidding entity (individual, partnership, joint venture, corporation, or limited liability company) for up to 4 individual proposals in a calendar year. The department may allow additional waivers for equipment malfunctions.
- (2) Submit a schedule of items on paper conforming to section 102 of the standard specifications. The department charges the bidder a \$75 administrative fee per proposal, payable at the time and place the department designates for receiving bids, to cover the costs of data entry. The department will accept a check or money order payable to: "Wisconsin, Dept. of Transportation."
- (3) In addition to the reasons specified in section 102 of the standard specifications, proposals are irregular and the department may reject them for one or more of the following:
 - 1. The bidder fails to provide the written request for waiver of the electronic submittal requirements.
 - 2. The bidder fails to pay the \$75 administrative fee before the time the department designates for the opening of bids unless the bidder requests on the waiver that they be billed for the \$75.
 - 3. The bidder exceeds 4 waivers of electronic submittal requirements within a calendar year.
- (4) In addition to the reasons specified in section 102 of the standard specifications, the department may refuse to issue bidding proposals for future contracts to a bidding entity that owes the department administrative fees for a waiver of electronic submittal requirements.

PROPOSAL BID BOND

DT1303 1/2006

Wisconsin Department of Transportation

Proposal Number	Project Number		Letting Date
Name of Principal			
Name of Surety		State in Which Surety is	Organized

We, the above-named Principal and the above-named Surety, are held and firmly bound unto the State of Wisconsin in the sum equal to the Proposal Guaranty for the total bid submitted for the payment to be made; we jointly and severally bind ourselves, our heirs, executors, administrators, successors and assigns. The condition of this obligation is that the Principal has submitted a bid proposal to the State of Wisconsin acting through the Department of Transportation for the improvement designated by the Proposal Number and Letting Date indicated above.

If the Principal is awarded the contract and, within the time and manner required by law after the prescribed forms are presented for signature, enters into a written contract in accordance with the bid, and files the bond with the Department of Transportation to guarantee faithful performance and payment for labor and materials, as required by law, or if the Department of Transportation shall reject all bids for the work described, then this obligation shall be null and void; otherwise, it shall be and remain in full force and effect. In the event of failure of the Principal to enter into the contract or give the specified bond, the Principal shall pay to the Department of Transportation within 10 business days of demand a total equal to the Proposal Guaranty as liquidated damages; the liability of the Surety continues for the full amount of the obligation as stated until the obligation is paid in full.

The Surety, for value received, agrees that the obligations of it and its bond shall not be impaired or affected by any extension of time within which the Department of Transportation may accept the bid; and the Surety does waive notice of any such extension.

IN WITNESS, the Principal and Surety have agreed and have signed by their proper officers and have caused their corporate seals to be affixed this date: **(DATE MUST BE ENTERED)**

PRINCIPAL

(Company Name) (Affix Corpo	rate Seal)			
(Signature and Title)				
(Company Name)	_			
(Signature and Title)				
(Company Name)				
(Signature and Title)		(Name of Surety) (Affix Seal)		
(Company Name)		(Signature of Attorney-in-Fact)		
(Signature and Title)				
NOTARY F	OR PRINCIPAL	NOTARY FO	R SURETY	
(Date)	(Dat	te)	
State of Wisconsin)	State of Wisconsin)	
) ss. County)) ss. _County)	
On the above date, this instrumen named person(s).	t was acknowledged before me by the	On the above date, this instrument w named person(s).	as acknowledged before me by the	
(Signature, Notary P	ublic, State of Wisconsin)	(Signature, Notary Publ	ic, State of Wisconsin)	
(Print or Type Name, Notary Public, State of Wisconsin)		(Print or Type Name, Notary Public, State of Wisconsin)		
(Date Comr	mission Expires)	(Date Commis	sion Expires)	

Notary Seal Notary Seal

IMPORTANT: A certified copy of Power of Attorney of the signatory agent must be attached to the bid bond.

CERTIFICATE OF ANNUAL BID BOND

DT1305 8/2003

Wisconsin Department of Transportation

(Date)

Time Period Valid (From/To)
Name of Surety	
Name of Contracto	r
Certificate Holder	Wisconsin Department of Transportation
	y that an annual bid bond issued by the above-named Surety is currently on file with the eartment of Transportation.
	is issued as a matter of information and conveys no rights upon the certificate holder mend, extend or alter the coverage of the annual bid bond.
Cancellation:	Should the above policy be cancelled before the expiration date, the issuing surety will give thirty (30) days written notice to the certificate holder indicated above.

(Signature of Authorized Contractor Representative)

March 2010

LIST OF SUBCONTRACTORS

Section 66.0901(7), Wisconsin Statutes, provides that as a part of the proposal, the bidder also shall submit a list of the subcontractors the bidder proposes to contract with and the class of work to be performed by each. In order to qualify for inclusion in the bidder's list a subcontractor shall first submit a bid in writing, to the general contractor at least 48 hours prior to the time of the bid closing. The list may not be added to or altered without the written consent of the municipality. A proposal of a bidder is not invalid if any subcontractor and the class of work to be performed by the subcontractor has been omitted from a proposal; the omission shall be considered inadvertent or the bidder will perform the work personally.

No subcontract, whether listed herein or later proposed, may be entered into without the written consent of the Engineer as provided in Subsection 108.1 of the Standard Specifications.

Name of Subcontractor	Class of Work	Estimated Value	
			_
			_
			_

DECEMBER 2000

CERTIFICATION REGARDING DEBARMENT, SUSPENSION, AND OTHER RESPONSIBILITY MATTERS - PRIMARY COVERED TRANSACTIONS

Instructions for Certification

- 1. By signing and submitting this proposal, the prospective contractor is providing the certification set out below.
- 2. The inability of a person to provide the certification required below will not necessarily result in denial of participation in this covered transaction. The prospective contractor shall submit an explanation of why it cannot provide the certification set out below. The certification or explanation will be considered in connection with the department or agency's determination whether to enter into this transaction. However, failure of the prospective contractor to furnish a certification or an explanation shall disqualify such person from participation in this transaction.
- 3. The certification in this clause is a material representation of fact upon which reliance was placed when the department determined to enter into this transaction. If it is later determined that the contractor knowingly rendered an erroneous certification in addition to other remedies available to the Federal Government the department may terminate this transaction for cause or default.
- 4. The prospective contractor shall provide immediate written notice to the department to whom this proposal is submitted if at any time the prospective contractor learns that its certification was erroneous when submitted or has become erroneous by reason of changed circumstances.
- 5. The terms "covered transaction," "debarred," "suspended," "ineligible," "lower tier covered transaction," "participant," "person," "primary covered transaction," "principal," "proposal," and "voluntarily excluded," as used in this clause, have the meanings set out in the Definitions and Coverage sections of the rules implementing Executive Order 12549. You may contact the department to which this proposal is being submitted for assistance in obtaining a copy of those regulations.
- 6. The prospective contractor agrees by submitting this proposal that, should this contract be entered into, it shall not knowingly enter into any lower tier covered transaction with a person who is debarred, suspended, declared ineligible, or voluntarily excluded from participation in this covered transaction, unless authorized by the department entering into this transaction.
- 7. The prospective contractor further agrees by submitting this proposal that it will include the clause titled "Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion-Lower Tier Covered Transaction," which is included as an addendum to PR-1273 "Required Contract Provisions Federal Aid Construction Contracts," without

modification, in all lower tier covered transactions and in all solicitations for lower tier covered transactions.

- 8. The contractor may rely upon a certification of a prospective subcontractor/materials supplier that it is not debarred, suspended, ineligible, or voluntarily excluded from the covered transaction, unless it knows that the certification is erroneous. A contractor may decide the method and frequency by which it determines the eligibility of its principals. Each contractor may, but is not required to, check the Disapproval List (telephone # 608/266/1631).
- 9. Nothing contained in the foregoing shall be construed to require establishment of a system of records in order to render in good faith the certification required by this clause. The knowledge and information of a contractor is not required to exceed that which is normally possessed by a prudent person in the ordinary course of business dealings.
- 10. Except for transactions authorized under paragraph 6 of these instructions, if a contractor in a covered transaction knowingly enters into a lower tier covered transaction with a person who is suspended, debarred, ineligible or voluntarily excluded from participation in this transaction, in addition to other remedies available to the Federal Government, the department may terminate this transaction for cause or default.

Certification Regarding Debarment, Suspension, and Other Responsibility Matters - Primary Covered Transactions

- (1) The prospective contractor certifies to the best of its knowledge and belief, that it and its principals:
 - (a) Are not presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from covered transactions by any Federal department or agency;
 - (b) Have not within a three-year period preceding this proposal been convicted of or had a civil judgment rendered against them for commission of fraud or a criminal offense in connection with obtaining, attempting to obtain, or performing a public (Federal, State or local) transaction or contract under a public transaction; violation of Federal or State antitrust statutes or commission of embezzlement, theft, forgery, bribery, falsification or destruction of records, making false statements or receiving stolen property;
 - (c) Are not presently indicted for or otherwise criminally or civilly charged by a governmental entity (Federal, State or local) with commission of any of the offense enumerated in paragraph (1)(b) of this certification; and
 - (d) Have not within a three-year period preceding this proposal had one or more public transactions (Federal, State or local) terminated for cause or default.
- (2) Where the prospective contractor is unable to certify to any of the statements in this certification, such prospective contractor shall attach an explanation to this proposal.

Special Provisions

Table of Contents

	Article Description	Page #
1.	General	2
2.	Scope of Work	2
3.	Prosecution and Progress	2
4.	Traffic	3
5.	Holiday Work Restrictions	3
6.	Railroad Insurance and Coordination - BNSF Railway Company.	4
7.	Environmental Protection, Aquatic Exotic Species Control	5
8.	Environmental Protection, Erosion Control.	6
9.	Information to Bidders, WPDES General Construction Storm Water Discharge Permit	6
10.	Construction Over or Adjacent to Navigable Waters.	6
11.	Utilities	7
12.	Notice to Contractor, Timber Rattlesnake	8
13.	Notice to Contractor – Archaeological Sites.	8
14.	Removing Asphaltic Surface Milling 7650-01-62, Item 204.0120.01	8
15.	Removing Apron Endwalls, Item 204.9060.S.01.	8
16.	Prepare Foundation for Asphaltic Paving, Item 211.0100.	9
17.	HMA Pavement Percent Within Limits (PWL) QMP.	9
18.	HMA Percent Within Limits (PWL) Test Strip Volumetrics, Item 460.0105.S; HMA Percent Within Limits (PWL) Test Strip Density Item 460.0110.S	
19.	Appendix A	23
20.	Reheating HMA Pavement Longitudinal Joints, Item 460.4110.S.	30
21.	Pipe Grates, Item 611.9800.S.	30
22.	Salvaged Rail	31
23.	Temporary Portable Rumble Strips, Item 643.0310.S.	32
24.	Locating No-Passing Zones, Item 648.0100	32
25.	Cleaning Ditch, Item SPV.0090.01.	32
26.	Reconstructing Stone Headwall, Item SPV.0105.01.	33
27.	Material Transfer Vehicle, Item SPV.0105.02.	33
28.	Milling and Removing Temporary Joint, Item SPV.0105.03.	34
29.	Reconstructing Concrete Block Retaining Wall Cap, Item SPV.0105.04.	34

STSP'S Revised June 28, 2018 SPECIAL PROVISIONS

1. General.

Perform the work under this construction contract for Project 7650-01-62, Hager City – Prescott, USH 63 to Coulee Creek, STH 35, Pierce County, Wisconsin as the plans show and execute the work as specified in the State of Wisconsin, Department of Transportation, Standard Specifications for Highway and Structure Construction, 2019 Edition, as published by the department, and these special provisions.

If all or a portion of the plans and special provisions are developed in the SI metric system and the schedule of prices is developed in the US standard measure system, the department will pay for the work as bid in the US standard system.

100-005 (20180628)

2. Scope of Work.

The work under this contract shall consist of sphaltic surface milling, HMA pavement, guardrail, pavement marking and all incidental items necessary to complete the work as shown on the plans and included in the proposal and contract.

104-005 (20090901)

3. Prosecution and Progress.

Begin work within ten calendar days after the engineer issues a written notice to do so.

Provide the time frame for construction of the project within the 2019 construction season to the engineer in writing within a month after executing the contract but at least 14 calendar days before the preconstruction conference. Assure that the time frame is consistent with the contract completion time. Upon approval, the engineer will issue the notice to proceed within ten calendar days before the beginning of the approved time frame.

To revise the time frame, submit a written request to the engineer at least two weeks before the beginning of the intended time frame. The engineer will approve or deny that request based on the conditions cited in the request and its effect on the department's scheduled resources.

All work shall be completed by November 16, 2019.

Surface milling and placement of the lower layer of pavement must occur in the same calendar day at any given location except within the full depth milling area in the town of Diamond Bluff unless approved by the engineer. Placement of the lower layer of pavement in the full depth milling area in the Town of Diamond Bluff must occur within 72 hours of milling operations unless approved by the engineer. Placement of the upper layer of pavement must occur within 7 calendar days of the lower layer of pavement unless approved by the engineer. Do not remove side road butt joint transitions until 24 hours prior to side road paving.

Migratory Birds

To avoid impacts to nesting birds, removal of trees and shrubs which are likely to support active nests, or ground disturbance and vehicle traffic in grasslands with potential ground-nesting migratory birds shall be completed between August 30 to May 1.

7650-01-62 2 of 35

4. Traffic.

Construct STH 35 under traffic utilizing standard detail drawing Traffic Control for Lane Closure with Flagging Operation. Maximum work zone lane closure shall be limited to one mile in length for milling and paving operations. A second flagging operation (work zone lane closure) may occur a minimum of two miles away in the same direction as the other closure.

Two-way traffic shall be maintained during non-work hours.

Do not deliver or store materials and equipment within the right-of-way except in areas that are already paved or graveled.

Provide access to all commercial, private, and field entrances at all times along STH 35, unless written permission can be obtained by the contractor from the property owner 48 hours in advance of closing the access.

Wisconsin Lane Closure System Advance Notification

Provide the following advance notification to the engineer for incorporation into the Wisconsin Lane Closure System (LCS).

TABLE 108-1 CLOSURE TYPE AND REQUIRED MINIMUM ADVANCE NOTIFICATION

Closure type with height, weight, or width restrictions (available width, all lanes in one direction < 16')	MINIMUM NOTIFICATION
Lane and shoulder closures	7 calendar days
Full roadway closures	7 calendar days
Ramp closures	7 calendar days
Detours	7 calendar days
Closure type without height, weight, or width restrictions (available width, all lanes in one direction ≥16')	MINIMUM NOTIFICATION
Lane and shoulder closures	3 business days
Ramp closures	3 business days
Modifying all closure types	3 business days

Discuss LCS completion dates and provide changes in the schedule to the engineer at weekly project meetings in order to manage closures nearing their completion date.

Notification of Emergency and Local Officials

Provide emergency access to the STH 35 work zone at all times. Notify the following organizations and departments at least 72 hours before lane closures are put into effect:

Wisconsin State Patrol (715) 839-3800
Pierce County Sheriff's Department (715) 273-5051
Pierce County Highway Department (715) 273.5096

5. Holiday Work Restrictions.

Do not perform work on, nor haul materials of any kind along or across any portion of the highway carrying STH 35 traffic, and entirely clear the traveled way and shoulders of such portions of the highway of equipment, barricades, signs, lights, and any other material that might impede the free flow of traffic during the following holiday periods:

7650-01-62 3 of 35

- From noon Friday, May 24, 2019 to 6:00 AM Tuesday, May 28, 2019 for Memorial Day;
- From noon Wednesday, July 3, 2019 to 6:00 AM Monday, July 8, 2019 for Independence Day;
- From noon Friday, August 30, 2019 to 6:00 AM Tuesday, September 3, 2019 for Labor Day. stp-107-005 (20050502)

Special Events

Do not perform work as described above during the following special events:

- From noon Friday, April 19, 2019 to 6:00 AM Monday, April 22, 2019 for the Spring Flood Run;
- From noon Friday, September 20, 2019 to 6:00 AM Monday, September 23, 2019 for the Fall Flood Run.

6. Railroad Insurance and Coordination - BNSF Railway Company.

A Description

Comply with standard spec 107.17 for all work affecting BNSF Railway Company property and any existing tracks.

A.1 Railroad Insurance Requirements

In addition to standard spec 107.26, provide railroad protective liability insurance coverage as specified in standard spec 107.17.3. Insurance is filed in the name of BNSF Railway Company.

Notify evidence of the required coverage, and duration to Contact Calvin Nutt, Manager of Public Projects; 80 44th Avenue NE, Minneapolis, MN 55421; Telephone (763) 782-3495; E-mail calvin.nutt@BNSF.com to determine the applicable railroad rules and regulations. Once determined send the RPLI policy to bnsf@certfocus.com. Approval of the policy will not take place until the Manager of Public Projects has been contacted.

Also send a copy to the following: Anna Davey, NW Region Railroad Coordinator; 1701 N 4th Street, Superior, WI 54880; Telephone (715) 392-7960; E-mail: anna.davey@dot.wi.gov.

Include the following information on the insurance document:

- Project ID: 7650-01-62

- Project Location: Hager City - Prescott, WI

- Route Name: STH 35, Pierce County

- Crossing ID: 080026V - 080033F

- Railroad Subdivision: Aurora Sub

Railroad Milepost: 391.06 – 396.40

- Work Performed: Paving of mainline

A.2 Train Operation

construction.

Approximately 44 through freight trains operate daily at up to 60 mph. Switching movements occur at a slower speed.

A.3 Names and Addresses of Railroad Representatives for Consultation and Coordination Construction Contact

Calvin Nutt, Manager of Public Projects; 80 44th Avenue NE, Minneapolis, MN 55421; Telephone (763) 782-3495; E-mail Calvin.Nutt@BNSF.com for consultation on railroad requirements during

Amend standard spec 108.4 to include the railroad in the distribution of the initial bar chart, and monthly schedule updates. The bar chart shall specifically show work involving coordination with the railroad.

7650-01-62 4 of 35

Flagging Contact

Notify the Construction Contact above a minimum of 40 working days in advance to arrange for a railroad flagger. Reference the Crossing ID, Wisconsin Milepost and Subdivision found in A.1.

Cable Locate Contact

In addition to contacting Diggers Hotline, contact the BNSF Communications Network Control Center at (800) 533-2891, five working days before the locate is needed. Reference Wisconsin Milepost 391-06 – 369.40 on Line Segment 0003.

BNSF will only locate railroad owned facilities located in the railroad right-of-way. The railroad does not locate any other utilities.

A.4 Work by Railroad

The railroad will perform the work described in this section, except for work described in other special provisions, and will be accomplished without cost to the contractor. None.

A.5 Temporary Grade Crossing

If a temporary grade crossing is desired, submit a written request to the railroad representative named in A.3 at least 40 days prior to the time needed. Approval is subject to the discretion of the railroad. The department has made no arrangements for a temporary grade crossing. stp-107-026 (20170615)

7. Environmental Protection, Aquatic Exotic Species Control.

Exotic invasive organisms such as VHS, zebra mussels, purple loosestrife, and Eurasian water milfoil are becoming more prolific in Wisconsin and pose adverse effects to waters of the state. Wisconsin State Statutes 30.07, "Transportation of Aquatic Plants and Animals; Placement of Objects in Navigable Waters", details the state law that requires the removal of aquatic plants and zebra mussels each time equipment is put into state waters.

At construction sites that involve navigable water or wetlands, use the follow cleaning procedures to minimize the chance of exotic invasive species infestation. Use these procedures for all equipment that comes in contact with waters of the state and/or infested water or potentially infested water in other states.

Ensure that all equipment that has been in contact with waters of the state, or with infested or potentially infested waters, has been decontaminated for aquatic plant materials and zebra mussels before being used in other waters of the state. Before using equipment on this project, thoroughly disinfect all equipment that has come into contact with potentially infested waters. Guidelines from the Wisconsin Department of Natural Resources for disinfection are available at:

http://dnr.wi.gov/topic/invasives/disinfection.html

Use the following inspection and removal procedures:

- 1. Before leaving the contaminated site, wash machinery and ensure that the machinery is free of all soil and other substances that could possibly contain exotic invasive species;
- 2. Drain all water from boats, trailers, bilges, live wells, coolers, bait buckets, engine compartments, and any other area where water may be trapped;
- 3. Inspect boat hulls, propellers, trailers and other surfaces. Scrape off any attached mussels, remove any aquatic plant materials (fragments, stems, leaves, seeds, or roots), and dispose of removed mussels and plant materials in a garbage can before leaving the area or invested waters; and
- 4. Disinfect your boat, equipment and gear by either:
 - 4.1. Washing with ~212 F water (steam clean), or
 - 4.2. Drying thoroughly for five days after cleaning with soap and water and/or high pressure water, or

7650-01-62 5 of 35

4.3. Disinfecting with either 200 ppm (0.5 oz per gallon or 1 Tablespoon per gallon) Chlorine for 10-minute contact time or 1:100 solution (38 grams per gallon) of Virkon Aquatic for 20- to 30-minute contact time. Note: Virkon is not registered to kill zebra mussel veligers nor invertebrates like spiny water flea. Therefore this disinfect should be used in conjunction with a hot water (>104° F) application.

Complete the inspection and removal procedure before equipment is brought to the project site and before the equipment leaves the project site.

stp-107-055 (20130615)

8. Environmental Protection, Erosion Control.

Supplement standard spec 107.18 as follows:

Construction methods shall utilize "Best Management Practices". Erosion and sediment transport shall be controlled by erosion control methods shown in the latest edition of WisDOT's Standard Specifications for Highway and Structure Construction through consultation with the Wisconsin Department of Natural Resources. The contractor's Erosion Control Implementation Plan (ECIP) shall be provided to the Regional Stormwater and Erosion Control Engineer at least 14 days prior to the preconstruction conference for review.

Adequately protect all disturbed bank areas as soon as possible.

If dewatering is required, the water must be pumped into a properly selected and sized dewatering basin before the clean/filtered water is allowed to enter any waterway or wetland. The basin must remove suspended solids and contaminants to the maximum extent practicable. A properly designed and constructed dewatering basin must take into consideration maximum pumping volume (gpm or cfs) and the sedimentation rate for soils to be encountered. Do not house any dewatering technique in a wetland.

Restrict the removal of vegetative cover and exposure of bare ground to the minimum amounts necessary to complete construction. Restoration of disturbed soils shall take place as soon as conditions permit. If sufficient vegetative cover will not be achieved because of late season construction, the site must be properly winterized.

All temporary stock piles must be in an upland location and protected with erosion control measures. Do not stockpile materials in wetlands, waterways, or floodplains.

9. Information to Bidders, WPDES General Construction Storm Water Discharge Permit.

The department has obtained coverage through the Wisconsin Department of Natural Resources to discharge storm water associated with land disturbing construction activities of this contract under the Wisconsin Pollutant Discharge Elimination System General Construction Storm Water Discharge Permit (WPDES Permit No. WI-S066796-1). A certificate of permit coverage is available from the regional office by contacting Matt Pfeifer at (715) 579-0789. Post the permit in a conspicuous place at the construction site.

stp-107-056 (20180628)

10. Construction Over or Adjacent to Navigable Waters.

The Trimbelle River is classified as a state navigable waterway under standard spec 107.19.

The Big River is classified as a state navigable waterway under standard spec 107.19.

stp-107-060 (20171130)

7650-01-62 6 of 35

11. Utilities.

This contract comes under the provision of Administrative Rule Trans 220.

stp-107-065 (20080501)

Limit the removal of topsoil to 1 foot maximum depth in areas of apron endwall replacements and ditch cleaning to avoid utility conflict.

Line outages have not been scheduled or requested for any electrical facility. Use appropriate means and methods for installing barrier systems under the energized lines.

Bevcomm has underground communication facilities within the project limits. A site watch is required during work in the following locations:

- Station 467+24 473+22 RT due to beamguard replacement
- Station 626+14 LT due to apron endwall replacement
- Station 681+99 LT due to ditch cleaning
- Facilities located from Station 280+00 to 347+00 have been discontinued.

Contact Chad Whitcomb at (715) 792-2103, 14 days prior to work to be onsite for review.

CenturyLink has underground communication facilities within the project limits. A site watch is required during work in the following locations:

- Station 720+30 721+70 LT due to beamguard replacement within approximately 4 feet of the posts
- Station 892+37 897+14 LT due to beamguard replacement within approximately 4 feet of the posts

Contact Jeremy Sisko at (714) 234-5534, two days prior to work to be onsite when posts and new beamquard are placed.

Pierce Pepin Cooperative Services has overhead electric facilities within the project limits. A site watch is required during work in the following locations:

- Station 454+90 LT & RT due to beamguard replacement

Pierce Pepin Cooperative Services has underground electric facilities within the project limits. A site watch is required during work in the following locations:

- Station 292+57 RT due to ditch cleaning
- Station 358+72 RT due to ditch cleaning
- Station 398+50 RT due to ditch cleaning
- Station 645+11 RT due to apron endwall replacement

Contact Brad Ristow at (717) 273-2473, two days prior to work to be onsite for review.

The following utility companies have facilities on or near the project site, but conflicts are not anticipated:

- Dairyland Power Cooperative Electricity
- Flint Hills Resources Gas/Petroleum
- We Energies Gas/Petroleum
- **Xcel Energy** Electricity

7650-01-62 7 of 35

12. Notice to Contractor, Timber Rattlesnake.

Timber Rattlesnake (Crotalus horridus), is a species of Special Concern and a Protected Wild Animal. Timbers emerge from hibernation as early as mid-April but may continue to emerge well into June. They remain active until as late as mid-October. Timbers primarily breed in August and females give birth the following mid-August or mid-September. Individual females in WI usually produce young only once every three to four years. If a snake is encountered during construction, coordinate with project staff and discontinue work in that area until coordination with WDNR can be accomplished.

13. Notice to Contractor – Archaeological Sites.

The department completed archeological and historical screening for project 7650-01-62 and identified several locations where archeological sites exist. These sites shall not be used for borrow or waste disposal, or the staging of personnel, equipment and/or supplies:

- 47PI139 (Murphy I): Station 346 370 LT
- · 47PI415 (P #396): Station 610 614 RT

14. Removing Asphaltic Surface Milling 7650-01-62, Item 204.0120.01.

Conform to standard spec 204 except as follows.

Any spare millings may be given to Pierce County at the contractor's discretion. Contact the Pierce County Highway Commissioner 14 days prior to construction to coordinate if millings will be provided to the county:

Chad Johnson 621 Cairns St. Ellsworth, WI 54011 Phone: 715.273.5096

15. Removing Apron Endwalls, Item 204.9060.S.01.

A Description

This special provision describes removing apron endwalls conforming to standard spec 204.

B (Vacant)

C Construction

Conform to standard spec 204.

D Measurement

The department will measure Removing Apron Endwalls by each individual unit acceptably completed.

E Payment

Add the following to standard spec 204.5:

ITEM NUMBER DESCRIPTION
204.9060.S.01 Removing Apron Endwalls
stp-204-025 (20150630)

UNIT

EACH

7650-01-62 8 of 35

16. Prepare Foundation for Asphaltic Paving, Item 211.0100.

Supplement standard spec 211.3.5 as follows:

After the surface mill, remove all surplus crack sealing, joint sealing, and asphalt patching materials to a minimum depth of 2 inches below the surface milled pavement. Completely remove unstable patches of asphaltic materials used to fill localized areas of pits, potholes, depressions, badly spalled areas, or disintegrated areas of old pavement. Remove any loose material with incipient spalling within or contiguous to such areas. Prior to refilling, all removal areas shall be cleaned by air blasting or other engineer approved methods.

Prior to placement of the HMA pavement or any wedging or leveling layers, refill these areas of removal, as described above, to the level of the milled surface. Payment for refilling these areas is paid for under bid item 465.0110 Asphaltic Surface Patching.

17. HMA Pavement Percent Within Limits (PWL) QMP.

A Description

This special provision describes percent within limits (PWL) pay determination, providing and maintaining a contractor Quality Control (QC) Program, department Quality Verification (QV) Program, required sampling and testing, dispute resolution, corrective action, pavement density, and payment for HMA pavements. Pay is determined by statistical analysis performed on contractor and department test results conducted according to the Quality Management Program (QMP) as specified in standard spec 460, except as modified below.

B Materials

Conform to the requirements of standard specs 450, 455, and 460 except where superseded by this special provision. The department will allow only one mix design for each HMA mixture type per layer required for the contract, unless approved by the engineer. The use of more than one mix design for each HMA pavement layer will require the contractor to construct a new test strip in accordance with HMA Pavement Percent Within Limits (PWL) QMP Test Strip Volumetrics and HMA Pavement Percent Within Limits (PWL) QMP Test Strip Density articles at no additional cost to the department.

Replace standard spec 460.2.8.2.1.3.1 Contracts with 5000 Tons of Mixture or Greater with the following:

460.2.8.2.1.3.1 Contracts under Percent within Limits

- (1) Furnish and maintain a laboratory at the plant site fully equipped for performing contractor QC testing. Have the laboratory on-site and operational before beginning mixture production.
- (2) Obtain random samples and perform tests according to this special provision and further defined in Appendix A: *Test Methods & Sampling for HMA PWL QMP Projects*. Obtain HMA mixture samples from trucks at the plant. For the sublot in which a QV sample is collected, discard the QC sample and test a split of the QV sample.
- (3) Perform sampling from the truck box and three-part splitting of HMA samples according to CMM 8-36. Sample size must be adequate to run the appropriate required tests in addition to one set of duplicate tests that may be required for dispute resolution (i.e., retained). This requires sample sizes which yield three splits for all random sampling per sublot. All QC samples shall provide the following: QC, QV, and Retained. The contractor shall take possession and test the QC portions. The department will observe the splitting and take possession of the samples intended for QV testing (i.e., QV portion from each sample) and the Retained portions. Additional sampling details are found in Appendix A. Label samples according to CMM 8-36. Additional handling instructions for retained samples are found in CMM 8-36.

7650-01-62 9 of 35

(4) Use the test methods identified below to perform the following tests at a frequency greater than or equal to that indicated:

- · Blended aggregate gradations in accordance with AASHTO T 30
- Asphalt content (AC) in percent determined by ignition oven method according to AASHTO T 308 as modified in CMM 8-36.6.3.6, chemical extraction according to AASHTO T 164 Method A or B, or automated extraction according to ASTM D8159 as modified in CMM 8-36.6.3.1.
- Bulk specific gravity (Gmb) of the compacted mixture according to AASHTO T 166.
- · Maximum specific gravity (Gmm) according to AASHTO T 209.
- · Air voids (Va) by calculation according to AASHTO T 269.
- Voids in Mineral Aggregate (VMA) by calculation according to AASHTO R35.

(5) Lot size shall consist of 3750 tons with sublots of 750 tons. Test each design mixture at a frequency of 1 test per 750 tons of mixture type produced and placed as part of the contract. Add a random sample for any fraction of 750 tons at the end of production for a specific mixture design. Partial lots with less than three sublot tests will be included into the previous lot for data analysis and pay adjustment. Volumetric lots will include all tonnage of mixture type under specified bid item unless otherwise specified in the plan.

⁽⁶⁾ Conduct field tensile strength ratio tests according to AASHTO T283, without freeze-thaw conditioning cycles, on each qualifying mixture in accordance with CMM 8-36.6.14. Test each full 50,000 ton production increment, or fraction of an increment, after the first 5,000 tons of production. Perform required increment testing in the first week of production of that increment. If field tensile strength ratio values are below the spec limit, notify the engineer. The engineer and contractor will jointly determine a corrective action.

Delete standard spec 460.2.8.2.1.5 and 460.2.8.2.1.6.

Replace standard spec 460.2.8.2.1.7 Corrective Action with the following:

460.2.8.2.1.7 Corrective Action

(1) Material must conform to the following action and acceptance limits based on individual QC and QV test results (tolerances relative to the JMF used on the PWL Test Strip):

ITEM	ACTION LIMITS	ACCEPTANCE LIMITS
Percent passing given sieve:		
37.5-mm	+/- 8.0	
25.0-mm	+/- 8.0	
19.0-mm	+/- 7.5	
12.5-mm	+/- 7.5	
9.5-mm	+/- 7.5	
2.36-mm	+/- 7.0	
75-µm	+/- 3.0	
AC in percent ^[1]	-0.3	-0.5
Va		- 1.5 & +2.0
VMA in percent ^[2]	- 0.5	-1.0

7650-01-62 10 of 35

- [1] The department will not adjust pay based on QC AC in percent test results; however corrective action will be applied to nonconforming material according to 460.2.8.2.1.7(3) as modified herein. [2] VMA limits based on minimum requirement for mix design nominal maximum aggregate size in table 460-1.
- (2) QV samples will be tested for Gmm, Gmb, and AC. Air voids and VMA will then be calculated using these test results.
- (3) Notify the engineer if any individual test result falls outside the action limits, investigate the cause and take corrective action to return to within action limits. If two consecutive test results fall outside the action limits, stop production. Production may not resume until approved by the engineer. Additional QV samples may be collected upon resuming production, at the discretion of the engineer.
- ⁽⁴⁾ For any additional tests outside the random number testing conducted for volumetrics, the data collected will not be entered into PWL calculations. Additional QV tests must meet acceptance limits or be subject to production stop and/or remove and replace.
- (5) Remove and replace unacceptable material at no additional expense to the department. Unacceptable material is defined as any individual QC or QV tests results outside the acceptance limits or a PWL value < 50. The engineer may allow such material to remain in place with a price reduction. The department will pay for such HMA Pavement allowed to remain in place at 50 percent of the contract unit price.

Replace standard spec 460.2.8.3.1.2 Personnel Requirements with the following:

460.2.8.3.1.2 Personnel Requirements

- (1) The department will provide at least one HTCP-certified Transportation Materials Sampling (TMS) Technician, to observe QV sampling of HMA mixtures.
- (2) Under departmental observation, a contractor TMS technician shall collect and split samples.
- (3) A department HTCP-certified Hot Mix Asphalt, Technician I, Production Tester (HMA-IPT) technician will ensure that all sampling is performed correctly and conduct testing, analyze test results, and report resulting data.
- ⁽⁴⁾ The department will make an organizational chart available to the contractor before mixture production begins. The organizational chart will include names, telephone numbers, and current certifications of all QV testing personnel. The department will update the chart with appropriate changes, as they become effective.

Replace standard spec 460.2.8.3.1.4 Department Verification Testing Requirements with the following:

460.2.8.3.1.4 Department Verification Testing Requirements

- (1) HTCP-certified department personnel will obtain QV random samples by directly supervising HTCP-certified contractor personnel sampling from trucks at the plant. Sample size must be adequate to run the appropriate required tests in addition to one set of duplicate tests that may be required for dispute resolution (i.e., retained). This requires sample sizes which yield three splits for all random sampling per sublot. All QV samples shall furnish the following: QC, QV, and Retained. The department will observe the splitting and take possession of the samples intended for QV testing (i.e., QV portion from each sample) and the Retained portions. The department will take possession of retained samples accumulated to date each day QV samples are collected. The department will retain samples until surpassing the analysis window of up to 5 lots, as defined in 460.2.8.3.1.7(2) of this special provision. Additional sampling details are found in Appendix A.
- (2) The department will verify product quality using the test methods specified here in 460.2.8.3.1.4(3). The department will identify test methods before construction starts and use only those methods during production of that material unless the engineer and contractor mutually agree otherwise.
- (3) The department will perform all testing conforming to the following standards:
 - Bulk specific gravity (Gmb) of the compacted mixture according to AASHTO T 166.
 - · Maximum specific gravity (Gmm) according to AASHTO T 209.

7650-01-62 11 of 35

- Air voids (Va) by calculation according to AASHTO T 269.
- · Voids in Mineral Aggregate (VMA) by calculation according to AASHTO R 35.
- Asphalt Content (AC) in percent determined by ignition oven method according to AASHTO T 308 as modified in CMM 8-36.6.3.6, chemical extraction according to AASHTO T 164 Method A or B, or automated extraction according to ASTM D8159 as modified in CMM 8-36.6.3.1.

(4) The department will randomly test each design mixture at the minimum frequency of one test for each lot.

Delete standard spec 460.2.8.3.1.6.

Replace standard spec 460.2.8.3.1.7 Dispute Resolution with the following:

460.2.8.3.1.7 Data Analysis for Volumetrics

(1) Analysis of test data for pay determination will be contingent upon QC and QV test results. Statistical analysis will be conducted on Gmm and Gmb test results for calculation of Va. If either Gmm or Gmb analysis results in non-comparable data as described in 460.2.8.3.1.7(2), subsequent testing will be performed for both parameters as detailed in the following paragraph.

(2) The engineer, upon completion of the first 3 lots, will compare the variances (F-test) and the means (t-test) of the QV test results with the QC test results. Additional comparisons incorporating the first 3 lots of data will be performed following completion of the 4th and 5th lots (i.e., lots 1-3, 1-4, and 1-5). A rolling window of 5 lots will be used to conduct F & t comparison for the remainder of the contract (i.e., lots 2-6, then lots 3-7, etc.), reporting comparison results for each individual lot. Analysis will use a set alpha value of 0.025. If the F- and t-tests report comparable data, the QC and QV data sets are determined to be statistically similar and QC data will be used to calculate the Va used in PWL and pay adjustment calculations. If the F- and t-tests result in non-comparable data, proceed to the *dispute resolution* steps found below. Note: if both QC and QV Va PWL result in a pay adjustment of 102% or greater, dispute resolution testing will not be conducted. Dispute resolution via further investigation is as follows:

^[1] The Retained portion of the split from the most recent lot in the analysis window (specifically the sublot identifying that variances or means do not compare) will be referee tested by the bureau's AASHTO accredited laboratory and certified personnel. If the non-comparison occurs following Lot 3, 4, or 5, all previous lots are subject to referee testing. Referee test results will replace the QV data of the sublot(s).

[2] Statistical analysis will be conducted with referee test results replacing QV results.

- i. If the F- and t-tests indicate variances and means compare, no further testing is required for the lot and QC data will be used for PWL and pay factor/adjustment calculations.
- ii. If the F- and t-tests indicate non-comparable variances or means, the Retained portion of the random QC sample will be tested by the department's regional lab for the remaining 4 sublots of the lot which the F- and t- tests indicate non-comparable datasets. The department's regional lab and the referee test results will be used for PWL and pay factor/adjustment calculations. Upon the second instance of non-comparable variance or means and for every instance thereafter, the department will assess a pay reduction for the additional testing of the remaining 4 sublots at \$2,000/lot under the HMA Regional Lab Testing administrative item.

[3] The contractor may choose to dispute the regional test results on a lot basis. In this event, the retained portion of each sublot will be referee tested by the department's AASHTO accredited laboratory and certified personnel. The referee Gmm and Gmb test results will supersede the regional lab results for the disputed lot.

i. If referee testing results in an increased calculated pay factor, the department will pay for the cost of the additional referee testing.

7650-01-62 12 of 35

- ii. If referee testing of a disputed lot results in an equal or lower calculated pay factor, the department will assess a pay reduction for the additional referee testing at \$2,000/lot under the Referee Testing administrative item.
- (3) The department will notify the contractor of the referee test results within 3 working days after receipt of the samples by the department's AASHTO accredited laboratory. The intent is to provide referee test results within 7 calendar days from completion of the lot.
- ⁽⁴⁾ The department will determine mixture conformance and acceptability by analyzing referee test results, reviewing mixture data, and inspecting the completed pavement according to the standard spec, this special provision, and accompanying Appendix A.
- (5) Unacceptable material (i.e., resulting in a PWL value less than 50 or individual QC or QV test results not meeting the Acceptance Requirements of 460.2.8.2.1.7 as modified herein) will be referee tested by the bureau's AASHTO accredited laboratory and certified personnel. Such material may be subject to remove and replace, at the discretion of the engineer. If the engineer allows the material to remain in place, it will be paid at 50% of the HMA Pavement contract unit price. Replacement or pay adjustment will be conducted on a sublot basis. If an entire PWL sublot is removed and replaced, the test results of the newly placed material will replace the original data for the sublot. Any remove and replace shall be performed at no additional cost to the department. Testing of replaced material must include a minimum of one QV result. [Note: If the removed and replaced material does not result in replacement of original QV data, an additional QV test will be conducted and under such circumstances will be entered into the HMA PWL Production spreadsheet for data analysis and pay determination.] The quantity of material paid at 50% the contract unit price will be deducted from PWL pay adjustments, along with accompanying data of this material.

Delete standard spec 460.2.8.3.1.8 Corrective Action.

C Construction

Replace standard spec 460.3.3.2 Pavement Density Determination with the following:

460.3.3.2 Pavement Density Determination

- (1) The engineer will determine the target maximum density using department procedures described in CMM 8-15. The engineer will determine density as soon as practicable after compaction and before placement of subsequent layers or before opening to traffic.
- (2) Do not re-roll compacted mixtures with deficient density test results. Do not operate continuously below the specified minimum density. Stop production, identify the source of the problem, and make corrections to produce work meeting the specification requirements.
- (3) A lot is defined as 7500 lane feet with sublots of 1500 lane feet (excluding shoulder, even if paved integrally) and placed within a single layer for each location and target maximum density category indicated in table 460-3. The contractor is required to complete three tests randomly per sublot and the department will randomly conduct one QV test per sublot. A partial quantity less than 750 lane feet will be included with the previous sublot. Partial lots with less than three sublots will be included in the previous lot for data analysis/acceptance and pay, by the engineer. If density lots/sublots are determined prior to construction of the test strip, any random locations within the test strip shall be omitted. Exclusions such as shoulders and appurtenances shall be tested and recorded in accordance with CMM 8-15. However, all acceptance testing of shoulders and appurtenances will be conducted by the department, and average lot (daily) densities must conform to standard spec Table 460-3. No density incentive or disincentive will be applied to shoulders or appurtenances. Offsets will not be applied to nuclear density gauge readings for shoulders or appurtenances. Unacceptable shoulder material will be handled according to standard spec 460.3.3.1 and CMM 8-15.11.
- (4) The three QC locations per sublot represent the outside, middle, and inside of the paving lane. The QC density testing procedures are detailed in Appendix A.

7650-01-62 13 of 35

- (5) QV nuclear testing will consist of one randomly selected location per sublot. The QV density testing procedures will be the same as the QC procedure at each testing location and are also detailed in Appendix A.
- ⁽⁶⁾ An HTCP-certified nuclear density technician (NUCDENSITYTEC-I) shall identify random locations and perform the testing for both the contractor and department. The responsible certified technician shall ensure that sample location and testing is performed correctly, analyze test results, and provide density results to the contractor weekly, or at the completion of each lot.
- (7) For any additional tests outside the random number testing conducted for density, the data collected will not be entered into PWL calculations. However, additional QV testing must meet the tolerances for material conformance as specified in the standard specification and this special provision. If additional density data identifies unacceptable material, proceed as specified in CMM 8-15.11.

Replace standard spec 460.3.3.3 Waiving Density Testing with Acceptance of Density Data with the following:

460.3.3.3 Analysis of Density Data

- (1) Analysis of test data for pay determination will be contingent upon test results from both the contractor (QC) and the department (QV).
- (2) As random density locations are paved, the data will be recorded in the HMA PWL Production Spreadsheet for analysis in chronological order. The engineer, upon completion of the analysis lot, will compare the variances (F-test) and the means (t-test) of the QV test results with the QC test results. Analysis will use a set alpha value of 0.025.
 - If the F- and t-tests indicate variances and means compare, the QC and QV data sets are determined to be statistically similar and QC data will be used for PWL and pay adjustment calculations.
 - ii. If the F- and t-tests indicate variances or means do not compare, the QV data will be used for subsequent calculations.
- (3) The department will determine mixture density conformance and acceptability by analyzing test results, reviewing mixture data, and inspecting the completed pavement according to standard spec, this special provision, and accompanying Appendix A.
- (4) Density resulting in a PWL value less than 50 or not meeting the requirements of 460.3.3.1 (any individual density test result falling more than 3.0 percent below the minimum required target maximum density as specified in standard spec Table 460-3) is unacceptable and may be subject to remove and replace at no additional cost to the department, at the discretion of the engineer.
 - Replacement may be conducted on a sublot basis. If an entire PWL sublot is removed and replaced, the test results of the newly placed material will replace the original data for the sublot.
 - ii. Testing of replaced material must include a minimum of one QV result. [Note: If the removed and replaced material does not result in replacement of original QV data, an additional QV test must be conducted and under such circumstances will be entered into the data analysis and pay determination.]
 - iii. If the engineer allows such material to remain in place, it will be paid for at 50% of the HMA Pavement contract unit price. The extent of unacceptable material will be addressed as specified in CMM 8-15.11. The quantity of material paid at 50% the contract unit price will be deducted from PWL pay adjustments, along with accompanying data of this material.

D Measurement

The department will measure the HMA Pavement bid items acceptably completed by the ton as specified in standard spec 450.4 and as follows in standard spec 460.5 as modified in this special provision.

E Payment

Replace standard spec 460.5.2 HMA Pavement with the following:

7650-01-62 14 of 35

460.5.2 HMA Pavement

460.5.2.1 General

- (1) Payment for HMA Pavement Type LT, MT, and HT mixes is full compensation for providing HMA mixture designs; for preparing foundation; for furnishing, preparing, hauling, mixing, placing, and compacting mixture; for HMA PWL QMP testing and aggregate source testing; for warm mix asphalt additives or processes; for stabilizer, hydrated lime and liquid antistripping agent, if required; and for all materials including asphaltic materials.
- (2) If provided for in the plan quantities, the department will pay for a leveling layer, placed to correct irregularities in an existing paved surface before overlaying, under the pertinent paving bid item. Absent a plan quantity, the department will pay for a leveling layer as extra work.

460.5.2.2 Calculation of Pay Adjustment for HMA Pavement using PWL

(1) Pay adjustments will be calculated using 65 dollars per ton of HMA pavement. The HMA PWL Production Spreadsheet, including data, will be made available to the contractor by the department as soon as practicable upon completion of each lot. The department will pay for measured quantities of mix based on this price multiplied by the following pay adjustment calculated in accordance with the HMA PWL Production Spreadsheet:

PAY FACTOR FOR HMA PAVEMENT AIR VOIDS & DENSITY

PERCENT WITHIN LIMITS	PAYMENT FACTOR, PF
(PWL)	(percent of \$65/ton)
≥ 90 to 100	PF = ((PWL - 90) * 0.4) + 100
\geq 50 to < 90	(PWL * 0.5) + 55
<50	50% ^[1]

where PF is calculated per air voids and density, denoted PFair voids & PFdensity

[1] Any material resulting in PWL value less than 50 shall be removed and replaced unless the engineer allows such material to remain in place. In the event the material remains in place, it will be paid at 50% of the contract unit price of HMA pavement.

For air voids, PWL values will be calculated using lower and upper specification limits of 2.0 and 4.3 percent, respectively. Lower specification limits for density shall be in accordance with standard spec Table 460-3. Pay adjustment will be determined on a lot basis and will be computed as shown in the following equation.

Pay Adjustment = $(PF-100)/100 \times (WP) \times (tonnage) \times (\$65/ton)^*$

*Note: If Pay Factor <50, the contract unit price will be used in lieu of \$65/ton

7650-01-62 15 of 35

The following weighted percentage (WP) values will be used for the corresponding parameter:

Parameter WP
Air Voids 0.5
Density 0.5

Individual Pay Factors for each air voids (PF_{air voids}) and density (PF_{density}) will be determined. PF_{air voids} will be multiplied by the total tonnage placed (i.e., from truck tickets), and PF_{density} will be multiplied by the calculated tonnage used to pave the mainline only (i.e., travel lane excluding shoulder) as determined in accordance with Appendix A.

The department will pay incentive for air voids and density under the following bid items:

ITEM NUMBER	DESCRIPTION	UNIT
460.2005	Incentive Density PWL HMA Pavement	DOL
460.2010	Incentive Air Voids HMA Pavement	DOL

The department will administer disincentives under the Disincentive Density HMA Pavement and the Disincentive Air Voids HMA Pavement administrative items.

The department will administer a disincentive under the Disincentive HMA Binder Content administrative item for each individual QV test result indicating asphalt binder content below the Action Limit in 460.2.8.2.1.7 presented herein. The department will adjust pay per sublot of mix at 65 dollars per ton of HMA pavement multiplied by the following pay adjustment calculated according to the HMA PWL Production Spreadsheet:

AC Binder	Pay Adjustment /	
Relative to JMF	<u>Sublot</u>	
-0.4% to -0.5%	75%	
More than -0.5%	50% ^[1]	

^[1] Any material resulting in an asphalt binder content more than 0.5% below the JMF AC content shall be removed and replaced unless the engineer allows such material to remain in place. In the event the material remains in place, it will be paid at 50% of the contract unit price of HMA pavement. Such material will be referee tested by the department's AASHTO accredited laboratory and HTCP certified personnel using automated extraction according to automated extraction according to ASTM D8159 as modified in CMM 8-36.6.3.1.

Note: PWL value determination is further detailed in the *Calculations* worksheet of the HMA PWL Production spreadsheet. stp-460-050 (20181119)

18. HMA Percent Within Limits (PWL) Test Strip Volumetrics, Item 460.0105.S; HMA Percent Within Limits (PWL) Test Strip Density Item 460.0110.S.

7650-01-62 16 of 35

A Description

This special provision describes the Hot Mix Asphalt (HMA) density and volumetric testing tolerances required for an HMA test strip. An HMA test strip is required for contracts constructed under HMA Percent Within Limits (PWL) QMP. A density test strip is required for each pavement layer placed over a specific, uniform underlying material, unless specified otherwise in the plans. Each contract is restricted to a single mix design per mix type per layer (e.g., upper layer and lower layer may have different mix type specified or may have the same mix type with different mix designs). Each mix design requires a separate test strip. Density and volumetrics testing will be conducted on the same test strip whenever possible.

Perform work according to standard spec 460 and as follows.

B Materials

Use materials conforming to HMA Pavement Percent Within Limits (PWL) QMP special provision.

C Construction

C.1 Test Strip

Submit the test strip start time and date to the department in writing at least 5 calendar days in advance of construction of the test strip. If the contractor fails to begin paving within 2 hours of the submitted start time, the test strip is delayed and the department will assess the contractor \$2,000 for each instance according to Section E of this document. Alterations to the start time and date must be submitted to the department in writing a minimum of 24 hours prior to the start time. The contractor will not be liable for changes in start time related to adverse weather days as defined by standard spec 101.3 or equipment breakdown verified by the department.

On the first day of production for a test strip, produce approximately 750 tons of HMA. (Note: adjust tonnage to accommodate natural break points in the project.) Locate test strips in a section of the roadway to allow a representative rolling pattern (i.e. not a ramp or shoulder, etc.).

C.1.1 Sampling and Testing Intervals

C.1.1.1 Volumetrics

Laboratory testing will be conducted from a split sample yielding three components, with portions designated for QC (quality control), QV (quality verification), and retained.

During production for the test strip, obtain sufficient HMA mixture for three-part split samples from trucks prior to departure from the plant. Collect three split samples during the production of test strip material. Perform sampling from the truck box and three-part splitting of HMA according to CMM 8-36. These three samples will be randomly selected by the engineer from each *third* of the test strip tonnage (T), excluding the first 50 tons:

Sample Number	Production Interval (tons)
<u>1</u>	50 to $\frac{T}{3}$
<u>2</u>	$\frac{T}{3}$ to $\frac{2T}{3}$
<u>3</u>	$\frac{2T}{3}$ to T

C.1.1.2 Density

Required field tests include contractor QC and department QV nuclear density gauge tests and pavement coring at ten individual locations (five in each half of the test strip length) in accordance with Appendix A: Test Methods and Sampling for HMA PWL QMP Projects. Both QV and QC teams shall have two nuclear density gauges present for correlation at the time the test strip is constructed. QC and QV teams may

7650-01-62 17 of 35

wish to scan with additional gauges at the locations detailed in Appendix A, as only gauges used during the test strip correlation phase will be allowed.

C.1.2 Field Tests

C.1.2.1 Density

A gauge comparison according to CMM 8-15.7 shall be completed prior to the day of test strip construction. Daily standardization of gauges on reference blocks and a project reference site shall be performed according to CMM 8-15.8. A standard count shall be performed for each gauge on the material placed for the test strip, prior to any additional data collection. Nuclear gauge readings and pavement cores shall be used to determine nuclear gauge correlation in accordance with Appendix A. The two to three readings for the five locations across the mat for each of two zones shall be provided to the engineer. The engineer will analyze the readings of each gauge relative to the densities of the cores taken at each location. The engineer will determine the average difference between the nuclear gauge density readings and the measured core densities to be used as a constant offset value. This offset will be used to adjust raw density readings of the specific gauge and shall appear on the density data sheet along with gauge and project identification. An offset is specific to the mix and layer, therefore a separate value shall be determined for each layer of each mix placed over a differing underlying material for the contract. This constitutes correlation of that individual gauge for the given layer. Two gauges per team are not required to be onsite daily after completion of the test strip. Any data collected without a correlated gauge will not be accepted.

The contractor is responsible for coring the pavement from the footprint of the density tests and filling core holes according to Appendix A. Coring and filling of pavement core holes must be approved by the engineer. The QV team is responsible for the labeling and safe transport of the cores from the field to the QC laboratory. Testing of cores shall be conducted by the contractor and witnessed by department personnel. The contractor is responsible for drying the cores following testing. The department will take possession of cores following laboratory testing and will be responsible for any verification testing at the discretion of the engineer.

The target maximum density to be used in determining core density is the average of the three volumetric/mix Gmm values from the test strip multiplied by 62.24 lb/ft³. In the event mix and density portions of the test strip procedure are separated, or if an additional density test strip is required, the mix portion must be conducted prior to density determination. The target maximum density to determine core densities shall then be the Gmm four-test running average (or three-test average from a PWL volumetric-only test strip) from the end of the previous day's production multiplied by 62.24 lb/ft³. If no PWL production volumetric test is to be taken in a density-only test strip, a non-random three-part split mix sample will be taken and tested for Gmm by the department representative. The department Gmm test results from this non-random test will be entered in the HMA PWL Test Strip Spreadsheet and must conform to the Acceptance Limits presented in C.2.1.

Exclusions such as shoulders and appurtenances shall be tested and reported according to CMM 8-15. However, all acceptance testing of shoulders and appurtenances will be conducted by the department, and average lot (daily) densities must conform to standard spec Table 460-3. No density incentive or disincentive will be applied to shoulders or appurtenances. However, unacceptable shoulder material will be handled according to standard spec 460.3.3.1 and CMM 8-15.11.

C.1.3 Laboratory Tests

C.1.3.1 Volumetrics

Obtain random samples according to C.1.1.1 and Appendix A. Perform tests the same day as taking the sample.

Theoretical maximum specific gravities of each mixture sample will be obtained according to AASHTO T 209. Bulk specific gravities of both gyratory compacted samples and field cores shall be determined according to AASHTO T 166. The bulk specific gravity values determined from field cores shall be used to calculate a correction factor (i.e., offset) for each QC and QV nuclear density gauge. The correction factor will be used throughout the remainder of the layer.

7650-01-62 18 of 35

C.2 Acceptance

C.2.1 Volumetrics

Produce mix conforming to the following limits based on individual QC and QV test results (tolerances based on most recent JMF):

ITEM	ACCEPTANCE LIMITS
Percent passing given sieve:	
37.5-mm	+/- 8.0
25.0-mm	+/- 8.0
19.0-mm	+/- 7.5
12.5-mm	+/- 7.5
9.5-mm	+/- 7.5
2.36-mm	+/- 7.0
75-µm	+/- 3.0
Asphaltic content in percent ^[1]	- 0.5
Air Voids	-1.5 & +2.0
VMA in percent ^[2]	- 1.0
Maximum specific gravity	+/- 0.024

^[1] Asphalt content more than -0.5% below the JMF will be referee tested by the department's AASHTO accredited laboratory and HTCP certified personnel using automated extraction according to WisDOT Modified ASTM D8159.

QV samples will be tested for Gmm, Gmb, and AC. Air voids and VMA will then be calculated using these test results.

Calculation of air voids shall use either the QC, QV, or retained split sample test results, as identified by conducting the paired t-test with the WisDOT PWL Test Strip Spreadsheet.

If QC and QV test results do not correlate as determined by the split sample comparison, the retained split sample will be tested by the department's AASHTO accredited laboratory and HTCP certified personnel as a referee test. Additional investigation shall be conducted to identify the source of the difference between QC and QV data. Referee data will be used to determine material conformance and pay.

C.2.2 Density

Compact all layers of test strip HMA mixture to the applicable density shown in the following table:

TABLE 460-3 MINIMUM REQUIRED DENSITY[1]

MIXTURE TYPE

LAYER	LT & MT	HT
LOWER	93.0 ^[2]	93.0 ^[3]

7650-01-62 19 of 35

 $^{^{[2]}}$ VMA limits based on minimum requirement for mix design nominal maximum aggregate size in <u>table 460-1</u>.

UPPER	93.0	93.0

^[1] If any individual core density test result falls more than 3.0 percent below the minimum required target maximum density, the engineer will investigate the acceptability of that material per CMM 8-15.11.

Nuclear density gauges are acceptable for use on the project only if correlation is completed for that gauge during the time of the test strip and the department issues documentation of acceptance stating the correlation offset value specific to the gauge and mix design. The offset is not to be entered into any nuclear density gauge as it will be applied by the department-furnished Field Density Worksheet.

C.2.3 Test Strip Approval and Material Conformance

All applicable laboratory and field testing associated with a test strip shall be completed prior to any additional mainline placement of the mix. All test reports shall be submitted to the department upon completion, and approved before paving resumes. The department will notify the contractor within 24 hours from start of test strip regarding approval to proceed with paving, unless an alternate time frame is agreed upon in writing with the department. The 24-hour approval time includes only working days as defined in standard spec 101.3.

The department will evaluate material conformance and make pay adjustments based on the PWL value of air voids and density for the test strip. The QC core densities and QC and QV mix results will be used to determine the PWL values as calculated in accordance with Appendix A.

The PWL values for air voids and density shall be calculated after determining core densities. An approved test strip is defined as the individual PWL values for air voids and density both being equal to or greater than 75, mixture volumetric properties conforming to the limits specified in C.2.1, and an acceptable gauge-to-core correlation. Further clarification on PWL test strip approval and appropriate post-test strip actions are shown in the following table:

PWL Test Strip Approval and Material Conformance Criteria

PWL Value for Air Voids and Density	Test Strip Approval	Material Conformance	Post-Test Strip Action
Both PWL ≥ 75	Approved ¹	Material paid for according to Section E.	Proceed with Production
50 ≤ Either PWL < 75	Not Approved	Material paid for according to Section E.	Consult BTS to determine need for additional test strip.
Either PWL < 50	Not Approved	Unacceptable material removed and replaced or paid for at 50% of the contract unit price according to Section E.	Construct additional Volumetrics or Density test strip as necessary.

¹ In addition to these PWL criteria, mixture volumetric properties must conform to the limits specified in C.2.1, split sample comparison must have a passing result and an acceptable gauge-to-core correlation must be completed.

7650-01-62 20 of 35

^[2] Minimum reduced by 2.0 percent for a lower layer constructed directly on crushed aggregate or recycled base courses.

^[3] Minimum reduced by 1.0 percent for lower layer constructed directly on crushed aggregate or recycled base courses.

A maximum of two test strips will be allowed to remain in place per pavement layer per contract. If material is removed, a new test strip shall replace the previous one at no additional cost to the department. If the contractor changes the mix design for a given mix type during a contract, no additional compensation will be paid by the department for the required additional test strip and the department will assess the contractor \$2,000 for the additional test strip according to Section E of this special provision. For simultaneously conducted density and volumetric test strip components, the following must be achieved:

- i. Passing/Resolution of Split Sample Comparison
- ii. Volumetrics/mix PWL value ≥ 75
- iii. Density PWL value ≥ 75
- iv. Acceptable correlation

If not conducted simultaneously, the mix portion of a test strip must accomplish (i) & (ii), while density must accomplish (iii) & (iv). If any applicable criteria are not achieved for a given test strip, the engineer, with authorization from the department's Bureau of Technical Services, will direct an additional test strip (or alternate plan approved by the department) be conducted to prove the criteria can be met prior to additional paving of that mix. For a density-only test strip, determination of mix conformance will be according to main production, i.e., HMA Pavement Percent Within Limits (PWL) QMP special provision.

D Measurement

The department will measure HMA Percent Within Limits (PWL) Test Strip as each unit of work, acceptably completed as passing the required air void, VMA, asphalt content, gradation, and density correlation for a Test Strip. Material quantities shall be determined according to standard spec 450.4 and detailed here within.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
460.0105.S	HMA Percent Within Limits (PWL) Test Strip Volumetrics	EACH
460.0110.S	HMA Percent Within Limits (PWL) Test Strip Density	EACH

These items are intended to compensate the contractor for the construction of the test strip for contracts paved under the HMA Pavement Percent Within Limits QMP article.

Payment for HMA Percent Within Limits (PWL) Test Strip Volumetrics is full compensation for volumetric sampling, splitting, and testing; for proper labeling, handling, and retention of split samples.

Payment for HMA Percent Within Limits (PWL) Test Strip Density is full compensation for collecting and measuring of pavement cores, acceptably filling core holes, providing of nuclear gauges and operator(s), and all other work associated with completion of a core-to-gauge correlation, as directed by the engineer.

Acceptable HMA mixture placed on the project as part of a volumetric or density test strip will be compensated by the appropriate HMA Pavement bid item with any applicable pay adjustments. If a test strip is delayed as defined in C.1 of this document, the department will assess the contractor \$2,000 for each instance, under the HMA Delayed Test Strip administrative item. If an additional test strip is required because the initial test strip is not approved by the department or the mix design is changed by the contractor, the department will assess the contractor \$2,000 for each additional test strip (i.e. \$2,000 for each individual volumetrics or density test strip) under the HMA Additional Test Strip administrative item.

Pay adjustment will be calculated using 65 dollars per ton of HMA pavement. The department will pay for measured quantities of mix based on \$65/ton multiplied by the following pay adjustment:

7650-01-62 21 of 35

PAY ADJUSTMENT FOR HMA PAVEMENT AIR VOIDS & DENSITY

 PERCENT WITHIN LIMITS
 PAYMENT FACTOR, PF

 (PWL)
 (percent of \$65/ton)

 \geq 90 to 100
 PF = ((PWL - 90) * 0.4) + 100

 \geq 50 to < 90</td>
 (PWL * 0.5) + 55

 <50</td>
 50%[1]

where, PF is calculated per air voids and density, denoted PFair voids & PFdensity

^[1]Material resulting in PWL value less than 50 shall be removed and replaced, unless the engineer allows for such material to remain in place. In the event the material remains in place, it will be paid at 50% of the contract unit price of HMA pavement.

For air voids, PWL values will be calculated using lower and upper specification limits of 2.0 and 4.3 percent, respectively. Lower specification limits for density will be according to Table 460-3 as modified herein. Pay adjustment will be determined for an acceptably completed test strip and will be computed as shown in the following equation:

Pay Adjustment = $(PF-100)/100 \times (WP) \times (tonnage) \times (\$65/ton)^*$

*Note: If Pay Factor <50, the contract unit price will be used in lieu of \$65/ton

The following weighted percentage (WP) values will be used for the corresponding parameter:

<u>Parameter</u>	WP
Air Voids	0.5
Density	0.5

Individual Pay Factors for each air voids (PF_{air voids}) and density (PF_{density}) will be determined. PF_{air voids} will be multiplied by the total tonnage produced (i.e., from truck tickets), and PF_{density} will be multiplied by the calculated tonnage used to pave the mainline only (i.e., traffic lane excluding shoulder) as determined in accordance with Appendix A.

The department will pay incentive for air voids under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
460.2005	Incentive Density PWL HMA Pavement	DOL
460.2010	Incentive Air Voids HMA Pavement	DOL

The department will administer disincentives under the Disincentive Density HMA Pavement and the Disincentive Air Voids HMA Pavement administrative items.

stp-460-040 (20181119)

7650-01-62 22 of 35

19. Appendix A.

Test Methods & Sampling for HMA PWL QMP Projects.

The following procedures are included with the HMA Pavement Percent Within Limits (PWL) Quality Management Program (QMP) special provision:

- WisDOT Procedure for Nuclear Gauge/Core Correlation Test Strip
- WisDOT Test Method for HMA PWL QMP Density Measurements for Main Production
- Sampling for WisDOT HMA PWL QMP
- · Calculation of PWL Mainline Tonnage Example

7650-01-62 23 of 35

<u>WisDOT Procedure for Nuclear Gauge/Core Correlation – Test Strip</u>




Figure 1: Nuclear/Core Correlation Location Layout

The engineer will identify two zones in which gauge/core correlation is to be performed. These two zones will be randomly selected within each *half* of the test strip length. (Note: Density zones shall not overlap and must have a minimum of 100 feet between the two zones; therefore, random numbers may be shifted (evenly) in order to meet these criteria.) Each zone shall consist of five locations across the mat as identified in Figure 1. The following shall be determined at each of the five locations within both zones:

- two one-minute nuclear density gauge readings for QC team*
- two one-minute nuclear density gauge readings for QV team*
- pavement core sample

*If the two readings exceed 1.0 pcf of one another, a third reading is conducted in the same orientation as the first reading. In this event, all three readings are averaged, the individual test reading of the three which falls farthest from the average value is discarded, and the average of the remaining two values is used to represent the location for the gauge.

The zones are supposed to be undisclosed to the contractor/roller operators. The engineer will not lay out density/core test sites until rolling is completed and the cold/finish roller is beyond the entirety of the zone. Sites are staggered across the 12-foot travel lane, and do not include shoulders. The outermost locations should be 1.5-feet from the center of the gauge to the edge of lane. [NOTE: This staggered layout is only applicable to the test strip. All mainline density locations after test strip should have a longitudinal- as well as transverse-random number to determine location as detailed in the *WisDOT Test Method for HMA PWL QMP Density Measurements for Main Production* section of this document.]


7650-01-62 24 of 35

Individual locations are represented by the symbol as seen in Figure 1 above. The symbol is two-part, comprised of the nuclear test locations and the location for coring the pavement, as distinguished here:





The nuclear site is the same for QC and QV readings for the test strip, i.e., the QC and QV teams are to take nuclear density gauge readings in the same footprint. Each of the QC and QV teams are to take a minimum of two one-minute readings per nuclear site, with the gauge rotated 180 degrees between readings, as seen here:






Figure 2: Nuclear gauge orientation for (a) 1st one-minute reading and (b) 2nd one-minute reading

Photos should be taken of each of the 10 core/gauge locations of the test strip. This should include gauge readings (pcf) and a labelled core within the gauge footprint. If a third reading is needed, all three readings should be recorded and documented. Only raw readings in pcf should be written on the pavement during the test strip, with a corresponding gauge ID/SN (generalized as QC-1 through QV-2 in the following Figure) in the following format:









Figure 3: Layout of raw gauge readings as recorded on pavement

Each core will then be taken from the center of the gauge footprint, and will be used to correlate each gauge with laboratory-measured bulk specific gravities of the pavement cores. One core in good condition must be obtained from each of the 10 locations. If a core is damaged at the time of extracting from the pavement, a replacement core should be taken immediately adjacent to the damaged core, i.e., from the same footprint. If a core is damaged during transport, it should be recorded as damaged and excluded from the correlation. Coring after traffic is on the pavement should be avoided. The contractor is responsible for coring of the pavement. Coring and filling of core holes must be approved by the engineer. The QV team is responsible for the labeling and safe transport of the cores from the field to the QC laboratory. Core density testing will be conducted by the contractor and witnessed by department personnel. The contractor is responsible for drying the cores following testing. The department will take possession of cores following initial testing and is responsible for any verification testing.

7650-01-62 25 of 35

Each core 150 mm (6 inches) in diameter will be taken at locations as identified in Figure 1. Each random core will be full thickness of the layer being placed. The contractor is responsible for thoroughly drying cores obtained from the mat in accordance with ASTM D 7227 prior to using specimens for in-place density determination in accordance with AASHTO T 166.

Cores must be taken before the pavement is open to traffic. Cores are cut under Department/project staff observation. Relabel each core immediately after extruding, or ensure that labels applied to pavement prior to cutting remain legible. The layer interface should also be marked immediately following extrusion. Cores should be cut at this interface, using a wet saw, to allow for density measurement of only the most recently placed layer. Cores should be protected from excessive temperatures such as direct sunlight. Also, there should be department custody (both in transport and storage) for the cores until they are tested, whether that be immediately after the test strip or subsequent day if agreed upon between Department and Contractor. Use of concrete cylinder molds works well to transport cores. Cores should be placed upside down (flat surface to bottom of cylinder mold) in the molds, one core per mold, cylinder molds stored upright, and ideally transported in a cooler. Avoid any stacking of pavement cores.

Fill all core holes with non-shrink rapid-hardening grout, mortar or concrete, or with HMA. When using grout, mortar or concrete, remove all water from the core holes prior to filling. Mix the mortar or concrete in a separate container prior to placement in the hole. If HMA is used, fill all core holes with hot-mix matching the same day's production mix type at same day compaction temperature +/- 20 F. The core holes shall be dry and coated with tack before filling, filled with a top layer no thicker than 2.25 inches, lower layers not to exceed 4 inches, and compacted with a Marshall hammer or similar tamping device using approximately 50 blows per layer. The finished surface shall be flush with the pavement surface. Any deviation in the surface of the filled core holes greater than 1/4 inch at the time of final inspection will require removal of the fill material to the depth of the layer thickness and replacement.

7650-01-62 26 of 35

<u>WisDOT Test Method for HMA PWL QMP Density Measurements for Main Production</u>

For nuclear density testing of the pavement beyond the test strip, QC tests will be completed at three locations per sublot, with a sublot defined as 1500 lane feet. The three locations will represent the outside, middle, and inside of the paving lane (i.e., the lane width will be divided into thirds as shown by the dashed longitudinal lines in Figure 3 and random numbers will be used to identify the specific transverse location within each third in accordance with CMM 8-15). Longitudinal locations within each sublot shall be determined with 3 independent random numbers. The PWL Density measurements do not include the shoulder and other appurtenances. Such areas are tested by the department and are not eligible for density incentive or disincentive. Each location will be measured with two one-minute gauge readings oriented 180 degrees from one another, in the same footprint as detailed in Figure 2 above. Each location requires a minimum of two readings per gauge. The density gauge orientation for the first test will be with the source rod towards the direction of paving. QV nuclear testing will consist of one randomly selected location per sublot. The QV is also comprised of two one-minute readings oriented 180 degrees from one another. For both QC and QV test locations, if the two readings exceed 1.0 pcf of one another, a third reading is conducted in the same orientation as the first reading. In this event, all three readings are averaged, the individual test reading of the three which falls farthest from the average value is discarded, and the average of the remaining two values is used to represent the location for the gauge. The sublot density testing layout is depicted in Figure 4, with QC test locations shown as solid lines and QV as dashed.




Figure 4: Locations of main lane HMA density testing (QC=solid lines, QV=dashed)

QC and QV nuclear density gauge readings will be statistically analyzed in accordance with Section 460.3.3.3 of the HMA PWL QMP SPV. (Note: For density data, if F- and t-tests compare, QC data will be used for the subsequent calculations of PWL value and pay determination. However, if an F- or t-test does not compare, the QV data will be used in subsequent calculations.)

7650-01-62 27 of 35

Sampling for WisDOT HMA PWL QMP Production

Sampling of HMA mix for QC, QV and Retained samples shall conform to CMM 8-36 except as modified here.

Delete CMM 8-36.4 Sampling Hot Mix Asphalt and replace with the following to update sublot tonnages:

Sampling Hot Mix Asphalt

At the beginning of the contract, the contractor determines the anticipated tonnage to be produced. The frequency of sampling is 1 per 750 tons (sublot) for QC and Retained Samples and 1 per 3750 tons (lot or 5 sublots) for QV as defined by the HMA PWL QMP SPV. A test sample is obtained randomly from each sublot. Each random sample shall be collected at the plant according to CMM 8-36.4.1 and 8-36.4.2. The contractor must submit the random numbers for all mix sampling to the department before production begins.

Example 1

Expected production for a contract is 12,400 tons. The number of required samples is determined based on this expected production (per HMA PWL QMP SPV) and is determined by the random sample calculation.

The approximate location of each sample within the prescribed sublots is determined by selecting random numbers using ASTM Method D-3665 or by using a calculator or computerized spreadsheet that has a random number generator. The random numbers selected are used in determining when a sample is to be taken and will be multiplied by the sublot tonnage. This number will then be added to the final tonnage of the previous sublot to yield the approximate cumulative tonnage of when each sample is to be taken.

To allow for plant start-up variability, the procedure calls for the first random sample to be taken at 50 tons or greater per production day (not intended to be taken in the first two truckloads). Random samples calculated for 0-50 ton should be taken in the next truck (51-75 ton).

This procedure is to be used for any number of samples per contract.

If the production is less than the final randomly generated sample tonnage, then the random sample is to be collected from the remaining portion of that sublot of production. If the randomly generated sample is calculated to be within the first 0-50 tons of the subsequent day of production, it should be taken in the next truck. Add a random sample for any fraction of 750 tons at the end of the contract. Lot size will consist of 3750 tons with sublots of 750 tons. Partial lots with less than three sublot tests will be included into the previous lot, by the engineer.

It's intended that the plant operator not be advised ahead of time when samples are to be taken. If the plant operator is involved in recording a Pb (%AC) to match up with the mix sample tonnage, then notification need not be earlier than 60 minutes before the mix sample being taken.

7650-01-62 28 of 35

If belt samples are used during troubleshooting, the blended aggregate will be obtained when the mixture production tonnage reaches approximately the sample tonnage. For plants with storage silos, this could be up to 60 minutes in advance of the mixture sample that's taken when the required tonnage is shipped from the plant.

QC, QV and retained samples shall be collected for all test strip and production mixture testing using a three-part splitting procedure according to CMM 8-36.5.2.

7650-01-62 29 of 35

<u>Calculation of PWL Mainline Tonnage Example</u>

A mill and overlay project in being constructed with a 12-foot travel lane and an integrally paved 3-foot shoulder. The layer thickness is 2 inches for the full width of paving. Calculate the tonnage in each sublot eligible for density incentive or disincentive.

Solution:

$$\frac{1500\,ft\,\times\,12\,ft}{9\,sf/sy}\times\frac{2\,in\,\times112\,lb/sy/in}{2000\,lb/ton}=224\,tons$$

stp-460-055 (20181119)

20. Reheating HMA Pavement Longitudinal Joints, Item 460.4110.S.

A Description

This special provision describes reheating the abutting edge of the previously compacted layer in the adjacent lane while paving mainline asphalt pavements.

B (Vacant)

C Construction

C.1 Equipment

Provide a self-contained heating unit that heats by convection only. Do not use forced air to enhance the flame. Provide a fireproof barrier between the flame and the heater's fuel source. The heater must produce a uniform distribution of heat within the heat box. Provide automatic controls to regulate the heater output and shutoff the heater when the paver stops or the heater control system loses power.

Mount the heater on the paver inside the paver's automatic leveling device.

C.2 Reheating Joints

Evenly reheat at least an 8 inch (200 mm) wide strip of the previously compacted layer in the adjacent lane as follows:

- Reheat the joint to within 60 degrees F (15 degrees C) of the mix temperature at the paver auger. Measure joint temperature immediately behind the heater.

The engineer may allow the required joint reheat temperatures to be cooler than specified to adjust for weather, wind, and other field conditions. Coordinate the heater output and paver speed to achieve the required joint reheat temperature without visible smoke emission.

D Measurement

The department will measure Reheating HMA Pavement Longitudinal Joints by the linear foot, acceptably completed, as measured along each joint for each layer of asphalt placed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER DESCRIPTION UNIT 460.4110.S Reheating HMA Pavement Longitudinal Joints LF

Payment is full compensation for all the work required under this bid item.

stp-460-015 (20140630)

21. Pipe Grates, Item 611.9800.S.

A Description

This special provision describes providing pipe grates on the ends of pipes.

7650-01-62 30 of 35

B Materials

Furnish steel conforming to the requirements of standard spec 506.2.2.1. Furnish steel pipe conforming to the requirements of standard spec 506.2.3.6.

Furnish pipe grates galvanized according to ASTM A123.

Furnish angles and brackets galvanized according to ASTM A123.

Furnish required hardware galvanized according to ASTM A153.

C Construction

Repair pipes, rods, angles and brackets on which the galvanized coating has been damaged according to the requirements of AASHTO M36M.

D Measurement

The department will measure Pipe Grates in units of work, where one unit is one grate, completed and accepted.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER DESCRIPTION UNIT 611.9800.S Pipe Grates EACH

Payment is full compensation for furnishing and installing all materials; and for drilling and connecting grates to pipes.

stp-611-010 (20030820)

22. Salvaged Rail.

Perform this work according to the pertinent requirements of standard spec 204 and standard spec 614 and as hereinafter provided.

Completely disassemble the existing beam guard and carefully remove all salvageable posts, blocks, guardrail and hardware (brackets, reflectors, nuts, washers, bolts and other appurtenances) in a manner that will preclude any damage (cutting or destructive measures are not allowed). Store the salvaged materials on the right-of-way, outside the limits of construction at a location approved by the engineer.

Store salvaged materials as follows:

Posts – Banded and neatly stacked on pallets.

Blocks - Banded and neatly stacked on pallets.

Beams - Banded and neatly stacked on pallets.

Hardware - In 5-gallon pails or burlap sacks.

Upon completion of the removal and storage of salvageable materials, contact the Pierce County Highway Commissioner.

Chad Johnson 621 Cairns St. Ellsworth, WI 54011

Phone: (715) 273-5096

Pierce County will inspect the materials and shall have the right to reject any damaged or otherwise unacceptable materials. Remove all other materials from the right-of-way and properly dispose of them, including items rejected by Pierce County.

Remove all other materials from the right-of-way and properly dispose of them, including items rejected by the Pierce County Highway Commissioner.

This work also includes entirely removing the posts and backfilling their hole as necessary.

Install the beam guard as detailed in the plans or as directed by the engineer within two working days after the completion of the removal of the beam guard. Beam guard must be installed prior to week shutdown, end of working day Friday, or as directed by the engineer.

7650-01-62 31 of 35

23. Temporary Portable Rumble Strips, Item 643.0310.S.

A Description

This special provision describes providing, relocating, maintaining, and removing temporary portable rumble strips.

B Materials

Furnish RoadQuake2 or Roadquake2F temporary portable rumble strips, by Plastic Safety Systems. Do not use alternate products or methods without preapproval by the Bureau of Traffic Operations.

C Construction

C.1 Placement

Provide rumble strips where the plans show or the engineer directs as follows:

- 1. Before placing rumble strips, clean the roadway of sand and other materials that may cause slippage.
- 2. Place one end of the rumble strips 6 inches from the roadway centerline. Extend the strips perpendicular to the direction of travel. Ensure strips lay flat on the roadway surface.
- Only one series of rumble strips, placed before the first work zone, is required per direction of travel for multiple work zones spaced 1 mile or less apart. Work zones spaced greater than 1 mile apart require a separate series of rumble strips.

C.2 Maintenance

Maintain rumble strips as follows:

- 1. If rumble strips slide, become out of alignment, or are no longer in the wheel path of approaching vehicles during the work period, thoroughly clean both sides of the rumble strips and reset on a clean roadway.
- 2. Repair or replace damaged rumble strips immediately.

D Measurement

The department will measure temporary portable rumble strips as a single lump sum unit of work, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER DESCRIPTION UNIT
643.0310.S Temporary Portable Rumble Strips LS

Payment is full compensation for providing, relocating, maintaining or replacing, and removing temporary portable rumble strips.

stp-643-020 (20161130)

24. Locating No-Passing Zones, Item 648.0100.

For this project, the spotting sight distance in areas with a 55 mph posted speed limit is 0.21 miles (1108 feet).

stp-648-005 (20060512)

25. Cleaning Ditch, Item SPV.0090.01.

A Description

This special provision describes minor grading, cleaning and finishing existing ditch flow lines to restore the conveyance of storm water as shown on the plans, according to the pertinent requirements of the standard specifications, and as hereinafter provided.

B (Vacant)

7650-01-62 32 of 35

C Construction

Grade and shape the ditch flow line as necessary to restore and allow unimpeded flow at inlet and outlet of each culvert pipe location. Do not excavate deeper than 1 foot nor disturb an overall lateral width greater than 10 feet. Grade and trim the lateral areas of disturbance to produce uniform side slope surfaces. Dispose of surplus material according to standard spec 205.3.12.

D Measurement

The department will measure Cleaning Ditch, completed according to the contract, by the linear foot, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBERDESCRIPTIONUNITSPV.0090.01Cleaning DitchLF

Payment is full compensation for all excavating, grading, shaping, compacting, and restoring the ditch flow line; and for furnishing and placing fill, topsoil, fertilizer, seed, and mulch.

26. Reconstructing Stone Headwall, Item SPV.0105.01.

A Description

This special provision describes reconstructing the existing stone headwall at Station 101+36, RT. Perform this work according to the pertinent requirements of standard spec 504 and standard spec 614 and as hereinafter provided:

B Materials

Furnish materials per standard spec 504.2.

C Construction

Reconstruct the stone headwall per standard spec 504.3 and per the plan details. Construction includes partial removal of existing headwall stone and debris within the headwall replacement area and replacement with a modified concrete masonry end wall. Construction to match into existing stone wall per plan details. Dispose of surplus debris material according to standard spec 205.3.12.

D Measurement

The department will measure Reconstructing Stone Headwall as a single lump sum unit of work, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBERDESCRIPTIONUNITSPV.0105.01Reconstructing Stone HeadwallLS

Payment is full compensation for excavating and backfilling; materials, including concrete masonry and steel reinforcement; forms; placing, including steel reinforcement; and for finishing, curing, protecting and heating.

27. Material Transfer Vehicle, Item SPV.0105.02.

A Description

This special provision describes furnishing Material Transfer Vehicle (MTV) and an operator for use on this project during HMA upper layer paving operations, as shown in the plans or as directed by the engineer, and as hereinafter provided.

B Materials

The MTV shall be self-propelled, remix and maintain constant temperature, and continually feed the paver hopper. The storage capacity shall be adequate to provide continuous forward movement of the paver.

7650-01-62 33 of 35

The paver speed shall be coordinated to match the delivery of material and capacity of the MTV to limit stopping of the paver.

C Construction

An operator shall remain with the vehicle at all times during moving operations and the paver's hopper shall remain full at all times to avoid segregation of coarse aggregates. No placement of HMA upper layer pavement shall be allowed without the use of the MTV.

D Measurement

The department will measure Material Transfer Vehicle as a single lump sum unit of work for each material transfer vehicle, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBERDESCRIPTIONUNITSPV.0105.02Material Transfer VehicleLS

Payment is full compensation for deploying the equipment and its operator.

28. Milling and Removing Temporary Joint, Item SPV.0105.03.

A Description

This special provision describes the milling and removing of the upper layer HMA wedge joint and any other temporary longitudinal or transverse joints, including sweeping and cleaning of the affected area prior to the abutting pavement placement.

B (Vacant)

C Construction

Immediately prior to the placement of the adjoining lane, mill any temporary wedge joint to a true line with a face perpendicular to the surface of the existing asphaltic surface pavement.

Immediately prior to continuation of paving operations, mill any temporary transverse joint to a true line with a face perpendicular to the surface of the existing asphaltic surface pavement.

The contractor becomes the owner of the removed asphaltic pavement and is responsible for the disposal as specified for disposing of materials under standard spec 204.3.1.3.

D Measurement

The department will measure Milling and Removing Temporary Joint as a single lump sum unit of work for all wedge joints, acceptably removed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBERDESCRIPTIONUNITSPV.0105.03Milling and Removing Temporary JointLS

Payment is full compensation for milling, removing, sweeping, cleaning, and disposing of materials.

29. Reconstructing Concrete Block Retaining Wall Cap, Item SPV.0105.04.

A Description

This special provision describes providing the reconstruction of the existing modular concrete block retaining wall cap, as shown in the plans and provided in the contract.

B Materials

Furnish modular concrete block cap units with a maximum 24-hour moisture absorption rate of 5.0 percent. Furnish cap units with a minimum 28-day compressive strength of 5,500 psi and an average of at least 5,800 psi for 3 units.

7650-01-62 34 of 35

Construction adhesive utilized to bond modular block units shall be suitable for use with masonry materials and meet requirements of the manufacturer.

C Construction

Remove the retaining wall cap modular concrete blocks without damaging the remaining wall parts. Replace contractor damaged parts and provide all other materials required to re-erect the retaining wall cap. Dispose of all surplus materials. Rebuild the retaining wall in kind and replace backfill in kind.

D Measurement

The department will measure Reconstructing Concrete Block Retaining Wall Cap as a single lump sum unit of work, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBERDESCRIPTIONUNITSPV.0105.04Reconstructing Concrete Block Retaining Wall CapLS

Payment is full compensation for removing and replacing the existing retaining wall cap, furnishing, backfill and all other components shown in the plan detail.

7650-01-62 35 of 35

November 2013 ASP-4

ADDITIONAL SPECIAL PROVISION 4

Payment to First-Tier Subcontractors

Within 10 calendar days of receiving a progress payment for work completed by a subcontractor, pay the subcontractor for that work. The prime contractor may withhold payment to a subcontractor if, within 10 calendar days of receipt of that progress payment, the prime contractor provides written notification to the subcontractor and the department documenting "just cause" for withholding payment.

The prime contractor may also withhold routine retainage from payments due subcontractors.

Payment to Lower-Tier Subcontractors

Ensure that subcontracting agreements at all tiers provide prompt payment rights to lower-tier subcontractors that parallel those granted first-tier subcontractors in this provision.

Release of Routine Retainage

After granting substantial completion the department may reduce the routine retainage withheld from the prime contractor to 75 percent of the original total amount retained.

When the Department sends the semi-final estimate the department may reduce the routine retainage withheld from the prime contractor to 10 percent of the original total amount retained.

Within 30 calendar days of receiving the semi-final estimate from the department, submit written certification that subcontractors at all tiers are paid in full for acceptably completed work and that no routine retainage is being withheld. The department will pay the prime contractor in full and reduce the routine retainage withheld from the prime contractor to zero when the department approves the final estimate.

This special provision does not limit the right of the department, prime contractor, or subcontractors at any tier to withhold payment for work not acceptably completed or work subject to an unresolved contract dispute.

ADDITIONAL SPECIAL PROVISION 6 ASP 6 - Modifications to the standard specifications

Make the following revisions to the standard specifications:

107.17.1 General

Replace paragraph seven with the following effective with the December 2018 letting:

(7) Have a professional engineer registered in the state of Wisconsin sign and seal the shop drawings. At least 30 calendar days before starting falsework, form, or shoring construction; submit a PDF file of shop drawings to the railroad's chief engineering officer and to the engineer. The engineer and the railroad may review the shop drawings. If the engineer or the railroad finds the shop drawings unsatisfactory, the contractor shall make the required changes. A satisfactory shop drawing review does not relieve the contractor of responsibility and liability for the structural integrity and proper functioning of the falsework, forms, or shoring.

109.1.1 General

Replace the entire text with the following effective with the January 2019 letting:

- (1) The engineer will use the US standard system to measure all work completed under the contract. The engineer will determine quantities of materials the contractor furnishes and work the contractor performs using measurement methods and computations conforming to standard engineering practice, modified to meet department requirements. The engineer will document these measurements using department procedures.
- (2) The engineer will measure the work as the contract measurement subsection for individual items specifies. The department will measure the actual quantities of work the contractor acceptably completes and make final payment based on those actual measured quantities except as follows:
 - 1. If the measurement subsection for a bid item specifically restricts the quantity measured for payment or allows for use of conversion factors.
 - If the engineer executes a contract change order modifying the method of measurement for specific bid items, the engineer will measure the quantities of applicable bid items for payment using the change order methods.
 - 3. If the engineer, under 105.3.1(2), approves a contractor-requested plan dimension change between US standard and SI metric dimensions, the engineer will measure whichever of the following is less:
 - Actual quantities constructed.
 - Quantities derived from the original plan dimensions.
 - 4. For substitutions made under 106.2.3 between US standard and SI metric products, the engineer will measure the actual quantities of the substitute products using the original contract measuring system.

305.2.1 General

Replace paragraph two with the following effective with the December 2018 letting:

(2) Where the contract specifies or allows 1 1/4-inch base, do not place reclaimed asphalt, reprocessed material, or blended materials below virgin aggregate materials unless the contract specifies or the engineer allows in writing. The department will allow virgin aggregate above reclaimed asphalt, reprocessed material, or blended materials in shoulder areas adjacent to concrete pavement.

420.3.2.1 General

Replace paragraph one with the following effective with the December 2018 letting:

(1) Use self-propelled grinding machines with depth, grade, and slope controls designed for grinding and texturing concrete. Equip grinding machines with diamond blades and a vacuuming system capable of removing liquid and solid residue from the ground surface. Shroud the machine to prevent discharging loosened material into adjacent work areas or live traffic lanes. Provide the specified effective wheelbase, defined as the center of the front to center of the rear main support wheels.

420.3.2.2 Continuous Grinding

Replace paragraph one with the following effective with the December 2018 letting:

(1) Under the Continuous Diamond Grinding Concrete Pavement bid item, ensure that the grinding machine, including the grinding head, weighs 35,000 pounds or more, will grind a strip at least 4 feet wide, and has an effective wheel base of 25 feet or more. For pavements with a design speed less than 40 miles per hour and areas difficult to access, the contractor may use equipment with an effective wheel base of 12 feet or more.

450.3.2.8 Jointing

Replace paragraphs three through five with the following effective with the December 2018 letting:

- (3) Construct notched wedge longitudinal joints for mainline paving if the pavement thickness conforms to the minimums specified in 460.3.2, unless the engineer directs or allows an alternate joint. Construct the wedge using a slope no steeper than 3:1. Extend the wedge 12 inches beyond the normal lane width, or as the engineer directs. Ensure that the wedge for all layers directly overlaps and slopes in the same direction.
- (4) Locate the joint at the pavement centerline for 2-lane roadways, or at lane lines if the roadway has more than 2 lanes. Construct a vertical notch 1/2-inch to 3/4-inch high on the centerline or lane line at the top of each wedge. Place a 1/2-inch to 3/4-inch notch at the outside bottom edge of the wedge after compacting each layer. Align the finished longitudinal joint line of the upper layer with the centerline or lane line.
- (5) Construct the wedge for each layer using an engineer-approved strike-off device that will provide a uniform slope and will not restrict the main screed. Shape and compact the wedge with a weighted steel side roller wheel the same width as the wedge. Apply a tack coat to the wedge surface and both notches before placing the adjacent lane.

455.2.4.3 Emulsified Asphalts

Replace paragraph two with the following effective with the December 2018 letting:

(2) The bill of lading for emulsified asphalts shall indicate the asphalt content of the original emulsion and dilution rate of the additional water added to the original emulsion. If undiluted samples are not available, test the diluted material and modify AASHTO M140, M208, or M316 to reflect properties resulting from dilution of the asphalt.

460.2.8.3.1.4 Department Verification Testing Requirements

Replace paragraph three with the following effective with the December 2018 letting:

(3) The department will perform testing conforming to the following standards:

Bulk specific gravity (G_{mb}) of the compacted mixture according to AASHTO T166.

Maximum specific gravity (G_{mm}) according to AASHTO T209.

Air voids (V_a) by calculation according to AASHTO T269.

VMA by calculation according to AASHTO R35.

Asphalt content by ignition oven according to AASHTO T308 as modified in CMM 8-36.6.3.6, chemical extraction according to AASHTO T-164, or Asphalt Analyzer™ according to manufacturer recommendations.

460.2.8.3.1.6 Acceptable Verification Parameters

Replace paragraph one with the following effective with the December 2018 letting:

- (1) The engineer will provide test results to the contractor within 2 mixture-production days after obtaining the sample. The quality of the product is acceptably verified if it meets the following limits:
 - Va is within a range of 2.0 to 4.3 percent. For SMA, Va is within a range of 2.7 to 5.3 percent.
 - VMA is within minus 0.5 of the minimum requirement for the mix design nominal maximum aggregate size.
 - Asphalt content is within minus 0.3 percent of the JMF.

460.2.8.3.1.7 Dispute Resolution

Replace paragraph one with the following effective with the December 2018 letting:

(1) When QV test results do not meet the specified limits for 100 percent pay, the bureau's AASHTO accredited laboratory and certified personnel will referee test the retained portion of the QV sample and the retained portion of the required forward and backward QC retained samples according to CMM 8-36.

460.5.2.1 General

Replace paragraphs five and six with the following effective with the December 2018 letting:

(5) The department will reduce pay for nonconforming QMP HMA mixtures as specified in 460.2.8.2.1.7, starting from the stop point to the point when the running average of 4 is back inside the warning limits. The engineer will determine the quantity of material subject to pay reduction based on the testing data and an inspection of the completed payement. The department will reduce pay as follows:

PAYMENT FOR MIXTURE[1][2][3]

	PRODUCED WITHIN	PRODUCED OUTSIDE
ITEM	WARNING BANDS	JMF LIMITS
Gradation	90%	75%
Asphalt Content ^[4]		
Air Voids	70%	50%
VMA	90%	75%

^[1] For projects or plants where the total production of each mixture design requires less than 4 tests refer to CMM 8-36.

- Payment is in percent of the contract unit price for the HMA Pavement bid item. The department will reduce pay based on the nonconforming property with lowest percent pay. If the quantity of material subject to pay adjustment based on the running average of 4 is also subject to pay adjustment resulting from dispute resolution in accordance with 460.2.8.3.1.7, the department will apply the single pay adjustment resulting in the lowest percent pay.
- [3] In addition to any pay adjustment listed in the table above, the department will adjust pay for nonconforming binder under the Nonconforming QMP Asphaltic Material administrative item. The department will deduct 25 percent of the contract unit price of the HMA Pavement bid item per ton of pavement placed with nonconforming PG binder the engineer allows to remain in place.
- ^[4] The department will not adjust pay based on a running average of 4 asphalt content tests; however, corrective action will be applied to nonconforming material according to 460.2.8.2.1.7.
- (6) If during a QV dispute resolution investigation the department discovers unacceptable mixture defined by one or more of the following:
 - Va greater than 5.0 or less than 1.5.
 - VMA more than 1.0 below the minimum allowed in table 460-1.
 - AC more than 0.5 % below the JMF target.

Remove and replace the material, or if the engineer allows the mixture to remain in place, the department will pay for the quantity of affected material at 50 percent of the contract price.

506.3.2 Shop Drawings

Replace paragraph four with the following effective with the December 2018 letting:

(4) Ensure that the fabricator submits a PDF file of shop drawings for railroad structures to the railroad company's chief engineering officer upon contract completion.

646.3.1.2 Liquid Marking

Replace paragraph five with the following effective with the January 2019 letting:

(5) Apply liquid marking and glass beads across the line at or exceeding the following:

LIQUID MARKING	PAVEMENT TYPE	THICKNESS	BEAD APPLICATION
		(mils)	(pounds per gallon)
Paint	all	16	8
Epoxy	SMA, seal coats, and polymer overlays	25	25
Epoxy	all other	20	22.5
Wet Reflective Epoxy	y all	20	18

646.3.2.3.2 Wet Reflective Epoxy

Replace paragraph five with the following effective with the January 2019 letting:

- (1) Apply wet reflective epoxy binder in a grooved slot, and provide a double drop bead system as follows:
 - First: wet reflective/recoverable elements at the application rate specified for the product chosen from the department's APL.
 - Second: glass beads at the application rate specified in 646.3.1.2(5).

650.3.1 General

Replace the entire text with the following effective with the December 2018 letting:

- (1) Department and contractor responsibilities for construction staking are specified in 105.6. Conform to 105.6 and the additional requirements specified here in 650.3 for the individual contractor-staking bid items the contract includes.
- (2) Protect and preserve known property and survey marks and land monuments as specified in 107.11.3. The contract may require related work under the 621 bid items.
- (3) Obtain or calculate benchmark data, grades, and alignment from plan information. The engineer will furnish data for the horizontal and vertical control points, control point ties, horizontal alignments, profiles, and elevations. Reestablish, set additional, and maintain the horizontal and vertical control points and control point ties, as needed for bid items.
- (4) Check horizontal and vertical information including but not limited to alignments, locations, elevations, and dimensions, that either the plans show or the engineer provides, for compatibility with existing field conditions. Conduct similar compatibility checks and accuracy checks of horizontal and vertical positions either the department or the contractor establishes in the field.
- (5) Perform survey work using conventional methods, or AMG methods capable of achieving the lines and grades the plans show for the work in question. Establish additional benchmarks and control points as necessary to support the method of operation.

650.3.1.1 Staking

- (1) Furnish, set, reference, and maintain stakes and markings necessary to establish the alignment, location, benchmarks, elevations, and continuous profile-grades for road and structure work as needed for bid items. Supervise and coordinate construction staking.
- (2) Maintain neat, orderly, and complete survey notes, drawings, and computations used in establishing the lines and grades. Make the survey notes and computations available to the engineer within 24 hours, upon request, as the work progresses.
- (3) Furnish surveying equipment, stakes, flags, pins, lath, whiskers, and other materials necessary to perform this work, subject to the engineer's approval.

650.3.1.2 Automated Machine Guidance

650.3.1.2.1 General

(1) The contractor may substitute AMG for conventional staking on all or part of the work under the individual staking bid items. Coordinate with the engineer throughout the course of construction to ensure that work performed using AMG conforms to the contract tolerances and that the methods employed conform to the contractor's AMG work plan and accepted industry standards. Revert to conventional staking methods for all or part of the work at any point during construction if AMG is producing unacceptable results.

650.3.1.2.2 AMG Work Plan

(1) Submit a comprehensive written AMG work plan for department review at least 5 business days before the preconstruction conference. In that plan discuss how AMG technology will be integrated into other

technologies employed on the project. List the staking bid items that will have work performed using AMG and, for each bid item listed, include the following:

- 1. Designate which portions of the contract will be done using AMG and which portions will be done using conventional staking.
- 2. Designate a single staff person as the primary contact for AMG technology issues.
- 3. List and map the primary and secondary control points required under 105.6.2 enveloping the site.
- 4. Describe the contractor's quality control procedures. Include the frequency and type of checks performed to ensure that the work conforms to the contract plans.
- (2) The engineer will review the plan to determine if it conforms to the contract. Do not perform AMG work until the engineer approves the governing portion of the AMG workplan. Perform the work as the contractor's AMG work plan provides. Update the plan as necessary.

650.3.1.2.3 Geometric and Surface Information

650.3.1.2.3.1 Department Responsibilities

(1) At any time after the contract is awarded the contractor may request the contractor data packet. The department will provide the packet within 5 business days of receiving the contractor's request.

650.3.1.2.3.2 Contractor Responsibilities

- (1) Develop and maintain a contractor construction model for areas of the project employing AMG. Confirm that the resulting model agrees with the contract plans.
- (2) If the engineer requests, provide the construction model to the department in LandXML or other engineer-approved format.

650.3.1.2.4 Managing and Updating Information

- (1) Notify the department of any errors or discrepancies in department-provided information. The department will determine what revisions may be required. The department will revise the contract plans, if necessary, to address errors or discrepancies that the contractor identifies. The department will provide the best available information related to those contract plan revisions.
- (2) Revise the construction model as required to support construction operations and to reflect any contract plan revisions the department makes. Perform checks to confirm that the revised construction model agrees with the contract plan revisions. If the engineer requests, provide construction model updates to the engineer. The department will pay for costs incurred to incorporate contract plan revisions as extra work.

650.3.1.2.5 Construction Checks

- (1) Check the work against the plan elevation at randomly selected points on cross-sections located at stations evenly divisible by 100 at the frequency the engineer approved as a part of the AMG work plan. Submit the results of these random checks to the engineer daily. Notify the engineer immediately if a check exceeds the tolerances specified in 650.3.1.2.6 below.
- (2) Check the work at additional points as the engineer directs. The department may conduct periodic independent checks.

650.3.1.2.6 Construction Tolerances

- (1) Ensure that the finished work vertically matches existing or other completed features. Ensure that the work conforms to revised plan elevations as follows:
 - Subgrade: +/- 0.10 feet.
 - Base: within the tolerance specified in 301.3.4.1(2).

650.3.3 Subgrade

Retitle and replace the entire text with the following effective with the December 2018 letting:

650.3.3 Subgrade Staking

(1) Set construction stakes or marks at intervals of 100 feet, or more frequently, for rural sections and at intervals of 50 feet, or more frequently, for urban sections. Include additional stakes at each cross-section as necessary to match the plan cross-section, achieve the required accuracy, and to support construction operations. Also set and maintain stakes as necessary to establish the horizontal and vertical positions of intersecting road radii, auxiliary lanes, horizontal and vertical curves, and curve

transitions. Locate stakes to within 0.25 feet horizontally and establish the grade elevation to within 0.03 feet vertically.

Errata

520.3.3 Laying Pipe

Correct errata by replacing "sections" with "joints" to clarify the intent that the last 3 joints need ties.

(5) Provide joint ties on the upstream and downstream ends of circular and horizontal elliptical concrete culvert and concrete cattle pass installations. Tie the next 3 pipe joints or, if using apron endwalls, the endwall joint and the last 2 pipe joints. Ties are not required on culverts with masonry endwalls unless the plans show otherwise.

608.3.3 Laying Pipe

Correct errata by replacing "sections" with "joints" to clarify the intent that the last 3 joints need ties.

(5) Provide joint ties on concrete storm sewer system infall and outfall pipes. Tie the last 3 pipe joints or, if using apron endwalls, the endwall joint and the next 2 pipe joints. Ties are not required on installations with masonry endwalls unless the plans show otherwise.

ADDITIONAL SPECIAL PROVISION 7

- A. Reporting 1st Tier and DBE Payments During Construction
 - 1. Comply with reporting requirements specified in the department's Civil Rights Compliance, Contractor's User Manual, Sublets and Payments.
 - 2. Report payments to all DBE firms within 10 calendar days of receipt of a progress payment by the department or a contractor for work performed, materials furnished, or materials stockpiled by a DBE firm. Report the payment as specified in A(1) for all work satisfactorily performed and for all materials furnished or stockpiled.
 - 3. Report payments to all first tier subcontractor relationships within 10 calendar days of receipt of a progress payment by the department for work performed. Report the payment as specified in A(1) for all work satisfactorily performed.
 - 4. All tiers shall report payments as necessary to comply with the DBE payment requirement as specified in A(2).
 - 5. Require all first tier relationships, DBE firms and all other tier relationships necessary to comply with the DBE payment requirement in receipt of a progress payment by contractor to acknowledge receipt of payment as specified in A(1), (2), (3) and (4).
 - 6. All agreements made by a contractor shall include the provisions in A(1), (2), (3), (4) and (5), and shall be binding on all first tier subcontractor relationships and all contractors and subcontractors utilizing DBE firms on the project.
- B. Costs for conforming to this special provision are incidental to the contract.

NOTE: CRCS Prime Contractor payment is currently not automated and will need to be manually loaded into the Civil Rights Compliance System. Copies of prime contractor payments received (check or ACH) will have to be forwarded to paul.ndon@dot.wi.gov within 5 days of payment receipt to be logged manually.

***Additionally, for information on Subcontractor Sublet assignments, Subcontractor Payments and Payment Tracking, please refer to the CRCS Payment and Sublets manual at:

 $\underline{https://wisconsindot.gov/Documents/doing-bus/civil-rights/labornwage/crcs-payments-sublets-\underline{manual.pdf}}$

ADDITIONAL SPECIAL PROVISION 9 Electronic Certified Payroll or Labor Data Submittal

(1) Use the department's Civil Rights Compliance System (CRCS) to electronically submit certified payroll reports for contracts with federal funds and labor data for contracts with state funds only. Details are available online through the department's highway construction contractor information (HCCI) site on the Labor, Wages, and EEO Information page at:

https://wisconsindot.gov/Pages/doing-bus/civil-rights/labornwage/default.aspx

- (2) Ensure that all tiers of subcontractors, including all trucking firms, either submit their weekly certified payroll reports (contracts with federal funds) or labor data (contracts with state funds only) electronically through CRCS. These payrolls or labor data are due within seven calendar days following the close of the payroll period. Every firm providing physical labor towards completing the project is a subcontractor under this special provision.
- (3) Upon receipt of contract execution, promptly make all affected firms aware of the requirements under this special provision and arrange for them to receive CRCS training as they are about to begin their submittals. The department will provide training either in a classroom setting at one of our regional offices or by telephone. Contact Paul Ndon at (414) 438-4584 to schedule the training.
- (4) The department will reject all paper submittals for information required under this special provision. All costs for conforming to this special provision are incidental to the contract.
- (5) Firms wishing to export payroll/labor data from their computer system into CRCS should have their payroll coordinator contact Paul Ndon at paul.ndon@dot.wi.gov. Not every contractor's payroll system is capable of producing export files. For details, see Section 4.8 CPR Auto Submit (Data Mapping) on pages 49-50; 66-71 of the CRCS Payroll Manual at:

https://wisconsindot.gov/Documents/doing-bus/civil-rights/labornwage/crcs-payroll-manual.pdf

Non-discrimination Provisions

During the performance of this contract, the contractor, for itself, its assignees, and successors in interest (hereinafter referred to as the "contractor") agrees as follows:

- **1. Compliance with Regulations:** The contractor (hereinafter includes consultants) will comply with the Acts and the Regulations relative to Non-discrimination in Federally-assisted programs of the U.S. Department of Transportation, Federal Highway Administration, as they may be amended from time to time, which are herein incorporated by reference and made a part of this contract.
- **2. Non-discrimination:** The contractor, with regard to the work performed by it during the contract, will not discriminate on the grounds of race, color, or national origin in the selection and retention of subcontractors, including procurements of materials and leases of equipment. The contractor will not participate directly or indirectly in the discrimination prohibited by the Acts and the Regulations, including employment practices when the contract covers any activity, project, or program set forth in Appendix B of 49 CFR Part 21.
- **3. Solicitations for Subcontracts, Including Procurements of Materials and Equipment:** In all solicitations, either by competitive bidding, or negotiation made by the contractor for work to be performed under a subcontract, including procurements of materials, or leases of equipment, each potential subcontractor or supplier will be notified by the contractor of the contractor's obligations under this contract and the Acts and the Regulations relative to Non-discrimination on the grounds of race, color, or national origin.
- **4. Information and Reports:** The contractor will provide all information and reports required by the Acts, the Regulations, and directives issued pursuant thereto and will permit access to its books, records, accounts, other sources of information, and its facilities as may be determined by the Recipient or the Federal Highway Administration to be pertinent to ascertain compliance with such Acts, Regulations, and instructions. Where any information required of a contractor is in the exclusive possession of another who fails or refuses to furnish the information, the contractor will so certify to the Recipient or the Federal Highway Administration, as appropriate, and will set forth what efforts it has made to obtain the information.
- **5. Sanctions for Noncompliance:** In the event of a contractor's noncompliance with the Non-discrimination provisions of this contract, the Recipient will impose such contract sanctions as it or the Federal Highway Administration may determine to be appropriate, including, but not limited to:
 - a. Withholding payments to the contractor under the contract until the contractor complies; and/or
 - b. Cancelling, terminating, or suspending a contract, in whole or in part.

6. Incorporation of Provisions: The contractor will include the provisions of paragraphs one through six in every subcontract, including procurements of materials and leases of equipment, unless exempt by the Acts, the Regulations and directives issued pursuant thereto. The contractor will take action with respect to any subcontract or procurement as the Recipient or the Federal Highway Administration may direct as a means of enforcing such provisions including sanctions for noncompliance. Provided, that if the contractor becomes involved in, or is threatened with litigation by a subcontractor, or supplier because of such direction, the contractor may request the Recipient to enter into any litigation to protect the interests of the Recipient. In addition, the contractor may request the United States to enter into the litigation to protect the interests of the United States.

During the performance of this contract, the contractor, for itself, its assignees, and successors in interest (hereinafter referred to as the "contractor") agrees to comply with the following non-discrimination statutes and authorities; including but not limited to:

Pertinent Non-Discrimination Authorities:

- Title VI of the Civil Rights Act of 1964 (42 U.S.C. § 2000d et seq., 78 stat. 252), (prohibits discrimination on the basis of race, color, national origin); and 49 CFR Part 21.
- The Uniform Relocation Assistance and Real Property Acquisition Policies Act of 1970, (42 U.S.C. § 4601), (prohibits unfair treatment of persons displaced or whose property has been acquired because of Federal or Federal-aid programs and projects);
- Federal-Aid Highway Act of 1973, (23 U.S.C. § 324 et seq.), (prohibits discrimination on the basis of sex);
- Section 504 of the Rehabilitation Act of 1973, (29 U.S.C. § 794 et seq.), as amended, (prohibits discrimination on the basis of disability); and 49 CFR Part 27;
- The Age Discrimination Act of 1975, as amended, (42 U.S.C. § 6101 et seq.), (prohibits discrimination on the basis of age);
- Airport and Airway Improvement Act of 1982, (49 USC § 471, Section 47123), as amended, (prohibits discrimination based on race, creed, color, national origin, or sex);
- The Civil Rights Restoration Act of 1987, (PL 100-209), (Broadened the scope, coverage and applicability of Title VI of the Civil Rights Act of 1964, The Age Discrimination Act of 1975 and Section 504 of the Rehabilitation Act of 1973, by expanding the definition of the terms "programs or activities" to include all of the programs or activities of the Federal-aid recipients, sub-recipients and contractors, whether such programs or activities are Federally funded or not);
- Titles II and III of the Americans with Disabilities Act, which prohibit discrimination on the basis of disability in the operation of public entities, public and private transportation systems, places of public accommodation, and certain testing entities (42 U.S.C. §§ 12131-12189) as implemented by Department of Transportation regulations at 49 C.F.R. parts 37 and 38;
- The Federal Aviation Administration's Non-discrimination statute (49 U.S.C. § 47123) (prohibits discrimination on the basis of race, color, national origin, and sex);

- Executive Order 12898, Federal Actions to Address Environmental Justice in Minority Populations and Low-Income Populations, which ensures Non-discrimination against minority populations by discouraging programs, policies, and activities with disproportionately high and adverse human health or environmental effects on minority and low-income populations;
- Executive Order 13166, Improving Access to Services for Persons with Limited English Proficiency, and resulting agency guidance, national origin discrimination includes discrimination because of Limited English proficiency (LEP). To ensure compliance with Title VI, you must take reasonable steps to ensure that LEP persons have meaningful access to your programs (70 Fed. Reg. at 74087 to 74100);
- Title IX of the Education Amendments of 1972, as amended, which prohibits you from discriminating because of sex in education programs or activities (20 U.S.C. 1681 et seq).

Effective August 2015 letting

BUY AMERICA PROVISION

All steel and iron materials permanently incorporated in this project shall be domestic products and all manufacturing and coating processes for these materials from smelting forward in the manufacturing process must have occurred within the United States. Coating includes epoxy coating, galvanizing, painting and any other coating that protects or enhances the value of a material subject to the requirements of Buy America. The exemption of this requirement is the minimal use of foreign materials if the total cost of such material permanently incorporated in the product does not exceed one-tenth of one percent (1/10 of 1%) of the total contract cost or \$2,500.00, whichever is greater. For purposes of this paragraph, the cost is that shown to be the value of the subject products as they are delivered to the project. The contractor shall take actions and provide documentation conforming to CMM 2-28.5 to ensure compliance with this "Buy America" provision.

https://wisconsindot.gov/rdwy/cmm/cm-02-28.pdf

Upon completion of the project certify to the engineer, in writing using department form WS4567, that all steel, iron, and coating processes for steel or iron incorporated into the contract work conform to these "Buy America" provisions. Attach a list of exemptions and their associated costs to the certification form. Department form WS4567 is available at:

https://wisconsindot.gov/hcciDocs/contracting-info/ws4567.doc

1 of 1





Page 1 of 6

Proposal ID: 20190312060 Project(s): 7650-01-62

Federal ID(s): N/A

SECTION: 0001 Contract Items

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0002	201.0105 Clearing	53.000 STA	·	<u> </u>
0004	201.0205 Grubbing	53.000 STA		<u> </u>
0006	203.0100 Removing Small Pipe Culverts	1.000 EACH		
8000	204.0100 Removing Pavement	84.000 SY		
0010	204.0115 Removing Asphaltic Surface Butt Joints	4,170.000 SY		
0012	204.0120 Removing Asphaltic Surface Milling	302,000.000 SY	<u> </u>	
0014	204.0180 Removing Delineators and Markers	115.000 EACH	<u> </u>	<u> </u>
0016	204.9060.S Removing (item description) 01. Apron Endwalls	4.000 EACH		
0018	205.0100 Excavation Common	100.000 CY	·	<u></u>
0020	208.0100 Borrow	400.000 CY	·	<u></u>
0022	211.0100 Prepare Foundation for Asphaltic Paving (project) 01. 7650-01-62	LS	LUMP SUM	·
0024	213.0100 Finishing Roadway (project) 01. 7650- 01-62	1.000 EACH		
0026	305.0110 Base Aggregate Dense 3/4-Inch	3,590.000 TON		<u> </u>
0028	305.0500 Shaping Shoulders	1,610.000 STA		<u></u>
0030	455.0605 Tack Coat	38,230.000 GAL		
0032	460.0105.S HMA Percent Within Limits (PWL) Test Strip Volumetrics	1.000 EACH	·	·





Page 2 of 6

Proposal ID: 20190312060 Project(s): 7650-01-62

Federal ID(s): N/A

SECTION: 0001 Contract Items

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0034	460.0110.S HMA Percent Within Limits (PWL) Test Strip Density	2.000 EACH	.	<u> </u>
0036	460.2005 Incentive Density PWL HMA Pavement	39,140.000 DOL	1.00000	39,140.00
0038	460.2010 Incentive Air Voids HMA Pavement	57,380.000 DOL	1.00000	57,380.00
0040	460.4110.S Reheating HMA Pavement Longitudinal Joints	80,403.000 LF		<u>-</u>
0042	460.6225 HMA Pavement 5 MT 58-28 S	57,375.000 TON	·	·
0044	465.0110 Asphaltic Surface Patching	100.000 TON	·	·
0046	465.0120 Asphaltic Surface Driveways and Field Entrances	170.000 TON		·
0048	465.0425 Asphaltic Shoulder Rumble Strips 2-Lane Rural	148,816.000 LF		
0050	465.0450 Asphaltic Intersection Rumble Strips	84.000 SY		·
0052	465.0475 Asphalt Centerline Rumble Strips 2-Lane Rural	69,363.000 LF		<u>-</u>
0054	520.1024 Apron Endwalls for Culvert Pipe 24-Inch	2.000 EACH	·	
0056	520.1036 Apron Endwalls for Culvert Pipe 36-Inch	1.000 EACH		
0058	520.1048 Apron Endwalls for Culvert Pipe 48-Inch	1.000 EACH		
0060	520.8700 Cleaning Culvert Pipes	17.000 EACH	<u> </u>	
0062	521.3124 Culvert Pipe Corrugated Steel 24-Inch	6.000 LF		·





Page 3 of 6

Proposal ID: 20190312060 Project(s): 7650-01-62

Federal ID(s): N/A

SECTION: 0001 Contract Items

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0064	524.0636 Apron Endwalls for Culvert Pipe Salvaged 36-Inch	1.000 EACH	·	·
0066	606.0200 Riprap Medium	56.000 CY		
0068	606.0600 Grouted Riprap Medium	10.000 CY		<u> </u>
0070	611.8115 Adjusting Inlet Covers	4.000 EACH	<u> </u>	
0072	611.9800.S Pipe Grates	2.000 EACH		
0074	614.0010 Barrier System Grading Shaping Finishing	42.000 EACH	·	·
0076	614.0370 Steel Plate Beam Guard Energy Absorbing Terminal	4.000 EACH	·	
0078	614.0396 Guardrail Mow Strip Asphalt	4,830.000 SY	<u> </u>	
0800	614.0920 Salvaged Rail	13,871.000 LF	<u> </u>	·
0082	614.2300 MGS Guardrail 3	1,909.400 LF	<u></u>	<u> </u>
0084	614.2330 MGS Guardrail 3 K	9,862.500 LF		
0086	614.2340 MGS Guardrail 3 L	225.000 LF	<u> </u>	
0088	614.2350 MGS Guardrail Short Radius	150.000 LF		
0090	614.2500 MGS Thrie Beam Transition	157.600 LF		
0092	614.2610 MGS Guardrail Terminal EAT	35.000 EACH		
0094	614.2630 MGS Guardrail Short Radius Terminal	3.000 EACH		





Page 4 of 6


Proposal ID: 20190312060 Project(s): 7650-01-62

Federal ID(s): N/A

SECTION: 0001 Contract Items

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0096	618.0100 Maintenance And Repair of Haul Roads (project) 01. 7650-01-62	1.000 EACH	·	·
0098	619.1000 Mobilization	1.000 EACH	·	<u> </u>
0100	624.0100 Water	35.000 MGAL		
0102	625.0500 Salvaged Topsoil	3,500.000 SY	·	
0104	627.0200 Mulching	2,000.000 SY		
0106	628.1504 Silt Fence	10,000.000 LF	·	
0108	628.1520 Silt Fence Maintenance	10,000.000 LF	·	
0110	628.1905 Mobilizations Erosion Control	4.000 EACH	·	
0112	628.1910 Mobilizations Emergency Erosion Control	4.000 EACH		
0114	628.2008 Erosion Mat Urban Class I Type B	3,900.000 SY	·	·
0116	628.7005 Inlet Protection Type A	4.000 EACH		·
0118	628.7015 Inlet Protection Type C	4.000 EACH	·	·
0120	628.7504 Temporary Ditch Checks	500.000 LF	·	
0122	628.7570 Rock Bags	60.000 EACH	·	·
0124	629.0210 Fertilizer Type B	60.000 CWT		
0126	630.0120 Seeding Mixture No. 20	2,510.000 LB	<u> </u>	·







Page 5 of 6

Proposal ID: 20190312060 Project(s): 7650-01-62

Federal ID(s): N/A

SECTION: 0001 Contract Items

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0128	630.0200 Seeding Temporary	2,510.000 LB	·	<u> </u>
0130	633.5200 Markers Culvert End	116.000 EACH		·
0132	642.5001 Field Office Type B	1.000 EACH		
0134	643.0300 Traffic Control Drums	2,500.000 DAY		
0136	643.0310.S Temporary Portable Rumble Strips	1.000 LS		
0138	643.0900 Traffic Control Signs	9,660.000 DAY	·	<u> </u>
0140	643.5000 Traffic Control	1.000 EACH		
0142	646.1020 Marking Line Epoxy 4-Inch	264,693.000 LF		
0144	646.3020 Marking Line Epoxy 8-Inch	2,285.000 LF		
0146	646.4520 Marking Line Same Day Epoxy 4-Inch	107,250.000 LF	·	
0148	646.5020 Marking Arrow Epoxy	1.000 EACH		
0150	646.5120 Marking Word Epoxy	1.000 EACH	·	
0152	646.7120 Marking Diagonal Epoxy 12-Inch	880.000 LF		
0154	646.8220 Marking Island Nose Epoxy	1.000 EACH	<u> </u>	
0156	648.0100 Locating No-Passing Zones	15.260 MI		
0158	649.0105 Temporary Marking Line Paint 4-Inch	40,080.000 LF	<u> </u>	
0160	650.6000 Construction Staking Pipe Culverts	5.000 EACH	<u> </u>	





Page 6 of 6

Proposal ID: 20190312060 Project(s): 7650-01-62

Federal ID(s): N/A

SECTION: 0001 Contract Items

Proposal Line Number	ltem ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0162	650.8000 Construction Staking Resurfacing Reference	80,560.000 LF		
0164	650.9910 Construction Staking Supplemental Control (project) 01. 7650-01-62	LS	LUMP SUM	
0166	690.0150 Sawing Asphalt	2,250.000 LF	<u></u>	·
0168	740.0440 Incentive IRI Ride	60,911.000 DOL	1.00000	60,911.00
0170	SPV.0090 Special 01. Cleaning Ditch	450.000 LF		
0172	SPV.0105 Special 01. Reconstructing Stone Headwall	LS	LUMP SUM	·
0174	SPV.0105 Special 02. Material Transfer Vehicle	LS	LUMP SUM	
0176	SPV.0105 Special 03. Milling and Removing Temporary Joint	LS	LUMP SUM	·
0178	SPV.0105 Special 04. Reconstructing Concrete Block Retaining Wall Cap	LS	LUMP SUM	·
	Section:	0001	Total:	·
			Total Bid:	·

PLEASE ATTACH SCHEDULE OF ITEMS HERE



Wisconsin Department of Transportation

February 26, 2019

Division of Transportation Systems Development

Bureau of Project Development 4822 Madison Yards Way, 4th Floor South Madison, WI 53705

Telephone: (608) 266-1631 Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

Proposal #60: 7650-01-62

Hager City - Prescott USH 63 to Coulee Creek

STH 35

Pierce County

Letting of March 12, 2019

This is Addendum No. 01, which provides for the following:

Special Provisions:

	Revised Special Provisions				
Article No.		Description			
3	Prosecution and Progress				

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist Proposal Management Section

ADDENDUM NO. 01 7650-01-62 February 26, 2019

Special Provisions

3. Prosecution and Progress

Replace paragraph five with the following:

Surface milling and placement of the lower layer of pavement must occur in the same calendar day at any given location except within the full depth milling area in the Town of Diamond Bluff unless approved by the engineer. Placement of the lower layer of pavement in the full depth milling area in the Town of Diamond Bluff must occur within 72 hours of milling operations unless approved by the engineer. Placement of the upper layer of pavement must occur within 14 calendar days of the lower layer of pavement unless approved by the engineer. Do not remove side road butt joint transitions until 24 hours prior to side road paving.

END OF ADDENDUM



Wisconsin Department of Transportation

Division of Transportation Systems Development

Bureau of Project Development 4822 Madison Yards Way, 4th Floor South Madison, WI 53705

Telephone: (608) 266-1631 Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

Proposal #60: 7650-01-62

Hager City - Prescott USH 63 to Coulee Creek

STH 35

Pierce County

Letting of March 12, 2019

This is Addendum No. 02, which provides for the following:

Schedule of Items:

	Revised Bid Item Quantities					
Bid Item	Item Description		Old	Revised	Proposal	
Did itelli			Quantity	Quantity	Total	
460.0110.S	HMA Percent Within Limits (PWL) Test Strip Density	EACH	2	-1	1	
460.2005	Incentive Density PWL HMA Pavement	DOL	39,140	-18,000	21,140	
460.4110.S	Reheating HMA Pavement Longitudinal Joints	LF	80,403	80,403	160,806	

Plan Sheets:

	Revised Plan Sheets
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
25	Miscellaneous Quantities

Schedule of Items

Attached, dated March 4, 2019, are the revised Schedule of Items Page 2.

Plan Sheets

The following $8\frac{1}{2}$ x 11-inch sheets are attached and made part of the plans for this proposal:

Revised: Miscellaneous Quantities sheet 25

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist Proposal Management Section

END OF ADDENDUM

Addendum No. 02 ID 7650-01-62 **Revised Sheet 25** March 4, 2019

ı		
	4	
	,	
	5	
	Ξ	
	3	

NOTE: TACK COAT REQUIRED PRIOR TO PAVING OVEN MILED SURFACE. CALEBURNONS BASED ON APPLICATION RATE OF 0.06 GALSY. HIMA PAVEMENT WEIGHT CALCULATIONS BASED ON UNIT WEIGHT OF 1.12 LB/SY/INCH.

160806

38230

ITEM TOTALS

FOR S.E. CORRECTION FOR SIDEROADS FOR PATCHING FOR DRIVEWAYS

- 170 170

100 100

B-47-0042 1.75" OVERLAY

111080 8980 2380 21000 35 11860 1590 450

32220 27366 6400 60242 180 34398

7300 5930 730 13850 30 7820 2270 300

LT & RT LT & RT

STH 35 101-66 - 262-60 264-17 - 401-00 401-60 - 433-60 433-60 - 734-21 734-21 - 736-11 735-11 - 907-10 UNDI STRIBUTED UNDISTRIBUTED UNDISTRIBUTED UNDISTRIBUTED

REMARKS

466.4110.5
REHEATING
HIMA
SPHALTIC
BALGE
PACHEMENT
HIMA
ASPHALTIC
DIVENTEDMA
SURFACE
JOINT SHT SE48S
TON
TON
TON
A65.0120
A65.012

460.0110.S
HMA
PERCENT
WITHIN
LIMITS
(PWL)
TEST STRIP I
DENSITY
EACH

460.0105.S HMA PERCENT WITHIN LIMITS (PWL) TEST STRIPS VOLUMETRICS EACH

LOCATION

ASPHALTIC PAVEMENT

								Ļ	
NOTATION	NOITATA	MIXTIBELISE	INDERI VING SUBEACE	NIT I UN	NOL	TONS THICKNESS	QUALITY MANAGEMEN	T PR	QUALITY MANAGEMENT PROGRAM TO BE USED FOR:
101100		MIN I ONE OSE	ONDERE IIING SOLVI ACE	DIO II CIM	2	CONVEGO	MIXTURE ACCEPTANCE	<u> </u>	DENSITY ACCEPTANCE
VARIOUS		PATCHING	BASE AGGREGATE	ASPHALTIC SURFACE	100	2.25"	QMP AS PER 465	▼	ACCEPTANCE BY ORDINARY COMPACTION
SIVING LANES	12' DRIVING LANES 101+50 - 907+10	LOWER LAYER*	MILLED EXISTING HMA SURFACE	5 MT 58-34 S	18,790	1.5"	PWL INCENTIVE AIR VOIDS HMA PAVEMENT 460.2070		ACCEPTANCE BY ORDINARY COMPACTION
4-6' SHOULDERS	101+50 - 907+10	LOWER LAYER*	MILLED EXISTING HMA SURFACE	5 MT 58-34 S	8,340	1.5"	PWL INCENTIVE AIR VOIDS HMA PAVEMENT 460.2070		ACCEPTANCE TESTING BY THE DEPARTMENT; NOT ELIGIBLE FOR INCENTIVE
SIDEROADS	101+50 - 907+10	LOWER LAYER	MILLED EXISTING HMA SURFACE	5 MT 58-34 S	210	1.5"	PWL INCENTIVE AIR VOIDS HMA PAVEMENT 460.20		ACCEPTANCE TESTING BY THE DEPARTMENT; NOT ELIGIBLE FOR INCENTIVE
NIVING LANES	12' DRIVING LANES 101+50 - 907+10	UPPER LAYER	5 MT 58-25 S HMA PAVEMENT	5 MT 58-34 S	21,140	1.75"	PWL INCENTIVE AIR VOIDS HMA PAVEMENT 460.20	NS &	INCENTIVE DENSITY PWL HMA PAVEMENT 460.2005
4-6' SHOULDERS	101+50-907+10	UPPER LAYER	5 MT 58-25 S HMA PAVEMENT	5 MT 58-34 S	8,655	1.75"	PWL INCENTIVE AIR VONS HMA PAVEMENT 460.20		ACCEPTANCE TESTING BY THE DEPARTMENT; NOT ELIGIBLE FOR INCENTIVE
SIDEROADS	101+50-907+10	UPPER LAYER	5 MT 58-25 S HMA PAVEMENT	5 MT 58-34 S	240	1.75"	PWL INCENTIVE AIR VOIDS HMA PAVEMENT 460.2000		ACCEPTANCE TESTING BY THE DEPARTMENT; NOT ELIGIBLE FOR INCENTIVE

*INCLUDES SE CORRECTION PLACED WITH LOWER LAYER

HWY: STH 35

7650-01-62

PROJECT NO:

COUNTY: PIERCE

MISCELLANEOUS QUANTITIES

22

SHEET

NOTE: ALL ITEMS AND QUANTITIES ON THIS SHEET ARE FOR ENGINEER ESTIMATE CATEGORY 0010 UNLESS OTHERWISE NOTED



03/04/2019 10:35:30



Proposal Schedule of Items

Page 2 of 6

Proposal ID: 20190312060 Project(s): 7650-01-62

Federal ID(s): N/A

SECTION: 0001 Contract Items

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0034	460.0110.S HMA Percent Within Limits (PWL) Test Strip Density	1.000 EACH	·	·
0036	460.2005 Incentive Density PWL HMA Pavement	21,140.000 DOL	1.00000	21,140.00
0038	460.2010 Incentive Air Voids HMA Pavement	57,380.000 DOL	1.00000	57,380.00
0040	460.4110.S Reheating HMA Pavement Longitudinal Joints	160,806.000 LF		·
0042	460.6225 HMA Pavement 5 MT 58-28 S	57,375.000 TON	·	
0044	465.0110 Asphaltic Surface Patching	100.000 TON	·	
0046	465.0120 Asphaltic Surface Driveways and Field Entrances	170.000 TON	·	·
0048	465.0425 Asphaltic Shoulder Rumble Strips 2-Lane Rural	148,816.000 LF	·	·
0050	465.0450 Asphaltic Intersection Rumble Strips	84.000 SY		<u> </u>
0052	465.0475 Asphalt Centerline Rumble Strips 2-Lane Rural	69,363.000 LF		·
0054	520.1024 Apron Endwalls for Culvert Pipe 24-Inch	2.000 EACH	·	
0056	520.1036 Apron Endwalls for Culvert Pipe 36-Inch	1.000 EACH	<u> </u>	
0058	520.1048 Apron Endwalls for Culvert Pipe 48-Inch	1.000 EACH		
0060	520.8700 Cleaning Culvert Pipes	17.000 EACH	<u></u>	
0062	521.3124 Culvert Pipe Corrugated Steel 24-Inch	6.000 LF		



Wisconsin Department of Transportation

March 6, 2019

Division of Transportation Systems Development

Bureau of Project Development 4822 Madison Yards Way, 4th Floor South Madison, WI 53705

Telephone: (608) 266-1631 Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

Proposal #60: 7650-01-62

Hager City - Prescott USH 63 to Coulee Creek

STH 35

Pierce County

Letting of March 12, 2019

This is Addendum No. 03, which provides for the following:

Schedule of Items:

	Revised Bid Item Quant	ities			
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
649.0105	Temporary Marking Line Paint 4-inch	Ŀ	40,080	-20,040	20,040

Plan Sheets:

	Revised Plan Sheets
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
26	Miscellaneous Quantities (Added existing pipe size and material.)
30	Miscellaneous Quantities (revised 649.0105 quantity)

Schedule of Items

Attached, dated March 6, 2019, are the revised Schedule of Items Page 5.

Plan Sheets

The following $8\frac{1}{2}$ x 11-inch sheets are attached and made part of the plans for this proposal: Revised: 26 and 30.

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist Proposal Management Section

END OF ADDENDUM


		$\sim \sim \sim$	~~	~~	\sim	\sim	\sim	\sim	~	~~~	~~~	\sim	~~	~~	~~~	~~~	~~~	\sim	Ľ
	LD VERIFIED **EXISTING PIPE	CMP CMP CMP	CMP CMP CMP	CMP	CMP	CMP	CMP CMP n/a	CMP	CMP CMP	CMP	O O O O O	CMP	CMP	O O O O	C C C C C C C C C C C C C C C C C C C	CMP CMP CMP	CMP CMP CMP	CMP CMP CMP EFOR MISE NOTED	
	OULD BE FIELD "EXISTING PIPE SIZE SIZE SIZE SIZE SIZE SIZE SIZE SIZ	(INCRES) 42" 60" 60"	36"	24"	30"	30"	30" 18" n/a	24" 48" 24"	18" 24"	24" 30"	30" 30" 72" 72" 72" 72" 72" 72" 72" 72" 72" 72	30"	24"	8 8 8 8 80 8 8 8	30" 30" 24" 24"	24" 72" 120" 36"	30" 30" 272" 24"	36" 48" 48" HIS SHEET AR NLESS OTHER	SC THEFT
dendum N 7650-01-6 vised She rch 6, 201	No. 03 52 set 26		NEW AEW RT, PIPE GRATE RT, CLEANING DITCHRIT REPLACE 6: END SECTION ONLY RT. CLEANING DITCHLT & RT		CLEANING DITCH RT NEW AEW RT	CLEANING DITCH RT DRIVEWAY CULVERT RT	DRIVEWAY CULVERT RT CLEANING DITCH RT	CLEANING DITCHLT CLEANING DITCHLT	CLEANING DITCH LT NEW AEW RT	CLEANING DITCH RT	CLEANING DITCHRT 48" CMP 30" CMP 30" CMP 30" CMP 77" CMP 72" C	CLEANING DITCHRT	NEW AEW RT CLEANING DITCH LT	CLEANING DITCH RT CLEANING DITCH IT & RT	CLEANING DITCH LT	SALVAGE & REINSTALL AEW LT		NOTE: ALL ITEMS AND QUANTITIES ON ENGINER ESTIMATE CATEGORY VODIO U	
	SPV.0105.01 RECONSTRUCTING STONE HEADWALL	3							1 1 1										
	SPV.0090.07 CLEANING	5	25 - 50	8 ' ' 8		25	25	25 25	25	25	25	25	- 25	 25 50	25 25			450	MISCELL ANEOLIS OLIANTITIES
	650.6000 CONSTRUCTION STAKING STAKING PIPE CULVERTS	ביין		- , ,									F 1					Ko	MAISCELLANE
	ES 533.5200 MARKERS VULVERT END	2 2 2 2	0000	100	000	. 20	- 1 1	- 2 -	0 0 0	- 000	00000	1000	0 0 0	0 0 0 0 0	00000	00000	00000	2 2 2 1	
	CULVERT PIPES 36 11.15 11.15 12.16 13.17 14.17 15.17 16.17 1																	2	
	524.0836 APRON T ENDWALLS FOR CULVERT FOR SALVAGED SALVAGED	1 1 1	1 1 1						1 1 1							11 -			. DIEBCE
	521.3124 CULVER PIPE CORRUGA STEEL 24-INCH		1 1 1 0				1 1 1		1 1 1		1 1 1 1 1							ω	Ι.
	S 520.8700 RT CLEANING CULVERT	,	1 1 1 1	. ←			1	- 1 1				+			111		—	1	\vdash
	520.1048 APRON ENDWALLS T FOR CULVERT OF PIPE FASHINCH										1 1 1 1 1							-	
	520,1036 APRON ENDWALLS FOR CULVERT PIPE 35-INCH						1 1 1												. 20
	520.1024 APRON ENDWALLS OR CULVERT PIPE 24-INCH	- · · · ·	1 1 1 1										- 1						HWVV. CTH 25
	204.0180 204.9080.S PERMOVING 204.9080.S PELINEATORS REMOVING FRAND AND AND AND AND AND AND AND AND AND												- 1					4	
	204.0180 REMOVING DELINEATOR: AND MARKERS	2 2 2 2	0000	100	0 0 - 1	- 2 5	- ' ' '	- 2 -	0 0 0	- 000	00000	000	2 2 2	0 0 0 0 0	00000	00000	00000	2 2 115	
	203.0100 REMOVING SMALL SIPE CULVERTS										1 1 1 1 1		1 1					-	7650-01-62
	G G	STH 35 101+36 110+31 126+13 126+25	142+16 199+73 219+67 225+47	274+26	292+57 323+75 335+35	347+41 358+72 365+00	397+41 397+80 398+00 - 399+00	409+36 419+33 423+32	429+15 433+07 435+41	439+62 453+34 466+92 484+83	186+79 194+79 198+61 504+95 508+97 508+11	513+57 518+66 548+64	558+96 564+01	578+17 586+51 590+86 599+12 626+14	645+11 659+72 670+70 681-99 687+38	593+30 700+76 721+14 750+14 753+90	785+28 792+88 811+54 816+98 840+92	855+89 865+96 891+86 ITEM TOTALS	PROJECT NO.

က

	က			
			Addendum No. 03 ID 7650-01-62 Revised Sheet 30 March 6, 2019	S ON THIS SHEET ARE FOR 010 UNLESS OTHERWISE NOTED
SAWING 690,0150 ASPHALT TION LF REMARKS	RT 46 BEGIN PROJECT RT 34 END PROJECT RT 2170 DRIVEWAYS & SIDEROADS 2250	MATERIAL TRANSFER VEHICLE STATION LS STH 35 101+50-907+10 1 TEM TOTALS 1	MILLING AND REMOVING TEMPORARY JOINT SPV 0105 03 LS H 35 H 750 - 807+10 1 M TOTALS 1	RECONSTRUCTING CONCRETE BLOCK RETAINING WALL CAP SPV.0105.04 LS STATION LS 408-68 - 410-75 TEM TOTALS NOTE: ALL ITEMS AND QUANITHES ON THIS SHEET ARE FOR ENGINEER ESTIMATE CATEGORY 0010 UNLESS OTHERWISE NOTED
STATION LOCATION STH 36	101+50 LT.8.RT 907+10 LT.8.RT UNDISTRIBUTED LT.8.RT ITEMTOTALS	MATERIAL T STATION STH 35 101+50 - 907+ ITEM TOTALS	MILLING AND STATION STH 36 101+50-907+10 ITEM TOTALS	STATION STH 35 408+65 - 410+75 ITEM TOTALS
	REMARKS YELLOW, VARIES SOLID WHITE, CHANNELIZING SOLID WHITE, CHANNELIZING SOLID WHITE, CHANNELIZING	SOLID WHITE, CHANNELIZING		
649.0105 TEMPORARY MARKING LINE	4-INCH LF 20040	20040		
646.8220 MARKING ISLAND NOSE	EACH			650.9910 SUPPLEMENTAL CONTROL (7650.01-62) LS
7120 RKING SONAL	12-INCH LF 	600	12 ZONES 648.0100 M 15.26 15.26	KINIG 600 SUPI CINIG CI NOE (76
	EACH		LOCATING NO-PASSING ZONES ON LOCATION M 1 0 - 907+10 LT & RT 15.2 OTALS 15.2	CONSTRUCTION STAKING 650 8000 RESURFACING REFERENCE LOCATION LF 80560 LT & RT 80560
646.5020 6 MARKING MARKING ARROW			LOCATING N STATION L 101+50-907+10 ITEM TOTALS	
646.4520 MARKING LINE SAME DAY EPOXY			LOCAT STATION STH 35 101+50-907+ ITEM TOTALS	STATION STH 35 101+50 - 907+10 ITEM TOTALS
646.3020 MARKING LINE EPOXY	8-INCH LF - 160 250 220	325 200 1180 1110 140 140 150 150 150 150 150 150 200 200 200 200 200 200 200 200		STATION STH 35 101+50- ITEM TOT
646.1020 MARKING LINE EPOXY		138		
	LOCATION - LT & RT LT RT LT	7		
	STATION LOO STH 35 101+50 - 907+10 101+50 - 907+10 101+50 - 103+10 127+20 - 128+70 131+00 - 133+20	16+60 - 162+0 16+60 - 162+0 24+80 - 243+80 24+80 - 243+80 27+80 - 243+80 27+40 - 280+80 406+70 - 410+70 637+60 - 639+00 638+00 - 642+30 642+80 - 644+30 644+15 646+70 - 652+50 686+70		

က







Page 5 of 6

Proposal ID: 20190312060 Project(s): 7650-01-62

Federal ID(s): N/A

SECTION: 0001 Contract Items

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0128	630.0200 Seeding Temporary	2,510.000 LB		
0130	633.5200 Markers Culvert End	116.000 EACH	·	
0132	642.5001 Field Office Type B	1.000 EACH	<u>-</u>	
0134	643.0300 Traffic Control Drums	2,500.000 DAY		
0136	643.0310.S Temporary Portable Rumble Strips	1.000 LS	<u> </u>	
0138	643.0900 Traffic Control Signs	9,660.000 DAY	<u> </u>	
0140	643.5000 Traffic Control	1.000 EACH	<u></u>	
0142	646.1020 Marking Line Epoxy 4-Inch	264,693.000 LF		
0144	646.3020 Marking Line Epoxy 8-Inch	2,285.000 LF		
0146	646.4520 Marking Line Same Day Epoxy 4-Inch	107,250.000 LF	<u> </u>	
0148	646.5020 Marking Arrow Epoxy	1.000 EACH		
0150	646.5120 Marking Word Epoxy	1.000 EACH	<u> </u>	
0152	646.7120 Marking Diagonal Epoxy 12-Inch	880.000 LF		
0154	646.8220 Marking Island Nose Epoxy	1.000 EACH		
0156	648.0100 Locating No-Passing Zones	15.260 MI	<u> </u>	
0158	649.0105 Temporary Marking Line Paint 4-Inch	20,040.000 LF	<u> </u>	
0160	650.6000 Construction Staking Pipe Culverts	5.000 EACH	<u> </u>	