

HIGHWAY WORK PROPOSAL

Wisconsin Department of Transportation
06/2017 s.66.0901(7) Wis. Stats

Proposal Number: **016**

<u>COUNTY</u>	<u>STATE PROJECT</u>	<u>FEDERAL</u>	<u>PROJECT DESCRIPTION</u>	<u>HIGHWAY</u>
Milwaukee	1100-25-80	N/A	Zoo Freeway; Center St Bridge B-40-880	IH 041

ADDENDUM REQUIRED ATTACHED AT BACK

This proposal, submitted by the undersigned bidder to the Wisconsin Department of Transportation, is in accordance with the advertised request for proposals. The bidder is to furnish and deliver all materials, and to perform all work for the improvement of the designated project in the time specified, in accordance with the appended Proposal Requirements and Conditions.

Proposal Guaranty Required: \$20,000.00 Payable to: Wisconsin Department of Transportation	Attach Proposal Guaranty on back of this PAGE.
Bid Submittal Date: May 14, 2019 Time (Local Time): 9:00 am	Firm Name, Address, City, State, Zip Code
Contract Completion Time August 29, 2019	SAMPLE NOT FOR BIDDING PURPOSES
Assigned Disadvantaged Business Enterprise Goal 0%	This contract is exempt from federal oversight.

This certifies that the undersigned bidder, duly sworn, is an authorized representative of the firm named above; that the bidder has examined and carefully prepared the bid from the plans, Highway Work Proposal, and all addenda, and has checked the same in detail before submitting this proposal or bid; and that the bidder or agents, officer, or employees have not, either directly or indirectly, entered into any agreement, participated in any collusion, or otherwise taken any action in restraint of free competitive bidding in connection with this proposal bid.

Do not sign, notarize, or submit this Highway Work Proposal when submitting an electronic bid on the Internet.

Subscribed and sworn to before me this date _____

(Signature, Notary Public, State of Wisconsin)

(Bidder Signature)

(Print or Type Name, Notary Public, State Wisconsin)

(Print or Type Bidder Name)

(Date Commission Expires)

(Bidder Title)

Notary Seal

Type of Work: Removals, excavation, concrete curb & gutter, fencing, pavement marking, signing, lighting, Structure B-40-880	For Department Use Only
Notice of Award Dated	Date Guaranty Returned

**PLEASE ATTACH
PROPOSAL GUARANTY HERE**

Effective with November 2007 Letting

PROPOSAL REQUIREMENTS AND CONDITIONS

The bidder, signing and submitting this proposal, agrees and declares as a condition thereof, to be bound by the following conditions and requirements.

If the bidder has a corporate relationship with the proposal design engineering company, the bidder declares that it did not obtain any facts, data, or other information related to this proposal from the design engineering company that was not available to all bidders.

The bidder declares that they have carefully examined the site of, and the proposal, plans, specifications and contract forms for the work contemplated, and it is assumed that the bidder has investigated and is satisfied as to the conditions to be encountered, as to the character, quality, and quantities of work to be performed and materials to be furnished, and as to the requirements of the specifications, special provisions and contract. It is mutually agreed that submission of a proposal shall be considered conclusive evidence that the bidder has made such examination.

The bidder submits herewith a proposal guaranty in proper form and amount payable to the party as designated in the advertisement inviting proposals, to be retained by and become the property of the owner of the work in the event the undersigned shall fail to execute the contract and contract bond and return the same to the office of the engineer within fourteen (14) days after having been notified in writing to do so; otherwise to be returned.

The bidder declares that they understand that the estimate of quantities in the attached schedule is approximate only and that the attached quantities may be greater or less in accordance with the specifications.

The bidder agrees to perform the said work, for and in consideration of the payment of the amount becoming due on account of work performed, according to the unit prices bid in the following schedule, and to accept such amounts in full payment of said work.

The bidder declares that all of the said work will be performed at their own proper cost and expense, that they will furnish all necessary materials, labor, tools, machinery, apparatus, and other means of construction in the manner provided in the applicable specifications and the approved plans for the work together with all standard and special designs that may be designed on such plans, and the special provisions in the contract of which this proposal will become a part, if and when accepted. The bidder further agrees that the applicable specifications and all plans and working drawings are made a part hereof, as fully and completely as if attached hereto.

The bidder, if awarded the contract, agrees to begin the work not later than ten (10) days after the date of written notification from the engineer to do so, unless otherwise stipulated in the special provisions.

The bidder declares that if they are awarded the contract, they will execute the contract agreement and begin and complete the work within the time named herein, and they will file a good and sufficient surety bond for the amount of the contract for performance and also for the full amount of the contract for payment.

The bidder, if awarded the contract, shall pay all claims as required by Section 779.14, Statutes of Wisconsin, and shall be subject to and discharge all liabilities for injuries pursuant to Chapter 102 of the Statutes of Wisconsin, and all acts amendatory thereto. They shall further be responsible for any damages to property or injury to persons occurring through their own negligence or that of their employees or agents, incident to the performance of work under this contract, pursuant to the Standard Specifications for Road and Bridge Construction applicable to this contract.

In connection with the performance of work under this contract, the contractor agrees to comply with all applicable state and federal statutes relating to non-discrimination in employment. No otherwise qualified person shall be excluded from employment or otherwise be subject to discrimination in employment in any manner on the basis of age, race, religion, color, gender, national origin or ancestry, disability, arrest or conviction record (in keeping with s.111.32), sexual orientation, marital status, membership in the military reserve, honesty testing, genetic testing, and outside use of lawful products. This provision shall include, but not be limited to the following: employment, upgrading, demotion or transfer; recruitment or recruitment advertising; layoff or termination; rates of pay or other forms of compensation, and selection for training, including apprenticeship. The contractor further agrees to ensure equal opportunity in employment to all applicants and employees and to take affirmative action to attain a representative workforce.

The contractor agrees to post notices and posters setting forth the provisions of the nondiscrimination clause, in a conspicuous and easily accessible place, available for employees and applicants for employment.

If a state public official (section 19.42, Stats.) or an organization in which a state public official holds at least a 10% interest is a party to this agreement, this contract is voidable by the state unless appropriate disclosure is made to the State of Wisconsin Ethics Board.

Effective with August 2015 Letting

BID PREPARATION

Preparing the Proposal Schedule of Items

A General

- (1) Obtain bidding proposals as specified in section 102 of the standard specifications prior to 11:45 AM of the last business day preceding the letting. Submit bidding proposals using one of the following methods:
 1. Electronic bid on the internet.
 2. Electronic bid on a printout with accompanying diskette or CD ROM.
 3. Paper bid under a waiver of the electronic submittal requirements.
- (2) Bids submitted on a printout with accompanying diskette or CD ROM or paper bids submitted under a waiver of the electronic submittal requirements govern over bids submitted on the internet.

- (3) The department will provide bidding information through the department's web site at:
<https://wisconsindot.gov/Pages/doing-bus/contractors/hcci/bid-let.aspx>

The contractor is responsible for reviewing this web site for general notices as well as information regarding proposals in each letting. The department will also post special notices of all addenda to each proposal through this web site no later than 4:00 PM local time on the Thursday before the letting. Check the department's web site after 5:00 PM local time on the Thursday before the letting to ensure all addenda have been accounted for before preparing the bid. When bidding using methods 1 and 2 above, check the Bid Express™ on-line bidding exchange at <http://www.bidx.com/> after 5:00 PM local time on the Thursday before the letting to ensure that the latest schedule of items Expedite file (*.ebs or *.00x) is used to submit the final bid.

- (4) Interested parties can subscribe to the Bid Express™ on-line bidding exchange by following the instructions provided at the www.bidx.com web site or by contacting:

Info Tech Inc.
5700 SW 34th Street, Suite 1235
Gainesville, FL 32608-5371
email: <mailto:customer.support@bidx.com>

- (5) The department will address equipment and process failures, if the bidder can demonstrate that those failures were beyond their control.
- (6) Contractors are responsible for checking on the issuance of addenda and for obtaining the addenda. Notice of issuance of addenda is posted on the department's web site at:
<https://wisconsindot.gov/Pages/doing-bus/contractors/hcci/bid-let.aspx>

or by calling the department at (608) 266-1631. Addenda can ONLY be obtained from the department's web site listed above or by picking up the addenda at the Bureau of Highway Construction, 4th floor, 4822 Madison Yards Way, Madison, WI, during regular business hours.

- (7) Addenda posted after 5:00 PM on the Thursday before the letting will be emailed to the eligible bidders for that proposal. All eligible bidders shall acknowledge receipt of the addenda whether they are bidding on the proposal or not. Not acknowledging receipt may jeopardize the awarding of the project.

B Submitting Electronic Bids

B.1 On the Internet

- (1) Do the following before submitting the bid:
 1. Have a properly executed annual bid bond on file with the department.

2. Have a digital ID on file with and enabled by Info Tech Inc. Using this digital ID will constitute the bidder's signature for proper execution of the bidding proposal.
- (2) In lieu of preparing, delivering, and submitting the proposal as specified in 102.6 and 102.9 of the standard specifications, submit the proposal on the internet as follows:
 1. Download the latest schedule of items reflecting all addenda from the Bid Express™ web site.
 2. Use Expedite™ software to enter a unit price for every item in the schedule of items.
 3. Submit the bid according to the requirements of Expedite™ software and the Bid Express™ web site. Do not submit a bid on a printout with accompanying diskette or CD ROM or a paper bid. If the bidder does submit a bid on a printout with accompanying diskette or a paper bid in addition to the internet submittal, the department will disregard the internet bid.
 4. Submit the bid before the hour and date the Notice to Contractors designates.
 5. Do not sign, notarize, and return the bidding proposal described in 102.2 of the standard specifications.
- (3) The department will not consider the bid accepted until the hour and date the Notice to Contractors designates.

B.2 On a Printout with Accompanying Diskette or CD ROM

- (1) Download the latest schedule of items from the Wisconsin pages of the Bid Express™ web site reflecting the latest addenda posted on the department's web site at:
<https://wisconsindot.gov/Pages/doing-bus/contractors/hcci/bid-let.aspx>
Use Expedite™ software to prepare and print the schedule of items. Provide a valid amount for all price fields. Follow instructions and review the help screens provided on the Bid Express™ web site to assure that the schedule of items is prepared properly.
- (2) Staple an 8 1/2 by 11 inch printout of the Expedite™ generated schedule of items to the other proposal documents submitted to the department as a part of the bidder's sealed bid. As a separate submittal, not in the sealed bid envelop but due at the same time and place as the sealed bid, also provide the Expedite™ generated schedule of items on a 3 1/2 inch computer diskette or CD ROM. Label each diskette or CD ROM with the bidder's name, the 4 character department-assigned bidder identification code from the top of the bidding proposal, and a list of the proposal numbers included on that diskette or CD ROM as indicated in the following example:

Bidder Name

BN00

Proposals: 1, 12, 14, & 22

- (3) If bidding on more than one proposal in the letting, the bidder may include all proposals for that letting on one diskette or CD ROM. Include only submitted proposals with no incomplete or other files on the diskette or CD ROM.
- (4) The bidder-submitted printout of the Expedite™ generated schedule of items is the governing contract document and must conform to the requirements of section 102 of the standard specifications. If a printout needs to be altered, cross out the printed information with ink or typewriter and enter the new information and initial it in ink. If there is a discrepancy between the printout and the diskette or CD ROM, the department will analyze the bid using the printout information.
- (5) In addition to the reasons specified in section 102 of the standard specifications, proposals are irregular and the department may reject them for one or more of the following:
 1. The check code printed on the bottom of the printout of the Expedite™ generated schedule of items is not the same on each page.
 2. The check code printed on the printout of the Expedite™ generated schedule of items is not the same as the check code for that proposal provided on the diskette or CD ROM.

3. The diskette or CD ROM is not submitted at the time and place the department designates.

C Waiver of Electronic Submittal

- (1) The bidder may request a waiver of the electronic submittal requirements. Submit a written request for a waiver in lieu of bids submitted on the internet or on a printout with accompanying diskette or CD ROM. Use the waiver that was included with the paper bid document sent to the bidder or type up a waiver on the bidder's letterhead. The department will waive the electronic submittal requirements for a bidding entity (individual, partnership, joint venture, corporation, or limited liability company) for up to 4 individual proposals in a calendar year. The department may allow additional waivers for equipment malfunctions.
- (2) Submit a schedule of items on paper conforming to section 102 of the standard specifications. The department charges the bidder a \$75 administrative fee per proposal, payable at the time and place the department designates for receiving bids, to cover the costs of data entry. The department will accept a check or money order payable to: "Wisconsin, Dept. of Transportation."
- (3) In addition to the reasons specified in section 102 of the standard specifications, proposals are irregular and the department may reject them for one or more of the following:
 1. The bidder fails to provide the written request for waiver of the electronic submittal requirements.
 2. The bidder fails to pay the \$75 administrative fee before the time the department designates for the opening of bids unless the bidder requests on the waiver that they be billed for the \$75.
 3. The bidder exceeds 4 waivers of electronic submittal requirements within a calendar year.
- (4) In addition to the reasons specified in section 102 of the standard specifications, the department may refuse to issue bidding proposals for future contracts to a bidding entity that owes the department administrative fees for a waiver of electronic submittal requirements.

PROPOSAL BID BOND

DT1303 1/2006

Wisconsin Department of Transportation

Proposal Number	Project Number	Letting Date
Name of Principal		
Name of Surety	State in Which Surety is Organized	

We, the above-named Principal and the above-named Surety, are held and firmly bound unto the State of Wisconsin in the sum equal to the Proposal Guaranty for the total bid submitted for the payment to be made; we jointly and severally bind ourselves, our heirs, executors, administrators, successors and assigns. The condition of this obligation is that the Principal has submitted a bid proposal to the State of Wisconsin acting through the Department of Transportation for the improvement designated by the Proposal Number and Letting Date indicated above.

If the Principal is awarded the contract and, within the time and manner required by law after the prescribed forms are presented for signature, enters into a written contract in accordance with the bid, and files the bond with the Department of Transportation to guarantee faithful performance and payment for labor and materials, as required by law, or if the Department of Transportation shall reject all bids for the work described, then this obligation shall be null and void; otherwise, it shall be and remain in full force and effect. In the event of failure of the Principal to enter into the contract or give the specified bond, the Principal shall pay to the Department of Transportation **within 10 business days of demand** a total equal to the Proposal Guaranty as liquidated damages; the liability of the Surety continues for the full amount of the obligation as stated until the obligation is paid in full.

The Surety, for value received, agrees that the obligations of it and its bond shall not be impaired or affected by any extension of time within which the Department of Transportation may accept the bid; and the Surety does waive notice of any such extension.

IN WITNESS, the Principal and Surety have agreed and have signed by their proper officers and have caused their corporate seals to be affixed this date: **(DATE MUST BE ENTERED)**

PRINCIPAL

(Company Name) **(Affix Corporate Seal)**

(Signature and Title)

(Company Name)

(Signature and Title)

(Company Name)

(Signature and Title)

(Company Name)

(Signature and Title)

NOTARY FOR PRINCIPAL

(Date)

State of Wisconsin)
) ss.
_____ County)

On the above date, this instrument was acknowledged before me by the named person(s).

(Signature, Notary Public, State of Wisconsin)

(Print or Type Name, Notary Public, State of Wisconsin)

(Date Commission Expires)

Notary Seal

(Name of Surety) **(Affix Seal)**

(Signature of Attorney-in-Fact)

NOTARY FOR SURETY

(Date)

State of Wisconsin)
) ss.
_____ County)

On the above date, this instrument was acknowledged before me by the named person(s).

(Signature, Notary Public, State of Wisconsin)

(Print or Type Name, Notary Public, State of Wisconsin)

(Date Commission Expires)

Notary Seal

IMPORTANT: A certified copy of Power of Attorney of the signatory agent must be attached to the bid bond.

CERTIFICATE OF ANNUAL BID BOND

DT1305 8/2003

Wisconsin Department of Transportation

Time Period Valid (From/To)	
Name of Surety	
Name of Contractor	
Certificate Holder	Wisconsin Department of Transportation

This is to certify that an annual bid bond issued by the above-named Surety is currently on file with the Wisconsin Department of Transportation.

This certificate is issued as a matter of information and conveys no rights upon the certificate holder and does not amend, extend or alter the coverage of the annual bid bond.

Cancellation: Should the above policy be cancelled before the expiration date, the issuing surety will give thirty (30) days written notice to the certificate holder indicated above.

(Signature of Authorized Contractor Representative)

(Date)

March 2010

LIST OF SUBCONTRACTORS

Section 66.0901(7), Wisconsin Statutes, provides that as a part of the proposal, the bidder also shall submit a list of the subcontractors the bidder proposes to contract with and the class of work to be performed by each. In order to qualify for inclusion in the bidder's list a subcontractor shall first submit a bid in writing, to the general contractor at least 48 hours prior to the time of the bid closing. The list may not be added to or altered without the written consent of the municipality. A proposal of a bidder is not invalid if any subcontractor and the class of work to be performed by the subcontractor has been omitted from a proposal; the omission shall be considered inadvertent or the bidder will perform the work personally.

No subcontract, whether listed herein or later proposed, may be entered into without the written consent of the Engineer as provided in Subsection 108.1 of the Standard Specifications.

[illegible]

DECEMBER 2000

**CERTIFICATION REGARDING DEBARMENT, SUSPENSION, AND OTHER
RESPONSIBILITY MATTERS - PRIMARY COVERED TRANSACTIONS**

Instructions for Certification

1. By signing and submitting this proposal, the prospective contractor is providing the certification set out below.
2. The inability of a person to provide the certification required below will not necessarily result in denial of participation in this covered transaction. The prospective contractor shall submit an explanation of why it cannot provide the certification set out below. The certification or explanation will be considered in connection with the department or agency's determination whether to enter into this transaction. However, failure of the prospective contractor to furnish a certification or an explanation shall disqualify such person from participation in this transaction.
3. The certification in this clause is a material representation of fact upon which reliance was placed when the department determined to enter into this transaction. If it is later determined that the contractor knowingly rendered an erroneous certification in addition to other remedies available to the Federal Government the department may terminate this transaction for cause or default.
4. The prospective contractor shall provide immediate written notice to the department to whom this proposal is submitted if at any time the prospective contractor learns that its certification was erroneous when submitted or has become erroneous by reason of changed circumstances.
5. The terms "covered transaction," "debarred," "suspended," "ineligible," "lower tier covered transaction," "participant," "person," "primary covered transaction," "principal," "proposal," and "voluntarily excluded," as used in this clause, have the meanings set out in the Definitions and Coverage sections of the rules implementing Executive Order 12549. You may contact the department to which this proposal is being submitted for assistance in obtaining a copy of those regulations.
6. The prospective contractor agrees by submitting this proposal that, should this contract be entered into, it shall not knowingly enter into any lower tier covered transaction with a person who is debarred, suspended, declared ineligible, or voluntarily excluded from participation in this covered transaction, unless authorized by the department entering into this transaction.
7. The prospective contractor further agrees by submitting this proposal that it will include the clause titled "Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion-Lower Tier Covered Transaction," which is included as an addendum to PR-1273 - "Required Contract Provisions Federal Aid Construction Contracts," without

modification, in all lower tier covered transactions and in all solicitations for lower tier covered transactions.

8. The contractor may rely upon a certification of a prospective subcontractor/materials supplier that it is not debarred, suspended, ineligible, or voluntarily excluded from the covered transaction, unless it knows that the certification is erroneous. A contractor may decide the method and frequency by which it determines the eligibility of its principals. Each contractor may, but is not required to, check the Disapproval List (telephone # 608/266/1631).
9. Nothing contained in the foregoing shall be construed to require establishment of a system of records in order to render in good faith the certification required by this clause. The knowledge and information of a contractor is not required to exceed that which is normally possessed by a prudent person in the ordinary course of business dealings.
10. Except for transactions authorized under paragraph 6 of these instructions, if a contractor in a covered transaction knowingly enters into a lower tier covered transaction with a person who is suspended, debarred, ineligible or voluntarily excluded from participation in this transaction, in addition to other remedies available to the Federal Government, the department may terminate this transaction for cause or default.

Certification Regarding Debarment, Suspension, and Other Responsibility Matters - Primary Covered Transactions

- (1) The prospective contractor certifies to the best of its knowledge and belief, that it and its principals:
 - (a) Are not presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from covered transactions by any Federal department or agency;
 - (b) Have not within a three-year period preceding this proposal been convicted of or had a civil judgment rendered against them for commission of fraud or a criminal offense in connection with obtaining, attempting to obtain, or performing a public (Federal, State or local) transaction or contract under a public transaction; violation of Federal or State antitrust statutes or commission of embezzlement, theft, forgery, bribery, falsification or destruction of records, making false statements or receiving stolen property;
 - (c) Are not presently indicted for or otherwise criminally or civilly charged by a governmental entity (Federal, State or local) with commission of any of the offense enumerated in paragraph (1)(b) of this certification; and
 - (d) Have not within a three-year period preceding this proposal had one or more public transactions (Federal, State or local) terminated for cause or default.
- (2) Where the prospective contractor is unable to certify to any of the statements in this certification, such prospective contractor shall attach an explanation to this proposal.

Special Provisions

Table of Contents

Article	Description	Page #
1.	General.....	2
2.	Scope of Work.....	2
3.	Prosecution and Progress.....	2
4.	Holiday and Special Event Work Restrictions.....	7
5.	Utilities.....	7
6.	Other Contracts.....	8
7.	Contractor Notification.....	8
8.	Contractor Document Submittals.....	9
9.	Railroad Insurance and Coordination - Soo Line Railroad Company (CP)	9
10.	Railroad Insurance and Coordination - Union Pacific Railway Company.....	11
11.	Lane Rental Fee Assessment.....	12
12.	Erosion Control.....	13
13.	Notice to Contractor, Verification of Asbestos Inspection, No Asbestos Found.....	14
14.	Removing Electrical Wires from Conduit, Item 204.9090.S.10.....	14
15.	Nighttime Work Lighting-Stationary.....	14
16.	Traffic Control Interim Lane Closure, Item 643.4100.S.....	16
17.	Lighting Systems.....	16
18.	HPC Masonry Structures, Item SPV.0035.01.....	17
19.	Traffic Control Close-Open Freeway Entrance Ramp, Item SPV. 0060.01.....	22
20.	Traffic Control Full Freeway Closure, Item SPV. 0060.02.....	22
21.	Fence Gate Salvaged, Item SPV.0060.03.....	23
22.	Field Facilities Office Space, Item SPV.0060.04.....	23
23.	Lighting Units Salvaged, Item SPV.0060.10.....	24
24.	Fence Temporary 6-FT, Item SPV.0090.01.....	25
25.	Remove and Replace Fence Decorative Bridge, Item SPV.0105.01.....	25
26.	Survey Project 1100-25-80, Item SPV.0105.02.....	26

SPECIAL PROVISIONS

1. General.

Perform the work under this construction contract for Project 1100-25-80, Zoo Freeway, Center St Bridge B-40-880, IH 41, Milwaukee County, Wisconsin as the plans show and execute the work as specified in the State of Wisconsin, Department of Transportation, Standard Specifications for Highway and Structure Construction, 2019 Edition, as published by the department, and these special provisions.

If all or a portion of the plans and special provisions are developed in the SI metric system and the schedule of prices is developed in the US standard measure system, the department will pay for the work as bid in the US standard system.

100-005 (20181119)

2. Scope of Work.

The work under this contract shall consist of removals, bridge removal, bridge concrete masonry, bridge girder replacement, concrete curb and gutter, concrete sidewalk, fencing, temporary pavement marking, permanent signing, traffic control and all incidental items necessary to complete the work as shown on the plans and included in the proposal and contract.

104-005 (20090901)

3. Prosecution and Progress.

Begin work within ten calendar days after the engineer issues a written notice to do so.

Provide the start date to the engineer in writing within a month after executing the contract but at least 14 calendar days before the preconstruction conference. Upon approval, the engineer will issue the notice to proceed within ten calendar days before the approved start date.

To revise the start date, submit a written request to the engineer at least two weeks before the intended start date. The engineer will approve or deny that request based on the conditions cited in the request and its effect on the department's scheduled resources.

Do not begin construction work prior to 12:01 AM on June 10, 2019.

The completion date is based on an expedited work schedule and may require extraordinary forces and equipment; work on Saturdays, Sundays, and nationally recognized legal holidays; and work at night.

Indicate on the proposed schedule of operations that a large force and adequate equipment will be needed to assure that the work will be completed within the established contract time.

Be advised that there may be multiple mobilizations and/or remobilizations to complete construction operations, for example such items as: structure work, traffic control, finishing items and other incidental items. No additional payment will be made, by the department, for additional mobilizations.

Supplement standard spec 108.10 with the following:

The department will not grant time extensions to the completion dates specified above for the following:

1. Severe weather as specified in standard spec 108.10.2.2.
2. Labor disputes that are not industry wide.
3. Delays in material deliveries.

Permitting the contractor to continue and finish the work or any part of after the time fixed for its completion, or after the date to which the time for completion may have been extended, will in no way operate as a waiver on the part of the department of any of its rights under the contract.

Final Completion of Work

Replace standard spec 108.11 paragraph (3) with the following:

The department will assess \$15,000 in daily liquidated damages. These liquidated damages reflect the cost of engineering, supervision, and a portion of road user costs.

Schedule of Operations

The department anticipates that the schedule of work shall be as follows:

Traffic Staging:

IH 41

- All lanes and ramps open to traffic during peak hours.
- Short-term lane closures permitted during off-peak and night time hours.
- Full freeway closures permitted during restricted night time hours for bridge removal, girder erection, and bridge deck pours.

Center Street

- All lanes and shoulders remain open at all times, except the eastbound right shoulder is permanently closed during bridge construction operations.

Construction:

Center Street

- Bridge removal and proposed bridge work Structure B-40-880.
- Fence, sidewalk, curb and gutter, and restoration work.

Traffic Control Deficiency Response Time Penalty

Supplement standard spec 643.3.2(8) with the following:

Upon receiving written notification from the engineer, clean, repair or replace traffic control devices not performing as intended to the satisfaction of the engineer within 12 hours. Failure to clean, repair or replace required traffic control within the time limits specified above will result in daily monetary deductions of \$500 for each 24-hour period (or portion thereof starting 12 hours after time of notification) in which the traffic control deficiency exists.

Contractor Coordination

Attend weekly scheduling meetings to discuss the near term schedule activities, address any long-term schedule issues, and discuss any relevant technical issues. Develop a rolling three-week schedule identifying the previous week worked and a two week "look ahead". Provide sufficient detail to include actual and planned activities and all the subcontractors for offsite and construction activities, addressing all activities including ramp and lane closure schedules to be performed and identifying issues requiring

engineering action or input. Submit plans for all traffic control for review by the engineer and approval a minimum of one week prior to implementation.

Advance Notification

Notify the engineer if there are any changes in the schedule, early completions, or cancellations of scheduled work.

Provide the engineer with a schedule of lane and ramp closures for the following week by 9:00 AM on Wednesday of the previous week. In addition, provide the following minimum advance notification to the engineer for incorporation into the Wisconsin Lane Closure System:

Service Ramp Closures	3 Business Days
Lane Closures	3 Business Days
Full Freeway Closures	14 Business Days
Construction Stage Changes	14 Calendar Days
Detours	14 Calendar Days

Obtain prior acceptance from the engineer and the WisDOT Statewide Traffic Operations Center (STOC) for Full Freeway Closures. Notify local emergency and police agencies seven calendar days prior to freeway closure.

Definitions - Freeway Work Restrictions

The following definitions apply to the contract for freeway work restrictions:

Weekday Peak Hours

- 5:30 AM – 7:00 PM Monday, Tuesday, Wednesday, Thursday, Friday

Weekday Off-Peak Hours

- 7:00 PM – 9:30 PM Monday, Tuesday, Wednesday, Thursday
- 7:00 PM – 11:00 PM Friday

Weekend Peak Hours

- 8:00 AM – 7:00 PM Saturday, Sunday

Weekend Off-Peak Hours

- 7:00 PM – 11:00 PM Saturday
- 7:00 PM – 9:30 PM Sunday

Night Time Hours

- 9:30 PM – 5:30 AM (Sunday PM to Monday AM, Monday PM to Tuesday AM, Tuesday PM to Wednesday AM, Wednesday PM to Thursday AM, Thursday PM to Friday AM)
- 11:00 PM – 8:00 AM (Friday PM to Saturday AM, Saturday PM to Sunday AM)

Extended Full Freeway Closure Hours (Bridge Demolition)

- 10:00 PM – 8:00 AM Friday and Saturday nights

Full Freeway Closure Hours (Girder Erection and Deck Pours)

- 11:00 PM – 4:30 AM Sunday through Thursday nights
- 11:00 PM – 6:00 AM Friday and Saturday nights

Center Street Restrictions

Center Street (Eastbound):

- Maintain a single through lane at all times.
- Permanently close the right shoulder as shown in the plans to facilitate the bridge construction work.
- Permanently close the sidewalk on the south side of the bridge and detour pedestrians to use the sidewalk on the north side of the street.

Center Street (Westbound):

- Maintain the right shoulder and a single through lane at all times.
- Keep the sidewalk open at all times on the north side of the street.

Maintain access to all driveways and intersections at all times, except short term closures will be permitted utilizing flagging operations during Night Time Hours only for operations to install traffic control devices, temporary concrete barrier, and for equipment and material deliveries, or as otherwise approved by the engineer.

Freeway Work Restrictions - General

No Weekday Peak or Weekend Peak Hour lane closures are allowed. No Weekday Off-Peak or Weekend Off-Peak Hour two-lane closures are allowed.

Provide a minimum of three lanes in each direction of the freeways and ensure that the freeways are entirely clear for traffic during Weekday Peak Hours and Weekend Peak Hours.

Provide a minimum of two lanes in each direction of the freeways and ensure that the freeways are entirely clear for traffic during Weekday Off-Peak and Weekend Off-Peak Hours.

Provide a minimum of one lane in each direction of the freeway and ensure that the freeways are entirely clear for traffic during Night Time Hours except as allowed during full closure.

Freeway Work Restrictions – Full Closure

No full freeway closures are permitted for the IH 41 southbound freeway lanes.

Full closure and detouring of IH 41 northbound freeway lanes will be restricted to Extended Full Freeway Closure Hours and Full Freeway Closure Hours. Extended Full Freeway Closure Hours will only be permitted for bridge demolition. Full Freeway Closure Hours will be permitted as approved by the engineer for other work operations, including full freeway closures to facilitate erection of girders and deck pours. Provide signed detour routes, as shown in the plans that are fully open and free of construction during all full freeway and system ramp closures.

Submit requests for freeway closures 14 calendar days prior to the planned closure events. Obtain prior approval from the engineer and the WisDOT SE Region Work Zone Traffic Engineer for said closures. Notify local emergency and police agencies 7 calendar days prior to closures.

Ramp Closures

No ramp closures are permitted during peak hours and off-peak hours.

No two consecutive entrance ramps or consecutive exit ramps may be closed unless approved by the engineer.

All entrance and exit ramps shall be posted three business days in advance of their closure with dates and time of closure.

Detours

Full freeway night time closures will require a detour for IH 41 northbound.

Work Zone Ingress/Egress.

Provide engineer approved signage and parallel deceleration and acceleration lanes for freeway access into and out of the work zones at locations approved by the engineer.

At the weekly traffic meetings, provide an Emergency Work Zone Access Plan and required updates, as approved by the engineer, to direct emergency responders accessing a mainline median barrier restricted work zone.

Locations of work zone egress or ingress for construction vehicles, other than as shown in the plans, is subject to approval from the engineer. Access into the work zones are not allowed directly from the freeway during peak, and off-peak hours, unless otherwise approved by the engineer. Access into the work zones from the freeway will be allowed during night-time hours, subject to approval by the engineer, if operations can be safely accomplished and do not result in non-construction traffic entering the work zones. Exiting work zones directly onto the freeway are only allowed when operations do not obstruct or slow traffic on the freeway. All construction vehicles shall yield to all through traffic at all locations.

Portable Changeable Message Signs

Obtain acceptance from the engineer regarding the location of all portable changeable message signs.

Obtain acceptance from the engineer regarding the wording of all messages on portable changeable message signs.

Equipment Parking/Materials Storage, Miscellaneous

Park or store equipment and materials only at work sites approved by the engineer. Parking equipment or storing materials on the shoulders or within 30' of the roadway during non-working hours is not permitted.

Comply with all local ordinances that apply to work operations pertaining to work during night time work hours. Furnish in writing any ordinance variance issued by the municipality or required permits to the engineer no less than three days before performing such work.

Keep open travel lanes free of construction debris at all times.

All work and operations shall be completed according to WisDOT Standard Detail Drawings, the MUTCD, and as directed by the engineer. Installing construction zone signage on existing sign posts or utility poles is not permitted.

General Restrictions

When engaged in roadway cleaning operations, use equipment having vacuum or water spray mechanisms to eliminate the dispersion of particulate matter into the atmosphere. If vacuum equipment is employed, it must have suitable self-contained particulate collectors to prevent discharge from the collection bin into the atmosphere.

4. Holiday and Special Event Work Restrictions.

Do not perform work on, nor haul materials of any kind along or across any portion of the highway carrying IH 41 traffic, and entirely clear the traveled way and shoulders of such portions of the highway of equipment, barricades, signs, lights, and any other material that might impede the free flow of traffic during the following holiday periods:

- From noon Wednesday, July 3, 2019 to 6:00 AM Friday, July 5, 2019 for Independence Day.

Additional Special Event Freeway Restrictions:

During Summerfest and State Fair:

- Maintain two open lanes on northbound IH 41 until one hour after the event closes each night.

During Milwaukee Brewer home games at Miller Park:

- Maintain two open lanes on northbound IH 41 until two hours after the game ends.

During other special events at Miller Park:

- Restrictions will be defined during construction on an as needed basis as determined by the engineer.

During Green Bay Packers home games:

- Maintain three open lanes on northbound IH 41 from three hours prior to the game to three hours after the game.

stp-107-005 (20181119)

5. Utilities.

This contract comes under the provision of Administrative Rule Trans 220.

stp-107-065 (20080501)

Additional information regarding recently relocated utility facilities may be available on permits issued to the utility companies. These permits can be viewed at the Region Office during normal working hours.

Underground and overhead utility facilities are located within the project limits. Utility adjustments are not required for this construction project. Coordinate construction activities with a call to Diggers Hotline or a direct call to the utilities that have facilities in the area as required per state statute. Use caution to ensure the integrity of underground facilities and maintain code clearances from overhead facilities at all times.

Contact utility companies listed in the plans prior to preparing bids to obtain current information on existing utility locations and the status of any new utility relocation work.

There may be discontinued utility facilities within the project limits. If a conflict with a discontinued utility facility is encountered, contact the appropriate utility owner/representative to coordinate construction activities and proper removal and disposal of said facility as necessary.

Known utilities in the project area are as follows:

City of Wauwatosa – Street Lighting has existing lighting facilities within the project limits on the Center Street Bridge. All lighting work to be included under project pay items.

Contact Randy Michelz, (414) 471-8429, of City of Wauwatosa - Lighting 7 days in advance to coordinate locations and any excavation near their facilities.

WisDOT – Lighting has existing lighting facilities along USH 45 throughout the project area. All lighting work to be included under project pay items.

Contact Eric Perea, (262) 574-5422 office / (414) 750-0935 cell, of WisDOT - Lighting 7 days in advance to coordinate locations and any excavation near their facilities.

The following utility owners have facilities within the project area; however, the utilities are not on the bridge structure, no adjustments are anticipated:

City of Wauwatosa – Sewer
Wauwatosa Water Utility
We Energies – Electric
We Energies - Gas

6. Other Contracts.

It is expected that routine maintenance by the city and county personnel may be required at certain times concurrently with the work being done under this contract.

The following contracts are anticipated to be under construction within the time period of this contract:

WisDOT Project 1060-35-81

IH 41, Zoo Interchange:

- Landscaping construction
WisDOT Contact: Steve Kuhl, (414) 745-7569; steven.kuhl@dot.wi.gov

City of Wauwatosa Local Project

Center Street (111th Street to Union Pacific Railroad bridge):

- Roadway reconstruction, sidewalk pedestrian ramps, and retaining wall construction. Center Street is anticipated to be closed to traffic through the city work zone.
City Contact: Bill Wehrley, (414) 479-8927; wwehrley@wauwatosa.net

7. Contractor Notification.

Replace standard spec 104.2.2.2(2) with the following:

- (2) If the contractor discovers the differing condition, provide a written notice, as specified in standard spec 104.3.3, of the specific differing condition before further disturbing the site and before further performing the affected work.

Replace standard spec 104.3.2 and 104.3.3 with the following:

104.3.2 (Vacant)

104.3.3 Contractor Initial Written Notice

- (1) If required by standard spec 104.2, or if the contractor believes that the department's action, the department's lack of action, or some other situation results in or necessitates a contract revision, promptly provide a written notice to the engineer. At a minimum, provide the following:
 1. A written description of the nature of the issue.
 2. The time and date of discovering the problem or issue.
 3. If appropriate, the location of the issue.
- (2) Provide the additional information specified in 104.3.5 as early as possible to assist the engineer in the timely resolution of an identified issue. The engineer will not require, in subsequent submissions, duplication of information already provided.

sef-104-005 (20141211)

8. Contractor Document Submittals.

This special provision describes minimum requirements for submitting project documents to the department. This special provision does not apply to shop drawing submittals.

Provide one electronic copy of all documents requiring department review, acceptance, or approval. Attach a completed engineer-provided transmittal sheet to each email submittal. The department will reject submittals with incomplete transmittal sheets and require re-submittal.

The department will return one reviewed, accepted, or approved original to the contractor. Additional return originals can be requested. Submit an additional original for each additional return original requested.

Submit electronic copies in PDF format via email to accounts the engineer determines. If possible, create PDFs from original documents in their native format (e.g. Word, Excel, AutoCAD, etc.). Scan other documents to PDF format with a minimum resolution of 600 dpi.

All costs for contractor document submittals are incidental to the contract.

sef-105-010 (20150619)

9. Railroad Insurance and Coordination - Soo Line Railroad Company (CP)

A Description

Comply with standard spec 107.17 for all work affecting Soo Line Railroad Company (CP) property and any existing tracks.

A.1 Railroad Insurance Requirements

In addition to standard spec 107.26, provide railroad protective liability insurance coverage as specified in standard spec 107.17.3. Insurance is filed in the name of Soo Line Railroad Company d/b/a Canadian Pacific.

Notify evidence of the required coverage, and duration to Jim Krieger, Manager Public Works; Canadian Pacific Plaza, 120 South 6th Street, Suite 700, Minneapolis, MN 55402; Telephone (612) 330-4555; E-mail: jim_krieger@cpr.ca.

Also send a copy to the following: Paul Derksen, SE Region Railroad Coordinator; 141 N. W. Barstow Street, Waukesha, WI 53188; Telephone (262) 548-8770; E-mail: paul.derksen@dot.wi.gov.

Include the following information on the insurance document:

- Project ID: 1100-25-80
- Project Location: Wauwatosa WI
- Route Name: IH 41
- Crossing ID: 390 506M
- Railroad Subdivision: Watertown
- Railroad Milepost: 92.8
- Work Performed: Traffic Control

A.2 Train Operation

Approximately 2 passenger trains and 21 through freight trains operate daily through the construction site. Passenger trains operate at up to 55 mph. Through freight trains operate at up to 55 mph.

A.3 Names and Addresses of Railroad Representatives for Consultation and Coordination

Construction Contact:

Jim Krieger, Manager Public Works; Canadian Pacific Plaza, 120 South 6th Street, Suite 700, Minneapolis, MN 55402; Telephone (612) 330-4555; E-mail jim_krieger@cpr.ca for consultation on railroad requirements during construction.

Amend standard spec 108.4 to include the railroad in the distribution of the initial bar chart, and monthly schedule updates. The bar chart shall specifically show work involving coordination with the railroad.

Flagging Contact:

Dave LeClaire, Supervisor of Public Works; Canadian Pacific Plaza, 120 South 6th Street, Suite 700, Minneapolis, MN 55402; Telephone (612) 330-4556; E-mail dave.leclaire@cpr.ca Reference the Crossing ID, Wisconsin Milepost and Subdivision found in A.1.

*Contact Soo Line (CP) prior to letting for flagman work hour availability.

Cable Locate Contact:

In addition to contacting Diggers Hotline, contact CP Call Before You Dig line at (866) 291-0741, five working days before the locate is needed. Reference the Crossing ID, Wisconsin Milepost and Subdivision found in A.1.

Soo Line (CP) will only locate railroad owned facilities located in the railroad right-of-way. The railroad does not locate any other utilities.

A.4 Work by Railroad

The railroad will perform the work described in this section, except for work described in other special provisions, and will be accomplished without cost to the contractor. none

A.5 Temporary Grade Crossing

If a temporary grade crossing is desired, submit a written request to the railroad representative named in A.3 at least 40 days prior to the time needed. Approval is subject to the discretion of the railroad. The department has made no arrangements for a temporary grade crossing.

A.6 Rail Security Awareness and Contractor Orientation

Prior to entry on railroad right-of-way, the contractor shall arrange for on-line security awareness and contractor orientation training and testing, and be registered through "e-RAILSAFE" for all contractor and subcontractor employees working on railroad right-of-way. See e-railsafe.com "Information". The security awareness and contractor orientation training is shown under the railroad's name.

The department has secured right of entry to railroad property; neither the contractor nor subcontractors or their employees will be required to sign a right of entry form.

The security awareness and contractor orientation certification is valid for 2 year(s) and must be renewed for projects that will carry over beyond the 2 year period. Contractor and subcontractor employees shall wear the identification badge issued by e-RAILSAFE when on railroad right-of-way. Costs associated with training and registration are incidental to other items in the contract.

stp-107-026 (20170615)

10. Railroad Insurance and Coordination - Union Pacific Railway Company.

A Description

Comply with standard spec 107.17 for all work affecting Union Pacific Railway Company property and any existing tracks.

A.1 Railroad Insurance Requirements

In addition to standard spec 107.26, provide railroad protective liability insurance coverage as specified in standard spec 107.17.3. Insurance is filed in the name of Union Pacific Railway Company.

Notify evidence of the required coverage, and duration to Danielle Allen, Contract Administrator; 1400 Dodge Street, Stop 1690, Omaha, NE 68179; Telephone (402) 544-8020; E-mail: danielleallen@up.com.

Also send a copy to the following: Paul Derksen, SE Region Railroad Coordinator; 141 N. W. Barstow Street, Waukesha, WI 53188; Telephone (262) 548-8770; E-mail: paul.derksen@dot.wi.gov.

Include the following information on the insurance document:

- Project ID: 1100-25-80
- Work Performed: Traffic Control

#	Route Name	City/County	Crossing ID	RR Subdivision	RR Milepost
	IH41	Wauwatosa / Milwaukee County	177 262X	Milwaukee	91.84
	North Ave	Wauwatosa / Milwaukee County	177263E	Milwaukee	92.07
	Center St	Wauwatosa / Milwaukee County	177264L	Milwaukee	92.62
	Burleigh St	Wauwatosa / Milwaukee County	177267G	Milwaukee	93.12

A.2 Train Operation

Approximately 12 through freight trains operate daily at up to 40 mph.

A.3 Names and Addresses of Railroad Representatives for Consultation and Coordination

Construction Contact

John Venice, Manager Special Projects - Industry & Public Projects Engineering Department; 101 North Wacker Drive - Suite 1920, Chicago, IL 60606; Telephone (312) 777-2043; E-mail jnvenice@up.com for consultation on railroad requirements during construction.

Amend standard spec 108.4 to include the railroad in the distribution of the initial bar chart, and monthly schedule updates. The bar chart shall specifically show work involving coordination with the railroad.

Flagging Contact

See Construction Contact. If more than 30 days of flagging is required contact UP 30 days prior to needing a flagger on site. Reference the Wisconsin Milepost and Subdivision located in A.1.

Cable Locate Contact

In addition to contacting Diggers Hotline, contact the UP Call Before You Dig line at (800) 336-9193 at least five working days before the locate is needed. Normal business hours are 6:30 AM to 6:30 PM, Central Time, Monday through Friday, except holidays and are subject to change. Calls will be routed at all times in case of an emergency. Reference the Wisconsin Milepost and Subdivision located in A.1.

UP will only locate railroad owned cable buried in the railroad right-of-way. The railroad does not locate any other utilities.

A.4 Work by Railroad

The railroad will perform the work described in this section, except for work described in other special provisions, and will be accomplished without cost to the contractor. none

A.5 Temporary Grade Crossing

If a temporary grade crossing is desired, submit a written request to the railroad representative named in A.3 at least 40 days prior to the time needed. Approval is subject to the discretion of the railroad. The department has made no arrangements for a temporary grade crossing.

A.6 Rail Security Awareness and Contractor Orientation

Prior to entry on railroad right-of-way, the contractor shall arrange for on-line security awareness and contractor orientation training and testing, and be registered through "e-RAILSAFE" for all contractor and subcontractor employees working on railroad right-of-way. See e-railsafe.com "Information". The security awareness and contractor orientation training is shown under the railroad's name.

The department has secured right of entry to railroad property; neither the contractor nor subcontractors or their employees will be required to sign a right of entry form.

The security awareness and contractor orientation certification is valid for 2 year(s) and must be renewed for projects that will carry over beyond the 2 year period. Contractor and subcontractor employees shall wear the identification badge issued by e-RAILSAFE when on railroad right-of-way. Costs associated with training and registration are incidental to other items in the contract.

stp-107-026 (20170615)

11. Lane Rental Fee Assessment.

A General

The contract designates some lane closures to perform the work. The contractor will not incur a Lane Rental Fee Assessment for closing lanes during the allowable lane closure times. The contractor will incur a Lane Rental Fee Assessment for each lane closure outside of the allowable lane closure times. If a lane is obstructed at any time due to contractor operations, it is considered a closure. The purpose of lane rental is to enforce compliance of lane restrictions and discourage unnecessary closures.

The allowable lane closure times are shown in the Prosecution and Progress article.

Submit the dates of the proposed lane, ramp, and roadway restrictions to the engineer as part of the progress schedule.

Coordinate lane, ramp, and roadway closures with any concurrent operations on adjacent roadways within 3 miles of the project. If other projects are in the vicinity of this project, coordinate lane closures to run concurrent with lane closures on adjacent projects when possible. When lane closures on adjacent projects extend into the limits of this project, Lane Rental Fee Assessments will only occur if the closure facilitates work under this contract.

B Lane Rental Fee Assessment

The Lane Rental Fee Assessment incurred for each lane closure, each ramp closure, and each full closure of a roadway, per direction of travel, is as follows:

- IH 41 - \$2,000 per lane, per direction of travel, per hour broken into 15 minute increments
- Service Ramps - \$2,000 per ramp, per hour broken into 15 minute increments

The Lane Rental Fee Assessment represents a portion of the cost of the interference and inconvenience to the road users for each closure. All lane, roadway, or ramp closure event increments 15 minutes and less will be assessed as a 15-minute increment.

The engineer, or designated representative, will be the sole authority in determining time period length for the Lane Rental Fee Assessment.

Lane Rental Fee Assessments will not be assessed for closures due to crashes, accidents or emergencies not initiated by the contractor.

The department will assess Lane Rental Fee Assessment by the dollar under the administrative item Failing to Open Road to Traffic. The total dollar amount of Lane Rental Fee Assessment will be computed by multiplying the Lane Rental Assessment Rate by the number of 15-minute increments of each lane closure event as described above.

Lane Rental Fee Assessment will be in effect from the time of the Notice to Proceed until the department issues final acceptance. If interim completion time or contract time expires before the completion of specified work in the contract, additional liquidated damages will be assessed as specified in standard spec 108.11 or as specified within this contract.

stp-108-070 (20161130)

12. Erosion Control.

Supplement standard spec 107.20 with the following:

Erosion control best management practices (BMP's) the plans show are at suggested locations. The actual locations shall be determined by the contractor's ECIP and by the engineer. Include each dewatering (mechanical pumping) operation in the ECIP submittal. The ECIP shall supplement information the plans show and not reproduce it. The ECIP shall identify how to implement the project's erosion control plan. ECIP shall demonstrate timely and diligently staged operations, continuing all construction operations methodically from the initial removals and topsoil stripping operations through the subsequent grading, paving, and re-application of top soil to minimize the exposure to possible erosion.

Provide the ECIP 14 days before the pre-construction conference. Provide 1 copy of the ECIP to the department and 1 copy of the ECIP to the WDNR Liaison (Kristina Betzold, (414) 263-8517, Kristina.betzold@wisconsin.gov). Do not implement the ECIP until department approval, and perform all work conforming to the approved ECIP.

Maintain Erosion Control BMP's until permanent vegetation is established or until the engineer determines that the BMP is no longer required.

Stockpile excess materials or spoils on upland areas away from wetlands, floodplains, and waterways. Install perimeter silt fence protection around stockpiles within a timeframe acceptable to the engineer. If stockpiled materials will be left for more than 14 days, install temporary seed and mulch or other temporary erosion control measures the engineer orders.

Re-apply topsoil on graded areas, as designated by the engineer, within a timeframe acceptable to the engineer after grading is completed within those areas. Seed, fertilize, and mulch/erosion mat top-soiled areas, as designated by the engineer, within 5 days after placement of topsoil. If graded areas are left not completed and exposed for more than 14 days, seed those areas with temporary seed and mulch.

Do not allow excavation for; structures, utilities, grading, maintaining drainage that requires dewatering (mechanical pumping) of water containing sediments (sand, silt, and clay particles) to leave the work site or discharge to a storm water conveyance system without sediment removal treatment. Before each dewatering operation, submit to the department a separate ECIP amendment describing in words and

pictorial format an appropriate BMP for sediment removal, conforming to WisDNR Storm Water Construction Technical Standard, Code 1061, Dewatering. Include reasoning, location, and schedule duration proposed for each operation. Per Code 1061, include all selection criteria: site assessment, dewatering practice selection, calculations, plans, specifications, operations, maintenance, and location of proposed treated water discharge. Provide a stabilized discharge area. If directing discharge towards or into an inlet structure, provide additional inlet protection for back-up protection. Dewatering is considered incidental to the project.

sef-107-010 (20170323)

13. Notice to Contractor, Verification of Asbestos Inspection, No Asbestos Found.

Ross Hartwick, License Number All-195369, inspected Structure B-40-880 for asbestos on December 10, 2018. No regulated Asbestos Containing Material (RACM) was found on this structure. A copy of the inspection report is available from: WisDOT Southeast Region Office, Chris Zacharias, 414-750-4955; christopher.zacharias@dot.wi.gov.

stp-107-127 (20120615)

14. Removing Electrical Wires from Conduit, Item 204.9090.S.10.

A Description

This special provision describes removing electrical wires from existing conduits and disposing of the resulting material as the plans show, conforming to standard spec 204, and as follows. The existing conduit shall be removed and replaced with the parapet construction.

B (Vacant)

C Construction

No removal work shall be permitted without approval from the engineer. Removal shall start as soon as the temporary lighting or permanent lighting, as applicable, is placed in approved operation. An inspection and approval by the engineer will take place before any associated proposed permanent or temporary lighting is approved for operation.

All electrical wires shall be removed from the existing embedded or underground conduits as the plans show and as the engineer directs. Any necessary splices or disconnections shall be done as part of this pay item. Removed wires become the property of the contractor. Properly dispose of all material off the project site.

D Measurement

The department will measure Removing Electrical Wires from Conduit by the linear foot, acceptably completed. The vertical length and wire slack shall be incidental.

E Payment

Add the following to standard spec 204.5:

ITEM NUMBER	DESCRIPTION	UNIT
204.9090.S.10	Removing Electrical Wires from Conduit	LF

15. Nighttime Work Lighting-Stationary.

A Description

This special provision describes furnishing portable lighting as necessary to complete nighttime work. Nighttime operations consist of work specifically scheduled to occur after sunset and before sunrise.

B (Vacant)

C Construction

C.1 General

This provision shall apply when providing, maintaining, moving, and removing portable light towers and equipment-mounted lighting fixtures for nighttime stationary work operations, for the duration of nighttime work on the contract.

At least 14 days before the nighttime work, furnish a lighting plan to the engineer for review and acceptance. Address the following in the plan:

1. Layout, including location of portable lighting – lateral placement, height, and spacing. Clearly show on the layout the location of all lights necessary for every aspect of work to be done at night.
2. Specifications, brochures, and technical data of all lighting equipment to be used.
3. The details on how the luminaires will be attached.
4. Electrical power source information.
5. Details on the louvers, shields, or methods to be employed to reduce glare.
6. Lighting calculations. Provide illumination with average to minimum uniformity ratio of 5:1 or less throughout the work area.
7. Detail information on any other auxiliary equipment.

C.2 Portable Lighting

Provide portable lighting that is sturdy and free standing and does not require any guy wires, braces, or any other attachments. Furnish portable lighting capable of being moved as necessary to keep up with the construction project. Position the portable lighting and trailers to minimize the risk of being impacted by traffic on the roadway or by construction traffic or equipment. Provide lightning protection for the portable lighting. Portable lighting shall withstand up to 60 mph wind velocity.

If portable generators are used as a power source, furnish adequate power to operate all required lighting equipment without any interruption during the nighttime work. Provide wiring that is weatherproof and installed according to local, state, federal (NECA and OSHA) requirements. Equip all power sources with a ground-fault circuit interrupter to prevent electrical shock.

C.3 Light Level and Uniformity

Position (spacing and mounting height) the luminaires to provide illumination with an average to minimum uniformity ratio of 5:1 or less throughout the work area.

Illuminate the area as necessary to incorporate construction vehicles, equipment, and personnel activities.

C.4 Glare Control

Design, install, and operate all lighting supplied under these specifications to minimize or avoid glare that interferes with all traffic on the roadway or that causes annoyance or discomfort for properties adjoining the roadway. Locate, aim, and adjust the luminaires to provide the adequate level of illumination and the specified uniformity in the work area without the creation of objectionable glare.

Provide louvers, shields, or visors, as needed, to reduce any objectionable levels of glare. As a minimum, ensure the following requirements are met to avoid objectionable glare on the roadways open to traffic in either direction or for adjoining properties:

1. Aim tower-mounted luminaires, either parallel or perpendicular to the roadway, so as to minimize light aimed toward approaching traffic.
2. Aim all luminaires such that the center of beam axis is no greater than 60 degrees above vertical (straight down).

If lighting does not meet above-mentioned criteria, adjust the lighting within 24 hours.

C.5 Continuous Operation

Provide and have available sufficient fuel, spare lamps, generators, and qualified personnel to ensure that the lights will operate continuously during nighttime operation. In the event of any failure of the lighting system, discontinue the operation until the adequate level of illumination is restored. Move and remove lighting as necessary.

D (Vacant)

E Payment

Costs for furnishing a lighting plan, and for providing, maintaining, moving, and removing portable lighting, tower mounted lighting, and equipment-mounted lighting required under this special provision are incidental to the contract.

stp-643-010 (20100709)

16. Traffic Control Interim Lane Closure, Item 643.4100.S.

A Description

This special provision describes closing a freeway/expressway traffic lane.

B (Vacant)

C Construction

Install and reposition traffic control devices as required to close a traffic lane. Remove and return the devices to their previous configuration when the closure is no longer required.

D Measurement

The department will measure Traffic Control Interim Lane Closure as each individual reposition/return cycle acceptably completed. The department will not measure additional moves or configuration changes as might be required solely to accommodate the contractor's operations.

The department will measure the closures by traffic lane and roadway. The department will not measure multiple closures in the same traffic lane on a project.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
643.4100.S	Traffic Control Interim Lane Closure	EACH

Payment is full compensation for closing and re-opening the affected traffic lane.

stp-643-030 (20170615)

17. Lighting Systems.

A General

Add the following to standard spec 651

All the work necessary to comply with revisions to standards specifications mentioned herewith shall be incidental to associated pay items or to the project including coordination, materials, and labor. No additional payment will be made to the contractor.

The lighting system is owned and maintained by the City of Wauwatosa. Please direct questions about the existing lighting system to Mr. Randy Michelz, City of Wauwatosa – Traffic & Electrical Superintendent, (414) 471-8429; rmichelz@wauwatosa.net.

Add the following to standard spec 651.3.1:

Any circuit that the contractor does not personally tag out at the disconnect shall be considered live and will be subject to being activated by another person with no notice to the contractor. Make tagouts with manufactured tags and endorse them with the date and the name of the contractor. Clear tagouts at the end of the workday. The department does not employ a load dispatcher and has no intent to do so. Each electrical worker is responsible for their own protection from automatic switching and from switching by others.

The plans show required disconnections of existing lighting circuits, most in the form of abandoning existing underground conductors in place. The contractor may need to mobilize several times per each existing lighting distribution center. The contractor is expected to build these costs into the various paid items for removals and installations.

Add the following to standard spec 651.5:

Work to disconnect and connect conductors will be incidental to the paid measurement of footage.

Work to disconnect and connect electrical system, splice through, or to connect conductors are incidental to the installation or removal of the roadway lighting pay items included in this contract. The department will not measure conductors or conduits that have been abandoned in place or removed for scrap. The department will allow, at the contractor's discretion, for the salvaging of conductors to be abandoned, if possible.

18. HPC Masonry Structures, Item SPV.0035.01.

This special provision describes specialized material and construction requirements for high-performance concrete used in bridge structures. Conform to standard spec 501, 502 and 509, as modified in this special provision. This special provision also describes QMP concrete pavement and structures. Conform to standard spec 715 as modified in this special provision.

Modify the standard spec as follows:

501.2.5.4.1 General

Replace the entire text with the following:

- (1) Use clean, hard, durable crushed limestone with 100percent fractured surfaces and free of an excess of thin or elongated pieces, frozen lumps, vegetation, deleterious substances or adherent coatings considered injurious.
- (2) Use virgin aggregates only.

501.2.5.4.2 Deleterious Substances

Replace paragraph one with the following:

- (1) The quantity of deleterious substances must not exceed the following percentages:

DELETERIOUS SUBSTANCE	PERCENT BY WEIGHT
Shale	1.0
Coal	1.0
Clay lumps	0.3
Soft fragments	5.0
Any combination of above	5.0
Thin or elongated pieces based on a 3:1 ratio	15.0
Materials passing the No. 200 sieve.....	1.5
Chert ^[1]	1.0

^[1] Material classified lithologically as chert and having a bulk specific gravity (saturated surface-dry basis) of less than 2.45. Determine the percentage of chert by dividing the weight of chert in the sample retained on a 3/8-inch sieve by the weight of the total sample.

501.2.5.4.3 Physical Properties

Replace paragraph one with the following:

- (1) The department will ensure that Los Angeles wear testing conforms to AASHTO T 96, soundness testing conforms to AASHTO T 104 using 5 cycles in sodium sulfate solution on aggregate retained on the No. 4 sieve, and freeze-thaw soundness testing conforms to AASHTO T 103. The percent wear must not exceed 30, the weighted soundness loss must not exceed 6 percent, and the weighted freeze-thaw average loss must not exceed 15 percent.

501.2.9 Concrete Curing Materials

Replace the entire text with the following:

- (1) Furnish burlap conforming to AASHTO M 182, class 1, 2, 3 or 4.

501.3.2.4.3.3 Extended Delivery Time

Delete paragraph one.

501.3.5.1 General

Replace paragraph one with the following:

- (1) Use central-mixed concrete as defined in 501.3.5.1(2) for all work under this special provision.

501.3.5.2 Delivery

Replace paragraph three with the following:

- (3) Deliver and discharge all concrete within one hour beginning when adding water to the cement, or when adding cement to the aggregates. A decrease in air temperature below 60 F or the use of department-approved retarders does not increase the discharge time.

501.3.7.1 Slump

Replace the entire text with the following:

- (1) Use a 2-inch to 4-inch slump
- (2) Perform the slump tests for concrete according to AASHTO T 119.

501.3.8.2.1 General

Replace paragraphs one and two with the following:

- (1) Take the following steps to ensure the quality of the concrete placed. Submit a written temperature control plan at or before the pre-pour meeting. In that plan, outline the actions to control concrete temperature if the concrete temperature at the point of placement exceeds 80 F. Do not place concrete without the engineer's written acceptance of that temperature control plan. Perform the work as outlined in the temperature control plan.
- (2) If the concrete temperature at the point of placement exceeds 80 F, do not place concrete for items covered in this special provision.

501.3.8.2.2 Bridge Decks

Replace the entire text with the following:

- (1) Do not place concrete for bridge decks when the air temperature is above 80 F.
- (2) For concrete placed in bridge decks, submit a written evaporation control plan at each pre-pour meeting. In that plan, outline the actions to maintain concrete surface evaporation at or below 0.15 pounds per square foot per hour. Do not place concrete for bridge decks without the engineer's written acceptance of that evaporation control plan. If the engineer accepts an evaporation control plan calling for ice, the

department will pay \$0.75 per pound for that ice. Perform the work as outlined in the evaporation control plan.

- (3) If predicting a concrete surface moisture evaporation rate exceeding 0.15 pounds per square foot per hour, do not place concrete for bridge decks.
- (4) Provide evaporation rate predictions to the engineer 24 hours before each bridge deck pour.
- (5) Compute the evaporation rate from the predicted air conditions at the time and place of the pour using the nomograph, or computerized equivalent, specified in CMM 5.25, figure 1. Use weather information from the nearest national weather service station. The engineer will use this information to determine if the pour will proceed as scheduled.
- (6) At least 8 hours before each pour, the engineer will inform the contractor in writing whether or not to proceed with the pour as scheduled. If the actual computed evaporation rate during the pour exceeds 0.15 pounds per square foot per hour, at the engineer's discretion, the contractor may be allowed to implement immediate corrective action and complete the pour. If the engineer allows the placement to continue, the department will pay \$0.75 per pound for the quantity of ice required to maintain the concrete surface evaporation at or below 0.15 pounds per square foot per hour.

502.3.2.1 Detailed Plans

Replace the entire text with the following:

- (1) As specified in 105.2, submit four copies of detailed plans and computations for falsework, signed and sealed by a professional engineer registered in the State of Wisconsin, three weeks before erection of falsework for review and acceptance. Acceptance of the detailed plans and computations will in no way relieve the contractor of the responsibility of providing a safe and stable structure and obtaining satisfactory results.

502.3.5.4 Superstructures

Delete paragraph six.

502.3.7.8 Floors

Replace paragraph five with the following:

- (5) Set the rails or tracks that the finish machine rides on, to the required elevation; and ensure they adjust to allow for settlement under load. Support the rails or tracks outside the limits of the finished riding surface. Do not support rails or tracks on the tops of girders, or within the finished riding surface, without the engineer's written permission.

Delete paragraph thirteen, fourteen, and fifteen.

Add the following to the end as paragraphs nineteen, twenty, twenty-one, twenty-two, and twenty three:

- (19) Do not place bridge deck concrete more than 10 feet ahead of the finishing machine. If there is a delay of more than 10 minutes during the placement of a bridge deck, cover all concrete (unfinished and finished) with wet burlap to protect the concrete from evaporation until placement operations resume.
- (20) Keep hand finishing, except for the edge of deck, to a minimum. Equip the finishing machine with a pan behind the screed. Apply micro texture using a broom or turf drag following the use of a 10-foot straight edge. Only finish by hand as necessary to close up finished concrete. Begin wet curing the deck within a timeframe acceptable to the engineer following the micro texture.
- (21) For bridge decks with a design speed of 40 mph or greater, provide longitudinal grooving according to the provision included in this contract.

- (22) Place HPC Masonry Structures for bridge decks during nighttime hours. Begin work no earlier than two hours before sunset and end no later than 2 hours after sunrise; unless alternate begin and end times are approved before the concrete placement by the engineer. To determine acceptable hours, use the sunset and sunrise times published by the National Weather Service for the proposed date of the concrete placement or as mutually agreed to by the contractor and the engineer.
- (23) Provide lighting as necessary to safely perform the required work and facilitate inspection during nighttime hours. Ensure that lighting does not interfere with or impede traffic on open roadways and does not cause glare, shine or directly face the eyes of oncoming drivers. After initial setup, drive through and observe the lighted work area from each direction on the main roadway. Adjust lighting alignment if lighting causes glare, shine or directly faces the eyes of oncoming drivers.

502.3.8.1 General

Replace paragraph one with the following:

- (1) Maintain adequate moisture throughout the concrete mass to support hydration for at least 14 days.

502.3.8.2.1 General

Replace the entire text with the following:

- (1) Wet-cure the concrete for bridge decks, structural approach slabs, sidewalks on bridges and raised medians on bridges for 14 days by use of a soaker hose system, or other engineer-approved methods. Cover the finished surface of bridge decks and overlays with one layer of wetted burlap or wetted cotton mats within 10 minutes after the finishing machine has passed. Apply the burlap/cotton gently to minimize marking of the fresh concrete. Keep the first layer of burlap/cotton continuously wet until the bridge deck or overlay is sufficiently hard to apply a second layer of wetted burlap/cotton. Immediately after applying the second layer of burlap/cotton, continue to keep the deck wet until placing and activating the soaker hose system. Throughout the remainder of the curing period, keep the burlap/cotton continuously wet with soaker hoses hooked up to a continuous water source. Inspect the burlap/cotton twice daily to ensure the entire surface is moist. If necessary, alter the soaker hose system as needed to ensure the entire surface is covered and stays moist. After 48 hours from the time of completion of the bridge deck or overlay pour, the soaker hose system and burlap/cotton may be covered with polyethylene sheeting. Provide a continuous flow of water through the soaker hose system for the entire curing period.
- (2) Do not uncover any portion of the deck during the first 7 days of the curing period except as allowed by the engineer.
- (3) Set up and test the fogging system before each bridge deck, structural approach slab, bridge mounted sidewalk or bridge mounted raised median pour. Keep the fogging system set up and operational during the pour.

502.3.8.2.3 Decks

Delete the entire text.

502.3.8.2.4 Parapets

Replace the entire text with the following:

- (1) Cure the inside and outside concrete faces and tops of railings or parapets by covering with wetted burlap within a timeframe acceptable to the engineer after form removal and surface finish application. Keep the burlap thoroughly wet for at least 7 days; or by covering for the same period with thoroughly wet polyethylene-coated burlap conforming to 502.2.6.4
- (2) Secure coverings along all edges to prevent moisture loss.

502.3.9.6 Bridge Decks

Replace paragraph two with the following:

- (2) Protect the underside of the deck, including the girders, for bridge deck and overlay pours by housing and heating when the national weather service forecast predicts temperatures to fall below 32° F during the cold weather protection period. Maintain a minimum temperature of 40° F in the enclosed area under the deck for the entire 14-day curing period.

502.5.1 General

Replace paragraph one with the following:

- (1) The department will pay for plan quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0035.01	HPC Masonry Structures	CY

Lighting for nighttime bridge deck placement is included.

710.5 Sampling and Testing

Add the following subsection:

710.5.7 Chloride Penetration Resistance

- (1) For each new or changed mix design, measure chloride penetration resistance according to AASHTO T 277 (Rapid Chloride Permeability Test) at a frequency of 1 test per 3 months (quarterly) of production.
- (2) Strip permeability samples for AASHTO T 277 testing of their molds and wet cure to an age of 7 days in a standard moist room or water tank. After 7 days, submerge the samples in water heated to 100 F until an age of 28 days. Upon completion of the curing process, obtain one sample from each cylinder and test according to AASHTO T 277.
- (3) Ensure that the initial accepted mix designs meet the chloride penetration resistance limit of 1500 coulombs based on the AASHTO T 277 Rapid Chloride Permeability test. Chloride resistance testing conducted quarterly using AASHTO T 277 Rapid Chloride Permeability Test during production will not be used for acceptance of previously accepted mixes and concrete masonry mixed and placed according to the contract requirements. For quarterly chloride resistance test results exceeding 1500 coulombs, the department may require adjustment of the concrete mix going forward to improve the chloride penetration resistance.

715.2.3.2 Structures

Replace paragraph one with the following:

- (1A) Develop and test each mix to be used for HPC Masonry Structures. Produce a laboratory trial mix for each mix, as well as a trial mix from each plant used to supply the project. Test all mixes at a department-qualified laboratory.
- (1B) The laboratory trial mix data must include the results of the following tests:
 1. AASHTO T 119 Slump of Hydraulic Cement Concrete.
 2. AASHTO T 121 Mass per Cubic Foot, Yield
 3. AASHTO T 152 Air Content.
 4. AASHTO T 22 Compressive Strength.
 5. AASHTO T 277 Rapid Determination of the Chloride Permeability of Concrete, using the modified curing procedure according to 710.5.7 (2) in this special provision.
 6. AASHTO T 309 Temperature.
 7. Water Cement Ratio.
- (1C) The 28-day compressive strength must be at least 4000 psi. The 28-day results of the permeability test must be at most 1500 coulombs.

Replace paragraph two with the following:

- (2) Provide a cementitious content within a range of 470 to 540 pounds per cubic yard. For all superstructure and substructure concrete, unless the engineer approves otherwise in writing, conform to one of the following:
 1. Use class C fly ash, class F fly ash, or grade 100 or 120 slag as a partial replacement for portland cement. For binary mixes use fly ash within a range of 15 to 30 percent or slag within a range of 20 to 30 percent. For ternary mixes use fly ash plus slag in combination within a range of 15 to 30 percent. Percentages are stated as percent by weight of the total cementitious material in the mix.
 2. Use a type IP, IS, or IT blended cement.

sef-715-005 (20180104)

19. Traffic Control Close-Open Freeway Entrance Ramp, Item SPV. 0060.01.

A Description

This special provision describes closing and re-opening a freeway entrance ramp and associated auxiliary lane.

B (Vacant)

C Construction

Install or reposition traffic control devices required for closing a freeway entrance ramp and adjacent auxiliary lanes. Remove or return traffic control devices to their previous configuration when the closure is no longer required.

D Measurement

The department will measure Traffic Control Close-Open Freeway Entrance Ramp by each individual ramp closure, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV. 0060.01	Traffic Control Close-Open Freeway Entrance Ramp	EACH

Payment is full compensation for daily surveillance; preparing and submitting the daily surveillance report with hourly metered tickets; mobilization; sweeping; and disposing of materials. Traffic Control devices will be paid separately.

sef-643-001 (20180627)

20. Traffic Control Full Freeway Closure, Item SPV. 0060.02.

A Description

This special provision describes closing and re-opening a freeway or expressway.

B (Vacant)

C Construction

Install or reposition traffic control devices required for a full freeway closure. Remove or return traffic control devices to their previous configuration when the full closure is no longer required.

D Measurement

The department will measure Traffic Control Full Freeway Closure by each individual freeway closure that is set up and later removed in each traffic direction, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV. 0060.02	Traffic Control Full Freeway Closure	EACH

Payment is full compensation for closing and re-opening the freeway. Traffic Control devices will be paid separately.

sef-643-003 (20180627)

21. Fence Gate Salvaged, Item SPV.0060.03.

A Description

This special provision describes removing, handling, storing, and re-installing of fence gate units at the locations the plans show, conforming to standard spec 204 and 616, and as follows.

B Material

C Construction

Any fence gate material damaged while removing, handling, storing, and re-installing shall be replaced or repaired by the contractor at no additional cost to the department.

Re-installation of the fence gate unit shall conform to plan details and standard spec 616.

Dispose of all surplus materials off the project site.

D Measurement

The department will measure the Fence Gate Salvaged by each individual unit, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0060.03	Fence Gate Salvaged	EACH

Payment is full compensation for removing, handling, and storing; for re-installing; for disposing of materials; and for providing all other materials required to re-install the salvaged fence gate unit.

22. Field Facilities Office Space, Item SPV.0060.04.

A Description

This special provision describes furnishing, equipping, and maintaining a field office as required in the contract at engineer-approved locations conforming to standard spec 642 and as follows.

B Materials

Provide Field Facilities Office Space conforming to standard spec 642.2.1 except delete paragraphs (1), (7), and (9).

Replace standard spec 642.2.1(4) with the following:

Provide and maintain suitable interior sanitary facilities conforming to State and local health requirements, in clean and good working condition, and stock with sanitary supplies for the duration of the contract. Furnish office space in an existing office building or existing building converted to office space with a minimum of 800 square feet. The facility shall have no fee parking with a minimum parking for 10 cars. The space shall include a meeting room with a minimum of 300 square feet. The exterior door(s) shall have locks in good working order and keys provided for all field staff. The office space shall be located within 2 miles of the construction project.

Equip the office as specified in standard spec 642.2.2.1 except delete paragraph (1) and (4) and add the following:

1. Three suitable office desks with drawers
2. Three ergonomically correct office chairs in working condition with at a minimum: 5-legged base with casters, seat adjustable from 15 to 22 inches from the floor with a seamless waterfall, rounded, front edge, and high backrest with no arms or adjustable arms.
3. Two 6-foot folding tables.
4. One 10-foot folding table.
5. Three 2-drawer file cabinets.
6. Three 4-shelf bookcases.
7. Ten folding chairs.

Provide for the professional cleaning of the field office during regular business hours twice monthly. Provide clearly marked recycling and waste receptacles within the field office, and separate recycling and waste dumpsters near the field office. Cover outdoor containers to keep out rain, snow, and wind-driven debris. Provide regularly scheduled recycling and waste pick-up.

The field office will be maintained for the engineer for a duration of two months after the contract completion date.

C Construction

Conform to standard spec 642.3 except delete paragraph (2).

D Measurement

The department will measure the Field Facilities Office Space as each office, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0060.04	Field Facilities Office Space	EACH

Payment is full compensation for providing, equipping, securing, and maintaining the facility; for parking, for telecommunications equipment, installation, and service fees; and for providing bottled water, utilities, ventilation, and toilet facilities as required, either independently or jointly with the field laboratory, for the time specified in standard spec 642.3.

The department will pay for the cost of telecommunications usage fees incurred by department staff.

SER-642-002 (20160808)

23. Lighting Units Salvaged, Item SPV.0060.10.

A Description

This special provision describes the removing, handling, storing, and re-installing of lighting units consisting of pole, arm, luminaire, wires, breakaway device, and associated hardware and appurtenances at the locations the plans show, conforming to standard spec 657 and 659, and as follows.

B Material

C Construction

No removal work will be permitted without approval from the engineer. Removal shall start as soon as the temporary lighting or permanent lighting, as applicable, is placed in approved operation. An inspection and approval by the engineer will take place before any associated proposed permanent or temporary lighting is approved for operation.

Any lighting unit damaged while removing, handling, storing, and re-installing shall be replaced or repaired by the contractor at no additional cost to the department.

Re-installation of the lighting units conforming to standard spec 657.3 and 659.3.

Dispose of all surplus materials off the project site.

D Measurement

The department will measure the Lighting Units Salvaged by each individual unit, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0060.10	Lighting Units Salvaged	EACH

Payment is full compensation for removing, handling, and storing; for re-installing; and for providing all other materials required to re-install the salvaged lighting unit and lamp disposal.

SER-657.2 (20171021)

24. Fence Temporary 6-FT, Item SPV.0090.01.

A Description

This special provision describes furnishing, erecting and maintaining temporary chain link fence 6-foot including gates, as shown on the plans and as directed by the engineer, according to spec 616, and as hereinafter provided.

B Materials

Fencing parts furnished do not have to be new materials. Used, re-rolled and open seam materials will be permitted. Gates shall be a minimum of 12 feet wide.

C Construction

Fence posts may be driven into the ground or set in augured holes, backfilled and compacted. Minimum embedment shall be 4 feet. In paved areas fence posts shall be fastened to either temporary concrete barrier or the pavement by methods ensuring a secure enclosure. Where fence is installed in areas that are not to be disturbed by subsequent construction activities, the disturbed area shall be restored in kind at no additional cost to the department.

D Measurement

The department will measure Fence Temporary 6-FT in place by the linear foot from end posts, center to center, along the ground line, acceptably completed. Temporary fence will be measured once for payment. Additional measurement for fence maintenance and removal will not be made.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0090.01	Fence Temporary 6-FT	LF

Payment is full compensation for furnishing all materials; erecting posts, gates and fence; maintain fencing; removing and disposing of fencing; and for restoring disturbed areas.

25. Remove and Replace Fence Decorative Bridge, Item SPV.0105.01.

A Description

This special provision describes removing, storing, and reinstalling the existing fence decorative bridge located in the areas of parapet removal on span two on the south side of bridge B-40-880; and the removing, storing, and reinstalling of the existing railing pipe on retaining wall R-40-758 at the locations the plans show.

B (Vacant)

C Construction

Complete all operations necessary to remove those sections of existing fence decorative bridge and railing pipe located in the areas of parapet removal without any damage to the fence and railing. Remove fence decorative bridge and railing pipe prior to the start of parapet removal to ensure no damage is done during the rehabilitation work. Label fence and railing pipe sections as necessary to ensure each section is replaced in the same location as it was removed. Store fence and railing sections in a safe and secure location ensuring no damage is done during storage. After the new parapet is in place, reinstall the sections of fence and railing in their original locations. Anchor bolts to be drilled and installed as necessary, bolt type and anchoring specified in plans.

D Measurement

The department will measure Remove and Replace Fence Decorative Bridge as a single lump sum, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0105.01	Remove and Replace Fence Decorative Bridge	LS

Payment is full compensation for removing, properly storing and reinstalling the fence decorative bridge and railing pipe; for repairing any damage caused by the contractor; and for all materials and incidentals necessary to complete the work.

26. Survey Project 1100-25-80, Item SPV.0105.02.

A Description

This special provision describes modifying standard spec 105.6 and 650 to define the requirements for construction staking for this contract. Conform to standard spec 105.6 and 650 and as follows.

The department will not perform any construction staking for this contract. Obtain engineer's approval before performing all survey required to lay out and construct the work under this contract.

Replace standard spec 650.1 with the following:

This section describes the contractor-performed construction staking required under individual contract bid items to establish the horizontal and vertical position for all aspects of construction including:

- bridge structure layout
- supplemental control
- traffic control items

B (Vacant)

C Construction

Add the following to standard spec 650.3.1 (5):

Confirm with engineer before using global positioning methods to establish the following:

1. Structure layout horizontal or vertical locations.

Replace standard spec 650.3.1(6) with the following:

(6) Maintain neat, orderly, and complete survey notes, drawings, and computations used in establishing the lines and grades. This includes:

- Raw data files
- Digital stakeout reports
- Control check reports
- Supplemental control files (along with method used to establish coordinates and elevation)
- Calibration report

Make the survey notes and computations available to the engineer within 24 hours as the work progresses unless a longer period is approved by the engineer.

D Measurement

Replace standard spec 650.4 with the following:

(1) The department will measure Survey Project 1100-25-80 as a separate single lump sum unit, acceptably completed.

E Payment

Replace standard spec 650.5 with the following:

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0105.02	Survey Project 1100-25-80	LS

Payment is full compensation for performing all survey work required to lay out and construct all work under this contract and for adjusting stakes to ensure compatibility with existing field conditions. The department will not make final payment for this item until the contractor submits all survey notes and computations used to establish the required lines and grades to the engineer within 24 hours of completing this work. Re-staking due to construction disturbance and knock-outs will be performed at no additional cost to the department.

sef-650-005 (20181219)

ADDITIONAL SPECIAL PROVISION 4

Payment to First-Tier Subcontractors

Within 10 calendar days of receiving a progress payment for work completed by a subcontractor, pay the subcontractor for that work. The prime contractor may withhold payment to a subcontractor if, within 10 calendar days of receipt of that progress payment, the prime contractor provides written notification to the subcontractor and the department documenting "just cause" for withholding payment.

The prime contractor may also withhold routine retainage from payments due subcontractors.

Payment to Lower-Tier Subcontractors

Ensure that subcontracting agreements at all tiers provide prompt payment rights to lower-tier subcontractors that parallel those granted first-tier subcontractors in this provision.

Release of Routine Retainage

After granting substantial completion the department may reduce the routine retainage withheld from the prime contractor to 75 percent of the original total amount retained.

When the Department sends the semi-final estimate the department may reduce the routine retainage withheld from the prime contractor to 10 percent of the original total amount retained.

Within 30 calendar days of receiving the semi-final estimate from the department, submit written certification that subcontractors at all tiers are paid in full for acceptably completed work and that no routine retainage is being withheld. The department will pay the prime contractor in full and reduce the routine retainage withheld from the prime contractor to zero when the department approves the final estimate.

This special provision does not limit the right of the department, prime contractor, or subcontractors at any tier to withhold payment for work not acceptably completed or work subject to an unresolved contract dispute.

ADDITIONAL SPECIAL PROVISION 6
ASP 6 - Modifications to the standard specifications

Make the following revisions to the standard specifications:

107.17.1 General

Replace paragraph seven with the following effective with the December 2018 letting:

- (7) Have a professional engineer registered in the state of Wisconsin sign and seal the shop drawings. At least 30 calendar days before starting falsework, form, or shoring construction; submit a PDF file of shop drawings to the railroad's chief engineering officer and to the engineer. The engineer and the railroad may review the shop drawings. If the engineer or the railroad finds the shop drawings unsatisfactory, the contractor shall make the required changes. A satisfactory shop drawing review does not relieve the contractor of responsibility and liability for the structural integrity and proper functioning of the falsework, forms, or shoring.
-

109.1.1 General

Replace the entire text with the following effective with the January 2019 letting:

- (1) The engineer will use the US standard system to measure all work completed under the contract. The engineer will determine quantities of materials the contractor furnishes and work the contractor performs using measurement methods and computations conforming to standard engineering practice, modified to meet department requirements. The engineer will document these measurements using department procedures.
- (2) The engineer will measure the work as the contract measurement subsection for individual items specifies. The department will measure the actual quantities of work the contractor acceptably completes and make final payment based on those actual measured quantities except as follows:
 1. If the measurement subsection for a bid item specifically restricts the quantity measured for payment or allows for use of conversion factors.
 2. If the engineer executes a contract change order modifying the method of measurement for specific bid items, the engineer will measure the quantities of applicable bid items for payment using the change order methods.
 3. If the engineer, under 105.3.1(2), approves a contractor-requested plan dimension change between US standard and SI metric dimensions, the engineer will measure whichever of the following is less:
 - Actual quantities constructed.
 - Quantities derived from the original plan dimensions.
 4. For substitutions made under 106.2.3 between US standard and SI metric products, the engineer will measure the actual quantities of the substitute products using the original contract measuring system.

205.5.2 Excavation

Replace the entire text with the following effective with the April 2019 letting:

205.5.2.1 General

- (1) Payment for the Excavation bid items under this section is full compensation for work specified for those excavation classes under 205 with no separate contract bid items; for hauling; and for constructing and removing temporary drainage installations as specified under 205.3.3.
- (2) Payment also includes removing walls, foundations, etc. with no separate contract bid items; for disposal of resulting material; and for backfilling basements or openings resulting from removing walls, foundations, etc.

205.5.2.2 Associated Work

- (1) The department will pay separately for removing concrete structures under the 203 and 204 bid items.
- (2) The department will pay separately for granular backfill the contract or engineer requires under the Backfill Granular bid items.
- (3) The department will pay separately for erosion control, fertilizing, and seeding of material disposal sites as specified for material disposal sites in 628.5.1.
- (4) If the contract does not include the Excavation Rock bid item, the department will pay 5 times the contract bid price of the Excavation Common bid item to remove boulders having volumes of one cubic yard or more. The department will pay for these boulder removals under the Removing Large Boulders administrative item.

205.5.2.3 Excavation Below Subgrade**205.5.2.3.1 General**

- (1) The department will only pay for engineer-approved EBS to correct problems beyond the contractor's control.

205.5.2.3.2 Quantity Overruns

- (1) The department will provide additional compensation for EBS quantity overruns if the following conditions are met:
 - The quantity of engineer-approved EBS, calculated exclusive of work covered under 205.5.2.3.3 or 301.5, exceeds the total contract EBS quantity the earthwork summary sheet shows by more than 25 percent.
 - The material exceeding that 25 percent threshold cannot be disposed of within the project right-of-way.
- (2) The department will pay 2 times the contract unit price, up to \$25,000, for the quantity of EBS meeting the above conditions. After exceeding \$25,000 per contract, the department will pay for additional EBS as determined under 109.4.

205.5.2.3.3 Subgrade Correction

- (1) Work performed under 105.3 to correct unacceptable work is the contractor's responsibility. For EBS work performed where the engineer did not approve the subgrade for subsequent operations, the department will pay for EBS at the contract price under the pertinent excavation and backfill bid items, or absent those bid items as extra work. For EBS work performed where the engineer approved the underlying layers for subsequent operations, the department will pay for EBS as follows:
 1. Up to a maximum of \$25,000 per contract, the department will pay as follows:
 - 1.1 For excavation: 3 times the contract unit price for the Excavation Common bid item under the EBS Post Grading administrative item.
 - 1.2 For backfill with the materials the engineer directs: at the contract unit price for the bid items of each material used to fill the excavation.
 - 1.3 For excavation or backfill without contract bid items: as extra work.
 2. After exceeding \$25,000 per contract, the department will pay for additional EBS in engineer-approved areas as determined under 109.4.

305.2.1 General

Replace paragraph two with the following effective with the December 2018 letting:

- (2) Where the contract specifies or allows 1 1/4-inch base, do not place reclaimed asphalt, reprocessed material, or blended materials below virgin aggregate materials unless the contract specifies or the engineer allows in writing. The department will allow virgin aggregate above reclaimed asphalt, reprocessed material, or blended materials in shoulder areas adjacent to concrete pavement.
-

420.3.2.1 General

Replace paragraph one with the following effective with the December 2018 letting:

- (1) Use self-propelled grinding machines with depth, grade, and slope controls designed for grinding and texturing concrete. Equip grinding machines with diamond blades and a vacuuming system capable of removing liquid and solid residue from the ground surface. Shroud the machine to prevent discharging loosened material into adjacent work areas or live traffic lanes. Provide the specified effective wheelbase, defined as the center of the front to center of the rear main support wheels.
-

420.3.2.2 Continuous Grinding

Replace paragraph one with the following effective with the December 2018 letting:

- (1) Under the Continuous Diamond Grinding Concrete Pavement bid item, ensure that the grinding machine, including the grinding head, weighs 35,000 pounds or more, will grind a strip at least 4 feet wide, and has an effective wheel base of 25 feet or more. For pavements with a design speed less than 40 miles per hour and areas difficult to access, the contractor may use equipment with an effective wheel base of 12 feet or more.
-

450.3.2.8 Jointing

Replace paragraphs three through five with the following effective with the December 2018 letting:

- (3) Construct notched wedge longitudinal joints for mainline paving if the pavement thickness conforms to the minimums specified in 460.3.2, unless the engineer directs or allows an alternate joint. Construct the wedge using a slope no steeper than 3:1. Extend the wedge 12 inches beyond the normal lane width, or as the engineer directs. Ensure that the wedge for all layers directly overlaps and slopes in the same direction.
 - (4) Locate the joint at the pavement centerline for 2-lane roadways, or at lane lines if the roadway has more than 2 lanes. Construct a vertical notch 1/2-inch to 3/4-inch high on the centerline or lane line at the top of each wedge. Place a 1/2-inch to 3/4-inch notch at the outside bottom edge of the wedge after compacting each layer. Align the finished longitudinal joint line of the upper layer with the centerline or lane line.
 - (5) Construct the wedge for each layer using an engineer-approved strike-off device that will provide a uniform slope and will not restrict the main screed. Shape and compact the wedge with a weighted steel side roller wheel the same width as the wedge. Apply a tack coat to the wedge surface and both notches before placing the adjacent lane.
-

455.2.4.3 Emulsified Asphalts

Replace paragraph two with the following effective with the December 2018 letting:

- (2) The bill of lading for emulsified asphalts shall indicate the asphalt content of the original emulsion and dilution rate of the additional water added to the original emulsion. If undiluted samples are not available, test the diluted material and modify AASHTO M140, M208, or M316 to reflect properties resulting from dilution of the asphalt.

460.2.8.3.1.4 Department Verification Testing Requirements

Replace paragraph three with the following effective with the December 2018 letting:

- (3) The department will perform testing conforming to the following standards:

Bulk specific gravity (G_{mb}) of the compacted mixture according to AASHTO T166.

Maximum specific gravity (G_{mm}) according to AASHTO T209.

Air voids (V_a) by calculation according to AASHTO T269.

VMA by calculation according to AASHTO R35.

Asphalt content by ignition oven according to AASHTO T308 as modified in CMM 8-36.6.3.6, chemical extraction according to AASHTO T-164, or Asphalt Analyzer™ according to manufacturer recommendations.

460.2.8.3.1.6 Acceptable Verification Parameters

Replace paragraph one with the following effective with the December 2018 letting:

- (1) The engineer will provide test results to the contractor within 2 mixture-production days after obtaining the sample. The quality of the product is acceptably verified if it meets the following limits:
- V_a is within a range of 2.0 to 4.3 percent. For SMA, V_a is within a range of 2.7 to 5.3 percent.
 - VMA is within minus 0.5 of the minimum requirement for the mix design nominal maximum aggregate size.
 - Asphalt content is within minus 0.3 percent of the JMF.
-

460.2.8.3.1.7 Dispute Resolution

Replace paragraph one with the following effective with the December 2018 letting:

- (1) When QV test results do not meet the specified limits for 100 percent pay, the bureau's AASHTO accredited laboratory and certified personnel will referee test the retained portion of the QV sample and the retained portion of the required forward and backward QC retained samples according to CMM 8-36.

460.5.2.1 General

Replace paragraphs five and six with the following effective with the December 2018 letting:

- (5) The department will reduce pay for nonconforming QMP HMA mixtures as specified in 460.2.8.2.1.7, starting from the stop point to the point when the running average of 4 is back inside the warning limits. The engineer will determine the quantity of material subject to pay reduction based on the testing data and an inspection of the completed pavement. The department will reduce pay as follows:

PAYMENT FOR MIXTURE^{[1] [2] [3]}		
ITEM	PRODUCED WITHIN WARNING BANDS	PRODUCED OUTSIDE JMF LIMITS
Gradation	90%	75%
Asphalt Content ^[4]	—	—
Air Voids	70%	50%
VMA	90%	75%

^[1] For projects or plants where the total production of each mixture design requires less than 4 tests refer to CMM 8-36.

^[2] Payment is in percent of the contract unit price for the HMA Pavement bid item. The department will reduce pay based on the nonconforming property with lowest percent pay. If the quantity of material subject to pay adjustment based on the running average of 4 is also subject to pay adjustment resulting from dispute resolution in accordance with 460.2.8.3.1.7, the department will apply the single pay adjustment resulting in the lowest percent pay.

^[3] In addition to any pay adjustment listed in the table above, the department will adjust pay for nonconforming binder under the Nonconforming QMP Asphaltic Material administrative item. The department will deduct 25 percent of the contract unit price of the HMA Pavement bid item per ton of pavement placed with nonconforming PG binder the engineer allows to remain in place.

^[4] The department will not adjust pay based on a running average of 4 asphalt content tests; however, corrective action will be applied to nonconforming material according to 460.2.8.2.1.7.

- (6) If during a QV dispute resolution investigation the department discovers unacceptable mixture defined by one or more of the following:
- Va greater than 5.0 or less than 1.5.
 - VMA more than 1.0 below the minimum allowed in table 460-1.
 - AC more than 0.5 % below the JMF target.

Remove and replace the material, or if the engineer allows the mixture to remain in place, the department will pay for the quantity of affected material at 50 percent of the contract price.

501.3.8.2.1 General

Replace paragraph two with the following effective with the April 2019 letting:

- (2) If the concrete temperature at the point of placement exceeds 90 F, do not place concrete under the following structure and concrete barrier bid items:

Concrete Masonry Bridges	Concrete Masonry Retaining Walls
Concrete Masonry Bridges HES	Concrete Masonry Retaining Walls HES
Concrete Masonry Culverts	Concrete Masonry Endwalls
Concrete Masonry Culverts HES	Concrete Masonry Overlay Decks
Concrete Barrier Single-Faced 32-Inch	Concrete Barrier (type)
Concrete Barrier Double-Faced 32-Inch	Concrete Barrier Fixed Object Protection (type)
Concrete Barrier Transition Section 32-Inch	Concrete Barrier Transition (type)

506.3.2 Shop Drawings

Replace paragraph four with the following effective with the December 2018 letting:

- (4) Ensure that the fabricator submits a PDF file of shop drawings for railroad structures to the railroad company's chief engineering officer upon contract completion.

603.3.1.1 General

Replace paragraph three with the following effective with the April 2019 letting:

- (3) Cast permanent barrier and transitions in place. Use construction methods conforming to 502 and conform to the hot weather placement requirements of 501.3.8.2. Use forms or engineer-approved slip form methods for barrier. Use forms for transitions. Construct barrier on horizontal curves as a series of 12-foot or shorter chords.

646.3.1.2 Liquid Marking

Replace paragraph five with the following effective with the January 2019 letting:

- (5) Apply liquid marking and glass beads across the line at or exceeding the following:

LIQUID MARKING	PAVEMENT TYPE	THICKNESS (mils)	BEAD APPLICATION (pounds per gallon)
Paint	all	16	8
Epoxy	SMA, seal coats, and polymer overlays	25	25
Epoxy	all other	20	22.5
Wet Reflective Epoxy	all	20	18

646.3.2.3.2 Wet Reflective Epoxy

Replace paragraph five with the following effective with the January 2019 letting:

- (1) Apply wet reflective epoxy binder in a grooved slot. and provide a double drop bead system as follows:
- First: wet reflective/recoverable elements at the application rate specified for the product chosen from the department's APL.
 - Second: glass beads at the application rate specified in 646.3.1.2(5).

650.3.1 General

Replace the entire text with the following effective with the December 2018 letting:

- (1) Department and contractor responsibilities for construction staking are specified in 105.6. Conform to 105.6 and the additional requirements specified here in 650.3 for the individual contractor-staking bid items the contract includes.
- (2) Protect and preserve known property and survey marks and land monuments as specified in 107.11.3. The contract may require related work under the 621 bid items.
- (3) Obtain or calculate benchmark data, grades, and alignment from plan information. The engineer will furnish data for the horizontal and vertical control points, control point ties, horizontal alignments, profiles, and elevations. Reestablish, set additional, and maintain the horizontal and vertical control points and control point ties, as needed for bid items.
- (4) Check horizontal and vertical information including but not limited to alignments, locations, elevations, and dimensions, that either the plans show or the engineer provides, for compatibility with existing field conditions. Conduct similar compatibility checks and accuracy checks of horizontal and vertical positions either the department or the contractor establishes in the field.
- (5) Perform survey work using conventional methods, or AMG methods capable of achieving the lines and grades the plans show for the work in question. Establish additional benchmarks and control points as necessary to support the method of operation.

650.3.1.1 Staking

- (1) Furnish, set, reference, and maintain stakes and markings necessary to establish the alignment, location, benchmarks, elevations, and continuous profile-grades for road and structure work as needed for bid items. Supervise and coordinate construction staking.
- (2) Maintain neat, orderly, and complete survey notes, drawings, and computations used in establishing the lines and grades. Make the survey notes and computations available to the engineer within 24 hours, upon request, as the work progresses.
- (3) Furnish surveying equipment, stakes, flags, pins, lath, whiskers, and other materials necessary to perform this work, subject to the engineer's approval.

650.3.1.2 Automated Machine Guidance**650.3.1.2.1 General**

- (1) The contractor may substitute AMG for conventional staking on all or part of the work under the individual staking bid items. Coordinate with the engineer throughout the course of construction to ensure that work performed using AMG conforms to the contract tolerances and that the methods employed conform to the contractor's AMG work plan and accepted industry standards. Revert to conventional staking methods for all or part of the work at any point during construction if AMG is producing unacceptable results.

650.3.1.2.2 AMG Work Plan

- (1) Submit a comprehensive written AMG work plan for department review at least 5 business days before the preconstruction conference. In that plan discuss how AMG technology will be integrated into other technologies employed on the project. List the staking bid items that will have work performed using AMG and, for each bid item listed, include the following:
 1. Designate which portions of the contract will be done using AMG and which portions will be done using conventional staking.
 2. Designate a single staff person as the primary contact for AMG technology issues.
 3. List and map the primary and secondary control points required under 105.6.2 enveloping the site.
 4. Describe the contractor's quality control procedures. Include the frequency and type of checks performed to ensure that the work conforms to the contract plans.
- (2) The engineer will review the plan to determine if it conforms to the contract. Do not perform AMG work until the engineer approves the governing portion of the AMG workplan. Perform the work as the contractor's AMG work plan provides. Update the plan as necessary.

650.3.1.2.3 Geometric and Surface Information**650.3.1.2.3.1 Department Responsibilities**

- (1) At any time after the contract is awarded the contractor may request the contractor data packet. The department will provide the packet within 5 business days of receiving the contractor's request.

650.3.1.2.3.2 Contractor Responsibilities

- (1) Develop and maintain a contractor construction model for areas of the project employing AMG. Confirm that the resulting model agrees with the contract plans.
- (2) If the engineer requests, provide the construction model to the department in LandXML or other engineer-approved format.

650.3.1.2.4 Managing and Updating Information

- (1) Notify the department of any errors or discrepancies in department-provided information. The department will determine what revisions may be required. The department will revise the contract plans, if necessary, to address errors or discrepancies that the contractor identifies. The department will provide the best available information related to those contract plan revisions.
- (2) Revise the construction model as required to support construction operations and to reflect any contract plan revisions the department makes. Perform checks to confirm that the revised construction model agrees with the contract plan revisions. If the engineer requests, provide construction model updates to the engineer. The department will pay for costs incurred to incorporate contract plan revisions as extra work.

650.3.1.2.5 Construction Checks

- (1) Check the work against the plan elevation at randomly selected points on cross-sections located at stations evenly divisible by 100 at the frequency the engineer approved as a part of the AMG work plan. Submit the results of these random checks to the engineer daily. Notify the engineer immediately if a check exceeds the tolerances specified in 650.3.1.2.6 below.
- (2) Check the work at additional points as the engineer directs. The department may conduct periodic independent checks.

650.3.1.2.6 Construction Tolerances

- (1) Ensure that the finished work vertically matches existing or other completed features. Ensure that the work conforms to revised plan elevations as follows:
 - Subgrade : +/- 0.10 feet.
 - Base : within the tolerance specified in 301.3.4.1(2).

650.3.3 Subgrade

Retitle and replace the entire text with the following effective with the December 2018 letting:

650.3.3 Subgrade Staking

- (1) Set construction stakes or marks at intervals of 100 feet, or more frequently, for rural sections and at intervals of 50 feet, or more frequently, for urban sections. Include additional stakes at each cross-section as necessary to match the plan cross-section, achieve the required accuracy, and to support construction operations. Also set and maintain stakes as necessary to establish the horizontal and vertical positions of intersecting road radii, auxiliary lanes, horizontal and vertical curves, and curve transitions. Locate stakes to within 0.25 feet horizontally and establish the grade elevation to within 0.03 feet vertically.

Errata

520.3.3 Laying Pipe

Correct errata by replacing "sections" with "joints" to clarify the intent that the last 3 joints need ties.

- (5) Provide joint ties on the upstream and downstream ends of circular and horizontal elliptical concrete culvert and concrete cattle pass installations. Tie the next 3 pipe joints or, if using apron endwalls, the endwall joint and the last 2 pipe joints. Ties are not required on culverts with masonry endwalls unless the plans show otherwise.
-

608.3.3 Laying Pipe

Correct errata by replacing "sections" with "joints" to clarify the intent that the last 3 joints need ties.

- (5) Provide joint ties on concrete storm sewer system infall and outfall pipes. Tie the last 3 pipe joints or, if using apron endwalls, the endwall joint and the next 2 pipe joints. Ties are not required on installations with masonry endwalls unless the plans show otherwise.

ADDITIONAL SPECIAL PROVISION 7

- A. Reporting 1st Tier and DBE Payments During Construction
1. Comply with reporting requirements specified in the department's Civil Rights Compliance, Contractor's User Manual, Sublets and Payments.
 2. Report payments to all DBE firms within 10 calendar days of receipt of a progress payment by the department or a contractor for work performed, materials furnished, or materials stockpiled by a DBE firm. Report the payment as specified in A(1) for all work satisfactorily performed and for all materials furnished or stockpiled.
 3. Report payments to all first tier subcontractor relationships within 10 calendar days of receipt of a progress payment by the department for work performed. Report the payment as specified in A(1) for all work satisfactorily performed.
 4. All tiers shall report payments as necessary to comply with the DBE payment requirement as specified in A(2).
 5. Require all first tier relationships, DBE firms and all other tier relationships necessary to comply with the DBE payment requirement in receipt of a progress payment by contractor to acknowledge receipt of payment as specified in A(1), (2), (3) and (4).
 6. All agreements made by a contractor shall include the provisions in A(1), (2), (3), (4) and (5), and shall be binding on all first tier subcontractor relationships and all contractors and subcontractors utilizing DBE firms on the project.
- B. Costs for conforming to this special provision are incidental to the contract.

NOTE: CRCS Prime Contractor payment is currently not automated and will need to be manually loaded into the Civil Rights Compliance System. Copies of prime contractor payments received (check or ACH) will have to be forwarded to paul.ndon@dot.wi.gov within 5 days of payment receipt to be logged manually.

***Additionally, for information on Subcontractor Sublet assignments, Subcontractor Payments and Payment Tracking, please refer to the CRCS Payment and Sublets manual at:

<https://wisconsindot.gov/Documents/doing-bus/civil-rights/labornwage/crcs-payments-sublets-manual.pdf>

ADDITIONAL SPECIAL PROVISION 9

Electronic Certified Payroll or Labor Data Submittal

(1) Use the department's Civil Rights Compliance System (CRCS) to electronically submit certified payroll reports for contracts with federal funds and labor data for contracts with state funds only. Details are available online through the department's highway construction contractor information (HCCI) site on the Labor, Wages, and EEO Information page at:

<https://wisconsindot.gov/Pages/doing-bus/civil-rights/labornwage/default.aspx>

(2) Ensure that all tiers of subcontractors, including all trucking firms, either submit their weekly certified payroll reports (contracts with federal funds) or labor data (contracts with state funds only) electronically through CRCS. These payrolls or labor data are due within seven calendar days following the close of the payroll period. Every firm providing physical labor towards completing the project is a subcontractor under this special provision.

(3) Upon receipt of contract execution, promptly make all affected firms aware of the requirements under this special provision and arrange for them to receive CRCS training as they are about to begin their submittals. The department will provide training either in a classroom setting at one of our regional offices or by telephone. Contact Paul Ndon at (414) 438-4584 to schedule the training.

(4) The department will reject all paper submittals for information required under this special provision. All costs for conforming to this special provision are incidental to the contract.

(5) Firms wishing to export payroll/labor data from their computer system into CRCS should have their payroll coordinator contact Paul Ndon at paul.ndon@dot.wi.gov. Not every contractor's payroll system is capable of producing export files. For details, see Section 4.8 CPR Auto Submit (Data Mapping) on pages 49-50; 66-71 of the CRCS Payroll Manual at:

<https://wisconsindot.gov/Documents/doing-bus/civil-rights/labornwage/crcs-payroll-manual.pdf>

Non-discrimination Provisions

During the performance of this contract, the contractor, for itself, its assignees, and successors in interest (hereinafter referred to as the "contractor") agrees as follows:

1. Compliance with Regulations: The contractor (hereinafter includes consultants) will comply with the Acts and the Regulations relative to Non-discrimination in Federally-assisted programs of the U.S. Department of Transportation, Federal Highway Administration, as they may be amended from time to time, which are herein incorporated by reference and made a part of this contract.

2. Non-discrimination: The contractor, with regard to the work performed by it during the contract, will not discriminate on the grounds of race, color, or national origin in the selection and retention of subcontractors, including procurements of materials and leases of equipment. The contractor will not participate directly or indirectly in the discrimination prohibited by the Acts and the Regulations, including employment practices when the contract covers any activity, project, or program set forth in Appendix B of 49 CFR Part 21.

3. Solicitations for Subcontracts, Including Procurements of Materials and Equipment: In all solicitations, either by competitive bidding, or negotiation made by the contractor for work to be performed under a subcontract, including procurements of materials, or leases of equipment, each potential subcontractor or supplier will be notified by the contractor of the contractor's obligations under this contract and the Acts and the Regulations relative to Non-discrimination on the grounds of race, color, or national origin.

4. Information and Reports: The contractor will provide all information and reports required by the Acts, the Regulations, and directives issued pursuant thereto and will permit access to its books, records, accounts, other sources of information, and its facilities as may be determined by the Recipient or the Federal Highway Administration to be pertinent to ascertain compliance with such Acts, Regulations, and instructions. Where any information required of a contractor is in the exclusive possession of another who fails or refuses to furnish the information, the contractor will so certify to the Recipient or the Federal Highway Administration, as appropriate, and will set forth what efforts it has made to obtain the information.

5. Sanctions for Noncompliance: In the event of a contractor's noncompliance with the Non-discrimination provisions of this contract, the Recipient will impose such contract sanctions as it or the Federal Highway Administration may determine to be appropriate, including, but not limited to:

- a. Withholding payments to the contractor under the contract until the contractor complies; and/or
- b. Cancelling, terminating, or suspending a contract, in whole or in part.

6. Incorporation of Provisions: The contractor will include the provisions of paragraphs one through six in every subcontract, including procurements of materials and leases of equipment, unless exempt by the Acts, the Regulations and directives issued pursuant thereto. The contractor will take action with respect to any subcontract or procurement as the Recipient or the Federal Highway Administration may direct as a means of enforcing such provisions including sanctions for noncompliance. Provided, that if the contractor becomes involved in, or is threatened with litigation by a subcontractor, or supplier because of such direction, the contractor may request the Recipient to enter into any litigation to protect the interests of the Recipient. In addition, the contractor may request the United States to enter into the litigation to protect the interests of the United States.

During the performance of this contract, the contractor, for itself, its assignees, and successors in interest (hereinafter referred to as the "contractor") agrees to comply with the following non-discrimination statutes and authorities; including but not limited to:

Pertinent Non-Discrimination Authorities:

- Title VI of the Civil Rights Act of 1964 (42 U.S.C. § 2000d et seq., 78 stat. 252), (prohibits discrimination on the basis of race, color, national origin); and 49 CFR Part 21.
- The Uniform Relocation Assistance and Real Property Acquisition Policies Act of 1970, (42 U.S.C. § 4601), (prohibits unfair treatment of persons displaced or whose property has been acquired because of Federal or Federal-aid programs and projects);
- Federal-Aid Highway Act of 1973, (23 U.S.C. § 324 et seq.), (prohibits discrimination on the basis of sex);
- Section 504 of the Rehabilitation Act of 1973, (29 U.S.C. § 794 et seq.), as amended, (prohibits discrimination on the basis of disability); and 49 CFR Part 27;
- The Age Discrimination Act of 1975, as amended, (42 U.S.C. § 6101 et seq.), (prohibits discrimination on the basis of age);
- Airport and Airway Improvement Act of 1982, (49 USC § 471, Section 47123), as amended, (prohibits discrimination based on race, creed, color, national origin, or sex);
- The Civil Rights Restoration Act of 1987, (PL 100-209), (Broadened the scope, coverage and applicability of Title VI of the Civil Rights Act of 1964, The Age Discrimination Act of 1975 and Section 504 of the Rehabilitation Act of 1973, by expanding the definition of the terms "programs or activities" to include all of the programs or activities of the Federal-aid recipients, sub-recipients and contractors, whether such programs or activities are Federally funded or not);
- Titles II and III of the Americans with Disabilities Act, which prohibit discrimination on the basis of disability in the operation of public entities, public and private transportation systems, places of public accommodation, and certain testing entities (42 U.S.C. §§ 12131-12189) as implemented by Department of Transportation regulations at 49 C.F.R. parts 37 and 38;
- The Federal Aviation Administration's Non-discrimination statute (49 U.S.C. § 47123) (prohibits discrimination on the basis of race, color, national origin, and sex);

- Executive Order 12898, Federal Actions to Address Environmental Justice in Minority Populations and Low-Income Populations, which ensures Non-discrimination against minority populations by discouraging programs, policies, and activities with disproportionately high and adverse human health or environmental effects on minority and low-income populations;
- Executive Order 13166, Improving Access to Services for Persons with Limited English Proficiency, and resulting agency guidance, national origin discrimination includes discrimination because of Limited English proficiency (LEP). To ensure compliance with Title VI, you must take reasonable steps to ensure that LEP persons have meaningful access to your programs (70 Fed. Reg. at 74087 to 74100);
- Title IX of the Education Amendments of 1972, as amended, which prohibits you from discriminating because of sex in education programs or activities (20 U.S.C. 1681 et seq).

Effective August 2015 letting

BUY AMERICA PROVISION

All steel and iron materials permanently incorporated in this project shall be domestic products and all manufacturing and coating processes for these materials from smelting forward in the manufacturing process must have occurred within the United States. Coating includes epoxy coating, galvanizing, painting and any other coating that protects or enhances the value of a material subject to the requirements of Buy America. The exemption of this requirement is the minimal use of foreign materials if the total cost of such material permanently incorporated in the product does not exceed one-tenth of one percent (1/10 of 1%) of the total contract cost or \$2,500.00, whichever is greater. For purposes of this paragraph, the cost is that shown to be the value of the subject products as they are delivered to the project. The contractor shall take actions and provide documentation conforming to CMM 2-28.5 to ensure compliance with this "Buy America" provision.

<https://wisconsindot.gov/rdwy/cmm/cm-02-28.pdf>

Upon completion of the project certify to the engineer, in writing using department form WS4567, that all steel, iron, and coating processes for steel or iron incorporated into the contract work conform to these "Buy America" provisions. Attach a list of exemptions and their associated costs to the certification form. Department form WS4567 is available at:

<https://wisconsindot.gov/hcciDocs/contracting-info/ws4567.doc>



Proposal Schedule of Items

Page 1 of 5

Proposal ID: 20190514016 Project(s): 1100-25-80

Federal ID(s): N/A

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0002	203.0200 Removing Old Structure (station) 01. 20+14.00CE	LS	LUMP SUM	_____.
0004	204.0150 Removing Curb & Gutter	10.000 LF	_____.	_____.
0006	204.0155 Removing Concrete Sidewalk	11.000 SY	_____.	_____.
0008	204.0170 Removing Fence	3.500 LF	_____.	_____.
0010	204.9090.S Removing (item description) 10. Electrical Wires from Conduit	540.000 LF	_____.	_____.
0012	206.1000 Excavation for Structures Bridges (structure) 01. B-40-880	LS	LUMP SUM	_____.
0014	213.0100 Finishing Roadway (project) 01. 1100-25- 80	1.000 EACH	_____.	_____.
0016	502.3200 Protective Surface Treatment	109.000 SY	_____.	_____.
0018	502.3210 Pigmented Surface Sealer	13.000 SY	_____.	_____.
0020	503.0137 Prestressed Girder Type I 36W-Inch	100.000 LF	_____.	_____.
0022	505.0600 Bar Steel Reinforcement HS Coated Structures	8,740.000 LB	_____.	_____.
0024	505.0905 Bar Couplers No. 5	74.000 EACH	_____.	_____.
0026	505.0910 Bar Couplers No. 10	13.000 EACH	_____.	_____.
0028	506.2605 Bearing Pads Elastomeric Non- Laminated	2.000 EACH	_____.	_____.
0030	506.4000 Steel Diaphragms (structure) 01. B-40- 880	2.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 2 of 5

Proposal ID: 20190514016 Project(s): 1100-25-80

Federal ID(s): N/A

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0032	516.0500 Rubberized Membrane Waterproofing	2.000 SY	_____.	_____.
0034	601.0331 Concrete Curb & Gutter 31-Inch	10.000 LF	_____.	_____.
0036	602.0410 Concrete Sidewalk 5-Inch	100.000 SF	_____.	_____.
0038	603.8000 Concrete Barrier Temporary Precast Delivered	250.000 LF	_____.	_____.
0040	603.8125 Concrete Barrier Temporary Precast Installed	250.000 LF	_____.	_____.
0042	616.0206 Fence Chain Link 6-FT	3.500 LF	_____.	_____.
0044	619.1000 Mobilization	1.000 EACH	_____.	_____.
0046	625.0100 Topsoil	225.000 SY	_____.	_____.
0048	628.1504 Silt Fence	30.000 LF	_____.	_____.
0050	628.1520 Silt Fence Maintenance	30.000 LF	_____.	_____.
0052	628.1905 Mobilizations Erosion Control	2.000 EACH	_____.	_____.
0054	628.1910 Mobilizations Emergency Erosion Control	2.000 EACH	_____.	_____.
0056	628.2008 Erosion Mat Urban Class I Type B	225.000 SY	_____.	_____.
0058	628.7020 Inlet Protection Type D	15.000 EACH	_____.	_____.
0060	629.0210 Fertilizer Type B	0.080 CWT	_____.	_____.
0062	630.0130 Seeding Mixture No. 30	4.000 LB	_____.	_____.



Proposal Schedule of Items

Page 3 of 5

Proposal ID: 20190514016 Project(s): 1100-25-80

Federal ID(s): N/A

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0064	634.0618 Posts Wood 4x6-Inch X 18-FT	1.000 EACH	_____.	_____.
0066	634.0816 Posts Tubular Steel 2x2-Inch X 16-FT	1.000 EACH	_____.	_____.
0068	637.2210 Signs Type II Reflective H	10.000 SF	_____.	_____.
0070	638.2102 Moving Signs Type II	2.000 EACH	_____.	_____.
0072	638.2602 Removing Signs Type II	1.000 EACH	_____.	_____.
0074	638.3000 Removing Small Sign Supports	1.000 EACH	_____.	_____.
0076	643.0300 Traffic Control Drums	3,955.000 DAY	_____.	_____.
0078	643.0420 Traffic Control Barricades Type III	690.000 DAY	_____.	_____.
0080	643.0705 Traffic Control Warning Lights Type A	1,380.000 DAY	_____.	_____.
0082	643.0715 Traffic Control Warning Lights Type C	1,060.000 DAY	_____.	_____.
0084	643.0800 Traffic Control Arrow Boards	80.000 DAY	_____.	_____.
0086	643.0900 Traffic Control Signs	3,010.000 DAY	_____.	_____.
0088	643.0920 Traffic Control Covering Signs Type II	10.000 EACH	_____.	_____.
0090	643.1050 Traffic Control Signs PCMS	145.000 DAY	_____.	_____.
0092	643.4100.S Traffic Control Interim Lane Closure	15.000 EACH	_____.	_____.
0094	643.5000 Traffic Control	1.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 4 of 5

Proposal ID: 20190514016 Project(s): 1100-25-80

Federal ID(s): N/A

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0096	649.0150 Temporary Marking Line Removable Tape 4-Inch	280.000 LF	_____.	_____.
0098	649.0850 Temporary Marking Stop Line Removable Tape 18-Inch	60.000 LF	_____.	_____.
0100	652.0125 Conduit Rigid Metallic 2-Inch	4.000 LF	_____.	_____.
0102	652.0225 Conduit Rigid Nonmetallic Schedule 40 2-Inch	105.000 LF	_____.	_____.
0104	653.0222 Junction Boxes 18x12x6-Inch	1.000 EACH	_____.	_____.
0106	655.0620 Electrical Wire Lighting 8 AWG	180.000 LF	_____.	_____.
0108	655.0630 Electrical Wire Lighting 4 AWG	360.000 LF	_____.	_____.
0110	657.6005 Anchor Assemblies Light Poles on Structures	1.000 EACH	_____.	_____.
0112	690.0150 Sawing Asphalt	10.000 LF	_____.	_____.
0114	690.0250 Sawing Concrete	10.000 LF	_____.	_____.
0116	715.0502 Incentive Strength Concrete Structures	500.000 DOL	1.00000	500.00
0118	SPV.0035 Special 01. HPC Masonry Structures	55.000 CY	_____.	_____.
0120	SPV.0060 Special 01. Traffic Control Close-Open Freeway Entrance Ramp	20.000 EACH	_____.	_____.
0122	SPV.0060 Special 02. Traffic Control Full Freeway Closure	5.000 EACH	_____.	_____.
0124	SPV.0060 Special 03. Fence Gate Salvaged	1.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 5 of 5

Proposal ID: 20190514016 Project(s): 1100-25-80

Federal ID(s): N/A

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0126	SPV.0060 Special 04. Field Facilities Office Space	1.000 EACH	_____.	_____.
0128	SPV.0060 Special 10. Lighting Units Salvaged	1.000 EACH	_____.	_____.
0130	SPV.0090 Special 01. Fence Temporary 6-ft	200.000 LF	_____.	_____.
0132	SPV.0105 Special 01. Remove and Preplace Fence Decorative Bridge	LS	LUMP SUM	_____.
0134	SPV.0105 Special 02. Survey Project 1100-25-80	LS	LUMP SUM	_____.
Section: 0001			Total:	_____.
			Total Bid:	_____.

PLEASE ATTACH SCHEDULE OF ITEMS HERE



Wisconsin Department of Transportation

May 2, 2019

**Division of Transportation Systems
Development**

Bureau of Project Development
4822 Madison Yards Way, 4th Floor South
Madison, WI 53705

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

**Proposal #16: 1100-25-80
Zoo Freeway
Center St Bridge B-40-880
IH 41
Milwaukee County**

Letting of May 14, 2019

This is Addendum No. 01, which provides for the following:

Special Provisions:

Revised Special Provisions	
Article No.	Description
3	Prosecution and Progress.

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

ADDENDUM NO. 01

1100-25-80

May 2, 2019

Special Provisions

3. Prosecution and Progress

Replace paragraph four with the following:

Do not begin construction work prior to 12:01 AM on July 10, 2019.

END OF ADDENDUM