


LAX
PROJECT ID: 7345-00-70
WITH: N/A
COUNTY: LA CROSSE

DECEMBER 2019
ORDER OF SHEETS

- Section No. 1 Title
- Section No. 2 Typical Sections and Details
- Section No. 3 Estimate of Quantities
- Section No. 3 Miscellaneous Quantities
- Section No. 4 Right of Way Plat
- Section No. 5 Plan and Profile (Includes Erosion Control)
- Section No. 6 Standard Detail Drawings
- Section No. 7 Sign Plates
- Section No. 8 Structure Plans
- Section No. 9 Computer Earthwork Data
- Section No. 9 Cross Sections

TOTAL SHEETS = 82



DESIGN DESIGNATION

A.A.D.T. (2020)	=	4700
A.A.D.T. (2040)	=	7500
D.H.V.	=	803
D.D.	=	60/40
T.	=	2.9%
DESIGN SPEED	=	60 MPH
ESALS	=	520,000

CONVENTIONAL SYMBOLS

PLAN

CORPORATE LIMITS

PROPERTY LINE

LOT LINE

LIMITED HIGHWAY EASEMENT

EXISTING RIGHT OF WAY

PROPOSED OR NEW R/W LINE

SLOPE INTERCEPT

REFERENCE LINE

EXISTING CULVERT

PROPOSED CULVERT (Box or Pipe)

COMBUSTIBLE FLUIDS

MARSH AREA

WOODED OR SHRUB AREA

PROFILE

GRADE LINE

ORIGINAL GROUND

MARSH OR ROCK PROFILE (To be noted as such)

SPECIAL DITCH

GRADE ELEVATION

CULVERT (Profile View)

UTILITIES

ELECTRIC

OVERHEAD UTILITY

FIBER OPTIC

GAS

SANITARY SEWER

STORM SEWER

TELEPHONE

WATER

UTILITY PEDESTAL

POWER POLE

TELEPHONE POLE

ROCK

LABEL

95.36

300'EB'


CAUTION

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

PLAN OF PROPOSED IMPROVEMENT

CTH D - CTH TT
LONG COULEE CREEK BRIDGE, B-32-0237
CTH V
LA CROSSE COUNTY

STATE PROJECT NUMBER
7345-00-70



HORIZONTAL POSITIONS SHOWN ON THIS PLAN ARE WISCONSIN COUNTY COORDINATES, LA CROSSE COUNTY, NAD83 (2011), IN U.S. SURVEY FEET. VALUES ARE GRID COORDINATES, GRID BEARINGS, AND GRID DISTANCES. GRID DISTANCES MAY BE USED AS GROUND DISTANCES.

TOTAL NET LENGTH OF CENTERLINE = 0.066 MI

STATE PROJECT	FEDERAL PROJECT	
	PROJECT	CONTRACT
7345-00-70		

ACCEPTED FOR
LA CROSSE COUNTY HIGHWAY DEPARTMENT

7/15/19
DATE

[Signature]
HIGHWAY COMMISSIONER

ORIGINAL PLANS PREPARED BY

SEH

WISCONSIN
TOREY R. LEONARD
E-42982-6
HOLMEN, WI
PROFESSIONAL ENGINEER

7/15/19
(Date)

[Signature]
(Signature)

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

PREPARED BY

Surveyor	SEH
Designer	SEH
Regional Examiner	ALEIGHA BURG
Regional Supervisor	OSCAR I. WINGER

APPROVED FOR THE DEPARTMENT

DATE: 7/17/19
[Signature]
(Signature)

E

STANDARD ABBREVIATIONS:

ABUT	ABUTMENT	CWT	HUNDREDWEIGHT
AC	ACRE	HYD	HYDRANT
AGG	AGGREGATE	ID	INSIDE DIAMETER
AECPRC	APRON ENDWALL FOR CULVERT PIPE REINFORCED CONCRETE	INV	INVERT
		IP	IRON PIPE OR PIN
AECPCS	APRON ENDWALL FOR CULVERT PIPE CORRUGATED STEEL	LHF	LEFT-HAND FORWARD
		L	LENGTH OF CURVE
ASPH	ASPHALTIC	LF	LINEAR FOOT
AVG	AVERAGE	LC	LONG CHORD OF CURVE
ADT	AVERAGE DAILY TRAFFIC	LS	LUMP SUM
BF	BACK FACE	MH	MANHOLE
BM	BENCH MARK	MOR	MID POINT OF RADIUS
BR	BRIDGE	MCE	MARKERS CULVERT END
CE	COMMERCIAL ENTRANCE	NC	NORMAL CROWN
CL OR C/L OR ¶	CENTER LINE	NO	NUMBER
Δ	CENTRAL ANGLE OR DELTA	OBLIT	OBLITERATE
CONC	CONCRETE	PAVT	PAVEMENT
CPRC	CULVERT PIPE REINFORCED	PE	PRIVATE ENTRANCE
CONCRETE		PVRC	POINT OF VERTICAL REVERSE CURVE
CPCS	CULVERT PIPE CORRUGATED STEEL	QOR	QUARTER POINT OF RADIUS
CR	CREEK	R	RADIUS
CY	CUBIC YARD	REQ'D	REQUIRED
C & G	CURB AND GUTTER	RES	RESIDENCE OR RESIDENTIAL
D	DEGREE OF CURVE	RHF	RIGHT-HAND FORWARD
DHV	DESIGN HOUR VOLUME	R/W	RIGHT-OF-WAY
DISCH	DISCHARGE	R	RIVER
DG	DITCH GRADE	RDWY	ROADWAY
DWY	DRIVEWAY	R/L OR R	REFERENCE LINE
X	EAST GRID COORDINATE	SALV	SALVAGED
EAT	STEEL PLATE BEAM GUARD ENERGY ABSORBING TERMINAL	SAN	SANITARY SEWER
		SF	SQUARE FEET
EOR	END POINT OF RADIUS	SY	SQUARE YARD
EL	ELEVATION	SDD	STANDARD DETAIL DRAWINGS
ENT	ENTRANCE	STA	STATION
ESALS	EQUIVALENT SINGLE AXLE LOADS	SS	STORM SEWER
EXC	EXCAVATION	SSPRC	STORM SEWER PIPE REINFORCED
EBS	EXCAVATION BELOW SUBGRADE	CONCRETE	
EXIST	EXISTING	SE	SUPERELEVATION RATE
FC	FACE OF CURB	TC	TOP OF CURB
FF	FACE TO FACE	T OR TN	TOWN
FERT	FERTILIZE	T	TRUCKS (PERCENT OF)
FE	FIELD ENTRANCE	TYP	TYPICAL
FL	FLOW LINE	VAR	VARIABLE
FO	FIBER OPTIC	VC	VERTICAL CURVE
		Y	NORTH GRID COORDINATE
		YD	YARD

GENERAL NOTES:

ELEVATIONS SHOWN ON THE PLAN ARE REFERENCED TO THE APPROXIMATE USGS DATUM.

WHEN THE QUANTITY OF BASE AGGREGATE OR ASPHALTIC SURFACE IS MEASURED FOR PAYMENT BY THE TON OR CUBIC YARD, THE DEPTH OR THICKNESS OF THE LAYER SHOWN ON THE PLANS IS APPROXIMATE AND THE ACTUAL THICKNESS WILL DEPEND ON THE DISTRIBUTION OF THE MATERIAL AS DIRECTED BY THE ENGINEER.

THE LOCATION OF EXISTING AND PROPOSED UTILITY INSTALLATIONS AS SHOWN ON THE PLANS IS APPROXIMATE. THERE MAY BE OTHER UTILITY INSTALLATIONS WITHIN THE PROJECT AREA THAT ARE NOT SHOWN.

NO TREES OR SHRUBS ARE TO BE REMOVED WITHOUT THE APPROVAL OF THE ENGINEER.

THE EXACT LOCATION OF THE EROSION CONTROL DEVICES SHALL BE DETERMINED IN THE FIELD.

UNLESS OTHERWISE SHOWN, DISTURBED AREAS WITHIN THE RIGHT-OF-WAY, EXCEPT THE AREAS WITHIN THE FINISHED SHOULDER POINTS, ARE TO BE 4-INCH SALVAGED TOPSOILED, FERTILIZED, AND SEEDED AND MULCHED.

A VERTICAL SAWCUT SHALL BE MADE THROUGH EXISTING DRIVEWAYS AND PAVEMENTS AT REMOVAL LIMITS.

EXCAVATION BELOW SUBGRADE (EBS) IS NOT USED TO BALANCE YARDAGE AND IS NOT SHOWN ON THE CROSS SECTIONS BUT IS MEASURED AND PAID FOR AS COMMON EXCAVATION.

THE 5" ASPHALTIC SURFACE SHALL BE CONSTRUCTED WITH 2.5" LOWER LAYER AND A 2.5" UPPER LAYER. USE 1/2" NOMINAL AGGREGATE FOR ASPHALT SURFACE.

THE 4" ASPHALTIC SURFACE SHALL BE CONSTRUCTED IN TWO EQUAL LAYERS. USE 1/2" NOMINAL AGGREGATE FOR ASPHALT SURFACE.

SILT FENCE IS TO BE PLACED AS SHOWN ON THE PLANS OR AS DIRECTED BY THE ENGINEER, AND IN PLACE PRIOR TO BRIDGE REMOVAL.

WETLANDS ARE PRESENT ALONG THE STREAMBANKS DOWNSTREAM OF THE STRUCTURE. AREAS OUTSIDE THE SLOPE INTERCEPTS SHALL NOT BE DISTURBED IN THIS AREA.

A CONVERSION FACTOR OF 2.1 TONS/CY IS USED TO ESTIMATE QUANTITIES FOR BASE AGGREGATE DENSE 3/4-INCH.

A CONVERSION FACTOR OF 2.0 TONS/CY IS USED TO ESTIMATE QUANTITIES FOR BASE AGGREGATE DENSE 1 1/4-INCH.

A CONVERSION FACTOR OF 112 LBS/IN/SY IS USED TO ESTIMATE QUANTITIES FOR ASPHALTIC SURFACE.

RUNOFF COEFFICIENT TABLE

A	HYDROLOGIC SOIL GROUP											
	B			C			D			E		
	SLOPE RANGE (PERCENT)			SLOPE RANGE (PERCENT)			SLOPE RANGE (PERCENT)			SLOPE RANGE (PERCENT)		
LAND USE:	0-2	2-6	6 & OVER	0-2	2-6	6 & OVER	0-2	2-6	6 & OVER	0-2	2-6	6 & OVER
ROW CROPS	.08	.16	.22	.12	.20	.27	.15	.24	.33	.19	.28	.38
	.22	.30	.38	.26	.34	.44	.30	.37	.50	.34	.41	.56
MEDIAN STRIP-TURF	.19	.20	.24	.19	.22	.26	.20	.23	.30	.20	.25	.30
	.24	.26	.30	.25	.28	.33	.26	.30	.37	.27	.32	.40
SIDE SLOPE-TURF			.25			.27			.28			.30
			.32			.34			.36			.38
PAVEMENT:												
ASPHALT						.70 - .95						
CONCRETE						.80 - .95						
BRICK						.70 - .80						
DRIVES, WALKS						.75 - .85						
ROOFS						.75 - .95						
GRAVEL ROADS, SHOULDERS						.40 - .60						

TOTAL PROJECT AREA = 1.2 ACRES
TOTAL AREA EXPECTED TO BE DISTURBED BY CONSTRUCTION ACTIVITIES = 1.3 ACRES

UTILITY CONTACTS

RIVERLAND ENERGY COOPERATIVE
1472 STATE HIGHWAY 35
ONALASKA, WI 54650
(608) 783-2238, EXT. 326
(608) 769-2880 MOBILE
BILL MASON, PROJECT MANAGER
bmason@riverlandenergy.com

MIDWEST NATURAL GAS
3600 STATE HIGHWAY 157, SUITE 200
LA CROSSE, WI 54602
(608) 780-0210
TROY AUNE
troya@midwestnaturalgas.com

CENTURY LINK
333 FRONT STREET NORTH
LA CROSSE, WI 54601
(608) 796-5142
BRIAN STEPLUGH
brian.steplugh@centurylink.com

XCEL ENERGY - ELECTRICITY
3215 COMMERCE STREET
LA CROSSE, WI 54603
(608) 789-3698
JAYMIE HOLTE
jaymie.l.holte@xcelenergy.com

DESIGN CONSULTANT


SEH
6808 ODANA RD, SUITE 200
MADISON, WI 53719
(608) 620-6192
CHRIS BLUM, PE
cblum@sehinc.com

LA CROSSE COUNTY

LA CROSSE CO. HIGHWAY DEPARTMENT
301 CARLSON ROAD
WEST SALEM, WI 54669
(608) 786-3810
RON CHAMBERLAIN, HIGHWAY COMMISSIONER
rchamberlain@lacrossecounty.org

WDNR LIAISON

DNR SERVICE CENTER
3550 MORMON COULEE ROAD
LA CROSSE, WI 54601
(608) 785-9115
KAREN KALVELAGE
karen.kalvelage@wisconsin.gov



PROJECT NO: 7345-00-70


HWY: CTH V

COUNTY: LA CROSSE


GENERAL NOTES

SHEET

E




TYPICAL EXISTING SECTION
STA 77+50 TO STA 81+00




TYPICAL FINISHED SECTION
*STA 77+50 TO 78+91.33
*STA 79+42.67 TO 81+00

* CONCRETE APPROACH SLAB BEGINS SOUTH OF THE BRIDGE AT STA 78+68.70 AND ENDS NORTH OF THE BRIDGE AT STA 79+65.37. SEE PLAN AND PROFILE SHEET AND SDD 13B02-A CONCRETE PAVEMENT APPROACH SLAB FOR REQUIREMENTS. THE CONCRETE SHALL BE 12" THICK AND THE BASE AGGREGATE DENSE 1 1/4-INCH SHALL BE 9" THICK.


BASE AGGREGATE DENSE 1 1/4-INCH BELOW CONCRETE SURFACE DRAIN AND CONCRETE PAVEMENT 8-INCH SHALL BE A MINIMUM OF 6" THICK.




**TYPICAL FINISHED PARTIAL SECTION
WITH STEEL THRIE BEAM STRUCTURE APPROACH**
STA 78+65.5 LT TO 78+90.11 LT



**TYPICAL FINISHED PARTIAL SECTION
WITH MGS GUARDRAIL**
STA 79+78.99 LT TO 80+94.01 LT




**TYPICAL FINISHED PARTIAL SECTION
WITH MGS GUARDRAIL**
STA 77+64.49 RT TO 78+67.01 RT
STA 79+43.89 RT TO 80+46.41 RT




TYPICAL EXISTING SECTION - HOLTER ROAD

STA 5+31'H' - STA 5+50'H'




TYPICAL FINISHED SECTION - HOLTER ROAD



STA 5+31'H' - STA 5+50'H'






TYPICAL FINISHED SECTION

PRIVATE ENTRANCE







PROJECT NO: 7345-00-70


HWY: CTH V

COUNTY: LA CROSSE

EROSION CONTROL

SHEET


E



PCMS
PHASE 1: ROAD CLOSURE BEGINS X/XX
PHASE 2: ROAD CLOSURE BEGINS X/XX

SEE THE FOLLOWING STANDARD DETAIL DRAWINGS FOR ADDITIONAL INFORMATION NOT SHOWN ON DETOUR SHEETS; INCLUDING SIGN CODES, SIGN SIZES, AND SPACING REQUIREMENTS:

- SDD 15C2-A "BARRICADES AND SIGNS FOR MAINLINE CLOSURES"
- SDD 15C2-B "BARRICADES AND SIGNS FOR VARIOUS MAINLINE CLOSURES"
- SDD 15C2-C "DETOUR SIGNING FOR MAINLINE CLOSURES"



DETOUR DETAIL A

DETOUR DETAIL B

PROJECT NO: 7345-00-70	HWY: CTH V	COUNTY: LA CROSSE	DETOUR SIGNING	SHEET	E
------------------------	------------	-------------------	----------------	-------	---

Estimate Of Quantities

7345-00-70					
Line	Item	Item Description	Unit	Total	Qty
0002	201.0105	Clearing	STA	3.000	3.000
0004	201.0205	Grubbing	STA	3.000	3.000
0006	203.0100	Removing Small Pipe Culverts	EACH	2.000	2.000
0008	203.0600.S	Removing Old Structure Over Waterway With Minimal Debris (station) 01. 79+02	LS	1.000	1.000
0010	205.0100	Excavation Common	CY	2,649.000	2,649.000
0012	206.1000	Excavation for Structures Bridges (structure) 01. B-32-0237	LS	1.000	1.000
0014	208.0100	Borrow	CY	291.000	291.000
0016	210.1500	Backfill Structure Type A	TON	570.000	570.000
0018	213.0100	Finishing Roadway (project) 01. 7345-00-70	EACH	1.000	1.000
0020	305.0110	Base Aggregate Dense 3/4-Inch	TON	154.000	154.000
0022	305.0120	Base Aggregate Dense 1 1/4-Inch	TON	1,662.000	1,662.000
0024	415.0080	Concrete Pavement 8-Inch	SY	46.000	46.000
0026	415.0410	Concrete Pavement Approach Slab	SY	118.000	118.000
0028	416.1010	Concrete Surface Drains	CY	13.000	13.000
0030	455.0605	Tack Coat	GAL	58.000	58.000
0032	465.0105	Asphaltic Surface	TON	320.000	320.000
0034	502.0100	Concrete Masonry Bridges	CY	340.000	340.000
0036	502.3200	Protective Surface Treatment	SY	247.000	247.000
0038	502.3210	Pigmented Surface Sealer	SY	83.000	83.000
0040	505.0400	Bar Steel Reinforcement HS Structures	LB	7,820.000	7,820.000
0042	505.0600	Bar Steel Reinforcement HS Coated Structures	LB	46,230.000	46,230.000
0044	516.0500	Rubberized Membrane Waterproofing	SY	28.000	28.000
0046	521.1518	Apron Endwalls for Culvert Pipe Sloped Side Drains Steel 18-Inch 6 to 1	EACH	2.000	2.000
0048	521.3118	Culvert Pipe Corrugated Steel 18-Inch	LF	28.000	28.000
0050	522.0136	Culvert Pipe Reinforced Concrete Class III 36-Inch	LF	86.000	86.000
0052	522.1036	Apron Endwalls for Culvert Pipe Reinforced Concrete 36-Inch	EACH	2.000	2.000
0054	550.2144	Piling CIP Concrete 14 X 0.25-Inch	LF	1,380.000	1,380.000
0056	606.0300	Riprap Heavy	CY	600.000	600.000
0058	612.0406	Pipe Underdrain Wrapped 6-Inch	LF	270.000	270.000
0060	614.0200	Steel Thrie Beam Structure Approach	LF	20.650	20.650
0062	614.0345	Steel Plate Beam Guard Short Radius	LF	37.500	37.500
0064	614.0390	Steel Plate Beam Guard Short Radius Terminal	EACH	1.000	1.000
0066	614.2300	MGS Guardrail 3	LF	50.000	50.000
0068	614.2500	MGS Thrie Beam Transition	LF	118.200	118.200
0070	614.2610	MGS Guardrail Terminal EAT	EACH	3.000	3.000
0072	618.0100	Maintenance And Repair of Haul Roads (project) 01. 7345-00-70	EACH	1.000	1.000

Estimate Of Quantities

7345-00-70

Line	Item	Item Description	Unit	Total	Qty
0074	619.1000	Mobilization	EACH	1.000	1.000
0076	624.0100	Water	MGAL	56.000	56.000
0078	625.0500	Salvaged Topsoil	SY	3,860.000	3,860.000
0080	627.0200	Mulching	SY	1,140.000	1,140.000
0082	628.1504	Silt Fence	LF	1,675.000	1,675.000
0084	628.1520	Silt Fence Maintenance	LF	1,675.000	1,675.000
0086	628.1905	Mobilizations Erosion Control	EACH	3.000	3.000
0088	628.1910	Mobilizations Emergency Erosion Control	EACH	3.000	3.000
0090	628.2027	Erosion Mat Class II Type C	SY	2,182.000	2,182.000
0092	628.6005	Turbidity Barriers	SY	50.000	50.000
0094	629.0210	Fertilizer Type B	CWT	2.900	2.900
0096	630.0120	Seeding Mixture No. 20	LB	80.000	80.000
0098	630.0140	Seeding Mixture No. 40	LB	8.000	8.000
0100	630.0160	Seeding Mixture No. 60	LB	13.000	13.000
0102	630.0200	Seeding Temporary	LB	93.000	93.000
0104	630.0500	Seed Water	MGAL	87.000	87.000
0106	633.5200	Markers Culvert End	EACH	4.000	4.000
0108	634.0612	Posts Wood 4x6-Inch X 12-FT	EACH	1.000	1.000
0110	637.2230	Signs Type II Reflective F	SF	7.460	7.460
0112	638.2602	Removing Signs Type II	EACH	7.000	7.000
0114	638.3000	Removing Small Sign Supports	EACH	7.000	7.000
0116	642.5001	Field Office Type B	EACH	1.000	1.000
0118	643.0420	Traffic Control Barricades Type III	DAY	1,406.000	1,406.000
0120	643.0705	Traffic Control Warning Lights Type A	DAY	1,924.000	1,924.000
0122	643.0900	Traffic Control Signs	DAY	10,212.000	10,212.000
0124	643.0920	Traffic Control Covering Signs Type II	EACH	2.000	2.000
0126	643.1050	Traffic Control Signs PCMS	DAY	14.000	14.000
0128	643.5000	Traffic Control	EACH	1.000	1.000
0130	645.0111	Geotextile Type DF Schedule A	SY	90.000	90.000
0132	645.0120	Geotextile Type HR	SY	622.000	622.000
0134	646.1020	Marking Line Epoxy 4-Inch	LF	1,137.500	1,137.500
0136	650.4500	Construction Staking Subgrade	LF	390.000	390.000
0138	650.5000	Construction Staking Base	LF	390.000	390.000
0140	650.6500	Construction Staking Structure Layout (structure) 01. B-32-0237	LS	1.000	1.000
0142	650.9910	Construction Staking Supplemental Control (project) 01. 7345-00-70	LS	1.000	1.000
0144	650.9920	Construction Staking Slope Stakes	LF	390.000	390.000
0146	690.0150	Sawing Asphalt	LF	48.000	48.000
0148	715.0415	Incentive Strength Concrete Pavement	DOL	500.000	500.000

Estimate Of Quantities

7345-00-70					
0150	715.0502	Incentive Strength Concrete Structures	DOL	2,040.000	2,040.000

201.0105 CLEARING
201.0205 GRUBBING

		CLEARING	GRUBBING
STATION	- STATION	STA	STA
77+00	- 79+50	3	3
TOTAL		3	3

203.0100 REMOVING SMALL PIPE CULVERTS

		REMOVE CULVERT	
STATION	LOCATION	EACH	COMMENT
77+65	RT/LT	1	36" CMCP
80+72	RT	1	18" CMCP
TOTAL		2	

521.1518 APRON ENDWALLS FOR CULVERT PIPE SLOPE SIDE DRAINS STEEL 18-INCH 6 TO 1
521.3118 CULVERT PIPE CORRUGATED STEEL 18-INCH
522.0136 CULVERT PIPE REINFORCED CONCRETE CLASS III 36-INCH
522.1036 APRON ENDWALL FOR CULVERT PIPE REINFORCED CONCRETE 36-INCH
633.5200 MARKERS CULVERT END

		AEW 18-INCH	CPCS 18-INCH	CPRC 36-INCH	AEW 36-INCH	MARKERS CULVERT END
STATION	LOCATION	EACH	LF	LF	EACH	EACH
77+65	RT/LT	-	-	86	2	2
80+72	RT/LT	2	28	-	-	2
TOTAL		2	28	86	2	4

205.0100 EXCAVATION COMMON
208.0100 BORROW

		EXC. COMMON	FILL	EXPANDED FILL	BORROW
STATION	- STATION	CY (3)	CY (1)	CY (2)	CY
77+10	- 81+50	2649	2261	2940	291
TOTAL		2649	2261	2940	291

- (1) - NOT A BID ITEM - FOR INFORMATIONAL PURPOSES ONLY.
(2) - FILL EXPANSION 30%
(3) - EXISTING ASPHALTIC PAVEMENT IS INCLUDED IN COMMON EXCAVATION TOTALS.

606.0300 RIPRAP HEAVY
645.0120 GEOTEXTILE TYPE HR

		RIPRAP	GEOTEXTILE	
STATION	- STATION	LOCATION	CY (1)	SY (1) COMMENTS
77+37	- 77+92	RT	50	- NO GEOTEXTILE REQ'D, TO BE TOPSOILED
78+48	- 79+15	RT	80	75 GEOTEXTILE AT SURFACE DRAIN
78+79	- 81+18	LT	225	27 GEOTEXTILE AT SURFACE DRAIN
		TOTAL	355	102

- (1) - SEE STRUCTURE PLAN FOR ADDITIONAL QUANTITY.

305.0110 BASE AGGREGATE DENSE 3/4-INCH
305.0120 BASE AGGREGATE DENSE 1 1/4-INCH
624.0100 WATER

		BASE 3/4-INCH	BASE 1 1/4-INCH	WATER
STATION	- STATION	TON	TON	MGAL
77+10	- 78+92	50	723	24
79+42	- 81+50	58	895	29
Private Entrance		46	44	3
TOTAL		154	1662	56

455.0605 TACK COAT
465.0105 ASPHALTIC SURFACE

		TACK COAT	ASPHALTIC SURFACE
STATION	- STATION	GAL	TON
77+50	- 78+92	25	136
79+42	- 81+00	33	184
TOTAL		58	320

614.0200 STEEL THRIE BEAM STRUCTURE APPROACH
614.0345 STEEL PLATE BEAM GUARD SHORT RADIUS
614.0370 STEEL PLATE BEAM GUARD SHORT RADIUS TERMINAL

		THRIE BEAM	SHORT RADIUS	SHORT RADIUS TERMINAL
STATION	- STATION	LOCATION	LF	LF EACH
78+57	- 78+92.61	LT	20.65	37.5 1
		TOTAL	20.65	37.5 1

614.2300 MGS GUARDRAIL 3
614.2500 MGS THRIE BEAM TRANSITION
614.2610 MGS GUARDRAIL TERMINAL EAT

		GUARDRAIL 3	THRIE BEAM TRANSITION	GUARDRAIL TERMINAL EAT
STATION	- STATION	LOCATION	LF	LF EACH
78+17.61	- 78+69.51	RT	12.5	39.4 1
79+41.39	- 80+46.41	RT	12.5	39.4 1
79+76.49	- 80+94.41	LT	25	39.4 1
		TOTAL	50	118.2 3

NOTE:
ALL ITEMS AND QUANTITIES ON THIS SHEET ARE FOR
ENGINEERS ESTIMATE CATEGORY 0010.

625.0500 SALVAGED TOPSOIL
627.0200 MULCHING
629.0210 FERTILIZER TYPE B
630.0120 SEEDING MIXTURE NO. 20
630.0140 SEEDING MIXTURE NO. 40
630.0160 SEEDING MIXTURE NO. 60
630.0200 SEEDING TEMPORARY
630.0500 SEED WATER

			SALVAGED			SEEDING	SEEDING	SEEDING	SEEDING	SEED
			TOPSOIL	MULCHING	FERTILIZER	#20	#40	#60	TEMPORARY	WATER
STATION	-	STATION LOCATION	SY	SY	CWT	LB	LB	LB	LB	MGAL
77+10	-	81+00 RT	1400	450	1.10	40	-	-	40	34
77+50	-	81+50 LT	1325	460	1.00	25	6	-	25	26
UNDISTRIBUTED			680	230	0.50	15	2	-	15	15
SUBTOTAL			3405	1140	2.60	80	8	0	80	75
LANDSCAPING RIPRAP STREAM BANKS										
77+38	-	79+15 RT	145	-	0.10	-	-	4	4	4
79+21	-	81+15 LT	220	-	0.15	-	-	6	6	5
UNDISTRIBUTED			90	-	0.05	-	-	3	3	3
SUBTOTAL			455	0	0.30	0	0	13	13	12
PROJECT TOTAL			3860	1140	2.90	80	8	13	93	87

628.1504 SILT FENCE
628.1520 SILT FENCE MAINTENANCE

			FENCE	MAINT.	
STATION	-	STATION LOCATION	LF	LF	COMMENTS
78+04	-	78+86 LT	95	95	PHASE 1
78+33	-	79+10 RT/LT	115	115	PHASE 1
79+00	-	79+82 RT/LT	200	200	PHASE 1
77+48	-	81+05 RT/LT	440	440	PHASE 2, SOUTH OF STREAM
77+59	-	81+50 RT/LT	490	490	PHASE 2, NORTH OF STREAM
UNDISTRIBUTED			335	335	
TOTAL			1675	1675	

628.2017 EROSION MAT CLASS II TYPE C

STATION	-	STATION LOCATION	SY
77+47	-	78+81 RT	400
77+50	-	77+70 LT	25
77+74	-	80+52 RT	520
80+80	-	81+00 RT	45
79+72	-	80+95 LT	325
79+83	-	81+50 LT	430
UNDISTRIBUTED			437
TOTAL			2182

628.1905 MOBILIZATIONS EROSION CONTROL
628.1910 MOBILIZATIONS EMERGENCY EROSION CONTROL

		MOBILIZATION	EMERGENCY MOB.	
DESCRIPTION		EACH	EACH	REMARKS
PROJECT 7345-00-70		1	1	PHASE 1
PROJECT 7345-00-70		2	2	PHASE 2
TOTAL		3	3	

628.6005 TURBIDITY BARRIERS

STATION	-	STATION LOCATION	SY
78+68	-	79+24 LT/RT	50
TOTAL			50

NOTE:
ALL ITEMS AND QUANTITIES ON THIS SHEET ARE FOR
ENGINEERS ESTIMATE CATEGORY 0010.

634.0612 POSTS WOOD 4x6-INCH X 12-FT
637.2230 SIGNS TYPE II REFLECTIVE F
638.2602 REMOVING SIGNS TYPE II
638.3000 REMOVING SMALL SIGN SUPPORTS

	SIGN		12' WOOD	SIGNS TYPE II	REMOVING	REMOVING SMALL	
	CODE	SIGN SIZE	POSTS	REFLECTIVE F	SIGNS TYPE II	SIGN SUPPORTS	
LOCATION			EACH	SF	EACH	EACH	COMMENTS
SW BRIDGE CORNER	-	-	-	-	1	1	EXISITNG OBJECT MARKER
SE BRIDGE CORNER	-	-	-	-	1	1	EXISITNG OBJECT MARKER
NW BRIDGE CORNER	-	-	-	-	1	1	EXISITNG OBJECT MARKER
NE BRIDGE CORNER	-	-	-	-	1	1	EXISITNG OBJECT MARKER
675' SOUTH OF BRIDGE	-	-	-	-	1	1	EXISTING NARROW BRIDGE SIGN
450' NORTH OF BRIDGE	-	-	-	-	1	1	EXISTING NARROW BRIDGE SIGN
CTHV/HOLTER ROAD	R1-1	36"x36"	1	7.46	1	1	STOP SIGN (REPLACEMENT)
TOTAL			1	7.46	7	7	

643.0900 TRAFFIC CONTROL SIGNS
643.0920 TRAFFIC CONTROL COVERING SIGNS TYPE II
643.1050 TRAFFIC CONTROL PCMS
643.5000 TRAFFIC CONTROL

		TRAFFIC	TRAFFIC	TRAFFIC	TRAFFIC	TRAFFIC	TRAFFIC
		CONTROL	CONTROL	CONTROL	CONTROL	CONTROL	CONTROL
		SIGNS	SIGNS	COVERING	PCMS	PCMS	CONTROL
DESCRIPTION	DAYS	EACH	DAYS	SIGNS TYPE II	EACH	DAYS (2)	EACH
PROJECT 7345-00-70	74	138	10212	2	2	14	1
TOTAL			10212	2		14	1

(1) - EACH LOCATION HAS ONE COVER/UNCOVER CYCLE
(2) - EACH TRAFFIC CONTROL PCMS SHALL BE IN PLACE FOR 7 DAYS PRIOR TO ROAD CLOSURE

650.4500 CONSTRUCTION STAKING SUBGRADE
650.5000 CONSTRUCTION STAKING BASE
650.9920 CONSTRUCTION STAKING SLOPE STAKES
650.9910 CONSTRUCTION STAKING SUPPLEMENTAL CONTROL 7345-00-70

		SUBGRADE	BASE	SLOPE	SUPPLEMENTAL
		LF	LF	STAKES	CONTROL
STATION - STATION				LF	LS
77+10 - 78+92		182	182	182	-
79+42 - 81+50		208	208	208	-
TOTAL		390	390	390	1

643.0420 TRAFFIC CONTROL BARRICADES TYPE III
643.0705 TRAFFIC CONTROL WARNING LIGHTS TYPE A

		BARRICADES	BARRICADES	WARNING	WARNING
		TYPE III	TYPE III	LIGHTS TYPE A	LIGHTS TYPE A
DESCRIPTION	DAYS	EACH	DAYS	EACH	DAYS
PROJECT 7345-00-70	74	19	1406	26	1924
TOTAL			1406	26	1924

646.1020 MARKING LINE EPOXY 4-INCH

			WHITE	YELLOW	
			SOLID	12.5' SKIPS	SOLID
STATION - STATION	LOCATION		LF	LF	
77+50 - 81+00	EDGE LINE & CL		700	350	87.5
TOTAL				1137.5	

690.0150 SAWING ASPHALT

STATION	LF	COMMENT
77+50	24	BEGIN PROJECT
81+00	24	END PROJECT
5+50	14	HOLTER ROAD
TOTAL	48	

R/W PROJECT NUMBER 7345-00-70	SHEET NUMBER	TOTAL SHEETS
R/W PROJECT NUMBER --	4.01	2
PLAT OF RIGHT OF WAY REQUIRED FOR CTH D - CTH TT LONG COULEE CREEK BRIDGE		
CTH V		LACROSSE


CONVENTIONAL ABBREVIATIONS			
ACCESS POINT/ DRIVEWAY CONNECTION	AP	RELEASE OF RIGHTS REMAINING	ROR
ACCESS RIGHTS	AR	RIGHT-OF-WAY	REM.
ACRES	AC.	SECTION	R/W
AND OTHERS	ET.AL.	STATION	SEC.
CENTERLINE	C/L	TEMPORARY LIMITED EASEMENT	STA.
CERTIFIED SURVEY MAP	CSM	VOLUME	TLE
CORNER	COR.		V.
DOCUMENT	DOC.	CURVE DATA	
EASEMENT	EASE.	LONG CHORD	LCH
HIGHWAY EASEMENT	H.E.	LONG CHORD BEARING	LCB
LAND CONTRACT	LC	RADIUS	R
MONUMENT	MON.	DEGREE OF CURVE	D
PAGE	P.	CENTRAL ANGLE OR DELTA	DELTA
PERMANENT LIMITED EASEMENT	PLE	LENGTH OF CURVE	L
PROPERTY LINE	PL	TANGENT	TAN
RECORDED AS	(100')		
REFERENCE LINE	R/L		

CONVENTIONAL SYMBOLS	
FOUND IRON PIPE/PIN	(1" UNLESS NOTED)
PROPOSED R/W LINE	--- (SET)
EXISTING H.E. LINE	--- (SET)
PROPERTY LINE	---
LOT & TIE LINES	---
SLOPE INTERCEPTS	--- (SIGN)
CORPORATE LIMITS	---
NO ACCESS (BY PREVIOUS ACQUISITION/CONTROL)	---
NO ACCESS (BY ACQUISITION)	---
NO ACCESS (BY STATUTORY AUTHORITY)	---
SECTION LINE	---
QUARTER LINE	---
SIXTEENTH LINE	---
EXISTING CENTERLINE	---
PROPOSED REFERENCE LINE	---
PARALLEL OFFSET	---

CONVENTIONAL UTILITY SYMBOLS	
WATER	---
GAS	---
TELEPHONE	---
OVERHEAD	---
TRANSMISSION LINES	---
ELECTRIC	---
CABLE TELEVISION	---
FIBER OPTIC	---
SANITARY SEWER	---
STORM SEWER	---
NON COMPENSABLE	---
COMPENSABLE	---
POWER POLE	---
TELEPHONE POLE	---
TELEPHONE PEDESTAL	---
ELECTRIC TOWER	---

BEGIN PROJECT
STA 77+00.00
Y = 195438.208
X = 444078.762

957.285' NORTH AND 1335.165' WEST
OF THE SE CORNER OF SECTION 31
T18N, R7W



END PROJECT
STA 81+55.00
Y = 195893.168
X = 444072.756

1412.218' NORTH AND 1341.171' WEST
OF THE SE CORNER 1/4 OF SECTION 31
T18N, R7W

NOTES:

POSITIONS SHOWN ON THIS PLAT ARE WISCONSIN COORDINATE REFERENCE SYSTEM COORDINATES (WISCRS), LA CROSSE COUNTY, NAD83 2011 IN US SURVEY FEET. VALUES SHOWN ARE GRID COORDINATES, GRID BEARINGS, AND GRID DISTANCES. GRID DISTANCES MAY BE USED AS GROUND DISTANCES.

ALL NEW RIGHT-OF-WAY MONUMENTS WILL BE TYPE 2 (TYPICALLY 3/4"X24" IRON REBARS) UNLESS OTHERWISE NOTED, AND WILL BE PLACED PRIOR TO THE COMPLETION OF THE PROJECT.

RIGHT-OF-WAY BOUNDARIES ARE DEFINED WITH COURSES OF THE PERIMETER OF THE HIGHWAY LANDS REFERENCED TO THE U.S. PUBLIC LAND SURVEY SYSTEM OR OTHER "SURVEYS" OF PUBLIC RECORD.

DIMENSIONING FOR THE NEW RIGHT-OF-WAY IS MEASURED ALONG AND PERPENDICULAR TO THE NEW REFERENCE LINES.

A TEMPORARY LIMITED EASEMENT (TLE) IS A RIGHT FOR CONSTRUCTION PURPOSES, AS DEFINED HEREIN, INCLUDING THE RIGHT TO OPERATE NECESSARY EQUIPMENT THEREON, THE RIGHT OF INGRESS AND EGRESS, AS LONG AS REQUIRED FOR SUCH PUBLIC PURPOSE, INCLUDING THE RIGHT TO PRESERVE, PROTECT, REMOVE, OR PLANT THEREON ANY VEGETATION THAT THE HIGHWAY AUTHORITIES MAY DEEM DESIRABLE. ALL (TLE)S ON THIS PLAT EXPIRE AT THE COMPLETION OF THE CONSTRUCTION PROJECT FOR WHICH THIS INSTRUMENT IS GIVEN.

PROPERTY LINES SHOWN ON THIS PLAT ARE DRAWN FROM DATA DERIVED FROM MAPS AND DOCUMENTS OF PUBLIC RECORD AND/OR EXISTING OCCUPATIONAL LINES. THIS PLAT MAY NOT BE A TRUE REPRESENTATION OF EXISTING PROPERTY LINES, EXCLUDING RIGHT-OF-WAY, AND SHOULD NOT BE USED AS A SUBSTITUTE FOR AN ACCURATE FIELD SURVEY.

LAYOUT
SCALE 0 1 MILE
TOTAL NET LENGTH OF CENTERLINE = .086

ORIGINAL PLAT PREPARED BY

SEH

WISCONSIN

JASON L. CANCE

S-2688

CHIPPEWA FALLS, WI

LAND SURVEYOR


2-11-2019 (Date)

(Signature)

LA CROSSE COUNTY

APPROVED FOR LACROSSE COUNTY

DATE: 2/14/19 (Signature)




SCHEDULE OF LANDS & INTERESTS REQUIRED						
PARCEL NUMBER	OWNERS	INTEREST REQUIRED	R/W NEW ACERS	R/W EXISTING ACERS	R/W TOTAL ACERS	TLE ACERS
1	THOMAS H HALE & CAROL L HALE	FEE/TLE	0.09	0.37	0.46	0.40
2	DAB HOWARD LLC	FEE/TLE	0.05	0.26	0.31	0.29
10	TREMPEALEAU ELECTRIC COOPERATIVE	RELEASE OF RIGHTS				
11	VERIZON NORTH INC.	RELEASE OF RIGHTS				

NOTE: OWNERS NAMES ARE SHOWN FOR REFERENCE PURPOSE ONLY AND ARE SUBJECT TO CHANGE PRIOR TO THE TRANSFER OF LAND INTEREST TO THE COUNTY.

COURSE TABLE			
TO	FROM	BEARING	DISTANCE
12	121	N01° 05' 42"W	949.99'
121	100	N89° 38' 56"W	1284.61'
100	101	S89° 14' 37"W	32.43'
101	102	S89° 14' 37"W	33.57'
102	103	N00° 47' 53"W	40.00'
103	104	S89° 14' 37"W	10.40'
104	105	N00° 45' 23"W	105.00'
105	106	N47° 36' 14"W	21.93'
106	107	N00° 45' 23"W	30.00'
107	108	N89° 14' 37"E	26.29'
108	109	N00° 47' 53"W	265.00'
109	110	N89° 14' 37"E	33.90'
110	111	N89° 14' 37"E	32.10'
111	112	S00° 47' 53"E	50.16'
112	113	S00° 47' 53"E	33.00'
113	114	S00° 47' 53"E	33.00'
114	115	N89° 32' 36"E	17.81'
115	116	S00° 45' 23"E	103.74'
116	117	S89° 14' 37"W	17.74'
117	118	S00° 47' 53"E	145.00'
118	119	N89° 14' 37"E	32.63'
119	120	S00° 45' 23"E	55.00'
120	100	S42° 10' 53"W	47.81'


R/W POINT TABLE		
POINT NAME	Y COORDS	X COORDS
100	195438.636	444111.192
101	195438.208	444078.762
102	195437.765	444045.198
103	195477.761	444044.641
104	195477.623	444034.238
105	195582.614	444032.852
106	195597.402	444016.655
107	195627.399	444016.259
108	195627.746	444042.551
109	195892.721	444038.860
110	195893.168	444072.756
111	195893.592	444104.854
112	195843.434	444105.553
113	195810.437	444106.013
114	195777.440	444106.472
115	195777.582	444124.286
116	195673.847	444125.656
117	195673.613	444107.919
118	195528.627	444109.939
119	195529.058	444142.569
120	195474.063	444143.295

REVISION DATE	DATE	SCALE, FEET	HWY: CTH V	STATE R/W PROJECT NUMBER	7345-00-70	PLAT SHEET	4.02
	GRID FACTOR	N/A	COUNTY: LA CROSSE	CONSTRUCTION PROJECT NUMBER	7345-00-70	PS&E SHEET	




Standard Detail Drawing List


08D02-06	CONCRETE SURFACE DRAINS FLUME TYPE AT STRUCTURES
08D21-01	DRIVEWAYS WITHOUT CURB & GUTTER
08E09-06	SILT FENCE
08E11-02	TURBIDITY BARRIER
08F01-11	APRON ENDWALLS FOR CULVERT PIPE
08F04-07	JOINT TIES FOR CONCRETE PIPE AND CONCRETE COLLAR DETAIL
08F07-05	STEEL APRON ENDWALLS FOR CULVERT PIPE AND PIPE ARCH SLOPED SIDE DRAINS
12A03-10	NAME PLATE (STRUCTURES)
13B02-09A	CONCRETE PAVEMENT APPROACH SLAB
14B15-11A	STEEL PLATE BEAM GUARD, CLASS "A" INSTALLATION & ELEMENTS
14B15-11B	STEEL PLATE BEAM GUARD, CLASS "A" INSTALLATION & ELEMENTS
14B15-11C	STEEL PLATE BEAM GUARD, CLASS "A", INSTALLATION & ELEMENTS
14B18-06A	STEEL PLATE BEAM GUARD, CLASS "A" (AT BRIDGES, OBSTACLES AND SIDEROADS/DRIVEWAYS)
14B20-11B	STEEL THRIE BEAM STRUCTURE APPROACH, CONNECTION TO SQUARE END PARAPETS
14B27-01A	STEEL PLATE BEAM GUARD SHORT RADIUS TERMINAL
14B27-01B	STEEL PLATE BEAM GUARD SHORT RADIUS TERMINAL
14B27-01C	STEEL PLATE BEAM GUARD SHORT RADIUS TERMINAL
14B42-06A	MIDWEST GUARDRAIL SYSTEM (MGS) GUARDRAIL
14B42-06B	MIDWEST GUARDRAIL SYSTEM (MGS) GUARDRAIL
14B42-06C	MIDWEST GUARDRAIL SYSTEM (MGS) GUARDRAIL
14B42-06D	MIDWEST GUARDRAIL SYSTEM (MGS) GUARDRAIL
14B44-04A	MIDWEST GUARDRAIL SYSTEM ENERGY ABSORBING TERMINAL (MGS)
14B44-04B	MIDWEST GUARDRAIL SYSTEM ENERGY ABSORBING TERMINAL (MGS)
14B44-04C	MIDWEST GUARDRAIL SYSTEM ENERGY ABSORBING TERMINAL (MGS)
14B45-05A	MIDWEST GUARDRAIL SYSTEM THRIE BEAM TRANSITION (MGS)
14B45-05B	MIDWEST GUARDRAIL SYSTEM THRIE BEAM TRANSITION (MGS)
14B45-05C	MIDWEST GUARDRAIL SYSTEM THRIE BEAM TRANSITION (MGS)
14B45-05D	MIDWEST GUARDRAIL SYSTEM THRIE BEAM TRANSITION (MGS)
15A03-02A	FLEXIBLE MARKER POST FOR CULVERT END
15A03-02B	FLEXIBLE MARKER POST FOR CULVERT END
15C02-07A	BARRICADES AND SIGNS FOR MAINLINE CLOSURES
15C02-07B	BARRICADES AND SIGNS FOR VARIOUS CLOSURES
15C02-07C	DETOUR SIGNING FOR MAINLINE CLOSURES
15C03-05	BARRICADES AND SIGNS FOR SIDEROAD CLOSURES
15C08-19A	LONGITUDINAL MARKING (MAINLINE)
15D38-02A	TEMPORARY TRAFFIC CONTROL SIGN MOUNTING
15D38-02B	ATTACHMENT OF SIGNS TO POSTS




SECTION F-F




SECTION C-C




SECTION D-D




SECTION H-H



SECTION E-E



LOCATION OF TIE BARS IN WINGWALL



* PARTIAL PLAN VIEW
SURFACE DRAIN WITHOUT PIPE
TYPE "B"

GENERAL NOTES

DETAILS OF CONSTRUCTION, MATERIALS, AND WORKMANSHIP NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS AND THE APPLICABLE SPECIAL PROVISIONS.

ALL STEEL REINFORCEMENT SHALL BE EMBEDDED 2 INCHES CLEAR
UNLESS OTHERWISE SHOWN OR NOTED.

- ① NO. 4 X 2'-0" TIE BARS SPACED AT 3'-0" CENTERS TO BE USED ONLY WHEN ADJACENT TO P.C. CONCRETE.
- ② NO. 4 X 2'-0" TIE BARS SPACED AT 12" CENTERS TO BE PLACED BY BRIDGE CONTRACTOR, OR DRILLED TIE BARS PLACED AS DIRECTED BY THE ENGINEER.
- ③ PIPE UNDERDRAIN MAY BE ANY OF THE MATERIALS LISTED IN SECTION 612.2 OF THE STANDARD SPECIFICATIONS EXCEPT DRAIN TILE.
- ④ MINIMUM REINFORCEMENT SHALL BE 6" X 6" - W4.0 X W4.0 OR NO. 3 BARS LONGITUDINAL AND TRANSVERSE SPACING 12" C-C.
- ⑤ LIMITS OF ADDITIONAL RIPRAP WHEN SPECIAL DITCH IS REQUIRED.
- ⑥ GEOTEXTILE FABRIC, TYPE 'R'
- ⑦ HOT POURED SEALANT UNLESS OTHERWISE SPECIFIED.
- ⑧ THIS DIMENSION MAY VARY DEPENDING ON THE SPACING OF POSTS FOR THE STEEL PLATE BEAM GUARD. THE TYPICAL LOCATION FOR THE SURFACE DRAIN IS WHERE THE POST SPACING WIDENS TO 3'-1/2".

CONCRETE SURFACE DRAINS FLUME TYPE AT STRUCTURES

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED

9/4/08


DATE _____

FHWA

/S/ Jerry H. Zogg

ROADWAY STANDARDS DEVELOPMENT

ENGINEER




*WHERE DRIVEWAY IS PAVED, APPROACH PAVEMENT SHOULD BE EXTENDED TO MATCH DRIVEWAY PAVEMENT.

PLAN VIEW
(UNPAVED SHOULDER ON HIGHWAY)

PLAN VIEW
(PAVED SHOULDER ON HIGHWAY)


RURAL DRIVEWAY INTERSECTION DETAIL
(NO CURB & GUTTER OR SIDEWALK)




TYPICAL CROSS SECTION FOR PRIVATE DRIVE OR FIELD ENTRANCE
AGGREGATE SURFACE

** SLOPE CAN VARY WITH SPEED. SEE 11-45-2.6.2.

POSTED SPEED MPH	MAX. SLOPE
<35	4:1
≥35 TO <60	6:1
≥60	10:1




TYPICAL CROSS SECTION FOR PRIVATE DRIVE OR FIELD ENTRANCE
ASPHALTIC SURFACE




TYPICAL DRIVEWAY PROFILES


DRIVEWAYS WITHOUT CURB & GUTTER	
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION	
APPROVED December, 2016 DATE	/S/ Rodney Taylor ROADWAY STANDARDS DEVELOPMENT UNIT SUPERVISOR
FHWA	




PLAN VIEW
TYPICAL APPLICATION OF SILT FENCE



SILT FENCE



PLAN VIEW
SILT FENCE AT MEDIAN SURFACE DRAINS




JOINING TWO LENGTHS OF SILT FENCE


GENERAL NOTES

DETAILS OF CONSTRUCTION NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS AND APPLICABLE SPECIAL PROVISIONS.

- ① HORIZONTAL BRACE REQUIRED WITH 2" X 4" WOODEN FRAME OR EQUIVALENT AT TOP OF POSTS.
- ② FOR MANUAL INSTALLATIONS THE TRENCH SHALL BE A MINIMUM OF 4" WIDE & 6" DEEP TO BURY AND ANCHOR THE GEOTEXTILE FABRIC. FOLD MATERIAL TO FIT TRENCH AND BACKFILL & COMPACT TRENCH WITH EXCAVATED SOIL.
- ③ WOOD POSTS SHALL BE A MINIMUM SIZE OF 1 1/8" X 1 1/8" OF OAK OR HICKORY.
- ④ SILT FENCE TO EXTEND ACROSS THE TOP OF THE PIPE.
- ⑤ CONSTRUCT SILT FENCE FROM A CONTINUOUS ROLL IF POSSIBLE BY CUTTING LENGTHS TO AVOID JOINTS. IF A JOINT IS NECESSARY USE ONE OF THE FOLLOWING TWO METHODS; A) OVERLAP THE END POSTS AND TWIST, OR ROTATE, AT LEAST 180 DEGREES, B) HOOK THE END OF EACH SILT FENCE LENGTH.




TRENCH DETAIL



SILT FENCE TIE BACK
(WHEN REQUIRED BY THE ENGINEER)

SILT FENCE	
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION	
APPROVED 4-29-05 DATE	/S/ Beth Canestra CHIEF ROADWAY DEVELOPMENT ENGINEER
FHWA	




GENERAL NOTES

DETAILS OF CONSTRUCTION, MATERIALS AND WORKMANSHIP NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS AND THE APPLICABLE SPECIAL PROVISIONS.

TURBIDITY BARRIER MAY BE REMOVED AT THE ENGINEERS DISCRETION, WHEN PERMANENT EROSION CONTROL MEASURES HAVE BEEN ESTABLISHED.

- ① DRIVEN STEEL POSTS, PIPES, OR CHANNELS. LENGTH SHALL BE SUFFICIENT TO SECURELY SUPPORT BARRIER AT HIGH WATER ELEVATIONS.
- ② SANDBAGS TO BE USED AS ADDITIONAL BALLAST WHEN ORDERED BY THE ENGINEER TO MEET ADVERSE FIELD CONDITIONS. SPACE AS APPROPRIATE FOR SITE CONDITIONS.
- ③ WHEN BARRIER HEIGHT, H, EXCEEDS 8 FT., POST SPACING MAY NEED TO BE DECREASED.
- ④ IN WATERWAYS SUBJECT TO FLUCTUATING WATER ELEVATIONS, PROVISIONS SHOULD BE MADE TO ALLOW THE WATER TO EQUALIZE ON EACH SIDE OF THE BARRIER. THIS MAY BE ACCOMPLISHED BY LEAVING A PORTION OF THE BARRIER OPEN ON THE UPSTREAM END.
- ⑤ ESTIMATED HIGH WATER ELEVATION DURING CONSTRUCTION PERIOD. MINIMUM BARRIER HEIGHT SHALL BE 2' GREATER THAN EITHER THE 02 ELEVATION OR THE ESTIMATED HIGH WATER ELEVATION DURING CONSTRUCTION, WHICHEVER IS GREATER.
- ⑥ FLOAT ALTERNATIVE WILL ONLY BE ALLOWED WITH WRITTEN APPROVAL OF THE ENGINEER, AND IS MEANT FOR LOCATIONS WHERE BED ROCK PREVENTS THE INSTALLATION OF POSTS.
- ⑦ ALLOW SUFFICIENT SLACK VERTICALLY AND HORIZONTALLY SO THAT SEDIMENT BUILD UP WILL NOT SEPARATE OR LOWER THE TURBIDITY BARRIER.
- ⑧ USE AS DIRECTED BY COAST GUARD OR DNR PERMIT WHEN WORKING IN NAVIGABLE WATERWAYS.



TURBIDITY BARRIER DETAIL SHOWING TYPICAL PLACEMENT AT STRUCTURES

TURBIDITY BARRIER

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED




6/04/02
DATE

FWHA

/S/ Beth Canestra
CHIEF ROADWAY DEVELOPMENT ENGINEER

METAL APRON ENDWALLS											
PIPE DIA. (IN.)	MIN. THICK. (Inches)		DIMENSIONS (Inches)						APPROX. SLOPE	BODY	
	STEEL	ALUM.	A (±1")	B (MAX.)	H (±1")	L (±1 1/2")	L ₁ ①	L ₂ ①			W (±2")
12	.064	.060	6	6	6	21	12	17 1/2	24	2 1/2 to 1	1 Pc.
15	.064	.060	7	8	6	26	14	21 3/4	30	2 1/2 to 1	1 Pc.
18	.064	.060	8	10	6	31	15	28 1/4	36	2 1/2 to 1	1 Pc.
21	.064	.060	9	12	6	36	18	29 5/8	42	2 1/2 to 1	1 Pc.
24	.064	.075	10	13	6	41	18	37 1/4	48	2 1/2 to 1	1 Pc.
30	.079	.075	12	16	8	51	18	52 1/4	60	2 1/2 to 1	1 Pc.
36	.079	.105	14	19	9	60	24	59 3/4	72	2 1/2 to 1	2 Pc.
42	.109	.105	16	22	11	69	24	75 5/8	84	2 1/2 to 1	2 Pc.
48	.109	.105	18	27	12	78	24	81	90	2 1/4 to 1	3 Pc.
54	.109	.105	18	30	12	84	30	85 1/2	102	2 1/4 to 1	3 Pc.
60	.109x	.105x	18	33	12	87	—	—	114	2 to 1	3 Pc.
66	.109x	.105x	18	36	12	87	—	—	120	2 to 1	3 Pc.
72	.109x	.105x	18	39	12	87	—	—	126	2 to 1	3 Pc.
78	.109x	.105x	18	42	12	87	—	—	132	1 1/2 to 1	3 Pc.
84	.109x	.105x	18	45	12	87	—	—	138	1 1/2 to 1	3 Pc.
90	.109x	.105x	18	37	12	87	—	—	144	1 1/2 to 1	3 Pc.
96	.109x	.105x	18	35	12	87	—	—	150	1 1/2 to 1	3 Pc.




* EXCEPT CENTER PANEL
SEE GENERAL NOTES



METAL ENDWALLS


REINFORCED CONCRETE APRON ENDWALLS								
PIPE DIA. (IN.)	DIMENSIONS (Inches)							APPROX. SLOPE
	T	A	B	C	D	E	G	
12	2	4	24	48 ⁷ / ₈	72 ⁷ / ₈	24	2	3 to 1
15	2 ¹ / ₄	6	27	46	73	30	2 ¹ / ₄	3 to 1
18	2 ¹ / ₂	9	27	46	73	36	2 ¹ / ₂	3 to 1
21	2 ³ / ₄	9	36	37 ¹ / ₂	73 ¹ / ₂	42	2 ³ / ₄	3 to 1
24	3	9 ¹ / ₂	43 ¹ / ₂	30	73 ¹ / ₂	48	3	3 to 1
27	3 ¹ / ₄	10 ¹ / ₂	49 ¹ / ₂	24	73 ¹ / ₂	54	3 ¹ / ₄	3 to 1
30	3 ¹ / ₂	12	54	19 ³ / ₄	73 ¹ / ₂	60	3 ¹ / ₂	3 to 1
36	4	15	63	34 ³ / ₄	97 ³ / ₄	72	4	3 to 1
42	4 ¹ / ₂	21	63	35	98	78	4 ¹ / ₂	3 to 1
48	5	24	72	26	98	84	5	3 to 1
54	5 ¹ / ₂	27	65	33 ¹ / ₄ -35	98 ¹ / ₄ -100	90	5 ¹ / ₂	2 ¹ / ₂ to 1
60	6	30-35	60	39	99	96	5	2 to 1
66	6 ¹ / ₂	24-30	72-78	21-27	99	102	5 ¹ / ₂	2 to 1
72	7	24-36	78	21	99	108	6	2 to 1
78	7 ¹ / ₂	24-36	78	21	99	114	6 ¹ / ₂	2 to 1
84	8	36	90 ¹ / ₂	21	111 ¹ / ₂	120	6 ¹ / ₂	1 ¹ / ₂ to 1
90	8 ¹ / ₂	41	87 ¹ / ₂	24	111 ¹ / ₂	132	6 ¹ / ₂	1 ¹ / ₂ to 1

* MINIMUM
** MAXIMUM




CONCRETE ENDWALLS


1" WIDE, 12 GA. (0.109" THICK) GALVANIZED STRAP WITH STANDARD 6" X 1/2" BAND BOLT AND NUT




ALTERNATE FOR TYPE 1 CONNECTION
END SECTION CONNECTOR STRAP




TYPE 1
FOR 12" THRU 24" CORR. PIPE



TYPE 2
FOR 30" THRU 96" CORR. PIPE



TYPE 3
FOR 42" THRU 96" CORR. PIPE



TYPE 5
ALTERNATE FOR:
ALL SIZES CORRUGATED CIRCULAR PIPE


NOTE: DIMPLED BAND FITS OVER OUTSIDE OF ENDWALL, AND CORRUGATED BAND FITS INSIDE ENDWALL. DIMPLED BAND MAY BE USED WITH HELICALLY CORRUGATED PIPE.

FOR CIRCUMFERENTIALLY CORRUGATED PIPE USE ENDWALL CONNECTION DETAILS 1, 2, 3 OR 5 AS APPLICABLE.

FOR HELICALLY CORRUGATED PIPE USE ENDWALL CONNECTION DETAILS 1, 2 OR 5.

FOR HELICALLY CORRUGATED PIPES WITH TWO CIRCUMFERENTIAL CORRUGATIONS AT EACH END USE ENDWALL CONNECTION DETAILS 1, 2 OR 3.

CONNECTION DETAILS



SECTION A-A

GENERAL NOTES

DETAILS OF CONSTRUCTION, MATERIALS AND WORKMANSHIP NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS AND THE APPLICABLE SPECIAL PROVISIONS.

CONCRETE CULVERT ENDWALLS MAY NOT BE USED WITH GALVANIZED STEEL OR ALUMINUM CULVERT PIPE OR VISE VERSA. GALVANIZED STEEL OR ALUMINUM ENDWALLS SHALL NORMALLY BE INSTALLED ON CULVERT PIPE OF THE SAME METAL.

ALL THREE PIECE STEEL APRON ENDWALLS FOR 60" DIAMETER PIPE AND LARGER SHALL HAVE 0.109" SIDES AND 0.138" CENTER PANELS. ALL THREE PIECE ALUMINUM APRON ENDWALLS FOR 60" DIAMETER PIPE AND LARGER SHALL HAVE 0.105" SIDES AND 0.134" CENTER PANELS. THE WIDTH OF CENTER PANELS SHALL BE GREATER THAN 20 PERCENT OF THE PIPE PERIMETER.

LAP SEAMS SHALL BE TIGHTLY JOINED BY GALVANIZED RIVETS OR BOLTS FOR STEEL UNITS AND ALUMINUM RIVETS AND BOLTS FOR ALUMINUM UNITS. FOR THE 60" THROUGH 96" DIAMETER APRON ENDWALL SIZES, THE REINFORCED EDGES AND CENTER PANEL SEAMS SHALL BE FURTHER REINFORCED WITH GALVANIZED STEEL OR ALUMINUM STIFFENER ANGLES. THE ANGLES SHALL BE ATTACHED BY GALVANIZED NUTS AND BOLTS FOR STEEL UNITS AND ALUMINUM NUTS AND BOLTS FOR ALUMINUM UNITS.




WHERE TWO OR MORE PIPES WITH APRON ENDWALLS ARE LAID ADJACENT TO EACH OTHER, THEY SHALL BE SEPARATED BY A DISTANCE SUFFICIENT TO PROVIDE A MINIMUM CLEARANCE OF 6 INCHES BETWEEN APRON ENDWALLS.


① FOR PIPE SIZES UP TO 60" DIAMETER, A 180° ROLLED EDGE MAY BE USED INSTEAD OF STEEL ROD REINFORCEMENT. SEE SECTION A-A.

APRON ENDWALLS FOR
CULVERT PIPE

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
11/30/94
DATE
/S/ Rory L. Rhinesmith
CHIEF ROADWAY DEVELOPMENT ENGINEER
FHWA






GENERAL NOTES

DETAILS OF CONSTRUCTION, MATERIALS AND WORKMANSHIP NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS AND THE APPLICABLE SPECIAL PROVISIONS.


SLOPED END SECTIONS SHALL CONFORM TO THE REQUIREMENTS OF THE STANDARD SPECIFICATIONS, SECTION 521 FOR STEEL APRON ENDWALLS.

SAFETY BARS SHALL BE FABRICATED FROM GALVANIZED STEEL PIPE MEETING THE REQUIREMENTS OF ASTM A-53, GRADE B, SCHEDULE 40 OR APPROVED EQUAL.

STEEL APRON ENDWALLS FOR CULVERT PIPE SLOPED SIDE DRAINS											
PIPE DIA. (IN.)	MIN. THICK. (Inches)	DIMENSIONS (Inches)				L DIMENSIONS					
		A	H	W	OVERALL WIDTH	SLOPE	LENGTH INCHES	SLOPE	LENGTH INCHES	SLOPE	LENGTH INCHES
15	.064	8	6	21	37	4:1	20	6:1	30	10:1	70
18	.064	8	6	24	40	4:1	32	6:1	48	10:1	100
21	.064	8	6	27	43	4:1	44	6:1	66	10:1	130
24	.064	8	6	30	46	4:1	56	6:1	84	10:1	160
30	.109	12	9	36	60	4:1	80	6:1	120	10:1	220
36	.109	12	9	42	66	4:1	104	6:1	156	10:1	280
42	.109	16	12	48	80	4:1	128	6:1	192	—	—
48	.109	16	12	54	86	4:1	152	6:1	228	—	—
54	.109	16	12	60	92	4:1	176	6:1	264	—	—
60	.109	16	12	66	98	4:1	200	6:1	300	—	—







*NOTE: THREE SAFETY BARS ARE SHOWN. ACTUAL NUMBER OF BARS REQUIRED AT A 2'-0" C-C MAX. SPACING WILL VARY DEPENDING ON THE LENGTH OF THE END SECTION.



STEEL APRON ENDWALLS FOR PIPE ARCH SLOPED SIDE DRAINS													
EQUIV. DIA. (Inches)	(Inches)		MIN. THICK. (Inches) ①	DIMENSIONS (Inches)				L DIMENSIONS					
	SPAN	RISE		A	H	W	OVERALL WIDTH	SLOPE	LENGTH INCHES	SLOPE	LENGTH INCHES	SLOPE	LENGTH INCHES
15	17	13	.064 *	7	6	30	44	4:1	19	6:1	30	10:1 ②	70
18	21	15	.064 *	8	6	27	43	4:1	20	6:1	30	10:1	70
21	24	18	.064 *	8	6	30	46	4:1	32	6:1	48	10:1	100
24	28	20	.064 *	8	6	34	50	4:1	40	6:1	60	10:1	120
30	35	24	.079 *	12	9	41	65	4:1	56	6:1	84	10:1	160
36	42	29	.109 *	12	9	48	72	4:1	76	6:1	114	10:1	210
42	49	33	.109	16	12	55	87	4:1	92	6:1	138	—	—
48	57	38	.109	16	12	63	95	4:1	112	6:1	168	—	—
54	64	43	.109	16	12	70	102	4:1	132	6:1	198	—	—


① * MINIMUM THICKNESS OF ALL 10:1 SLOPED SIDE DRAINS IS 0.109".
② ACTUAL SLOPE GREATER THAN 10:1.




STEEL APRON ENDWALLS FOR CULVERT PIPE AND PIPE ARCH SLOPED SIDE DRAINS

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
9/14/2012 /S/ Jerry H. Zogg
DATE ROADWAY STANDARDS DEVELOPMENT
FHWA ENGINEER



TYPICAL NAME PLATE
(BRIDGES, CULVERTS, AND RETAINING WALLS)




**NUMBERING DESIGNATION
MULTI-UNIT STRUCTURES**

GENERAL NOTES


NAME PLATES TO BE INSTALLED ON BRIDGES, CULVERTS, AND RETAINING WALLS SHALL CONFORM TO THE REQUIREMENTS OF SECTION 502.3.11 OF THE STANDARD SPECIFICATIONS.

THE BRIDGE NUMBER AND YEAR BUILT SHOWN ON THIS DRAWING ARE EXAMPLES ONLY. SEE CONSTRUCTION PLANS FOR INDIVIDUAL NUMBERING AND YEAR BUILT.

- ① EPOXY RESIN SHALL BE FROM AN APPROVED MANUFACTURER AND USED IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS.
- ② REHABILITATION OF AN EXISTING STRUCTURE SHOULD USE THE DATE OF ORIGINAL STRUCTURE CONSTRUCTION.




SECTION A-A



ALTERNATE LUG

- ① ADHERE ANCHOR LUG TO PRECAST RETAINING WALL WITH EPOXY RESIN.



ALTERNATE LUG
(FOR ATTACHMENT TO PRECAST STRUCTURES)

**NAME PLATE
(STRUCTURES)**


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED


3/26/10
DATE

FHWA


/S/ Scot Becker
CHIEF STRUCTURAL DEVELOPMENT ENGINEER



**SKewed APPROACH
(PAVEMENT MORE THAN TWO LANES)**




**SKews > 20°
(PAVEMENT WIDTH ≤ 30')**




**SKews ≤ 20°
(PAVEMENT WIDTH ≤ 30')**

APPROACH SLAB AND ADJACENT PAVEMENT


- * (RS) = REINFORCED CONCRETE SLAB
- * (PS) = PAVED CONCRETE SHOULDER OR CONCRETE DRAINAGE SLAB
- * (NRS) = NON - REINFORCED CONCRETE SLAB
- *** STANDARD DOWEL BAR DIAMETER (SEE SDD 13C11 AND SDD 13C13)



**SECTION A - A
REINFORCEMENT POSITIONING DETAIL**



**SECTION B - B
BEND DETAIL
BOTTOM REINFORCEMENT**




**SECTION C - C
TRANSITION DETAIL
APPROACH SLAB TO ADJACENT PAVEMENT**

GENERAL NOTES


THE CONTRACTOR MAY SPLICE NO. 6 BARS IN THE APPROACH SLAB FOR SKEWED STRUCTURES ONLY. STAGGER SPLICES WITH A MAXIMUM OF ONE SPLICE PER BAR. THE LENGTH OF LAP IS 20 INCHES.

TACK WELD DOWEL BARS TO THE BASKETS ON ALTERNATE ENDS.

- ① THE CONTRACTOR MAY USE NO. 4 BARS SPACED AT 2' - 0" C - C IN BOTH THE LONGITUDINAL AND TRANSVERSE DIRECTIONS FOR TOP REINFORCEMENT AS AN ALTERNATIVE TO THE WELDED WIRE FABRIC.
- ② THE CONTRACTOR MAY OMIT THE BARS BETWEEN REINFORCED SLABS WHERE SLAB REINFORCEMENT BARS EXTEND ACROSS THE CENTERLINE OR REFERENCE LINE.
- ③ DO NOT CONSTRUCT AN EXPANSION JOINT OR INSTALL DOWEL BARS WHEN ABUTTING AN HMA PAVEMENT.
- ④ USE A JOINT SEALANT MEETING THE REQUIREMENTS OF ASTM D6690.
- ⑤ PLACE EXPANSION CAP ON THE END OF THE DOWEL THAT IS NOT TACK WELDED TO THE BASKET. DO NOT FORCE DOWEL BAR PAST THE DOWEL STOP.
- ⑥ EXTEND EXPANSION JOINT THROUGH ANY ADJACENT TIED CONCRETE.
- (A) STANDARD CONTRACTION JOINT NORMAL TO \overline{C} OR \overline{R} .
- (B) STANDARD LONGITUDINAL JOINT WITH TIE BARS.
- (C) 1 1/2" EXPANSION JOINT WITH DOWEL BARS NORMAL TO \overline{C} OR \overline{R} .



**SECTION D - D
CONTRACTION JOINT**



EXPANSION JOINT DETAIL

CONCRETE PAVEMENT APPROACH SLAB


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
November 2018 /S/ Peter Kemp P.E.
DATE PAVEMENT SUPERVISOR
FHWA


GENERAL NOTES

- W6 X 9 OR W6 X 8.5 STEEL POSTS AND NOTCHED PLASTIC BLOCKOUTS ARE ACCEPTABLE ALTERNATIVES FOR 6" X 8" WOOD POSTS WITH WOOD OR PLASTIC BLOCKOUTS. USE APPROVED NOTCHED PLASTIC BLOCKOUTS WITH STEEL POSTS. APPROVED PLASTIC BLOCKOUT DESIGNS MAY VARY FROM THIS TYPICAL DETAIL WHEN USED IN CONJUNCTION WITH STEEL POSTS. DO NOT MIX STEEL POSTS AND WOOD POSTS IN A SINGLE INSTALLATION.
- USE STRUCTURAL STEEL POSTS CONFORMING TO ASTM A 36. GALVANIZED POSTS ACCORDING TO AASHTO M 111. EITHER SET THE POSTS IN DRILLED HOLES OR DRIVE TO GRADE. REMOVE MUSHROOMING CAUSED BY DRIVING AND REPAIR DAMAGED SPELTER COATING ON GALVANIZED POSTS.
- INSTALL STEEL POSTS WITH HOLES ON APPROACHING TRAFFIC SIDE.
- USE EITHER WOOD OR APPROVED PLASTIC BLOCKOUTS ON WOOD POSTS.
- IF THE DISTANCE FROM BACK OF POST TO SHOULDER HINGE POINT IS LESS THAN 2 FEET INSTALL LONGER POST AT HALF POST SPACING, W BEAM (LHW).
- IF ROCK IS ENCOUNTERED DURING EXCAVATION, THE ENGINEER MAY APPROVE USING A 12 INCH DIAMETER POST HOLE EXTENDING 20 INCHES DEEP INTO THE ROCK. PLACE GRANULAR MATERIAL IN THE BOTTOM OF THE HOLE APPROXIMATELY 2 1/2 INCHES DEEP. CUT THE POSTS TO LENGTH AND PLACE IN THE HOLE. BACKFILL WITH MATERIAL EXCAVATED FROM THE HOLE AND COMPACT ADEQUATELY.
- WHEN USING STEEL POSTS AND WOOD BLOCKOUTS INSTALL FOUR 16D GALVANIZED NAILS. INSTALL NAILS AT THE BACK CORNERS OF THE BLOCK AND BEND THE NAILS OVER THE FLANGE OF THE STEEL POST.


INSTALL BEAM GUARD SECTIONS AND ALL NECESSARY HARDWARE ACCORDING TO THE APPLICABLE PLAN AND CURRENT STANDARD AND SUPPLEMENTAL SPECIFICATIONS. ALL DIMENSIONS ARE SUBJECT TO MANUFACTURER'S TOLERANCES EXCEPT WHERE ALLOWABLE TOLERANCES ARE SHOWN.




END VIEW
SETTING STEEL OR WOOD POST IN ROCK ⑥




END VIEW
LOCATED ALONG A CURBED ROADWAY



END VIEW
LOCATED ALONG A ROADWAY SHOULDER
STANDARD INSTALLATION




END VIEW
STEEL POST & NOTCHED
PLASTIC BLOCKOUT ALTERNATIVE
STANDARD INSTALLATION




END VIEW
LONGER POST AT HALF
POST SPACING W BEAM
(LHW)

TYPICAL INSTALLATION OF STEEL PLATE BEAM GUARD




STEEL POST &
HOLE PUNCHING DETAIL
(W6 X 9) ①


ALL HOLES 3/8" DIAMETER EXCEPT AS NOTED




WOOD POST
(6" X 8") NOMINAL




WOOD OR PLASTIC
BLOCKOUT FOR
WOOD POSTS



TYPICAL NOTCHED
PLASTIC BLOCKOUT
FOR STEEL POSTS ①




PLAN VIEW
WOOD POST, BLOCKOUT & BEAM



PLAN VIEW
STEEL POST, NOTCHED
PLASTIC BLOCKOUT & BEAM


STEEL PLATE BEAM GUARD,
CLASS "A"
INSTALLATION & ELEMENTS

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION




FRONT VIEW

POST SPACING STANDARD INSTALLATION




FRONT VIEW


POST SPACING FOR LONGER POST
AT HALF POST SPACING W BEAM (LHW)



SECTION THRU W BEAM



FRONT VIEW
BEAM SPLICE AT WOOD POST
AND POST MOUNTING DETAIL




FRONT VIEW
BEAM SPLICE AT STEEL POST

TYPICAL SPLICING DETAILS
OF STEEL PLATE BEAM GUARD

GENERAL NOTES

FURNISH GUARDRAIL DEFLECTORS FROM APPROVED PRODUCTS LIST.


- ⑨ DO NOT INSTALL REFLECTORS ON THE FIRST 50 FEET OF THE APPROACH END OF THE ENERGY ABSORBING TERMINA. START REFLECTORS AT POST #9 AND SPACE EVENLY EVERY 100 FEET (MAX.) TO THE END OF GUARDRAIL RUN, USING A MINIMUM OF 3 REFLECTORS.
- ⑫ 8 - 5/8" ϕ X 2" BUTTON HEAD BOLTS WITH OVAL SHOULDERS & RECESS NUTS.
- ⑬ 5/8" DIA. BUTTON HEAD BOLT AND RECESS NUT WITH 5/8" DIA. F844 FLAT WASHER UNDER NUT.




NESTED W BEAM (NW)

USE ALL OTHER STANDARD BEAM GUARD DETAILS FOR
CONSTRUCTING NESTED W BEAM (NW)

* USE DOUBLE SIDED WHITE GUARDRAIL REFLECTORS ON ROADWAYS WITH BI-DIRECTIONAL TRAFFIC (NO MEDIAN). USE SINGLE SIDED WHITE (RIGHT SIDE) AND SINGLE SIDED YELLOW (LEFT SIDE) ON ROADWAYS WITH MEDIAN SEPARATION.




4" X 12" GUARDRAIL REFLECTOR DETAIL
AND TYPICAL INSTALLATION *



4"x 12" GUARDRAIL REFLECTOR


STEEL PLATE BEAM GUARD,
CLASS "A",
INSTALLATION & ELEMENTS

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION



DETAIL FOR DOUBLE BLOCKS

THE NUMBER OF DOUBLE BLOCK POSTS
WITHIN A BARRIER RUN IS UNLIMITED




DETAIL FOR TRIPLE BLOCKS


TRIPLE BLOCK DETAIL IS LIMITED TO ONE
LOCATION WITHIN A BEAM GUARD RUN.

NOTES: USE DOUBLE OR TRIPLE BLOCKS WHEN UNDERGROUND OBSTACLES
PREVENT THE POST FROM BEING INSTALLED.

DO NOT USE EXTRA BLOCKOUTS IF IT CAUSES THE POST TO BE DRIVEN BEYOND
SHOULDER HINGE POINT OR CAUSES A FIXED OBJECT TO BE WITHIN THE DEFLECTION
DISTANCE OF THE BARRIER.



PLAN VIEW BEAM LAPPING DETAIL




POST DRIVING FOR CONTINUOUS UNDERGROUND OBSTRUCTION


STEEL PLATE BEAM GUARD,
CLASS "A",
INSTALLATION & ELEMENTS

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION


APPROVED
June 2017 /S/ Rodney Taylor
DATE ROADWAY STANDARDS DEVELOPMENT
FHWA UNIT SUPERVISOR




BEAM GUARD AT SIDEROADS OR DRIVEWAYS



BEAM GUARD AT OBSTACLES EXIT END - ONE WAY TRAFFIC



BEAM GUARD AT FULL WIDTH BRIDGES




BEAM GUARD AT OBSTACLES - TWO WAY TRAFFIC

(RAIL TO OBSTACLE CLEARANCE 3'-6" TO 4'-6")

TABLE 1
FLARE RATES FOR BEAM
GUARD AT NARROW BRIDGES

POSTED SPEED (MPH)	FLARE RATE
25	13:1
30	15:1
35	16:1
40	18:1
45	21:1
50	24:1
55	26:1
65	30:1



BEAM GUARD AT NARROW BRIDGES (FLARED TO SHOULDER EDGE, THEN PARALLEL TO ROADWAY)

GENERAL NOTES

DETAILS OF CONSTRUCTION, MATERIALS AND WORKMANSHIP SHALL CONFORM TO THE PERTINENT STANDARD SPECIFICATIONS AND THE APPLICABLE SPECIAL PROVISIONS.

W6 X 9 OR W6 X 8.5 STEEL POSTS WITH NOTCHED PLASTIC BLOCKOUTS ARE ACCEPTABLE ALTERNATIVES FOR 6" X 8" WOOD POSTS WITH WOOD OR PLASTIC BLOCKOUTS. USE APPROVED NOTCHED PLASTIC BLOCKOUTS WITH STEEL POSTS.

THE LOCATIONS AND LENGTHS OF BEAM GUARD ARE SHOWN ELSEWHERE IN THE PLAN.


- STEEL THRIE BEAM STRUCTURAL APPROACH (STBSA) - SEE CURRENT SDD 14B20.
- USE AN APPROVED END TREATMENT FOR THE TRAFFIC APPROACH SIDE OF BRIDGE/OBSTACLES. USE TYPE 2 ANCHORAGE ONLY AT THE DOWNSTREAM ENDS OF BEAM GUARD LOCATED ALONG ROADWAYS WITH ONE WAY TRAFFIC.

MINIMUM LATERAL DISTANCE FROM FACE OF BEAM GUARD TO FIXED OBJECT	POST SPACING
3'-6"	3' - 1 1/2"
4'-6"	6' - 3"


STEEL PLATE BEAM GUARD
CLASS "A"
AT BRIDGES, OBSTACLES
AND SIDEROADS/DRIVEWAYS

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
8-21-07 /S/ Jerry H. Zogg
DATE ROADWAY STANDARDS DEVELOPMENT
ENGINEER
FHWA



**THRIE BEAM CONNECTION TO BRIDGE
PARAPET WITH SQUARE ENDS**




**W BEAM TRANSITION AND CONNECTION TO
BRIDGE PARAPETS WITH SQUARE ENDS
(USE ONLY ON THE TRAFFIC EXIT END OF ONE WAY BRIDGES)**

GENERAL NOTES

THESE ARE TYPICAL CONNECTION DETAILS. ADJUST THE POSITION OF CONNECTIONS TO EXISTING BRIDGES TO FIT THE ACTUAL BRIDGE AND SITE DIMENSIONS.

BOLTS, NUTS AND WASHERS SHALL CONFORM TO ASTM A325, A449 AND GALVANIZED PER STANDARD SPECIFICATIONS 614.

- ① DRILLING BOLT HOLES THROUGH THE PARAPET, BOLTS, NUTS, WASHERS AND REPAIRING DAMAGED CONCRETE ARE INCIDENTAL TO THE CONTRACT.
 - ② BOLTS MAY BE A325 BOLTS OR A449 BOLTS. BOLT LENGTH AND THREADING LENGTH ARE TO ALLOW FOR A TIGHT CONNECTION BETWEEN RIGID BARRIER AND THRIE BEAM CONNECTION PLATE. CONTRACTOR IS TO FIELD VERIFY BOLT LENGTH AND THREAD LENGTH. ONE ROUND WASHER REQUIRED BETWEEN BOLT HEAD AND THRIE BEAM TERMINAL CONNECTOR. BOLTS THAT EXTEND THROUGH THE PARAPET AND OUT THE BACK FACE REQUIRE A HARDENED ROUND STEEL WASHER THAT IS 2" O.D. X 5/8" THICK AND ONE PLATE WASHER. REPAIR ANY DAMAGED CONCRETE FROM BOLT INSTALLATION.
 - ③ THE RECESS FOR A W-BEAM CONNECTION, WHICH EXISTS ON SOME PARAPETS OF THIS TYPE, SHALL BE FILLED WITH A TREATED TIMBER BLOCKOUT. BLOCKOUT SIZE IS 1'-6" X 2'-0" X 3 1/2".
 - ④ W6 X 9 OR W6 X 8.5 STEEL POSTS AND NOTCHED PLASTIC BLOCKOUTS ARE ACCEPTABLE ALTERNATIVES FOR 6" X 8" WOOD POST WITH WOOD OR PLASTIC BLOCKOUTS. USE APPROVED NOTCHED PLASTIC BLOCKOUTS WITH STEEL POSTS.
- DO NOT USE STEEL POSTS AND NOTCHED PLASTIC BLOCKOUTS IN THE STEEL THRIE BEAM STRUCTURAL APPROACH AND THE TRANSITION SECTION OF STEEL PLATE BEAM GUARD, CLASS "A" INSTALLATIONS.



STEEL THRIE BEAM STRUCTURE APPROACH, CONNECTION TO SQUARE END PARAPETS


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED


8/31/2012
DATE

FHWA

/S/ Jerry H. Zogg
ROADWAY STANDARDS DEVELOPMENT
ENGINEER



TYPICAL LAYOUT
(8' RADIUS SHOWN)



SECTION A-A
(CRT POST)

TYPICAL LAP SPLICES
(8' RADIUS SHOWN)

GENERAL NOTES

ALL ANGLES, CHANNELS, AND PLATES SHALL CONFORM TO THE REQUIREMENTS OF ASTM A36 AND THE STRUCTURAL TUBING SHALL CONFORM TO ASTM A 500. WELDING SHALL MEET THE CURRENT REQUIREMENTS OF THE AMERICAN WELDING SOCIETY STRUCTURAL WELDING CODE ANSI/AWS D1.1. ALL STRUCTURAL STEEL SHALL BE GALVANIZED IN ACCORDANCE WITH ASTM A 123. PUNCHING, DRILLING, CUTTING, OR WELDING WILL NOT BE PERMITTED AFTER GALVANIZING. FURNISH AND INSTALL HARDWARE PER STANDARD SPECIFICATION 614.2, UNLESS NOTED OTHERWISE.


SHOP BEND CURVED RAIL SECTIONS.

SEE STANDARD DETAIL DRAWING 14 B 15 FOR OTHER DETAIL.

- ① ON THE 8 FOOT RADIUS INSTALLATION, DO NOT INSTALL BUTTON HEAD BOLT AT CENTER CRT POST.
- ② RADIUS FROM 8' - 36'. SEE PLAN.
- ③ HEIGHT TRANSITION MAY BE REQUIRED. SEE PLAN OR PROJECT ENGINEER.
- ④ 5/8" Ø X 1'-6" BUTTON HEAD BOLT AND RECESS NUT WITH ROUND WASHER UNDER NUT.

RADIUS	NUMBER OF CRT POSTS	*NUMBER AND LENGTH OF CURVED RAILS	REQUIRED AREA FREE OF FIXED OBJECTS (LENGTH x WIDTH)
8'	5	1 at 12.5'	25' x 15'
16'	7	1 at 25'	30' x 15'
24'	9	1 at 25' and 1 at 12.5'	40' x 20'
32'	11	2 at 25'	50' x 20'


* THE NUMBER OF RAILS IS BASED ON A 90° INTERSECTION. SEE PLAN FOR NON 90° INSTALLATIONS.




SECTION B-B
(BEAM GUARD POST)

STEEL PLATE BEAM GUARD
SHORT RADIUS TERMINAL

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION



PLAN VIEW




ELEVATION VIEW


STEEL PLATE BEAM GUARD SHORT RADIUS TERMINAL

GENERAL NOTES

- ATTACH W BEAM RAIL TO THE STEEL PIPE WITH A $\frac{5}{8}$ " X 2" BUTTON HEAD BOLT WITH NO WASHER. CONNECTION TO THE POST IS NOT REQUIRED.
- INSTALL GALVANIZED $\frac{3}{4}$ " (6X19) PREFORMED WIRE OR INDEPENDENT WIRE ROPE CORE CONFORMING TO AASHTO M 30. MANUFACTURE WIRE ROPE OUT OF IMPROVED PLOW STEEL WITH A MINIMUM BREAKING STRENGTH OF 42,800 PSI.



DETAIL A




DETAIL B


(BEAM GUARD AND TERMINAL SECTION NOT SHOWN)

STEEL PLATE BEAM GUARD
SHORT RADIUS TERMINAL


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION




RECTANGULAR PLATE WASHER




DETAIL D




END PLATE




SECTION C-C
(END PLATE REMOVED)




ANCHOR BRACKET




DETAIL C




WOOD BREAKAWAY POST




BEARING PLATE



SOIL PLATE











CABLE ASSEMBLY




STEEL TUBE

<p>STEEL PLATE BEAM GUARD SHORT RADIUS TERMINAL</p>	
<p>STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION</p>	
<p>APPROVED 12/18/08 DATE</p>	<p>/S/ Jerry H. Zogg ROADWAY STANDARDS DEVELOPMENT ENGINEER</p>
<p>FHWA</p>	

- ① WOOD OR STEEL POSTS (w6X9 OR w6X8.5) MAY BE USED. DO NOT INTERMIX WOOD AND STEEL POSTS. INSTALL STEEL POSTS WITH HOLES ON APPROACHING TRAFFIC SIDE.
- ② USE WOOD OR APPROVED PLASTIC BLOCKOUTS. WOOD BLOCKOUTS MAY BE CONSTRUCTED OUT OF TWO OR MORE WOOD BLOCKOUTS. SEE ALTERNATE WOOD BLOCKOUT DETAIL. DIMENSIONS OF APPROVED PLASTIC BLOCKOUTS MAY VARY.
- ③ IF ROCK IS ENCOUNTERED DURING EXCAVATION, PROVIDE A HOLE 12 INCHES IN DIAMETER EXTENDING 20 INCHES DEEP INTO THE ROCK. PLACE APPROXIMATELY 2 1/2" INCHES OF GRANULAR MATERIAL IN THE BOTTOM OF THE HOLE. CUT THE POSTS THE TO LENGTH AND INSTALL. BACKFILL WITH EXCAVATED MATERIAL AND COMPACT. BACKFILL IS TO BE FREE OF LARGE ROCKS.
- ④ WHEN THE DISTANCE FROM BACK OF POST TO SHOULDER HINGE POINT IS LESS THAN 2 FEET INSTALL LONGER POST AT HALF POST SPACING (K).
- ⑤ FOR NEW MGS INSTALLATION TOP OF W-BEAM RAIL TOLERANCE IS $\pm 1"$. FOR EXISTING MGS INSTALLATION TOP OF W-BEAM IS BETWEEN 27 $\frac{3}{4}"$ TO 32".
- ⑥ WHEN USING STEEL POST AND WOOD BLOCKOUTS INSTALL FOUR 16D GALVANIZED NAILS. INSTALL NAILS AT THE BACK CORNERS OF THE BLOCK AND BEND THE NAILS OVER THE FLANGE OF THE STEEL POST.
- ⑦ TOTAL POST LENGTH FOR TYPE K IS 7' - 0".
TOTAL POST LENGTH FOR OTHER MGS TYPES IS 6' - 0".




WOOD POST (6" X 8") NOMINAL ⁽¹⁾




**MIDWEST GUARDRAIL SYSTEM
(MGS) GUARDRAIL**


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION




**FRONT VIEW
POST SPACING STANDARD INSTALLATION**




**FRONT VIEW
HALF POST SPACING (HS) AND
HALF POST SPACING WITH LONGER POSTS (K)**




**FRONT VIEW
QUARTER POST SPACING (QS)**




**FRONT VIEW
MID-SPAN BEAM SPLICE**



FRONT VIEW AT STEEL POST




FRONT VIEW AT WOOD POST



**ONE SIDED REFLECTOR DETAIL
AND TYPICAL INSTALLATION**

GENERAL NOTES


- ⑧ DO NOT INSTALL REFLECTORS ON THE FIRST 50 FEET OF THE APPROACH END OF THE ENERGY ABSORBING TERMINAL. RAIL SPLICE LOCATIONS ARE THE ONLY ACCEPTABLE LOCATIONS FOR REFLECTORS.
 - ⑨ 25 FEET OF HALF POST SPACING IS REQUIRED ON APPROACH AND DEPARTURE ENDS OF QUARTER POST SPACING.
- POST BOLTS ARE A 3/8" DIAMETER ASTM A307 GUARDRAIL BOLT. A POST BOLT REQUIRES 3/4" DIAMETER A563A DOUBLE RECESSED (DR) HEAVY HEX NUT AND 3/4" DIAMETER F844 FLAT WASHER. POST BOLTS MAY BE LONGER IF MULTIPLE BLOCKOUTS ARE BEING USED.
- GUARD RAIL SPLICE BOLTS ARE A 3/8" DIAMETER ASTM A307 GUARDRAIL HEAD BOLT. A GUARDRAIL SPLICE BOLT REQUIRES 3/4" DIAMETER A563A DOUBLE RECESSED (DR) HEAVY HEX NUT.



SECTION THRU W-BEAM RAIL


**MIDWEST GUARDRAIL SYSTEM
(MGS) GUARDRAIL**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION



DETAIL FOR 16" BLOCKOUT DEPTH

IT IS ACCEPTABLE TO USE BLOCKOUTS UP TO 16" DEEP TO INCREASE THE POST OFFSET TO AVOID UNDERGROUND OBSTACLES. THERE IS NO LIMIT TO THE NUMBER OF POSTS THAT CAN HAVE ADDITIONAL BLOCKOUTS UP TO 16" DEEP.




DETAIL FOR 36" BLOCKOUT DEPTH

NOTES: UNDER SPECIAL CIRCUMSTANCES, SUCH AS AVOIDING OBSTACLES THAT ARE NOT RELOCATED, IT IS ACCEPTABLE TO INSTALL ADDITIONAL BLOCKOUTS TO OBTAIN UP TO 36" DEPTH FOR ONE OR TWO POSTS IN A SECTION OF GUARDRAIL.

DO NOT USE 16" OR 36" BLOCKOUTS IF IT CAUSES THE POST TO BE DRIVEN BEYOND SHOULDER HINGE POINT OR CAUSES A FIXED OBJECT TO BE WITHIN THE DEFLECTION DISTANCE OF THE BARRIER.


NOTE:

1. ALL FILLETS SHALL HAVE A MINIMUM RADIUS OF $\frac{3}{16}$ ".
2. IF THE BOLT EXTENDS MORE THAN $\frac{1}{4}$ " FROM THE NUT THE BOLT SHOULD BE TRIMMED BACK.




POST BOLT TABLE

L	T (MIN.)
1 ¼"	1 ⅝"
2"	1 ¾"
10"	4"
14"	4 ⅙"
18"	4"
21"	4 ⅙"
25"	4"




ALTERNATE BOLT HEAD




POST BOLT, SPLICE BOLT AND RECESS NUT


- ⑥ WHEN USING STEEL POST AD WOOD BLOCKOUTS, INSTALL FOUR 16D GALVANIZED NAILS. INSTALL NAILS AT THE BACK CORNERS OF THE BLOCK AND BEND THE NAILS OVER THE FLANGE OF THE STEEL POST.




PLAN VIEW
BEAM LAPPING DETAIL



POST DRIVING FOR CONTINUOUS UNDERGROUND OBSTRUCTION



SIDE VIEW




PLAN VIEW


ALTERNATE WOOD BLOCKOUT DETAIL

MIDWEST GUARDRAIL SYSTEM (MGS) GUARDRAIL


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION




MISSING POST IN NORMAL BEAM GUARD RUN




MISSING POST NEAR APPROACH THRIE BEAM TRANSITION




MISSING POST IN NORMAL BEAM GUARD RUN NEAR EAT



MISSING POST IN NORMAL BEAM GUARD RUN
NEAR FLARED BEAM GUARD



MISSING POST IN NORMAL BEAM GUARD RUN
NEAR TYPE 2 TERMINAL



CROSS SECTION VIEW

- (1) MINIMUM OF 2 FEET OF GRADING BEHIND POST.
- (2) SEE SDD 14B45 FOR MORE DETAILS.
- (3) SEE SDD 14B47 FOR MORE DETAILS.
- (4) SEE SDD 14B44 FOR MORE DETAILS.
- (5) SEE MISSING POST IN NORMAL BEAM GUARD RUN FOR DISTANCE TO NEXT MISSING POST AND AREA FOR WELL DRAINED, COMPACTED SOILS.
- (6) SEE PLAN FOR SHOULDER DESIGN.

**MIDWEST GUARDRAIL SYSTEM
(MGS) GUARDRAIL**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
7/2018
DATE
/S/ Rodney Taylor
ROADWAY STANDARDS DEVELOPMENT
UNIT SUPERVISOR
FHWA

- (A) THE SLOPE IN THE AREA BOUNDED BY THE GRADELINE, THE HINGE POINT LINE (HPL) AND THE CLEAR ZONE LIMITS (CZL) SHALL BE 4:1 OR FLATTER.
- (B) AFTER FINAL ASSEMBLY, RECHECK CABLE TO BE SURE IT IS TAUT AND HAS NOT RELAXED
- (C) DIFFERENT MANUFACTURERS REQUIRE DIFFERENT PERFORATED W - BEAM RAIL END PANELS. SEE MANUFACTURER'S INFORMATION.
- (D) ATTACH ALUMINUM SHEET TO E.A.T. HEAD USING 4 STAINLESS STEEL SELF - TAPPING SCREWS. ONE SCREW PER CORNER.
- (E) HARDWARE MAY VARY BETWEEN MANUFACTURER. SEE MANUFACTURER'S DRAWING FOR INFORMATION.

DIMENSIONS MAY VARY, MANUFACTURER'S INFORMATION.

THE CENTER OF THE UPPER 3 1/2" DIAMETER HOLE ON POST NUMBER 3 THROUGH POST 9 IS TO BE FLUSH WITH THE GROUND LINE UP TO A MAXIMUM OF 2" ABOVE GROUND LINE. WOOD BLOCKS ON POSTS NUMBERED 3 THROUGH 9 MAY BE ADJUSTED UP TO 3" ABOVE THE TOP OF POST.





Diagram illustrating the plan view of a bridge structure, showing various slopes, clear zone limits, and dimensions. Key features include:

- Clear Zone Limits:** Indicated by dashed lines, either as shown elsewhere in the plans or, if not shown elsewhere, 15 feet beyond the hinge point line.
- Slopes:**
 - 4:1 TAPER:** Slope on the left side.
 - GRADELINE:** The line separating the bridge deck from the approach.
 - HINGE POINT LINE:** The line marking the end of the bridge structure.
 - SLOPE 10:1 MAX.:** Slope on the right side.
 - 25:1 FLARE:** Slope on the right side.
 - 2'-0" OFFSET TO FACE OF RAIL:** Offset from the face of the rail to the edge of the shoulder.
 - 5'-0" MIN. TO HINGE POINT:** Minimum distance from the hinge point to the edge of the shoulder.
 - SLOPE 10:1 OR FLATTER TO HINGE POINT:** Slope on the right side.
- Dimensions:**
 - 2'-0" (AT POST NO. 9):** Dimension from the edge of the shoulder to the face of the rail.
 - 5'-4" AT POST NO. 5:** Dimension from the edge of the shoulder to the face of the rail.
- Other Labels:**
 - EDGE OF SHOULDER:** The line marking the edge of the shoulder.
 - DIRECTION OF TRAVEL:** Indicated by arrows pointing right.
 - PLAN:** The title of the diagram.

PLAN



ELEVATION




Diagram illustrating the placement of a W5-59 sign and its mounting structure on a shoulder. The diagram shows the sign (W5-59) mounted on a post (13) with a height of 4'-0". The sign is positioned 1'-0" from the edge of the shoulder. The mounting structure is 1'-0" high. The sign is 2'-0" offset to the face of the rail. The sign is labeled W5-59, (D), (12), and (1). The mounting structure is labeled (13). The sign is placed behind post no. 1. The diagram also shows the shoulder hinge point, the slope (10:1 or flatter), and the normal slope. The distance from the hinge point to the sign is 5'-0" MIN. The distance from the hinge point to the sign is 1'-6" MIN. BELOW GRADE. The diagram also shows the shoulder hinge point, the slope (10:1 or flatter), and the normal slope. The distance from the hinge point to the sign is 1'-6" MIN. BELOW GRADE.

8

C

10

12

15

9

7

1

E

FINISHED GROUND ELEVATION

BOTTOM OF STRUT IS PLACED FLUSH WITH AND PARALLEL TO THE FINISHED SURFACE

14

16

POST NO. 2 *


DETAIL "B"

2

POST NO. 1 *


DETAIL "B"

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION




GENERIC GROUND STRUT⁹ ^E


BILL OF MATERIALS	
PART NO.	DESCRIPTION MATERIALS PROVIDED BY MGS EAT MANUFACTURER. SEE MANUFACTURER'S DETAILS FOR MORE INFORMATION.
①	UPPER POST NO. 1 6" X 6" TUBE
②	LOWER POST NO. 1
③	WOOD CRT
④	WOOD BLOCKOUT
⑤	PIPE SLEEVE
⑥	BEARING PLATE
⑦	BCT CABLE ASSEMBLY
⑧	ANCHOR CABLE BOX
⑨	GROUND STRUT
⑩	PERFORATED W-BEAM RAIL END PANEL, 12'-6" LONG.
⑪	STANDARD W-BEAM RAIL. MULTIPLE SECTIONS REQUIRED. SECTIONS VARY IN LENGTH.
⑫	IMPACT HEAD
⑬	EAT MARKER POST - YELLOW (SEE APPROVED PRODUCTS LIST)
⑭	SOIL PLATE
⑮	UPPER POST NO. 2
⑯	LOWER POST NO. 2




GENERIC ANCHOR CABLE BOX⁹ ^E




BEARING PLATE⁶ ^E




UPPER POST NO. 1 ⁽¹⁾ (E)




LOWER POST NO. 1 ⁽²⁾ (E)




WOOD CRT POST ⁽³⁾ (E)
POSTS NUMBER 3-9




UPPER POST NO. 2 ⁽¹⁵⁾ (E)




LOWER POST NO. 2 ⁽¹⁶⁾ (E)




WOOD BLOCKOUT ⁽⁴⁾
REQ'D. AT ALL POSTS EXCEPT POST NO'S 1 & 2




REFLECTIVE SHEETING DETAIL ^(E)



E.A.T. MARKER POST ⁽¹³⁾



SIDE VIEW




TOP VIEW

ALTERNATE WOOD
BLOCKOUT DETAIL


**MIDWEST GUARDRAIL SYSTEM
ENERGY ABSORBING TERMINAL
(MGS)**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
7/2018 DATE /S/ Rodney Taylor
ROADWAY STANDARDS DEVELOPMENT
UNIT SUPERVISOR
FHWA



TWO WAY TRAFFIC



ONE WAY TRAFFIC

(T) THRIE BEAM CONNECTION

(W) W-BEAM CONNECTION WHEN REQUIRED

TYPICAL LOCATIONS OF THRIE BEAM AND W-BEAM CONNECTIONS TO BRIDGE

GENERAL NOTES

IF ROCK IS ENCOUNTERED, REMOVE ROCK TO FULL DEPTH OF POST PLUS 2 1/2", AND 12" DIAMETER AROUND POST. SEE 14B42 FOR MORE DETAILS.

TRANSITION USES STEEL POSTS ONLY.


SEE STANDARD DETAIL DRAWING 14 B 42 FOR MORE INFORMATION.

POST 2 THROUGH 17 USES STEEL POST ONLY


① BRIDGE RAILING TYPE "W" DOES NOT REQUIRE A TERMINAL CONNECTOR.

② OPTIONAL CURB AND GUTTER OR DRAINAGE FEATURE SEE PLAN FOR INFORMATION.

⑬ STEEL OR WOOD POST IS ACCEPTABLE AT POST 1. SEE SDD14B42



PLAN VIEW



ELEVATION VIEW


MIDWEST GUARDRAIL SYSTEM THRIE BEAM TRANSITION

MIDWEST GUARDRAIL SYSTEM
THRIE BEAM TRANSITION (MGS)


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

GENERAL NOTES


- 2 OPTIONAL CURB AND GUTTER OR DRAINAGE FEATURE SEE PLAN FOR INFORMATION.
- 3 WHEN USING STEEL POSTS AND WOOD BLOCKOUTS INSTALL FOUR 10D GALVANIZED NAILS. INSTALL NAILS AT THE BACK CORNERS OF THE BLOCK AND BEND THE NAILS OVER THE FLANGE OF THE STEEL POST.
- 4 TOLERANCE FOR TOP OF W-BEAM RAIL IS $\pm 1"$.
- 13 STEEL OR WOOD POST IS ACCEPTABLE AT POST 1. SEE SDD 14B42




SECTION A-A
POSTS 1-5



SECTION D-D
POSTS 12-17



SECTION B-B
POST 6



SECTION C-C
POSTS 7-11







PLATE WASHER DETAIL



SPLICE DETAIL




THRIE BEAM
TERMINAL CONNECTOR




SECTION THRU THRIE
BEAM RAIL ELEMENT

MIDWEST GUARDRAIL SYSTEM
THRIE BEAM TRANSITION (MGS)


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION




W-BEAM TO THRIE BEAM TRANSITION SECTION




6'-3" THRIE BEAM SECTION



12'-6" THRIE BEAM SECTION




SIDE VIEW



TOP VIEW


ALTERNATE WOOD BLOCKOUT DETAIL




FRONT VIEW

SIDE VIEW

STEEL POSTS 1-5




TOP VIEW



FRONT VIEW


BLOCKOUT POSTS 1-5




FRONT VIEW

SIDE VIEW

STEEL POSTS 6-17



TOP VIEW



FRONT VIEW

BLOCKOUT POSTS 6-17

GENERAL NOTES

STEEL POSTS ARE W6X9 OR W6X8.5.

BOLT HOLES FOR POST ARE ON FRONT AND OF SIDE OF POST.


③ WHEN USING STEEL POSTS AND WOOD BLOCKOUTS INSTALL FOUR 16D GALVANIZED NAILS. INSTALL NAILS AT THE BACK CORNERS OF THE BLOCK AND BEND THE NAILS OVER THE FLANGE OF THE STEEL POST.

⑤ WOOD BLOCKS MAY BE CONSTRUCTED OUT OF 2 WOOD BLOCKS. SEE ALTERNATE WOOD BLOCK DETAIL.

⑬ STEEL OR WOOD POST IS ACCEPTABLE AT POST 1. SEE SDD 14B42.



**MIDWEST GUARDRAIL SYSTEM
THRIE BEAM TRANSITION (MGS)**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION




GENERAL NOTES

- THESE ARE TYPICAL CONNECTION DETAILS. ADJUST THE POSTION OF CONNECTIONS TO EXISTING BRIDGES TO FIT THE ACTUAL BRIDGE AND SITE DIMENSIONS.
- ② OPTIONAL CURB AND GUTTER OR DRAINAGE FEATURE SEE PLAN FOR INFORMATION.
- ④ TOLERANCE FOR TOP OF BEAM IS $\pm 1"$.
- ⑥ DRILLING BOLT HOLES THROUGH THE PARAPET, BOLTS, NUTS, WASHERS AND REPAIRING DAMAGED CONCRETE ARE INCIDENTAL TO THE CONTRACT.
- ⑦ BOLTS MAY BE A325 BOLTS OR A449 BOLTS. BOLT LENGTH AND THREADING LENGTH ARE TO ALLOW FOR A TIGHT CONNECTION BETWEEN RIGID BARRIER AND THRIE BEAM CONNECTION PLATE. CONTRACTOR IS TO FIELD VERIFY BOLT LENGTH AND THREAD LENGTH. ONE ROUND WASHER REQUIRED BETWEEN BOLT HEAD AND THRIE BEAM CONNECTOR PLATE. BOLTS THAT EXTEND THROUGH THE PARAPET AND OUT THE BACK FACE REQUIRE A HARDENED ROUND STEEL WASHER THAT IS 2" O.D. X 5/8" THICK AND ONE PLATE WASHER. REPAIR ANY DAMAGED CONCRETE FROM BOLT INSTALLATION.
- ⑧ THE RECESS FOR A W-BEAM CONNECTION, WHICH EXISTS ON SOME PARAPETS OF THIS TYPE, SHALL BE FILLED WITH A TREATED TIMBER BLOCKOUT. BLOCKOUT SIZE IS 1'-6" X 2'-0" X 3 1/2".




SECTION F-F





DRILL HOLE LOCATION

MIDWEST GUARDRAIL SYSTEM THRIE BEAM TRANSITION (MGS)	
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION	
APPROVED 07/2018 DATE	/S/ Rodney Taylor ROADWAY STANDARDS DEVELOPMENT UNIT SUPERVISOR
FHWA	



PLAN VIEW
DIVIDED HIGHWAY




PLAN VIEW
UNDIVIDED HIGHWAY


FLEXIBLE MARKER POST LOCATION

GENERAL NOTES

DETAILS OF CONSTRUCTION, MATERIALS AND WORKMANSHIP NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS AND THE APPLICABLE SPECIAL PROVISIONS.





PLAN VIEW
CONCRETE MASONRY ENDWALLS FOR
CULVERT PIPE AND PIPE ARCH




CROSS SECTION
FLEXIBLE MARKER POST

FLEXIBLE MARKER POST
FOR CULVERT END


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION




FLEXIBLE MARKER POSTS




SECTION A-A




SECTION B-B





SECTION C-C




DETAIL B



DETAIL C




FLEXIBLE MARKER POST ANCHORS



FRONT VIEW SIDE VIEW


ALTERNATE 3



FRONT VIEW SIDE VIEW

ALTERNATE 3

FLEXIBLE MARKER POST FOR CULVERT END	
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION	
APPROVED 10/1/2012 DATE	/S/ Travis Feltes STATE TRAFFIC ENGINEER OF DESIGN
FHWA	




DETAIL A
MAINLINE CLOSURE WITH POSTED DETOUR
WORK ZONE GREATER THAN OR EQUAL TO 1/2 MILE FROM
DETOUR ROUTE (1000 FEET IF URBAN)

DETAIL B
MAINLINE CLOSURE WITH POSTED DETOUR
WORK ZONE LESS THAN 1/2 MILE FROM
DETOUR ROUTE (1000 FEET IF URBAN)

- LEGEND**
- SIGN ON PERMANENT SUPPORT
 - TYPE III BARRICADE
 - TYPE III BARRICADE WITH ATTACHED SIGN
 - TYPE "A" WARNING LIGHT (FLASHING)
 - WORK AREA
 - FLAGS, 16" X 16" MIN. (ORANGE)

SPEED LIMIT (MPH)	"STOP AHEAD" ADVANCE WARNING DISTANCE (FT)
25	200
30	200
35	350
40	350
45	500
50	550
55	750

- DETOUR M4 - 8
- EAST M3 - X
- XX M1 - 4 OR XX M1 - 6 OR COUNTY M1 - 5A
- M05 - 1 OR M06 - 1




DETAIL C
MAINLINE CLOSURE, NO POSTED DETOUR

SEE SDD 15C2-SHEET "b"
FOR GENERAL NOTES
AND FOOTNOTES ① THROUGH ⑦


**BARRICADES AND SIGNS
FOR MAINLINE CLOSURES**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
November 2018 /S/ Andrew Heidtke
DATE WORK ZONE ENGINEER
FHWA



DETAIL D
ROAD CLOSURE BARRICADE DETAIL
APPROACH VIEW



DETAIL E
LANE CLOSURE BARRICADE DETAIL
APPROACH VIEW

SEE SDD 15C2 - SHEET "a" FOR LEGEND

GENERAL NOTES

THE EXACT NUMBER, LOCATION, AND SPACING OF ALL SIGNS AND BARRICADES SHALL BE ADJUSTED TO FIT FIELD CONDITIONS AS APPROVED BY THE ENGINEER.

ANY SIGNS TEMPORARY OR EXISTING, WHICH CONFLICT WITH TRAFFIC CONTROL "IN USE", SHALL BE REMOVED OR COVERED AS NEEDED AND AS APPROVED BY THE ENGINEER.

THE SPACING BETWEEN TRAFFIC CONTROL SIGNS SHOULD BE ADJUSTED TO NOT CONFLICT WITH AND SHOULD PROVIDE A DESIRABLE MINIMUM OF 200 FEET CLEARANCE TO EXISTING SIGNS THAT WILL REMAIN IN PLACE.

BARRICADES THAT MUST BE MOVED FOR A WORK OPERATION SHALL BE IMMEDIATELY RE-ESTABLISHED UPON COMPLETION OF THE OPERATION, OR FOR CONTINUING OPERATIONS, AT THE END OF EACH WORKING DAY.

SIGNS THAT WILL BE IN PLACE LESS THAN 7 CONTINUOUS DAYS AND NIGHTS MAY BE MOUNTED ON PORTABLE SUPPORTS.

ALL TYPE III BARRICADES SHALL HAVE RAILS REFLECTORIZED ON BOTH FACES. STRIPES SHALL BE PROPERLY SLOPED DOWN TOWARD THE TRAFFIC SIDE OR AS SHOWN IN THE ROAD CLOSURE BARRICADE DETAIL "D" FOR FULL ROAD CLOSURES.

TYPE "A" LOW - INTENSITY FLASHING WARNING LIGHTS SHALL BE VISIBLE ON BOTH SIDES OF THE BARRICADE.

THE R11 - 2, R11 - 3, M4 - 9, R11 - 4, AND R10 - 61 SIGNS PLACED ON THE BARRICADES SHALL COVER NO MORE THAN THE TOP RAIL. THE SIGNS SHALL NOT COVER ANY PORTION OF THE MIDDLE RAIL OR BOTTOM RAILS.

"WO" AND "MO" SIGNS ARE THE SAME AS "W" AND "M" SIGNS EXCEPT THE BACKGROUND IS ORANGE.

ALL SIGNS SHALL BE 48" X 48" UNLESS OTHERWISE NOTED BELOW:


- R11 - 2 SHALL BE 48" X 30"
- R11 - 3 SHALL, R11 - 4 AND R10 - 61 SHALL BE 60" X 30"
- M4 - 9 SHALL BE 30" X 24"
- M3 - X SHALL BE 24" X 12" (36" X 18" IF NEEDED TO MATCH EXISTING SIGNS)
- M4 - 8 SHALL BE 24" X 12" (36" X 18" IF NEEDED TO MATCH EXISTING SIGNS)
- M1 - 4, M1 - 5A AND M1 - 6 SHALL BE 24" X 24" (36" X 36" IF NEEDED TO MATCH EXISTING SIGNS)
- MO5 - 1 AND MO6 - 1 SHALL BE 21" X 21" (30" X 30" IF NEEDED TO MATCH EXISTING SIGNS)
- D1 - X SHALL BE AS SHOWN ON SPECIFIC PROJECT SIGNING DETAIL SHEETS.
- R1 - 1 SHALL BE 36" X 36"

- ① TWO WARNING LIGHTS SHALL BE PROVIDED ON THE CENTER BARRICADE AND A MINIMUM OF ONE WARNING LIGHT SHALL BE PROVIDED ON EACH OF THE OTHER BARRICADES WITHIN THE ROADWAY LIMITS. SPACING OF THE WARNING LIGHTS SHALL BE UNIFORM TO THE EDGE OF ROADWAY AS SHOWN (APPROX. 8 FOOT LIGHT SPACING).
- ② THESE SIGNS AND BARRICADES ARE NOT REQUIRED IF ROAD CLOSURE BEGINS AT AN INTERSECTION.
- ③ FOR ROAD CLOSURE WITHOUT LOCAL ACCESS TO PROJECT, SEE ROAD CLOSURE BARRICADE DETAIL "D".
- ④ FOR ROAD CLOSURE WITH LOCAL ACCESS TO PROJECT, SEE ROAD CLOSURE BARRICADE DETAIL "E".
- ⑤ FOR BRIDGE OR CULVERT REPLACEMENTS, SUBSTITUTE "BRIDGE OUT" INSTEAD OF "ROAD CLOSED" ON R11 - 2 AND R11 - 3 SIGNS.
- ⑥ INSTALL DETOUR AND COMMUNITY GUIDE SIGNS AND ARROWS ONLY IF SPECIFIED IN THE CONTRACT. IF THERE ARE EXISTING ROUTE MARKER ASSEMBLIES THAT WILL REMAIN IN PLACE, ADJUST THE LOCATION OF THE DETOUR ROUTE SIGNS TO CORRESPOND WITH THE EXISTING ASSEMBLIES. MODIFY EXISTING SIGNS WHERE POSSIBLE. SEE SPECIFIC PROJECT DETOUR SIGNING DETAIL SHEETS. IF DETOUR SIGNS ARE BEING INSTALLED BY OTHERS, PLACE THE CONTRACTED TRAFFIC CONTROL SIGNS TO ALLOW FOR PLACEMENT OF ALL WARNING, DETOUR AND GUIDE SIGNS AS SHOWN.
- ⑦ "EAST" CARDINAL DIRECTION MARKERS AND RIGHT TURN ARROWS ARE SHOWN. USE OTHER CARDINAL DIRECTIONS AND ARROWS AS APPROPRIATE.

BARRICADES AND SIGNS FOR VARIOUS CLOSURES

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION


APPROVED
November 2018 /S/ Andrew Heidtke
DATE WORK ZONE ENGINEER
FHWA



SEE SPECIFIC PROJECT DETOUR
SIGNING DETAIL SHEETS AND
DETAIL A OR B ON SDD SHEET 15C02 - SHEET "a"


THIS DRAWING PROVIDES GENERAL GUIDANCE
ON TYPICAL DETOUR SIGN LAYOUT AND SPACING.
SEE PROJECT DETOUR SIGNING SHEETS FOR
SPECIFIC DETAILS FOR EACH PROJECT.

MATCH POINT



DETAIL F
DETOUR SIGNING

LEGEND



GENERAL NOTES

THE EXACT NUMBER, LOCATION AND SPACING OF ALL SIGNS SHALL BE ADJUSTED TO FIT FIELD CONDITIONS AS APPROVED BY THE ENGINEER.

IF THERE ARE EXISTING ROUTE MARKER ASSEMBLIES THAT WILL REMAIN IN PLACE, ADJUST THE LOCATION OF THE DETOUR ROUTE SIGNS TO CORRESPOND WITH THE EXISTING ASSEMBLIES. SEE SPECIFIC PROJECT DETOUR SIGNING DETAIL SHEETS. MODIFY EXISTING SIGNS WHERE POSSIBLE.

THE SPACING BETWEEN TRAFFIC CONTROL AND DETOUR SIGNS SHOULD BE ADJUSTED TO NOT CONFLICT WITH AND TO PROVIDE A DESIRABLE MINIMUM OF 200 FEET CLEARANCE TO EXISTING SIGNS THAT WILL REMAIN IN PLACE.

ANY SIGNS TEMPORARY OR EXISTING, WHICH CONFLICT WITH TRAFFIC CONTROL "IN USE" SHALL BE REMOVED OR COVERED AS NEEDED AND AS APPROVED BY THE ENGINEER.


SIGNS THAT WILL BE IN PLACE LESS THAN 7 CONTINUOUS DAYS AND NIGHTS MAY BE MOUNTED ON PORTABLE SUPPORTS.

"MO" SIGNS ARE THE SAME AS "M" SIGNS EXCEPT THE BACKGROUND IS ORANGE.

SIGN SIZES SHALL BE AS FOLLOWS:

- M3-X SHALL BE 24" X 12" (36" X 18" IF NEEDED TO MATCH EXISTING SIGNS)
- M4-8 SHALL BE 24" X 12" (36" X 18" IF NEEDED TO MATCH EXISTING SIGNS)
- M1-4, M1-5A AND M1-6 SHALL BE 24" X 24" (30" X 30" IF NEEDED TO MATCH EXISTING SIGNS)
- M05-1 AND M06-1 SHALL BE 21" X 21" (30" X 30" IF NEEDED TO MATCH EXISTING SIGNS)
- M4-9 AND M4-59 SHALL BE 30" X 24"
- M4-8a SHALL BE 24" X 18"
- G20-51 SHALL BE 60" X 24"
- W20-2A SHALL BE 48" X 48"
- D1-X SHALL BE AS SHOWN ON SPECIFIC PROJECT SIGNING DETAIL SHEETS.

- * OPTIONAL SIGNS. SEE SPECIFIC PROJECT DETOUR SIGNING DETAIL SHEETS.
- ** FOR A TOWN ROAD OR LOCAL STREET DETOURED ONTO A STATE TRUNK HIGHWAY, PLACE A ROAD NAME PLAQUE ABOVE THE M4-9 SIGN AS SPECIFIED IN THE CONTRACT.




PLACE SIGNS BEYOND INTERSECTIONS
WITH STATE OR COUNTY TRUNK
HIGHWAYS OR AT 4 MILE MAXIMUM
SPACING (4 BLOCKS IF URBAN AREA)


DETOUR SIGNING
FOR MAINLINE CLOSURES

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION


APPROVED
November 2018 /S/ Andrew Heidtke
DATE WORK ZONE ENGINEER
FHWA




DETAIL 1
(NO ACCESS TO PROJECT)



DETAIL 3
(PUBLIC CROSS-TRAFFIC MAINTAINED. CONTRACTOR, LOCAL BUSINESS AND RESIDENT ACCESS).



DETAIL 2
(PUBLIC CROSS-TRAFFIC MAINTAINED. NO ACCESS TO PROJECT).



DETAIL 4
(CONTRACTOR, LOCAL BUSINESS AND RESIDENT ACCESS TO PROJECT)

GENERAL NOTES

THE EXACT NUMBER, LOCATION, AND SPACING OF ALL SIGNS AND BARRICADES SHALL BE ADJUSTED TO FIT FIELD CONDITIONS AS APPROVED BY THE ENGINEER.

ANY SIGNS TEMPORARY OR EXISTING, WHICH CONFLICT WITH TRAFFIC CONTROL "IN USE" SHALL BE REMOVED OR COVERED AS NEEDED AND AS APPROVED BY THE ENGINEER.

THE SPACING BETWEEN TRAFFIC CONTROL SIGNS SHOULD BE ADJUSTED TO NOT CONFLICT WITH AND SHOULD PROVIDE A DESIRABLE MINIMUM OF 200 FEET CLEARANCE TO EXISTING SIGNS THAT WILL REMAIN IN PLACE.

IF A "STOP" SIGN MUST BE REMOVED FOR A WORK OPERATION, A TEMPORARY "STOP" SIGN SHALL BE PLACED PRIOR TO THE SIGN REMOVAL, OR A FLAGGER SHALL BE PROVIDED UNTIL THE SIGN IS RE-ESTABLISHED.

BARRICADES THAT MUST BE MOVED FOR A WORK OPERATION SHALL BE IMMEDIATELY RE-ESTABLISHED UPON COMPLETION OF THE OPERATION OR, FOR CONTINUING OPERATIONS, AT THE END OF EACH WORKING DAY.

SIGNS THAT WILL BE IN PLACE LESS THAN 7 CONTINUOUS DAYS AND NIGHTS MAY BE MOUNTED ON PORTABLE SUPPORTS.

ALL TYPE III BARRICADES SHALL HAVE RAILS REFLECTORIZED ON BOTH FACES. STRIPES SHALL BE PROPERLY SLOPED DOWN TOWARD THE TRAFFIC SIDE OR AS SHOWN IN THE ROAD CLOSURE BARRICADE DETAIL D FOR FULL ROAD CLOSURES.

TYPE "A" LOW-INTENSITY FLASHING WARNING LIGHTS SHALL BE VISIBLE ON BOTH SIDES OF THE BARRICADE.

THE R11-2, R11-3 AND R11-4 SIGNS PLACED ON BARRICADES SHALL COVER NO MORE THAN THE TOP RAIL. THE SIGNS SHALL NOT COVER ANY PORTION OF THE MIDDLE OR BOTTOM RAILS.

ALL SIGNS SHALL BE 48" X 48" UNLESS OTHERWISE NOTED BELOW:

R11-2 SHALL BE 48" X 30".

R11-4 AND R11-3 SHALL BE 60" X 30".

*OMIT THE "ROAD CLOSED 500 FT." SIGN IF THE LAST INTERSECTION IS 500 FT. OR LESS FROM THE WORK ZONE.

**500' MAX. OR AT LAST INTERSECTION WHICHEVER IS CLOSER.


LEGEND

- SIGN ON PERMANENT SUPPORT
- TYPE III BARRICADE
- TYPE III BARRICADE WITH ATTACHED SIGN
- TYPE "A" WARNING LIGHT (FLASHING)
- WORK AREA


BARRICADES AND SIGNS FOR SIDEROAD CLOSURES

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
7/2018
DATE
/S/ Andrew Heidtke
WORK ZONE ENGINEER
FHWA




TWO WAY TRAFFIC




ONE WAY TRAFFIC

PERMANENT PAVEMENT MARKING



TWO WAY TRAFFIC



ONE WAY TRAFFIC

TEMPORARY PAVEMENT MARKING

GENERAL NOTES

DETAILS OF CONSTRUCTION NOT SHOWN ON THIS DRAWING SHALL CONFORM TO STANDARD SPECIFICATIONS AND SPECIAL PROVISIONS.

- ① LOCATE THE NO PASSING ZONE W14-3 SIGN WITHIN 50 FEET OF THE "T" MARKING.

NOTE

ARROW SYMBOL (→) SHOWS DIRECTION OF TRAVEL


LEGEND

- "T" MARKING
- POST MOUNTED SIGN

LONGITUDINAL MARKING
(MAINLINE)

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
7/2018 /S/ Matthew R. Rauch
DATE STATE SIGNING AND MARKING ENGINEER
FHWA





DETAIL OF TUBULAR STEEL SIGN POST

TUBULAR STEEL POSTS

AREA OF SIGN INSTALLATION (SQ. FT.)	NUMBER OF REQUIRED TUBULAR STEEL POSTS
9 OR LESS	1
GREATER THAN 9 LESS THAN OR EQUAL TO 18	2
GREATER THAN 18 LESS THAN OR EQUAL TO 27	3

SIGNS WIDER THAN 3 FEET OR LARGER THAN 9 SQ. FT. SHALL BE MOUNTED ON MULTIPLE POSTS (SEE ABOVE TABLE).

SIGNS LARGER THAN 27 SQ. FT. SHALL NOT BE MOUNTED ON TUBULAR STEEL POSTS.




URBAN AREA


POST MOUNTING DETAIL FOR TEMPORARY TRAFFIC CONTROL FIXED MESSAGE SIGNS

WOOD POST EMBEDMENT DEPTH

AREA OF SIGN INSTALLATION (SQ. FT.)	D (MIN)
20 OR LESS	4'
GREATER THAN 20	5'



4" x 6" WOOD POST MODIFICATION



RURAL AREA

4" X 6" WOOD POST

POST SPACING REQUIREMENTS		NUMBER OF WOOD POSTS REQUIRED
L	E	
48" OR LESS AND LESS THAN 20 SQ. FT.	-	1
LESS THAN 60"	12"	2
60" TO 120"	L/5	2
GREATER THAN 120" LESS THAN 168"	12"	3
168" AND GREATER	12"	4


SEE NOTE ③

GENERAL NOTES

- ① 6 FEET FROM THE EDGE OF PAVEMENT (EDGE LINE LOCATION) UNLESS OTHERWISE DIRECTED BY THE PROJECT ENGINEER. LATERAL OFFSET SHOULD BE ADJUSTED TO AVOID THE DITCH FLOWLINE.
- ② THE EXISTENCE OF CURB AND GUTTER DOES NOT IN ITSELF MANDATE THE VERTICAL CLEARANCE ILLUSTRATED. THAT HEIGHT IS TYPICALLY MEASURED WHERE THERE IS SIDEWALK ADJACENT TO THE ROADWAY OR PARKING IS PERMITTED. IN THE ABSENCE OF SIDEWALK, VERTICAL CLEARANCE IS MEASURED FROM THE TOP OF THE CURB. IF NO SIDEWALK AND NO PARKING, VERTICAL CLEARANCE MAY BE REDUCED TO 5 FOOT MINIMUM. OFFSET OF SIGNS IS MEASURED FROM THE CURB FLOWLINE.
- ③ FOR SIGNS REQUIRING 4 POSTS, SPACE INTERMEDIATE POSTS EVENLY.

TEMPORARY TRAFFIC CONTROL SIGN MOUNTING

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION



NUTS, BOLTS AND LAGS USED FOR MOUNTING SIGNS SHALL HAVE HEXAGONAL HEADS AND SHALL BE EITHER:

- A. HOT DIP GALVANIZED IN ACCORDANCE WITH ASTM DESIGNATION: A 153, CLASS D, OR SC 3
- B. ELECTRO-GALVANIZED IN ACCORDANCE WITH ASTM DESIGNATION: B 633, TYPE III, SC 3

THREADS ON BOLTS AND NUTS SHALL BE MANUFACTURED WITH SUFFICIENT ALLOWANCE FOR THE CADMIUM PLATE OR GALVANIZED COATING TO PERMIT THE NUTS TO RUN FREELY ON THE BOLTS.

- WOOD POSTS (4" x 4" or 4" x 6")
- LAG SCREWS - 3/8" x 3"
 - MACHINE BOLTS - 5/16" x 6-1/2" OR 7" LENGTH W/ NUTS



- SQUARE STEEL POSTS (2" x 2")
- MACHINE BOLTS - 3/8" x 3-1/4" LENGTH W/ NUTS
 - RIVETS - 9/32" (6605-9-6) BULB-TITE, TRI-FOLD, ALUMINUM BODY/MANDREL O.D. FLANGE .720-.765 INCH, GRIP RANGE .042-.375 INCH

- WASHERS (ALL POSTS) -
- 1-1/4" O.D. x 3/8" I.D. x 1/16" STEEL
 - 1-1/4" O.D. x 3/8" I.D. x .080 NYLON FOR ALL TYPE H SIGNS

* TWO DIFFERENT FASTENING SYSTEMS ARE SHOWN FOR ILLUSTRATION PURPOSES. ON ANY INDIVIDUAL SIGN, EITHER ONE OR THE OTHER SYSTEM SHALL BE USED. ACTUAL NUMBER OF FASTENERS PER SIGN VARIES WITH THE SIGN AREA. FOR A SINGLE POST INSTALLATION, ALL SIGNS GREATER THAN 9 SQ. FT. REQUIRE THE USE OF 3 FASTENERS.



ATTACHMENT OF SIGNS TO POSTS	
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION	
APPROVED June 2017 DATE	/S/ Andrew Heldtke WORK ZONE ENGINEER
FHWA	

URBAN AREA



✱✱ The existence of curb and gutter does not in itself mandate the vertical clearance illustrated. That height is typically measured where there is sidewalk adjacent to the roadway or parking is permitted. In the absence of sidewalk vertical clearance is measured from the top of the curb. Offset of signs is measured from the flow line.

RURAL AREA (See Note 2)



* 6 feet from edge of a paved shoulder or 12 feet from the edge of pavement (edge line location) or 2 feet from outside edge of gravel, whichever is greater unless directed by project engineer.

POST EMBEDMENT DEPTH

Area of Sign Installation (Sq. Ft.)	D (Min)
20 or Less	4'
Greater than 20	5'

GENERAL NOTES


1. Signs wider than 4 feet or 20 sq.ft or larger, shall be mounted on multiple posts. Refer to plate A4-4.
2. If signs are mounted on barrier wall, see A4-10 sign plate.
3. For expressways and freeways, mounting height is 7'-3" (±) or 6'-3" (±) depending upon existence of a sub-sign.
4. J-Assemblies are considered to be one sign for mounting height.
5. Minimum mounting height for signs mounted on traffic signal poles is 5'-3" (±).
6. Offset distance shall be consistent with existing signs or consistent throughout length of project.
7. The (±) tolerance for mounting height is 3 inches.
8. Folding signs shall be mounted at a height of 5'-3" (±) or as directed by the Engineer.
9. The Double Arrow sign (W12-1) shall be mounted at a height of 2'-3" (±). The Chevron sign (W1-8), Roundabout Chevron panel (R6-4B), Enhanced Reference Markers, Clearance Markers (W5-52), Mile Markers (D10 series), In Road Object Markers (W5-54) & End of Road Markers (W5-56) shall be mounted at a height of 4'-3" (±).

TYPICAL INSTALLATION
OF PERMANENT TYPE II
SIGNS ON SINGLE POSTS

WISCONSIN DEPT OF TRANSPORTATION

APPROVED *Matthew R. Rauch*
for State Traffic Engineer

DATE 8/21/17 PLATE NO. A4-3.21



Nuts, bolts and lags used for mounting signs shall have hexagonal heads and shall be either :



- a. Hot dip galvanized in accordance with ASTM Designation: A 153, Class D, or SC 3
- b. Electro-galvanized in accordance with ASTM Designation : B 633, TYPE III, SC 3.

Threads on bolts and nuts shall be manufactured with sufficient allowance for the cadmium plate or galvanized coating to permit the nuts to run freely on the bolts.

- STRINGER BOLTING TO ALUMINUM SIGNS (SEE SIGN PLATE A4-18)
- MACHINE BOLTS - 5/16" X 1-3/4" Length w/ lock nuts
- WOOD POSTS (4" x 4" or 4" x 6")
- LAG SCREWS - 3/8" X 3" (NO STRINGERS ON BACK OF SIGN)
 - 3/8" X 4" (STRINGERS ON BACK OF SIGN)
- SQUARE STEEL POSTS (2" x 2")
- MACHINE BOLTS - 3/8" X 3-1/4" Length w/ nuts (NO STRINGER ON BACK OF SIGN)
 - 3/8" X 5" Length w/ nuts (STRINGERS ON BACK OF SIGN)
- RIVETS - 9/32" (6605-9-6) BULB-TITE, TRI-FOLD, ALUMINUM BODY/MANDREL
- O.D. FLANGE .720-.765 INCH, GRIP RANGE .042-.375 INCH
- WASHERS (ALL POSTS) -
- 1-1/4" O.D. X 3/8" I.D. X 1/16" STEEL
 - 1-1/4" O.D. X 3/8" I.D. X .080 NYLON

* Two different fastening systems are shown for illustration purposes. On any individual sign, either one or the other system shall be used. Actual number of fasteners per sign varies with the sign area, but normally there are two. For a single post installation, all signs greater than 9 sq. ft. require the use of 3 fasteners.

ATTACHMENT OF SIGNS TO POSTS	
WISCONSIN DEPT OF TRANSPORTATION	
APPROVED	<i>Matthew R. Rauch</i> For State Traffic Engineer
DATE 8/11/16	PLATE NO. A4-8.8



SIDE VIEW

GENERAL NOTES

1. All 4 x 6 Wood Posts shall be modified by having two 1 1/2" diameter holes drilled perpendicular to the roadway centerline.

4 X 6 WOOD POST MODIFICATIONS

WISCONSIN DEPT OF TRANSPORTATION

APPROVED

Chester J. Spang
for State Traffic Engineer

DATE 3/27/97

PLATE NO. A4-11.2

PROJECT NO:


HWY:

COUNTY:

SHEET NO:

E

7



NOTES

- 1. Sign is Type II - Type H Reflective - reference WIS DOT Standard Specification for HIGHWAY and STRUCTURE CONSTRUCTION latest edition.
- 2. Color:
Background - Red
Message - White
- 3. Message Series - C

7

SIZE	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	Q	R	S	T	U	V	W	X	Y	Z	Area sq. ft.
1	30				5/8	10	12 1/2	45°		12 3/4																	5.18
2S	30				5/8	10	12 1/2	45°		12 3/4																	5.18
2M	36				3/4	12	15	45°		15 3/8																	7.46
3	36				3/4	12	15	45°		15 3/8																	7.46
4	48				1	16	20	45°		20 1/2																	13.25
5	48				1	16	20	45°		20 1/2																	13.25
6	18				3/8	6	7 3/4	45°		7 3/4																	1.86
7	12				1/4	4	5	45°		5 1/8																	0.78


STANDARD SIGN

R1 - 1


WISCONSIN DEPT OF TRANSPORTATION

APPROVED *Matthew R. Rauch*
for State Traffic Engineer


DATE 11/12/15 PLATE NO. R1-1.13



PLAN
SINGLE-SPAN REINFORCED CONCRETE FLAT SLAB



ELEVATION
LOOKING NORMAL TO C/L SUBSTRUCTURES




DETAIL
AT BOTH ENDS OF BRIDGE

BENCHMARK (DATUM = NAVD 88)				
NO.	STATION	DESCRIPTION	ELEV	
1	76+68.91, 22.78' LT	RR SPIKE IN PP	745.98	
2	82+98.37, 83.83' RT	TOP C/L BOTTOM CONC STEP AT HOUSE N7414	754.23	
3	78+90.53, 12.17' RT	TOP METAL RAIL EXISTING PROJECT BRIDGE	750.50	

LIST OF DRAWINGS

- 1 GENERAL PLAN
- 2 CROSS SECTION AND QUANTITIES
- 3 SUBSURFACE EXPLORATION
- 4-6 SOUTH ABUTMENT DETAILS
- 7-10 NORTH ABUTMENT DETAILS
- 11-12 SUPERSTRUCTURE DETAILS
- 13 SINGLE SLOPE PARAPET 42SS
- 14 MISCELLANEOUS DETAILS



SEH CONTACT: CHRIS BLUM, PE, 608.620.6192
WISDOT BRIDGE OFFICE CONTACT: BILL DREHER, PE, 608.266.8489

STATE PROJECT NUMBER

7345-00-70

DESIGN DATA

LIVE LOAD:
DESIGN LOADING: HL-93
INVENTORY RATING FACTOR: RF = 1.09
OPERATING RATING FACTOR: RF = 1.41
WISCONSIN STANDARD PERMIT VEHICLE (WIS-SPV) = 250 KIPS
STRUCTURE IS DESIGNED FOR A FUTURE WEARING SURFACE OF 20 PSF
INVENTORY AND OPERATING RATINGS DO NOT INCLUDE FUTURE WEARING SURFACE.

MATERIAL PROPERTIES:
CONCRETE MASONRY - SUPERSTRUCTURE f'c = 4,000 psi
- ALL OTHER f'c = 3,500 psi
HIGH STRENGTH BAR STEEL REINFORCEMENT AASHTO GRADE 60 fy = 60,000 psi

FOUNDATION DATA

SOUTH ABUTMENT TO BE SUPPORTED ON 14" DIA CIP PILES (0.25 SHELL THICKNESS) WITH A REQUIRED DRIVING RESISTANCE OF 120 TONS* PER PILE AS DETERMINED BY THE MODIFIED GATES DYNAMIC EQUATION, ESTIMATED 60-FEET LONG.
NORTH ABUTMENT TO BE SUPPORTED ON 14" DIA CIP PILES (0.25 SHELL THICKNESS) WITH A REQUIRED DRIVING RESISTANCE OF 150 TONS* PER PILE AS DETERMINED BY THE MODIFIED GATES DYNAMIC EQUATION, ESTIMATED 60-FEET LONG.

*THE FACTORED AXIAL RESISTANCE OF PILES IN COMPRESSION USED FOR DESIGN IS THE REQUIRED DRIVING RESISTANCE MULTIPLIED BY A RESISTANCE FACTOR OF 0.5 USING MODIFIED GATES TO DETERMINE DRIVEN PILE CAPACITY.

HYDRAULIC DATA

100 YEAR FREQUENCY
Q₁₀₀ 1400 CFS
Q₁₀₀ THRU STRUCTURE 1400 CFS
VELOCITY 9.0 FPS
HIGH WATER₁₀₀ EL 742.72 FT
WATERWAY AREA 155 SQ FT
DRAINAGE AREA 6.2 SQ MI



TRAFFIC DATA


ADT (2020) = 4700
ADT (2040) = 7500
DHV = 803
DD = 60/40 %
T = 2.9 %
DESIGN SPEED = 60 MPH

2 YEAR FREQUENCY


Q₂ 250 CFS
Q₂ HIGH WATER EL 737.08 FT
Q₂ VELOCITY 5.2 FPS

SCOUR CODE 8

NO.	DATE	REVISION	BY
<div> SHORT ELLIOTT HENDRICKSON INC.</div>			
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION			
ACCEPTED	 SDR		09/19/19
CHIEF STRUCTURES DESIGN ENGINEER		DATE	
STRUCTURE B-32-237			
CTH V OVER LONG COULEE CREEK			
COUNTY	LA CROSSE	TOWN/CITY/VILLAGE	HOLLAND
DESIGN SPEC. AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS			
DESIGNED BY	CJB	DESIGN CK'D.	TN
DRAWN BY	DLF	PLANS CK'D.	CJB
GENERAL PLAN			SHEET 1 OF 14



PROFILE GRADE LINE



CROSS SECTION THRU BRIDGE
(LOOKING NORTH)

TOTAL ESTIMATED QUANTITIES - B-32-237


BID ITEM NUMBER	BID ITEMS	UNIT	SOUTH ABUT	NORTH ABUT	SUPER	TOTALS
203.0600.S	REMOVING OLD STRUCTURE OVER WATERWAY WITH MINIMAL DEBRIS STATION 79+02	LS	-	-	-	1
206.1000	EXCAVATION FOR STRUCTURES BRIDGES B-32-237	LS	-	-	-	1
① 210.1500	BACKFILL STRUCTURE TYPE A	TON	285	285	-	570
⑤ 502.0100	CONCRETE MASONRY BRIDGES	CY	61	70	209	340
③ 502.3200	PROTECTIVE SURFACE TREATMENT	SY	-	-	247	247
④ 502.3210	PIGMENTED SURFACE SEALER	SY	-	-	83	83
505.0400	BAR STEEL REINFORCEMENT HS STRUCTURES	LB	3470	4350	-	7820
⑤ 505.0600	BAR STEEL REINFORCEMENT HS COATED STRUCTURES	LB	2615	3930	39,685	46,230
516.0500	RUBBERIZED MEMBRANE WATERPROOFING	SY	13	15	-	28
550.2144	PILING CIP CONCRETE 14 x 0.25-INCH	LF	720	660	-	1380
606.0300	RIPRAP HEAVY	CY	115	130	-	245
② 612.0406	PIPE UNDERDRAIN WRAPPED 6-INCH	LF	130	140	-	270
614.0150	ANCHOR ASSEMBLIES FOR STEEL PLATE BEAM GUARD	EA	-	-	4	4
645.0111	GEOTEXTILE TYPE DF SCHEDULE A	SY	45	45	-	90
645.0120	GEOTEXTILE TYPE HR	SY	250	270	-	520
NON-BID ITEMS						
	FILLER	SIZE	—	—	—	1/2 & 3/4
	NAMEPLATE	SIZE	1	—	—	1

- ① A FACTOR OF 2.0 WAS USED TO CONVERT CU YDS TO TONS.
- ② INCLUDES RODENT SHIELD FOR PIPE UNDERDRAIN PER SDD 8F6-4.
- ③ FURNISH AND APPLY A PROTECTIVE SURFACE TREATMENT TO THE ENTIRE TOP OF THE BRIDGE DECK AND PAVING NOTCH AREA.
- ④ APPLY PIGMENTED SURFACE SEALER TO THE INSIDE FACES, ENDS, AND TOP OF THE CONCRETE PARAPETS PER THE STANDARD SPECIFICATIONS AND THE SUPERSTRUCTURE DETAILS SHEET.
- ⑤ INCLUDES ITEMS FOR 42SS PARAPETS.

GENERAL NOTES

- DRAWINGS SHALL NOT BE SCALED.
- FOR EXISTING STRUCTURE SEE PROFILE GRADE LINE THIS SHEET.
- REFER TO ROADWAY DRAWINGS FOR EXISTING UTILITY LOCATIONS.
- BAR STEEL REINFORCEMENT SHALL BE EMBEDDED 2" CLEAR UNLESS OTHERWISE SHOWN OR NOTED.
- THE FIRST OR FIRST TWO DIGITS OF THE BAR MARK SIGNIFIES THE BAR SIZE.
- BEVEL EXPOSED EDGES OF CONCRETE 3/4" UNLESS OTHERWISE NOTED.
- SLAB FALSEWORK SHALL BE SUPPORTED ON PILES OR THE SUBSTRUCTURE UNLESS AN ALTERNATE METHOD IS APPROVED BY THE ENGINEER.
- THE SLOPE OF THE FILL IN FRONT OF THE ABUTMENTS SHALL BE COVERED WITH RIPRAP HEAVY AND GEOTEXTILE TYPE HR TO THE EXTENT SHOWN ON THE GENERAL PLAN SHEET AND IN THE ABUTMENTS DETAILS.
- SEAL ALL EXPOSED HORIZONTAL AND VERTICAL SURFACES OF 1/2" FILLER WITH NON-STAINING GRAY NON-BITUMINOUS JOINT SEALER (1" DEEP & HOLD 1/8" BELOW SURFACE OF CONCRETE).
- THE UPPER LIMITS OF EXCAVATION FOR STRUCTURES BRIDGES B-32-237 SHALL BE THE EXISTING GROUNDLINE.
- EXCAVATION BELOW THE ABUTMENTS AND ABUTMENTS BEDDING MATERIALS REQUIRES ENGINEER APPROVAL. GEOTEXTILE SHALL BE SET AT THE BOTTOM OF EXCAVATION AND EXTEND 2'-0" ABOVE BOTTOM OF ABUTMENT.
- THE QUANTITY FOR BACKFILL STRUCTURE TYPE A IS CALCULATED BASED ON THE BACKFILL STRUCTURE LIMITS DETAILS SHOWN ON SHEET 14.
- BACKFILL STRUCTURE BEYOND BACKFILL PAY LIMITS SHALL BE INCIDENTAL TO EXCAVATION FOR STRUCTURES. LIMITS OF EXCAVATION SHALL BE DETERMINED BY THE CONTRACTOR.
- AT THE BACKFACE OF ABUTMENTS ALL VOLUME WHICH CANNOT BE PLACED BEFORE ABUTMENT CONSTRUCTION AND IS NOT OCCUPIED BY THE NEW STRUCTURE SHALL BE BACKFILLED WITH STRUCTURE BACKFILL.
- JOINT FILLER SHALL CONFORM TO THE REQUIREMENTS OF AASHTO DESIGNATION M153 TYPE 1, 2, OR 3 OR AASHTO DESIGNATION M213.
- APPLY A PROTECTIVE SURFACE TREATMENT PER THE STANDARD SPECIFICATIONS AND THE SUPERSTRUCTURE DETAILS SHEET.
- SEE ROADWAY PLANS FOR ADDITIONAL RIPRAP REQUIRED.

NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION			
STRUCTURE B-32-237			
DRAWN BY		DLF	PLANS CK'D. CJB
CROSS SECTION AND QUANTITIES			SHEET 2 OF 14



BORING #	DATE COMPLETED	NORTHING (Y)	EASTING (X)
B-1	2-19-2016	-	-
B-2	2-22-2016	-	-
B-3	2-22-2016	-	-
B-4	2-22-2016	-	-


STATE PROJECT NUMBER

7345-00-70

MATERIAL SYMBOLS

	ASPHALT		TOPSOIL		PEAT
	CONCRETE		FILL		GRAVEL
	SAND		CLAY		SILT
	BOULDERS OR COBBLES		LIMESTONE		BEDROCK (UNKNOWN)
	SHALE		SANDSTONE		IGNEOUS/META

LEGEND OF BORING



- (1) UNCONFINED STRENGTH, AS DETERMINED BY A POCKET PENETROMETER (TSF)
- (2) UNLESS OTHERWISE, SPECIFIED THE SPT 'N' VALUE IS BASED ON AASHTO T-206, STANDARD PENETRATION TEST. THE SPT 'N' VALUE PRESENTED HAS NOT BEEN CORRECTED FOR OVERBURDEN PRESSURE OR HAMMER EFFICIENCY.

GROUND WATER ELEVATION

- ▽ AT TIME OF DRILLING
- ▼ END OF DRILLING
- ▽ AFTER DRILLING

ABBREVIATIONS

F-FINE M-MEDIUM C-COARSE ST-SHELBY TUBE

SUBSURFACE EXPLORATION FOR FOUNDATION DESIGN AND BIDDERS INFORMATION

BORINGS WERE COMPLETED AT POINTS APPROXIMATELY AS INDICATED ON THIS DRAWING TO OBTAIN INFORMATION CONCERNING THE CHARACTER OF SUBSURFACE MATERIALS FOUND AT THE SITE. BECAUSE THE INVESTIGATED DEPTHS ARE LIMITED AND THE AREA OF THE BORINGS IS VERY SMALL IN RELATION TO THE ENTIRE SITE, THE WISCONSIN DEPARTMENT OF TRANSPORTATION DOES NOT WARRANT SIMILAR SUBSURFACE CONDITIONS BELOW, BETWEEN, OR BEYOND THESE BORINGS. VARIATIONS IN SOIL CONDITIONS SHOULD BE EXPECTED AND FLUCTUATIONS IN GROUNDWATER LEVELS MAY OCCUR.

NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION			
STRUCTURE B-32-237			
DRAWN BY		DLF	PLANS CK'D. CJB
SUBSURFACE EXPLORATION			SHEET 3 OF 14


PLOT TIME: 11:53:37 AM

PLOT DATE: 9/18/2019

FILE NAME : S:\K0\1\Locad\35908\5-final-dsgn\51-drawings\20-Struct\bridge\B32237a1.dgn

8

8




NOTE

SEE ABUTMENT NOTES ON SHEET 6 ((1)(2)(3)(4)(5)).

⊙ INDICATES WING NUMBER.

FF = FRONT FACE
BF = BACK FACE
EF = EACH FACE




NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION			
STRUCTURE B-32-237			
DRAWN BY		DLF	PLANS CK'D. CJB
SOUTH ABUTMENT DETAILS			SHEET 4 OF 14


FF = FRONT FACE
BF = BACK FACE
EF = EACH FACE




NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION			
STRUCTURE B-32-237			
		DRAWN BY DLF	PLANS CK'D. CJB
SOUTH ABUTMENT DETAILS		SHEET 5 OF 14	



TYP WING 1 & WING 2 ELEVATION




TYP SECTION THRU WING 1 & WING 2



ABUTMENT NOTES:

- 1) SEAL ALL EXPOSED HORIZ. AND VERTICAL SURFACES OF 1/2" FILLER WITH NON-STAINING GRAY NON-BITUMOUS JOINT SEALER. (1" DEEP AND HOLD 1/8" BELOW SURFACE OF CONCRETE). EXTEND SEALER 3" BELOW GUTTER LINE AT INSIDE FACE. FILLER INCLUDED IN WING LENGTH.
 - 2) 18" RUBBERIZED MEMBRANE WATERPROOFING. SEAL ALL HORIZ & VERT JOINTS ON BACKFACE. VERTICAL WATERPROOFING TO EXTEND FROM BRIDGE SEAT TO TOP OF WING.
 - 3) KEYED CONSTRUCTION JOINT FORMED BY A BEVELED 2" X 6".
 - 4) OPTIONAL KEYED CONSTRUCTION JOINT FORMED BY A BEVELED 2" X 6" WITH MEMBRANE ON BACKFACE.
 - 5) A506 BARS MAY BE PLACED AFTER CONC HAS BEEN POURED BUT BEFORE INITIAL SET HAS TAKEN PLACE.
- PIPE UNDERDRAIN WRAPPED (6-INCH) SLOPE 0.5% MIN TO SUITABLE DRAINAGE. ATTACH RODENT SHIELD AT END OF PIPE.
- ATTACH RODENT SHIELD AT END OF PIPE UNDERDRAIN. FOR RODENT SHIELD DETAIL SEE MISCELLANEOUS DETAILS SHEET 14.



SOUTH ABUTMENT TO BE SUPPORTED ON 14" DIA CIP PILES (0.25 SHELL THICKNESS) WITH A REQUIRED DRIVING RESISTANCE OF 120 TONS PER PILE AS DETERMINED BY THE MODIFIED GATES DYNAMIC EQUATION. ESTIMATED 60-FEET LONG.

TYPICAL SECTION THRU BODY
ALL HORIZ BARS TO BE A604 UNLESS OTHERWISE SHOWN OR NOTED

FF = FRONT FACE
BF = BACK FACE
EF = EACH FACE

* DIMENSION IS TAKEN NORMAL TO C/L SUBSTRUCTURE UNITS

STATE PROJECT NUMBER

7345-00-70

NOTE: THE FIRST DIGIT OF THE BAR MARK SIGNIFIES THE ENGLISH BAR DIAMETER SIZE.

DIMENSIONS IN BENDING DETAILS ARE OUT TO OUT.

BILL OF BARS SOUTH ABUTMENT

BAR MARK	COAT	NO. REQ'D.	LENGTH (FT-IN)	BAR SERIES	BENT	LOCATION
A401		12	28 - 0		X	BODY AT PILES
A402		24	2 - 3			BODY AT PILES
A503		60	18 - 1		X	BODY STIRRUPS
A604		12	48 - 8			BODY HORIZ
A805		14	27 - 3		X	BODY HORIZ BF
A506	X	47	2 - 0			BODY DOWELS
A507	X	26	19 - 3		X	WING STIRRUPS
A608	X	9	15 - 6		X	WING 1 HORIZ BF & TOP
A509	X	8	14 - 1			WING 1 HORIZ FF
A610	X	9	13 - 10		X	WING 2 HORIZ BF & TOP
A511	X	8	15 - 3			WING 2 HORIZ FF
A512	X	34	10 - 8		X	WING VERT
A413	X	12	11 - 7			WING HORIZ EF
A614	X	4	11 - 7			WING HORIZ EF TOP
A515		17	5 - 8		X	BODY TOP ADD'L REINF
A416		4	18 - 0			BODY TOP ADD'L REINF
A417		8	6 - 5			BODY VERT ABUT ENDS

SOUTH ABUTMENT
DETAILS

SHEET 6 OF 14



FF = FRONT FACE
BF = BACK FACE
EF = EACH FACE



NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION			
STRUCTURE B-32-237			
DRAWN BY		DLF	PLANS CK'D. CJB
NORTH ABUTMENT DETAILS		SHEET 7 OF 14	

PLOT TIME: 11:53:37 AM

PLOT DATE: 9/8/2019

FILE NAME : S:\K01\Local\35908\5-final-dsgn\51-drawings\20-Struct\bridge\B32237a2.dgn

STATE PROJECT NUMBER

7345-00-70


NOTE

SEE ABUTMENT NOTES ON SHEET 9 (④ ①).

③ INDICATES WING NUMBER.

FF = FRONT FACE
BF = BACK FACE
EF = EACH FACE


8




FOOTING LAYOUT

NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION			
STRUCTURE B-32-237			
DRAWN BY		DLF	PLANS CK'D. CJB
NORTH ABUTMENT DETAILS			SHEET 8 OF 14

8




TYP SECTION THRU WING 4



WING 4 ELEVATION

STEEL TROWEL TOP SURFACE OF ABUTMENT, PLACE MULTIPLE LAYERS OF POLYETHYLENE SHEETS OVER ENTIRE ABUTMENT TOP BEFORE PLACING SUPERSTRUCTURE. TOTAL THICKNESS OF SHEETS SHALL BE AT LEAST 0.03"




NORTH ABUTMENT TO BE SUPPORTED ON 14" DIA CIP PILES (0.25 SHELL THICKNESS) WITH A REQUIRED DRIVING RESISTANCE OF 150 TONS PER PILE AS DETERMINED BY THE MODIFIED GATES DYNAMIC EQUATION. ESTIMATED 60-FEET LONG.

TYPICAL SECTION THRU BODY

ALL HORIZ BARS TO BE B604 UNLESS OTHERWISE SHOWN OR NOTED

* DIMENSION IS TAKEN NORMAL TO C/L SUBSTRUCTURE UNITS




ABUTMENT NOTES:


- ① SEAL ALL EXPOSED HORIZ. AND VERTICAL SURFACES OF 1/2" FILLER WITH NON-STAINING GRAY NON-BITUMINOUS JOINT SEALER. (1" DEEP AND HOLD 1/8" BELOW SURFACE OF CONCRETE). EXTEND SEALER 3" BELOW GUTTER LINE AT INSIDE FACE. FILLER INCLUDED IN WING LENGTH.
- ② 18" RUBBERIZED MEMBRANE WATERPROOFING. SEAL ALL HORIZ & VERT JOINTS ON BACKFACE. VERTICAL WATERPROOFING TO EXTEND FROM BRIDGE SEAT TO TOP OF WING.
- ③ OPTIONAL KEYED CONSTRUCTION JOINT FORMED BY A BEVELED 2" X 6" WITH MEMBRANE ON BACKFACE.
- ◆ PIPE UNDERDRAIN WRAPPED (6-INCH) SLOPE 0.5% MIN TO SUITABLE DRAINAGE. ATTACH RODENT SHIELD AT END OF PIPE.
- ① ATTACH RODENT SHIELD AT END OF PIPE UNDERDRAIN. FOR RODENT SHIELD DETAIL SEE MISCELLANEOUS DETAILS SHEET 14.

FF = FRONT FACE
BF = BACK FACE
EF = EACH FACE


NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION			
STRUCTURE B-32-237			
		DRAWN BY DLF	PLANS CK'D. CJB
NORTH ABUTMENT DETAILS		SHEET 9 OF 14	



WING 3 ELEVATION



TYP SECTION THRU WING 3



TYP SECTION THRU WING 3
OVERHANG

STATE PROJECT NUMBER			
7345-00-70			
NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION			
STRUCTURE B-32-237			
DRAWN BY		DLF	PLANS CK'D. CJB
NORTH ABUTMENT DETAILS			SHEET 10 OF 14



SUPERSTRUCTURE NOTES

/L



FINAL TOP OF DECK ELEVATIONS

Diagram illustrating the bottom of the slab and the centerline of the abutments for a parabolic arch bridge. The span is 50'-0". The diagram shows the profile of the arch and the vertical dimensions of the bottom of the slab at various points along the span.

Key dimensions and points:

- Span: 50'-0"
- Centerline of Abutment (C/L ABUT): 0.00 PT
- Bottom of Slab (B/S): 0.10 PT, 0.20 PT, 0.25 PT, 0.30 PT, 0.40 PT, 0.50 PT, 0.60 PT, 0.70 PT, 0.75 PT, 0.80 PT, 0.90 PT
- Vertical dimensions (from bottom of slab to centerline of abutment): 0", 3/4", 1 3/8", 1 5/8", 1 7/8", 2 3/16", 2 1/4", 2 3/16", 1 7/8", 1 5/8", 1 3/8", 3/4", 0"

CAMBER DIAGRAM

NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION			
STRUCTURE B-32-237			
		DRAWN BY DLF	PLANS CK'D. CJB
SUPERSTRUCTURE DETAILS		SHEET 11 OF 14	







STATE PROJECT NUMBER

7345-00-70

NOTE: THE FIRST ONE OR TWO DIGITS OF THE BAR MARK SIGNIFIES THE ENGLISH BAR DIAMETER SIZE.

DIMENSIONS IN BENDING DETAILS ARE OUT TO OUT.

BILL OF BARS						SUPERSTRUCTURE
BAR MARK	COAT	NO. REQ'D.	LENGTH (FT-IN)	BAR SERIES	BENT	LOCATION
S501	X	152	4 - 5		X	PARAPET VERT
S502	X	160	6 - 8		X	PARAPET VERT
S503	X	32	27 - 10			PARAPET HORIZ
S504	X	86	8 - 8		X	END OF DECK
S505	X	86	3 - 11		X	END OF DECK
S606	X	75	48 - 8			BOT TRANS
S507	X	52	48 - 8			TOP TRANS
S1108	X	90	52 - 8			BOT LONG
S509	X	43	51 - 1			TOP LONG
S510	X	8	5 - 10		X	PARAPET VERT
S411	X	43	3 - 6		X	AT NORTH ABUT KEY
S412	X	4	25 - 4			AT NORTH ABUT KEY







NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION			
STRUCTURE B-32-237			
DRAWN BY		DLF	PLANS CK'D. CJB
SUPERSTRUCTURE DETAILS			SHEET 12 OF 14

PLOT TIME: 11:16:39 AM

PLOT DATE: 9/18/2019

FILE NAME : S:\K0\1\1cchd\35908\5-final-dsgn\51-drawings\20-Struct\bridge\32237\5542.dgn

8




STATE PROJECT NUMBER									
7345-00-70									
BILL OF BARS FOR ABUTMENT PARAPETS									
BAR MARK	COAT	SOUTH ABUT.		NORTH ABUT.		LENGTH (FT-IN)	BENT	BAR SERIES	LOCATION
R501	X	5	5	23	5	5-10	X		PARAPET VERT.
R502	X	5	5	23	5	6-8	X		PARAPET VERT.
R503	X	12	12	12	12	3-0	X		PARAPET VERT.
R504	X	17	17	17	17	5-7	X		PARAPET VERT.
R505	X	5	5	5	5	6-5	X		PARAPET VERT.
R506	X	6	6	6	6	6-6	X		PARAPET VERT.
R507	X	1	1	-	1	11-7	X		PARAPET HORIZ.
R508	X	5	5	-	5	11-7			PARAPET HORIZ.
R509	X	6	6	6	6	5-5	X	▲	PARAPET VERT.
R510	X	2	2	-	2	11-7	X		PARAPET HORIZ.
R511	X	-	-	1	-	23-7	X		PARAPET HORIZ.
R512	X	-	-	5	-	23-7			PARAPET HORIZ.
R513	X	-	-	2	-	23-7	X		PARAPET HORIZ.

▲ LENGTH SHOWN FOR BAR IS AN AVERAGE LENGTH AND SHOULD ONLY BE USED FOR BAR WEIGHT CALCULATIONS. SEE BAR SERIES TABLE FOR ACTUAL LENGTHS.


BAR SERIES TABLE

BAR MARK	NO. REQ'D	LENGTH
R509	4 SERIES OF 6	4'-9" TO 6'-1"

BUNDLE AND TAG EACH SERIES SEPARATELY.



■ BENCH MARK CAP (WHEN SUPPLIED). AVOID PLACING A BENCH MARK CAP BELOW A RAIL OR FENCE SYSTEM THAT IS ATTACHED TO THE TOP OF THE PARAPET.




DETAIL OF ANCHOR ASSEMBLY

NOTE: HEX HEAD CAP SCREWS & WASHERS TO BE GALVANIZED IN ACCORDANCE WITH AASHTO M232 CLASS C.


ASSEMBLY SHALL BE BID ITEM "ANCHOR ASSEMBLIES FOR STEEL PLATE BEAM GUARD", EACH.

NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION			
STRUCTURE B-32-237			
DRAWN BY		DLF	PLANS CK'D. CJB
SINGLE SLOPE PARAPET 42SS			SHEET 13 OF 14



8



PILE DETAILS



END PLATE DETAIL



ABUTMENT BACKFILL DIAGRAM
FOR WINGS PARALLEL TO ROADWAY

$$L = \text{OUT TO OUT OF ABUTMENT, INCLUDING WINGS (FT)}$$


$$H = \text{AVERAGE ABUTMENT FILL HEIGHT (FT)}$$

$$EF = \text{EXPANSION FACTOR (1.20 FOR CY BID ITEMS AND 1.00 FOR TON BID ITEMS)}$$

$$V_{CF} = (L)(3.0')(H) + (L)(0.5)(1.5H)(H)$$


$$V_{CY} = V_{CF} (EF) / 27$$

$$V_{TON} = V_{CY} (2.0)$$



TYPICAL SECTION
THRU ABUTMENT

- ▲ BACKFILL PAY LIMITS. BACKFILL BEYOND BACKFILL PAY LIMITS SHALL BE INCIDENTAL TO EXCAVATION FOR STRUCTURES. LIMITS OF EXCAVATION SHALL BE DETERMINED BY THE CONTRACTOR.
- ◆ PIPE UNDERDRAIN WRAPPED (6 INCH). SLOPE 0.5% MIN. TO SUITABLE DRAINAGE. ATTACH RODENT SHIELD AT ENDS OF PIPE UNDERDRAIN.



RODENT SHIELD DETAIL

* DIMENSIONS ARE APPROXIMATE. THE GRATE IS SIZED TO FIT INTO A PIPE COUPLING. ORIENT SO SLOTS ARE VERTICAL.

THE RODENT SHIELD, PIPE COUPLING AND SCREWS SHALL BE CONSIDERED INCIDENTAL TO THE BID ITEM "PIPE UNDERDRAIN WRAPPED 6-INCH".

THE RODENT SHIELD SHALL BE A PVC GRATE SIMILAR TO THIS DETAIL. THE GRATE IS COMMERCIALY AVAILABLE AS A FLOOR STRAINER. A PIPE COUPLING IS REQUIRED FOR THE ATTACHMENT OF THIS SHIELD TO THE EXPOSED END OF THE PIPE UNDERDRAIN. THE SHIELD SHALL BE FASTENED TO THE PIPE COUPLING WITH TWO OR MORE NO. 10 X 1-INCH STAINLESS STEEL SHEET METAL SCREWS.

NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION			
STRUCTURE B-32-237			
DRAWN BY		DLF	PLANS CK'D. CJB
MISCELLANEOUS DETAILS			SHEET 14 OF 14


EARTHWORK SUMMARY


STATION	Real Station	Distance	AREA (SF)		Incremental Vol (CY) (Unadjusted)		Cumulative Vol (CY)		
			Cut	Fill	Cut	Fill	Cut	Expanded Fill	Mass Ordinate
						(1)	1.00	1.30	
								(2)	
77+10	7710.00	0.00	0.00	10.41	0	0	0	0	0
77+50	7750.00	40.00	59.24	89.60	44	74	44	96	-52
78+00	7800.00	50.00	255.47	283.87	291	346	335	546	-211
78+50	7850.00	50.00	232.60	241.05	452	486	787	1,178	-390
79+00	7900.00	50.00	277.00	111.64	472	327	1,259	1,602	-343
79+50	7950.00	50.00	155.07	40.85	400	141	1,659	1,786	-127
80+00	8000.00	50.00	171.44	187.74	302	212	1,961	2,061	-99
80+50	8050.00	50.00	208.79	178.57	352	339	2,314	2,502	-188
80+72.01	8072.01	22.01	181.83	144.17	159	132	2,473	2,673	-200
81+00	8100.00	27.99	56.65	85.67	124	119	2,596	2,828	-231
81+50	8150.00	50.00	0.00	7.24	52	86	2,649	2,940	-291


TOTALS


2,6492,261


(1) - NOT A BID ITEM - FOR INFORMATIONAL PURPOSES ONLY
(2) - FILL EXPANSION 30%
EXISTING ASPHALTIC PAVEMENT IS INCLUDED IN COMMON EXCAVATION TOTALS
EARTHWORK FOR STREAM REALIGNMENT IN INCLUDED IN TOTALS











Notes



Wisconsin Department of Transportation

Dedicated people creating transportation solutions
through innovation and exceptional service.

<http://www.dot.wisconsin.gov>