

WKE

PROJECT ID:

3180-00-74

COUNTY:


RACINE COUNTY

FEB 11, 2020

ORDER OF SHEETS

Section No. 1	Title
Section No. 2	Typical Sections and Details
Section No. 3	Estimate of Quantities
Section No. 3	Miscellaneous Quantities
Section No. 4	Right of Way Plat
Section No. 5	Plan and Profile
Section No. 6	Standard Detail Drawings
Section No. 7	Sign Plates
Section No. 8	Structure Plans
Section No. 9	Computer Earthwork Data
Section No. 9	Cross Sections

TOTAL SHEETS = 110



DESIGN DESIGNATION

A.A.D.T.	2014	=	7,700
A.A.D.T.	2040	=	10,000
D.H.V.		=	23.8
D.D.		=	59/41
T.		=	27.7
DESIGN SPEED		=	55 MPH
ESALS		=	4,400,000

CONVENTIONAL SYMBOLS

PLAN	
CORPORATE LIMITS	////
PROPERTY LINE	---
LOT LINE	---
LIMITED HIGHWAY EASEMENT	
EXISTING RIGHT OF WAY	---
PROPOSED OR NEW R/W LINE	---
SLOPE INTERCEPT	300EB
REFERENCE LINE	---
EXISTING CULVERT	---
PROPOSED CULVERT (Box or Pipe)	---
COMBUSTIBLE FLUIDS	CAUTION
MARSH AREA	---
WOODED OR SHRUB AREA	---

PROFILE	
GRADE LINE	---
ORIGINAL GROUND	---
MARSH OR ROCK PROFILE (To be noted as such)	---
SPECIAL DITCH	---
GRADE ELEVATION	95.36
CULVERT (Profile View)	---
UTILITIES	
ELECTRIC	E
FIBER OPTIC	FO
GAS	G
SANITARY SEWER	SAN
STORM SEWER	SS
TELEPHONE	T
WATER	W
UTILITY PEDESTAL	---
POWER POLE	---
TELEPHONE POLE	---

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

PLAN OF PROPOSED IMPROVEMENT

BURLINGTON BYPASS

RACINE CO LINE TO STH 83

STH 11

RACINE COUNTY

STATE PROJECT NUMBER
3180-00-74

STATE PROJECT	FEDERAL PROJECT	
	PROJECT	CONTRACT
3180-00-74	WISC 2020045	1


NET EXCEPTION TO CL LENGTH
STA 1026+04.02 - STA 1027+48.07
B-51-90, B-51-91

BEGIN PROJECT
STA 1000+00
Y=161868.668
X=499309.390

NET EXCEPTION TO CL LENGTH
STA 1077+34.98 - STA 1080+07.56
B-51-99, B-51-100

END PROJECT
STA 1125+00

T-2-N



LAYOUT
SCALE 0 2 MILES

TOTAL NET LENGTH OF CENTERLINE = 2.289 MILES

HORIZONTAL POSITIONS SHOWN ON THIS PLAN ARE WISCONSIN COUNTY COORDINATES, RACINE COUNTY, NAD83 (2011), IN U.S. SURVEY FEET. VALUES ARE GRID COORDINATES, GRID BEARINGS, AND GRID DISTANCES. GRID DISTANCES MAY BE USED AS GROUND DISTANCES.

ELEVATIONS SHOWN ON THIS PLAN ARE REFERENCED TO THE NORTH AMERICAN VERTICAL DATUM NAVD88 (2012).

STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION	
PREPARED BY	
Surveyor	WISDOT
Designer	STEVEN ROTIER
Project Manager	DOUG CAIN
Regional Examiner	WISDOT
Regional Supervisor	BEN ERUCHALU
APPROVED FOR THE DEPARTMENT	
DATE: 10/01/2019	Douglas A. Cain (Signature)

GENERAL NOTES

THE LOCATIONS OF EXISTING AND PROPOSED UTILITY INSTALLATIONS AS SHOWN ON THE PLANS ARE APPROXIMATE. THERE MAY BE OTHER UTILITY INSTALLATIONS WITHIN THE PROJECT AREA THAT ARE NOT SHOWN. COORDINATE CONSTRUCTION ACTIVITIES WITH A CALL TO DIGGERS HOTLINE, OR A DIRECT CALL TO THE UTILITIES THAT HAVE FACILITIES IN THE AREA. NOT ALL UTILITIES ARE MEMBERS OF DIGGERS HOTLINE.

VERIFY EXISTING PAVEMENT ELEVATIONS AT ALL TIE-INS TO EXISTING PAVEMENT PRIOR TO CONSTRUCTION. NOTIFY ENGINEER IF A DISCREPANCY IS FOUND BETWEEN PROPOSED PLAN ELEVATIONS AND EXISTING PAVEMENT ELEVATIONS.

COORDINATE HMA PAVING OPERATIONS CONSISTENT WITH PLAN TYPICAL SECTIONS, AND CONSTRUCT PAVEMENT TO AVOID LOCATING LONGITUDINAL CONSTRUCTION JOINTS WITHIN DRIVING, TURNING, BIKE, OR PARKING LANES.

SAWCUT EXISTING ASPHALT PAVEMENT AT THE MATCHLINE AS INDICATED ON THE PLAN OR AS DIRECTED BY THE ENGINEER.

WHEN DEFINING THE PAVEMENT STRUCTURE, THE BOTTOM OF THE BASE AGGREGATE DENSE IS CONSIDERED THE SUBGRADE LINE. THE SELECT CRUSHED MATERIAL LAYER IS A SUBGRADE IMPROVEMENT.

DO NOT REMOVE ANY TREES OR SHRUBS WITHOUT APPROVAL OF THE ENGINEER.

COORDINATE REVIEW OF ALL PROPOSED SIGN LOCATIONS WITH THE ENGINEER BEFORE INSTALLATION.

RESTORE EXISTING DRIVEWAYS AND FIELD ENTRANCES IN KIND AS DIRECTED BY THE ENGINEER IN THE FIELD.

THE EXACT LOCATION OF PRIVATE ENTRANCES IS TO BE DETERMINED IN THE FIELD BY THE ENGINEER.

STH 11 HMA PAVEMENT				
	THICKNESS	LAYER	ASPHALT MIX	DEPTH
MAINLINE	7 ¹ / ₄ INCH	UPPER UPPER	4MT 58-28 S	1 ³ / ₄ INCH
		LOWER UPPER	3MT 58-28 S	2 ³ / ₄ INCH
		LOWER	3MT 58-28 S	2 ³ / ₄ INCH
SHOULDERS	1 ³ / ₄ INCH		4MT 58-28S	1 ³ / ₄ INCH
BASE PATCH	6 ¹ / ₄ INCH	UPPER	4MT 58-28 S	1 ³ / ₄ INCH
		LOWER	ASPHALTIC BASE	4 ¹ / ₂ INCH

ORDER OF SECTION 2 SHEETS

Project Overview

Typical Sections

Construction Details

Plan Details

Traffic Signals

Pavement Marking

Traffic Control

Detour

Alignment

STANDARD ABBREVIATIONS

AP	ACCESS POINT	NOM	NOMINAL
AC	ACRE	NC	NORMAL CROWN
ADJ	ADJUST	N	NORTH
AECPRC	APRON ENDWALLS FOR CULVERT PIPE REINFORCED CONCRETE	Y	NORTH GRID COORDINATE
AH	AHEAD	NB	NORTHBOUND
AC	ASPHALT CEMENT	NO	NUMBER
ASPH	ASPHALTIC	OPT	OPTIONAL
ACP	ASPHALTIC CONCRETE PAVEMENT	OD	OUTSIDE DIAMETER
AVG	AVERAGE	PAVT	PAVEMENT
ADT	AVERAGE DAILY TRAFFIC	PLE	PERMANENT LIMITED EASEMENT
BK	BACK	PACS	PIPE ARCH CORRUGATED STEEL POINT
BAD	BASE AGGREGATE DENSE	P	POINT
BM	BENCHMARK	PC	POINT OF CURVATURE
CB	CATCH BASIN	PI	POINT OF INTERSECTION
C/L	CENTER LINE	PT	POINT OF TANGENCY
C/L CONST	CENTER LINE CONSTRUCTION	PVC	POINT OF VERTICAL CURVE
Δ	CENTRAL ANGLE OR DELTA	PVI	POINT OF VERTICAL INTERSECTION
CL	CLASS	PVT	POINT OF VERTICAL TANGENCY
CONC	CONCRETE	PVC	POLYVINYL CHLORIDE
CONST	CONSTRUCTION	PCC	PORTLAND CEMENT CONCRETE
CMCP	CORRUGATED METAL CULVERT PIPE	LB	POUND
CTH	COUNTY TRUNK HIGHWAY	PSF	POUNDS PER SQUARE FOOT
CABC	CRUSHED AGGREGATE BASE COURSE	PSI	POUNDS PER SQUARE INCH
CFS	CUBIC FEET PER SECOND	PE	PRIVATE ENTRANCE
CY	CUBIC YARD	PGL	PROFILE GRADE LINE
CP	CULVERT PIPE	PL	PROPERTY LINE
CPCS	CULVERT PIPE CORRUGATED STEEL	Q100	100-YEAR FLOW RATE
CPRC	CULVERT PIPE REINFORCED CONCRETE	R	RADIUS
CPRCHE	CULVERT PIPE REINFORCED CONCRETE HORIZONTAL ELLIPTICAL	RR	RAILROAD
C & G	CURB AND GUTTER	R	RANGE
D	DEGREE OF CURVE	R/L	REFRENCE LINE
DHV	DESIGN HOUR VOLUME	REINF	REINFORCING OR REINFORCEMENT
DIA	DIAMETER	REQD	REQUIRED
DD	DIRECTIONAL DISTRIBUTION	RT	RIGHT
DWY	DRIVEWAY	R/W	RIGHT-OF-WAY
E	EAST	RD	ROAD
X	EAST GRID COORDINATE	RDWY	ROADWAY
EB	EASTBOUND	SEC	SECTION
EL	ELEVATION	SHLDR	SHOULDER
ESALS	EQUIVALENT SINGLE AXLE LOADS	S	SOUTH
EXC	EXCAVATION	SB	SOUTHBOUND
EBS	EXCAVATION BELOW SUBGRADE	SQ	SQUARE
EXIST	EXISTING	SF	SQUARE FEET
FPS	FEET PER SECOND	SW	SIDEWALK
FERT	FERTILIZE	SY	SQUARE YARD
FE	FIELD ENTRANCE	SDD	STANDARD DETAIL DRAWINGS
FL	FLOW LINE	STH	STATE TRUNK HIGHWAYS
FT	FOOT	STA	STATION
GN	GRID NORTH	SS	STORM SEWER
HES	HIGH EARLY STRENGTH	SSPRC	STORM SEWER PIPE REINFORCED CONCRETE
HP	HIGH POINT	ST	STREET
HW	HIGH WATER	STR	STRUCTURE OR STRUCTURAL
HMA	HOT MIX ASPHALT	SE	SUPERELEVATION
CWT	HUNDREDWEIGHT	T	TANGENT
HWD	HYDRANT	TEMP	TEMPORARY
INL	INLET	TI	TEMPORARY INTEREST
ID	INSIDE DIAMETER	TLE	TEMPORARY LIMITED EASEMENT
I	INTERSECTION ANGLE	t	TON
INV	INVERT	T	TOWN
IP	IRON PIPE OR PIN	T/L	TRANSIT LINE
JT	JOINT	T	TRUCKS (PERCENT OF)
LT	LEFT	TYP	TYPICAL
LC	LENGTH OF CURVE	USH	UNITED STATES HIGHWAY
LF	LINEAR FOOT	VAR	VARIABLE
LP	LOW POINT	V	VELOCITY OF DESIGN SPEED
LS	LUMP SUM	VERT	VERTICAL
MH	MANHOLE	VC	VERTICAL CURVE
MAX	MAXIMUM	VOL	VOLUME
MGAL	MEGAGALLON	WM	WATERMAIN
MPH	MILES PER HOUR	WV	WATER VALVE
MIN	MINIMUM	W	WEST
MON	MONUMENT	WB	WESTBOUND
		YD	YARD

UTILITY CONTACTS

Matthew Dinnauer AT&T Wisconsin - Communication Line 2005 Pewaukee Rd Waukesha, WI 53188 (262) 896-7690 md9542@att.com	Richard Trgovec Midwest Fiber Networks LLC - Communication Line 6070 North Flint Rd Glendale, WI 53209 (414) 459-3554 rtrgovec@midwestfibernetworks.com
Pete Kruzela Charter Communications 1320 N Dr Martin Luther King Jr Dr Milwaukee, WI 53212-4002 (414) 908-1339 wis.engineering@charter.com	Mary Fisher PaeTec Communications, LLC - Communication Line 13935 Bishops Dr Brookfield, WI 53005 (262) 792-7938 Mary.B.Fisher@windstream.com
Peter Riggs, Director of Public Works City of Burlington DPW 2200 South Pine St Burlington, WI 53105 (262) 342-1182 priggs@burlington-wi.gov	Nicole Smullen We Energies - Electricity 333 West Everett St, Room A299 Milwaukee, WI 53203 (414) 221-5617 Nicole.Smullen@weenergygroup.com
	Nicole Smullen We Energies - Gas/Petroleum 333 West Everett St, Room A299 Milwaukee, WI 53203 (414) 221-5617 Nicole.Smullen@weenergygroup.com


WisDOT CONTACTS



Doug Cain, Project Manager Wisconsin Department of Transportation 141 NW Barstow Street Waukesha, WI 53187-0798 (262) 548-5603 douglas.cain@dot.wi.gov	Steven Rotier, Design Leader Wisconsin Department of Transportation 141 NW Barstow Street Waukesha, WI 53187-0798 (262) 548-5679 steven.rotier@dot.wi.gov
Eric Perea Wisconsin Department of Transportation - Street Lighting 141 NW Barstow Street Waukesha, WI 53187-0798 (262) 574-5422 eric.perea@dot.wi.gov	Parwinder Virk Wisconsin Department of Transportation - WisDOT Signal 141 NW Barstow St Waukesha, WI 53188 (414) 852-0829 parwinder.virk@dot.wi.gov

OTHER CONTACTS


Kristina Betzold - DNR Liason
Wisconsin Department of Natural Resources
2300 N. Dr. Martin Luther King Jr. Drive
Milwaukee, WI 53212
(414) 507-4946
kristina.betzold@wisconsin.gov








NOTES: * SEE SDD SHOULDER RUMBLE STRIP, MILLING




OUTSIDE SHOULDER (TYP.)




SHOULDER WITH CURB AND GUTTER

STA 1051+45 - 1053+52 LT
STA 1051+54 - 1054+57 RT
STA 1080+23 - 1085+50 LT




RIGHT TURN LANE

STA 1040+05 - 1044+75 RT
STA 1058+71 - 1063+71 LT
STA 1087+83 - 1092+75 RT
STA 1092+58 - 1096+30 LT (0-10' WIDE)
STA 1119+92 - 1123+05 RT




INSIDE SHOULDER (TYP.)



ACCELERATION LANE - CTH P


STA 1043+00 - 1056+42 LT
STA 1047+31 - 1060+24 RT





LEFT TURN LANE

STA 1089+00 - 1092+80 EB
STA 1093+80 - 1101+20 WB
STA 1117+35 - 1124+25 EB

NOTE:
PAVE THE TRAVEL LANES, LANE #1 AND LANE #2,
WITH TANDEM PAVERS (ECHELON) TO ELIMINATE A
COLD CONSTRUCTION JOINT BETWEEN THE TRAVEL LANES.




TYPICAL PAVEMENT CROSS SECTIONS OF
LONGITUDINAL JOINTS



REMOVING CONCRETE SURFACE PARTIAL DEPTH

NOTE:

- * UPPER LAYER 4MT 58-28 S IS INCIDENTAL TO THE BASE PATCHING ASPHALTIC ITEM
- ** BASE AGGREGATE DENSE 1 $\frac{1}{4}$ " PAID BY SEPARATE BID ITEM.

**BASE PATCHING ASPHALTIC**



PROJECT NO: 3180-00-74

HWY: STH 11

COUNTY: RACINE

PLAN DETAILS

SHEET

9

E

FILE NAME : N:\PDS\C3D\31800004\SHEETSPLAN\021201_PD.DWG
LAYOUT NAME - 021200

PLOT DATE : 4/30/2019 6:41 AM

PLOT BY : ROTIER, STEVEN J

PLOT NAME :

PLOT SCALE : 1 IN:40 FT

WISDOT/CADDs SHEET 42


LEGEND

- A

HMA PAVEMENT 7 1/4"
- B

HMA PAVEMENT 1 3/4" (SEE CONSTRUCTION DETAILS)
- BASE PATCHING ASPHALTIC
- XXXX

SAWCUT
- INLET PROTECTION (TYPE)
- REMOVING CONCRETE SURFACE PARTIAL DEPTH



PROJECT NO: 3180-00-74	HWY: STH 11	COUNTY: RACINE	PLAN DETAILS	SHEET 10	E
------------------------	-------------	----------------	--------------	----------	---

LEGEND

A

HMA PAVEMENT 7 $\frac{1}{4}$ "

B

HMA PAVEMENT 1 $\frac{3}{4}$ " (SEE CONSTRUCTION DETAILS)

BASE PATCHING ASPHALTIC



SAWCUT




INLET PROTECTION (TYPE)




REMOVING CONCRETE SURFACE PARTIAL DEPTH



STA 1003+00
BASE PATCHING ASPHALTIC
12'X30'



STA 1007+70
BASE PATCHING ASPHALTIC
12'X25'



STH 11 WB

1003+00

1004+00

1005+00

1006+00

1007+00

1008+00

STH 11 EB

LEGEND



HMA PAVEMENT 7 1/4"



HMA PAVEMENT 1 3/4" (SEE CONSTRUCTION DETAILS)



BASE PATCHING ASPHALTIC



SAWCUT



INLET PROTECTION (TYPE)



REMOVING CONCRETE SURFACE PARTIAL DEPTH

N

STH 11 WB

1009+00

1010+00

1011+00

1012+00

1013+00

1014+00

STH 11 EB

LEGEND



HMA PAVEMENT 7 1/4"



HMA PAVEMENT 1 3/4" (SEE CONSTRUCTION DETAILS)



BASE PATCHING ASPHALTIC



SAWCUT



INLET PROTECTION (TYPE)



REMOVING CONCRETE SURFACE PARTIAL DEPTH



STH 11 WB

STH 11 EB

1015+00

1016+00

1017+00

1018+00

1019+00

1020+00

1021+00

PROJECT NO: 3180-00-74

HWY: STH 11

COUNTY: RACINE

PLAN DETAILS


SHEET

13

E


LEGEND

- (A) HMA PAVEMENT 7 $\frac{1}{4}$ "
- (B) HMA PAVEMENT 1 $\frac{3}{4}$ " (SEE CONSTRUCTION DETAILS)
- XXXX BASE PATCHING ASPHALTIC
- XXXX SAWCUT
- INLET PROTECTION (TYPE)
- REMOVING CONCRETE SURFACE PARTIAL DEPTH



LEGEND

- (A) HMA PAVEMENT 7 ½"
- (B) HMA PAVEMENT 1 ¾" (SEE CONSTRUCTION DETAILS)
- XXXX SAWCUT
- INLET PROTECTION (TYPE)
- REMOVING CONCRETE SURFACE PARTIAL DEPTH



LEGEND

- A

 HMA PAVEMENT 7 1/4"
- B


 HMA PAVEMENT 1 3/4" (SEE CONSTRUCTION DETAILS)
- XXXX

 BASE PATCHING ASPHALTIC
- XXXX

 SAWCUT
- X

 INLET PROTECTION (TYPE)
- XXXX

 REMOVING CONCRETE SURFACE PARTIAL DEPTH



LEGEND

- A

 HMA PAVEMENT 7 1/4"
- B


 HMA PAVEMENT 1 3/4" (SEE CONSTRUCTION DETAILS)
- XXXX

 BASE PATCHING ASPHALTIC
- XXXX

 SAWCUT
- X


 INLET PROTECTION (TYPE)
- XXXX

 REMOVING CONCRETE SURFACE PARTIAL DEPTH




LEGEND


- (A) HMA PAVEMENT 7 1/4"
- (B) HMA PAVEMENT 1 3/4" (SEE CONSTRUCTION DETAILS)
- [Cross-hatch] BASE PATCHING ASPHALTIC
- [XXXX] SAWCUT
- [X] INLET PROTECTION (TYPE)
- [Diagonal lines] REMOVING CONCRETE SURFACE PARTIAL DEPTH



LEGEND

- (A) HMA PAVEMENT 7 1/4"
- (B) HMA PAVEMENT 1 3/4" (SEE CONSTRUCTION DETAILS)
- XXXXX BASE PATCHING ASPHALTIC
- XXXXX SAWCUT
- X INLET PROTECTION (TYPE)
- REMOVING CONCRETE SURFACE PARTIAL DEPTH





LEGEND

- A

HMA PAVEMENT 7 1/4"
- B

HMA PAVEMENT 1 3/4" (SEE CONSTRUCTION DETAILS)
- BASE PATCHING ASPHALTIC
- XXXX

SAWCUT
- INLET PROTECTION (TYPE)
- REMOVING CONCRETE SURFACE PARTIAL DEPTH



LEGEND



HMA PAVEMENT 7 1/4"



HMA PAVEMENT 1 3/4" (SEE CONSTRUCTION DETAILS)




BASE PATCHING ASPHALTIC




SAWCUT



INLET PROTECTION (TYPE)




REMOVING CONCRETE SURFACE PARTIAL DEPTH




LEGEND

- (A) HMA PAVEMENT 7 $\frac{1}{4}$ "
- (B) HMA PAVEMENT 1 $\frac{3}{4}$ " (SEE CONSTRUCTION DETAILS)
- XXXX SAWCUT
- INLET PROTECTION (TYPE)
- REMOVING CONCRETE SURFACE PARTIAL DEPTH




LEGEND

- (A) HMA PAVEMENT 7 $\frac{1}{4}$ "
- (B) HMA PAVEMENT 1 $\frac{3}{4}$ " (SEE CONSTRUCTION DETAILS)
- BASE PATCHING ASPHALTIC
- XXXX SAWCUT
- INLET PROTECTION (TYPE)
- REMOVING CONCRETE SURFACE PARTIAL DEPTH



LEGEND

	HMA PAVEMENT 7 1/4"
	HMA PAVEMENT 1 3/4" (SEE CONSTRUCTION DETAILS)
	BASE PATCHING ASPHALTIC
	SAWCUT
	INLET PROTECTION (TYPE)
	REMOVING CONCRETE SURFACE PARTIAL DEPTH



LEGEND

- A


 HMA PAVEMENT 7 1/4"
- B

 HMA PAVEMENT 1 3/4" (SEE CONSTRUCTION DETAILS)
- XXXX

 BASE PATCHING ASPHALTIC
- XXXX

 SAWCUT
- X

 INLET PROTECTION (TYPE)
- REMOVING CONCRETE SURFACE PARTIAL DEPTH




LEGEND

- A

HMA PAVEMENT 7 1/4"
- B

HMA PAVEMENT 1 3/4" (SEE CONSTRUCTION DETAILS)
- BASE PATCHING ASPHALTIC
- XXXX

SAWCUT
- INLET PROTECTION (TYPE)
- REMOVING CONCRETE SURFACE PARTIAL DEPTH



LEGEND



HMA PAVEMENT 7 1/4"



HMA PAVEMENT 1 3/4" (SEE CONSTRUCTION DETAILS)




BASE PATCHING ASPHALTIC




SAWCUT



INLET PROTECTION (TYPE)



REMOVING CONCRETE SURFACE PARTIAL DEPTH



LEGEND



HMA PAVEMENT 7 1/4"



HMA PAVEMENT 1 3/4" (SEE CONSTRUCTION DETAILS)



BASE PATCHING ASPHALTIC




SAWCUT



INLET PROTECTION (TYPE)




REMOVING CONCRETE SURFACE PARTIAL DEPTH



LEGEND

- (A) HMA PAVEMENT 7 1/4"
- (B) HMA PAVEMENT 1 3/4" (SEE CONSTRUCTION DETAILS)
- [Cross-hatch] BASE PATCHING ASPHALTIC
- [XXXX] SAWCUT
- [X] INLET PROTECTION (TYPE)
- [Diagonal lines] REMOVING CONCRETE SURFACE PARTIAL DEPTH




LEGEND

- ☒ CONTROL CABINET
- NONMETALLIC CONDUIT 2", UNLESS OTHERWISE NOTED
- LOOP DETECTOR CONDUIT 1" NONMETALLIC
- ◀● SIGNAL HEAD, TRAFFIC SIGNAL STANDARD, PEDESTAL BASE
- (XX) ○ MONOTUBE BASE, POLE, 15'-30' ARM
- (XX) ○ MONOTUBE BASE, POLE, 35'-55' ARM
- ⊥● PEDESTRIAN HEAD WITH PUSH BUTTON
- ⊥● PUSH BUTTON
- LUMINAIRE, TRAFFIC POLE, TRANSFORMER BASE
- * □ * LOOP DETECTOR IN 1" NONMETALLIC CONDUIT
- PULL BOX, 24" X 36"

CONSTRUCTION NOTES:

- EXISTING CONDUIT RUNS TO BE ABANDONED IN PLACE. CONTRACTOR TO REMOVE ANY CONDUCTORS REMAINING IN THE CONDUIT.
- ABANDONED LOOP DETECTOR CONDUIT TO REMAIN IN PLACE. LOOP DETECTOR WIRE AND LEAD-IN CABLE TO BE REMOVED BY THE CONTRACTOR.
- CABINET AND CONTROLLER SHALL BE REMOVED BY WISDOT ELECTRICAL PERSONNEL.
- THE LOCATIONS OF EXISTING UTILITY INSTALLATIONS ARE APPROXIMATE. THERE MAY BE OTHER UTILITY INSTALLATIONS WITHIN THE PROJECT WHICH ARE NOT SHOWN.
- GRAYSHADE REPRESENTS EXISTING. BOLD REPRESENTS ITEMS TO BE REMOVED.



MONOTUBE STRUCTURE NUMBERS	
SB4	= S-51-1105
SB10	= S-51-1106
SB13	= S-51-1107
SB2	= S-51-1108

NOTE: ALL LENSES ARE 12-INCH
GRAYSHADE REPRESENTS EXISTING

TRAFFIC CONTROL SIGNAL
STH 11/36/83 & STH 83/PINE ST
CITY OF BURLINGTON
RACINE COUNTY

SIGNAL NO. S51-0993

REGION CONTACT: P. VIRK
DESIGNED BY:
REVISED BY: S. WAGNER

PAGE 1 OF 3

PROJECT NO: 3180-00-74

HWY: STH 11



COUNTY: RACINE

TRAFFIC SIGNAL REMOVAL PLAN



SHEET

31


E



TRAFFIC CONTROL SIGNAL STH 11/36/83 & STH 83/PINE ST CITY OF BURLINGTON RACINE COUNTY	
SIGNAL NO. S51-0993	
REGION CONTACT: P. VIRK DESIGNED BY: REVISED BY: S. WAGNER	PAGE 2 OF 3



TRAFFIC CONTROL SIGNAL	
STH 11/36/83 & STH 83/PINE ST	
CITY OF BURLINGTON	
RACINE COUNTY	
SIGNAL NO. S51-0993	
REGION CONTACT: P. VIRK	PAGE 3 OF 3
DESIGNED BY:	
REVISED BY: S. WAGNER	





- CONSTRUCTION NOTES:
1. * LOCATION IS TO FRONT CENTER OF DETECTOR LOOP.
 2. THE CONTRACTOR SHALL HAVE THE PULL BOXES AND CONDUIT RUNS INSPECTED 5 WORKING DAYS PRIOR TO PLACING SIGNAL CABLE INTO SYSTEM. CONTACT THE WISDOT ELECTRICAL FIELD UNIT TO MAKE ARRANGEMENTS. (414) 266-1170.
 3. THE LOCATIONS OF EXISTING AND PROPOSED UTILITY INSTALLATIONS ARE APPROXIMATE. THERE MAY BE OTHER UTILITY INSTALLATIONS WITHIN THE PROJECT WHICH ARE NOT SHOWN.
 4. ALL LUMINAIRES ARE LED-C UNLESS OTHERWISE NOTED.
 5. CABINET WIRING WILL BE DONE BY WISDOT ELECTRICAL FIELD UNIT.

MONOTUBE STRUCTURE NUMBERS	
SB4 =	S-51-1105
SB10 =	S-51-1106
SB13 =	S-51-1107
SB2 =	S-51-1108

INSTALL RADAR ADVANCE DETECTION FOR EB & WB 4/24/17
REMOVED FYA ON ALL APPROACHES WITH PROTECTED LT ONLY; ADD NEAR LEFT HEADS ON 7-28-16 10-12-16
REPLACE CABINET & CONTROLLER; INSTALL FYA ALL APPROACHES; ACTIVATE PHASES 1, 3, 5 & 7; ADD CELL MODEM 3/2/15
INITIAL INSTALL 5/13/08



REVISION			
REV. NO.	REPLACE LOOPS 61 & 62; MOVE PB7 & PB8		
4	APPROVAL RECOMMENDED		APPROVED
	REGION		CENTRAL OFFICE
	DATE	BY	DATE
	6/27/19	PSV	6/27/19
TRAFFIC CONTROL SIGNAL STH 11/36/83 & STH 83/PINE ST CITY OF BURLINGTON RACINE COUNTY			
SIGNAL NO. S51-0993			
CABINET TYPE: TS2-E CONTROLLER TYPE: ECONOLITE			
WISCONSIN DEPARTMENT OF TRANSPORTATION			
APPROVAL RECOMMENDED		MITZI M DOBERSEK REGION TRAFFIC ENGINEER	
DATE 2/07/07		JOANNA L BUSH STATE TRAFFIC ENGINEER	
APPROVED		DATE 5/13/08	
REGION CONTACT: P. VIRK		DESIGNED BY: S. WAGNER	
REVISOR: S. WAGNER		PAGE 1 OF 4	



TRAFFIC CONTROL SIGNAL	
STH 11/36/83 & STH 83/PINE ST	
CITY OF BURLINGTON	
RACINE COUNTY	
SIGNAL NO. S51-0993	
REGION CONTACT: P. VIRK	PAGE 2 OF 4
DESIGNED BY:	
REVISED BY: S. WAGNER	

2

2



TRAFFIC CONTROL SIGNAL	
STH 11/36/83 & STH 83/PINE ST	
CITY OF BURLINGTON	
RACINE COUNTY	
SIGNAL NO. S51-0993	
REGION CONTACT: P. VIRK DESIGNED BY: REVISED BY: S. WAGNER	PAGE 3 OF 4

PROJECT NO:	3180-00-74
-------------	------------

HWY: STH 11

COUNTY: RACINE

TRAFFIC SIGNAL PLAN

SHEET	36	E
-------	----	---

FILE NAME : N:\PDS\C3D\CAD\31800004\SIG\S51-0993_16.DWG
LAYOUT NAME - S51-0993_PG3

PLOT DATE : 6/28/2019 9:06 AM PLOT BY : WAGNER, SCOTT H

PLOT BY : WAGNER, SCOTT H PLOT NAME :

PLOT NAME :

PLOT SCALE :


#####

PLOT SCALE : #####


#DOT/CADDIS SHEET 42

	HEAD NUMBERS	F L A S H
Ø1	4,5, 29	R
Ø2	6,7,8	R
Ø3	25,26, 30	R
Ø4	14,15,16	R
Ø5	9,10, 31	R
Ø6	1,2,3	R
Ø7	27,28, 32	R
Ø8	11,12,13	R
Ø2P	19,20	
Ø4P	23,24	
Ø6P	17,18	
Ø8P	21,22	
OLE		
OLF		
OLG		
OLH		



RING 1



RING 2



BARRIER



N

CONTROLLER LOGIC

PHASE NUMBER	PHASE LOCKING	DUAL ENTRY W / Ø	PHASE RECALL	PHASE ACTIVE
1		6		X
2	X	6	MIN	X
3		8		X
4		8		X
5		2		X
6	X	2	MIN	X
7		4		X
8		4		X

TYPE OF INTERCONNECT/COMMUNICATION	
NONE	
CLOSED LOOP	
TWISTED PAIR	
FIBER OPTIC*	
FIBER OPTIC (ETHERNET)	
RADIO	
CELL MODEM	X

TYPE OF COORDINATION	
NONE	X
TBC	
TRAFFIC RESPONSIVE	
ADAPTIVE	
*LOCATION OF MASTER CONTROLLER NO:	S-
SIGNAL SYSTEM NO:	SS-

TYPE OF LIGHTING	
BY OTHER AGENCY	
IN TRAFFIC CABINET	X
IN SEPARATE DOT LIGHTING CABINET	

TYPE OF PRE-EMPT	
NONE	X
RAILROAD	
EMERGENCY VEHICLE	
GTT	
TOMAR	
HARDWIRE	
OTHER	
LIFT BRIDGE	
QUEUE DETECTION	

DETECTOR LOGIC

DETECTOR INPUT	3	1	7	5	11	9	15	13
PLAN LOOP DETECTOR*(S)	21	11	41	31	45	43	62	52
CALLED PHASE	2	1	4	3	4	4	6	5
CALL OPTION	X	X		X	X	X	X	X
DELAY TIME								
EXTENTION OPTION	X	X	X	X	X	X	X	X
EXTEND TIME			X					
USE ADDED INITIAL	X						X	
CROSS SWITCH PHASE								



DETECTOR INPUT	4	2	8	6	12	10	16	14
PLAN LOOP DETECTOR*(S)	22	12	42	32	51	44	71	61
CALLED PHASE	2	1	4	3	5	4	7	6
CALL OPTION	X	X	X	X	X	X	X	X
DELAY TIME								
EXTENTION OPTION	X	X	X	X	X	X	X	X
EXTEND TIME								
USE ADDED INITIAL	X							X
CROSS SWITCH PHASE								

DETECTOR INPUT	19	17	23	21			33	35
PLAN LOOP DETECTOR*(S)	82	72		84			23	63
CALLED PHASE	8	7		8			2	6
CALL OPTION	X	X		X				
DELAY TIME								
EXTENTION OPTION	X	X		X			X	X
EXTEND TIME							X	X
USE ADDED INITIAL								
CROSS SWITCH PHASE								


DETECTOR INPUT	20	18	24	22			34	36
PLAN LOOP DETECTOR*	83	81		85			24	64
CALLED PHASE	8	8		8			2	6
CALL OPTION	X			X				
DELAY TIME								
EXTENTION OPTION	X	X		X			X	X
EXTEND TIME		X						
USE ADDED INITIAL								
CROSS SWITCH PHASE								



STH 11/36/83 & STH 83/PINE ST	
CITY OF BURLINGTON	
RACINE COUNTY	
SIGNAL NO: S51-0993	CABINET TYPE: TS2
CONTROLLER TYPE: ECONOLITE	
DATE: 05/2019	PAGE NO. 4 OF 4


LEGEND			
1	MARKING LINE EPOXY 4-INCH WHITE	10	MARKING WORD EPOXY WHITE
2	MARKING LINE EPOXY 4-INCH YELLOW	11	MARKING LINE GROOVED WET REFLECTIVE CONTRAST EPOXY 8-INCH WHITE (3' LINE 9' GAP)
3	MARKING LINE GROOVED WET REFLECTIVE CONTRAST EPOXY 4-INCH WHITE (12.5' LINE W 37.5' GAP)	12	MARKING DIAGONAL EPOXY 12-INCH WHITE
4	MARKING LINE EPOXY 4-INCH DOUBLE YELLOW	13	MARKING LINE GROOVED WET REFLECTIVE CONTRAST EPOXY 4-INCH YELLOW (2' LINE 6' GAP)
5	MARKING LINE GROOVED WET REFLECTIVE CONTRAST EPOXY 8-INCH WHITE	14	MARKING LINE 4-INCH EPOXY WHITE (3' LINE 12' GAP)
6	MARKING STOP LINE EPOXY 18-INCH WHITE	15	MARKING LINE 4-INCH EPOXY YELLOW (3' LINE 12' GAP)
7	MARKING ISLAND NOSE EPOXY - YELLOW	16	MARKING LINE 8-INCH EPOXY WHITE (3' LINE 12' GAP)
8	MARKING ARROW EPOXY TYPE 2 - WHITE	17	MARKING LINE 8-INCH EPOXY WHITE
9	MARKING ARROW EPOXY TYPE 5 - WHITE	18	MARKING CORRUGATED MEDIAN PAINT YELLOW




NOTE:
* REMOVE EXISTING GROOVED PAVEMENT MARKING, PAID AS
MARKING REMOVAL LINE WATER BLASTING 4-INCH









2

2

STH 11/STH 36 DETOUR
WORK ZONE
SIGN ON PERMANENT SUPPORT
PCMS

PCMS MESSAGING	
FRAME 1	FRAME 2
HWY 11 TO CLOSE	XXXDAY XX XX XX

SEE SDD DETOUR SIGNING FOR
MAINLINE CLOSURES

SEE SDD BARRICADES AND
SIGNS FOR SIDEROAD CLOSURES

SEE SDD BARRICADES AND SIGNS
FOR VARIOUS MAINLINE CLOSURES

SEE SDD BARRICADES AND SIGNS FOR
SIDEROAD CLOSURES, DETAIL 2


SEE SDD TRAFFIC
CONTROL, LANE CLOSURE

SEE SDD DETOUR SIGNING FOR
MAINLINE CLOSURES


SEE SDD BARRICADES AND
SIGNS FOR VARIOUS
MAINLINE CLOSURES

SEE SDD BARRICADES AND SIGNS FOR
SIDEROAD CLOSURES

NOTES
SEE TRAFFIC CONTROL SHEETS FOR MORE DETAILS
SEE SDD DETOUR SIGNING FOR MAINLINE CLOSURES




NOTES:
SEE DETOUR SHEETS FOR MORE DETAILS



LEGEND

-  WORK AREA
-  DIRECTION OF TRAFFIC
-  SIGN ON PERMANENT SUPPORT
-  SIGN ON TEMPORARY SUPPORT
-  TRAFFIC CONTROL DRUM
-  TRAFFIC CONTROL DRUM WITH TYPE C STEADY BURN LIGHT
-  FLASHING ARROW BOARD
-  TYPE III BARRICADE
-  TYPE III BARRICADE WITH ATTACHED SIGN
-  TEMPORARY MARKING LINE REMOVABLE TAPE 4-INCH
-  MARKING REMOVAL LINE

N



NOTES:
SEE DETOUR SHEETS FOR MORE DETAILS.

* PLACE "RAMP CLOSED BEGINNING" SIGN 7
CALENDAR DAYS PRIOR TO CLOSURE OR AS
DIRECTED BY ENGINEER.

PROJECT NO: 3180-00-74

HWY: STH 11

COUNTY: RACINE

TRAFFIC CONTROL - CTH P/STH 11 WB RAMPs

SHEET

48

E

FILE NAME : N:\PDS\C3D\31800004\SHEETPLAN\025001_TC.DWG
LAYOUT NAME - at CTH P north


PLOT DATE : 4/30/2019 7:15 AM

PLOT BY : ROTIER, STEVEN J


PLOT NAME :

PLOT SCALE : 1 IN:100 FT

WISDOT/CADDs SHEET 42




NOTES:
SEE DETOUR SHEETS FOR MORE DETAILS.
* PLACE "RAMP CLOSED BEGINNING" SIGN 7
CALENDAR DAYS PRIOR TO CLOSURE OR AS
DIRECTED BY ENGINEER.




LEGEND


- | | | | |
|---|--|---|--|
|  | WORK AREA |  | TYPE III BARRICADE |
|  | DIRECTION OF TRAFFIC |  | TYPE III BARRICADE WITH ATTACHED SIGN |
|  | SIGN ON PERMANENT SUPPORT |  | TEMPORARY MARKING LINE REMOVABLE TAPE 4-INCH |
|  | SIGN ON TEMPORARY SUPPORT |  | MARKING REMOVAL LINE |
|  | TRAFFIC CONTROL DRUM | | |
|  | TRAFFIC CONTROL DRUM WITH TYPE C STEADY BURN LIGHT | | |
|  | FLASHING ARROW BOARD | | |



NOTES:
SEE DETOUR SHEETS FOR MORE DETAILS





EB STH 11/NB STH 36 DETOUR ----->--
WB STH 11/SB STH 36 DETOUR ---<---
WORK ZONE [Hatched Box]
SIGN ON PERMANENT SUPPORT [Sign Symbol]




A		B	
M4-8 24"x12" DETOUT DETOUR	M4-8 24"x12" DETOUT DETOUR	M4-8 24"x12" DETOUT DETOUR	M4-8 24"x12" DETOUT DETOUR
M3-1 24"x12" NORTH EAST	M3-2 24"x12" NORTH EAST	M3-3 24"x12" SOUTH WEST	M3-4 24"x12" SOUTH WEST
M1-6 24"x24" 36 11	M1-6 24"x24" 36 11	M1-6 24"x24" 36 11	M1-6 24"x24" 36 11
MO6-1 21"x21" ↑ ↑	MO6-1 21"x21" ↑ ↑	MO6-1 21"x21" ↑ ↑	MO6-1 21"x21" ↑ ↑








NOTES
SEE TRAFFIC CONTROL SHEETS FOR MORE DETAILS





NOTES
SEE TRAFFIC CONTROL SHEETS FOR MORE DETAILS
SEE SDD DETOUR SIGNING FOR MAINLINE CLOSURES

PROJECT NO: 3180-00-74

HWY: STH 11

COUNTY: RACINE

DETOUR: STH 11/STH 83

SHEET

58

E

FILE NAME : N:\PDS\C3D\31800004\SHEETSP\N\027001_DT.DWG
LAYOUT NAME - STH11DETOURsat83


PLOT DATE : 9/30/2019 10:23 AM

PLOT BY : ROTIER, STEVEN J

PLOT NAME :

PLOT SCALE : 1 IN:200 FT

WISDOT/CADDs SHEET 42



NOTES
SEE SDD TRAFFIC CONTROL, ADVANCED WIDTH
RESTRICTION SIGNING

PROJECT NO: 3180-00-74

HWY: STH 11

COUNTY: RACINE

DETOUR - OSOW SIGNING

SHEET

59

E

FILE NAME : N:\PDS\C3D\31800004\SHEETSPLAN\027001_DT.DWG
LAYOUT NAME - *****


PLOT DATE : 9/30/2019 10:23 AM


PLOT BY : ROTIER, STEVEN J


PLOT NAME :


PLOT SCALE : CUSTOM

WISDOT/CADDs SHEET 42









Estimate Of Quantities

3180-00-74

Line	Item	Item Description	Unit	Total	Qty
0002	204.0109.S	Removing Concrete Surface Partial Depth	SF	2,040.000	2,040.000
0004	204.0110	Removing Asphaltic Surface	SY	70,116.000	70,116.000
0006	204.0125	Removing Asphaltic Surface Milling	TON	2,372.000	2,372.000
0008	204.9105.S	Removing (item description) 01. LOOP DETECTOR WIRE & LEAD-IN CABLE STH 11/36/83 & STH 83/PINE ST	LS	1.000	1.000
0010	205.0100	Excavation Common	CY	36.000	36.000
0012	211.0100	Prepare Foundation for Asphaltic Paving (project) 01. 3180-00-74	LS	1.000	1.000
0014	213.0100	Finishing Roadway (project) 01. 3180-00-74	EACH	1.000	1.000
0016	305.0110	Base Aggregate Dense 3/4-Inch	TON	1,280.000	1,280.000
0018	305.0120	Base Aggregate Dense 1 1/4-Inch	TON	4,037.000	4,037.000
0020	390.0203	Base Patching Asphaltic	SY	208.000	208.000
0022	455.0605	Tack Coat	GAL	11,310.000	11,310.000
0024	460.0105.S	HMA Percent Within Limits (PWL) Test Strip Volumetrics	EACH	3.000	3.000
0026	460.0110.S	HMA Percent Within Limits (PWL) Test Strip Density	EACH	3.000	3.000
0028	460.2005	Incentive Density PWL HMA Pavement	DOL	27,360.000	27,360.000
0030	460.2010	Incentive Air Voids HMA Pavement	DOL	34,310.000	34,310.000
0032	460.6223	HMA Pavement 3 MT 58-28 S	TON	23,560.000	23,560.000
0034	460.6224	HMA Pavement 4 MT 58-28 S	TON	10,740.000	10,740.000
0036	465.0400	Asphaltic Shoulder Rumble Strips	LF	35,710.000	35,710.000
0038	618.0100	Maintenance And Repair of Haul Roads (project) 01. 3180-00-74	EACH	1.000	1.000
0040	619.1000	Mobilization	EACH	1.000	1.000
0042	625.0100	Topsoil	SY	280.000	280.000
0044	627.0200	Mulching	SY	280.000	280.000
0046	628.1504	Silt Fence	LF	300.000	300.000
0048	628.7010	Inlet Protection Type B	EACH	12.000	12.000
0050	628.7015	Inlet Protection Type C	EACH	35.000	35.000
0052	628.7020	Inlet Protection Type D	EACH	6.000	6.000
0054	629.0210	Fertilizer Type B	CWT	0.180	0.180
0056	630.0130	Seeding Mixture No. 30	LB	5.000	5.000
0058	630.0500	Seed Water	MGAL	6.000	6.000
0060	642.5201	Field Office Type C	EACH	1.000	1.000
0062	643.0300	Traffic Control Drums	DAY	14,700.000	14,700.000
0064	643.0420	Traffic Control Barricades Type III	DAY	5,450.000	5,450.000
0066	643.0705	Traffic Control Warning Lights Type A	DAY	7,500.000	7,500.000
0068	643.0715	Traffic Control Warning Lights Type C	DAY	2,950.000	2,950.000
0070	643.0800	Traffic Control Arrow Boards	DAY	250.000	250.000
0072	643.0900	Traffic Control Signs	DAY	15,750.000	15,750.000
0074	643.0920	Traffic Control Covering Signs Type II	EACH	86.000	86.000

Estimate Of Quantities

3180-00-74

Line	Item	Item Description	Unit	Total	Qty
0076	643.1000	Traffic Control Signs Fixed Message	SF	6.750	6.750
0078	643.1050	Traffic Control Signs PCMS	DAY	128.000	128.000
0080	643.5000	Traffic Control	EACH	1.000	1.000
0082	646.1020	Marking Line Epoxy 4-Inch	LF	56,684.000	56,684.000
0084	646.1545	Marking Line Grooved Wet Ref Contrast Epoxy 4-Inch	LF	6,710.000	6,710.000
0086	646.3020	Marking Line Epoxy 8-Inch	LF	1,204.000	1,204.000
0088	646.3545	Marking Line Grooved Wet Ref Contrast Epoxy 8-Inch	LF	6,153.000	6,153.000
0090	646.5020	Marking Arrow Epoxy	EACH	20.000	20.000
0092	646.5120	Marking Word Epoxy	EACH	7.000	7.000
0094	646.6120	Marking Stop Line Epoxy 18-Inch	LF	132.000	132.000
0096	646.7120	Marking Diagonal Epoxy 12-Inch	LF	255.000	255.000
0098	646.8020	Marking Corrugated Median Epoxy	SF	105.000	105.000
0100	646.8220	Marking Island Nose Epoxy	EACH	5.000	5.000
0102	646.9010	Marking Removal Line Water Blasting 4-Inch	LF	1,663.000	1,663.000
0104	646.9100	Marking Removal Line 8-Inch	LF	518.000	518.000
0106	649.0150	Temporary Marking Line Removable Tape 4-Inch	LF	2,775.000	2,775.000
0108	650.5000	Construction Staking Base	LF	20,592.000	20,592.000
0110	650.9910	Construction Staking Supplemental Control (project) 01. 3180-00-74	LS	1.000	1.000
0112	652.0225	Conduit Rigid Nonmetallic Schedule 40 2-Inch	LF	57.000	57.000
0114	652.0800	Conduit Loop Detector	LF	176.000	176.000
0116	653.0135	Pull Boxes Steel 24x36-Inch	EACH	2.000	2.000
0118	653.0905	Removing Pull Boxes	EACH	2.000	2.000
0120	655.0700	Loop Detector Lead In Cable	LF	1,096.000	1,096.000
0122	655.0800	Loop Detector Wire	LF	704.000	704.000
0124	690.0150	Sawing Asphalt	LF	850.000	850.000
0126	740.0440	Incentive IRI Ride	DOL	14,960.000	14,960.000
0128	ASP.1T0A	On-the-Job Training Apprentice at \$5.00/HR	HRS	800.000	800.000
0130	ASP.1T0G	On-the-Job Training Graduate at \$5.00/HR	HRS	1,000.000	1,000.000

REMOVING CONCRETE SURFACE PARTIAL DEPTH

204.0109.S.01				
REMOVING CONCRETE SURFACE PARTIAL DEPTH				
LOCATION	STA	TO	STA	SF
STH 11 EASTBOUND				
	967+40	TO	970+00	2,040
TOTAL				2,040

REMOVING ASPHALTIC SURFACE

204.0110 REMOVING ASPHALTIC SURFACE				
LOCATION	STA	TO	STA	SY
STH 11 EASTBOUND				
MAINLANES	1021+45	TO	1026+04	1,285
MAINLANES	1027+48	TO	1077+35	14,043
MAINLANES	1080+08	TO	1124+40	13,205
OFF-RAMP AT CTH P	1040+05	TO	1045+75	900
ON-RAMP AT CTH P	1046+00	TO	1060+24	1,494
LEFT TURN LANE AT YAHNKE SPUR	1088+83	TO	1093+00	556
RIGHT TURN LANE AT YAHNKE SPUR	1087+84	TO	1095+30	850
LEFT TURN LANE AT STH 83	1117+26	TO	1124+25	932
RIGHT TURN LANE AT STH 83	1119+92	TO	1124+80	617
STH 11 WESTBOUND				
MAINLANES	1021+45	TO	1026+04	1,285
MAINLANES	1027+48	TO	1077+59	14,124
MAINLANES	1080+22	TO	1124+30	16,370
ON-RAMP AT CTH P	1043+00	TO	1057+25	1,489
OFF-RAMP AT CTH P	1058+00	TO	1064+00	867
LEFT TURN LANE AT YAHNKE SPUR	1094+00	TO	1101+57	1,009
RIGHT TURN LANE AT YAHNKE SPUR	1092+58	TO	1096+30	496
RIGHT TURN LANE AT STH 83	1123+05	TO	1124+30	128
STH 11 INTERSECTION AT YAHNKE SPUR	1093+00	TO	1094+00	467
TOTAL				70,116

REMOVING ASPHALTIC SURFACE MILLING

204.0125 REMOVING ASPHALTIC SURFACE MILLING				
LOCATION	STA	TO	STA	TON
STH 11 EASTBOUND				
6-FT LEFT SHOULDER (TYP)	1021+45	TO	1026+04	28
3-FT LEFT SHOULDER (TYP)	1027+48	TO	1074+00	174
8-FT LEFT SHOULDER (TYP)	1074+00	TO	1077+35	23
3-FT LEFT SHOULDER (TYP)	1080+08	TO	1089+00	34
3-FT LEFT SHOULDER (TYP)	1100+30	TO	1117+30	63
10-FT RIGHT SHOULDER (TYP)	1021+45	TO	1026+04	59
8-FT RIGHT SHOULDER (TYP)	1027+48	TO	1040+50	131
8-FT RIGHT SHOULDER (TYP)	1047+75	TO	1074+67	261
10-FT RIGHT SHOULDER (TYP)	1074+67	TO	1077+35	46
8-FT RIGHT SHOULDER (TYP)	1080+08	TO	1088+50	84
8-FT RIGHT SHOULDER (TYP)	1094+75	TO	1120+50	258
STH 11 WESTBOUND				
3-FT LEFT SHOULDER (TYP)	1021+45	TO	1026+04	12
6-FT LEFT SHOULDER (TYP)	1027+48	TO	1030+50	22
3-FT LEFT SHOULDER (TYP)	1030+50	TO	1077+59	173
6-FT LEFT SHOULDER (TYP)	1080+22	TO	1083+00	26
3-FT LEFT SHOULDER (TYP)	1083+00	TO	1089+25	23
3-FT LEFT SHOULDER (TYP)	1101+60	TO	1118+80	62
8-FT RIGHT SHOULDER (TYP)	1021+45	TO	1026+04	32
10-FT RIGHT SHOULDER (TYP)	1027+48	TO	1031+25	46
8-FT RIGHT SHOULDER (TYP)	1031+25	TO	1055+75	255
8-FT RIGHT SHOULDER (TYP)	1063+00	TO	1077+59	145
8-FT RIGHT SHOULDER (TYP)	1080+22	TO	1085+50	52
10-FT RIGHT SHOULDER (TYP)	1085+50	TO	1088+28	35
8-FT RIGHT SHOULDER (TYP)	1088+28	TO	1092+75	44
8-FT RIGHT SHOULDER (TYP)	1095+50	TO	1123+75	279
TOTAL				2,372

3

PREPARE FOUNDATION FOR ASPHALTIC PAVING	
211.0100	
PREPARE FOUNDATION FOR ASPHALTIC PAVING	
LOCATION	LS
PROJECT	1
TOTAL	1

FINISHING ROADWAY	
213.0100	
FINISHING ROADWAY (3180-00-74)	
LOCATION	EACH
PROJECT	1
TOTAL	1

BASE AGGREGATE					
*					
			305.0110		305.0120
			BASE		BASE
			AGGREGATE		AGGREGATE
			DENSE 3/4-INCH		DENSE 1 1/4-INCH
LOCATION	STA	TO	STA	TON	TON
STH 11 EASTBOUND					
	1021+45	TO	1026+04	30	71
	1027+48	TO	1077+35	323	913
	1080+08	TO	1124+40	287	911
STH 11 WESTBOUND					
	1021+45	TO	1026+04	30	71
	1027+48	TO	1077+59	325	916
	1080+22	TO	1124+30	286	1,013
TOTAL				1,280	3,966

*ADDITIONAL QUANTITY SHOWN ELSEWHERE

3

BASE PATCHING						
*						
		205.0100		305.0120	390.0203	
		EXCAVATION		BASE AGGREGATE	BASE PATCHING	
		COMMON		DENSE 1 1/4-INCH	ASPHALTIC	
LOCATION	STA	TO	STA	CY	TON	SY
STH 11 WESTBOUND						
	1000+00	TO	1002+00	-	-	34
	1002+00	TO	1004+00	-	-	40
	1006+00	TO	1008+00	-	-	34
UNDISTRIBUTED**				36	71	100
TOTAL				36	71	208

*ADDITIONAL QUANTITY SHOWN ELSEWHERE

**ITEMS USED FOR BASE PATCHING LOCATIONS WHERE THERE IS POOR SUBGRADE MATERIAL AS DETERMINED BY THE ENGINEER

ASPHALTIC ITEMS

LOCATION	STA	TO	STA	455.0605	460.6223	460.6224
				TACK COAT	HMA PAVEMENT 3 MT 58-28 S	HMA PAVEMENT 4 MT 58-28 S
				GAL	TON	TON
STH 11 EASTBOUND						
MAINLANES	1021+45	TO	1026+04	180	432	158
MAINLANES	1027+48	TO	1077+35	1,966	4,718	1,730
MAINLANES	1080+08	TO	1124+40	1,849	4,437	1,627
OFF-RAMP AT CTH P	1040+05	TO	1045+75	126	302	111
ON-RAMP AT CTH P	1046+00	TO	1060+24	209	502	184
LEFT TURN LANE AT YAHNKE SPUR	1088+83	TO	1093+00	78	187	68
RIGHT TURN LANE AT YAHNKE SPUR	1087+84	TO	1095+30	119	286	105
LEFT TURN LANE AT STH 83	1117+26	TO	1124+25	130	313	115
RIGHT TURN LANE AT STH 83	1119+92	TO	1124+80	86	207	76
6-FT LEFT SHOULDER (TYP)	1021+45	TO	1026+04	17	--	30
3-FT LEFT SHOULDER (TYP)	1027+48	TO	1074+00	109	--	192
8-FT LEFT SHOULDER (TYP)	1074+00	TO	1077+35	14	--	25
3-FT LEFT SHOULDER (TYP)	1080+08	TO	1089+00	21	--	38
3-FT LEFT SHOULDER (TYP)	1100+30	TO	1117+30	40	--	70
10-FT RIGHT SHOULDER (TYP)	1021+45	TO	1026+04	37	--	65
8-FT RIGHT SHOULDER (TYP)	1027+48	TO	1040+50	82	--	145
8-FT RIGHT SHOULDER (TYP)	1047+75	TO	1074+67	163	--	287
10-FT RIGHT SHOULDER (TYP)	1074+67	TO	1077+35	29	--	51
8-FT RIGHT SHOULDER (TYP)	1080+08	TO	1088+50	53	--	93
8-FT RIGHT SHOULDER (TYP)	1094+75	TO	1120+50	161	--	284

ASPHALTIC ITEMS

LOCATION	STA	TO	STA	455.0605	460.6223	460.6224
				TACK COAT	HMA PAVEMENT 3 MT 58-28 S	HMA PAVEMENT 4 MT 58-28 S
				GAL	TON	TON
STH 11 WESTBOUND						
MAINLANES	1021+45	TO	1026+04	195	432	167
MAINLANES	1027+48	TO	1077+59	1,977	4,746	1,582
MAINLANES	1080+22	TO	1124+30	2,292	5,500	1,833
ON-RAMP AT CTH P	1043+00	TO	1057+25	208	500	167
OFF-RAMP AT CTH P	1058+00	TO	1064+00	121	291	97
LEFT TURN LANE AT YAHNKE SPUR	1094+00	TO	1101+57	141	339	113
RIGHT TURN LANE AT YAHNKE SPUR	1092+58	TO	1096+30	69	167	56
RIGHT TURN LANE AT STH 83	1123+05	TO	1124+30	18	43	14
3-FT LEFT SHOULDER (TYP)	1021+45	TO	1026+04	8	--	12
6-FT LEFT SHOULDER (TYP)	1027+48	TO	1030+50	14	--	22
3-FT LEFT SHOULDER (TYP)	1030+50	TO	1077+59	108	--	173
6-FT LEFT SHOULDER (TYP)	1080+22	TO	1083+00	16	--	26
3-FT LEFT SHOULDER (TYP)	1083+00	TO	1089+25	15	--	23
3-FT LEFT SHOULDER (TYP)	1101+60	TO	1118+80	39	--	62
8-FT RIGHT SHOULDER (TYP)	1021+45	TO	1026+04	20	--	32
10-FT RIGHT SHOULDER (TYP)	1027+48	TO	1031+25	29	--	46
8-FT RIGHT SHOULDER (TYP)	1031+25	TO	1055+75	160	--	255
8-FT RIGHT SHOULDER (TYP)	1063+00	TO	1077+59	91	--	145
8-FT RIGHT SHOULDER (TYP)	1080+22	TO	1085+50	33	--	52
10-FT RIGHT SHOULDER (TYP)	1085+50	TO	1088+28	22	--	35
8-FT RIGHT SHOULDER (TYP)	1088+28	TO	1092+75	28	--	44
8-FT RIGHT SHOULDER (TYP)	1095+50	TO	1123+75	174	--	279
STH 11 INTERSECTION AT YAHNKE SPUR	1093+00	TO	1094+00	65	157	52
TOTAL				11,310	23,560	10,740

HMA PERCENT WITHIN LIMITS

QUALITY MANAGEMENT PROGRAM USED								460.2005	460.2010	460.0110.S.01	460.0105.S.01	
								INCENTIVE DENSITY PWL HMA PAVEMENT	INCENTIVE AIR VOIDS HMA PAVEMENT	HMA PAVEMENT PWL TEST STRIP DENSITY	HMA PAVEMENT PWL TEST STRIP VOLUMETRICS	
LOCATION	STATION RANGE	MIXTURE USE	UNDERLYING SURFACE	BID ITEM	THICKNESS	TONS	MIXTURE ACCEPTANCE	DENSITY ACCEPTANCE	DOL	DOL	EACH	EACH
4-12' DRIVING LANES	1021+45 - 1125+00	LOWER	BASE AGGREGATE	3 MT 58-28S	2 3/4"	10,140	PWL INCENTIVE AIR VOIDS 460.2010	INCENTIVE DENSITY PWL HMA PAVEMENT 460.2005	10,140	10,140	1	1
TURN LANES	1021+45 - 1125+00	LOWER	BASE AGGREGATE	3 MT 58-28S	2 3/4"	1,650	PWL INCENTIVE AIR VOIDS 460.2010	QMP AS PER SS 460	--	1,650		--
4-12' DRIVING LANES	1021+45 - 1125+00	LOWER UPPER	3 MT 58-28S	3 MT 58-28S	2 3/4"	10,140	PWL INCENTIVE AIR VOIDS 460.2010	INCENTIVE DENSITY PWL HMA PAVEMENT 460.2005	10,140	10,140	1	1*
TURN LANES	1021+45 - 1125+00	LOWER UPPER	3 MT 58-28S	3 MT 58-28S	2 3/4"	1,650	PWL INCENTIVE AIR VOIDS 460.2010	QMP AS PER SS 460	--	1,650		--
4-12' DRIVING LANES	1021+45 - 1125+00	UPPER UPPER	3 MT 58-28S	4 MT 58-28S	1 3/4"	7,080	PWL INCENTIVE AIR VOIDS 460.2010	INCENTIVE DENSITY HMA PAVEMENT 460.2000	7,080	7,080	1	1
SHOULDER AND TURN LANES	1021+45 - 1125+00	UPPER UPPER	3 MT 58-28S	4 MT 58-28S	1 3/4"	3,650	PWL INCENTIVE AIR VOIDS 460.2010	QMP AS PER SS 460	--	3,650		--
TOTAL									27,360	34,310	3	3

*THIS TEST STRIP MAY OR MAY NOT BE REQUIRED BASED UPON CONTRACTOR OPERATION

3

ASPHALTIC RUMBLE STRIP

465.0400 ASPHALTIC SHOULDER RUMBLE STRIPS				
LOCATION	STA	TO	STA	LF
STH 11 EASTBOUND				
LEFT SHOULDER	1021+45	TO	1025+75	430
LEFT SHOULDER	1027+75	TO	1077+00	4,925
LEFT SHOULDER	1080+30	TO	1117+25	2,545
RIGHT SHOULDER	1000+00	TO	1025+75	2,575
RIGHT SHOULDER	1027+75	TO	1077+00	4,125
RIGHT SHOULDER	1080+30	TO	1119+00	2,870
STH 11 WESTBOUND				
LEFT SHOULDER	1021+45	TO	1025+75	430
LEFT SHOULDER	1027+75	TO	1077+30	4,955
LEFT SHOULDER	1080+50	TO	1119+00	2,625
RIGHT SHOULDER	1000+00	TO	1025+75	2,575
RIGHT SHOULDER	1027+75	TO	1077+30	4,005
RIGHT SHOULDER	1080+50	TO	1122+00	3,650
TOTAL				35,710

3

INLET PROTECTION

				628.7010 INLET PROTECTION TYPE B	628.7015 INLET PROTECTION TYPE C	628.7020 INLET PROTECTION TYPE D
LOCATION	STA	TO	STA	EACH	EACH	EACH
STH 11						
	967+00	TO	970+25	2	4	--
	1027+48	TO	1077+35	6	6	--
	1080+08	TO	1124+40	4	25	6
TOTAL				12	35	6

HAUL ROAD

618.0100	
MAINTENANCE AND REPAIR OF HAUL ROADS	
LOCATION	EACH
PROJECT	1
TOTAL	1

MOBILIZATION

619.1000	
MOBILIZATION	
LOCATION	EACH
PROJECT	1
TOTAL	1

QMP INCENTIVE: IRI RIDE

740.0440	
INCENTIVE IRI RIDE	
LOCATION	DOL
PROJECT	14,960
TOTAL	14,960

FIELD OFFICE

642.5201	
FIELD OFFICE TYPE C	
LOCATION	EACH
PROJECT	1
TOTAL	1

TRAFFIC CONTROL

		DURATION # OF DAYS	643.0300		643.0420		643.0705		643.0715		643.0800		643.0900		643.0920	643.1000	643.1050	
			DRUMS		BARRICADES TYPE III		WARNING LIGHTS TYPE A		TYPE C		ARROW BOARDS		SIGNS		COVERING SIGNS TYPE II	FIXED MESSAGE SIGN	SIGNS PCMS	
LOCATION			EACH*	DAYS	EACH*	DAYS	EACH*	DAYS	EACH*	DAYS	EACH*	DAYS	EACH*	DAYS	EACH	SF	EACH*	DAYS
STH 11 (INTERSECTION W/ STH 83)	ROAD & INSIDE LANE(S) CLOSURE	50	102	5,100	10	500	17	850	14	700	2	100	15	750	--	--	1	14
STH 83/PINE ST	TURN LANE CLOSURES	50	23	1,150	16	800	22	1,100	--	--	--	--	25	1,250	--	--	--	--
STH 11 AND CTH P EB RAMPS	ROAD AND TURN LANE CLOSURES	50	43	2,150	16	800	22	1,100	26	1,300	1	50	19	950	12	--	--	--
STH 11 AND CTH P WB RAMPS	ROAD AND TURN LANE CLOSURE	50	30	1,500	19	950	29	1,450	--	--	--	--	14	700	--	--	--	--
STH 11 AND STH 36	ROAD AND LANE CLOSURE(S)	50	88	4,400	16	800	22	1,100	19	950	2	100	20	1,000	--	--	2	100
STH 11 AND CTH JS	STH 11 WB TO CTH JS	50	--	--	3	150	6	300	--	--	--	--	3	150	--	6.75	1	14
STH 11 AND YAHNKE RD	ACCESS TO BUCK TRAIL ARCHERS	50	8	400	29	1,450	32	1,600	--	--	--	--	9	450	24	--	--	--
WB DETOUR ROUTE		50	--	--	--	--	--	--	--	--	--	--	24	1,200	--	--	--	--
WB DETOUR ROUTE	STH 11 / STH 83	50	--	--	--	--	--	--	--	--	--	--	29	1,450	1	--	--	--
WB DETOUR ROUTE	STH 11 / CTH JS	50	--	--	--	--	--	--	--	--	--	--	10	500	6	--	--	--
WB DETOUR ROUTE	STH 11 / STH 36	50	--	--	--	--	--	--	--	--	--	--	11	550	--	--	--	--
EB DETOUR ROUTE		50	--	--	--	--	--	--	--	--	--	--	24	1,200	--	--	--	--
EB DETOUR ROUTE	STH 11 / STH 83	50	--	--	--	--	--	--	--	--	--	--	6	300	36	--	--	--
EB DETOUR ROUTE	STH 11 / CTH JS	50	--	--	--	--	--	--	--	--	--	--	60	3,000	--	--	--	--
EB DETOUR ROUTE	STH 11 / STH 36	50	--	--	--	--	--	--	--	--	--	--	5	250	7	--	--	--
STH 11 AND IH 43		50	--	--	--	--	--	--	--	--	--	--	2	100	--	--	--	--
STH 11 AND STH 120		50	--	--	--	--	--	--	--	--	--	--	12	600	--	--	--	--
STH 11 AND STH 142		50	--	--	--	--	--	--	--	--	--	--	5	250	--	--	--	--
STH 11 AND STH 83		50	--	--	--	--	--	--	--	--	--	--	5	250	--	--	--	--
STH 11 AND US 45		50	--	--	--	--	--	--	--	--	--	--	12	600	--	--	--	--
STH 83 (NORTH OF FOX RIVER)		50	--	--	--	--	--	--	--	--	--	--	5	250	--	--	--	--
TOTAL			14,700		5,450		7,500		2,950		250		15,750		86	6.75	128	

NOTES:
* FOR INFORMATION ONLY

TRAFFIC CONTROL

		643.5000
STAGE	LOCATION	EACH
ALL	PROJECT	1
TOTAL		1

3

3

MARKING

			646.1020					646.3020		646.1545		646.3545	
			LINE EPOXY 4-INCH					LINE EPOXY 8-INCH		LINE GROOVED WET REFLECTIVE CONTRAST EPOXY 4-INCH		LINE GROOVED WET REFLECTIVE CONTRAST EPOXY 8-INCH	
			(12.5' LINE, 37.5' GAP)			(3' LINE, 12' GAP)	(3' LINE, 12' GAP)	(3' LINE, 12' GAP)		(12.5' LINE, 37.5' GAP)	(2' LINE, 6' GAP)	(3' LINE, 9' GAP)	
			(WHITE)	(YELLOW)	(WHITE)	(WHITE)	(YELLOW)	(WHITE)	(WHITE)	(WHITE)	(YELLOW)	(WHITE)	(YELLOW)
STATION	TO	STATION	LF	LF						LF	LF	LF	LF
947+25	TO	954+50	--	--	--	--	--	--	--	175	--	--	--
966+30	TO	971+50	--	--	--	--	--	1,010	--	--	--	--	--
1000+00	TO	1040+05	8,010	8,010	--	--	--	--	--	2,000	--	--	--
1040+05	TO	1050+10	1,795	2,010	--	--	--	--	--	500	--	800	78
1050+10	TO	1053+50	680	680	--	--	--	--	--	175	--	--	--
1053+50	TO	1063+50	1,795	2,000	--	--	--	--	--	500	--	865	72
1063+50	TO	1087+85	4,870	4,870	--	--	--	--	--	1,213	--	--	--
1087+85	TO	1101+60	2,625	2,530	--	--	--	--	--	688	--	2,310	39
1101+60	TO	1117+25	3,130	3,130	--	--	--	--	--	788	--	--	--
1117+25	TO	1124+75	1,460	1,470	--	--	--	--	--	363	--	1,880	39
1131+75	TO	1134+25	--	--	--	--	--	--	--	63	--	--	--
1149+25	TO	1156+00	--	--	--	--	--	--	--	175	--	--	--
YAHNKE SPUR			--	100	--	--	--			--	70	70	--
EB RAMP AT CTH P			1,680	1,895	175	--	--	167	27	--	--	--	--
WB RAMP AT CTH P			1,680	1,975	75	15	24	--	--	--	--	--	--
SUBTOTAL			27,725	28,670	250	15	24	1,177	27	6,640	70	5,925	228
TOTAL			56,684					1,204		6,710		6,153	

MARKING

		646.5020		646.5120	646.6120	646.7120	646.8020	646.8220
		ARROW EPOXY		WORD EPOXY	STOP LINE EPOXY	DIAGONAL EPOXY	CORRUGATED MEDIAN EPOXY	ISLAND NOSE EPOXY
		TYPE 2	TYPE 5	(ONLY)	18-INCH	12-INCH	(YELLOW)	(YELLOW)
		(WHITE)	(WHITE)	(WHITE)	(WHITE)	(WHITE)		
STATION	TO STATION	EACH	EACH	EACH	LF	LF	SF	EACH
966+30	TO 970+00	--	--	--	--	178	--	--
1040+05	TO 1050+10	2	1	1	--	--	--	--
1050+10	TO 1053+50	--	2	--	--	--	--	--
1053+50	TO 1063+50	2	1	1	--	--	--	--
1087+85	TO 1101+60	2	--	1	--	49	--	2
1117+25	TO 1124+75	2	--	--	39	22	--	1
YAHNKE SPUR		2	--	--	33	6	--	--
EB RAMP AT CTH P		4	--	2	48	--	--	1
WB RAMP AT CTH P		2	--	2	12	--	105	1
SUBTOTAL		16	4	7	132	255	105	5
TOTAL		20		7	132	255	105	5

TEMPORARY MARKING

		646.9010		646.9100	649.0150
		MARKING REMOVAL LINE WATER BLASTING		MARKING REMOVAL LINE	TEMPORARY MARKING LINE REMOVABLE TAPE
		4-INCH		8-INCH	4-INCH
					(WHITE)
STATION	TO	STATION	LF	LF	LF
947+50	TO	954+25	175	--	675
966+30	TO	970+00	--	518	550
1000+00	TO	1021+45	1,075	--	--
1131+75		1134+25	63	--	230
1149+25	TO	1156+00	175	--	660
CTH P SOUTHBOUND			175	--	660
TOTAL			1,663	518	2,775

RESTORATION

				625.0100	627.0200	628.1504	629.0210	630.0130	630.0500
				TOPSOIL	MULCHING	SILT FENCE	FERTILIZER	SEEDING MIXTURE	
				SY	SY	LF	TYPE B	NO.30	SEED WATER
LOCATION	STA	TO	STA				CWT	LB	MGAL
STH 11 EASTBOUND									
	1120+00	TO	1123+00	280	280	300	0.18	5	6
TOTAL				280	280	300	0.18	5	6

SURVEY PROJECT

	650.5000	650.9910
	CONSTRUCTION	CONSTRUCTION
	STAKING BASE	STAKING
		SUPPLEMENTAL CONTROL
LOCATION	LF	LS
PROJECT	20,592	1
TOTAL	20,592	1

SAWING ASPHALT

				690.0150
				SAWING ASPHALT
LOCATION	STA	TO	STA	LF
STH 11 EASTBOUND				
	1000+00	TO	1026+04	35
	1027+48	TO	1077+35	49
	1080+08	TO	1124+40	221
STH 11 WESTBOUND				
	1000+00	TO	1026+04	277
	1027+48	TO	1077+59	50
	1080+22	TO	1124+30	50
UNDISTRIBUTED**				168
TOTAL				850

**ITEMS USED FOR BASE PATCHING LOCATIONS WHERE THERE IS POOR SUBGRADE MATERIAL AS DETERMINED BY THE ENGINEER

STH 11/36/83 & STH 83/PINE ST
RACINE COUNTY
CATEGORY 0010
S51-0993

REMOVE LOOP DETECTOR WIRE AND LEAD-IN CABLE	
204.9105.S.01	
REMOVING LOOP DETECTOR WIRE & LEAD-IN CABLE	
LOCATION	L.S.
STH 11/36/83 & STH 83/PINE ST	1
TOTAL	1

TRAFFIC DETECTOR LOOPS								
LOOP NO.	HOME RUN PB	LOCATION*	SIZE (FT)x(FT)	NO. OF TURNS	SDD INSTALLATION REFERENCE	652.0800 CONDUIT	655.0700 LOOP DETECTOR	655.0800 LOOP DETECTOR
						LOOP DETECTOR L.F.	LEAD IN CABLE L.F.	WIRE L.F.
61	PB8	1120+57.1, 35.7' RT	6'X20'	4	LOOP DETECTOR INSTALLED IN BASE COURSE WITH PULL (SPlice) BOX OFF ROADWAY (OPTION 2)	84	636	336
62	PB7	1122+32.1, 37.7' RT	6'X20'	4	LOOP DETECTOR INSTALLED IN BASE COURSE WITH PULL (SPlice) BOX OFF ROADWAY (OPTION 2)	92	460	368
TOTAL						176	1096	704



* LOCATION IS TO FRONT CENTER OF DETECTOR LOOP
* * FINAL LOCATION TO BE DETERMINED BY THE ENGINEER IN THE FIELD.

PULL BOXES		
653.0135		
PULL BOXES STEEL		
PULL BOX NO.	LOCATION*	24x36-INCH EACH
PB7	1122+32.1, 67.4' RT	1
PB8	1120+57.1, 6231' RT	1
TOTAL		2

* FINAL LOCATION TO BE DETERMINED BY THE ENGINEER IN THE FIE



CONDUIT		
652.0225		
CONDUIT RIGID NONMETALLIC SCHEDULE 40		
2-INCH		
FROM	TO	L.F.
PB7	EX. CONDUIT	21
PB8	EX. CONDUIT	36
TOTAL		57


REMOVE PULL BOXES	
653.0905	
REMOVING PULL BOXES	
PULL BOX NO.	EACH
PB7	1
PB8	1
TOTAL	2



BENCHMARKS			
NO.	STATION	ELEV.	DESCRIPTION
3592	1077+71.50	789.660'	HMOD BRASS DISC NW COR B-51-100 9A011


STH 11 SUPERELEVATION TABLE			
STATION	TYPE	LEFT	RIGHT
1060+00	END NC	-0.02	-0.02
1060+50	REV. CROWN	0.02	-0.02
1062+20	BEGIN FS	0.055	-0.055
1072+00	END FS	0.055	-0.055
1073+25	REV. CROWN	0.02	-0.02
1074+50	REV. CROWN	-0.02	0.02
1082+00	BEGIN FS	-0.055	0.055
1092+50	END FS	-0.055	0.055
1094+00	REV. CROWN	-0.02	0.02
1095+00	BEGIN NC	-0.02	-0.02






5

5




PROJECT NO: 3180-00-74	HWY: STH 11	COUNTY: RACINE	PLAN AND PROFILE: STH 11 EB PGL	SHEET 78
------------------------	-------------	----------------	---------------------------------	----------


5





5





PROJECT NO:	3180-00-74	HWY:	STH 11	COUNTY:	RACINE	PLAN AND PROFILE:	STH 11 EB PGL	SHEET	79	E
-------------	------------	------	--------	---------	--------	-------------------	---------------	-------	----	---





BENCHMARKS			
NO.	STATION	ELEV.	DESCRIPTION
3592	1077+71.50	789.660'	HMOD BRASS DISC NW COR B-51-100 9A011

STH 11 SUPERELEVATION TABLE			
STATION	TYPE	LEFT	RIGHT
1060+00	END NC	-0.02	-0.02
1060+50	REV. CROWN	0.02	-0.02
1062+20	BEGIN FS	0.055	-0.055
1072+00	END FS	0.055	-0.055
1073+25	REV. CROWN	0.02	-0.02
1074+50	REV. CROWN	-0.02	0.02
1082+00	BEGIN FS	-0.055	0.055
1092+50	END FS	-0.055	0.055
1094+00	REV. CROWN	-0.02	0.02
1095+00	BEGIN NC	-0.02	-0.02



PROJECT NO: 3180-00-74

HWY: STH 11

COUNTY: RACINE

PLAN AND PROFILE: STH 11 WB PGL

SHEET

82

E

FILE NAME : N:\PDS\C3D\31800004\SHEETSPLAN\050101_PPWB.DWG
LAYOUT NAME - WB3


PLOT DATE : 4/30/2019 7:38 AM

PLOT BY : ROTIER, STEVEN J

PLOT NAME :


PLOT SCALE : 1 IN:200 FT

WISDOT/CADDs SHEET 44





5

5




PROJECT NO: 3180-00-74	HWY: STH 11	COUNTY: RACINE	PLAN AND PROFILE: STH 11 WB PGL	SHEET 83
------------------------	-------------	----------------	---------------------------------	----------




Standard Detail Drawing List

08E09-06	SILT FENCE
08E10-02	INLET PROTECTION TYPE A, B, C AND D
09B02-10	CONDUIT
09B04-11	PULL BOX
09F15-04B	LOOP DETECTOR INSTALLED IN BASE COURSE WITH PULL (SPLICE) BOX OFF ROADWAY (OPTION 2)
13A05-05A	SHOULDER RUMBLE STRIP, MILLING
13A10-02C	2-LANE RURAL SHOULDER RUMBLE STRIP, MILLING
15C02-07A	BARRICADES AND SIGNS FOR MAINLINE CLOSURES
15C02-07B	BARRICADES AND SIGNS FOR VARIOUS CLOSURES
15C02-07C	DETOUR SIGNING FOR MAINLINE CLOSURES
15C02-07F	ADVANCED WIDTH RESTRICTION SIGNING
15C03-05	BARRICADES AND SIGNS FOR SIDEROAD CLOSURES
15C07-14B	PAVEMENT MARKING WORDS
15C07-14C	PAVEMENT MARKING ARROWS
15C08-19A	LONGITUDINAL MARKING (MAINLINE)
15C08-19C	PAVEMENT MARKING (TURN LANES)
15C11-07B	CHANNELIZING DEVICES DRUMS, CONES, BARRICADES AND VERTICAL PANELS
15C18-04	MEDIAN ISLAND MARKING
15C27-03B	PAVEMENT MARKING (ISLANDS)
15C33-03	STOP LINE AND CROSSWALK PAVEMENT MARKING
15D12-07A	TRAFFIC CONTROL, LANE CLOSURE
15D20-04	TRAFFIC CONTROL, SINGLE LANE CLOSURE, NON-FREEWAY/EXPRESSWAY
15D38-02A	TEMPORARY TRAFFIC CONTROL SIGN MOUNTING
15D38-02B	ATTACHMENT OF SIGNS TO POSTS




TYPICAL APPLICATION OF SILT FENCE

NOTE: ADDITIONAL POST DEPTH OR TIE BACKS MAY BE REQUIRED IN UNSTABLE SOILS




SILT FENCE



PLAN VIEW


SILT FENCE AT MEDIAN SURFACE DRAINS




GENERAL NOTES

DETAILS OF CONSTRUCTION NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS AND APPLICABLE SPECIAL PROVISIONS.

- ① HORIZONTAL BRACE REQUIRED WITH 2" X 4" WOODEN FRAME OR EQUIVALENT AT TOP OF POSTS.
- ② FOR MANUAL INSTALLATIONS THE TRENCH SHALL BE A MINIMUM OF 4" WIDE & 6" DEEP TO BURY AND ANCHOR THE GEOTEXTILE FABRIC. FOLD MATERIAL TO FIT TRENCH AND BACKFILL & COMPACT TRENCH WITH EXCAVATED SOIL.
- ③ WOOD POSTS SHALL BE A MINIMUM SIZE OF 1 1/8" X 1 1/8" OF OAK OR HICKORY.
- ④ SILT FENCE TO EXTEND ACROSS THE TOP OF THE PIPE.
- ⑤ CONSTRUCT SILT FENCE FROM A CONTINUOUS ROLL IF POSSIBLE BY CUTTING LENGTHS TO AVOID JOINTS. IF A JOINT IS NECESSARY USE ONE OF THE FOLLOWING TWO METHODS; A) OVERLAP THE END POSTS AND TWIST, OR ROTATE, AT LEAST 180 DEGREES, B) HOOK THE END OF EACH SILT FENCE LENGTH.



TRENCH DETAIL



SILT FENCE TIE BACK (WHEN REQUIRED BY THE ENGINEER)

SILT FENCE

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED

4-29-05



DATE

/S/ Beth Conn

CHIEF ROADWAY DEVELOPER

FHWA

ENGINEER



INLET PROTECTION, TYPE A


GENERAL NOTES

INLET PROTECTION DEVICES SHALL BE MAINTAINED OR REPLACED AT THE DIRECTION OF THE ENGINEER.

MANUFACTURED ALTERNATIVES APPROVED AND LISTED ON THE
DEPARTMENT'S EROSION CONTROL PRODUCT ACCEPTABILITY LIST MAY BE
SUBSTITUTED.


WHEN REMOVING OR MAINTAINING INLET PROTECTION, CARE SHALL BE TAKEN SO THAT THE SEDIMENT TRAPPED ON THE GEOTEXTILE FABRIC DOES NOT FALL INTO THE INLET. ANY MATERIAL FALLING INTO THE INLET SHALL BE REMOVED IMMEDIATELY.

- ① FINISHED SIZE, INCLUDING FLAP POCKETS WHERE REQUIRED, SHALL EXTEND A MINIMUM OF 10" AROUND THE PERIMETER TO FACILITATE MAINTENANCE OR REMOVAL.
- ② FOR INLET PROTECTION, TYPE C (WITH CURB BOX), AN ADDITIONAL 18" OF FABRIC IS WRAPPED AROUND THE WOOD AND SECURED WITH STAPLES. THE WOOD SHALL NOT BLOCK THE ENTIRE HEIGHT OF THE CURB BOX OPENING.
- ③ FLAP POCKETS SHALL BE LARGE ENOUGH TO ACCEPT WOOD 2X4.



INLET PROTECTION, TYPE B (WITHOUT CURB BOX)

(CAN BE INSTALLED IN ANY INLET WITHOUT A CURB BOX)



INLET PROTECTION, TYPE C (WITH CURB BOX)

INSTALLATION NOTES

TYPE B & C

TRIM EXCESS FABRIC IN THE FLOW LINE TO WITHIN 3" OF THE GRATE.


THE CONTRACTOR SHALL DEMONSTRATE A METHOD OF MAINTENANCE, USING A SEWN FLAP, HAND HOLDS OR OTHER METHOD TO PREVENT ACCUMULATED SEDIMENT FROM ENTERING THE INLET.

TYPE D

DO NOT INSTALL INLET PROTECTION TYPE D IN INLETS SHALLOWER THAN 30", MEASURED FROM THE BOTTOM OF THE INLET TO THE TOP OF THE GRATE.

TRIM EXCESS FABRIC IN THE FLOW LINE TO WITHIN 3" OF THE GRATE.

THE INSTALLED BAG SHALL HAVE A MINIMUM SIDE CLEARANCE, BETWEEN THE INLET WALLS AND THE BAG, MEASURED AT THE BOTTOM OF THE OVERFLOW HOLES, OF 3". WHERE NECESSARY THE CONTRACTOR SHALL CINCH THE BAG, USING PLASTIC ZIP TIES, TO ACHIEVE THE 3" CLEARANCE. THE TIES SHALL BE PLACED AT A MAXIMUM OF 4" FROM THE BOTTOM OF THE BAG.



INLET PROTECTION, TYPE D

(CAN BE INSTALLED IN ANY INLET TYPE WITH
OR WITHOUT A CURB BOX AS PER NOTE (2))

INLET PROTECTION TYPE A, B, C, AND D

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION


APPROVED

10/16/02


DA

/S/ Beth Connolly 87

CHIEF ROADWAY DEVELOPMENT ENGINEER



PLAN VIEW
ARROW MARK



SIDE ELEVATION
DETAIL FOR CONDUIT UNDER PAVED HIGHWAYS

*DEPTH OF CONDUIT AND LENGTH OF PULL BOX VARIES
WITH HEIGHT OF CURB USED. ALSO SEE PULL BOX S.D.D. 9B4

GENERAL NOTES

DETAILS OF CONSTRUCTION, MATERIALS AND WORKMANSHIP NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE CONTRACT.

METALLIC (STANDARD SPECIFICATION 652.2.2) OR NONMETALLIC (STANDARD SPECIFICATION 652.2.3) CONDUIT SHALL BE FURNISHED AND PLACED AS SHOWN.

DEPTH OF CONDUIT INSTALLED BELOW THE TRAVELED WAY SHALL BE 24 INCHES MINIMUM AND 36 INCHES MAXIMUM.

DEPTH OF CONDUIT INSTALLED THAT IS NOT BELOW THE TRAVELED WAY SHALL BE 18 INCHES MINIMUM AND 36 INCHES MAXIMUM.

ANY EXCEPTION TO THE MAXIMUM DEPTH SHALL BE ONLY WITH THE WRITTEN APPROVAL OF THE ENGINEER.

THE TRENCH SHALL NOT BE BACKFILLED PRIOR TO INSPECTION OF THE CONDUIT.

ALL METALLIC CONDUIT RACEWAY ENDS SHALL BE REAMED AND THREADED.

ALL METALLIC CONDUIT IN WHICH WIRE OR CABLE IS TO BE INSTALLED SHALL BE BUSHED WITH APPROVED THREADED BUSHINGS BEFORE INSTALLATION OF THE WIRE OR CABLE.

ALL METALLIC CONDUITS IN WHICH WIRE OR CABLE IS NOT TO BE INSTALLED SHALL BE CAPPED WITH THREADED PROTECTIVE CAPS, AS APPROVED BY THE ENGINEER.

ALL NONMETALLIC CONDUIT SHALL BE CAPPED OR PLUGGED IMMEDIATELY AFTER INSTALLATION AND SHALL REMAIN CAPPED OR PLUGGED UNTIL WIRE/CABLES ARE INSTALLED.

NONMETALLIC CONDUITS IN WHICH WIRE OR CABLE IS NOT BEING INSTALLED SHALL REMAIN CAPPED OR PLUGGED.

BENDING OF PVC ELECTRICAL CONDUIT SHALL BE ACCOMPLISHED BY USING A BLANKET OR EMERSION TYPE TANK DESIGNED FOR THE PURPOSE OF BENDING PVC ELECTRICAL CONDUIT.

ALL CUT ENDS SHALL BE TRIMMED INSIDE AND OUTSIDE TO REMOVE ALL ROUGH EDGES ON NONMETALLIC CONDUIT. (SEE NEC 347.5)

WHEN REQUIRED TO CONNECT NONMETALLIC CONDUIT TO METALLIC CONDUIT, ONLY U.L. LISTED ADAPTER FITTINGS SHALL BE USED.

PRIOR TO CONDUIT ACCEPTANCE, CONDUIT CAPS OR PLUGS SHALL BE REMOVED, AND THE CAPS, PLUGS AND CONDUIT ENDS SHALL BE THOROUGHLY CLEANED AND THEN THE CAPS OR PLUGS REINSTALLED TO ENSURE THAT THE CAPS OR PLUGS CAN BE EASILY REMOVED IN THE FUTURE.

ALL CONDUIT BEING FURNISHED AND INSTALLED SHALL HAVE THE U.L. LABEL FIRMLY ATTACHED.

CONDUIT RUNS SHALL BE THE SAME SIZE OF CONDUIT FROM ONE END TO THE OTHER (FROM PULL BOX TO PULL BOX-OR-JUNCTION BOX TO JUNCTION BOX-OR-BASE TO BASE, ETC.).

TRACER WIRE SHALL BE INSTALLED AS STATED IN THE STANDARD SPECIFICATION, ITEM 652.3.1.1.

ALL CONDUIT RUNS SHALL BE STRAIGHT (WITHOUT BENDS) FROM PULL BOX TO PULL BOX, PULL BOX TO BASE AND BASE TO BASE AS SHOWN ON THE PLANS.

CONDUIT

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
March, 2017 /S/ Ahmet Demirbilek
DATE STATE ELECTRICAL 88
FHWA

TABLE OF NOMINAL DIMENSIONS AND WEIGHTS

DIMENSION IN INCHES		CORRUGATED STEEL PIPE								
PIPE DIAMETER (INSIDE)	A	12	12	12	18	18	18	24	24	24
PIPE LENGTH **	B	24	30	36	24	30	36	36	42	48
WALL THICKNESS	C	0.064	0.064	0.064	0.064	0.064	0.064	0.064	0.064	0.064
COVER	D	10 1/4	10 1/4	10 1/4	16 1/4	16 1/4	16 1/4	22 1/4	22 1/4	22 1/4
FRAME	E	14 1/2	14 1/2	14 1/2	20 1/2	20 1/2	20 1/2	26 1/2	26 1/2	26 1/2
FRAME	F	8 1/2	8 1/2	8 1/2	14 1/2	14 1/2	14 1/2	20 1/2	20 1/2	20 1/2
FRAME	G	11 1/2	11 1/2	11 1/2	17 1/2	17 1/2	17 1/2	23 1/2	23 1/2	23 1/2
WEIGHT IN POUNDS *										
FRAME AND COVER		60	60	60	110	110	110	155	155	155

* THE ACTUAL WEIGHT OF THE MANHOLE FRAME AND COVER MAY VARY WITHIN 5 PERCENT PLUS OR MINUS OF THE WEIGHTS SHOWN.

** NORMALLY USED LENGTHS. THE PROJECT ENGINEER SHALL DETERMINE IF PIPE LENGTHS, OTHER THAN THOSE SPECIFIED, SHALL BE USED, TO A MAXIMUM OF 48" (CONTINUOUS LENGTH, NON-SPLICED). THE ADDITIONAL LENGTH SHALL BE INCIDENTAL TO THE PULL BOX BID PRICE.

GENERAL NOTES

DETAILS OF CONSTRUCTION, MATERIALS AND WORKMANSHIP NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE CONTRACT.

ALL FRAMES AND COVERS SHALL BE HEAVY DUTY TYPE, SUITABLE FOR VEHICULAR TRAFFIC LOADS.

PULL BOXES LOCATED IN THE ROADWAYS SHALL HAVE LOCKING COVERS.







ENTRANCE HOLES INTO PULL BOXES SHALL BE CUT WITH A CIRCULAR HOLE SAW OR HYDRAULIC CONDUIT PUNCH. HOLE SIZE SHALL BE THE OUTSIDE DIAMETER OF THE CONDUIT THAT IS TO FIT IN THE OPENING PLUS NO MORE THAN 1/4".

THE CONTRACTOR SHALL NOT INSTALL WIRE IN ANY PULL BOX UNTIL ITS INSTALLATION HAS BEEN INSPECTED AND ACCEPTED BY THE ENGINEER.


GROUNDING LUGS (MECHANICAL CONNECTORS) SHALL BE U.L. LISTED AND APPROVED FOR USE WITH COPPER WIRE.

ALL METALLIC CONDUIT IN WHICH WIRE AND/OR CABLE IS TO BE INSTALLED, SHALL BE BUSHED BEFORE INSTALLATION OF THE WIRE AND/OR CABLE.

WHEN PULL BOXES ARE INSTALLED FOR FUTURE USE, DO NOT INSTALL THE EQUIPMENT GROUNDING LUG. THE EQUIPMENT GROUNDING LUG, THE EQUIPMENT GROUNDING ELECTRODE AND THE EQUIPMENT GROUNDING CONDUCTOR SHALL BE REQUIRED AND INSTALLED UNDER A FUTURE WIRING CONTRACT.



PULL BOX	
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION	
APPROVED Sept. 2014 DATE	/S/ Ahmet Demirelek STATE ELECTRICAL 89
FHWA	



*RECESS PULL (SPlice) BOX SO THAT THE COVER IS 3\"

LOOP DETECTOR INSTALLATION DETAIL

GENERAL NOTES

DETAILS OF CONSTRUCTION, MATERIALS AND WORKMANSHIP NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE CONTRACT.

LOOP SIZE, CONFIGURATION LOCATION, NUMBER OF TURNS OF WIRE AND ASSOCIATED SIGNAL PHASE SHALL BE AS SHOWN ON THE PLANS.

PITCH LEAD OUT CONDUIT TO DRAIN TO ROADSIDE PULL (SPlice) BOX.

SPlices SHALL BE INSTALLED BY USING CAST IN PLACE SPlice KITS LISTED ON THE DEPARTMENTS APPROVED PRODUCTS LIST OR AN ENGINEER APPROVED EQUAL. NON-INSULATED BUTT SPlices TO FIT #12 AWG STRANDED WIRE SHALL BE USED. SPlices SHALL BE SOLDERED AND INSULATED FROM EACH OTHER AS PER INSTRUCTIONS INCLUDED IN THE SPlice KIT.

MEASURE GROUND RESISTANCE USING A MEGGER. REPLACE LOOP WIRE NOT ATTAINING A READING OF INFINITY TO GROUND.

AFTER SPlicing THE LOOP WIRE TO THE LOOP LEAD-IN CABLE, THE CONTRACTOR SHALL MEASURE INDUCTANCE, GROUND RESISTANCE AND WIRE RESISTANCE AT THE CABINET END OF THE LEAD-IN CABLE AND FURNISH A COPY OF THE READINGS TO THE PROJECT ENGINEER FOR EVALUATION.

LOOP DETECTOR LEADS SHALL BE IDENTIFIED WITH THEIR ASSOCIATED LOOP BY USE OF WATERPROOF TAGS AT BOTH ENDS OF THE CABLE. A LISTING OF THE CABLE IDENTIFICATION PER INDIVIDUAL LOOP LEAD-IN SHALL BE PLACED IN THE CABINET.


THE #12 AWG. LOOP WIRE IN THE PULL (SPlice) BOX SHALL BE HAND TWISTED AT LEAST 3 TWISTS PER FOOT BEFORE BEING SPliced TO THE LOOP LEAD-IN CABLE.

SPlices OF LOOP WIRE TO LEAD-IN CABLE SHALL BE MADE ONLY IN PULL (SPlice) BOXES AT THE SIDE OF THE ROAD.


THE #12 AWG LOOP WIRE SHALL BE INSTALLED FROM THE ROADSIDE PULL (SPlice) BOX, THROUGH THE LOOP CONDUIT, BACK TO THE ROADSIDE PULL (SPlice) BOX, AND BE INSTALLED IN ONE, NON-SPliced CONTINUOUS LENGTH.

PROTECTION OF THE CONDUITS IN THE BASE COURSE SHALL BE REQUIRED AFTER INSTALLATION AND BEFORE NEW PAVEMENT IS INSTALLED.

SHOULD INSTALLATION REPAIR BE REQUIRED, IT SHALL BE DONE UNDER THE DIRECTION OF THE PROJECT ENGINEER.



TYPICAL PLAN OF LOOP DETECTOR WITH 24\"




MULTI-LANE INSTALLATION


LOOP DETECTOR INSTALLED IN BASE COURSE WITH PULL (SPlice) BOX OFF ROADWAY (OPTION 2)	
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION	
APPROVED Sept. 2014 DATE	/S/ Ahmet Demirelek STATE ELECTRICAL 90
FHWA	

6

6



PLAN VIEW
SHOULDER WITH GROOVES



PLAN VIEW
(SINGLE GROOVE)

PLACEMENT DETAIL FOR MILLED RUMBLE STRIP


GENERAL NOTES

DETAILS OF CONSTRUCTION SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS AND APPLICABLE SPECIAL PROVISIONS.


RUMBLE STRIPS ON EXPRESSWAYS

DO NOT INSTALL RUMBLE STRIPS ACROSS SIDE ROAD INTERSECTIONS, COMMERCIAL DRIVEWAYS, PRIVATE DRIVEWAYS OR ADJACENT TO RIGHT TURN LANES, LEFT TURN LANES, TURN LANE TAPERS, BRIDGE DECKS, BRIDGE APPROACHES, OR 100 FEET IN ADVANCE OF RAILROAD CROSSING. THE ATTACHED STANDARD DETAIL DRAWING SHOWS THE LOCATION OF THE RUMBLE STRIPS AT INTERCHANGE AREAS.


① CONCRETE PAVEMENT - RUMBLE STRIPS SHALL BE A MINIMUM OF 6" AWAY FROM TRANSVERSE JOINTS.




ISOMETRIC



SECTION VIEW
CONCRETE PAVEMENT EXTENDS INTO RIGHT SHOULDER)




SECTION VIEW
TYPICAL LOCATIONS OF SHOULDER RUMBLE STRIPS
IN RURAL DIVIDED HIGHWAYS
(ONE ROADWAY IS SHOWN)




SECTION A-A

SHOULDER RUMBLE STRIP,
MILLING


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION




SHOULDER GROOVES AT MISCELLANEOUS CROSSINGS




SHOULDER GROOVES AT BRIDGES



SHOULDER GROOVES AT DRIVEWAYS^①



SHOULDER GROOVES AT RIGHT TURN LANE



SHOULDER GROOVES AT INTERSECTIONS WITH APPROACH TAPER


* GREATER OF 100' OR APPROACH TAPER LENGTH

GENERAL NOTES

- ① SHOULDER GROOVES MAY BE OMITTED IN AREAS WITH HIGH CONCENTRATIONS OF DRIVEWAYS. WHEN DIRECTED BY THE ENGINEER.

2-LANE RURAL SHOULDER
RUMBLE STRIP, MILLING

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION



LEGEND

- SIGN ON PERMANENT SUPPORT
- TYPE III BARRICADE
- TYPE III BARRICADE WITH ATTACHED SIGN
- TYPE "A" WARNING LIGHT (FLASHING)
- WORK AREA
- FLAGS, 16" X 16" MIN. (ORANGE)

SPEED LIMIT (MPH)	"STOP AHEAD" ADVANCE WARNING DISTANCE (FT)
25	200
30	200
35	350
40	350
45	500
50	550
55	750


SEE SDD 15C2-SHEET "b" FOR GENERAL NOTES AND FOOTNOTES ① THROUGH ⑦

BARRICADES AND SIGNS FOR MAINLINE CLOSURES


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
November 2018 /S/ Andrew Heidtke
DATE WORK ZONE ENGINEER 93

FHWA



DETAIL D
ROAD CLOSURE BARRICADE DETAIL
APPROACH VIEW



DETAIL E
LANE CLOSURE BARRICADE DETAIL
APPROACH VIEW

SEE SDD 15C2 - SHEET "a" FOR LEGEND

GENERAL NOTES

THE EXACT NUMBER, LOCATION, AND SPACING OF ALL SIGNS AND BARRICADES SHALL BE ADJUSTED TO FIT FIELD CONDITIONS AS APPROVED BY THE ENGINEER.

ANY SIGNS TEMPORARY OR EXISTING, WHICH CONFLICT WITH TRAFFIC CONTROL "IN USE", SHALL BE REMOVED OR COVERED AS NEEDED AND AS APPROVED BY THE ENGINEER.

THE SPACING BETWEEN TRAFFIC CONTROL SIGNS SHOULD BE ADJUSTED TO NOT CONFLICT WITH AND SHOULD PROVIDE A DESIRABLE MINIMUM OF 200 FEET CLEARANCE TO EXISTING SIGNS THAT WILL REMAIN IN PLACE.

BARRICADES THAT MUST BE MOVED FOR A WORK OPERATION SHALL BE IMMEDIATELY RE-ESTABLISHED UPON COMPLETION OF THE OPERATION, OR FOR CONTINUING OPERATIONS, AT THE END OF EACH WORKING DAY.

SIGNS THAT WILL BE IN PLACE LESS THAN 7 CONTINUOUS DAYS AND NIGHTS MAY BE MOUNTED ON PORTABLE SUPPORTS.

ALL TYPE III BARRICADES SHALL HAVE RAILS REFLECTORIZED ON BOTH FACES. STRIPES SHALL BE PROPERLY SLOPED DOWN TOWARD THE TRAFFIC SIDE OR AS SHOWN IN THE ROAD CLOSURE BARRICADE DETAIL "D" FOR FULL ROAD CLOSURES.

TYPE "A" LOW - INTENSITY FLASHING WARNING LIGHTS SHALL BE VISIBLE ON BOTH SIDES OF THE BARRICADE.

THE R11 - 2, R11 - 3, M4 - 9, R11 - 4, AND R10 - 61 SIGNS PLACED ON THE BARRICADES SHALL COVER NO MORE THAN THE TOP RAIL. THE SIGNS SHALL NOT COVER ANY PORTION OF THE MIDDLE RAIL OR BOTTOM RAILS.

"WO" AND "MO" SIGNS ARE THE SAME AS "W" AND "M" SIGNS EXCEPT THE BACKGROUND IS ORANGE.

ALL SIGNS SHALL BE 48" X 48" UNLESS OTHERWISE NOTED BELOW:


- R11 - 2 SHALL BE 48" X 30"
- R11 - 3 SHALL, R11 - 4 AND R10 - 61 SHALL BE 60 " X 30"
- M4 - 9 SHALL BE 30" X 24"
- M3 - X SHALL BE 24" X 12" (36" X 18" IF NEEDED TO MATCH EXISTING SIGNS)
- M4 - 8 SHALL BE 24" X 12" (36" X 18" IF NEEDED TO MATCH EXISTING SIGNS)
- M1 - 4, M1 - 5A AND M1 - 6 SHALL BE 24" X 24" (36" X 36" IF NEEDED TO MATCH EXISTING SIGNS)
- MO5 - 1 AND MO6 - 1 SHALL BE 21" X 21" (30" X 30" IF NEEDED TO MATCH EXISTING SIGNS)
- D1 - X SHALL BE AS SHOWN ON SPECIFIC PROJECT SIGNING DETAIL SHEETS.
- R1 - 1 SHALL BE 36" X 36"

- 1 TWO WARNING LIGHTS SHALL BE PROVIDED ON THE CENTER BARRICADE AND A MINIMUM OF ONE WARNING LIGHT SHALL BE PROVIDED ON EACH OF THE OTHER BARRICADES WITHIN THE ROADWAY LIMITS. SPACING OF THE WARNING LIGHTS SHALL BE UNIFORM TO THE EDGE OF ROADWAY AS SHOWN (APPROX. 8 FOOT LIGHT SPACING).
- 2 THESE SIGNS AND BARRICADES ARE NOT REQUIRED IF ROAD CLOSURE BEGINS AT AN INTERSECTION.
- 3 FOR ROAD CLOSURE WITHOUT LOCAL ACCESS TO PROJECT, SEE ROAD CLOSURE BARRICADE DETAIL "D".
- 4 FOR ROAD CLOSURE WITH LOCAL ACCESS TO PROJECT, SEE ROAD CLOSURE BARRICADE DETAIL "E".
- 5 FOR BRIDGE OR CULVERT REPLACEMENTS, SUBSTITUTE "BRIDGE OUT" INSTEAD OF "ROAD CLOSED" ON R11 - 2 AND R11 - 3 SIGNS.
- 6 INSTALL DETOUR AND COMMUNITY GUIDE SIGNS AND ARROWS ONLY IF SPECIFIED IN THE CONTRACT. IF THERE ARE EXISTING ROUTE MARKER ASSEMBLIES THAT WILL REMAIN IN PLACE, ADJUST THE LOCATION OF THE DETOUR ROUTE SIGNS TO CORRESPOND WITH THE EXISTING ASSEMBLIES. MODIFY EXISTING SIGNS WHERE POSSIBLE. SEE SPECIFIC PROJECT DETOUR SIGNING DETAIL SHEETS. IF DETOUR SIGNS ARE BEING INSTALLED BY OTHERS, PLACE THE CONTRACTED TRAFFIC CONTROL SIGNS TO ALLOW FOR PLACEMENT OF ALL WARNING, DETOUR AND GUIDE SIGNS AS SHOWN.
- 7 "EAST" CARDINAL DIRECTION MARKERS AND RIGHT TURN ARROWS ARE SHOWN. USE OTHER CARDINAL DIRECTIONS AND ARROWS AS APPROPRIATE.

BARRICADES AND SIGNS FOR VARIOUS CLOSURES

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION


APPROVED
November 2018 /S/ Andrew Heidtke
DATE WORK ZONE ENGINEER 94
FHWA



SEE SPECIFIC PROJECT DETOUR
SIGNING DETAIL SHEETS AND
DETAIL A OR B ON SDD SHEET 15C02 - SHEET "a"

THIS DRAWING PROVIDES GENERAL GUIDANCE
ON TYPICAL DETOUR SIGN LAYOUT AND SPACING.
SEE PROJECT DETOUR SIGNING SHEETS FOR
SPECIFIC DETAILS FOR EACH PROJECT.

MATCH POINT



DETAIL F
DETOUR SIGNING

LEGEND

- SIGN ON PERMANENT SUPPORT
- WORK AREA
- DETOUR EAST (M4 - 8)
- DETOUR WEST (M4 - 8)
- DETOUR EAST (M1 - 4)
- DETOUR WEST (M1 - 6)
- DETOUR EAST (M1 - 5A)
- DETOUR WEST (M1 - 5A)
- DETOUR EAST (M05 - 1)
- DETOUR WEST (M06 - 1)
- DETOUR EAST (M06 - 1)

GENERAL NOTES

THE EXACT NUMBER, LOCATION AND SPACING OF ALL SIGNS SHALL BE ADJUSTED TO FIT FIELD CONDITIONS AS APPROVED BY THE ENGINEER.

IF THERE ARE EXISTING ROUTE MARKER ASSEMBLIES THAT WILL REMAIN IN PLACE, ADJUST THE LOCATION OF THE DETOUR ROUTE SIGNS TO CORRESPOND WITH THE EXISTING ASSEMBLIES. SEE SPECIFIC PROJECT DETOUR SIGNING DETAIL SHEETS. MODIFY EXISTING SIGNS WHERE POSSIBLE.

THE SPACING BETWEEN TRAFFIC CONTROL AND DETOUR SIGNS SHOULD BE ADJUSTED TO NOT CONFLICT WITH AND TO PROVIDE A DESIRABLE MINIMUM OF 200 FEET CLEARANCE TO EXISTING SIGNS THAT WILL REMAIN IN PLACE.

ANY SIGNS TEMPORARY OR EXISTING, WHICH CONFLICT WITH TRAFFIC CONTROL "IN USE" SHALL BE REMOVED OR COVERED AS NEEDED AND AS APPROVED BY THE ENGINEER.


SIGNS THAT WILL BE IN PLACE LESS THAN 7 CONTINUOUS DAYS AND NIGHTS MAY BE MOUNTED ON PORTABLE SUPPORTS.

"MO" SIGNS ARE THE SAME AS "M" SIGNS EXCEPT THE BACKGROUND IS ORANGE.

SIGN SIZES SHALL BE AS FOLLOWS:

- M3-X SHALL BE 24" X 12" (36" X 18" IF NEEDED TO MATCH EXISTING SIGNS)
- M4-8 SHALL BE 24" X 12" (36" X 18" IF NEEDED TO MATCH EXISTING SIGNS)
- M1-4, M1-5A AND M1-6 SHALL BE 24" X 24" (30" X 30" IF NEEDED TO MATCH EXISTING SIGNS)
- M05-1 AND M06-1 SHALL BE 21" X 21" (30" X 30" IF NEEDED TO MATCH EXISTING SIGNS)
- M4-9 AND M4-9R SHALL BE 30" X 24"
- M4-8a SHALL BE 24" X 18"
- G20-51 SHALL BE 60" X 24"
- W20-2A SHALL BE 48" X 48"
- D1-X SHALL BE AS SHOWN ON SPECIFIC PROJECT SIGNING DETAIL SHEETS.

- * OPTIONAL SIGNS. SEE SPECIFIC PROJECT DETOUR SIGNING DETAIL SHEETS.
- ** FOR A TOWN ROAD OR LOCAL STREET DETOURED ONTO A STATE TRUNK HIGHWAY, PLACE A ROAD NAME PLAQUE ABOVE THE M4-9 SIGN AS SPECIFIED IN THE CONTRACT.




PLACE SIGNS BEYOND INTERSECTIONS
WITH STATE OR COUNTY TRUNK
HIGHWAYS OR AT 4 MILE MAXIMUM
SPACING (4 BLOCKS IF URBAN AREA)

DETOUR SIGNING
FOR MAINLINE CLOSURES

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
November 2018 /S/ Andrew Heidtke
DATE WORK ZONE ENGINEER 95

FHWA



LEGEND

⊙ SIGN ON PERMANENT SUPPORT

GENERAL NOTES


- THE EXACT NUMBER, LOCATION AND SPACING OF ALL SIGNS SHALL BE ADJUSTED TO FIT FIELD CONDITIONS AS APPROVED BY THE ENGINEER.
- THE SPACING BETWEEN SIGNS SHOULD BE ADJUSTED TO NOT CONFLICT WITH AND TO PROVIDE A DESIRABLE MINIMUM OF 200 FEET CLEARANCE TO EXISTING SIGNS THAT WILL REMAIN IN PLACE.
- ANY SIGNS TEMPORARY OR EXISTING, WHICH CONFLICT WITH TRAFFIC CONTROL "IN USE" SHALL BE REMOVED OR COVERED AS NEEDED AND AS APPROVED BY THE ENGINEER.
- ALL SIGNS ARE 48" X 48" UNLESS OTHERWISE NOTED.
- "WO" SIGNS ARE THE SAME AS "W" SIGNS EXCEPT THE BACKGROUND IS ORANGE.
- WIDTH ON SIGN TO BE APPROXIMATELY ONE FOOT LESS THAN AVAILABLE WIDTH.
- * PLACE 500 FEET BEFORE THE W20 - 1A AND 500 FEET BEFORE ADDITIONAL SIGNS FOR ROADWAYS WITH A PRE - CONSTRUCTION SPEED LIMIT OF 45 MPH OR MORE. FOR 35-40 MPH, USE 350 FOOT TYPICAL SPACING. FOR 25-30 MPH, USE 200 FOOT TYPICAL SPACING.
- ** SIGN SHALL BE VISIBLE FROM ROADWAY.
- *** ADDITIONAL SIGNS NEEDED IF THERE IS AN ON RAMP BETWEEN SIGNS.




ADVANCED WIDTH RESTRICTION SIGNING

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION


APPROVED
November 2018 /S/ Andrew Heidtke
DATE WORK ZONE ENGINEER 96
FHWA




DETAIL 1
(NO ACCESS TO PROJECT)



DETAIL 3
(PUBLIC CROSS-TRAFFIC MAINTAINED.
CONTRACTOR, LOCAL BUSINESS AND
RESIDENT ACCESS TO PROJECT)



DETAIL 2
(PUBLIC CROSS-TRAFFIC MAINTAINED.
NO ACCESS TO PROJECT)



DETAIL 4
(CONTRACTOR, LOCAL BUSINESS AND
RESIDENT ACCESS TO PROJECT)

GENERAL NOTES

THE EXACT NUMBER, LOCATION, AND SPACING OF ALL SIGNS AND BARRICADES SHALL BE ADJUSTED TO FIT FIELD CONDITIONS AS APPROVED BY THE ENGINEER.

ANY SIGNS TEMPORARY OR EXISTING, WHICH CONFLICT WITH TRAFFIC CONTROL "IN USE" SHALL BE REMOVED OR COVERED AS NEEDED AND AS APPROVED BY THE ENGINEER.

THE SPACING BETWEEN TRAFFIC CONTROL SIGNS SHOULD BE ADJUSTED TO NOT CONFLICT WITH AND SHOULD PROVIDE A DESIRABLE MINIMUM OF 200 FEET CLEARANCE (500 FEET DESIRABLE) TO EXISTING SIGNS THAT WILL REMAIN IN PLACE.

IF A "STOP" SIGN MUST BE REMOVED FOR A WORK OPERATION, A TEMPORARY "STOP" SIGN SHALL BE PLACED PRIOR TO THE SIGN REMOVAL, OR A FLAGGER SHALL BE PROVIDED UNTIL THE SIGN IS REESTABLISHED.

BARRICADES THAT MUST BE MOVED FOR A WORK OPERATION SHALL BE IMMEDIATELY REESTABLISHED UPON COMPLETION OF THE OPERATION OR FOR CONTINUING OPERATIONS, AT THE END OF EACH WORKING DAY.

SIGNS THAT WILL BE IN PLACE LESS THAN SEVEN CONTINUOUS DAYS AND NIGHTS MAY BE MOUNTED ON PORTABLE SUPPORTS.

ALL TYPE III BARRICADES SHALL HAVE RAILS REFLECTORIZED ON BOTH FACES. STRIPES SHALL BE PROPERLY SLOPED DOWN TOWARD THE TRAFFIC SIDE OR AS SHOWN IN THE ROAD CLOSURE BARRICADE DETAIL "D" FOR FULL ROAD CLOSURES.

TYPE "A" LOW-INTENSITY FLASHING WARNING LIGHTS SHALL BE VISIBLE ON BOTH SIDES OF THE BARRICADE.

THE R11-2, R11-3, AND R11-4 SIGNS PLACED ON BARRICADES SHALL COVER NO MORE THAN THE TOP RAIL. THE SIGNS SHALL NOT COVER ANY PORTION OF THE MIDDLE OR BOTTOM RAILS.

ALL SIGNS SHALL BE 48" X 48" UNLESS OTHERWISE NOTED BELOW:
R11-2 SHALL BE 48" X 30".
R11-4 AND R11-3 SHALL BE 60" X 30".

- * OMIT THE "ROAD CLOSED 500 FT." SIGN IF THE LAST INTERSECTION IS 500 FEET OR LESS FROM THE WORK ZONE.
- ** 500' MAX. OR AT LAST INTERSECTION, WHICHEVER IS CLOSEST.

LEGEND

- SIGN ON PERMANENT SUPPORT
- TYPE III BARRICADE
- TYPE III BARRICADE WITH ATTACHED SIGN
- TYPE "A" WARNING LIGHT (FLASHING)
- WORK AREA

BARRICADES AND SIGNS FOR SIDEROAD CLOSURES







STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
July 2018 /S/ Andrew Heidtke
DATE WORK ZONE ENGINEER 97


FHWA

GENERAL NOTES


DETAILS OF INSTALLATION, MATERIALS AND WORKMANSHIP NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS AND APPLICABLE SPECIAL PROVISIONS.




PAVEMENT MARKING WORDS			
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION			
APPROVED			
June 2017	/S/ Matthew R. Rauch		
DATE	STATE SIGNING AND MARK	98	EER
FHWA			




TYPE 2




TYPE 6




TYPE 4



TYPE 3




TYPE 7



TYPE 1

GENERAL NOTES

DETAILS OF INSTALLATION, MATERIALS AND WORKMANSHIP NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS AND APPLICABLE SPECIAL PROVISIONS.




TYPE 5 LANE DROP ARROW


PAVEMENT MARKING ARROWS

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
June 2017 /S/ Matthew R. Rauch
DATE STATE SIGNING AND MAR 99
FHWA




TWO WAY TRAFFIC




ONE WAY TRAFFIC

PERMANENT PAVEMENT MARKING



TWO WAY TRAFFIC



ONE WAY TRAFFIC

TEMPORARY PAVEMENT MARKING

GENERAL NOTES

DETAILS OF CONSTRUCTION NOT SHOWN ON THIS DRAWING SHALL CONFORM TO STANDARD SPECIFICATIONS AND SPECIAL PROVISIONS.

① LOCATE THE NO PASSING ZONE W14-3 SIGN WITHIN 50 FEET OF THE "T" MARKING.

NOTE

ARROW SYMBOL (➡) SHOWS DIRECTION OF TRAVEL




LEGEND

- "T" MARKING
- POST MOUNTED SIGN

LONGITUDINAL MARKING (MAINLINE)			
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION			
APPROVED	7/2018	/S/ Matthew R. Rauch	
DATE		STATE SIGNING AND MAR	100
FHWA		INEER	

TURN LANE OPTIONS

LENGTH OF TURN BAY (L) OF 0-47' DOES NOT REQUIRE PAVEMENT MARKING ARROWS OR WORDS



*(SEE TURN LANE OPTIONS FOR PLACEMENT OF PAVEMENT MARKING ARROWS AND WORDS)


GENERAL NOTES

- ① 8" WHITE
- ② QUANTITY AND LOCATION OF TYPE 3 ARROW ARE THE SAME AS THE TYPE II ARROWS IN THE ADJACENT TURN LANE. FOR TURN LANES WITH A PHYSICAL SEPARATION, THE ARROWS AND ONLY MARKING ARE ELIMINATED.


→ DIRECTION OF TRAFFIC
L = LENGTH OF TURN BAY

PAVEMENT MARKING
(TURN LANES)

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORT 101




DRUM




42" CONE

DO NOT USE IN TAPERS
½ SPACING OF DRUMS




VERTICAL PANEL

THE STRIPES SHALL SLOPE DOWNWARD TO
THE TRAFFIC SIDE FOR CHANNELIZATION.



TYPE II BARRICADE

FOR RAILS LESS THAN 36" LONG, 4" WIDE STRIPES
MAY BE USED. ALL STRIPES SHALL SLOPE DOWNWARD
TO THE TRAFFIC SIDE FOR CHANNELIZATION.



TYPE III BARRICADE

IF SIGN MOUNTED, DO NOT COVER MORE THAN 50% OF THE TOP
TWO RAILS OR 33% OF THE TOTAL AREA OF THE THREE RAILS.

* IF USED FOR A PERMANENT APPLICATION USE RED SHEETING.


GENERAL NOTES

- ① REFLECTIVE SHEETING SHALL FOLLOW THE REQUIREMENTS IN THE APPROVED PRODUCTS LISTING FOR SIGN SHEETING.
- ② LOCATION OF WARNING LIGHTS WHEN SHOWN ON THE PLAN.

CHANNELIZING DEVICES
DRUMS, CONES, BARRICADES
AND VERTICAL PANELS

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
June 2017 /S/ Andrew Heidtke
DATE WORK ZONE ENGINEER 102
FHWA




MEDIAN ISLAND DETAIL


GENERAL NOTE

DIAGONALS ARE OPTIONAL WHEN PAINTED ISLAND IS LESS THAN 6 FEET AT WIDEST POINT.

➡ DIRECTION OF TRAVEL




APPROACH MARKINGS FOR OTHER MEDIAN TYPES




NON APPROACH MARKINGS


MEDIAN ISLAND MARKING			
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION			
APPROVED			
June 2017	/S/ Matthew Rauch		
DATE	STATE SIGNING AND MARK	103	ER
FHWA			



MEDIAN ISLAND WITH SQUARE BLUNT NOSE



MEDIAN ISLAND WITH ROUND BLUNT NOSE



MEDIAN ISLAND WITH SLOPED NOSE

TYPICAL PLACEMENT OF
PAVEMENT MARKING ON MEDIAN ISLANDS

GENERAL NOTES


WHEN CONCRETE CORRUGATED MEDIAN IS CONSTRUCTED TO SEPARATE TRAFFIC OPERATING IN THE OPPOSING DIRECTION, YELLOW PAVEMENT MARKING SHALL BE APPLIED TO THE FLAT PORTION OF THE CONCRETE CORRUGATED MEDIAN. THE ITEM OF PAVEMENT MARKING, CONCRETE CORRUGATED MEDIAN, WILL BE MEASURED IN PLACE AND ACCEPTED IN ACCORDANCE WITH THE CONTRACT AND PAID FOR AT THE CONTRACT UNIT PRICE PER SQUARE FOOT.

- ISLAND NOSE MARKING
- CURB MARKING
- CORRUGATED MEDIAN MARKING
- DIRECTION OF TRAVEL


PAVEMENT MARKINGS
(ISLANDS)

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
7/2018
DATE
/S/ Matthew R. Rauch
STATE SIGNING AND MAP ENGINEER
104
FHWA



TYPICAL STOP LINE PAVEMENT MARKING
WITH CURB AND GUTTER




TYPICAL STOP LINE PAVEMENT MARKING
FOR SIDEROADS WITH RIGHT TURN LANE


GENERAL NOTES

STOP SIGN SHALL BE PLACED A MINIMUM OF 6 FEET TO A MAXIMUM OF 50 FEET FROM THE EDGE LINE LOCATION.

- 1 18-INCH STOP LINES MAY BE DELETED OR ADDED BY THE PROJECT ENGINEER BASED ON VISIBILITY AND SIGHT LINES.
- 2 IF STOP SIGN IS LESS THAN OR EQUAL TO 40 FEET FROM THE EDGE LINE THAN NO STOP LINE IS REQUIRED.
- 3 IF STOP SIGN IS LESS THAN OR EQUAL TO 30 FEET FROM THE FLANGELINE EXTENSION THAN NO STOP LINE IS REQUIRED.
- 4 MOVE CLOSER TO EDGE OF TRAVEL LANE AS NEEDED FOR VISIBILITY AND SIGHT LINES. (NO CLOSER THAN 4 FEET).



TYPICAL STOP LINE PAVEMENT MARKING
FOR SIDEROADS WITH CROSSWALK MARKING



TYPICAL STOP LINE PAVEMENT MARKING
WITHOUT CURB AND GUTTER

STOP LINE AND CROSSWALK PAVEMENT MARKING			
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION			
APPROVED			
DATE	Sept., 2017	/S/ Matthew R. Rauch	VEER
FHWA	STATE SIGNING AND MAR 105		

GENERAL NOTES

THE EXACT NUMBER, LOCATION, AND SPACING OF ALL SIGNS AND DEVICES SHALL BE ADJUSTED TO FIT FIELD CONDITIONS AS APPROVED BY THE ENGINEER.

THE SPACING BETWEEN SIGNS SHOULD BE ADJUSTED TO NOT CONFLICT WITH AND TO PROVIDE A MINIMUM OF 200 FEET (500 FEET DESIRABLE) CLEARANCE TO EXISTING SIGNS.

THIS LANE CLOSURE IS TYPICAL FOR CLOSING RIGHT LANE - REVERSE FOR CLOSING LEFT LANE.

ALL SIGNS ARE 48" x 48" UNLESS OTHERWISE NOTED.

"WO" IS THE SAME AS "W" EXCEPT THE BACKGROUND IS ORANGE.

ANY SIGNS TEMPORARY OR EXISTING, WHICH CONFLICT WITH TRAFFIC CONTROL "IN USE" SHALL BE REMOVED OR COVERED AS NEEDED OR AS APPROVED BY THE ENGINEER.

FOR A LANE CLOSURE THAT IS IN PLACE LESS THAN 7 CONTINUOUS DAYS AND NIGHTS, THE ADVANCED WARNING SIGNS MAY BE MOUNTED ON PORTABLE SUPPORTS.

REMOVE PAVEMENT MARKINGS IF LANE CLOSURE IS TO BE IN PLACE 4 OR MORE CONTINUOUS DAYS AND NIGHTS.

IF THE HORIZONTAL ALIGNMENT IS SUCH THAT A CURVE MAY REQUIRE ADDITIONAL DELINEATION, THE DEVICE SPACING MAY BE DECREASED TO 50 FEET.

WARNING LIGHTS ARE NOT REQUIRED IF THE LANE CLOSURE IS A DAYTIME ONLY OPERATION.


ADJUSTMENTS IN BUFFER SPACE NEED TO BE INCORPORATED WHEN THE LANE CLOSURE OCCURS

NEAR AN INTERCHANGE EXIT OR ENTRANCE RAMP OR INTERSECTION. THE LANE CLOSURE MUST TAKE PLACE FAR ENOUGH IN ADVANCE OF AN EXIT OR ENTRANCE RAMP TO STILL ALLOW FOR ADEQUATE BUFFER SPACE. THE MINIMUM LENGTH OF THE BUFFER SPACE BEFORE AN EXIT RAMP SHOULD BE ONE HALF THE LENGTH OF THE TRANSITION AREA. THE ENTRANCE RAMP SHOULD BE FOLLOWED BY THE ORIGINAL BUFFER SPACE LENGTH OF 800 FEET DESIRABLE PRIOR TO ANOTHER TRAFFIC CONTROL CHANGE SUCH AS A CROSSOVER MANEUVER.

CONSIDER ROADWAY GEOMETRICS WHEN LOCATING SIGNS AND ARROW BOARD SO THE DRIVER HAS A CLEAR VIEW OF THE ARROW BOARD AND LANE CLOSURE DRUMS.

LEGEND


- TYPE III BARRICADE WITH ATTACHED SIGN
- SIGN ON PERMANENT SUPPORT
- TRAFFIC CONTROL DRUM WITH TYPE "C" STEADY BURN LIGHT
- TRAFFIC CONTROL DRUM
- TYPE "A" WARNING LIGHT (FLASHING)
- REMOVING PAVEMENT MARKING
- DIRECTION OF TRAFFIC
- WORK AREA
- FLASHING ARROW BOARD



TRAFFIC CONTROL
LANE CLOSURE

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
November 2018 /S/ Andrew Heidtke
DATE WORK ZONE ENGINEER 106
FHWA



GENERAL NOTES

THIS LANE CLOSURE DETAIL IS TYPICAL FOR CLOSING THE LEFT LANE. FOR A RIGHT LANE CLOSURE, REVERSE THE TRAFFIC CONTROL.

THIS DETAIL MAY BE USED FOR ROADWAYS WITH EITHER TWO OR THREE LANES IN EACH DIRECTION.

THE EXACT NUMBER, LOCATION, AND SPACING OF ALL SIGNS AND DEVICES SHALL BE ADJUSTED TO FIT FIELD CONDITIONS AS APPROVED BY THE ENGINEER.

THE SPACING BETWEEN TRAFFIC CONTROL SIGNS SHOULD BE ADJUSTED TO NOT CONFLICT WITH AND SHOULD PROVIDE A DESIRABLE MINIMUM OF 200 FEET CLEARANCE TO EXISTING SIGNS THAT WILL REMAIN IN PLACE.

ALL SIGNS ARE 48"x48" UNLESS OTHERWISE NOTED. IF NECESSARY DUE TO SPACE CONSTRAINTS IN URBAN AREAS, 36" X 36" SIGNS MAY BE USED IF APPROVED BY DISTRICT TRAFFIC UNIT.

"WO" SIGNS ARE THE SAME AS "W" SIGNS EXCEPT THE BACKGROUND IS ORANGE.

SIGNS THAT WILL BE IN PLACE LESS THAN 7 CONTINUOUS DAYS AND NIGHTS, OR THAT WILL BE PLACED IN A CLOSED LANE, MAY BE MOUNTED ON PORTABLE SUPPORTS.

ANY SIGNS TEMPORARY OR EXISTING, WHICH CONFLICT WITH TRAFFIC CONTROL "IN USE" SHALL BE REMOVED OR COVERED AS NEEDED AND AS APPROVED BY THE ENGINEER.

REMOVE PAVEMENT MARKINGS AND PLACE TEMPORARY PAVEMENT MARKING, REMOVABLE TAPE IF LANE CLOSURE IS TO BE IN PLACE FOR 4 OR MORE CONTINUOUS DAYS AND NIGHTS.

ON UNDIVIDED ROADWAYS, OMIT THE SIGNS SHOWN ON LEFT SIDE OF ROAD.

W20-1A, G20-1 AND G20-2A SIGNS ARE NOT REQUIRED IF THE LANE CLOSURE IS WITHIN A LARGER WORK ZONE WHERE THESE SIGNS ARE ALREADY PRESENT.

OMIT G20-1 SIGNS IF LENGTH OF WORK AREA IS 2 MILES OR LESS.

CONSIDER GEOMETRICS WHEN LOCATING SIGNS AND ARROWBOARDS SO THE APPROACHING DRIVER HAS A CLEAR VIEW OF THE ARROWBOARDS AND LANE CLOSURE DRUMS.

PLACE THE ARROWBOARD AS CLOSE AS POSSIBLE TO THE BEGINNING OF THE LANE CLOSURE TAPER, PREFERABLY ON THE SHOULDER OR TERRACE.

CHANNELIZING DEVICES PLACED ADJACENT TO WORK AREA SHALL BE PULLED BACK FROM THE TRAVEL LANE WHEN WORK IS NOT IN PROGRESS.

BARRICADES IN A CLOSED LANE THAT MUST BE MOVED FOR A WORK OPERATION SHALL BE IMMEDIATELY RE-ESTABLISHED UPON COMPLETION OF THE OPERATION OR, FOR CONTINUING OPERATIONS, AT THE END OF EACH WORKING DAY.

WARNING LIGHTS ARE NOT REQUIRED IF THE LANE CLOSURE IS A DAYTIME ONLY OPERATION.

TABLE 1
TAPER AND BUFFER SPACE
FOR 12' LANE WIDTH

S	L	BUFFER SPACE
25	125'	55'
30	180'	85'
35	245'	120'
40	320'	170'
45	540'	220'
50	600'	280'
55	660'	335'

FOR LANE WIDTH OTHER THAN 12':

L = WS AT 45 MPH OR GREATER

L = $\frac{WS^2}{60}$ AT 40 MPH OR LESS

L = TAPER LENGTH IN FEET

S = NON-CONSTRUCTION SPEED LIMIT (MPH)

W = WIDTH OF LANE CLOSURE


LEGEND

- TYPE III BARRICADE WITH ATTACHED SIGN
- SIGN ON PERMANENT SUPPORT
- TRAFFIC CONTROL DRUM WITH TYPE "C" STEADY BURN LIGHT
- TRAFFIC CONTROL DRUM
- FLASHING ARROW BOARD
- DIRECTION OF TRAFFIC
- REMOVING PAVEMENT MARKING (SEE GENERAL NOTES)
- WORK AREA

TRAFFIC CONTROL,
SINGLE LANE CLOSURE,
NON-FREEWAY/EXPRESSWAY

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
June 2016 /S/ Peter Amakobe Atepe
DATE STATEWIDE WORK ZONE SAFETY ENGINEER 107 IC
FHWA





DETAIL OF TUBULAR STEEL SIGN POST

TUBULAR STEEL POSTS

AREA OF SIGN INSTALLATION (SQ. FT.)	NUMBER OF REQUIRED TUBULAR STEEL POSTS
9 OR LESS	1
GREATER THAN 9 LESS THAN OR EQUAL TO 18	2
GREATER THAN 18 LESS THAN OR EQUAL TO 27	3

SIGNS WIDER THAN 3 FEET OR LARGER THAN 9 SQ. FT. SHALL BE MOUNTED ON MULTIPLE POSTS (SEE ABOVE TABLE).

SIGNS LARGER THAN 27 SQ.FT. SHALL NOT BE MOUNTED ON TUBULAR STEEL POSTS.




URBAN AREA


POST MOUNTING DETAIL FOR TEMPORARY TRAFFIC CONTROL FIXED MESSAGE SIGNS

WOOD POST
EMBEDMENT DEPTH


AREA OF SIGN INSTALLATION (SQ. FT.)	D (MIN)
20 OR LESS	4'
GREATER THAN 20	5'



4"x6" WOOD POST MODIFICATION



RURAL AREA




4" X 6" WOOD POST

POST SPACING REQUIREMENTS		NUMBER OF WOOD POSTS REQUIRED
L	E	
48" OR LESS AND LESS THAN 20 SQ. FT.	-	1
LESS THAN 60"	12"	2
60" TO 120"	L/5	2
GREATER THAN 120" LESS THAN 168"	12"	3
168" AND GREATER	12"	4

SEE NOTE (3)

GENERAL NOTES

- ① 6 FEET FROM THE EDGE OF PAVEMENT (EDGE LINE LOCATION) UNLESS OTHERWISE DIRECTED BY THE PROJECT ENGINEER. LATERAL OFFSET SHOULD BE ADJUSTED TO AVOID THE DITCH FLOWLINE.
- ② THE EXISTENCE OF CURB AND GUTTER DOES NOT IN ITSELF MANDATE THE VERTICAL CLEARANCE ILLUSTRATED. THAT HEIGHT IS TYPICALLY MEASURED WHERE THERE IS SIDEWALK ADJACENT TO THE ROADWAY OR PARKING IS PERMITTED. IN THE ABSENCE OF SIDEWALK, VERTICAL CLEARANCE IS MEASURED FROM THE TOP OF THE CURB, IF NO SIDEWALK AND NO PARKING. VERTICAL CLEARANCE MAY BE REDUCED TO 5 FOOT MINIMUM. OFFSET OF SIGNS IS MEASURED FROM THE CURB FLOWLINE.
- ③ FOR SIGNS REQUIRING 4 POSTS, SPACE INTERMEDIATE POSTS EVENLY.



NUTS, BOLTS AND LAGS USED FOR MOUNTING SIGNS SHALL HAVE HEXAGONAL HEADS AND SHALL BE EITHER:

- A. HOT DIP GALVANIZED IN ACCORDANCE WITH ASTM DESIGNATION: A 153, CLASS D, OR SC 3
- B. ELECTRO-GALVANIZED IN ACCORDANCE WITH ASTM DESIGNATION: B 633, TYPE III, SC 3

THREADS ON BOLTS AND NUTS SHALL BE MANUFACTURED WITH SUFFICIENT ALLOWANCE FOR THE CADMIUM PLATE OR GALVANIZED COATING TO PERMIT THE NUTS TO RUN FREELY ON THE BOLTS.

- WOOD POSTS (4" x 4" or 4" x 6")
- LAG SCREWS - 3/8" x 3"
 - MACHINE BOLTS - 5/16" x 6-1/2" OR 7" LENGTH W/ NUTS

- SQUARE STEEL POSTS (2" x 2")
- MACHINE BOLTS - 3/8" x 3-1/4" LENGTH W/ NUTS
 - RIVETS - 9/32" (6605-9-6) BULB-TITE, TRI-FOLD, ALUMINUM BODY/MANDREL O.D. FLANGE .720-.765 INCH, GRIP RANGE .042-.375 INCH


- WASHERS (ALL POSTS) -
- 1-1/4" O.D. x 3/8" I.D. x 1/16" STEEL
 - 1-1/4" O.D. x 3/8" I.D. x .080 NYLON FOR ALL TYPE H SIGNS

* TWO DIFFERENT FASTENING SYSTEMS ARE SHOWN FOR ILLUSTRATION PURPOSES. ON ANY INDIVIDUAL SIGN, EITHER ONE OR THE OTHER SYSTEM SHALL BE USED. ACTUAL NUMBER OF FASTENERS PER SIGN VARIES WITH THE SIGN AREA. FOR A SINGLE POST INSTALLATION, ALL SIGNS GREATER THAN 9 SQ. FT. REQUIRE THE USE OF 3 FASTENERS.

ATTACHMENT OF SIGNS TO POSTS	
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION	
APPROVED June 2017 DATE	/S/ Andrew Heidtke WORK ZONE EN 109
FHWA	

NOTES

- 1. All Signs Type II - Type H Reflective
- 2. Color:
Background - White
Message - Black
- 3. Message Series - C
- 4. Base Material .040" aluminum




FMS-1

7

7

Notes



Wisconsin Department of Transportation

Dedicated people creating transportation solutions through innovation and exceptional service.

<http://www.dot.wisconsin.gov>