HIGHWAY WORK PROPOSAL

Wisconsin Department of Transportation 06/2017 s.66.0901(7) Wis. Stats

Proposal Number: 011

COUNTY STATE PROJECT **FEDERAL** PROJECT DESCRIPTION **HIGHWAY** Menominee 9650-17-61 WISC 2020351 Shawano - Neopit; Wolf River Bridge B-STH 047 73-0004 Menominee 9650-17-70 WISC 2020356 Shawano - Neopit; Duquaine Rd To N STH 047 Jct Of Cth Vv

ADDENDUM REQUIRED

ATTACHED AT BACK

This proposal, submitted by the undersigned bidder to the Wisconsin Department of Transportation, is in accordance with the advertised request for proposals. The bidder is to furnish and deliver all materials, and to perform all work for the improvement of the designated project in the time specified, in accordance with the appended Proposal Requirements and Conditions.

Proposal Guaranty Required: \$100,000.00 Payable to: Wisconsin Department of Transportation	Attach Proposal Guaranty on back of this PAGE.
Bid Submittal Date: July 14, 2020 Time (Local Time): 9:00 am	Firm Name, Address, City, State, Zip Code SAMPLE
Contract Completion Time November 05, 2021	NOT FOR BIDDING PURPOSES
Assigned Disadvantaged Business Enterprise Goal 8%	This contract is exempt from federal oversight.

This certifies that the undersigned bidder, duly sworn, is an authorized representative of the firm named above; that the bidder has examined and carefully prepared the bid from the plans, Highway Work Proposal, and all addenda, and has checked the same in detail before submitting this proposal or bid; and that the bidder or agents, officer, or employees have not, either directly or indirectly, entered into any agreement, participated in any collusion, or otherwise taken any action in restraint of free competitive bidding in connection with this proposal bid.

Do not sign, notarize, or submit this Highway Work Proposal when submitting an electronic bid on the Internet.

Subscribed and sworn to before me this date ______

(Signature, Notary Public, State of Wisconsin)

(Print or Type Name, Notary Public, State Wisconsin)

(Print or Type Bidder Name)

(Date Commission Expires)

(Bidder Title)

Notary Seal

Type of Work:

Grading, Base, Milling, Asphalt Pavement, Concrete Approach Slabs, Bridge Deck Rehabilitation, Box Culvert Construction, Culvert Pipe, Storm Sewer, Curb and Gutter, Concrete Driveway, Sidewalk, Fence, Beam Guard, Signs, Pavement Markings, Street Lighting, Traffic Signals, Water Main

Notice of Award Dated

Date Guaranty Returned

PLEASE ATTACH PROPOSAL GUARANTY HERE

Effective with November 2007 Letting

PROPOSAL REQUIREMENTS AND CONDITIONS

The bidder, signing and submitting this proposal, agrees and declares as a condition thereof, to be bound by the following conditions and requirements.

If the bidder has a corporate relationship with the proposal design engineering company, the bidder declares that it did not obtain any facts, data, or other information related to this proposal from the design engineering company that was not available to all bidders.

The bidder declares that they have carefully examined the site of, and the proposal, plans, specifications and contract forms for the work contemplated, and it is assumed that the bidder has investigated and is satisfied as to the conditions to be encountered, as to the character, quality, and quantities of work to be performed and materials to be furnished, and as to the requirements of the specifications, special provisions and contract. It is mutually agreed that submission of a proposal shall be considered conclusive evidence that the bidder has made such examination.

The bidder submits herewith a proposal guaranty in proper form and amount payable to the party as designated in the advertisement inviting proposals, to be retained by and become the property of the owner of the work in the event the undersigned shall fail to execute the contract and contract bond and return the same to the office of the engineer within fourteen (14) days after having been notified in writing to do so; otherwise to be returned.

The bidder declares that they understand that the estimate of quantities in the attached schedule is approximate only and that the attached quantities may be greater or less in accordance with the specifications.

The bidder agrees to perform the said work, for and in consideration of the payment of the amount becoming due on account of work performed, according to the unit prices bid in the following schedule, and to accept such amounts in full payment of said work.

The bidder declares that all of the said work will be performed at their own proper cost and expense, that they will furnish all necessary materials, labor, tools, machinery, apparatus, and other means of construction in the manner provided in the applicable specifications and the approved plans for the work together with all standard and special designs that may be designed on such plans, and the special provisions in the contract of which this proposal will become a part, if and when accepted. The bidder further agrees that the applicable specifications and all plans and working drawings are made a part hereof, as fully and completely as if attached hereto.

The bidder, if awarded the contract, agrees to begin the work not later than ten (10) days after the date of written notification from the engineer to do so, unless otherwise stipulated in the special provisions.

The bidder declares that if they are awarded the contract, they will execute the contract agreement and begin and complete the work within the time named herein, and they will file a good and sufficient surety bond for the amount of the contract for performance and also for the full amount of the contract for payment.

The bidder, if awarded the contract, shall pay all claims as required by Section 779.14, Statutes of Wisconsin, and shall be subject to and discharge all liabilities for injuries pursuant to Chapter 102 of the Statutes of Wisconsin, and all acts amendatory thereto. They shall further be responsible for any damages to property or injury to persons occurring through their own negligence or that of their employees or agents, incident to the performance of work under this contract, pursuant to the Standard Specifications for Road and Bridge Construction applicable to this contract.

In connection with the performance of work under this contract, the contractor agrees to comply with all applicable state and federal statutes relating to non-discrimination in employment. No otherwise qualified person shall be excluded from employment or otherwise be subject to discrimination in employment in any manner on the basis of age, race, religion, color, gender, national origin or ancestry, disability, arrest or conviction record (in keeping with s.111.32), sexual orientation, marital status, membership in the military reserve, honesty testing, genetic testing, and outside use of lawful products. This provision shall include, but not be limited to the following: employment, upgrading, demotion or transfer; recruitment or recruitment advertising; layoff or termination; rates of pay or other forms of compensation, and selection for training, including apprenticeship. The contractor further agrees to ensure equal opportunity in employment to all applicants and employees and to take affirmative action to attain a representative workforce.

The contractor agrees to post notices and posters setting forth the provisions of the nondiscrimination clause, in a conspicuous and easily accessible place, available for employees and applicants for employment.

If a state public official (section 19.42, Stats.) or an organization in which a state public official holds at least a 10% interest is a party to this agreement, this contract is voidable by the state unless appropriate disclosure is made to the State of Wisconsin Ethics Board.

Effective with August 2015 Letting

BID PREPARATION

Preparing the Proposal Schedule of Items

A General

- (1) Obtain bidding proposals as specified in section 102 of the standard specifications prior to 11:45 AM of the last business day preceding the letting. Submit bidding proposals using one of the following methods:
 - 1. Electronic bid on theinternet.
 - 2. Electronic bid on a printout with accompanying diskette or CD ROM.
 - 3. Paper bid under a waiver of the electronic submittal requirements.
- (2) Bids submitted on a printout with accompanying diskette or CD ROM or paper bids submitted under a waiver of the electronic submittal requirements govern over bids submitted on the internet.
- (3) The department will provide bidding information through the department's web site at: https://wisconsindot.gov/Pages/doing-bus/contractors/hcci/bid-let.aspx

The contractor is responsible for reviewing this web site for general notices as well as information regarding proposals in each letting. The department will also post special notices of all addenda to each proposal through this web site no later than 4:00 PM local time on the Thursday before the letting. Check the department's web site after 5:00 PM local time on the Thursday before the letting to ensure all addenda have been accounted for before preparing the bid. When bidding using methods 1 and 2 above, check the Bid ExpressTM on-line bidding exchange at http://www.bidx.com/ after 5:00 PM local time on the Thursday before the letting to ensure that the latest schedule of items Expedite file (*.ebs or *.00x) is used to submit the final bid.

(4) Interested parties can subscribe to the Bid ExpressTM on-line bidding exchange by following the instructions provided at the www.bidx.com web site or by contacting:

Info Tech Inc.
5700 SW 34th Street, Suite 1235
Gainesville, FL 32608-5371
email: mailto:customer.support@bidx.com

- (5) The department will address equipment and process failures, if the bidder can demonstrate that those failures were beyond their control.
- (6) Contractors are responsible for checking on the issuance of addenda and for obtaining the addenda. Notice of issuance of addenda is posted on the department's web site at: https://wisconsindot.gov/Pages/doing-bus/contractors/hcci/bid-let.aspx

or by calling the department at (608) 266-1631. Addenda can ONLY be obtained from the departments web site listed above or by picking up the addenda at the Bureau of Highway Construction, 4th floor, 4822 Madison Yards Way, Madison, WI, during regular business hours

(7) Addenda posted after 5:00 PM on the Thursday before the letting will be emailed to the eligible bidders for that proposal. All eligible bidders shall acknowledge receipt of the addenda whether they are bidding on the proposal or not. Not acknowledging receipt may jeopardize the awarding of the project.

B Submitting Electronic Bids

B.1 On the Internet

- (1) Do the following before submitting the bid:
 - 1. Have a properly executed annual bid bond on file with the department.

- 2. Have a digital ID on file with and enabled by Info Tech Inc. Using this digital ID will constitute the bidder's signature for proper execution of the bidding proposal.
- (2) In lieu of preparing, delivering, and submitting the proposal as specified in 102.6 and 102.9 of the standard specifications, submit the proposal on the internet as follows:
 - 1. Download the latest schedule of items reflecting all addenda from the Bid Express TM web site.
 - 2. Use Expedite TM software to enter a unit price for every item in the schedule of items.
 - 3. Submit the bid according to the requirements of ExpediteTM software and the Bid ExpressTM web site. Do not submit a bid on a printout with accompanying diskette or CD ROM or a paper bid. If the bidder does submit a bid on a printout with accompanying diskette or a paper bid in addition to the internet submittal, the department will disregard the internet bid.
 - 4. Submit the bid before the hour and date the Notice to Contractors designates.
 - 5. Do not sign, notarize, and return the bidding proposal described in 102.2 of the standard specifications.
- (3) The department will not consider the bid accepted until the hour and date the Notice to Contractors designates.

B.2 On a Printout with Accompanying Diskette or CD ROM

(1) Download the latest schedule of items from the Wisconsin pages of the Bid ExpressTM web site reflecting the latest addenda posted on the department's web site at:

https://wisconsindot.gov/Pages/doing-bus/contractors/hcci/bid-let.aspx

Use Expedite TM software to prepare and print the schedule of items. Provide a valid amount for all price fields. Follow instructions and review the help screens provided on the Bid Express Web site to assure that the schedule of items is prepared properly.

(2) Staple an 8 1/2 by 11 inch printout of the ExpediteTM generated schedule of items to the other proposal documents submitted to the department as a part of the bidder's sealed bid. As a separate submittal, not in the sealed bid envelop but due at the same time and place as the sealed bid, also provide the ExpediteTM generated schedule of items on a 3 1/2 inch computer diskette or CD ROM. Label each diskette or CD ROMwith the bidder's name, the 4 character department-assigned bidder identification code from the top of the bidding proposal, and a list of the proposal numbers included on that diskette or CD ROM as indicated in the following example:

Bidder Name

BN00

Proposals: 1, 12, 14, & 22

- (3) If bidding on more than one proposal in the letting, the bidder may include all proposals for that letting on one diskette or CD ROM. Include only submitted proposals with no incomplete or other files on the diskette or CD ROM.
- (4) The bidder-submitted printout of the ExpediteTM generated schedule of items is the governing contract document and must conform to the requirements of section 102 of the standard specifications. If a printout needs to be altered, cross out the printed information with ink or typewriter and enter the new information and initial it in ink. If there is a discrepancy between the printout and the diskette or CD ROM, the department will analyze the bid using the printout information.
- (5) In addition to the reasons specified in section 102 of the standard specifications, proposals are irregular and the department may reject them for one or more of the following:
 - 1. The check code printed on the bottom of the printout of the ExpediteTM generated schedule of items is not the same on each page.
 - 2. The check code printed on the printout of the ExpediteTM generated schedule of items is not the same as the check code for that proposal provided on the diskette or CD ROM.

3. The diskette or CD ROM is not submitted at the time and place the department designates.

C Waiver of Electronic Submittal

- (1) The bidder may request a waiver of the electronic submittal requirements. Submit a written request for a waiver in lieu of bids submitted on the internet or on a printout with accompanying diskette or CD ROM. Use the waiver that was included with the paper bid document sent to the bidder or type up a waiver on the bidder's letterhead. The department will waive the electronic submittal requirements for a bidding entity (individual, partnership, joint venture, corporation, or limited liability company) for up to 4 individual proposals in a calendar year. The department may allow additional waivers for equipment malfunctions.
- (2) Submit a schedule of items on paper conforming to section 102 of the standard specifications. The department charges the bidder a \$75 administrative fee per proposal, payable at the time and place the department designates for receiving bids, to cover the costs of data entry. The department will accept a check or money order payable to: "Wisconsin, Dept. of Transportation."
- (3) In addition to the reasons specified in section 102 of the standard specifications, proposals are irregular and the department may reject them for one or more of the following:
 - 1. The bidder fails to provide the written request for waiver of the electronic submittal requirements.
 - 2. The bidder fails to pay the \$75 administrative fee before the time the department designates for the opening of bids unless the bidder requests on the waiver that they be billed for the \$75.
 - 3. The bidder exceeds 4 waivers of electronic submittal requirements within a calendar year.
- (4) In addition to the reasons specified in section 102 of the standard specifications, the department may refuse to issue bidding proposals for future contracts to a bidding entity that owes the department administrative fees for a waiver of electronic submittal requirements.

DT1303 1/2006

Proposal Number	Project Number		Letting Date
Name of Principal			
Name of Surety			Organized

We, the above-named Principal and the above-named Surety, are held and firmly bound unto the State of Wisconsin in the sum equal to the Proposal Guaranty for the total bid submitted for the payment to be made; we jointly and severally bind ourselves, our heirs, executors, administrators, successors and assigns. The condition of this obligation is that the Principal has submitted a bid proposal to the State of Wisconsin acting through the Department of Transportation for the improvement designated by the Proposal Number and Letting Date indicated above.

If the Principal is awarded the contract and, within the time and manner required by law after the prescribed forms are presented for signature, enters into a written contract in accordance with the bid, and files the bond with the Department of Transportation to guarantee faithful performance and payment for labor and materials, as required by law, or if the Department of Transportation shall reject all bids for the work described, then this obligation shall be null and void; otherwise, it shall be and remain in full force and effect. In the event of failure of the Principal to enter into the contract or give the specified bond, the Principal shall pay to the Department of Transportation within 10 business days of demand a total equal to the Proposal Guaranty as liquidated damages; the liability of the Surety continues for the full amount of the obligation as stated until the obligation is paid in full.

The Surety, for value received, agrees that the obligations of it and its bond shall not be impaired or affected by any extension of time within which the Department of Transportation may accept the bid; and the Surety does waive notice of any such extension.

IN WITNESS, the Principal and Surety have agreed and have signed by their proper officers and have caused their corporate seals to be affixed this date: **(DATE MUST BE ENTERED)**

PRINCIPAL

(Company Name) (Affix Corporate	Seal)		
(Signature and Title)	_		
(Company Name)	_		
(Signature and Title)			
(Company Name)			
(Signature and Title)		(Name of Surety) (Affix Seal)	
(Company Name)		(Signature of Attorney-in-Fact)	
(Signature and Title)			
NOTARY FOR F	PRINCIPAL	NOTARY FO	OR SURETY
(Date	1	(Da	te)
State of Wisconsin)	State of Wisconsin)
() ss. County))ss. _County)
On the above date, this instrument was named person(s).	acknowledged before me by the	On the above date, this instrument w named person(s).	as acknowledged before me by the
(Signature, Notary Public,	State of Wisconsin)	(Signature, Notary Publ	ic, State of Wisconsin)
(Print or Type Name, Notary P	ublic, State of Wisconsin)	(Print or Type Name, Notary	Public, State of Wisconsin)
(Date Commission	on Expires)	(Date Commis	sion Expires)

Notary Seal Notary Seal

IMPORTANT: A certified copy of Power of Attorney of the signatory agent must be attached to the bid bond.

CERTIFICATE OF ANNUAL BID BOND

DT1305 8/2003

Wisconsin Department of Transportation

(Date)

Time Period Valid (From/To)
Name of Surety	
Name of Contracto	r
Certificate Holder	Wisconsin Department of Transportation
	y that an annual bid bond issued by the above-named Surety is currently on file with the eartment of Transportation.
	is issued as a matter of information and conveys no rights upon the certificate holder mend, extend or alter the coverage of the annual bid bond.
Cancellation:	Should the above policy be cancelled before the expiration date, the issuing surety will give thirty (30) days written notice to the certificate holder indicated above.

(Signature of Authorized Contractor Representative)

March 2010

LIST OF SUBCONTRACTORS

Section 66.0901(7), Wisconsin Statutes, provides that as a part of the proposal, the bidder also shall submit a list of the subcontractors the bidder proposes to contract with and the class of work to be performed by each. In order to qualify for inclusion in the bidder's list a subcontractor shall first submit a bid in writing, to the general contractor at least 48 hours prior to the time of the bid closing. The list may not be added to or altered without the written consent of the municipality. A proposal of a bidder is not invalid if any subcontractor and the class of work to be performed by the subcontractor has been omitted from a proposal; the omission shall be considered inadvertent or the bidder will perform the work personally.

No subcontract, whether listed herein or later proposed, may be entered into without the written consent of the Engineer as provided in Subsection 108.1 of the Standard Specifications.

Name of Subcontractor	Class of Work	Estimated Value	
			_
			_
			_

DECEMBER 2000

CERTIFICATION REGARDING DEBARMENT, SUSPENSION, AND OTHER RESPONSIBILITY MATTERS - PRIMARY COVERED TRANSACTIONS

Instructions for Certification

- 1. By signing and submitting this proposal, the prospective contractor is providing the certification set out below.
- 2. The inability of a person to provide the certification required below will not necessarily result in denial of participation in this covered transaction. The prospective contractor shall submit an explanation of why it cannot provide the certification set out below. The certification or explanation will be considered in connection with the department or agency's determination whether to enter into this transaction. However, failure of the prospective contractor to furnish a certification or an explanation shall disqualify such person from participation in this transaction.
- 3. The certification in this clause is a material representation of fact upon which reliance was placed when the department determined to enter into this transaction. If it is later determined that the contractor knowingly rendered an erroneous certification in addition to other remedies available to the Federal Government the department may terminate this transaction for cause or default.
- 4. The prospective contractor shall provide immediate written notice to the department to whom this proposal is submitted if at any time the prospective contractor learns that its certification was erroneous when submitted or has become erroneous by reason of changed circumstances.
- 5. The terms "covered transaction," "debarred," "suspended," "ineligible," "lower tier covered transaction," "participant," "person," "primary covered transaction," "principal," "proposal," and "voluntarily excluded," as used in this clause, have the meanings set out in the Definitions and Coverage sections of the rules implementing Executive Order 12549. You may contact the department to which this proposal is being submitted for assistance in obtaining a copy of those regulations.
- 6. The prospective contractor agrees by submitting this proposal that, should this contract be entered into, it shall not knowingly enter into any lower tier covered transaction with a person who is debarred, suspended, declared ineligible, or voluntarily excluded from participation in this covered transaction, unless authorized by the department entering into this transaction.
- 7. The prospective contractor further agrees by submitting this proposal that it will include the clause titled "Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion-Lower Tier Covered Transaction," which is included as an addendum to PR-1273 "Required Contract Provisions Federal Aid Construction Contracts," without

modification, in all lower tier covered transactions and in all solicitations for lower tier covered transactions.

- 8. The contractor may rely upon a certification of a prospective subcontractor/materials supplier that it is not debarred, suspended, ineligible, or voluntarily excluded from the covered transaction, unless it knows that the certification is erroneous. A contractor may decide the method and frequency by which it determines the eligibility of its principals. Each contractor may, but is not required to, check the Disapproval List (telephone # 608/266/1631).
- 9. Nothing contained in the foregoing shall be construed to require establishment of a system of records in order to render in good faith the certification required by this clause. The knowledge and information of a contractor is not required to exceed that which is normally possessed by a prudent person in the ordinary course of business dealings.
- 10. Except for transactions authorized under paragraph 6 of these instructions, if a contractor in a covered transaction knowingly enters into a lower tier covered transaction with a person who is suspended, debarred, ineligible or voluntarily excluded from participation in this transaction, in addition to other remedies available to the Federal Government, the department may terminate this transaction for cause or default.

Certification Regarding Debarment, Suspension, and Other Responsibility Matters - Primary Covered Transactions

- (1) The prospective contractor certifies to the best of its knowledge and belief, that it and its principals:
 - (a) Are not presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from covered transactions by any Federal department or agency;
 - (b) Have not within a three-year period preceding this proposal been convicted of or had a civil judgment rendered against them for commission of fraud or a criminal offense in connection with obtaining, attempting to obtain, or performing a public (Federal, State or local) transaction or contract under a public transaction; violation of Federal or State antitrust statutes or commission of embezzlement, theft, forgery, bribery, falsification or destruction of records, making false statements or receiving stolen property;
 - (c) Are not presently indicted for or otherwise criminally or civilly charged by a governmental entity (Federal, State or local) with commission of any of the offense enumerated in paragraph (1)(b) of this certification; and
 - (d) Have not within a three-year period preceding this proposal had one or more public transactions (Federal, State or local) terminated for cause or default.
- (2) Where the prospective contractor is unable to certify to any of the statements in this certification, such prospective contractor shall attach an explanation to this proposal.

Special Provisions

Table of Contents

	Article	Description	Page #
1.	General		3
2.	Scope of Work		3
3.	Prosecution and Progress		3
4.	Traffic		6
5.	Holiday Work Restrictions		8
6.	Utilities		8
7.	Municipality Acceptance of Sanitary Sev	ver and Water Main Construction	10
8.	Information to Bidders, U.S. Army Corps	of Engineers Section 404 Permit	10
9.	Information to Bidders, WPDES Genera	Construction Storm Water Discharge Permit	10
10.	Archaeological Sites		10
11.	Environmental Protection, Aquatic Exoti	c Species Control.	11
12.	Environmental Protection – Dewatering.		12
13.	Erosion Control Structures		13
14.	Construction Over or Adjacent to Naviga	able Waters	13
15.	Health and Safety Requirements for Wo	rkers Remediating Petroleum Contamination	13
16.	Notice to Contractor – Hazardous Mater	ials Contamination	14
17.	Notice to Contractor, Notification of Den	nolition and/or Renovation No Asbestos Found	15
18.	Native American Hiring		16
19.	MITW Permits.		17
20.	Coordination with Businesses and Resid	lents	17
21.		With Minimal Debris Station Station 154+20, Item	17
22.	Minimal Debris Removal for Full Depth I	Deck Repair and Concrete Surface Repair	18
23.	Excavation, Hauling, and Disposal of Pe	troleum Contaminated Soil, Item 205.0501.S	18
24.	Pigmented Surface Sealer		20
25.	Non-Shrink Grout, Item 502.0120.S		20
26.	Protective Surface Treatment Reseal, Ite	em 502.3215.S	21
27.	Precast Concrete Wingwalls C-73-0004	Item 504.1000.S.01	22
28.	Precast Concrete Box Culvert, 6 FT x 3	FT, Item 504.2000.S.01	22
29.	Cleaning Parapets, Item 509.9050.S		23
30.	Adjusting Manhole Covers		23
31.	Cover Plates Temporary, Item 611.8120).S	24
32.	Insulation Board Polystyrene, 2-Inch, Ite	m 612.0902.S.01	24
33.	Fence Chain Link Salvage 5-ft		25
34.			
35.	Field Office		25

36.	Electrical Service Meter Breaker Pedestal STH 47 & Warrington Rd, Item 656.0200.01; Electrical Service Meter Breaker Pedestal STH 47 & Tribal Office Loop, Item 656.0200.02; Electrical Service Meter Breaker Pedestal STH 47 & Lyons Rd, Item 656.0200.03; Electrical Service Meter Breaker Pedestal STH 47 & STH 55, Item 656.0200.04; Electrical Service Meter Breaker Pedestal STH 47 & Wolf River Dr, Item 656.0200.05	26
37.	Pedestrian Push Buttons, Item 658.0500.	26
38.	Luminaires Utility LED-B, Item 659.1120.	26
39.	Salvage Existing Light Pole Assembly, Item SPV.0060.01.	26
40.	Light Pole Type 5 Special, Item SPV.0060.02.	27
41.	Lighting Control Cabinet 120/240 30-Inch Special, Item SPV.0060.03.	28
42.	Lane Shift, Item SPV.0060.04	28
43.	Sanitary Chimney Seals, Item SPV.0060.05.	29
44.	Removing Water Main Valve & Valve Box, Item SPV.0060.06.	29
45.	Cap Water Main to Remain in Service, Item SPV.0060.07.	30
46.	Abandoning Water Main Valve Box, Item SPV.0060.08.	30
47.	Salvage Hydrant, Item SPV.0060.09.	31
48.	Adjusting Water Main Valve Box, Item SPV.0060.10.	31
49.	Adjusting Hydrant, Item SPV.0060.11.	31
50.	Water Main Gate Valve & Box 6-Inch, Item SPV.00060.12.	32
51.	Tracer Wire Access Box, Item SPV.0060.13.	33
52.	Water Main Coupling 6-Inch, Item SPV.0060.14; Water Main Bend 45-Degree 6-Inch, Item SPV.0060.15.	33
53.	Water Main Tapping Sleeve 6x6-Inch, Item SPV.0060.16.	34
54.	Steel Plate Beam Guard Connection, Item SPV.0060.17	34
55.	Concrete Curb and Gutter 24-Inch Type D, Item SPV.0090.01	35
56.	Water Main 6-Inch, Item SPV.0090.02.	35
57.	Construction Staking Sidewalk, Item SPV.0090.03.	39
58.	Rectangular Rapid Flashing Beacon System STH 47 & Warrington Road, Item SPV.0105.01	40
59.	Temporary Stream Diversion Pipes, Keshena Lake Outlet, Item SPV.0105.02	42
60.	Preparing Topsoil for Lawn Type Turf, Item SPV.0180.01.	43

9650-17-61, 9650-17-70 2 of 44

STSP'S Revised November 21, 2019 SPECIAL PROVISIONS

1. General.

Perform the work under this construction contract for Project 9650-17-61, Shawano – Neopit, Wolf River Bridge B-73-0004 and Project 9650-17-70, Shawano – Neopit, Duquaine Road to N Jct County VV, STH 47 in Menominee County, Wisconsin as the plans show and execute the work as specified in the State of Wisconsin, Department of Transportation, Standard Specifications for Highway and Structure Construction, 2020 Edition, as published by the department, and these special provisions.

If all or a portion of the plans and special provisions are developed in the SI metric system and the schedule of prices is developed in the US standard measure system, the department will pay for the work as bid in the US standard system.

100-005 (20191121)

2. Scope of Work.

The work under this contract shall consist of grading, base aggregate dense, HMA pavement, concrete sidewalk, concrete curb and gutter, storm sewer, water main, pavement marking, signing, lighting, landscaping, structure rehabilitation B-73-4, remove Structure C-73-2, construct C-73-4, and all incidental items necessary to complete the work as shown on the plans and included in the proposal and contract. 104-005 (20090901)

3. Prosecution and Progress.

Begin work within ten calendar days after the engineer issues a written notice to do so.

Provide the start date to the engineer in writing within a month after executing the contract but at least 14 calendar days before the preconstruction conference. Upon approval, the engineer will issue the notice to proceed within ten calendar days before the approved start date.

To revise the start date, submit a written request to the engineer at least 2 weeks before the intended start date. The engineer will approve or deny that request based on the conditions cited in the request and its effect on the department's scheduled resources.

Staging

Stage 1A

Construct the temporary diversion pipes under the northbound lane near the STH 47 and CTH VV (south) intersection.

Stage 1B

Construct the temporary diversion pipes and new box culvert under the southbound lane near the STH 47 and CTH VV (south) intersection. After completion, build southbound STH 47 lane and curb and gutter in this area.

Stage 1C

Construct the new box culvert under the northbound lane near the STH 47 & CTH VV (south) intersection. After completion, build northbound STH 47 lane and curb & gutter in this area and CTH VV (south) curb and gutter and pavement.

Stage 2

Stage 2 may be completed concurrent with Stage 3 and Stage 4.

Stage 2A

Construct beam guard for southbound STH 47 between STH 55 and CTH VV (north). This work includes concrete overlay and railing repair of bridge structure.

9650-17-61, 9650-17-70 3 of 44

Stage 2B

Construct beam guard for northbound STH 47 between STH 55 and CTH VV (north). This work includes concrete overlay and railing repair of bridge structure.

Stage 3A

Install cross pipe at Station 139+66. Temporary gravel widening will be required to construct this culvert.

Stage 3B

Construct the southbound lane of STH 47 from Dodge Road to Station 151+75 and the intersections of Dodge Road, Morrin Street, Brooks Lane, Tribal Office Loop Road (south), and Tribal Office Loop Road (north). Construct main entrance to Menominee Indian High School at Station 102+80.

Stage 4

Construct the northbound lane of STH 47 from Dodge Road to Station 151+75 and the intersections of Warrington Road, Chief Little Wave Road, Chief Carron Road, and Our Children's Road.

Stage 5A

Install cross pipes at Station 175+75, Station 189+65 and Station 200+35. Culverts at Station 175+75 and Station 189+65 may not be constructed concurrently. Temporary widening will be required to construct these culverts.

Stage 5B

Construct the northbound lane of STH 47 from 155+50 to CTH VV (north) and the intersections of Blacksmith Road, Rabbit Ridge Road, STH 55, and Oshkosh Road. Access will be maintained to CTH VV (south) and STH 55 at all times. Blacksmith Road, Rabbit Ridge Road, and Oshkosh Road will be closed during this stage.

Stage 6

Construct the southbound lane of STH 47 from 155+50 to CTH VV (north) and the intersections of Fairgrounds Road, Lyons Road (south), Lyons Road (north), Wolf River Drive, and CTH VV (north).

Interim Completion

Complete construction operations on STH 47 to the stage necessary to reopen it to through traffic prior to 12:01 AM November 16, 2020. Do not reopen until completing the following work: All work in Stages 1A through 1C.

If the contractor fails to complete the work necessary to reopen STH 47 to through traffic prior to 12:01 AM November 16, 2020, the department will assess the contractor \$1875 in interim liquidated damages for each calendar day that the roadway remains closed after 12:01 AM, November 16, 2020. An entire calendar day will be charged for any period of time within a calendar day that the road remains closed beyond 12:01 AM.

Winter Shutdown

Winter shutdown will commence with the completion of Stage 1C in the Fall of 2020. Do not resume work until April 1, 2021 unless approved by the engineer. Provide a start date in writing at least 14 days prior to the planned recommencement of work in 2021. Upon approval the engineer will issue the notice to proceed within 10 days of the approved start date.

Fish Spawning

There shall be no instream disturbance of Wolf River as a result of construction activity under or for this contract, from March 1 to June 15 both dates inclusive, and from November 1 to November 30 both dates inclusive, in order to avoid adverse impacts upon the spawning of Lake Sturgeon.

Any change to this limitation will require submitting a written request by the contractor to the engineer, subsequent review and concurrence by the Department of Natural Resources in the request, and final approval by the engineer. The approval will include all conditions to the request as mutually agreed upon by WisDOT, DNR, and MITW Environmental Services Department.

9650-17-61, 9650-17-70 4 of 44

Migratory Birds

Swallow and other migratory birds' nests have been observed on or under the existing bridge. All active nests (when eggs or young are present) of migratory birds are protected under the federal Migratory Bird Treaty Act.

The nesting season for swallows and other birds is usually between May 1 and August 30. Either prevent active nests from becoming established or apply for a depredation permit from the US Fish and Wildlife Service for work that may disturb or destroy active nests. The need for a permit may be avoided by removing the existing bridge structure prior to nest occupation by birds or clearing nests from all structures before the nests become active in early spring. As a last resort, prevent birds from nesting by installing a suitable netting device on the remaining structure prior to nesting activity. Include the cost for preventing nesting in the cost of Removing Old Structure Over Waterway with Minimal Debris.

Bald Eagles

Bald eagles are known to nest and live along the Wolf River corridor. All cranes or other objects which could potentially be utilized for nesting platforms must be lowered when construction activities are not occurring.

Wood Turtles

Wood Turtles have been documented in the area. Silt fence with small animal exclusionary turn-arounds shall be installed prior to May 1 to discourage turtles from entering the work area. All work shall stop if turtles are encountered during construction operations. Turtles shall be hand removed from the construction area and placed in a safe area outside the construction zone in the direction which the turtle was traveling.

Inspect fencing at least twice weekly on non-consecutive days and after any significant rain event.

Mussels

A Natural Heritage Inventory revealed records for two state threatened or endangered mussel species. This project has been approved with the assumption that all work will occur on the bridge deck and erosion control and stormwater best management practices will be installed to capture all debris. If the bridge deck must be removed, the project must be stopped until the WDNR, WisDOT REC, and MITW Environmental Services Department can conduct a habitat suitability analysis. If necessary, mussels shall be relocated to an appropriate area upstream prior to re-initiating construction activities.

Northern Long-eared Bat (Myotis septentrionalis)

Northern Long-eared Bats (NLEB) have the potential to inhabit the project limits because they roost in trees. Roosts may not have been observed on this project, but conditions to support the species exist. The species and all active roosts are protected by the Federal Endangered Species Act. If an individual bat or active roost is encountered during construction operations, stop work and notify the engineer and the WisDOT Regional Environmental Coordinator (REC).

In accordance to the final 4(d) rule issued for the NLEB, the department has determined that the proposed activity may affect, but will not result in prohibited take of the NLEB. The activity involves tree removal but will not occur within 0.25 miles of a known hibernacula, nor will the activity remove a known maternity roost tree or any other tree within 150 feet of a known maternity roost tree.

If additional trees need to be removed, no Clearing shall occur without prior approval from the engineer, following coordination with the WisDOT REC. Additional tree removal beyond the area originally specified will require consultation with the United States Fish and Wildlife Service (USFWS) and may require a bat presence/absence survey. Notify the engineer if additional Clearing cannot be avoided to begin coordination with the WisDOT REC. The WisDOT REC will initiate consultation with the USFWS and determine if a survey is necessary.

9650-17-61, 9650-17-70 5 of 44

Submit a schedule and description of Clearing operations with the ECIP 14 days prior to any Clearing operations. The department will determine, based on schedule and scope of work, what additional erosion control measures shall be implemented prior to the start of Clearing operations, and list those additional measures in the ECIP.

4(f) and 6(f) Properties

The following properties have protection under 4(f) and/or 6(f): Menominee Indian High School, Keshena Primary School, Menominee Nation Early Childhood, and Menominee Indians Veterans Memorial Park. Restore all disturbed areas. Excavation and temporary easements along the Menominee Indians Veterans Memorial Park should not infringe on the tree driplines along STH 47.

4. Traffic.

Construct STH 47 in six stages. Maintain STH 47 with 11-foot minimum lane width at all times except as noted hereinafter.

Maintain access to local residences and business except when construction operations in the area require denial of access. If access will be denied, provide property owners three business days' notice prior to access restriction.

Maintain access for pedestrians and bicycles at all times during construction.

Stage 1A

Restrict traffic to one 11-foot travel lane on southbound STH 47 in the area near the STH 47 & CTH VV (south) intersection using trailer mounted traffic signals. Video actuation will be used for both directions of STH 47. CTH VV (south) will be closed to traffic during this stage and traffic will be detoured on Go Around Road.

Stage 1B

Restrict traffic to one 11-foot travel lane on northbound STH 47 in the area near the STH 47 & CTH VV (south) intersection using trailer mounted traffic signals. Video actuation will be used for both directions of STH 47. CTH VV (south) will be closed to traffic during this stage and traffic will be detoured on Go Around Road.

Stage 1C:

Restrict traffic to one 11-foot travel lane on southbound STH 47 in the area near the STH 47 & CTH VV (south) intersection using trailer mounted traffic signals. Video actuation will be used for both directions of STH 47. CTH VV (south) will be closed to traffic during this stage and traffic will be detoured on Go Around Road.

Stage 2A

Restrict traffic to one 12-foot travel lane on northbound STH 47 between STH 55 and CTH VV (north) using trailer mounted traffic signals with video actuation.

Stage 2B

Restrict traffic to one 12-foot travel lane on southbound STH 47 between STH 55 and CTH VV (north) using trailer mounted traffic signals with video actuation.

Stage 3A

Once temporary widening and cross pipe under the north bound lane of STH 47 at Station 139+66 are installed, shift traffic to temporary widening so the cross pipe under southbound lane of STH 47 can be installed. Open both northbound and southbound STH 47 lanes to traffic at end of each day with minimum driving surface of dense graded base.

All traffic will remain on STH 47 and be shifted to temporary widening at cross pipe location. Maintain STH 47 traffic on gravel during the work week and unmilled asphalt during the weekend. During construction activities, restrict traffic to one lane along STH 47 using flagging.

9650-17-61, 9650-17-70 6 of 44

Stage 3B

Maintain access to Dodge Road, Tribal Office Loop Road (south), and Tribal Office Loop Road (north) at all times. Morrin Street and Brooks Lane will need to be closed; however, they will not be allowed to be closed at the same time. Construct main entrance to Menominee Indian High School at Station 102+80 LT half at a time to allow access for bus/vehicle traffic. All right-turns from the east side streets and all left-turns from the west side streets will be prohibited during construction.

Southbound traffic will remain on STH 47. Maintain southbound STH 47 traffic on gravel during the work week and unmilled asphalt during the weekend. Detour northbound local traffic from Duquaine Rd to CTH VV (south) on Go Around Road. Detour truck traffic along STH 29 and STH 45. Use temporary lane closures to remove pavement markings and apply temporary pavement markings when approved by the engineer. Utilize flaggers for southbound traffic short term lane closures for moving and delivery of construction equipment and materials.

Stage 4

Side street closures will occur throughout Stage 4. Close Warrington Road only when Chief Carron Road is open. Close Chief Little Wave Road only when Chief Carron Road is open and close Chief Carron Road only when Chief Little Wave Road and Warrington Road are open. Close Our Children's Road only when Chief Carron Road is open. All right-turns from the east side streets and all left-turns from the west side streets will be prohibited during construction.

Southbound traffic will remain on STH 47. Detour northbound local traffic from Duquaine Rd to CTH VV (south) on Go Around Road. Detour truck traffic along STH 29 and STH 45. Use temporary lane closures to remove pavement markings and apply temporary pavement markings when approved by the engineer. Utilize flaggers for southbound traffic short term lane closures for moving and delivery of construction equipment and materials. Remove the STH 47 northbound detours after Stage 4 completion.

Stage 5A

Once temporary widening and cross pipes are installed at Station 175+75 and Station 189+65, shift traffic to temporary widening and install the cross pipes under the southbound lane of STH 47. Once southbound widening is installed at Station 200+35, shift traffic to temporary widening and install new culvert under northbound lane and install temporary widening along northbound lane. Shift traffic to temporary widening along northbound lane and install cross pipe under southbound lanes. Open both northbound and southbound STH 47 lanes to traffic at end of each day with minimum driving surface of dense graded base.

All traffic will remain on STH 47. Maintain STH 47 traffic on gravel during the weekdays and asphalt during the weekend. During construction activities, restrict traffic to one lane along STH 47 using trailer mounted traffic signals with video actuation. Temporarily shift traffic onto shoulder in order to complete construction activities

Stage 5B

All traffic will remain on STH 47. Maintain STH 47 traffic on gravel during the work week and unmilled asphalt during the weekend. During construction activities, restrict traffic to one lane along STH 47 using flagging.

Stage 6

Access will be maintained to CTH VV (north) at all times. Closures of side streets will occur throughout Stage 6. Close Lyons Road (south) only when Lyons Road (north) is open and close Lyons Road (north) only when Lyons Road (south) is open. Close Courthouse Lane only when Wolf River Drive is open and close Wolf River Drive only when Courthouse Lane is open.

All traffic will remain on STH 47. Maintain STH 47 traffic on gravel during the work week and unmilled asphalt during the weekend. During construction activities, restrict traffic to one lane along STH 47 using flagging.

Wisconsin Lane Closure System Advance Notification

Provide the following advance notification to the engineer for incorporation into the Wisconsin Lane Closure System (LCS).

9650-17-61, 9650-17-70 7 of 44

TABLE 108-1 CLOSURE TYPE AND REQUIRED MINIMUM ADVANCE NOTIFICATION

Closure type with height, weight, or width restrictions (available width, all lanes in one direction < 16')	MINIMUM NOTIFICATION
Lane and shoulder closures	7 calendar days
Full roadway closures	7 calendar days
Ramp closures	7 calendar days
Detours	7 calendar days
Closure type without height, weight, or width restrictions (available width, all lanes in one direction ≥16')	MINIMUM NOTIFICATION
Lane and shoulder closures	3 business days
Ramp closures	3 business days
Modifying all closure types	3 business days

Discuss LCS completion dates and provide changes in the schedule to the engineer at weekly project meetings in order to manage closures nearing their completion date.

5. Holiday Work Restrictions.

Do not perform work on, nor haul materials of any kind along or across any portion of the highway carrying STH 47 traffic, and entirely clear the traveled way and shoulders of such portions of the highway of equipment, barricades, signs, lights, and any other material that might impede the free flow of traffic during the following holiday periods:

- From noon Friday, July 31, 2020 to 6:00 AM Monday, August 3, 2020 for Menominee Nation Contest Pow-wow;
- From noon Friday, September 4, 2020 to 6:00 AM Tuesday, September 8, 2020 for Labor Day;
- From noon Friday, May 21, 2021 to 6:00 AM Monday, May 24, 2021 for Veterans Pow-wow;
- From noon Friday, May 28, 2021 to 6:00 AM Tuesday, June 1, 2021 for Memorial Day;
- From noon Friday, July 2, 2021 to 6:00 AM Tuesday, July 6, 2021 for Independence Day;
- From noon Friday, August 6, 2021 to 6:00 AM Monday, August 9, 2021 for Menominee Nation Contest Pow-wow:
- From noon Friday, September 3, 2021 to 6:00 AM Tuesday, September 7, 2021 for Labor Day. stp-107-005 (20181119)

6. Utilities.

This contract comes under the provision of Administrative Rule Trans 220.

stp-107-065 (20080501)

There are known underground and overhead utility facilities located near or within the project limits. The contractor shall coordinate his construction activities with a call to Diggers Hotline or a direct call to utilities, which have facilities in the area, as required per statutes. The contractor shall use caution to ensure the entirety of underground facilities and shall maintain code clearance from overhead facilities at all times.

Some of the utility work described below is dependent on prior work being performed by the contractor at a specific site. In such situations, provide the engineer and the affected utility a good faith notice of when the utility is to start work at the site. Provide this notice 14 to 16 calendar days in advance of when the prior work will be completed, and the site will be available to the utility owner. Follow-up with a confirmation notice to the engineer and the utility owner not less than three working days before the site will be ready for the utility owner to begin its work.

The utilities on this project are Alliant Energies, Frontier Communications, Charter Communications, and the Menominee Indian Tribe of Wisconsin.

9650-17-61, 9650-17-70 8 of 44

Project 9650-17-70

Alliant Energy has overhead and underground facilities within the project limits. Facilities run from Station 83+60 to Station 203+20 approximately 30 to 70 feet from the reference line.

Alliant has overhead and underground crossings throughout the project corridor. New poles will be installed at the following locations: 83+60 RT, 83+60 LT, 84+60 LT, 86+41 RT, 87+67 LT, 87+91 RT, 90+13 RT, 90+58 RT, 91+60 LT, 93+03 RT, 95+37 RT, 96+11 RT, 96+13 LT, 98+26 LT, 100+38 RT, 102+48 RT, 103+95 LT/RT, 106+03 RT, 107+28 RT, 109+24 LT/RT, 111+12 RT, 111+47 RT, 111+80 RT, 117+67 RT, 118+91 RT, 120+42 LT/RT, 121+85 RT, 122+66 LT, 123+40 RT, 123+86 RT, 125+69 RT, 125+79 LT, 126+84 RT, 128+41 RT, 129+64 RT, 131+22 RT, 132+65 RT, 134+00 RT, 135+39 RT, 142+28 LT, 144+87 LT, 152+87 RT, 154+03 RT (to be installed after box culvert is completed), 155+83 RT, 156+79 RT, 158+60 RT, 159+53 RT, 161+80 RT, 165+48 RT, 166+00 RT, 170+48 RT, 173+39 RT, 174+81 LT/RT, 177+31 RT, 179+67 RT, 181+50 RT, 183+94 RT, 186+29 RT, 187+78 RT, 189+26 RT, 191+16 RT, 192+07 RT, 193+98 RT, 195+90 RT, 197+65 LT, 198+38 RT, and 200+64 RT.

Estimated construction time required is 140 working days. Alliant Energy will temporarily relocate facilities between 151+00 and 156+00 prior to August 15, 2020. All relocations will be completed by Spring 2021.

Frontier Communications has overhead and underground communications along the project corridor. In general, Frontier will be placing their new lines approximately 3 feet inside of the right-of-way. Frontier will be abandoning most of their old cable to install new fiber and telephone throughout the project. They will be placing new facilities joint with Alliant Energy.

Frontier Communications will temporarily relocate facilities between 151+00 and 156+00 prior to August 15, 2020. They will need 10 working days after Alliant Energy relocations are complete. All relocations will be completed by Spring 2021.

Charter Communications also has communication cable along the project corridor. In general, Charter will be placing their new facilities joint with Alliant Energy (overhead and underground) or will be utilizing existing facilities with grade adjustments. New pedestals will be placed at 152+35 LT and 164+32 LT. Charter Communications will temporarily relocate facilities between 151+00 and 156+00 prior to August 15, 2020. They will need 10 working days after Alliant Energy relocations are complete. All relocations will be completed by Spring 2021.

Conflicts with underground facilities are anticipated at the following locations and will require a representative from Charter Communications be on site during excavation to perform necessary adjustments: 103+43 RT, 112+72 RT, 113+09 RT, 120+98 LT, 122+76 LT, 128+00 RT, 139+18 RT, 139+66 RT, 146+90 LT, 154+21 LT and 156+64 LT. Existing vaults at the following locations will be adjusted to grade: 104+33 LT, 104+38 RT, 132+54 RT, 140+63 LT, 147+64 LT and 155+50 LT. Existing pedestals at the following locations will be moved and adjusted to grade: 116+46 RT, 117+69 RT and 118+90 RT. Existing pedestals at the following locations will be adjusted to grade: 101+80 RT, 104+36 RT, 107+35 LT, 114+63 RT, 117+71 LT, 120+99 RT, 122+72 LT, 132+50 RT, 140+26 RT, 144+33 LT, 145+95 LT, 156+76 RT, 158+40 RT and 161+87 RT. An on-site inspector from Charter must be present any time construction work is conducted within 10 feet of the facility. The maximum unsupported exposed length of a Charter facility is 5 feet. At no time should the facility be used as a brace to support equipment or sheeting/shoring materials. Adjustment of existing facilities in coordination with construction operations is expected to take approximately 10 working days.

Menominee Indian Tribe of Wisconsin has water distribution facilities within the project limits. At all locations where the proposed storm sewer pipe will be crossing the water main, 2-inch Insulation Board Polystyrene will be installed. Water main valve and hydrant adjustments will be done throughout the project to accommodate the grade changes.

All work on the Menominee Indian Tribe of Wisconsin water distribution facilities is included in the scope of the project and also includes the following:

- The hydrant at Station 103+25, RT will be salvaged and reinstalled to avoid the proposed sidewalk. Bends will be installed to avoid conflict with the proposed storm sewer.
- The hydrant at Station 109+61, RT will be extended to the west approximately 5 feet.
- Bends will be installed at storm sewer crossing locations 103+22 and 185+25 to avoid conflict.

9650-17-61, 9650-17-70 9 of 44

Menominee Indian Tribe of Wisconsin has sanitary sewer facilities within the project limits.

Work on the following Menominee Indian Tribe of Wisconsin sanitary sewer facilities is included in the scope of the project:

Manhole covers will be adjusted throughout the project to accommodate for the change in grade.

Additional work outside the scope of this project to be done by others is planned to be completed prior to the start of this project. Work includes:

- Pipe lining the majority of the existing sanitary sewer between Morrin Street and Lyons Road.
- Replacing select sanitary manholes between Morrin Street and Lyons Road.
- Replacing manhole castings on remaining manholes between Morrin Street and Lyons Road.
- Replacing sanitary sewer pipe crossing STH 47 at Chief Little Wave Road, Our Children's Road and approximately 400' south of CTH VV.
- Relaying sanitary sewer pipe crossing the Tribal Office Loop Road along STH 47 and crossing STH 47 at CTH VV and approximately 150' south of CTH VV.
- Replacing sanitary sewer crossing adjacent to the proposed box culvert C-73-004 with insulated pipe.

Project 9650-17-61

All utility coordination was done under Project 9650-17-70.

7. Municipality Acceptance of Sanitary Sewer and Water Main Construction.

Both the department and the Menominee Indian Tribe of Wisconsin personnel will inspect construction of sanitary sewer and water main under this contract. However, construction staking, testing, and acceptance of the sanitary sewer and water main construction will be by the Menominee Indian Tribe of Wisconsin.

stp-105-001 (20140630)

8. Information to Bidders, U.S. Army Corps of Engineers Section 404 Permit.

The department has obtained a U.S. Army Corps of Engineers Section 404 permit. Comply with the requirements of the permit in addition to requirements of the special provisions. A copy of the permit is available from the regional office by contacting Dan Erva at (715) 365-5776.

stp-107-054 (20080901)

9. Information to Bidders, WPDES General Construction Storm Water Discharge Permit.

The department has obtained coverage through the Wisconsin Department of Natural Resources to discharge storm water associated with land disturbing construction activities of this contract under the Wisconsin Pollutant Discharge Elimination System General Construction Storm Water Discharge Permit (WPDES Permit No. WI-S066796-1). A certificate of permit coverage is available from the regional office by contacting Stacy Hagenbucher at (715) 365-5770. Post the permit in a conspicuous place at the construction site.

stp-107-056 (20180628)

10. Archaeological Sites.

Various archaeologically sensitive sites are located approximately at the following locations:

Chief Carron Rd.

Station 10+50E - Station 12+25E LT

9650-17-61, 9650-17-70 10 of 44

```
STH 47:
```

Station 132+25 - Station 135+75 LT Station 134+00 - Station 136+00 RT Station 141+60 - Station 143+40 RT Station 146+20 - Station 148+00 RT Station 149+00 - Station 151+80 RT Station 155+40 - Station 156+40 RT Station 157+00 - Station 162+00 LT Station: 159+20 - Station 166+75 RT Station 167+30 - Station 171+20 LT Station 169+20 - Station 171+40 RT Station 172+00 - Station 174+50 LT Station 198+40 - Station 206+75 RT Station 209+00 - Station 209+60 LT Station 211+00 - Station 213+30 RT Station 215+40 - Station 217+00 LT Station 215+60 - Station 220+50 RT

CTH VV (S):

Station 11+25J - Station 12+30 J RT

Fairgrounds Rd.:

Station 8+50K - Station 9+75K LT

Blacksmith Rd.

Station 10+25L - Station 12+50L LT & RT

Rabbit Ridge Rd.:

Station 10+25N - Station 12+75N RT

Courthouse Ln.:

Station 7+00Q - Station 9+75Q LT

STH 55:

Station 10+75Q - Station 11+65Q RT

Notify the Bureau of Technical Services – Environmental Process and Document Section (BTS-EPDS) at (608) 266-0099 at least two weeks before commencement of any ground disturbing activities. BTS-EPDS will determine if a qualified archaeologist will need to be on site during construction of this area.

Do not use the site for borrow or waste disposal. Do not use the site area not currently capped by asphalt/concrete for the staging of personnel, equipment and/or supplies.

11. Environmental Protection, Aquatic Exotic Species Control.

Exotic invasive organisms such as VHS, zebra mussels, purple loosestrife, and Eurasian water milfoil are becoming more prolific in Wisconsin and pose adverse effects to waters of the state. Wisconsin State Statutes 30.07, "Transportation of Aquatic Plants and Animals; Placement of Objects in Navigable Waters", details the state law that requires the removal of aquatic plants and zebra mussels each time equipment is put into state waters.

At construction sites that involve navigable water or wetlands, use the follow cleaning procedures to minimize the chance of exotic invasive species infestation. Use these procedures for all equipment that comes in contact with waters of the state and/or infested water or potentially infested water in other states.

9650-17-61, 9650-17-70 11 of 44

Ensure that all equipment that has been in contact with waters of the state, or with infested or potentially infested waters, has been decontaminated for aquatic plant materials and zebra mussels before being used in other waters of the state. Before using equipment on this project, thoroughly disinfect all equipment that has come into contact with potentially infested waters. Guidelines from the Wisconsin Department of Natural Resources for disinfection are available at:

http://dnr.wi.gov/topic/invasives/disinfection.html

Use the following inspection and removal procedures:

- 1. Before leaving the contaminated site, wash machinery and ensure that the machinery is free of all soil and other substances that could possibly contain exotic invasive species;
- 2. Drain all water from boats, trailers, bilges, live wells, coolers, bait buckets, engine compartments, and any other area where water may be trapped;
- 3. Inspect boat hulls, propellers, trailers and other surfaces. Scrape off any attached mussels, remove any aquatic plant materials (fragments, stems, leaves, seeds, or roots), and dispose of removed mussels and plant materials in a garbage can before leaving the area or invested waters; and
- 4. Disinfect your boat, equipment and gear by either:
 - 4.1. Washing with ~212 F water (steam clean), or
 - 4.2. Drying thoroughly for five days after cleaning with soap and water and/or high pressure water, or
 - 4.3. Disinfecting with either 200 ppm (0.5 oz per gallon or 1 Tablespoon per gallon) Chlorine for 10-minute contact time or 1:100 solution (38 grams per gallon) of Virkon Aquatic for 20- to 30-minute contact time. Note: Virkon is not registered to kill zebra mussel veligers nor invertebrates like spiny water flea. Therefore, this disinfect should be used in conjunction with a hot water (>104° F) application.

Complete the inspection and removal procedure before equipment is brought to the project site and before the equipment leaves the project site.

stp-107-055 (20130615)

12. Environmental Protection – Dewatering.

General

Add the following to standard spec 107.18:

If dewatering is required, treat the water to remove suspended sediments by filtration, settlement or other appropriate best management practice prior to discharge. Submit the proposed means and methods of dewatering for each required location for approval as part of the Erosion Control Implementation Plan (ECIP). Include details of how the intake will be managed to not cause an increase in the background level turbidity prior to treatment and any additional measures necessary to prevent sediments from reaching the project limits or wetlands and waterways.

Guidance on Dewatering can be found on the Wisconsin Department of Natural Resources website located in the Storm Water Construction Technical Standards, Dewatering Code #1061, "Dewatering". This document can be found at the WisDNR website:

http://dnr.wi.gov/topic/stormwater/standards/const standards.html

Work includes furnishing all materials, excavation, maintenance, cleaning, disposal of surplus material and removal of the dewatering system and is incidental to contract work.

ncr-107-025 (20160401)

Contaminated Groundwater

The Menominee Tribal Utility Department, under legislation adopted by the Tribal Government of the Menominee Indian Tribe of Wisconsin, prohibits the discharge of any groundwater, storm water, surface water, surface drainage, and hazardous materials (i.e., gasoline, benzene, naphtha, fuel oil, or other flammable or explosive liquid, solid or gas) into any sanitary sewer.

The department and others have completed testing for groundwater contamination at locations within and adjacent to this project where excavation is required. Based on the depth to groundwater and planned excavation depths, dewatering of petroleum hydrocarbon contaminated groundwater exceeding the DNR's Chapter NR 140 Enforcement Standards (ESs) and/or Preventive Action Limits (PALs) may be

9650-17-61, 9650-17-70 12 of 44

necessary during storm sewer and utilities installation at sites listed in Hazardous Materials Contamination and as shown on the plans.

If contaminated groundwater, strong petroleum odors or free-phase petroleum product, such as, gasoline floating on the water table, are encountered elsewhere within the project limits, then terminate dewatering activities in the area and notify the engineer.

Implement means and methods as necessary to accomplish dewatering and meet requirements for management of petroleum contaminated water. Dewatering means and methods implemented by the contractor, including location and depth of dewatering operations, pumping rates, length of dewatering area, and dewatering methods, such as, wells, well points, and/or sump pumps, will likely affect quantity and quality of recovered water. Employ dewatering methods and techniques in a manner that does not cause a discharge or migration of contaminants into uncontaminated areas.

Water generated from dewatering activities within the contaminated groundwater areas includes groundwater and water that may enter an excavation at ground surface, such as, rain water or storm water. Employ construction methods and techniques in a manner that will minimize the need for dewatering, and if dewatering is required, minimize the volume of water generated.

Coordinate dewatering activities within the contaminated groundwater areas under this contract with the department's engineer and environmental consultant. Do not treat, discharge or transport contaminated water off-site without prior approval from the engineer or environmental consultant.

Provide a schedule of operations in the contaminated groundwater areas to the engineer and environmental consultant at the pre-construction conference.

Provide the engineer and environmental consultant with a dewatering plan at least 45 calendar days prior to the scheduled date of beginning dewatering activities in the contaminated groundwater areas. Describe the proposed means and methods to accomplish dewatering and include scheduled start and end dates, estimated pumping rates and times, anticipated daily volumes, containerization, treatment methods and/or disposal location, and any other information pertinent to contaminated groundwater management.

Provide the engineer and environmental consultant with documentation of contaminated groundwater management and disposal within 90 calendar days after completion of construction dewatering activities.

All costs associated with dewatering activities within the contaminated groundwater areas shall be considered incidental to construction.

13. Erosion Control Structures.

Within three calendar days after completing the excavation for a substructure unit, place riprap or other permanent erosion control items required by the contract or deemed necessary by the engineer around the unit at a minimum to a height equivalent to the calculated water elevation resulting from a storm that occurs on the average of once every two years (Q2) as shown on the plan, or as the engineer directs.

In the event that construction activity does not disturb the existing ground below the Q2 elevation, the above timing requirements for permanent erosion control shall be waived.

stp-107-070 (20191121)

14. Construction Over or Adjacent to Navigable Waters.

The Wolf River is classified as a state navigable waterway under standard spec 107.19. stp-107-060 (20171130)

15. Health and Safety Requirements for Workers Remediating Petroleum Contamination.

Add the following to standard spec 107.1(2):

Soil contamination with gasoline, diesel fuel, fuel oil, or other petroleum related products may be encountered during excavation activities. Prepare a site specific Health and Safety Plan complying with the Occupational Safety and Health Administration (OSHA) standard for Hazardous Waste Operation and Emergency Response (HAZWOPER), 29 CFR 1910.120.

9650-17-61, 9650-17-70 13 of 44

All site workers taking part in remediation activities or who will have the reasonable probability of exposure of safety or health hazards associated with the hazardous material shall have completed Health and Safety training that meets OSHA requirements. Before the start of remediation work, submit to the engineer a site specific Health and Safety Plan, and written verification that workers will have completed up-to-date OSHA training.

Develop, delineate, and enforce the health and safety exclusions zones for each contaminated site location pursuant to 29 CFR 1910.120.

stp-107-115 (20150630)

16. Notice to Contractor – Hazardous Materials Contamination

The following sites are known or suspected to have hazardous materials contamination:

Site Name and Location	Description
Wolf River Express/	Petroleum contaminated soil and groundwater exceeding NR 720 and
Former Trading Post	NR 140 standards, respectively, are present beneath STH 47 easement.
N845 Hwy. 47/55	
Keshena, WI DNR BRRTS No. 03-40-001523	Petroleum Contaminated Soil within Construction Limits: Station 152+75 to Station 153+40, from reference line to project limit LT of reference line, at a depth of approximately 2 to 10 feet below existing grade. Petroleum hydrocarbons were detected in soil, including ethylbenzene (45,300 micrograms per kilogram (μ g/kg)), naphthalene (65,700 μ g/kg), toluene (2,690 μ g/kg), total trimethylbenzenes (367,900 μ g/kg), total xylenes (245,300 μ g/kg), and total lead (136 milligrams per kilogram (μ g/kg)).
	Petroleum Contaminated Groundwater within Construction Limits: Station 152+75 to Station 153+40, from reference line to project limit LT of reference line; depth to groundwater approximately 6 feet below existing grade. Petroleum hydrocarbons were detected in groundwater within project limits, including ethylbenzene (72.2 micrograms per liter (µg/L)), naphthalene (70.5 µg/L), toluene (4.8 µg/L), total trimethylbenzenes (429.4 µg/L), and total xylenes (330.1 µg/L).
Legendz Bait & Tackle N848 Hwy. 47/55 Keshena, WI	Petroleum contaminated soil exceeding NR 720 standards and petroleum contaminated groundwater below NR 140 standards are present beneath STH 47 easement.
	Petroleum Contaminated Soil within Construction Limits: Station 153+55 to Station 153+95, from reference line to project limit RT of reference line, at a depth of approximately 2 to 7 feet below existing grade. Petroleum hydrocarbons were detected in soil, including naphthalene (874 μ g/kg) and total lead (34.9 mg/kg).
	Petroleum Contaminated Groundwater within Construction Limits: Station 153+55 to Station 153+95, from reference line to project limit RT of reference line; depth to groundwater approximately 6 feet below existing grade. Naphthalene (5.9 $\mu g/L)$ was detected in groundwater within project limits.

For further information regarding approval of the soil and groundwater management methods or to obtain a copy of the various hazardous materials investigation reports for this project, contact one of the following persons:

9650-17-61, 9650-17-70 14 of 44

Greer Lundquist
Wisconsin Department of Transportation
501 Hanson Lake Road
Rhinelander, WI 54501
Telephone: (715) 365-5758

Email: Greerl.Lundquist@dot.wi.gov.

Kyle Wagoner AECOM Technical Services 200 Indiana Avenue Stevens Point, WI 54481 Telephone: (715) 342-3038

Email: kyle.wagoner@aecom.com

17. Notice to Contractor, Notification of Demolition and/or Renovation No Asbestos Found.

John Roelke, License Number All-119523, inspected Structure B-73-4 for asbestos on January 23, 2018. No regulated Asbestos Containing Material (RACM) was found on this structure. A copy of the inspection report is available from: Dan Erva, (715) 365-5776.

A visual inspection of Structure C-73-4 was completed and no possible ACM was found. WisDOT agreed a formal asbestos inspection was not necessary do to the lack of possible ACM material.

In accordance with NR447 and DHS159, ensure that DNR or DHS receives a completed Notification of Demolition and/or Renovation (DNR Form 4500-113 (R 4/11), or subsequent revision) via U.S. mail, hand-delivery, or using the online notification system at least 10 working days before beginning any construction or demolition. Pay all associated fees. Provide a copy of the completed 4500-113 form to Dan Erva, (715) 365-5776 and DOT BTS-ESS attn: Hazardous Materials Specialist, PO Box 7965, Madison, WI 53707-7965. In addition, comply with all local or municipal asbestos requirements.

Use the following information to complete WisDNR form 4500-113:

- Site Name: Structure B-73-4, STH 47 over Wolf River
- Site Address: 0.3M N jct STH 55 to N and 0.6M S jct CTH C
- Ownership Information: WisDOT Transportation Northcentral Region, 510 N. Hanson Lake Rd., Rhinelander, Wisconsin 54501
- Contact: Dan Erva
- Phone: (715) 365-5776
- Age: 34 years old. This structure was constructed in 1986.
- Area: 13334 SF of deck

Use the following information to complete WisDNR form 4500-113:

- Site Name: Structure C-73-2, STH 47 over Keshena Lake Outlet
- Site Address: Intersection of CTH VV/STH 47, Village of Keshena, Menominee County
- Ownership Information: WisDOT Transportation Northcentral Region, 510 N. Hanson Lake Rd., Rhinelander, Wisconsin 54501
- Contact: Dan Erva
- Phone: (715) 365-5776
- Age: 90 years old. This structure was constructed in 1930.
- Area: 2,500 SF of deck

Insert the following paragraph in Section 6.g.:

 If asbestos not previously identified is found or previously non-friable asbestos becomes crumbled, pulverized, or reduced to a powder, stop work immediately, notify the engineer, and the engineer will notify the department's Bureau of Technical Services at (608) 266-1476 for an emergency response as specified in standard spec 107.24. Keep material wet until it is abated or until it is determined to be non-asbestos containing material.

9650-17-61, 9650-17-70 15 of 44

18. Native American Hiring.

Pre-Bid

Before bid submittal, contact the Menominee Indian Tribe of Wisconsin to provide information on hiring procedures and future employment opportunities, and gather information on the tribal work force.

Menominee Indian Tribe of Wisconsin tribal labor office contact information:

Contact: Nicole Fish, Director of Lending and Taxes

Address: N559 Library Road, P.O. Box 910, Keshena, WI 54135

Office: (715) 799-5171 Email: nfish@mitw.org

Maintain documentation of all efforts made to communicate with the Menominee Indian Tribe of Wisconsin (MITW). Pre-bid, submit documentation in conjunction with the Proposal Request Form to the Bureau of Project Development at:

DOTDTSDHighwayConstructionContractors@dot.wi.gov

The Eligible Bidders list will not be updated until this documentation is received. Include the following information in documentation:

- Proposal number/route number/termini/county.
- Persons contacted.
- Method of communication (phone, email, written, in person).
- Information exchanged (hiring procedures, available positions, referrals received, employee performance, etc.).

After Execution

At a minimum of three days before the tribal coordination meeting, contact the MITW to provide the following information regarding available employment opportunities for prime and subcontractors:

- Job classification/trade
- Job qualifications and required skills
- Employment period
- Wage
- Copy of job application

After receiving employment opportunities, the MITW will within two business days provide employment referrals or provide other recruitment sources to obtain qualified referrals.

Document all efforts made to communicate job opportunities and the results of hiring activities throughout the life of the contract. At any time during the life of the contract, provide MITW communication documentation within five business days of request by the department.

Tribal Coordination Meeting

Between execution of contract and the project preconstruction conference, setup and coordinate a meeting with the Tribal officials and leaders at MITW and notify and invite WisDOT Statewide Tribal Liaison, 4822 Madison Yards Way, 4th Floor South, P.O. Box 7965, Madison, WI 53707-7965, sandy.stankevich@dot.wi.gov, (715) 365-5784. The prime contractor and all subcontractors shall attend this meeting. Discuss available employment opportunities and other tribal areas of interest such as scope of work, Tribal regulations, borrow sites, waste sites, and available aggregate.

Project Completion

As a part of the document submittals required under standard spec 109.7, submit documentation summarizing communications regarding job opportunities throughout the life of the contract. Provide final report to the tribe and Statewide Tribal Affairs compiling the results of hiring activities for the prime contractor as well as for subcontractors at all tiers.

stp-107-200 (20191121)

9650-17-61, 9650-17-70 16 of 44

19. MITW Permits.

Storm water and surface water permits through MITW have been obtained. Submit a Stormwater Pollution Prevention Plan (SWPPP) to MITW Environmental Services and review it with WisDOT Stormwater and Erosion Control Engineer for consistency with TRANS 401. Submit the Notice of Termination to MITW upon completion of the project.

Obtain the required MITW Construction Permit. Satisfy all requirements of the MITW Construction Permit including payment of the applicable tax.

20. Coordination with Businesses and Residents.

The contractor shall arrange and conduct a meeting between the contractor, the department, affected residents, local officials and business people to discuss the project schedule of operations including vehicular and pedestrian access during construction operations. Hold the first meeting at least one week before the start of work under this contract and weekly after that. The contractor shall arrange for a suitable location for meetings that provides reasonable accommodation for public involvement. The department will prepare and coordinate publication of the meeting notices and mailings for meetings. The contractor shall schedule meetings with at least 2 weeks' prior notice to the engineer to allow for these notifications.

stp-108-060 (20141107)

21. Removing Old Structure Over Waterway With Minimal Debris Station Station 154+20, Item 203.0600.S.01.

Conform to standard spec 203 as modified in this special provision.

Add the following to standard spec 203:

203.3.6 Removals Over Waterways and Wetlands

203.3.6.2 Removing Old Structure Over Waterway with Minimal Debris

- (1) Remove the existing Structure C-73-2 over the Keshena Lake Outlet in large sections and conforming to the contractor's approved structure removal and clean-up plan. During superstructure removal, prevent all large pieces and minimize the number of small pieces from entering the waterway or wetland. Remove all reinforcing steel, all concrete, and all other debris that falls into the waterway or wetland. The contractor may leave limited amounts of small concrete pieces scattered over the waterway floor or wetland only if the engineer allows.
- (2) Submit a structure removal and clean-up plan as part of the erosion control implementation plan required under standard spec 107.20. Do not start work under the structure removal and clean-up plan without the department's written approval of the plan. Include the following information in the structure removal and clean-up plan:
 - Methods and schedule to remove the structure.
 - Methods to control potentially harmful environmental impacts.
 - Methods for superstructure removal that prevent all large pieces and minimize the number of small pieces from entering the waterway or wetlands.
 - Methods to control dust and contain slurry.
 - Methods for removing piers and abutments. If blasting in water, include restrictions that regulatory agencies and the contract require.
 - Methods for cleaning the waterway or wetlands.
- (3) If stockpiling spoil material, place it on an upland site an adequate distance from the waterway, wetland, or any open water created by excavation. Install silt fence between the spoil pile and the waterway, wetland, or excavation site.

Add the following Removing Old Structure bid item to standard spec 203.5.1:

ITEM NUMBER DESCRIPTION UNIT

203.0600.S.01 Removing Old Structure Over Waterway With Minimal Debris Station 154+20 LS

stp-203-020 (20190618)

9650-17-61, 9650-17-70 17 of 44

22. Minimal Debris Removal for Full Depth Deck Repair and Concrete Surface Repair.

Conform to standard spec 203 as modified in this special provision.

Add the following to standard spec 203:

203.3.6 Removals Over Waterways and Wetlands

203.3.6.2 Full Depth Deck Repair and Concrete Surface Repair with Minimal Debris

- (1) During full depth repairs and concrete surface repairs, remove the existing concrete over the Wolf River in large sections and conforming to the contractor's approved structure removal and clean-up plan. During full depth repairs and concrete surface repairs, prevent all large pieces and minimize the number of small pieces from entering the waterway or wetland. Remove all reinforcing steel, all concrete, and all other debris that falls into the waterway or wetland. The contractor may leave limited amounts of small concrete pieces scattered over the waterway floor or wetland only if the engineer allows.
- (2) Submit a structure removal and clean-up plan as part of the erosion control implementation plan required under standard spec 107.20. Do not start work under the structure removal and clean-up plan without the department's written approval of the plan. Include the following information in the structure removal and clean-up plan:
 - Methods and schedule to complete the repairs.
 - Methods to control potentially harmful environmental impacts.
 - Methods for concrete removal that prevent all large pieces and minimize the number of small pieces from entering the waterway or wetlands.
 - Methods to control dust and contain slurry.
 - Methods for removing concrete on piers and abutments. If blasting in water, include restrictions that regulatory agencies and the contract require.
 - Methods for cleaning the waterway or wetlands.
- (3) If stockpiling spoil material, place it on an upland site an adequate distance from the waterway, wetland, or any open water created by excavation. Install silt fence between the spoil pile and the waterway, wetland, or excavation site.

203.5.1 General

(5) Payment for "Minimal Debris Removal for Full Depth Repair and Concrete Surface Repair" shall be incidental to the full depth repair and concrete surface repair items respectively.

23. Excavation, Hauling, and Disposal of Petroleum Contaminated Soil, Item 205.0501.S.

A Description

A.1 General

This special provision describes excavating, loading, hauling, and disposing of petroleum contaminated soil at a DNR approved bioremediation facility. The closest DNR approved bioremediation facility is:

Marathon County Solid Waste Department Landfill

R18500 East Wisconsin Highway 29

Ringle, WI 54471

Contact: Meleesa Johnson, Director Telephone: (715) 446-3101, Ext. 104

Email: meleesa.johnson@co.marathon.wi.us

Perform this work conforming to standard spec 205 and Chapters NR 700-754 of the Wisconsin Administrative Code, as supplemented herein. Per NR 718.07, a solid waste collection and transportation service-operating license is required under NR 502.06 for each vehicle used to transport contaminated soil.

A.2 Notice to the Contractor - Contaminated Soil Locations

The department completed testing for soil and groundwater contamination for locations within this project where excavation is required. Testing indicated that petroleum-contaminated soil is present at the following locations the plans show:

9650-17-61, 9650-17-70 18 of 44

- 1. Station 152+75 to 153+40 LT.
- Station 153+55 to 153+95 RT.

If contaminated soils are encountered elsewhere on the project, terminate excavation activities in the area and notify the engineer.

For further information regarding previous investigation and remediation activities at these sites contact:

Name: Greer Lundquist

Address: 501 Hanson Lake Road, Rhinelander, WI 54501

Phone: (715) 365-5758

E-mail: Greerl.Lundquist@dot.wi.gov

A.3 Coordination

Coordinate work under this contract with the environment consultant:

Consultant: AECOM Technical Services

Address: 200 Indiana Avenue, Stevens Point, WI 54481

Contact: Kyle Wagoner Phone: (715) 342-3038

E-mail: kyle.wagoner@aecom.com

The role of the environmental consultant will be limited to:

- 1. Determining the location and limits of contaminated soil to be excavated based on soil analytical results from previous investigations, visual observations, and field screening of soil that is excavated;
- 2. Identifying contaminated soils to be hauled to the bioremediation facility;
- 3. Documenting that activities associated with management of contaminated soil are in conformance with the contaminated soil management methods for this project as specified herein; and
- 4. Obtaining the necessary approvals for disposal of contaminated soil from the bioremediation facility.

Provide at least a 14-calendar day notice of the preconstruction conference date to the environmental consultant. At the preconstruction conference, provide a schedule for all excavation activities in the areas of contamination to the environmental consultant. Also notify the environmental consultant at least three calendar days before beginning excavation activities in each of the contaminated areas.

Coordinate with the environmental consultant to ensure that the environmental consultant is present during excavation activities in the contaminated areas. Perform excavation work in each of the contaminated areas on a continuous basis until excavation work is completed.

Identify the DNR approved bioremediation facility that will be used for disposal of contaminated soils and provide this information to the environmental consultant no later than 30 calendar days before beginning excavation activities in the contaminated areas or at the preconstruction conference, whichever comes first. The environmental consultant will be responsible for obtaining the necessary approvals for disposal of contaminated soils from the bioremediation facility. Do not transport contaminated soil offsite without prior approval from the environmental consultant.

A.4 Health and Safety Requirements

Add the following to standard spec 107.1:

During excavation activities, expect to encounter soil contaminated with gasoline, diesel fuel, fuel oil, or other petroleum related products. Site workers taking part in activities that will result in the reasonable probability of exposure to safety and health hazards associated with hazardous materials shall have completed health and safety training that meets the Occupational Safety and Health Administration (OSHA) requirements for Hazardous Waste Operations and Emergency Response (HAZWOPER), as provided in 29 CFR 1910.120.

Prepare a site-specific Health and Safety Plan, and develop, delineate and enforce the health and safety exclusion zones for each contaminated site location as required by 29 CFR 1910.120. Submit the site-specific health and safety plan and written documentation of up-to-date OSHA training to the engineer before the start of work.

B (Vacant)

9650-17-61, 9650-17-70 19 of 44

C Construction

Add the following to standard spec 205.3:

Control operations in the contaminated areas to minimize the quantity of contaminated soil excavated.

The environmental consultant will periodically evaluate soil excavated from the contaminated areas to determine if the soil will require offsite bioremediation. The environmental consultant will evaluate excavated soil based on field screening results, visual observations, and soil analytical results from previous environmental investigations. Assist the environmental consultant in collecting soil samples for evaluation using excavation equipment. The sampling frequency shall be a maximum of one sample for every 15 cubic yards excavated.

Directly load and haul soils designated by the environmental consultant for offsite bioremediation to the DNR approved bioremediation facility. Use loading and hauling practices that are appropriate to prevent any spills or releases of petroleum-contaminated soils or residues. Before transport, sufficiently dewater soils designated for off-site bioremediation so as not to contain free liquids.

D Measurement

The department will measure Excavation, Hauling, and Disposal of Petroleum Contaminated Soil in tons of contaminated soil, accepted by the bioremediation facility as documented by weight tickets generated by the bioremediation facility.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBERDESCRIPTIONUNIT205.0501.SExcavation, Hauling, and Disposal of Petroleum Contaminated SoilTON

Payment is full compensation for excavating, segregating, loading, hauling, and treatment via bioremediation of contaminated soil; obtaining solid waste collection and transportation service operating licenses; assisting in the collection soil samples for field evaluation; and dewatering of soils before transport, if necessary.

stp-205-003 (20150630)

24. Pigmented Surface Sealer.

Remove standard spec 502.3.13.3 (1) and replace with the following:

(1) Apply pigmented surface sealer conforming to standard spec 502.2.11 to the inside and top faces of parapets and outside faces of parapets where indicated on the plans, including parapets on abutment wings. Use gray sealer unless the contract specifies a different color. Do not seal surfaces where the contract requires staining or other treatment.

25. Non-Shrink Grout, Item 502.0120.S.

A Description

This special provision describes furnishing and placing Non-Shrink Grout.

B Material

Furnish non-shrink grout which is quick-setting, with rapid strength gain, and high-bond strength. Grout shall not contain calcium chloride or admixture containing calcium chloride or other ingredient in sufficient quantity to cause corrosion to steel reinforcement. Mix grout just before use according to the manufacturer's instructions. Follow manufacturer's recommendation for dosage of corrosion inhibitor admixture.

Use structural non-shrink grout that meets a minimum compressive strength of 4,000 psi within 24 hours when tested as specified in AASHTO T 106. Meet all the requirements of AASHTO T 160 with the exception that the contractor-supplied cube molds will remain intact with a top firmly attached throughout the curing period. Use structural non-shrink grout with no expansion after seven days. Refer to Table 1 for structural non-shrink grout requirements.

9650-17-61, 9650-17-70 20 of 44

Table 1 Structural Non-Shrink Grout

Properties ^[1]	Requirements	ASTM	AASHTO
Accelerated Weathering	As Specified in ASTM or AASHTO	C 666	T 260
Compressive Strength	>5,000 psi @ 28 days		T 106
Accepted Bond Strengths	>1,000 psi @ 24 Hours	C 882	
Test Medium	<3% White Utah Road Salt		T 161
Accepted Weight Loss	<15% @ 300 Cycles		T 161
Length Change	No expansion after 7 days		T 160

^[1] Certified test results from a private AASHTO accredited testing laboratory will suffice for acceptance.

C Construction

Place Non-Shrink Grout conforming to standard spec 501 and standard spec 502 and as the plans show.

D Measurement

The department will measure Non-Shrink Grout by the cubic foot, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBERDESCRIPTIONUNIT502.0120.SNon-Shrink GroutCF

Payment for Non-Shrink Grout is full compensation for providing all materials; placing, finishing, protecting and curing the Non-Shrink Grout.

stp-502-035 (20161130)

26. Protective Surface Treatment Reseal, Item 502.3215.S.

A Description

This special provision describes resealing existing structures with protective surface treatment.

B Materials

Furnish a clear commercial protective surface treatment selected from the department's approved products list.

C Construction

Apply protective surface treatment to the entire top surface of the bridge deck; as shown in the plans.

Ensure that the concrete is surface-dry for a minimum of one day before application. Delay application if rain is expected or protect from rain for up to 12 hours after application.

Ensure that the concrete is clean. Air blast immediately before applying the protective surface treatment to remove all dust or loose particles. Also ensure that application equipment is clean and functioning properly.

Use the manufacturer's recommended methods. Apply at the rate the manufacturer recommends unless that rate causes ponding.

Do not open the bridge to service until trafficked areas are dry enough to sustain traffic without causing damage to the treatment or creating a safety hazard.

D Measurement

The department will measure Protective Surface Treatment Reseal by the square yard, acceptably completed.

9650-17-61, 9650-17-70 21 of 44

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER DESCRIPTION UNIT 502.3215.S Protective Surface Treatment Reseal SY

Payment is full compensation for resealing, including surface preparation and cleaning.

stp-502-055 (20080902)

27. Precast Concrete Wingwalls C-73-0004, Item 504.1000.S.01.

A Description

This special provision describes furnishing, transporting, and placing precast wingwalls and cutoff walls.

B (Vacant)

C Construction

Alternate details for the precast wingwall units of equal strength and hydraulic capacity may be submitted to the engineer for approval. The contractor may build department-approved cast-in-place wingwalls as an alternative to precast apron endwalls. Build these endwalls conforming to standard spec 504.2 and standard spec 504.3.

D Measurement

The department will measure Precast Concrete Wingwalls C-73-4, completed according to the contract and accepted, as a single complete unit of work. Each unit shall consist of the two precast wingwalls required for the box culvert.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBERDESCRIPTIONUNIT504.1000.S.01Precast Concrete Wingwalls C-73-0004LS

Payment is full compensation for furnishing, transporting and placing the precast wingwalls and precast cutoff walls.

stp-504-010 (20080902)

28. Precast Concrete Box Culvert, 6 FT x 3 FT, Item 504.2000.S.01.

A Description

This special provision describes furnishing and installing precast concrete box culverts of the size and length the plans show.

B Materials

Provide materials and fabricate Precast Concrete Box Culvert according to ASTM C1577, except that the concrete mixture shall contain not less than 565 pounds of Portland cement, blended cement or Portland cement plus pozzolanic admixture per cubic yard. Slab thickness, areas of reinforcement, and other details shall be as the plans show.

C (Vacant)

D Measurement

The department will measure Precast Concrete Box Culvert, 6 FT x 3 FT, completed according to the contract and accepted, in length by the linear foot in place. The box culvert will be measured on the centerline of the box along the flow line.

9650-17-61, 9650-17-70 22 of 44

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER DESCRIPTION UNIT 504.2000.S.01. Precast Concrete Box Culvert, 6 FT x 3 FT LF

Payment is full compensation for furnishing, hauling and placing the box, including joint ties, and mastic.

stp-504-015 (20160607)

29. Cleaning Parapets, Item 509.9050.S.

A Description

This special provision describes cleaning the inside face and top surface of the concrete parapet at the edge of the deck and cleaning the inside face and top surface and outside face of the concrete parapet between the travel way and the sidewalk as the plans show and as the engineer directs.

B (Vacant)

C Construction

C.1 Blast Cleaning Operation

Blast clean the inside face and top surface of the concrete parapet according to SSPC SP-13 and ASTM D4259 for an abrasive blast cleaning to a surface roughness and finish as the engineer directs. Before abrasive blast cleaning operations are to begin for the entire bridge parapet, prepare a representative trial area on the parapet concrete surface, and have the method of blast cleaning approved by the engineer.

C.2 Water Cleaning Operation

After abrasive blast cleaning operations are completed, clean the prepared parapet surface with water according to ASTM D4258. Remove with this water cleaning all dust and loose material from the parapet inside face and top that is to be coated with pigmented surface sealer. Provide an adequate drying time of the parapet inside face, outside face, and top surface before coating with the pigmented surface sealer. Remove all loose concrete, dirt, dust, or blast material that remains on the bridge deck, as the engineer directs.

C.3 Surface Finish Operation

After water cleaning operations are complete, provide a sack rubbed finish on all cleaned surfaces of the concrete parapet in accordance with standard spec 502.3.7.

D Measurement

The department will measure Cleaning Parapets in length by the linear foot of parapet, acceptably cleaned.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBERDESCRIPTIONUNIT509.9050.SCleaning ParapetsLF

Payment is full compensation for abrasive blast cleaning; for water cleaning; for applying the surface finish; and for all additional cleanup of the concrete surface and surrounding bridge deck area.

30. Adjusting Manhole Covers.

This special provision describes adjusting manhole covers conforming to standard spec 611 as modified in this special provision.

9650-17-61, 9650-17-70 23 of 44

Adjust manhole covers located in pavement areas in two separate operations. Initially, remove designated manhole covers along with sufficient pavement to permit installation of temporary cover plate over the opening. Fill the excavated area with asphaltic pavement mixture, which shall remain in place until contract milling and paving operations permit setting the manhole frames to grade. During the second phase, remove the asphaltic pavement mixture surrounding the manhole plus the temporary cover plate, and set the manhole cover to final grade. The department will measure and pay for the items of asphaltic pavement mixture, temporary cover plate, milling, and paving separately.

Revise standard spec 611.3.7 by deleting the last paragraph.

Set the manhole frames so that they comply with the surface requirements of standard spec 450.3.2.9. At the completion of the paving, a 6-foot straightedge shall be placed over the centerline of each manhole frame parallel to the direction of traffic. A measurement shall be made at each side of the frame. The two measurements shall be averaged. If this average is greater than 5/8 inches, reset the manhole frame to the correct plane and elevation. If this average is 5/8 inches or less but greater than 3/8 inches, the manhole frame shall be allowed to remain in place but shall be paid for at 50 percent of the contract unit price.

If the manhole frame is higher than the adjacent pavement, the two measurements shall be made at each end of the straightedge. These two measurements shall be averaged. The same criteria for acceptance and payment as above, shall apply.

stp-611-005 (20030820)

31. Cover Plates Temporary, Item 611.8120.S.

A Description

This special provision describes providing and removing steel plates to cover and support asphaltic pavement and traffic loading at manholes, inlets and similar structures during milling and paving operations.

B Materials

Provide a 0.25 inch minimum thickness steel plate that extends to the outside edge of the existing masonry.

C (Vacant)

D Measurement

The department will measure Cover Plates Temporary as each individual unit, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER DESCRIPTION UNIT 611.8120.S Cover Plates Temporary EACH

Payment is full compensation for furnishing, installing, and removing the cover plates.

The steel plates shall become the property of the contractor when no longer needed in the contract work. stp-611-006 (20151210)

32. Insulation Board Polystyrene, 2-Inch, Item 612.0902.S.01.

A Description

This special provision describes furnishing and placing polystyrene insulation board as the plans show.

B Materials

Provide polystyrene insulation board that conforms to the requirements for Extruded Insulation Board, AASHTO Designation M230 as modified in this special provision.

Delete flammability requirement.

9650-17-61, 9650-17-70 24 of 44

B.1 Certification

Before installation, obtain from the manufacturer a certification indicating compliance and furnish it to the engineer.

C (Vacant)

D Measurement

The department will measure Insulation Board Polystyrene (size) by area in square yards of work, completed and accepted.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBERDESCRIPTIONUNIT612.0902.S.01Insulation Board Polystyrene 2-InchSY

Payment is full compensation for all excavation; and for furnishing and placing the insulation board. stp-612-005 (20030820)

33. Fence Chain Link Salvage 5-ft.

Add the following to standard spec 616.1:

- (2) Replace existing fence elements that are deformed, have section loss due to rust, or as determined in the field by the engineer, with new fence components.
- (3) Remove fence system (including grout within sleeve) only as necessary to complete deck repairs and to replace failing and deteriorated fence components and as determined in the field by the engineer.

Add the following to standard spec 616.3.3.5:

(3) In locations where fence posts are removed, fill sleeve and bevel away from post with non-shrink grout after setting post. Leave no voids.

Add the following to standard spec 616.5(5):

Grout will be paid for under the "Non-Shrink Grout" bid item".

34. Topsoil

Urban areas are from the south project limits to the Blacksmith Rd./Lyons Rd. intersection. Rural areas are from the Blacksmith Rd./Lyons Rd. intersection to the north project limits.

35. Field Office.

Add the following to standard spec 642:

For field offices without handwashing facilities, the contract shall provide and maintain a portable handwashing station at every project field office. The station shall include a hands-free sink with foot pump-operated faucet, soap dispenser, paper towel dispenser, fresh water supply, and collection tank for gray water. Regularly service and maintain the handwashing station and all supplies as needed, and properly dispose of all materials. Costs associated with the handwashing station are incidental to the field office bid item.

9650-17-61, 9650-17-70 25 of 44

36. Electrical Service Meter Breaker Pedestal STH 47 & Warrington Rd, Item 656.0200.01; Electrical Service Meter Breaker Pedestal STH 47 & Tribal Office Loop, Item 656.0200.02; Electrical Service Meter Breaker Pedestal STH 47 & Lyons Rd, Item 656.0200.03; Electrical Service Meter Breaker Pedestal STH 47 & STH 55, Item 656.0200.04; Electrical Service Meter Breaker Pedestal STH 47 & Wolf River Dr, Item 656.0200.05.

Replace standard spec 656.2.3, Meter Breaker Pedestal Service, paragraph (1) with the following:

Furnish an approved service having a meter breaker pedestal, 22,000-AIC circuit breakers unless the local utility requires otherwise, grounding electrodes and connections, conduit and fittings, and all necessary conductors and equipment required by the WSEC and the utility for a service connection. Furnish a pedestal with a 100 A 2-pole main breaker and a 30 A spare breaker. When the meter breaker pedestal is energized, install an approved meter seal at all access points on the meter trough. Meter shall be time of use type.

37. Pedestrian Push Buttons, Item 658.0500.

Replace standard spec 658.2(5) with the following:

Band a R10-25 series sign directly above each push button as the plans show.

38. Luminaires Utility LED-B, Item 659.1120.

Replace standard spec 659.2 with the following:

(2) Furnish Leotek Green Cobra LED Model #GCM2-40H-MV-NW-3R-GY-950-PCR7-WL-WISDOT-B-SC light fixtures from the WisDOT approved products list.

39. Salvage Existing Light Pole Assembly, Item SPV.0060.01.

A Description

This special provision describes removing, salvaging, and temporarily storing existing city-owned light pole assemblies, including light poles, arms and luminaries as shown on the plans and as hereinafter provided. Specific salvage items are noted in the plans.

B (Vacant)

C Construction

Arrange for the de-energizing of the lighting system with the local electrical utility after receiving approval from the engineer that the existing lighting system can be removed.

Notify the Community Development Office of the Menominee Indian Tribe of Wisconsin (MITW), (715) 799-5155 at least 3 working days prior to the removal of the lighting system.

Salvage light pole assemblies per plan from their concrete footing and disassemble out of traffic in accordance to standard spec 204 and as shown on the plans. Remove wiring/cabling per plan and dispose of properly off department right-of-way. Ensure that access handhole doors and hardware remain intact. Make a reasonable effort to inspect salvaged equipment for damage or defects.

Notify the Community Development Office of the MITW when salvaged light pole assemblies are ready for pick up. Temporarily store and protect light pole assemblies from any damage prior to pick up by the MITW.

Any material damaged by the contractor shall be replaced at the contractor's expense.

D Measurement

The department will measure Salvage Existing Light Pole Assembly as each individual Salvage Existing Light Pole Assembly, acceptably completed.

9650-17-61, 9650-17-70 26 of 44

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER DESCRIPTION UNIT SPV.0060.01 Salvage Existing Light Pole Assembly EACH

Payment is full compensation for salvaging, removing, disassembling lighting equipment, disposing of scrap material, and storage.

40. Light Pole Type 5 Special, Item SPV.0060.02.

A Description

This special provision describes furnishing and installing a WisDOT Standard Light Pole Type 5, including a festoon receptacle box and lighting assembly banner arms.

B Materials

Furnish all materials in accordance with the plans and the following applicable standard specification sections and articles:

- a) Standard spec 651 General Requirements for Electrical Work.
- b) Standard spec 655 Electrical Wiring.
- c) Standard spec 657 Poles, Arms, Standards, and Bases.
- d) Standard spec 659 Lighting

Provide aluminum WisDOT Standard Pole Type 5.

Provide two 18" long breakaway banner arms with factory welded brackets aimed perpendicular to the roadway,

The festoon GFCI receptacle shall be a 20-amp, 120 volt, duplex, ground fault interrupting premium specification in a weather-proof, cast metal receptacle box with an outdoor cover. The receptacle, box and cover shall be black. The receptacle box shall be painted to match the light pole. The outdoor cover shall be designed to be weather-proof while the receptacle is in use. The cover shall be rugged, UV resistant, non-corrosive, non-conductive, made of polycarbonate designed to protect the receptacle without cracking or breaking.

Include the wiring and additional slack wiring required to connect the receptacle circuits within the transformer base pedestal. Install wires within the light poles that are XLP, USE rated, copper, no smaller than No. 12 AWG and sized to accommodate the receptacles supplied. Fuses shall be small-dimension, 1 1/2 in. x 13/32 in., cylindrical fuses of the time-delay type. The fuses shall be rated for 500 V AC and meet the requirements of UL 248-14. The fuses shall have a listed interrupting rating of not less than 10,000 rms symmetrical amperes at rated voltage. They shall be sized at 300 percent of the starting or operating current whichever is greater, but in no case greater than 50 percent of the branch circuit conductor ampacity installed in accordance with WisDOT Standard Detail Drawing Electrical Handhole Wiring.

C Construction

Construct WisDOT Standard Pole Type 5 in accordance with standard spec 657.

Install the festoon receptacles at the locations shown on the plans with all necessary wiring, miscellaneous accessories, and hardware as required for a complete and fully operational unit. Follow manufacturer instructions for transportation, installation and wiring.

Mount the festoon receptacle box on the pole 10 feet above the top of the transformer base. Mount only one duplex festoon receptacle and box on each pole.

Install mounted banner arms at 14' and 17' from the bottom of the pole. Installation shall follow the supplier's recommendations, supplied to the engineer by the equipment fabricator.

Verify the mounting height and orientation of banner brackets and festoon receptacle box with the Community Development Office of MITW, (715) 799-5155 prior to the contractor installing.

9650-17-61, 9650-17-70 27 of 44

D Measurement

The department will measure Light Pole Type 5 Special as each individual light pole, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER

DESCRIPTION

UNIT

SPV.0060.02

Light Pole Type 5 Special

EACH

Payment is full compensation for fabricating and installing WisDOT Pole Type 5 with festoon receptacle box and lighting assembly banner arms. Lighting assembly banner arm shall include two lighting assembly banner arms, and mounting hardware. Festoon Receptacle Box shall include Festoon Receptacle, box, cover, wiring, fuses, and all hardware and fittings. Item includes coordination with all other construction operations.

41. Lighting Control Cabinet 120/240 30-Inch Special, Item SPV.0060.03.

A Description

This special provision describes furnishing and installing a WisDOT Lighting Control Cabinet 120/240 30-Inch except for the addition of festoon circuits and RRFB circuit as shown on plans. This special provision includes all power and control components within the cabinet as shown on the Plans and as described hereinafter.

B Materials

Furnish a WisDOT Lighting Control Cabinet 120/240 30-Inch in accordance with standard spec 659 and as shown in the plan details.

Submit shop drawings for all parts and wiring plans to the engineer for approval prior to ordering the equipment. The equipment shall not be ordered prior to approval of the shop drawings by the engineer.

C Construction

Construct the Lighting Control Cabinet in accordance with standard spec 659.

Connect the control cabinet to the concrete base in accordance with the cabinet manufacturer's recommendations and industry standards.

Place a copy of the control cabinet wiring schematic in a plastic protector and affix to the inside of the door to the cabinet.

D Measurement

The department will measure Lighting Control Cabinet Special for each unit, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBERDESCRIPTIONUNITSPV.0060.03Lighting Control Cabinet 120/240 30-Inch SpecialEACH

Payment is full compensation for furnishing and installing the lighting cabinet including circuit wiring connections, hardware, and fittings the plans show; and for making the lighting system fully operational.

42. Lane Shift, Item SPV.0060.04.

A Description

Lane Shift will consist of constructing a temporary one-lane roadway to permit the installation of culvert pipes with fill greater than 4 feet.

B Materials

Furnish fill conforming to the pertinent requirements of standard spec 208. Furnish Base Aggregate Dense conforming to the pertinent requirements of standard spec 305.

9650-17-61, 9650-17-70 28 of 44

C Construction

Place fill and base aggregate dense as needed to maintain traffic across the lane shift.

Upon completion of work requiring traffic to use the lane shift, remove materials according to standard spec 205.

D Measurement

The department will measure Lane Shift in units of each temporary roadway, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER DESCRIPTION UNIT SPV.0060.04 Lane Shift EACH

Payment is full compensation for placing, removing and disposal of fill material and Base Aggregate Dense. Traffic control and erosion control items will be measured and paid separately.

43. Sanitary Chimney Seals, Item SPV.0060.05.

A Description

This special provision describes installing an external chimney seal to sanitary manholes.

B Materials

Furnish an external Type I Flexible Watertight Frame/Chimney Joint conforming to the Standard Specifications for Sewer & Water Construction in Wisconsin, 6th Edition, December 22, 2003 with Addendum No. 1, December 22, 2004 and Addendum No. 2, April 22, 2008 Section.

C Construction

Excavate around manhole as necessary to install external chimney seal. Backfill to required plan elevations.

D Measurement

The department will measure Sanitary Chimney Seal as each individual item, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBERDESCRIPTIONUNITSPV.0060.05Sanitary Chimney SealsEACH

Payment is full compensation for excavation, sealing, and backfilling.

44. Removing Water Main Valve & Valve Box, Item SPV.0060.06.

A Description

This work shall consist of Removing Water Main Valve & Valve Boxes as shown on the plans.

B Vacant

C Construction

Remove water main valve and remove water main valve box to five feet below finish grade. Dispose of removed valve and valve boxes.

D Measurement

The department will measure Removing Water Main Valve & Valve Boxes as each individual item, acceptably completed.

9650-17-61, 9650-17-70 29 of 44

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER DESCRIPTION UNIT SPV.0060.06 Removing Water Main Valve & Valve Box EACH

Payment is full compensation for removing, excavating, backfilling, dewatering, sheeting, shoring and disposal.

45. Cap Water Main to Remain in Service, Item SPV.0060.07.

A Description

This work shall consist of furnishing and installing a pipeline cap manufactured of materials specifically intended for use as a pipeline cap on the open end of the pipeline to remain in service as shown on the plans.

B Vacant

C Construction

Cap pipelines to remain in service as shown on the plans.

D Measurement

The department will measure Cap Water Main to Remain in Service as each individual cap, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBERDESCRIPTIONUNITSPV.0060.07Cap Water Main to Remain in ServiceEACH

Payment is full compensation for excavating, backfilling, dewatering, sheeting, shoring, furnishing and installing the cap, regardless of pipe size.

46. Abandoning Water Main Valve Box, Item SPV.0060.08.

A Description

This special provision describes abandoning the existing water main valve box.

B Vacant

C Construction

Remove water main valve box to 3 feet below finish grade. Dispose of removed valve boxes. Fill remaining valve box with Class B bedding materials.

D Measurement

The department will measure Abandoning Water Main Valve Box as each individual item, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

 ITEM NUMBER
 DESCRIPTION
 UNIT

 SPV.0060.08
 Abandoning Water Main Valve Box
 EACH

Payment is full compensation for excavating, backfilling, dewatering, sheeting, shoring and disposal.

Class B bedding materials required for filling the valve box is incidental to the work.

9650-17-61, 9650-17-70 30 of 44

47. Salvage Hydrant, Item SPV.0060.09.

A Description

This special provision describes salvaging the existing hydrant and reinstalling it at a new location.

B Materials

The existing hydrant shall be reused

C Construction

Remove existing hydrant. Excavate and install hydrant in accordance with the details on the plans. Support hydrant on a concrete block.

Any material damaged by the contractor shall be replaced at the contractor's expense.

D Measurement

The department will measure Salvage Hydrant as each individual Salvage Hydrant, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBERDESCRIPTIONUNITSPV.0060.09Salvage HydrantEACH

Payment is full compensation for excavating, backfilling, dewatering, sheeting, shoring, for removing hydrant, reinstalling hydrant, drainage stone, thrust blocking and support block.

48. Adjusting Water Main Valve Box, Item SPV.0060.10.

A Description

This special provision describes adjusting the water main valve box.

B Vacant

C Construction

Excavate around the existing water main valve box as necessary and rotate the valve box assembly to position top at the required elevation. Furnish and install valve box extensions as necessary.

D Measurement

The department will measure Adjusting Water Main Valve Box for adjustments at each location, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBERDESCRIPTIONUNITSPV.0060.10Adjusting Water Main Valve BoxEACH

Payment is full compensation for excavating, backfilling, dewatering, sheeting, shoring, and installing extensions.

49. Adjusting Hydrant, Item SPV.0060.11.

A Description

This special provision describes adjusting the existing hydrant.

B Vacant

9650-17-61, 9650-17-70 31 of 44

C Construction

Excavate around the existing hydrant as necessary to install or remove extensions to obtain the required elevation. Furnish and install extensions as necessary.

D Measurement

The department will measure Adjusting Hydrant for adjustment at each location, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER DESCRIPTION UNIT SPV.0060.11 Adjusting Hydrant EACH

Payment is full compensation for excavating, backfilling, dewatering, sheeting, shoring, and extensions.

50. Water Main Gate Valve & Box 6-Inch, Item SPV.00060.12.

A Description

This work shall consist of furnishing and installing gate valves and valve boxes at the locations as shown on the plans.

B Materials

B.1 Valves

- a) Kennedy
- b) Waterous
- c) Mueller A 2360-20Or similar
- d) Resilient wedge (AWWA C-515)
- e) Epoxy lined per AWWA C550
- f) Stainless steel hardware

B.2 Valve Boxes

- a) Tyler
- b) Mueller
- c) East Jordan American made
- d) Or similar
- e) Cast iron valve boxes shall meet the requirements of Chapter 8.29.0 of the Standard Specifications. Furnish extension if required to meet existing surface or finished grades.
- f) 3 piece, screw type box with 5-1/4" shaft and no-tilt drop cover marked "Water".

C Construction

Provide sufficient quantities of crushed stone or rock conforming to the requirements of ASTM C33, Gradation No. 2 over and around the valve to prevent sand blockages of the valve bonnet and box.

Install gate valves and valve boxes in accordance with the requirements of the "Standard Specifications for Sewer and Water Construction in Wisconsin," Sixth Edition, dated December 22, 2003, including all Addenda thereto.

D Measurement

The department will measure 6-inch Gate Valve & Box, as each individual valve and box, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER DESCRIPTION UNIT SPV.0060.12 Water Main Gate Valve & Box 6-Inch EACH

9650-17-61, 9650-17-70 32 of 44

Payment is full compensation for excavating, backfilling, dewatering, sheeting, shoring, for furnishing and installing gate valves, adjusting valve box height, for furnishing and installing bolts, nuts, and gaskets.

51. Tracer Wire Access Box, Item SPV.0060.13.

A Description

This special provision describes furnishing and installing tracer wire access box.

B Materials

The tracer wire access box shall include an ABS tube, cast iron cover and collar and locking cover.

C Construction

The tracer wire access box cover shall be set flush with the surface after final grading is completed.

D Measurement

The department will measure Tracer Wire Access Box as each individual tracer wire access box, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBERDESCRIPTIONUNITSPV.0060.13Tracer Wire Access BoxEACH

Payment is full compensation for providing all materials, installing, connecting, and cleanup.

52. Water Main Coupling 6-Inch, Item SPV.0060.14; Water Main Bend 45-Degree 6-Inch, Item SPV.0060.15.

A Description

This work shall consist of furnishing and installing water main fittings of various sizes and type in the locations as shown on the plans.

B Materials

- 1. Water main fittings shall be push on or mechanical joint (mechanical joint where tie rods are required) and shall meet the requirements of Chapter 8.22.0 of the Standard Specifications.
- 2. Compact style fittings per AWWA C153 are acceptable.
- 3. Cement lined per AWWA C104.
- 4. Cor-Blue T-bolt required for mechanical joint.

C Construction

Install in accordance with the requirements of the "Standard Specifications for Sewer and Water Construction in Wisconsin," Sixth Edition, dated December 22, 2003, including all Addenda thereto, and the requirements of the bid item Water Main.

D Measurement

The department will measure water main couplings and bends as each individual fitting, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0060.14	Water Main Coupling 6-Inch	EACH
SPV.0060.15	Water Main Bend 45-Degree 6-Inch	EACH

9650-17-61, 9650-17-70 33 of 44

Payment is full compensation for excavating, backfilling, dewatering, sheeting, shoring, for furnishing and installing water main fittings.

53. Water Main Tapping Sleeve 6x6-Inch, Item SPV.0060.16.

A Description

This special provision describes furnishing and installing water main tapping sleeves of the size and type described on the plans, meeting the requirements of the plans, the "Standard Specifications for Sewer and Water Construction in Wisconsin," Sixth Edition, dated December 22, 2003, including all Addenda thereto, the requirements for the Bid Item Water Main, and as hereinafter described.

B Materials

Provide restrained joint fittings conforming to Chapter 8.22.0 of the "Standard Specifications for Sewer and Water Construction in Wisconsin," Sixth Edition, dated December 22, 2003, including all Addenda thereto; compact style in accordance with AWWA C153; cement line conforming to AWWA C104.

Tapping Sleeve shall be Smith Blair 665, Romac Industries SSTIII, or approved equal.

Mega Lugs required for all thrust restraints.

C Construction

Install in accordance with the requirements of the "Standard Specifications for Sewer and Water Construction in Wisconsin," Sixth Edition, dated December 22, 2003, including all Addenda thereto, and the requirements of the bid item Water Main.

D Measurement

The department will measure Water Main Tapping Sleeve (size) as a single unit, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBERDESCRIPTIONUNITSPV.0060.16Water Main Tapping Sleeve 6x6-InchEACH

Payment is full compensation for furnishing all materials; for all excavations; for sheeting and shoring, laying pipe, and making connections to all new or existing facilities; for furnishing all bedding material; dewatering; for backfilling and compaction, testing and disinfection of water mains, testing of backfill compaction, removing sheeting and shoring, cleanup, and restoring the site of the work.

54. Steel Plate Beam Guard Connection, Item SPV.0060.17.

A Description

This special provision describes providing the work to make connections from existing steel plate beam guard to new steel plate beam guard.

B Materials

Furnish all bolts, connector plates, and other necessary materials to complete the connection.

C Construction

Connect to existing guardrail at the nearest post or midrail section.

D Measurement

The department will measure Steel Plate Beam Guard Connection by each, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER DESCRIPTION UNIT
SPV.0060.17 Steel Plate Beam Guard Connection EACH

9650-17-61, 9650-17-70 34 of 44

Payment is full compensation for furnishing all materials and for making connections.

55. Concrete Curb and Gutter 24-Inch Type D, Item SPV.0090.01.

A Description

This special provision describes constructing concrete curb, concrete curb and gutter, and concrete gutter according to the details shown in the plans, the requirements of standard spec 601.

B Materials

Provide materials that conform to the requirements of standard spec 601.2.

C Construction

Construct according to the requirements of standard spec 601.3.

D Measurement

The department will measure Concrete Curb and Gutter 24-Inch Type D in length by the linear foot, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item(s):

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0090.01	Concrete Curb and Gutter 24-Inch Type D	LF

Payment will be made according to standard spec 601.5.

ncr-601-015 (20141015)

56. Water Main 6-Inch, Item SPV.0090.02.

A Description

This work shall consist of excavating required trenches, furnishing and installing water mains and tracer wires and backfilling the trenches, as shown on the plans and contract as hereinafter provided.

B Material

B.1 General

Water mains installed in trenches shall be PVC with push on or mechanical joints. PVC water mains shall be installed with tracer wire.

B.2 PVC Pipe

PVC pipe shall conform to AWWA C900, pressure class 150, SDR 18, cast iron outside diameter.

B.3 Pipe Joints

Joints for PVC pipe shall be elastomeric gasket type meeting ASTM F477 and assembly shall be per AWWA M23.

At fittings, also restrain pipeline joints for the following length from fittings:

	Restrained L	<u>-ength (feet)</u>	
Pipe Size (In)	45° Bend	90° Bend	Tee Hydrant or Dead End
6	11	20	14
8	19	34	24
10	28	51	36
12	39	73	51

Joints for copper pipe shall be compression fitting type joints.

9650-17-61, 9650-17-70 35 of 44

B.4 Tracer Wire

Tracer Wire shall be 14 gauge AWG solid copper wire with 15 mil polyethylene coating, blue color.

Tracer wire joints shall be wrapped splices with solder or cadweld bonding of the copper wire, split bolt connections or compression connections (wire nuts not permitted). All exposed areas should be wrapped to provide a watertight joint.

Tape the tracer wire to the top of the utility pipeline every 10 feet.

C Construction

C.1 General

Manipulation of existing valves required in order to construct work shall be performed by the Menominee Indian Tribe of Wisconsin only. Contact the Menominee Indian Tribe of Wisconsin at least 48 hours in advance to coordinate and schedule any required valve manipulation. Contact Marlin Waupoose at (715) 799-3587.

Water customers shall not have their water service interrupted for more than 4 hours per day. Customers scheduled for interruption shall be notified at least 24 hours in advance.

C.2 Performance Tests

C.2.1 Hydrostatic Pressure Test

- (1) After pipe and appurtenances have been constructed, perform a hydrostatic pressure test.
 - (a) Necessary equipment includes: test plugs, reaction blocking, hoses, pressure gauges, measuring devices, and hand pumps, to perform the work required in connection with the tests.
- (2) Slowly fill each test section with water, care being taken to expel all air from the pipes.
- (3) Tap the pipe, if necessary, at high points to vent the air.
- (4) Maintained at 150 P.S.I. for at least one hour.
- (5) Tighten leaks found at mechanical joints, until the leaking stops.
 - (a) Remove and replace any cracked or defective pipes, fittings, valves or joints discovered as a consequence of the pressure test with sound material, and the test shall be repeated until satisfactory.
 - (b) Leakage Test
 - i. After the pipe has been subjected to the above pressure test, a leakage test as described herein shall be performed.
 - ii. If water does not have to be added to the pipeline during the pressure test, to maintain 150 psi, the requirement for the leakage test may be waived.
 - Necessary equipment includes: test plugs, reaction blocking, hoses, pressure gauges, measuring devices and hand pumps, to perform the work required in connection with the tests.
 - iii. The duration of each leakage test is two hours.
 - iv. The main pressure during the test is 150 P.S.I.
 - v. Leakage is defined as the quantity of water to be supplied into the newly laid pipe, or any valved section thereof necessary to maintain the specified test pressure after the pipe has been filled with water and the air expelled.
 - vi. The engineer will approve the system of measuring this volume of water prior to commencement of the test.
 - vii. The maximum leakage in gallons per hour is determined by the following equation:

$$L = SD \times (P)^{1/2} 133,200$$

L = allowable leakage in gallons per hour S = length of pipeline tested in feet

D = nominal diameter of the pipe in inches P = test pressure in psig

9650-17-61, 9650-17-70 36 of 44

^{*}Based on 11.65 gpd per mile of pipe per inch of nominal diameter, at 150 psi.

a. The allowable leakage per 1,000 feet of pipeline is as follows:

Pipe Size (in.)	Allowable Leakage (gpd)
4	0.37
6	0.55
8	0.74
10	0.92
12	1.10
14	1.29
18	1.66

- b. In case the section under test contains joints of various diameters, the allowable leakage will be the sum of the computed leakage for each size of joint.
- viii. Should the test disclose leakage greater than that permitted, locate and repair the defective pipe until the leakage is within the specified allowance.
- (c) Continuity Test

Perform tracer wire continuity testing utilizing a standard 5 watt generator to provide an AC current restricted to 33 kHz or less.

C.2.2 Presentation of Test Results

- (1) At the conclusion of the Performance Tests, the Owner or Owner's representative will furnish a written report or the results of the tests.
- (2) The report will identify the specific type and length of pipe tested, the pressures, the duration of the test, the amount of leakage, etc.
- (3) The report will be signed by the contractor.

C.3 Disinfection of Complete Watermains

AWWA C-651 Standard for Disinfecting Watermains.

Clean the main prior to disinfection, except when using the tablet method.

Chlorinate main using one of the following forms of chlorine:

- (1) Liquid Chlorine in combination with a solution feed, vacuum operated chlorinator and a booster pump.
- (2) Calcium or Sodium Hypochlorite solution injected into the main with achemical feed pump.
- (3) Calcium Hypochlorite tablets, 5 grams each containing approximately 65 percent available chlorine by weight.
- (4) Calcium Hypochlorite tablets may not be used on solvent-welded plastic or on screw-joint steel pipe.

Methods of Chlorine Application:

- (1) Continuous Feed Method:
 - (a) Flow water from the existing distribution system at a constant, measured rate into the newly-laid pipeline.
 - (b) Feed the chlorine dose at a constant, measured rate.
 - (c) Proportion the two rates to deliver chlorine concentration at a minimum of 25 mg/l available chlorine. Fill the entire main is with chlorine solution.
 - (d) Retain the chlorinated water in the main for at least 24 hours. Operate all valves and hydrants in the section treated to disinfect the appurtenances.
 - (e) At the end of the 24 hour period, a 10 mg/l free chlorine residual throughout the length of the main is required.
 - (f) If the initial disinfection fails to produce a free chlorine residual of 10 mg/l, rechlorinated the main with 25 mg/l available chlorine until a residual of 10 mg/l is obtained.

9650-17-61, 9650-17-70 37 of 44

(2) Slug Method

- (a) Flow water from the existing distribution system at a constant, measured rate into the newly laid pipeline.
- (b) Feed the chlorine dose at a constant, measured rate.
- (c) Proportion the two rates so that the chlorine concentration in the water entering the pipeline is maintained at no less than 100 mg/l.
- (d) Apply the chlorine continuously and for a sufficient period to develop a solid column or "slug" or chlorinated water that will, as it passes along the line, expose all interior surfaces to a chlorine concentration of at least 100 mg/l for at least 3 hours.
- (e) As the chlorinated water flows past tees and crosses, operate related valves and hydrants to disinfect appurtenances.

(3) Tablet Method

- (a) During construction place, 5 gram calcium hypochlorite tablets in each section of pipe.
- (b) Place one such tablet in each hydrant, hydrant branch and other appurtenance.
- (c) The number of 5 gram tablets required for each pipe section to provide a dose of 25 mg/l shall be 0.0012 *dL* rounded to the next higher integer, where *d* is the inside pipe diameter, in inches, and *L* is the length of the pipe section, in feet.
- (d) The number of tablets required for various pipe diameters is as follows:

Pipe Diameter (in.)	Number of Tablets 13 Ft. Pipe	Length 20 Ft. Pipe Length
4	1	1
6	1	1
8	1	2
10	2	3
12	3	4
16	4	7

- (e) Attach the tablets with a food-grade adhesive.
- (f) Tablet adhesive only on the broadside attached to the surface of the pipe.
- (g) Attach all the tablets inside and at the top of the main, with approximately equal numbers of tablets at each end of a given pipe length.
- (h) If the tablets are attached before the pipe section is placed in the trench, mark their position on the section so it can be readily determined that the pipe is installed with the tablets at the top.
- (i) When installation has been completed, fill the main at a velocity no greater than 1 foot per second.
- (j) Take precautions to eliminate air pockets.
- (k) Chlorinate pipe for at least 24 hours.
- (I) If the water temperature is less than 41^OF, chlorinate the pipe for at least 48 hours.
- (m) After the applicable retention period, flush the heavily chlorinated water from the main until chlorine concentration in the water leaving the main is no higher than 1 mg/l.
- (n) Direct discharge from the watermain to the ground or surface waters may not be allowable. A WPDES (Wisconsin Pollutant Discharge Eliminate System) general permit is required for discharges of chlorinated water out of hydrants or watermains.
- (o) WPDES general permits are available from the DNR area district wastewater engineer.

9650-17-61, 9650-17-70 38 of 44

Following a satisfactorily observed chlorine residual and flushing, two successive sets of samples taken at 24 hour intervals, will be tested for bacteriological analysis:

- (1) Furnish a sampling tap consisting of a standard corporation cock installed in the main with a copper tube gooseneck assembly.
- 2) After sampling remove the gooseneck assembly and retained for future use.
- (3) Obtain one bacteriologically safe water sample from each location prior to the main being placed into service.

After disinfection has been completed open all valves and the facilities be placed in operation.

D Measurement

The department will measure Water Main (size) by the linear foot, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER DESCRIPTION UNIT

SPV.0090.02 Water Main 6-Inch

LF

Payment is full compensation for all excavating, backfilling, dewatering, sheeting, shoring, removing existing watermain, for furnishing and installing watermains, bedding material, initial backfill, and all test procedures.

57. Construction Staking Sidewalk, Item SPV.0090.03.

A Description

This special provision describes contractor-performed construction staking required for sidewalk to establish the horizontal and vertical position.

B (Vacant)

C Construction

Conform to the requirements in standard spec 650.3.1.

Set constructions stakes or marks at 50-foot intervals, maximum. Set and maintain stakes as necessary to achieve the required accuracy and to support the method of operations. Set additional construction stakes as necessary to establish location and grade of sidewalk, including points where alignment or grade changes, along intersecting radii, and at the radius points of intersecting road radii. Locate stakes to within 0.02 feet horizontally and establish elevations to within 0.01 feet vertically.

D Measurement

The department will measure Construction Staking Sidewalk by the linear foot, acceptably completed, measured along the sidewalk reference line.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBERDESCRIPTIONUNITSPV.0090.03Construction Staking SidewalkLF

The department will not make final payment until the contractor submits survey notes and computations used to establish the required lines and grades to the engineer within 21 days of completing this work. The department will deduct from payments due the contractor for the additional costs specified in standard spec 105.6.

Payment is full compensation for locating and setting construction stakes; for adjusting stakes to ensure compatibility with existing field conditions; and for relocating and resetting damaged or missing construction stakes.

9650-17-61, 9650-17-70 39 of 44

58. Rectangular Rapid Flashing Beacon System STH 47 & Warrington Road, Item SPV.0105.01.

A Description

This work shall consist of furnishing and installing an AC powered Rectangular Rapid Flashing Beacon (RRFB) system. The RRFB shall be hardwired and pedestrian-activated by a pushbutton as shown on the plans.

B Materials

B.1 General Requirements

The RRFB shall be in conformance with all applicable FHWA MUTCD standards and guidelines and shall meet or exceed the requirements specified in FHWA Memorandum IA-21, Interim Approval for Optional Use of Pedestrian-Actuated Rectangular Rapid-Flashing Beacons at Uncontrolled Marked Crosswalks.

Furnish a crosswalk assembly with one light bar or two light bars mounted back-to-back and shall employ mounting bracket for several post type/size options. See applicable plans for whether assemblies require one light bar or two light bars. Each light bar shall house three LED light arrays: two rapidly and alternately flashing rectangular amber (vehicle) indications and one amber side-mounted (pedestrian) indication. The AC-powered system shall utilize one controller with remote hardwired light bars and pushbuttons. The system shall be capable of an integrated 900 MHz radio.

The Pedestrian Indication LEDs shall be side-mounted so as to be visible to pedestrians in the crosswalk, and shall flash concurrently with the vehicle indications to confirm that the RRFB is in operation.

The RRFB system shall be pedestrian-activated, utilizing ADA compliant Push Buttons that are hardwired. The activation and deactivation of all indications shall be synchronized. Active vehicle indications shall be visible in a direct line of sight at distances over 1000 feet during the day, and over 1 mile at night.

The system shall be AC powered with applicable circuit breaker and Lightning suppression.

B.2 Hardware Requirements

(A) System

- 1. The System shall operate on AC power.
- Upon activation by ADA-compliant pushbutton, there are two ways the system can be activated; hardwired to all light bars, or if used, an integrated 900 MHz transceiver radio shall wirelessly activate all integral indications, using spread spectrum radio frequency to minimize RF interference.
- 3. When activated, all indications associated with a given crosswalk shall simultaneously commence operation within 120msec and shall cease operation at a predetermined time (programmable timeout) after any pedestrian actuation.
- 4. Flash rates with the frequencies of 5 to 30 flashes/second shall not be used to avoid inducing seizures.
- 5. The duration of the flash cycle (timeout) shall be programmable from 1 second to 24 hours, in increments of seconds.
- Individual components shall be independently replaceable, equipped with approved terminal strips or wire-end molded connectors.

(B) RRFB Controller

- 1. Shall be completely programmable, including flash pattern and duration.
- 2. Shall seamlessly integrate with the 900 MHz FHSS wireless transceiver to form a network of connected devices, if required.
- 3. Shall allow ADA compliant pushbuttons.

9650-17-61, 9650-17-70 40 of 44

(C) Power Supply

1. Shall be powered by 120 VAC to 12 VDC.

(D) Enclosure

- 1. Shall be constructed of aluminum, no less than 0.080" thickness.
- 2. Shall be vented to promote airflow for internal components.
- 3. Shall include screening on all vents and drains to deter insects and foreign matter.
- 4. Shall include a replaceable #2 traffic lock and keys.
- 5. Shall utilize tamper-resistant stainless steel hinges.
- 6. Shall include a removable control panel to which all control circuit components mount.

B.3 Material Specifications

Furnish a complete RRFB system with single or multiple assemblies. Each assembly may consist of, but is not limited to, controller and electrical components (including wiring and solid-state circuit boards) and LED indications in a light bar. An assembly may include the following items:

(A) Light Indications

- 1. The light bar housing shall be constructed of durable, corrosion-resistant powder-coated aluminum with stainless steel fasteners.
- 2. Enclosed components shall be modular in design whereby any component can be easily replaced using common hand tools, without having to remove the housing from the pole.
- 3. All mounting hardware required for mounting the light bar housing shall be provided and universal to multiple poles.
- 4. Each indication shall be a minimum size of approximately 5" wide x 2" high.
- 5. A pedestrian LED indication shall be side-mounted in the light bar housing: assembly to be mounted so it is directed toward, and visible to, pedestrians in the crosswalk.
- 6. The outside edges of the two indications, including any housing, shall not protrude beyond the outside edges of the integral signage of the assembly.
- 7. The light intensity of the indications shall meet the minimum specifications for Class 1 yellow peak luminous intensity in the Society of Automotive engineers (SAE) standard J595 (Directional Flashing Optical Warning Devices for Authorized Emergency, Maintenance, and Service Vehicles) dated January 2005.
- 8. All exposed hardware shall be anti-vandal.
- To minimize excessive glare during nighttime conditions, an automatic signal dimming device should be used to reduce the brilliance of the RRFB indications during nighttime conditions.

(B) Controller

- The Controller shall be housed in a NEMA type aluminum enclosure intended for indoor or outdoor use, primarily to provide a degree of protection against corrosion, windblown dust and rain, splashing water, hose-directed water and damage from ice formation.
- 2. The Controller shall be, in the unlikely event of failure, replaceable independently of other components.

(C) Signs

All signs shall be supplied and installed under separate bid items. However, the assemblies
must be constructed to allow the appropriate space for the installation of the signs in the
field.

(D) Pushbutton

1. The pushbutton shall be supplied and installed under a separate bid item.

9650-17-61, 9650-17-70 41 of 44

- (E) Traffic Signal Standards Aluminum 13-FT
 - 1. The traffic signal standard shall be supplied and installed under a separate bid item.
- (F) Pedestal Base
 - 1. The pedestal base shall be supplied and installed under a separate bid item.
- (G) Concrete Base
 - The concrete base and anchor bolts shall be supplied and installed under a separate bid item.
- (H) Hardware
 - 1. Furnish all hardware, connections, etc to make the RRFB system fully operational.

B.4 Warranty

The system shall be supported by a three-year manufacturer's warranty.

C Construction

The RRFB system will consist of multiple assemblies to be constructed by the contractor as shown on the plans. Make the RRFB system fully operational.

D Measurement

The department will measure Rectangular Rapid Flashing Beacon System STH 47 & Warrington Road as a single lump sum unit, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item.

ITEM NUMBERDESCRIPTIONUNITSPV.0105.01Rectangular Rapid Flashing Beacon System STH 47 & Warrington RoadLS

Payment is full compensation for furnishing and installing a fully operational RRFB system.

Temporary Stream Diversion Pipes, Keshena Lake Outlet, Item SPV.0105.02.

A Description

This special provision describes delivering, installing, and maintaining temporary stream diversion pipes to divert flow around construction of the Structure C-73-4 in accordance to standard spec 205, 520, and 628, as shown on the plans, and as herein provided.

B Materials

B.1 Culvert Pipe Temporary

Culvert pipe temporary shall be in accordance to standard spec 520.2.6.

B.2 Backfill

Backfill shall be in accordance to standard spec 520.2.5.3.

B.3 Silt Fence

Silt fence shall be in accordance to standard spec 628.2.6.

B.4 Sand Bags

Sand bags shall be in accordance to standard spec 628.2.8.

Cellular Concrete

Provide cellular concrete meeting the following specifications: 1 part cement, 1 part fly ash, 8 parts sand, or an approved equal, and water. Provide cement meeting the requirements of standard spec 501.2.1 for Type I Portland Cement. Provide sand meeting the requirements of standard spec 501.2.5.3. Provide water meeting the requirements of standard spec 501.2.4.

9650-17-61, 9650-17-70 42 of 44

C Construction

C.1 General

Install silt fence prior to excavation.

Construct temporary stream diversion pipes in accordance to standard spec 520.3.1.

C.2 Excavating and Constructing Foundations for Pipe Culverts

Excavate and construct foundations for the temporary stream diversion pipes in accordance to standard spec 520.3.2.2.

C.3 Laying Pipe

Lay temporary stream diversion pipes in accordance to standard spec 520.3.3.

C.4 Backfilling Trenches

Backfill temporary stream diversion pipes in accordance to standard spec 520.3.4.2.

C.5 Abandoning Pipe

Plug both ends of the pipe to be abandoned as directed in standard spec 204.3.3.1. Tap the pipe where necessary and fill from these locations with cellular concrete.

C.6 Diversion Channel Staging

The temporary diversion pipes must be fully constructed before removal of the existing culvert begins. Use sand bags or similar methods to direct water in the main channel away from the mouth of the diversion to allow installation of the pipes at the upstream end of the temporary diversion. Divert the flow of the main stream into the temporary diversion after construction of the temporary pipes are complete.

Once the flow is diverted to the temporary pipes, remove the existing culvert and construct the culvert in two stages in order to maintain a single lane of traffic for the duration of construction. The temporary diversion pipe limits fall within the limits of the proposed riprap. As a result, some of the riprap will not be placed prior to flow being restored to the stream. Place all riprap outside the limits of the temporary diversion pipes prior to flow being restored to the stream.

Once the riprap is placed, restore the flow through the culvert. Remove the temporary stream diversion pipes and their components to the maximum extent practicable without impacting traffic. Fill with the original excavated material if deemed suitable by the engineer to the bottom of final roadway subgrade elevation and compact the material. Coarse Aggregate No. 2 may be used as fill. Dispose of temporary culvert pipes, sand bags, and any excess material. Abandon in place all remaining portions of the temporary diversion pipes. Place the remaining riprap to the extents shown in the plan.

D Measurement

The department will measure Temporary Stream Diversion Pipes, Keshena Lake Outlet as a single lump sum unit of work, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid items:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0105.02	Temporary Stream Diversion Pipes, Keshena Lake Outlet	LS

Payment is full compensation for installing, removing, and disposing of temporary culvert pipes (including bends) and sandbags for abandoning pipe, including brick, concrete block and cellular concrete; and for restoring the alignment and flow to the natural or relocated stream.

Excavation and miscellaneous backfill (excluding Backfill Structure) for the Temporary Stream Diversion Pipes shall be paid for separately under the bid item Excavation for Structures.

The department will pay separately for silt fence required for the Temporary Stream Diversion.

60. Preparing Topsoil for Lawn Type Turf, Item SPV.0180.01.

A Description

This special provision describes preparing the bed of topsoil or salvaged topsoil, for seeding or placing sod.

9650-17-61, 9650-17-70 43 of 44

B (Vacant)

C Construction

Prepare and finish the subgrade so that rocks, concrete debris, or wood larger than three inches in diameter are not present within 1 foot of the finished surface of the topsoil.

Remove or break down all clods and lumps in the topsoil by using harrows or discs, screening, or other appropriate methods to provide a uniformly textured soil, in which 100 percent of the topsoil passes a one-inch sieve and at least 90 percent passes a No. 10 sieve.

Remove rocks, twigs, clods, and other foreign material that will not break down, and dress the entire surface to present a uniform appearance.

Shape the topsoil so that the horizontal or sloped surface between any two points ten feet apart does not vary by more than one inch. Roll with a turf type roller to a uniform minimum compacted depth of 6 inches.

Shape and compact the topsoil adjacent to pavements, sidewalks, and curbs to 1 inch below the top of the abutting surface. Before seeding, correct locations that vary by more than \(\frac{1}{4}\)-inch.

D Measurement

The department will measure Preparing Topsoil for Lawn Type Turf, acceptably completed, in area by the square yard.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBERDESCRIPTIONUNITSPV.0180.01Preparing Topsoil for Lawn Type TurfSY

Payment is full compensation for preparing the subgrade and topsoil bed for sod or seed as described above.

ncr-625-005 (20150430)

9650-17-61, 9650-17-70 44 of 44

ADDITIONAL SPECIAL PROVISION 3

DISADVANTAGED BUSINESS ENTERPRISE [DBE] PROGRAM IMPLEMENTATION

1. Description

- a. The federal DBE program requirements outlined in the Code of Federal Regulations at 49 CFR Part 26 apply to this Wisconsin Department of Transportation contract. WisDOT is a recipient of federal funds and this contract includes federal funds. United States Department of Transportation Federal DBE Program requires the following provisions:
 - (1) Pursuant to the federal DBE program regulation at 49 CFR Part 26, a contractor's failure to comply with any provision of the DBE regulations will be considered a material breach of contract. This is non-negotiable. If a contractor fails to carry out the DBE program and Title VI nondiscrimination requirements of its contracts, the following sanctions will be assessed depending upon the facts, reasoning, severity and remedial efforts of the contractor: termination of contract, withholding payment, assessment of monetary sanctions, assessment of liquidated damages and/or suspension/debarment proceedings that may result in the disqualification of the contractor from bidding for a designated period of time.
 - (2) The contractor shall utilize the specific DBEs listed to perform the work and supply the materials for which each is listed unless the contractor obtains the federal fund recipient's [DOT] written consent. Unless [WisDOT] consent is provided, the contractor shall not be entitled to any payment for work or material unless it is performed or supplied by the listed DBE.
- b. The Wisconsin Department of Transportation [WisDOT] is committed to the compliant administration of the DBE Program. Each WisDOT Secretary affirms this commitment with his/her signed assurance. https://wisconsindot.gov/Documents/doing-bus/civil-rights/dbe/policy-statement.pdf
 - (1) The department encourages the contractor to assist and develop DBE firms to become fully knowledgeable contractors to successfully perform on its contracts. Under the contract, the contractor agrees to provide the assistance to participating DBE's in the following areas:
 - i. Produce accurate and complete quotes.
 - ii. Understand highway plans applicable to their work.
 - iii. Understand specifications and contract requirements applicable to their work.
 - iv. Understand contracting reporting requirements.
 - (2) Wisconsin DOT identifies the assigned DBE goal in its contract advertisements and posts the contract DBE goal on the cover of the bidding proposal. The contractor can meet the assigned, specified contract DBE goal by subcontracting work to a DBE or by procuring services or materials from a DBE. The department calculates the DBE participation as the dollar value of DBE participation included in the bid expressed as a percentage of the total contract bid amount.
 - (3) For more comprehensive information on the disadvantaged business program, visit the department's Civil Rights and Compliance Section website at: https://wisconsindot.gov/Pages/doing-bus/civil-rights/dbe/default.aspx

2. Definitions

Interpret these terms, used throughout this additional special provision, as follows:

- a. Bid Percentage: The DBE percentage indicated in the bidding proposal at the time of bid.
- b. **DBE:** A small business certified as disadvantaged business enterprise (DBE) under the federal DBE program and included on the Wisconsin UCP DBE Directory deemed ready, willing and able.
- c. **DBE goal:** The amount of DBE participation expected in the contract as shown on the cover of the Highway Work Proposal.
- d. **Manufacturer:** A firm that operates or maintains a factory or establishment that produces, on the premises, the materials, supplies, articles, or equipment required under the contract.
- e. **Supplier:** A firm that owns, operates, or maintains a store, warehouse, or other establishment in which the materials, supplies, articles or equipment required under the contract are bought, kept in stock, and regularly sold or leased to the public.
- f. **Voluntary Achievement:** The amount of DBE participation achieved and reported in the contract in excess of the assigned goal.

3. DBE Percentage Required at Bid Submission

Indicate the bid percentage (i.e. 0% through 100%) of DBE participation on the completed bidding proposal. For electronic submittals, show the percentage in the miscellaneous data folder, Item 3, DBE Percent. For paper submittals, show the percentage on the sheet included after the schedule of items. By submission of the bid, the bidder contractually commits to DBE participation at or above the bid percentage, or certifies that they have utilized comprehensive good faith efforts to solicit and utilize DBE firms to meet the DBE participation requirements of this contract proposal, and that the bid percentage is reflective of these good faith efforts. The bid percentage should demonstrate the efforts of the prime contractor prior to bid. If the bidder does not indicate the bid percentage of DBE participation on the completed bidding proposal, the department will consider the bid irregular and may reject the bid.

4. WisDOT Interpretation of Federal DBE Program Provision

Prime contractors must utilize the specific DBEs listed to perform the work and/or supply the materials for which each is listed on the Commitment to Subcontract to DBE Form [DT1506] and approved by WisDOT's DBE office to execute its contract. The approved Commitment to Subcontract to DBE Form [DT1506] becomes a contract document/record.

a. Department's DBE Evaluation Process

WisDOT evaluates DBE using the Commitment to Subcontract to DBE, payments to subcontractors and contract documentation. The prime contractor shall list the specific DBE certified firms and items of work s/he intends to use toward the fulfillment of the assigned DBE contract goal. The prime contractor receives DBE credit for payments made to the DBE firms performing the work listed on the approved Form DT1506.

b. Documentation Submittal

The contractor is to identify, by name, the DBE firms whose utilization is intended to satisfy this provision, the items of work of the DBE subcontract or supply agreement and the dollar value of those items of work by completing the Commitment to Subcontract to DBE Form [DT1506]. Effective January 1, 2017, the contractor will be required to submit the documentation within 5 business days after bid opening. All necessary supporting documentation including Attachment 'A' forms and/or Good Faith Efforts Form

[DT1202] must be submitted no later than 2 business days from contractor's initial submission of the DT 1506. The contractor must provide a signed Attachment 'A' form to the DBE office within the time limit in order to receive authorization for contract execution; the DBE office reserves the right accept alternate documentation in lieu of the signed form in extenuating circumstances. Documentation must be submitted to the DBE Office by email at DBE_Alert@dot.wi.gov (DBE_Alert@dot.wi.gov) or by postal mail ATTN: DBE Office, PO Box 7965, Madison, WI 53707-7965.

(1) Bidder Meets DBE Goal

If the bidder indicates that the contract DBE goal is met, after award and before execution, the department will evaluate the Commitment to Subcontract to DBE Form DT1506 and attachment A(s) to verify the actual DBE percentage calculation. If the DBE commitment is verified, the contract is eligible for execution with respect to the DBE commitment.

(2) Bidder Does Not Meet DBE Goal

- i. If the bidder indicates a bid percentage on the Commitment to Subcontract to DBE Form [DT1506] that does not meet the contract DBE goal, the bidder must submit a Good Faith Efforts Form [DT1202] and supporting documentation. After award and before execution, the department will evaluate the bidder's DBE commitment and consider the bidder's good faith efforts submission.
- ii. The department will evaluate the bidder's good faith effort request and notify the bidder of one of the following:
 - (a) If the department grants a good faith efforts, the bid is eligible for contract execution with respect to DBE commitment.
 - (b) If the department rejects the good faith efforts request, the department may declare the bid ineligible for execution. The department will provide a written explanation of why the good faith efforts request was rejected. The bidder may appeal the department's rejection as allowed under 7 a. & b.

c. Bidder Fails to Submit Documentation

If the contractor fails to furnish the Commitment to Subcontract to DBE Form [DT1506] within the specified time, the department may cancel the award. Delay in fulfilling this requirement is not a cause for extension of the contract time and shall not be used as a tool to delay execution.

5. Department's Criteria for Good Faith Effort

Appendix A of 49 CFR Part 26, is the guiding regulation concerning good faith efforts. However, the federal regulations do not explicitly define "good faith" but states that bidder must actively and aggressively attempt to meet the goal. The federal regulations are general and do not include every factor or effort that can be considered. As a result, each state must establish its own processes and consider the factors established in its own practices to create a process for making a determination of adequate good faith. WisDOT evaluates good faith on a contract basis just as each contract award is evaluated individually.

The department will only approve a contractor's good faith efforts if the bidder has made the effort, given the relevant circumstances under the contract that a bidder actively and aggressively seeking to meet the goal would make. The department will evaluate the bidder's good faith effort to determine whether a good faith efforts will be granted. The bidder must demonstrate, on the DT1202 that they have aggressively solicited DBE participation in an attempt to meet the contract DBE goal and attaining the stated DBE goal is not feasible.

a. The department, in conjunction with industry stakeholders, has developed the following guidance for contractor good faith effort. The guidance and the attached appendices provide a framework for the actions required by all parties in the processing and evaluation of bidder's total efforts to achieve the project specific DBE goal prior to the bid letting date.

- b. Prime Contractors should:
 - (1) <u>Document</u> all efforts and decisions made toward achieving the DBE goal on the contract. The bidder should use the Civil Rights & Compliance System [CRCS] and related WisDOT- approved DBE outreach tools, including the Bid Express Small Business Network, to foster DBE participation on all applicable contracts.
 - (2) Prime contractors <u>may</u> request assistance with DBE outreach and follow-up by contacting the department's DBE Support Services Office by phone or email request at least 14 days prior to the bid letting date. Requesting assistance with outreach <u>is not</u> a decisive factor in the review Good faith effort evaluation. Phone numbers are 414-438-4584 and/or 414-659-0487; Fax: 414-438-5392; E-mail: DOTDBESupportServices@dot.wi.gov.
 - (3) Request quotes by identifying potential items to subcontract and solicit. Prime contractors are strongly encouraged to include in their initial contacts a single page including a detailed list of items for which they are accepting quotes, by project, within a letting. See attached sample entitled "Sample Contractor Solicitation Letter" in Appendix A. Prime contractors should also indicate a willingness to accept quotes in areas they are planning to perform themselves, as required by federal rules. In some cases, it might be appropriate to use DBE's to do work in a prime contractor's area of specialization.
 - i. Solicit quotes from certified DBE firms who match 'possible items to subcontract' using all reasonable and available means. Additionally, forward copies of solicitations highlighting the work areas for which you are seeking quotes to DOTDBESupportServices@dot.wi.gov.
 - ii. SBN is the preferred outreach tool. https://www.bidx.com/wi/main. Other acceptable means include postal mail, email, fax, phone call.
 - (a) Primes must ask DBE firms for a response in their solicitations. See *Sample Contractors Solicitation Letter* in Appendix. This letter can be included as an attachment to the SBN sub-quote request.
 - (b) Solicit quotes at least 10 calendar days prior to the letting date, at least two Fridays before the letting, to allow DBE firms sufficient time to respond. Prime contractors should contact DBE firms early, asking if they need help organizing their quote, assistance confirming equipment needs, or other assistance supporting their submission of a competitive quote for their services.
 - (c) Second solicitation should take place within 5 calendar days. Email and SBN are the preferred delivery of the follow-up solicitation.
 - iii. Upon request, provide interested DBE firms with adequate information about plans, specifications and the requirements of the contract by letter, information session, email, phone call and/or referral.
 - iv. When potential exists, the contractor should advise interested DBE firms on how to obtain bonding, line of credit or insurance if requested.
 - v. Document DBE firm's interest in quoting by taking appropriate steps to follow up initial solicitation with:
 - (a) Email to all prospective DBE firms in relevant work areas.
 - (b) Phone call log to DBE firms who express interest via written response or call.
 - (c) Fax/letter confirmation
 - (d) Signed copy of Bid Express SBN Record of Subcontractor Outreach Effort.
- c. <u>Evaluate DBE quotes</u> Documentation is critical if a prime does not utilize the DBE firm's quote for any reason.
 - (1) Evaluate DBE firm's capability to perform 'possible items to subcontract' using legitimate reasons, including but not limited to, *a discussion with the DBE firm* regarding its capabilities prior to the bid letting. If lack of capacity is your reason for not utilizing the DBE quote, you are required to contact the DBE by phone and email regarding their ability to perform the work indicated in the UCP directory listed as their work area by NAICS code. Only the work area and/or NAICS code listed in the UCP directory can be counted toward DBE credit. Documentation of the conversation is required.
 - (2) In striving to meet an assigned DBE contract goal, prime contractors are expected to use DBE quotes that are responsive and reasonable. This includes DBE quotes that are not the low quote.

- (3) Special Circumstance Evaluation of DBE quotes with tied bid items. "Tied quotes are the condition in which a subcontractor submits quotes including multiple areas of expertise across multiple work areas noting that the items and price are tied. Typically this type of quoting represents a cost saving to the prime but is not clearly stated as a discount; tied quotes are usually presented as 'all or none' quote to the prime." When non-DBE subcontractors submit tied bid items in their quotes to the prime, the DBE firms' quote may seem not competitive. In such a case, the following steps are taken in comparing the relevant quotes. These are qualitative examples.
 - i. Compare bid items common to both quotes, noting the reasonableness in the price comparison.
 - ii. Review quotes from other firms for the bid items not quoted by the DBE firm to see if combining both can provide the same competitive advantage that the tied bid items offered.
- d. Immediately after notification of contract award, the prime submits all 'Commitment to Subcontract' forms to the DBE Office. Prime contractor has 5 days to submit the completed form for the DBE firms it intends to use on the contract for DBE credit. If the goal is not met in full, the prime contractor must provide the following information along with WisDOT form DT1202: Certificate of Good Faith Efforts.
 - (1) The names, addresses, e-mail addresses, telephone numbers of DBE's contacted. The dates of both initial and follow-up contact.
 - (2) A description of information provided to the DBE's regarding the plans, specifications, and estimated quantities for portions of the work to be performed by that DBE.
 - (3) Photocopies or electronic copies of all written solicitations to DBE's. A printed copy of SBN solicitation is acceptable.
 - (4) Documentation of each quote received from a DBE and, if rejected, the reason for that rejection.
 - (5) Bidder attendance at any pre-solicitation or pre-bid meetings the department held to inform DBE's of participation opportunities available on the project.

The prime contractor must obtain written consent from the DBE Office to change or replace any DBE firm listed on the approved Commitment to Subcontract to DBE Form [DT1506]. If the prime contractor utilizes another contractor, including the use of its own workforce, to perform the work assigned to a DBE on the approved DT1506, the prime contractor will not be entitled to payment for that work. Any changes to DBE after the approval of the DT1506 must be reviewed and approved by the DBE office prior to the change.

6. Use of Joint Checks

The use of joint checks is allowable if it is a commonly recognized business practice in the material industry. A joint check is defined as a two-party check between a DBE, a prime contractor and the regular dealer of materials supplier who is neither the prime nor an affiliate of the prime. Typically, the prime contractor issues one check as payor to the DBE subcontractor and to the supplier jointly (to guarantee payment to the supplier) as payment for the material/supplies used by the DBE in cases where the prime has submitted the DBE and material for DBE credit. The DBE subcontractor gains the opportunity to establish a direct contracting relationship with the supplier to potentially facilitate a business rapport that results in a line of credit or increased partnering opportunities.

The cost of material and supplies purchased by the DBE is part of the value of work performed by the DBE to be counted toward the goal. To receive credit, the DBE must be responsible for negotiating price, determining quality and quantity, ordering the materials, and installing (where applicable) and "paying for the material itself." See 49 CFR 26.55(c)(1).

The approval to use joint checks constitutes a commitment to provide further information to WisDOT, upon request by staff. WisDOT will allow the use of joint checks when the following conditions are met:

- a. The Prime must request permission to use joint checks from the DBE Office by submitting the Application to Use Joint Checks.
 - (1) Request should be made when the DBE Commitment form or Request to Sublet is submitted; the request will not be considered if submitted after the DBE Subcontractor starts its work.
 - (2) Approval/Permission must be granted prior to the issuance of any joint checks.
 - (3) The payment schedule for the supplier must be presented to the DBE office before the first check is issued.
 - (4) The joint check for supplies must be strictly for the cost of supplies.
- b. DBE subcontractor is responsible to furnish and/or install the material/work item. The DBE subcontractor shall not be an 'extra participant' in the transaction; the DBE's role in the transaction cannot be limited solely to signing the check(s) to release payment to the material supplier. At a minimum, the DBE subcontractor's tasks should include the following.
 - (1) The DBE subcontractor (not the prime/payor) negotiates the quantities, price and delivery of materials;
 - (2) The DBE subcontractor consents to sign/release the check to the supplier by signing the Application to Use Joint Checks after establishing the conditions and documentation of payment within the subcontract terms or in a separate written document.
- c. The Prime contractor/payor acts solely as a guarantor,
 - (1) The prime agrees to furnish the check used for the payment of materials/supplies under the contract.
 - (2) The prime contractor/payor cannot require the subcontractor to use a specific supplier or the prime contractors negotiated unit price.

7. Bidder's Appeal Process

- a. A bidder can appeal the department's decision to deny the bidder's good faith effort submission. The bidder must provide written documentation refuting the specific reasons for rejection as stated in the department's rejection notice. The bidder may meet in person with the department if so requested. Failure to appeal within 7 calendar days after receiving the department's written denial notice of a good faith effort evaluation constitutes a forfeiture of the bidder's right of appeal. A contract cannot be executed without documentation that the DBE provisions have been fulfilled.
- b. The department will appoint a representative, who did not participate in the original determination, to assess the bidder's appeal. The department will issue a written decision within 5 calendar days after the bidder presents all written and oral testimony. In that written decision, the department will explain the basis for finding that the bidder did or did not meet the contract DBE goal or make an adequate good faith effort to meet the contract DBE goal. The department's decision is final. If the department finds that the bidder did not meet the contract DBE goal or did not make adequate efforts to meet the DBE goal, the department may declare the bid ineligible for execution.

8. Department's Criteria for DBE Participation

Directory of DBE firms

a. The only resource for DBE certified firms certified in the state of Wisconsin is the Wisconsin Unified Certification Program [UCP] DBE List. Wisconsin Department of Transportation maintains a current list of certified DBE firms titled Wisconsin UCP DBE Directory on the website at:

https://wisconsindot.gov/Documents/doing-bus/civil-rights/dbe/dbe-ucp-directory.xlsx

b. The DBE office is also available to assist at 414-438-4583 or 608-267-3849.

9. Counting DBE Participation

Assessing DBE Work

- a. The department will only count the DBE usage towards the contract DBE goal if the DBE firm is certified as a DBE by one of the unified certification program agencies. If a firm becomes DBE certified before entering into a subcontract, the department may consider that DBE usage towards the contract goal. The department only counts the value of the work a DBE actually performs towards the DBE goal. The department assesses the DBE work as follows:
- b. The department counts work performed by the DBE's own resources. The department includes the cost of materials and supplies the DBE obtains for the work. The department also includes the cost of equipment the DBE leases for the work. The department will not include the cost of materials, supplies, or equipment the DBE purchases or leases from the prime contractor or its affiliate, except the department will count non-project specific leases the DBE has in place before the work is advertised.
- c. The department counts fees and commissions the DBE charges for providing a bona fide professional, technical, consultant, or managerial services. The department also counts fees and commissions the DBE charges for providing bonds or insurance. The department will only count costs the engineer deems reasonable based on experience or prevailing market rates.
- d. If a DBE subcontracts work, the department counts the value of the subcontracted work only if the DBE's subcontractor is also a DBE.
- e. The contractor shall maintain records and may be required to furnish periodic reports documenting its performance under this item.
- f. It is the prime contractor's responsibility to determine whether the work that is committed and/or contracted to a DBE certified firm can be counted for DBE credit by referencing the work type and NAICS code listed for the DBE firm on the Wisconsin UCP DBE Directory.
- g. It is the prime contractor's responsibility to assess the DBE firm's ability to perform the work for which s/he is committing/contracting the DBE to do. Note that the department encourages the prime contractor to assist and develop DBE firms to become fully knowledgeable contractors to successfully perform on its contracts.

10. Commercially Useful Function

- a. Commercially useful function is evaluated after the contract has been executed, while the DBE certified firm is performing its work items. A DBE performs a commercially useful function when it is responsible for execution of the work of the contract and is carrying out its responsibilities by actually performing, managing, and supervising the work involved.
- b. The department uses Form DT1011: DBE Commercially Useful Function Review and Certification to evaluate whether the DBE is performing a commercially useful function. WisDOT counts expenditures of a DBE toward the DBE goal only if the DBE is performing a commercially useful function on that contract.
- c. A DBE is performing a commercially useful function if the following conditions are met:
 - (1) For contract work, the DBE is responsible for executing a distinct portion of the contract work and it is carrying out its responsibilities by actually performing, managing, and supervising that work.
 - (2) For materials and supplies, the DBE is responsible for negotiating price, determining quality and quantity, ordering, and paying for those materials and supplies.

11. Credit Evaluation for Trucking

All bidders are expected to adhere to the department's current trucking policy posted on the HCCI website at https://wisconsindot.gov/Documents/doing-bus/civil-rights/dbe/trucking-utilization-policy.pdf

12. Credit Evaluation for Manufacturers, Suppliers, Brokers

The department will calculate the amount of DBE credit awarded to a prime using a DBE firm for the provisions of materials and supplies on a contract-by-contract basis. The department will count the material and supplies that a DBE provides under the contract for DBE credit based on whether the DBE is a manufacturer, supplier or broker. Generally, DBE crediting measures and evaluates the DBE owner's role, responsibility and contribution to the transaction: maximum DBE credit when the DBE manufactures materials or supplies; DBE credit decreases when the DBE solely supplies material and minimal credit is allotted when the DBE's role is administrative or transactional.

It is the bidder's responsibility to find out if the DBE is considered a supplier or a manufacturer before listing them on Commitment to Subcontract to DBE form DT1506.

a. Manufacturers

- (1) A manufacturer is a firm that operates or maintains a factory or establishment that produces, on the premises, the materials, supplies, articles, or equipment required under the contract and of the general character described by the specifications.
- (2) If the materials or supplies are obtained from a DBE manufacturer, count **100**% percent of the cost of the materials or supplies toward DBE goals.
- b. Regular Dealers of Material and/or Supplies
 - (1) A regular dealer is a firm that owns, operates, or maintains a store, warehouse, or other establishment in which the materials, supplies, articles or equipment of the general character described by the specifications and required under the contract are bought, kept in stock, and regularly sold or leased to the public in the usual course of business.
 - (2) If the materials or supplies are purchased from a DBE regular dealer, count **60%** percent of the cost of the materials or supplies toward DBE goals.
 - (3) At a minimum, a regular dealer must meet the following criteria to be counted for DBE credit:
 - i. The DBE firm must be an established, regular business that engages, as its principal business and under its own name, in the purchase and sale or lease of the products in question.
 - ii. The DBE firm must both own and operate distribution equipment for the product--bulk items such as petroleum products, steel, cement, gravel, stone, or asphalt. If some of the distribution equipment is leased, the lease agreement must accompany the DBE Commitment form for evaluation of the dealer's control before the DBE office approves the DBE credit.
- c. Brokers, Transaction Expediters, Packagers, Manufacturers Representatives
 - (1) No portion of the cost of the materials, supplies, services themselves will count for DBE credit; however, WisDOT will evaluate the fees or commissions charged when a prime purchases materials, supplies or services from a DBE certified firm which is neither a manufacturer nor a regular dealer, namely: brokers, packagers, manufacturers' representatives or other persons who arrange or expedite transactions.
 - (2) Brokerage fees have historically been calculated as 10% of the purchase amount.
 - (3) WisDOT may count the amount of fees or commissions charged for assistance in the procurement of the materials and supplies, or fees or transportation charges for the delivery of materials or supplies required on a job site.
 - (4) The evaluation will review the contract need for the item/service, review the sub-contract or invoice for the item/service, compare the fees customarily allowed for similar services to determine whether they are reasonable.

When DBE suppliers are contracted, additional documentation must accompany the DT1506 and Attachment 'A' forms. An invoice or bill-of-sale that includes the company names of the bidder and the DBE supplier and documentation of the calculations used as the basis for the purchase agreement, subcontract or invoice. WisDOT recognizes that the amount on the Attachment 'A' form may be more or less than the amount on the invoice. Please respond to the following questions and submit with your DBE Commitment Form.

- 1. What is the product or material?
- 2. Is this item in the prime's inventory or was the item purchased when contract was awarded?
- 3. Which contract line items were referenced to develop this quote?
- 4. What is the amount of material or product used on the project?

13. Credit Evaluation for DBE Primes

Wisconsin DOT calculates DBE credit based on the amount and type of work performed by DBE certified firms. If the prime contractor is a DBE certified firm, the department will only count the work that DBE prime contractor performs with its own forces for DBE credit. We will also calculate DBE credit for the work performed by any other DBE certified subcontractor, DBE certified supplier, DBE certified manufacturer on that contract in that DBE's approved work areas/NAICS code. Crediting for manufacturers and suppliers is calculated consistent with paragraph 12 of this document and 49 CFR Part 26.

14. Joint Venture

If a DBE performs as a participant in a joint venture, the department will only count that portion of the total dollar value of the contract equal to that portion of the work that the DBE performs with its own forces for DBE credit.

15. Mentor Protégé

- a. If a DBE performs as a participant in a mentor protégé agreement, the department will count for credit the portion of the work performed by the DBE protégé firm.
- b. DBE credit will be evaluated and confirmed by the DBE Office for any contracts on which the mentor protégé team identifies itself to the DBE Office as a current participant of the Mentor Protégé Program.
- c. Refer to WisDOT's Mentor Protégé guidelines for guidance on the number of contracts and amount of DBE credit that can be counted on any WisDOT project.

16. DBE Replacement or Termination

Contractual Requirement

The contractor shall utilize the specific DBEs listed to perform the work and supply the materials for which each is listed unless the contractor obtains written consent from the Department's DBE Office. If the Department does not provide consent to replace or terminate a DBE firm, the prime contractor shall not be entitled to any payment for work or material unless it is performed or supplied by the listed DBE.

Contractor Considerations

a. A prime contractor cannot terminate and/or replace a DBE subcontractor listed on the approved Commitment to Subcontract to DBE Form [DT1506] without prior written consent from the DBE Office. This includes, but is not limited to, instances in which a prime contractor seeks to perform work originally designated for a DBE subcontractor with its own forces or those of an affiliate, a non-DBE firm, or with another DBE firm.

- b. If a prime contractor feels it is necessary to replace or terminate a DBE firm that has been approved for DBE credit toward its contract, s/he will be required to provide reasons and documentation to support why the prime cannot fulfill the contractual commitment that it made to the Department regarding the DBE utilization.
- c. Prime contractor is required to make affirmative efforts to find another DBE subcontractor to perform at least the same amount of work under the contract as the DBE that was terminated, to the extent needed to meet the assigned DBE contract goal.
- d. In circumstances when a DBE subcontractor fails to complete its work on the contract for any reason or is terminated from a contract, the prime contractor is expected to make affirmative efforts to maintain its commitment to the assigned DBE goal.
- e. The DBE firm should communicate with the prime contractor regarding its schedule and capacity in the context of the contract. If the DBE anticipates that it cannot fulfill its subcontract, s/he shall advise the prime contractor and suggest a DBE that may replace their services or provide written consent to be released from its subcontract.
 - (1) Before the prime contractor can request to terminate or substitute a DBE firm; s/he must:
 - i. Make every effort to fulfill the DBE commitment by working with the listed DBE to ensure that they are fully knowledgeable of your expectations for successful performance on the contract. Document these efforts in writing.
 - ii. If those efforts fail, provide written notice to the DBE subcontractor of your *intent to* request to terminate and/or replace the firm including the reason(s) you want to pursue this action.
 - iii. Copy the DBE Office on all correspondence related to changing a DBE firm who has been approved for DBE credit on a contract including the preparation and coordination efforts with the DBE on the contract.
 - iv. Clearly state the amount of time the DBE firm has to remedy and/or respond to your notice of intent to replace/terminate their firm from the contract. The DBE shall be allowed five days to respond, in writing. Exception: The prime contractor must provide a verifiable reason for a response period shorter than five days. For example a WisDOT project manager must verify that waiting 5 days for a DBE performing traffic control work to respond would affect the public safety.
 - v. The DBE subcontractor must forward a written response to the prime contractor and copy the DBE Office. The written response must outline why it objects to the proposed termination of its subcontract and list the reasons that WisDOT should not approve the request for their firm to be replaced or removed from the contract.

The Request to Replace or Terminate a DBE

The prime contractor must provide a written request to replace or terminate a DBE firm that has been approved for DBE credit on a WisDOT contract. The written request can be an email or printed document delivered by email or fax; at minimum, the request must contain the following:

- 1. Contract ID number.
- 2. Wisconsin DOT Contract Project Manager name and contact information.
- 3. DBE name and work type and/or NAICS code.
- 4. Contract's progress schedule.
- 5. Reason(s) for requesting that the DBE be replaced or terminated.
- 6. Attach/include all communication with the DBE to deploy/address/resolve work completion,

WisDOT will review your request and any supporting documentation that you submit to evaluate whether the circumstance and the reasons constitute a good cause for replacing or terminating the DBE that was approved for DBE credit on that contract.

Examples of Good Causes to Replace a DBE according to the federal DBE program guidelines [49 CFR part 26.53]

- The listed DBE subcontractor fails or refuses to execute a written contract.
- The listed DBE subcontractor fails or refuses to perform the work of its subcontract in a way consistent
 with normal industry standards. Provided, however, that good cause does not exist if the failure or
 refusal of the DBE subcontractor to perform its work on the subcontract results from the bad faith or
 discriminatory action of the prime contractor.
- The listed DBE subcontractor fails or refuses to meet the prime contractor's reasonable, nondiscriminatory bond requirements.
- The listed DBE subcontractor becomes bankrupt, insolvent, or exhibits credit unworthiness.
- The listed DBE subcontractor is ineligible to work on public works projects because of suspension and debarment proceedings pursuant 2 CFR Parts 180, 215 and 1,200 or applicable state law.
- You have determined that the listed DBE subcontractor is not a responsible contractor.
- The listed DBE subcontractor voluntarily withdraws from the project and provides to you written notice of its withdrawal.
- The listed DBE is ineligible to receive DBE credit for the type of work required.
- A DBE owner dies or becomes disabled with the result that the listed DBE contractor is unable to complete its work on the contract.

Evaluation and Response to the Request

If WisDOT determines that your reasons comply with the good cause standards; the DBE office will send the prime contractor and the WisDOT project manager an email stating that we concur with the reasons and approve the replacement or termination.

If WisDOT determines that your reasons do not comply with the good cause standards of the federal DBE program, the DBE Office will send the prime contractor an email that includes *the requirement* to utilize the committed DBE, *remedial actions* to support the completion of the contractual commitment, a list of available WisDOT support services *and administrative remedies that may be invoked* for failure to comply with federal DBE guidelines for DBE replacement.

The Wisconsin Department of transportation contact for all actions related to replacing a DBE is the DBE Program Chief and/or the DBE Program Engineer which can be reached at DBE_Alert@dot.wi.gov or by calling 608-267-3849.

17. DBE Utilization beyond the approved DBE Commitment Form DT1506

If the Prime/subcontractor increases the scope of work for a participating DBE or adds a DBE subcontractor that was not on the approved Form DT1506 at any time after contract award, s/he should follow these steps so that the participation can be accurately credited toward the DBE goal.

- a. Send an email to the DBE Engineer at <u>DBE_Alert@dot.wi.gov</u> describing the work to be performed by the new DBE including the proposed schedule or duration, DBE name and contact information. You may also call the DBE Engineer at 414-659-0487 to notify him of the change verbally.
 If the scope change added work for a participating DBE; list the date and reason for the scope change.
- b. Forward a complete, signed Attachment 'A' form to the DBE Office at DBE_Alert@dot.wi.gov. A complete Attachment A includes DBE contact information, signature, subcontract value and proper description of the work areas to be performed by the DBE.
 - The DBE office will confirm the DBE participation and revise the DT1506 based on the email/discussion and attach the new/revised Attachment A to the Contract record/documentation.

18. Contract Modifications

When additional opportunity is available by contract modifications, the Prime Contractor shall utilize DBE Subcontractors that were committed to equal work items, in the original contract.

19. Payment

Costs for conforming to this Additional Special Provision (ASP) and any associated DBE requirements are incidental to the contract.

APPENDIX A Sample Contractor Solicitation Letter Page 1 This sample is provided as a guide not a requirement

GFW SAMPLE MEMORANDUM

TO: DBE FIRMS

DATE:

CC:

FROM: POTENTIAL PRIME CONTRACTOR OR MAJOR SUBCONTRACTOR

SUBJECT: REQUEST FOR DBE QUOTES

LET DATE & TIME MONTH DAY YEAR DBE OFFICE ENGINEER

Our company is considering bidding on the projects indicated on the next page, as a prime and/or a subcontractor for the Wisconsin Department of Transportation Month-date -year Letting. Page 2 lists the projects and work items that we may subcontract for this letting. We are interested in obtaining subcontractor quotes for these projects and work categories. Also note that we are willing to accept quotes in areas we may be planning to perform ourselves as required by federal rules.

Please review page 2, respond whether you plan to quote, highlight the projects and work items you are interested in performing and return it via fax or email within 3 days. Plans, specifications and addenda are available through WisDOT at the DBE Support Services office or at the Highway Construction Contract Information (HCCI) site at https://wisconsindot.gov/Pages/doing-bus/contractors/hcci/default.aspx

Your quote should include all of the costs required to complete the items you propose to perform including labor, equipment, material, and related bonding or insurance. The quote should note items that you are DBE certified to perform, tied items, and any special terms. Page 2, with the indicated projects and items you plan to quote, should be used as a cover sheet for your quote.

Please make every effort to have your quotes into our office by time deadline the prior to the letting date. <u>Make sure</u> the correct letting date, project ID and proposal number, unit price and extension are included in your quote. We prefer quotes be sent via SBN but prime's alternatives are acceptable. Our office hours are include hours and days. Please call our office as soon as possible prior to the letting if you need information/clarification to prepare your quote at contact number.

If you wish to discuss or evaluate your quote in more detail, contact us after the contract is awarded. Status of the contract can be checked at WisDOT's HCCI site at https://wisconsindot.gov/Pages/doing-bus/contractors/hcci/default.aspx All questions should be directed to:

Project Manager, John Doe, Phone: (000) 123-4567

Email: Joe@joetheplumber.com

Fax: (000) 123- 4657

Sample Contractor Solicitation Letter Page 2 This sample is provided as a guide not a requirement

REQUEST FOR QUOTATION

etting Date:							
roject ID:							
ease check all that apply	the prejects o	nd itama li	atad balaw				
Yes, we will be quoting on No, we are not interested in Please take our name off your We have questions about questions	n quoting on to our monthly I	he letting OBE conta	or its items ct list			his number	
Prime Contractor 's Contact P	erson	٦		DBE Co	ntractor Co	ontact Perso	n
hone:			Phone				
rax:		_	Fax				
Email:		_	Email				
anian.		_	Lillan				
-		_					
Please	circle the jo	bs and ite	ems you wi	ill be quo	ting below	I	
	1	9	3	4	5	6	7
	1	2	J				
	1	2	3	1			
County	1	Δ	3	<u> </u>			
County ORK DESCRIPTION:	1 X	2	X	X		X	X
County ORK DESCRIPTION: Clear and Grub		2				X X	X
County ORK DESCRIPTION: Clear and Grub Dump Truck Hauling	X	2	X	X			
County ORK DESCRIPTION: Clear and Grub Dump Truck Hauling Curb & Gutter/Sidewalk, Etc.	X X	2	X X	X X		X	X
County ORK DESCRIPTION: Clear and Grub Dump Truck Hauling Curb & Gutter/Sidewalk, Etc. Erosion Control Items	X X X	2	X X X	X X X		X X	X
County ORK DESCRIPTION: Clear and Grub Dump Truck Hauling Curb & Gutter/Sidewalk, Etc. Erosion Control Items Signs and Posts/Markers Traffic Control	X X X X	X	X X X X	X X X X		X X X	X X X
County ORK DESCRIPTION: Clear and Grub Dump Truck Hauling Curb & Gutter/Sidewalk, Etc. Erosion Control Items Signs and Posts/Markers Traffic Control	X X X X		X X X X	X X X X		X X X X	X X X X
County ORK DESCRIPTION: Clear and Grub Dump Truck Hauling Curb & Gutter/Sidewalk, Etc. Erosion Control Items Signs and Posts/Markers Traffic Control Electrical Work/Traffic Signals	X X X X	X	X X X X X	X X X X X X X	X	X X X X X X	X X X X
Proposal No. County /ORK DESCRIPTION: Clear and Grub Dump Truck Hauling Curb & Gutter/Sidewalk, Etc. Erosion Control Items Signs and Posts/Markers Traffic Control Electrical Work/Traffic Signals Pavement Marking Sawing Pavement	X X X X	X	X X X X X X	X X X X X X X X	X	X X X X X X X	X X X X X X
County ORK DESCRIPTION: Clear and Grub Dump Truck Hauling Curb & Gutter/Sidewalk, Etc. Erosion Control Items Signs and Posts/Markers Traffic Control Electrical Work/Traffic Signals Pavement Marking	X X X X	X X X	X X X X X X X	X X X X X X X X	X	X X X X X X	X X X X X
County CORK DESCRIPTION: Clear and Grub Dump Truck Hauling Curb & Gutter/Sidewalk, Etc. Erosion Control Items Signs and Posts/Markers Traffic Control Electrical Work/Traffic Signals Pavement Marking Sawing Pavement QMP, Base	X X X X	X X X X	X X X X X X X	X X X X X X X X	X	X X X X X X X	X X X X X X
County CORK DESCRIPTION: Clear and Grub Dump Truck Hauling Curb & Gutter/Sidewalk, Etc. Erosion Control Items Signs and Posts/Markers Traffic Control Electrical Work/Traffic Signals Pavement Marking Sawing Pavement QMP, Base Pipe Underdrain	X X X X X	X X X X	X X X X X X X	X X X X X X X X	X	X X X X X X X	X X X X X X
County ORK DESCRIPTION: Clear and Grub Dump Truck Hauling Curb & Gutter/Sidewalk, Etc. Erosion Control Items Signs and Posts/Markers Traffic Control Electrical Work/Traffic Signals Pavement Marking Sawing Pavement	X X X X X	X X X X	X X X X X X X	X X X X X X X X X X	X X X	X X X X X X X X	X X X X X X X

APPENDIX B BEST PRACTICES FOR PRIME CONTRACTOR & DBE SUBCONTRACTOR GOOD FAITH EFFORT

This list is not a set of requirements; it is a list of potential strategies

Primes

- Ø Prime contractor open houses inviting DBE firms to see the bid "war room" or providing technical assistance.
- Ø Participate in speed networking and mosaic exercises as arranged by DBE office.
- Ø Host information sessions not directly associated with a bid letting.
- Ø Participate in a formal mentor protégé or joint venture with a DBE firm.
- Ø Participate in WisDOT advisory committees i.e. TRANSAC, or Mega Project committee meetings.
- Ø Facilitate a small group DBE 'training session' Clarifying how your firm prepares for bid letting, evaluates subcontractors, preferred qualifications and communication methods.
- Ø Encourage subcontractors to solicit and highlight DBE participation in their quotes to you.
- Ø Quality of communication, not quantity creates the best results. Contractors should do as thorough a job as possible in communicating with DBE firms before the bid and provide any assistance requested to assure best possible bid.

DBE

- Ø DBE firms should contact primes as soon as possible with questions regarding their quotes or bid; seven days prior is optimal.
- Ø Continually check for contract addendums on the HCCI website through the Thursday prior to letting to stay abreast of changes.
- Ø Review the status of contracts on the HCCI website reviewing the 'apparent low bidder' list, and bid tabs at a minimum.
- Ø Prepare a portfolio or list of related projects and prime and supplier references; be sure to note transportation-related projects of similar size and scope, firm expertise and staffing.
- Ø Participate in DBE office assessment programs.
- Ø Participate on advisory and mega-project committees.
- Ø Sign up to receive the DBE Contracting Update.
- Ø Consider membership in relevant industry or contractor organizations.
- Ø Active participation is a must. Quote as many projects as you can reasonably work on; quoting the primes and bidding as a prime with the department are the only ways to get work.

APPENDIX C

Types of Efforts considered in determining GFE

This list represents concepts being assessed; analysis requires additional steps

- 1. Whether the contractor attended any pre-solicitation or pre-bid meetings that were scheduled by WisDOT to inform DBEs of contracting and subcontracting opportunities.
- 2. Whether the contractor provided written notice to a reasonable number of specific DBEs that their interest in the contract was being solicited, in sufficient time to allow the DBEs to participate effectively.
- 3. Whether the contractor followed up initial solicitations of interest by contacting DBEs to determine if the DBEs were interested; returned the phone calls of interested DBE firms.
- 4. Whether the contractor selected portions of the work to be performed by DBEs in order to increase the likelihood of meeting the DBE goal.
- 5. Whether the contractor provided interested DBEs with adequate information about the plans, specifications and requirements of the contract.
- 6. Whether the contractor negotiated in good faith with interested DBEs, not rejected DBEs as unqualified without sound reasons based on a thorough investigation of their capabilities.
- 7. Whether the contractor made efforts to assist interested DBEs in being more competitive.
- 8. Whether the contractor effectively used the services of available minority community organizations: minority contractors groups, local, state, and Federal minority business assistance offices, and other organizations that provide assistance to small businesses and DBE firms.
- 9. Whether Prime used CRCS to identify DBE who specialize in relevant work areas.
- 10. Whether the contractor used available resources including contacting the DBE office, using WisDOT's website
- 11. Whether the contractor returned calls of firms expressing interest in a timely manner.

APPENDIX D

Good Faith Effort Evaluation Guidance Excerpt from Appendix A of 49 CFR Part 26

APPENDIX A TO PART 26 -- GUIDANCE CONCERNING GOOD FAITH EFFORTS

- I. When, as a recipient, you establish a contract goal on a DOT assisted contract, a bidder must, in order to be responsible and/or responsive, make good faith efforts to meet the goal. The bidder can meet this requirement in either of two ways. First, the bidder can meet the goal, documenting commitments for participation by DBE firms sufficient for this purpose. Second, even if it doesn't meet the goal, the bidder can document adequate good faith efforts. This means that the bidder must show that it took all necessary and reasonable steps to achieve a DBE goal or other requirement of this part which, by their scope, intensity, and appropriateness to the objective, could reasonably be expected to obtain sufficient DBE participation, even if they were not fully successful.
- II. In any situation in which you have established a contract goal, part 26 requires you to use the good faith efforts mechanism of this part. As a recipient, it is up to you to make a fair and reasonable judgment whether a bidder that did not meet the goal made adequate good faith efforts. It is important for you to consider the quality, quantity, and intensity of the different kinds of efforts that the bidder has made. The efforts employed by the bidder should be those that one could reasonably expect a bidder to take if the bidder were actively and aggressively trying to obtain DBE participation sufficient to meet the DBE contract goal. Mere pro forma efforts are not good faith efforts to meet the DBE contract requirements. We emphasize, however, that your determination concerning the sufficiency of the firm's good faith efforts is a judgment call: meeting quantitative formulas is not required.
- III. The Department also strongly cautions you against requiring that a bidder meet a contract goal (i.e., obtain a specified amount of DBE participation) in order to be awarded a contract, even though the bidder makes an adequate good faith efforts showing. This rule specifically prohibits you from ignoring bona fide good faith efforts.
- IV. The following is a list of types of actions which you should consider as part of the bidder's good faith efforts to obtain DBE participation. It is not intended to be a mandatory checklist, nor is it intended to be exclusive or exhaustive. Other factors or types of efforts may be relevant in appropriate cases.
 - A. Soliciting through all reasonable and available means (e.g. attendance at pre-bid meetings, advertising and/or written notices) the interest of all certified DBEs who have the capability to perform the work of the contract. The bidder must solicit this interest within sufficient time to allow the DBEs to respond to the solicitation. The bidder must determine with certainty if the DBEs are interested by taking appropriate steps to follow up initial solicitations.
 - B. Selecting portions of the work to be performed by DBEs in order to increase the likelihood that the DBE goals will be achieved. This includes, where appropriate, breaking out contract work items into economically feasible units to facilitate DBE participation, even when the prime contractor might otherwise prefer to perform these work items with its own forces.
 - C. Providing interested DBEs with adequate information about the plans, specifications, and requirements of the contract in a timely manner to assist them in responding to a solicitation.
 - D. (1) Negotiating in good faith with interested DBEs. It is the bidder's responsibility to make a portion of the work available to DBE subcontractors and suppliers and to select those portions of the work or material needs consistent with the available DBE subcontractors and suppliers, so as to facilitate DBE participation. Evidence of such negotiation includes the names, addresses, and telephone numbers of DBEs that were considered; a description of the information provided regarding the plans and specifications for the work selected for subcontracting; and evidence as to why additional agreements could not be reached for DBEs to perform the work.
 - (2) A bidder using good business judgment would consider a number of factors in negotiating with subcontractors, including DBE subcontractors, and would take a firm's price and capabilities as well as contract goals into consideration. However, the fact that there may be some additional costs involved in finding and using DBEs is not in itself sufficient reason for a bidder's failure to meet the contract DBE goal, as long as such costs are reasonable. Also, the ability or desire of a prime contractor to perform the work of a

- contract with its own organization does not relieve the bidder of the responsibility to make good faith efforts. Prime contractors are not, however, required to accept higher quotes from DBEs if the price difference is excessive or unreasonable.
- E. Not rejecting DBEs as being unqualified without sound reasons based on a thorough investigation of their capabilities. The contractor's standing within its industry, membership in specific groups, organizations, or associations and political or social affiliations (for example union vs. non-union employee status) are not legitimate causes for the rejection or non solicitation of bids in the contractor's efforts to meet the project goal.
- F. Making efforts to assist interested DBEs in obtaining bonding, lines of credit, or insurance as required by the recipient or contractor.
- G. Making efforts to assist interested DBEs in obtaining necessary equipment, supplies, materials, or related assistance or services.
- H. Effectively using the services of available minority/women community organizations; minority/women contractors' groups; local, state, and Federal minority/women business assistance offices; and other organizations as allowed on a case-by-case basis to provide assistance in the recruitment and placement of DBEs.
- V. In determining whether a bidder has made good faith efforts, you may take into account the performance of other bidders in meeting the contract. For example, when the apparent successful bidder fails to meet the contract goal, but others meet it, you may reasonably raise the question of whether, with additional reasonable efforts, the apparent successful bidder could have met the goal. If the apparent successful bidder fails to meet the goal, but meets or exceeds the average DBE participation obtained by other bidders, you may view this, in conjunction with other factors, as evidence of the apparent successful bidder having made good faith efforts.

Appendix E Small Business Network [SBN] Overview

The Small Business Network is a part of the Bid Express® service that was created to ensure that prime bidders have a centralized online location to find subs - including small and disadvantaged business enterprises (DBEs). It is available for prime bidders to use as part of their Basic Service subscription.

Within the Small Business Network. **Prime Contractors** can:

1. Easily select proposals, work types and items:

a. After adding applicable work types, select items that you wish to quote. Enter the sub-quote quantities and add comments, if desired. Adding or removing items and work types can be done quickly. If needed, you can save the sub-quote for completion at a later time.

2. Create sub-quotes for the subcontracting community:

- a. Create sub-quotes with ease using the intuitive sub-quote creator. In seven short steps, you can rapidly create a custom sub-quote directed to all subcontractors that bid on the applicable work types. Steps include: provide contact information and sub-quote expiration date, select letting and proposal, add work types and items, specify terms and conditions, upload attachments, and select vendors.
- b. Create a sub-quote to send to subcontractors or suppliers that lists the items in a proposal that you want quoted
- c. Create an unlimited number of sub-quotes for items you want quoted, and optionally mark them as a DBE-preferred request.
- d. Add attachments to sub-quotes.

3. View sub-quote requests & responses:

- a. After logging into the Bid Express service, you can quickly review all of your sub-quote requests and all unsolicited sub-quote requests from subcontractors. To simplify the Small Business Network home screen, sub-quote requests can be hidden with one click if they are not applicable.
- b. View or receive unsolicited sub-quotes that subcontractors have posted, complete with terms, conditions and pricing.

4. View Record of Subcontractor Outreach Effort:

- a. For each sub-quote produced, a *Record of Subcontractor Outreach Effort* is generated that shows the response statistics for a particular sub-quote. If accepted by the letting agency, this report may serve as proof of a "Good Faith" effort in reaching out to the DBE community.
- b. Easily locate pre-qualified and certified small and disadvantaged businesses.
- c. Advertise to small and disadvantaged businesses more efficiently and cost effectively.
- d. Document your interactions with subs/DBEs by producing an Outreach Report (may be accepted as proof of DBE outreach at the discretion of each agency).

The Small Business Network is a part of the Bid Express® service that was created to ensure that small businesses have a centralized area to access information about upcoming projects. It can help small businesses learn more about opportunities, compete more effectively, network with other contractors and subcontractors, and win more jobs.

1. View and reply to sub-quote requests from primes:

a. After logging into the Bid Express service, you can quickly review all incoming sub-quote requests and all unsolicited sub-quotes created by your company. Receive notifications by selected work type. To simplify on the Small Business Network home screen, sub-quote requests can be filtered by work types relevant to your interests, or hidden with one click if they are not applicable.

2. Select items when responding to sub-quote requests from primes:

- a. You have the freedom to choose and price any number of items when responding to a sub-quote request. Quantities can be modified, and per-item comments are also available.
- b. View requests for sub-quotes for work that primes have posted for projects they are bidding, add your pricing, terms, and conditions, and submit completed sub-quotes to the requesting primes.
- c. Add attachments to a sub-quote.

3. Create and send unsolicited sub-quotes to specific contractors:

a. Create unsolicited sub-quotes with ease using the intuitive sub-quote creator. In eight short steps, you can rapidly create a custom sub-quote directed at any number of specific vendors of your choosing. Steps include: provide contact information and sub-quote expiration date, select letting and proposal, add work types and items, specify terms and conditions, upload attachments, and select vendors.

4. Easily select and price items for unsolicited sub-quotes:

- a. After adding applicable work types, select items that you wish to quote. The extended price calculates automatically, cutting out costly calculation errors. Comments can be provided on a per-item basis as well.
- b. Create an unsolicited sub-quote that lists the items from a proposal that you want to quote, include pricing, terms and conditions, and send it to selected prime/plan holder.
- c. Add attachments to a sub-quote.
- d. Add unsolicited work items to sub-quotes that you are responding to.

5. Easy Access to Valuable Information

- a. Receive a confirmation that your sub-quote was opened by a prime.
- b. View Bid Tab Analysis data from past bids, including the high, average and low prices of items.
- c. View important notices and publications from DOT targeted to small and disadvantaged businesses.

6. Accessing Small Business Network for WisDOT contracting opportunities

- a. If you are a contractor not yet subscribing to the Bid Express service, go to www.bidx.com and select "Order Bid Express." The Small Business Network is a part of the Bid Express Basic Service.
- DBE firms can request a Bid Express Small Business Network Account at no cost by calling 414-438-4588.

November 2013 ASP-4

ADDITIONAL SPECIAL PROVISION 4

Payment to First-Tier Subcontractors

Within 10 calendar days of receiving a progress payment for work completed by a subcontractor, pay the subcontractor for that work. The prime contractor may withhold payment to a subcontractor if, within 10 calendar days of receipt of that progress payment, the prime contractor provides written notification to the subcontractor and the department documenting "just cause" for withholding payment.

The prime contractor may also withhold routine retainage from payments due subcontractors.

Payment to Lower-Tier Subcontractors

Ensure that subcontracting agreements at all tiers provide prompt payment rights to lower-tier subcontractors that parallel those granted first-tier subcontractors in this provision.

Release of Routine Retainage

After granting substantial completion the department may reduce the routine retainage withheld from the prime contractor to 75 percent of the original total amount retained.

When the Department sends the semi-final estimate the department may reduce the routine retainage withheld from the prime contractor to 10 percent of the original total amount retained.

Within 30 calendar days of receiving the semi-final estimate from the department, submit written certification that subcontractors at all tiers are paid in full for acceptably completed work and that no routine retainage is being withheld. The department will pay the prime contractor in full and reduce the routine retainage withheld from the prime contractor to zero when the department approves the final estimate.

This special provision does not limit the right of the department, prime contractor, or subcontractors at any tier to withhold payment for work not acceptably completed or work subject to an unresolved contract dispute.

Additional Special Provision 6 ASP 6 - Modifications to the standard specifications

Make the following revisions to the standard specifications:

104.3 Contractor Notification

Replace the entire text with the following effective with the December 2019 letting:

104.3.1 General

(1) Subsection 104.3 specifies the step-by-step communication process to be followed to expedite the resolution of potential contract revisions identified by the contractor. Both contractor actions and department responses are outlined. The contractor's non-compliance with the requirements of 104.3 may constitute a waiver of entitlement to a pay adjustment under 109.4 or a time extension under 108.10. The department and contractor can mutually agree to extend any time frame specified throughout 104.3.

104.3.2 Contractor Initial Oral Notification

(1) If required by 104.2, or if the contractor believes that the department's action, the department's lack of action, or some other situation results in or necessitates a contract revision, the contractor must promptly provide oral notification to the project engineer. Upon notification, the project engineer will attempt to resolve the identified issue.

104.3.3 Contractor 5-Day Written Statement

(1) If the project engineer has not responded or resolved the identified issue within 5 business days after receipt of initial notification, provide a contractor written statement to the project engineer in the following format:

Part 1 - Executive Summary (label page 1.1 through page 1.x)

Include a detailed, factual statement of the request for additional compensation and contract time. Include the date the issue was identified, the date initial notification was given to the project engineer, and the dates and specific locations of work involved.

Part 2 - Contractor's Basis of Entitlement (label page 2.1 through page 2.x)

Include references to relevant contract provisions and a narrative summarizing how the contract provisions support the request for a revision to the original contract.

Part 3 - Contractor's Request for Damages (label page 3.1 through page 3.x)

When requesting additional compensation, include an itemized list of costs with a narrative supporting the requested amount and explaining how the costs are tied to the requested contract revision.

When requesting additional contract time, include a copy of the schedule that was in effect when the issue occurred and a detailed narrative explaining how the issue impacted controlling items of work. Provide a time impact analysis utilizing base and updated schedules.

If the full extent of either compensation or time is not known at the date of submittal of the contractor 5-Day written statement, provide a brief statement as to why, and include estimated compensation and time.

Part 4 - Supporting Documentation (label page 4.1 through page 4.x)

Include copies of the following:

- A. Relevant excerpts from specifications, special provisions, plans, change orders, or other contract documents
- B. Communication on the issue, including: letters, e-mails, meeting minutes, etc.
- C. Any other documentation to support or clarify the contractor's position, including: daily work records, cost summary sheets, weigh tickets, test results, sketches, etc.
- (2) With the submittal of the written statement, the contractor may also request a meeting with the region.

104.3.4 Region One-Day Written Acknowledgment

(1) Within one business day after the contractor provides the 5-day written statement, the project engineer will provide a region one-day written acknowledgment to the contractor. The project engineer will continue to resolve the issue.

104.3.5 Region 5-Day Written Response

(1) Within 5 business days after receiving the contractor 5-day written statement, the project engineer may request specific additional information to allow the project engineer to decide whether item 1 or 2 of 104.3.6(1) applies. The project engineer will state the information needed and date it is to be

received for further review. Submit additional information as an amendment to the contractor 5-day written statement.

104.3.6 Region Final Decision

- (1) Within 10 business days after receiving the contractor 5-day written statement or additional information requested in 104.3.5(1), whichever comes last, the region will consider all information and provide a region final decision in writing to the contractor with one or more of the following responses:
 - 1. The region will confirm that the contractor is entitled to a contract revision and a contract change order is necessary as specified in 104.2. The project engineer will give direction concerning the potential change.
 - 2. The region will deny that the contractor is entitled to a contract revision. The project engineer will provide a statement as to why the issue is not a change to the contract. At a minimum, the project engineer will respond to the contractor's issues and refer to the contract to show why the issues are not a change from the original contract.
- (2) If the contractor does not agree with the region's decision the contractor may pursue the issue as a claim as specified in 105.13. Alternatively, if the contractor and department mutually agree, the department will get a third-party advisory opinion according to the department's dispute resolution procedures.
- (3) If a third party reviews the issue, their recommendation is not binding on either party. The region has 10 business days after receipt of the third party's written recommendation to render a decision. If the department fails to respond in writing within those 10 business days or the contractor disagrees with the region's decision, the contractor may pursue the issue as a claim as specified in 105.13.

104.6.1.2.1 General

Replace paragraph one with the following effective with the December 2019 letting:

- (1) Conduct construction operations and provide facilities required to maintain the portion of the project open to the public in a condition that safely and adequately accommodates public traffic. Use barricades, signs, flaggers, and temporary barrier as specified in part VI, of the WMUTCD and ensure that the contractor's use of the right-of-way conforms to 107.9. Throughout the life of the contract, and as the engineer directs, conduct construction operations and provide facilities as follows:
 - Conduct flagging operations conforming to plan details and the department's flagging handbook.
 - Use drums, barricades, and temporary barrier to delineate and shield abrupt drop-offs and other hazards.
 - Furnish, erect, and maintain traffic control devices and facilities conforming to 643.
 - Furnish, erect, and maintain temporary pedestrian devices and facilities conforming to 644.

104.6.1.2.2 Flagging

Replace paragraph three with the following effective with the December 2019 letting:

(3) Provide associated advanced warning signs that meet the retroreflective requirements of 637.2.2.2. Provide temporary portable rumble strips from the department's APL installed according to manufacturer's instructions and as specified in the flagging plan details. Provide guidance service through the worksite using pilot vehicles if required.

Replace paragraph five with the following effective with the December 2019 letting:

(5) Flagging is incidental to the contract and includes costs for advance signing, temporary portable rumble strips, and pilot vehicle guidance service.

104.8 Rights in the Use of Materials Found on the Project

Replace paragraph two with the following effective with the December 2019 letting:

- (2) Do not excavate or remove material from within the right-of-way that is not within the vertical and horizontal excavation limits the plans show except as follows:
 - If the contract does not identify potential source areas, obtain written authorization from the engineer to use those sources. Complete required environmental documentation and obtain necessary permits. The department will reduce pay by \$1.50 per cubic yard under the Material from Right-of-Way administrative item for material obtained from those areas.
 - If the contract identifies potential source areas that were evaluated and permitted in the original
 environmental document, do not begin excavating in those areas until the engineer allows in writing.
 Additional environmental documentation and environmental permits are not required. The department will
 not reduce pay for material obtained from those areas.

The department may suspend use of these sources if the contractor's operation affects the essential functions or characteristics of the project.

104.10.1 General

Replace paragraph one with the following effective with the December 2019 letting:

- (1) Subsection 104.10 specifies a 2-step process for contractors to follow in submitting a cost reduction incentive (CRI) for modifying the contract in order to reduce direct construction costs computed at contract bid prices. The initial submittal is referred to as a CRI concept and the second submittal is a CRI proposal. The contractor and the department will equally share all savings generated to the contract due to a CRI as specified in 104.10.4.2(1). The department encourages the contractor to submit CRI concepts for the following situations:
 - 1. The contractor generates the original cost savings idea and formulates it into a concept.
 - 2. The department generates the original cost savings idea and obtains the contractor's assistance to formulate the idea into a concept.

Replace paragraph five with the following effective with the December 2019 letting:

- (5) The department will consider a CRI that changes but does not impair the essential functions or characteristics of the project. These functions or characteristics include, but are not limited to, appearance, service life, economy of operations, ease of maintenance, design, and safety of structures and pavements, construction phasing or procedures, or other contract requirements. The department will not consider a CRI that changes the following:
 - Permanent pavement type.
 - Permanent structural cross section above the subgrade.

104.10.2 Submittal and Review of a CRI Concept

Replace paragraphs five and six with the following effective with the December 2019 letting:

- (5) The department may consider a CRI concept that addresses a potential change under 104.2.
- (6) The department will not implement a contractor-initiated CRI concept, or portion of that concept, without sharing the cost savings with the contractor as specified in 104.10.4.2.
- (7) The savings generated by the CRI must be sufficient to warrant its review and processing and offset the level of risk. The department will assess the risk of the CRI relative to departmental design policies and criteria for the project. The department may reject a CRI concept for the following reasons:
 - 1. It requires excessive time or costs for the contractor to develop the CRI proposal.
 - 2. It requires excessive time or costs for review, evaluation, investigation, or implementation.
 - 3. It introduces an inappropriate level of risk.

104.10.4.2 Payment for the CRI Work

Replace paragraph one with the following effective with the December 2019 letting:

- (1) The department will pay for completed CRI work as specified for progress payments under 109.6. The department will pay for CRI's under the Cost Reduction Incentive administrative item. When all CRI costs are determined, the department will execute a contract change order that does the following:
 - 1. Adjusts the contract time, interim completion dates, or both.
 - 2. Pays the contractor for the unpaid balance of the CRI work.
 - 3. Pays the contractor 50 percent of the net savings resulting from the CRI, calculated as follows:

NS = CW - CRW - CC - DC

Where:

NS = Net Savings

CW = The cost of the work required by the original contract that is revised by the CRI. CW is computed at contract bid prices if applicable.

CRW = The cost of the revised work, computed at contract bid prices if applicable.

CC = The contractor's cost of developing the CRI proposal.

DC = The department's cost for investigating, evaluating, and implementing the CRI proposal.

105.13 Claims Process for Unresolved Changes

Replace the entire text with the following effective with the December 2019 letting:

105.13.1 General

- (1) Before submitting a claim, the department and contractor can mutually agree to have the department get a third-party advisory opinion as specified in 104.3.6.
- (2) The department and contractor can mutually agree to extend any time frame specified throughout 105.13 and can mutually agree to utilize an alternative dispute resolution method at any point before the department renders its final decision.
- (3) The department and contractor share costs related to referral to a dispute review board (DRB) as prescribed in the department's dispute resolution procedures.

105.13.2 Notice of Claim

- (1) If the contractor has followed the procedures for revising the contract specified in 104.2 and provided the notification specified in 104.3, but still disagrees with the region, the contractor may pursue the issue as a claim. File a notice of claim with the project engineer concerning the disagreement within 14 calendar days of receiving the region's decision under 104.3.6(1).
- (2) The project engineer may deny the applicable portion of a claim if the contractor does not do the following:
 - 1. File the notice of claim within 14 calendar days as specified in 105.13.2(1).
 - 2. Give the project engineer sufficient access to keep a record of the actual labor, materials, and equipment used to perform the claimed work.
- (3) Upon filing the notice of claim, maintain records as specified for force account statements in 109.4.5. Unless the project engineer issues a suspension, continue to perform the disputed work. The department will continue to make progress payments to the contractor as specified in 109.6.

105.13.3 Submission of Claim

- (1) Submit the claim to the project engineer as promptly as possible following the submission of the Notice of Claim, but not later than the end of the time allowed under 109.7 for the contractor to respond in writing to the engineer-issued semi-final estimate. If the contractor does not submit the claim within that response time, the department will deny the claim.
- (2) The department will not accept the submission of a claim until the resolution process in 104.3 has been completed and the contractor makes no further requests to submit updated information that may affect the region's final decision.

105.13.4 Content of Claim

- (1) The final contractor written statement under 104.3.3 is considered the content of the claim. If the contractor makes a request to submit updated information that may affect the region's final decision under 104.3.6, submit the updated information as an amendment to the contractor written statement and continue the resolution process in 104.3 before submitting a claim.
- (2) The department may refer the claimant of a false claim to the appropriate authority for criminal prosecution. Certify the claim using the following form:

The undersigned is duly authorized to certify this claim on behalf of (the contractor).

(The contractor) certifies that this claim is made in good faith, that the supporting data are accurate and complete to the best of (the contractor's) knowledge and belief, and that the amount requested accurately reflects the contract adjustment for which (the contractor) believes that the department is liable.

(THE CONTRACTOR)
Ву:
(Name and Title)
Date of Execution:

105.13.5 Department Final Decision

- (1) The department will have up to 28 calendar days, from the contractor's submission of the claim, to perform a final review of the claim and conduct all meetings. The department may request, in writing, that the contractor submit additional information related to the claim. Submit that additional information, or notify the department in writing to base its decision on the information previously submitted. Either the contractor or region may request a meeting to present their views. Before the meeting, both parties will agree upon written ground rules for the meeting.
- (2) Upon completion of the 28 calendar days for the department's review and meetings, the department will have up to 21 calendar days to render a written decision. The department will consider written and oral submissions from the contractor and region, and may consider other relevant information in the project records.
- (3) The department will provide the following in its final decision:
 - 1. A concise description of the claim.
 - 2. A clear, contractual basis for its decision that includes a reference to 104.2 on revisions to the contract and as appropriate, specific reference to language regarding the bid items in question.
 - 3. Other facts the department relies on to support its decision.
 - 4. A concise statement of the circumstances surrounding the claim and reasons for its decision. If the department rejects the claim in whole or in part, the department will explain why the claimed work is not a change to the contract work.
 - 5. The amount of money or other relief, if any, the department will grant the contractor.
- (4) If the contractor disagrees with the department's final decision, the contractor may initiate a legal action pursuant to state statutes.

106.3.4.2.2.2 Freeze-Thaw Soundness

Replace paragraph one with the following effective with the December 2019 letting:

- (1) Perform freeze-thaw soundness testing according to AASHTO T103 as modified in CMM 8-60.2. Provide freeze/thaw soundness test results based on the fraction retained on the No. 4 sieve as follows:
 - 1. Using virgin crushed stone aggregates produced from limestone/dolomite sources in one or more of the following counties or from out of state:

Brown	Columbia	Crawford	Dane	Dodge
Fond du Lac	Grant	Green	Green Lake	Iowa
Jefferson	Lafayette	Marinette	Oconto	Outagamie
Rock	Shawano	Walworth	Winnebago	

2. Using gravel aggregates produced from pit sources in one or more of the following counties or from out of state:

Dodge Washington Waukesha

108.10.3 Excusable Compensable Delays

Replace paragraph two with the following effective with the June 2020 letting:

- (2) The following are compensable delays:
 - 1. A contract change for revised work as specified for extra work under 104.2.2.1, for a differing site condition under 104.2.2.2, or for significant changes in the character of the work under 104.2.2.4.
 - 2. A contract change for an engineer-ordered suspension under 104.2.2.3.
 - 3. The unexpected discovery of human remains, an archaeological find, or historical find consistent with 107.25.
 - 4. The unexpected discovery of a hazardous substance consistent with 107.24.
 - 5. The non-completion of work that utilities or other third parties perform, if the contract specifies a number of days or a completion date for that utility or third-party work. For delays covered under Trans 220 of the Wisconsin administrative code, the engineer will grant a time extension, but the contractor must seek recovery of delay costs from the utility.

208.5 Payment

Replace paragraph three with the following effective with the December 2019 letting:

(3) The department will adjust pay for material obtained from within the project right-of-way limits but outside project excavation limits, furnished under 208.2.2, as specified in 104.8.

301.2.3 Sampling and Testing

Replace paragraph one with the following effective with the December 2019 letting:

(1) Department and contractor testing shall conform to the following: Sampling^[1].....AASHTO T2 Gradation^[7] AASHTO T27 Wear......AASHTO T96

^[1] As modified in CMM 8-60.

301.2.4.5 Aggregate Base Physical Properties

Replace paragraph one with the following effective with the December 2019 letting:

(1) Furnish aggregates conforming to the following:

TABLE 301-2 AGGREGATE BASE PHYSICAL PROPERTIES

PROPERTY	CRUSHED STONE	CRUSHED GRAVEL	CRUSHED CONCRETE	RECLAIMED ASPHALT	REPROCESSED MATERIAL	BLENDED MATERIAL
Gradation AASHTO T27						
dense	305.2.2.1	305.2.2.1	305.2.2.1	305.2.2.2	305.2.2.1	305.2.2.1 ^[1]
open-graded	310.2	310.2	not allowed	not allowed	not allowed	not allowed
Wear AASHTO T96 loss by weight	<=50%	<=50%	note ^[2]		note ^[2]	note ^[3]
Sodium sulfate soundness AASHTO T104 loss by weight						
dense	<=18%	<=18%				note ^[3]
open-graded	<=12%	<=12%	not allowed	not allowed	not allowed	not allowed
Freeze/thaw soundness AASHTO T103 ^[6] loss by weight						
dense	<=18%	<=18%	note ^[2]			note ^[3]
open-graded	<=18%	<=18%	not allowed	not allowed	not allowed	not allowed
Liquid limit AASHTO T89	<=25	<=25	<=25			note ^[3]
Plasticity AASHTO T90	<=6 ^[4]	<=6 ^[4]	<=6 ^[4]			note ^[3]
Fracture ASTM D5821 ^[6] min one face by count						
dense	58%	58%	58%		note ^[5]	note ^[3]
open-graded	90%	90%	not allowed	not allowed	not allowed	not allowed

^[1] The final aggregate blend must conform to the specified gradation.

- LA wear maximum of 50 percent loss, by weight.
- Freeze thaw maximum of 42 percent loss, by weight.

No requirement for material taken from within the project limits. For material supplied from a source outside the project limits:

^[3] Required as specified for the individual component materials defined in columns 2 - 6 of the table before blending.

^[4] For base placed between old and new pavements, use crushed stone, crushed gravel, or crushed concrete with a plasticity index of 3 or less.

^{[5] &}gt;=75 percent by count of non-asphalt coated particles.

^[6] as modified in CMM 8-60.

450.2.2 Aggregate Sampling and Testing

Replace paragraph one with the following effective with the December 2019 letting:

(1) The department and the contractor will sample and test according to the following methods, except as revised with the engineer's approval:

Sampling aggregates	AASHTO T2
Material finer than No. 200 sieve	AASHTO T11
Sieve analysis of aggregates	AASHTO T27
Mechanical analysis of extracted aggregate	AASHTO T30
Sieve analysis of mineral filler	AASHTO T37
Los Angeles abrasion of coarse aggregate	AASHTO T96
Freeze-thaw soundness of coarse aggregate ^[1]	AASHTO T103
Sodium sulfate soundness of aggregates (R-4, 5 cycles)	AASHTO T104
Extraction of bitumen	AASHTO T164
[1] As modified in CMM 8-60.2.	

450.3.2.6.3 Compaction Roller Pattern Determined by Growth Curve

Add 450.3.2.6.3 as a new subsection effective with the December 2019 letting:

450.3.2.6.3 Compaction Roller Pattern Determined by Growth Curve

- (1) When specified in 460.3.3.1, compact asphaltic mixture using the roller pattern established during construction of a control strip. Use 2 or more rollers per paver if placing more than 165 tons per hour.
- (2) On the first day of production, construct a control strip under the direct observation of department personnel. After compacting the control strip with a minimum of 3 passes, mark the gauge outline and take a one-minute wet density measurement using a nuclear density gauge in back scatter mode at a single location. Take a density measurement at the same location after each subsequent pass. Continue compacting and testing until the increase in density is less than 1 pcf for 3 consecutive passes. Submit the final roller pattern to the engineer in writing. Once the roller pattern is established do not change the pattern or decrease the number, type, or weight of rollers without the engineer's written approval.
- (3) After establishing the roller pattern, and under the direct observation of the engineer, cut at least one 4-inch diameter or larger core from the control strip density gauge outline. Prepare cores and determine density according to AASHTO T166. Dry cores after testing. Fill core holes and obtain engineer approval before opening to traffic. The department will maintain custody of cores throughout the entire sampling and testing process. The department will label cores, transport cores to testing facilities, witness testing, store dried cores, and provide subsequent verification testing.

450.3.2.8 Jointing

Replace paragraph three with the following effective with the December 2019 letting:

(3) Construct notched wedge longitudinal joints for mainline paving of HMA layers 1.75 inches or greater. Extend the wedge beyond the normal lane width as the plans show or as the engineer directs.

Replace paragraph five with the following effective with the December 2019 letting:

- (5) Construct the wedge for each layer using an engineer-approved strike-off device that will provide a uniform slope and will not restrict the main screed. Shape and compact the wedge with a weighted steel side roller wheel or vibratory plate compactor the same width as the wedge. Apply a tack coat to the wedge surface and both notches before placing the adjacent lane.
- (6) Clean longitudinal and transverse joints coated with dust and, if necessary, paint with hot asphaltic material, a cutback, or emulsified asphalt to ensure a tightly bonded, sealed joint.

455.2.5 Tack Coat

Replace paragraph one with the following effective with the December 2019 letting:

(1) Under the Tack Coat bid item, furnish type SS-1h, CSS-1h, QS-1h, CQS-1h, or modified emulsified asphalt with an "h" suffix, unless the contract specifies otherwise.

460.2.2.3 Aggregate Gradation Master Range

Replace paragraph one with the following effective with the December 2019 letting:

(1) Ensure that the aggregate blend, including recycled material and mineral filler, conforms to the gradation requirements in table 460-1. The values listed are design limits; production values may exceed those limits.

TABLE 460-1 AGGREGATE GRADATION MASTER RANGE AND VMA REQUIREMENTS

		PERCENT PASSING DESIGNATED SIEVES						
SIEVE				NOMINA	AL SIZE			
0.272	No. 1	No. 2	No.3	No. 4	No. 5	No. 6	SMA No. 4	SMA No. 5
	(37.5 mm)	(25.0 mm)	(19.0 mm)	(12.5 mm)	(9.5 mm)	(4.75 mm)	(12.5 mm)	(9.5 mm)
50.0-mm	100							
37.5-mm	90 - 100	100						
25.0-mm	90 max	90 - 100	100					
19.0-mm		90 max	90 - 100	100			100	
12.5-mm			90 max	90 - 100	100		90 - 97	100
9.5-mm				90 max	90 - 100	100	58 - 80	90 - 100
4.75-mm					90 max	90 - 100	25 - 35	35 - 45
2.36-mm	15 - 41	19 - 45	23 - 49	28 - 58	32 - 67	90 max	15 - 25	18 - 28
1.18-mm						30 - 55		
0.60-mm							18 max	18 max
0.075-mm	0 - 6.0	1.0 - 7.0	2.0 - 8.0	2.0 - 10.0	2.0 - 10.0	6.0 - 13.0	8.0 - 11.0	8.0 - 12.0
% VMA	11.0 min	12.0 min	13.0 min	14.0 min ^[1]	15.0 min ^[2]	16.0 - 17.5	16.0 min	17.0 min

^{[1] 14.5} for LT and MT mixes.

460.2.7 HMA Mixture Design

Replace paragraph one with the following effective with the December 2019 letting:

(1) For each HMA mixture type used under the contract, develop and submit an asphaltic mixture design according to CMM 8-66 and conforming to the requirements of table 460-1 and table 460-2. Ensure that SMA mixture designs adhere to AASHTO R 46 and AASHTO M 325 in addition to the required test procedures outlined in CMM 8-66 table 1 and CMM 8-66 table 2. Determine the specific gravity of fines or super fines used as a mineral filler or additional stabilizer in SMA designs according to AASHTO T 100. The values listed are design limits; production values may exceed those limits. The department will review mixture designs and report the results of that review to the designer according to CMM 8-66.

^{[2] 15.5} for LT and MT mixes.

TABLE 460-2 MIXTURE REQUIREMENTS

Mixture type	LT	MT	HT	SMA
LA Wear (AASHTO T96)				
100 revolutions(max % loss)	13	13	13	13
500 revolutions(max % loss)	50	45	45	35
Soundness (AASHTO T104) (sodium sulfate, max % loss)	12	12	12	12
Freeze/Thaw (AASHTO T103 as modified in CMM 8-60.2) (specified counties, max % loss)	18	18	18	18
Fractured Faces (ASTM D5821 as modified in CMM 860) (one face/2 face, % by count)	65/	75 / 60	98 / 90	100/90
Flat & Elongated (ASTM D4791) (max %, by weight)	5 (5:1 ratio)	5 (5:1 ratio)	5 (5:1 ratio)	20 (3:1 ratio)
Fine Aggregate Angularity (AASHTO T304, method A, min)	40 ^[1]	43 ^[1]	45	45
Sand Equivalency (AASHTO T176, min)	40	40 ^[2]	45	50
Clay Lumps and Friable Particle in Aggregate (AASHTO T112)	<= 1%	<= 1%	<= 1%	<= 1%
Plasticity Index of Material Added to Mix Design as Mineral Filler (AASHTO T89/90)	<= 4	<= 4	<= 4	<= 4
Gyratory Compaction				
Gyrations for Nini	6	7	8	7
Gyrations for Ndes	40	75	100	65
Gyrations for Nmax	60	115	160	100
Air Voids, %Va (%Gmm Ndes)	4.0 (96.0)	4.0 (96.0)	4.0 (96.0)	4.5 (95.5)
% Gmm Nini	<= 91.5 ^[3]	<= 89.0 ^[3]	<= 89.0	
% Gmm Nmax	<= 98.0	<= 98.0	<= 98.0	<= 98.0
Dust to Binder Ratio ^[4] (% passing 0.075/Pbe)	0.6 - 1.2 ^[5]	0.6 - 1.2 ^[5]	0.6 - 1.2 ^[5]	1.2 - 2.0
Voids filled with Binder (VFB or VFA, %)	68 - 80 ^{[6] [8]}	65 - 75 ^{[6] [7] [9]}	65 - 75 ^{[6] [7] [9]}	70 - 80
Tensile Strength Ratio (TSR) (AASHTO T283)[10] [11]				
no antistripping additive	0.75 min	0.75 min	0.75 min	0.80 min
with antistripping additive	0.80 min	0.80 min	0.80 min	0.80 min
Draindown (AASHTO T305) (%)				<= 0.30
Minimum Effective Asphalt Content, Pbe (%)				5.5
-				

^[1] For No 6 (4.75 mm) nominal maximum size mixes, the specified fine aggregate angularity is 43 for LT and 45 MT mixes.

^[2] For No 6 (4.75 mm) nominal maximum size mixes, the specified sand equivalency is 43 for MT mixes.

^[3] The percent maximum density at initial compaction is only a guideline.

^[4] For a gradation that passes below the boundaries of the caution zone (ref. AASHTO M323), the dust to binder ratio limits are 0.6 - 1.6.

^[5] For No 6 (4.75 mm) nominal maximum size mixes, the specified dust to binder ratio limits are 1.0 - 2.0 for LT mixes and 1.5 - 2.0 for MT and HT mixes.

^[6] For No. 6 (4.75mm) nominal maximum size mixes, the specified VFB is 67 - 79 percent for LT mixes and 66 - 77 percent for MT and HT mixes.

^[7] For No. 5 (9.5mm) and No. 4 (12.5 mm) nominal maximum size mixtures, the specified VFB range is 70 - 76 percent.

^[8] For No. 2 (25.0mm) nominal maximum size mixes, the specified VFB lower limit is 67 percent.

460.2.8.2.1.3.1 Contracts with 5000 Tons of Mixture or Greater

Replace paragraph four with the following effective with the December 2019 letting:

(4) Use the test methods identified below, or other methods the engineer approves, to perform the following tests at the frequency indicated:

Blended aggregate gradations:

Drum plants:

- Field extraction by ignition oven according to AASHTO T308 as modified in CMM 8-36.6.3.6, chemical extraction according to AASHTO T-164 method A or B; or automated extraction according to ASTM D8159 as modified in CMM 8-36.6.3.1. Gradation of resulting aggregate sample determined according to AASHTO T30.
- Belt samples, optional for virgin mixtures, obtained from stopped belt or from the belt discharge using an engineer-approved sampling device and performed according to AASHTO T11 and T27.

Batch plants:

 Field extraction by ignition oven according to AASHTO T308 as modified in CMM 8-36.6.3.6, chemical extraction according to AASHTO T-164 method A or B; or automated extraction according to ASTM D8159 as modified in CMM 8-36.6.3.1. Gradation of resulting aggregate sample determined according to AASHTO T30.

Asphalt content (AC) in percent:

AC by ignition oven according to AASHTO T308 (CMM 8-36.6.3.6), by chemical extraction according to AASHTO T-164 method A or B; or by automated extraction according to ASTM D8159 as modified in CMM 8-36.6.3.1. Gradation of resulting aggregate sample determined according to AASHTO T30.

Bulk specific gravity of the compacted mixture according to AASHTO T166.

Maximum specific gravity according to AASHTO T209.

Air voids (Va) by calculation according to AASHTO T269.

VMA by calculation according to AASHTO R35.

460.2.8.2.1.4.2 Control Charts

Replace paragraph one with the following effective with the December 2019 letting:

- (1) Maintain standardized control charts at the laboratory. Record contractor test results on the charts the same day as testing. Record data on the standardized control charts as follows:
 - Blended aggregate gradation tests in percent passing. Of the following, plot sieves required in table 460-1: 37.5-mm, 25.0-mm, 19.0-mm, 12.5-mm, 9.5-mm, 4.75-mm, 2.36-mm, 1.18-mm, 0.60-mm, and 0.075-mm.
 - Asphalt material content in percent.
 - Air voids in percent.
 - VMA in percent.
- (2) Plot both the individual test point and the running average of the last 4 data points on each chart. Show QC data in black with the running average in red. Draw the warning limits with a dashed green line and the JMF limits with a dashed red line. The contractor may use computer generated black-and-white printouts with a legend that clearly identifies the specified color-coded components.

^[9] For No. 1 (37.5mm) nominal maximum size mixes, the specified VFB lower limit is 67 percent.

^[10] WisDOT eliminates freeze-thaw conditioning cycles from the TSR test procedure.

^[11] Run TSR at asphalt content corresponding to 3.0% air void regressed design, or 4.5% air void design for SMA, using distilled water for testing.

460.2.8.2.1.5 Control Limits

Replace paragraph one with the following effective with the December 2019 letting:

(1) Conform to the following control limits for the JMF and warning limits based on a running average of the last 4 data points:

ITEM	JMF LIMITS	WARNING LIMITS
Percent passing given sieve:		
37.5-mm	+/- 6.0	+/- 4.5
25.0-mm	+/- 6.0	+/- 4.5
19.0-mm	+/- 5.5	+/- 4.0
12.5-mm	+/- 5.5	+/- 4.0
9.5-mm	+/- 5.5	+/- 4.0
4.75-mm	+/- 5.0	+/- 4.0
2.36-mm	+/- 5.0	+/- 4.0
1.18-mm	+/- 4.0	+/- 3.0
0.60-mm	+/- 4.0	+/- 3.0
0.075-mm	+/- 2.0	+/- 1.5
Asphaltic content in percent	- 0.3	- 0.2
Air voids in percent ^[1]	+1.3/-1.0	+1.0/-0.7
VMA in percent ^[2]	- 0.5	- 0.2

^[1] For SMA, JMF limits are +/-1.3 and warning limits are +/-1.0.

460.3.2 Thickness

Replace paragraph one with the following effective with the December 2019 letting:

(1) Provide the plan thickness for lower and upper layers limited as follows:

NOMINAL	MINIMUM	MAX LOWER	MAX UPPER	MAX SINGLE
SIZE	LAYER	LAYER	LAYER	LAYER
	THICKNESS	THICKNESS	THICKNESS	THICKNESS[3]
	(in inches)	(in inches)	(in inches)	(in inches)
No. 1 (37.5 mm)	4.5	6	4.5	6
No. 2 (25.0 mm)	3.0	5	4	6
No. 3 (19.0 mm	2.25	4	3	5
No. 4 (12.5 mm) ^[1]	1.75	3[2]	2.5	4
No. 5 (9.5 mm) ^[1]	1.25	3[2]	2	3
No. 6 (4.75 mm)	0.75	1.25	1.25	1.25

^[1] SMA mixtures use nominal size No. 4 (12.5 mm) or No. 5 (9.5 mm).

^[2] VMA limits are based on requirements for each mix design nominal maximum aggregate size in table 460-1. For No. 6 (4.75mm) mixes, JMF limits are +/- 0.5 and warning limits are +/- 0.2.

^[2] SMA mixtures with nominal sizes of No. 4 (12.5 mm) and No. 5 (9.5 mm) have no maximum lower layer thickness specified.

^[3] For use on cross-overs and shoulders.

⁽²⁾ Place leveling layers using No. 4 (12.5 mm), No. 5 (9.5 mm), or No. 6 (4.75 mm) mixtures. Leveling layers may be thinner than the minimum lower layer thickness for the mixture used.

⁽³⁾ Place wedging layers as the contract specifies or engineer directs. Wedging layers have no specified minimum or maximum thickness.

460.3.3.1 Minimum Required Density

Replace paragraph one with the following effective with the December 2019 letting:

(1) Compact No. 6 mixtures in lower layers as specified in 450.3.2.6.2 and in upper layers as specified in 450.3.2.6.3. For other HMA mixtures, compact all layers to the density table 460-3 specifies.

TABLE 460-3	MINIMIIM	REQUIRED	DENSITY[1]
I ADLL TUUT		ILLGOUILLD	DEMOIL 1.

The state of the s						
		PERCENT OF TARGET MAXIMUM DENSITY				
LOCATION	LAYER		MIXTURE TYPE			
		LT and MT	НТ	SMA ^[5]		
TRAFFIC LANES[2]	LOWER	93.0 ^[3]	93.0 ^[4]			
TRAFFIC LANES	UPPER	93.0	93.0	93.0		
SHOULDERS &	LOWER	91.0	91.0			
APPURTENANCES	UPPER	92.0	92.0	92.0		

^[1] The table values are for average lot density. If any individual density test result falls more than 3.0 percent below the minimum required target maximum density, the engineer will investigate the acceptability of that material according to CMM 8-15.11.

460.3.3.2 Pavement Density Determination

Replace paragraph three with the following effective with the December 2019 letting:

(3) A lot is defined in CMM 8-15 and placed within a single layer for each location and target maximum density category indicated in table 460-3. The lot density is the average of all samples taken for that lot. The department determines the number of tests per lot according to CMM 8-15.

460.5.2.1 General

Replace paragraph six with the following effective with the December 2019 letting:

- (6) If during a QV dispute resolution investigation the department discovers unacceptable mixture defined by one or more of the following:
 - Va less than 2.5 or greater than 6.5 percent for SMA, or for other mixes, less than 1.5 or greater than 5.0 percent.
 - VMA more than 1.0 percent below the minimum or above the maximum specified in table 460-1.
 - AC more than 0.5 % below the JMF target.

Remove and replace the material, or if the engineer allows the mixture to remain in place, the department will pay for the quantity of affected material at 50 percent of the contract price.

^[2] Includes side roads, crossovers, turn lanes, ramps, parking lanes, bike lanes, and park-and-ride lots as defined by the contract plans.

^[3] Minimum reduced by 2.0 percent for a lower layer constructed directly on crushed aggregate or recycled base courses.

^[4] Minimum reduced by 1.0 percent for a lower layer constructed directly on crushed aggregate or recycled base courses.

501.2.5.5 Sampling and Testing

Replace paragraph one with the following effective with the December 2019 letting:

(1) Sample and test aggregates for concrete according to the following:

Sampling aggregates ^[1]	AASHTO T2
Lightweight pieces in aggregate	AASHTO T113
Material finer than No. 200 sieve ^[1]	AASHTO T11
Unit weight of aggregate	AASHTO T19
Organic impurities in sands	AASHTO T21
Sieve analysis of aggregates	AASHTO T27
Effect of organic impurities in fine aggregate	AASHTO T71
Los Angeles abrasion of coarse aggregate	AASHTO T96
Alkali Silica Reactivity of Aggregates	ASTM C1260
Alkali Silica Reactivity of Combinations of Cementitious Materials and Aggregates	ASTM C1567
Freeze-thaw soundness of coarse aggregate ^[1]	AASHTO T103
Sodium sulfate soundness of coarse aggregates (R-4, 5 cycles)	AASHTO T104
Specific gravity and absorption of fine aggregate	AASHTO T84
Specific gravity and absorption of coarse aggregate ^[1]	AASHTO T85
Flat & elongated pieces based on a 3:1 ratio ^[1]	ASTM D4791
Sampling fresh concrete	AASHTO R60
Making and curing concrete compressive strength test specimens	AASHTO T23
Compressive strength of molded concrete cylinders	AASHTO T22
[1] As modified in CMM 8-60.	

505.2.2 Bar Steel Reinforcement

Replace paragraph one with the following effective with the December 2019 letting:

(1) Conform to AASHTO M31, type S or type W.

505.2.3 High-Strength Bar Steel Reinforcement

Replace paragraph one with the following effective with the December 2019 letting:

(1) Conform to AASHTO M31, grade 60, type S or type W.

505.2.4.1 General

Replace paragraph one with the following effective with the December 2019 letting:

(1) Conform to AASHTO M31, grade 60, type S or type W. Ensure that the coating is applied in a CRSI certified epoxy coating plant. Bend bars that require bending before coating, unless the fabricator can bend the bar without damaging the coating.

505.2.6.1 General

Replace paragraph one with the following effective with the December 2019 letting:

(1) For dowel bars and straight tie bars, there is no requirement for bend tests. Ensure that the bars are the specified diameter and length the plans show.

505.2.6.2.2 Solid Dowel Bars

Replace paragraph one with the following effective with the December 2019 letting:

(1) Furnish coated bars conforming to AASHTO M31 grade 40 or 60. Alternatively the contractor may furnish dowel bars conforming to AASHTO M227 grade 70-80. Coat in a plant certified by the Concrete Reinforcing Steel Institute with a thermosetting epoxy conforming to AASHTO M254, type B.

520.3.7 Deflection Testing

Replace paragraphs three and four with the following effective with the June 2020 letting:

- (3) Test 100 percent of the installed length of pipe 24 inches or greater in diameter. Ensure that the mandrel passes through the entire section in one pass when pulled by hand without using excessive force. If the designated length of pipe fails, the engineer may require additional testing.
- (4) For pipe less than 24 inches in diameter, the engineer will designate at least 10 percent of the installed length of pipe for testing. The mandrel must pass through the entire section in one pass when pulled by hand without using excessive force. If the designated length of pipe fails, engineer may require additional testing.
- (5) Relay or replace pipe that does not pass deflection testing. Retest all relayed or replaced pipe.

608.3.7 Deflection Testing

Replace paragraphs three and four with the following effective with the June 2020 letting:

- (3) Test 100 percent of the installed length of pipe 24 inches or greater in diameter. Ensure that the mandrel passes through the entire section in one pass when pulled by hand without using excessive force. If the designated length of pipe fails, the engineer may require additional testing.
- (4) For pipe less than 24 inches in diameter, the engineer will designate at least 10 percent of the installed length of pipe for testing. The mandrel must pass through the entire section in one pass when pulled by hand without using excessive force. If the designated length of pipe fails, engineer may require additional testing.
- (5) Relay or replace pipe that does not pass deflection testing. Retest all relayed or replaced pipe.

625.3.2 Processing Topsoil or Salvaged Topsoil

Delete paragraph four effective with the December 2019 letting.

701.3.1 General

Replace the entire text with the following effective with the December 2019 letting:

(1) Perform contract required QC tests for samples randomly located according to CMM 8-30. Use the test methods specified in table 701-1.

TABLE 701-1 TESTING AND CERTIFICATION STANDARDS

		T
TEST	TEST	MINIMUM REQUIRED CERTIFICATION
	STANDARD	(any one of the certifications listed for each test)
Random Sampling	CMM 8-30.9.2	Transportation Materials Sampling Technician (TMS) Aggregate Technician I (AGGTEC-I) AGGTEC-I Assistant Certified Technician (ACT-AGG) PCC Technician I (PCCTEC-I) PCCTEC-I Assistant Certified Technician (ACT-PCC) Grading Technician I (GRADINGTEC-I) Grading Assistant Certified Technician (ACT-GRADING)
Sampling Aggregates	AASHTO T2 ^{[1][4]}	TMS, AGGTECT-1, ACT-AGG
Percent passing the No. 200 sieve	AASHTO T11 ^[1]	
Fine and coarse aggregate gradation	AASHTO T27 ^[1]	AGGTEC-I, ACT-AGG
Aggregate moisture content	AASHTO T255 ^[1]	AGG120-1, AG1-AGG
Fractured faces	ASTM D5821 ^[1]	
Liquid limit	AASHTO T89	Aggregate Testing for Transportation Systems (ATTS)
Plasticity index	AASHTO T90 ^[3]	GRADINGTEC-I, or ACT-GRADING
Sampling freshly mixed concrete	AASHTO R60	
Air content of fresh concrete	AASHTO T152 ^[2]	
Air void system of fresh concrete	AASHTO TP118 ^[5]	DOOTEO 4
Concrete slump	AASHTO T119 ^[2]	PCCTEC-1 ACT-PCC
Concrete temperature	ASTM C1064	7,611.66
Making and curing concrete cylinders	AASHTO T23	
Moist curing for concrete cylinders	AASHTO M201	
Concrete compressive strength	AASHTO T22	Concrete Strength Tester (CST)
Concrete flexural strength	AASHTO T97	CST Assistant Certified Technician (ACT-CST)
Profiling		PROFILER

^[1] As modified in CMM 8-60.

715.2.1 General

Replace paragraph five with the following effective with the December 2019 letting:

(5) For new lab-qualified mixes, test the air void system of the proposed concrete mix. Include the SAM number as a part of the mix design submittal.

^[2] As modified in CMM 8-70.

^[3] A plasticity check, if required under individual QMP provisions, may be performed by an AGGTEC-I in addition to the certifications listed for liquid limit and plasticity index tests.

^[4] Plant personnel may operate equipment to obtain samples under the direct observation of a TMS or higher.

^[5] Consolidate by rodding.

715.3.1.1 General

Replace paragraph two with the following effective with the December 2019 letting:

- (2) Test the air void system at least once per lot and enter the SAM number in the MRS for information only. SAM testing is not required for the following:
 - For lots with less than 4 sublots.
 - High early strength (HES) concrete.
 - Special high early strength (SHES) concrete.
 - Concrete placed under the following bid items:
 - Concrete Pavement Approach Slab
 - Concrete Masonry Culverts
 - Concrete Masonry Retaining Walls
 - Steel Grid Floor Concrete Filled
 - Crash Cushions Permanent
 - Crash Cushions Permanent Low Maintenance
 - Crash Cushions Temporary

730.3.1 General

Replace paragraph three with the following effective with the December 2019 letting:

- (3) Stockpile tests^[1] can be used for multiple projects. If placement on a project does not begin within 120 calendar days after the date the stockpile sample was obtained, retest the stockpile before placement begins.
 - [1] Replace the stockpile test with an in-place production test for concrete pavement recycled and processed onsite; test on the first day of production.

730.3.2 Contractor QC Testing

Replace paragraph four with the following effective with the December 2019 letting:

(4) Submit test results to the engineer within one business day of obtaining the sample, except any aggregate classification with recycled asphalt may be submitted within two business days.

730.3.4.1 Contractor QC Testing

Replace the entire text with the following effective with the December 2019 letting:

- (1) For small quantity contracts with <= 500 tons, submit 2 production tests or 1 stockpile test. Production tests are valid for 3 years from the date the production sample was obtained. Begin placement within 3 years of the date sampled.
- (2) For small quantity contracts with <= 6000 tons and >= 500 tons, do the following:
 - 1. Conduct one QC stockpile test before placement.
 - 2. Submit 2 production tests or conduct 1 loadout test instead of placement tests. Production tests are valid for 3 years from the date the production sample was obtained; the first day of placement must be within 3 years of the date sampled.
 - 3. If the actual quantity placed is more than 6000 tons, on the next day of placement perform one additional random QC test for each 3000 tons of overrun, or fraction thereof.

740.3.2 Contractor QC Testing

Replace paragraph three with the following effective with the December 2019 letting:

- (3) Field-locate the beginning and ending points for each profile run. Measure the profiles of each standard and partial segment. Define primary segments starting at a project terminus and running contiguously along the mainline to the other project terminus. Define segments one wheel path wide and distinguished by length as follows:
 - 1. Standard segments are 500 feet long.
 - 2. Partial segments are less than 500 feet long.

Errata

104.6.1.2.3 Drop-Off and Hazard Protection

Correct errata by changing 2 inches or greater to greater than 2 inches.

(1) Eliminate vertical drop-offs greater than 2 inches and edge slopes steeper than 3:1 between adjacent lanes open to traffic.

305.3.3.3 Shoulders Adjacent to Asphaltic Pavement or Surfacing

Correct errata by changing 2-inch or more to greater than 2-inch.

(2) If the roadway remains open to through traffic during construction and a greater than 2-inch drop-off occurs within 3 feet or less from the edge of the traveled way, eliminate the drop-off within 48 hours after completing that days paving. Unless the special provisions specify otherwise, provide aggregate shoulder material compacted to a temporary 3:1 or flatter cross slope from the surface of the pavement edge.

501.3.2.2 Concrete Proportions

Correct errata in footnote [8] by allowing either grade 100 or grade 120 slag in C-S concrete.

[8] For grade C-S concrete, use grade 100 or grade 120 slag.

614.3.6 Thrie Beam Structure Approach Retro Fits

Correct errata by deleting the galvanization reference already required under 614.3.1.

(2) Install posts and drill holes into existing thrie beam conforming to 614.3.2.

628.3.7 Mobilizations for Erosion Control

Correct errata by clarifying that mobilizations for erosion control include proceeding with the work.

(1) Move personnel, equipment, and materials to the project site and promptly proceed with construction of erosion control items at the stages the contract indicates or the engineer directs.

ADDITIONAL SPECIAL PROVISION 7

- A. Reporting 1st Tier and DBE Payments During Construction
 - 1. Comply with reporting requirements specified in the department's Civil Rights Compliance, Contractor's User Manual, Sublets and Payments.
 - 2. Report payments to all DBE firms within 10 calendar days of receipt of a progress payment by the department or a contractor for work performed, materials furnished, or materials stockpiled by a DBE firm. Report the payment as specified in A(1) for all work satisfactorily performed and for all materials furnished or stockpiled.
 - 3. Report payments to all first tier subcontractor relationships within 10 calendar days of receipt of a progress payment by the department for work performed. Report the payment as specified in A(1) for all work satisfactorily performed.
 - 4. All tiers shall report payments as necessary to comply with the DBE payment requirement as specified in A(2).
 - 5. Require all first tier relationships, DBE firms and all other tier relationships necessary to comply with the DBE payment requirement in receipt of a progress payment by contractor to acknowledge receipt of payment as specified in A(1), (2), (3) and (4).
 - 6. All agreements made by a contractor shall include the provisions in A(1), (2), (3), (4) and (5), and shall be binding on all first tier subcontractor relationships and all contractors and subcontractors utilizing DBE firms on the project.
- B. Costs for conforming to this special provision are incidental to the contract.

NOTE: CRCS Prime Contractor payment is currently not automated and will need to be manually loaded into the Civil Rights Compliance System. Copies of prime contractor payments received (check or ACH) will have to be forwarded to paul.ndon@dot.wi.gov within 5 days of payment receipt to be logged manually.

***Additionally, for information on Subcontractor Sublet assignments, Subcontractor Payments and Payment Tracking, please refer to the CRCS Payment and Sublets manual at:

 $\underline{https://wisconsindot.gov/Documents/doing-bus/civil-rights/labornwage/crcs-payments-sublets-\underline{manual.pdf}}$

ADDITIONAL SPECIAL PROVISION 9 Electronic Certified Payroll or Labor Data Submittal

(1) Use the department's Civil Rights Compliance System (CRCS) to electronically submit certified payroll reports for contracts with federal funds and labor data for contracts with state funds only. Details are available online through the department's highway construction contractor information (HCCI) site on the Labor, Wages, and EEO Information page at:

https://wisconsindot.gov/Pages/doing-bus/civil-rights/labornwage/default.aspx

- (2) Ensure that all tiers of subcontractors, including all trucking firms, either submit their weekly certified payroll reports (contracts with federal funds) or labor data (contracts with state funds only) electronically through CRCS. These payrolls or labor data are due within seven calendar days following the close of the payroll period. Every firm providing physical labor towards completing the project is a subcontractor under this special provision.
- (3) Upon receipt of contract execution, promptly make all affected firms aware of the requirements under this special provision and arrange for them to receive CRCS training as they are about to begin their submittals. The department will provide training either in a classroom setting at one of our regional offices or by telephone. Contact Paul Ndon at (414) 438-4584 to schedule the training.
- (4) The department will reject all paper submittals for information required under this special provision. All costs for conforming to this special provision are incidental to the contract.
- (5) Firms wishing to export payroll/labor data from their computer system into CRCS should have their payroll coordinator contact Paul Ndon at paul.ndon@dot.wi.gov. Not every contractor's payroll system is capable of producing export files. For details, see Section 4.8 CPR Auto Submit (Data Mapping) on pages 49-50; 66-71 of the CRCS Payroll Manual at:

https://wisconsindot.gov/Documents/doing-bus/civil-rights/labornwage/crcs-payroll-manual.pdf

REQUIRED CONTRACT PROVISIONS FEDERAL-AID CONSTRUCTION CONTRACTS

- I. General
- II. Nondiscrimination
- III. Nonsegregated Facilities
- IV. Davis-Bacon and Related Act Provisions
- V. Contract Work Hours and Safety Standards Act
- VI. Subletting or Assigning the Contract
- VII. Safety: Accident Prevention
- VIII. False Statements Concerning Highway Projects
- IX. Implementation of Clean Air Act and Federal Water Pollution Control Act
- Compliance with Governmentwide Suspension and Debarment Requirements
- Certification Regarding Use of Contract Funds for Lobbying

ATTACHMENTS

A. Employment and Materials Preference for Appalachian Development Highway System or Appalachian Local Access Road Contracts (included in Appalachian contracts only)

I. GENERAL

1. Form FHWA-1273 must be physically incorporated in each construction contract funded under Title 23 (excluding emergency contracts solely intended for debris removal). The contractor (or subcontractor) must insert this form in each subcontract and further require its inclusion in all lower tier subcontracts (excluding purchase orders, rental agreements and other agreements for supplies or services).

The applicable requirements of Form FHWA-1273 are incorporated by reference for work done under any purchase order, rental agreement or agreement for other services. The prime contractor shall be responsible for compliance by any subcontractor, lower-tier subcontractor or service provider.

Form FHWA-1273 must be included in all Federal-aid designbuild contracts, in all subcontracts and in lower tier subcontracts (excluding subcontracts for design services, purchase orders, rental agreements and other agreements for supplies or services). The design-builder shall be responsible for compliance by any subcontractor, lower-tier subcontractor or service provider.

Contracting agencies may reference Form FHWA-1273 in bid proposal or request for proposal documents, however, the Form FHWA-1273 must be physically incorporated (not referenced) in all contracts, subcontracts and lower-tier subcontracts (excluding purchase orders, rental agreements and other agreements for supplies or services related to a construction contract).

2. Subject to the applicability criteria noted in the following sections, these contract provisions shall apply to all work performed on the contract by the contractor's own organization and with the assistance of workers under the contractor's immediate superintendence and to all work performed on the contract by piecework, station work, or by subcontract.

- 3. A breach of any of the stipulations contained in these Required Contract Provisions may be sufficient grounds for withholding of progress payments, withholding of final payment, termination of the contract, suspension / debarment or any other action determined to be appropriate by the contracting agency and FHWA.
- 4. Selection of Labor: During the performance of this contract, the contractor shall not use convict labor for any purpose within the limits of a construction project on a Federal-aid highway unless it is labor performed by convicts who are on parole, supervised release, or probation. The term Federal-aid highway does not include roadways functionally classified as local roads or rural minor collectors.

II. NONDISCRIMINATION

The provisions of this section related to 23 CFR Part 230 are applicable to all Federal-aid construction contracts and to all related construction subcontracts of \$10,000 or more. The provisions of 23 CFR Part 230 are not applicable to material supply, engineering, or architectural service contracts.

In addition, the contractor and all subcontractors must comply with the following policies: Executive Order 11246, 41 CFR 60, 29 CFR 1625-1627, Title 23 USC Section 140, the Rehabilitation Act of 1973, as amended (29 USC 794), Title VI of the Civil Rights Act of 1964, as amended, and related regulations including 49 CFR Parts 21, 26 and 27; and 23 CFR Parts 200, 230, and 633.

The contractor and all subcontractors must comply with: the requirements of the Equal Opportunity Clause in 41 CFR 60-1.4(b) and, for all construction contracts exceeding \$10,000, the Standard Federal Equal Employment Opportunity Construction Contract Specifications in 41 CFR 60-4.3.

Note: The U.S. Department of Labor has exclusive authority to determine compliance with Executive Order 11246 and the policies of the Secretary of Labor including 41 CFR 60, and 29 CFR 1625-1627. The contracting agency and the FHWA have the authority and the responsibility to ensure compliance with Title 23 USC Section 140, the Rehabilitation Act of 1973, as amended (29 USC 794), and Title VI of the Civil Rights Act of 1964, as amended, and related regulations including 49 CFR Parts 21, 26 and 27; and 23 CFR Parts 200, 230, and 633.

The following provision is adopted from 23 CFR 230, Appendix A, with appropriate revisions to conform to the U.S. Department of Labor (US DOL) and FHWA requirements.

1. Equal Employment Opportunity: Equal employment opportunity (EEO) requirements not to discriminate and to take affirmative action to assure equal opportunity as set forth under laws, executive orders, rules, regulations (28 CFR 35, 29 CFR 1630, 29 CFR 1625-1627, 41 CFR 60 and 49 CFR 27) and orders of the Secretary of Labor as modified by the provisions prescribed herein, and imposed pursuant to 23 U.S.C. 140 shall constitute the EEO and specific affirmative action standards for the contractor's project activities under

this contract. The provisions of the Americans with Disabilities Act of 1990 (42 U.S.C. 12101 et seq.) set forth under 28 CFR 35 and 29 CFR 1630 are incorporated by reference in this contract. In the execution of this contract, the contractor agrees to comply with the following minimum specific requirement activities of EEO:

- a. The contractor will work with the contracting agency and the Federal Government to ensure that it has made every good faith effort to provide equal opportunity with respect to all of its terms and conditions of employment and in their review of activities under the contract.
- b. The contractor will accept as its operating policy the following statement:

"It is the policy of this Company to assure that applicants are employed, and that employees are treated during employment, without regard to their race, religion, sex, color, national origin, age or disability. Such action shall include: employment, upgrading, demotion, or transfer; recruitment or recruitment advertising; layoff or termination; rates of pay or other forms of compensation; and selection for training, including apprenticeship, pre-apprenticeship, and/or on-the-job training."

- 2. EEO Officer: The contractor will designate and make known to the contracting officers an EEO Officer who will have the responsibility for and must be capable of effectively administering and promoting an active EEO program and who must be assigned adequate authority and responsibility to do so
- 3. Dissemination of Policy: All members of the contractor's staff who are authorized to hire, supervise, promote, and discharge employees, or who recommend such action, or who are substantially involved in such action, will be made fully cognizant of, and will implement, the contractor's EEO policy and contractual responsibilities to provide EEO in each grade and classification of employment. To ensure that the above agreement will be met, the following actions will be taken as a minimum:
- a. Periodic meetings of supervisory and personnel office employees will be conducted before the start of work and then not less often than once every six months, at which time the contractor's EEO policy and its implementation will be reviewed and explained. The meetings will be conducted by the EEO Officer.
- b. All new supervisory or personnel office employees will be given a thorough indoctrination by the EEO Officer, covering all major aspects of the contractor's EEO obligations within thirty days following their reporting for duty with the contractor.
- c. All personnel who are engaged in direct recruitment for the project will be instructed by the EEO Officer in the contractor's procedures for locating and hiring minorities and women.
- d. Notices and posters setting forth the contractor's EEO policy will be placed in areas readily accessible to employees, applicants for employment and potential employees.
- e. The contractor's EEO policy and the procedures to implement such policy will be brought to the attention of employees by means of meetings, employee handbooks, or other appropriate means.

- **4. Recruitment:** When advertising for employees, the contractor will include in all advertisements for employees the notation: "An Equal Opportunity Employer." All such advertisements will be placed in publications having a large circulation among minorities and women in the area from which the project work force would normally be derived.
- a. The contractor will, unless precluded by a valid bargaining agreement, conduct systematic and direct recruitment through public and private employee referral sources likely to yield qualified minorities and women. To meet this requirement, the contractor will identify sources of potential minority group employees, and establish with such identified sources procedures whereby minority and women applicants may be referred to the contractor for employment consideration.
- b. In the event the contractor has a valid bargaining agreement providing for exclusive hiring hall referrals, the contractor is expected to observe the provisions of that agreement to the extent that the system meets the contractor's compliance with EEO contract provisions. Where implementation of such an agreement has the effect of discriminating against minorities or women, or obligates the contractor to do the same, such implementation violates Federal nondiscrimination provisions.
- c. The contractor will encourage its present employees to refer minorities and women as applicants for employment. Information and procedures with regard to referring such applicants will be discussed with employees.
- **5. Personnel Actions:** Wages, working conditions, and employee benefits shall be established and administered, and personnel actions of every type, including hiring, upgrading, promotion, transfer, demotion, layoff, and termination, shall be taken without regard to race, color, religion, sex, national origin, age or disability. The following procedures shall be followed:
- a. The contractor will conduct periodic inspections of project sites to insure that working conditions and employee facilities do not indicate discriminatory treatment of project site personnel.
- b. The contractor will periodically evaluate the spread of wages paid within each classification to determine any evidence of discriminatory wage practices.
- c. The contractor will periodically review selected personnel actions in depth to determine whether there is evidence of discrimination. Where evidence is found, the contractor will promptly take corrective action. If the review indicates that the discrimination may extend beyond the actions reviewed, such corrective action shall include all affected persons.
- d. The contractor will promptly investigate all complaints of alleged discrimination made to the contractor in connection with its obligations under this contract, will attempt to resolve such complaints, and will take appropriate corrective action within a reasonable time. If the investigation indicates that the discrimination may affect persons other than the complainant, such corrective action shall include such other persons. Upon completion of each investigation, the contractor will inform every complainant of all of their avenues of appeal.

6. Training and Promotion:

a. The contractor will assist in locating, qualifying, and increasing the skills of minorities and women who are

applicants for employment or current employees. Such efforts should be aimed at developing full journey level status employees in the type of trade or job classification involved.

- b. Consistent with the contractor's work force requirements and as permissible under Federal and State regulations, the contractor shall make full use of training programs, i.e., apprenticeship, and on-the-job training programs for the geographical area of contract performance. In the event a special provision for training is provided under this contract, this subparagraph will be superseded as indicated in the special provision. The contracting agency may reserve training positions for persons who receive welfare assistance in accordance with 23 U.S.C. 140(a).
- c. The contractor will advise employees and applicants for employment of available training programs and entrance requirements for each.
- d. The contractor will periodically review the training and promotion potential of employees who are minorities and women and will encourage eligible employees to apply for such training and promotion.
- 7. Unions: If the contractor relies in whole or in part upon unions as a source of employees, the contractor will use good faith efforts to obtain the cooperation of such unions to increase opportunities for minorities and women. Actions by the contractor, either directly or through a contractor's association acting as agent, will include the procedures set forth below:
- a. The contractor will use good faith efforts to develop, in cooperation with the unions, joint training programs aimed toward qualifying more minorities and women for membership in the unions and increasing the skills of minorities and women so that they may qualify for higher paying employment.
- b. The contractor will use good faith efforts to incorporate an EEO clause into each union agreement to the end that such union will be contractually bound to refer applicants without regard to their race, color, religion, sex, national origin, age or disability.
- c. The contractor is to obtain information as to the referral practices and policies of the labor union except that to the extent such information is within the exclusive possession of the labor union and such labor union refuses to furnish such information to the contractor, the contractor shall so certify to the contracting agency and shall set forth what efforts have been made to obtain such information.
- d. In the event the union is unable to provide the contractor with a reasonable flow of referrals within the time limit set forth in the collective bargaining agreement, the contractor will, through independent recruitment efforts, fill the employment vacancies without regard to race, color, religion, sex, national origin, age or disability; making full efforts to obtain qualified and/or qualifiable minorities and women. The failure of a union to provide sufficient referrals (even though it is obligated to provide exclusive referrals under the terms of a collective bargaining agreement) does not relieve the contractor from the requirements of this paragraph. In the event the union referral practice prevents the contractor from meeting the obligations pursuant to Executive Order 11246, as amended, and these special provisions, such contractor shall immediately notify the contracting agency.
- 8. Reasonable Accommodation for Applicants / Employees with Disabilities: The contractor must be familiar

with the requirements for and comply with the Americans with Disabilities Act and all rules and regulations established there under. Employers must provide reasonable accommodation in all employment activities unless to do so would cause an undue hardship.

- 9. Selection of Subcontractors, Procurement of Materials and Leasing of Equipment: The contractor shall not discriminate on the grounds of race, color, religion, sex, national origin, age or disability in the selection and retention of subcontractors, including procurement of materials and leases of equipment. The contractor shall take all necessary and reasonable steps to ensure nondiscrimination in the administration of this contract.
- a. The contractor shall notify all potential subcontractors and suppliers and lessors of their EEO obligations under this contract.
- b. The contractor will use good faith efforts to ensure subcontractor compliance with their EEO obligations.

10. Assurance Required by 49 CFR 26.13(b):

- a. The requirements of 49 CFR Part 26 and the State DOT's U.S. DOT-approved DBE program are incorporated by reference.
- b. The contractor or subcontractor shall not discriminate on the basis of race, color, national origin, or sex in the performance of this contract. The contractor shall carry out applicable requirements of 49 CFR Part 26 in the award and administration of DOT-assisted contracts. Failure by the contractor to carry out these requirements is a material breach of this contract, which may result in the termination of this contract or such other remedy as the contracting agency deems appropriate.
- 11. Records and Reports: The contractor shall keep such records as necessary to document compliance with the EEO requirements. Such records shall be retained for a period of three years following the date of the final payment to the contractor for all contract work and shall be available at reasonable times and places for inspection by authorized representatives of the contracting agency and the FHWA.
- a. The records kept by the contractor shall document the following:
- (1) The number and work hours of minority and nonminority group members and women employed in each work classification on the project;
 - (2) The progress and efforts being made in cooperation with unions, when applicable, to increase employment opportunities for minorities and women; and
 - (3) The progress and efforts being made in locating, hiring, training, qualifying, and upgrading minorities and women;
- b. The contractors and subcontractors will submit an annual report to the contracting agency each July for the duration of the project, indicating the number of minority, women, and non-minority group employees currently engaged in each work classification required by the contract work. This information is to be reported on Form FHWA-1391. The staffing data should represent the project work force on board in all or any part of the last payroll period preceding the end of July. If on-the-job training is being required by special provision, the contractor

will be required to collect and report training data. The employment data should reflect the work force on board during all or any part of the last payroll period preceding the end of July.

III. NONSEGREGATED FACILITIES

This provision is applicable to all Federal-aid construction contracts and to all related construction subcontracts of \$10,000 or more.

The contractor must ensure that facilities provided for employees are provided in such a manner that segregation on the basis of race, color, religion, sex, or national origin cannot result. The contractor may neither require such segregated use by written or oral policies nor tolerate such use by employee custom. The contractor's obligation extends further to ensure that its employees are not assigned to perform their services at any location, under the contractor's control, where the facilities are segregated. The term "facilities" includes waiting rooms, work areas, restaurants and other eating areas, time clocks, restrooms, washrooms, locker rooms, and other storage or dressing areas, parking lots, drinking fountains, recreation or entertainment areas, transportation, and housing provided for employees. The contractor shall provide separate or single-user restrooms and necessary dressing or sleeping areas to assure privacy between sexes.

IV. DAVIS-BACON AND RELATED ACT PROVISIONS

This section is applicable to all Federal-aid construction projects exceeding \$2,000 and to all related subcontracts and lower-tier subcontracts (regardless of subcontract size). The requirements apply to all projects located within the right-of-way of a roadway that is functionally classified as Federal-aid highway. This excludes roadways functionally classified as local roads or rural minor collectors, which are exempt. Contracting agencies may elect to apply these requirements to other projects.

The following provisions are from the U.S. Department of Labor regulations in 29 CFR 5.5 "Contract provisions and related matters" with minor revisions to conform to the FHWA-1273 format and FHWA program requirements.

1. Minimum wages

a. All laborers and mechanics employed or working upon the site of the work, will be paid unconditionally and not less often than once a week, and without subsequent deduction or rebate on any account (except such payroll deductions as are permitted by regulations issued by the Secretary of Labor under the Copeland Act (29 CFR part 3)), the full amount of wages and bona fide fringe benefits (or cash equivalents thereof) due at time of payment computed at rates not less than those contained in the wage determination of the Secretary of Labor which is attached hereto and made a part hereof, regardless of any contractual relationship which may be alleged to exist between the contractor and such laborers and mechanics.

Contributions made or costs reasonably anticipated for bona fide fringe benefits under section 1(b)(2) of the Davis-Bacon Act on behalf of laborers or mechanics are considered wages paid to such laborers or mechanics, subject to the provisions

of paragraph 1.d. of this section; also, regular contributions made or costs incurred for more than a weekly period (but not less often than quarterly) under plans, funds, or programs which cover the particular weekly period, are deemed to be constructively made or incurred during such weekly period. Such laborers and mechanics shall be paid the appropriate wage rate and fringe benefits on the wage determination for the classification of work actually performed, without regard to skill, except as provided in 29 CFR 5.5(a)(4). Laborers or mechanics performing work in more than one classification may be compensated at the rate specified for each classification for the time actually worked therein: Provided, That the employer's payroll records accurately set forth the time spent in each classification in which work is performed. The wage determination (including any additional classification and wage rates conformed under paragraph 1.b. of this section) and the Davis-Bacon poster (WH-1321) shall be posted at all times by the contractor and its subcontractors at the site of the work in a prominent and accessible place where it can be easily seen by the workers.

- b.(1) The contracting officer shall require that any class of laborers or mechanics, including helpers, which is not listed in the wage determination and which is to be employed under the contract shall be classified in conformance with the wage determination. The contracting officer shall approve an additional classification and wage rate and fringe benefits therefore only when the following criteria have been met:
 - (i) The work to be performed by the classification requested is not performed by a classification in the wage determination; and
 - (ii) The classification is utilized in the area by the construction industry; and
 - (iii) The proposed wage rate, including any bona fide fringe benefits, bears a reasonable relationship to the wage rates contained in the wage determination.
 - (2) If the contractor and the laborers and mechanics to be employed in the classification (if known), or their representatives, and the contracting officer agree on the classification and wage rate (including the amount designated for fringe benefits where appropriate), a report of the action taken shall be sent by the contracting officer to the Administrator of the Wage and Hour Division, Employment Standards Administration, U.S. Department of Labor, Washington, DC 20210. The Administrator, or an authorized representative, will approve, modify, or disapprove every additional classification action within 30 days of receipt and so advise the contracting officer or will notify the contracting officer within the 30-day period that additional time is necessary.
 - (3) In the event the contractor, the laborers or mechanics to be employed in the classification or their representatives, and the contracting officer do not agree on the proposed classification and wage rate (including the amount designated for fringe benefits, where appropriate), the contracting officer shall refer the questions, including the views of all interested parties and the recommendation of the contracting officer, to the Wage and Hour Administrator for determination. The Wage and Hour Administrator, or an authorized representative, will issue a determination within 30 days of receipt and so advise the contracting officer or

will notify the contracting officer within the 30-day period that additional time is necessary.

- (4) The wage rate (including fringe benefits where appropriate) determined pursuant to paragraphs 1.b.(2) or 1.b.(3) of this section, shall be paid to all workers performing work in the classification under this contract from the first day on which work is performed in the classification.
- c. Whenever the minimum wage rate prescribed in the contract for a class of laborers or mechanics includes a fringe benefit which is not expressed as an hourly rate, the contractor shall either pay the benefit as stated in the wage determination or shall pay another bona fide fringe benefit or an hourly cash equivalent thereof.
- d. If the contractor does not make payments to a trustee or other third person, the contractor may consider as part of the wages of any laborer or mechanic the amount of any costs reasonably anticipated in providing bona fide fringe benefits under a plan or program, Provided, That the Secretary of Labor has found, upon the written request of the contractor, that the applicable standards of the Davis-Bacon Act have been met. The Secretary of Labor may require the contractor to set aside in a separate account assets for the meeting of obligations under the plan or program.

2. Withholding

The contracting agency shall upon its own action or upon written request of an authorized representative of the Department of Labor, withhold or cause to be withheld from the contractor under this contract, or any other Federal contract with the same prime contractor, or any other federallyassisted contract subject to Davis-Bacon prevailing wage requirements, which is held by the same prime contractor, so much of the accrued payments or advances as may be considered necessary to pay laborers and mechanics, including apprentices, trainees, and helpers, employed by the contractor or any subcontractor the full amount of wages required by the contract. In the event of failure to pay any laborer or mechanic, including any apprentice, trainee, or helper, employed or working on the site of the work, all or part of the wages required by the contract, the contracting agency may, after written notice to the contractor, take such action as may be necessary to cause the suspension of any further payment, advance, or guarantee of funds until such violations have ceased.

3. Payrolls and basic records

a. Payrolls and basic records relating thereto shall be maintained by the contractor during the course of the work and preserved for a period of three years thereafter for all laborers and mechanics working at the site of the work. Such records shall contain the name, address, and social security number of each such worker, his or her correct classification, hourly rates of wages paid (including rates of contributions or costs anticipated for bona fide fringe benefits or cash equivalents thereof of the types described in section 1(b)(2)(B) of the Davis-Bacon Act), daily and weekly number of hours worked, deductions made and actual wages paid. Whenever the Secretary of Labor has found under 29 CFR 5.5(a)(1)(iv) that the wages of any laborer or mechanic include the amount of any costs reasonably anticipated in providing benefits under a plan or program described in section 1(b)(2)(B) of the Davis-

Bacon Act, the contractor shall maintain records which show that the commitment to provide such benefits is enforceable, that the plan or program is financially responsible, and that the plan or program has been communicated in writing to the laborers or mechanics affected, and records which show the costs anticipated or the actual cost incurred in providing such benefits. Contractors employing apprentices or trainees under approved programs shall maintain written evidence of the registration of apprenticeship programs and certification of trainee programs, the registration of the apprentices and trainees, and the ratios and wage rates prescribed in the applicable programs.

- b.(1) The contractor shall submit weekly for each week in which any contract work is performed a copy of all payrolls to the contracting agency. The payrolls submitted shall set out accurately and completely all of the information required to be maintained under 29 CFR 5.5(a)(3)(i), except that full social security numbers and home addresses shall not be included on weekly transmittals. Instead the payrolls shall only need to include an individually identifying number for each employee (e.g., the last four digits of the employee's social security number). The required weekly payroll information may be submitted in any form desired. Optional Form WH-347 is available for this purpose from the Wage and Hour Division Web site at http://www.dol.gov/esa/whd/forms/wh347instr.htm or its successor site. The prime contractor is responsible for the submission of copies of payrolls by all subcontractors. Contractors and subcontractors shall maintain the full social security number and current address of each covered worker, and shall provide them upon request to the contracting agency for transmission to the State DOT, the FHWA or the Wage and Hour Division of the Department of Labor for purposes of an investigation or audit of compliance with prevailing wage requirements. It is not a violation of this section for a prime contractor to require a subcontractor to provide addresses and social security numbers to the prime contractor for its own records, without weekly submission to the contracting agency...
- (2) Each payroll submitted shall be accompanied by a "Statement of Compliance," signed by the contractor or subcontractor or his or her agent who pays or supervises the payment of the persons employed under the contract and shall certify the following:
 - (i) That the payroll for the payroll period contains the information required to be provided under §5.5 (a)(3)(ii) of Regulations, 29 CFR part 5, the appropriate information is being maintained under §5.5 (a)(3)(i) of Regulations, 29 CFR part 5, and that such information is correct and complete;
 - (ii) That each laborer or mechanic (including each helper, apprentice, and trainee) employed on the contract during the payroll period has been paid the full weekly wages earned, without rebate, either directly or indirectly, and that no deductions have been made either directly or indirectly from the full wages earned, other than permissible deductions as set forth in Regulations, 29 CFR part 3;
 - (iii) That each laborer or mechanic has been paid not less than the applicable wage rates and fringe benefits or cash equivalents for the classification of work performed, as specified in the applicable wage determination incorporated into the contract.

- (3) The weekly submission of a properly executed certification set forth on the reverse side of Optional Form WH–347 shall satisfy the requirement for submission of the "Statement of Compliance" required by paragraph 3.b.(2) of this section.
- (4) The falsification of any of the above certifications may subject the contractor or subcontractor to civil or criminal prosecution under section 1001 of title 18 and section 231 of title 31 of the United States Code.
- c. The contractor or subcontractor shall make the records required under paragraph 3.a. of this section available for inspection, copying, or transcription by authorized representatives of the contracting agency, the State DOT, the FHWA, or the Department of Labor, and shall permit such representatives to interview employees during working hours on the job. If the contractor or subcontractor fails to submit the required records or to make them available, the FHWA may, after written notice to the contractor, the contracting agency or the State DOT, take such action as may be necessary to cause the suspension of any further payment, advance, or guarantee of funds. Furthermore, failure to submit the required records upon request or to make such records available may be grounds for debarment action pursuant to 29 CFR 5.12.

4. Apprentices and trainees

a. Apprentices (programs of the USDOL).

Apprentices will be permitted to work at less than the predetermined rate for the work they performed when they are employed pursuant to and individually registered in a bona fide apprenticeship program registered with the U.S. Department of Labor, Employment and Training Administration, Office of Apprenticeship Training, Employer and Labor Services, or with a State Apprenticeship Agency recognized by the Office, or if a person is employed in his or her first 90 days of probationary employment as an apprentice in such an apprenticeship program, who is not individually registered in the program, but who has been certified by the Office of Apprenticeship Training, Employer and Labor Services or a State Apprenticeship Agency (where appropriate) to be eligible for probationary employment as an apprentice.

The allowable ratio of apprentices to journeymen on the job site in any craft classification shall not be greater than the ratio permitted to the contractor as to the entire work force under the registered program. Any worker listed on a payroll at an apprentice wage rate, who is not registered or otherwise employed as stated above, shall be paid not less than the applicable wage rate on the wage determination for the classification of work actually performed. In addition, any apprentice performing work on the job site in excess of the ratio permitted under the registered program shall be paid not less than the applicable wage rate on the wage determination for the work actually performed. Where a contractor is performing construction on a project in a locality other than that in which its program is registered, the ratios and wage rates (expressed in percentages of the journeyman's hourly rate) specified in the contractor's or subcontractor's registered program shall be observed.

Every apprentice must be paid at not less than the rate specified in the registered program for the apprentice's level of progress, expressed as a percentage of the journeymen hourly rate specified in the applicable wage determination. Apprentices shall be paid fringe benefits in accordance with the provisions of the apprenticeship program. If the apprenticeship program does not specify fringe benefits, apprentices must be paid the full amount of fringe benefits listed on the wage determination for the applicable classification. If the Administrator determines that a different practice prevails for the applicable apprentice classification, fringes shall be paid in accordance with that determination.

In the event the Office of Apprenticeship Training, Employer and Labor Services, or a State Apprenticeship Agency recognized by the Office, withdraws approval of an apprenticeship program, the contractor will no longer be permitted to utilize apprentices at less than the applicable predetermined rate for the work performed until an acceptable program is approved.

b. Trainees (programs of the USDOL).

Except as provided in 29 CFR 5.16, trainees will not be permitted to work at less than the predetermined rate for the work performed unless they are employed pursuant to and individually registered in a program which has received prior approval, evidenced by formal certification by the U.S. Department of Labor, Employment and Training Administration.

The ratio of trainees to journeymen on the job site shall not be greater than permitted under the plan approved by the Employment and Training Administration.

Every trainee must be paid at not less than the rate specified in the approved program for the trainee's level of progress, expressed as a percentage of the journeyman hourly rate specified in the applicable wage determination. Trainees shall be paid fringe benefits in accordance with the provisions of the trainee program. If the trainee program does not mention fringe benefits, trainees shall be paid the full amount of fringe benefits listed on the wage determination unless the Administrator of the Wage and Hour Division determines that there is an apprenticeship program associated with the corresponding journeyman wage rate on the wage determination which provides for less than full fringe benefits for apprentices. Any employee listed on the payroll at a trainee rate who is not registered and participating in a training plan approved by the Employment and Training Administration shall be paid not less than the applicable wage rate on the wage determination for the classification of work actually performed. In addition, any trainee performing work on the job site in excess of the ratio permitted under the registered program shall be paid not less than the applicable wage rate on the wage determination for the work actually performed.

In the event the Employment and Training Administration withdraws approval of a training program, the contractor will no longer be permitted to utilize trainees at less than the applicable predetermined rate for the work performed until an acceptable program is approved.

c. Equal employment opportunity. The utilization of apprentices, trainees and journeymen under this part shall be in conformity with the equal employment opportunity requirements of Executive Order 11246, as amended, and 29 CFR part 30.

d. Apprentices and Trainees (programs of the U.S. DOT).

Apprentices and trainees working under apprenticeship and skill training programs which have been certified by the Secretary of Transportation as promoting EEO in connection with Federal-aid highway construction programs are not subject to the requirements of paragraph 4 of this Section IV. The straight time hourly wage rates for apprentices and trainees under such programs will be established by the particular programs. The ratio of apprentices and trainees to journeymen shall not be greater than permitted by the terms of the particular program.

- **5. Compliance with Copeland Act requirements.** The contractor shall comply with the requirements of 29 CFR part 3, which are incorporated by reference in this contract.
- **6. Subcontracts.** The contractor or subcontractor shall insert Form FHWA-1273 in any subcontracts and also require the subcontractors to include Form FHWA-1273 in any lower tier subcontracts. The prime contractor shall be responsible for the compliance by any subcontractor or lower tier subcontractor with all the contract clauses in 29 CFR 5.5.
- **7. Contract termination: debarment.** A breach of the contract clauses in 29 CFR 5.5 may be grounds for termination of the contract, and for debarment as a contractor and a subcontractor as provided in 29 CFR 5.12.
- **8. Compliance with Davis-Bacon and Related Act requirements.** All rulings and interpretations of the Davis-Bacon and Related Acts contained in 29 CFR parts 1, 3, and 5 are herein incorporated by reference in this contract.
- 9. Disputes concerning labor standards. Disputes arising out of the labor standards provisions of this contract shall not be subject to the general disputes clause of this contract. Such disputes shall be resolved in accordance with the procedures of the Department of Labor set forth in 29 CFR parts 5, 6, and 7. Disputes within the meaning of this clause include disputes between the contractor (or any of its subcontractors) and the contracting agency, the U.S. Department of Labor, or the employees or their representatives.

10. Certification of eligibility.

- a. By entering into this contract, the contractor certifies that neither it (nor he or she) nor any person or firm who has an interest in the contractor's firm is a person or firm ineligible to be awarded Government contracts by virtue of section 3(a) of the Davis-Bacon Act or 29 CFR 5.12(a)(1).
- b. No part of this contract shall be subcontracted to any person or firm ineligible for award of a Government contract by virtue of section 3(a) of the Davis-Bacon Act or 29 CFR 5.12(a)(1).
- c. The penalty for making false statements is prescribed in the U.S. Criminal Code, 18 U.S.C. 1001.

V. CONTRACT WORK HOURS AND SAFETY STANDARDS ACT

The following clauses apply to any Federal-aid construction contract in an amount in excess of \$100,000 and subject to the overtime provisions of the Contract Work Hours and Safety Standards Act. These clauses shall be inserted in addition to the clauses required by 29 CFR 5.5(a) or 29 CFR 4.6. As used in this paragraph, the terms laborers and mechanics include watchmen and guards.

- 1. Overtime requirements. No contractor or subcontractor contracting for any part of the contract work which may require or involve the employment of laborers or mechanics shall require or permit any such laborer or mechanic in any workweek in which he or she is employed on such work to work in excess of forty hours in such workweek unless such laborer or mechanic receives compensation at a rate not less than one and one-half times the basic rate of pay for all hours worked in excess of forty hours in such workweek.
- 2. Violation; liability for unpaid wages; liquidated damages. In the event of any violation of the clause set forth in paragraph (1.) of this section, the contractor and any subcontractor responsible therefor shall be liable for the unpaid wages. In addition, such contractor and subcontractor shall be liable to the United States (in the case of work done under contract for the District of Columbia or a territory, to such District or to such territory), for liquidated damages. Such liquidated damages shall be computed with respect to each individual laborer or mechanic, including watchmen and guards, employed in violation of the clause set forth in paragraph (1.) of this section, in the sum of \$10 for each calendar day on which such individual was required or permitted to work in excess of the standard workweek of forty hours without payment of the overtime wages required by the clause set forth in paragraph (1.) of this section.
- 3. Withholding for unpaid wages and liquidated damages. The FHWA or the contacting agency shall upon its own action or upon written request of an authorized representative of the Department of Labor withhold or cause to be withheld, from any moneys payable on account of work performed by the contractor or subcontractor under any such contract or any other Federal contract with the same prime contractor, or any other federally-assisted contract subject to the Contract Work Hours and Safety Standards Act, which is held by the same prime contractor, such sums as may be determined to be necessary to satisfy any liabilities of such contractor or subcontractor for unpaid wages and liquidated damages as provided in the clause set forth in paragraph (2.) of this section
- **4. Subcontracts.** The contractor or subcontractor shall insert in any subcontracts the clauses set forth in paragraph (1.) through (4.) of this section and also a clause requiring the subcontractors to include these clauses in any lower tier subcontracts. The prime contractor shall be responsible for compliance by any subcontractor or lower tier subcontractor with the clauses set forth in paragraphs (1.) through (4.) of this section.

VI. SUBLETTING OR ASSIGNING THE CONTRACT

This provision is applicable to all Federal-aid construction contracts on the National Highway System.

- 1. The contractor shall perform with its own organization contract work amounting to not less than 30 percent (or a greater percentage if specified elsewhere in the contract) of the total original contract price, excluding any specialty items designated by the contracting agency. Specialty items may be performed by subcontract and the amount of any such specialty items performed may be deducted from the total original contract price before computing the amount of work required to be performed by the contractor's own organization (23 CFR 635.116).
- a. The term "perform work with its own organization" refers to workers employed or leased by the prime contractor, and equipment owned or rented by the prime contractor, with or without operators. Such term does not include employees or equipment of a subcontractor or lower tier subcontractor, agents of the prime contractor, or any other assignees. The term may include payments for the costs of hiring leased employees from an employee leasing firm meeting all relevant Federal and State regulatory requirements. Leased employees may only be included in this term if the prime contractor meets all of the following conditions:
- the prime contractor maintains control over the supervision of the day-to-day activities of the leased employees;
- (2) the prime contractor remains responsible for the quality of the work of the leased employees;
- (3) the prime contractor retains all power to accept or exclude individual employees from work on the project; and
 - (4) the prime contractor remains ultimately responsible for the payment of predetermined minimum wages, the submission of payrolls, statements of compliance and all other Federal regulatory requirements.
- b. "Specialty Items" shall be construed to be limited to work that requires highly specialized knowledge, abilities, or equipment not ordinarily available in the type of contracting organizations qualified and expected to bid or propose on the contract as a whole and in general are to be limited to minor components of the overall contract.
- 2. The contract amount upon which the requirements set forth in paragraph (1) of Section VI is computed includes the cost of material and manufactured products which are to be purchased or produced by the contractor under the contract provisions.
- 3. The contractor shall furnish (a) a competent superintendent or supervisor who is employed by the firm, has full authority to direct performance of the work in accordance with the contract requirements, and is in charge of all construction operations (regardless of who performs the work) and (b) such other of its own organizational resources (supervision, management, and engineering services) as the contracting officer determines is necessary to assure the performance of the contract.
- 4. No portion of the contract shall be sublet, assigned or otherwise disposed of except with the written consent of the contracting officer, or authorized representative, and such consent when given shall not be construed to relieve the contractor of any responsibility for the fulfillment of the contract. Written consent will be given only after the contracting agency has assured that each subcontract is

evidenced in writing and that it contains all pertinent provisions and requirements of the prime contract.

5. The 30% self-performance requirement of paragraph (1) is not applicable to design-build contracts; however, contracting agencies may establish their own self-performance requirements.

VII. SAFETY: ACCIDENT PREVENTION

- This provision is applicable to all Federal-aid construction contracts and to all related subcontracts.
- 1. In the performance of this contract the contractor shall comply with all applicable Federal, State, and local laws governing safety, health, and sanitation (23 CFR 635). The contractor shall provide all safeguards, safety devices and protective equipment and take any other needed actions as it determines, or as the contracting officer may determine, to be reasonably necessary to protect the life and health of employees on the job and the safety of the public and to protect property in connection with the performance of the work covered by the contract.
- 2. It is a condition of this contract, and shall be made a condition of each subcontract, which the contractor enters into pursuant to this contract, that the contractor and any subcontractor shall not permit any employee, in performance of the contract, to work in surroundings or under conditions which are unsanitary, hazardous or dangerous to his/her health or safety, as determined under construction safety and health standards (29 CFR 1926) promulgated by the Secretary of Labor, in accordance with Section 107 of the Contract Work Hours and Safety Standards Act (40 U.S.C. 3704).
- 3. Pursuant to 29 CFR 1926.3, it is a condition of this contract that the Secretary of Labor or authorized representative thereof, shall have right of entry to any site of contract performance to inspect or investigate the matter of compliance with the construction safety and health standards and to carry out the duties of the Secretary under Section 107 of the Contract Work Hours and Safety Standards Act (40 U.S.C.3704).

VIII. FALSE STATEMENTS CONCERNING HIGHWAY PROJECTS

This provision is applicable to all Federal-aid construction contracts and to all related subcontracts.

In order to assure high quality and durable construction in conformity with approved plans and specifications and a high degree of reliability on statements and representations made by engineers, contractors, suppliers, and workers on Federal-aid highway projects, it is essential that all persons concerned with the project perform their functions as carefully, thoroughly, and honestly as possible. Willful falsification, distortion, or misrepresentation with respect to any facts related to the project is a violation of Federal law. To prevent any misunderstanding regarding the seriousness of these and similar acts, Form FHWA-1022 shall be posted on each Federal-aid highway project (23 CFR 635) in one or more places where it is readily available to all persons concerned with the project:

18 U.S.C. 1020 reads as follows:

"Whoever, being an officer, agent, or employee of the United States, or of any State or Territory, or whoever, whether a person, association, firm, or corporation, knowingly makes any false statement, false representation, or false report as to the character, quality, quantity, or cost of the material used or to be used, or the quantity or quality of the work performed or to be performed, or the cost thereof in connection with the submission of plans, maps, specifications, contracts, or costs of construction on any highway or related project submitted for approval to the Secretary of Transportation; or

Whoever knowingly makes any false statement, false representation, false report or false claim with respect to the character, quality, quantity, or cost of any work performed or to be performed, or materials furnished or to be furnished, in connection with the construction of any highway or related project approved by the Secretary of Transportation; or

Whoever knowingly makes any false statement or false representation as to material fact in any statement, certificate, or report submitted pursuant to provisions of the Federal-aid Roads Act approved July 1, 1916, (39 Stat. 355), as amended and supplemented;

Shall be fined under this title or imprisoned not more than 5 years or both."

IX. IMPLEMENTATION OF CLEAN AIR ACT AND FEDERAL WATER POLLUTION CONTROL ACT

This provision is applicable to all Federal-aid construction contracts and to all related subcontracts.

By submission of this bid/proposal or the execution of this contract, or subcontract, as appropriate, the bidder, proposer, Federal-aid construction contractor, or subcontractor, as appropriate, will be deemed to have stipulated as follows:

- 1. That any person who is or will be utilized in the performance of this contract is not prohibited from receiving an award due to a violation of Section 508 of the Clean Water Act or Section 306 of the Clean Air Act.
- 2. That the contractor agrees to include or cause to be included the requirements of paragraph (1) of this Section X in every subcontract, and further agrees to take such action as the contracting agency may direct as a means of enforcing such requirements.

X. CERTIFICATION REGARDING DEBARMENT, SUSPENSION, INELIGIBILITY AND VOLUNTARY EXCLUSION

This provision is applicable to all Federal-aid construction contracts, design-build contracts, subcontracts, lower-tier subcontracts, purchase orders, lease agreements, consultant contracts or any other covered transaction requiring FHWA approval or that is estimated to cost \$25,000 or more – as defined in 2 CFR Parts 180 and 1200.

1. Instructions for Certification – First Tier Participants:

- a. By signing and submitting this proposal, the prospective first tier participant is providing the certification set out below.
- b. The inability of a person to provide the certification set out below will not necessarily result in denial of participation in this

covered transaction. The prospective first tier participant shall submit an explanation of why it cannot provide the certification set out below. The certification or explanation will be considered in connection with the department or agency's determination whether to enter into this transaction. However, failure of the prospective first tier participant to furnish a certification or an explanation shall disqualify such a person from participation in this transaction.

- c. The certification in this clause is a material representation of fact upon which reliance was placed when the contracting agency determined to enter into this transaction. If it is later determined that the prospective participant knowingly rendered an erroneous certification, in addition to other remedies available to the Federal Government, the contracting agency may terminate this transaction for cause of default.
- d. The prospective first tier participant shall provide immediate written notice to the contracting agency to whom this proposal is submitted if any time the prospective first tier participant learns that its certification was erroneous when submitted or has become erroneous by reason of changed circumstances.
- e. The terms "covered transaction," "debarred," "suspended," "ineligible," "participant," "person," "principal," and "voluntarily excluded," as used in this clause, are defined in 2 CFR Parts 180 and 1200. "First Tier Covered Transactions" refers to any covered transaction between a grantee or subgrantee of Federal funds and a participant (such as the prime or general contract). "Lower Tier Covered Transactions" refers to any covered transaction under a First Tier Covered Transaction (such as subcontracts). "First Tier Participant" refers to the participant who has entered into a covered transaction with a grantee or subgrantee of Federal funds (such as the prime or general contractor). "Lower Tier Participant" refers any participant who has entered into a covered transaction with a First Tier Participant or other Lower Tier Participants (such as subcontractors and suppliers).
- f. The prospective first tier participant agrees by submitting this proposal that, should the proposed covered transaction be entered into, it shall not knowingly enter into any lower tier covered transaction with a person who is debarred, suspended, declared ineligible, or voluntarily excluded from participation in this covered transaction, unless authorized by the department or agency entering into this transaction.
- g. The prospective first tier participant further agrees by submitting this proposal that it will include the clause titled "Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion-Lower Tier Covered Transactions," provided by the department or contracting agency, entering into this covered transaction, without modification, in all lower tier covered transactions and in all solicitations for lower tier covered transactions exceeding the \$25,000 threshold.
- h. A participant in a covered transaction may rely upon a certification of a prospective participant in a lower tier covered transaction that is not debarred, suspended, ineligible, or voluntarily excluded from the covered transaction, unless it knows that the certification is erroneous. A participant is responsible for ensuring that its principals are not suspended, debarred, or otherwise ineligible to participate in covered transactions. To verify the eligibility of its principals, as well as the eligibility of any lower tier prospective participants, each participant may, but is not required to, check the Excluded Parties List System website (https://www.epls.gov/), which is compiled by the General Services Administration.

- i. Nothing contained in the foregoing shall be construed to require the establishment of a system of records in order to render in good faith the certification required by this clause. The knowledge and information of the prospective participant is not required to exceed that which is normally possessed by a prudent person in the ordinary course of business dealings.
- j. Except for transactions authorized under paragraph (f) of these instructions, if a participant in a covered transaction knowingly enters into a lower tier covered transaction with a person who is suspended, debarred, ineligible, or voluntarily excluded from participation in this transaction, in addition to other remedies available to the Federal Government, the department or agency may terminate this transaction for cause or default.

* * * * *

2. Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion – First Tier Participants:

- a. The prospective first tier participant certifies to the best of its knowledge and belief, that it and its principals:
- (1) Are not presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from participating in covered transactions by any Federal department or agency;
- (2) Have not within a three-year period preceding this proposal been convicted of or had a civil judgment rendered against them for commission of fraud or a criminal offense in connection with obtaining, attempting to obtain, or performing a public (Federal, State or local) transaction or contract under a public transaction; violation of Federal or State antitrust statutes or commission of embezzlement, theft, forgery, bribery, falsification or destruction of records, making false statements, or receiving stolen property;
- (3) Are not presently indicted for or otherwise criminally or civilly charged by a governmental entity (Federal, State or local) with commission of any of the offenses enumerated in paragraph (a)(2) of this certification; and
- (4) Have not within a three-year period preceding this application/proposal had one or more public transactions (Federal, State or local) terminated for cause or default.
- b. Where the prospective participant is unable to certify to any of the statements in this certification, such prospective participant shall attach an explanation to this proposal.

2. Instructions for Certification - Lower Tier Participants:

(Applicable to all subcontracts, purchase orders and other lower tier transactions requiring prior FHWA approval or estimated to cost \$25,000 or more - 2 CFR Parts 180 and 1200)

- a. By signing and submitting this proposal, the prospective lower tier is providing the certification set out below.
- b. The certification in this clause is a material representation of fact upon which reliance was placed when this transaction was entered into. If it is later determined that the prospective lower tier participant knowingly rendered an erroneous certification, in addition to other remedies available to the Federal Government, the department, or agency with which

this transaction originated may pursue available remedies, including suspension and/or debarment.

- c. The prospective lower tier participant shall provide immediate written notice to the person to which this proposal is submitted if at any time the prospective lower tier participant learns that its certification was erroneous by reason of changed circumstances.
- d. The terms "covered transaction," "debarred,"
 "suspended," "ineligible," "participant," "person," "principal,"
 and "voluntarily excluded," as used in this clause, are defined
 in 2 CFR Parts 180 and 1200. You may contact the person to
 which this proposal is submitted for assistance in obtaining a
 copy of those regulations. "First Tier Covered Transactions"
 refers to any covered transaction between a grantee or
 subgrantee of Federal funds and a participant (such as the
 prime or general contract). "Lower Tier Covered Transactions"
 refers to any covered transaction under a First Tier Covered
 Transaction (such as subcontracts). "First Tier Participant"
 refers to the participant who has entered into a covered
 transaction with a grantee or subgrantee of Federal funds
 (such as the prime or general contractor). "Lower Tier
 Participant" refers any participant who has entered into a
 covered transaction with a First Tier Participant or other Lower
 Tier Participants (such as subcontractors and suppliers).
- e. The prospective lower tier participant agrees by submitting this proposal that, should the proposed covered transaction be entered into, it shall not knowingly enter into any lower tier covered transaction with a person who is debarred, suspended, declared ineligible, or voluntarily excluded from participation in this covered transaction, unless authorized by the department or agency with which this transaction originated.
- f. The prospective lower tier participant further agrees by submitting this proposal that it will include this clause titled "Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion-Lower Tier Covered Transaction," without modification, in all lower tier covered transactions and in all solicitations for lower tier covered transactions exceeding the \$25,000 threshold.
- g. A participant in a covered transaction may rely upon a certification of a prospective participant in a lower tier covered transaction that is not debarred, suspended, ineligible, or voluntarily excluded from the covered transaction, unless it knows that the certification is erroneous. A participant is responsible for ensuring that its principals are not suspended, debarred, or otherwise ineligible to participate in covered transactions. To verify the eligibility of its principals, as well as the eligibility of any lower tier prospective participants, each participant may, but is not required to, check the Excluded Parties List System website (https://www.epls.gov/), which is compiled by the General Services Administration.
- h. Nothing contained in the foregoing shall be construed to require establishment of a system of records in order to render in good faith the certification required by this clause. The knowledge and information of participant is not required to exceed that which is normally possessed by a prudent person in the ordinary course of business dealings.
- i. Except for transactions authorized under paragraph e of these instructions, if a participant in a covered transaction knowingly enters into a lower tier covered transaction with a person who is suspended, debarred, ineligible, or voluntarily excluded from participation in this transaction, in addition to other remedies available to the Federal Government, the

department or agency with which this transaction originated may pursue available remedies, including suspension and/or debarment.

* * * * *

Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion--Lower Tier Participants:

- 1. The prospective lower tier participant certifies, by submission of this proposal, that neither it nor its principals is presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from participating in covered transactions by any Federal department or agency.
- 2. Where the prospective lower tier participant is unable to certify to any of the statements in this certification, such prospective participant shall attach an explanation to this proposal.

* * * * :

XI. CERTIFICATION REGARDING USE OF CONTRACT FUNDS FOR LOBBYING

This provision is applicable to all Federal-aid construction contracts and to all related subcontracts which exceed \$100,000 (49 CFR 20).

- 1. The prospective participant certifies, by signing and submitting this bid or proposal, to the best of his or her knowledge and belief. that:
- a. No Federal appropriated funds have been paid or will be paid, by or on behalf of the undersigned, to any person for influencing or attempting to influence an officer or employee of any Federal agency, a Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress in connection with the awarding of any Federal contract, the making of any Federal grant, the making of any Federal loan, the entering into of any cooperative agreement, and the extension, continuation, renewal, amendment, or modification of any Federal contract, grant, loan, or cooperative agreement.
- b. If any funds other than Federal appropriated funds have been paid or will be paid to any person for influencing or attempting to influence an officer or employee of any Federal agency, a Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress in connection with this Federal contract, grant, loan, or cooperative agreement, the undersigned shall complete and submit Standard Form-LLL, "Disclosure Form to Report Lobbying," in accordance with its instructions.
- 2. This certification is a material representation of fact upon which reliance was placed when this transaction was made or entered into. Submission of this certification is a prerequisite for making or entering into this transaction imposed by 31 U.S.C. 1352. Any person who fails to file the required certification shall be subject to a civil penalty of not less than \$10,000 and not more than \$100,000 for each such failure.
- 3. The prospective participant also agrees by submitting its bid or proposal that the participant shall require that the language of this certification be included in all lower tier subcontracts, which exceed \$100,000 and that all such recipients shall certify and disclose accordingly.

ATTACHMENT A - EMPLOYMENT AND MATERIALS PREFERENCE FOR APPALACHIAN DEVELOPMENT HIGHWAY SYSTEM OR APPALACHIAN LOCAL ACCESS ROAD CONTRACTS

This provision is applicable to all Federal-aid projects funded under the Appalachian Regional Development Act of 1965.

- 1. During the performance of this contract, the contractor undertaking to do work which is, or reasonably may be, done as on-site work, shall give preference to qualified persons who regularly reside in the labor area as designated by the DOL wherein the contract work is situated, or the subregion, or the Appalachian counties of the State wherein the contract work is situated, except:
- a. To the extent that qualified persons regularly residing in the area are not available.
- b. For the reasonable needs of the contractor to employ supervisory or specially experienced personnel necessary to assure an efficient execution of the contract work.
- c. For the obligation of the contractor to offer employment to present or former employees as the result of a lawful collective bargaining contract, provided that the number of nonresident persons employed under this subparagraph (1c) shall not exceed 20 percent of the total number of employees employed by the contractor on the contract work, except as provided in subparagraph (4) below.
- 2. The contractor shall place a job order with the State Employment Service indicating (a) the classifications of the laborers, mechanics and other employees required to perform the contract work, (b) the number of employees required in each classification, (c) the date on which the participant estimates such employees will be required, and (d) any other pertinent information required by the State Employment Service to complete the job order form. The job order may be placed with the State Employment Service in writing or by telephone. If during the course of the contract work, the information submitted by the contractor in the original job order is substantially modified, the participant shall promptly notify the State Employment Service.
- 3. The contractor shall give full consideration to all qualified job applicants referred to him by the State Employment Service. The contractor is not required to grant employment to any job applicants who, in his opinion, are not qualified to perform the classification of work required.
- 4. If, within one week following the placing of a job order by the contractor with the State Employment Service, the State Employment Service is unable to refer any qualified job applicants to the contractor, or less than the number requested, the State Employment Service will forward a certificate to the contractor indicating the unavailability of applicants. Such certificate shall be made a part of the contractor's permanent project records. Upon receipt of this certificate, the contractor may employ persons who do not normally reside in the labor area to fill positions covered by the certificate, notwithstanding the provisions of subparagraph (1c) above.
- 5. The provisions of 23 CFR 633.207(e) allow the contracting agency to provide a contractual preference for the use of mineral resource materials native to the Appalachian region.

6. The contractor shall include the provisions of Sections 1 through 4 of this Attachment A in every subcontract for work which is, or reasonably may be, done as on-site work.

Non-discrimination Provisions

During the performance of this contract, the contractor, for itself, its assignees, and successors in interest (hereinafter referred to as the "contractor") agrees as follows:

- **1. Compliance with Regulations:** The contractor (hereinafter includes consultants) will comply with the Acts and the Regulations relative to Non-discrimination in Federally-assisted programs of the U.S. Department of Transportation, Federal Highway Administration, as they may be amended from time to time, which are herein incorporated by reference and made a part of this contract.
- **2. Non-discrimination:** The contractor, with regard to the work performed by it during the contract, will not discriminate on the grounds of race, color, or national origin in the selection and retention of subcontractors, including procurements of materials and leases of equipment. The contractor will not participate directly or indirectly in the discrimination prohibited by the Acts and the Regulations, including employment practices when the contract covers any activity, project, or program set forth in Appendix B of 49 CFR Part 21.
- **3. Solicitations for Subcontracts, Including Procurements of Materials and Equipment:** In all solicitations, either by competitive bidding, or negotiation made by the contractor for work to be performed under a subcontract, including procurements of materials, or leases of equipment, each potential subcontractor or supplier will be notified by the contractor of the contractor's obligations under this contract and the Acts and the Regulations relative to Non-discrimination on the grounds of race, color, or national origin.
- **4. Information and Reports:** The contractor will provide all information and reports required by the Acts, the Regulations, and directives issued pursuant thereto and will permit access to its books, records, accounts, other sources of information, and its facilities as may be determined by the Recipient or the Federal Highway Administration to be pertinent to ascertain compliance with such Acts, Regulations, and instructions. Where any information required of a contractor is in the exclusive possession of another who fails or refuses to furnish the information, the contractor will so certify to the Recipient or the Federal Highway Administration, as appropriate, and will set forth what efforts it has made to obtain the information.
- **5. Sanctions for Noncompliance:** In the event of a contractor's noncompliance with the Non-discrimination provisions of this contract, the Recipient will impose such contract sanctions as it or the Federal Highway Administration may determine to be appropriate, including, but not limited to:
 - a. Withholding payments to the contractor under the contract until the contractor complies; and/or
 - b. Cancelling, terminating, or suspending a contract, in whole or in part.

6. Incorporation of Provisions: The contractor will include the provisions of paragraphs one through six in every subcontract, including procurements of materials and leases of equipment, unless exempt by the Acts, the Regulations and directives issued pursuant thereto. The contractor will take action with respect to any subcontract or procurement as the Recipient or the Federal Highway Administration may direct as a means of enforcing such provisions including sanctions for noncompliance. Provided, that if the contractor becomes involved in, or is threatened with litigation by a subcontractor, or supplier because of such direction, the contractor may request the Recipient to enter into any litigation to protect the interests of the Recipient. In addition, the contractor may request the United States to enter into the litigation to protect the interests of the United States.

During the performance of this contract, the contractor, for itself, its assignees, and successors in interest (hereinafter referred to as the "contractor") agrees to comply with the following non-discrimination statutes and authorities; including but not limited to:

Pertinent Non-Discrimination Authorities:

- Title VI of the Civil Rights Act of 1964 (42 U.S.C. § 2000d et seq., 78 stat. 252), (prohibits discrimination on the basis of race, color, national origin); and 49 CFR Part 21.
- The Uniform Relocation Assistance and Real Property Acquisition Policies Act of 1970, (42 U.S.C. § 4601), (prohibits unfair treatment of persons displaced or whose property has been acquired because of Federal or Federal-aid programs and projects);
- Federal-Aid Highway Act of 1973, (23 U.S.C. § 324 et seq.), (prohibits discrimination on the basis of sex);
- Section 504 of the Rehabilitation Act of 1973, (29 U.S.C. § 794 et seq.), as amended, (prohibits discrimination on the basis of disability); and 49 CFR Part 27;
- The Age Discrimination Act of 1975, as amended, (42 U.S.C. § 6101 et seq.), (prohibits discrimination on the basis of age);
- Airport and Airway Improvement Act of 1982, (49 USC § 471, Section 47123), as amended, (prohibits discrimination based on race, creed, color, national origin, or sex);
- The Civil Rights Restoration Act of 1987, (PL 100-209), (Broadened the scope, coverage and applicability of Title VI of the Civil Rights Act of 1964, The Age Discrimination Act of 1975 and Section 504 of the Rehabilitation Act of 1973, by expanding the definition of the terms "programs or activities" to include all of the programs or activities of the Federal-aid recipients, sub-recipients and contractors, whether such programs or activities are Federally funded or not);
- Titles II and III of the Americans with Disabilities Act, which prohibit discrimination on the basis of disability in the operation of public entities, public and private transportation systems, places of public accommodation, and certain testing entities (42 U.S.C. §§ 12131-12189) as implemented by Department of Transportation regulations at 49 C.F.R. parts 37 and 38;
- The Federal Aviation Administration's Non-discrimination statute (49 U.S.C. § 47123) (prohibits discrimination on the basis of race, color, national origin, and sex);

- Executive Order 12898, Federal Actions to Address Environmental Justice in Minority Populations and Low-Income Populations, which ensures Non-discrimination against minority populations by discouraging programs, policies, and activities with disproportionately high and adverse human health or environmental effects on minority and low-income populations;
- Executive Order 13166, Improving Access to Services for Persons with Limited English Proficiency, and resulting agency guidance, national origin discrimination includes discrimination because of Limited English proficiency (LEP). To ensure compliance with Title VI, you must take reasonable steps to ensure that LEP persons have meaningful access to your programs (70 Fed. Reg. at 74087 to 74100);
- Title IX of the Education Amendments of 1972, as amended, which prohibits you from discriminating because of sex in education programs or activities (20 U.S.C. 1681 et seq).

SEPTEMBER 2002

NOTICE OF REQUIREMENT FOR AFFIRMATIVE ACTION TO ENSURE EQUAL EMPLOYMENT OPPORTUNITY (EXECUTIVE ORDER 11246)

- 1. The Offeror's or Bidder's attention is called to the "Employment Practices" and "Equal Opportunity Clause" set forth in the Required Contract Provisions, FHWA 1273.
- 2. The goals and timetables for minority and female participation expressed in percentage terms for the contractor's aggregate work force in each trade, on all construction work in the covered area, are as follows:

Goals for Minority Participation for Each Trade:

County	<u>%</u>	_County_	_%_	_County_	<u>%</u>
Adams	1.7	Iowa	1.7	Polk	2.2
Ashland	1.2	Iron	1.2	Portage	0.6
Barron	0.6	Jackson	0.6	Price	0.6
Bayfield	1.2	Jefferson	7.0	Racine	8.4
Brown	1.3	Juneau	0.6	Richland	1.7
Buffalo	0.6	Kenosha	3.0	Rock	3.1
Burnett	2.2	Kewaunee	1.0	Rusk	0.6
Calumet	0.9	La Crosse	0.9	St. Croix	2.9
Chippewa	0.5	Lafayette	0.5	Sauk	1.7
Clark	0.6	Langlade	0.6	Sawyer	0.6
Columbia	1.7	Lincoln	0.6	Shawano	1.0
Crawford	0.5	Manitowoc	1.0	Sheboygan	7.0
Dane	2.2	Marathon	0.6	Taylor	0.6
Dodge	7.0	Marinette	1.0	Trempealeau	0.6
Door	1.0	Marquette	1.7	Vernon	0.6
Douglas	1.0	Menominee	1.0	Vilas	0.6
Dunn	0.6	Milwaukee	8.0	Walworth	7.0
Eau Claire	0.5	Monroe	0.6	Washburn	0.6
Florence	1.0	Oconto	1.0	Washington	8.0
Fond du Lac	1.0	Oneida	0.6	Waukesha	8.0
Forest	1.0	Outagamie	0.9	Waupaca	1.0
Grant	0.5	Ozaukee	8.0	Waushara	1.0
Green	1.7	Pepin	0.6	Winnebago	0.9
Green Lake	1.0	Pierce	2.2	Wood	0.6

Goals for female participation for each trade: 6.9%

These goals are applicable to all the contractor's construction work, (whether or not it is federal or federally assisted), performed in the covered area. If the contractor performs construction work in the geographical area located outside of the covered area, it shall apply the goals established for such geographical area where the work is actually performed. With regard to this second area, the contractor also is subject to the goals for both its federally involved and nonfederally involved construction.

The contractor's compliance with the Executive Order and the Regulations in 41 CFR Part 60-4 shall be based on its implementation of the Equal Opportunity Clause, specific affirmative action obligations required by the specifications set forth in 41 CFR 60-4.3(a), and its efforts to meet the goals. The hours of minority and female employment and training must be substantially uniform throughout the length of the contract, and in each trade, and the contractor shall make a good faith effort to employ minorities and women evenly on each of its projects. The transfer of minority or female employees or trainees from contractor to contractor or from project to project for the sole purpose of meeting the contractor's goals shall be a violation of the contract, the Executive Order and the Regulations in 41 CFR Part 60-4. Compliance with the goals will be measured against the total work hours performed.

3. The contractor shall provide written notification to the Director of the Office of Federal Contract Compliance Programs within ten (10) working days of award of any construction subcontract in excess of \$10,000.00 at any tier for construction work under the contract resulting from this solicitation. The notification shall list the name, address and telephone number of the subcontractor, employer identification number of the subcontractor; estimated dollar amount of the subcontract; estimated starting and completion dates of the subcontract; and the geographical area in which the subcontract is to be performed.

As referred to in this section, the Director means:

Director Office of Federal Contract Compliance Programs Ruess Federal Plaza 310 W. Wisconsin Ave., Suite 1115 Milwaukee, WI 53202

The "Employer Identification Number" means the Federal Social Security number used on the Employer's Quarterly Federal Tax Return, U.S. Treasury Department Form 941.

4. As used in this notice, and in the contract resulting from solicitation, the "covered area" is the county(ies) in Wisconsin to which this proposal applies.

APRIL 2013

ADDITIONAL FEDERAL-AID PROVISIONS

NOTICE TO ALL BIDDERS

To report bid rigging activities call:

1-800-424-9071

The U.S. Department of Transportation (DOT) operates the above toll-free "hotline" Monday through Friday, 8:00 a.m. to 5:00 p.m., Eastern Time. Anyone with knowledge of possible bid rigging, bidding collusion, or other fraudulent activities should use the "hotline" to report such activities.

The "hotline" is part of the DOT's continuing effort to identify and investigate highway construction contract fraud and abuse and is operated under the direction of the DOT Inspector General. All information will be treated confidentially and caller anonymity will be respected.

Effective August 2015 letting

BUY AMERICA PROVISION

All steel and iron materials permanently incorporated in this project shall be domestic products and all manufacturing and coating processes for these materials from smelting forward in the manufacturing process must have occurred within the United States. Coating includes epoxy coating, galvanizing, painting and any other coating that protects or enhances the value of a material subject to the requirements of Buy America. The exemption of this requirement is the minimal use of foreign materials if the total cost of such material permanently incorporated in the product does not exceed one-tenth of one percent (1/10 of 1%) of the total contract cost or \$2,500.00, whichever is greater. For purposes of this paragraph, the cost is that shown to be the value of the subject products as they are delivered to the project. The contractor shall take actions and provide documentation conforming to CMM 2-28.5 to ensure compliance with this "Buy America" provision.

https://wisconsindot.gov/rdwy/cmm/cm-02-28.pdf

Upon completion of the project certify to the engineer, in writing using department form WS4567, that all steel, iron, and coating processes for steel or iron incorporated into the contract work conform to these "Buy America" provisions. Attach a list of exemptions and their associated costs to the certification form. Department form WS4567 is available at:

https://wisconsindot.gov/hcciDocs/contracting-info/ws4567.doc

1 of 1

Cargo Preference Act Requirement

All Federal-aid projects shall comply with 46 CFR 381.7 (a) – (b) as follows:

- (a) Agreement Clauses. "Use of United States-flag vessels:"
- (1) Pursuant to Pub. L. 664 (43 U.S.C. 1241(b)) at least 50 percent of any equipment, materials or commodities procured, contracted for or otherwise obtained with funds granted, guaranteed, loaned, or advanced by the U.S. Government under this agreement, and which may be transported by ocean vessel, shall be transported on privately owned United States-flag commercial vessels, if available.
- (2) Within 20 days following the date of loading for shipments originating within the United States or within 30 working days following the date of loading for shipments originating outside the United States, a legible copy of a rated, 'on-board' commercial ocean bill-of-lading in English for each shipment of cargo described in paragraph (a)(1) of this section shall be furnished to both the Contracting Officer (through the prime contractor in the case of subcontractor bills-of-lading) and to the Division of National Cargo, Office of Market Development, Maritime Administration, Washington, DC 20590."
- (b) Contractor and Subcontractor Clauses. "Use of United States-flag vessels: The contractor agrees—"
- (1) To utilize privately owned United States-flag commercial vessels to ship at least 50 percent of the gross tonnage (computed separately for dry bulk carriers, dry cargo liners, and tankers) involved, whenever shipping any equipment, material, or commodities pursuant to this contract, to the extent such vessels are available at fair and reasonable rates for United States-flag commercial vessels.
- (2) To furnish within 20 days following the date of loading for shipments originating within the United States or within 30 working days following the date of loading for shipments originating outside the United States, a legible copy of a rated, 'on-board' commercial ocean bill-of-lading in English for each shipment of cargo described in paragraph (b) (1) of this section to both the Contracting Officer (through the prime contractor in the case of subcontractor bills-of-lading) and to the Division of National Cargo, Office of Market Development, Maritime Administration, Washington, DC 20590.
- (3) To insert the substance of the provisions of this clause in all subcontracts issued pursuant to this contract.

WISCONSIN DEPARTMENT OF TRANSPORTATION DIVISION OF TRANSPORTATION AND SYSTEM DEVELOPMENT

SUPPLEMENTAL REQUIRED CONTRACT PROVISIONS FOR PROJECTS WITH FEDERAL AID

I. PREVAILING WAGE RATES

The attached U.S. Department of Labor (Davis-Bacon Minimum Wage Rates) furnishes the minimum prevailing wage rates pursuant to the Davis-Bacon and Related Acts. The wage rates shown are the minimum rates required by the contract to be paid during its life, however this is not a representation that labor can be obtained at these rates. It is the responsibility of bidders to inform themselves as to the local labor conditions and prospective changes or adjustments of wage rates. No increase in the contract price will be allowed or authorized on account of the payment of wage rates in excess of those listed herein.

II. COVERAGE OF TRUCK DRIVERS

Truck drivers are covered by Davis-Bacon Minimum Wage Rates in the following circumstances:

- Drivers of a contractor or subcontractor for time spent working on the site of the work.
- Drivers of a contractor or subcontractor for time spent loading and/or unloading materials and supplies on the site of the work, if such time is not de minimis. https://www.dol.gov/whd/FOH/FOH Ch15.pdf
- Truck drivers transporting materials or supplies between a facility that is deemed part of the site of the work and the actual construction site.
- Truck drivers transporting portions of the building or work between a site
 established specifically for the performance of the contract where a
 significant portion of such building or work is constructed and the physical
 place where the building or work called for in the contract will remain.

Truck drivers are not covered by Davis-Bacon Minimum Wage Rates in the following circumstances:

- Material delivery truck drivers while off the site of the work.
- Drivers of a contractor or subcontractor traveling between a Davis-Bacon job and a commercial supply facility while they are off the site of the work."
- Truck drivers whose time spent on the site of the work is de minimis, such as only a few minutes at a time merely to pick up or drop off materials or supplies.

Details are available online at:

https://www.dol.gov/whd/recovery/pwrb/Tab9.pdf https://wisconsindot.gov/Pages/doing-bus/civil-rights/labornwage/trckng.aspx

III. POSTINGS AT THE SITE OF THE WORK

In addition to the required postings furnished by the department, the contractor shall post the following in at least one conspicuous and accessible place at the site of work:

a. A copy of the contractor's Equal Employment Opportunity Policy.

All required documents shall be posted by the first day of work and be accurate and complete. Postings must be readable, in an area where they will be noticed, and maintained until the last day of work.

IV. RESOURCES

Required information regarding compliance with federal provisions is found in the following resources:

- · FHWA-1273 included in this contract
- U.S. Department of Labor Prevailing Wage Resource Book
- · U.S. Department of Labor Field Operations Handbook
- U.S. Code of Federal Regulations
- Any applicable law, Act, or Executive Order enacted by the federal government at the time of the letting of this contract

"General Decision Number: WI20200010 03/06/2020

Superseded General Decision Number: WI20190010

State: Wisconsin

Construction Type: Highway

Counties: Wisconsin Statewide.

HIGHWAY, AIRPORT RUNWAY & TAXIWAY CONSTRUCTION PROJECTS (does not include bridges over navigable waters; tunnels; buildings in highway rest areas; and railroad construction)

Note: Under Executive Order (EO) 13658, an hourly minimum wage of \$10.80 for calendar year 2020 applies to all contracts subject to the Davis-Bacon Act for which the contract is awarded (and any solicitation was issued) on or after January 1, 2015. If this contract is covered by the EO, the contractor must pay all workers in any classification listed on this wage determination at least \$10.80 per hour (or the applicable wage rate listed on this wage determination, if it is higher) for all hours spent performing on the contract in calendar year 2020. If this contract is covered by the EO and a classification considered necessary for performance of work on the contract does not appear on this wage determination, the contractor must pay workers in that classification at least the wage rate determined through the conformance process set forth in 29 CFR 5.5(a)(1)(ii) (or the EO minimum wage rate, if it is higher than the conformed wage rate). The EO minimum wage rate will be adjusted annually. Please note that this EO applies to the above-mentioned types of contracts entered into by the federal government that are subject to the Davis-Bacon Act itself, but it does not apply to contracts subject only to the Davis-Bacon Related Acts, including those set forth at 29 CFR 5.1(a)(2)-(60). Additional information on contractor requirements and worker protections under the EO is available at www.dol.gov/whd/govcontracts.

Modification Number	Publication Date
0	01/03/2020
1	01/24/2020
2	02/28/2020
3	03/06/2020

BRWI0001-002 06/03/2019

CRAWFORD, JACKSON, JUNEAU, LA CROSSE, MONROE, TREMPEALEAU, AND VERNON COUNTIES

	Rates	Fringes
BRICKLAYER	.\$ 33.80	24.28
BRWI0002-002 06/01/2019		

	Rates	Fringes		
BRICKLAYER	\$ 39.94	23.30		
BRWI0002-005 06/01/2019				
ADAMS, ASHLAND, BARRON, BROWN, BURNETT, CALUMET, CHIPPEWA, CLARK, COLUMBIA, DODGE, DOOR, DUNN, FLORENCE, FOND DU LAC, FOREST, GREEN LAKE, IRON, JEFFERSON, KEWAUNEE, LANGLADE, LINCOLN, MANITOWOC, MARATHON, MARINETTE, MARQUETTE, MENOMINEE, OCONTO, ONEIDA, OUTAGAMIE, POLK, PORTAGE, RUSK, ST CROIX, SAUK, SHAWANO, SHEBOYGAN, TAYLOR, VILAS, WALWORTH, WAUPACA, WAUSHARA, WINNEBAGO, AND WOOD COUNTIES				
	Rates	Fringes		
CEMENT MASON/CONCRETE FINISHER	\$ 35.51	23.37		
BRWI0003-002 06/03/2019				
BROWN, DOOR, FLORENCE, KEWAUNEE,	MARINETTE, AND (OCONTO COUNTIES		
	Rates	Fringes		
BRICKLAYER	•	23.90		
BRWI0004-002 06/01/2019				
KENOSHA, RACINE, AND WALWORTH COU	NTIES			
	Rates	Fringes		
BRICKLAYER	\$ 38.43	25.10		
BRWI0006-002 06/01/2019				
ADAMS, CLARK, FOREST, LANGLADE, L ONEIDA, PORTAGE, PRICE, TAYLOR, V				
	Rates	Fringes		
BRICKLAYER		23.02		
BRWI0007-002 06/03/2019				
GREEN, LAFAYETTE, AND ROCK COUNTI	ES			
	Rates	Fringes		
BRICKLAYER	•	24.22		
BRWI0008-002 06/01/2019				

MILWAUKEE, OZAUKEE, WASHINGTON, AND WAUKESHA COUNTIES

CALUMET, FOND DU LAC, MANITOWOC, AND SHEBOYGAN COUNTIES

Rates Fringes

BRICKLAYER...... 34.18 23.90

BRWI0019-002 06/03/2019

BARRON, BUFFALO, BURNETT, CHIPPEWA, DUNN, EAU CLAIRE, PEPIN, PIERCE, POLK, RUSK, ST. CROIX, SAWYER AND WASHBURN COUNTIES

COLUMBIA AND SAUK COUNTIES

BURNETT (W. of Hwy 48), PIERCE (W. of Hwy 29), POLK (W. of Hwys 35, 48 & 65), AND ST. CROIX (W. of Hwy 65) COUNTIES

ADAMS, BARRON, BAYFIELD (Eastern 2/3), BROWN, BUFFALO, BURNETT (E. of Hwy 48), CALUMET, CHIPPEWA, CLARK, COLUMBIA, CRAWFORD, DANE, DODGE, DOOR, DUNN, EAU CLAIRE, FLORENCE (except area bordering Michigan State Line), FOND DU LAC, FOREST, GRANT, GREEN, GREEN LAKE, IOWA, IRON, JACKSON, JEFFERSON, JUNEAU, KEWAUNEE, LA CROSSE, LAFAYETTE, LANGLADE, LINCOLN, MANITOWOC, MARATHON, MARINETTE (except N.E. corner), MARQUETTE, MENOMINEE, MONROE, OCONTO, ONEIDA, OUTAGAMIE, PEPIN, PIERCE (E. of Hwys 29 & 65), POLK (E. of Hwys 35, 48 & 65), PORTAGE, PRICE, RICHLAND, ROCK, RUSK, SAUK, SAWYER, SHAWANO, SHEBOYGAN, ST CROIX (E. of Hwy 65), TAYLOR, TREMPEALEAU, VERNON, VILAS, WALWORTH, WASHBURN, WAUPACA, WAUSHARA, WINNEBAGO, AND WOOD COUNTIES

	Rates	Fringes
	Naces	11 Iliges
CARPENTER		
CARPENTER	\$ 33.56	18.00
MILLWRIGHT	\$ 35.08	18.35
PILEDRIVER	\$ 34.12	18.00
CARP0252-010 06/01/2016 ASHLAND COUNTY		
	Rates	Fringes
Carpenters		
Carpenter	\$ 33.56	18.00
Millwright		18.35
Pile Driver	\$ 34.12	18.00

______ CARP0264-003 06/01/2016

KENOSHA, MILWAUKEE, OZAUKEE, RACINE, WAUKESHA, AND WASHINGTON COUNTIES

	Rates	Fringes
CARPENTER	\$ 35.78	22.11
CARP0361-004 05/01/2018		

BAYFIELD (West of Hwy 63) AND DOUGLAS COUNTIES

	Rates	Fringes
CARPENTER	.\$ 36.15	20.43
CARP2337-001 06/01/2016		

ZONE A: MILWAUKEE, OZAUKEE, WAUKESHA AND WASHINGTON

ZONE B: KENOSHA & RACINE

	Rates	Fringes
PILEDRIVERMAN		
Zone A	\$ 31.03	22.69
Zone B	\$ 31.03	22.69

ELEC0014-002 06/03/2019

ASHLAND, BARRON, BAYFIELD, BUFFALO, BURNETT, CHIPPEWA, CLARK (except Maryville, Colby, Unity, Sherman, Fremont, Lynn & Sherwood), CRAWFORD, DUNN, EAU CLAIRE, GRANT, IRON, JACKSON, LA CROSSE, MONROE, PEPIN, PIERCE, POLK, PRICE, RICHLAND, RUSK, ST CROIX, SAWYER, TAYLOR, TREMPEALEAU, VERNON, AND WASHBURN COUNTIES

Rates Fringes Electricians:.....\$ 35.59 20.87 ELEC0014-007 06/03/2019 REMAINING COUNTIES Rates Fringes Teledata System Installer Installer/Technician.....\$ 27.25 14.34 Low voltage construction, installation, maintenance and removal of teledata facilities (voice, data, and video) including outside plant, telephone and data inside wire, interconnect, terminal equipment, central offices, PABX, fiber optic cable and equipment, micro waves, V-SAT, bypass, CATV, WAN (wide area networks), LAN (local area networks), and ISDN (integrated systems digital network). ._____ ELEC0127-002 06/01/2019 KENOSHA COUNTY Rates Fringes Electricians:.....\$ 40.49 30%+12.07 ELEC0158-002 06/03/2019 BROWN, DOOR, KEWAUNEE, MANITOWOC (except Schleswig), MARINETTE(Wausuakee and area South thereof), OCONTO, MENOMINEE (East of a ine 6 miles West of the West boundary of Oconto County), SHAWANO (Except Area North of Townships of Aniwa and Hutchins) COUNTIES Rates Fringes Electricians:.....\$ 33.52 29.75%+10.26 ELEC0159-003 06/01/2019 COLUMBIA, DANE, DODGE (Area West of Hwy 26, except Chester and Emmet Townships), GREEN, LAKE (except Townships of Berlin, Seneca, and St. Marie), IOWA, MARQUETTE (except Townships of Neshkoka, Crystal Lake, Newton, and Springfield), and SAUK COUNTIES Rates Fringes Electricians:.....\$ 40.30

ELEC0219-004 06/01/2016

FLORENCE COUNTY (Townships of Aurora, Commonwealth, Fern, Florence and Homestead) AND MARINETTE COUNTY (Township of Niagara)

	Rates	Fringes
Electricians: Electrical contracts over \$180,000 Electrical contracts under \$180,000	.\$ 30.18	18.63 18.42
ELEC0242-005 05/16/2018		
DOUGLAS COUNTY		
	Rates	Fringes
Electricians:		26.17
ELEC0388-002 06/03/2019		
ADAMS, CLARK (Colby, Freemont, Ly Sherwood, Unity), FOREST, JUNEAU MARINETTE (Beecher, Dunbar, Goods West of a line 6 miles West of the County), ONEIDA, PORTAGE, SHAWANG AND WOOD COUNTIES	J, LANGLADE, LIN man & Pembine), ne West boundary	ICOLN, MARATHON, MENOMINEE (Area of Oconto
	Rates	Fringes
Electricians:	.\$ 33.56	26%+11.01
RACINE COUNTY (Except Burlington	Township)	
	Rates	Fringes
Electricians:	.\$ 40.30	22.19
ELEC0494-005 06/01/2019		
MILWAUKEE, OZAUKEE, WASHINGTON,	AND WAUKESHA COU	NTIES
	Rates	Fringes
Electricians:	.\$ 41.03	25.11
* ELEC0494-006 01/01/2020		
CALLES (T. 1. C.N	\	c o

CALUMET (Township of New Holstein), DODGE (East of Hwy 26 including Chester Township), FOND DU LAC, MANITOWOC (Schleswig), and SHEBOYGAN COUNTIES

	Rates	Fringes
Electricians:	\$ 34.99	22.31

ELEC0494-013 06/01/2019

DODGE (East of Hwy 26 including Chester Twp, excluding Emmet Twp), FOND DU LAC (Except Waupuin), MILWAUKEE, OZAUKEE, MANITOWOC (Schleswig), WASHINGTON, AND WAUKESHA COUNTIES

F	Rates	Fringes
Sound & Communications		
Installer\$	20.53	18.13
Technician\$	30.18	19.58

Installation, testing, maintenance, operation and servicing of all sound, intercom, telephone interconnect, closed circuit TV systems, radio systems, background music systems, language laboratories, electronic carillion, antenna distribution systems, clock and program systems and low-voltage systems such as visual nurse call, audio/visual nurse call systems, doctors entrance register systems. Includes all wire and cable carrying audio, visual, data, light and radio frequency signals. Includes the installation of conduit, wiremold, or raceways in existing structures that have been occupied for six months or more where required for the protection of the wire or cable, but does not mean a complete conduit or raceway system. work covered does not include the installation of conduit, wiremold or any raceways in any new construction, or the installation of power supply outlets by means of which external electric power is supplied to any of the foregoing equipment or products

FLECOTT 002 05 (04 (2040

ELEC0577-003 06/01/2019

CALUMET (except Township of New Holstein), GREEN LAKE (N. part including Townships of Berlin, St Marie, and Seneca), MARQUETTE (N. part including Townships of Crystal Lake, Neshkoro, Newton, and Springfield), OUTAGAMIE, WAUPACA, WAUSHARA, AND WINNEBAGO COUNTIES

	Rates	Fringes
Electricians:	.\$ 33.15	28.50%+10.00
ELEC0890-003 06/01/2019		

DODGE (Emmet Township only), GREEN, JEFFERSON, LAFAYETTE, RACINE (Burlington Township), ROCK AND WALWORTH COUNTIES

	Rates	Fringes
Electricians:	.\$ 35.91	25.95%+10.83

ELEC0953-001 06/02/2019

ı	Rates	Fringes
Line Construction: (1) Lineman\$ (2) Heavy Equipment	47.53	21.43
Operator\$	42.78	19.80
(3) Equipment Operator\$	38.02	18.40
(4) Heavy Groundman Driver\$	33.27	16.88
(5) Light Groundman Driver\$	30.89	16.11
(6) Groundsman\$	26.14	14.60

ENGI0139-005 06/03/2019

	Rates	Fringes
Power Equipment Operator		
Group 1	.\$ 41.17	23.03
Group 2	.\$ 40.67	23.03
Group 3	.\$ 40.17	23.03
Group 4	.\$ 39.91	23.03
Group 5	.\$ 39.62	23.03
Group 6	.\$ 33.72	23.03

HAZARDOUS WASTE PREMIUMS:

EPA Level ""A"" protection - \$3.00 per hour EPA Level ""B"" protection - \$2.00 per hour EPA Level ""C"" protection - \$1.00 per hour

POWER EQUIPMENT OPERATORS CLASSIFICATIONS

GROUP 1: Cranes, tower cranes, and derricks with or without attachments with a lifting capacity of over 100 tons; or cranes, tower cranes, and derricks with boom, leads and/or jib lengths measuring 176 feet or longer.

GROUP 2: Cranes, tower cranes and derricks with or without attachments with a lifting capacity of 100 tons or less; or cranes, tower cranes, and derricks with boom, leads, and/or jibs lengths measuring 175 feet or under and Backhoes (excavators) weighing 130,000 lbs and over; caisson rigs; pile driver; dredge operator; dredge engineer; Boat Pilot.

GROUP 3: Mechanic or welder - Heavy duty equipment; cranes with a lifting capacity of 25 tons or under; concrete breaker (manual or remote); vibratory/sonic concrete breaker; concrete laser screed; concrete slipform paver; concrete batch plant operator; concrete pvt. spreader - heavy duty (rubber tired); concrete spreader & distributor; automatic subgrader (concrete); concrete grinder & planing machine; concrete slipform curb & gutter machine; slipform concrete placer; tube finisher; hydro blaster (10,000 psi & over); bridge paver; concrete conveyor system; concrete

pump; Rotec type Conveyor; stabilizing mixer (self-propelled); shoulder widener; asphalt plant engineer; bituminious paver; bump cutter & grooving machine; milling machine; screed (bituminous paver); asphalt heater, planer & scarifier; Backhoes (excavators) weighing under 130,000 lbs; grader or motor patrol; tractor (scraper, dozer, pusher, loader); scraper - rubber tired (single or twin engine); endloader; hydraulic backhoe (tractor type); trenching machine; skid rigs; tractor, side boom (heavy); drilling or boring machine (mechanical heavy); roller over 5 tons; percussion or rotary drilling machine; air track; blaster; loading machine (conveyor); tugger; boatmen; winches & A-frames; post driver; material hoist.

GROUP 4: Greaser, roller steel (5 tons or less); roller (pneumatic tired) - self propelled; tractor (mounted or towed compactors & light equipment); shouldering machine; self- propelled chip spreader; concrete spreader; finishing machine; mechanical float; curing machine; power subgrader; joint sawer (multiple blade) belting machine; burlap machine; texturing machine; tractor endloader (rubber tired) - light; jeep digger; forklift; mulcher; launch operator; fireman, environmental burner

GROUP 5: Air compressor; power pack; vibrator hammer and extractor; heavy equipment, leadman; tank car heaters; stump chipper; curb machine operator; Concrete proportioning plants; generators; mudjack operator; rock breaker; crusher or screening plant; screed (milling machine); automatic belt conveyor and surge bin; pug mill operator; Oiler, pump (over 3 inches); Drilling Machine Tender.

GROUP 6: Off-road material hauler with or without ejector.

IRON0008-002 06/01/2019

BROWN, CALUMET, DOOR, FOND DU LAC, KEWAUNEE, MANITOWOC, MARINETTE, OCONTO, OUTAGAMI, SHAWANO, SHEBOYGAN, AND WINNEBAGO COUNTIES:

Rates Fringes
IRONWORKER......\$ 35.07 27.62

Paid Holidays: New Year's Day, Memorial Day, July 4th, Labor Day, Thanksgiving Day & Christmas Day.

IRON0008-003 06/01/2019

KENOSHA, MILWAUKEE, OZAUKEE, RACINE, WALWORTH (N.E. 2/3), WASHINGTON, AND WAUKESHA COUNTIES

Rates

Fringes

IRONWORKER	.\$ 37.12	27.87
Paid Holidays: New Year's Day, Day, Thanksgiving Day & Christ	mas Day.	
IRON0383-001 06/01/2019		
ADAMS, COLUMBIA, CRAWFORD, DANE, GRANT, GREENE, (Excluding S.E. t JEFFERSON, JUNEAU, LA CROSSE, LA MARQUETTE, MENOMINEE, MONROE, PO area, vicinity of Edgerton and M WAUSHARA, AND WOOD COUNTIES	ip), GREEN LAKE, FAYETTE, LANGLAD RTAGE, RICHLAND,	IOWA, DE, MARATHON, ROCK (Northern
	Rates	Fringes
IRONWORKER	.\$ 35.50	26.57
IRON0498-005 06/01/2019		
GREEN (S.E. 1/3), ROCK (South of WALWORTH (S.W. 1/3) COUNTIES:	Edgerton and Mi	ilton), and
	Rates	Fringes
IRONWORKER	.\$ 40.25	40.53
IRON0512-008 06/03/2019		
BARRON, BUFFALO, CHIPPEWA, CLARK PEPIN, PIERCE, POLK, RUSK, ST CR COUNTIES		
	Rates	Fringes
IRONWORKER		29.40
IRON0512-021 06/03/2019		
ASHLAND, BAYFIELD, BURNETT, DOUG PRICE, SAWYER, VILAS AND WASHBU		DLN, ONEIDA,
	Rates	Fringes
IRONWORKER	•	29.40
LAB00113-002 06/03/2019		
MILWAUKEE AND WAUKESHA COUNTIES		

Rates

Fringes

LABORER

Group 1\$ 29.02	21.92
Group 2\$ 29.17	21.92
Group 3\$ 29.37	21.92
Group 4\$ 29.52	21.92
Group 5\$ 29.67	21.92
Group 6\$ 25.51	21.92

LABORERS CLASSIFICATIONS

GROUP 1: General Laborer; Tree Trimmer; Conduit Layer; Demolition and Wrecking Laborer; Guard Rail, Fence, and Bridge Builder; Landscaper; Multiplate Culvert Assembler; Stone Handler; Bituminous Worker (Shoveler, Loader, and Utility Man); Batch Truck Dumper or Cement Handler; Bituminous Worker (Dumper, Ironer, Smoother, and Tamper); Concrete Handler

GROUP 2: Air Tool Operator; Joint Sawer and Filler (Pavement); Vibrator or Tamper Operator (Mechanical Hand Operated); Chain Saw Operator; Demolition Burning Torch Laborer

GROUP 3: Bituminous Worker (Raker and Luteman); Formsetter (Curb, Sidewalk, and Pavement); Strike Off Man

GROUP 4: Line and Grade Specialist

GROUP 5: Blaster and Powderman

GROUP 6: Flagperson; traffic control person

LAB00113-003 06/03/2019

OZAUKEE AND WASHINGTON COUNTIES

		Rates	Fringes	;
LABORER				
Group	1	\$ 28.27	21.9	€2
Group	2	\$ 28.37	21.9	92
Group	3	\$ 28.42	21.9	€2
Group	4	\$ 28.62	21.9	€2
Group	5	\$ 28.47	21.9	€2
Group	6	\$ 25.36	21.9	€2

LABORERS CLASSIFICATIONS

GROUP 1: General Laborer; Tree Trimmer; Conduit Layer; Demolition and Wrecking Laborer; Guard Rail, Fence, and Bridge Builder; Landscaper; Multiplate Culvert Assembler; Stone Handler; Bituminous Worker (Shoveler, Loader, and Utility Man); Batch Truck Dumper or Cement Handler; Bituminous Worker (Dumper, Ironer, Smoother, and Tamper); Concrete Handler

GROUP 2: Air Tool Operator; Joint Sawer and Filler

(Pavement); Vibrator or Tamper Operator (Mechanical Hand Operated);

GROUP 3: Bituminous Worker (Raker and Luteman); Formsetter (Curb, Sidewalk, and Pavement); Strike Off Man

GROUP 4: Line and Grade Specialist

GROUP 5: Blaster; powderman

GROUP 6: Flagperson and Traffic Control Person

LAB00113-011 06/03/2019

KENOSHA AND RACINE COUNTIES

	1	Rates	Fringes
LABORER			
Group	1\$	28.08	21.92
Group	2\$	28.23	21.92
Group	3\$	28.43	21.92
Group	4\$	28.40	21.92
Group	5\$	28.73	21.92
Group	6\$	25.22	21.92

LABORERS CLASSIFICATIONS:

GROUP 1: General laborer; Tree Trimmer; Conduit Layer; Demolition and Wrecking Laborer; Guard Rail, Fence, and Bridge Builder; Landscaper; Multiplate Culvert Assembler; Stone Handler; Bituminous Worker (Shoveler, Loader, and Utility Man); Batch Truck Dumper or Cement Handler; Bituminous worker (Dumper, Ironer, Smoother, and Tamper); Concrete Handler

GROUP 2: Air Tool Operator; Joint Sawer and Filler (Pavement); Vibrator or Tamper Operator (Mechanical Hand Operated); Chain Saw Operator; Demolition Burning Torch Laborer

GROUP 3: Bituminous Worker (Raker and Luteman); Formsetter (Curb, Sidewalk, and Pavement); Strike Off Man

GROUP 4: Line and Grade Specialist

GROUP 5: Blaster and Powderman

GROUP 6: Flagman; traffic control person

LAB00140-002 06/03/2019

ADAMS, ASHLAND, BARRON, BAYFIELD, BROWN, BUFFALO, BURNETT, CALUMET, CHIPPEWA, CLARK, COLUMBIA, CRAWFORD, DODGE, DOOR, DOUGLAS, DUNN, EAU CLAIRE, FLORENCE, FOND DU LAC, FOREST, GRANT, GREEN, GREEN LAKE, IRON, JACKSON, JUNEAU, IOWA,

JEFFERSON, KEWAUNEE, LA CROSSE, LAFAYETTE, LANGLADE, LINCOLN, MANITOWOC, MARATHON, MARINETTE, MARQUETTE, MENOMINEE, MONROE, OCONTO, ONEIDA, OUTAGAMIE, PEPIN, PIERCE, POLK, PORTAGE, PRICE, RICHLAND, ROCK, RUSK, SAUK, SAWYER, SHAWANO, SHEBOYGAN, ST. CROIX, TAYLOR, TREMPEALEAU, VERNON, VILLAS, WALWORTH, WASHBURN, WAUPACA, WAUSHARA, WINNEBAGO, AND WOOD COUNTIES

	I	Rates	Fringes
LABORER			
Group	1\$	32.84	17.54
Group	2\$	32.94	17.54
Group	3\$	32.99	17.54
Group	4\$	33.19	17.54
Group	5\$	33.04	17.54
Group	6\$	29.47	17.54

LABORER CLASSIFICATIONS

GROUP 1: General Laborer; Tree Trimmer; Conduit Layer; Demolition and Wrecking Laborer; Guard Rail, Fence, and Bridge Builder; Landscaper; Multiplate Culvert Assembler; Stone Handler; Bitminous Worker (Shoveler, Loader, and Utility Man); Batch Truck Dumper or Cement Handler; Bituminous Worker (Dumper, Ironer, Smoother and Tamper); Concrete Handler

GROUP 2: Air Tool Operator; Joint Sawer and Filler (Pavement); Vibrator or Tamper Operator (Mechanical Hand Operated); Chain Saw Operator, Demolition Burning Torch Laborer

GROUP 3: Bituminous Worker (Raker and Luteman); Formsetter (Curb, Sidewalk and Pavement); Strike Off Man

GROUP 4: Line and Grade Secialist

GROUP 5: Blaster; powderman

GROUP 6: Flagperson; Traffic Control

LAB00464-003 06/03/2019

DANE COUNTY

		Rates	Fringes
LABORER			
Group	1\$	33.12	17.54
Group	2\$	33.22	17.54
Group	3\$	33.27	17.54
Group	4\$	33.47	17.54
Group	5\$	33.32	17.54
Group	6\$	29.47	17.54

LABORERS CLASSIFICATIONS:

GROUP 1: General Laborer; Tree Trimmer; Conduit Layer; Demolition and Wrecking Laborer; Guard Rail, Fence, and Bridge Builder; Landscaper; Multiplate Culvert Assembler; Stone Handler; Bituminous Worker (Shoveler, Loader, and Utility Man); Batch Truck Dumper or Cement Handler; Bituminious Worker (Dumper, Ironer, Smoother, and Tamper); Concrete Handler

GROUP 2: Air Tool Operator; Joint Sawer and Filler (Pavement); Vibrator or Tamper Operator (Mechanical Hand Operated); Chain Saw Operator; Demolition Burning Torch Laborer

GROUP 3: Bituminous Worker (Raker and Luteman); Formsetter (Curb, Sidewalk, and Pavement); Strike Off Man

GROUP 4: Line and Grade Specialist

GROUP 5: Blaster; Powderman

GROUP 6: Flagperson and Traffic Control Person

PAIN0106-008 05/01/2017

ASHLAND, BAYFIELD, BURNETT, AND DOUGLAS COUNTIES

	F	Rates	Fringes
Painters:			
New:			
Brush,	Roller\$	30.33	17.27
Spray,	Sandblast, Steel\$	30.93	17.27
Repaint	:		
Brush,	Roller\$	28.83	17.27
Spray,	Sandblast, Steel\$	29.43	17.27

PAIN0108-002 06/01/2019

RACINE COUNTY

	Rates	Fringes	
Painters:			
Brush, Roller	\$ 36.08	20.36	
Spray & Sandblast	\$ 37.08	20.36	

PAIN0259-002 05/01/2008

BARRON, CHIPPEWA, DUNN, EAU CLAIRE, PEPIN, PIERCE, POLK, RUSK, SAWYER, ST. CROIX, AND WASHBURN COUNTIES

	Rates	Fringes
PAINTER	.\$ 24.11	12.15

BUFFALO, CRAWFORD, JACKSON, LA CROSSE, MONROE, TREMPEALEAU, AND VERNON COUNTIES

	Rates	Fringes	
PAINTER	.\$ 22.03	12.45	
PAIN0781-002 06/01/2019			
JEFFERSON, MILWAUKEE, OZAUKEE, W	ASHINGTON, AND W	AUKESHA COUNTIES	
	Rates	Fringes	
Painters: Bridge Brush Spray & Sandblast	.\$ 32.95 .\$ 33.70	23.86 23.86 23.86	
PAIN0802-002 06/01/2019			
COLUMBIA, DANE, DODGE, GRANT, GR ROCK, AND SAUK COUNTIES	EEN, IOWA, LAFAY	ETTE, RICHLAND,	
	Rates	Fringes	
PAINTER Brush	.\$ 30.93	18.44	
PREMIUM PAY: Structural Steel, Spray, Bridg hour.	es = \$1.00 add	litional per	
PAIN0802-003 06/01/2019			
ADAMS, BROWN, CALUMET, CLARK, DOOR, FOND DU LAC, FOREST, GREEN LAKE, IRON, JUNEAU, KEWAUNEE, LANGLADE, LINCOLN, MANITOWOC, MARATHON, MARINETTE, MARQUETTE, MENOMINEE, OCONTO, ONEIDA, OUTAGAMIE, PORTAGE, PRICE, SHAWANO, SHEBOYGAN, TAYLOR, VILAS, WAUSHARA, WAUPACA, WINNEBAGO, AND WOOD COUNTIES			
	Rates	Fringes	
PAINTER		18.58	
PAIN0934-001 06/01/2017			
KENOSHA AND WALWORTH COUNTIES			
	Rates	Fringes	
Painters: Brush	.\$ 33.74	18.95	

SprayStructural Steel	18.95 18.95
PAIN1011-002 06/02/2019	
FLORENCE COUNTY	

	Rates	Fringes	
Painters:	\$ 25.76	13.33	
DI 400500 040 06 (04 /2047			_

PLAS0599-010 06/01/2017

	Rates	Fringes
CEMENT MASON/CONCRETE FINISH	ER	
Area 1	\$ 39.46	17.17
Area 2 (BAC)	\$ 35.07	19.75
Area 3	\$ 35.61	19.40
Area 4	\$ 34.70	20.51
Area 5	\$ 36.27	18.73
Area 6	\$ 32.02	22.99

AREA DESCRIPTIONS

AREA 1: BAYFIELD, DOUGLAS, PRICE, SAWYER, AND WASHBURN COUNTIES

AREA 2: ADAMS, ASHLAND, BARRON, BROWN, BURNETT, CALUMET, CHIPPEWA, CLARK, COLUMBIA, DODGE, DOOR, DUNN, FLORENCE, FOND DU LAC, FOREST, GREEN LAKE, IRON, JEFFERSON, KEWAUNEE, LANGLADE, LINCOLN, MANITOWOC, MARATHON, MARINETTE, MARQUETTE, MENOMINEE, OCONTO, ONEIDA, OUTAGAMIE, POLK, PORTAGE, RUSK, ST CROIX, SAUK, SHAWANO, SHEBOYGAN, TAYLOR, VILAS, WALWORTH, WAUPACA, WAUSHARA, WINNEBAGO, AND WOOD COUNTIES

AREA 3: BUFFALO, CRAWFORD, EAU CLAIRE, JACKSON, JUNEAU, LA CROSSE MONROE, PEPIN, PIERCE, RICHLAND, TREMPEALEAU, AND VERNON COUNTIES

AREA 4: MILWAUKEE, OZAUKEE, WASHINGTON, AND WAUKESHA COUNTIES

AREA 5: DANE, GRANT, GREEN, IOWA, LAFAYETTE, AND ROCK COUNTIES

AREA 6: KENOSHA AND RACINE COUNTIES

TEAM0039-001 06/01/2019

	Rates	Fringes
TRUCK DRIVER 1 & 2 Axles 3 or more Axles; Euclids Dumptor & Articulated,	\$ 29.57	22.03

Truck Mechanic	\$ 29.72	22.03
WELL DRILLER	\$ 16.52	3.70

WELDERS - Receive rate prescribed for craft performing operation to which welding is incidental.

Note: Executive Order (EO) 13706, Establishing Paid Sick Leave for Federal Contractors applies to all contracts subject to the Davis-Bacon Act for which the contract is awarded (and any solicitation was issued) on or after January 1, 2017. If this contract is covered by the EO, the contractor must provide employees with 1 hour of paid sick leave for every 30 hours they work, up to 56 hours of paid sick leave each year. Employees must be permitted to use paid sick leave for their own illness, injury or other health-related needs, including preventive care; to assist a family member (or person who is like family to the employee) who is ill, injured, or has other health-related needs, including preventive care; or for reasons resulting from, or to assist a family member (or person who is like family to the employee) who is a victim of, domestic violence, sexual assault, or stalking. Additional information on contractor requirements and worker protections under the EO is available at www.dol.gov/whd/govcontracts.

Unlisted classifications needed for work not included within the scope of the classifications listed may be added after award only as provided in the labor standards contract clauses (29CFR 5.5 (a) (1) (ii)).

The body of each wage determination lists the classification and wage rates that have been found to be prevailing for the cited type(s) of construction in the area covered by the wage determination. The classifications are listed in alphabetical order of ""identifiers"" that indicate whether the particular rate is a union rate (current union negotiated rate for local), a survey rate (weighted average rate) or a union average rate (weighted union average rate).

Union Rate Identifiers

A four letter classification abbreviation identifier enclosed in dotted lines beginning with characters other than ""SU"" or ""UAVG"" denotes that the union classification and rate were prevailing for that classification in the survey. Example: PLUM0198-005 07/01/2014. PLUM is an abbreviation identifier of the union which prevailed in the survey for this classification, which in this example would be Plumbers. 0198 indicates the local union number or district council number where applicable, i.e., Plumbers Local 0198. The next number, 005 in the example, is an internal number used in processing

the wage determination. 07/01/2014 is the effective date of the most current negotiated rate, which in this example is July 1, 2014.

Union prevailing wage rates are updated to reflect all rate changes in the collective bargaining agreement (CBA) governing this classification and rate.

Survey Rate Identifiers

Classifications listed under the ""SU"" identifier indicate that no one rate prevailed for this classification in the survey and the published rate is derived by computing a weighted average rate based on all the rates reported in the survey for that classification. As this weighted average rate includes all rates reported in the survey, it may include both union and non-union rates. Example: SULA2012-007 5/13/2014. SU indicates the rates are survey rates based on a weighted average calculation of rates and are not majority rates. LA indicates the State of Louisiana. 2012 is the year of survey on which these classifications and rates are based. The next number, 007 in the example, is an internal number used in producing the wage determination. 5/13/2014 indicates the survey completion date for the classifications and rates under that identifier.

Survey wage rates are not updated and remain in effect until a new survey is conducted.

Union Average Rate Identifiers

Classification(s) listed under the UAVG identifier indicate that no single majority rate prevailed for those classifications; however, 100% of the data reported for the classifications was union data. EXAMPLE: UAVG-OH-0010 08/29/2014. UAVG indicates that the rate is a weighted union average rate. OH indicates the state. The next number, 0010 in the example, is an internal number used in producing the wage determination. 08/29/2014 indicates the survey completion date for the classifications and rates under that identifier.

A UAVG rate will be updated once a year, usually in January of each year, to reflect a weighted average of the current negotiated/CBA rate of the union locals from which the rate is based.

WAGE DETERMINATION APPEALS PROCESS

- 1.) Has there been an initial decision in the matter? This can be:
- * an existing published wage determination
- * a survey underlying a wage determination
- * a Wage and Hour Division letter setting forth a position on a wage determination matter

* a conformance (additional classification and rate) ruling

On survey related matters, initial contact, including requests for summaries of surveys, should be with the Wage and Hour Regional Office for the area in which the survey was conducted because those Regional Offices have responsibility for the Davis-Bacon survey program. If the response from this initial contact is not satisfactory, then the process described in 2.) and 3.) should be followed.

With regard to any other matter not yet ripe for the formal process described here, initial contact should be with the Branch of Construction Wage Determinations. Write to:

Branch of Construction Wage Determinations Wage and Hour Division U.S. Department of Labor 200 Constitution Avenue, N.W. Washington, DC 20210

2.) If the answer to the question in 1.) is yes, then an interested party (those affected by the action) can request review and reconsideration from the Wage and Hour Administrator (See 29 CFR Part 1.8 and 29 CFR Part 7). Write to:

Wage and Hour Administrator U.S. Department of Labor 200 Constitution Avenue, N.W. Washington, DC 20210

The request should be accompanied by a full statement of the interested party's position and by any information (wage payment data, project description, area practice material, etc.) that the requestor considers relevant to the issue.

3.) If the decision of the Administrator is not favorable, an interested party may appeal directly to the Administrative Review Board (formerly the Wage Appeals Board). Write to:

Administrative Review Board U.S. Department of Labor 200 Constitution Avenue, N.W. Washington, DC 20210

4.) All decisions by the Administrative Review Board are final.

END OF GENERAL DECISION"

NOTICE TO BIDDERS WAGE RATE DECISION

The wage rate decision of the Department of Labor which has been incorporated in these advertised specifications is incomplete in that the classifications may be omitted from the Department of Labor's decision.


Since the bidder is responsible, independently, for ascertaining area practice with respect to the necessity, or lack of necessity, for the use of these classifications in the prosecution of the work contemplated by this project, no inference may be drawn from the omission of these classifications concerning prevailing area practices relative to their use. Further, this omission will not, per se, be construed as establishing any governmental liability for increased labor cost if it is subsequently determined that such classifications are required.

There may be omissions and/or errors in the federal wage rates. The bidder is responsible for evaluating and determining the correct applicable rate.

If a project includes multiple types of construction (highway, bridge over navigable water, sanitary sewer and water main, building) and there is not a separate wage determination for this type of work included in the proposal, use the wage determination that is in the proposal.

If a project includes multiple types of construction, different wage rate determinations may be inserted into the contract (WI10/Highway = in all WisDOT highway contracts, WI15/Heavy = bridge over navigable water per USDOL and US Coast Guard designation, WI8/Heavy (Sewer & Water Line & Tunnel) = sanitary sewer and water main if the cost is more than 20% of the contract and/or at least \$1,000,000, and Building). If multiple wage rate determinations are inserted into the contract, use the classification in the wage determination for the work being done. Use WI15 wage rates when working on the bridge and/or structure from bank to bank. Use WI8 wage rates when working on any sanitary sewer or water main work. Use Building wage rates for all work done within the footprint of the building. Use WI10 wage rates for all other highway work in the contract and approaches to structures. For example, if a laborer is working within the footprint of a building, use the Laborer rate in the Building wage determination inserted in the contract. If a laborer is working on a bridge/structure within the banks, use the Laborer rate in the WI15/Heavy wage determination if inserted in the contract. If the laborer is working on the highway, use the Laborer rate in the WI10/Highway wage determination.







Proposal Schedule of Items

Page 1 of 16

Proposal ID: 20200714011 **Project(s):** 9650-17-61, 9650-17-70


Federal ID(s): WISC 2020351, WISC 2020356

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0002	201.0105 Clearing	57.500 STA		
0004	201.0205 Grubbing	57.500 STA		
0006	203.0100 Removing Small Pipe Culverts	26.000 EACH		
0008	203.0600.S Removing Old Structure Over Waterway With Minimal Debris (station) 01. 154+20	LS	LUMP SUM	
0010	204.0100 Removing Concrete Pavement	351.000 SY		
0012	204.0120 Removing Asphaltic Surface Milling	42,600.000 SY	·	·
0014	204.0150 Removing Curb & Gutter	3,050.000 LF		·
0016	204.0155 Removing Concrete Sidewalk	3,770.000 SY	·	·
0018	204.0165 Removing Guardrail	885.000 LF		·
0020	204.0190 Removing Surface Drains	2.000 EACH		
0022	204.0220 Removing Inlets	14.000 EACH		·
0024	204.0245 Removing Storm Sewer (size) 01. 12-Inch	70.000 LF		
0026	204.0245 Removing Storm Sewer (size) 02. 15-Inch	298.000 LF		·
0028	204.0245 Removing Storm Sewer (size) 03. 18-Inch	434.000 LF	·	
0030	205.0100 Excavation Common	20,836.000 CY		







Proposal Schedule of Items

Page 2 of 16

Proposal ID: 20200714011 **Project(s):** 9650-17-61, 9650-17-70


Federal ID(s): WISC 2020351, WISC 2020356

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0032	205.0501.S Excavation, Hauling, and Disposal of Petroleum Contaminated Soil	980.000 TON	·	·
0034	206.2000 Excavation for Structures Culverts (structure) 01. C-73-0004	LS	LUMP SUM	<u> </u>
0036	208.0100 Borrow	9,113.000 CY		
0038	210.1500 Backfill Structure Type A	195.000 TON		<u> </u>
0040	210.2500 Backfill Structure Type B	530.000 TON		
0042	211.0100 Prepare Foundation for Asphaltic Paving (project) 01. 9650-17-70	LS	LUMP SUM	·
0044	211.0400 Prepare Foundation for Asphaltic Shoulders	27.000 STA	·	·
0046	213.0100 Finishing Roadway (project) 01. 9650- 17-61	1.000 EACH		·
0048	213.0100 Finishing Roadway (project) 02. 9650- 17-70	1.000 EACH	·	·
0050	305.0110 Base Aggregate Dense 3/4-Inch	970.000 TON		
0052	305.0120 Base Aggregate Dense 1 1/4-Inch	20,680.000 TON		
0054	311.0110 Breaker Run	6,676.000 TON		
0056	415.0410 Concrete Pavement Approach Slab	177.000 SY		
0058	416.0160 Concrete Driveway 6-Inch	1,215.000 SY		
0060	416.0610 Drilled Tie Bars	22.000 EACH		







Proposal Schedule of Items

Page 3 of 16

Proposal ID: 20200714011 **Project(s):** 9650-17-61, 9650-17-70


Federal ID(s): WISC 2020351, WISC 2020356

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0062	416.1010 Concrete Surface Drains	9.000 CY		
0064	450.4000 HMA Cold Weather Paving	600.000 TON		
0066	455.0605 Tack Coat	2,660.000 GAL		·
0068	460.2000 Incentive Density HMA Pavement	5,010.000 DOL	1.00000	5,010.00
0070	460.5223 HMA Pavement 3 LT 58-28 S	830.000 TON		·
0072	460.5244 HMA Pavement 4 LT 58-34 S	6,990.000 TON		·
0074	465.0110 Asphaltic Surface Patching	2,000.000 TON		·
0076	465.0120 Asphaltic Surface Driveways and Field Entrances	234.000 TON	·	·
0078	465.0125 Asphaltic Surface Temporary	52.000 TON		
0800	502.0120.S Non-Shrink Grout	2.000 CF		
0082	502.3200 Protective Surface Treatment	1,195.000 SY	·	
0084	502.3210 Pigmented Surface Sealer	346.000 SY	·	
0086	502.3215.S Protective Surface Treatment Reseal	200.000 SY	·	
0088	504.0100 Concrete Masonry Culverts	36.000 CY	<u> </u>	
0090	504.1000.S Precast Concrete Wingwalls (structure) 01. C-73-0004	LS	LUMP SUM	·
0092	504.2000.S Precast Concrete Box Culvert (ft X ft) 01. 6 FT x 3 FT	80.000 LF	·	







Page 4 of 16


Proposal ID: 20200714011 **Project(s):** 9650-17-61, 9650-17-70

Federal ID(s): WISC 2020351, WISC 2020356

SECTION: 0001 Contract Items

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0094	505.0600 Bar Steel Reinforcement HS Coated Structures	4,870.000 LB		
0096	509.0301 Preparation Decks Type 1	145.000 SY		
0098	509.0302 Preparation Decks Type 2	80.000 SY		
0100	509.0500 Cleaning Decks	1,200.000 SY		
0102	509.1500 Concrete Surface Repair	350.000 SF	·	
0104	509.2000 Full-Depth Deck Repair	4.000 SY		
0106	509.2500 Concrete Masonry Overlay Decks	90.000 CY		
0108	509.9050.S Cleaning Parapets	630.000 LF		
0110	511.1200 Temporary Shoring (structure) 01. C-73- 0004	800.000 SF	·	
0112	513.8006 Railing Steel Pedestrian Type C1	31.000 LF	·	
0114	516.0500 Rubberized Membrane Waterproofing	7.000 SY		
0116	521.1012 Apron Endwalls for Culvert Pipe Steel 12-Inch	2.000 EACH	·	
0118	522.0124 Culvert Pipe Reinforced Concrete Class III 24-Inch	240.000 LF	·	
0120	522.0136 Culvert Pipe Reinforced Concrete Class III 36-Inch	112.000 LF	·	
0122	522.0418 Culvert Pipe Reinforced Concrete Class IV 18-Inch	144.000 LF		







Page 5 of 16


Proposal ID: 20200714011 **Project(s):** 9650-17-61, 9650-17-70

Federal ID(s): WISC 2020351, WISC 2020356

SECTION: 0001 Contract Items

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0124	522.0424 Culvert Pipe Reinforced Concrete Class IV 24-Inch	50.000 LF		
0126	522.0430 Culvert Pipe Reinforced Concrete Class IV 30-Inch	78.000 LF		
0128	522.1012 Apron Endwalls for Culvert Pipe Reinforced Concrete 12-Inch	8.000 EACH	.	
0130	522.1015 Apron Endwalls for Culvert Pipe Reinforced Concrete 15-Inch	6.000 EACH		
0132	522.1018 Apron Endwalls for Culvert Pipe Reinforced Concrete 18-Inch	9.000 EACH		
0134	522.1024 Apron Endwalls for Culvert Pipe Reinforced Concrete 24-Inch	11.000 EACH		
0136	522.1030 Apron Endwalls for Culvert Pipe Reinforced Concrete 30-Inch	3.000 EACH		
0138	522.1036 Apron Endwalls for Culvert Pipe Reinforced Concrete 36-Inch	3.000 EACH	.	·
0140	601.0411 Concrete Curb & Gutter 30-Inch Type D	55.000 LF		
0142	602.0405 Concrete Sidewalk 4-Inch	97,600.000 SF	·	
0144	602.0505 Curb Ramp Detectable Warning Field Yellow	160.000 SF		
0146	602.0605 Curb Ramp Detectable Warning Field Radial Yellow	532.000 SF	·	·
0148	602.1500 Concrete Steps	90.000 SF		
0150	603.8000 Concrete Barrier Temporary Precast Delivered	837.500 LF	·	·







Page 6 of 16

Proposal ID: 20200714011 **Project(s):** 9650-17-61, 9650-17-70

Federal ID(s): WISC 2020351, WISC 2020356

SECTION: 0001 Contract Items

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0152	603.8125 Concrete Barrier Temporary Precast Installed	1,850.000 LF		.
0154	606.0200 Riprap Medium	213.000 CY		
0156	606.0300 Riprap Heavy	571.000 CY		
0158	608.0412 Storm Sewer Pipe Reinforced Concrete Class IV 12-Inch	1,457.000 LF	·	
0160	608.0415 Storm Sewer Pipe Reinforced Concrete Class IV 15-Inch	1,628.000 LF	·	
0162	608.0418 Storm Sewer Pipe Reinforced Concrete Class IV 18-Inch	158.000 LF	·	
0164	608.0424 Storm Sewer Pipe Reinforced Concrete Class IV 24-Inch	2,654.000 LF		
0166	608.0430 Storm Sewer Pipe Reinforced Concrete Class IV 30-Inch	390.000 LF	·	.
0168	608.0436 Storm Sewer Pipe Reinforced Concrete Class IV 36-Inch	372.000 LF		
0170	611.0420 Reconstructing Manholes	12.000 EACH		
0172	611.0530 Manhole Covers Type J	11.000 EACH		
0174	611.0624 Inlet Covers Type H	72.000 EACH		
0176	611.0639 Inlet Covers Type H-S	7.000 EACH		<u> </u>
0178	611.0645 Inlet Covers Type MS-A	11.000 EACH		
0180	611.0654 Inlet Covers Type V	3.000 EACH		



05/13/2020 13:39:10



Proposal Schedule of Items

Page 7 of 16


Proposal ID: 20200714011 **Project(s):** 9650-17-61, 9650-17-70

Federal ID(s): WISC 2020351, WISC 2020356

SECTION: 0001 Contract Items

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0182	611.2004 Manholes 4-FT Diameter	5.000 EACH		
0184	611.2005 Manholes 5-FT Diameter	17.000 EACH	·	
0186	611.3004 Inlets 4-FT Diameter	10.000 EACH		
0188	611.3220 Inlets 2x2-FT	2.000 EACH		
0190	611.3230 Inlets 2x3-FT	59.000 EACH		
0192	611.3901 Inlets Median 1 Grate	11.000 EACH		
0194	611.8110 Adjusting Manhole Covers	20.000 EACH		
0196	611.8120.S Cover Plates Temporary	135.000 EACH		
0198	612.0212 Pipe Underdrain Unperforated 12-Inch	50.000 LF		
0200	612.0902.S Insulation Board Polystyrene (inch) 01. 2-Inch	286.000 SY	·	·
0202	614.0200 Steel Thrie Beam Structure Approach	20.650 LF		
0204	614.0305 Steel Plate Beam Guard Class A	310.000 LF		·
0206	614.0905 Crash Cushions Temporary	6.000 EACH		
0208	614.2300 MGS Guardrail 3	558.000 LF	<u></u>	
0210	614.2500 MGS Thrie Beam Transition	118.200 LF	<u> </u>	
0212	614.2610 MGS Guardrail Terminal EAT	5.000 EACH		







Page 8 of 16

Proposal ID: 20200714011 **Project(s):** 9650-17-61, 9650-17-70

Federal ID(s): WISC 2020351, WISC 2020356

SECTION: 0001 Contract Items

Description	Approximate Quantity and Units	Unit Price	Bid Amount
616.0405 Fence Chain Link Salvaged 5-FT	327.000 LF	·	·
618.0100 Maintenance And Repair of Haul Roads project) 01. 9650-17-70	1.000 EACH	·	·
619.1000 Mobilization	1.000 EACH	·	
624.0100 Water	220.000 MGAL	·	·
625.0100 Fopsoil	44,460.000 SY		
627.0200 Mulching	5,654.000 SY		
628.1504 Silt Fence	8,916.000 LF		
628.1520 Silt Fence Maintenance	2,700.000 LF		
628.1905 Mobilizations Erosion Control	15.000 EACH		
628.1910 Mobilizations Emergency Erosion Control	15.000 EACH		
628.2002 Erosion Mat Class I Type A	32,816.000 SY		
628.2006 Erosion Mat Urban Class I Type A	11,784.000 SY		
628.7005 nlet Protection Type A	93.000 EACH		
628.7015 nlet Protection Type C	83.000 EACH	<u> </u>	<u> </u>
628.7020 nlet Protection Type D	2.000 EACH	<u>.</u>	
628.7555 Culvert Pipe Checks	663.000 EACH		
	fence Chain Link Salvaged 5-FT 18.0100 Maintenance And Repair of Haul Roads project) 01. 9650-17-70 19.1000 Mobilization 24.0100 Vater 25.0100 Topsoil 27.0200 Mulching 28.1504 Silt Fence 28.1520 Silt Fence Maintenance 28.1905 Mobilizations Erosion Control 28.1910 Mobilizations Emergency Erosion Control 28.2002 Trosion Mat Class I Type A 28.2006 Trosion Mat Urban Class I Type A 28.7005 The Protection Type C 28.7020 The Protection Type C 28.7020 The Protection Type D 28.7555	tence Chain Link Salvaged 5-FT LF 18.0100 1.000 Alaintenance And Repair of Haul Roads project) 01. 9650-17-70 19.1000 1.000 Aloilization EACH 24.0100 220.000 Water MGAL 25.0100 44,460.000 Alopsoil SY 27.0200 5,654.000 Alulching SY 28.1504 8,916.000 Bilt Fence LF 28.1520 2,700.000 Bilt Fence LF 28.1905 15.000 Aloilizations Erosion Control EACH 28.2002 32,816.000 Aloilizations Emergency Erosion Control EACH 28.2002 32,816.000 Arosion Mat Class I Type A SY 28.7005 93.000 Alet Protection Type A EACH 28.7015 83.000 Alet Protection Type C EACH 28.7020 2.000 Alet Protection Type D EACH 28.7555 663.000	rence Chain Link Salvaged 5-FT



05/13/2020 13:39:10

Page 9 of 16



Proposal Schedule of Items

Proposal ID: 20200714011 **Project(s):** 9650-17-61, 9650-17-70

Federal ID(s): WISC 2020351, WISC 2020356

SECTION: 0001 Contract Items

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0246	629.0210 Fertilizer Type B	28.000 CWT	·	·
0248	630.0120 Seeding Mixture No. 20	98.000 LB		·
0250	630.0130 Seeding Mixture No. 30	196.000 LB	·	·
0252	630.0140 Seeding Mixture No. 40	638.000 LB		
0254	630.0500 Seed Water	115.000 MGAL		
0256	633.5200 Markers Culvert End	10.000 EACH		<u> </u>
0258	634.0616 Posts Wood 4x6-Inch X 16-FT	19.000 EACH		<u> </u>
0260	637.2210 Signs Type II Reflective H	18.000 SF		<u> </u>
0262	637.2230 Signs Type II Reflective F	33.000 SF		<u> </u>
0264	638.2102 Moving Signs Type II	171.000 EACH		<u> </u>
0266	638.2602 Removing Signs Type II	6.000 EACH		<u> </u>
0268	638.3000 Removing Small Sign Supports	5.000 EACH		<u> </u>
0270	642.5001 Field Office Type B	1.000 EACH		<u> </u>
0272	643.0300 Traffic Control Drums	48,896.000 DAY		<u> </u>
0274	643.0420 Traffic Control Barricades Type III	7,679.000 DAY	<u> </u>	<u> </u>
0276	643.0705 Traffic Control Warning Lights Type A	5,400.000 DAY		
0278	643.0715 Traffic Control Warning Lights Type C	4,042.000 DAY	·	



05/13/2020 13:39:10



Proposal Schedule of Items

Page 10 of 16


Proposal ID: 20200714011 **Project(s):** 9650-17-61, 9650-17-70

Federal ID(s): WISC 2020351, WISC 2020356

SECTION: 0001 Contract Items

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0280	643.0900 Traffic Control Signs	98,443.000 DAY		<u> </u>
0282	643.0920 Traffic Control Covering Signs Type II	4.000 EACH	·	<u> </u>
0284	643.1000 Traffic Control Signs Fixed Message	128.000 SF	·	<u> </u>
0286	643.1070 Traffic Control Cones 42-Inch	3,810.000 DAY		·
0288	643.5000 Traffic Control	1.000 EACH		
0290	644.1410 Temporary Pedestrian Surface Asphalt	2,000.000 SF		
0292	644.1601 Temporary Pedestrian Curb Ramp	532.000 DAY		
0294	645.0105 Geotextile Type C	9.000 SY		
0296	645.0120 Geotextile Type HR	309.000 SY		
0298	645.0220 Geogrid Type SR	5,340.000 SY		
0300	646.1020 Marking Line Epoxy 4-Inch	15,884.000 LF		
0302	646.1040 Marking Line Grooved Wet Ref Epoxy 4- Inch	9,490.000 LF	·	·
0304	646.3020 Marking Line Epoxy 8-Inch	199.000 LF		
0306	646.4520 Marking Line Same Day Epoxy 4-Inch	25,950.000 LF		
0308	646.5020 Marking Arrow Epoxy	33.000 EACH		
0310	646.5120 Marking Word Epoxy	1.000 EACH		







Page 11 of 16


Proposal ID: 20200714011 **Project(s):** 9650-17-61, 9650-17-70

Federal ID(s): WISC 2020351, WISC 2020356

SECTION: 0001 Contract Items

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0312	646.5220 Marking Symbol Epoxy	29.000 EACH		
0314	646.6120 Marking Stop Line Epoxy 18-Inch	335.000 LF		
0316	646.6464 Cold Weather Marking Epoxy 4-Inch	25,374.000 LF		
0318	646.6468 Cold Weather Marking Epoxy 8-Inch	199.000 LF		
0320	646.7420 Marking Crosswalk Epoxy Transverse Line 6-Inch	2,063.000 LF		·
0322	646.7520 Marking Crosswalk Epoxy Block Style 24-Inch	444.000 LF		·
0324	646.9000 Marking Removal Line 4-Inch	4,658.000 LF		
0326	648.0100 Locating No-Passing Zones	0.820 MI		
0328	649.0105 Temporary Marking Line Paint 4-Inch	10,279.000 LF		·
0330	649.0150 Temporary Marking Line Removable Tape 4-Inch	13,902.000 LF	<u>-</u>	·
0332	649.0250 Temporary Marking Line Removable Tape 8-Inch	828.000 LF	:	·
0334	649.0850 Temporary Marking Stop Line Removable Tape 18-Inch	123.000 LF	·	·
0336	650.4000 Construction Staking Storm Sewer	126.000 EACH		
0338	650.4500 Construction Staking Subgrade	13,980.000 LF		
0340	650.5000 Construction Staking Base	13,980.000 LF	·	







Page 12 of 16


Proposal ID: 20200714011 **Project(s):** 9650-17-61, 9650-17-70

Federal ID(s): WISC 2020351, WISC 2020356

SECTION: 0001 Contract Items

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0342	650.5500 Construction Staking Curb Gutter and Curb & Gutter	18,916.000 LF		·
0344	650.6000 Construction Staking Pipe Culverts	8.000 EACH		<u> </u>
0346	650.6500 Construction Staking Structure Layout (structure) 01. C-73-0004	LS	LUMP SUM	
0348	650.8000 Construction Staking Resurfacing Reference	12,817.000 LF		·
0350	650.8500 Construction Staking Electrical Installations (project) 01. 9650-17-70	LS	LUMP SUM	·
0352	650.9000 Construction Staking Curb Ramps	45.000 EACH		
0354	650.9910 Construction Staking Supplemental Control (project) 01. 9650-17-70	LS	LUMP SUM	·
0356	650.9920 Construction Staking Slope Stakes	13,980.000 LF		
0358	652.0225 Conduit Rigid Nonmetallic Schedule 40 2-Inch	13,908.000 LF	:	·
0360	652.0235 Conduit Rigid Nonmetallic Schedule 40 3-Inch	599.000 LF	·	·
0362	653.0164 Pull Boxes Non-Conductive 24x42-Inch	30.000 EACH		·
0364	654.0101 Concrete Bases Type 1	2.000 EACH		
0366	654.0105 Concrete Bases Type 5	78.000 EACH		
0368	654.0230 Concrete Control Cabinet Bases Type L30	5.000 EACH		·
0370	655.0610 Electrical Wire Lighting 12 AWG	10,680.000 LF	·	







Page 13 of 16


Proposal ID: 20200714011 **Project(s):** 9650-17-61, 9650-17-70

Federal ID(s): WISC 2020351, WISC 2020356

SECTION: 0001 Contract Items

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0372	655.0620 Electrical Wire Lighting 8 AWG	72,305.000 LF		<u> </u>
0374	655.0630 Electrical Wire Lighting 4 AWG	10,330.000 LF	·	<u> </u>
0376	655.0635 Electrical Wire Lighting 2 AWG	2,782.000 LF	<u></u>	
0378	656.0200 Electrical Service Meter Breaker Pedestal (location) 01. STH 47 & Warrington Road	LS	LUMP SUM	
0380	656.0200 Electrical Service Meter Breaker Pedestal (location) 02. STH 47 & Tribal Office Loop	LS	LUMP SUM	
0382	656.0200 Electrical Service Meter Breaker Pedestal (location) 03. STH 47 & Lyons Road	LS	LUMP SUM	<u> </u>
0384	656.0200 Electrical Service Meter Breaker Pedestal (location) 04. STH 47 & STH 55	LS	LUMP SUM	·
0386	656.0200 Electrical Service Meter Breaker Pedestal (location) 05. STH 47 & Wolf River Dr	LS	LUMP SUM	<u> </u>
0388	657.0100 Pedestal Bases	2.000 EACH	<u></u>	
0390	657.0255 Transformer Bases Breakaway 11 1/2- Inch Bolt Circle	78.000 EACH		<u> </u>
0392	657.0322 Poles Type 5-Aluminum	56.000 EACH	<u> </u>	
0394	657.0420 Traffic Signal Standards Aluminum 13-FT	2.000 EACH	·	
0396	657.0615 Luminaire Arms Single Member 4 1/2- Inch Clamp 8-FT	78.000 EACH	·	
0398	658.0500 Pedestrian Push Buttons	2.000 EACH		







Page 14 of 16


Proposal ID: 20200714011 **Project(s):** 9650-17-61, 9650-17-70

Federal ID(s): WISC 2020351, WISC 2020356

SECTION: 0001 Contract Items

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0400	659.1120 Luminaires Utility LED B	78.000 EACH		
0402	659.2130 Lighting Control Cabinets 120/240 30- Inch	2.000 EACH	·	<u>·</u>
0404	661.0100 Temporary Traffic Signals for Bridges (structure) 01. B-73-0004	LS	LUMP SUM	·
0406	661.0100 Temporary Traffic Signals for Bridges (structure) 02. C-73-0004	LS	LUMP SUM	·-
0408	661.0100 Temporary Traffic Signals for Bridges (structure) 03. Culvert STA. 175+75	LS	LUMP SUM	·
0410	661.0100 Temporary Traffic Signals for Bridges (structure) 04. Culvert STA. 200+35	LS	LUMP SUM	·
0412	690.0150 Sawing Asphalt	26,462.000 LF		·
0414	690.0250 Sawing Concrete	147.000 LF		·
0416	715.0415 Incentive Strength Concrete Pavement	500.000 DOL	1.00000	500.00
0418	715.0502 Incentive Strength Concrete Structures	500.000 DOL	1.00000	500.00
0420	740.0440 Incentive IRI Ride	21,340.000 DOL	1.00000	21,340.00
0422	SPV.0060 Special 01. Salvage Existing Light Pole Assembly	13.000 EACH	·	<u> </u>
0424	SPV.0060 Special 02. Light Pole Type 5 Special	22.000 EACH	<u> </u>	
0426	SPV.0060 Special 03. Lighting Control Cabinet 120/240 30-Inch Special	3.000 EACH		:
0428	SPV.0060 Special 04. Lane Shift	5.000 EACH		,







Page 15 of 16

Proposal ID: 20200714011 **Project(s):** 9650-17-61, 9650-17-70

Federal ID(s): WISC 2020351, WISC 2020356

SECTION: 0001 Contract Items

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0430	SPV.0060 Special 05. Sanitary Chimney Seals	32.000 EACH		
0432	SPV.0060 Special 06. Removing Water Main Valve & Valve Box	2.000 EACH	.	.
0434	SPV.0060 Special 07. Cap Water Main to Remain in Service	1.000 EACH		.
0436	SPV.0060 Special 08. Abandoning Water Main Valve Box	8.000 EACH		.
0438	SPV.0060 Special 09. Salvage Hydrant	3.000 EACH		
0440	SPV.0060 Special 10. Adjusting Water Main Valve Box	23.000 EACH		·
0442	SPV.0060 Special 11. Adjusting Hydrant	5.000 EACH		
0444	SPV.0060 Special 12. Water Main Gate Valve & Box 6-Inch	4.000 EACH	·	
0446	SPV.0060 Special 13. Tracer Wire Access Box	3.000 EACH		
0448	SPV.0060 Special 14. Water Main Coupling 6-Inch	1.000 EACH		
0450	SPV.0060 Special 15. Water Main Bend 45-Degree 6-Inch	12.000 EACH		·
0452	SPV.0060 Special 16. Water Main Tapping Sleeve 6x6-Inch	1.000 EACH		·
0454	SPV.0060 Special 17. Steel Plate Beam Guard Connection	1.000 EACH		·
0456	SPV.0090 Special 01. Concrete Curb & Gutter 24- Inch Type D	18,861.000 LF		



Wisconsin Department of Transportation

05/13/2020 13:39:10

Proposal Schedule of Items

Page 16 of 16

Proposal ID: 20200714011 **Project(s):** 9650-17-61, 9650-17-70

Federal ID(s): WISC 2020351, WISC 2020356

SECTION: 0001 Contract Items

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0458	SPV.0090 Special 02. Water Main 6-Inch	29.000 LF	<u> </u>	
0460	SPV.0090 Special 03. Construction Staking Sidewalk	2,200.000 LF	·	
0462	SPV.0105 Special 01. Rectangular Rapid Flashing Beacon System STH 47 & Warrington Road	LS	LUMP SUM	
0464	SPV.0105 Special 02. Temporary Stream Diversion Pipe, Keshena Lake Outlet	LS	LUMP SUM	
0466	SPV.0180 Special 01. Preparing Topsoil for Lawn Type Turf	27,920.000 SY	·	<u> </u>
	Section: 000	1	Total:	·
			Total Bid:	

PLEASE ATTACH SCHEDULE OF ITEMS HERE



Wisconsin Department of Transportation

July 7, 2020

Division of Transportation Systems Development

Bureau of Project Development 4822 Madison Yards Way, 4th Floor South Madison, WI 53705

Telephone: (608) 266-1631 Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

Federal Wage Rate Addendum #01

Letting of July 14, 2020

Attached is a copy of the revised WI 10 Highway Davis Bacon Prevailing Wage Rates that are included in proposals 01 - 05, 08, 09, and 11 - 13; and WI 15 Heavy Davis Bacon Prevailing Wage Rates that are included in proposals 02 and 08. These wage rates are effective for all proposals they are included in in the July 14, 2020 letting. The updated wage rates for WI10 are dated June 19, 2020 and are effective on or after June 29, 2020. The updated wage rates for WI 15 are dated July 3, 2020 and are effective on or after July 13, 2020.

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractors.

Sincerely,

Mike Coleman

Proposal Development Specialist Proposal Management Section

"General Decision Number: WI20200010 06/19/2020

Superseded General Decision Number: WI20190010

State: Wisconsin

Construction Type: Highway

Counties: Wisconsin Statewide.

HIGHWAY, AIRPORT RUNWAY & TAXIWAY CONSTRUCTION PROJECTS (does not include bridges over navigable waters; tunnels; buildings in highway rest areas; and railroad construction)

Note: Under Executive Order (EO) 13658, an hourly minimum wage of \$10.80 for calendar year 2020 applies to all contracts subject to the Davis-Bacon Act for which the contract is awarded (and any solicitation was issued) on or after January 1, 2015. If this contract is covered by the EO, the contractor must pay all workers in any classification listed on this wage determination at least \$10.80 per hour (or the applicable wage rate listed on this wage determination, if it is higher) for all hours spent performing on the contract in calendar year 2020. If this contract is covered by the EO and a classification considered necessary for performance of work on the contract does not appear on this wage determination, the contractor must pay workers in that classification at least the wage rate determined through the conformance process set forth in 29 CFR 5.5(a)(1)(ii) (or the EO minimum wage rate, if it is higher than the conformed wage rate). The EO minimum wage rate will be adjusted annually. Please note that this EO applies to the above-mentioned types of contracts entered into by the federal government that are subject to the Davis-Bacon Act itself, but it does not apply to contracts subject only to the Davis-Bacon Related Acts, including those set forth at 29 CFR 5.1(a)(2)-(60). Additional information on contractor requirements and worker protections under the EO is available at www.dol.gov/whd/govcontracts.

Modification	Number	Publication	Date
0		01/03/2020	
1		01/24/2020	
2		02/28/2020	
3		03/06/2020	
4		06/05/2020	
5		06/12/2020	
6		06/19/2020	

BRWI0001-002 06/03/2019

CRAWFORD, JACKSON, JUNEAU, LA CROSSE, MONROE, TREMPEALEAU, AND VERNON COUNTIES

	Rates	Fringes
BRICKLAYER	.\$ 33.80	24.28
BRWI0002-002 06/01/2019		
ASHLAND, BAYFIELD, DOUGLAS, AND	IRON COUNTIES	
	Rates	Fringes
BRICKLAYER	.\$ 39.94	23.30
BRWI0002-005 06/01/2019		
ADAMS, ASHLAND, BARRON, BROWN, BUCLARK, COLUMBIA, DODGE, DOOR, DUIFOREST, GREEN LAKE, IRON, JEFFERS LINCOLN, MANITOWOC, MARATHON, MAIOCONTO, ONEIDA, OUTAGAMIE, POLK, SHAWANO, SHEBOYGAN, TAYLOR, VILAS WINNEBAGO, AND WOOD COUNTIES	NN, FLORENCE, FO SON, KEWAUNEE, L RINETTE, MARQUET PORTAGE, RUSK,	ND DU LAC, ANGLADE, TE, MENOMINEE, ST CROIX, SAUK,
	Rates	Fringes
CEMENT MASON/CONCRETE FINISHER	.\$ 35.51	23.37
BRWI0003-002 06/03/2019		
BROWN, DOOR, FLORENCE, KEWAUNEE,	MARINETTE, AND	OCONTO COUNTIES
	Rates	Fringes
BRICKLAYER		
BRWI0004-002 06/01/2019		
KENOSHA, RACINE, AND WALWORTH COL	JNTIES	
	Rates	Fringes
BRICKLAYER	.\$ 38.43	25.10
BRWI0006-002 06/01/2019		

ADAMS, CLARK, FOREST, LANGLADE, LINCOLN, MARATHON, MENOMINEE, ONEIDA, PORTAGE, PRICE, TAYLOR, VILAS AND WOOD COUNTIES

Rates	Fringes
•	23.02
IES	
Rates	Fringes
\$ 35.57	24.22
AND WAUKESHA COU	NTIES
Rates	Fringes
	24.22
AND SHEBOYGAN C	OUNTIES
Rates	Fringes
•	23.90
•	
Rates	Fringes
•	24.68
Rates	Fringes
\$ 35.56	24.23
	AND WAUKESHA COURates AND SHEBOYGAN CRATES AND SHEB

CARP0087-001 05/01/2016

BURNETT (W. of Hwy 48), PIERCE (W. of Hwy 29), POLK (W. of Hwys 35, 48 & 65), AND ST. CROIX (W. of Hwy 65) COUNTIES

	Rates	Fringes
Carpenter & Piledrivermen	.\$ 36.85	18.39
CARP0252-002 06/01/2016		

ADAMS, BARRON, BAYFIELD (Eastern 2/3), BROWN, BUFFALO, BURNETT (E. of Hwy 48), CALUMET, CHIPPEWA, CLARK, COLUMBIA, CRAWFORD, DANE, DODGE, DOOR, DUNN, EAU CLAIRE, FLORENCE (except area bordering Michigan State Line), FOND DU LAC, FOREST, GRANT, GREEN, GREEN LAKE, IOWA, IRON, JACKSON, JEFFERSON, JUNEAU, KEWAUNEE, LA CROSSE, LAFAYETTE, LANGLADE, LINCOLN, MANITOWOC, MARATHON, MARINETTE (except N.E. corner), MARQUETTE, MENOMINEE, MONROE, OCONTO, ONEIDA, OUTAGAMIE, PEPIN, PIERCE (E. of Hwys 29 & 65), POLK (E. of Hwys 35, 48 & 65), PORTAGE, PRICE, RICHLAND, ROCK, RUSK, SAUK, SAWYER, SHAWANO, SHEBOYGAN, ST CROIX (E. of Hwy 65), TAYLOR, TREMPEALEAU, VERNON, VILAS, WALWORTH, WASHBURN, WAUPACA, WAUSHARA, WINNEBAGO, AND WOOD COUNTIES

	Rates	Fringes	
CARPENTER			
CARPENTER	\$ 33.56	18.00	
MILLWRIGHT	\$ 35.08	18.35	
PILEDRIVER	\$ 34.12	18.00	

CARP0252-010 06/01/2016

ASHLAND COUNTY

	Rates	Fringes
Carpenters		
Carpenter	\$ 33.56	18.00
Millwright	\$ 35.08	18.35
Pile Driver	\$ 34.12	18.00

CARP0264-003 06/01/2016

KENOSHA, MILWAUKEE, OZAUKEE, RACINE, WAUKESHA, AND WASHINGTON COUNTIES

	Rates	Fringes
CARPENTER	\$ 35.78	22.11
CARP0361-004 05/01/2018		

BAYFIELD (West of Hwy 63) AND DOUGLAS COUNTIES

	Rates	Fringes
CARPENTER	\$ 36.15	20.43
CARP2337-001 06/01/2016		

ZONE A: MILWAUKEE, OZAUKEE, WAUKESHA AND WASHINGTON

ZONE B: KENOSHA & RACINE

	Rates	Fringes	
PILEDRIVERMAN			
Zone A	\$ 31.03	22.69	
Zone B	\$ 31.03	22.69	

ELEC0014-002 06/03/2019

ASHLAND, BARRON, BAYFIELD, BUFFALO, BURNETT, CHIPPEWA, CLARK (except Maryville, Colby, Unity, Sherman, Fremont, Lynn & Sherwood), CRAWFORD, DUNN, EAU CLAIRE, GRANT, IRON, JACKSON, LA CROSSE, MONROE, PEPIN, PIERCE, POLK, PRICE, RICHLAND, RUSK, ST CROIX, SAWYER, TAYLOR, TREMPEALEAU, VERNON, AND WASHBURN COUNTIES

	Rates	Fringes
Electricians:	\$ 35.59	20.87
ELEC0014-007 06/03/2019		

REMAINING COUNTIES

K	Rates	Fringes
Teledata System Installer		
<pre>Installer/Technician\$</pre>	27.25	14.34

Low voltage construction, installation, maintenance and

removal of teledata facilities (voice, data, and video) including outside plant, telephone and data inside wire, interconnect, terminal equipment, central offices, PABX, fiber optic cable and equipment, micro waves, V-SAT, bypass, CATV, WAN (wide area networks), LAN (local area networks), and ISDN (integrated systems digital network).

ELEC0127-002 06/01/2020

KENOSHA COUNTY

Rates Fringes

Electricians:.....\$ 41.62 30%+12.70

ELEC0158-002 06/03/2019

BROWN, DOOR, KEWAUNEE, MANITOWOC (except Schleswig), MARINETTE(Wausuakee and area South thereof), OCONTO, MENOMINEE (East of a ine 6 miles West of the West boundary of Oconto County), SHAWANO (Except Area North of Townships of Aniwa and Hutchins) COUNTIES

COLUMBIA, DANE, DODGE (Area West of Hwy 26, except Chester and Emmet Townships), GREEN, LAKE (except Townships of Berlin, Seneca, and St. Marie), IOWA, MARQUETTE (except Townships of Neshkoka, Crystal Lake, Newton, and Springfield), and SAUK COUNTIES

FLORENCE COUNTY (Townships of Aurora, Commonwealth, Fern, Florence and Homestead) AND MARINETTE COUNTY (Township of Niagara)

Rates Fringes

Elect	tri	сi	an	S	:
	C 1	~~	+ 0	. :	,

Electrical contracts over

\$180,000.....\$ 32.38 18.63

Electrical contracts under

\$180,000.....\$ 30.18 18.42

ELEC0242-005 05/16/2018

DOUGLAS COUNTY

Rates Fringes

Electricians:.....\$ 36.85 26.17

ELEC0388-002 06/03/2019

ADAMS, CLARK (Colby, Freemont, Lynn, Mayville, Sherman, Sherwood, Unity), FOREST, JUNEAU, LANGLADE, LINCOLN, MARATHON, MARINETTE (Beecher, Dunbar, Goodman & Pembine), MENOMINEE (Area West of a line 6 miles West of the West boundary of Oconto County), ONEIDA, PORTAGE, SHAWANO (Aniwa and Hutchins), VILAS AND WOOD COUNTIES

Rates	Fringes
-------	---------

Electricians:.....\$ 33.56 26%+11.01

* ELEC0430-002 06/01/2020

RACINE COUNTY (Except Burlington Township)

Rates Fringes

Electricians:.....\$ 41.86 22.66

MILWAUKEE, OZAUKEE, WASHINGTON, AND WAUKESHA COUNTIES

Rates Fringes

Electricians:.....\$ 42.84 25.54

CALUMET (Township of New Holstein), DODGE (East of Hwy 26 including Chester Township), FOND DU LAC, MANITOWOC (Schleswig), and SHEBOYGAN COUNTIES

^{*} ELEC0494-005 06/01/2020

^{*} ELEC0494-006 06/01/2020

	Rates	Fringes
Electricians:	\$ 36.32	22.51
ELEC0494-013 06/01/2019		

DODGE (East of Hwy 26 including Chester Twp, excluding Emmet Twp), FOND DU LAC (Except Waupuin), MILWAUKEE, OZAUKEE, MANITOWOC (Schleswig), WASHINGTON, AND WAUKESHA COUNTIES

	Rates	Fringes
Sound & Communications		
Installer	\$ 20.53	18.13
Technician	\$ 30.18	19.58

Installation, testing, maintenance, operation and servicing of all sound, intercom, telephone interconnect, closed circuit TV systems, radio systems, background music systems, language laboratories, electronic carillion, antenna distribution systems, clock and program systems and low-voltage systems such as visual nurse call, audio/visual nurse call systems, doctors entrance register systems. Includes all wire and cable carrying audio, visual, data, light and radio frequency signals. Includes the installation of conduit, wiremold, or raceways in existing structures that have been occupied for six months or more where required for the protection of the wire or cable, but does not mean a complete conduit or raceway system. work covered does not include the installation of conduit, wiremold or any raceways in any new construction, or the installation of power supply outlets by means of which external electric power is supplied to any of the foregoing equipment or products

ELEC0577-003 06/01/2019

CALUMET (except Township of New Holstein), GREEN LAKE (N. part including Townships of Berlin, St Marie, and Seneca), MARQUETTE (N. part including Townships of Crystal Lake, Neshkoro, Newton, and Springfield), OUTAGAMIE, WAUPACA, WAUSHARA, AND WINNEBAGO COUNTIES

Rates Fringes

Electricians:	.\$ 33.15	28.50%+10.00

ELEC0890-003 06/01/2020

DODGE (Emmet Township only), GREEN, JEFFERSON, LAFAYETTE, RACINE (Burlington Township), ROCK AND WALWORTH COUNTIES

	Rates	Fringes
Electricians:	\$ 37.41	25.95%+11.11
ELEC0953-001 06/02/2019		

	F	Rates	Fringes
(2) Heavy E Operator (3) Equipme (4) Heavy (on:	47.53 42.78 38.02 33.27	21.43 19.80 18.40 16.88 16.11
(6) Grounds	sman\$	26.14	14.60

ENGI0139-005 06/01/2020

	Rates	Fringes
Power Equipment Operator		
Group 1	41.62	23.80
Group 2	41.12	23.80
Group 3	40.62	23.80
Group 4	40.36	23.80
Group 5	40.07	23.80
Group 6	34.17	23.80

HAZARDOUS WASTE PREMIUMS:

EPA Level ""A"" protection - \$3.00 per hour EPA Level ""B"" protection - \$2.00 per hour EPA Level ""C"" protection - \$1.00 per hour

POWER EQUIPMENT OPERATORS CLASSIFICATIONS

GROUP 1: Cranes, tower cranes, and derricks with or without attachments with a lifting capacity of over 100 tons; or cranes, tower cranes, and derricks with boom, leads and/or jib lengths measuring 176 feet or longer.

GROUP 2: Cranes, tower cranes and derricks with or without

attachments with a lifting capacity of 100 tons or less; or cranes, tower cranes, and derricks with boom, leads, and/or jibs lengths measuring 175 feet or under and Backhoes (excavators) weighing 130,000 lbs and over; caisson rigs; pile driver; dredge operator; dredge engineer; Boat Pilot.

GROUP 3: Mechanic or welder - Heavy duty equipment; cranes with a lifting capacity of 25 tons or under; concrete breaker (manual or remote); vibratory/sonic concrete breaker; concrete laser screed; concrete slipform paver; concrete batch plant operator; concrete pvt. spreader heavy duty (rubber tired); concrete spreader & distributor; automatic subgrader (concrete); concrete grinder & planing machine; concrete slipform curb & gutter machine; slipform concrete placer; tube finisher; hydro blaster (10,000 psi & over); bridge paver; concrete conveyor system; concrete pump; Rotec type Conveyor; stabilizing mixer (self-propelled); shoulder widener; asphalt plant engineer; bituminious paver; bump cutter & grooving machine; milling machine; screed (bituminous paver); asphalt heater, planer & scarifier; Backhoes (excavators) weighing under 130,000 lbs; grader or motor patrol; tractor (scraper, dozer, pusher, loader); scraper - rubber tired (single or twin engine); endloader; hydraulic backhoe (tractor type); trenching machine; skid rigs; tractor, side boom (heavy); drilling or boring machine (mechanical heavy); roller over 5 tons; percussion or rotary drilling machine; air track; blaster; loading machine (conveyor); tugger; boatmen; winches & A-frames; post driver; material hoist.

GROUP 4: Greaser, roller steel (5 tons or less); roller (pneumatic tired) - self propelled; tractor (mounted or towed compactors & light equipment); shouldering machine; self- propelled chip spreader; concrete spreader; finishing machine; mechanical float; curing machine; power subgrader; joint sawer (multiple blade) belting machine; burlap machine; texturing machine; tractor endloader (rubber tired) - light; jeep digger; forklift; mulcher; launch operator; fireman, environmental burner

GROUP 5: Air compressor; power pack; vibrator hammer and extractor; heavy equipment, leadman; tank car heaters; stump chipper; curb machine operator; Concrete proportioning plants; generators; mudjack operator; rock breaker; crusher or screening plant; screed (milling machine); automatic belt conveyor and surge bin; pug mill operator; Oiler, pump (over 3 inches); Drilling Machine Tender.

GROUP 6: Off-road material hauler with or without ejector.

* IRON0008-002 06/01/2020

BROWN, CALUMET, DOOR, FOND DU LAC, KEWAUNEE, MANITOWOC, MARINETTE, OCONTO, OUTAGAMI, SHAWANO, SHEBOYGAN, AND WINNEBAGO COUNTIES:

Rates Fringes

IRONWORKER.....\$ 37.31 27.62

Paid Holidays: New Year's Day, Memorial Day, July 4th, Labor Day, Thanksgiving Day & Christmas Day.

* IRON0008-003 06/01/2020

KENOSHA, MILWAUKEE, OZAUKEE, RACINE, WALWORTH (N.E. 2/3), WASHINGTON, AND WAUKESHA COUNTIES

Rates Fringes

IRONWORKER.....\$ 39.11 27.87

Paid Holidays: New Year's Day, Memorial Day, July 4th, Labor Day, Thanksgiving Day & Christmas Day.

ADAMS, COLUMBIA, CRAWFORD, DANE, DODGE, FLORENCE, FOREST, GRANT, GREENE, (Excluding S.E. tip), GREEN LAKE, IOWA, JEFFERSON, JUNEAU, LA CROSSE, LAFAYETTE, LANGLADE, MARATHON, MARQUETTE, MENOMINEE, MONROE, PORTAGE, RICHLAND, ROCK (Northern area, vicinity of Edgerton and Milton), SAUK, VERNON, WAUPACA, WAUSHARA, AND WOOD COUNTIES

	Rates	Fringes
IRONWORKER	.\$ 37.10	27.06

IRON0498-005 06/01/2019

GREEN (S.E. 1/3), ROCK (South of Edgerton and Milton), and WALWORTH (S.W. 1/3) COUNTIES:

^{*} IRON0383-001 06/01/2020

	Rates	Fringes	
IRONWORKER	\$ 40.25	40.53	

IRON0512-008 06/03/2019

BARRON, BUFFALO, CHIPPEWA, CLARK, DUNN, EAU CLAIRE, JACKSON, PEPIN, PIERCE, POLK, RUSK, ST CROIX, TAYLOR, AND TREMPEALEAU COUNTIES

	Rates	Fringes	
IRONWORKER	\$ 37.60	29.40	
TROUGHA 004 06 /02 /0240			_

IRON0512-021 06/03/2019

ASHLAND, BAYFIELD, BURNETT, DOUGLAS, IRON, LINCOLN, ONEIDA, PRICE, SAWYER, VILAS AND WASHBURN COUNTIES

	Rates	Fringes
IRONWORKER	\$ 33.19	29.40
LAB00113-002 06/03/2019		

MILWAUKEE AND WAUKESHA COUNTIES

	F	Rates	Fringes
LABORER			
Group	1\$	29.02	21.92
Group	2\$	29.17	21.92
Group	3\$	29.37	21.92
Group	4\$	29.52	21.92
Group	5\$	29.67	21.92
Group	6\$	25.51	21.92

LABORERS CLASSIFICATIONS

GROUP 1: General Laborer; Tree Trimmer; Conduit Layer; Demolition and Wrecking Laborer; Guard Rail, Fence, and Bridge Builder; Landscaper; Multiplate Culvert Assembler; Stone Handler; Bituminous Worker (Shoveler, Loader, and Utility Man); Batch Truck Dumper or Cement Handler; Bituminous Worker (Dumper, Ironer, Smoother, and Tamper); Concrete Handler

GROUP 2: Air Tool Operator; Joint Sawer and Filler (Pavement); Vibrator or Tamper Operator (Mechanical Hand Operated); Chain Saw Operator; Demolition Burning Torch Laborer

GROUP 3: Bituminous Worker (Raker and Luteman); Formsetter (Curb, Sidewalk, and Pavement); Strike Off Man

GROUP 4: Line and Grade Specialist

GROUP 5: Blaster and Powderman

GROUP 6: Flagperson; traffic control person

LAB00113-003 06/03/2019

OZAUKEE AND WASHINGTON COUNTIES

	Rat	tes	Fringes
LABORER			
Group	1\$ 28	3.27	21.92
Group	2\$ 28	3.37	21.92
Group	3\$ 28	3.42	21.92
Group	4\$ 28	3.62	21.92
Group	5\$ 28	3.47	21.92
Group	6\$ 25	5.36	21.92

LABORERS CLASSIFICATIONS

GROUP 1: General Laborer; Tree Trimmer; Conduit Layer; Demolition and Wrecking Laborer; Guard Rail, Fence, and Bridge Builder; Landscaper; Multiplate Culvert Assembler; Stone Handler; Bituminous Worker (Shoveler, Loader, and Utility Man); Batch Truck Dumper or Cement Handler; Bituminous Worker (Dumper, Ironer, Smoother, and Tamper); Concrete Handler

GROUP 2: Air Tool Operator; Joint Sawer and Filler (Pavement); Vibrator or Tamper Operator (Mechanical Hand Operated);

GROUP 3: Bituminous Worker (Raker and Luteman); Formsetter (Curb, Sidewalk, and Pavement); Strike Off Man

GROUP 4: Line and Grade Specialist

GROUP 5: Blaster; powderman

GROUP 6: Flagperson and Traffic Control Person

LAB00113-011 06/03/2019

KENOSHA AND RACINE COUNTIES

	F	Rates	Fringes
LABORER			
Group	1\$	28.08	21.92
Group	2\$	28.23	21.92
Group	3\$	28.43	21.92
Group 4	4\$	28.40	21.92
Group	5\$	28.73	21.92
Group	6\$	25.22	21.92

LABORERS CLASSIFICATIONS:

GROUP 1: General laborer; Tree Trimmer; Conduit Layer; Demolition and Wrecking Laborer; Guard Rail, Fence, and Bridge Builder; Landscaper; Multiplate Culvert Assembler; Stone Handler; Bituminous Worker (Shoveler, Loader, and Utility Man); Batch Truck Dumper or Cement Handler; Bituminous worker (Dumper, Ironer, Smoother, and Tamper); Concrete Handler

GROUP 2: Air Tool Operator; Joint Sawer and Filler (Pavement); Vibrator or Tamper Operator (Mechanical Hand Operated); Chain Saw Operator; Demolition Burning Torch Laborer

GROUP 3: Bituminous Worker (Raker and Luteman); Formsetter (Curb, Sidewalk, and Pavement); Strike Off Man

GROUP 4: Line and Grade Specialist

GROUP 5: Blaster and Powderman

GROUP 6: Flagman; traffic control person

LAB00140-002 06/03/2019

ADAMS, ASHLAND, BARRON, BAYFIELD, BROWN, BUFFALO, BURNETT, CALUMET, CHIPPEWA, CLARK, COLUMBIA, CRAWFORD, DODGE, DOOR, DOUGLAS, DUNN, EAU CLAIRE, FLORENCE, FOND DU LAC, FOREST, GRANT, GREEN, GREEN LAKE, IRON, JACKSON, JUNEAU, IOWA, JEFFERSON, KEWAUNEE, LA CROSSE, LAFAYETTE, LANGLADE, LINCOLN, MANITOWOC, MARATHON, MARINETTE, MARQUETTE, MENOMINEE, MONROE,

OCONTO, ONEIDA, OUTAGAMIE, PEPIN, PIERCE, POLK, PORTAGE, PRICE, RICHLAND, ROCK, RUSK, SAUK, SAWYER, SHAWANO, SHEBOYGAN, ST. CROIX, TAYLOR, TREMPEALEAU, VERNON, VILLAS, WALWORTH, WASHBURN, WAUPACA, WAUSHARA, WINNEBAGO, AND WOOD COUNTIES

	1	Rates	Fringes
LABORER			
Group	1\$	32.84	17.54
Group	2\$	32.94	17.54
Group	3\$	32.99	17.54
Group	4\$	33.19	17.54
Group	5\$	33.04	17.54
Group	6\$	29.47	17.54

LABORER CLASSIFICATIONS

GROUP 1: General Laborer; Tree Trimmer; Conduit Layer; Demolition and Wrecking Laborer; Guard Rail, Fence, and Bridge Builder; Landscaper; Multiplate Culvert Assembler; Stone Handler; Bitminous Worker (Shoveler, Loader, and Utility Man); Batch Truck Dumper or Cement Handler; Bituminous Worker (Dumper, Ironer, Smoother and Tamper); Concrete Handler

GROUP 2: Air Tool Operator; Joint Sawer and Filler (Pavement); Vibrator or Tamper Operator (Mechanical Hand Operated); Chain Saw Operator, Demolition Burning Torch Laborer

GROUP 3: Bituminous Worker (Raker and Luteman); Formsetter (Curb, Sidewalk and Pavement); Strike Off Man

GROUP 4: Line and Grade Secialist

GROUP 5: Blaster; powderman

GROUP 6: Flagperson; Traffic Control

LABO0464-003 06/03/2019

DANE COUNTY

	Rates	Fringes
LABORER		
Group	1\$ 33.12	17.54
Group	2\$ 33.22	17.54

Group 3\$ 33.27	17.54
Group 4\$ 33.47	17.54
Group 5\$ 33.32	17.54
Group 6\$ 29.47	17.54

LABORERS CLASSIFICATIONS:

GROUP 1: General Laborer; Tree Trimmer; Conduit Layer; Demolition and Wrecking Laborer; Guard Rail, Fence, and Bridge Builder; Landscaper; Multiplate Culvert Assembler; Stone Handler; Bituminous Worker (Shoveler, Loader, and Utility Man); Batch Truck Dumper or Cement Handler; Bituminious Worker (Dumper, Ironer, Smoother, and Tamper); Concrete Handler

GROUP 2: Air Tool Operator; Joint Sawer and Filler (Pavement); Vibrator or Tamper Operator (Mechanical Hand Operated); Chain Saw Operator; Demolition Burning Torch Laborer

GROUP 3: Bituminous Worker (Raker and Luteman); Formsetter (Curb, Sidewalk, and Pavement); Strike Off Man

GROUP 4: Line and Grade Specialist

GROUP 5: Blaster; Powderman

GROUP 6: Flagperson and Traffic Control Person

PAIN0106-008 05/01/2017

ASHLAND, BAYFIELD, BURNETT, AND DOUGLAS COUNTIES

	F	Rates	Fringes
Painters:			
New:			
Brush,	Roller\$	30.33	17.27
Spray,	Sandblast, Steel\$	30.93	17.27
Repaint	• •		
Brush,	Roller\$	28.83	17.27
Spray,	Sandblast, Steel\$	29.43	17.27

PAIN0108-002 06/01/2019

RACINE COUNTY

Rates Fringes

Painters:	
-----------	--

Brush, Roller\$	36.08	20.36
Spray & Sandblast\$	37.08	20.36

PAIN0259-002 05/01/2008

BARRON, CHIPPEWA, DUNN, EAU CLAIRE, PEPIN, PIERCE, POLK, RUSK, SAWYER, ST. CROIX, AND WASHBURN COUNTIES

	Rates	Fringes
PAINTER	\$ 24.11	12.15
PAIN0259-004 05/01/2015		

BUFFALO, CRAWFORD, JACKSON, LA CROSSE, MONROE, TREMPEALEAU, AND VERNON COUNTIES

	Rates	Fringes
PAINTER	\$ 22.03	12.45
PAIN0781-002 06/01/2019		

JEFFERSON, MILWAUKEE, OZAUKEE, WASHINGTON, AND WAUKESHA COUNTIES

R	Rates	Fringes
Painters:		
Bridge\$	33.30	23.86
Brush\$	32.95	23.86
Spray & Sandblast\$	33.70	23.86

PAIN0802-002 06/01/2019

COLUMBIA, DANE, DODGE, GRANT, GREEN, IOWA, LAFAYETTE, RICHLAND, ROCK, AND SAUK COUNTIES

	Rates	Fringes
PAINTER		
Brush	\$ 30.93	18.44

PREMIUM PAY:

Structural Steel, Spray, Bridges = \$1.00 additional per hour.

PAIN0802-003 06/01/2019

ADAMS, BROWN, CALUMET, CLARK, DOOR, FOND DU LAC, FOREST, GREEN LAKE, IRON, JUNEAU, KEWAUNEE, LANGLADE, LINCOLN, MANITOWOC, MARATHON, MARINETTE, MARQUETTE, MENOMINEE, OCONTO, ONEIDA, OUTAGAMIE, PORTAGE, PRICE, SHAWANO, SHEBOYGAN, TAYLOR, VILAS, WAUSHARA, WAUPACA, WINNEBAGO, AND WOOD COUNTIES

	Rates	Fringes
PAINTER	.\$ 30.93	18.58
PAIN0934-001 06/01/2017		
KENOSHA AND WALWORTH COUNTIES		
	Rates	Fringes
Painters: Brush	.\$ 34.74	18.95 18.95 18.95
PAIN1011-002 06/02/2019		
FLORENCE COUNTY		
	Rates	Fringes
Painters:	.\$ 25.76	13.33
PLAS0599-010 06/01/2017		
	Rates	Fringes
CEMENT MASON/CONCRETE FINISHER Area 1	.\$ 35.07 .\$ 35.61 .\$ 34.70 .\$ 36.27	17.17 19.75 19.40 20.51 18.73 22.99

AREA 1: BAYFIELD, DOUGLAS, PRICE, SAWYER, AND WASHBURN COUNTIES

AREA DESCRIPTIONS

AREA 2: ADAMS, ASHLAND, BARRON, BROWN, BURNETT, CALUMET, CHIPPEWA, CLARK, COLUMBIA, DODGE, DOOR, DUNN, FLORENCE, FOND DU LAC, FOREST, GREEN LAKE, IRON, JEFFERSON, KEWAUNEE, LANGLADE, LINCOLN, MANITOWOC, MARATHON, MARINETTE, MARQUETTE, MENOMINEE, OCONTO, ONEIDA, OUTAGAMIE, POLK, PORTAGE, RUSK, ST CROIX, SAUK, SHAWANO, SHEBOYGAN, TAYLOR, VILAS, WALWORTH, WAUPACA, WAUSHARA, WINNEBAGO, AND WOOD COUNTIES

AREA 3: BUFFALO, CRAWFORD, EAU CLAIRE, JACKSON, JUNEAU, LA CROSSE MONROE, PEPIN, PIERCE, RICHLAND, TREMPEALEAU, AND VERNON COUNTIES

AREA 4: MILWAUKEE, OZAUKEE, WASHINGTON, AND WAUKESHA COUNTIES

AREA 5: DANE, GRANT, GREEN, IOWA, LAFAYETTE, AND ROCK COUNTIES

AREA 6: KENOSHA AND RACINE COUNTIES

TEAM0039-001 06/01/2019

	Rates	Fringes
TRUCK DRIVER 1 & 2 Axles 3 or more Axles; Euclids Dumptor & Articulated,	.\$ 29.57	22.03
Truck Mechanic	.\$ 29.72	22.03
WELL DRILLER	.\$ 16.52	3.70

WELDERS - Receive rate prescribed for craft performing operation to which welding is incidental.

Note: Executive Order (EO) 13706, Establishing Paid Sick Leave for Federal Contractors applies to all contracts subject to the Davis-Bacon Act for which the contract is awarded (and any solicitation was issued) on or after January 1, 2017. If this contract is covered by the EO, the contractor must provide employees with 1 hour of paid sick leave for every 30 hours they work, up to 56 hours of paid sick leave each year. Employees must be permitted to use paid sick leave for their own illness, injury or other health-related needs, including preventive care; to assist a family member (or person who is

like family to the employee) who is ill, injured, or has other health-related needs, including preventive care; or for reasons resulting from, or to assist a family member (or person who is like family to the employee) who is a victim of, domestic violence, sexual assault, or stalking. Additional information on contractor requirements and worker protections under the EO is available at www.dol.gov/whd/govcontracts.

Unlisted classifications needed for work not included within the scope of the classifications listed may be added after award only as provided in the labor standards contract clauses (29CFR 5.5 (a) (1) (ii)).

The body of each wage determination lists the classification and wage rates that have been found to be prevailing for the cited type(s) of construction in the area covered by the wage determination. The classifications are listed in alphabetical order of ""identifiers"" that indicate whether the particular rate is a union rate (current union negotiated rate for local), a survey rate (weighted average rate) or a union average rate (weighted union average rate).

Union Rate Identifiers

A four letter classification abbreviation identifier enclosed in dotted lines beginning with characters other than ""SU"" or ""UAVG"" denotes that the union classification and rate were prevailing for that classification in the survey. Example: PLUM0198-005 07/01/2014. PLUM is an abbreviation identifier of the union which prevailed in the survey for this classification, which in this example would be Plumbers. 0198 indicates the local union number or district council number where applicable, i.e., Plumbers Local 0198. The next number, 005 in the example, is an internal number used in processing the wage determination. 07/01/2014 is the effective date of the most current negotiated rate, which in this example is July 1, 2014.

Union prevailing wage rates are updated to reflect all rate changes in the collective bargaining agreement (CBA) governing this classification and rate.

Survey Rate Identifiers

Classifications listed under the ""SU"" identifier indicate that no one rate prevailed for this classification in the survey and

the published rate is derived by computing a weighted average rate based on all the rates reported in the survey for that classification. As this weighted average rate includes all rates reported in the survey, it may include both union and non-union rates. Example: SULA2012-007 5/13/2014. SU indicates the rates are survey rates based on a weighted average calculation of rates and are not majority rates. LA indicates the State of Louisiana. 2012 is the year of survey on which these classifications and rates are based. The next number, 007 in the example, is an internal number used in producing the wage determination. 5/13/2014 indicates the survey completion date for the classifications and rates under that identifier.

Survey wage rates are not updated and remain in effect until a new survey is conducted.

Union Average Rate Identifiers

Classification(s) listed under the UAVG identifier indicate that no single majority rate prevailed for those classifications; however, 100% of the data reported for the classifications was union data. EXAMPLE: UAVG-OH-0010 08/29/2014. UAVG indicates that the rate is a weighted union average rate. OH indicates the state. The next number, 0010 in the example, is an internal number used in producing the wage determination. 08/29/2014 indicates the survey completion date for the classifications and rates under that identifier.

A UAVG rate will be updated once a year, usually in January of each year, to reflect a weighted average of the current negotiated/CBA rate of the union locals from which the rate is based.

WAGE DETERMINATION APPEALS PROCESS

- 1.) Has there been an initial decision in the matter? This can be:
- * an existing published wage determination
- * a survey underlying a wage determination
- * a Wage and Hour Division letter setting forth a position on a wage determination matter
- * a conformance (additional classification and rate) ruling

On survey related matters, initial contact, including requests for summaries of surveys, should be with the Wage and Hour

Regional Office for the area in which the survey was conducted because those Regional Offices have responsibility for the Davis-Bacon survey program. If the response from this initial contact is not satisfactory, then the process described in 2.) and 3.) should be followed.

With regard to any other matter not yet ripe for the formal process described here, initial contact should be with the Branch of Construction Wage Determinations. Write to:

Branch of Construction Wage Determinations Wage and Hour Division U.S. Department of Labor 200 Constitution Avenue, N.W. Washington, DC 20210

2.) If the answer to the question in 1.) is yes, then an interested party (those affected by the action) can request review and reconsideration from the Wage and Hour Administrator (See 29 CFR Part 1.8 and 29 CFR Part 7). Write to:

Wage and Hour Administrator U.S. Department of Labor 200 Constitution Avenue, N.W. Washington, DC 20210

The request should be accompanied by a full statement of the interested party's position and by any information (wage payment data, project description, area practice material, etc.) that the requestor considers relevant to the issue.

3.) If the decision of the Administrator is not favorable, an interested party may appeal directly to the Administrative Review Board (formerly the Wage Appeals Board). Write to:

Administrative Review Board U.S. Department of Labor 200 Constitution Avenue, N.W. Washington, DC 20210

4.) All decisions by the Administrative Review Board are final.

END OF GENERAL DECISION"

"General Decision Number: WI20200015 07/03/2020

Superseded General Decision Number: WI20190015

State: Wisconsin

Construction Type: Heavy

Counties: Wisconsin Statewide.

HEAVY CONSTRUCTION PROJECTS (Excluding Tunnel, Sewer, and Water Lines).

Note: Under Executive Order (EO) 13658, an hourly minimum wage of \$10.80 for calendar year 2020 applies to all contracts subject to the Davis-Bacon Act for which the contract is awarded (and any solicitation was issued) on or after January 1, 2015. If this contract is covered by the EO, the contractor must pay all workers in any classification listed on this wage determination at least \$10.80 per hour (or the applicable wage rate listed on this wage determination, if it is higher) for all hours spent performing on the contract in calendar year 2020. If this contract is covered by the EO and a classification considered necessary for performance of work on the contract does not appear on this wage determination, the contractor must pay workers in that classification at least the wage rate determined through the conformance process set forth in 29 CFR 5.5(a)(1)(ii) (or the EO minimum wage rate, if it is higher than the conformed wage rate). The EO minimum wage rate will be adjusted annually. Please note that this EO applies to the above-mentioned types of contracts entered into by the federal government that are subject to the Davis-Bacon Act itself, but it does not apply to contracts subject only to the Davis-Bacon Related Acts, including those set forth at 29 CFR 5.1(a)(2)-(60). Additional information on contractor requirements and worker protections under the EO is available at www.dol.gov/whd/govcontracts.

Modification Number	Publication Date
0	01/03/2020
1	01/24/2020
2	02/28/2020
3	03/06/2020
4	06/05/2020
5	06/12/2020
6	06/19/2020
7	07/03/2020

BOIL0107-001 01/01/2017

	Rates	Fringes
BOILERMAKER Boilermaker Small Boiler Repair (under 25,000 lbs/hr)		29.89 16.00
BRWI0001-002 06/03/2019		
CRAWFORD, JACKSON, JUNEAU, LA C VERNON COUNTIES	ROSSE, MONRO	DE, TREMPEALEAU, AND
	Rates	Fringes
BRICKLAYER	\$ 33.80	24.28
BRWI0002-002 06/01/2019		
ASHLAND, BAYFIELD, DOUGLAS, AND	IRON COUNT	IES
	Rates	Fringes
BRICKLAYER BRWI0002-005 06/01/2019	\$ 39.94	23.30
ADAMS, ASHLAND, BARRON, BROWN, CLARK, COLUMBIA, DODGE, DOOR, D FOREST, GREEN LAKE, IRON, JEFFE LINCOLN, MANITOWOC, MARATHON, M OCONTO, ONEIDA, OUTAGAMIE, POLK SHAWANO, SHEBOYGAN, TAYLOR, VIL WINNEBAGO, AND WOOD COUNTIES	UNN, FLORENC RSON, KEWAUM ARINETTE, MA , PORTAGE, M	CE, FOND DU LAC, NEE, LANGLADE, ARQUETTE, MENOMINEE, RUSK, ST CROIX, SAUK,
	Rates	Fringes
CEMENT MASON/CONCRETE FINISHER.	\$ 35.51	23.37
BRWI0003-002 06/03/2019		
BROWN, DOOR, FLORENCE, KEWAUNEE	, MARINETTE	, AND OCONTO COUNTIES
	Rates	Fringes
BRICKLAYER	\$ 34.18	23.90
BRWI0004-002 06/01/2019		

KENOSHA, RACINE, AND WALWORTH COUNTIES

	Rates	Fringes
BRICKLAYER	\$ 38.43	25.10
BRWI0006-002 06/01/2019		
ADAMS, CLARK, FOREST, LANGLADE, ONEIDA, PORTAGE, PRICE, TAYLOR,		
	Rates	Fringes
BRICKLAYER	\$ 35.06	23.02
BRWI0007-002 06/03/2019		
GREEN, LAFAYETTE, AND ROCK COUN	ITIES	
	Rates	Fringes
BRICKLAYER	\$ 35.57	24.22
BRWI0008-002 06/01/2019		
MILWAUKEE, OZAUKEE, WASHINGTON,	AND WALKESI	HA COUNTIES
HILMONIE, OZNONIE, MASHINGTON,	AND MACKESI	
TEMPOREE, OZNOREL, WASHINGTON,		Fringes
BRICKLAYER	Rates\$ 38.93	Fringes 24.22
BRICKLAYER	Rates\$ 38.93	Fringes
BRICKLAYER	Rates\$ 38.93	Fringes 24.22
BRICKLAYERBRWI0009-001 06/03/2019 GREEN LAKE, MARQUETTE, OUTAGAMI	Rates\$ 38.93	Fringes 24.22
BRICKLAYERBRWI0009-001 06/03/2019 GREEN LAKE, MARQUETTE, OUTAGAMI	Rates\$ 38.93 E, SHAWANO, Rates	Fringes 24.22 WAUPACA, WASHARA,
BRICKLAYER BRWI0009-001 06/03/2019 GREEN LAKE, MARQUETTE, OUTAGAMI AND WINNEBAGO COUNTIES	Rates\$ 38.93 E, SHAWANO, Rates	Fringes 24.22 WAUPACA, WASHARA, Fringes
BRICKLAYER BRWI0009-001 06/03/2019 GREEN LAKE, MARQUETTE, OUTAGAMI AND WINNEBAGO COUNTIES BRICKLAYER	Rates\$ 38.93 E, SHAWANO, Rates\$ 34.18	Fringes 24.22 WAUPACA, WASHARA, Fringes 23.90
BRICKLAYER BRWI0009-001 06/03/2019 GREEN LAKE, MARQUETTE, OUTAGAMI AND WINNEBAGO COUNTIES BRICKLAYER BRWI0011-002 06/03/2019	Rates\$ 38.93 E, SHAWANO, Rates\$ 34.18	Fringes 24.22 WAUPACA, WASHARA, Fringes 23.90

BRWI0013-002 06/03/2019		
DANE, GRANT, IOWA, AND RICHLAND C	OUNTIES	
	Rates	Fringes
BRICKLAYER	\$ 35.56	24.23
BRWI0019-002 06/03/2019		
BARRON, BUFFALO, BURNETT, CHIPPEW PIERCE, POLK, RUSK, ST. CROIX, SA	= =	
	Rates	Fringes
BRICKLAYER	\$ 33.40	24.68
BRWI0021-002 06/03/2019		
DODGE AND JEFFERSON COUNTIES		
	Rates	Fringes
BRICKLAYER	\$ 35.75	24.02
BRWI0034-002 06/03/2019		
COLUMBIA AND SAUK COUNTIES		
	Rates	Fringes
BRICKLAYER	\$ 35.56	24.23
CARP0087-001 05/01/2016		
BURNETT (W. of Hwy 48), PIERCE (W 35, 48 & 65), AND ST. CROIX (W. o		•
	Rates	Fringes
Carpenter & Piledrivermen	\$ 36.85	18.39
CARP0252-002 06/01/2016		
ADAMS, BARRON, BAYFIELD (Easter		

BURNETT (E. of Hwy 48), CALUMET, CHIPPEWA, CLARK, COLUMBIA, CRAWFORD, DANE, DODGE, DOOR, DUNN, EAU CLAIRE, FLORENCE (except

area bordering Michigan State Line), FOND DU LAC, FOREST, GRANT, GREEN, GREEN LAKE, IOWA, IRON, JACKSON, JEFFERSON, JUNEAU, KEWAUNEE, LA CROSSE, LAFAYETTE, LANGLADE, LINCOLN, MANITOWOC, MARATHON, MARINETTE (except N.E. corner), MARQUETTE, MENOMINEE, MONROE, OCONTO, ONEIDA, OUTAGAMIE, PEPIN, PIERCE (E. of Hwys 29 & 65), POLK (E. of Hwys 35, 48 & 65), PORTAGE, PRICE, RICHLAND, ROCK, RUSK, SAUK, SAWYER, SHAWANO, SHEBOYGAN, ST CROIX (E. of Hwy 65), TAYLOR, TREMPEALEAU, VERNON, VILAS, WALWORTH, WASHBURN, WAUPACA, WAUSHARA, WINNEBAGO, AND WOOD COUNTIES

	Rates	Fringes
CARPENTER		
CARPENTER	\$ 33.56	18.00
MILLWRIGHT	\$ 35.08	18.35
PILEDRIVER	\$ 34.12	18.00
CARROSES 040 06 (04 (204 6		

CARP0252-010 06/01/2016

ASHLAND COUNTY

	Rates	Fringes
Carpenters		
Carpenter	\$ 33.56	18.00
Millwright	\$ 35.08	18.35
Pile Driver	\$ 34.12	18.00

CARP0264-003 06/01/2016

KENOSHA, MILWAUKEE, OZAUKEE, RACINE, WAUKESHA, AND WASHINGTON COUNTIES

	Rates	Fringes
CARPENTER	\$ 35.78	22.11
CARP0361-004 05/01/2018		
BAYFIELD (West of Hwy 63) AND D	OUGLAS COUNTIES	

	Rates	Fringes
CARPENTER	\$ 36.15	20.43
CARP2337-001 06/01/2016		

ZONE A: MILWAUKEE, OZAUKEE, WAUKESHA AND WASHINGTON

ZONE B: KENOSHA & RACINE

	Rates	Fringes
PILEDRIVERMAN		
Zone A	\$ 31.03	22.69
Zone B	\$ 31.03	22.69
CARP2337-003 06/01/2019		
	Rates	Fringes
MILLWRIGHT		
Zone A	\$ 33.58	21.53
Zone B		21.53
ZONE DEFINITIONS		
ZONE A: MILWAUKEE, OZAUKEE, WAUK	KESHA AND	WASHINGTON COUNTIES

ZONE B: KENOSHA & RACINE COUNTIES

ELEC0014-002 06/03/2019

ASHLAND, BARRON, BAYFIELD, BUFFALO, BURNETT, CHIPPEWA, CLARK (except Maryville, Colby, Unity, Sherman, Fremont, Lynn & Sherwood), CRAWFORD, DUNN, EAU CLAIRE, GRANT, IRON, JACKSON, LA CROSSE, MONROE, PEPIN, PIERCE, POLK, PRICE, RICHLAND, RUSK, ST CROIX, SAWYER, TAYLOR, TREMPEALEAU, VERNON, AND WASHBURN COUNTIES

	Rates	Fringes
Electricians:	\$ 35.59	20.87
ELEC0014-007 06/03/2019		

REMAINING COUNTIES

Rates	Fringes
Teledata System Installer	
<pre>Installer/Technician\$ 27.25</pre>	14.34

Low voltage construction, installation, maintenance and

removal of teledata facilities (voice, data, and video) including outside plant, telephone and data inside wire, interconnect, terminal equipment, central offices, PABX, fiber optic cable and equipment, micro waves, V-SAT, bypass, CATV, WAN (wide area networks), LAN (local area networks), and ISDN (integrated systems digital network).

ELEC0127-002 06/01/2020

KENOSHA COUNTY

Rates Fringes

Electricians:.....\$ 41.62 30%+12.70

ELEC0158-002 06/03/2019

BROWN, DOOR, KEWAUNEE, MANITOWOC (except Schleswig), MARINETTE(Wausuakee and area South thereof), OCONTO, MENOMINEE (East of a ine 6 miles West of the West boundary of Oconto County), SHAWANO (Except Area North of Townships of Aniwa and Hutchins) COUNTIES

COLUMBIA, DANE, DODGE (Area West of Hwy 26, except Chester and Emmet Townships), GREEN, LAKE (except Townships of Berlin, Seneca, and St. Marie), IOWA, MARQUETTE (except Townships of Neshkoka, Crystal Lake, Newton, and Springfield), and SAUK COUNTIES

FLORENCE COUNTY (Townships of Aurora, Commonwealth, Fern, Florence and Homestead) AND MARINETTE COUNTY (Township of Niagara)

Rates Fringes

Electricians: Electrical contracts over \$180,000	¢ 22 28	18.63
Electrical contracts under \$180,000		18.42
ELEC0242-005 05/16/2018		
DOUGLAS COUNTY		
	Rates	Fringes
Electricians:	.\$ 36.85	26.17
ELEC0388-002 06/03/2019		
ADAMS, CLARK (Colby, Freemont, L Sherwood, Unity), FOREST, JUNEA MARINETTE (Beecher, Dunbar, Good West of a line 6 miles West of t County), ONEIDA, PORTAGE, SHAWAN AND WOOD COUNTIES	NU, LANGLADE, L Iman & Pembine) The West bounda	INCOLN, MARATHON, , MENOMINEE (Area ry of Oconto
	Rates	Fringes
Electricians:	.\$ 33.56	26%+11.01
ELEC0430-002 06/01/2020		
RACINE COUNTY (Except Burlington	Township)	
	Rates	Fringes
Electricians: ELEC0494-005 06/01/2020	.\$ 41.86	22.66
MILWAUKEE, OZAUKEE, WASHINGTON,	AND WAUKESHA C	OUNTIES
	Rates	Fringes

CALUMET (Township of New Holstein), DODGE (East of Hwy 26 including Chester Township), FOND DU LAC, MANITOWOC (Schleswig), and SHEBOYGAN COUNTIES

ELEC0494-006 06/01/2020

	Rates	Fringes
Electricians:	\$ 36.32	22.51
ELEC0494-013 06/01/2019		

DODGE (East of Hwy 26 including Chester Twp, excluding Emmet Twp), FOND DU LAC (Except Waupuin), MILWAUKEE, OZAUKEE, MANITOWOC (Schleswig), WASHINGTON, AND WAUKESHA COUNTIES

	Rates	Fringes
Sound & Communications		
Installer	\$ 20.53	18.13
Technician	\$ 30.18	19.58

Installation, testing, maintenance, operation and servicing of all sound, intercom, telephone interconnect, closed circuit TV systems, radio systems, background music systems, language laboratories, electronic carillion, antenna distribution systems, clock and program systems and low-voltage systems such as visual nurse call, audio/visual nurse call systems, doctors entrance register systems. Includes all wire and cable carrying audio, visual, data, light and radio frequency signals. Includes the installation of conduit, wiremold, or raceways in existing structures that have been occupied for six months or more where required for the protection of the wire or cable, but does not mean a complete conduit or raceway system. work covered does not include the installation of conduit, wiremold or any raceways in any new construction, or the installation of power supply outlets by means of which external electric power is supplied to any of the foregoing equipment or products

ELEC0577-003 06/01/2019

CALUMET (except Township of New Holstein), GREEN LAKE (N. part including Townships of Berlin, St Marie, and Seneca), MARQUETTE (N. part including Townships of Crystal Lake, Neshkoro, Newton, and Springfield), OUTAGAMIE, WAUPACA, WAUSHARA, AND WINNEBAGO COUNTIES

Rates Fringes

Electricians:	\$ 33.15	28.50%+10.00

ELEC0890-003 06/01/2020

DODGE (Emmet Township only), GREEN, JEFFERSON, LAFAYETTE, RACINE (Burlington Township), ROCK AND WALWORTH COUNTIES

	Rates	Fringes
Electricians:	\$ 37.41	25.95%+11.11
ELEC0953-001 06/02/2019		

1	Rates	Fringes
Line Construction: (1) Lineman\$ (2) Heavy Equipment Operator\$ (3) Equipment Operator\$ (4) Heavy Groundman Driver\$ (5) Light Groundman Driver\$	47.53 42.78 38.02 33.27 30.89	21.43 19.80 18.40 16.88 16.11
(6) Groundsman\$	26.14	14.60

ENGI0139-001 06/01/2020

KENOSHA, MILWAUKEE, OZAUKEE, RACINE, WASHINGTON, AND WAUKESHA COUNTIES

	Rates	Fringes
Power Equipment Operator		
Group 1	\$ 47.66	23.15
Group 2	\$ 47.16	23.15
Group 3	\$ 46.66	23.15
Group 4	\$ 45.97	23.15
Group 5	\$ 42.39	23.15
Group 6	\$ 37.24	23.15

HAZARDOUS WASTE PREMIUMS:

EPA Level ""A"" Protection: \$3.00 per hour EPA Level ""B"" Protection: \$2.00 per hour EPA Level ""C"" Protection: \$1.00 per hour

POWER EQUIPMENT OPERATORS CLASSIFICATIONS

GROUP 1: Cranes, Tower Cranes, Pedestal Tower Cranes and Derricks with or w/o attachments with a lifting capacity of

over 100 tons; or Cranes, Tower Cranes, Pedestal Tower Cranes and Derricks with boom, leads, and/or jib lengths measuring 176 feet or longer; Self-Erecting Tower Cranes over 4000 lbs lifting capacity; All Cranes with Boom Dollies; Boring Machines (directional); Master Mechanic. \$0.50 additional per hour per 100 tons or 100 ft of boom over 200 ft or lifting capacity of crane over 200 tons to a maximum of 300 tons or 300 ft. Thereafter an increase of \$0.01 per ft or ton, whichever is greater.

- GROUP 2: Cranes, Tower Cranes, Pedestal Tower Cranes and Derricks with or without attachments with a lifting capacity of 100 tons or less; or Cranes, Tower Cranes Portable Tower Cranes, Pedestal Tower Cranes and Derricks with boom, leadsand/or jib lengths measuring 175 feet or less; Backhoes (excavators) 130,000 lbs and over; Caisson Rigs; Pile Drivers; Boring Machines (vertical or horizontal), Versi-Lift, Tri-Lift, Gantry 20,000 lbs & over.
- GROUP 3: Backhoe (excavator) under 130,000 lbs; Self-erecting Tower Crane 4000 lbs & under lifting capacity; Traveling Crane (bridge type); Skid Rigs; Dredge Operator; Mechanic; Concrete Paver (over 27E); Concrete Spreader and Distributor; Forklift/ Telehandler (machinery- moving / steel erection); Hydro Blaster, 10,000 psi and over
- GROUP 4: Material Hoists; Stack Hoists; Hydraulic Backhoe (tractor or truck mounted); Hydraulic Crane, 5 tons or under (tractor or truck mounted); Hoist (tuggers 5 tons & over); Hydro-Excavators/Daylighters; Concrete Pumps Rotec type Conveyors; Tractor/Bulldozer/End Loader (over 40 hp); Motor Patrol; Scraper Operator; Sideboom; Straddle Carrier; Welder; Bituminous Plant and Paver Operator; Roller over 5 tons; Rail Leveling Machine (Railroad); Tie Placer; Tie Extractor; Tie Tamper; Stone Leveler; Rotary Drill Operator and Blaster; Percussion Drill Operator; Air Track Drill and/or Hammers; Gantrys (under 20,000 lbs); Tencher (wheel type or chain type having 8 inch or larger bucket); Milling Machine; Off-Road Material Haulers.
- GROUP 5: Backfiller; Concrete Auto Breaker (large); Concrete Finishing Machines (road type); Rubber Tired Roller; Concrete Batch Hopper; Concrete Conveyor Systems; Grout Pumps; Concrete Mixers (14S or over); Screw Type Pumps and Gypsum Pumps; Tractor, Bulldozer, End Loader (under 40 hp); Trencher (chain type, bucket under 8 inch); Industrial Locomotives; Rollers under 5 tons; Stump Grinder/Chipper (Large); Timber Equipment; Firemen (pile drivers and derricks); Personnel Hoist, Telehandler over 8000 lbs; Robotic Tool Carrier with or without attachments

GROUP 6: Tampers - Compactors (riding type); Assistant Engineer; A-Frames and Winch Trucks; Concrete Auto Breaker; Hydrohammers (small); Brooms and Sweepers; Hoist (tuggers under 5 tons); Boats (Tug, Safety, Work Barges, Launch); Shouldering Machine Operator; Prestress Machines; Screed Operator; Stone Crushers and Screening Plants; Screed Operators (milling machine), Farm or Industrial Tractor Mounted Equipment; Post Hole Digger; Fireman (asphalt plants); Air Compressors over 400 CFM; Generators, over 150 KW; Augers (vertical and horizontal); Air, Electric, Hydraulic Jacks (slipform); Skid Steer Loaders (with or without attachments); Boiler Operators (temporary heat); Refrigeration Plant/Freeze Machines; Power Pack Vibratory/Ultra Sound Drivers and Extractors; Welding Machines; Heaters (mechanical); Pumps; Winches (small electric); Oiler and Greaser; Rotary Drill Tender; Conveyor; Forklifts/Telehandler 8000 lbs & under; Elevators: Automatic Hoists; Pumps (well points); Combination Small Equipment Operators

ENGI0139-003 06/03/2019

REMAINING COUNTIES

	Rates	Fringes
Power Equipment Operator		
Group 1	\$ 41.52	22.45
Group 2	\$ 40.27	22.45
Group 3	\$ 38.97	22.45
Group 4	\$ 38.44	22.45
Group 5	\$ 36.37	22.45
Group 6	\$ 34.84	22.45

HAZARDOUS WASTE PREMIUMS:

EPA Level ""A"" Protection: \$3.00 per hour EPA Level ""B"" Protection: \$2.00 per hour EPA Level ""C"" Protection: \$1.00 per hour

POWER EQUIPMENT OPERATORS CLASSIFICATIONS

GROUP 1: Cranes, Tower Cranes and Derricks with or without attachments with a lifting capacity of over 100 tons; Cranes, Tower Cranes, and Derricks with boom, leads and/or jib lengths 176 ft or longer.

GROUP 2: Backhoes (Excavators) weighing 130,00 lbs and over; Cranes, Tower Cranes and Derricks with or without

attachments with a lifting capacity of 100 tons or less; Cranes, Tower Cranes, and Derricks with boom, leads, and/or jib lengths 175 ft or less; Caisson Rigs; Pile Driver

GROUP 3: Backhoes (Excavators) weighing under 130,000 lbs; Travelling Crane (bridge type); Milling Machine; Concrete Paver over 27 E; Concrete Spreader and Distributor; Concrete Laser Screed; Concrete Grinder and Planing Machine; Slipform Curb and Gutter Machine; Boring Machine (Directional); Dredge Operator; Skid Rigs; over 46 meter Concrete Pump.

GROUP 4: Hydraulic Backhoe (tractor or truck mounted); Hydraulic Crane, 10 tons or less; Tractor, Bulldozer, or End Loader (over 40 hp); Motor Patrol; Scraper Operator; Bituminous Plant and Paver Operator; Screed-Milling Machine; Roller over 5 tons; Concrete pumps 46 meter and under; Grout Pumps; Rotec type machine; Hydro Blaster, 10,000 psi and over; Rotary Drill Operator; Percussion Drilling Machine; Air Track Drill with or without integral hammer; Blaster; Boring Machine (vertical or horizontal); Side Boom; Trencher, wheel type or chain type having 8 inch or larger bucket; Rail Leveling Machine (Railroad); Tie Placer; Tie Extractor; Tie Tamper; Stone Leveler; Straddle Carrier; Material Hoists; Stack Hoist; Man Hoists; Mechanic and Welder; Off Road Material Haulers.

GROUP 5: Tractor, Bulldozer, or Endloader (under 40 hp); Tampers -Compactors, riding type; Stump Chipper, large; Roller, Rubber Tire; Backfiller; Trencher, chain type (bucket under 8 inch); Concrete Auto Breaker, large; Concrete Finishing Machine (road type); Concrete Batch Hopper; Concrete Conveyor Systems; Concrete Mixers, 14S or over; Pumps, Screw Type and Gypsum); Hydrohammers, small; Brooms and Sweeeprs; Lift Slab Machine; Roller under 5 tons; Industrial Locomotives; Fireman (Pile Drivers and Derricks); Pumps (well points); Hoists, automatic; A-Frames and Winch Trucks; Hoists (tuggers); Boats (Tug, Safety, Work Barges and Launches); Assistant Engineer

GROUP 6: Shouldering Machine Operator; Farm or Industrial Tractor mounted equipment; Post Hole Digger; Auger (vertical and horizontal); Skid Steer Loader with or without attachments; Robotic Tool Carrier with or without attachments; Power Pack Vibratory/Ultra Sound Driver and Extractor; Fireman (Asphalt Plants); Screed Operator; Stone Crushers and Screening Plants; Air, Electric, Hydraulic Jacks (Slip Form); Prestress Machines; Air Compressor, 400 CFM or over; Refrigeration Plant/Freese Machine; Boiler Operators (temporary heat); Forklifts; Welding Machines;

Generators; Pumps over 3""; Heaters, Mechanical; Combination small equipment operator; Winches, small electric; Oiler; Greaser; Rotary Drill Tender; Conveyor; Elevator Operator

IRON0008-002 06/01/2020

BROWN, CALUMET, DOOR, FOND DU LAC, KEWAUNEE, MANITOWOC, MARINETTE, OCONTO, OUTAGAMI, SHAWANO, SHEBOYGAN, AND WINNEBAGO COUNTIES:

Rates Fringes
IRONWORKER.....\$ 37.31 27.62

Paid Holidays: New Year's Day, Memorial Day, July 4th, Labor Day, Thanksgiving Day & Christmas Day.

IRON0008-003 06/01/2020

KENOSHA, MILWAUKEE, OZAUKEE, RACINE, WALWORTH (N.E. 2/3), WASHINGTON, AND WAUKESHA COUNTIES

Paid Holidays: New Year's Day, Memorial Day, July 4th, Labor Day, Thanksgiving Day & Christmas Day.

IRON0383-001 06/01/2020

ADAMS, COLUMBIA, CRAWFORD, DANE, DODGE, FLORENCE, FOREST, GRANT, GREENE, (Excluding S.E. tip), GREEN LAKE, IOWA, JEFFERSON, JUNEAU, LA CROSSE, LAFAYETTE, LANGLADE, MARATHON, MARQUETTE, MENOMINEE, MONROE, PORTAGE, RICHLAND, ROCK (Northern area, vicinity of Edgerton and Milton), SAUK, VERNON, WAUPACA, WAUSHARA, AND WOOD COUNTIES

BARRON, BUFFALO, CHIPPEWA, CLARK, DUNN, EAU CLAIRE, JACKSON, PEPIN, PIERCE, POLK, RUSK, ST CROIX, TAYLOR, AND TREMPEALEAU COUNTIES

	Rates	Fringes
IRONWORKER	\$ 37.60	29.40
IRON0512-021 06/03/2019		

ASHLAND, BAYFIELD, BURNETT, DOUGLAS, IRON, LINCOLN, ONEIDA, PRICE, SAWYER, VILAS AND WASHBURN COUNTIES

	Rates	Fringes
IRONWORKER	\$ 33.19	29.40
LAB00113-002 06/03/2019		

MILWAUKEE AND WAUKESHA COUNTIES

	F	Rates	Fringes
LABORER			
Group	1\$	29.02	21.92
Group	2\$	29.17	21.92
Group	3\$	29.37	21.92
Group	4\$	29.52	21.92
Group	5\$	29.67	21.92
Group	6\$	25.51	21.92

LABORERS CLASSIFICATIONS

GROUP 1: General Laborer; Tree Trimmer; Conduit Layer; Demolition and Wrecking Laborer; Guard Rail, Fence, and Bridge Builder; Landscaper; Multiplate Culvert Assembler; Stone Handler; Bituminous Worker (Shoveler, Loader, and Utility Man); Batch Truck Dumper or Cement Handler; Bituminous Worker (Dumper, Ironer, Smoother, and Tamper); Concrete Handler

GROUP 2: Air Tool Operator; Joint Sawer and Filler (Pavement); Vibrator or Tamper Operator (Mechanical Hand Operated); Chain Saw Operator; Demolition Burning Torch Laborer

GROUP 3: Bituminous Worker (Raker and Luteman); Formsetter (Curb, Sidewalk, and Pavement); Strike Off Man

GROUP 4: Line and Grade Specialist

GROUP 5: Blaster and Powderman

GROUP 6: Flagperson; traffic control person

LABO0113-003 06/03/2019

OZAUKEE AND WASHINGTON COUNTIES

		Rates	Fringes
LABORER			
Group	1\$	28.27	21.92
Group	2\$	28.37	21.92
Group	3\$	28.42	21.92
Group	4\$	28.62	21.92
Group	5\$	28.47	21.92
Group	6\$	25.36	21.92

LABORERS CLASSIFICATIONS

GROUP 1: General Laborer; Tree Trimmer; Conduit Layer; Demolition and Wrecking Laborer; Guard Rail, Fence, and Bridge Builder; Landscaper; Multiplate Culvert Assembler; Stone Handler; Bituminous Worker (Shoveler, Loader, and Utility Man); Batch Truck Dumper or Cement Handler; Bituminous Worker (Dumper, Ironer, Smoother, and Tamper); Concrete Handler

GROUP 2: Air Tool Operator; Joint Sawer and Filler (Pavement); Vibrator or Tamper Operator (Mechanical Hand Operated);

GROUP 3: Bituminous Worker (Raker and Luteman); Formsetter (Curb, Sidewalk, and Pavement); Strike Off Man

GROUP 4: Line and Grade Specialist

GROUP 5: Blaster; powderman

GROUP 6: Flagperson and Traffic Control Person

LAB00113-011 06/03/2019

KENOSHA AND RACINE COUNTIES

	Rates	Fringes
1	.\$ 28.08	21.92
2	.\$ 28.23	21.92
3	.\$ 28.43	21.92
4	.\$ 28.40	21.92
5	.\$ 28.73	21.92
6	.\$ 25.22	21.92
	2	Rates 1

LABORERS CLASSIFICATIONS:

GROUP 1: General laborer; Tree Trimmer; Conduit Layer; Demolition and Wrecking Laborer; Guard Rail, Fence, and Bridge Builder; Landscaper; Multiplate Culvert Assembler; Stone Handler; Bituminous Worker (Shoveler, Loader, and Utility Man); Batch Truck Dumper or Cement Handler; Bituminous worker (Dumper, Ironer, Smoother, and Tamper); Concrete Handler

GROUP 2: Air Tool Operator; Joint Sawer and Filler (Pavement); Vibrator or Tamper Operator (Mechanical Hand Operated); Chain Saw Operator; Demolition Burning Torch Laborer

GROUP 3: Bituminous Worker (Raker and Luteman); Formsetter (Curb, Sidewalk, and Pavement); Strike Off Man

GROUP 4: Line and Grade Specialist

GROUP 5: Blaster and Powderman

GROUP 6: Flagman; traffic control person

LAB00140-002 06/03/2019

ADAMS, ASHLAND, BARRON, BAYFIELD, BROWN, BUFFALO, BURNETT, CALUMET, CHIPPEWA, CLARK, COLUMBIA, CRAWFORD, DODGE, DOOR, DOUGLAS, DUNN, EAU CLAIRE, FLORENCE, FOND DU LAC, FOREST, GRANT, GREEN, GREEN LAKE, IRON, JACKSON, JUNEAU, IOWA, JEFFERSON, KEWAUNEE, LA CROSSE, LAFAYETTE, LANGLADE, LINCOLN, MANITOWOC, MARATHON, MARINETTE, MARQUETTE, MENOMINEE, MONROE, OCONTO, ONEIDA, OUTAGAMIE, PEPIN, PIERCE, POLK, PORTAGE, PRICE, RICHLAND, ROCK, RUSK, SAUK, SAWYER, SHAWANO, SHEBOYGAN, ST. CROIX, TAYLOR, TREMPEALEAU, VERNON, VILLAS, WALWORTH, WASHBURN, WAUPACA, WAUSHARA, WINNEBAGO, AND WOOD COUNTIES

LABORER

Group 1	\$ 32.84	17.54
Group 2	\$ 32.94	17.54
Group 3	\$ 32.99	17.54
Group 4	\$ 33.19	17.54
Group 5	\$ 33.04	17.54
Group 6	\$ 29.47	17.54

LABORER CLASSIFICATIONS

GROUP 1: General Laborer; Tree Trimmer; Conduit Layer; Demolition and Wrecking Laborer; Guard Rail, Fence, and Bridge Builder; Landscaper; Multiplate Culvert Assembler; Stone Handler; Bitminous Worker (Shoveler, Loader, and Utility Man); Batch Truck Dumper or Cement Handler; Bituminous Worker (Dumper, Ironer, Smoother and Tamper); Concrete Handler

GROUP 2: Air Tool Operator; Joint Sawer and Filler (Pavement); Vibrator or Tamper Operator (Mechanical Hand Operated); Chain Saw Operator, Demolition Burning Torch Laborer

GROUP 3: Bituminous Worker (Raker and Luteman); Formsetter (Curb, Sidewalk and Pavement); Strike Off Man

GROUP 4: Line and Grade Secialist

GROUP 5: Blaster; powderman

GROUP 6: Flagperson; Traffic Control

LABO0464-003 06/03/2019

DANE COUNTY

	Rates	Fringes
LABORER		
Group	1\$ 33.12	17.54
Group	2\$ 33.22	17.54
Group	3\$ 33.27	17.54
Group	4\$ 33.47	17.54
Group	5\$ 33.32	17.54
Group	6\$ 29.47	17.54

LABORERS CLASSIFICATIONS:

GROUP 1: General Laborer; Tree Trimmer; Conduit Layer; Demolition and Wrecking Laborer; Guard Rail, Fence, and Bridge Builder; Landscaper; Multiplate Culvert Assembler; Stone Handler; Bituminous Worker (Shoveler, Loader, and Utility Man); Batch Truck Dumper or Cement Handler; Bituminious Worker (Dumper, Ironer, Smoother, and Tamper); Concrete Handler

GROUP 2: Air Tool Operator; Joint Sawer and Filler (Pavement); Vibrator or Tamper Operator (Mechanical Hand Operated); Chain Saw Operator; Demolition Burning Torch Laborer

GROUP 3: Bituminous Worker (Raker and Luteman); Formsetter (Curb, Sidewalk, and Pavement); Strike Off Man

GROUP 4: Line and Grade Specialist

GROUP 5: Blaster; Powderman

GROUP 6: Flagperson and Traffic Control Person

PAIN0106-008 05/01/2017

ASHLAND, BAYFIELD, BURNETT, AND DOUGLAS COUNTIES

	Ī	Rates	Fringes
Painters:			
New:			
Brush,	Roller\$	30.33	17.27
Spray,	Sandblast, Steel\$	30.93	17.27
Repaint	:		
Brush,	Roller\$	28.83	17.27
Spray,	Sandblast, Steel\$	29.43	17.27

PAIN0108-002 06/01/2019

RACINE COUNTY

	Rates	Fringes
Painters:		
Brush, Roller	\$ 36.08	20.36
Spray & Sandblast	\$ 37.08	20.36

PAIN0259-002 05/01/2008

BARRON, CHIPPEWA, DUNN, EAU CLAIRE, PEPIN, PIERCE, POLK, RUSK,

SAWYER, ST. CROIX, AND WASHBURN COUNTIES

	Rates	Fringes
PAINTER		12.15
PAIN0259-004 05/01/2015		
BUFFALO, CRAWFORD, JACKSON, LA VERNON COUNTIES	CROSSE, MONR	OE, TREMPEALEAU, AND
	Rates	Fringes
PAINTER		12.45
PAIN0781-002 06/01/2019		
JEFFERSON, MILWAUKEE, OZAUKEE,	WASHINGTON,	AND WAUKESHA COUNTIES
	Rates	Fringes
Painters: Bridge Brush Spray & Sandblast	\$ 32.95 \$ 33.70	23.86 23.86 23.86
PAIN0802-002 06/01/2019		
COLUMBIA, DANE, DODGE, GRANT, G ROCK, AND SAUK COUNTIES	REEN, IOWA,	LAFAYETTE, RICHLAND,
	Rates	Fringes
PAINTER Brush	\$ 30.93	18.44
PREMIUM PAY: Structural Steel, Spray, Brid hour.	ges = \$1.0	0 additional per
PAIN0802-003 06/01/2019		
ADAMS, BROWN, CALUMET, CLARK, D	OOR, FOND DU	LAC, FOREST, GREEN

ADAMS, BROWN, CALUMET, CLARK, DOOR, FOND DU LAC, FOREST, GREEN LAKE, IRON, JUNEAU, KEWAUNEE, LANGLADE, LINCOLN, MANITOWOC, MARATHON, MARINETTE, MARQUETTE, MENOMINEE, OCONTO, ONEIDA, OUTAGAMIE, PORTAGE, PRICE, SHAWANO, SHEBOYGAN, TAYLOR, VILAS,

WAUSHARA, WAUPACA, WINNEBAGO, AND WOOD COUNTIES

	Rates	Fringes
PAINTER	.\$ 30.93	18.58
PAIN0934-001 06/01/2017		
KENOSHA AND WALWORTH COUNTIES		
	Rates	Fringes
Painters: Brush	.\$ 34.74	18.95 18.95 18.95
PAIN1011-002 06/02/2019		
FLORENCE COUNTY		
FLORENCE COUNTY		
PLOKENCE COUNTY	Rates	Fringes
Painters:	.\$ 25.76	J
	.\$ 25.76	J
Painters:	.\$ 25.76	J
Painters:	.\$ 25.76 Rates .\$ 39.46 .\$ 35.07 .\$ 35.61 .\$ 34.70 .\$ 36.27	13.33

AREA 1: BAYFIELD, DOUGLAS, PRICE, SAWYER, AND WASHBURN COUNTIES

AREA 2: ADAMS, ASHLAND, BARRON, BROWN, BURNETT, CALUMET, CHIPPEWA, CLARK, COLUMBIA, DODGE, DOOR, DUNN, FLORENCE, FOND DU LAC, FOREST, GREEN LAKE, IRON, JEFFERSON, KEWAUNEE, LANGLADE, LINCOLN, MANITOWOC, MARATHON, MARINETTE, MARQUETTE, MENOMINEE, OCONTO, ONEIDA, OUTAGAMIE, POLK, PORTAGE, RUSK, ST CROIX, SAUK, SHAWANO, SHEBOYGAN, TAYLOR, VILAS, WALWORTH, WAUPACA, WAUSHARA, WINNEBAGO, AND WOOD

1	\cap	П	N	т	т	F	C
١	 .,	u	ıv			_	7

COUNTIES		
AREA 3: BUFFALO, CRAWFORD, EAU CROSSE MONROE, PEPIN, PIERCE, VERNON COUNTIES		
AREA 4: MILWAUKEE, OZAUKEE, WA	SHINGTON, AND WA	AUKESHA COUNTIES
AREA 5: DANE, GRANT, GREEN, I COUNTIES	OWA, LAFAYETTE,	AND ROCK
AREA 6: KENOSHA AND RACINE COUN	TIES	
PLUM0011-003 05/07/2018		
ASHLAND, BAYFIELD, BURNETT, DOUG COUNTIES	iLAS, IRON, SAWYE	R, AND WASHBURN
	Rates	Fringes
PLUMBER	•	20.72
PLUM0075-002 06/01/2016		
MILWAUKEE, OZAUKEE, WASHINGTON,	AND WAUKESHA COL	INTIES
	Rates	Fringes
PLUMBER	.\$ 40.27	21.47
PLUM0075-004 06/01/2016		
DODGE (Watertown), GREEN, JEFFER COUNTIES	SON, LAFAYETTE,	AND ROCK
	Rates	Fringes
PLUMBER	.\$ 40.52	21.47
PLUM0075-009 06/01/2016		

COLUMBIA, DANE, IOWA, MARQUETTE, RICHLAND AND SAUK COUNTIES

PLUMBER.....\$ 38.82

Rates

Fringes

20.12

PLUM0111-007 05/28/2018		
MARINETTE COUNTY (Niagara only)		
	Rates	Fringes
PLUMBER/PIPEFITTER	.\$ 33.33	24.48
* PLUM0118-002 06/01/2020		
KENOSHA, RACINE, AND WALWORTH CO	DUNTIES	
	Rates	Fringes
Plumber and Steamfitter	.\$ 43.95	24.35
PLUM0400-003 06/04/2018		
ADAMS, BROWN, CALUMET, DODGE (exc LAC, GREEN LAKE, KEWAUNEE, MANITO Niagara), MENOMINEE, OCONTO, OUT WAUPACA, WAUSHARA, AND WINNEBAGO	DWOC, MARINETTE (AGAMIE, SHAWANO)	(except
	Rates	Fringes
PLUMBER/PIPEFITTER	.\$ 36.74	19.06
PLUM0434-002 06/03/2018		
BARON, BUFFALO, CHIPPEWA, CLARK, FLORENCE, FOREST, GRANT, JACKSON LINCOLN, MARATHON, MONROE, ONEID PORTAGE, PRICE, RUSK, ST. CROIX, VILAS, AND WOOD COUNTIES	I, JUNEAU, LA CRO DA, PEPIN, PIERCO	DSSE, LANGLADE, E, POLK,
	Rates	Fringes
PIPEFITTER	.\$ 40.15	18.57

DODGE (Watertown), GREEN, JEFFERSON, LAFAYETTE, MILWAUKEE, OZAUKEE, ROCK, WASHINGTON AND WAUKESHA COUNTIES

PLUM0601-003 06/03/2019

Rates

Fringes

PIPEFITTER	.\$ 46.89	25.29		
PLUM0601-009 06/04/2017				
COLUMBIA, DANE, IOWA, MARQUETTE,	RICHLAND AND S	AUK COUNTIES		
	Rates	Fringes		
PIPEFITTER	•			
TEAM0039-002 06/01/2019				
	Rates	Fringes		
TRUCK DRIVER 1 & 2 Axle Trucks 3 or more axles; Euclids or Dumptor, Articulated	.\$ 29.57	22.03		
Truck, Mechanic	.\$ 29.72	22.03		
SUWI2011-001 11/16/2011				
	Rates	Fringes		
WELL DRILLER				
WELDERS - Receive rate prescribed for craft performing operation to which welding is incidental.				

Note: Executive Order (EO) 13706, Establishing Paid Sick Leave for Federal Contractors applies to all contracts subject to the Davis-Bacon Act for which the contract is awarded (and any solicitation was issued) on or after January 1, 2017. If this contract is covered by the EO, the contractor must provide employees with 1 hour of paid sick leave for every 30 hours they work, up to 56 hours of paid sick leave each year. Employees must be permitted to use paid sick leave for their own illness, injury or other health-related needs, including preventive care; to assist a family member (or person who is like family to the employee) who is ill, injured, or has other health-related needs, including preventive care; or for reasons resulting from, or to assist a family member (or person who is like family to the employee) who is a victim of, domestic violence, sexual assault, or stalking. Additional information on contractor requirements and worker protections under the EO is available at www.dol.gov/whd/govcontracts.

Unlisted classifications needed for work not included within the scope of the classifications listed may be added after award only as provided in the labor standards contract clauses (29CFR 5.5 (a) (1) (ii)).

The body of each wage determination lists the classification and wage rates that have been found to be prevailing for the cited type(s) of construction in the area covered by the wage determination. The classifications are listed in alphabetical order of ""identifiers"" that indicate whether the particular rate is a union rate (current union negotiated rate for local), a survey rate (weighted average rate) or a union average rate (weighted union average rate).

Union Rate Identifiers

A four letter classification abbreviation identifier enclosed in dotted lines beginning with characters other than ""SU"" or ""UAVG"" denotes that the union classification and rate were prevailing for that classification in the survey. Example: PLUM0198-005 07/01/2014. PLUM is an abbreviation identifier of the union which prevailed in the survey for this classification, which in this example would be Plumbers. 0198 indicates the local union number or district council number where applicable, i.e., Plumbers Local 0198. The next number, 005 in the example, is an internal number used in processing the wage determination. 07/01/2014 is the effective date of the most current negotiated rate, which in this example is July 1, 2014.

Union prevailing wage rates are updated to reflect all rate changes in the collective bargaining agreement (CBA) governing this classification and rate.

Survey Rate Identifiers

Classifications listed under the ""SU"" identifier indicate that no one rate prevailed for this classification in the survey and the published rate is derived by computing a weighted average rate based on all the rates reported in the survey for that classification. As this weighted average rate includes all rates reported in the survey, it may include both union and non-union rates. Example: SULA2012-007 5/13/2014. SU indicates the rates are survey rates based on a weighted average calculation of rates and are not majority rates. LA indicates the State of Louisiana. 2012 is the year of survey on which

these classifications and rates are based. The next number, 007 in the example, is an internal number used in producing the wage determination. 5/13/2014 indicates the survey completion date for the classifications and rates under that identifier.

Survey wage rates are not updated and remain in effect until a new survey is conducted.

Union Average Rate Identifiers

Classification(s) listed under the UAVG identifier indicate that no single majority rate prevailed for those classifications; however, 100% of the data reported for the classifications was union data. EXAMPLE: UAVG-OH-0010 08/29/2014. UAVG indicates that the rate is a weighted union average rate. OH indicates the state. The next number, 0010 in the example, is an internal number used in producing the wage determination. 08/29/2014 indicates the survey completion date for the classifications and rates under that identifier.

A UAVG rate will be updated once a year, usually in January of each year, to reflect a weighted average of the current negotiated/CBA rate of the union locals from which the rate is based.

WAGE DETERMINATION APPEALS PROCESS

- 1.) Has there been an initial decision in the matter? This can be:
- * an existing published wage determination
- * a survey underlying a wage determination
- * a Wage and Hour Division letter setting forth a position on a wage determination matter
- * a conformance (additional classification and rate) ruling

On survey related matters, initial contact, including requests for summaries of surveys, should be with the Wage and Hour Regional Office for the area in which the survey was conducted because those Regional Offices have responsibility for the Davis-Bacon survey program. If the response from this initial contact is not satisfactory, then the process described in 2.) and 3.) should be followed.

With regard to any other matter not yet ripe for the formal process described here, initial contact should be with the

Branch of Construction Wage Determinations. Write to:

Branch of Construction Wage Determinations Wage and Hour Division U.S. Department of Labor 200 Constitution Avenue, N.W. Washington, DC 20210

2.) If the answer to the question in 1.) is yes, then an interested party (those affected by the action) can request review and reconsideration from the Wage and Hour Administrator (See 29 CFR Part 1.8 and 29 CFR Part 7). Write to:

Wage and Hour Administrator U.S. Department of Labor 200 Constitution Avenue, N.W. Washington, DC 20210

The request should be accompanied by a full statement of the interested party's position and by any information (wage payment data, project description, area practice material, etc.) that the requestor considers relevant to the issue.

3.) If the decision of the Administrator is not favorable, an interested party may appeal directly to the Administrative Review Board (formerly the Wage Appeals Board). Write to:

Administrative Review Board U.S. Department of Labor 200 Constitution Avenue, N.W. Washington, DC 20210

4.) All decisions by the Administrative Review Board are final.

END OF GENERAL DECISION"



Wisconsin Department of Transportation

June 15, 2020

Division of Transportation Systems Development

Bureau of Project Development 4822 Madison Yards Way, 4th Floor South Madison, WI 53705

Telephone: (608) 266-1631 Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

Proposal #11: 9650-17-61, WISC 2020 351 9650-17-70, WISC 2020 352

Shawano - Neopit Shawano - Neopit

Wolf River Bridge B-73-0004 Duquaine Rd to N Jct of CTH VV

STH 47 STH 47

Menominee County Menominee County

Letting of July 14, 2020

This is Addendum No. 01, which provides for the following:

Schedule of Items:

Added Bid Item Quantities					
Pid Itom	Itom Description	Unit	Old	Revised	Proposal
Bid Item Item Description		Unit	Quantity	Quantity	Total
ASP.1TOA	On the Job Training Apprentice	HRS	0	2,400	2,400
ASP.1.TOG	On the Job Training Graduate	HRS	0	1,980	1,980

Other

ASP 1 is being added to the proposal

Schedule of Items

Attached, dated June 15, 2020, are the revised Schedule of Items Page 16.

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist Proposal Management Section

END OF ADDENDUM

ADDITIONAL SPECIAL PROVISION 1 (ASP 1) FOR TRANSPORTATION ALLIANCE FOR NEW SOLUTIONS (TrANS) PROGRAM EMPLOYMENT PLACEMENTS AND APPRENTICESHIPS

The Safe, Accountable, Flexible, Efficient Transportation Equity Act: A Legacy for Users (SAFETEA-LU), Section 5204(e) – Surface Transportation Workforce Development Training and Education, provides for 100 percent Federal funding if the core program funds are used for training, education, or workforce development purposes, including "pipeline" activities. The core programs includes: Congestion Mitigation and Air Quality Improvement (CMAQ) Program, Highway Bridge Program (HBP), Interstate Maintenance (IM), National Highway System (NHS), and Surface Transportation Program (STP). These workforce development activities cover surface transportation workers, including OJT/SS programs for women and minorities as authorized in 23 U.S.C. §140(b).

Trans is an employment program originally established in 1995 in Southeastern Wisconsin. Currently Trans has expanded to include Trans program locations to serve contractors in Southeast (Milwaukee and surrounding counties), Southcentral (Dane County and surrounding counties including Rock County), and most Northeastern Wisconsin counties from locations in Keshena, Rhinelander and surrounding far Northern areas. Trans attempts to meet contractor's needs in other geographic locations as possible. It is an industry driven plan of services to address the outreach, preparation, placement and retention of women, minorities and non-minorities as laborers and apprentices in the highway skilled trades. These candidate preparation and contractor coordination services are provided by community based organizations. For a list of the Trans Coordinators contact the Disadvantaged Business Enterprise Office at (414) 438-4583 in Milwaukee or (608) 266-6961 in Madison. These services are provided to you at no cost.

I. BASIC CONCEPTS

Training reimbursements to employing contractors for new placements, rehires or promotions to apprentice of TrANS Program graduates will be made as follows:

- 1) On-the-Job Training, Item ASP.1T0G, ASP 1 Graduate. At the rate of \$5.00 per hour on federal aid projects when TrANS graduates are initially hired, or seasonally rehired, as unskilled laborers or the equivalent.

 Eligibility and Duration: To the employing contractor, for up to 2000 hours
- from the point of initial hire as a TrANS program placement.

 Contract Goal: To maintain the intent of the Equal Employment Opportunity program, it is a goal that 6 (number) TrANS Graduate(s) be utilized on this contract.
 - 2) On-the-Job Training, Item ASP.1T0A, ASP 1 Apprentice. At the rate of \$5.00 per hour on federal aid projects at the point when an employee who came out of the TrANS Program is subsequently entered into an apprenticeship contract in an underutilized skilled trade (this will include the Skilled Laborer Apprenticeship when that standard is implemented).

<u>Eligibility and Duration:</u> To the employing contractor, for the length of time the TrANS graduate is in apprentice status.

- Contract Go al: To maintain the intent of the Equal Employment Opportunity program, it is a goal that <u>3</u> (number) TrANS Apprentice(s) be utilized on this contract.
 - The maximum duration of reimbursement is two years as a TrANS graduate plus time in apprentice status.
 - 4) If a TrANS program is not available in the contractor's area and another training program is utilized, payment of On-the-Job Training hours may be approved by the Wisconsin Department of Transportation (WisDOT) if the training program meets the established acceptance criteria. Only On-the-Job Training Hours accumulated after WisDOT approval will be reimbursed as specified under Items ASP.1T0G and ASP.1T0A. For more information, contact the Disadvantaged Business Enterprise Office at the phone numbers listed above.
 - 5) WisDOT reserves the right to deny payments under items ASP.1T0G and ASP.1T0A if the contractor either fails to provide training or there is evidence of a lack of good faith in meeting the requirements of this training special provision.

I. RATIONALE AND SPECIAL NOTE

The \$5.00 per hour now being paid for TrANS placements is intended to cover the duration of two years to allow for reaching entry-level laborer status. An additional incentive, the \$5.00 rate, would promote movement into the underutilized skilled trades' apprenticeships and applies until the individual completes their apprenticeship. These incentives benefit TrANS candidates by giving them a better opportunity to enter a skilled trade; benefits contractors who will be assisted in meeting their EEO profiles and goals; and benefits the public who will see the program reinforce larger public-private employment reform in Wisconsin. The pool of TrANS graduates was created for the purpose of addressing underutilization in the skilled trades, an objective that is further reinforced by a parallel retention pilot program, known as the Companywide Reporting. Whether or not reimbursement is involved, the WisDOT reassures contractors who are in the Companywide Program that TrANS placements still contribute toward fulfilling the new hire goal of 50% women and minorities. Based on data administered by United States Department of Labor (US DOL), the highway skilled trades remain underutilized for women statewide (less than 6.9%); and for minorities in all counties (% varies by county).

<u>NOTE</u>: Unless using other advancement strategies, contractors are encouraged to use some or all of this monetary incentive to offset the cut in hourly wages an individual may incur when entering an apprenticeship if the full general laborer hourly rate has been previously paid. No special accounting measures are required.

II. IMPLEMENTATION

The implementation of ASP 1 is intended to cover only the amount of time it takes for underutilization to be resolved across the trades. This will be measured annually at the county and/or state levels using data administered by WisDWD in relation to goals set by the USDOL-

OFCCP. With appropriate state and federal approvals, we may also do some measurement at the company level.

It is the contractor's responsibility to note on their Certified Payrolls if their employee is a TrANS graduate or a TrANS apprentice. The District EEO Coordinators utilize the information on the Certified Payrolls to track the hours accumulated by TrANS Graduates and TrANS apprentices on WisDOT contracts. Payment under this ASP 1 is made based on the hours recorded off of the Certified Payrolls. Tracking may eventually include improved linkages with the WisDWD apprentice database, information from company and committee level sources.

TrANS is nondiscriminatory by regulation, and is a tool for optional use by contractors to address the underutilization of women and minorities as laborers and apprentices in our industry's skilled trades.

IV. TRANS TRAINING

As part of the contractor's equal employment opportunity affirmative action program, training shall be provided to employees enrolled in apprenticeship and on-the-job training programs as follows:

The contractor shall provide on-the-job training aimed at developing full journey workers in the type of trade or job classifications involved. In the event the contractor subcontracts a portion of the contract work, the contractor shall determine how many, if any, of the trainees are to be trained by the subcontractor provided, however, that the contractor shall retain the primary responsibility for meeting the training requirements imposed by this special provision. The contractor shall also insure that this training special provision is made applicable to such subcontract.

Training and upgrading of minorities and women toward journey workers status is a primary objective of this training special provision. Accordingly, the contractor shall make every effort to enroll minority trainees and women (e.g., by conducting systematic and direct recruitment through public and private sources likely to yield minority trainees and women trainees); to the extent such persons are available within a reasonable area of recruitment. The contractor will be given an opportunity and will be responsible for demonstrating the steps that they have taken in pursuance thereof, prior to determination as to whether the contractor is in compliance with this training special provision. This training commitment is not intended, and shall not be used, to discriminate against any applicant for training, whether a member of a minority group or not.

No employee shall be employed as a trainee in any classification in which they have successfully completed a training course leading to journey workers status or in which they have been employed as a journey worker. The contractor should satisfy this requirement by including appropriate questions in the employee application or by other suitable means. Regardless of the method used, the contractor's records should document the findings in each case.

V. APPRENTICESHIP TRAINING

The Federal Highway Administration's (FHWA) policy is to require full use of all available training and skill improvement opportunities to assure increased participation of minority groups, disadvantaged persons and women in all phases of the highway construction industry. The FHWA On-the-Job Training (OJT) Program requires the State transportation agencies (STAs) to establish apprenticeships and training programs targeted to move women, minorities, and disadvantaged individuals into journey-level positions to ensure that a competent workforce is available to meet highway construction hiring needs, and to address the historical underrepresentation of members of these groups in highway construction skilled crafts.

The OJT Supportive Services (OJT/SS) Program was established in Title 23 Code of Federal Regulations (CFR), Part 230) to supplement the OJT program and support STA training programs by providing services to highway construction contractors and assistance to highway construction apprentices and trainees. The primary objectives of OJT/SS are:

- (1) To increase the overall effectiveness of the State highway agencies' approved training programs.
- (2) To seek other ways to increase the training opportunities for women, minorities, and disadvantaged individuals.

The STAs are responsible for establishing procedures, subject to the availability of Surface Transportation and Bridge Funds under 23 U.S.C. §140(b) (Nondiscrimination), for the provision of supportive services with respect to training programs approved under 23 CFR, Part 230(a) (Equal Employment Opportunity on Federal and Federal-aid Construction Contracts – including Supportive Services).

The contractor and subcontractor shall maintain records to demonstrate compliance with these apprenticeship requirements. Reasonable exemptions and modifications to and from any or all of these requirements will be determined by the Wisconsin Department of Transportation-Civil Rights Office. A request for an exemption or modification, with justification, shall be made in writing, addressed to WisDOT Civil Rights Office, 4802 Sheboygan Avenue, P.O. Box 7965, Rm. 451, Madison, WI 53707.



06/15/2020 08:45:53



Proposal Schedule of Items

Page 16 of 16

Federal ID(s): WISC 2020351, WISC 2020356

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0458	SPV.0090	29.000		
	Special 02. Water Main 6-Inch	LF	·	·
0460	SPV.0090	2,200.000		
	Special 03. Construction Staking Sidewalk	LF	:	:
0462	SPV.0105			
	Special 01. Rectangular Rapid Flashing Beacon System STH 47 & Warrington Road	LS	LUMP SUM	<u> </u>
0464	SPV.0105			
	Special 02. Temporary Stream Diversion Pipe, Keshena Lake Outlet	LS	LUMP SUM	·
0466	SPV.0180	27,920.000		
	Special 01. Preparing Topsoil for Lawn Type Turf	SY	·	·
0468	ASP.1T0A	2,400.000		
	On-the-Job Training Apprentice at \$5.00/HR	HRS	5.00000	12,000.00
0470	ASP.1T0G	1,980.000		
	On-the-Job Training Graduate at \$5.00/HR	HRS	5.00000	9,900.00
	Section: 000	1	Total:	<u> </u>
			Total Bid:	



Wisconsin Department of Transportation

June 25, 2020

Division of Transportation Systems Development

Bureau of Project Development 4822 Madison Yards Way, 4th Floor South Madison, WI 53705

Telephone: (608) 266-1631 Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

Proposal #11: 9650-17-61, WISC 2020 351

Shawano - Neopit

Wolf River Bridge B-73-0004

STH 47

Menominee County

9650-17-70, WISC 2020 356

Shawano - Neopit

Duquaine Rd to N Jct of CTH VV

STH 47

Menominee County

Letting of July 14, 2020

This is Addendum No. 02, which provides for the following:

Schedule of Items:

Revised Bid Item Quantities						
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total	
690.0150	Sawing Asphalt	LF	26,462	-454	26,008	

Added Bid Item Quantities						
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total	
204.0115	Removing Asphaltic Surface Butt Joints	SY	0	578	578	

Plan Sheets:

Revised Plan Sheets			
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)		
193	Miscellaneous Quantities (added Removing Asphaltic Surface Butt Joints item at numerous locations)		
241	Miscellaneous Quantities (revised Sawing Asphalt quantities)		
242	Miscellaneous Quantities (revised Sawing Asphalt quantities)		
243	Miscellaneous Quantities (revised Sawing Asphalt quantities)		

Added Plan Sheets				
Plan	Dian Chart Title (brief description of why sheet was added)			
Sheet	Plan Sheet Title (brief description of why sheet was added)			
17A	Construction Details (added butt joint details)			
193A	Miscellaneous Quantities (items were previously on Sheet 193 but had to be moved due to			
	space limitations)			

Schedule of Items

Attached, dated June 25, 2020, are the revised Schedule of Items Pages 14 and 16.

Plan Sheets

The following $8\frac{1}{2}$ x 11-inch sheets are attached and made part of the plans for this proposal:

Revised: 193, 241, 242, and 243.

Added: 17A, 193A.


The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist Proposal Management Section

END OF ADDENDUM



REMOVING PAVEMENT	0000		KEMOVIN	REMOVING ASPHALTIC SURFACE MILLING	URFACE MI	ITING		00707	
	Z04.0100 REMOVING PAVEMENT						YY	REMOVING ASPHALTIC	
	SY 40F		1. 6	NOTA	i c	FASS	NTS (E	SURFACE	
215+12 - 212+49 215+25 - 215+67	124		o IAGE	. .	146+00	STH 47 LT, 2.5" DEPTH		9200	
TAGE 2 S	229				82+55 9+32 'A'	STH 47 LT	7 5 5 7		
3 9650-17-70						HIGH SCHOOL DRIVEWAY	788 288 288		
- 106+60	17					BROOKS LN	۲ پ	i	
	16			9+15 'H' -	9+25 'H' TI	TRIBAL OFFICE LOOP RD (S)	- 88 - 人		
116+17 - 116+40	26 9					STAGE 3 SUBTOTAL		9,200	
	n [4	82+45 -	146+00	STH 47 RT, 2.5" DEPTH		10.200	
,	: =		-	82+45 -	82+55	STH 47 RT	7 15	0	
,	6			14+28 'B' -	14+38 'B'	WARRINGTON RD	~ 24 人	1	
	10				10+89 'C'	CHIEF LITTLE WAVE RD	35	1	
149+89 - 150+00	13				10+70 E	CHIEF CARRON RD	¥ 8	-	
STAGE 3 SUBTOTAL	77.			10+86 F - 10+74 'G' - 10+74 'G	10+96 F. 10+84 'G'	WOLF CI OUR CHILDRENS RD	₹		
PROJECT 9650-17-61 TOTAL PROJECT 9650-17-70 TOTAL	229					STAGE 4 SUBTOTAL	\ \ \ \	10,200	
	į		2	158+00 -	221+50	STH 47 RT, 2.5" DEPTH	\ - 	11,100	
					11+30 'L'	BLACKSMITH RD	ر 4 ال	- 1	
					11+20 'N'	RABBIT RIDGE RD	18	1	
				10+64 'Q' -	10+74 'Q'	STH 55	₹ 23 %	1	
					13+03 R	OSHNOSH ND	8 7		
				- 0++177	06+1.77	STAGE 5 SUBTOTAL	13 7	11 100	
								2	
			9	158+00 -	221+50	STH 47 LT, 2.5" DEPTH	イース	12,100	
					9+15 'M'	LYONS RD (S)	ZZ	1	
					9+80 'O'	LYONS RD (N)	22	1	
					9+32 'P'	WOLF RIVER DR	了 25 人	ı	
				9+22 C	9+32 'Q'	COURTHOUSE LN	36		
		II F			10+10 K	CIR VV (N)	8 8	<	
		D 9 Rev		04+177	00+177	STAGE 6 SUBTOTAL	人 181 人	12,100	
		965 /is							
		50 ed	PROJECT 9(PROJECT 9650-17-70 TOTAL			678	42,600	
		-17 I Sł					5		
		No '-70 nee 020					l J		
) et 1:							
						ALL ITEMS ARE CATEGORY 0010 UNLESS OTHERWISE SPECIFIED.	RY 0010 UNLES	S OTHERWISE SP	ECIFIED.


	STAGE STATION - STATION 1 154+03 - 154+36 3 9+00 - 9+32 131+48 - 131+83 E 132+05 - 14+38 112+66 - 171+69 112+66 - 175+60 125+53 - 178+66 1179+80 - 180+13 197+93 209+57 PROJECT 9850-17-70 TOTAL	20 REIN STOR (SIZE)	I PROJECT LOCATION	9650-17-70 9650-17-70	103+20 9650-17-70 NE CORNER STH 47/WARRINGTON RD	9650-17-70 CROSS STH 47	9650-17-70	9650-17-70 STH 47, RT	133+6/ 9550-17-70 STH 47, KI 14, 14, 14, 134+8/ 9550-17-70 STH 47, RT	9650-17-70	9650-17-70	9650-17-70 CROSS CTH VV	215+40 9650-17-61 NWCORNER B-73-004 29 215+61 9650-17-61 NE CORNER B-73-004 27		PROJECT 9630-17-61 101AL PROJECT 9650-17-70 TOTAL																
등다 프로그 뜨겁로 다른 다른 하는 무슨	1	ZU4JT3U REMOVING CURB & GUTTER LF 44	STAGE 1 SUBTOTAL 44 ST.	MORRIN ST, LT/RT 66			STAGE 3 SUBTOTAL 292), LT	STH 47, RI 190 STH 47 RT 834	STH 47, RT 9		OUR CHILDRENS RD NE RADIUS, STH 47, RT 408 STH 47 RT 39	AGE 4 S UBTOTAL 1,917	36		STH 55 NE RADIUS, STH 47, RT STH 55 NW RADIUS, STH 47 RT 17	STOTAL	AIRGROUNDS RD SE RADIUS, STH 47 LT 113	S TAGE 6 S UBTOTAL 225	3,050										

		က					
						Addendum No. 02 ID 9650-17-70 Revised Sheet 241 June 25, 2020	ALL ITEMS ARE CATEGORY 0010 UNLESS OTHERWISE SPECIFIED.
690.0250 SAWING CONCRETE LF			1 1 1 1		2 1 1 1 1 1 1 2 1 1 1 2 1 1 1 2 1 1 1 2 1 1 1 2 1 1 1 1 2 1 1 1 2 1 1 1 1 2 1 1 1 1 1 2 1	5 5 8 8 8 8 8 8 8 8 8 8 8 8 8 8 8 8 8 8	010 UNI ESS OTHE
690.0150 SAWING ASPHALT	70 2 5 5 7	2 2 2 2 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4	13 to 15 to	24 33 34 24 24 24 329 329	23 24 2 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4	235 112 24 24 258 258 470 17 17 17	ARE CATEGORY OC
LOCATION	STH 47, RT STH 47, CROSS STH 47, CROSS	STH 47, LT STH 47, RT DRIVEWAY, RT	STH 47, CROSS STH 47, CROSS STH 47, LT STH 47, RT STH 47, CROSS	STH 47, CROSS STH 47, LT STH 47, LT STH 47, RT DRIVEWAY, RT DRIVEWAY, RT CHIEF LITTLE WAVE RD STH 47, CROSS STH 47, CROSS STH 47, LT	STH 47, RT DRIVEWAY, RT STH 47, CROSS STH 47, CROSS STH 47, LT STH 47, LT MORRIN ST, CROSS MORRIN ST DRIVEWAY, LT CONCRETE CURB AND GUTTER CONCRETE CURB AND GUTTER STH 47, CROSS STH 47, CROSS STH 47, CROSS	STH 47, CROSS STH 47, CROSS STH 47, CROSS STH 47, RT / WOLF CT, RT STH 47, RT / WOLF CT, RT STH 47, RT STH 47, RT STH 47, LT CONCRETE SIDEWALK, LT/RT	ALL ITEMS
SAMNG PAVEMENT (CONT.) STATION STATION	- 105+45 105+55	105+55 - 107+95 105+55 - 107+95 106+66 - 107+13	107-95 108-05 108-05 - 109-80 108-05 - 109-80 109-80	109+90	116+45 116+55 - 9D+00 121+00 125+50 125+60	125+60 - 127+95 126+85 - 127+95 127+95 128+05 - 10F+96 128+05 - 10F+96 128+05 - 128+75 129+53 - 128+75 129+27 - 129+44 10F+49 SUBTOTAL	
690.0250 SAWING CONCRETE LF	10 4 -					:	
690.0150 SAWING ASPHALT		28 8 6	25 560 70 108 74 75 75 75 75 75 75 75 75 75 75 75 75 75	25 25 24 2 25 25 25 25 25 25 25 25 25 25 25 25 2	2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2	24 322 322 322 322 411 411 105 5,337 5,337	
LOCATION	CONCRETE SIDEWALK, LT/RT CONCRETE CURB AND GUTTER, LT/RT STH 47. CROSS	STH 47, LT STH 47, LT STH 47, CROSS	STH 47, CROSS STH 47, LT STH 47, RT DODGE RD STH 47, CROSS	STH 47, CROSS STH 47, LT STH 47, RT STH 47, CROSS STH 47, CROSS STH 47, LT STH 47, RT DRIVEWAY, RT STH 47, CROSS	STH 47, CROSS STH 47, LT STH 47, CROSS	STH 47, CROSS STH 47, LT STH 47, RT DRIVEWAY, LT SCHOOL ENTRANCE WARRINGTON RD CONCRETE SIDEWALK RT STH 47, CROSS STH 47, CROSS STH 47, LT	
SAWING PAVEMENT STATION STATION	82+46 82+46 82+46	82+46 - 82+74 82+46 - 82+74 82+74	82+84 - 88+44 82+84 - 88+44 82+84 - 88+44 83+19 - 83+37 88+44	88+53 - 91+12 88+53 - 91+12 91+12 - 91+22 91+22 - 93+57 92+16 - 92+41	93+67 - 94+15 93+67 - 94+15 94+15 - 94+15 94+25 - 97+15 94+26 - 97+15 94+26 - 97+15 97+25 - 100+11 97+25 - 100+11	100+21 - 103-43 100+21 - 103-43 100+21 - 103-43 101+51 - 101+72 108-98 - 118-37 128-40 - 148-38 103+22 - 105-45 103-53 - 105-45 SUBTOTAL	

				~	_	_																		•								II F) S	969 Vis		-1 [°] S	n No. 02 7-70 Sheet 242 2020	ALL ITEMS ARE CATEGORY 0010 LINI ESS OTHERWISE SPECIEIED	
690.0250 SAWING CONCRETE	ㅂ	4	1	1 0	o m	» m	4	22	1	1	:					1	;	!	1	1	:	ı		:		:	:	1			1	1	!			:	22	LINI ESS OF	HLLIO
690.0150 SAWING ASPHALT	۳	(ス		ce ce		۲ ا	マ :		く 25 し	25	~ 35 人	~ 45 45 45 47 47 47 47 47 47 47 47 47 47 47 47 47	Y 141	人 5 5 5 7	33 33	Z6 Z	人 524	く 574 ノ	23 🗸	~ ® 人	? ※ シ	۲ ۶ ;	~ 36 347 7	8 2	2 81	75 ~	人 15 15 15 15		28 8 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6	~ 8 8 人	~ 205 人	24 🔨	248	~ 430 人	~ 22	27 ≺	6,448	RE CATEGORY OF	
	LOCATION	CONCRETE CURB AND GUTTER, LT/RT	STH 47, LT	CONCEETE SEEMIN DE	CONCRETE SIDEWALK, KI	CONCRETE SIDEWALK, RT	CONCRETE SIDEWALK, RT	CONCRETE SIDEWALK, RT	DRIVEWAY, LT	DRIVEWAY, LT	STH 47, CROSS	STH 47, CROSS	N ACKSMITH DO I	STH 47. LT	STH 47. CROSS	STH 47, CROSS	STH 47, LT	STH 47, RT	LYONS RD, LT	LYONS RD, RT	LYONS RD (SOUTH), CROSS	SITH 47, CKOSS	STH 47 RT	RABBIT BINGE CROSS	RABBIT RIDGE, CROSS	RABBIT RIDGE, LT	RABBIT RIDGE, RT	SIH4/, LI	SIH 47, KI STH 47, CDOSS	STH 47, CROSS	STH 47, RT	DRIVEWAY, RT	SIH 47, LI / LYONS KD (NOKIH), KI	LYONS RD (NORTH), LT / STH 47, LT	STH 47, CROSS	STH 47, CROSS		ALI ITEMS A	2011
SAWING PAVEMENT (CONT.)	STATION STATION	8K+91		15/+63 - 163+28	158+95	159+63	161+42	162+33	163+23 - 163+48	163+99 - 164+24	163+21	163+33	111 +30 - 165+07		165+08	165+19	165+19 - 167+73	165+19 - 167+93	9M+05 - 9M+63	9M+05 - 9M+74	9M+68	167+84	168+06 - 171+41	10N+37	10N+47			16/+85 - 1/5+5/	175,57	176+14	176+18 - 185+20	178+84	170-85 - 80+70		185+20	185+30	SUBTOTAL		
690.0250 SAWING CONCRETE	ㅂ	•		; ч	o		:	1				ı		: :	;		:	:	:	:	:	:	¦ ლ	30	S 60	;	;	: 5	<u>s</u> 6	2 :	;	;	m m	ກເດ	:	78			
690.0150 SAWING ASPHALT	ر لا	く 282 く	~ 115 ~ 7.5 ~	8	: 8	ン 54 54	24	人 24	~ 096 人	360	人 15 一	ン 25 26 7 7	3000	24	24	Y ? ノ	102	~ 88 人	24		~ 212 人	→ 50 	₹ :	- - - -	~ : : ·		\ \tag{2}	₹ 8 •	\ : :	<u></u>	人 (8)	\ \ \ \	\ ' _		~ 28 ~	3,734	3		
	LOCATION	STH 47, RT	BROOKS LN	CONCRETE SIDEWALK LT	OUR CHILDRENS RD CROSS	STH 47. LT	STH 47, CROSS	STH 47, CROSS	STH 47, LT	STH 47, RT	STH 47, CROSS	STH 47, CROSS	STH 47 DT	STH 47, CROSS	STH 47, CROSS	STH 47, LT	STH 47, RT	STH 47, LT	STH 47, CROSS	STH 47, CROSS	STH 47, LT	SIT 47, KI	CONCRETE SIDEWAIK IT	CONCRETE SIDEWALK RT	CONCRETE SIDEWALK, LT	ASPHALT SIDEWALK, RT	DRIVEWAY, RT	I RIBAL OFFICE LOOP RD (NORTH), CROSS	DRIVEWAY, LI	DRIVEWAY, ET	DRIVEWAY, LT	CTH VV, CROSS	CONCRETE SIDEWALK, KI	CONCRETE SIDEWALK, IT	FAIRGROUNDS RD, CROSS				
SAWING PAVEMENT (CONT.)	STATION STATION			105+64 - 105+64	10.5+84	132+21 - 132+75	132+75	132+85	132+85 - 136+45	132+85 - 136+45	136+45	136+55	136+55 - 139+61	139+61	139+73	139+73 - 140+04	139+73 - 140+75	140+24 - 140+75	140+75	140+85			144+48 - 144+72 144+78	145+47 - 145+77	146+19		147+66	91+19				111434	155+36	156+60	8K+91	SUBTOTAL			

3 243 **E** wsdot/cadds sheef 41 ALL ITEMS ARE CATEGORY 0010 UNLESS OTHERWISE SPECIFIED. Addendum No. 02 ID 9650-17-70 Revised Sheet 243 June 25, 2020 0050 0010 0010 0010 LANE SHIFT SPV.0060.04 EACH C-73-0004 CULVERT @ STA 139+67 CULVERT @ STA 175+75 CULVERT @ STA 200+35 PROJECT 9650-17-70 TOTAL LANE SHIFT STAGE 690.0250 SAWING CONCRETE 690.0150 SAWING ASPHALT 349 346 27 27 73 228 243 29 29 724 5,001 35 14 113 136 428 38 38 28 STH 47, CROSS
STH 47, CROSS
STH 47, LT
STH 4 STH 47, LT STH 47, RT STH 47, RT STH 47, LT STH 47, RT STH 47, RT STH 47, LT SAWING PAVEMENT (CONT.) 188+79 188+76 191+18 191+06 195+24 192+62 194+66 195+49 207+68 205+92 212+12 219+06 219+57 189+62 189+42 195+86 200+21 200+20 PROJECT 9650-17-70 TOTAL 195+58 188+77 187+87 189+53 189+92 191+15 191+26 200+52 185+30 185+30 191+29 192+20 193+90 197+93 197+77 188+89 188+86 190+05 189+75 200+52 200+53 210+36 215+66 191+21 195+59 215+80







Proposal Schedule of Items

Page 14 of 16

Federal ID(s): WISC 2020351, WISC 2020356

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0400	659.1120 Luminaires Utility LED B	78.000 EACH		
0402	659.2130 Lighting Control Cabinets 120/240 30- Inch	2.000 EACH		·-
0404	661.0100 Temporary Traffic Signals for Bridges (structure) 01. B-73-0004	LS	LUMP SUM	·
0406	661.0100 Temporary Traffic Signals for Bridges (structure) 02. C-73-0004	LS	LUMP SUM	·
0408	661.0100 Temporary Traffic Signals for Bridges (structure) 03. Culvert STA. 175+75	LS	LUMP SUM	
0410	661.0100 Temporary Traffic Signals for Bridges (structure) 04. Culvert STA. 200+35	LS	LUMP SUM	·
0412	690.0150 Sawing Asphalt	26,008.000 LF	·	·
0414	690.0250 Sawing Concrete	147.000 LF		
0416	715.0415 Incentive Strength Concrete Pavement	500.000 DOL	1.00000	500.00
0418	715.0502 Incentive Strength Concrete Structures	500.000 DOL	1.00000	500.00
0420	740.0440 Incentive IRI Ride	21,340.000 DOL	1.00000	21,340.00
0422	SPV.0060 Special 01. Salvage Existing Light Pole Assembly	13.000 EACH	<u> </u>	<u> </u>
0424	SPV.0060 Special 02. Light Pole Type 5 Special	22.000 EACH		
0426	SPV.0060 Special 03. Lighting Control Cabinet 120/240 30-Inch Special	3.000 EACH		<u> </u>
0428	SPV.0060 Special 04. Lane Shift	5.000 EACH		



Proposal Schedule of Items

Page 16 of 16

Federal ID(s): WISC 2020351, WISC 2020356

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0458	SPV.0090 Special 02. Water Main 6-Inch	29.000 LF	·	
0460	SPV.0090 Special 03. Construction Staking Sidewalk	2,200.000 LF	·	·
0462	SPV.0105 Special 01. Rectangular Rapid Flashing Beacon System STH 47 & Warrington Road	LS	LUMP SUM	·
0464	SPV.0105 Special 02. Temporary Stream Diversion Pipe, Keshena Lake Outlet	LS	LUMP SUM	·
0466	SPV.0180 Special 01. Preparing Topsoil for Lawn Type Turf	27,920.000 SY		·
0468	ASP.1T0A On-the-Job Training Apprentice at \$5.00/HR	2,400.000 HRS	5.00000	12,000.00
0470	ASP.1T0G On-the-Job Training Graduate at \$5.00/HR	1,980.000 HRS	5.00000	9,900.00
0472	204.0115 Removing Asphaltic Surface Butt Joints	578.000 SY		
	Section: 000)1	Total:	·

Total Bid:



Wisconsin Department of Transportation

Division of Transportation Systems Development

Bureau of Project Development 4822 Madison Yards Way, 4th Floor South Madison, WI 53705

Telephone: (608) 266-1631 Facsimile (FAX): (608) 266-8459

July 9, 2020

NOTICE TO ALL CONTRACTORS:

Proposal #11: 9650-17-61, WISC 2020 351

Shawano - Neopit

Wolf River Bridge B-73-0004

STH 47

Menominee County

9650-17-70, WISC 2020 356

Shawano - Neopit

Duquaine Road to N Jct County VV

STH 47

Menominee County

Letting of July 14, 2020

This is Addendum No. 03, which provides for the following:

Special Provisions:

	Revised Special Provisions
Article No.	Description
33	Fence Chain Link Salvage 5-ft

Schedule of Items:

	Revised Bid Item Quantitie	es			
Bid Item	Item Description	Unit	Old	Revised	Proposal
Did itelli	item Description	Offic	Quantity	Quantity	Total
201.0105	Clearing	STA	57.5	19.5	77
201.0205	Grubbing	STA	57.5	19.5	77

Plan Sheets:

	Revised Plan Sheets
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
192	Miscellaneous Quantities (revised Clearing and Grubbing quantities)

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist Proposal Management Section

ADDENDUM NO. 03 9650-17-70 July 9, 2020

Special Provisions

33. Fence Chain Link Salvage 5-ft

Replace paragraph three with the following:

(3) Remove entire fence system (including grout within sleeve) to complete deck repairs and to replace failing and deteriorated fence components. Pipe sleeves that required deck removal for replacement shall be paid for as "Concrete Surface Repair""

Schedule of Items

Attached, dated July 9, 2020, are the revised Schedule of Items Page 1.

Plan Sheets

The following $8\frac{1}{2}$ x 11-inch sheets are attached and made part of the plans for this proposal: Revised: 192.

END OF ADDENDUM

11+00 102+00


122+00 133+00 141+00 144+00

146+00

155+00 162+00 168+00 175+00

182+00 00+6







Proposal Schedule of Items

Page 1 of 16

Federal ID(s): WISC 2020351, WISC 2020356

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0002	201.0105 Clearing	77.000 STA	·	
0004	201.0205 Grubbing	77.000 STA		
0006	203.0100 Removing Small Pipe Culverts	26.000 EACH	·	
8000	203.0600.S Removing Old Structure Over Waterway With Minimal Debris (station) 01. 154+20	LS	LUMP SUM	
0010	204.0100 Removing Concrete Pavement	351.000 SY		·
0012	204.0120 Removing Asphaltic Surface Milling	42,600.000 SY	·	·
0014	204.0150 Removing Curb & Gutter	3,050.000 LF		·
0016	204.0155 Removing Concrete Sidewalk	3,770.000 SY		
0018	204.0165 Removing Guardrail	885.000 LF		·
0020	204.0190 Removing Surface Drains	2.000 EACH		
0022	204.0220 Removing Inlets	14.000 EACH		·
0024	204.0245 Removing Storm Sewer (size) 01. 12-Inch	70.000 LF		
0026	204.0245 Removing Storm Sewer (size) 02. 15-Inch	298.000 LF		
0028	204.0245 Removing Storm Sewer (size) 03. 18-Inch	434.000 LF	·	·
0030	205.0100 Excavation Common	20,836.000 CY		