#### HIGHWAY WORK PROPOSAL

Wisconsin Department of Transportation 06/2017 s.66.0901(7) Wis. Stats

STATE PROJECT

COUNTY

Notice of Award Dated

**HIGHWAY** 

Proposal Number:

Milwaukee 1228-28-70 WISC 2020412 Hillside Interchange; W Wisconsin To IH 043

**FEDERAL** 

W Walnut St

PROJECT DESCRIPTION

# ADDENDUM REQUIRED

## ATTACHED AT BACK

This proposal, submitted by the undersigned bidder to the Wisconsin Department of Transportation, is in accordance with the advertised request for proposals. The bidder is to furnish and deliver all materials, and to perform all work for the improvement of the designated project in the time specified, in accordance with the appended Proposal Requirements and Conditions.

Proposal Guaranty Required: \$100,000.00 Attach Proposal Guaranty on back of this PAGE. Payable to: Wisconsin Department of Transportation Firm Name, Address, City, State, Zip Code Bid Submittal Date: September 15, 2020 SAMPLE Time (Local Time): 9:00 am NOT FOR BIDDING PURPOSES **Contract Completion Time** September 30, 2021 This contract is exempt from federal oversight. Assigned Disadvantaged Business Enterprise Goal 12%

This certifies that the undersigned bidder, duly sworn, is an authorized representative of the firm named above; that the bidder has examined and carefully prepared the bid from the plans, Highway Work Proposal, and all addenda, and has checked the same in detail before submitting this proposal or bid; and that the bidder or agents, officer, or employees have not, either directly or indirectly, entered into any agreement, participated in any collusion, or otherwise taken any action in restraint of free competitive bidding in connection with this proposal bid.

For Department Use Only
Excavation, Base, Concrete Pavement, Curb and Gutter, Sidewalk, Signs, Pavement Marking, Bridge Rehabilitation, Street Lighting.

**Date Guaranty Returned** 

# PLEASE ATTACH PROPOSAL GUARANTY HERE

#### **Effective with November 2007 Letting**

### PROPOSAL REQUIREMENTS AND CONDITIONS

The bidder, signing and submitting this proposal, agrees and declares as a condition thereof, to be bound by the following conditions and requirements.

If the bidder has a corporate relationship with the proposal design engineering company, the bidder declares that it did not obtain any facts, data, or other information related to this proposal from the design engineering company that was not available to all bidders.

The bidder declares that they have carefully examined the site of, and the proposal, plans, specifications and contract forms for the work contemplated, and it is assumed that the bidder has investigated and is satisfied as to the conditions to be encountered, as to the character, quality, and quantities of work to be performed and materials to be furnished, and as to the requirements of the specifications, special provisions and contract. It is mutually agreed that submission of a proposal shall be considered conclusive evidence that the bidder has made such examination.

The bidder submits herewith a proposal guaranty in proper form and amount payable to the party as designated in the advertisement inviting proposals, to be retained by and become the property of the owner of the work in the event the undersigned shall fail to execute the contract and contract bond and return the same to the office of the engineer within fourteen (14) days after having been notified in writing to do so; otherwise to be returned.

The bidder declares that they understand that the estimate of quantities in the attached schedule is approximate only and that the attached quantities may be greater or less in accordance with the specifications.

The bidder agrees to perform the said work, for and in consideration of the payment of the amount becoming due on account of work performed, according to the unit prices bid in the following schedule, and to accept such amounts in full payment of said work.

The bidder declares that all of the said work will be performed at their own proper cost and expense, that they will furnish all necessary materials, labor, tools, machinery, apparatus, and other means of construction in the manner provided in the applicable specifications and the approved plans for the work together with all standard and special designs that may be designed on such plans, and the special provisions in the contract of which this proposal will become a part, if and when accepted. The bidder further agrees that the applicable specifications and all plans and working drawings are made a part hereof, as fully and completely as if attached hereto.

The bidder, if awarded the contract, agrees to begin the work not later than ten (10) days after the date of written notification from the engineer to do so, unless otherwise stipulated in the special provisions.

The bidder declares that if they are awarded the contract, they will execute the contract agreement and begin and complete the work within the time named herein, and they will file a good and sufficient surety bond for the amount of the contract for performance and also for the full amount of the contract for payment.

The bidder, if awarded the contract, shall pay all claims as required by Section 779.14, Statutes of Wisconsin, and shall be subject to and discharge all liabilities for injuries pursuant to Chapter 102 of the Statutes of Wisconsin, and all acts amendatory thereto. They shall further be responsible for any damages to property or injury to persons occurring through their own negligence or that of their employees or agents, incident to the performance of work under this contract, pursuant to the Standard Specifications for Road and Bridge Construction applicable to this contract.

In connection with the performance of work under this contract, the contractor agrees to comply with all applicable state and federal statutes relating to non-discrimination in employment. No otherwise qualified person shall be excluded from employment or otherwise be subject to discrimination in employment in any manner on the basis of age, race, religion, color, gender, national origin or ancestry, disability, arrest or conviction record (in keeping with s.111.32), sexual orientation, marital status, membership in the military reserve, honesty testing, genetic testing, and outside use of lawful products. This provision shall include, but not be limited to the following: employment, upgrading, demotion or transfer; recruitment or recruitment advertising; layoff or termination; rates of pay or other forms of compensation, and selection for training, including apprenticeship. The contractor further agrees to ensure equal opportunity in employment to all applicants and employees and to take affirmative action to attain a representative workforce.

The contractor agrees to post notices and posters setting forth the provisions of the nondiscrimination clause, in a conspicuous and easily accessible place, available for employees and applicants for employment.

If a state public official (section 19.42, Stats.) or an organization in which a state public official holds at least a 10% interest is a party to this agreement, this contract is voidable by the state unless appropriate disclosure is made to the State of Wisconsin Ethics Board.

#### **Effective with August 2015 Letting**

# BID PREPARATION

#### Preparing the Proposal Schedule of Items

#### A General

- (1) Obtain bidding proposals as specified in section 102 of the standard specifications prior to 11:45 AM of the last business day preceding the letting. Submit bidding proposals using one of the following methods:
  - 1. Electronic bid on theinternet.
  - 2. Electronic bid on a printout with accompanying diskette or CD ROM.
  - 3. Paper bid under a waiver of the electronic submittal requirements.
- (2) Bids submitted on a printout with accompanying diskette or CD ROM or paper bids submitted under a waiver of the electronic submittal requirements govern over bids submitted on the internet.
- (3) The department will provide bidding information through the department's web site at: <a href="https://wisconsindot.gov/Pages/doing-bus/contractors/hcci/bid-let.aspx">https://wisconsindot.gov/Pages/doing-bus/contractors/hcci/bid-let.aspx</a>

The contractor is responsible for reviewing this web site for general notices as well as information regarding proposals in each letting. The department will also post special notices of all addenda to each proposal through this web site no later than 4:00 PM local time on the Thursday before the letting. Check the department's web site after 5:00 PM local time on the Thursday before the letting to ensure all addenda have been accounted for before preparing the bid. When bidding using methods 1 and 2 above, check the Bid Express<sup>TM</sup> on-line bidding exchange at <a href="http://www.bidx.com/">http://www.bidx.com/</a> after 5:00 PM local time on the Thursday before the letting to ensure that the latest schedule of items Expedite file (\*.ebs or \*.00x) is used to submit the final bid.

(4) Interested parties can subscribe to the Bid Express<sup>TM</sup> on-line bidding exchange by following the instructions provided at the www.bidx.com web site or by contacting:

Info Tech Inc. 5700 SW 34th Street, Suite 1235 Gainesville, FL 32608-5371 email: mailto:customer.support@bidx.com

- (5) The department will address equipment and process failures, if the bidder can demonstrate that those failures were beyond their control.
- (6) Contractors are responsible for checking on the issuance of addenda and for obtaining the addenda. Notice of issuance of addenda is posted on the department's web site at:

  <a href="https://wisconsindot.gov/Pages/doing-bus/contractors/hcci/bid-let.aspx">https://wisconsindot.gov/Pages/doing-bus/contractors/hcci/bid-let.aspx</a>

or by calling the department at (608) 266-1631. Addenda can ONLY be obtained from the departments web site listed above or by picking up the addenda at the Bureau of Highway Construction, 4<sup>th</sup> floor, 4822 Madison Yards Way, Madison, WI, during regular business hours

(7) Addenda posted after 5:00 PM on the Thursday before the letting will be emailed to the eligible bidders for that proposal. All eligible bidders shall acknowledge receipt of the addenda whether they are bidding on the proposal or not. Not acknowledging receipt may jeopardize the awarding of the project.

#### **B Submitting Electronic Bids**

#### B.1 On the Internet

- (1) Do the following before submitting the bid:
  - 1. Have a properly executed annual bid bond on file with the department.

- 2. Have a digital ID on file with and enabled by Info Tech Inc. Using this digital ID will constitute the bidder's signature for proper execution of the bidding proposal.
- (2) In lieu of preparing, delivering, and submitting the proposal as specified in 102.6 and 102.9 of the standard specifications, submit the proposal on the internet as follows:
  - 1. Download the latest schedule of items reflecting all addenda from the Bid Express TM web site.
  - 2. Use Expedite TM software to enter a unit price for every item in the schedule of items.
  - 3. Submit the bid according to the requirements of Expedite<sup>TM</sup> software and the Bid Express<sup>TM</sup> web site. Do not submit a bid on a printout with accompanying diskette or CD ROM or a paper bid. If the bidder does submit a bid on a printout with accompanying diskette or a paper bid in addition to the internet submittal, the department will disregard the internet bid.
  - 4. Submit the bid before the hour and date the Notice to Contractors designates.
  - Do not sign, notarize, and return the bidding proposal described in 102.2 of the standard specifications.
- (3) The department will not consider the bid accepted until the hour and date the Notice to Contractors designates.

#### B.2 On a Printout with Accompanying Diskette or CD ROM

(1) Download the latest schedule of items from the Wisconsin pages of the Bid Express<sup>TM</sup> web site reflecting the latest addenda posted on the department's web site at:

https://wisconsindot.gov/Pages/doing-bus/contractors/hcci/bid-let.aspx

Use Expedite TM software to prepare and print the schedule of items. Provide a valid amount for all price fields. Follow instructions and review the help screens provided on the Bid Express Web site to assure that the schedule of items is prepared properly.

(2) Staple an 8 1/2 by 11 inch printout of the Expedite<sup>TM</sup> generated schedule of items to the other proposal documents submitted to the department as a part of the bidder's sealed bid. As a separate submittal, not in the sealed bid envelop but due at the same time and place as the sealed bid, also provide the Expedite<sup>TM</sup> generated schedule of items on a 3 1/2 inch computer diskette or CD ROM. Label each diskette or CD ROM with the bidder's name, the 4 character department-assigned bidder identification code from the top of the bidding proposal, and a list of the proposal numbers included on that diskette or CD ROM as indicated in the following example:

**Bidder Name** 

**BN00** 

Proposals: 1, 12, 14, & 22

- (3) If bidding on more than one proposal in the letting, the bidder may include all proposals for that letting on one diskette or CD ROM. Include only submitted proposals with no incomplete or other files on the diskette or CD ROM.
- (4) The bidder-submitted printout of the Expedite<sup>TM</sup> generated schedule of items is the governing contract document and must conform to the requirements of section 102 of the standard specifications. If a printout needs to be altered, cross out the printed information with ink or typewriter and enter the new information and initial it in ink. If there is a discrepancy between the printout and the diskette or CD ROM, the department will analyze the bid using the printout information.
- (5) In addition to the reasons specified in section 102 of the standard specifications, proposals are irregular and the department may reject them for one or more of the following:
  - 1. The check code printed on the bottom of the printout of the Expedite TM generated schedule of items is not the same on each page.
  - 2. The check code printed on the printout of the Expedite<sup>TM</sup> generated schedule of items is not the same as the check code for that proposal provided on the diskette or CD ROM.

3. The diskette or CD ROM is not submitted at the time and place the department designates.

#### C Waiver of Electronic Submittal

- (1) The bidder may request a waiver of the electronic submittal requirements. Submit a written request for a waiver in lieu of bids submitted on the internet or on a printout with accompanying diskette or CD ROM. Use the waiver that was included with the paper bid document sent to the bidder or type up a waiver on the bidder's letterhead. The department will waive the electronic submittal requirements for a bidding entity (individual, partnership, joint venture, corporation, or limited liability company) for up to 4 individual proposals in a calendar year. The department may allow additional waivers for equipment malfunctions.
- (2) Submit a schedule of items on paper conforming to section 102 of the standard specifications. The department charges the bidder a \$75 administrative fee per proposal, payable at the time and place the department designates for receiving bids, to cover the costs of data entry. The department will accept a check or money order payable to: "Wisconsin, Dept. of Transportation."
- (3) In addition to the reasons specified in section 102 of the standard specifications, proposals are irregular and the department may reject them for one or more of the following:
  - 1. The bidder fails to provide the written request for waiver of the electronic submittal requirements.
  - 2. The bidder fails to pay the \$75 administrative fee before the time the department designates for the opening of bids unless the bidder requests on the waiver that they be billed for the \$75.
  - 3. The bidder exceeds 4 waivers of electronic submittal requirements within a calendar year.
- (4) In addition to the reasons specified in section 102 of the standard specifications, the department may refuse to issue bidding proposals for future contracts to a bidding entity that owes the department administrative fees for a waiver of electronic submittal requirements.

#### PROPOSAL BID BOND

DT1303 1/2006

Wisconsin Department of Transportation

Proposal Number	Project Number		Letting Date
Name of Principal			
Name of Surety		State in Which Surety is	Organized

We, the above-named Principal and the above-named Surety, are held and firmly bound unto the State of Wisconsin in the sum equal to the Proposal Guaranty for the total bid submitted for the payment to be made; we jointly and severally bind ourselves, our heirs, executors, administrators, successors and assigns. The condition of this obligation is that the Principal has submitted a bid proposal to the State of Wisconsin acting through the Department of Transportation for the improvement designated by the Proposal Number and Letting Date indicated above.

If the Principal is awarded the contract and, within the time and manner required by law after the prescribed forms are presented for signature, enters into a written contract in accordance with the bid, and files the bond with the Department of Transportation to guarantee faithful performance and payment for labor and materials, as required by law, or if the Department of Transportation shall reject all bids for the work described, then this obligation shall be null and void; otherwise, it shall be and remain in full force and effect. In the event of failure of the Principal to enter into the contract or give the specified bond, the Principal shall pay to the Department of Transportation within 10 business days of demand a total equal to the Proposal Guaranty as liquidated damages; the liability of the Surety continues for the full amount of the obligation as stated until the obligation is paid in full.

The Surety, for value received, agrees that the obligations of it and its bond shall not be impaired or affected by any extension of time within which the Department of Transportation may accept the bid; and the Surety does waive notice of any such extension.

IN WITNESS, the Principal and Surety have agreed and have signed by their proper officers and have caused their corporate seals to be affixed this date: **(DATE MUST BE ENTERED)** 

#### **PRINCIPAL**

(Company Name) (Affix Corpo	rate Seal)		
(Signature and Title)			
(Company Name)	<u> </u>		
(Signature and Title)			
(Company Name)	<u> </u>		
(Signature and Title)		(Name of Surety) (Affix Seal)	
(Company Name)		(Signature of Attorney-in-Fact)	
(Signature and Title)			
NOTARY F	OR PRINCIPAL	NOTARY FO	R SURETY
(	Date)	(Dat	te)
State of Wisconsin	)	State of Wisconsin	)
	) ss. County )		) ss. _County )
On the above date, this instrument was acknowledged before me by the named person(s).		On the above date, this instrument w named person(s).	as acknowledged before me by the
(Signature, Notary P	ublic, State of Wisconsin)	(Signature, Notary Publi	ic, State of Wisconsin)
(Print or Type Name, Notary Public, State of Wisconsin)		(Print or Type Name, Notary Public, State of Wisconsin)	
(Date Com	mission Expires)	(Date Commis	sion Expires)

Notary Seal Notary Seal

IMPORTANT: A certified copy of Power of Attorney of the signatory agent must be attached to the bid bond.

# **CERTIFICATE OF ANNUAL BID BOND**

DT1305 8/2003

Wisconsin Department of Transportation

(Date)

Time Period Valid (	From/To)
Name of Surety	
Name of Contractor	r
Certificate Holder	Wisconsin Department of Transportation
	y that an annual bid bond issued by the above-named Surety is currently on file with the eartment of Transportation.
	is issued as a matter of information and conveys no rights upon the certificate holder mend, extend or alter the coverage of the annual bid bond.
Cancellation:	Should the above policy be cancelled before the expiration date, the issuing surety will give thirty (30) days written notice to the certificate holder indicated above.

(Signature of Authorized Contractor Representative)

#### March 2010

#### LIST OF SUBCONTRACTORS

Section 66.0901(7), Wisconsin Statutes, provides that as a part of the proposal, the bidder also shall submit a list of the subcontractors the bidder proposes to contract with and the class of work to be performed by each. In order to qualify for inclusion in the bidder's list a subcontractor shall first submit a bid in writing, to the general contractor at least 48 hours prior to the time of the bid closing. The list may not be added to or altered without the written consent of the municipality. A proposal of a bidder is not invalid if any subcontractor and the class of work to be performed by the subcontractor has been omitted from a proposal; the omission shall be considered inadvertent or the bidder will perform the work personally.

No subcontract, whether listed herein or later proposed, may be entered into without the written consent of the Engineer as provided in Subsection 108.1 of the Standard Specifications.

Name of Subcontractor	Class of Work	Estimated Value	
			_
			_

#### **DECEMBER 2000**

# CERTIFICATION REGARDING DEBARMENT, SUSPENSION, AND OTHER RESPONSIBILITY MATTERS - PRIMARY COVERED TRANSACTIONS

## **Instructions for Certification**

- 1. By signing and submitting this proposal, the prospective contractor is providing the certification set out below.
- 2. The inability of a person to provide the certification required below will not necessarily result in denial of participation in this covered transaction. The prospective contractor shall submit an explanation of why it cannot provide the certification set out below. The certification or explanation will be considered in connection with the department or agency's determination whether to enter into this transaction. However, failure of the prospective contractor to furnish a certification or an explanation shall disqualify such person from participation in this transaction.
- 3. The certification in this clause is a material representation of fact upon which reliance was placed when the department determined to enter into this transaction. If it is later determined that the contractor knowingly rendered an erroneous certification in addition to other remedies available to the Federal Government the department may terminate this transaction for cause or default.
- 4. The prospective contractor shall provide immediate written notice to the department to whom this proposal is submitted if at any time the prospective contractor learns that its certification was erroneous when submitted or has become erroneous by reason of changed circumstances.
- 5. The terms "covered transaction," "debarred," "suspended," "ineligible," "lower tier covered transaction," "participant," "person," "primary covered transaction," "principal," "proposal," and "voluntarily excluded," as used in this clause, have the meanings set out in the Definitions and Coverage sections of the rules implementing Executive Order 12549. You may contact the department to which this proposal is being submitted for assistance in obtaining a copy of those regulations.
- 6. The prospective contractor agrees by submitting this proposal that, should this contract be entered into, it shall not knowingly enter into any lower tier covered transaction with a person who is debarred, suspended, declared ineligible, or voluntarily excluded from participation in this covered transaction, unless authorized by the department entering into this transaction.
- 7. The prospective contractor further agrees by submitting this proposal that it will include the clause titled "Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion-Lower Tier Covered Transaction," which is included as an addendum to PR-1273 "Required Contract Provisions Federal Aid Construction Contracts," without

modification, in all lower tier covered transactions and in all solicitations for lower tier covered transactions.

- 8. The contractor may rely upon a certification of a prospective subcontractor/materials supplier that it is not debarred, suspended, ineligible, or voluntarily excluded from the covered transaction, unless it knows that the certification is erroneous. A contractor may decide the method and frequency by which it determines the eligibility of its principals. Each contractor may, but is not required to, check the Disapproval List (telephone # 608/266/1631).
- 9. Nothing contained in the foregoing shall be construed to require establishment of a system of records in order to render in good faith the certification required by this clause. The knowledge and information of a contractor is not required to exceed that which is normally possessed by a prudent person in the ordinary course of business dealings.
- 10. Except for transactions authorized under paragraph 6 of these instructions, if a contractor in a covered transaction knowingly enters into a lower tier covered transaction with a person who is suspended, debarred, ineligible or voluntarily excluded from participation in this transaction, in addition to other remedies available to the Federal Government, the department may terminate this transaction for cause or default.

Certification Regarding Debarment, Suspension, and Other Responsibility Matters - Primary Covered Transactions

- (1) The prospective contractor certifies to the best of its knowledge and belief, that it and its principals:
  - (a) Are not presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from covered transactions by any Federal department or agency;
  - (b) Have not within a three-year period preceding this proposal been convicted of or had a civil judgment rendered against them for commission of fraud or a criminal offense in connection with obtaining, attempting to obtain, or performing a public (Federal, State or local) transaction or contract under a public transaction; violation of Federal or State antitrust statutes or commission of embezzlement, theft, forgery, bribery, falsification or destruction of records, making false statements or receiving stolen property;
  - (c) Are not presently indicted for or otherwise criminally or civilly charged by a governmental entity (Federal, State or local) with commission of any of the offense enumerated in paragraph (1)(b) of this certification; and
  - (d) Have not within a three-year period preceding this proposal had one or more public transactions (Federal, State or local) terminated for cause or default.
- (2) Where the prospective contractor is unable to certify to any of the statements in this certification, such prospective contractor shall attach an explanation to this proposal.

# **Special Provisions**

# **Table of Contents**

	Article	Description	Page #
1.	General		3
2.	Scope of Work		3
3.	Prosecution and Progress		3
4.	Lane Rental Fee Assessment		7
5.	Traffic		8
6.	Holiday Work Restrictions		9
7.	Utilities		10
8.	Other Contracts		13
9.	Railroad Insurance and Coordination - Soc	Line Railroad Company (CP)	14
10.	Contractor Notification		15
11.	Erosion Control		15
12.	Material Stockpile and Equipment Storage		16
13.	Information to Bidders, Use of Recovered I	Material	17
14.	Notice to Contractor, Notification of Demol	ition and/or Renovation No Asbestos Found	17
15.	Removing Luminaires, Item 204.9060.S.10	000	23
16.	Cold Patch, Item 495.1000.S.		24
17.	Expansion Device		24
18.	Sawing Pavement Deck Preparation Areas	s, Item 509.0310.S.	25
19.	Cleaning Decks to Reapply Concrete Maso	onry Overlay, Item 509.0505.S	26
20.	Concrete Masonry Deck Repair, Item 509.	2100.S	26
21.	Polymer Overlay, Item 509.5100.S		27
22.	Removing Concrete Masonry Deck Overla	y B-40-292 Item 509.9005.S.0001	32
23.	Removing Asphaltic Concrete Deck Overla	y B-40-292, Item 509.9010.S.0001	33
24.	Preparation and Coating of Top Flanges B	-40-429, Item 517.0900.S.0001	34
25.		0.S.4001; Concrete Staining B-40-293, Item	35
26.	Structure Repainting General		36
27.	Structure Repainting Recycled Abrasive B-	-40-429, Item 517.1800.S.0001	37
28.	Labeling and Disposal of Waste Material		39
29.	Negative Pressure Containment and Collection 517.4500.S.0001	ction of Waste Materials, B-40-429, Item	40
30.	Portable Decontamination Facility, Item 51	7.6001	42
31.	Nighttime Work Lighting-Stationary		43
32.	Traffic Control		44
33.	Traffic Control Signs Removal		44
34.	Traffic Control Interim Lane Closure, Item	643.4100.S.	44
35.	Temporary Bus Stop Pad, Item SPV.0060.	0003	45
36.	Fuse Holders, Item SPV.0060.1001; Fuses	Type FNQ, Item SPV.0060.1002	46

37.	Distribution Center Preventive Maintenance, Item SPV.0060.1003.	46
38.	Tunnel Luminaire Maintenance 150 Watt HPS, Item SPV.0060.1004; Tunnel Luminaire Maintenance 200 Watt HPS, Item SPV.0060.1005; Tunnel Luminaire Maintenance 250 Watt HPS, Item SPV.0060.1006; Tunnel Luminaire Maintenance 400 Watt HPS, Item SPV.0060.1007	47
39.	Group Clean Tunnel Luminaires, Item SPV.0060.1008	48
40.	Group Luminaire Maintenance Sign Light 250W MV, Item SPV.0060.1009.	49
41.	Cleaning and Painting Bearings, Item SPV.0060.4001.	50
42.	Protect Existing Light Fixtures and Utilities B-40-292, Item SPV.0105.4112; Protect Existing Light Fixtures and Utilities B-40-293, Item SPV.0105.4122.	51
43.	Temporary Lighting and Ventilation B-40-292, Item SPV.0105.4131; Temporary Lighting and Ventilation B-40-293, Item SPV.0105.4141	51
44.	Adjusting TES Manhole Cover, Item SPV.0060.5001.	52
45.	Adjusting Water Boxes, Item SPV.0060.5002.	53
46.	Field Facilities Office Space, Item SPV.0060.5003.	54
47.	Traffic Control Close-Open Freeway Entrance Ramp, Item SPV.0060.5004	54
48.	Pavement Cleanup Project 1228-28-70, Item SPV.0075.0003.	55
49.	Pavement Marking Contrast Epoxy 4-inch, Item SPV 0090.0001.	56
50.	Pavement Marking Contrast Epoxy 8-inch, Item SPV 0090.0002.	57
51.	Ventilation Opening Edge Repair, Item SPV.0090.4002.	57
52.	Remove and Replace Sidewalk Cover Plate, Item SPV.0105.4105	58
53.	Slip-Resistant Treatment of Sidewalk Cover Plate B-40-686, Item SPV.0105.4205; Slip-Resistant Treatment of Sidewalk Cover Plate B-40-689, Item SPV.0105.4305.	58
54.	Shotcrete Surface Repair, Item SPV.0165.4202.	59
55.	Cleaning Tunnel Wall and Ceiling, Item SPV.0180.4301.	
56.	Hydro-Demolition of Concrete Masonry Deck Overlay Structure B-40-293, Item SPV.0180.4302	60

1228-28-70 2 of 61

# STSP'S Revised November 21, 2019 SPECIAL PROVISIONS

#### 1. General.

Perform the work under this construction contract for Project 1228-28-70, Hillside Interchange, W Wisconsin to W Walnut St, IH 43, Milwaukee County, Wisconsin as the plans show and execute the work as specified in the State of Wisconsin, Department of Transportation, Standard Specifications for Highway and Structure Construction, 2020 Edition, as published by the department, and these special provisions.

If all or a portion of the plans and special provisions are developed in the SI metric system and the schedule of prices is developed in the US standard measure system, the department will pay for the work as bid in the US standard system.

100-005 (20191121)

#### 2. Scope of Work.

The work under this contract shall consist of Polymer Modified Asphalt overlays or thin polymer overlays, concrete overlays, concrete surface repairs, steel girder repainting, approach slabs, concrete pavement and sidewalks and all incidental items necessary to complete the work as shown on the plans and included in the proposal and contract.

104-005 (20090901)

#### 3. Prosecution and Progress.

Begin work within ten calendar days after the engineer issues a written notice to do so.

Provide the start date to the engineer in writing within a month after executing the contract but at least 14 calendar days before the preconstruction conference. Upon approval, the engineer will issue the notice to proceed within ten calendar days before the approved start date.

To revise the start date, submit a written request to the engineer at least two weeks before the intended start date. The engineer will approve or deny that request based on the conditions cited in the request and its effect on the department's scheduled resources.

Provide an individual to serve as the contractor's sole point of contact for field utility coordination and communication for the duration of the project.

Be advised that there may be multiple mobilizations and/or remobilizations to complete construction operations, for example such items as: traffic control, base patching, milling and resurfacing, pavement marking and other incidental items related to staging. No additional payment will be made by the department for additional mobilizations.

#### **General**

Comply with all local ordinances, including those pertaining to work during night time hours. Furnish ordinance variance issued by the municipality or required permits to the engineer in writing three business days prior to performing such work.

Park equipment or store materials only at work sites approved by the engineer.

Keep sidewalks open unless otherwise shown on the plans or as approved by the engineer. Maintain pedestrian access to adjacent properties, businesses, and at bus stops or provide where necessary, as directed by the engineer.

Notify all local emergency services at least 48 hours prior to closing and re-opening lanes or ramps on IH 43.

1228-28-70 3 of 61

#### **Contractor Coordination**

Attend weekly scheduling meetings to discuss near term schedule activities, address any long-term schedule issues, and discuss any relevant technical issues. Develop a rolling three-week schedule identifying the previous week worked and a two week "look ahead". Provide sufficient detail to include actual and planned activities and all the subcontractors for offsite and construction activities, addressing all activities including ramp and lane closure schedules to be performed and identifying issues requiring engineering action or input.

#### **Interim Liquidated Damage**

#### Northbound IH 43 off-ramp to Kilbourn Avenue

At the beginning of the project, close the IH 43 northbound off ramp to Kilbourn Avenue to through traffic for a maximum of 120 calendar days. Do not reopen until completing the following work: All work on Structure B-40-292, new concrete pavement, and all approach slabs.

If the contractor fails to complete the work necessary to reopen the northbound off ramp to Kilbourn Avenue in its entirety to traffic within 120 calendar days, the department will assess the contractor \$3,000 in interim liquidated damages for each calendar day the contract work remains incomplete beyond 120 calendar days. An entire calendar day will be charged for any period of time within a calendar day that the road remains closed beyond 12:01 AM.

#### Northbound IH 43 on-ramp from Kilbourn Avenue

At the beginning of the project, close the IH 43 northbound on ramp from Kilbourn Avenue to through traffic for a maximum of 120 calendar days. Do not reopen until completing the following work: All work on Structure B-40-293, new concrete pavement, and all approach slabs.

If the contractor fails to complete the work necessary to reopen the northbound on ramp from Kilbourn Avenue in its entirety to traffic within 120 calendar days, the department will assess the contractor \$1,000 in interim liquidated damages for each calendar day the contract work remains incomplete beyond 120 calendar days. An entire calendar day will be charged for any period of time within a calendar day that the road remains closed beyond 12:01 AM.

#### 12th Street

At the beginning of the project, close 12<sup>th</sup> Street to through traffic for a maximum of 50 calendar days. Do not reopen until completing the following work: All work on Structure B-40-429, new concrete pavement, and all approach slabs.

If the contractor fails to complete the work necessary to reopen 12<sup>th</sup> Street in its entirety to traffic within 50 calendar days, the department will assess the contractor \$2,500 in interim liquidated damages for each calendar day the contract work remains incomplete beyond 50 calendar days. An entire calendar day will be charged for any period of time within a calendar day that the road remains closed beyond 12:01 AM.

If contract time expires prior to completing all work specified in the contract, additional liquidated damages will be affixed according to standard spec 108.11.

#### **Schedule of Operations**

The schedule of operations shall conform to the construction staging as shown in the Traffic Control plans, unless approved otherwise by the engineer in writing. Work on more than one bridge may be performed at the same time using multiple crews although all stages for each bridge are intended to be constructed in sequential order. Work shall be performed to minimize impacts to the traveling public.

Do not begin work prior to March 1, 2021.

The department anticipates that the schedule for each stage shall be as follows:

#### Phase 1 construction - Long term closures:

- B-40-429 (12th St. over STH 145): Concrete overlay, replacement of approach slab, concrete sidewalks including curb and gutter where needed, concrete surface repair.
- B-40-292/293 (Kilbourn Tunnel Ramps): Concrete overlay, reconstruction of approach slab, concrete pavement including curb and gutter, concrete sidewalks.

1228-28-70 4 of 61

#### Phase 2 construction – Night time closures:

#### Stage 1

- B-40-429 (12th St. over STH 145): Girder Painting on the northern and southern section
- B-40-683-1 (Wisconsin Avenue) thin polymer overlay of the outside lanes
- B-40-683-2 (11th Street) thin polymer overlay
- B-40-685 (State Street) thin polymer overlay
- B-40-686 (Highland Avenue) thin polymer overlay of the outside lanes
- B-40-687 (IH 43 SB to Highland Exit Over STH 145) thin polymer overlay
- B-40-688 (Ramp to IH 43 NB over IH 43 Exit Ramp to STH 145) thin polymer overlay
- B-40-692 (Walnut Street) thin polymer overlay of the outside lanes
- B-40-690/691 (IH 43 NB and SB over STH 145) thin polymer overlay of the outside lanes

#### Stage 2

- B-40-429 (12th St. over STH 145): Girder Painting on the middle section
- B-40-683-1 (Wisconsin Avenue) thin polymer overlay of the inside lanes
- B-40-684 (Wells Street) thin polymer overlay
- B-40-686 (Highland Avenue) thin polymer overlay of the inside lanes
- B-40-689 (Winnebago Street) thin polymer overlay
- B-40-692 (Walnut Street) thin polymer overlay of the inside lanes
- B-40-690/691 (IH 43 NB and SB over STH 145) thin polymer overlay of the inside lanes

#### **Freeway and Ramp Work Restrictions**

#### **Definitions**

The following definitions apply to this contract for freeway work restrictions:

System Ramps Freeway to freeway ramps

Service Ramps Freeway to/from local road ramps

## **Weekday Peak Hours**

•	5:30 AM – 9:30 PM	Monday, Tuesday, Wednesday, Thursday (2 – 3 lane segments)
•	5:30 AM – 7:00 PM	Monday, Tuesday, Wednesday, Thursday (4 lane segments)
•	5:30 AM - 11:00 PM	Friday (all segments)

#### **Weekend Peak Hours**

•	8:00 AM – 9:30 PM	Saturday (all segments)
•	8:00 AM – 9:30 PM	Sunday (2 – 3 lane segments)
•	8:00 AM - 7:00 PM	Sunday (4 lane segments

#### Weekday Off-Peak Hours

• 7:00 PM – 9:30 PM Monday, Tuesday, Wednesday, Thursday (4 lane segments)

#### Weekend Off-Peak Hours

• 7:00 PM – 9:30 PM Sunday (4 lane segments)

#### **Night Time Hours**

- 9:30 PM 5:30 AM (Sunday PM to Monday AM, Monday PM to Tuesday AM, Tuesday PM to Wednesday AM, Wednesday PM to Thursday AM, Thursday PM to Friday AM) (all segments)
- 9:30 PM 8:00 AM (Friday PM to Saturday AM, Saturday PM to Sunday AM) (all segments)

1228-28-70 5 of 61

#### **Full Freeway and System Ramp Closure Hours**

- 11:00 PM 4:30 AM (Sunday PM to Monday AM, Monday PM to Tuesday AM, Tuesday PM to Wednesday AM, Wednesday PM to Thursday AM, Thursday PM to Friday AM)
- 11:00 PM 6:00 AM (Friday PM to Saturday AM, Saturday PM to Sunday AM)

#### **Local Street Work Restrictions**

The following definitions apply to this contract for local street closure restrictions:

#### Peak and Off-Peak Hours:

• 6:00 AM – 9:00 PM Monday, Tuesday, Wednesday, Thursday, Friday, Saturday, Sunday

#### **Night-Time Hours**

 9:00 PM – 6:00 AM (Sunday PM to Monday AM, Monday PM to Tuesday AM, Tuesday PM to Wednesday AM, Wednesday PM to Thursday AM, Thursday PM to Friday AM, Friday PM to Saturday AM, Saturday PM to Sunday AM)

All construction work shall be performed during night time hours as defined above except in Kilbourn Tunnel ramp areas and 12<sup>th</sup> Street over STH 145.

No full freeway closures allowed. No peak or off-peak hour lane closures.

Do not close freeway lanes or shoulders and ensure that the freeways are entirely clear for traffic during Weekday Peak Hours and Weekend Peak Hours. One freeway lane and/or shoulder may be closed on the freeway and system ramps, during Weekday Off-Peak and Weekend Off-Peak Hours but it must be approved by the engineer. Provide a minimum of one lane in each direction of the freeway that is entirely clear for traffic during Night Time Hours except as allowed during full closure. Service ramp closures will be permitted from 9:00 PM to 6:00 AM (Sunday PM to Monday AM, Monday PM to Tuesday AM, Tuesday PM to Wednesday AM, Wednesday PM to Thursday AM, Thursday PM to Friday AM) and from 10:30 PM to 8:30 AM (Friday PM to Saturday AM, Saturday PM to Sunday AM) unless otherwise approved by the engineer for safety or operational reasons associated with other adjacent lane closures.

Follow standard details and traffic control details for closures. Lane restrictions of the freeway beyond that shown on the traffic control plans are subject to lane rental fee assessments and must be approved by the engineer. If plan details are not provided in the traffic control plan, furnish plans for review by the engineer. Once approved, allow at least three business days prior to closure of roadway, lane, and ramp as identified in Contractor Coordination.

Do not begin or continue any work that closes traffic lanes outside the allowed time periods specified in this contract. If the contractor fails to open freeway lanes of traffic and/or ramps to traffic by the specified times, assessments will be made as shown in the Lane Rental Fee Assessment article.

#### Freeway and System Ramp Closure Restrictions

Full closure and detouring of freeway roads and system ramps will be restricted to Full Freeway and System Ramp Closure Hours unless otherwise specified.

#### General

Provide Milwaukee County Transit System – Coordinator of Street Supervision, Melanie Flynn, (414) 343-1764, with a schedule of any closures that effect any MCTS route and/or stop 14 calendar days prior to closure.

#### **Ramp Closures**

Service ramp closures will be permitted during Night-Time Hours only unless otherwise approved by the engineer.

No two consecutive entrance ramps or consecutive exit ramps may be closed unless it is approved by the engineer.

All entrance and exit ramps shall be posted three business days in advance of their closure with dates and time closure.

1228-28-70 6 of 61

#### **Work Zone Ingress/Egress**

All locations of work zone egress or ingress for construction vehicles are subject to approval from the engineer. Submit to the engineer locations from freeway access into and out of the work zone for each stage and plans, for approval, that include signage and parallel deceleration and acceleration lanes for each freeway access into and out of the work zones. Submit locations and plans 14 calendar days prior to each stage for approval by the engineer.

At the weekly traffic meetings, provide updated information to the Work Zone Access Plan, as approved by the engineer, to direct emergency responders accessing a mainline median barrier restricted work zone. Access for emergency responders shall be maintained at all times and not restricted by vehicles, equipment or the storage of equipment, vehicles or materials.

Access into the work zones are not allowed directly from the freeway during peak or off-peak hours. Access into the work zones from the freeway will be allowed during nighttime hours and at other times, subject to approval by the engineer, if operations can be safely accomplished and do not result in non-construction traffic entering the work zones. Exiting work zones directly onto the freeway are only allowed when operations do not obstruct or slow traffic on the freeway. All construction vehicles shall yield to all through traffic at all locations.

#### Portable Changeable Message Signs

Obtain acceptance from the engineer regarding the wording of all messages on portable changeable message signs.

#### **Temporary Pavement Markings**

Temporary pavement markings shall be placed same day and shall be placed in the exact configuration where permanent pavement markings will be placed. Any water blasting required for pavement marking removal should be considered incidental to the temporary pavement marking items.

#### 4. Lane Rental Fee Assessment.

#### A General

The contract designates some lane closures to perform the work. The contractor will not incur a Lane Rental Fee Assessment for closing lanes during the allowable lane closure times. The contractor will incur a Lane Rental Fee Assessment for each lane closure outside of the allowable lane closure times. If a lane is obstructed at any time due to contractor operations, it is considered a closure. The purpose of lane rental is to enforce compliance of lane restrictions and discourage unnecessary closures.

The allowable lane closure times are shown in the Prosecution and Progress article.

Submit the dates of the proposed lane, ramp, and roadway restrictions to the engineer as part of the progress schedule.

Coordinate lane, ramp, and roadway closures with any concurrent operations on adjacent roadways within 3 miles of the project. If other projects are in the vicinity of this project, coordinate lane closures to run concurrent with lane closures on adjacent projects when possible. When lane closures on adjacent projects extend into the limits of this project, Lane Rental Fee Assessments will only occur if the closure facilitates work under this contract.

#### **B** Lane Rental Fee Assessment

The Lane Rental Fee Assessment incurred for each lane closure, each ramp closure, and each full closure of a roadway, per direction of travel, is as follows:

- IH 43 and/or System Ramp Night Time Hours- \$8,000 per lane, per direction of travel, per hour broken into 15 minute increments.
- IH 43 and/or System Ramp Off Peak Hours- \$2,000 per lane, per direction of travel, per hour broken into 15 minute increments.
- Service Ramps- \$4,000 per lane, per direction of travel, per hour broken into 15 minute increments.

The Lane Rental Fee Assessment represents a portion of the cost of the interference and inconvenience to the road users for each closure. All lane, roadway, or ramp closure event increments 15 minutes and less will be assessed as a 15-minute increment.

1228-28-70 7 of 61

The engineer, or designated representative, will be the sole authority in determining time period length for the Lane Rental Fee Assessment.

Lane Rental Fee Assessments will not be assessed for closures due to crashes, accidents or emergencies not initiated by the contractor.

The department will assess Lane Rental Fee Assessment by the dollar under the administrative item Failing to Open Road to Traffic. The total dollar amount of Lane Rental Fee Assessment will be computed by multiplying the Lane Rental Assessment Rate by the number of 15-minute increments of each lane closure event as described above.

Lane Rental Fee Assessment will be in effect from the time of the Notice to Proceed until the department issues final acceptance. If interim completion time or contract time expires before the completion of specified work in the contract, additional liquidated damages will be assessed as specified in standard spec 108.11 or as specified within this contract.

stp-108-070 (20161130)

#### Traffic.

#### **Wisconsin Lane Closure System Advance Notification**

Provide the following advance notification to the engineer for incorporation into the Wisconsin Lane Closure System (LCS).

Closure type with height, weight, or width restrictions MINIMUM NOTIFICATION (available width, all lanes in one direction less than 16 feet) Lane and shoulder closures 7 calendar days Full roadway closures 7 calendar days Ramp closures 7 calendar days 7 calendar days **Detours** Closure type without height, weight, or width restrictions MINIMUM NOTIFICATION (available width, all lanes in one direction 16 feet or greater) Lane and shoulder closures 3 business days Ramp closures 3 business days Modifying all closure types 3 business days

TABLE 108-1 CLOSURE TYPE AND REQUIRED MINIMUM ADVANCE NOTIFICATION

Discuss LCS completion dates and provide changes in the schedule to the engineer at weekly project meetings in order to manage closures nearing their completion date.

#### General

Keep IH 43, IH 94, IH 794, all system ramps and all service ramps open to through traffic at all times for the duration of this project except as noted below and in the Prosecution and Progress article in these special provisions.

Coordinate traffic requirements under this contract with other ongoing department construction projects. This contractor shall be responsible for implementing and coordinating with other contractors all traffic control shown on the plans.

#### **Schedule of Operations - Traffic Control**

Traffic shifts shown in a given stage may occur at different times during that stage depending on the controlling elements for a given traffic movement as approved by the engineer. Staging of the project may need to deviate from the staging listed below in order to meet interim completion dates. The department anticipates that the schedule of major traffic shifts and roadway opening and closing for each stage shall be as follows, unless approved by the engineer:

1228-28-70 8 of 61

#### Phase 1 Traffic - Long term closures:

- B-40-429 (12th St. over STH 145): Long term ramp closure.
- B-40-292/293 (Kilbourn Tunnel Ramps): Long term ramp closures.

#### Phase 2 Traffic - Night time closures:

#### Stage 1

- B-40-429 (12th St. over STH 145): Outside lane closures on STH 145
- B-40-683-1 (Wisconsin Avenue) Outside lane closures
- B-40-683-2 (11th Street) Full overnight closure.
- B-40-685 (State Street) Full overnight closure.
- B-40-686 (Highland Avenue) Outside lane closures
- B-40-687 (IH 43 SB to Highland Exit Over STH 145) Full overnight closure.
- B-40-688 (Ramp to IH 43 NB over IH 43 Exit Ramp to STH 145) Full overnight closure.
- B-40-692 (Walnut Street) Outside lane closures
- B-40-690/691 (IH 43 NB & SB over STH 145) Outside lane closures

#### Stage 2

- B-40-429 (12th St. over STH 145): Inside lane closures on STH 145
- B-40-683-1 (Wisconsin Avenue) Inside lane closure
- B-40-684 (Wells Street) Full overnight closure.
- B-40-686 (Highland Avenue) Inside lane closures
- B-40-689 (Winnebago Street) Full overnight closure.
- B-40-692 (Walnut Street) Inside lane closure
- B-40-690/691 (IH 43 NB & SB over STH 145) Inside lane closures

#### 6. Holiday Work Restrictions.

The department will continue to work with the City of Milwaukee and other stakeholders as plans progress.

The following definitions shall apply for this project:

Do not perform work on, nor haul materials of any kind along or across any portion of the highway carrying IH-43, IH 94, IH 794, or local street traffic, and entirely clear the traveled way and shoulders of such portions of the highway of equipment, barricades, signs, lights, and any other material that might impede the free flow of traffic during the following holiday periods:

- From noon Friday, April 2, 2021 to 6:00 AM Monday, April 5, 2021 for Easter;
- From noon Friday, May 28, 2021 to 6:00 AM Tuesday, June 1, 2021 for Memorial Day;
- From noon Friday, July 2, 2021 to 6:00 AM Monday, July 5, 2021 for Independence Day;
- From noon Friday, September 3, 2021 to 6:00 AM Tuesday, September 7, 2021 for Labor Day.

stp-107-005 (20181119)

#### **Freeway Special Event Restrictions**

#### 2021:

 During Pride Fest, schedule anticipated for June 4 – 6, 2021, no full freeway or system ramp closures on IH 43, IH 94, and 794 in both directions until one hour after the event closes each night.

1228-28-70 9 of 61

- During Polish Fest, schedule anticipated for June 11 13, 2021, no full freeway or system ramp closures on IH 43, IH 94, and 794 in both directions until one hour after the event closes each night.
- During Summerfest, schedule anticipated for June 23 July 4, 2021, no full freeway or system ramp closures on IH 43, IH 94, and 794 in both directions until one hour after the event closes each night.
- During Festa Italiana, schedule anticipated for July 16 18, 2021, no full freeway or system ramp closures on IH 43, IH 94, and 794 in both directions until one hour after the event closes each night.
- During German Fest, schedule anticipated for July 23 25, 2021, no full freeway or system ramp closures on IH 43, IH 94, and 794 in both directions until one hour after the event closes each night.
- During Wisconsin State Fair, schedule anticipated for August 5 15, 2021, no full freeway or system ramp closures on IH 43, IH 94, and 794 in both directions until one hour after the event closes each night.
- During Irish Fest, schedule anticipated for August 12 15, 2021, no full freeway or system ramp closures on IH 43, IH 94, and 794 in both directions until one hour after the event closes each night.
- During Mexican Fiesta, schedule anticipated for August 20 22, 2021, no full freeway or system ramp closures on IH 43, IH 94, and 794 in both directions until one hour after the event closes each night.
- On days with a Milwaukee Bucks home game at Fiserv Forum, maintain all inbound travel lanes on IH 43, IH 94, and IH 794 to Fiserv Forum starting at two hours before the game. Maintain all outbound lanes on IH 43, IH 94, and IH 794 from Fiserv Forum until three hours after the start of the game. Restrictions during other special events at Fiserv Forum will be determined on an as needed basis as determined by the engineer.
- On days with a Milwaukee Brewer home game at Miller Park, maintain all inbound travel lanes on IH 43, IH 94, and IH 794 to Miller Park starting at three hours before the game. Maintain all outbound lanes on IH 43, IH 94, and IH 794 from Miller Park until four hours after the start of the game. Restriction during other special events at Miller Park will be determined on an as needed basis as determined by the engineer.
- On days with a Green Bay Packers "Gold Package" games at Lambeau Field, no additional lane closures will be allowed from that shown in the plans, 4 hours prior to 4 hours after the game.
   Restriction during other special events at Lambeau Field will be determined on an as needed basis as determined by the engineer.

#### 7. Utilities.

This contract comes under the provisions of Administrative Rule TRANS 220.

stp-107-065 (20080501)

Contact utility companies listed in the plans prior to preparing bids to obtain current information on existing utility locations and the status of any new utility relocation work.

Utility companies will be performing utility work and adjustments within the limits and during the life of the project. The contractor shall cooperate and coordinate construction activities with these companies.

There may be discontinued utility facilities within the project limits. If a conflict with a discontinued utility facility is encountered, contact the appropriate utility owner/representative to coordinate construction activities and proper removal and disposal of said facility as necessary.

1228-28-70 10 of 61

Known utilities in the project area are as follows:

AT&T Legacy (aka. AT&T Corporation) has facilities within the project limits. No conflicts are anticipated.

AT&T Legacy contact Ken Nine of JMC Engineers & Associates, Inc. (574-842-8830 office/ 574-904-6336 cell).

**AT&T Wisconsin** has existing underground communication facilities within the project limits in the following locations:

- B-40-292: Kilbourn Tunnel Under Wells St a15 Duct package exist above the tunnel. These lines will remain in place without adjustment.
- B-40-684: Wells St Bridge over I-43 Beginning beyond the easterly project limits and running westerly, a 15 FC package attached to underside of the north side of the structure and continuing to beyond the westerly project limits. These lines will remain in place without adjustment.
- B-40-685: State St Bridge over I-43 Beginning beyond the easterly project limits and running westerly, an 8 FC package attached to underside of the north side of the structure and continuing to beyond the westerly project limits. These lines will remain in place without adjustment.
- B-40-686: Highland Av Bridge over I-43 Beginning beyond the easterly project limits and running westerly, an 8 FC package attached to underside of the north side of the structure and continuing to beyond the westerly project limits. These lines will remain in place without adjustment.
- B-40-692: Walnut Bridge over I-43 Beginning beyond the easterly project limits and running westerly, a 6 FC package attached to underside of the north side of the structure and continuing to beyond the westerly project limits. These lines will remain in place without adjustment.

AT&T Wisconsin contact is Jay Bulanek, (262) 896-7669 office / (414) 491-2855 cell.

**ATC Management, Inc. (aka. American Transmission Company)** has existing underground transmission facilities within the project limits in the following locations:

Structure B-40-692: Beginning beyond the easterly project limits and running westerly
underground in Walnut Street and continuing beyond the northerly project limits. These lines will
remain in place without adjustment.

American Transmission Company contact is Tony Marciniak, (262) 506-6814.

**Charter Communications** has existing underground communication facilities within the project limits in the following locations:

- Charter has underground facilities at 6th and Kilbourn Ave. The remainder of Charters facilities are located within the city owned conduit system. No conflicts are anticipated.

Charter Communications contact is Beau Abuya, (414) 908-1343.

City of Milwaukee- Communication Line has existing underground facilities in the following locations:

- B-40-683-1: Wisconsin Ave Bridge over I-43 Beginning beyond the easterly project limits and running westerly, a conduit is attached to underside of the structure continuing to beyond the westerly project limits. This conduit will remain in place without adjustment.
- B-40-685: State St Bridge over I-43 Beginning beyond the easterly project limits and running westerly, a conduit is attached to underside of the structure continuing to beyond the westerly project limits. This conduit will remain in place without adjustment.
- B-40-689: Winnebago St/ Vilet St over I-43 Beginning beyond the easterly project limits and running westerly, a conduit is attached to underside of the structure continuing to beyond the westerly project limits. This conduit will remain in place without adjustment.

1228-28-70 11 of 61

- B-40-692: Walnut Bridge over I-43 – Beginning beyond the easterly project limits and running westerly, a conduit is attached to underside of the structure continuing to beyond the westerly project limits. This conduit will remain in place without adjustment.

City of Milwaukee - Communications contact is David Henke, (414) 286-3248.

City of Milwaukee – City Underground Conduit (CUC) has existing underground facilities in the following locations:

- 12th St south bridge approach: There is a City Underground Conduit (CUC) manhole that will
  need to be adjusted to grade. The manhole is located in the North 12th Street south bridge
  approach. Adjust manhole as shown in the plans and in the bid items for this project.
- B-40-429: 12th St Bridge over W Fond Du Lac Beginning beyond the southerly project limits and running northerly, a conduit is attached to underside of the structure continuing to beyond the northerly project limits. This conduit will remain in place without adjustment.

City of Milwaukee - CUC contact is Karen Rogney, (414) 286-3243.

**City of Milwaukee – Forestry** has existing facilities within the project limits. At the 6th and Kilbourn Avenue off ramps there is landscaping and irrigation lines by the Milwaukee Gateway Funjet Sign. Prior to working at the 6th and Kilbourn Avenue off ramps contact the City of Milwaukee forces to cap off the existing water line for the irrigation system. It is anticipated to take 5 working days to perform the work. The irrigation system and landscaping will be replaced by the City of Milwaukee after construction.

City of Milwaukee - Forestry contact is Andy Witczak, (414) 708-3785.

City of Milwaukee - Sewer has no plans to relocate facilities within the project limits.

City of Milwaukee - Sewer contact is Brian Heard, (414) 286-2470.

City of Milwaukee - Street Lighting has existing underground facilities in the following locations:

- 12th St Bridge: There is a City of Milwaukee will install temporary overhead circuity north and south of the North 12th Street Bridge in order to keep the remaining street lights working. The City will require 3 working days to complete the temporary overhead circuity in advance of the Bridge work. During construction but after the bridge work is completed the City of Milwaukee will require 15 working days to install permanent street lighting facilities and remove the temporary facilities.

City of Milwaukee Temporary Street Light contact Mark MacRae, (414) 286-5928 office / (414) 708-0434 cell.

City of Milwaukee - Street Lighting contact is Denis Kozelek, (414-286-3252).

City of Milwaukee - Water has existing underground facilities in the following locations:

- 12th St Bridge: There is a City of Milwaukee Water valve box at Station 71+95 that will be adjusted during construction as part of the contract.

City of Milwaukee – Water contact is Dave Goldapp, (414) 286-6301 office / (414) 708-2695 cell.

**Marquette University – Communication Line** has existing underground facilities in the following locations:

 B-40-683-1: Wisconsin Ave Bridge over I-43 - Beginning beyond the easterly project limits and running westerly, a conduit is attached to underside of the structure continuing to beyond the westerly project limits. This conduit will remain in place without adjustment.

Marquette University facilities contact is Michael Jahner, (414) 288-6104 office / (414) 313-9583 cell.

1228-28-70 12 of 61

**Midwest Fiber Networks LLC (MWFN) – Communication Line** has facilities within the project limits. No relocation of facilities is necessary.

Midwest Fiber Networks LLC - Contact is Patrick Graham, (414) 672-5612.

**PaeTec Communications, LLC (aka Windstream) – Communication Line** has existing underground communication facilities within the project limits in the following locations:

- B-40-692: Walnut Bridge over I-43 – Facilities are located on the north side of W Walnut St north of the existing sidewalk in the existing ROW on the west and east side of IH 43. These facilities will remain in place without adjustment.

PaeTec Communications, LLC (aka Windstream) contact is Mary Beth Fisher, (262) 792-7938.

**We Energies – Electric** has existing overhead and underground electric facilities within the project limits in the following locations:

12<sup>th</sup> St Bridge: An underground electric line beginning beyond the southerly project limits and running northerly to manhole MH82-8018 at 71+83; 22RT' then northerly under the structure to manhole MH82-8017 at 76+87; 22RT, then continuing northly to beyond the project limits. Both manholes will be adjusted by We Energies during construction. Allow 3 days per manhole for We Energies to complete adjustment work. This line will remain in place without adjustment.

We Energies - Electric contact Tom Ross, (414) 540-5784 office / (414) 416-8123 cell.

We Energies – Gas has no existing underground gas facilities within the project limits.

We Energies – Gas contact is Alex Dantinne, (920) 621-6903.

We Energies - Steam has no existing underground gas facilities within the project limits.

We Energies – Steam contact is Robert Baumann, (414) 221-2425 office / (414) 587-2136 cell.

WisDOT - Communication has no underground communication lines within the project limits.

WisDOT – Communication contact is Jeff Madson, (414) 225-3723.

WisDOT - Street Lighting has no underground electric lines and street light poles within the project limits.

WisDOT - Street Lighting contact is Eric Perea, (262) 574-5422 office / (414) 750-0935 cell.

#### 8. Other Contracts.

Modifications to the traffic control plan may be required by the engineer to be safe and consistent with the adjacent work by others.

The following projects may be under construction concurrently with the work under this contract. Coordinate activities, detours, work zone traffic control, roadway and lane closures, and other work items as required with other contracts.

#### Project 1060-11-73

EW Freeway, 25th St Mitchell Blvd USH 18 Bridges, IH 94

WisDOT Contact: Scott Anderson; (262) 548-6894; ScottM.Anderson@dot.wi.gov.

#### Project 1300-09-72

Lake Freeway, Milwaukee River to Lincoln Memorial Drive, IH 794

WisDOT Contact: Chris Zacharias; (414) 750-4955; <a href="mailto:Christopher.Zacharias@dot.wi.gov">Christopher.Zacharias@dot.wi.gov</a>.

1228-28-70 13 of 61

#### Project 1228-09-74

EW Freeway, Marquette I/C, IH 94

WisDOT Contact: Evan Limberatos; (262) 548-8797; Evan.Limbertos@dot.wi.gov

#### Project 1228-22-71

North South Freeway, Capitol Dr-2100 Feet N of Hampton Ave, IH 43

WisDOT Contact: David Pittman; (262) 548-6439; <a href="mailto:David.Pittman@dot.wi.gov">David.Pittman@dot.wi.gov</a>

#### 9. Railroad Insurance and Coordination - Soo Line Railroad Company (CP).

#### **A Description**

Comply with standard spec 107.17 for all work affecting Soo Line Railroad Company (CP) property and any existing tracks.

#### A.1 Railroad Insurance Requirements

In addition to standard spec 107.26, provide railroad protective liability insurance coverage as specified in standard spec 107.17.3. Insurance is filed in the name of Soo Line Railroad Company d/b/a Canadian Pacific.

Notify evidence of the required coverage, and duration to Brian Osborne, Manager Public Works; Canadian Pacific Plaza, 120 South 6th Street, Suite 700, Minneapolis, MN 55402; Telephone (612) 330-4555; E-mail: <a href="mailto:brian\_osborne@cpr.ca">brian\_osborne@cpr.ca</a>

Also send a copy to the following: Paul Derksen, SE Region Railroad Coordinator; 141 N. W. Barstow Street, Waukesha, WI 53188; Telephone (262) 548-8770; E-mail: paul.derksen@dot.wi.gov.

Include the following information on the insurance document:

Project ID: 1228-28-70

- Project Location: Milwaukee, WI

- Route Name: IH 43, Hillside Interchange

Crossing ID: 386 497J

- Railroad Subdivision: Watertown

- Railroad Milepost: 86

- Work Performed near crossing: Traffic Control

#### A.2 Train Operation

Approximately 2 passenger trains and 20 through freight trains operate daily through the construction site. Passenger trains operate at up to 40 mph. Through freight trains operate at up to 40 mph.

# A.3 Names and Addresses of Railroad Representatives for Consultation and Coordination

#### **Construction Contact**

Brian Osborne, Manager Public Works; Canadian Pacific Plaza, 120 South 6<sup>th</sup> Street, Suite 700, Minneapolis, MN 55402; Telephone (612) 330-4555; E-mail <a href="mailto:brian\_osborne@cpr.ca">brian\_osborne@cpr.ca</a> for consultation on railroad requirements during construction.

Amend standard spec 108.4 to include the railroad in the distribution of the initial bar chart, and monthly schedule updates. The bar chart shall specifically show work involving coordination with the railroad.

#### **Flagging Contact**

Matthew R. Miller, Supervisor of Public Works; Canadian Pacific Plaza, 120 South 6<sup>th</sup> Street, Suite 700, Minneapolis, MN 55402; Telephone (612) 330-4556; E-mail <a href="mill0470@cpr.ca">mill0470@cpr.ca</a>. Reference the Crossing ID, Wisconsin Milepost and Subdivision found in A.1.

\* Contact Soo Line (CP) prior to letting for flagman work hour availability.

1228-28-70 14 of 61

#### **Cable Locate Contact**

In addition to contacting Diggers Hotline, contact CP Call Before You Dig line at (866) 291-0741, five working days before the locate is needed. Reference the Crossing ID, Wisconsin Milepost and Subdivision found in A.1.

Soo Line (CP) will only locate railroad owned facilities located in the railroad right-of-way. The railroad does not locate any other utilities.

#### A.4 Work by Railroad

The railroad will perform the work described in this section, except for work described in other special provisions, and will be accomplished without cost to the contractor. None

#### A.5 Temporary Grade Crossing

If a temporary grade crossing is desired, submit a written request to the railroad representative named in A.3 at least 40 days prior to the time needed. Approval is subject to the discretion of the railroad. The department has made no arrangements for a temporary grade crossing.

stp-107-026 (20190717)

#### 10. Contractor Notification.

Replace standard spec 104.2.2.2(2) with the following:

(2) If the contractor discovers the differing condition, provide a written notice, as specified in 104.3.3, of the specific differing condition before further disturbing the site and before further performing the affected work.

Replace standard spec 104.3.2 and 104.3.3 with the following:

#### 104.3.2 (Vacant)

#### 104.3.3 Contractor Initial Written Notice

- (1) If required by 104.2, or if the contractor believes that the department's action, the department's lack of action, or some other situation results in or necessitates a contract revision, promptly provide a written notice to the engineer. At a minimum, provide the following:
  - 1. A written description of the nature of the issue.
  - 2. The time and date of discovering the problem or issue.
  - 3. If appropriate, the location of the issue.
- (2) Provide the additional information specified in 104.3.5 as early as possible to assist the engineer in the timely resolution of an identified issue. The engineer will not require, in subsequent submissions, duplication of information already provided.

sef-104-005 (20141211)

#### 11. Erosion Control

Add the following to standard spec 107.20 as paragraphs nine through fifteen:

(9) Erosion control best management practices (BMP's) the plans show are at suggested locations. The actual locations shall be determined by the contractor's ECIP and by the engineer. Include each dewatering (mechanical pumping) operation in the ECIP submittal. The ECIP shall supplement information the plans show and not reproduce it. The ECIP shall identify how to implement the project's erosion control plan. ECIP shall demonstrate timely and diligently staged operations, continuing all construction operations methodically from the initial removals and topsoil stripping operations through the subsequent grading, paving, and re-application of top soil to minimize the exposure to possible erosion.

Kristina Betzold. (414) 507-4946. KRISTINA.BETZOLD@WISCONSIN.GOV for DNR liasion

(10)Provide the ECIP 14 days before the pre-construction conference. Provide 1 copy of the ECIP to the department and 1 copy of the ECIP to the WDNR Liaison Kristina Betzold, (414) 507-4946, <a href="MRISTINA.BETZOLD@WISCONSIN.GOV">KRISTINA.BETZOLD@WISCONSIN.GOV</a>. Do not implement the ECIP until department approval, and perform all work conforming to the approved ECIP.

1228-28-70 15 of 61

- (11)Maintain Erosion Control BMP's until permanent vegetation is established or until the engineer determines that the BMP is no longer required.
- (12)Stockpile excess materials or spoils on upland areas away from wetlands, floodplains, and waterways. Install perimeter silt fence protection around stockpiles within a timeframe acceptable to the engineer. If stockpiled materials will be left for more than 14 days, install temporary seed and mulch or other temporary erosion control measures the engineer orders.
- (13)Re-apply topsoil on graded areas, as designated by the engineer, within a timeframe acceptable to the engineer after grading is completed within those areas. Seed, fertilize, and mulch/erosion mat top-soiled areas, as designated by the engineer, within 5 days after placement of topsoil. If graded areas are left not completed and exposed for more than 14 days, seed those areas with temporary seed and mulch.

#### Dewatering (Mechanical Pumping) for Bypass Water (sediment-free) Operations

If dewatering bypass operations are required from one pipe structure to another downstream pipe structure or from the upstream to downstream end of a culvert and the bypass flow is not transporting sediments (sand, silt, and clay particles) from a tributary work site area, bypass pumping operations will be allowed provided that the department has been made aware of and approves operation. When pumping bypass flows, the discharge location will need to be stable and not produce any erosion from the discharge velocity that would cause release of sediment downstream. Dewatering is considered incidental to the contract.

#### Dewatering (Mechanical Pumping) for Treatment Water (sediment-laden) Operations

If dewatering operations require pumping of water containing sediments (sand, silt, and clay particles), the discharge will not be allowed to leave the work site or discharge to a storm water conveyance system without sediment removal treatment. Do not allow any excavation for; structures, utilities, grading, maintaining drainage that requires dewatering (mechanical pumping) of water containing sediments (sand, silt, and clay particles) to leave the work site or discharge to a storm water conveyance system without sediment removal treatment.

Prior to each dewatering operation, submit to the department a separate ECIP amendment for sediment removal. Guidance on dewatering can be found on the Wisconsin DNR website located in the Storm Water Construction Technical Standards, Dewatering Code #1061,

#### http://dnr.wi.gov/topic/stormwater/standards/const standards.html.

Include reasoning, location, and schedule duration proposed for each operation. Per Code 1061, include all selection criteria: site assessment, dewatering practice selection, calculations, plans, specifications, operations, maintenance, and location of proposed treated water discharge. Provide a stabilized discharge area. If directing discharge towards or into an inlet structure, provide additional inlet protection for back-up protection. Dewatering is considered incidental to the contract.

# **Maintaining Drainage**

Maintain drainage at and through worksite during construction conforming to standard spec 107.20, 204.3.2.1(3), 205.3.3 and 520.3.1(2). Use existing storm sewers, existing culvert pipes, existing drainage channels, temporary culvert pipes, or temporary drainage channels to maintain existing surface and pipe drainage. Pumps may be required to drain the surface, pipe, and structure discharges during construction. Costs for furnishing, operating, and maintaining the pumps is considered incidental to the contract.

SER-107-003 (20161220)

# 12. Material Stockpile and Equipment Storage.

Submit a map showing all proposed material stockpile and equipment storage locations to the engineer 14 calendar days before either the preconstruction conference or proposed use, whichever comes first. Identify the purpose; length, width and height; and duration of material stockpile or equipment storage at each location. Obtain written permission and necessary permits from the property owner and local governments/agencies and submit two copies to the engineer. Do not stockpile material or store equipment until the engineer approves.

SER-107-011 (20181019)

1228-28-70 16 of 61

#### 13. Information to Bidders, Use of Recovered Material.

The department encourages the use of waste materials and recovered industrial byproducts as material substitutions (106.2.1), provided they meet standard specification gradation requirements, conform to NR 538 requirements, and follow standard engineering practice for their intended use.

sef-106-005 (20141211)

#### 14. Notice to Contractor, Notification of Demolition and/or Renovation No Asbestos Found.

Andrew Heeter, License Number All-194672, inspected Structure B-40-292 for asbestos on 6/17-2014. No regulated Asbestos Containing Material (RACM) was found on this structure. A copy of the inspection report is available from: David Pittman, (262) 548-6439.

In accordance with NR447 and DHS159, ensure that DNR or DHS receives a completed Notification of Demolition and/or Renovation (DNR Form 4500-113 (R 4/11), or subsequent revision) via U.S. mail, hand-delivery, or using the online notification system at least 10 working days before beginning any construction or demolition. Pay all associated fees. Provide a copy of the completed 4500-113 form to Andrew Malsom, (262) 548-6705 and DOT BTS-ESS attn: Hazardous Materials Specialist, PO Box 7965, Madison, WI 53707-7965. In addition, comply with all local or municipal asbestos requirements.

Use the following information to complete WisDNR form 4500-113:

- Site Name: Structure B-40-292, USH 18/W. Wells St., N 10th St. over RAMP IH 43NB-KILBOURN ST
- Site Address: 0.1M E JCT IH 43 TO N
- Ownership Information: WisDOT SE Region, 141 NW Barstow Street, Waukesha, WI 53187
- Contact: Steven KuhlPhone: 414-531-6932
- Age: 52 years old. This structure was constructed in 1968
- Area: 14662 SF of deck

Insert the following paragraph in Section 6.g.:

If asbestos not previously identified is found or previously non-friable asbestos becomes crumbled, pulverized, or reduced to a powder, stop work immediately, notify the engineer, and the engineer will notify the department's Bureau of Technical Services at (608) 266-1476 for an emergency response as specified in standard spec 107.24. Keep material wet until it is abated or until it is determined to be non-asbestos containing material.

Andrew Heeter, License Number All-194672, inspected Structure B-40-293 for asbestos on 6/17/2014. No regulated Asbestos Containing Material (RACM) was found on this structure. A copy of the inspection report is available from: David Pittman, (262) 548-6439.

In accordance with NR447 and DHS159, ensure that DNR or DHS receives a completed Notification of Demolition and/or Renovation (DNR Form 4500-113 (R 4/11), or subsequent revision) via U.S. mail, hand-delivery, or using the online notification system at least 10 working days before beginning any construction or demolition. Pay all associated fees. Provide a copy of the completed 4500-113 form to Andrew Malsom, (262) 548-6705 and DOT BTS-ESS attn: Hazardous Materials Specialist, PO Box 7965, Madison, WI 53707-7965. In addition, comply with all local or municipal asbestos requirements.

Use the following information to complete WisDNR form 4500-113:

- Site Name: Structure B-40-293, LOCAL STS-PARKING RAMPS over RAMP KILBOURN ST/STH 145 IH 43NB
- Site Address: 0.1M E JCT IH 43 TO N
- Ownership Information: WisDOT SE Region, 141 NW Barstow Street, Waukesha, WI 53187
- Contact: Steven KuhlPhone: 414-531-6932
- Age: 52 years old. This structure was constructed in 1968
- Area: 17308 SF of deck

1228-28-70 17 of 61

If asbestos not previously identified is found or previously non-friable asbestos becomes crumbled, pulverized, or reduced to a powder, stop work immediately, notify the engineer, and the engineer will notify the department's Bureau of Technical Services at (608) 266-1476 for an emergency response as specified in standard spec 107.24. Keep material wet until it is abated or until it is determined to be non-asbestos containing material.

stp-107-125 (20120615)

John Roelke, License Number All-119523, inspected Structure B-40-429 for asbestos on 9/3/2014. No regulated Asbestos Containing Material (RACM) was found on this structure. A copy of the inspection report is available from: David Pittman, (262) 548-6439.

In accordance with NR447 and DHS159, ensure that DNR or DHS receives a completed Notification of Demolition and/or Renovation (DNR Form 4500-113 (R 4/11), or subsequent revision) via U.S. mail, hand-delivery, or using the online notification system at least 10 working days before beginning any construction or demolition. Pay all associated fees. Provide a copy of the completed 4500-113 form to Andrew Malsom, (262) 548-6705 and DOT BTS-ESS attn: Hazardous Materials Specialist, PO Box 7965, Madison, WI 53707-7965. In addition, comply with all local or municipal asbestos requirements.

Use the following information to complete WisDNR form 4500-113:

- Site Name: Structure B-40-429, N 12TH STREET over STH 145
- Site Address: 0.1 M N JCT VILET ST
- Ownership Information: WisDOT SE Region, 141 NW Barstow Street, Waukesha, WI 53187
- Contact: Steven KuhlPhone: (414) 531-6932
- Age: 37 years old. This structure was constructed in 1983.
- Area: 25472 SF of deck

Insert the following paragraph in Section 6.g.:

If asbestos not previously identified is found or previously non-friable asbestos becomes crumbled, pulverized, or reduced to a powder, stop work immediately, notify the engineer, and the engineer will notify the department's Bureau of Technical Services at (608) 266-1476 for an emergency response as specified in standard spec 107.24. Keep material wet until it is abated or until it is determined to be non-asbestos containing material.

Andrew Heeter, License Number All-194672, inspected Structure B-40-683 for asbestos on 6/17/2014. No regulated Asbestos Containing Material (RACM) was found on this structure. A copy of the inspection report is available from: David Pittman, (262) 548-6439.

In accordance with NR447 and DHS159, ensure that DNR or DHS receives a completed Notification of Demolition and/or Renovation (DNR Form 4500-113 (R 4/11), or subsequent revision) via U.S. mail, hand-delivery, or using the online notification system at least 10 working days before beginning any construction or demolition. Pay all associated fees. Provide a copy of the completed 4500-113 form to Andrew Malsom, (262) 548-6705 and DOT BTS-ESS attn: Hazardous Materials Specialist, PO Box 7965, Madison, WI 53707-7965. In addition, comply with all local or municipal asbestos requirements.

Use the following information to complete WisDNR form 4500-113:

- Site Name: Structure B-40-683. Wisconsin Ave over IH43
- Site Address: 0.5M N JCT I-94
- Ownership Information: WisDOT SE Region, 141 NW Barstow Street, Waukesha, WI 53187
- Contact: Steven KuhlPhone: (414) 531-6932
- Age: 14 years old. This structure was constructed in 2006.
- Area: 34668 SF of deck

1228-28-70 18 of 61

If asbestos not previously identified is found or previously non-friable asbestos becomes crumbled, pulverized, or reduced to a powder, stop work immediately, notify the engineer, and the engineer will notify the department's Bureau of Technical Services at (608) 266-1476 for an emergency response as specified in standard spec 107.24. Keep material wet until it is abated or until it is determined to be non-asbestos containing material.

Andrew Heeter, License Number All-194672, inspected Structure B-40-684 for asbestos on 6/17/2014. No regulated Asbestos Containing Material (RACM) was found on this structure. A copy of the inspection report is available from: David Pittman, (262) 548-6439.

In accordance with NR447 and DHS159, ensure that DNR or DHS receives a completed Notification of Demolition and/or Renovation (DNR Form 4500-113 (R 4/11), or subsequent revision) via U.S. mail, hand-delivery, or using the online notification system at least 10 working days before beginning any construction or demolition. Pay all associated fees. Provide a copy of the completed 4500-113 form to Andrew Malsom, (262) 548-6705 and DOT BTS-ESS attn: Hazardous Materials Specialist, PO Box 7965, Madison, WI 53707-7965. In addition, comply with all local or municipal asbestos requirements.

Use the following information to complete WisDNR form 4500-113:

- Site Name: Structure B-40-684, USH 18 EB - WELLS ST over IH 43

- Site Address: 1.1 MI E JCT STH 57

- Ownership Information: WisDOT SE Region, 141 NW Barstow Street, Waukesha, WI 53187

Contact: Steven KuhlPhone: (414) 531-6932

- Age: 15 years old. This structure was constructed in 2005.

- Area: 16191 SF of deck

Insert the following paragraph in Section 6.g.:

If asbestos not previously identified is found or previously non-friable asbestos becomes crumbled, pulverized, or reduced to a powder, stop work immediately, notify the engineer, and the engineer will notify the department's Bureau of Technical Services at (608) 266-1476 for an emergency response as specified in standard spec 107.24. Keep material wet until it is abated or until it is determined to be non-asbestos containing material.

Andrew Heeter, License Number All-194672, inspected Structure B-40-685 for asbestos on 6/17/2014. No regulated Asbestos Containing Material (RACM) was found on this structure. A copy of the inspection report is available from: David Pittman, (262) 548-6439.

In accordance with NR447 and DHS159, ensure that DNR or DHS receives a completed Notification of Demolition and/or Renovation (DNR Form 4500-113 (R 4/11), or subsequent revision) via U.S. mail, hand-delivery, or using the online notification system at least 10 working days before beginning any construction or demolition. Pay all associated fees. Provide a copy of the completed 4500-113 form to Andrew Malsom, (262) 548-6705 and DOT BTS-ESS attn: Hazardous Materials Specialist, PO Box 7965, Madison, WI 53707-7965. In addition, comply with all local or municipal asbestos requirements.

Use the following information to complete WisDNR form 4500-113:

- Site Name: Structure B-40-685, USH 18 WB (STATE ST.) over IH 43

- Site Address: 1.1 MI E JCT STH 57

- Ownership Information: WisDOT SE Region, 141 NW Barstow Street, Waukesha, WI 53187

Contact: Steven KuhlPhone: (414) 531-6932

- Age: 15 years old. This structure was constructed in 2005.

- Area: 17125 SF of deck

1228-28-70 19 of 61

If asbestos not previously identified is found or previously non-friable asbestos becomes crumbled, pulverized, or reduced to a powder, stop work immediately, notify the engineer, and the engineer will notify the department's Bureau of Technical Services at (608) 266-1476 for an emergency response as specified in standard spec 107.24. Keep material wet until it is abated or until it is determined to be non-asbestos containing material.

Andrew Heeter, License Number All-194672, inspected Structure B-40-686 for asbestos on 6/17/2014. No regulated Asbestos Containing Material (RACM) was found on this structure. A copy of the inspection report is available from: David Pittman, (262) 548-6439.

In accordance with NR447 and DHS159, ensure that DNR or DHS receives a completed Notification of Demolition and/or Renovation (DNR Form 4500-113 (R 4/11), or subsequent revision) via U.S. mail, hand-delivery, or using the online notification system at least 10 working days before beginning any construction or demolition. Pay all associated fees. Provide a copy of the completed 4500-113 form to Andrew Malsom, (262) 548-6705 and DOT BTS-ESS attn: Hazardous Materials Specialist, PO Box 7965, Madison, WI 53707-7965. In addition, comply with all local or municipal asbestos requirements.

Use the following information to complete WisDNR form 4500-113:

- Site Name: Structure B-40-686, HIGHLAND AVENUE over IH 43

- Site Address: 0.4 MI S JCT STH 145

- Ownership Information: WisDOT SE Region, 141 NW Barstow Street, Waukesha, WI 53187

Contact: Steven KuhlPhone: (414) 531-6932

- Age: 14 years old. This structure was constructed in 2006.

- Area: 15825 SF of deck

Insert the following paragraph in Section 6.g.:

If asbestos not previously identified is found or previously non-friable asbestos becomes crumbled, pulverized, or reduced to a powder, stop work immediately, notify the engineer, and the engineer will notify the department's Bureau of Technical Services at (608) 266-1476 for an emergency response as specified in standard spec 107.24. Keep material wet until it is abated or until it is determined to be non-asbestos containing material.

Andrew Heeter, License Number All-194672, inspected Structure B-40-687 for asbestos on 6/6/2014. No regulated Asbestos Containing Material (RACM) was found on this structure. A copy of the inspection report is available from: David Pittman, (262) 548-6439.

In accordance with NR447 and DHS159, ensure that DNR or DHS receives a completed Notification of Demolition and/or Renovation (DNR Form 4500-113 (R 4/11), or subsequent revision) via U.S. mail, hand-delivery, or using the online notification system at least 10 working days before beginning any construction or demolition. Pay all associated fees. Provide a copy of the completed 4500-113 form to Andrew Malsom, (262) 548-6705 and DOT BTS-ESS attn: Hazardous Materials Specialist, PO Box 7965, Madison, WI 53707-7965. In addition, comply with all local or municipal asbestos requirements.

Use the following information to complete WisDNR form 4500-113:

- Site Name: Structure B-40-687, I43 SB to Highland Exitover STH 145 to I43 SB Entrance

- Site Address: 0.1 MI S JCT STH145

- Ownership Information: WisDOT SE Region, 141 NW Barstow Street, Waukesha, WI 53187

Contact: Steven KuhlPhone: (414) 531-6932

- Age: 14 years old. This structure was constructed in 2006.

- Area: 10344 SF of deck

1228-28-70 20 of 61

If asbestos not previously identified is found or previously non-friable asbestos becomes crumbled, pulverized, or reduced to a powder, stop work immediately, notify the engineer, and the engineer will notify the department's Bureau of Technical Services at (608) 266-1476 for an emergency response as specified in standard spec 107.24. Keep material wet until it is abated or until it is determined to be non-asbestos containing material.

Andrew Heeter, License Number All-194672, inspected Structure B-40-688 for asbestos on 6/6/2014. No regulated Asbestos Containing Material (RACM) was found on this structure. A copy of the inspection report is available from: David Pittman, (262) 548-6439.

In accordance with NR447 and DHS159, ensure that DNR or DHS receives a completed Notification of Demolition and/or Renovation (DNR Form 4500-113 (R 4/11), or subsequent revision) via U.S. mail, hand-delivery, or using the online notification system at least 10 working days before beginning any construction or demolition. Pay all associated fees. Provide a copy of the completed 4500-113 form to Andrew Malsom, (262) 548-6705 and DOT BTS-ESS attn: Hazardous Materials Specialist, PO Box 7965, Madison, WI 53707-7965. In addition, comply with all local or municipal asbestos requirements.

Use the following information to complete WisDNR form 4500-113:

- Site Name: Structure B-40-688, RAMP HIGHLAND AVE IH 43 NB over RAMP IH 43 NB STH 145
- Site Address: HIGHLAND ENT TO I 43 NB
- Ownership Information: WisDOT SE Region, 141 NW Barstow Street, Waukesha, WI 53187
- Contact: Steven KuhlPhone: (414) 531-6932
- Age: 14 years old. This structure was constructed in 2006.
- Area: 11768 SF of deck

Insert the following paragraph in Section 6.g.:

If asbestos not previously identified is found or previously non-friable asbestos becomes crumbled, pulverized, or reduced to a powder, stop work immediately, notify the engineer, and the engineer will notify the department's Bureau of Technical Services at (608) 266-1476 for an emergency response as specified in standard spec 107.24. Keep material wet until it is abated or until it is determined to be non-asbestos containing material.

Andrew Heeter, License Number All-194672, inspected Structure B-40-689 for asbestos on 6/17/2014. No regulated Asbestos Containing Material (RACM) was found on this structure. A copy of the inspection report is available from: David Pittman, (262) 548-6439.

In accordance with NR447 and DHS159, ensure that DNR or DHS receives a completed Notification of Demolition and/or Renovation (DNR Form 4500-113 (R 4/11), or subsequent revision) via U.S. mail, hand-delivery, or using the online notification system at least 10 working days before beginning any construction or demolition. Pay all associated fees. Provide a copy of the completed 4500-113 form to Andrew Malsom, (262) 548-6705 and DOT BTS-ESS attn: Hazardous Materials Specialist, PO Box 7965, Madison, WI 53707-7965. In addition, comply with all local or municipal asbestos requirements.

Use the following information to complete WisDNR form 4500-113:

- Site Name: Structure B-40-689, WINNEBAGO ST over IH 43
- Site Address: 0.1 MI S JCT STH 145
- Ownership Information: WisDOT SE Region, 141 NW Barstow Street, Waukesha, WI 53187
- Contact: Steven Kuhl
- Phone: (414) 531-6932
- Age: 14 years old. This structure was constructed in 2006.
- Area: 32804 SF of deck

Insert the following paragraph in Section 6.g.:

If asbestos not previously identified is found or previously non-friable asbestos becomes crumbled, pulverized, or reduced to a powder, stop work immediately, notify the engineer, and the engineer will notify the department's Bureau of Technical Services at (608) 266-1476 for an emergency response

1228-28-70 21 of 61

as specified in standard spec 107.24. Keep material wet until it is abated or until it is determined to be non-asbestos containing material.

Andrew Heeter, License Number All-194672, inspected Structure B-40-690 for asbestos on 6/6/2014. No regulated Asbestos Containing Material (RACM) was found on this structure. A copy of the inspection report is available from: David Pittman, (262) 548-6439.

In accordance with NR447 and DHS159, ensure that DNR or DHS receives a completed Notification of Demolition and/or Renovation (DNR Form 4500-113 (R 4/11), or subsequent revision) via U.S. mail, hand-delivery, or using the online notification system at least 10 working days before beginning any construction or demolition. Pay all associated fees. Provide a copy of the completed 4500-113 form to Andrew Malsom, (262) 548-6705 and DOT BTS-ESS attn: Hazardous Materials Specialist, PO Box 7965, Madison, WI 53707-7965. In addition, comply with all local or municipal asbestos requirements.

Use the following information to complete WisDNR form 4500-113:

- Site Name: Structure B-40-690, IH 43 NB over STH 145
- Site Address: 1.0 MI N JCT IH 94
- Ownership Information: WisDOT SE Region, 141 NW Barstow Street, Waukesha, WI 53187
- Contact: Steven KuhlPhone: (414) 531-6932
- Age: 14 years old. This structure was constructed in 2006.
- Area: 19329 SF of deck

#### Insert the following paragraph in Section 6.g.:

If asbestos not previously identified is found or previously non-friable asbestos becomes crumbled, pulverized, or reduced to a powder, stop work immediately, notify the engineer, and the engineer will notify the department's Bureau of Technical Services at (608) 266-1476 for an emergency response as specified in standard spec 107.24. Keep material wet until it is abated or until it is determined to be non-asbestos containing material.

Andrew Heeter, License Number All-194672, inspected Structure B-40-691 for asbestos on 6/6/2014. No regulated Asbestos Containing Material (RACM) was found on this structure. A copy of the inspection report is available from: David Pittman, (262) 548-6439.

In accordance with NR447 and DHS159, ensure that DNR or DHS receives a completed Notification of Demolition and/or Renovation (DNR Form 4500-113 (R 4/11), or subsequent revision) via U.S. mail, hand-delivery, or using the online notification system at least 10 working days before beginning any construction or demolition. Pay all associated fees. Provide a copy of the completed 4500-113 form to Andrew Malsom, (262) 548-6705 and DOT BTS-ESS attn: Hazardous Materials Specialist, PO Box 7965, Madison, WI 53707-7965. In addition, comply with all local or municipal asbestos requirements.

Use the following information to complete WisDNR form 4500-113:

- Site Name: Structure B-40-691, IH-43 SB over STH 145
- Site Address: 0.8 MI S JCT NORTH AVE
- Ownership Information: WisDOT SE Region, 141 NW Barstow Street, Waukesha, WI 53187
- Contact: Steven KuhlPhone: (414) 531-6932
- Age: 15 years old. This structure was constructed in 2005.
- Area: 16531 SF of deck

#### Insert the following paragraph in Section 6.g.:

If asbestos not previously identified is found or previously non-friable asbestos becomes crumbled, pulverized, or reduced to a powder, stop work immediately, notify the engineer, and the engineer will notify the department's Bureau of Technical Services at (608) 266-1476 for an emergency response as specified in standard spec 107.24. Keep material wet until it is abated or until it is determined to be non-asbestos containing material.

1228-28-70 22 of 61

Andrew Heeter, License Number All-194672, inspected Structure B-40-692 for asbestos on 6/17/2014. No regulated Asbestos Containing Material (RACM) was found on this structure. A copy of the inspection report is available from: David Pittman, (262) 548-6439.

In accordance with NR447 and DHS159, ensure that DNR or DHS receives a completed Notification of Demolition and/or Renovation (DNR Form 4500-113 (R 4/11), or subsequent revision) via U.S. mail, hand-delivery, or using the online notification system at least 10 working days before beginning any construction or demolition. Pay all associated fees. Provide a copy of the completed 4500-113 form to Andrew Malsom, (262) 548-6705 and DOT BTS-ESS attn: Hazardous Materials Specialist, PO Box 7965, Madison, WI 53707-7965. In addition, comply with all local or municipal asbestos requirements.

Use the following information to complete WisDNR form 4500-113:

- Site Name: Structure B-40-692, WALNUT ST over IH 43
- Site Address: 1.2 MI N JCT IH 94
- Ownership Information: WisDOT SE Region, 141 NW Barstow Street, Waukesha, WI 53187
- Contact: Steven KuhlPhone: (414) 531-6932
- Age: 14 years old. This structure was constructed in 2006.
- Area: 30180 SF of deck

Insert the following paragraph in Section 6.g.:

If asbestos not previously identified is found or previously non-friable asbestos becomes crumbled, pulverized, or reduced to a powder, stop work immediately, notify the engineer, and the engineer will notify the department's Bureau of Technical Services at (608) 266-1476 for an emergency response as specified in standard spec 107.24. Keep material wet until it is abated or until it is determined to be non-asbestos containing material.

stp-107-125 (20120615)

# 15. Removing Luminaires, Item 204.9060.S.1000.

# **A** Description

This special provision describes removing existing luminaires and lamps from light poles or bridge decks as the plans show, conforming to standard spec 204, and as follows. Light poles or bridge deck shall remain in service.

#### **B** Material

Removed luminaires and lamps become the property of the contractor. Properly dispose of all material off the project site. Lamps, which are considered a hazardous material, become property of the contractor and shall be disposed of in an environmentally sound manner.

#### **C** Construction

No removal work will be permitted without approval from the engineer. Removal shall start as soon as the temporary lighting or permanent lighting, as applicable, is placed in approved operation. An inspection and approval by the engineer will take place before any associated proposed permanent or temporary lighting is approved for operation.

# **D** Measurement

The department will measure Removing Luminaires by each individual unit, acceptably completed.

#### **E** Payment

Add the following to standard spec 204.5:

ITEM NUMBERDESCRIPTIONUNIT204.9060.S.1000Removing LuminairesEACH

SER-204.11 (20171021)

1228-28-70 23 of 61

# 16. Cold Patch, Item 495.1000.S.

# **A** Description

This special provision describes furnishing cold patch and filling potholes and other voids in existing pavement surfaces as the engineer directs.

#### **B** Materials

Furnish a mixture of course aggregate, natural sand, and MC-250 bituminous material designed to have a workability range of 15-100° F without heating. Ensure that the mixture:

- Adheres to wet surfaces.
- Resists damage from water, salt, and deicing products.
- Requires no mixing or special handling before use.
- Supports traffic immediately after placement and compaction.

Conform to the following gradation:

SIEVE SIZE	PERCENT PASSING (by weight)
1/2-inch (12.5 mm)	100
3/8-inch (9.5 mm)	90 - 100
No. 4 (4.75 mm)	90 max
No. 8 (2.38 mm)	20 - 65
No. 200 (0.074 mm)	2 - 10
Ritumen	48-54

The department will accept cold patch based primarily on the engineer's visual inspection. The department may also test for gradation.

#### **C** Construction

Stockpile cold patch on site on a smooth, firm, well-drained area cleared of vegetation and foreign material. Cover the stockpile and ensure that it is easily accessible. Replenish the stockpile throughout the project duration but limit the size at any given time to 10 tons on site unless the engineer approves otherwise. Dispose of unused material at project completion unless the engineer directs otherwise.

Place cold patch by hand. Remove ponded water and loose debris before placement. Compact flush with a tamper, roller, or vehicle tire after placement.

Refill patched areas as necessary to maintain a flush pavement surface until project completion.

#### **D** Measurement

The department will measure Cold Patch by the ton, acceptably stockpiled on site.

# **E** Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

•		•	•	•
ITEM NUMBER	DESCRIPTION			UNIT
495.1000.S	Cold Patch			TON

Payment for Cold Patch is full compensation for providing and maintaining patches; for furnishing and replenishing stockpiled material on-site; and for disposing of excess material at project completion.

stp-495-010 (20160607)

# 17. Expansion Device.

# **A** Description

This special provision describes furnishing and installing an expansion device as the plans show conforming to standard spec 502 as modified in this special provision.

1228-28-70 24 of 61

#### **B** Materials

The minimum thickness of the polychloroprene strip seal shall be 1/4 inch for non-reinforced elastomeric glands and 1/8 inch for reinforced glands. Furnish the strip seal gland in lengths suitable for a continuous one-piece installation at each individual expansion joint location. Provide preformed polychloroprene strip seals that conform to the requirements ASTM D3542, and have the following physical properties:

Property Requirements	Value	Test Method
Tensile Strength, min.	2000 psi	ASTM D412
Elongation @ Break, min	250%	ASTM D412
Hardness, Type A, Durometer	55 ± 5 pts.	ASTM D2240
Compression Set, 70 hours @212°F, max.	35%	D395 Method B Modified
Ozone Resistance, after 70 hrs. at 100°F under 20% Strain with 100 pphm ozone	No Cracks	ASTM D1149 Method A
Mass Change in Oil 3 after 70 hr. 212°F Mass Change, max.	45%	ASTM D471

Install the elastomeric strip seal gland with tools recommended by the manufacturer, and with a lubricant adhesive conforming to the requirements of ASTM D4070.

The manufacturer and model number shall be one of the following approved strip seal expansion device products:

# Model Number Strip Seal Gland Size<sup>[1]</sup>

Manufacturer	4-Inch	5-Inch	6-Inch
D.S. Brown	SSA2-A2R-400	SSA2-A2R-XTRA	SSA2-A2R-XTRA
R.J. Watson	RJA-RJ400	RJA-RJ500	RJA-RJ600
Watson Bowman Acme	A-SE400	A-SE500	A-SE800
Commercial Fabricators	A-AS400		

<sup>[1]</sup> Expansion device strip seal gland size requirement of 4", 5", and 6" shall be as the plans show.

Furnish manufacturer's certification for production of polychloroprene represented showing test results for the cured material supplied and certifying that it meets all specified requirements.

The steel extrusion or retainer shall conform to ASTM designation A 709 grade 36 steel. After fabrication, steel shall be galvanized conforming to the requirements ASTM A123.

Manufacturer's certifications for adhesive and steel shall attest that the materials meet the specification requirements.

stp-502-020 (20171130)

# 18. Sawing Pavement Deck Preparation Areas, Item 509.0310.S.

# **A** Description

This special provision describes sawing around deteriorated areas requiring deck repairs under the Preparation Decks bid items on decks receiving asphalt or polymer overlays and for deck repairs that will not receive an overlay.

#### B (Vacant)

#### **C** Construction

The department will sound and mark areas of deteriorated concrete that require deck preparation. The engineer may identify and mark additional areas as the work is being performed.

Wet cut a minimum of 1 inch deep and at least 2 inches outside of the marked areas. Bound each marked area by providing cuts aligned parallel and perpendicular to the deck centerline.

1228-28-70 25 of 61

Remove sawing sludge after completing each area. Do not allow sludge or resulting residue to enter a live lane of traffic, storm sewer, stream, lake, reservoir, marsh, or wetland. Dispose of sludge at an acceptable material disposal site located off the project limits or, if the engineer allows, within the project limits.

#### **D** Measurement

The department will measure Sawing Pavement Deck Preparation Areas by the linear foot, acceptably completed, measured as the total linear feet of bounding cuts.

The department will not measure for payment over-cuts or cuts made beyond what is required to bound engineer-marked deterioration limits.

# **E** Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER DESCRIPTION UNIT 509.0310.S Sawing Pavement Deck Preparation Areas LF

Payment is full compensation for making all saw cuts; and for debris disposal.

stp-509-070 (20180628)

# 19. Cleaning Decks to Reapply Concrete Masonry Overlay, Item 509.0505.S.

#### **A** Description

This special provision describes cleaning the entire bridge deck after the existing concrete masonry overlay is removed, prior to placing a new concrete masonry overlay.

# B (Vacant)

#### **C** Construction

Blast-clean the entire surface of the deck, the vertical faces of curbs, sidewalks and parapets to the depth of the adjoining concrete overlay. Blast-clean all exposed existing reinforcing steel. Repair damage to existing epoxy-coated reinforcement remaining in place that is either uncovered by or damaged by the contractor's operations. Use engineer-approved patching or repair material compatible with the existing coating and inert in concrete.

Clean the surface on which the new concrete will be placed to remove all loose particles and dust by either brooming and water pressure using a high-pressure nozzle, or by water and air pressure. Use water for cleaning that conforms to specifications for water under standard spec 501.2.4.

#### **D** Measurement

The department will measure Cleaning Decks to Reapply Concrete Masonry Overlay by the square yard, acceptably completed.

#### E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBERDESCRIPTIONUNIT509.0505.SCleaning Decks to Reapply Concrete Masonry OverlaySY

Payment for Cleaning Decks to Reapply Concrete Masonry Overlay is full compensation for cleaning the concrete surfaces.

stp-509-065 (20171130)

# 20. Concrete Masonry Deck Repair, Item 509.2100.S.

#### **A** Description

This special provision describes providing concrete masonry on the sawed deck preparation areas of the concrete bridge deck and in full depth deck, curb, and joint repair areas. Conform to standard spec 502 and standard spec 509.

1228-28-70 26 of 61

#### **B** Materials

#### **B.1 Neat Cement**

Furnish a neat cement bonding grout. Mix the neat cement in a water-cement ratio approximately equal to 5 gallons of water per 94 pounds of cement.

#### **B.2 Concrete**

Furnish grade C, C-FA, C-S, C-IS, C-IF, C-IT, or E concrete conforming to standard spec 501 for deck preparation, full-depth deck repair, curb repair and joint repair areas except as follows:

- 1. The contractor may increase slump of grade E concrete to 3 inches.
- 2. The contractor may use ready-mixed concrete.

Provide QMP for class II ancillary concrete as specified in standard spec 716.

#### **C** Construction

#### **C.1 Neat Cement**

Immediately before placing the concrete deck patching, coat the prepared surfaces with a neat cement mixture. Ensure the prepared concrete surfaces are moist without any standing water before coating with the neat cement mixture. Brush the neat cement mixture over the prepared concrete surfaces to ensure that all parts receive an even coating, and do not allow excess neat cement to collect in pockets. Apply the neat cement at a rate that ensures the cement does not dry out before being covered with the new concrete.

# **C.2 Placing Concrete**

Place concrete conforming to standard spec 509. As determined by the engineer, consolidate smaller areas by internal vibration, strike them off, and finish the areas with hand floats to produce plane surfaces that conform to the grade and elevation of the adjoining surfaces. Give all deck patching areas a final hand float finish.

# **C.3 Curing Concrete**

Cure the concrete masonry deck patching conforming to standard spec 502.2.6(1).

#### **D** Measurement

The department will measure the Concrete Masonry Deck Repair bid item by the cubic yard, acceptably completed.

The department will measure concrete used in deck preparation areas and in full depth deck, curb, and joint repair as part of the Concrete Masonry Deck Repair bid item.

The department will not measure wasted concrete.

# **E** Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBERDESCRIPTIONUNIT509.2100.SConcrete Masonry Deck RepairCY

Payment is full compensation for furnishing, hauling, preparing, placing, finishing, curing, and protecting all materials.

stp-509-060 (20191121)

# 21. Polymer Overlay, Item 509.5100.S.

# **A Description**

This special provision describes providing two layers of a two-component polymer overlay system to the bridge decks the plans show.

1228-28-70 27 of 61

#### **B** Materials

#### **B.1 General**

Furnish materials specifically designed for use over concrete bridge decks. Furnish polymer liquid binders from the department's approved product list.

# **B.2 Polymer Resin**

Furnish a polymer resin base and hardener composed of two-component, 100 percent solids, 100 percent reactive, thermosetting compound with the following properties:

Property	Requirements	Test Method
Gel Time <sup>[1]</sup>	15 - 45 minutes @ 73° to 75° F	ASTM C881
Viscosity <sup>[1]</sup>	7 - 70 poises	ASTM D2393, Brookfield RVT, Spindle No. 3, 20 rpm
Shore D Hardness <sup>[2]</sup>	60-75	ASTM D2240
Absorption <sup>[2]</sup>	1% maximum at 24 hr	ASTM D570
Tensile Elongation <sup>[2]</sup>	30% - 70% @ 7 days	ASTM D638
Tensile Strength <sup>[2]</sup>	2000 to 5000 psi @ 7 days	ASTM D638
Chloride Permeability <sup>[2]</sup>	<100 coulombs @ 28 days	AASHTO T277

<sup>[1]</sup> Uncured, mixed polymer binder

Ensure that the polymer resin when mixed with aggregate has the following properties:

Property	Requirement <sup>[1]</sup>	Test Method
Minimum Compressive Strength	1,000 psi @ 8 hrs 5,000 psi @ 24 hrs	ASTM C579 Method B, Modified <sup>[2]</sup>
Thermal Compatibility	No Delaminations	ASTM C884
Minimum Pull-off Strength	250 psi @ 24 hrs	ASTM C1583

<sup>[1]</sup> Based on samples cured or aged and tested at 75°F

# **B.3 Aggregates**

Furnish natural or synthetic aggregate that is non-polishing; clean; free of surface moisture; fractured or angular in shape; free from silt, clay, asphalt, or other organic materials; and conform to the following:

# **Aggregate Properties**

Property	Requirement	Test Method
Moisture Content <sup>[1]</sup>	1/2 of the measured aggregate absorption, %	ASTM C566
Hardness	≥6.5	Mohs Scale
Fractured Faces	100% with at least 1 fractured face & 80% with at least 2 fractured faces of material retained on No.16	ASTM D5821
Absorption	≤1%	ASTM C128

<sup>[1]</sup> Sampled and tested by the department before placement.

1228-28-70 28 of 61

<sup>[2]</sup> Cured, mixed polymer binder

Plastic inserts that will provide 2-inch by 2-inch cubes shall be placed in the oversized brass molds.

#### Gradation

Sieve Size	% Passing by Weight
No. 4	100
No. 8	30 – 75
No. 16	0 – 5
No. 30	0 – 1

# B.4 Approval of Bridge Deck Polymer Overlay System

A minimum of 20 working days before application, submit product data sheets and specifications from the manufacturer, and a certified report of test or analysis from an independent laboratory to the engineer for approval. The department will sample and test the aggregates for gradation and moisture content before placement. If requested, supply the department with samples of the polymer for the purpose of acceptance testing.

# **B.4.1 Product Data Sheets and Specifications**

Product data sheets and specifications from the manufacture consists of literature from the manufacturer showing general instructions, application recommendations/methods, product properties, general instructions, or any other applicable information.

# **B.4.2 Certified Report of Test or Analysis**

Conform to the following:

<u>Polymer Binder:</u> Submit a certified report of test or analysis from an independent laboratory dated less than 3 years before the date of the project letting showing the polymer binder meets the requirements of section B.2.

<u>Aggregates:</u> Submit a certified report of test or analysis from an independent laboratory dated less than 6 months before the date of the project letting showing the aggregates meet the requirements of section B.3.

#### **C** Construction

# C.1 General

Ensure that the overlay system is 1/4 inch thick or thicker.

Conform to the following:

<u>Field Review:</u> Conduct a field review of the existing deck to identify any possible surface preparation and material compatibility issues.

<u>Pre-Installation Meeting</u>: Conduct a pre-installation meeting with the manufacturer's representative and the engineer before construction. Discuss the field review findings, verification testing of the surface preparation and establish procedures for maintaining optimum working conditions and coordination of work. Furnish the engineer a copy of the recommended procedures and apply the overlay system according to the manufacturer's instructions. Supply for the engineer's use for the duration of the project, a Concrete Surface Profile (CSP) chip set of 10 from the International Concrete Repair Institute (ICRI).

<u>Manufacturer's Representative:</u> An experienced manufacturer's representative familiar with the overlay system installation procedures shall be present at all times during surface preparation and overlay placement to provide quality assurance that the work is being performed properly. This requirement may be reduced at the engineer's discretion.

<u>Material Storage</u>: Store and handle materials according to the manufacturer's recommendations. Store resin materials in their original containers in a dry area. Store all aggregates in a dry environment and protect aggregates from contaminants on the job site.

# **C.2 Deck Preparation**

#### C.2.1 Deck Repair

Remove all asphaltic patches and unsound or disintegrated areas of the concrete decks as the plans show, or as the engineer directs. Work performed to repair the concrete deck will be paid for under other items. Ensure that products used for deck patching are compatible with the polymer overlay system.

1228-28-70 29 of 61

NOTE: Some polymer systems require concrete patch material to be in place a minimum of 28-days before overlaying - contact polymer manufacturer before completing deck patching/repair.

#### C.2.2 Surface Preparation

Determine an acceptable shotblasting machine operation (size of shot, flow of shot, forward speed, and/or number of passes) that provides a surface profile meeting CSP 5 (medium-heavy shotblast) according to the ICRI Technical Guideline No. 310.2. If the engineer requires additional verification of the surface preparation, test the tensile bond strength according to ASTM C1593. The surface preparation will be considered acceptable if the tensile bond strength is greater than or equal to 250 psi or the failure area at a depth of 1/4 inches or more is greater than 50 percent of the test area. Continue adjustment of the shotblasting machine and necessary testing until the surface is acceptable to the engineer or a passing test result is obtained.

Prepare the entire deck using the final accepted adjustments to the shotblasting machine as determined above. Thoroughly blast clean with hand-held equipment any areas inaccessible by the shotblasting equipment. Do not perform surface preparation more than 24 hours before the application of the overlay system.

Protect drains, expansion joints, access hatches, or other appurtenances on the deck from damage by the shot and sand blasting operations and from materials adhering and entering. Tape or form all construction joints to provide a clean straight edge.

Before shot blasting, remove pavement markings within the treatment area using an approved mechanical or blasting method.

Prepare the vertical concrete surfaces adjacent to the deck a minimum of 2" above the overlay according to SSPC-SP 13 (free of contaminants, dust, and loose concrete) by sand blasting, using wire wheels, or other approved method.

Just before overlay placement, clean all dust, debris, and concrete fines from the prepared surfaces including the vertical surfaces with compressed air. When using compressed air, the air stream must be free of oil. Any grease, oil, or other foreign matter that rests on or has absorbed into the concrete shall be removed completely. If prepared surfaces (including the first layer of the polymer overlay) are exposed to rain or dew, lightly sandblast (brush/breeze blast) the exposed surfaces.

The engineer may consider alternate surface preparation methods per the overlay system manufacture's recommendations. The engineer will approve the final surface profile and deck cleanliness before the contractor placing the polymer overlay.

#### C.2.3 Transitional Area

If the plans show, create a transitional area approaching transverse expansion joints and ends of the deck using an approved mechanical or blasting method. Remove 1/4 inch to 5/16 inch of concrete adjacent to the joint or end of deck and taper a distance of 3 feet.

If the plans show, create a transitional area on the approach pavement. Prep and place the first lift 3 feet beyond the end of the deck the same width as the deck. Prep and place the second lift 6 feet beyond the end of the deck the same width as the deck.

#### C.3 Overlay Application

Perform the handling and mixing of the polymer resin and hardening agent in a safe manner to achieve the desired results according to the manufacturer's instructions. Do not apply the overlay system if any of the following exists:

- 1. Ambient air temperature is below 50 F or above 100 F.
- 2. Deck temperature is below 50 F.
- 3. Moisture content in the deck exceeds 4.5 percent when measured by an electronic moisture meter or shows visible moisture after 2 hours when measured in accordance with ASTM D4263.
- 4. Rain is forecasted during the minimum curing periods listed under C.5.
- 5. Materials component temperatures below 65 F or above 99 F.
- 6. Concrete age is less than 28 days unless approved by the engineer.
- 7. The deck temperature exceeds 100 F.
- 8. If the gel time is 10 minutes or less at the predicted high air temperature for the day.

1228-28-70 30 of 61

After the deck has been shotblasted or during the overlay curing period, only necessary surface preparation and overlay application equipment will be allowed on the deck. Provide appropriate protective measures to prevent contamination from equipment allowed on the deck during preparation and application operations. Begin overlay placement as soon as possible after surface preparation operations.

The polymer overlay shall consist of a two-course application of polymer and aggregate. Each of the two courses shall consist of a layer of polymer covered with a layer of aggregate in sufficient quantity to completely cover the polymer. Apply the polymer and aggregate according to the manufacturer's requirements. Apply the overlay using equipment designed for this purpose. The application machine shall feature positive displacement volumetric metering and be capable of storing and mixing the polymer resins at the proper mix ratio. Disperse the aggregate using a method that provides a uniform, consistent coverage of aggregate and minimizes aggregate rolling or bouncing into final position. First course applications that do not receive enough aggregate before the polymer gels shall be removed and replaced. A second course applied with insufficient aggregate may be left in place but will require additional applications before opening to traffic.

After completion of each course, cure the overlay according to the manufacturer's instructions. Follow the minimum cure times listed under C.5 or as prescribed by the manufacturer. Remove the excess aggregate from the surface treatment by sweeping, blowing, or vacuuming without tearing or damaging the surface; the material may be re-used if approved by the engineer and manufacturer. Apply all courses of the overlay system before opening the area to traffic. Do not allow equipment or traffic on the treated area until directed by the engineer.

After the first layer of coating has cured to the point where the aggregate cannot be pulled out, apply the second layer. Before applying the second layer, broom and blow off the first layer with compressed air to remove all loose excess aggregate.

Before opening to traffic, clean expansion joints and joint seals of all debris and polymer. A minimum of 3 days following opening to traffic, remove loosened aggregates from the deck, expansion joints, and approach pavement.

# C.4 Application Rates

Apply the polymer overlay in two separate courses in accordance with the manufacturer's instructions, but not less than the following rate of application.

Course	Minimum Polymer Rate <sup>[1]</sup> (GAL/100 SF)	Aggregate <sup>[2]</sup> (LBS/SY)
1	2.5	10+
2	5.0	14+

<sup>&</sup>lt;sup>[1]</sup> The minimum total applications rate is 7.5 GAL/100 SF.

# **C.5 Minimum Curing Periods**

As a minimum, cure the coating as follows:

	Average temperature of deck, polymer and aggregate components in degrees F							
Course	50-54	55-59	60-64	65-69	70-74	75-79	80-84	85-99
1	6 hrs.	5 hrs.	4 hrs.	3 hrs.	2.5 hrs	2 hrs	1.5 hrs.	1 hr.
2	8 hrs.	6.5 hrs.	6.5 hrs.	5 hrs.	4 hrs.	3 hrs.	3 hrs.	3 hrs.

If faster cure times are desired and achievable, submit to the engineer a certified test report from an independent laboratory showing the material is able to reach a compressive strength of 1000 psi as tested per ASTM C 579 Method B within the temperature ranges and cure times for which the product is proposed to be placed. Establish ambient air, material, and substrate temperatures from the manufacturer for field applications. Field applications will not be allowed below the documented temperatures.

1228-28-70 31 of 61

<sup>&</sup>lt;sup>[2]</sup> Application of aggregate shall be of sufficient quantity to completely cover the polymer.

#### C.6 Repair of Polymer Overlay

Repair all areas of unbonded, uncured, or damaged polymer overlay for no additional compensation. Submit repair procedures from the manufacturer to the engineer for approval. Absent a manufacturer's repair procedures and with the approval of the engineer, complete repairs according to the following: Saw cut the limits of the area to the top of the concrete; remove the overlay by scarifying, grinding, or other approved methods; shot blast or sand blast and air blast the concrete before placement of polymer overlay; and place the polymer overlay according to section C.3.

#### **D** Measurement

The department will measure Polymer Overlay by the square yard acceptably completed.

# E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER DESCRIPTION UNIT 509.5100.S Polymer Overlay SY

Payment is full compensation for preparing the surface; for tensile bond testing; for creating the transitional area; for providing the overlay; for cleanup; and for sweeping/vacuuming and disposing of excess materials.

The department will pay separately for Concrete Deck Repair.

stp-509-030 (20170615)

# 22. Removing Concrete Masonry Deck Overlay B-40-292 Item 509.9005.S.0001.

#### **A** Description

This special provision describes removing concrete bridge deck overlays by milling the entire bridge deck as the plans show.

Conform to standard spec 204 as modified in this special provision.

#### B (Vacant)

# **C** Construction

#### C.1 Milling

Use a self-propelled milling machine that is specially designed and constructed for milling bridge decks. It shall mill without tearing or gouging the concrete masonry underlying the deck overlay. The machine shall consist of a cutting drum with carbide or diamond tip teeth. Space the teeth on the drum to mill a surface finish that is acceptable to the engineer.

Shroud the machine to prevent discharge of any loosened material into adjacent work areas or live traffic lanes. Equip the machine with electronic devices that provide accurate depth, grade and slope control, and an acceptable dust control system.

Perform milling in a manner that precludes damage to the bridge floor and results in a uniform textured finish that:

- 1. Is free of sharp protrusions;
- 2. Has uniform transverse grooves that measure up to 1/4 inch vertically and transversely; and
- 3. If applicable, is acceptable to the manufacturer of the sheet waterproof membrane.

Windrowing and storing of the removed milled concrete masonry on the bridge is only permitted in connection with the continuous removal and pick-up operation. During nonworking hours, clear the bridge of all materials and equipment.

#### **D** Measurement

The department will measure Removing Concrete Masonry Deck Overlay (Structure) in area by the square yard, acceptably completed.

1228-28-70 32 of 61

# E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER DESCRIPTION UNIT

509.9005.S.0001 Removing Concrete Masonry Deck Overlay B-40-292

SY

Payment is full compensation for removing the concrete masonry; and for properly disposing of all materials.

stp-509-005 (20171130)

# 23. Removing Asphaltic Concrete Deck Overlay B-40-292, Item 509.9010.S.0001.

# **A** Description

This special provision describes removing asphalt bridge deck overlays with or without an underlayment of waterproof membrane by milling the entire bridge deck as the plans show.

Conform to standard spec 204 as modified in this special provision.

# B (Vacant)

#### **C** Construction

#### C.1 Milling

Use a self-propelled milling machine that is specially designed and constructed for milling bridge decks. It shall mill without tearing or gouging the concrete masonry underlying the deck overlay. The machine shall consist of a cutting drum with carbide or diamond tip teeth. Space the teeth on the drum to mill a surface finish that is acceptable to the engineer.

Shroud the machine to prevent discharge of any loosened material into adjacent work areas or live traffic lanes. Equip the machine with electronic devices that provide accurate depth, grade and slope control, and an acceptable dust control system.

Perform milling in a manner that precludes damage to the bridge floor and results in a uniform textured finish that:

- Is free of sharp protrusions;
- Has uniform transverse grooves that measure up to 1/4 inch vertically and transversely; and
- If applicable, is acceptable to the manufacturer of the sheet waterproof membrane.

Windrowing or storing of the removed milled asphaltic concrete on the bridge is only permitted in connection with the continuous removal and pick-up operation. During nonworking hours, clear the bridge of all materials and equipment.

#### **D** Measurement

The department will measure Removing Asphaltic Concrete Deck Overlay (Structure) in area by the square yard, acceptably completed.

# **E** Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBERDESCRIPTIONUNIT509.9010.S.0001Removing Asphaltic Concrete Deck Overlay B-40-292SY

Payment is full compensation for removing the asphaltic concrete with or without an underlayment of waterproof membrane; and for properly disposing of all materials.

stp-509-010 (20171130)

1228-28-70 33 of 61

# 24. Preparation and Coating of Top Flanges B-40-429, Item 517.0900.S.0001.

# **A** Description

This special provision describes thoroughly cleaning and coating the top surface and edges of the top flanges, removing loose paint, rust, mill scale, dirt, oil, grease, or other foreign substances until the specified finish is obtained.

#### B (Vacant)

#### **C** Construction

For top flanges and edges that have no paint on them and in accordance with the department's Pre-Qualified Paint Systems for Structure Overcoating Cleaning and Priming, clean the top surface and edges of the top flanges and paint them with one coat of an approved zinc rich primer. Paint for Solvent Cleaning for Overcoat-minimum Cleaning (SP-1) is not allowed.

For top flanges and edges that have paint on them and in accordance with the department's Pre-Qualified Paint Systems for Structure Overcoating Cleaning and Priming, clean all areas of rust and loose paint on the top surface and edges of the top flanges. Wash the top surface and edges of the top flanges and paint them with one coat of an approved zinc-rich primer in accordance with paint manufacture's recommendations. If flash rusting occurs before the application of the primer, stop painting application, remove the flash rusting and paint cleaned surface. Paint for Solvent Cleaning for Overcoat-minimum Cleaning (SP-1) is not allowed.

Where plans call for the cleaning of other painted structural steel including hanger assemblies, bearings, field splices, and connections, clean areas of loose paint and rust in accordance with the department's Pre-Qualified Paint Systems for Structure Overcoating Cleaning and Priming, or and in accordance with paint manufacture's cleaning recommendations. Sound paint need not be removed with the exception of an area 12 inch on either side of hanger assembly centerlines. Clean this area to base metal according to the paint manufacture's cleaning recommendations and paint them one coat of an approved zinc-rich primer in accordance with paint manufacture's recommendations. Paint for Solvent Cleaning for Overcoat-minimum Cleaning (SP-1) is not allowed.

For areas of exposed steel members that are to be imbedded in new concrete and in accordance with the department's Pre-Qualified Paint Systems for Structure Overcoating Cleaning and Priming, thoroughly clean the surface area of exposed steel members that are to be imbedded in the new concrete and solvent wash and paint one coat of an approved zinc rich primer in accordance with paint manufacture's recommendations to these areas. Paint for Solvent Cleaning for Overcoat-minimum Cleaning (SP-1) is not allowed.

According to the approved project specific hazardous material containment plan, furnish and erect tarpaulins or other materials to collect all of the spent paint containing material resulting from blasting or hand and power tool cleaning and coating. Minimize dust during all clean-up activities. Collect and store waste material at the end of each work day or more often if needed. Store waste materials in the hazardous waste containers provided. Lock and secure all waste containers at the end of each work day. Cover containers at all times except when adding or removing waste material. Store the containers in an accessible and secured area, not located in a storm water runoff course, flood plain or exposed to standing water. Transportation and disposal of such waste material will be the responsibility of the department.

Damage to existing painted surfaces as a result of construction operations, shall be restored to the approval of the engineer at the contractor's expense.

#### **D** Measurement

The department will measure Preparation and Coating of Top Flanges (Structure) as a single complete lump sum unit of work for the structure, completed according to the contract and accepted.

#### E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER DESCRIPTION UNIT 517.0900.S.0001 Preparation and Coating of Top Flanges B-40-429 LS

Payment is full compensation for preparing and cleaning the designated surfaces; and for furnishing and applying the coating.

stp-517-010 (20140630)

1228-28-70 34 of 61

# 25. Concrete Staining B-40-292, Item 517.1010.S.4001; Concrete Staining B-40-293, Item 517.1010.S.4002.

# **A** Description

This special provision describes providing a two coat concrete stain on the exposed concrete surfaces of structures as the plans show.

#### **B** Materials

#### **B.1 Mortar**

Use mortar for sack rubbing the concrete surfaces as given in standard spec 502.3.7.5 or use one of the following products:

Preblended, Packaged Type II Cement: Tri-Mix by TK Products

Thoroseal Pearl Gray by Thoro Products

The mortar shall contain one of the following acrylic bonding admixtures mixed and applied according to manufacturer's recommendations:

Acrylic Bonding Admixture: TK-225 by TK Products

Achro 60 by Thoro Products
Achro Set by Master Builders

#### **B.2 Concrete Stain**

Use concrete stain manufactured for use on exterior concrete surfaces, consisting of a base coat and a pigmented sealer finish coat. Use the following products, or equal as approved by the department, as part of the two coat finish system:

Tri-Sheen Concrete Surfacer, Smooth by TK Products

Tri-Sheen Acrylic by TK Products

TK-1450 Natural Look Urethane Anti-Graffiti Primers by TK Products

Safe-Cure & Seal EPX by Chem Masters

H&C Concrete Stain Solid Color Water Based by Sherwin-Williams

#### **C** Construction

#### C.1 General

Furnish, prepare, apply, cure, and store all materials according to the product manufacturer's specifications for the type and condition of application required.

Match or exceed the stain manufacturer's minimum recommended curing time of the concrete or 28 days, whichever is greater, before staining.

#### C.2 Preparation of Concrete Surfaces

Provide a sack rubbed finish as specified in standard spec 502.3.7.5, using mortar as indicated above on concrete surfaces with open voids or honeycombing.

Following the sack rubbing, clean all concrete surfaces that are to be coated to ensure that the surface is free of all laitance, dirt, dust, grease, efflorescence, and any foreign material and that the surface will accept the coating material according to product requirements. As a minimum, clean the surface using a 3000-psi water blast. Hold the nozzle of the water blaster approximately 6 inches from the concrete surface and move it continuously in a sweeping motion. Give special attention to smooth concrete surfaces to produce an acceptable surface texture. Correct any surface problems resulting from the surface preparation methods. Grit blasting of the concrete surface is not allowed.

#### C.3 Staining Concrete Surfaces

Apply the concrete stain according to the manufacturer's recommendations.

Apply the concrete stain when the temperature of the concrete surface is 45° F or higher, or as given by the manufacturer.

1228-28-70 35 of 61

The color of the stain shall be as given on the plan. Tint the base coat to match the finish coat; the two coats shall be compatible with each other.

Do not begin staining the structure until earthwork operations are completed to a point where this work can begin without receiving damage. Where this work is adjacent to exposed soil or pavement areas, provide temporary covering protection from overspray or splatter.

#### C.4 Test Areas

Before applying stain to the structure, apply the stain to sample panels measuring a minimum of 48 inches x 48 inches and constructed to demonstrate workmanship in the use of the form liner specified on the structure if applicable. Match or exceed the stain manufacturer's minimum recommended curing time of the concrete or 28 days, whichever is greater, before staining. Prepare the concrete surfaces of the sample panels and apply stain using the same materials and in the same manner as proposed for the structure, including staining of the joints between the stones produced by the form liner if applicable. Do not apply stain to the structure until the department approves the test panels.

#### C.5 Surfaces to be Coated.

Apply concrete stain to the surfaces according to the plan.

#### **D** Measurement

The department will measure Concrete Staining (Structure) in area by the square foot of surface, acceptably prepared and stained.

# **E** Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
517.1010.S.4001	Concrete Staining B-40-292	SF
517.1010.S.4002	Concrete Staining B-40-293	SF

Payment is full compensation for furnishing and applying the two coat system; for preparing the concrete surface; and for preparing the sample panels.

stp-517-110 (20140630)

# 26. Structure Repainting General.

#### A General

#### A.1 Inspection

On all structures in this contract, notify the engineer of any missing or broken bolts or nuts, any missing or broken rivets, or of any cracks or flaws in the steel members while cleaning or painting.

#### A.2 Date Painted

At the completion of all painting work, stencil in black paint or contrasting color paint the date of painting the bridge. The numbers shall be three inches (75 mm) in height and shall show the month and year in which the painting was completed: e.g., 11-95 (November 1995). On each bridge painted, stencil the date at two locations. On truss bridges, stencil the date on the cover plates of end posts near and above the top of the railings at the oncoming traffic end. On steel girder bridges, stencil the date on the inside of the outside stringers at the abutments. The date on grade separation bridges shall be readable when going under the structure or at some equally visible surface near the ends of the bridge, as designated by the engineer.

#### A.3 Graffiti Removal

Remove any graffiti on concrete abutments, piers, pier caps, parapet railings, slope paving or any other location at the direction of the engineer. Use a brush sandblast to remove graffiti.

The above work will not be measured and paid for separately, but will be considered incidental to other items in the contract.

#### B (Vacant)

1228-28-70 36 of 61

#### **C** Construction

# **C.1 Repainting Methods**

Do not perform blasting, cleaning and painting on days of high winds. Prevailing winds in excess of 15 mph (25 km/hr) shall be considered high winds.

Place the final field coat of paint on the exterior of the exterior beams as a continuous painting operation. Stop at splices, vertical stiffeners or other appropriate locations so that lap marks are not evident or noticeable.

Completely clean and remove spent abrasive and other waste materials resulting from the contractor's operation from bridge deck surfaces, gutter lines, drains, curbs, bridge seats, pier caps, slope paving, roadway below, and all structural members and assemblies.

# C.2 Inspection

Add the following to standard spec 105.9:

Furnish, erect and move scaffolding and other equipment to allow the inspector to closely observe all affected surfaces. The scaffolding, with appropriate safety devices, shall meet the approval of the engineer. stp-517-005 (20150630)

# 27. Structure Repainting Recycled Abrasive B-40-429, Item 517.1800.S.0001.

# **A** Description

This special provision describes surface preparation and painting of the metal surfaces according to the manufacturer's recommendations as modified in this special provision.

#### A.1 Areas to be Cleaned and Painted

All structural metal surfaces of:

1. Structure B-40-429 57,700 SF.

Areas are approximate and given for informational purposes only.

#### **B** Materials

# **B.1 Coating System**

Furnish a complete coating system from the department's approved list for "Structure Repainting Recycle Abrasive Structure". The color for the finish coating material shall match the color number the plans show according to Federal Standard Number 595. Supply the engineer with the product data sheets for approval before any coating is applied. The product data sheets shall indicate the mixing and thinning directions, the recommended spray nozzles and pressures, and the minimum drying time between coats.

The color of the primer must be such that a definite contrast between it and the color of the blasted steel is readily apparent. There shall be a color contrast between all subsequent coats for the paint system selected. Submit color samples of the primer and all coats to the engineer for approval before any application of paint.

#### **C** Construction

# **C.1 Surface Preparation**

Before blast cleaning, solvent clean all surfaces to be coated according to SSPC-SP1.

All metal surfaces must be blast cleaned in accordance with SSPC-SP10 and verified before painting.

Upon completion of surface preparation, test representative surfaces, which were previously rusted (i.e. pitted steel) for the presence of residual chloride. Perform Surface Contamination Tests (SCAT) in accordance with the manufacturer's recommendations. The tests must be witnessed by the engineer. If chlorides are detected at levels greater than  $7 \text{ug/cm}^2$ , continue to clean the affected areas until results are below the specified limit. Submit anticipated testing frequencies and chloride remediation methods to the engineer for review and approval.

1228-28-70 37 of 61

Apply the prime coat the same day that the metal surfaces receive the No. 10 blast or re-blast before application. Cleaned surfaces shall be of the specified condition immediately before paint application. If rust bloom occurs before applying the primer, stop the painting operation in the area of the rust bloom and re-blast and clean the area to SSPC SP-10 before applying the primer.

The steel grit and any associated equipment brought to the site and used for blast cleaning shall be clean. Remove immediately dirty grit or equipment brought to the site at no expense to the department. Furnish an abrasive that has a gradation such that it will produce a uniform surface profile between 1 to 3 mils on the steel surface, as measured in accordance with ISO 8503-5.

The abrasive blasting and recovery system shall be a completely integrated self-contained system for abrasive blasting and recovery. It shall be an open blast and recovery system that will allow no emissions from the recovery operation. The recovery equipment shall be such that the amount of contaminants in the clean recycled steel grit shall be less than 1 percent by weight as per SSPC AB-2.

Remove by grinding all fins, tears, slivers, and burred or sharp edges that are present on any steel member, or that appear during the blasting operation, and re-blast the area to give a 1 to 3 mils surface profile.

Remove all spent material and paint residue from steel surfaces with a good commercial grade vacuum cleaner equipped with a brush-type cleaning tool, and test cleanliness in accordance with ASTM D4285. The airline used for surface preparation shall have an in-line water trap and the air shall be free of oil and water as it leaves the airline.

Take care to protect freshly coated surfaces from subsequent blast cleaning operations. Thoroughly wire brush damaged primed surfaces with a non-rusting tool, or if visible rust occurs, re-blast to a near white condition. Clean and re-prime the brushed or blast cleaned surfaces in accordance with this specification.

# **C.2 Coating Application**

Apply paint according to the manufacturer's recommendations in a neat workmanlike manner. Paint application shall normally be by airless spray or inaccessible areas by brush, roller or other methods approved by the engineer.

The engineer may allow the use of conventional spray equipment after satisfactory demonstration by the contractor of the proper application technique and handling of that equipment.

Mix the paint or coatings according to the manufacturer's directions to a smooth lump-free consistency. Keep paint thoroughly mixed during the painting application.

After the inspector approves the entire cleaned surface to be coated, apply a prime coat uniformly to the entire surface. Either before or after applying the prime coat, brush or spray a stripe coat of primer on all plate edges, bolt heads, nuts, and washers. Apply succeeding coats as the product data sheet shows.

Remove all dry spray by vacuuming, wiping, or sanding if necessary.

If the application of the coating at the required thickness in one coat produces runs, bubbles, or sags; apply a "mist-coating" in multiple passes of the spray gun; separate the passes by several minutes. Where excessive coating thickness produces "mud-cracking", remove such coating back to soundly bonded coating and re-coat the area to the required thickness.

The resultant paint film shall be smooth and uniform, without skips or areas of excessive paint in accordance with SSPC PA1.

The coating is supplied for normal use without thinning. If in cool weather it is necessary to thin the coating for proper application, thin according to the manufacturer's recommendations.

During surface preparation and coating application the ambient and steel temperature shall be between 39 degrees F and 100 degrees F. The steel temperature shall be at least 5 degrees F above the dew point temperature. (This requires the steel to be dry and free of any condensation or ice regardless of the actual temperature of the steel.) The relative humidity shall not exceed 85%. The manufacturer's ambient condition requirements must be followed if they are more stringent.

Paint thickness shall be within the requirements for a three coat paint system listed in the department's approved list for Structure Repainting Recycle Abrasive Structure and the paint system being used.

Time to recoat shall be according to the manufacturer's recommendations.

1228-28-70 38 of 61

The dry film thickness will be determined by use of a magnetic film thickness gage. The gage shall be calibrated for dry film thickness measurement according to SSPC-PA 2. Dry film thickness in each area measured will be based on an average of three gage readings, after calibration of the gage to account for surface profile of the bare steel as a result of surface preparation.

#### **D** Measurement

The department will measure Structure Repainting Recycled Abrasive (Structure) as a single complete lump sum unit of work, completed according to the contract and accepted.

#### **E** Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBERDESCRIPTIONUNIT517.1800.S.0001Structure Repainting Recycled Abrasive B-40-429LS

Payment is full compensation for preparing and cleaning the designated surfaces; furnishing and applying the paint; and for providing the listed equipment.

stp-517-050 (20190618)

# 28. Labeling and Disposal of Waste Material.

The EPA ID number for Structure B-40-429 is WIR000173518.

The state has an exclusive mandatory use contract with a private waste management contractor to transport and dispose of hazardous waste.

The state's waste management contractor shall furnish and deliver appropriate hazardous waste containers and site-specific labels to each bridge site. The provided containers shall be placed at preselected drop-off and pick-up points at each bridge site, and these locations shall be determined at the preconstruction conference. The custody of the containers and labels shall be the responsibility of the painting contractor while they are at the job site.

Contact the waste management contractor a minimum of 10 working days in advance to request container drop-off or pickup. Provide the waste management contractor with the project ID, structure number, EPA ID, and the agreed-upon location for container staging. Contact information for the waste management contractor is located on the WisDOT Internet site at <a href="http://wisconsindot.gov/Documents/doing-bus/eng-consultants/cnslt-rsrces/environment/hazwaste-contacts.pdf">http://wisconsindot.gov/Documents/doing-bus/eng-consultants/cnslt-rsrces/environment/hazwaste-contacts.pdf</a>.


Report all reportable spills and discharges according to the contingency plan.

Labels are site-specific. Check the labels to ensure that the project ID, structure number, and EPA ID match the structure generating the waste. Apply a label to each drum when it is opened for the first time. Fill in the date on the label the first day material is accumulated in the drum. The following page is an example of a properly filled-in label.

During paint removal operations, continuously monitor and notify the project inspector of the status of waste generation and quantity stored so that timely disposal can be arranged.

stp-517-055 (20190618)

1228-28-70 39 of 61



# 29. Negative Pressure Containment and Collection of Waste Materials, B-40-429, Item 517.4500.S.0001.

# **A** Description

This special provision describes providing a dust collector to maintain a negative air pressure in the enclosure; furnishing and erecting enclosures as required to contain, collect and store waste material resulting from the preparation of steel surfaces for painting, and repainting, including collection of such waste material, and labeling and storing waste material in approved hazardous waste containers.

1228-28-70 40 of 61

#### B (Vacant)

#### **C** Construction

Erect an enclosure to completely enclose (surround) the blasting operations. The ground, slope paving, or roadway cannot be used as the bottom of the enclosure unless covered by approved containment materials. So that there are no visible emissions to the air or ground or water, design, erect, operate, maintain and disassemble the enclosures in such a manner to effectively contain and collect dust and waste materials resulting from surface preparation and paint over spray. Suspend all enclosures over water from the structure or as approved by the engineer.

Construct the enclosure of flexible materials such as tarpaulins or of rigid materials such as plywood, or of a combination of flexible and rigid materials and meet SSPC Guide 6 requirements with Level 1 emissions. Systems manufactured and provided by Eagle Industries, Detroit Tarps, or equal, are preferred. The tarpaulins shall be a non-permeable material, either as part of the tarp system or have a separate non-permeable lining. Maintain all materials free of tears, cuts or holes. The vertical sides of the enclosure shall extend from the bottom of the deck down to the level of the covered work platform or covered barge where used for structures over water and shall be fastened securely to those levels to prevent the wind from lifting them. Bulkheads are required between beams to enclose the blasting area as approved by the engineer. Where bulkheads are required, construct them of plywood and properly seal them. To prevent spent materials and paint over spray from escaping the enclosed area, overlap and fasten together all seams. Place groundcovers under all equipment before operations or as approved by the engineer.

To allow proper cleaning, inspection of structures or equipment, and painting, provide safe adequate artificial lighting in areas where natural light is inadequate.

Provide a dust collector so that there are no visible emissions outside of the enclosure and so that a negative air pressure inside the enclosure is maintained. The dust collector shall be sized to maintain the minimum air flow based on the cross-sectional area of the enclosure.

A combination of positive air input and negative air pressure may be needed to maintain the minimum airflow within the enclosure.

Filter all air exhausted from the enclosure to create a negative pressure within the enclosure so as to remove all hazardous and other particulate matter.

After all debris has been removed and all painting has been approved in the containment area is complete, remove containment in accordance with SSPC Guide 6.

As a safety factor for structures over water, provide for scum control. Provide a plan for corrective measures to mitigate scum forming and list the procedures, labor and equipment needed to assure compliance. Effectively contain the scum that forms on the water and does not sink in place from moving upstream or downstream by the use of floating boom devices.

If, in the use of floating boom devices, the scum tends to collect at the devices, contain, collect, store the scum, and do not allow it to travel upstream or downstream beyond the devices. Remove the scum at least once a day or more often if needed.

Collect and store at the bridge site for disposal all waste material or scum collected by this operation, or any that may have fallen onto the ground tarps. Collect and store all waste material and scum at the end of each workday or more often if needed. Storage shall be in provided hazardous waste containers. Label each container as it is filled, using the labels provided by the Hazardous Waste Disposal contractor. Check the label and ensure that the project ID, bridge number and EPA ID match the structure. Fill in the generation date when the first material is placed in the container. Secure all containers at the end of each workday. Keep the containers covered at all times except to add or remove waste material. Store the containers in an accessible and secured area, not located in a storm water runoff course, flood plain, or exposed to standing water.

In a separate operation, recover the recyclable abrasive for future application, and collect the paint and/or corrosion particles for disposal.

#### **D** Measurement

The department will measure Negative Pressure Containment and Collection of Waste Materials (Structure) as a single complete lump sum unit of work for each structure designated in the contract, completed in accordance with the contract and accepted.

1228-28-70 41 of 61

# **E** Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER DESCRIPTION UNIT

517.4500.S.0001 Negative Pressure Containment and Collection of Waste Materials B-40-429 LS

Payment is full compensation for designing, erecting, operating, maintaining, and disassembling the containment devices; providing negative pressure exhaust ventilation; collecting, labeling, and for storing spent materials in provided hazardous waste containers.

stp-517-065 (20140630)

# 30. Portable Decontamination Facility, Item 517.6001.

# **A Description**

This special provision describes furnishing and maintaining weekly, or more often if needed, a single unit portable decontamination facility.

#### **B** Materials

Supply and operate all equipment in accordance with OSHA.

Supply adequate heating equipment with the necessary fuel to maintain a minimum temperature of 68° F in the facility.

The portable decontamination facility shall consist of a separate "Dirty Room", "Shower Room" and "Clean Room". The facility shall be constructed so as to permit use by either sex. The facility shall have adequate ventilation.

The "Dirty Room" shall have appropriately marked containers for disposable garments, clothing that requires laundering, worker shoes, and any other related equipment. Each container shall be lined with poly bags for transporting clothing, or for disposal. Benches shall be provided for personnel.

The "Shower Room" shall include self-contained individual showering stalls that are stable and well secured to the facility. Provide showers with a continuous supply of potable hot and cold water. The wastewater must be retained for filtration, treatment, and/or for proper disposal.

The "Clean Room" shall be equipped with secure storage facilities for street clothes and separate storage facilities for protective clothing. The lockers shall be sized to store clothing, valuables and other personal belongings for each worker. Benches shall be provided for personnel.

Supply a separate hand wash facility, either attached to the decontamination facility or outside the containment.

# **C** Construction

Properly contain, store, and dispose of the wastewater.

#### **D** Measurement

The department will measure Portable Decontamination Facility by each individual unit, acceptably completed.

#### E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER DESCRIPTION UNIT 517.6001.S. Portable Decontamination Facility EACH

Payment is full compensation for furnishing and maintaining a portable decontamination facility.

stp-517-060 (20140630)

1228-28-70 42 of 61

# 31. Nighttime Work Lighting-Stationary.

# **A** Description

This special provision describes furnishing portable lighting as necessary to complete nighttime work. Nighttime operations consist of work specifically scheduled to occur after sunset and before sunrise.

#### B (Vacant)

#### **C** Construction

#### C.1 General

This provision shall apply when providing, maintaining, moving, and removing portable light towers and equipment-mounted lighting fixtures for nighttime stationary work operations, for the duration of nighttime work on the contract.

At least 14 days before the nighttime work, furnish a lighting plan to the engineer for review and acceptance. Address the following in the plan:

- 1. Layout, including location of portable lighting lateral placement, height, and spacing. Clearly show on the layout the location of all lights necessary for every aspect of work to be done at night.
- 2. Specifications, brochures, and technical data of all lighting equipment to be used.
- 3. The details on how the luminaires will be attached.
- 4. Electrical power source information.
- 5. Details on the louvers, shields, or methods to be employed to reduce glare.
- 6. Lighting calculations. Provide illumination with average to minimum uniformity ratio of 5:1 or less throughout the work area.
- 7. Detail information on any other auxiliary equipment.

# **C.2 Portable Lighting**

Provide portable lighting that is sturdy and free standing and does not require any guy wires, braces, or any other attachments. Furnish portable lighting capable of being moved as necessary to keep up with the construction project. Position the portable lighting and trailers to minimize the risk of being impacted by traffic on the roadway or by construction traffic or equipment. Provide lighting protection for the portable lighting. Portable lighting shall withstand up to 60 mph wind velocity.

If portable generators are used as a power source, furnish adequate power to operate all required lighting equipment without any interruption during the nighttime work. Provide wiring that is weatherproof and installed according to local, state, federal (NECA and OSHA) requirements. Equip all power sources with a ground-fault circuit interrupter to prevent electrical shock.

#### C.3 Light Level and Uniformity

Position (spacing and mounting height) the luminaires to provide illumination with an average to minimum uniformity ratio of 5:1 or less throughout the work area.

Illuminate the area as necessary to incorporate construction vehicles, equipment, and personnel activities.

#### C.4 Glare Control

Design, install, and operate all lighting supplied under these specifications to minimize or avoid glare that interferes with all traffic on the roadway or that causes annoyance or discomfort for properties adjoining the roadway. Locate, aim, and adjust the luminaires to provide the adequate level of illumination and the specified uniformity in the work area without the creation of objectionable glare.

Provide louvers, shields, or visors, as needed, to reduce any objectionable levels of glare. As a minimum, ensure the following requirements are met to avoid objectionable glare on the roadways open to traffic in either direction or for adjoining properties:

- 1. Aim tower-mounted luminaires, either parallel or perpendicular to the roadway, so as to minimize light aimed toward approaching traffic.
- 2. Aim all luminaires such that the center of beam axis is no greater than 60 degrees above vertical (straight down).

If lighting does not meet above-mentioned criteria, adjust the lighting within 24 hours.

1228-28-70 43 of 61

#### **C.5 Continuous Operation**

Provide and have available sufficient fuel, spare lamps, generators, and qualified personnel to ensure that the lights will operate continuously during nighttime operation. In the event of any failure of the lighting system, discontinue the operation until the adequate level of illumination is restored. Move and remove lighting as necessary.

# D (Vacant)

# **E** Payment

Costs for furnishing a lighting plan, and for providing, maintaining, moving, and removing portable lighting, tower mounted lighting, and equipment-mounted lighting required under this special provision are incidental to the contract.

stp-643-010 (20100709)

#### 32. Traffic Control.

Supplement standard spec 643.3.1 with the following:

Provide the Milwaukee County Sheriff's Department, the Wisconsin State Patrol, Milwaukee Police Department and the engineer a current telephone number with which the contractor or his representative can be contacted during non-working hours in the event a safety hazard develops.

Do not park or store equipment, contractor's and personal vehicles or construction materials within the clear zone or on any roadway carrying traffic during working and non-working hours except at locations and periods of time approved by the engineer.

Do not permit construction or personnel equipment or vehicles to directly cross the live traffic lanes of IH-43. Yield to all through traffic at all locations. Equip all vehicles or equipment operating in the live traffic lanes with a hazard identification beam (flashing yellow signal light) that is visible from 360 degrees. Operate the flashing yellow beam only when merging or exiting live traffic lanes or when parked or operating on shoulders, except when parked behind barrier wall. Do not park personal vehicles within the access control limits of the freeway. Do not cross live traffic lanes of IH-43 with equipment or vehicles.

Obtain prior approval from the engineer for the locations of egress or ingress for construction vehicles to prosecute the work.

Do not disturb, remove or obliterate any traffic control signs, advisory signs, sand barrel array, shoulder delineators or beam guard in place along the traveled roadways without the approval of the engineer.

Ensure that Flagging operations conform to standard spec 104.6.1. (4) and chapter 6E of the WMUTCD.

Replace standard spec 643.3.1.(7) with the following:

Provide equipment, forces, and materials to promptly restore any traffic control devices or pavement markings damaged or disturbed within 2 hours of being contacted.

SER-643-001 (20170808)

# 33. Traffic Control Signs Removal

Supplement standard spec 643.3.8.3 with the following:

Remove all signs on temporary mounts and other potential associated hazards to the traveling public from the right-of-way when not in use.

SEF Rev. 14 1212

# 34. Traffic Control Interim Lane Closure, Item 643.4100.S.

# **A** Description

This special provision describes closing a freeway/expressway traffic lane.

1228-28-70 44 of 61

#### B (Vacant)

#### **C** Construction

Install and reposition traffic control devices as required to close a traffic lane. Remove and return the devices to their previous configuration when the closure is no longer required.

#### **D** Measurement

The department will measure Traffic Control Interim Lane Closure as each individual reposition/return cycle, acceptably completed. The department will not measure additional moves or configuration changes as might be required solely to accommodate the contractor's operations.

The department will measure the closures by traffic lane and roadway. The department will not measure multiple closures in the same traffic lane on a project.

# **E** Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER DESCRIPTION UNIT
643.4100.S Traffic Control Interim Lane Closure EACH

Payment is full compensation for closing and re-opening the affected traffic lane.

stp-643-030 (20170615)

# 35. Temporary Bus Stop Pad, Item SPV.0060.0003.

# **A** Description

This special provision describes furnishing, maintaining, moving, and removing temporary pavement for temporary bus stop pads in the sidewalks/lanes during construction, and for temporary bus stop pads in the terrace, as shown on the plans.

#### **B** Materials

Furnish pressure treated 2x4 framing lumber, pressure treated 3/4 inch plywood with skid resistant surface coating, and weather resistant deck screws 3 1/2 inch minimum for framing and 1 5/8 inch minimum for plywood with temporary pedestrian safety fence on both sides.

#### **C** Construction

Construct temporary bus stop pads 8 feet in length by 5 feet minimum width that meet the requirements of the current Americans with Disabilities Act Accessibility Guidelines (ADAAG) connect the temporary pad to the existing sidewalk per typical plan.

Provide a firm, stable, and slip-resistant surface layer with vertical joints no higher than 1/4 inch and horizontal joints no wider than 1/2 inch. Sheet materials up to 1 inch thick may be lapped if the edge is beveled at 45 degrees or flatter. Asphalt may also be used to ramp up to materials up to 1 inch thick.

Separate temporary bus stop pads in the sidewalk/travel lane from construction operations with temporary fencing with a minimum strength and height required to contain livestock, as approved by the engineer. Locate the temporary bus stop pads outside the immediate work area, as directed by the engineer. Connect temporary bus stop pads in the lane to crosswalks, existing sidewalks, or permanent sidewalks.

Replace or move temporary bus stop pads if required for utility installation or paving operation.

Temporary bus stop signs and poles will be furnished and installed by Milwaukee County Transit System.

#### **D** Measurement

The department will measure Temporary Bus Stop Pad as each individual unit, acceptably completed.

# **E** Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER DESCRIPTION UNIT SPV.0060.0003 Temporary Bus Stop Pad EACH

1228-28-70 45 of 61

Payment is full compensation for furnishing and installing all materials; for constructing; for reconstructing or moving; for removing; and for furnishing and installing temporary pedestrian barricades.

# Fuse Holders, Item SPV.0060.1001; Fuses Type FNQ, Item SPV.0060.1002.

# **A Description**

This special provision describes replacing Fuse Holders or Fuses Type FNQ during luminaire maintenance, conforming to standard spec 659, and as follows. Fuses and fuse holders that are installed as a part of the bid item for pole wire, which is Electrical Wire Lighting 12 AWG will be paid under that bid item.

#### **B** Materials

Use materials conforming to standard spec 659.2.

#### **C** Construction

Use construction methods conforming to standard spec 659.3.2 except 659.3.2(2) replace 'fast acting fuses' with 'time delay fuses'.

#### **D** Materials

The department will measure Fuse Holders and Fuses Type FNQ as each individual unit, acceptably completed.

# E Payment

The department will pay for measured quantities at the contract unit price under the following bid items:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0060.1001	Fuse Holders	EACH
SPV.0060.1002	Fuses Type FNQ	EACH

Payment is full compensation for furnishing and installing the materials; troubleshooting or inspecting to determine if replacing fuses or fuse holders are necessary.

SER-659.4 (20170407)

# 37. Distribution Center Preventive Maintenance, Item SPV.0060.1003.

# **A** Description

This special provision describes maintaining lighting cabinets and the site, including inspecting, cleaning, testing, adjusting, and keeping records. Major repairs or component replacement will not be included.

# **B** Materials

Furnish materials such as primer, paint, lubrication, anti-seize, electrical cleaning solvents, incandescent lamps, warning decals, small parts, and connectors. All items shall be suitable for electrical maintenance, as approved by the engineer. The department will furnish padlocks and WisDOT decals.

# **C** Construction

Perform the following tasks:

- Apply state-furnished WisDOT decals as needed to cabinets and to remote meters.
- Apply standard ANSI voltage warning decals (text varies by location; in most cases, "Warning 480 Volts") where needed to cabinets and to remote meters. These will be measured separately as Plaques Sequence Identification, generally 2 units per cabinet.
- Apply cabinet plaques where needed. These will be measured separately as Plaques Sequence Identification, generally 2 or 3 units per cabinet. Engineer to supply text.
- Spot prime and spot paint inside and out as needed, in colors to match the existing surfaces.
- Test the photo control circuit and other 120 VAC apparatus for proper function.
- Replace the incandescent lamp as necessary.

1228-28-70 46 of 61

- Inspect all electrical components, including conductors. Inform the engineer of all reportable conditions.
- Tighten and otherwise make good all electrical connections, including grounding connections.
- Remove debris, animal nests, the accumulation of dirt, etc., from inside and near the cabinet.
- Trim weeds, saplings, and brush a reasonable distance around, including a sufficient distance to ensure access to the meter, the fence gate, the cabinet door, We Energies transformer (hot stick side) and the first pull box off the cabinet.
- Inspect the fence gate and its padlocks. Trim saplings that interfere with gate function.
- Wipe the photocell clean.
- In general, short of replacing any component or making any repair beyond these requirements, leave behind a clean, orderly and functioning cabinet, fence gate and site.

#### **D** Measurement

The department will measure Distribution Center Preventive Maintenance by each unit, acceptably completed.

#### **E** Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

 ITEM NUMBER
 DESCRIPTION
 UNIT

 SPV.0060.1003
 Distribution Center Preventive Maintenance
 EACH

Payment is full compensation for the required maintenance and adjustment of the distribution center, and recording and forwarding all reportable conditions.

# 38. Tunnel Luminaire Maintenance 150 Watt HPS, Item SPV.0060.1004; Tunnel Luminaire Maintenance 200 Watt HPS, Item SPV.0060.1005; Tunnel Luminaire Maintenance 250 Watt HPS, Item SPV.0060.1006; Tunnel Luminaire Maintenance 400 Watt HPS. Item SPV.0060.1007.

# **A Description**

This special provision describes the maintenance of tunnel luminaires. At the same locations, inspect the installation and troubleshoot nonfunctioning luminaires. Report problems to the engineer, or repair for payment under separate items of work, as directed by the engineer. All work must conform to standard spec 651 and 659 and as follows.

# **B** Materials

Furnish high-pressure sodium light bulbs with wattages as shown in miscellaneous quantiles. High-pressure sodium shall have base type E39 Mogul and average rated life of minimum 30,000 hours.

#### **C** Construction

Append standard spec 659.3 with the following:

#### 659.3.1 General

(2) Clean and relamp luminaires whose lamps have failed or are on the obvious verge of failure. If not replacing, clean under the bid item Group Clean Tunnel Luminaires.

# 659.3.6 Inspection, Limited Testing and Troubleshooting

Replace standard spec 651.3.3 (8) and (9) with the following:

Record any obvious damage, electrical malfunction, electrical hazards, and other potential problems with the existing installation, that are encountered, and convey such information to the engineer at the end of the work day. Replace blown fuses for separate payment. Replace nonfunctioning luminaires with state-furnished materials, for separate payment, and furnish and install a lamp. When outages for which the repair is beyond the scope of this contract are encountered, convey this information in writing to the engineer. This will complete the contractor's work for inspection and troubleshooting at that location. Demonstrate the function of lamps at the end of the closure period for that lane or tunnel. Thereafter, the twenty-day prove-in period will be waived.

1228-28-70 47 of 61

# 659.3.7 Cleaning and Relamping; Other Incidental Work

Level and aim each luminaire that is of a type that can be leveled or aimed. Clean the optical surfaces, consisting of the reflector and both sides of the lens or refractor, with a detergent solution and two rinses. Lightly wipe with a damp chamois to remove dirt film, and polish with a non-abrasive compound free of wax or silicone, leaving the reflector bright.

In lieu of the manual cleaning process, an automatic washer designed specifically for the cleaning of refractors or lenses may be used, provided that, in the judgment of the engineer, it produces a final cleaning result equal to the washing process described above.

Throughout the cleaning process, keep the gasket dry.

#### **D** Measurement

The department will measure Spot Luminaire Maintenance Tunnel (Various) by the unit, acceptably completed.

# E Payment

The department will pay for measured quantities at the contract unit price under the following bid items:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0060.1004	Tunnel Luminaire Maintenance 150 Watt HPS	EACH
SPV.0060.1005	Tunnel Luminaire Maintenance 200 Watt HPS	EACH
SPV.0060.1006	Tunnel Luminaire Maintenance 250 Watt HPS	EACH
SPV.0060.1007	Tunnel Luminaire Maintenance 400 Watt HPS	EACH

Payment is full compensation for performing maintenance, providing materials, and properly disposing of HPS light bulbs in accordance to all environmental regulations.

# 39. Group Clean Tunnel Luminaires, Item SPV.0060.1008.

#### **A Description**

This special provision describes cleaning tunnel luminaires not requiring relamping.

#### B (Vacant)

# **C** Construction

Level and aim each luminaire that is of a type that can be leveled or aimed. Clean the optical surfaces, consisting of the reflector and both sides of the lens or refractor, with a detergent solution and two rinses. Lightly wipe with a damp chamois to remove dirt film, and polish with a non-abrasive compound free of wax or silicone, leaving the reflector bright.

In lieu of the manual cleaning process, an automatic washer designed specifically for the cleaning of refractors or lenses may be used, provided that, in the judgment of the engineer, it produces a final cleaning result equal to the washing process described above.

Throughout the cleaning process, keep the gasket dry.

#### **D** Measurement

The department will measure Group Clean Tunnel Luminaires by the unit, acceptably completed.

#### **E** Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBERDESCRIPTIONUNITSPV.0060.1008Group Clean Tunnel LuminairesEACH

Payment is full compensation for performing all required work.

1228-28-70 48 of 61

# 40. Group Luminaire Maintenance Sign Light 250W MV, Item SPV.0060.1009.

# **A** Description

This special provision describes luminaire maintenance, generally on a sequential basis. At the same locations, inspect light poles and troubleshoot nonfunctioning luminaires. Report problems to the engineer, or repair for payment under separate items of work, as directed by the engineer. Perform work according to standard spec 659.

#### **B** Materials

Append standard spec 659.2.1 as follows:

250-watt mercury vapor lamps shall be deluxe white

#### **C** Construction

Append standard spec 659.3 with the following:

#### **C.1 Location Plans**

At the preconstruction conference, the department will furnish detailed location maps illustrating the location, lamp type and wattage, pole height, and other information regarding the work under this item.

# C.2 Inspection, Limited Testing and Troubleshooting

Record any obvious pole damage, structural weakness, electrical malfunction, electrical hazards, and other potential problems with the existing installation that are encountered and convey such information to the engineer at the end of the work day. Replace blown fuses for separate payment. Replace nonfunctioning luminaires with state-furnished materials, for separate payment, and furnish and install a lamp. When outages for which the repair is beyond the scope of this contract are encountered, convey this information in writing to the engineer. This will complete the contractor's work for inspection and troubleshooting at that location. Thereafter, the lamp (only) will be required to operate for 20 consecutive nights without failure. Replace each lamp that fails; that lamp shall again be subjected to a 20 consecutive night test. **Exception:** At his option, the engineer may waive the 20-day prove-in period, location-by-location, in cases where he does not wish to pay the cost of traffic control, or where he judges that the public inconvenience of closed lanes or ramps would not be justified.

# C.3 Lamp Identification

Some luminaires lack NEMA lamp identification stickers. Instead, a color patch on the sequence plaque on the pole shaft identifies the lamp types and wattages. Pole plaques are in many cases outdated and inaccurate. The color patch code is shown in the plans. Where the NEMA label and the pole plaque conflict, follow the NEMA label.

# C.4 Sign Bridge Lighting

Access to most overhead sign lighting installations can be accomplished without closing freeway lanes, since these overhead sign structures span the mainline freeway roadways and can be serviced from aerial walkways. Median mounted signs on single pole sign supports in some cases are not accessible for servicing without lane closures. Lane closures for these locations shall conform to the bid items for Traffic Control in these special provisions, except the use of standard traffic delineation and a standard sign is required in addition to the use of the arrow flasher board.

#### C.5 Cleaning and Relamping – Other Incidental Work

Level and aim each luminaire that is of a type that can be leveled or aimed. Clean the optical surfaces, consisting of the reflector and both sides of the lens or refractor, with a detergent solution and two rinses. Lightly wipe with a damp chamois to remove dirt film, and polish with a non-abrasive compound free of wax or silicone, leaving the reflector bright.

In lieu of the manual cleaning process, an automatic washer designed specifically for the cleaning of refractors or lenses may be used, provided that, in the judgment of the engineer, it produces a final cleaning result equal to the washing process described above.

Throughout the cleaning process, keep the gasket dry.

#### **D** Measurement

The department will measure Group Luminaire Maintenance (Various) by each individual unit, acceptably completed. Two units of work will be measured on twin lighting units.

1228-28-70 49 of 61

#### **E** Payment

The department will pay for the measured quantities under the following bid items:

ITEM DESCRIPTION UNIT
SPV.0060.1009 Group Luminaire Maintenance Sign Light 250W MV EACH

Payment is full compensation for cleaning and relamping; making for incidental repairs; inspecting and troubleshooting; properly disposing of HPS light bulbs in accordance to all environmental regulations; and for conformance to the limited 20-night prove-in period as described above.

# 41. Cleaning and Painting Bearings, Item SPV.0060.4001.

# **A** Description

This special provision describes cleaning and painting the existing steel bearings on structures as shown on the plans, as directed by the engineer, and in accordance with standard spec 517.

#### **B** Materials

Furnish a complete epoxy coating system from the department's approved product list. Use the same coating system for all repairs due to handling, shipping and erecting, and for all other uncoated areas. The color of epoxy shall be white, and the urethane coating material shall match the color number shown on the plans in accordance with Federal Standard Number 595B, as printed in 1989. Supply the engineer with the product data sheets before any coating is applied. The product data sheets shall indicate the mixing and thinning directions, the minimum drying time for shop or field applied coats, and the recommended procedures for coating galvanized bolts, nuts, and washers.

#### **C** Construction

# C.1 Surface Preparation

Clean areas of loose paint and rust by wire brushing, grinding, or other mechanical means. Sound paint does not need to be removed.

After cleanup and storage of waste material, blast cleaning is allowed for only those areas where paint has been removed. Shield adjacent painted areas during blast cleaning operations. The blasting sand does not have to be collected.

Furnish adequate containment methods as required to contain and collect waste material resulting from the preparation of painted steel surfaces for painting. All cleanup activities should minimize dust. Store waste materials in hazardous waste containers provided by the department.

#### **C.2 Coating Application**

Apply paint in a neat, workmanlike manner, and in accordance with the manufacturer's instructions and recommendations. Paint application shall be brushed on.

#### **D** Measurement

The department will measure Cleaning and Painting Bearings as each individual bearing, acceptably completed.

#### E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBERDESCRIPTIONUNITSPV.0060.4001Cleaning and Painting BearingsEACH

Payment is full compensation for preparing and cleaning the designated bearings; furnishing and applying the paint; cleaning up and containing and collecting all waste materials.

1228-28-70 50 of 61

# 42. Protect Existing Light Fixtures and Utilities B-40-292, Item SPV.0105.4112; Protect Existing Light Fixtures and Utilities B-40-293, Item SPV.0105.4122.

# **A** Description

This special provision describes protecting existing components including, but not limited to, light fixtures, cameras, signs, conduits, pipes, utilities, utility supports, steel hardware, and antenna bushing supports within Kilbourn Tunnels from damage during the construction. The scope of work under this special provision includes all surfaces where no work is to be performed under this contract.

#### B (Vacant)

# **C** Construction

Remove or cover existing light fixtures in the tunnel from damage due to construction operations. Reinstall removed fixtures at the end of construction. Exercise care not to damage lamps inside the fixtures.

Cover and protect all exposed lighting conduits and other utility pipes/cables from damage due to constructions operations.

Coordinate with the utility owner if any utility or fixture is be temporarily removed for performance of the work. Reinstall the removed items after performance of the work and demonstrate to the utility owner that the reinstalled utility or fixture is functional. Provide required hardware to reinstall the utility or fixture. Replace any utility or fixture damaged during removal and reinstallation at no cost to the department.

Remove all concrete and other materials used for construction from the surface of utilities and fixtures as directed by the engineer. Replace light fixtures and utilities damaged due to construction operations at no cost to the department.

#### **D** Measurement

The department will measure Protecting Existing Light Fixtures and Utilities as a single lump sum unit of work, acceptably completed.

# **E** Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0105.4112	Protect Existing Light Fixtures and Utilities B-40-292	LS
SPV.0105.4121	Protect Existing Light Fixtures and Utilities B-40-293	LS

Payment is full compensation for protecting existing utilities and fixtures; for removing and reinstalling utilities and fixtures where necessary; for cleaning the utilities and fixtures; and for replacing damaged utilities and fixtures.

# 43. Temporary Lighting and Ventilation B-40-292, Item SPV.0105.4131; Temporary Lighting and Ventilation B-40-293, Item SPV.0105.4141.

# **A** Description

This special provision describes providing temporary lighting and ventilation in Kilbourn Tunnel during construction.

# B (Vacant)

#### **C** Construction

Existing tunnel lighting and ventilation systems will be turned off during the construction. Provide work lights within and around the work zone in a way that provides adequate illumination to perform and inspect the work. Provide temporary lighting for the workers from the work location to at least two exits.

Close off and seal existing ventilation grilles in the tunnel roof to prevent construction dust entering into the ventilation system. Coordinate with MacArthur Square parking structure maintenance staff before closing the ventilation grilles. Close and seal the tunnel opening at MacArthur Square Parking Structure to prevent air flow from the tunnel to the Parking Structure when the Parking structure ventilation system is turned on. Provide temporary ventilation fans and ducts for tunnel ventilation during construction.

Conform to all local, state, and federal regulations for lighting and air quality inside the tunnel.

1228-28-70 51 of 61

#### **D** Measurement

The department will measure Temporary Lighting and Ventilation as a single lump sum unit of work, acceptably completed.

# E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0105.4131	Temporary Lighting and Ventilation B-40-292	LS
SPV.0105.4132	Temporary Lighting and Ventilation B-40-293	LS

Payment is full compensation for providing lighting and ventilation in the tunnels; and for closing and sealing off existing ventilation grilles and tunnel opening at parking structure.

# 44. Adjusting TES Manhole Cover, Item SPV.0060.5001.

# **A** Description

This special provision describes adjusting the existing chimney of the block, precast, or brick round manholes; furnishing, installing and removing protection of the cables in the manhole during adjustment operations. Perform work in accordance with the standard specifications, the provisions of the article Adjusting Manhole Covers, as shown on the plans, and as hereinafter specified.

#### **B** Material

Furnish and install materials that conform to the requirements of standard spec 519. Salvage and reinstall existing covers on the manholes. The city will supply covers designated for replacement. Contractor shall contact Ricardo Lopez, Inventory Clerk at (414) 286-6123 prior to obtaining the frames and lids from the DPW Field Headquarters at 3850 N. 35<sup>th</sup> St. Contractor must have the "Castings Requisitions Form" which shall be supplied by the city at the preconstruction meeting to obtain the covers.

#### **C** Construction

Report any pre-existing problems to Karen Rogney of City Underground Conduits Section at (414) 286-3243 three working days in advance of any construction on manholes.

Before removing the pavement around the manhole, the contractor shall place a ¾-inch plywood cover or equal over existing active street lighting, traffic control, communication or private vendor electrical cables. This cover shall be properly supported to/at the manhole floor.

Break out and remove pavement around manhole. Remove existing covers and store and secure them properly. Any damaged, lost, or stolen covers shall be the responsibility of the contractor and shall be replaced at contractor's expense.

Remove existing chimney to surface of concrete roof slab. If manhole does not have an existing concrete roof slab, remove sufficient chimney as to provide adequate corbel to fit new cast iron frame and cover.

Adjust manhole cover to proposed grade using bricks or concrete rings as necessary. Completely underpin entire flange area of manhole frame with mortar, bricks and/or concrete rings. Remove wedges/shims. Fill voids with grout. Do not back plaster inside walls.

After completion of paving, remove the temporary  $\frac{3}{4}$ -inch plywood cover or equal which is over the existing electrical cables in the manhole as mentioned above.

Notify Karen Rogney three working days in advance of completion of each manhole adjustment, for inspection and acceptance of work performed. The contractor will receive no payment until the above work is approved by City Underground Conduits Section.

#### **D** Measurement

The department will measure Adjusting TES Manhole Cover by the unit, acceptably completed.

1228-28-70 52 of 61

#### E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBERDESCRIPTIONUNITSPV.0060.5001Adjusting TES Manhole CoverEACH

Payment is full compensation for furnishing all required materials, exclusive of frames, grates, or lids available and designated for adjusting; for removing, reinstalling and adjusting the covers; and for furnishing all labor, tools, equipment and incidentals necessary for adjusting each cover, complete in accordance with the requirements of the plans and contract. Covers to be adjusted and which are rendered unfit for use by the contractor through the contractor's operations will be replaced by the contractor in kind at the contractor's own cost and expense.

# 45. Adjusting Water Boxes, Item SPV.0060.5002.

# **A** Description

This special provision describes adjusting, protecting, and maintaining accessibility, for the duration of the paving project, to all City of Milwaukee water service boxes, water valve boxes and water manhole frames and lids located within the project limits.

#### **B** Materials

All material for the adjustment of these facilities shall meet City of Milwaukee specifications and will be provided by the City of Milwaukee by contacting Andray DeCordova, Milwaukee Water Works, at (414) 708-3209 (or Dave Goldapp, Milwaukee Water Works at (414) 286-6301).

If there is contractor damage, the materials must still be provided by the City of Milwaukee, however, in this case, the contractor will be charged for all materials. Materials furnished by the City of Milwaukee and not used on the project shall be delivered back to DPW Field Headquarters – Infrastructure, Operations, Water Works at 3850 N. 35<sup>th</sup> St.

#### **C** Construction

The contractor, or authorized project representative, shall contact Milwaukee Water Works prior to the start of construction. The city will locate, mark, inspect and repair all water service boxes, water valve boxes and water manhole frames and lids within the limits of the project prior to commencement of work on the project.

All water service boxes, water valve boxes and water manhole frames and lids within the project limits shall be adjusted to proposed elevations by the contractor using materials meeting city specifications.

Throughout the duration of the project, the contractor must ensure that all water service boxes, water valve boxes and water manholes are adequately located and identified by blue paint, and that at all times, all water appurtenances remain accessible for operation by city forces. Exercise caution working adjacent to water facilities to avoid damage and ensure accessibility.

Upon completion of the contract, the city will inspect all water facilities to ensure the water boxes and manholes are clean, properly aligned, and accessible. The contractor shall be responsible to make identified repairs and adjustments, and if any repairs or adjustments are made by the city, the cost will be charged to the contractor.

#### **D** Measurement

The department will measure Adjusting Water Boxes as each individual unit, acceptably completed.

#### E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBERDESCRIPTIONUNITSPV.0060.5002Adjusting Water BoxesEACH

Payment is full compensation for all excavation, backfilling, disposal of surplus materials, water box or manhole adjustments, water box or manhole clean-out, and restoration of the work site.

1228-28-70 53 of 61

# 46. Field Facilities Office Space, Item SPV.0060.5003.

# **A** Description

This special provision describes furnishing, equipping, and maintaining a field office as required in the contract at engineer-approved locations conforming to standard spec 642 and as follows.

#### **B** Materials

Provide Field Facilities Office Space conforming to standard spec 642.2.1 except delete paragraphs (1), (7), and (9).

Replace standard spec 642.2.1(4) with the following:

Provide and maintain suitable interior sanitary facilities conforming to State and local health requirements, in clean and good working condition, and stock with sanitary supplies for the duration of the contract. Furnish office space in an existing office building or existing building converted to office space with a minimum of 1200 square feet. The facility shall have no fee parking with a minimum parking for 15 cars. The space shall include a meeting room with a minimum of 350 square feet. The exterior door(s) shall have locks in good working order and keys provided for all field staff. The office space shall be located within 2 miles of the construction project.

Equip the office as specified in standard spec 642.2.2.1 except delete paragraph (1) and (4) and add the following:

- 1. Five suitable office desks with drawers and locks.
- 2. Five ergonomically correct office chairs in working condition with at a minimum: 5-legged base with casters, seat adjustable from 15 to 22 inches from the floor with a seamless waterfall, rounded, front edge, and high backrest with no arms or adjustable arms.
- 3. Four 6-foot folding tables.
- 4. One 10-foot folding table.
- 5. Five 2-drawer file cabinets.
- 6. Three 4-shelf bookcases.
- 7. Twenty folding chairs.

Provide for the professional cleaning of the field office during regular business hours twice monthly. Provide clearly marked recycling and waste receptacles within the field office, and separate recycling and waste dumpsters near the field office. Cover outdoor containers to keep out rain, snow, and wind-driven debris. Provide regularly scheduled recycling and waste pick-up.

#### **C** Construction

Conform to standard spec 642.3 except delete paragraph (2).

#### **D** Measurement

The department will measure the Field Facilities Office Space as each office, acceptably completed.

#### **E** Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBERDESCRIPTIONUNITSPV.0060.0002Field Facilities Office SpaceEACH

Payment is full compensation for providing, equipping, securing, and maintaining the facility; for parking, for telecommunications equipment, installation, and service fees; and for providing bottled water, utilities, fuel, ventilation, and toilet facilities as required, either independently or jointly with the field laboratory, for the time specified in standard spec 642.3.

The department will pay for the cost of telecommunications usage fees incurred by department staff. SER-642-002 (20160808)

# 47. Traffic Control Close-Open Freeway Entrance Ramp, Item SPV.0060.5004.

#### **A** Description

This special provision describes closing and re-opening a freeway entrance ramp and associated auxiliary lane.

1228-28-70 54 of 61

#### B (Vacant)

#### **C** Construction

Install or reposition traffic control devices required for closing a freeway entrance ramp and adjacent auxiliary lanes. Remove or return traffic control devices to their previous configuration when the closure is no longer required.

#### **D** Measurement

The department will measure Traffic Control Close-Open Freeway Entrance Ramp by each individual ramp closure, acceptably completed.

# **E** Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER DESCRIPTION UNIT
SPV.0060.5004 Traffic Control Close-Open Freeway Entrance Ramp EACH

Payment is full compensation for daily surveillance; preparing and submitting the daily surveillance report with hourly metered tickets; mobilization; sweeping; and disposing of materials. Traffic Control devices will be paid separately.

sef-643-001 (20180627)

# 48. Pavement Cleanup Project 1228-28-70, Item SPV.0075.0003.

# **A Description**

This special provision describes cleanup of dust and debris from pavements within and adjacent to the job site. Pavement Cleanup includes surveillance and reporting of all active haul routes.

#### **B** Materials

#### **B.1 Pavement Cleanup**

Furnish a vacuum-type street sweeper equipped with a power broom, water spray system, and a vacuum collection system.

Use vacuum equipment with a self-contained particulate collector capable of preventing discharge from the collection bin into the atmosphere.

Use a vacuum-type sweeper as the primary sweeper, except as specified in this special provision or approved by the engineer.

#### **C** Construction

#### C.1 Surveillance

Provide daily surveillance of active haul routes to identify if material is being tracked from the jobsite. Document the condition of the roads and all sweeping recommendations in a daily report. Submit reports to the engineer daily, including hourly metered tickets for that day's sweeping activities.

# **C.2 Pavement Cleanup**

Keep all pavements, sidewalks, driveways, curb lanes and gutters within the project boundaries, free of dust and debris generated from all activity under the contract. Keep all pavements, sidewalks, driveways, curb lanes, and gutters adjacent to the project free of dust and debris that are caused by land disturbing, dust generating activities, as defined in the contractor's Dust Control Implementation Plan (DCIP). Provide routine sweeping of all pavements, sidewalks, driveways, curb lanes and gutters on local-street active haul routes as defined in the DCIP or as directed by the engineer. Include the following roadways for routine sweeping:

- And all other roadways approved by the department

In addition to routine sweeping, conduct sweepings as the engineer directs or approves, to eliminate dust problems that might arise during off-work hours or emergencies. Provide the engineer with a contact person available at all times to respond to requests for emergency sweeping. Coordinate with engineer to determine deadlines for responding to emergency sweeping requests and cleaning up spillage and material tracked to/from the project.

1228-28-70 55 of 61

Skid steers with mechanical power brooms may only be used on sidewalks and driveways whose pavements will not support the weight of a street sweeper, unless otherwise approved by the engineer. Do not dry sweep. Ensure all broomed equipment used for sweeping has a functioning water bar.

#### **D** Measurement

The department will measure Pavement Cleanup (Project 1228-28-70) by the hour, acceptably completed.

Tickets shall include:

- Date
- Company
- Operator name
- Equipment make/model
- Routes swept
- Total hours.

Total hours shall be to the nearest 0.25 hour that work under this item was performed.

# **E** Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBERDESCRIPTIONUNITSPV. 0075.0003Pavement Cleanup Project 1228-28-70HRS

Payment is full compensation for daily surveillance; preparing and submitting the daily surveillance report with hourly metered tickets; mobilization; sweeping; and disposing of materials.

sef-104-006 (20170323)

# 49. Pavement Marking Contrast Epoxy 4-inch, Item SPV 0090.0001.

# **A** Description

This special provision describes applying contrast epoxy marking conforming to standard spec 646, as the plans show, and as follows.

#### **B** Materials

Furnish epoxy pavement marking materials conforming of standard spec 646.2.

#### **C** Construction

Apply two 1  $\frac{1}{2}$ -inch wide black epoxy lines with a 4-inch separation between the two black lines for the first pass, followed by a 4-inch wide white epoxy line second pass, for a total width of 7 inches. Apply epoxy pavement marking conforming to standard spec 646.3.

#### **D** Measurement

The department will measure Marking Contrast Epoxy 4-Inch Special by the linear foot, acceptably completed, measured once as the length of the centerline of the completed installation.

# **E** Payment

The department will pay for measured quantities at the contract unit price under the following bid items:

ITEM NUMBERDESCRIPTIONUNITSPV.0090.0001Pavement Marking Contrast Epoxy 4-InchLF

Payment is full compensation for providing replacement marking.

SER-646-001 (20180214)

1228-28-70 56 of 61

# 50. Pavement Marking Contrast Epoxy 8-inch, Item SPV 0090.0002.

# **A** Description

This special provision describes applying contrast epoxy marking conforming to standard spec 646, as the plans show, and as follows.

#### **B** Materials

Furnish epoxy pavement marking materials conforming of standard spec 646.2.

#### **C** Construction

Apply two 1 ½-inch wide black epoxy lines with a 8-inch separation between the two black lines for the first pass, followed by an 8-inch wide white epoxy line second pass, for a total width of 7 inches. Apply epoxy pavement marking conforming to standard spec 646.3.

#### **D** Measurement

The department will measure Marking Contrast Epoxy 8-Inch Special by the linear foot, acceptably completed, measured once as the length of the centerline of the completed installation.

# **E** Payment

The department will pay for measured quantities at the contract unit price under the following bid items:

 ITEM NUMBER
 DESCRIPTION
 UNIT

 SPV.0090.0002
 Pavement Marking Contrast Epoxy 8-Inch
 LF

Payment is full compensation for providing replacement marking.

SER-646-002 (20180214)

# 51. Ventilation Opening Edge Repair, Item SPV.0090.4002.

#### **A** Description

This special provision describes concrete surface repair to the edges of ventilation openings in the roof of Kilbourn Tunnel as shown on the plans, and as provided herein.

#### **B** Materials

Furnish concrete and steel reinforcement in accordance with standard spec 502 and 505 and these special provisions. Use high strength epoxy coated steel reinforcement.

#### **C** Construction

Perform work in accordance with the applicable requirements of the standard specifications in general, and standard spec 501, 502, 505, and 509 in particular, except as modified herein or shown on the plans. Before starting the repair, conduct a survey of the concrete surfaces and mark areas requiring repair for engineer's inspection. Notify the engineer 48 hours in advance of the inspection. Remove concrete only from locations approved by the engineer. Define the limits of removal on the existing surface with a 1-inch deep saw cut.

Mask and protect existing steel grating and grating support angle during the performance of this work. Remove and reinstall the grating if necessary. Coordinate with MacArthur Square parking structure maintenance staff before removing the grating.

#### **D** Measurement

The department will measure Ventilation Opening Edge Repair by the linear foot of work, acceptably completed.

#### **E** Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

 ITEM NUMBER
 DESCRIPTION
 UNIT

 SPV.0090.4002
 Ventilation Opening Edge Repair
 LF

1228-28-70 57 of 61

Payment is full compensation for removing unsound concrete; furnishing and placing concrete; and scaffolding and formwork. Repairing and replacing existing damaged reinforcement bars is incidental to this work.

# 52. Remove and Replace Sidewalk Cover Plate, Item SPV.0105.4105.

# **A** Description

This special provision describes removing and replacing existing sidewalk cover plate as shown on the plans and as specified herein.

#### **B** Materials

Furnish materials conforming to standard spec 506. Slip resistant treatment shall be as indicated on the plans.

#### **C** Construction

Conform to standard spec 502.3.6.3.3. Remove and dispose of existing sidewalk cover plate. Exercise care not to damage existing concrete. Reuse embedded parts of existing sidewalk cover plate.

#### **D** Measurement

The department will measure Remove and Replace Sidewalk Cover Plate as a single lump sum unit of work, acceptably completed.

# **E** Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0105.4105	Remove and Replace Sidewalk Cover Plate	LS

Payment is full compensation for removing existing sidewalk cover plate, furnishing and installing new cover plate, and for applying slip-resistant coating.

# 53. Slip-Resistant Treatment of Sidewalk Cover Plate B-40-686, Item SPV.0105.4205; Slip-Resistant Treatment of Sidewalk Cover Plate B-40-689, Item SPV.0105.4305.

# **A** Description

This special provision describes removing the existing sidewalk cover plate, removing the existing slip-resistant treatment on the cover plate, applying new slip-resistant treatment on the cover plate and reinstalling the cover plate as specified herein.

# **B** Materials

Slip resistant treatment shall be as indicated on the plans.

#### **C** Construction

Conform to standard spec 502.3.6.3.3. Remove existing sidewalk cover plate. Remove any remaining slip-resistant treatment. Apply new slip-resistant treatment and hot-dip galvanize the assembly. Reuse existing fasteners and embedded parts of existing sidewalk cover plate.

Cover and protect the sidewalk where the cover plate is removed until the cover plate is reinstalled.

#### **D** Measurement

The department will measure Slip-Resistant Treatment of Sidewalk Cover Plate as a single lump sum unit of work, acceptably completed.

# **E** Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0105.4205	Remove and Replace Sidewalk Cover Plate B-40-686	LS
SPV.0105.4305	Remove and Replace Sidewalk Cover Plate B-40-689	LS

1228-28-70 58 of 61

Payment is full compensation for removing existing sidewalk cover plate, transporting the cover plate, applying slip-resistant treatment on the cover plate, and galvanizing.

# 54. Shotcrete Surface Repair, Item SPV.0165.4202.

# **A** Description

This special provision describes performing concrete surface repair using shotcrete as provided herein.

# **B** Materials

Furnish materials in accordance with standard spec 502.2.

## **C** Construction

Perform shotcrete work in accordance with ACI 506.2 Specification for Shotcrete and details on the plans.

# **D** Measurement

The department will measure Shotcrete Surface Repair by the square foot of work acceptably completed.

# **E** Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBERDESCRIPTIONUNITSPV.0165.4202Shotcrete Surface RepairSF

Payment is full compensation for providing concrete, work platforms, falsework; for surface preparation, placing, finishing, curing, and protecting.

# 55. Cleaning Tunnel Wall and Ceiling, Item SPV.0180.4301.

# **A** Description

This special provision describes cleaning and preparing the concrete surface to receive concrete staining as provided herein.

## **B** Materials

Submit cleaning procedures for concrete, including cleaning techniques, protective measures, and control of runoff.

Use clean water, which is potable, non-staining, and free of oils, acids, alkalis, and organic matter. Water spray apparatus shall consist of pumps, backflow preventions, and misting unit capable of applying a constant spray rate set between 0.4 and 0.8 gallons/square foot/minute. Pressure wash unit shall be capable of delivering water at a pressure between 100 and 1000 psi with flow rate of 4 gallons/minute. Use 45 degree fan tip. Use only natural fiber or nylon brushes for applying cleaners. Do not use metal wire brushes on concrete.

Concrete cleaner shall be: Diedrich 707X, 808X, and 707N by Diedrich Technologies.

## **C** Construction

Start work at the tunnel ceiling. Wet the concrete surface by soaking for 24 hrs with a low-pressure misting system to swell and loosen soiling. Avoid excessive wetting. Use as little as water as possible to keep the soiled areas moist or use controls to provide intermittent spray according to temperature, exposure, and humidity. The time of soaking operation will vary considerably depending on the degree and nature of soiling. Experiment with soaking times necessary to achieve the degree of cleaning required. Brush heavily soiled areas with specified bristle brushes as needed to loosen deposits and improve the action of the water misting. Some stains may require considerable effort, but take care at all times to avoid damaging the concrete. Collect runoff and direct the water to predetermined, reviewed drainage paths. Collect runoff and dispose of legally. Do not let the runoff into the tunnel drainage system. Perform a final rinse down with pressurized water spray after the soiling reaches a state that allows easy removal without damaging the concrete. If soaking and pressure wash is unsuccessful, use chemical cleaner specified.

1228-28-70 59 of 61

#### D Measurement

The department will measure Cleaning Tunnel Wall and Ceiling by the square yard of work, acceptably completed.

# **E** Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBERDESCRIPTIONUNITSPV.0180.4301Cleaning Tunnel Wall and CeilingSY

Payment is full compensation for cleaning the entire area of tunnel ceiling and walls.

# 56. Hydro-Demolition of Concrete Masonry Deck Overlay Structure B-40-293, Item SPV.0180.4302.

# **A Description**

This special provision describes removal of existing concrete surface (partial depth) by means of hydrodemolition, as indicated on the plans and as specified herein.

# A.1 General

Concrete removals shall be performed with approved high pressure hydro-demolition equipment. The equipment shall consist of filtering and pumping units operating with a remote controlled robotic device. Equipment shall be capable of operating at 35,000 psi and 32 gallons per minute. Equipment shall be capable of removing concrete to the depth specified on the plans and shall be capable of removing all rust and laitance from exposed reinforcement designated to remain in place.

Hydro-demolition contractor shall supply all necessary equipment, parts and manpower to maintain preestablished production rates and assure adherence to construction schedule.

Equipment shall be capable of performing concrete removals as shown on the plans. The contractor shall submit hydro-demolition equipment specifications, including robot size specifications, and the required water supply and consumption rates. Operation of the hydro-demolition equipment shall be performed and supervised by qualified personnel certified by the equipment manufacturer. Present evidence of certification to the engineer.

# A.2 Equipment

A trial area will be designated by the engineer to demonstrate that equipment, personnel and methods of operation are capable of producing results satisfactory to the engineer. The trial area shall consist of two sections, approximately 50 square feet each, one section deteriorated concrete and one section sound concrete.

In the area of sound concrete, the equipment shall be adjusted to remove the minimum depth as shown on the plans. The equipment shall be readjusted to remove the deteriorated concrete. If the engineer finds the results satisfactory, these parameters shall be used for production removal.

If in the sole opinion of the engineer the hydro-demolition equipment does not produce satisfactory removal of the concrete, the engineer may require that the equipment be removed from the project and replaced with equipment that can meet the requirements of this special provision.

Make adjustments to the operating parameters, as required, to perform concrete removal as indicated on the plans and to adjust to the variance in the compressive strength of the concrete. If a bond exists between the remaining concrete and reinforcing steel, the concrete will not be required to be removed. If there is a loss of bond between the remaining concrete and the reinforcing steel, the adjacent concrete shall be removed to a depth that will provide a minimum 1 inch clearance around the reinforcing steel.

Maintain on the job site, an inventory of common wear parts and replacement accessories for equipment adequate to ensure that routine maintenance tasks can be performed readily.

## B (Vacant)

# **C** Construction

Submit layout details for aggregate dams or hay bales that will be used for filtering wastewater prior to discharge for each phase of work.

1228-28-70 60 of 61

Water for use during hydro-demolition and cleanup process shall conform to standard spec 501.2.4. The contractor is responsible for supplying all equipment and tools necessary to tap into the water source.

Vacuum runoff water generated by the hydro-demolition process. Do not allow runoff water and debris to constitute a hazard on adjacent or underlying roadways, waterways, drainage areas, or storm sewers, nor be allowed to erode existing slopes.

All concrete within the marked boundaries shall be removed to the minimum depth shown on the plans using hydro-demolition. Mark areas where delaminations exist beyond the minimum removal depth. Removal beyond the minimum removal depth shall be done according to 509.3.4 of standard spec for Preparation Decks Type 1 and Preparation Decks Type 2. Preparation Decks Type 1 and Preparation Decks Type 2 may be performed using hydro-demolition equipment or equipment conforming to standard spec 509.3.4.

Any areas of prepared surface contaminated by materials detrimental to a good bond as the result of the contractor's operations shall require additional removals until a clean surface is obtained, at no additional cost to the department.

At all locations where exposed reinforcement is designated to remain in place, exercise caution to avoid damaging it during removal of concrete. Any reinforcement damaged by the contractor's operations shall be repaired or replaced at no cost to the department.

Removal in areas that are not accessible to hydro-demolition equipment shall be performed by other means, in accordance with standard spec 509.

Clean the surface on which the new concrete will be placed to remove all loose particles and dust by brooming and water pressure, or by water and air pressure.

# **D** Measurement

The department will measure Hydro-demolition of Concrete Masonry Deck Overlay Structure (Structure) by the square yard of work, acceptably completed.

# **E** Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBERDESCRIPTIONUNITSPV.0180.4302Hydro-Demolition of Concrete Masonry Deck Overlay Structure B-40-293SY

Payment is full compensation for removing the overlay and any underlying deteriorated concrete, loading, hauling, and satisfactorily storing or disposing of the material.

Removing unsound concrete beyond the minimum depth shown on the plans for hydro-demolition will be paid for separately under bid items Preparation Decks Type 1 and Preparation Decks Type 2.

1228-28-70 61 of 61

# ADDITIONAL SPECIAL PROVISION 1 (ASP 1) FOR TRANSPORTATION ALLIANCE FOR NEW SOLUTIONS (TrANS) PROGRAM EMPLOYMENT PLACEMENTS AND APPRENTICESHIPS

The Safe, Accountable, Flexible, Efficient Transportation Equity Act: A Legacy for Users (SAFETEA-LU), Section 5204(e) – Surface Transportation Workforce Development Training and Education, provides for 100 percent Federal funding if the core program funds are used for training, education, or workforce development purposes, including "pipeline" activities. The core programs includes: Congestion Mitigation and Air Quality Improvement (CMAQ) Program, Highway Bridge Program (HBP), Interstate Maintenance (IM), National Highway System (NHS), and Surface Transportation Program (STP). These workforce development activities cover surface transportation workers, including OJT/SS programs for women and minorities as authorized in 23 U.S.C. §140(b).

Trans is an employment program originally established in 1995 in Southeastern Wisconsin. Currently Trans has expanded to include Trans program locations to serve contractors in Southeast (Milwaukee and surrounding counties), Southcentral (Dane County and surrounding counties including Rock County), and most Northeastern Wisconsin counties from locations in Keshena, Rhinelander and surrounding far Northern areas. Trans attempts to meet contractor's needs in other geographic locations as possible. It is an industry driven plan of services to address the outreach, preparation, placement and retention of women, minorities and non-minorities as laborers and apprentices in the highway skilled trades. These candidate preparation and contractor coordination services are provided by community based organizations. For a list of the Trans Coordinators contact the Disadvantaged Business Enterprise Office at (414) 438-4583 in Milwaukee or (608) 266-6961 in Madison. These services are provided to you at no cost.

# I. BASIC CONCEPTS

Training reimbursements to employing contractors for new placements, rehires or promotions to apprentice of TrANS Program graduates will be made as follows:

- 1) On-the-Job Training, Item ASP.1T0G, ASP 1 Graduate. At the rate of \$5.00 per hour on federal aid projects when TrANS graduates are initially hired, or seasonally rehired, as unskilled laborers or the equivalent.
  - <u>Eligibility and Duration:</u> To the employing contractor, for up to 2000 hours from the point of initial hire as a TrANS program placement.
  - <u>Contract Goal:</u> To maintain the intent of the Equal Employment Opportunity program, it is a goal that \_\_\_3\_\_ (number) TrANS Graduate(s) be utilized on this contract.
- 2) On-the-Job Training, Item ASP.1T0A, ASP 1 Apprentice. At the rate of \$5.00 per hour on federal aid projects at the point when an employee who came out of the TrANS Program is subsequently entered into an apprenticeship contract in an underutilized skilled trade (this will include the Skilled Laborer Apprenticeship when that standard is implemented).

<u>Eligibility and Duration:</u> To the employing contractor, for the length of time the TrANS graduate is in apprentice status.

<u>Contract Goal:</u> To maintain the intent of the Equal Employment Opportunity program, it is a goal that <u>2</u> (number) TrANS Apprentice(s) be utilized on this contract.

- The maximum duration of reimbursement is two years as a TrANS graduate plus time in apprentice status.
- 4) If a TrANS program is not available in the contractor's area and another training program is utilized, payment of On-the-Job Training hours may be approved by the Wisconsin Department of Transportation (WisDOT) if the training program meets the established acceptance criteria. Only On-the-Job Training Hours accumulated after WisDOT approval will be reimbursed as specified under Items ASP.1T0G and ASP.1T0A. For more information, contact the Disadvantaged Business Enterprise Office at the phone numbers listed above.
- 5) WisDOT reserves the right to deny payments under items ASP.1T0G and ASP.1T0A if the contractor either fails to provide training or there is evidence of a lack of good faith in meeting the requirements of this training special provision.

# I. RATIONALE AND SPECIAL NOTE

The \$5.00 per hour now being paid for TrANS placements is intended to cover the duration of two years to allow for reaching entry-level laborer status. An additional incentive, the \$5.00 rate, would promote movement into the underutilized skilled trades' apprenticeships and applies until the individual completes their apprenticeship. These incentives benefit TrANS candidates by giving them a better opportunity to enter a skilled trade; benefits contractors who will be assisted in meeting their EEO profiles and goals; and benefits the public who will see the program reinforce larger public-private employment reform in Wisconsin. The pool of TrANS graduates was created for the purpose of addressing underutilization in the skilled trades, an objective that is further reinforced by a parallel retention pilot program, known as the Companywide Reporting. Whether or not reimbursement is involved, the WisDOT reassures contractors who are in the Companywide Program that TrANS placements still contribute toward fulfilling the new hire goal of 50% women and minorities. Based on data administered by United States Department of Labor (US DOL), the highway skilled trades remain underutilized for women statewide (less than 6.9%); and for minorities in all counties (% varies by county).

<u>NOTE</u>: Unless using other advancement strategies, contractors are encouraged to use some or all of this monetary incentive to offset the cut in hourly wages an individual may incur when entering an apprenticeship if the full general laborer hourly rate has been previously paid. No special accounting measures are required.

# II. IMPLEMENTATION

The implementation of ASP 1 is intended to cover only the amount of time it takes for underutilization to be resolved across the trades. This will be measured annually at the county and/or state levels using data administered by WisDWD in relation to goals set by the USDOL-

OFCCP. With appropriate state and federal approvals, we may also do some measurement at the company level.

It is the contractor's responsibility to note on their Certified Payrolls if their employee is a TrANS graduate or a TrANS apprentice. The District EEO Coordinators utilize the information on the Certified Payrolls to track the hours accumulated by TrANS Graduates and TrANS apprentices on WisDOT contracts. Payment under this ASP 1 is made based on the hours recorded off of the Certified Payrolls. Tracking may eventually include improved linkages with the WisDWD apprentice database, information from company and committee level sources.

TrANS is nondiscriminatory by regulation, and is a tool for optional use by contractors to address the underutilization of women and minorities as laborers and apprentices in our industry's skilled trades.

# IV. TRANS TRAINING

As part of the contractor's equal employment opportunity affirmative action program, training shall be provided to employees enrolled in apprenticeship and on-the-job training programs as follows:

The contractor shall provide on-the-job training aimed at developing full journey workers in the type of trade or job classifications involved. In the event the contractor subcontracts a portion of the contract work, the contractor shall determine how many, if any, of the trainees are to be trained by the subcontractor provided, however, that the contractor shall retain the primary responsibility for meeting the training requirements imposed by this special provision. The contractor shall also insure that this training special provision is made applicable to such subcontract.

Training and upgrading of minorities and women toward journey workers status is a primary objective of this training special provision. Accordingly, the contractor shall make every effort to enroll minority trainees and women (e.g., by conducting systematic and direct recruitment through public and private sources likely to yield minority trainees and women trainees); to the extent such persons are available within a reasonable area of recruitment. The contractor will be given an opportunity and will be responsible for demonstrating the steps that they have taken in pursuance thereof, prior to determination as to whether the contractor is in compliance with this training special provision. This training commitment is not intended, and shall not be used, to discriminate against any applicant for training, whether a member of a minority group or not.

No employee shall be employed as a trainee in any classification in which they have successfully completed a training course leading to journey workers status or in which they have been employed as a journey worker. The contractor should satisfy this requirement by including appropriate questions in the employee application or by other suitable means. Regardless of the method used, the contractor's records should document the findings in each case.

# V. APPRENTICESHIP TRAINING

The Federal Highway Administration's (FHWA) policy is to require full use of all available training and skill improvement opportunities to assure increased participation of minority groups, disadvantaged persons and women in all phases of the highway construction industry. The FHWA On-the-Job Training (OJT) Program requires the State transportation agencies (STAs) to establish apprenticeships and training programs targeted to move women, minorities, and disadvantaged individuals into journey-level positions to ensure that a competent workforce is available to meet highway construction hiring needs, and to address the historical underrepresentation of members of these groups in highway construction skilled crafts.

The OJT Supportive Services (OJT/SS) Program was established in Title 23 Code of Federal Regulations (CFR), Part 230) to supplement the OJT program and support STA training programs by providing services to highway construction contractors and assistance to highway construction apprentices and trainees. The primary objectives of OJT/SS are:

- (1) To increase the overall effectiveness of the State highway agencies' approved training programs.
- (2) To seek other ways to increase the training opportunities for women, minorities, and disadvantaged individuals.

The STAs are responsible for establishing procedures, subject to the availability of Surface Transportation and Bridge Funds under 23 U.S.C. §140(b) (Nondiscrimination), for the provision of supportive services with respect to training programs approved under 23 CFR, Part 230(a) (Equal Employment Opportunity on Federal and Federal-aid Construction Contracts – including Supportive Services).

The contractor and subcontractor shall maintain records to demonstrate compliance with these apprenticeship requirements. Reasonable exemptions and modifications to and from any or all of these requirements will be determined by the Wisconsin Department of Transportation-Civil Rights Office. A request for an exemption or modification, with justification, shall be made in writing, addressed to WisDOT Civil Rights Office, 4802 Sheboygan Avenue, P.O. Box 7965, Rm. 451, Madison, WI 53707.

# **ADDITIONAL SPECIAL PROVISION 3**

# DISADVANTAGED BUSINESS ENTERPRISE [DBE] PROGRAM IMPLEMENTATION

# 1. Description

- a. The federal DBE program requirements outlined in the Code of Federal Regulations at 49 CFR Part 26 apply to this Wisconsin Department of Transportation contract. WisDOT is a recipient of federal funds and this contract includes federal funds. United States Department of Transportation Federal DBE Program requires the following provisions:
  - (1) Pursuant to the federal DBE program regulation at 49 CFR Part 26, a contractor's failure to comply with any provision of the DBE regulations will be considered a material breach of contract. This is non-negotiable. If a contractor fails to carry out the DBE program and Title VI nondiscrimination requirements of its contracts, the following sanctions will be assessed depending upon the facts, reasoning, severity and remedial efforts of the contractor: termination of contract, withholding payment, assessment of monetary sanctions, assessment of liquidated damages and/or suspension/debarment proceedings that may result in the disqualification of the contractor from bidding for a designated period of time.
  - (2) The contractor shall utilize the specific DBEs listed to perform the work and supply the materials for which each is listed unless the contractor obtains the federal fund recipient's [DOT] written consent. Unless [WisDOT] consent is provided, the contractor shall not be entitled to any payment for work or material unless it is performed or supplied by the listed DBE.
- b. The Wisconsin Department of Transportation [WisDOT] is committed to the compliant administration of the DBE Program. Each WisDOT Secretary affirms this commitment with his/her signed assurance. <a href="https://wisconsindot.gov/Documents/doing-bus/civil-rights/dbe/policy-statement.pdf">https://wisconsindot.gov/Documents/doing-bus/civil-rights/dbe/policy-statement.pdf</a>
  - (1) The department encourages the contractor to assist and develop DBE firms to become fully knowledgeable contractors to successfully perform on its contracts. Under the contract, the contractor agrees to provide the assistance to participating DBE's in the following areas:
    - i. Produce accurate and complete quotes.
    - ii. Understand highway plans applicable to their work.
    - iii. Understand specifications and contract requirements applicable to their work.
    - iv. Understand contracting reporting requirements.
  - (2) Wisconsin DOT identifies the assigned DBE goal in its contract advertisements and posts the contract DBE goal on the cover of the bidding proposal. The contractor can meet the assigned, specified contract DBE goal by subcontracting work to a DBE or by procuring services or materials from a DBE. The department calculates the DBE participation as the dollar value of DBE participation included in the bid expressed as a percentage of the total contract bid amount.
  - (3) For more comprehensive information on the disadvantaged business program, visit the department's Civil Rights and Compliance Section website at: <a href="https://wisconsindot.gov/Pages/doing-bus/civil-rights/dbe/default.aspx">https://wisconsindot.gov/Pages/doing-bus/civil-rights/dbe/default.aspx</a>

# 2. Definitions

Interpret these terms, used throughout this additional special provision, as follows:

- a. Bid Percentage: The DBE percentage indicated in the bidding proposal at the time of bid.
- b. **DBE:** A small business certified as disadvantaged business enterprise (DBE) under the federal DBE program and included on the Wisconsin UCP DBE Directory deemed ready, willing and able.
- c. **DBE goal:** The amount of DBE participation expected in the contract as shown on the cover of the Highway Work Proposal.
- d. **Manufacturer:** A firm that operates or maintains a factory or establishment that produces, on the premises, the materials, supplies, articles, or equipment required under the contract.
- e. **Supplier:** A firm that owns, operates, or maintains a store, warehouse, or other establishment in which the materials, supplies, articles or equipment required under the contract are bought, kept in stock, and regularly sold or leased to the public.
- f. **Voluntary Achievement:** The amount of DBE participation achieved and reported in the contract in excess of the assigned goal.

# 3. DBE Percentage Required at Bid Submission

Indicate the bid percentage (i.e. 0% through 100%) of DBE participation on the completed bidding proposal. For electronic submittals, show the percentage in the miscellaneous data folder, Item 3, DBE Percent. For paper submittals, show the percentage on the sheet included after the schedule of items. By submission of the bid, the bidder contractually commits to DBE participation at or above the bid percentage, or certifies that they have utilized comprehensive good faith efforts to solicit and utilize DBE firms to meet the DBE participation requirements of this contract proposal, and that the bid percentage is reflective of these good faith efforts. The bid percentage should demonstrate the efforts of the prime contractor prior to bid. If the bidder does not indicate the bid percentage of DBE participation on the completed bidding proposal, the department will consider the bid irregular and may reject the bid.

# 4. WisDOT Interpretation of Federal DBE Program Provision

Prime contractors must utilize the specific DBEs listed to perform the work and/or supply the materials for which each is listed on the Commitment to Subcontract to DBE Form [DT1506] and approved by WisDOT's DBE office to execute its contract. The approved Commitment to Subcontract to DBE Form [DT1506] becomes a contract document/record.

# a. Department's DBE Evaluation Process

WisDOT evaluates DBE using the Commitment to Subcontract to DBE, payments to subcontractors and contract documentation. The prime contractor shall list the specific DBE certified firms and items of work s/he intends to use toward the fulfillment of the assigned DBE contract goal. The prime contractor receives DBE credit for payments made to the DBE firms performing the work listed on the approved Form DT1506.

# b. Documentation Submittal

The contractor is to identify, by name, the DBE firms whose utilization is intended to satisfy this provision, the items of work of the DBE subcontract or supply agreement and the dollar value of those items of work by completing the Commitment to Subcontract to DBE Form [DT1506]. Effective January 1, 2017, the contractor will be required to submit the documentation within 5 business days after bid opening. All necessary supporting documentation including Attachment 'A' forms and/or Good Faith Efforts Form

[DT1202] must be submitted no later than 2 business days from contractor's initial submission of the DT 1506. The contractor must provide a signed Attachment 'A' form to the DBE office within the time limit in order to receive authorization for contract execution; the DBE office reserves the right accept alternate documentation in lieu of the signed form in extenuating circumstances. Documentation must be submitted to the DBE Office by email at DBE\_Alert@dot.wi.gov (DBE\_Alert@dot.wi.gov) or by postal mail ATTN: DBE Office, PO Box 7965, Madison, WI 53707-7965.

# (1) Bidder Meets DBE Goal

If the bidder indicates that the contract DBE goal is met, after award and before execution, the department will evaluate the Commitment to Subcontract to DBE Form DT1506 and attachment A(s) to verify the actual DBE percentage calculation. If the DBE commitment is verified, the contract is eligible for execution with respect to the DBE commitment.

# (2) Bidder Does Not Meet DBE Goal

- i. If the bidder indicates a bid percentage on the Commitment to Subcontract to DBE Form [DT1506] that does not meet the contract DBE goal, the bidder must submit a Good Faith Efforts Form [DT1202] and supporting documentation. After award and before execution, the department will evaluate the bidder's DBE commitment and consider the bidder's good faith efforts submission.
- ii. The department will evaluate the bidder's good faith effort request and notify the bidder of one of the following:
  - (a) If the department grants a good faith efforts, the bid is eligible for contract execution with respect to DBE commitment.
  - (b) If the department rejects the good faith efforts request, the department may declare the bid ineligible for execution. The department will provide a written explanation of why the good faith efforts request was rejected. The bidder may appeal the department's rejection as allowed under 7 a. & b.

# c. Bidder Fails to Submit Documentation

If the contractor fails to furnish the Commitment to Subcontract to DBE Form [DT1506] within the specified time, the department may cancel the award. Delay in fulfilling this requirement is not a cause for extension of the contract time and shall not be used as a tool to delay execution.

# 5. Department's Criteria for Good Faith Effort

Appendix A of 49 CFR Part 26, is the guiding regulation concerning good faith efforts. However, the federal regulations do not explicitly define "good faith" but states that bidder must actively and aggressively attempt to meet the goal. The federal regulations are general and do not include every factor or effort that can be considered. As a result, each state must establish its own processes and consider the factors established in its own practices to create a process for making a determination of adequate good faith. WisDOT evaluates good faith on a contract basis just as each contract award is evaluated individually.

The department will only approve a contractor's good faith efforts if the bidder has made the effort, given the relevant circumstances under the contract that a bidder actively and aggressively seeking to meet the goal would make. The department will evaluate the bidder's good faith effort to determine whether a good faith efforts will be granted. The bidder must demonstrate, on the DT1202 that they have aggressively solicited DBE participation in an attempt to meet the contract DBE goal and attaining the stated DBE goal is not feasible.

a. The department, in conjunction with industry stakeholders, has developed the following guidance for contractor good faith effort. The guidance and the attached appendices provide a framework for the actions required by all parties in the processing and evaluation of bidder's total efforts to achieve the project specific DBE goal prior to the bid letting date.

- b. Prime Contractors should:
  - (1) <u>Document</u> all efforts and decisions made toward achieving the DBE goal on the contract. The bidder should use the Civil Rights & Compliance System [CRCS] and related WisDOT- approved DBE outreach tools, including the Bid Express Small Business Network, to foster DBE participation on all applicable contracts.
  - (2) Prime contractors <u>may</u> request assistance with DBE outreach and follow-up by contacting the department's DBE Support Services Office by phone or email request at least 14 days prior to the bid letting date. Requesting assistance with outreach <u>is not</u> a decisive factor in the review Good faith effort evaluation. Phone numbers are 414-438-4584 and/or 414-659-0487; Fax: 414-438-5392; E-mail: DOTDBESupportServices@dot.wi.gov.
  - (3) Request quotes by identifying potential items to subcontract and solicit. Prime contractors are strongly encouraged to include in their initial contacts a single page including a detailed list of items for which they are accepting quotes, by project, within a letting. See attached sample entitled "Sample Contractor Solicitation Letter" in Appendix A. Prime contractors should also indicate a willingness to accept quotes in areas they are planning to perform themselves, as required by federal rules. In some cases, it might be appropriate to use DBE's to do work in a prime contractor's area of specialization.
    - i. Solicit quotes from certified DBE firms who match 'possible items to subcontract' using all reasonable and available means. Additionally, forward copies of solicitations highlighting the work areas for which you are seeking quotes to <a href="mailto:DOTDBESupportServices@dot.wi.gov">DOTDBESupportServices@dot.wi.gov</a>.
    - ii. SBN is the preferred outreach tool. <a href="https://www.bidx.com/wi/main">https://www.bidx.com/wi/main</a>. Other acceptable means include postal mail, email, fax, phone call.
      - (a) Primes must ask DBE firms for a response in their solicitations. See *Sample Contractors Solicitation Letter* in Appendix. This letter can be included as an attachment to the SBN sub-quote request.
      - (b) Solicit quotes at least 10 calendar days prior to the letting date, at least two Fridays before the letting, to allow DBE firms sufficient time to respond. Prime contractors should contact DBE firms early, asking if they need help organizing their quote, assistance confirming equipment needs, or other assistance supporting their submission of a competitive quote for their services.
      - (c) Second solicitation should take place within 5 calendar days. Email and SBN are the preferred delivery of the follow-up solicitation.
    - iii. Upon request, provide interested DBE firms with adequate information about plans, specifications and the requirements of the contract by letter, information session, email, phone call and/or referral.
    - iv. When potential exists, the contractor should advise interested DBE firms on how to obtain bonding, line of credit or insurance if requested.
    - v. Document DBE firm's interest in quoting by taking appropriate steps to follow up initial solicitation with:
      - (a) Email to all prospective DBE firms in relevant work areas.
      - (b) Phone call log to DBE firms who express interest via written response or call.
      - (c) Fax/letter confirmation
      - (d) Signed copy of Bid Express SBN Record of Subcontractor Outreach Effort.
- c. <u>Evaluate DBE quotes</u> Documentation is critical if a prime does not utilize the DBE firm's quote for any reason.
  - (1) Evaluate DBE firm's capability to perform 'possible items to subcontract' using legitimate reasons, including but not limited to, *a discussion with the DBE firm* regarding its capabilities prior to the bid letting. If lack of capacity is your reason for not utilizing the DBE quote, you are required to contact the DBE by phone and email regarding their ability to perform the work indicated in the UCP directory listed as their work area by NAICS code. Only the work area and/or NAICS code listed in the UCP directory can be counted toward DBE credit. Documentation of the conversation is required.
  - (2) In striving to meet an assigned DBE contract goal, prime contractors are expected to use DBE quotes that are responsive and reasonable. This includes DBE quotes that are not the low quote.

- (3) Special Circumstance Evaluation of DBE quotes with tied bid items. "Tied quotes are the condition in which a subcontractor submits quotes including multiple areas of expertise across multiple work areas noting that the items and price are tied. Typically this type of quoting represents a cost saving to the prime but is not clearly stated as a discount; tied quotes are usually presented as 'all or none' quote to the prime." When non-DBE subcontractors submit tied bid items in their quotes to the prime, the DBE firms' quote may seem not competitive. In such a case, the following steps are taken in comparing the relevant quotes. These are qualitative examples.
  - i. Compare bid items common to both quotes, noting the reasonableness in the price comparison.
  - ii. Review quotes from other firms for the bid items not quoted by the DBE firm to see if combining both can provide the same competitive advantage that the tied bid items offered.
- d. Immediately after notification of contract award, the prime submits all 'Commitment to Subcontract' forms to the DBE Office. Prime contractor has 5 days to submit the completed form for the DBE firms it intends to use on the contract for DBE credit. If the goal is not met in full, the prime contractor must provide the following information along with WisDOT form DT1202: Certificate of Good Faith Efforts.
  - (1) The names, addresses, e-mail addresses, telephone numbers of DBE's contacted. The dates of both initial and follow-up contact.
  - (2) A description of information provided to the DBE's regarding the plans, specifications, and estimated quantities for portions of the work to be performed by that DBE.
  - (3) Photocopies or electronic copies of all written solicitations to DBE's. A printed copy of SBN solicitation is acceptable.
  - (4) Documentation of each quote received from a DBE and, if rejected, the reason for that rejection.
  - (5) Bidder attendance at any pre-solicitation or pre-bid meetings the department held to inform DBE's of participation opportunities available on the project.

The prime contractor must obtain written consent from the DBE Office to change or replace any DBE firm listed on the approved Commitment to Subcontract to DBE Form [DT1506]. If the prime contractor utilizes another contractor, including the use of its own workforce, to perform the work assigned to a DBE on the approved DT1506, the prime contractor will not be entitled to payment for that work. Any changes to DBE after the approval of the DT1506 must be reviewed and approved by the DBE office prior to the change.

# 6. Use of Joint Checks

The use of joint checks is allowable if it is a commonly recognized business practice in the material industry. A joint check is defined as a two-party check between a DBE, a prime contractor and the regular dealer of materials supplier who is neither the prime nor an affiliate of the prime. Typically, the prime contractor issues one check as payor to the DBE subcontractor and to the supplier jointly (to guarantee payment to the supplier) as payment for the material/supplies used by the DBE in cases where the prime has submitted the DBE and material for DBE credit. The DBE subcontractor gains the opportunity to establish a direct contracting relationship with the supplier to potentially facilitate a business rapport that results in a line of credit or increased partnering opportunities.

The cost of material and supplies purchased by the DBE is part of the value of work performed by the DBE to be counted toward the goal. To receive credit, the DBE must be responsible for negotiating price, determining quality and quantity, ordering the materials, and installing (where applicable) and "paying for the material itself." See 49 CFR 26.55(c)(1).

The approval to use joint checks constitutes a commitment to provide further information to WisDOT, upon request by staff. WisDOT will allow the use of joint checks when the following conditions are met:

- a. The Prime must request permission to use joint checks from the DBE Office by submitting the Application to Use Joint Checks.
  - (1) Request should be made when the DBE Commitment form or Request to Sublet is submitted; the request will not be considered if submitted after the DBE Subcontractor starts its work.
  - (2) Approval/Permission must be granted prior to the issuance of any joint checks.
  - (3) The payment schedule for the supplier must be presented to the DBE office before the first check is issued.
  - (4) The joint check for supplies must be strictly for the cost of supplies.
- b. DBE subcontractor is responsible to furnish and/or install the material/work item. The DBE subcontractor shall not be an 'extra participant' in the transaction; the DBE's role in the transaction cannot be limited solely to signing the check(s) to release payment to the material supplier. At a minimum, the DBE subcontractor's tasks should include the following.
  - (1) The DBE subcontractor (not the prime/payor) negotiates the quantities, price and delivery of materials;
  - (2) The DBE subcontractor consents to sign/release the check to the supplier by signing the Application to Use Joint Checks after establishing the conditions and documentation of payment within the subcontract terms or in a separate written document.
- c. The Prime contractor/payor acts solely as a guarantor,
  - (1) The prime agrees to furnish the check used for the payment of materials/supplies under the contract.
  - (2) The prime contractor/payor cannot require the subcontractor to use a specific supplier or the prime contractors negotiated unit price.

# 7. Bidder's Appeal Process

- a. A bidder can appeal the department's decision to deny the bidder's good faith effort submission. The bidder must provide written documentation refuting the specific reasons for rejection as stated in the department's rejection notice. The bidder may meet in person with the department if so requested. Failure to appeal within 7 calendar days after receiving the department's written denial notice of a good faith effort evaluation constitutes a forfeiture of the bidder's right of appeal. A contract cannot be executed without documentation that the DBE provisions have been fulfilled.
- b. The department will appoint a representative, who did not participate in the original determination, to assess the bidder's appeal. The department will issue a written decision within 5 calendar days after the bidder presents all written and oral testimony. In that written decision, the department will explain the basis for finding that the bidder did or did not meet the contract DBE goal or make an adequate good faith effort to meet the contract DBE goal. The department's decision is final. If the department finds that the bidder did not meet the contract DBE goal or did not make adequate efforts to meet the DBE goal, the department may declare the bid ineligible for execution.

# 8. Department's Criteria for DBE Participation

# **Directory of DBE firms**

a. The only resource for DBE certified firms certified in the state of Wisconsin is the Wisconsin Unified Certification Program [UCP] DBE List. Wisconsin Department of Transportation maintains a current list of certified DBE firms titled Wisconsin UCP DBE Directory on the website at:

https://wisconsindot.gov/Documents/doing-bus/civil-rights/dbe/dbe-ucp-directory.xlsx

b. The DBE office is also available to assist at 414-438-4583 or 608-267-3849.

# 9. Counting DBE Participation

# **Assessing DBE Work**

- a. The department will only count the DBE usage towards the contract DBE goal if the DBE firm is certified as a DBE by one of the unified certification program agencies. If a firm becomes DBE certified before entering into a subcontract, the department may consider that DBE usage towards the contract goal. The department only counts the value of the work a DBE actually performs towards the DBE goal. The department assesses the DBE work as follows:
- b. The department counts work performed by the DBE's own resources. The department includes the cost of materials and supplies the DBE obtains for the work. The department also includes the cost of equipment the DBE leases for the work. The department will not include the cost of materials, supplies, or equipment the DBE purchases or leases from the prime contractor or its affiliate, except the department will count non-project specific leases the DBE has in place before the work is advertised.
- c. The department counts fees and commissions the DBE charges for providing a bona fide professional, technical, consultant, or managerial services. The department also counts fees and commissions the DBE charges for providing bonds or insurance. The department will only count costs the engineer deems reasonable based on experience or prevailing market rates.
- d. If a DBE subcontracts work, the department counts the value of the subcontracted work only if the DBE's subcontractor is also a DBE.
- e. The contractor shall maintain records and may be required to furnish periodic reports documenting its performance under this item.
- f. It is the prime contractor's responsibility to determine whether the work that is committed and/or contracted to a DBE certified firm can be counted for DBE credit by referencing the work type and NAICS code listed for the DBE firm on the Wisconsin UCP DBE Directory.
- g. It is the prime contractor's responsibility to assess the DBE firm's ability to perform the work for which s/he is committing/contracting the DBE to do. Note that the department encourages the prime contractor to assist and develop DBE firms to become fully knowledgeable contractors to successfully perform on its contracts.

# 10. Commercially Useful Function

- a. Commercially useful function is evaluated after the contract has been executed, while the DBE certified firm is performing its work items. A DBE performs a commercially useful function when it is responsible for execution of the work of the contract and is carrying out its responsibilities by actually performing, managing, and supervising the work involved.
- b. The department uses Form DT1011: DBE Commercially Useful Function Review and Certification to evaluate whether the DBE is performing a commercially useful function. WisDOT counts expenditures of a DBE toward the DBE goal only if the DBE is performing a commercially useful function on that contract.
- c. A DBE is performing a commercially useful function if the following conditions are met:
  - (1) For contract work, the DBE is responsible for executing a distinct portion of the contract work and it is carrying out its responsibilities by actually performing, managing, and supervising that work.
  - (2) For materials and supplies, the DBE is responsible for negotiating price, determining quality and quantity, ordering, and paying for those materials and supplies.

# 11. Credit Evaluation for Trucking

All bidders are expected to adhere to the department's current trucking policy posted on the HCCI website at <a href="https://wisconsindot.gov/Documents/doing-bus/civil-rights/dbe/trucking-utilization-policy.pdf">https://wisconsindot.gov/Documents/doing-bus/civil-rights/dbe/trucking-utilization-policy.pdf</a>

# 12. Credit Evaluation for Manufacturers, Suppliers, Brokers

The department will calculate the amount of DBE credit awarded to a prime using a DBE firm for the provisions of materials and supplies on a contract-by-contract basis. The department will count the material and supplies that a DBE provides under the contract for DBE credit based on whether the DBE is a manufacturer, supplier or broker. Generally, DBE crediting measures and evaluates the DBE owner's role, responsibility and contribution to the transaction: maximum DBE credit when the DBE manufactures materials or supplies; DBE credit decreases when the DBE solely supplies material and minimal credit is allotted when the DBE's role is administrative or transactional.

It is the bidder's responsibility to find out if the DBE is considered a supplier or a manufacturer before listing them on Commitment to Subcontract to DBE form DT1506.

# a. Manufacturers

- (1) A manufacturer is a firm that operates or maintains a factory or establishment that produces, on the premises, the materials, supplies, articles, or equipment required under the contract and of the general character described by the specifications.
- (2) If the materials or supplies are obtained from a DBE manufacturer, count **100**% percent of the cost of the materials or supplies toward DBE goals.
- b. Regular Dealers of Material and/or Supplies
  - (1) A regular dealer is a firm that owns, operates, or maintains a store, warehouse, or other establishment in which the materials, supplies, articles or equipment of the general character described by the specifications and required under the contract are bought, kept in stock, and regularly sold or leased to the public in the usual course of business.
  - (2) If the materials or supplies are purchased from a DBE regular dealer, count **60%** percent of the cost of the materials or supplies toward DBE goals.
  - (3) At a minimum, a regular dealer must meet the following criteria to be counted for DBE credit:
    - i. The DBE firm must be an established, regular business that engages, as its principal business and under its own name, in the purchase and sale or lease of the products in question.
    - ii. The DBE firm must both own and operate distribution equipment for the product--bulk items such as petroleum products, steel, cement, gravel, stone, or asphalt. If some of the distribution equipment is leased, the lease agreement must accompany the DBE Commitment form for evaluation of the dealer's control before the DBE office approves the DBE credit.
- c. Brokers, Transaction Expediters, Packagers, Manufacturers Representatives
  - (1) No portion of the cost of the materials, supplies, services themselves will count for DBE credit; however, WisDOT will evaluate the fees or commissions charged when a prime purchases materials, supplies or services from a DBE certified firm which is neither a manufacturer nor a regular dealer, namely: brokers, packagers, manufacturers' representatives or other persons who arrange or expedite transactions.
  - (2) Brokerage fees have historically been calculated as 10% of the purchase amount.
  - (3) WisDOT may count the amount of fees or commissions charged for assistance in the procurement of the materials and supplies, or fees or transportation charges for the delivery of materials or supplies required on a job site.
  - (4) The evaluation will review the contract need for the item/service, review the sub-contract or invoice for the item/service, compare the fees customarily allowed for similar services to determine whether they are reasonable.

When DBE suppliers are contracted, additional documentation must accompany the DT1506 and Attachment 'A' forms. An invoice or bill-of-sale that includes the company names of the bidder and the DBE supplier and documentation of the calculations used as the basis for the purchase agreement, subcontract or invoice. WisDOT recognizes that the amount on the Attachment 'A' form may be more or less than the amount on the invoice. Please respond to the following questions and submit with your DBE Commitment Form.

- 1. What is the product or material?
- 2. Is this item in the prime's inventory or was the item purchased when contract was awarded?
- 3. Which contract line items were referenced to develop this quote?
- 4. What is the amount of material or product used on the project?

# 13. Credit Evaluation for DBE Primes

Wisconsin DOT calculates DBE credit based on the amount and type of work performed by DBE certified firms. If the prime contractor is a DBE certified firm, the department will only count the work that DBE prime contractor performs with its own forces for DBE credit. We will also calculate DBE credit for the work performed by any other DBE certified subcontractor, DBE certified supplier, DBE certified manufacturer on that contract in that DBE's approved work areas/NAICS code. Crediting for manufacturers and suppliers is calculated consistent with paragraph 12 of this document and 49 CFR Part 26.

# 14. Joint Venture

If a DBE performs as a participant in a joint venture, the department will only count that portion of the total dollar value of the contract equal to that portion of the work that the DBE performs with its own forces for DBE credit.

# 15. Mentor Protégé

- a. If a DBE performs as a participant in a mentor protégé agreement, the department will count for credit the portion of the work performed by the DBE protégé firm.
- b. DBE credit will be evaluated and confirmed by the DBE Office for any contracts on which the mentor protégé team identifies itself to the DBE Office as a current participant of the Mentor Protégé Program.
- c. Refer to WisDOT's Mentor Protégé guidelines for guidance on the number of contracts and amount of DBE credit that can be counted on any WisDOT project.

# 16. DBE Replacement or Termination

# **Contractual Requirement**

The contractor shall utilize the specific DBEs listed to perform the work and supply the materials for which each is listed unless the contractor obtains written consent from the Department's DBE Office. If the Department does not provide consent to replace or terminate a DBE firm, the prime contractor shall not be entitled to any payment for work or material unless it is performed or supplied by the listed DBE.

# **Contractor Considerations**

a. A prime contractor cannot terminate and/or replace a DBE subcontractor listed on the approved Commitment to Subcontract to DBE Form [DT1506] without prior written consent from the DBE Office. This includes, but is not limited to, instances in which a prime contractor seeks to perform work originally designated for a DBE subcontractor with its own forces or those of an affiliate, a non-DBE firm, or with another DBE firm.

- b. If a prime contractor feels it is necessary to replace or terminate a DBE firm that has been approved for DBE credit toward its contract, s/he will be required to provide reasons and documentation to support why the prime cannot fulfill the contractual commitment that it made to the Department regarding the DBE utilization.
- c. Prime contractor is required to make affirmative efforts to find another DBE subcontractor to perform at least the same amount of work under the contract as the DBE that was terminated, to the extent needed to meet the assigned DBE contract goal.
- d. In circumstances when a DBE subcontractor fails to complete its work on the contract for any reason or is terminated from a contract, the prime contractor is expected to make affirmative efforts to maintain its commitment to the assigned DBE goal.
- e. The DBE firm should communicate with the prime contractor regarding its schedule and capacity in the context of the contract. If the DBE anticipates that it cannot fulfill its subcontract, s/he shall advise the prime contractor and suggest a DBE that may replace their services or provide written consent to be released from its subcontract.
  - (1) Before the prime contractor can request to terminate or substitute a DBE firm; s/he must:
    - i. Make every effort to fulfill the DBE commitment by working with the listed DBE to ensure that they are fully knowledgeable of your expectations for successful performance on the contract. Document these efforts in writing.
    - ii. If those efforts fail, provide written notice to the DBE subcontractor of your *intent to* request to terminate and/or replace the firm including the reason(s) you want to pursue this action.
    - iii. Copy the DBE Office on all correspondence related to changing a DBE firm who has been approved for DBE credit on a contract including the preparation and coordination efforts with the DBE on the contract.
    - iv. Clearly state the amount of time the DBE firm has to remedy and/or respond to your notice of intent to replace/terminate their firm from the contract. The DBE shall be allowed five days to respond, in writing. Exception: The prime contractor must provide a verifiable reason for a response period shorter than five days. For example a WisDOT project manager must verify that waiting 5 days for a DBE performing traffic control work to respond would affect the public safety.
    - v. The DBE subcontractor must forward a written response to the prime contractor and copy the DBE Office. The written response must outline why it objects to the proposed termination of its subcontract and list the reasons that WisDOT should not approve the request for their firm to be replaced or removed from the contract.

# The Request to Replace or Terminate a DBE

The prime contractor must provide a written request to replace or terminate a DBE firm that has been approved for DBE credit on a WisDOT contract. The written request can be an email or printed document delivered by email or fax; at minimum, the request must contain the following:

- 1. Contract ID number.
- 2. Wisconsin DOT Contract Project Manager name and contact information.
- 3. DBE name and work type and/or NAICS code.
- 4. Contract's progress schedule.
- 5. Reason(s) for requesting that the DBE be replaced or terminated.
- 6. Attach/include all communication with the DBE to deploy/address/resolve work completion,

WisDOT will review your request and any supporting documentation that you submit to evaluate whether the circumstance and the reasons constitute a good cause for replacing or terminating the DBE that was approved for DBE credit on that contract.

Examples of Good Causes to Replace a DBE according to the federal DBE program guidelines [49 CFR part 26.53]

- The listed DBE subcontractor fails or refuses to execute a written contract.
- The listed DBE subcontractor fails or refuses to perform the work of its subcontract in a way consistent
  with normal industry standards. Provided, however, that good cause does not exist if the failure or
  refusal of the DBE subcontractor to perform its work on the subcontract results from the bad faith or
  discriminatory action of the prime contractor.
- The listed DBE subcontractor fails or refuses to meet the prime contractor's reasonable, nondiscriminatory bond requirements.
- The listed DBE subcontractor becomes bankrupt, insolvent, or exhibits credit unworthiness.
- The listed DBE subcontractor is ineligible to work on public works projects because of suspension and debarment proceedings pursuant 2 CFR Parts 180, 215 and 1,200 or applicable state law.
- · You have determined that the listed DBE subcontractor is not a responsible contractor.
- The listed DBE subcontractor voluntarily withdraws from the project and provides to you written notice of its withdrawal.
- The listed DBE is ineligible to receive DBE credit for the type of work required.
- A DBE owner dies or becomes disabled with the result that the listed DBE contractor is unable to complete its work on the contract.

# **Evaluation and Response to the Request**

If WisDOT determines that your reasons comply with the good cause standards; the DBE office will send the prime contractor and the WisDOT project manager an email stating that we concur with the reasons and approve the replacement or termination.

If WisDOT determines that your reasons do not comply with the good cause standards of the federal DBE program, the DBE Office will send the prime contractor an email that includes *the requirement* to utilize the committed DBE, *remedial actions* to support the completion of the contractual commitment, a list of available WisDOT support services *and administrative remedies that may be invoked* for failure to comply with federal DBE guidelines for DBE replacement.

The Wisconsin Department of transportation contact for all actions related to replacing a DBE is the DBE Program Chief and/or the DBE Program Engineer which can be reached at <a href="mailto:DBE\_Alert@dot.wi.gov">DBE\_Alert@dot.wi.gov</a> or by calling 608-267-3849.

# 17. DBE Utilization beyond the approved DBE Commitment Form DT1506

If the Prime/subcontractor increases the scope of work for a participating DBE or adds a DBE subcontractor that was not on the approved Form DT1506 at any time after contract award, s/he should follow these steps so that the participation can be accurately credited toward the DBE goal.

- a. Send an email to the DBE Engineer at <u>DBE\_Alert@dot.wi.gov</u> describing the work to be performed by the new DBE including the proposed schedule or duration, DBE name and contact information. You may also call the DBE Engineer at 414-659-0487 to notify him of the change verbally.
  If the scope change added work for a participating DBE; list the date and reason for the scope change.
- b. Forward a complete, signed Attachment 'A' form to the DBE Office at <a href="mailto:DBE\_Alert@dot.wi.gov">DBE\_Alert@dot.wi.gov</a>. A complete Attachment A includes DBE contact information, signature, subcontract value and proper description of the work areas to be performed by the DBE.
  - The DBE office will confirm the DBE participation and revise the DT1506 based on the email/discussion and attach the new/revised Attachment A to the Contract record/documentation.

# 18. Contract Modifications

When additional opportunity is available by contract modifications, the Prime Contractor shall utilize DBE Subcontractors that were committed to equal work items, in the original contract.

# 19. Payment

Costs for conforming to this Additional Special Provision (ASP) and any associated DBE requirements are incidental to the contract.

# APPENDIX A Sample Contractor Solicitation Letter Page 1 This sample is provided as a guide not a requirement

#### **GFW SAMPLE MEMORANDUM**

TO: DBE FIRMS

DATE:

CC:

FROM: POTENTIAL PRIME CONTRACTOR OR MAJOR SUBCONTRACTOR

SUBJECT: REQUEST FOR DBE QUOTES

**LET DATE & TIME**MONTH DAY YEAR
DBE OFFICE ENGINEER

Our company is considering bidding on the projects indicated on the next page, as a prime and/or a subcontractor for the Wisconsin Department of Transportation Month-date -year Letting. Page 2 lists the projects and work items that we may subcontract for this letting. We are interested in obtaining subcontractor quotes for these projects and work categories. Also note that we are willing to accept quotes in areas we may be planning to perform ourselves as required by federal rules.

Please review page 2, respond whether you plan to quote, highlight the projects and work items you are interested in performing and return it via fax or email within 3 days. Plans, specifications and addenda are available through WisDOT at the DBE Support Services office or at the Highway Construction Contract Information (HCCI) site at https://wisconsindot.gov/Pages/doing-bus/contractors/hcci/default.aspx

Your quote should include all of the costs required to complete the items you propose to perform including labor, equipment, material, and related bonding or insurance. The quote should note items that you are DBE certified to perform, tied items, and any special terms. Page 2, with the indicated projects and items you plan to quote, should be used as a cover sheet for your quote.

Please make every effort to have your quotes into our office by time deadline the prior to the letting date. <u>Make sure</u> the correct letting date, project ID and proposal number, unit price and extension are included in your quote. We prefer quotes be sent via SBN but prime's alternatives are acceptable. Our office hours are include hours and days. Please call our office as soon as possible prior to the letting if you need information/clarification to prepare your quote at contact number.

If you wish to discuss or evaluate your quote in more detail, contact us after the contract is awarded. Status of the contract can be checked at WisDOT's HCCI site at <a href="https://wisconsindot.gov/Pages/doing-bus/contractors/hcci/default.aspx">https://wisconsindot.gov/Pages/doing-bus/contractors/hcci/default.aspx</a> All questions should be directed to:

Project Manager, John Doe,

Phone: (000) 123-4567

Email: Joe@joetheplumber.com

Fax: (000) 123- 4657

# Sample Contractor Solicitation Letter Page 2 This sample is provided as a guide not a requirement

REQUEST FOR QUOTATION

etting Date:							
roject ID:							
ease check all that apply	_						
Yes, we will be quoting on No, we are not interested in Please take our name off you We have questions about questions	n quoting on to our monthly D	he letting OBE conta	or its items ct list			his number	
Prime Contractor 's Contact P	erson	<b>¬</b>		DBE Co	ntractor Co	ontact Perso	n
3			DI				
Phone:		_	Phone				
Tax:		_	Fax				
Email:		_	Email				
		_					
	circle the jo						T 7
Proposal No.	1	2	3	4	5	6	7
ORK DESCRIPTION:	X		X	X		X	X
ORK DESCRIPTION: Clear and Grub	X X		X X	X X		X X	X
ORK DESCRIPTION: Clear and Grub Dump Truck Hauling							
ORK DESCRIPTION: Clear and Grub Dump Truck Hauling Curb & Gutter/Sidewalk, Etc.	X		X	X		X	X
ORK DESCRIPTION: Clear and Grub Dump Truck Hauling Curb & Gutter/Sidewalk, Etc. Erosion Control Items	X		X X	X X		X X	X
Clear and Grub Dump Truck Hauling Curb & Gutter/Sidewalk, Etc. Erosion Control Items Signs and Posts/Markers	X X X	X	X X X	X X X		X X X	X X X
County  /ORK DESCRIPTION:  Clear and Grub  Dump Truck Hauling  Curb & Gutter/Sidewalk, Etc.  Erosion Control Items  Signs and Posts/Markers  Traffic Control  Electrical Work/Traffic Signals	X X X	X	X X X X	X X X X		X X X X	X X X X
Clear and Grub Dump Truck Hauling Curb & Gutter/Sidewalk, Etc. Erosion Control Items Signs and Posts/Markers Traffic Control	X X X	X X	X X X X X X	X X X X X X	X	X X X X X X	X X X X X
Clear and Grub Dump Truck Hauling Curb & Gutter/Sidewalk, Etc. Erosion Control Items Signs and Posts/Markers Traffic Control Electrical Work/Traffic Signals Pavement Marking	X X X	X X X	X X X X X	X X X X X X X	X	X X X X X X X	X X X X X X
Clear and Grub Dump Truck Hauling Curb & Gutter/Sidewalk, Etc. Erosion Control Items Signs and Posts/Markers Traffic Control Electrical Work/Traffic Signals Pavement Marking Sawing Pavement QMP, Base	X X X X	X X	X X X X X X	X X X X X X X X		X X X X X X	X X X X X
Clear and Grub Dump Truck Hauling Curb & Gutter/Sidewalk, Etc. Erosion Control Items Signs and Posts/Markers Traffic Control Electrical Work/Traffic Signals Pavement Marking Sawing Pavement QMP, Base Pipe Underdrain	X X X X	X X X	X X X X X X	X X X X X X X X X	X X	X X X X X X X X	X X X X X X X
Clear and Grub Dump Truck Hauling Curb & Gutter/Sidewalk, Etc. Erosion Control Items Signs and Posts/Markers Traffic Control Electrical Work/Traffic Signals Pavement Marking Sawing Pavement QMP, Base Pipe Underdrain Beam Guard	X X X X	X X X	X X X X X X	X X X X X X X X	X	X X X X X X X	X X X X X X X
Clear and Grub Dump Truck Hauling Curb & Gutter/Sidewalk, Etc. Erosion Control Items Signs and Posts/Markers Traffic Control Electrical Work/Traffic Signals Pavement Marking Sawing Pavement QMP, Base Pipe Underdrain	X X X X	X X X	X X X X X X	X X X X X X X X X	X X	X X X X X X X X	X X X X X X X

# APPENDIX B BEST PRACTICES FOR PRIME CONTRACTOR & DBE SUBCONTRACTOR GOOD FAITH EFFORT

# This list is not a set of requirements; it is a list of potential strategies

# **Primes**

- Ø Prime contractor open houses inviting DBE firms to see the bid "war room" or providing technical assistance.
- Ø Participate in speed networking and mosaic exercises as arranged by DBE office.
- Ø Host information sessions not directly associated with a bid letting.
- Ø Participate in a formal mentor protégé or joint venture with a DBE firm.
- Ø Participate in WisDOT advisory committees i.e. TRANSAC, or Mega Project committee meetings.
- Ø Facilitate a small group DBE 'training session' Clarifying how your firm prepares for bid letting, evaluates subcontractors, preferred qualifications and communication methods.
- Ø Encourage subcontractors to solicit and highlight DBE participation in their quotes to you.
- Ø Quality of communication, not quantity creates the best results. Contractors should do as thorough a job as possible in communicating with DBE firms before the bid and provide any assistance requested to assure best possible bid.

# **DBE**

- Ø DBE firms should contact primes as soon as possible with questions regarding their quotes or bid; seven days prior is optimal.
- Ø Continually check for contract addendums on the HCCI website through the Thursday prior to letting to stay abreast of changes.
- Ø Review the status of contracts on the HCCI website reviewing the 'apparent low bidder' list, and bid tabs at a minimum.
- Ø Prepare a portfolio or list of related projects and prime and supplier references; be sure to note transportation-related projects of similar size and scope, firm expertise and staffing.
- Ø Participate in DBE office assessment programs.
- Ø Participate on advisory and mega-project committees.
- Ø Sign up to receive the DBE Contracting Update.
- Ø Consider membership in relevant industry or contractor organizations.
- Ø Active participation is a must. Quote as many projects as you can reasonably work on; quoting the primes and bidding as a prime with the department are the only ways to get work.

# **APPENDIX C**

# Types of Efforts considered in determining GFE

This list represents concepts being assessed; analysis requires additional steps

- 1. Whether the contractor attended any pre-solicitation or pre-bid meetings that were scheduled by WisDOT to inform DBEs of contracting and subcontracting opportunities.
- 2. Whether the contractor provided written notice to a reasonable number of specific DBEs that their interest in the contract was being solicited, in sufficient time to allow the DBEs to participate effectively.
- 3. Whether the contractor followed up initial solicitations of interest by contacting DBEs to determine if the DBEs were interested; returned the phone calls of interested DBE firms.
- 4. Whether the contractor selected portions of the work to be performed by DBEs in order to increase the likelihood of meeting the DBE goal.
- 5. Whether the contractor provided interested DBEs with adequate information about the plans, specifications and requirements of the contract.
- 6. Whether the contractor negotiated in good faith with interested DBEs, not rejected DBEs as unqualified without sound reasons based on a thorough investigation of their capabilities.
- 7. Whether the contractor made efforts to assist interested DBEs in being more competitive.
- 8. Whether the contractor effectively used the services of available minority community organizations: minority contractors groups, local, state, and Federal minority business assistance offices, and other organizations that provide assistance to small businesses and DBE firms.
- 9. Whether Prime used CRCS to identify DBE who specialize in relevant work areas.
- 10. Whether the contractor used available resources including contacting the DBE office, using WisDOT's website
- 11. Whether the contractor returned calls of firms expressing interest in a timely manner.

# **APPENDIX D**

# **Good Faith Effort Evaluation Guidance**

# Excerpt from Appendix A of 49 CFR Part 26

# APPENDIX A TO PART 26 -- GUIDANCE CONCERNING GOOD FAITH EFFORTS

- I. When, as a recipient, you establish a contract goal on a DOT assisted contract, a bidder must, in order to be responsible and/or responsive, make good faith efforts to meet the goal. The bidder can meet this requirement in either of two ways. First, the bidder can meet the goal, documenting commitments for participation by DBE firms sufficient for this purpose. Second, even if it doesn't meet the goal, the bidder can document adequate good faith efforts. This means that the bidder must show that it took all necessary and reasonable steps to achieve a DBE goal or other requirement of this part which, by their scope, intensity, and appropriateness to the objective, could reasonably be expected to obtain sufficient DBE participation, even if they were not fully successful.
- II. In any situation in which you have established a contract goal, part 26 requires you to use the good faith efforts mechanism of this part. As a recipient, it is up to you to make a fair and reasonable judgment whether a bidder that did not meet the goal made adequate good faith efforts. It is important for you to consider the quality, quantity, and intensity of the different kinds of efforts that the bidder has made. The efforts employed by the bidder should be those that one could reasonably expect a bidder to take if the bidder were actively and aggressively trying to obtain DBE participation sufficient to meet the DBE contract goal. Mere pro forma efforts are not good faith efforts to meet the DBE contract requirements. We emphasize, however, that your determination concerning the sufficiency of the firm's good faith efforts is a judgment call: meeting quantitative formulas is not required.
- III. The Department also strongly cautions you against requiring that a bidder meet a contract goal (i.e., obtain a specified amount of DBE participation) in order to be awarded a contract, even though the bidder makes an adequate good faith efforts showing. This rule specifically prohibits you from ignoring bona fide good faith efforts.
- IV. The following is a list of types of actions which you should consider as part of the bidder's good faith efforts to obtain DBE participation. It is not intended to be a mandatory checklist, nor is it intended to be exclusive or exhaustive. Other factors or types of efforts may be relevant in appropriate cases.
  - A. Soliciting through all reasonable and available means (e.g. attendance at pre-bid meetings, advertising and/or written notices) the interest of all certified DBEs who have the capability to perform the work of the contract. The bidder must solicit this interest within sufficient time to allow the DBEs to respond to the solicitation. The bidder must determine with certainty if the DBEs are interested by taking appropriate steps to follow up initial solicitations.
  - B. Selecting portions of the work to be performed by DBEs in order to increase the likelihood that the DBE goals will be achieved. This includes, where appropriate, breaking out contract work items into economically feasible units to facilitate DBE participation, even when the prime contractor might otherwise prefer to perform these work items with its own forces.
  - C. Providing interested DBEs with adequate information about the plans, specifications, and requirements of the contract in a timely manner to assist them in responding to a solicitation.
  - D. (1) Negotiating in good faith with interested DBEs. It is the bidder's responsibility to make a portion of the work available to DBE subcontractors and suppliers and to select those portions of the work or material needs consistent with the available DBE subcontractors and suppliers, so as to facilitate DBE participation. Evidence of such negotiation includes the names, addresses, and telephone numbers of DBEs that were considered; a description of the information provided regarding the plans and specifications for the work selected for subcontracting; and evidence as to why additional agreements could not be reached for DBEs to perform the work.
    - A bidder using good business judgment would consider a number of factors in negotiating with subcontractors, including DBE subcontractors, and would take a firm's price and capabilities as well as contract goals into consideration. However, the fact that there may be some additional costs involved in finding and using DBEs is not in itself sufficient reason for a bidder's failure to meet the contract DBE goal, as long as such costs are reasonable. Also, the ability or desire of a prime contractor to perform the work of a

- contract with its own organization does not relieve the bidder of the responsibility to make good faith efforts. Prime contractors are not, however, required to accept higher quotes from DBEs if the price difference is excessive or unreasonable.
- E. Not rejecting DBEs as being unqualified without sound reasons based on a thorough investigation of their capabilities. The contractor's standing within its industry, membership in specific groups, organizations, or associations and political or social affiliations (for example union vs. non-union employee status) are not legitimate causes for the rejection or non solicitation of bids in the contractor's efforts to meet the project goal.
- F. Making efforts to assist interested DBEs in obtaining bonding, lines of credit, or insurance as required by the recipient or contractor.
- G. Making efforts to assist interested DBEs in obtaining necessary equipment, supplies, materials, or related assistance or services.
- H. Effectively using the services of available minority/women community organizations; minority/women contractors' groups; local, state, and Federal minority/women business assistance offices; and other organizations as allowed on a case-by-case basis to provide assistance in the recruitment and placement of DBEs.
- V. In determining whether a bidder has made good faith efforts, you may take into account the performance of other bidders in meeting the contract. For example, when the apparent successful bidder fails to meet the contract goal, but others meet it, you may reasonably raise the question of whether, with additional reasonable efforts, the apparent successful bidder could have met the goal. If the apparent successful bidder fails to meet the goal, but meets or exceeds the average DBE participation obtained by other bidders, you may view this, in conjunction with other factors, as evidence of the apparent successful bidder having made good faith efforts.

# Appendix E Small Business Network [SBN] Overview

The Small Business Network is a part of the Bid Express® service that was created to ensure that prime bidders have a centralized online location to find subs - including small and disadvantaged business enterprises (DBEs). It is available for prime bidders to use as part of their Basic Service subscription.

Within the Small Business Network. **Prime Contractors** can:

# 1. Easily select proposals, work types and items:

a. After adding applicable work types, select items that you wish to quote. Enter the sub-quote quantities and add comments, if desired. Adding or removing items and work types can be done quickly. If needed, you can save the sub-quote for completion at a later time.

# 2. Create sub-quotes for the subcontracting community:

- a. Create sub-quotes with ease using the intuitive sub-quote creator. In seven short steps, you can rapidly create a custom sub-quote directed to all subcontractors that bid on the applicable work types. Steps include: provide contact information and sub-quote expiration date, select letting and proposal, add work types and items, specify terms and conditions, upload attachments, and select vendors.
- b. Create a sub-quote to send to subcontractors or suppliers that lists the items in a proposal that you want quoted
- c. Create an unlimited number of sub-quotes for items you want quoted, and optionally mark them as a DBE-preferred request.
- d. Add attachments to sub-quotes.

# 3. View sub-quote requests & responses:

- a. After logging into the Bid Express service, you can quickly review all of your sub-quote requests and all unsolicited sub-quote requests from subcontractors. To simplify the Small Business Network home screen, subquote requests can be hidden with one click if they are not applicable.
- b. View or receive unsolicited sub-quotes that subcontractors have posted, complete with terms, conditions and pricing.

# 4. View Record of Subcontractor Outreach Effort:

- a. For each sub-quote produced, a *Record of Subcontractor Outreach Effort* is generated that shows the response statistics for a particular sub-quote. If accepted by the letting agency, this report may serve as proof of a "Good Faith" effort in reaching out to the DBE community.
- b. Easily locate pre-qualified and certified small and disadvantaged businesses.
- c. Advertise to small and disadvantaged businesses more efficiently and cost effectively.
- d. Document your interactions with subs/DBEs by producing an Outreach Report (may be accepted as proof of DBE outreach at the discretion of each agency).

The Small Business Network is a part of the Bid Express® service that was created to ensure that small businesses have a centralized area to access information about upcoming projects. It can help small businesses learn more about opportunities, compete more effectively, network with other contractors and subcontractors, and win more jobs.

# 1. View and reply to sub-quote requests from primes:

a. After logging into the Bid Express service, you can quickly review all incoming sub-quote requests and all unsolicited sub-quotes created by your company. Receive notifications by selected work type. To simplify on the Small Business Network home screen, sub-quote requests can be filtered by work types relevant to your interests, or hidden with one click if they are not applicable.

# 2. Select items when responding to sub-quote requests from primes:

- a. You have the freedom to choose and price any number of items when responding to a sub-quote request. Quantities can be modified, and per-item comments are also available.
- b. View requests for sub-quotes for work that primes have posted for projects they are bidding, add your pricing, terms, and conditions, and submit completed sub-quotes to the requesting primes.
- c. Add attachments to a sub-quote.

# 3. Create and send unsolicited sub-quotes to specific contractors:

a. Create unsolicited sub-quotes with ease using the intuitive sub-quote creator. In eight short steps, you can rapidly create a custom sub-quote directed at any number of specific vendors of your choosing. Steps include: provide contact information and sub-quote expiration date, select letting and proposal, add work types and items, specify terms and conditions, upload attachments, and select vendors.

# 4. Easily select and price items for unsolicited sub-quotes:

- a. After adding applicable work types, select items that you wish to quote. The extended price calculates automatically, cutting out costly calculation errors. Comments can be provided on a per-item basis as well.
- b. Create an unsolicited sub-quote that lists the items from a proposal that you want to quote, include pricing, terms and conditions, and send it to selected prime/plan holder.
- c. Add attachments to a sub-quote.
- d. Add unsolicited work items to sub-quotes that you are responding to.

# 5. Easy Access to Valuable Information

- a. Receive a confirmation that your sub-quote was opened by a prime.
- b. View Bid Tab Analysis data from past bids, including the high, average and low prices of items.
- c. View important notices and publications from DOT targeted to small and disadvantaged businesses.

# 6. Accessing Small Business Network for WisDOT contracting opportunities

- a. If you are a contractor not yet subscribing to the Bid Express service, go to <a href="www.bidx.com">www.bidx.com</a> and select "Order Bid Express." The Small Business Network is a part of the Bid Express Basic Service.
- DBE firms can request a Bid Express Small Business Network Account at no cost by calling 414-438-4588.

November 2013 ASP-4

# ADDITIONAL SPECIAL PROVISION 4

# **Payment to First-Tier Subcontractors**

Within 10 calendar days of receiving a progress payment for work completed by a subcontractor, pay the subcontractor for that work. The prime contractor may withhold payment to a subcontractor if, within 10 calendar days of receipt of that progress payment, the prime contractor provides written notification to the subcontractor and the department documenting "just cause" for withholding payment.

The prime contractor may also withhold routine retainage from payments due subcontractors.

# **Payment to Lower-Tier Subcontractors**

Ensure that subcontracting agreements at all tiers provide prompt payment rights to lower-tier subcontractors that parallel those granted first-tier subcontractors in this provision.

# **Release of Routine Retainage**

After granting substantial completion the department may reduce the routine retainage withheld from the prime contractor to 75 percent of the original total amount retained.

When the Department sends the semi-final estimate the department may reduce the routine retainage withheld from the prime contractor to 10 percent of the original total amount retained.

Within 30 calendar days of receiving the semi-final estimate from the department, submit written certification that subcontractors at all tiers are paid in full for acceptably completed work and that no routine retainage is being withheld. The department will pay the prime contractor in full and reduce the routine retainage withheld from the prime contractor to zero when the department approves the final estimate.

This special provision does not limit the right of the department, prime contractor, or subcontractors at any tier to withhold payment for work not acceptably completed or work subject to an unresolved contract dispute.

# Additional Special Provision 6 ASP 6 - Modifications to the standard specifications

Make the following revisions to the standard specifications:

#### 104.3 Contractor Notification

Replace the entire text with the following effective with the December 2019 letting:

## 104.3.1 General

(1) Subsection 104.3 specifies the step-by-step communication process to be followed to expedite the resolution of potential contract revisions identified by the contractor. Both contractor actions and department responses are outlined. The contractor's non-compliance with the requirements of 104.3 may constitute a waiver of entitlement to a pay adjustment under 109.4 or a time extension under 108.10. The department and contractor can mutually agree to extend any time frame specified throughout 104.3.

## 104.3.2 Contractor Initial Oral Notification

(1) If required by 104.2, or if the contractor believes that the department's action, the department's lack of action, or some other situation results in or necessitates a contract revision, the contractor must promptly provide oral notification to the project engineer. Upon notification, the project engineer will attempt to resolve the identified issue.

# 104.3.3 Contractor 5-Day Written Statement

(1) If the project engineer has not responded or resolved the identified issue within 5 business days after receipt of initial notification, provide a contractor written statement to the project engineer in the following format:

# Part 1 - Executive Summary (label page 1.1 through page 1.x)

Include a detailed, factual statement of the request for additional compensation and contract time. Include the date the issue was identified, the date initial notification was given to the project engineer, and the dates and specific locations of work involved.

# Part 2 - Contractor's Basis of Entitlement (label page 2.1 through page 2.x)

Include references to relevant contract provisions and a narrative summarizing how the contract provisions support the request for a revision to the original contract.

# Part 3 - Contractor's Request for Damages (label page 3.1 through page 3.x)

When requesting additional compensation, include an itemized list of costs with a narrative supporting the requested amount and explaining how the costs are tied to the requested contract revision.

When requesting additional contract time, include a copy of the schedule that was in effect when the issue occurred and a detailed narrative explaining how the issue impacted controlling items of work. Provide a time impact analysis utilizing base and updated schedules.

If the full extent of either compensation or time is not known at the date of submittal of the contractor 5-Day written statement, provide a brief statement as to why, and include estimated compensation and time.

# Part 4 - Supporting Documentation (label page 4.1 through page 4.x)

Include copies of the following:

- A. Relevant excerpts from specifications, special provisions, plans, change orders, or other contract documents
- B. Communication on the issue, including: letters, e-mails, meeting minutes, etc.
- C. Any other documentation to support or clarify the contractor's position, including: daily work records, cost summary sheets, weigh tickets, test results, sketches, etc.
- (2) With the submittal of the written statement, the contractor may also request a meeting with the region.

# 104.3.4 Region One-Day Written Acknowledgment

(1) Within one business day after the contractor provides the 5-day written statement, the project engineer will provide a region one-day written acknowledgment to the contractor. The project engineer will continue to resolve the issue.

# 104.3.5 Region 5-Day Written Response

(1) Within 5 business days after receiving the contractor 5-day written statement, the project engineer may request specific additional information to allow the project engineer to decide whether item 1 or 2 of 104.3.6(1) applies. The project engineer will state the information needed and date it is to be

received for further review. Submit additional information as an amendment to the contractor 5-day written statement.

# 104.3.6 Region Final Decision

- (1) Within 10 business days after receiving the contractor 5-day written statement or additional information requested in 104.3.5(1), whichever comes last, the region will consider all information and provide a region final decision in writing to the contractor with one or more of the following responses:
  - 1. The region will confirm that the contractor is entitled to a contract revision and a contract change order is necessary as specified in 104.2. The project engineer will give direction concerning the potential change.
  - 2. The region will deny that the contractor is entitled to a contract revision. The project engineer will provide a statement as to why the issue is not a change to the contract. At a minimum, the project engineer will respond to the contractor's issues and refer to the contract to show why the issues are not a change from the original contract.
- (2) If the contractor does not agree with the region's decision the contractor may pursue the issue as a claim as specified in 105.13. Alternatively, if the contractor and department mutually agree, the department will get a third-party advisory opinion according to the department's dispute resolution procedures.
- (3) If a third party reviews the issue, their recommendation is not binding on either party. The region has 10 business days after receipt of the third party's written recommendation to render a decision. If the department fails to respond in writing within those 10 business days or the contractor disagrees with the region's decision, the contractor may pursue the issue as a claim as specified in 105.13.

#### 104.6.1.2.1 General

Replace paragraph one with the following effective with the December 2019 letting:

- (1) Conduct construction operations and provide facilities required to maintain the portion of the project open to the public in a condition that safely and adequately accommodates public traffic. Use barricades, signs, flaggers, and temporary barrier as specified in part VI, of the WMUTCD and ensure that the contractor's use of the right-of-way conforms to 107.9. Throughout the life of the contract, and as the engineer directs, conduct construction operations and provide facilities as follows:
  - Conduct flagging operations conforming to plan details and the department's flagging handbook.
  - Use drums, barricades, and temporary barrier to delineate and shield abrupt drop-offs and other hazards.
  - Furnish, erect, and maintain traffic control devices and facilities conforming to 643.
  - Furnish, erect, and maintain temporary pedestrian devices and facilities conforming to 644.

# 104.6.1.2.2 Flagging

Replace paragraph three with the following effective with the December 2019 letting:

(3) Provide associated advanced warning signs that meet the retroreflective requirements of 637.2.2.2. Provide temporary portable rumble strips from the department's APL installed according to manufacturer's instructions and as specified in the flagging plan details. Provide guidance service through the worksite using pilot vehicles if required.

Replace paragraph five with the following effective with the December 2019 letting:

(5) Flagging is incidental to the contract and includes costs for advance signing, temporary portable rumble strips, and pilot vehicle guidance service.

# 104.8 Rights in the Use of Materials Found on the Project

Replace paragraph two with the following effective with the December 2019 letting:

- (2) Do not excavate or remove material from within the right-of-way that is not within the vertical and horizontal excavation limits the plans show except as follows:
  - If the contract does not identify potential source areas, obtain written authorization from the engineer to use those sources. Complete required environmental documentation and obtain necessary permits. The department will reduce pay by \$1.50 per cubic yard under the Material from Right-of-Way administrative item for material obtained from those areas.
  - If the contract identifies potential source areas that were evaluated and permitted in the original
    environmental document, do not begin excavating in those areas until the engineer allows in writing.
     Additional environmental documentation and environmental permits are not required. The department will
    not reduce pay for material obtained from those areas.

The department may suspend use of these sources if the contractor's operation affects the essential functions or characteristics of the project.

#### 104.10.1 General

Replace paragraph one with the following effective with the December 2019 letting:

- (1) Subsection 104.10 specifies a 2-step process for contractors to follow in submitting a cost reduction incentive (CRI) for modifying the contract in order to reduce direct construction costs computed at contract bid prices. The initial submittal is referred to as a CRI concept and the second submittal is a CRI proposal. The contractor and the department will equally share all savings generated to the contract due to a CRI as specified in 104.10.4.2(1). The department encourages the contractor to submit CRI concepts for the following situations:
  - 1. The contractor generates the original cost savings idea and formulates it into a concept.
  - 2. The department generates the original cost savings idea and obtains the contractor's assistance to formulate the idea into a concept.

# Replace paragraph five with the following effective with the December 2019 letting:

- (5) The department will consider a CRI that changes but does not impair the essential functions or characteristics of the project. These functions or characteristics include, but are not limited to, appearance, service life, economy of operations, ease of maintenance, design, and safety of structures and pavements, construction phasing or procedures, or other contract requirements. The department will not consider a CRI that changes the following:
  - Permanent pavement type.
  - Permanent structural cross section above the subgrade.

# 104.10.2 Submittal and Review of a CRI Concept

Replace paragraphs five and six with the following effective with the December 2019 letting:

- (5) The department may consider a CRI concept that addresses a potential change under 104.2.
- (6) The department will not implement a contractor-initiated CRI concept, or portion of that concept, without sharing the cost savings with the contractor as specified in 104.10.4.2.
- (7) The savings generated by the CRI must be sufficient to warrant its review and processing and offset the level of risk. The department will assess the risk of the CRI relative to departmental design policies and criteria for the project. The department may reject a CRI concept for the following reasons:
  - 1. It requires excessive time or costs for the contractor to develop the CRI proposal.
  - 2. It requires excessive time or costs for review, evaluation, investigation, or implementation.
  - 3. It introduces an inappropriate level of risk.

# 104.10.4.2 Payment for the CRI Work

Replace paragraph one with the following effective with the December 2019 letting:

- (1) The department will pay for completed CRI work as specified for progress payments under 109.6. The department will pay for CRI's under the Cost Reduction Incentive administrative item. When all CRI costs are determined, the department will execute a contract change order that does the following:
  - 1. Adjusts the contract time, interim completion dates, or both.
  - 2. Pays the contractor for the unpaid balance of the CRI work.
  - 3. Pays the contractor 50 percent of the net savings resulting from the CRI, calculated as follows:

## NS = CW - CRW - CC - DC

## Where:

NS = Net Savings

**CW** = The cost of the work required by the original contract that is revised by the CRI. CW is computed at contract bid prices if applicable.

**CRW** = The cost of the revised work, computed at contract bid prices if applicable.

**CC** = The contractor's cost of developing the CRI proposal.

**DC** = The department's cost for investigating, evaluating, and implementing the CRI proposal.

# 105.13 Claims Process for Unresolved Changes

Replace the entire text with the following effective with the December 2019 letting:

# 105.13.1 General

- (1) Before submitting a claim, the department and contractor can mutually agree to have the department get a third-party advisory opinion as specified in 104.3.6.
- (2) The department and contractor can mutually agree to extend any time frame specified throughout 105.13 and can mutually agree to utilize an alternative dispute resolution method at any point before the department renders its final decision.
- (3) The department and contractor share costs related to referral to a dispute review board (DRB) as prescribed in the department's dispute resolution procedures.

# 105.13.2 Notice of Claim

- (1) If the contractor has followed the procedures for revising the contract specified in 104.2 and provided the notification specified in 104.3, but still disagrees with the region, the contractor may pursue the issue as a claim. File a notice of claim with the project engineer concerning the disagreement within 14 calendar days of receiving the region's decision under 104.3.6(1).
- (2) The project engineer may deny the applicable portion of a claim if the contractor does not do the following:
  - 1. File the notice of claim within 14 calendar days as specified in 105.13.2(1).
  - 2. Give the project engineer sufficient access to keep a record of the actual labor, materials, and equipment used to perform the claimed work.
- (3) Upon filing the notice of claim, maintain records as specified for force account statements in 109.4.5. Unless the project engineer issues a suspension, continue to perform the disputed work. The department will continue to make progress payments to the contractor as specified in 109.6.

# 105.13.3 Submission of Claim

- (1) Submit the claim to the project engineer as promptly as possible following the submission of the Notice of Claim, but not later than the end of the time allowed under 109.7 for the contractor to respond in writing to the engineer-issued semi-final estimate. If the contractor does not submit the claim within that response time, the department will deny the claim.
- (2) The department will not accept the submission of a claim until the resolution process in 104.3 has been completed and the contractor makes no further requests to submit updated information that may affect the region's final decision.

# 105.13.4 Content of Claim

- (1) The final contractor written statement under 104.3.3 is considered the content of the claim. If the contractor makes a request to submit updated information that may affect the region's final decision under 104.3.6, submit the updated information as an amendment to the contractor written statement and continue the resolution process in 104.3 before submitting a claim.
- (2) The department may refer the claimant of a false claim to the appropriate authority for criminal prosecution. Certify the claim using the following form:

The undersigned is duly authorized to certify this claim on behalf of (the contractor).

(The contractor) certifies that this claim is made in good faith, that the supporting data are accurate and complete to the best of (the contractor's) knowledge and belief, and that the amount requested accurately reflects the contract adjustment for which (the contractor) believes that the department is liable.

(THE CONTRACTOR)
Ву:
(Name and Title)
Date of Execution:

# 105.13.5 Department Final Decision

- (1) The department will have up to 28 calendar days, from the contractor's submission of the claim, to perform a final review of the claim and conduct all meetings. The department may request, in writing, that the contractor submit additional information related to the claim. Submit that additional information, or notify the department in writing to base its decision on the information previously submitted. Either the contractor or region may request a meeting to present their views. Before the meeting, both parties will agree upon written ground rules for the meeting.
- (2) Upon completion of the 28 calendar days for the department's review and meetings, the department will have up to 21 calendar days to render a written decision. The department will consider written and oral submissions from the contractor and region, and may consider other relevant information in the project records.
- (3) The department will provide the following in its final decision:
  - 1. A concise description of the claim.
  - 2. A clear, contractual basis for its decision that includes a reference to 104.2 on revisions to the contract and as appropriate, specific reference to language regarding the bid items in question.
  - 3. Other facts the department relies on to support its decision.
  - 4. A concise statement of the circumstances surrounding the claim and reasons for its decision. If the department rejects the claim in whole or in part, the department will explain why the claimed work is not a change to the contract work.
  - 5. The amount of money or other relief, if any, the department will grant the contractor.
- (4) If the contractor disagrees with the department's final decision, the contractor may initiate a legal action pursuant to state statutes.

# 106.3.4.2.2.2 Freeze-Thaw Soundness

Replace paragraph one with the following effective with the December 2019 letting:

- (1) Perform freeze-thaw soundness testing according to AASHTO T103 as modified in CMM 8-60.2. Provide freeze/thaw soundness test results based on the fraction retained on the No. 4 sieve as follows:
  - 1. Using virgin crushed stone aggregates produced from limestone/dolomite sources in one or more of the following counties or from out of state:

Brown	Columbia	Crawford	Dane	Dodge
Fond du Lac	Grant	Green	Green Lake	Iowa
Jefferson	Lafayette	Marinette	Oconto	Outagamie
Rock	Shawano	Walworth	Winnebago	

2. Using gravel aggregates produced from pit sources in one or more of the following counties or from out of state:

Dodge Washington Waukesha

# 108.10.3 Excusable Compensable Delays

Replace paragraph two with the following effective with the June 2020 letting:

- (2) The following are compensable delays:
  - 1. A contract change for revised work as specified for extra work under 104.2.2.1, for a differing site condition under 104.2.2.2, or for significant changes in the character of the work under 104.2.2.4.
  - 2. A contract change for an engineer-ordered suspension under 104.2.2.3.
  - 3. The unexpected discovery of human remains, an archaeological find, or historical find consistent with 107.25.
  - 4. The unexpected discovery of a hazardous substance consistent with 107.24.
  - 5. The non-completion of work that utilities or other third parties perform, if the contract specifies a number of days or a completion date for that utility or third-party work. For delays covered under Trans 220 of the Wisconsin administrative code, the engineer will grant a time extension, but the contractor must seek recovery of delay costs from the utility.

# 208.5 Payment

Replace paragraph three with the following effective with the December 2019 letting:

(3) The department will adjust pay for material obtained from within the project right-of-way limits but outside project excavation limits, furnished under 208.2.2, as specified in 104.8.

# 301.2.3 Sampling and Testing

Replace paragraph one with the following effective with the December 2019 letting:

(1) Department and contractor testing shall conform to the following: Sampling<sup>[1]</sup>.....AASHTO T2 Gradation<sup>[7]</sup> AASHTO T27 Wear......AASHTO T96 

<sup>[1]</sup> As modified in CMM 8-60.

# 301.2.4.5 Aggregate Base Physical Properties

Replace paragraph one with the following effective with the December 2019 letting:

(1) Furnish aggregates conforming to the following:

# TABLE 301-2 AGGREGATE BASE PHYSICAL PROPERTIES

PROPERTY	CRUSHED STONE	CRUSHED GRAVEL	CRUSHED CONCRETE	RECLAIMED ASPHALT	REPROCESSED MATERIAL	BLENDED MATERIAL
Gradation AASHTO T27						
dense	305.2.2.1	305.2.2.1	305.2.2.1	305.2.2.2	305.2.2.1	305.2.2.1 <sup>[1]</sup>
open-graded	310.2	310.2	not allowed	not allowed	not allowed	not allowed
Wear AASHTO T96 loss by weight	<=50%	<=50%	note <sup>[2]</sup>		note <sup>[2]</sup>	note <sup>[3]</sup>
Sodium sulfate soundness AASHTO T104 loss by weight						
dense	<=18%	<=18%				note <sup>[3]</sup>
open-graded	<=12%	<=12%	not allowed	not allowed	not allowed	not allowed
Freeze/thaw soundness  AASHTO T103 <sup>[6]</sup> loss by weight						
dense	<=18%	<=18%	note <sup>[2]</sup>			note <sup>[3]</sup>
open-graded	<=18%	<=18%	not allowed	not allowed	not allowed	not allowed
Liquid limit AASHTO T89	<=25	<=25	<=25			note <sup>[3]</sup>
Plasticity AASHTO T90	<=6 <sup>[4]</sup>	<=6 <sup>[4]</sup>	<=6 <sup>[4]</sup>			note <sup>[3]</sup>
Fracture  ASTM D5821 <sup>[6]</sup> min one face by count						
dense	58%	58%	58%		note <sup>[5]</sup>	note <sup>[3]</sup>
open-graded	90%	90%	not allowed	not allowed	not allowed	not allowed

<sup>[1]</sup> The final aggregate blend must conform to the specified gradation.

- LA wear maximum of 50 percent loss, by weight.
- Freeze thaw maximum of 42 percent loss, by weight.

No requirement for material taken from within the project limits. For material supplied from a source outside the project limits:

<sup>[3]</sup> Required as specified for the individual component materials defined in columns 2 - 6 of the table before blending.

<sup>[4]</sup> For base placed between old and new pavements, use crushed stone, crushed gravel, or crushed concrete with a plasticity index of 3 or less.

<sup>[5] &</sup>gt;=75 percent by count of non-asphalt coated particles.

<sup>[6]</sup> as modified in CMM 8-60.

# 450.2.2 Aggregate Sampling and Testing

Replace paragraph one with the following effective with the December 2019 letting:

(1) The department and the contractor will sample and test according to the following methods, except as revised with the engineer's approval:

Sampling aggregates	AASHTO T2
Material finer than No. 200 sieve	AASHTO T11
Sieve analysis of aggregates	AASHTO T27
Mechanical analysis of extracted aggregate	AASHTO T30
Sieve analysis of mineral filler	AASHTO T37
Los Angeles abrasion of coarse aggregate	AASHTO T96
Freeze-thaw soundness of coarse aggregate <sup>[1]</sup>	AASHTO T103
Sodium sulfate soundness of aggregates (R-4, 5 cycles)	AASHTO T104
Extraction of bitumen	AASHTO T164
[1] As modified in CMM 8-60.2.	

# 450.3.2.6.3 Compaction Roller Pattern Determined by Growth Curve

Add 450.3.2.6.3 as a new subsection effective with the December 2019 letting:

# 450.3.2.6.3 Compaction Roller Pattern Determined by Growth Curve

- (1) When specified in 460.3.3.1, compact asphaltic mixture using the roller pattern established during construction of a control strip. Use 2 or more rollers per paver if placing more than 165 tons per hour.
- (2) On the first day of production, construct a control strip under the direct observation of department personnel. After compacting the control strip with a minimum of 3 passes, mark the gauge outline and take a one-minute wet density measurement using a nuclear density gauge in back scatter mode at a single location. Take a density measurement at the same location after each subsequent pass. Continue compacting and testing until the increase in density is less than 1 pcf for 3 consecutive passes. Submit the final roller pattern to the engineer in writing. Once the roller pattern is established do not change the pattern or decrease the number, type, or weight of rollers without the engineer's written approval.
- (3) After establishing the roller pattern, and under the direct observation of the engineer, cut at least one 4-inch diameter or larger core from the control strip density gauge outline. Prepare cores and determine density according to AASHTO T166. Dry cores after testing. Fill core holes and obtain engineer approval before opening to traffic. The department will maintain custody of cores throughout the entire sampling and testing process. The department will label cores, transport cores to testing facilities, witness testing, store dried cores, and provide subsequent verification testing.

# 450.3.2.8 Jointing

Replace paragraph three with the following effective with the December 2019 letting:

(3) Construct notched wedge longitudinal joints for mainline paving of HMA layers 1.75 inches or greater. Extend the wedge beyond the normal lane width as the plans show or as the engineer directs.

Replace paragraph five with the following effective with the December 2019 letting:

- (5) Construct the wedge for each layer using an engineer-approved strike-off device that will provide a uniform slope and will not restrict the main screed. Shape and compact the wedge with a weighted steel side roller wheel or vibratory plate compactor the same width as the wedge. Apply a tack coat to the wedge surface and both notches before placing the adjacent lane.
- (6) Clean longitudinal and transverse joints coated with dust and, if necessary, paint with hot asphaltic material, a cutback, or emulsified asphalt to ensure a tightly bonded, sealed joint.

# 455.2.5 Tack Coat

Replace paragraph one with the following effective with the December 2019 letting:

(1) Under the Tack Coat bid item, furnish type SS-1h, CSS-1h, QS-1h, CQS-1h, or modified emulsified asphalt with an "h" suffix, unless the contract specifies otherwise.

#### 460.2.2.3 Aggregate Gradation Master Range

Replace paragraph one with the following effective with the December 2019 letting:

(1) Ensure that the aggregate blend, including recycled material and mineral filler, conforms to the gradation requirements in table 460-1. The values listed are design limits; production values may exceed those limits.

TABLE 460-1 AGGREGATE GRADATION MASTER RANGE AND VMA REQUIREMENTS

	PERCENT PASSING DESIGNATED SIEVES							
SIEVE	NOMINAL SIZE							
0.272	No. 1	No. 2	No.3	No. 4	No. 5	No. 6	SMA No. 4	SMA No. 5
	(37.5 mm)	(25.0 mm)	(19.0 mm)	(12.5 mm)	(9.5 mm)	(4.75 mm)	(12.5 mm)	(9.5 mm)
50.0-mm	100							
37.5-mm	90 - 100	100						
25.0-mm	90 max	90 - 100	100					
19.0-mm		90 max	90 - 100	100			100	
12.5-mm			90 max	90 - 100	100		90 - 97	100
9.5-mm				90 max	90 - 100	100	58 - 80	90 - 100
4.75-mm					90 max	90 - 100	25 - 35	35 - 45
2.36-mm	15 - 41	19 - 45	23 - 49	28 - 58	32 - 67	90 max	15 - 25	18 - 28
1.18-mm						30 - 55		
0.60-mm							18 max	18 max
0.075-mm	0 - 6.0	1.0 - 7.0	2.0 - 8.0	2.0 - 10.0	2.0 - 10.0	6.0 - 13.0	8.0 - 11.0	8.0 - 12.0
% VMA	11.0 min	12.0 min	13.0 min	14.0 min <sup>[1]</sup>	15.0 min <sup>[2]</sup>	16.0 - 17.5	16.0 min	17.0 min

<sup>[1] 14.5</sup> for LT and MT mixes.

#### 460.2.7 HMA Mixture Design

Replace paragraph one with the following effective with the December 2019 letting:

(1) For each HMA mixture type used under the contract, develop and submit an asphaltic mixture design according to CMM 8-66 and conforming to the requirements of table 460-1 and table 460-2. Ensure that SMA mixture designs adhere to AASHTO R 46 and AASHTO M 325 in addition to the required test procedures outlined in CMM 8-66 table 1 and CMM 8-66 table 2. Determine the specific gravity of fines or super fines used as a mineral filler or additional stabilizer in SMA designs according to AASHTO T 100. The values listed are design limits; production values may exceed those limits. The department will review mixture designs and report the results of that review to the designer according to CMM 8-66.

<sup>[2] 15.5</sup> for LT and MT mixes.

#### **TABLE 460-2 MIXTURE REQUIREMENTS**

Mixture type	LT	MT	HT	SMA
LA Wear (AASHTO T96)				
100 revolutions(max % loss)	13	13	13	13
500 revolutions(max % loss)	50	45	45	35
Soundness (AASHTO T104) (sodium sulfate, max % loss)	12	12	12	12
Freeze/Thaw (AASHTO T103 as modified in CMM 8-60.2) (specified counties, max % loss)	18	18	18	18
Fractured Faces (ASTM D5821 as modified in CMM 860) (one face/2 face, % by count)	65/	75 / 60	98 / 90	100/90
Flat & Elongated (ASTM D4791) (max %, by weight)	5 (5:1 ratio)	5 (5:1 ratio)	5 (5:1 ratio)	20 (3:1 ratio)
Fine Aggregate Angularity (AASHTO T304, method A, min)	40 <sup>[1]</sup>	43 <sup>[1]</sup>	45	45
Sand Equivalency (AASHTO T176, min)	40	40 <sup>[2]</sup>	45	50
Clay Lumps and Friable Particle in Aggregate (AASHTO T112)	<= 1%	<= 1%	<= 1%	<= 1%
Plasticity Index of Material Added to Mix Design as Mineral Filler (AASHTO T89/90)	<= 4	<= 4	<= 4	<= 4
Gyratory Compaction				
Gyrations for Nini	6	7	8	7
Gyrations for Ndes	40	75	100	65
Gyrations for Nmax	60	115	160	100
Air Voids, %Va (%Gmm Ndes)	4.0 (96.0)	4.0 (96.0)	4.0 (96.0)	4.5 (95.5)
% Gmm Nini	<= 91.5 <sup>[3]</sup>	<= 89.0 <sup>[3]</sup>	<= 89.0	
% Gmm Nmax	<= 98.0	<= 98.0	<= 98.0	<= 98.0
Dust to Binder Ratio <sup>[4]</sup> (% passing 0.075/Pbe)	0.6 - 1.2 <sup>[5]</sup>	0.6 - 1.2 <sup>[5]</sup>	0.6 - 1.2 <sup>[5]</sup>	1.2 - 2.0
Voids filled with Binder (VFB or VFA, %)	68 - 80 <sup>[6] [8]</sup>	65 - 75 <sup>[6] [7] [9]</sup>	65 - 75 <sup>[6] [7] [9]</sup>	70 - 80
Tensile Strength Ratio (TSR) (AASHTO T283)[10] [11]				
no antistripping additive	0.75 min	0.75 min	0.75 min	0.80 min
with antistripping additive	0.80 min	0.80 min	0.80 min	0.80 min
Draindown (AASHTO T305) (%)				<= 0.30
Minimum Effective Asphalt Content, Pbe (%)				5.5
-				

<sup>[1]</sup> For No 6 (4.75 mm) nominal maximum size mixes, the specified fine aggregate angularity is 43 for LT and 45 MT mixes.

<sup>[2]</sup> For No 6 (4.75 mm) nominal maximum size mixes, the specified sand equivalency is 43 for MT mixes.

<sup>[3]</sup> The percent maximum density at initial compaction is only a guideline.

<sup>[4]</sup> For a gradation that passes below the boundaries of the caution zone (ref. AASHTO M323), the dust to binder ratio limits are 0.6 - 1.6.

<sup>[5]</sup> For No 6 (4.75 mm) nominal maximum size mixes, the specified dust to binder ratio limits are 1.0 - 2.0 for LT mixes and 1.5 - 2.0 for MT and HT mixes.

<sup>&</sup>lt;sup>[6]</sup> For No. 6 (4.75mm) nominal maximum size mixes, the specified VFB is 67 - 79 percent for LT mixes and 66 - 77 percent for MT and HT mixes.

<sup>&</sup>lt;sup>[7]</sup> For No. 5 (9.5mm) and No. 4 (12.5 mm) nominal maximum size mixtures, the specified VFB range is 70 - 76 percent.

<sup>[8]</sup> For No. 2 (25.0mm) nominal maximum size mixes, the specified VFB lower limit is 67 percent.

#### 460.2.8.2.1.3.1 Contracts with 5000 Tons of Mixture or Greater

Replace paragraph four with the following effective with the December 2019 letting:

(4) Use the test methods identified below, or other methods the engineer approves, to perform the following tests at the frequency indicated:

#### Blended aggregate gradations:

#### Drum plants:

- Field extraction by ignition oven according to AASHTO T308 as modified in CMM 8-36.6.3.6, chemical extraction according to AASHTO T-164 method A or B; or automated extraction according to ASTM D8159 as modified in CMM 8-36.6.3.1. Gradation of resulting aggregate sample determined according to AASHTO T30.
- Belt samples, optional for virgin mixtures, obtained from stopped belt or from the belt discharge using an engineer-approved sampling device and performed according to AASHTO T11 and T27.

#### Batch plants:

 Field extraction by ignition oven according to AASHTO T308 as modified in CMM 8-36.6.3.6, chemical extraction according to AASHTO T-164 method A or B; or automated extraction according to ASTM D8159 as modified in CMM 8-36.6.3.1. Gradation of resulting aggregate sample determined according to AASHTO T30.

#### Asphalt content (AC) in percent:

AC by ignition oven according to AASHTO T308 (CMM 8-36.6.3.6), by chemical extraction according to AASHTO T-164 method A or B; or by automated extraction according to ASTM D8159 as modified in CMM 8-36.6.3.1. Gradation of resulting aggregate sample determined according to AASHTO T30.

Bulk specific gravity of the compacted mixture according to AASHTO T166.

Maximum specific gravity according to AASHTO T209.

Air voids (Va) by calculation according to AASHTO T269.

VMA by calculation according to AASHTO R35.

#### 460.2.8.2.1.4.2 Control Charts

Replace paragraph one with the following effective with the December 2019 letting:

- (1) Maintain standardized control charts at the laboratory. Record contractor test results on the charts the same day as testing. Record data on the standardized control charts as follows:
  - Blended aggregate gradation tests in percent passing. Of the following, plot sieves required in table 460-1: 37.5-mm, 25.0-mm, 19.0-mm, 12.5-mm, 9.5-mm, 4.75-mm, 2.36-mm, 1.18-mm, 0.60-mm, and 0.075-mm.
  - Asphalt material content in percent.
  - Air voids in percent.
  - VMA in percent.
- (2) Plot both the individual test point and the running average of the last 4 data points on each chart. Show QC data in black with the running average in red. Draw the warning limits with a dashed green line and the JMF limits with a dashed red line. The contractor may use computer generated black-and-white printouts with a legend that clearly identifies the specified color-coded components.

<sup>[9]</sup> For No. 1 (37.5mm) nominal maximum size mixes, the specified VFB lower limit is 67 percent.

<sup>[10]</sup> WisDOT eliminates freeze-thaw conditioning cycles from the TSR test procedure.

<sup>[11]</sup> Run TSR at asphalt content corresponding to 3.0% air void regressed design, or 4.5% air void design for SMA, using distilled water for testing.

#### 460.2.8.2.1.5 Control Limits

Replace paragraph one with the following effective with the December 2019 letting:

(1) Conform to the following control limits for the JMF and warning limits based on a running average of the last 4 data points:

Percent passing given sieve:	
37.5-mm +/- 6.0 +/- 4.5	
25.0-mm +/- 6.0 +/- 4.5	
19.0-mm +/- 5.5 +/- 4.0	
12.5-mm +/- 5.5 +/- 4.0	
9.5-mm +/- 5.5 +/- 4.0	
4.75-mm +/- 5.0 +/- 4.0	
2.36-mm +/- 5.0 +/- 4.0	
1.18-mm +/- 4.0 +/- 3.0	
0.60-mm +/- 4.0 +/- 3.0	
0.075-mm +/- 2.0 +/- 1.5	
Asphaltic content in percent - 0.3 - 0.2	
Air voids in percent <sup>[1]</sup> +1.3/-1.0 +1.0/-0.7	
VMA in percent <sup>[2]</sup> - 0.5 - 0.2	

<sup>[1]</sup> For SMA, JMF limits are +/-1.3 and warning limits are +/-1.0.

#### 460.3.2 Thickness

Replace paragraph one with the following effective with the December 2019 letting:

(1) Provide the plan thickness for lower and upper layers limited as follows:

NOMINAL	MINIMUM	MAX LOWER	MAX UPPER	MAX SINGLE
SIZE	LAYER	LAYER	LAYER	LAYER
	THICKNESS	THICKNESS	THICKNESS	THICKNESS[3]
	(in inches)	(in inches)	(in inches)	(in inches)
No. 1 (37.5 mm)	4.5	6	4.5	6
No. 2 (25.0 mm)	3.0	5	4	6
No. 3 (19.0 mm	2.25	4	3	5
No. 4 (12.5 mm) <sup>[1]</sup>	1.75	3[2]	2.5	4
No. 5 (9.5 mm) <sup>[1]</sup>	1.25	3[2]	2	3
No. 6 (4.75 mm)	0.75	1.25	1.25	1.25

<sup>[1]</sup> SMA mixtures use nominal size No. 4 (12.5 mm) or No. 5 (9.5 mm).

<sup>&</sup>lt;sup>[2]</sup> VMA limits are based on requirements for each mix design nominal maximum aggregate size in table 460-1. For No. 6 (4.75mm) mixes, JMF limits are +/- 0.5 and warning limits are +/- 0.2.

<sup>&</sup>lt;sup>[2]</sup> SMA mixtures with nominal sizes of No. 4 (12.5 mm) and No. 5 (9.5 mm) have no maximum lower layer thickness specified.

<sup>[3]</sup> For use on cross-overs and shoulders.

<sup>(2)</sup> Place leveling layers using No. 4 (12.5 mm), No. 5 (9.5 mm), or No. 6 (4.75 mm) mixtures. Leveling layers may be thinner than the minimum lower layer thickness for the mixture used.

<sup>(3)</sup> Place wedging layers as the contract specifies or engineer directs. Wedging layers have no specified minimum or maximum thickness.

#### 460.3.3.1 Minimum Required Density

Replace paragraph one with the following effective with the December 2019 letting:

(1) Compact No. 6 mixtures in lower layers as specified in 450.3.2.6.2 and in upper layers as specified in 450.3.2.6.3. For other HMA mixtures, compact all layers to the density table 460-3 specifies.

<b>TABLE 460-3</b>	MINIMIIM	REQUIRED	DENSITY[1]
I ADLL TUUT		ILLGOUILLD	DEMOIL 1.

The state of the s					
		PERCENT OF TARGET MAXIMUM DENSITY			
LOCATION	LAYER	MIXTURE TYPE			
		LT and MT	HT	SMA <sup>[5]</sup>	
TDAFFIO LANGO	LOWER	93.0 <sup>[3]</sup>	93.0 <sup>[4]</sup>		
TRAFFIC LANES <sup>[2]</sup>	UPPER	93.0	93.0	93.0	
SHOULDERS &	LOWER	91.0	91.0		
APPURTENANCES	UPPER	92.0	92.0	92.0	

<sup>&</sup>lt;sup>[1]</sup> The table values are for average lot density. If any individual density test result falls more than 3.0 percent below the minimum required target maximum density, the engineer will investigate the acceptability of that material according to CMM 8-15.11.

#### 460.3.3.2 Pavement Density Determination

Replace paragraph three with the following effective with the December 2019 letting:

(3) A lot is defined in CMM 8-15 and placed within a single layer for each location and target maximum density category indicated in table 460-3. The lot density is the average of all samples taken for that lot. The department determines the number of tests per lot according to CMM 8-15.

#### 460.5.2.1 General

Replace paragraph six with the following effective with the December 2019 letting:

- (6) If during a QV dispute resolution investigation the department discovers unacceptable mixture defined by one or more of the following:
  - Va less than 2.5 or greater than 6.5 percent for SMA, or for other mixes, less than 1.5 or greater than 5.0 percent.
  - VMA more than 1.0 percent below the minimum or above the maximum specified in table 460-1.
  - AC more than 0.5 % below the JMF target.

Remove and replace the material, or if the engineer allows the mixture to remain in place, the department will pay for the quantity of affected material at 50 percent of the contract price.

<sup>[2]</sup> Includes side roads, crossovers, turn lanes, ramps, parking lanes, bike lanes, and park-and-ride lots as defined by the contract plans.

<sup>[3]</sup> Minimum reduced by 2.0 percent for a lower layer constructed directly on crushed aggregate or recycled base courses.

<sup>[4]</sup> Minimum reduced by 1.0 percent for a lower layer constructed directly on crushed aggregate or recycled base courses.

#### 501.2.5.5 Sampling and Testing

Replace paragraph one with the following effective with the December 2019 letting:

(1) Sample and test aggregates for concrete according to the following:

Sampling aggregates <sup>[1]</sup>	AASHTO T2
Lightweight pieces in aggregate	AASHTO T113
Material finer than No. 200 sieve <sup>[1]</sup>	AASHTO T11
Unit weight of aggregate	AASHTO T19
Organic impurities in sands	AASHTO T21
Sieve analysis of aggregates	AASHTO T27
Effect of organic impurities in fine aggregate	AASHTO T71
Los Angeles abrasion of coarse aggregate	AASHTO T96
Alkali Silica Reactivity of Aggregates	ASTM C1260
Alkali Silica Reactivity of Combinations of Cementitious Materials and Aggregates	ASTM C1567
Freeze-thaw soundness of coarse aggregate <sup>[1]</sup>	AASHTO T103
Sodium sulfate soundness of coarse aggregates (R-4, 5 cycles)	AASHTO T104
Specific gravity and absorption of fine aggregate	AASHTO T84
Specific gravity and absorption of coarse aggregate <sup>[1]</sup>	AASHTO T85
Flat & elongated pieces based on a 3:1 ratio[1]	ASTM D4791
Sampling fresh concrete	AASHTO R60
Making and curing concrete compressive strength test specimens	AASHTO T23
Compressive strength of molded concrete cylinders	AASHTO T22
[1] As modified in CMM 8-60.	

#### 505.2.2 Bar Steel Reinforcement

Replace paragraph one with the following effective with the December 2019 letting:

(1) Conform to AASHTO M31, type S or type W.

#### 505.2.3 High-Strength Bar Steel Reinforcement

Replace paragraph one with the following effective with the December 2019 letting:

(1) Conform to AASHTO M31, grade 60, type S or type W.

#### 505.2.4.1 General

Replace paragraph one with the following effective with the December 2019 letting:

(1) Conform to AASHTO M31, grade 60, type S or type W. Ensure that the coating is applied in a CRSI certified epoxy coating plant. Bend bars that require bending before coating, unless the fabricator can bend the bar without damaging the coating.

#### 505.2.6.1 General

Replace paragraph one with the following effective with the December 2019 letting:

(1) For dowel bars and straight tie bars, there is no requirement for bend tests. Ensure that the bars are the specified diameter and length the plans show.

#### 505.2.6.2.2 Solid Dowel Bars

Replace paragraph one with the following effective with the December 2019 letting:

(1) Furnish coated bars conforming to AASHTO M31 grade 40 or 60. Alternatively the contractor may furnish dowel bars conforming to AASHTO M227 grade 70-80. Coat in a plant certified by the Concrete Reinforcing Steel Institute with a thermosetting epoxy conforming to AASHTO M254, type B.

#### 520.3.7 Deflection Testing

Replace paragraphs three and four with the following effective with the June 2020 letting:

- (3) Test 100 percent of the installed length of pipe 24 inches or greater in diameter. Ensure that the mandrel passes through the entire section in one pass when pulled by hand without using excessive force. If the designated length of pipe fails, the engineer may require additional testing.
- (4) For pipe less than 24 inches in diameter, the engineer will designate at least 10 percent of the installed length of pipe for testing. The mandrel must pass through the entire section in one pass when pulled by hand without using excessive force. If the designated length of pipe fails, engineer may require additional testing.
- (5) Relay or replace pipe that does not pass deflection testing. Retest all relayed or replaced pipe.

#### 608.3.7 Deflection Testing

Replace paragraphs three and four with the following effective with the June 2020 letting:

- (3) Test 100 percent of the installed length of pipe 24 inches or greater in diameter. Ensure that the mandrel passes through the entire section in one pass when pulled by hand without using excessive force. If the designated length of pipe fails, the engineer may require additional testing.
- (4) For pipe less than 24 inches in diameter, the engineer will designate at least 10 percent of the installed length of pipe for testing. The mandrel must pass through the entire section in one pass when pulled by hand without using excessive force. If the designated length of pipe fails, engineer may require additional testing.
- (5) Relay or replace pipe that does not pass deflection testing. Retest all relayed or replaced pipe.

#### 625.3.2 Processing Topsoil or Salvaged Topsoil

Delete paragraph four effective with the December 2019 letting.

#### 701.3.1 General

Replace the entire text with the following effective with the December 2019 letting:

(1) Perform contract required QC tests for samples randomly located according to CMM 8-30. Use the test methods specified in table 701-1.

**TABLE 701-1 TESTING AND CERTIFICATION STANDARDS** 

TEST	TEST STANDARD	MINIMUM REQUIRED CERTIFICATION
	STANDARD	(any one of the certifications listed for each test)
Random Sampling	CMM 8-30.9.2	Transportation Materials Sampling Technician (TMS) Aggregate Technician I (AGGTEC-I) AGGTEC-I Assistant Certified Technician (ACT-AGG) PCC Technician I (PCCTEC-I) PCCTEC-I Assistant Certified Technician (ACT-PCC) Grading Technician I (GRADINGTEC-I) Grading Assistant Certified Technician (ACT-GRADING)
Sampling Aggregates	AASHTO T2 <sup>[1][4]</sup>	TMS, AGGTECT-1, ACT-AGG
Percent passing the No. 200 sieve	AASHTO T11[1]	
Fine and coarse aggregate gradation	AASHTO T27 <sup>[1]</sup>	AGGTEC-I. ACT-AGG
Aggregate moisture content	AASHTO T255 <sup>[1]</sup>	AGG120-1, AC1-AGG
Fractured faces	ASTM D5821 <sup>[1]</sup>	
Liquid limit	AASHTO T89	Aggregate Testing for Transportation Systems (ATTS)
Plasticity index	AASHTO T90 <sup>[3]</sup>	GRADINGTEC-I, or ACT-GRADING
Sampling freshly mixed concrete	AASHTO R60	
Air content of fresh concrete	AASHTO T152 <sup>[2]</sup>	
Air void system of fresh concrete	AASHTO TP118 <sup>[5]</sup>	DOCTEO 4
Concrete slump	AASHTO T119 <sup>[2]</sup>	PCCTEC-1 ACT-PCC
Concrete temperature	ASTM C1064	7.611.60
Making and curing concrete cylinders	AASHTO T23	
Moist curing for concrete cylinders	AASHTO M201	
Concrete compressive strength	AASHTO T22	Concrete Strength Tester (CST)
Concrete flexural strength	AASHTO T97	CST Assistant Certified Technician (ACT-CST)
Profiling	_	PROFILER

<sup>[1]</sup> As modified in CMM 8-60.

#### 715.2.1 General

Replace paragraph five with the following effective with the December 2019 letting:

(5) For new lab-qualified mixes, test the air void system of the proposed concrete mix. Include the SAM number as a part of the mix design submittal.

<sup>[2]</sup> As modified in CMM 8-70.

<sup>[3]</sup> A plasticity check, if required under individual QMP provisions, may be performed by an AGGTEC-I in addition to the certifications listed for liquid limit and plasticity index tests.

<sup>[4]</sup> Plant personnel may operate equipment to obtain samples under the direct observation of a TMS or higher.

<sup>[5]</sup> Consolidate by rodding.

#### 715.3.1.1 General

Replace paragraph two with the following effective with the December 2019 letting:

- (2) Test the air void system at least once per lot and enter the SAM number in the MRS for information only. SAM testing is not required for the following:
  - For lots with less than 4 sublots.
  - High early strength (HES) concrete.
  - Special high early strength (SHES) concrete.
  - Concrete placed under the following bid items:
    - Concrete Pavement Approach Slab
    - Concrete Masonry Culverts
    - Concrete Masonry Retaining Walls
    - Steel Grid Floor Concrete Filled
    - Crash Cushions Permanent
    - Crash Cushions Permanent Low Maintenance
    - Crash Cushions Temporary

#### 730.3.1 General

Replace paragraph three with the following effective with the December 2019 letting:

- (3) Stockpile tests<sup>[1]</sup> can be used for multiple projects. If placement on a project does not begin within 120 calendar days after the date the stockpile sample was obtained, retest the stockpile before placement begins.
  - [1] Replace the stockpile test with an in-place production test for concrete pavement recycled and processed onsite; test on the first day of production.

#### 730.3.2 Contractor QC Testing

Replace paragraph four with the following effective with the December 2019 letting:

(4) Submit test results to the engineer within one business day of obtaining the sample, except any aggregate classification with recycled asphalt may be submitted within two business days.

#### 730.3.4.1 Contractor QC Testing

Replace the entire text with the following effective with the December 2019 letting:

- (1) For small quantity contracts with <= 500 tons, submit 2 production tests or 1 stockpile test. Production tests are valid for 3 years from the date the production sample was obtained. Begin placement within 3 years of the date sampled.
- (2) For small quantity contracts with <= 6000 tons and > 500 tons, do the following:
  - 1. Conduct one QC stockpile test before placement.
  - 2. Submit 2 production tests or conduct 1 loadout test instead of placement tests. Production tests are valid for 3 years from the date the production sample was obtained; the first day of placement must be within 3 years of the date sampled.
  - 3. If the actual quantity placed is more than 6000 tons, on the next day of placement perform one additional random QC test for each 3000 tons of overrun, or fraction thereof.

#### 740.3.2 Contractor QC Testing

Replace paragraph three with the following effective with the December 2019 letting:

- (3) Field-locate the beginning and ending points for each profile run. Measure the profiles of each standard and partial segment. Define primary segments starting at a project terminus and running contiguously along the mainline to the other project terminus. Define segments one wheel path wide and distinguished by length as follows:
  - 1. Standard segments are 500 feet long.
  - 2. Partial segments are less than 500 feet long.

#### **Errata**

#### 104.6.1.2.3 Drop-Off and Hazard Protection

Correct errata by changing 2 inches or greater to greater than 2 inches.

(1) Eliminate vertical drop-offs greater than 2 inches and edge slopes steeper than 3:1 between adjacent lanes open to traffic.

#### 305.3.3.3 Shoulders Adjacent to Asphaltic Pavement or Surfacing

Correct errata by changing 2-inch or more to greater than 2-inch.

(2) If the roadway remains open to through traffic during construction and a greater than 2-inch drop-off occurs within 3 feet or less from the edge of the traveled way, eliminate the drop-off within 48 hours after completing that days paving. Unless the special provisions specify otherwise, provide aggregate shoulder material compacted to a temporary 3:1 or flatter cross slope from the surface of the pavement edge.

#### 501.3.2.2 Concrete Proportions

Correct errata in footnote [8] by allowing either grade 100 or grade 120 slag in C-S concrete.

[8] For grade C-S concrete, use grade 100 or grade 120 slag.

#### 614.3.6 Thrie Beam Structure Approach Retro Fits

Correct errata by deleting the galvanization reference already required under 614.3.1.

(2) Install posts and drill holes into existing thrie beam conforming to 614.3.2.

#### **628.3.7 Mobilizations for Erosion Control**

Correct errata by clarifying that mobilizations for erosion control include proceeding with the work.

(1) Move personnel, equipment, and materials to the project site and promptly proceed with construction of erosion control items at the stages the contract indicates or the engineer directs.

#### **ADDITIONAL SPECIAL PROVISION 7**

- A. Reporting 1<sup>st</sup> Tier and DBE Payments During Construction
  - 1. Comply with reporting requirements specified in the department's Civil Rights Compliance, Contractor's User Manual, Sublets and Payments.
  - 2. Report payments to all DBE firms within 10 calendar days of receipt of a progress payment by the department or a contractor for work performed, materials furnished, or materials stockpiled by a DBE firm. Report the payment as specified in A(1) for all work satisfactorily performed and for all materials furnished or stockpiled.
  - 3. Report payments to all first tier subcontractor relationships within 10 calendar days of receipt of a progress payment by the department for work performed. Report the payment as specified in A(1) for all work satisfactorily performed.
  - 4. All tiers shall report payments as necessary to comply with the DBE payment requirement as specified in A(2).
  - 5. Require all first tier relationships, DBE firms and all other tier relationships necessary to comply with the DBE payment requirement in receipt of a progress payment by contractor to acknowledge receipt of payment as specified in A(1), (2), (3) and (4).
  - 6. All agreements made by a contractor shall include the provisions in A(1), (2), (3), (4) and (5), and shall be binding on all first tier subcontractor relationships and all contractors and subcontractors utilizing DBE firms on the project.
- B. Costs for conforming to this special provision are incidental to the contract.

NOTE: CRCS Prime Contractor payment is currently not automated and will need to be manually loaded into the Civil Rights Compliance System. Copies of prime contractor payments received (check or ACH) will have to be forwarded to <a href="mailto:paul.ndon@dot.wi.gov">paul.ndon@dot.wi.gov</a> within 5 days of payment receipt to be logged manually.

\*\*\*Additionally, for information on Subcontractor Sublet assignments, Subcontractor Payments and Payment Tracking, please refer to the CRCS Payment and Sublets manual at:

 $\underline{https://wisconsindot.gov/Documents/doing-bus/civil-rights/labornwage/crcs-payments-sublets-\underline{manual.pdf}}$ 

# ADDITIONAL SPECIAL PROVISION 9 Electronic Certified Payroll or Labor Data Submittal

(1) Use the department's Civil Rights Compliance System (CRCS) to electronically submit certified payroll reports for contracts with federal funds and labor data for contracts with state funds only. Details are available online through the department's highway construction contractor information (HCCI) site on the Labor, Wages, and EEO Information page at:

https://wisconsindot.gov/Pages/doing-bus/civil-rights/labornwage/default.aspx

- (2) Ensure that all tiers of subcontractors, including all trucking firms, either submit their weekly certified payroll reports (contracts with federal funds) or labor data (contracts with state funds only) electronically through CRCS. These payrolls or labor data are due within seven calendar days following the close of the payroll period. Every firm providing physical labor towards completing the project is a subcontractor under this special provision.
- (3) Upon receipt of contract execution, promptly make all affected firms aware of the requirements under this special provision and arrange for them to receive CRCS training as they are about to begin their submittals. The department will provide training either in a classroom setting at one of our regional offices or by telephone. Contact Paul Ndon at (414) 438-4584 to schedule the training.
- (4) The department will reject all paper submittals for information required under this special provision. All costs for conforming to this special provision are incidental to the contract.
- (5) Firms wishing to export payroll/labor data from their computer system into CRCS should have their payroll coordinator contact Paul Ndon at <a href="mailto:paul.ndon@dot.wi.gov">paul.ndon@dot.wi.gov</a>. Not every contractor's payroll system is capable of producing export files. For details, see Section 4.8 CPR Auto Submit (Data Mapping) on pages 49-50; 66-71 of the CRCS Payroll Manual at:

https://wisconsindot.gov/Documents/doing-bus/civil-rights/labornwage/crcs-payroll-manual.pdf

## REQUIRED CONTRACT PROVISIONS FEDERAL-AID CONSTRUCTION CONTRACTS

- I. General
- II. Nondiscrimination
- III. Nonsegregated Facilities
- IV. Davis-Bacon and Related Act Provisions
- Contract Work Hours and Safety Standards Act Provisions
- VI. Subletting or Assigning the Contract
- VII. Safety: Accident Prevention
- VIII. False Statements Concerning Highway Projects
- IX. Implementation of Clean Air Act and Federal Water Pollution Control Act
- Compliance with Governmentwide Suspension and Debarment Requirements
- Certification Regarding Use of Contract Funds for Lobbying

#### **ATTACHMENTS**

A. Employment and Materials Preference for Appalachian Development Highway System or Appalachian Local Access Road Contracts (included in Appalachian contracts only)

#### I. GENERAL

1. Form FHWA-1273 must be physically incorporated in each construction contract funded under Title 23 (excluding emergency contracts solely intended for debris removal). The contractor (or subcontractor) must insert this form in each subcontract and further require its inclusion in all lower tier subcontracts (excluding purchase orders, rental agreements and other agreements for supplies or services).

The applicable requirements of Form FHWA-1273 are incorporated by reference for work done under any purchase order, rental agreement or agreement for other services. The prime contractor shall be responsible for compliance by any subcontractor, lower-tier subcontractor or service provider.

Form FHWA-1273 must be included in all Federal-aid designbuild contracts, in all subcontracts and in lower tier subcontracts (excluding subcontracts for design services, purchase orders, rental agreements and other agreements for supplies or services). The design-builder shall be responsible for compliance by any subcontractor, lower-tier subcontractor or service provider.

Contracting agencies may reference Form FHWA-1273 in bid proposal or request for proposal documents, however, the Form FHWA-1273 must be physically incorporated (not referenced) in all contracts, subcontracts and lower-tier subcontracts (excluding purchase orders, rental agreements and other agreements for supplies or services related to a construction contract).

2. Subject to the applicability criteria noted in the following sections, these contract provisions shall apply to all work performed on the contract by the contractor's own organization and with the assistance of workers under the contractor's immediate superintendence and to all work performed on the contract by piecework, station work, or by subcontract.

- 3. A breach of any of the stipulations contained in these Required Contract Provisions may be sufficient grounds for withholding of progress payments, withholding of final payment, termination of the contract, suspension / debarment or any other action determined to be appropriate by the contracting agency and FHWA.
- 4. Selection of Labor: During the performance of this contract, the contractor shall not use convict labor for any purpose within the limits of a construction project on a Federal-aid highway unless it is labor performed by convicts who are on parole, supervised release, or probation. The term Federal-aid highway does not include roadways functionally classified as local roads or rural minor collectors.

#### II. NONDISCRIMINATION

The provisions of this section related to 23 CFR Part 230 are applicable to all Federal-aid construction contracts and to all related construction subcontracts of \$10,000 or more. The provisions of 23 CFR Part 230 are not applicable to material supply, engineering, or architectural service contracts.

In addition, the contractor and all subcontractors must comply with the following policies: Executive Order 11246, 41 CFR 60, 29 CFR 1625-1627, Title 23 USC Section 140, the Rehabilitation Act of 1973, as amended (29 USC 794), Title VI of the Civil Rights Act of 1964, as amended, and related regulations including 49 CFR Parts 21, 26 and 27; and 23 CFR Parts 200, 230, and 633.

The contractor and all subcontractors must comply with: the requirements of the Equal Opportunity Clause in 41 CFR 60-1.4(b) and, for all construction contracts exceeding \$10,000, the Standard Federal Equal Employment Opportunity Construction Contract Specifications in 41 CFR 60-4.3.

Note: The U.S. Department of Labor has exclusive authority to determine compliance with Executive Order 11246 and the policies of the Secretary of Labor including 41 CFR 60, and 29 CFR 1625-1627. The contracting agency and the FHWA have the authority and the responsibility to ensure compliance with Title 23 USC Section 140, the Rehabilitation Act of 1973, as amended (29 USC 794), and Title VI of the Civil Rights Act of 1964, as amended, and related regulations including 49 CFR Parts 21, 26 and 27; and 23 CFR Parts 200, 230, and 633.

The following provision is adopted from 23 CFR 230, Appendix A, with appropriate revisions to conform to the U.S. Department of Labor (US DOL) and FHWA requirements.

1. Equal Employment Opportunity: Equal employment opportunity (EEO) requirements not to discriminate and to take affirmative action to assure equal opportunity as set forth under laws, executive orders, rules, regulations (28 CFR 35, 29 CFR 1630, 29 CFR 1625-1627, 41 CFR 60 and 49 CFR 27) and orders of the Secretary of Labor as modified by the provisions prescribed herein, and imposed pursuant to 23 U.S.C. 140 shall constitute the EEO and specific affirmative action standards for the contractor's project activities under

this contract. The provisions of the Americans with Disabilities Act of 1990 (42 U.S.C. 12101 et seq.) set forth under 28 CFR 35 and 29 CFR 1630 are incorporated by reference in this contract. In the execution of this contract, the contractor agrees to comply with the following minimum specific requirement activities of EEO:

- a. The contractor will work with the contracting agency and the Federal Government to ensure that it has made every good faith effort to provide equal opportunity with respect to all of its terms and conditions of employment and in their review of activities under the contract.
- b. The contractor will accept as its operating policy the following statement:

"It is the policy of this Company to assure that applicants are employed, and that employees are treated during employment, without regard to their race, religion, sex, color, national origin, age or disability. Such action shall include: employment, upgrading, demotion, or transfer; recruitment or recruitment advertising; layoff or termination; rates of pay or other forms of compensation; and selection for training, including apprenticeship, pre-apprenticeship, and/or on-the-job training."

- 2. EEO Officer: The contractor will designate and make known to the contracting officers an EEO Officer who will have the responsibility for and must be capable of effectively administering and promoting an active EEO program and who must be assigned adequate authority and responsibility to do so.
- 3. Dissemination of Policy: All members of the contractor's staff who are authorized to hire, supervise, promote, and discharge employees, or who recommend such action, or who are substantially involved in such action, will be made fully cognizant of, and will implement, the contractor's EEO policy and contractual responsibilities to provide EEO in each grade and classification of employment. To ensure that the above agreement will be met, the following actions will be taken as a minimum:
- a. Periodic meetings of supervisory and personnel office employees will be conducted before the start of work and then not less often than once every six months, at which time the contractor's EEO policy and its implementation will be reviewed and explained. The meetings will be conducted by the EEO Officer.
- b. All new supervisory or personnel office employees will be given a thorough indoctrination by the EEO Officer, covering all major aspects of the contractor's EEO obligations within thirty days following their reporting for duty with the contractor.
- c. All personnel who are engaged in direct recruitment for the project will be instructed by the EEO Officer in the contractor's procedures for locating and hiring minorities and women.
- d. Notices and posters setting forth the contractor's EEO policy will be placed in areas readily accessible to employees, applicants for employment and potential employees.
- e. The contractor's EEO policy and the procedures to implement such policy will be brought to the attention of employees by means of meetings, employee handbooks, or other appropriate means.

- **4. Recruitment:** When advertising for employees, the contractor will include in all advertisements for employees the notation: "An Equal Opportunity Employer." All such advertisements will be placed in publications having a large circulation among minorities and women in the area from which the project work force would normally be derived.
- a. The contractor will, unless precluded by a valid bargaining agreement, conduct systematic and direct recruitment through public and private employee referral sources likely to yield qualified minorities and women. To meet this requirement, the contractor will identify sources of potential minority group employees, and establish with such identified sources procedures whereby minority and women applicants may be referred to the contractor for employment consideration.
- b. In the event the contractor has a valid bargaining agreement providing for exclusive hiring hall referrals, the contractor is expected to observe the provisions of that agreement to the extent that the system meets the contractor's compliance with EEO contract provisions. Where implementation of such an agreement has the effect of discriminating against minorities or women, or obligates the contractor to do the same, such implementation violates Federal nondiscrimination provisions.
- c. The contractor will encourage its present employees to refer minorities and women as applicants for employment. Information and procedures with regard to referring such applicants will be discussed with employees.
- **5. Personnel Actions:** Wages, working conditions, and employee benefits shall be established and administered, and personnel actions of every type, including hiring, upgrading, promotion, transfer, demotion, layoff, and termination, shall be taken without regard to race, color, religion, sex, national origin, age or disability. The following procedures shall be followed:
- a. The contractor will conduct periodic inspections of project sites to insure that working conditions and employee facilities do not indicate discriminatory treatment of project site personnel.
- b. The contractor will periodically evaluate the spread of wages paid within each classification to determine any evidence of discriminatory wage practices.
- c. The contractor will periodically review selected personnel actions in depth to determine whether there is evidence of discrimination. Where evidence is found, the contractor will promptly take corrective action. If the review indicates that the discrimination may extend beyond the actions reviewed, such corrective action shall include all affected persons.
- d. The contractor will promptly investigate all complaints of alleged discrimination made to the contractor in connection with its obligations under this contract, will attempt to resolve such complaints, and will take appropriate corrective action within a reasonable time. If the investigation indicates that the discrimination may affect persons other than the complainant, such corrective action shall include such other persons. Upon completion of each investigation, the contractor will inform every complainant of all of their avenues of appeal.

#### 6. Training and Promotion:

a. The contractor will assist in locating, qualifying, and increasing the skills of minorities and women who are

applicants for employment or current employees. Such efforts should be aimed at developing full journey level status employees in the type of trade or job classification involved.

- b. Consistent with the contractor's work force requirements and as permissible under Federal and State regulations, the contractor shall make full use of training programs, i.e., apprenticeship, and on-the-job training programs for the geographical area of contract performance. In the event a special provision for training is provided under this contract, this subparagraph will be superseded as indicated in the special provision. The contracting agency may reserve training positions for persons who receive welfare assistance in accordance with 23 U.S.C. 140(a).
- c. The contractor will advise employees and applicants for employment of available training programs and entrance requirements for each.
- d. The contractor will periodically review the training and promotion potential of employees who are minorities and women and will encourage eligible employees to apply for such training and promotion.
- 7. Unions: If the contractor relies in whole or in part upon unions as a source of employees, the contractor will use good faith efforts to obtain the cooperation of such unions to increase opportunities for minorities and women. Actions by the contractor, either directly or through a contractor's association acting as agent, will include the procedures set forth below:
- a. The contractor will use good faith efforts to develop, in cooperation with the unions, joint training programs aimed toward qualifying more minorities and women for membership in the unions and increasing the skills of minorities and women so that they may qualify for higher paying employment.
- b. The contractor will use good faith efforts to incorporate an EEO clause into each union agreement to the end that such union will be contractually bound to refer applicants without regard to their race, color, religion, sex, national origin, age or disability.
- c. The contractor is to obtain information as to the referral practices and policies of the labor union except that to the extent such information is within the exclusive possession of the labor union and such labor union refuses to furnish such information to the contractor, the contractor shall so certify to the contracting agency and shall set forth what efforts have been made to obtain such information.
- d. In the event the union is unable to provide the contractor with a reasonable flow of referrals within the time limit set forth in the collective bargaining agreement, the contractor will, through independent recruitment efforts, fill the employment vacancies without regard to race, color, religion, sex, national origin, age or disability; making full efforts to obtain qualified and/or qualifiable minorities and women. The failure of a union to provide sufficient referrals (even though it is obligated to provide exclusive referrals under the terms of a collective bargaining agreement) does not relieve the contractor from the requirements of this paragraph. In the event the union referral practice prevents the contractor from meeting the obligations pursuant to Executive Order 11246, as amended, and these special provisions, such contractor shall immediately notify the contracting agency.
- 8. Reasonable Accommodation for Applicants / Employees with Disabilities: The contractor must be familiar

with the requirements for and comply with the Americans with Disabilities Act and all rules and regulations established there under. Employers must provide reasonable accommodation in all employment activities unless to do so would cause an undue hardship.

- 9. Selection of Subcontractors, Procurement of Materials and Leasing of Equipment: The contractor shall not discriminate on the grounds of race, color, religion, sex, national origin, age or disability in the selection and retention of subcontractors, including procurement of materials and leases of equipment. The contractor shall take all necessary and reasonable steps to ensure nondiscrimination in the administration of this contract.
- The contractor shall notify all potential subcontractors and suppliers and lessors of their EEO obligations under this contract.
- b. The contractor will use good faith efforts to ensure subcontractor compliance with their EEO obligations.

#### 10. Assurance Required by 49 CFR 26.13(b):

- a. The requirements of 49 CFR Part 26 and the State DOT's U.S. DOT-approved DBE program are incorporated by reference.
- b. The contractor or subcontractor shall not discriminate on the basis of race, color, national origin, or sex in the performance of this contract. The contractor shall carry out applicable requirements of 49 CFR Part 26 in the award and administration of DOT-assisted contracts. Failure by the contractor to carry out these requirements is a material breach of this contract, which may result in the termination of this contract or such other remedy as the contracting agency deems appropriate.
- 11. Records and Reports: The contractor shall keep such records as necessary to document compliance with the EEO requirements. Such records shall be retained for a period of three years following the date of the final payment to the contractor for all contract work and shall be available at reasonable times and places for inspection by authorized representatives of the contracting agency and the FHWA.
- a. The records kept by the contractor shall document the following:
- (1) The number and work hours of minority and nonminority group members and women employed in each work classification on the project;
  - (2) The progress and efforts being made in cooperation with unions, when applicable, to increase employment opportunities for minorities and women; and
  - (3) The progress and efforts being made in locating, hiring, training, qualifying, and upgrading minorities and women;
- b. The contractors and subcontractors will submit an annual report to the contracting agency each July for the duration of the project, indicating the number of minority, women, and non-minority group employees currently engaged in each work classification required by the contract work. This information is to be reported on <a href="Form FHWA-1391">Form FHWA-1391</a>. The staffing data should represent the project work force on board in all or any part of the last payroll period preceding the end of July. If on-the-job training is being required by special provision, the contractor

will be required to collect and report training data. The employment data should reflect the work force on board during all or any part of the last payroll period preceding the end of July.

#### **III. NONSEGREGATED FACILITIES**

This provision is applicable to all Federal-aid construction contracts and to all related construction subcontracts of \$10,000 or more.

The contractor must ensure that facilities provided for employees are provided in such a manner that segregation on the basis of race, color, religion, sex, or national origin cannot result. The contractor may neither require such segregated use by written or oral policies nor tolerate such use by employee custom. The contractor's obligation extends further to ensure that its employees are not assigned to perform their services at any location, under the contractor's control, where the facilities are segregated. The term "facilities" includes waiting rooms, work areas, restaurants and other eating areas, time clocks, restrooms, washrooms, locker rooms, and other storage or dressing areas, parking lots, drinking fountains, recreation or entertainment areas, transportation, and housing provided for employees. The contractor shall provide separate or single-user restrooms and necessary dressing or sleeping areas to assure privacy between sexes.

#### IV. DAVIS-BACON AND RELATED ACT PROVISIONS

This section is applicable to all Federal-aid construction projects exceeding \$2,000 and to all related subcontracts and lower-tier subcontracts (regardless of subcontract size). The requirements apply to all projects located within the right-of-way of a roadway that is functionally classified as Federal-aid highway. This excludes roadways functionally classified as local roads or rural minor collectors, which are exempt. Contracting agencies may elect to apply these requirements to other projects.

The following provisions are from the U.S. Department of Labor regulations in 29 CFR 5.5 "Contract provisions and related matters" with minor revisions to conform to the FHWA-1273 format and FHWA program requirements.

#### 1. Minimum wages

a. All laborers and mechanics employed or working upon the site of the work, will be paid unconditionally and not less often than once a week, and without subsequent deduction or rebate on any account (except such payroll deductions as are permitted by regulations issued by the Secretary of Labor under the Copeland Act (29 CFR part 3)), the full amount of wages and bona fide fringe benefits (or cash equivalents thereof) due at time of payment computed at rates not less than those contained in the wage determination of the Secretary of Labor which is attached hereto and made a part hereof, regardless of any contractual relationship which may be alleged to exist between the contractor and such laborers and mechanics.

Contributions made or costs reasonably anticipated for bona fide fringe benefits under section 1(b)(2) of the Davis-Bacon Act on behalf of laborers or mechanics are considered wages paid to such laborers or mechanics, subject to the provisions

of paragraph 1.d. of this section; also, regular contributions made or costs incurred for more than a weekly period (but not less often than quarterly) under plans, funds, or programs which cover the particular weekly period, are deemed to be constructively made or incurred during such weekly period. Such laborers and mechanics shall be paid the appropriate wage rate and fringe benefits on the wage determination for the classification of work actually performed, without regard to skill, except as provided in 29 CFR 5.5(a)(4). Laborers or mechanics performing work in more than one classification may be compensated at the rate specified for each classification for the time actually worked therein: Provided, That the employer's payroll records accurately set forth the time spent in each classification in which work is performed. The wage determination (including any additional classification and wage rates conformed under paragraph 1.b. of this section) and the Davis-Bacon poster (WH-1321) shall be posted at all times by the contractor and its subcontractors at the site of the work in a prominent and accessible place where it can be easily seen by the workers.

- b.(1) The contracting officer shall require that any class of laborers or mechanics, including helpers, which is not listed in the wage determination and which is to be employed under the contract shall be classified in conformance with the wage determination. The contracting officer shall approve an additional classification and wage rate and fringe benefits therefore only when the following criteria have been met:
  - (i) The work to be performed by the classification requested is not performed by a classification in the wage determination; and
  - (ii) The classification is utilized in the area by the construction industry; and
  - (iii) The proposed wage rate, including any bona fide fringe benefits, bears a reasonable relationship to the wage rates contained in the wage determination.
  - (2) If the contractor and the laborers and mechanics to be employed in the classification (if known), or their representatives, and the contracting officer agree on the classification and wage rate (including the amount designated for fringe benefits where appropriate), a report of the action taken shall be sent by the contracting officer to the Administrator of the Wage and Hour Division, Employment Standards Administration, U.S. Department of Labor, Washington, DC 20210. The Administrator, or an authorized representative, will approve, modify, or disapprove every additional classification action within 30 days of receipt and so advise the contracting officer or will notify the contracting officer within the 30-day period that additional time is necessary.
  - (3) In the event the contractor, the laborers or mechanics to be employed in the classification or their representatives, and the contracting officer do not agree on the proposed classification and wage rate (including the amount designated for fringe benefits, where appropriate), the contracting officer shall refer the questions, including the views of all interested parties and the recommendation of the contracting officer, to the Wage and Hour Administrator for determination. The Wage and Hour Administrator, or an authorized representative, will issue a determination within 30 days of receipt and so advise the contracting officer or

will notify the contracting officer within the 30-day period that additional time is necessary.

- (4) The wage rate (including fringe benefits where appropriate) determined pursuant to paragraphs 1.b.(2) or 1.b.(3) of this section, shall be paid to all workers performing work in the classification under this contract from the first day on which work is performed in the classification.
- c. Whenever the minimum wage rate prescribed in the contract for a class of laborers or mechanics includes a fringe benefit which is not expressed as an hourly rate, the contractor shall either pay the benefit as stated in the wage determination or shall pay another bona fide fringe benefit or an hourly cash equivalent thereof.
- d. If the contractor does not make payments to a trustee or other third person, the contractor may consider as part of the wages of any laborer or mechanic the amount of any costs reasonably anticipated in providing bona fide fringe benefits under a plan or program, Provided, That the Secretary of Labor has found, upon the written request of the contractor, that the applicable standards of the Davis-Bacon Act have been met. The Secretary of Labor may require the contractor to set aside in a separate account assets for the meeting of obligations under the plan or program.

#### 2. Withholding

The contracting agency shall upon its own action or upon written request of an authorized representative of the Department of Labor, withhold or cause to be withheld from the contractor under this contract, or any other Federal contract with the same prime contractor, or any other federallyassisted contract subject to Davis-Bacon prevailing wage requirements, which is held by the same prime contractor, so much of the accrued payments or advances as may be considered necessary to pay laborers and mechanics, including apprentices, trainees, and helpers, employed by the contractor or any subcontractor the full amount of wages required by the contract. In the event of failure to pay any laborer or mechanic, including any apprentice, trainee, or helper, employed or working on the site of the work, all or part of the wages required by the contract, the contracting agency may, after written notice to the contractor, take such action as may be necessary to cause the suspension of any further payment, advance, or guarantee of funds until such violations have ceased.

#### 3. Payrolls and basic records

a. Payrolls and basic records relating thereto shall be maintained by the contractor during the course of the work and preserved for a period of three years thereafter for all laborers and mechanics working at the site of the work. Such records shall contain the name, address, and social security number of each such worker, his or her correct classification, hourly rates of wages paid (including rates of contributions or costs anticipated for bona fide fringe benefits or cash equivalents thereof of the types described in section 1(b)(2)(B) of the Davis-Bacon Act), daily and weekly number of hours worked, deductions made and actual wages paid. Whenever the Secretary of Labor has found under 29 CFR 5.5(a)(1)(iv) that the wages of any laborer or mechanic include the amount of any costs reasonably anticipated in providing benefits under a plan or program described in section 1(b)(2)(B) of the Davis-

Bacon Act, the contractor shall maintain records which show that the commitment to provide such benefits is enforceable, that the plan or program is financially responsible, and that the plan or program has been communicated in writing to the laborers or mechanics affected, and records which show the costs anticipated or the actual cost incurred in providing such benefits. Contractors employing apprentices or trainees under approved programs shall maintain written evidence of the registration of apprenticeship programs and certification of trainee programs, the registration of the apprentices and trainees, and the ratios and wage rates prescribed in the applicable programs.

- b.(1) The contractor shall submit weekly for each week in which any contract work is performed a copy of all payrolls to the contracting agency. The payrolls submitted shall set out accurately and completely all of the information required to be maintained under 29 CFR 5.5(a)(3)(i), except that full social security numbers and home addresses shall not be included on weekly transmittals. Instead the payrolls shall only need to include an individually identifying number for each employee ( e.g., the last four digits of the employee's social security number). The required weekly payroll information may be submitted in any form desired. Optional Form WH-347 is available for this purpose from the Wage and Hour Division Web site at http://www.dol.gov/esa/whd/forms/wh347instr.htm or its successor site. The prime contractor is responsible for the submission of copies of payrolls by all subcontractors. Contractors and subcontractors shall maintain the full social security number and current address of each covered worker, and shall provide them upon request to the contracting agency for transmission to the State DOT, the FHWA or the Wage and Hour Division of the Department of Labor for purposes of an investigation or audit of compliance with prevailing wage requirements. It is not a violation of this section for a prime contractor to require a subcontractor to provide addresses and social security numbers to the prime contractor for its own records, without weekly submission to the contracting agency..
- (2) Each payroll submitted shall be accompanied by a "Statement of Compliance," signed by the contractor or subcontractor or his or her agent who pays or supervises the payment of the persons employed under the contract and shall certify the following:
  - (i) That the payroll for the payroll period contains the information required to be provided under §5.5 (a)(3)(ii) of Regulations, 29 CFR part 5, the appropriate information is being maintained under §5.5 (a)(3)(i) of Regulations, 29 CFR part 5, and that such information is correct and complete;
  - (ii) That each laborer or mechanic (including each helper, apprentice, and trainee) employed on the contract during the payroll period has been paid the full weekly wages earned, without rebate, either directly or indirectly, and that no deductions have been made either directly or indirectly from the full wages earned, other than permissible deductions as set forth in Regulations, 29 CFR part 3;
  - (iii) That each laborer or mechanic has been paid not less than the applicable wage rates and fringe benefits or cash equivalents for the classification of work performed, as specified in the applicable wage determination incorporated into the contract.

- (3) The weekly submission of a properly executed certification set forth on the reverse side of Optional Form WH–347 shall satisfy the requirement for submission of the "Statement of Compliance" required by paragraph 3.b.(2) of this section.
- (4) The falsification of any of the above certifications may subject the contractor or subcontractor to civil or criminal prosecution under section 1001 of title 18 and section 231 of title 31 of the United States Code.
- c. The contractor or subcontractor shall make the records required under paragraph 3.a. of this section available for inspection, copying, or transcription by authorized representatives of the contracting agency, the State DOT, the FHWA, or the Department of Labor, and shall permit such representatives to interview employees during working hours on the job. If the contractor or subcontractor fails to submit the required records or to make them available, the FHWA may, after written notice to the contractor, the contracting agency or the State DOT, take such action as may be necessary to cause the suspension of any further payment, advance, or guarantee of funds. Furthermore, failure to submit the required records upon request or to make such records available may be grounds for debarment action pursuant to 29 CFR 5.12.

#### 4. Apprentices and trainees

a. Apprentices (programs of the USDOL).

Apprentices will be permitted to work at less than the predetermined rate for the work they performed when they are employed pursuant to and individually registered in a bona fide apprenticeship program registered with the U.S. Department of Labor, Employment and Training Administration, Office of Apprenticeship Training, Employer and Labor Services, or with a State Apprenticeship Agency recognized by the Office, or if a person is employed in his or her first 90 days of probationary employment as an apprentice in such an apprenticeship program, who is not individually registered in the program, but who has been certified by the Office of Apprenticeship Training, Employer and Labor Services or a State Apprenticeship Agency (where appropriate) to be eligible for probationary employment as an apprentice.

The allowable ratio of apprentices to journeymen on the job site in any craft classification shall not be greater than the ratio permitted to the contractor as to the entire work force under the registered program. Any worker listed on a payroll at an apprentice wage rate, who is not registered or otherwise employed as stated above, shall be paid not less than the applicable wage rate on the wage determination for the classification of work actually performed. In addition, any apprentice performing work on the job site in excess of the ratio permitted under the registered program shall be paid not less than the applicable wage rate on the wage determination for the work actually performed. Where a contractor is performing construction on a project in a locality other than that in which its program is registered, the ratios and wage rates (expressed in percentages of the journeyman's hourly rate) specified in the contractor's or subcontractor's registered program shall be observed.

Every apprentice must be paid at not less than the rate specified in the registered program for the apprentice's level of progress, expressed as a percentage of the journeymen hourly rate specified in the applicable wage determination. Apprentices shall be paid fringe benefits in accordance with the provisions of the apprenticeship program. If the apprenticeship program does not specify fringe benefits, apprentices must be paid the full amount of fringe benefits listed on the wage determination for the applicable classification. If the Administrator determines that a different practice prevails for the applicable apprentice classification, fringes shall be paid in accordance with that determination.

In the event the Office of Apprenticeship Training, Employer and Labor Services, or a State Apprenticeship Agency recognized by the Office, withdraws approval of an apprenticeship program, the contractor will no longer be permitted to utilize apprentices at less than the applicable predetermined rate for the work performed until an acceptable program is approved.

b. Trainees (programs of the USDOL).

Except as provided in 29 CFR 5.16, trainees will not be permitted to work at less than the predetermined rate for the work performed unless they are employed pursuant to and individually registered in a program which has received prior approval, evidenced by formal certification by the U.S. Department of Labor, Employment and Training Administration.

The ratio of trainees to journeymen on the job site shall not be greater than permitted under the plan approved by the Employment and Training Administration.

Every trainee must be paid at not less than the rate specified in the approved program for the trainee's level of progress, expressed as a percentage of the journeyman hourly rate specified in the applicable wage determination. Trainees shall be paid fringe benefits in accordance with the provisions of the trainee program. If the trainee program does not mention fringe benefits, trainees shall be paid the full amount of fringe benefits listed on the wage determination unless the Administrator of the Wage and Hour Division determines that there is an apprenticeship program associated with the corresponding journeyman wage rate on the wage determination which provides for less than full fringe benefits for apprentices. Any employee listed on the payroll at a trainee rate who is not registered and participating in a training plan approved by the Employment and Training Administration shall be paid not less than the applicable wage rate on the wage determination for the classification of work actually performed. In addition, any trainee performing work on the job site in excess of the ratio permitted under the registered program shall be paid not less than the applicable wage rate on the wage determination for the work actually performed.

In the event the Employment and Training Administration withdraws approval of a training program, the contractor will no longer be permitted to utilize trainees at less than the applicable predetermined rate for the work performed until an acceptable program is approved.

c. Equal employment opportunity. The utilization of apprentices, trainees and journeymen under this part shall be in conformity with the equal employment opportunity requirements of Executive Order 11246, as amended, and 29 CFR part 30.

d. Apprentices and Trainees (programs of the U.S. DOT).

Apprentices and trainees working under apprenticeship and skill training programs which have been certified by the Secretary of Transportation as promoting EEO in connection with Federal-aid highway construction programs are not subject to the requirements of paragraph 4 of this Section IV. The straight time hourly wage rates for apprentices and trainees under such programs will be established by the particular programs. The ratio of apprentices and trainees to journeymen shall not be greater than permitted by the terms of the particular program.

- **5. Compliance with Copeland Act requirements.** The contractor shall comply with the requirements of 29 CFR part 3, which are incorporated by reference in this contract.
- **6. Subcontracts.** The contractor or subcontractor shall insert Form FHWA-1273 in any subcontracts and also require the subcontractors to include Form FHWA-1273 in any lower tier subcontracts. The prime contractor shall be responsible for the compliance by any subcontractor or lower tier subcontractor with all the contract clauses in 29 CFR 5.5.
- **7. Contract termination: debarment.** A breach of the contract clauses in 29 CFR 5.5 may be grounds for termination of the contract, and for debarment as a contractor and a subcontractor as provided in 29 CFR 5.12.
- 8. Compliance with Davis-Bacon and Related Act requirements. All rulings and interpretations of the Davis-Bacon and Related Acts contained in 29 CFR parts 1, 3, and 5 are herein incorporated by reference in this contract.
- 9. Disputes concerning labor standards. Disputes arising out of the labor standards provisions of this contract shall not be subject to the general disputes clause of this contract. Such disputes shall be resolved in accordance with the procedures of the Department of Labor set forth in 29 CFR parts 5, 6, and 7. Disputes within the meaning of this clause include disputes between the contractor (or any of its subcontractors) and the contracting agency, the U.S. Department of Labor, or the employees or their representatives.

#### 10. Certification of eligibility.

- a. By entering into this contract, the contractor certifies that neither it (nor he or she) nor any person or firm who has an interest in the contractor's firm is a person or firm ineligible to be awarded Government contracts by virtue of section 3(a) of the Davis-Bacon Act or 29 CFR 5.12(a)(1).
- b. No part of this contract shall be subcontracted to any person or firm ineligible for award of a Government contract by virtue of section 3(a) of the Davis-Bacon Act or 29 CFR 5.12(a)(1).
- c. The penalty for making false statements is prescribed in the U.S. Criminal Code, 18 U.S.C. 1001.

## V. CONTRACT WORK HOURS AND SAFETY STANDARDS ACT

The following clauses apply to any Federal-aid construction contract in an amount in excess of \$100,000 and subject to the overtime provisions of the Contract Work Hours and Safety Standards Act. These clauses shall be inserted in addition to the clauses required by 29 CFR 5.5(a) or 29 CFR 4.6. As used in this paragraph, the terms laborers and mechanics include watchmen and guards.

- 1. Overtime requirements. No contractor or subcontractor contracting for any part of the contract work which may require or involve the employment of laborers or mechanics shall require or permit any such laborer or mechanic in any workweek in which he or she is employed on such work to work in excess of forty hours in such workweek unless such laborer or mechanic receives compensation at a rate not less than one and one-half times the basic rate of pay for all hours worked in excess of forty hours in such workweek.
- 2. Violation; liability for unpaid wages; liquidated damages. In the event of any violation of the clause set forth in paragraph (1.) of this section, the contractor and any subcontractor responsible therefor shall be liable for the unpaid wages. In addition, such contractor and subcontractor shall be liable to the United States (in the case of work done under contract for the District of Columbia or a territory, to such District or to such territory), for liquidated damages. Such liquidated damages shall be computed with respect to each individual laborer or mechanic, including watchmen and guards, employed in violation of the clause set forth in paragraph (1.) of this section, in the sum of \$10 for each calendar day on which such individual was required or permitted to work in excess of the standard workweek of forty hours without payment of the overtime wages required by the clause set forth in paragraph (1.) of this section.
- 3. Withholding for unpaid wages and liquidated damages. The FHWA or the contacting agency shall upon its own action or upon written request of an authorized representative of the Department of Labor withhold or cause to be withheld, from any moneys payable on account of work performed by the contractor or subcontractor under any such contract or any other Federal contract with the same prime contractor, or any other federally-assisted contract subject to the Contract Work Hours and Safety Standards Act, which is held by the same prime contractor, such sums as may be determined to be necessary to satisfy any liabilities of such contractor or subcontractor for unpaid wages and liquidated damages as provided in the clause set forth in paragraph (2.) of this section.
- **4. Subcontracts.** The contractor or subcontractor shall insert in any subcontracts the clauses set forth in paragraph (1.) through (4.) of this section and also a clause requiring the subcontractors to include these clauses in any lower tier subcontracts. The prime contractor shall be responsible for compliance by any subcontractor or lower tier subcontractor with the clauses set forth in paragraphs (1.) through (4.) of this section.

#### VI. SUBLETTING OR ASSIGNING THE CONTRACT

This provision is applicable to all Federal-aid construction contracts on the National Highway System.

- 1. The contractor shall perform with its own organization contract work amounting to not less than 30 percent (or a greater percentage if specified elsewhere in the contract) of the total original contract price, excluding any specialty items designated by the contracting agency. Specialty items may be performed by subcontract and the amount of any such specialty items performed may be deducted from the total original contract price before computing the amount of work required to be performed by the contractor's own organization (23 CFR 635.116).
- a. The term "perform work with its own organization" refers to workers employed or leased by the prime contractor, and equipment owned or rented by the prime contractor, with or without operators. Such term does not include employees or equipment of a subcontractor or lower tier subcontractor, agents of the prime contractor, or any other assignees. The term may include payments for the costs of hiring leased employees from an employee leasing firm meeting all relevant Federal and State regulatory requirements. Leased employees may only be included in this term if the prime contractor meets all of the following conditions:
- the prime contractor maintains control over the supervision of the day-to-day activities of the leased employees;
- (2) the prime contractor remains responsible for the quality of the work of the leased employees;
- (3) the prime contractor retains all power to accept or exclude individual employees from work on the project; and
- (4) the prime contractor remains ultimately responsible for the payment of predetermined minimum wages, the submission of payrolls, statements of compliance and all other Federal regulatory requirements.
- b. "Specialty Items" shall be construed to be limited to work that requires highly specialized knowledge, abilities, or equipment not ordinarily available in the type of contracting organizations qualified and expected to bid or propose on the contract as a whole and in general are to be limited to minor components of the overall contract.
- 2. The contract amount upon which the requirements set forth in paragraph (1) of Section VI is computed includes the cost of material and manufactured products which are to be purchased or produced by the contractor under the contract provisions.
- 3. The contractor shall furnish (a) a competent superintendent or supervisor who is employed by the firm, has full authority to direct performance of the work in accordance with the contract requirements, and is in charge of all construction operations (regardless of who performs the work) and (b) such other of its own organizational resources (supervision, management, and engineering services) as the contracting officer determines is necessary to assure the performance of the contract.
- 4. No portion of the contract shall be sublet, assigned or otherwise disposed of except with the written consent of the contracting officer, or authorized representative, and such consent when given shall not be construed to relieve the contractor of any responsibility for the fulfillment of the contract. Written consent will be given only after the contracting agency has assured that each subcontract is

evidenced in writing and that it contains all pertinent provisions and requirements of the prime contract.

5. The 30% self-performance requirement of paragraph (1) is not applicable to design-build contracts; however, contracting agencies may establish their own self-performance requirements.

#### VII. SAFETY: ACCIDENT PREVENTION

- This provision is applicable to all Federal-aid construction contracts and to all related subcontracts.
- 1. In the performance of this contract the contractor shall comply with all applicable Federal, State, and local laws governing safety, health, and sanitation (23 CFR 635). The contractor shall provide all safeguards, safety devices and protective equipment and take any other needed actions as it determines, or as the contracting officer may determine, to be reasonably necessary to protect the life and health of employees on the job and the safety of the public and to protect property in connection with the performance of the work covered by the contract.
- 2. It is a condition of this contract, and shall be made a condition of each subcontract, which the contractor enters into pursuant to this contract, that the contractor and any subcontractor shall not permit any employee, in performance of the contract, to work in surroundings or under conditions which are unsanitary, hazardous or dangerous to his/her health or safety, as determined under construction safety and health standards (29 CFR 1926) promulgated by the Secretary of Labor, in accordance with Section 107 of the Contract Work Hours and Safety Standards Act (40 U.S.C. 3704).
- 3. Pursuant to 29 CFR 1926.3, it is a condition of this contract that the Secretary of Labor or authorized representative thereof, shall have right of entry to any site of contract performance to inspect or investigate the matter of compliance with the construction safety and health standards and to carry out the duties of the Secretary under Section 107 of the Contract Work Hours and Safety Standards Act (40 U.S.C.3704).

## VIII. FALSE STATEMENTS CONCERNING HIGHWAY PROJECTS

This provision is applicable to all Federal-aid construction contracts and to all related subcontracts.

In order to assure high quality and durable construction in conformity with approved plans and specifications and a high degree of reliability on statements and representations made by engineers, contractors, suppliers, and workers on Federal-aid highway projects, it is essential that all persons concerned with the project perform their functions as carefully, thoroughly, and honestly as possible. Willful falsification, distortion, or misrepresentation with respect to any facts related to the project is a violation of Federal law. To prevent any misunderstanding regarding the seriousness of these and similar acts, Form FHWA-1022 shall be posted on each Federal-aid highway project (23 CFR 635) in one or more places where it is readily available to all persons concerned with the project:

18 U.S.C. 1020 reads as follows:

"Whoever, being an officer, agent, or employee of the United States, or of any State or Territory, or whoever, whether a person, association, firm, or corporation, knowingly makes any false statement, false representation, or false report as to the character, quality, quantity, or cost of the material used or to be used, or the quantity or quality of the work performed or to be performed, or the cost thereof in connection with the submission of plans, maps, specifications, contracts, or costs of construction on any highway or related project submitted for approval to the Secretary of Transportation; or

Whoever knowingly makes any false statement, false representation, false report or false claim with respect to the character, quality, quantity, or cost of any work performed or to be performed, or materials furnished or to be furnished, in connection with the construction of any highway or related project approved by the Secretary of Transportation; or

Whoever knowingly makes any false statement or false representation as to material fact in any statement, certificate, or report submitted pursuant to provisions of the Federal-aid Roads Act approved July 1, 1916, (39 Stat. 355), as amended and supplemented;

Shall be fined under this title or imprisoned not more than 5 years or both."

## IX. IMPLEMENTATION OF CLEAN AIR ACT AND FEDERAL WATER POLLUTION CONTROL ACT

This provision is applicable to all Federal-aid construction contracts and to all related subcontracts.

By submission of this bid/proposal or the execution of this contract, or subcontract, as appropriate, the bidder, proposer, Federal-aid construction contractor, or subcontractor, as appropriate, will be deemed to have stipulated as follows:

- 1. That any person who is or will be utilized in the performance of this contract is not prohibited from receiving an award due to a violation of Section 508 of the Clean Water Act or Section 306 of the Clean Air Act.
- 2. That the contractor agrees to include or cause to be included the requirements of paragraph (1) of this Section X in every subcontract, and further agrees to take such action as the contracting agency may direct as a means of enforcing such requirements.

# X. CERTIFICATION REGARDING DEBARMENT, SUSPENSION, INELIGIBILITY AND VOLUNTARY EXCLUSION

This provision is applicable to all Federal-aid construction contracts, design-build contracts, subcontracts, lower-tier subcontracts, purchase orders, lease agreements, consultant contracts or any other covered transaction requiring FHWA approval or that is estimated to cost \$25,000 or more – as defined in 2 CFR Parts 180 and 1200.

#### 1. Instructions for Certification – First Tier Participants:

- a. By signing and submitting this proposal, the prospective first tier participant is providing the certification set out below.
- b. The inability of a person to provide the certification set out below will not necessarily result in denial of participation in this

covered transaction. The prospective first tier participant shall submit an explanation of why it cannot provide the certification set out below. The certification or explanation will be considered in connection with the department or agency's determination whether to enter into this transaction. However, failure of the prospective first tier participant to furnish a certification or an explanation shall disqualify such a person from participation in this transaction.

- c. The certification in this clause is a material representation of fact upon which reliance was placed when the contracting agency determined to enter into this transaction. If it is later determined that the prospective participant knowingly rendered an erroneous certification, in addition to other remedies available to the Federal Government, the contracting agency may terminate this transaction for cause of default.
- d. The prospective first tier participant shall provide immediate written notice to the contracting agency to whom this proposal is submitted if any time the prospective first tier participant learns that its certification was erroneous when submitted or has become erroneous by reason of changed circumstances.
- e. The terms "covered transaction," "debarred,"
  "suspended," "ineligible," "participant," "person," "principal,"
  and "voluntarily excluded," as used in this clause, are defined
  in 2 CFR Parts 180 and 1200. "First Tier Covered
  Transactions" refers to any covered transaction between a
  grantee or subgrantee of Federal funds and a participant (such
  as the prime or general contract). "Lower Tier Covered
  Transactions" refers to any covered transaction under a First
  Tier Covered Transaction (such as subcontracts). "First Tier
  Participant" refers to the participant who has entered into a
  covered transaction with a grantee or subgrantee of Federal
  funds (such as the prime or general contractor). "Lower Tier
  Participant" refers any participant who has entered into a
  covered transaction with a First Tier Participant or other Lower
  Tier Participants (such as subcontractors and suppliers).
- f. The prospective first tier participant agrees by submitting this proposal that, should the proposed covered transaction be entered into, it shall not knowingly enter into any lower tier covered transaction with a person who is debarred, suspended, declared ineligible, or voluntarily excluded from participation in this covered transaction, unless authorized by the department or agency entering into this transaction.
- g. The prospective first tier participant further agrees by submitting this proposal that it will include the clause titled "Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion-Lower Tier Covered Transactions," provided by the department or contracting agency, entering into this covered transaction, without modification, in all lower tier covered transactions and in all solicitations for lower tier covered transactions exceeding the \$25,000 threshold.
- h. A participant in a covered transaction may rely upon a certification of a prospective participant in a lower tier covered transaction that is not debarred, suspended, ineligible, or voluntarily excluded from the covered transaction, unless it knows that the certification is erroneous. A participant is responsible for ensuring that its principals are not suspended, debarred, or otherwise ineligible to participate in covered transactions. To verify the eligibility of its principals, as well as the eligibility of any lower tier prospective participants, each participant may, but is not required to, check the Excluded Parties List System website (https://www.epls.gov/), which is compiled by the General Services Administration.

- i. Nothing contained in the foregoing shall be construed to require the establishment of a system of records in order to render in good faith the certification required by this clause. The knowledge and information of the prospective participant is not required to exceed that which is normally possessed by a prudent person in the ordinary course of business dealings.
- j. Except for transactions authorized under paragraph (f) of these instructions, if a participant in a covered transaction knowingly enters into a lower tier covered transaction with a person who is suspended, debarred, ineligible, or voluntarily excluded from participation in this transaction, in addition to other remedies available to the Federal Government, the department or agency may terminate this transaction for cause or default.

\* \* \* \* \*

# 2. Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion – First Tier Participants:

- a. The prospective first tier participant certifies to the best of its knowledge and belief, that it and its principals:
- Are not presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from participating in covered transactions by any Federal department or agency;
- (2) Have not within a three-year period preceding this proposal been convicted of or had a civil judgment rendered against them for commission of fraud or a criminal offense in connection with obtaining, attempting to obtain, or performing a public (Federal, State or local) transaction or contract under a public transaction; violation of Federal or State antitrust statutes or commission of embezzlement, theft, forgery, bribery, falsification or destruction of records, making false statements, or receiving stolen property;
- (3) Are not presently indicted for or otherwise criminally or civilly charged by a governmental entity (Federal, State or local) with commission of any of the offenses enumerated in paragraph (a)(2) of this certification; and
- (4) Have not within a three-year period preceding this application/proposal had one or more public transactions (Federal, State or local) terminated for cause or default.
- b. Where the prospective participant is unable to certify to any of the statements in this certification, such prospective participant shall attach an explanation to this proposal.

#### 2. Instructions for Certification - Lower Tier Participants:

(Applicable to all subcontracts, purchase orders and other lower tier transactions requiring prior FHWA approval or estimated to cost \$25,000 or more - 2 CFR Parts 180 and 1200)

- a. By signing and submitting this proposal, the prospective lower tier is providing the certification set out below.
- b. The certification in this clause is a material representation of fact upon which reliance was placed when this transaction was entered into. If it is later determined that the prospective lower tier participant knowingly rendered an erroneous certification, in addition to other remedies available to the Federal Government, the department, or agency with which

this transaction originated may pursue available remedies, including suspension and/or debarment.

- c. The prospective lower tier participant shall provide immediate written notice to the person to which this proposal is submitted if at any time the prospective lower tier participant learns that its certification was erroneous by reason of changed circumstances.
- d. The terms "covered transaction," "debarred,"
  "suspended," "ineligible," "participant," "person," "principal,"
  and "voluntarily excluded," as used in this clause, are defined
  in 2 CFR Parts 180 and 1200. You may contact the person to
  which this proposal is submitted for assistance in obtaining a
  copy of those regulations. "First Tier Covered Transactions"
  refers to any covered transaction between a grantee or
  subgrantee of Federal funds and a participant (such as the
  prime or general contract). "Lower Tier Covered Transactions"
  refers to any covered transaction under a First Tier Covered
  Transaction (such as subcontracts). "First Tier Participant"
  refers to the participant who has entered into a covered
  transaction with a grantee or subgrantee of Federal funds
  (such as the prime or general contractor). "Lower Tier
  Participant" refers any participant who has entered into a
  covered transaction with a First Tier Participant or other Lower
  Tier Participants (such as subcontractors and suppliers).
- e. The prospective lower tier participant agrees by submitting this proposal that, should the proposed covered transaction be entered into, it shall not knowingly enter into any lower tier covered transaction with a person who is debarred, suspended, declared ineligible, or voluntarily excluded from participation in this covered transaction, unless authorized by the department or agency with which this transaction originated.
- f. The prospective lower tier participant further agrees by submitting this proposal that it will include this clause titled "Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion-Lower Tier Covered Transaction," without modification, in all lower tier covered transactions and in all solicitations for lower tier covered transactions exceeding the \$25,000 threshold.
- g. A participant in a covered transaction may rely upon a certification of a prospective participant in a lower tier covered transaction that is not debarred, suspended, ineligible, or voluntarily excluded from the covered transaction, unless it knows that the certification is erroneous. A participant is responsible for ensuring that its principals are not suspended, debarred, or otherwise ineligible to participate in covered transactions. To verify the eligibility of its principals, as well as the eligibility of any lower tier prospective participants, each participant may, but is not required to, check the Excluded Parties List System website (https://www.epls.gov/), which is compiled by the General Services Administration.
- h. Nothing contained in the foregoing shall be construed to require establishment of a system of records in order to render in good faith the certification required by this clause. The knowledge and information of participant is not required to exceed that which is normally possessed by a prudent person in the ordinary course of business dealings.
- i. Except for transactions authorized under paragraph e of these instructions, if a participant in a covered transaction knowingly enters into a lower tier covered transaction with a person who is suspended, debarred, ineligible, or voluntarily excluded from participation in this transaction, in addition to other remedies available to the Federal Government, the

department or agency with which this transaction originated may pursue available remedies, including suspension and/or debarment.

\* \* \* \* \*

#### Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion--Lower Tier Participants:

- 1. The prospective lower tier participant certifies, by submission of this proposal, that neither it nor its principals is presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from participating in covered transactions by any Federal department or agency.
- 2. Where the prospective lower tier participant is unable to certify to any of the statements in this certification, such prospective participant shall attach an explanation to this proposal.

\* \* \* \* \*

## XI. CERTIFICATION REGARDING USE OF CONTRACT FUNDS FOR LOBBYING

This provision is applicable to all Federal-aid construction contracts and to all related subcontracts which exceed \$100,000 (49 CFR 20).

- 1. The prospective participant certifies, by signing and submitting this bid or proposal, to the best of his or her knowledge and belief, that:
- a. No Federal appropriated funds have been paid or will be paid, by or on behalf of the undersigned, to any person for influencing or attempting to influence an officer or employee of any Federal agency, a Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress in connection with the awarding of any Federal contract, the making of any Federal grant, the making of any Federal loan, the entering into of any cooperative agreement, and the extension, continuation, renewal, amendment, or modification of any Federal contract, grant, loan, or cooperative agreement.
- b. If any funds other than Federal appropriated funds have been paid or will be paid to any person for influencing or attempting to influence an officer or employee of any Federal agency, a Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress in connection with this Federal contract, grant, loan, or cooperative agreement, the undersigned shall complete and submit Standard Form-LLL, "Disclosure Form to Report Lobbying," in accordance with its instructions.
- 2. This certification is a material representation of fact upon which reliance was placed when this transaction was made or entered into. Submission of this certification is a prerequisite for making or entering into this transaction imposed by 31 U.S.C. 1352. Any person who fails to file the required certification shall be subject to a civil penalty of not less than \$10,000 and not more than \$100,000 for each such failure.
- 3. The prospective participant also agrees by submitting its bid or proposal that the participant shall require that the language of this certification be included in all lower tier subcontracts, which exceed \$100,000 and that all such recipients shall certify and disclose accordingly.

# ATTACHMENT A - EMPLOYMENT AND MATERIALS PREFERENCE FOR APPALACHIAN DEVELOPMENT HIGHWAY SYSTEM OR APPALACHIAN LOCAL ACCESS ROAD CONTRACTS

This provision is applicable to all Federal-aid projects funded under the Appalachian Regional Development Act of 1965.

- 1. During the performance of this contract, the contractor undertaking to do work which is, or reasonably may be, done as on-site work, shall give preference to qualified persons who regularly reside in the labor area as designated by the DOL wherein the contract work is situated, or the subregion, or the Appalachian counties of the State wherein the contract work is situated, except:
- a. To the extent that qualified persons regularly residing in the area are not available.
- b. For the reasonable needs of the contractor to employ supervisory or specially experienced personnel necessary to assure an efficient execution of the contract work.
- c. For the obligation of the contractor to offer employment to present or former employees as the result of a lawful collective bargaining contract, provided that the number of nonresident persons employed under this subparagraph (1c) shall not exceed 20 percent of the total number of employees employed by the contractor on the contract work, except as provided in subparagraph (4) below.
- 2. The contractor shall place a job order with the State Employment Service indicating (a) the classifications of the laborers, mechanics and other employees required to perform the contract work, (b) the number of employees required in each classification, (c) the date on which the participant estimates such employees will be required, and (d) any other pertinent information required by the State Employment Service to complete the job order form. The job order may be placed with the State Employment Service in writing or by telephone. If during the course of the contract work, the information submitted by the contractor in the original job order is substantially modified, the participant shall promptly notify the State Employment Service.
- 3. The contractor shall give full consideration to all qualified job applicants referred to him by the State Employment Service. The contractor is not required to grant employment to any job applicants who, in his opinion, are not qualified to perform the classification of work required.
- 4. If, within one week following the placing of a job order by the contractor with the State Employment Service, the State Employment Service is unable to refer any qualified job applicants to the contractor, or less than the number requested, the State Employment Service will forward a certificate to the contractor indicating the unavailability of applicants. Such certificate shall be made a part of the contractor's permanent project records. Upon receipt of this certificate, the contractor may employ persons who do not normally reside in the labor area to fill positions covered by the certificate, notwithstanding the provisions of subparagraph (1c) above.
- 5. The provisions of 23 CFR 633.207(e) allow the contracting agency to provide a contractual preference for the use of mineral resource materials native to the Appalachian region.

6. The contractor shall include the provisions of Sections 1 through 4 of this Attachment A in every subcontract for work which is, or reasonably may be, done as on-site work.

#### **Non-discrimination Provisions**

During the performance of this contract, the contractor, for itself, its assignees, and successors in interest (hereinafter referred to as the "contractor") agrees as follows:

- **1. Compliance with Regulations:** The contractor (hereinafter includes consultants) will comply with the Acts and the Regulations relative to Non-discrimination in Federally-assisted programs of the U.S. Department of Transportation, Federal Highway Administration, as they may be amended from time to time, which are herein incorporated by reference and made a part of this contract.
- **2. Non-discrimination:** The contractor, with regard to the work performed by it during the contract, will not discriminate on the grounds of race, color, or national origin in the selection and retention of subcontractors, including procurements of materials and leases of equipment. The contractor will not participate directly or indirectly in the discrimination prohibited by the Acts and the Regulations, including employment practices when the contract covers any activity, project, or program set forth in Appendix B of 49 CFR Part 21.
- **3. Solicitations for Subcontracts, Including Procurements of Materials and Equipment:** In all solicitations, either by competitive bidding, or negotiation made by the contractor for work to be performed under a subcontract, including procurements of materials, or leases of equipment, each potential subcontractor or supplier will be notified by the contractor of the contractor's obligations under this contract and the Acts and the Regulations relative to Non-discrimination on the grounds of race, color, or national origin.
- **4. Information and Reports:** The contractor will provide all information and reports required by the Acts, the Regulations, and directives issued pursuant thereto and will permit access to its books, records, accounts, other sources of information, and its facilities as may be determined by the Recipient or the Federal Highway Administration to be pertinent to ascertain compliance with such Acts, Regulations, and instructions. Where any information required of a contractor is in the exclusive possession of another who fails or refuses to furnish the information, the contractor will so certify to the Recipient or the Federal Highway Administration, as appropriate, and will set forth what efforts it has made to obtain the information.
- **5. Sanctions for Noncompliance:** In the event of a contractor's noncompliance with the Non-discrimination provisions of this contract, the Recipient will impose such contract sanctions as it or the Federal Highway Administration may determine to be appropriate, including, but not limited to:
  - a. Withholding payments to the contractor under the contract until the contractor complies; and/or
  - b. Cancelling, terminating, or suspending a contract, in whole or in part.

**6. Incorporation of Provisions:** The contractor will include the provisions of paragraphs one through six in every subcontract, including procurements of materials and leases of equipment, unless exempt by the Acts, the Regulations and directives issued pursuant thereto. The contractor will take action with respect to any subcontract or procurement as the Recipient or the Federal Highway Administration may direct as a means of enforcing such provisions including sanctions for noncompliance. Provided, that if the contractor becomes involved in, or is threatened with litigation by a subcontractor, or supplier because of such direction, the contractor may request the Recipient to enter into any litigation to protect the interests of the Recipient. In addition, the contractor may request the United States to enter into the litigation to protect the interests of the United States.

During the performance of this contract, the contractor, for itself, its assignees, and successors in interest (hereinafter referred to as the "contractor") agrees to comply with the following non-discrimination statutes and authorities; including but not limited to:

#### **Pertinent Non-Discrimination Authorities:**

- Title VI of the Civil Rights Act of 1964 (42 U.S.C. § 2000d et seq., 78 stat. 252), (prohibits discrimination on the basis of race, color, national origin); and 49 CFR Part 21.
- The Uniform Relocation Assistance and Real Property Acquisition Policies Act of 1970, (42 U.S.C. § 4601), (prohibits unfair treatment of persons displaced or whose property has been acquired because of Federal or Federal-aid programs and projects);
- Federal-Aid Highway Act of 1973, (23 U.S.C. § 324 et seq.), (prohibits discrimination on the basis of sex);
- Section 504 of the Rehabilitation Act of 1973, (29 U.S.C. § 794 et seq.), as amended, (prohibits discrimination on the basis of disability); and 49 CFR Part 27;
- The Age Discrimination Act of 1975, as amended, (42 U.S.C. § 6101 et seq.), (prohibits discrimination on the basis of age);
- Airport and Airway Improvement Act of 1982, (49 USC § 471, Section 47123), as amended, (prohibits discrimination based on race, creed, color, national origin, or sex);
- The Civil Rights Restoration Act of 1987, (PL 100-209), (Broadened the scope, coverage and applicability of Title VI of the Civil Rights Act of 1964, The Age Discrimination Act of 1975 and Section 504 of the Rehabilitation Act of 1973, by expanding the definition of the terms "programs or activities" to include all of the programs or activities of the Federal-aid recipients, sub-recipients and contractors, whether such programs or activities are Federally funded or not);
- Titles II and III of the Americans with Disabilities Act, which prohibit discrimination on the basis of disability in the operation of public entities, public and private transportation systems, places of public accommodation, and certain testing entities (42 U.S.C. §§ 12131-12189) as implemented by Department of Transportation regulations at 49 C.F.R. parts 37 and 38;
- The Federal Aviation Administration's Non-discrimination statute (49 U.S.C. § 47123) (prohibits discrimination on the basis of race, color, national origin, and sex);

- Executive Order 12898, Federal Actions to Address Environmental Justice in Minority Populations and Low-Income Populations, which ensures Non-discrimination against minority populations by discouraging programs, policies, and activities with disproportionately high and adverse human health or environmental effects on minority and low-income populations;
- Executive Order 13166, Improving Access to Services for Persons with Limited English Proficiency, and resulting agency guidance, national origin discrimination includes discrimination because of Limited English proficiency (LEP). To ensure compliance with Title VI, you must take reasonable steps to ensure that LEP persons have meaningful access to your programs (70 Fed. Reg. at 74087 to 74100);
- Title IX of the Education Amendments of 1972, as amended, which prohibits you from discriminating because of sex in education programs or activities (20 U.S.C. 1681 et seq).

#### **SEPTEMBER 2002**

# NOTICE OF REQUIREMENT FOR AFFIRMATIVE ACTION TO ENSURE EQUAL EMPLOYMENT OPPORTUNITY (EXECUTIVE ORDER 11246)

- 1. The Offeror's or Bidder's attention is called to the "Employment Practices" and "Equal Opportunity Clause" set forth in the Required Contract Provisions, FHWA 1273.
- 2. The goals and timetables for minority and female participation expressed in percentage terms for the contractor's aggregate work force in each trade, on all construction work in the covered area, are as follows:

#### **Goals for Minority Participation for Each Trade:**

_County_	<u>%</u>	_County_	_%_	_County_	<u>%</u>
Adams	1.7	Iowa	1.7	Polk	2.2
Ashland	1.2	Iron	1.2	Portage	0.6
Barron	0.6	Jackson	0.6	Price	0.6
Bayfield	1.2	Jefferson	7.0	Racine	8.4
Brown	1.3	Juneau	0.6	Richland	1.7
Buffalo	0.6	Kenosha	3.0	Rock	3.1
Burnett	2.2	Kewaunee	1.0	Rusk	0.6
Calumet	0.9	La Crosse	0.9	St. Croix	2.9
Chippewa	0.5	Lafayette	0.5	Sauk	1.7
Clark	0.6	Langlade	0.6	Sawyer	0.6
Columbia	1.7	Lincoln	0.6	Shawano	1.0
Crawford	0.5	Manitowoc	1.0	Sheboygan	7.0
Dane	2.2	Marathon	0.6	Taylor	0.6
Dodge	7.0	Marinette	1.0	Trempealeau	0.6
Door	1.0	Marquette	1.7	Vernon	0.6
Douglas	1.0	Menominee	1.0	Vilas	0.6
Dunn	0.6	Milwaukee	8.0	Walworth	7.0
Eau Claire	0.5	Monroe	0.6	Washburn	0.6
Florence	1.0	Oconto	1.0	Washington	8.0
Fond du Lac	1.0	Oneida	0.6	Waukesha	8.0
Forest	1.0	Outagamie	0.9	Waupaca	1.0
Grant	0.5	Ozaukee	8.0	Waushara	1.0
Green	1.7	Pepin	0.6	Winnebago	0.9
Green Lake	1.0	Pierce	2.2	Wood	0.6

#### Goals for female participation for each trade: 6.9%

These goals are applicable to all the contractor's construction work, (whether or not it is federal or federally assisted), performed in the covered area. If the contractor performs construction work in the geographical area located outside of the covered area, it shall apply the goals established for such geographical area where the work is actually performed. With regard to this second area, the contractor also is subject to the goals for both its federally involved and nonfederally involved construction.

The contractor's compliance with the Executive Order and the Regulations in 41 CFR Part 60-4 shall be based on its implementation of the Equal Opportunity Clause, specific affirmative action obligations required by the specifications set forth in 41 CFR 60-4.3(a), and its efforts to meet the goals. The hours of minority and female employment and training must be substantially uniform throughout the length of the contract, and in each trade, and the contractor shall make a good faith effort to employ minorities and women evenly on each of its projects. The transfer of minority or female employees or trainees from contractor to contractor or from project to project for the sole purpose of meeting the contractor's goals shall be a violation of the contract, the Executive Order and the Regulations in 41 CFR Part 60-4. Compliance with the goals will be measured against the total work hours performed.

3. The contractor shall provide written notification to the Director of the Office of Federal Contract Compliance Programs within ten (10) working days of award of any construction subcontract in excess of \$10,000.00 at any tier for construction work under the contract resulting from this solicitation. The notification shall list the name, address and telephone number of the subcontractor, employer identification number of the subcontractor; estimated dollar amount of the subcontract; estimated starting and completion dates of the subcontract; and the geographical area in which the subcontract is to be performed.

As referred to in this section, the Director means:

Director Office of Federal Contract Compliance Programs Ruess Federal Plaza 310 W. Wisconsin Ave., Suite 1115 Milwaukee, WI 53202

The "Employer Identification Number" means the Federal Social Security number used on the Employer's Quarterly Federal Tax Return, U.S. Treasury Department Form 941.

4. As used in this notice, and in the contract resulting from solicitation, the "covered area" is the county(ies) in Wisconsin to which this proposal applies.

#### **APRIL 2013**

#### ADDITIONAL FEDERAL-AID PROVISIONS

#### NOTICE TO ALL BIDDERS

To report bid rigging activities call:

#### 1-800-424-9071

The U.S. Department of Transportation (DOT) operates the above toll-free "hotline" Monday through Friday, 8:00 a.m. to 5:00 p.m., Eastern Time. Anyone with knowledge of possible bid rigging, bidding collusion, or other fraudulent activities should use the "hotline" to report such activities.

The "hotline" is part of the DOT's continuing effort to identify and investigate highway construction contract fraud and abuse and is operated under the direction of the DOT Inspector General. All information will be treated confidentially and caller anonymity will be respected.

#### **Effective August 2015 letting**

#### **BUY AMERICA PROVISION**

All steel and iron materials permanently incorporated in this project shall be domestic products and all manufacturing and coating processes for these materials from smelting forward in the manufacturing process must have occurred within the United States. Coating includes epoxy coating, galvanizing, painting and any other coating that protects or enhances the value of a material subject to the requirements of Buy America. The exemption of this requirement is the minimal use of foreign materials if the total cost of such material permanently incorporated in the product does not exceed one-tenth of one percent (1/10 of 1%) of the total contract cost or \$2,500.00, whichever is greater. For purposes of this paragraph, the cost is that shown to be the value of the subject products as they are delivered to the project. The contractor shall take actions and provide documentation conforming to CMM 2-28.5 to ensure compliance with this "Buy America" provision.

#### https://wisconsindot.gov/rdwy/cmm/cm-02-28.pdf

Upon completion of the project certify to the engineer, in writing using department form WS4567, that all steel, iron, and coating processes for steel or iron incorporated into the contract work conform to these "Buy America" provisions. Attach a list of exemptions and their associated costs to the certification form. Department form WS4567 is available at:

https://wisconsindot.gov/hcciDocs/contracting-info/ws4567.doc

1 of 1

#### Cargo Preference Act Requirement

All Federal-aid projects shall comply with 46 CFR 381.7 (a) – (b) as follows:

- (a) Agreement Clauses. "Use of United States-flag vessels:"
- (1) Pursuant to Pub. L. 664 (43 U.S.C. 1241(b)) at least 50 percent of any equipment, materials or commodities procured, contracted for or otherwise obtained with funds granted, guaranteed, loaned, or advanced by the U.S. Government under this agreement, and which may be transported by ocean vessel, shall be transported on privately owned United States-flag commercial vessels, if available.
- (2) Within 20 days following the date of loading for shipments originating within the United States or within 30 working days following the date of loading for shipments originating outside the United States, a legible copy of a rated, 'on-board' commercial ocean bill-of-lading in English for each shipment of cargo described in paragraph (a)(1) of this section shall be furnished to both the Contracting Officer (through the prime contractor in the case of subcontractor bills-of-lading) and to the Division of National Cargo, Office of Market Development, Maritime Administration, Washington, DC 20590."
- (b) Contractor and Subcontractor Clauses. "Use of United States-flag vessels: The contractor agrees—"
- (1) To utilize privately owned United States-flag commercial vessels to ship at least 50 percent of the gross tonnage (computed separately for dry bulk carriers, dry cargo liners, and tankers) involved, whenever shipping any equipment, material, or commodities pursuant to this contract, to the extent such vessels are available at fair and reasonable rates for United States-flag commercial vessels.
- (2) To furnish within 20 days following the date of loading for shipments originating within the United States or within 30 working days following the date of loading for shipments originating outside the United States, a legible copy of a rated, 'on-board' commercial ocean bill-of-lading in English for each shipment of cargo described in paragraph (b) (1) of this section to both the Contracting Officer (through the prime contractor in the case of subcontractor bills-of-lading) and to the Division of National Cargo, Office of Market Development, Maritime Administration, Washington, DC 20590.
- (3) To insert the substance of the provisions of this clause in all subcontracts issued pursuant to this contract.

# WISCONSIN DEPARTMENT OF TRANSPORTATION DIVISION OF TRANSPORTATION AND SYSTEM DEVELOPMENT

# SUPPLEMENTAL REQUIRED CONTRACT PROVISIONS FOR PROJECTS WITH FEDERAL AID

#### I. PREVAILING WAGE RATES

The attached U.S. Department of Labor (Davis-Bacon Minimum Wage Rates) furnishes the minimum prevailing wage rates pursuant to the Davis-Bacon and Related Acts. The wage rates shown are the minimum rates required by the contract to be paid during its life, however this is not a representation that labor can be obtained at these rates. It is the responsibility of bidders to inform themselves as to the local labor conditions and prospective changes or adjustments of wage rates. No increase in the contract price will be allowed or authorized on account of the payment of wage rates in excess of those listed herein.

#### II. COVERAGE OF TRUCK DRIVERS

Truck drivers are covered by Davis-Bacon Minimum Wage Rates in the following circumstances:

- Drivers of a contractor or subcontractor for time spent working on the site of the work.
- Drivers of a contractor or subcontractor for time spent loading and/or unloading materials and supplies on the site of the work, if such time is not de minimis. https://www.dol.gov/whd/FOH/FOH\_Ch15.pdf
- Truck drivers transporting materials or supplies between a facility that is deemed part of the site of the work and the actual construction site.
- Truck drivers transporting portions of the building or work between a site
  established specifically for the performance of the contract where a
  significant portion of such building or work is constructed and the physical
  place where the building or work called for in the contract will remain.

Truck drivers are not covered by Davis-Bacon Minimum Wage Rates in the following circumstances:

- Material delivery truck drivers while off the site of the work.
- Drivers of a contractor or subcontractor traveling between a Davis-Bacon job and a commercial supply facility while they are off the site of the work."
- Truck drivers whose time spent on the site of the work is de minimis, such as only a few minutes at a time merely to pick up or drop off materials or supplies.

Details are available online at:

https://www.dol.gov/whd/recovery/pwrb/Tab9.pdf https://wisconsindot.gov/Pages/doing-bus/civil-rights/labornwage/trckng.aspx

#### III. POSTINGS AT THE SITE OF THE WORK

In addition to the required postings furnished by the department, the contractor shall post the following in at least one conspicuous and accessible place at the site of work:

a. A copy of the contractor's Equal Employment Opportunity Policy.

All required documents shall be posted by the first day of work and be accurate and complete. Postings must be readable, in an area where they will be noticed, and maintained until the last day of work.

#### IV. RESOURCES

Required information regarding compliance with federal provisions is found in the following resources:

- · FHWA-1273 included in this contract
- U.S. Department of Labor Prevailing Wage Resource Book
- · U.S. Department of Labor Field Operations Handbook
- U.S. Code of Federal Regulations
- Any applicable law, Act, or Executive Order enacted by the federal government at the time of the letting of this contract

"General Decision Number: WI20200010 07/17/2020

Superseded General Decision Number: WI20190010

State: Wisconsin

Construction Type: Highway

Counties: Wisconsin Statewide.

HIGHWAY, AIRPORT RUNWAY & TAXIWAY CONSTRUCTION PROJECTS (does not include bridges over navigable waters; tunnels; buildings in highway rest areas; and railroad construction)

Note: Under Executive Order (EO) 13658, an hourly minimum wage of \$10.80 for calendar year 2020 applies to all contracts subject to the Davis-Bacon Act for which the contract is awarded (and any solicitation was issued) on or after January 1, 2015. If this contract is covered by the EO, the contractor must pay all workers in any classification listed on this wage determination at least \$10.80 per hour (or the applicable wage rate listed on this wage determination, if it is higher) for all hours spent performing on the contract in calendar year 2020. If this contract is covered by the EO and a classification considered necessary for performance of work on the contract does not appear on this wage determination, the contractor must pay workers in that classification at least the wage rate determined through the conformance process set forth in 29 CFR 5.5(a)(1)(ii) (or the EO minimum wage rate, if it is higher than the conformed wage rate). The EO minimum wage rate will be adjusted annually. Please note that this EO applies to the above-mentioned types of contracts entered into by the federal government that are subject to the Davis-Bacon Act itself, but it does not apply to contracts subject only to the Davis-Bacon Related Acts, including those set forth at 29 CFR 5.1(a)(2)-(60). Additional information on contractor requirements and worker protections under the EO is available at www.dol.gov/whd/govcontracts.

${\tt Modification}$	Number	Publication	Date
0		01/03/2020	
1		01/24/2020	
2		02/28/2020	
3		03/06/2020	
4		06/05/2020	
5		06/12/2020	
6		06/19/2020	
7		07/17/2020	

### BRWI0001-002 06/03/2019

CRAWFORD, JACKSON, JUNEAU, LA CROSSE, MONROE, TREMPEALEAU, AND VERNON COUNTIES

	Rates	Fringes
BRICKLAYER	.\$ 33.80	24.28
BRWI0002-002 06/01/2019		
ASHLAND, BAYFIELD, DOUGLAS, AND	IRON COUNTIES	
	Rates	Fringes
BRICKLAYER	.\$ 39.94	23.30
BRWI0002-005 06/01/2019		
ADAMS, ASHLAND, BARRON, BROWN, ECLARK, COLUMBIA, DODGE, DOOR, DUFOREST, GREEN LAKE, IRON, JEFFER LINCOLN, MANITOWOC, MARATHON, MAOCONTO, ONEIDA, OUTAGAMIE, POLK, SHAWANO, SHEBOYGAN, TAYLOR, VILAWINNEBAGO, AND WOOD COUNTIES	INN, FLORENCE, FO SON, KEWAUNEE, RINETTE, MARQUE PORTAGE, RUSK,	OND DU LAC, LANGLADE, TTE, MENOMINEE, ST CROIX, SAUK,
	Rates	Fringes
CEMENT MASON/CONCRETE FINISHER	.\$ 35.51	23.37
BRWI0003-002 06/03/2019		
BROWN, DOOR, FLORENCE, KEWAUNEE,	MARINETTE, AND	OCONTO COUNTIES
	Rates	Fringes
BRICKLAYER	.\$ 34.18	23.90
BRWI0004-002 06/01/2019		
KENOSHA, RACINE, AND WALWORTH CO	OUNTIES	
	Rates	Fringes
BRICKLAYER	.\$ 38.43	25.10
BRWI0006-002 06/01/2019		<b></b>

ADAMS, CLARK, FOREST, LANGLADE, LINCOLN, MARATHON, MENOMINEE, ONEIDA, PORTAGE, PRICE, TAYLOR, VILAS AND WOOD COUNTIES

	Rates	Fringes
BRICKLAYER	.\$ 35.06	23.02
BRWI0007-002 06/03/2019		
GREEN, LAFAYETTE, AND ROCK COUNT	IES	
	Rates	Fringes
BRICKLAYER	.\$ 35.57	24.22
BRWI0008-002 06/01/2019		
MILWAUKEE, OZAUKEE, WASHINGTON,	AND WAUKESHA COU	NTIES
	Rates	Fringes
BRICKLAYER	•	24.22
BRWI0011-002 06/03/2019		
CALUMET, FOND DU LAC, MANITOWOC,	AND SHEBOYGAN C	OUNTIES
	Rates	Fringes
BRICKLAYER	.\$ 34.18	23.90
BRWI0019-002 06/03/2019		
BARRON, BUFFALO, BURNETT, CHIPPEL PIERCE, POLK, RUSK, ST. CROIX, SA	•	•
	Rates	Fringes
BRICKLAYER	.\$ 33.40	24.68
COLUMBIA AND SAUK COUNTIES		
	Rates	Fringes
BRICKLAYER	.\$ 35.56	24.23

-----

### CARP0087-001 05/01/2016

BURNETT (W. of Hwy 48), PIERCE (W. of Hwy 29), POLK (W. of Hwys 35, 48 & 65), AND ST. CROIX (W. of Hwy 65) COUNTIES

	Rates	Fringes
Carpenter & Piledrivermen	.\$ 36.85	18.39
CARP0252-002 06/01/2016		

ADAMS, BARRON, BAYFIELD (Eastern 2/3), BROWN, BUFFALO, BURNETT (E. of Hwy 48), CALUMET, CHIPPEWA, CLARK, COLUMBIA, CRAWFORD, DANE, DODGE, DOOR, DUNN, EAU CLAIRE, FLORENCE (except area bordering Michigan State Line), FOND DU LAC, FOREST, GRANT, GREEN, GREEN LAKE, IOWA, IRON, JACKSON, JEFFERSON, JUNEAU, KEWAUNEE, LA CROSSE, LAFAYETTE, LANGLADE, LINCOLN, MANITOWOC, MARATHON, MARINETTE (except N.E. corner), MARQUETTE, MENOMINEE, MONROE, OCONTO, ONEIDA, OUTAGAMIE, PEPIN, PIERCE (E. of Hwys 29 & 65), POLK (E. of Hwys 35, 48 & 65), PORTAGE, PRICE, RICHLAND, ROCK, RUSK, SAUK, SAWYER, SHAWANO, SHEBOYGAN, ST CROIX (E. of Hwy 65), TAYLOR, TREMPEALEAU, VERNON, VILAS, WALWORTH, WASHBURN, WAUPACA, WAUSHARA, WINNEBAGO, AND WOOD COUNTIES

F	Rates	Fringes
CARPENTER		
CARPENTER\$	33.56	18.00
MILLWRIGHT\$	35.08	18.35
PILEDRIVER\$	34.12	18.00

CARP0252-010 06/01/2016

#### ASHLAND COUNTY

	Rates	Fringes
Carpenters		
Carpenter	\$ 33.56	18.00
Millwright	\$ 35.08	18.35
Pile Driver	\$ 34.12	18.00

CARP0264-003 06/01/2016

KENOSHA, MILWAUKEE, OZAUKEE, RACINE, WAUKESHA, AND WASHINGTON COUNTIES

	Rates	Fringes
CARPENTER	\$ 35.78	22.11
CARP0361-004 05/01/2018		
BAYFIELD (West of Hwy 63) AND [	OOUGLAS COUN	TIES
	Rates	Fringes
CARPENTER	\$ 36.15	20.43
CARP2337-001 06/01/2016		
ZONE A: MILWAUKEE, OZAUKEE, WAL	JKESHA AND W	ASHINGTON
ZONE B: KENOSHA & RACINE		
	Rates	Fringes
PILEDRIVERMAN		
Zone B		22.69 22.69
ELEC0014-002 06/03/2019		
ASHLAND, BARRON, BAYFIELD, BUFFALO, BURNETT, CHIPPEWA, CLARK (except Maryville, Colby, Unity, Sherman, Fremont, Lynn & Sherwood), CRAWFORD, DUNN, EAU CLAIRE, GRANT, IRON, JACKSON, LA CROSSE, MONROE, PEPIN, PIERCE, POLK, PRICE, RICHLAND, RUSK, ST CROIX, SAWYER, TAYLOR, TREMPEALEAU, VERNON, AND WASHBURN COUNTIES		
	Rates	Fringes

REMAINING COUNTIES

	Rates	Fringes
Teledata System Installer		
Installer/Technician	.\$ 27.25	14.34

Low voltage construction, installation, maintenance and removal of teledata facilities (voice, data, and video) including outside plant, telephone and data inside wire, interconnect, terminal equipment, central offices, PABX, fiber optic cable and equipment, micro waves, V-SAT, bypass, CATV, WAN (wide area networks), LAN (local area networks), and ISDN (integrated systems digital network).

-----

ELEC0127-002 06/01/2020

KENOSHA COUNTY

Rates Fringes

Electricians:.....\$ 41.62 30%+12.70

ELEC0158-002 06/03/2019

BROWN, DOOR, KEWAUNEE, MANITOWOC (except Schleswig), MARINETTE(Wausuakee and area South thereof), OCONTO, MENOMINEE (East of a ine 6 miles West of the West boundary of Oconto County), SHAWANO (Except Area North of Townships of Aniwa and Hutchins) COUNTIES

COLUMBIA, DANE, DODGE (Area West of Hwy 26, except Chester and Emmet Townships), GREEN, LAKE (except Townships of Berlin, Seneca, and St. Marie), IOWA, MARQUETTE (except Townships of Neshkoka, Crystal Lake, Newton, and Springfield), and SAUK COUNTIES

FLORENCE COUNTY (Townships of Aurora, Commonwealth, Fern, Florence and Homestead) AND MARINETTE COUNTY (Township of Niagara)

	Rates	Fringes
Electricians: Electrical contracts over \$180,000 Electrical contracts under	.\$ 32.38	18.63
\$180,000	.\$ 30.18 	18.42
ELEC0242-005 05/16/2018		
DOUGLAS COUNTY		
	Rates	Fringes
Electricians:		26.17
ELEC0388-002 06/03/2019		
ADAMS, CLARK (Colby, Freemont, L Sherwood, Unity), FOREST, JUNEA MARINETTE (Beecher, Dunbar, Good West of a line 6 miles West of t County), ONEIDA, PORTAGE, SHAWAN AND WOOD COUNTIES	U, LANGLAD man & Pemb he West bo	E, LINCOLN, MARATHON, ine), MENOMINEE (Area undary of Oconto
	Rates	Fringes
Electricians:  ELEC0430-002 06/01/2020	.\$ 33.56 	
RACINE COUNTY (Except Burlington	Township)	
	Rates	Fringes
Electricians:	.\$ 41.86	22.66
ELEC0494-005 06/01/2020		
MILWAUKEE, OZAUKEE, WASHINGTON,	AND WAUKES	HA COUNTIES
	Rates	Fringes
Electricians: ELEC0494-006 06/01/2020	•	25.54
CALUMET (Township of New Holstei including Chester Township), FON	• -	,

### (Schleswig), and SHEBOYGAN COUNTIES

	Rates	Fringes
Electricians:	.\$ 36.32	22.51

<sup>\*</sup> ELEC0494-013 06/07/2020

DODGE (East of Hwy 26 including Chester Twp, excluding Emmet Twp), FOND DU LAC (Except Waupuin), MILWAUKEE, OZAUKEE, MANITOWOC (Schleswig), WASHINGTON, AND WAUKESHA COUNTIES

	Rates	Fringes
Sound & Communications		
Installer	\$ 21.46	18.52
Technician	\$ 31.34	20.00

Installation, testing, maintenance, operation and servicing of all sound, intercom, telephone interconnect, closed circuit TV systems, radio systems, background music systems, language laboratories, electronic carillion, antenna distribution systems, clock and program systems and low-voltage systems such as visual nurse call, audio/visual nurse call systems, doctors entrance register systems. Includes all wire and cable carrying audio, visual, data, light and radio frequency signals. Includes the installation of conduit, wiremold, or raceways in existing structures that have been occupied for six months or more where required for the protection of the wire or cable, but does not mean a complete conduit or raceway system. covered does not include the installation of conduit, wiremold or any raceways in any new construction, or the installation of power supply outlets by means of which external electric power is supplied to any of the foregoing equipment or products

\_\_\_\_\_

### ELEC0577-003 06/01/2019

CALUMET (except Township of New Holstein), GREEN LAKE (N. part including Townships of Berlin, St Marie, and Seneca), MARQUETTE (N. part including Townships of Crystal Lake, Neshkoro, Newton, and Springfield), OUTAGAMIE, WAUPACA, WAUSHARA, AND WINNEBAGO COUNTIES

Rates

Fringes

Electricians:		
ELEC0890-003 06/01/2020		
DODGE (Emmet Township only), GREE RACINE (Burlington Township), ROC		
	Rates	Fringes
Electricians:		25.95%+11.11
ELEC0953-001 06/02/2019		
	Rates	Fringes
Line Construction: (1) Lineman		21.43
Operator(3) Equipment Operator		19.80 18.40
<ul><li>(4) Heavy Groundman Driver</li><li>(5) Light Groundman Driver</li><li>(6) Groundsman</li></ul>	\$ 30.89 \$ 26.14	16.88 16.11 14.60
ENGI0139-005 06/01/2020		
	Rates	Fringes
Power Equipment Operator	¢ 41 62	22.00
Group 1		23.80 23.80
Group 3		23.80
Group 4		23.80
Group 5		23.80
Group 6		23.80
HAZARDOUS WASTE PREMIUMS:		

# POWER EQUIPMENT OPERATORS CLASSIFICATIONS

EPA Level ""A"" protection - \$3.00 per hour EPA Level ""B"" protection - \$2.00 per hour EPA Level ""C"" protection - \$1.00 per hour

GROUP 1: Cranes, tower cranes, and derricks with or without attachments with a lifting capacity of over 100 tons; or cranes, tower cranes, and derricks with boom, leads and/or jib lengths measuring 176 feet or longer.

GROUP 2: Cranes, tower cranes and derricks with or without attachments with a lifting capacity of 100 tons or less; or cranes, tower cranes, and derricks with boom, leads, and/or jibs lengths measuring 175 feet or under and Backhoes (excavators) weighing 130,000 lbs and over; caisson rigs; pile driver; dredge operator; dredge engineer; Boat Pilot.

GROUP 3: Mechanic or welder - Heavy duty equipment; cranes with a lifting capacity of 25 tons or under; concrete breaker (manual or remote); vibratory/sonic concrete breaker; concrete laser screed; concrete slipform paver; concrete batch plant operator; concrete pvt. spreader heavy duty (rubber tired); concrete spreader & distributor; automatic subgrader (concrete); concrete grinder & planing machine; concrete slipform curb & gutter machine; slipform concrete placer; tube finisher; hydro blaster (10,000 psi & over); bridge paver; concrete conveyor system; concrete pump; Rotec type Conveyor; stabilizing mixer (self-propelled); shoulder widener; asphalt plant engineer; bituminious paver; bump cutter & grooving machine; milling machine; screed (bituminous paver); asphalt heater, planer & scarifier; Backhoes (excavators) weighing under 130,000 lbs; grader or motor patrol; tractor (scraper, dozer, pusher, loader); scraper - rubber tired (single or twin engine); endloader; hydraulic backhoe (tractor type); trenching machine; skid rigs; tractor, side boom (heavy); drilling or boring machine (mechanical heavy); roller over 5 tons; percussion or rotary drilling machine; air track; blaster; loading machine (conveyor); tugger; boatmen; winches & A-frames; post driver; material hoist.

GROUP 4: Greaser, roller steel (5 tons or less); roller (pneumatic tired) - self propelled; tractor (mounted or towed compactors & light equipment); shouldering machine; self- propelled chip spreader; concrete spreader; finishing machine; mechanical float; curing machine; power subgrader; joint sawer (multiple blade) belting machine; burlap machine; texturing machine; tractor endloader (rubber tired) - light; jeep digger; forklift; mulcher; launch operator; fireman, environmental burner

GROUP 5: Air compressor; power pack; vibrator hammer and extractor; heavy equipment, leadman; tank car heaters; stump chipper; curb machine operator; Concrete proportioning plants; generators; mudjack operator; rock breaker; crusher or screening plant; screed (milling machine); automatic belt conveyor and surge bin; pug mill operator; Oiler, pump (over 3 inches); Drilling Machine Tender.

GROUP 6: Off-road material hauler with or without ejector.

-----

IRON0008-002 06/01/2020

BROWN, CALUMET, DOOR, FOND DU LAC, KEWAUNEE, MANITOWOC, MARINETTE, OCONTO, OUTAGAMI, SHAWANO, SHEBOYGAN, AND WINNEBAGO COUNTIES:

Rates Fringes

IRONWORKER.....\$ 37.31 27.62

Paid Holidays: New Year's Day, Memorial Day, July 4th, Labor Day, Thanksgiving Day & Christmas Day.

-----

IRON0008-003 06/01/2020

KENOSHA, MILWAUKEE, OZAUKEE, RACINE, WALWORTH (N.E. 2/3), WASHINGTON, AND WAUKESHA COUNTIES

Rates Fringes

IRONWORKER.....\$ 39.11 27.87

Paid Holidays: New Year's Day, Memorial Day, July 4th, Labor Day, Thanksgiving Day & Christmas Day.

-----

IRON0383-001 06/01/2020

ADAMS, COLUMBIA, CRAWFORD, DANE, DODGE, FLORENCE, FOREST, GRANT, GREENE, (Excluding S.E. tip), GREEN LAKE, IOWA, JEFFERSON, JUNEAU, LA CROSSE, LAFAYETTE, LANGLADE, MARATHON, MARQUETTE, MENOMINEE, MONROE, PORTAGE, RICHLAND, ROCK (Northern area, vicinity of Edgerton and Milton), SAUK, VERNON, WAUPACA, WAUSHARA, AND WOOD COUNTIES

Rates Fringes

IRONWORKER.....\$ 37.10 27.06

IRON0498-005 06/01/2019

GREEN (S.E. 1/3), ROCK (South of Edgerton and Milton), and WALWORTH (S.W. 1/3) COUNTIES:

	Rates	Fringes
IRONWORKER	.\$ 40.25	40.53
IRON0512-008 06/03/2019		

BARRON, BUFFALO, CHIPPEWA, CLARK, DUNN, EAU CLAIRE, JACKSON, PEPIN, PIERCE, POLK, RUSK, ST CROIX, TAYLOR, AND TREMPEALEAU COUNTIES

	Rates	Fringes
IRONWORKER	\$ 37.60	29.40
IRON0512-021 06/03/2019		

ASHLAND, BAYFIELD, BURNETT, DOUGLAS, IRON, LINCOLN, ONEIDA, PRICE, SAWYER, VILAS AND WASHBURN COUNTIES

	Rates	Fringes
IRONWORKER	\$ 33.19	29.40

<sup>\*</sup> LAB00113-002 06/01/2020

# MILWAUKEE AND WAUKESHA COUNTIES

	·	Rates	Fringes
LABORER			
Group	1\$	30.05	22.26
Group	2\$	30.20	22.26
Group	3\$	30.40	22.26
Group	4\$	30.55	22.26
Group	5\$	30.70	22.26
Group	6\$	26.54	22.26

### LABORERS CLASSIFICATIONS

GROUP 1: General Laborer; Tree Trimmer; Conduit Layer; Demolition and Wrecking Laborer; Guard Rail, Fence, and Bridge Builder; Landscaper; Multiplate Culvert Assembler; Stone Handler; Bituminous Worker (Shoveler, Loader, and Utility Man); Batch Truck Dumper or Cement Handler; Bituminous Worker (Dumper, Ironer, Smoother, and Tamper); Concrete Handler

GROUP 2: Air Tool Operator; Joint Sawer and Filler (Pavement); Vibrator or Tamper Operator (Mechanical Hand Operated); Chain Saw Operator; Demolition Burning Torch Laborer

GROUP 3: Bituminous Worker (Raker and Luteman); Formsetter (Curb, Sidewalk, and Pavement); Strike Off Man

GROUP 4: Line and Grade Specialist

GROUP 5: Blaster and Powderman

GROUP 6: Flagperson; traffic control person

\_\_\_\_\_

### OZAUKEE AND WASHINGTON COUNTIES

	F	Rates	Fringes
LABORER			
Group	1\$	29.30	22.26
Group	2\$	29.40	22.26
Group	3\$	29.45	22.26
Group	4\$	29.65	22.26
Group	5\$	29.50	22.26
Group	6\$	26.39	22.26

### LABORERS CLASSIFICATIONS

GROUP 1: General Laborer; Tree Trimmer; Conduit Layer; Demolition and Wrecking Laborer; Guard Rail, Fence, and Bridge Builder; Landscaper; Multiplate Culvert Assembler; Stone Handler; Bituminous Worker (Shoveler, Loader, and Utility Man); Batch Truck Dumper or Cement Handler; Bituminous Worker (Dumper, Ironer, Smoother, and Tamper); Concrete Handler

GROUP 2: Air Tool Operator; Joint Sawer and Filler (Pavement); Vibrator or Tamper Operator (Mechanical Hand Operated);

GROUP 3: Bituminous Worker (Raker and Luteman); Formsetter (Curb, Sidewalk, and Pavement); Strike Off Man

GROUP 4: Line and Grade Specialist

GROUP 5: Blaster; powderman

<sup>\*</sup> LAB00113-003 06/01/2020

-----

### \* LAB00113-011 06/01/2020

#### KENOSHA AND RACINE COUNTIES

	I	Rates	Fringes
LABORER			
Group	1\$	29.11	22.26
Group	2\$	29.26	22.26
Group	3\$	29.46	22.26
Group	4\$	29.43	22.26
Group	5\$	29.76	22.26
Group	6\$	26.25	22.26

### LABORERS CLASSIFICATIONS:

GROUP 1: General laborer; Tree Trimmer; Conduit Layer; Demolition and Wrecking Laborer; Guard Rail, Fence, and Bridge Builder; Landscaper; Multiplate Culvert Assembler; Stone Handler; Bituminous Worker (Shoveler, Loader, and Utility Man); Batch Truck Dumper or Cement Handler; Bituminous worker (Dumper, Ironer, Smoother, and Tamper); Concrete Handler

GROUP 2: Air Tool Operator; Joint Sawer and Filler (Pavement); Vibrator or Tamper Operator (Mechanical Hand Operated); Chain Saw Operator; Demolition Burning Torch Laborer

GROUP 3: Bituminous Worker (Raker and Luteman); Formsetter (Curb, Sidewalk, and Pavement); Strike Off Man

GROUP 4: Line and Grade Specialist

GROUP 5: Blaster and Powderman

GROUP 6: Flagman; traffic control person

-----

ADAMS, ASHLAND, BARRON, BAYFIELD, BROWN, BUFFALO, BURNETT, CALUMET, CHIPPEWA, CLARK, COLUMBIA, CRAWFORD, DODGE, DOOR, DOUGLAS, DUNN, EAU CLAIRE, FLORENCE, FOND DU LAC, FOREST, GRANT, GREEN, GREEN LAKE, IRON, JACKSON, JUNEAU, IOWA, JEFFERSON, KEWAUNEE, LA CROSSE, LAFAYETTE, LANGLADE, LINCOLN,

<sup>\*</sup> LAB00140-002 06/01/2020

MANITOWOC, MARATHON, MARINETTE, MARQUETTE, MENOMINEE, MONROE, OCONTO, ONEIDA, OUTAGAMIE, PEPIN, PIERCE, POLK, PORTAGE, PRICE, RICHLAND, ROCK, RUSK, SAUK, SAWYER, SHAWANO, SHEBOYGAN, ST. CROIX, TAYLOR, TREMPEALEAU, VERNON, VILLAS, WALWORTH, WASHBURN, WAUPACA, WAUSHARA, WINNEBAGO, AND WOOD COUNTIES

		Rates	Fringes
LABORER			
Group	1\$	33.72	17.95
Group	2\$	33.82	17.95
Group	3\$	33.87	17.95
Group	4\$	34.07	17.95
Group	5\$	33.92	17.95
Group	6\$	30.35	17.95

### LABORER CLASSIFICATIONS

GROUP 1: General Laborer; Tree Trimmer; Conduit Layer; Demolition and Wrecking Laborer; Guard Rail, Fence, and Bridge Builder; Landscaper; Multiplate Culvert Assembler; Stone Handler; Bitminous Worker (Shoveler, Loader, and Utility Man); Batch Truck Dumper or Cement Handler; Bituminous Worker (Dumper, Ironer, Smoother and Tamper); Concrete Handler

GROUP 2: Air Tool Operator; Joint Sawer and Filler (Pavement); Vibrator or Tamper Operator (Mechanical Hand Operated); Chain Saw Operator, Demolition Burning Torch Laborer

GROUP 3: Bituminous Worker (Raker and Luteman); Formsetter (Curb, Sidewalk and Pavement); Strike Off Man

GROUP 4: Line and Grade Secialist

GROUP 5: Blaster; powderman

GROUP 6: Flagperson; Traffic Control

\_\_\_\_\_

DANE COUNTY

	Rates	Fringes
LABORER		
Group 1	\$ 34.00	17.95

<sup>\*</sup> LAB00464-003 06/01/2020

Group	2\$	34.10	17.95
Group	3\$	34.15	17.95
Group	4\$	34.35	17.95
Group	5\$	34.20	17.95
Group	6\$	30.35	17.95

### LABORERS CLASSIFICATIONS:

GROUP 1: General Laborer; Tree Trimmer; Conduit Layer; Demolition and Wrecking Laborer; Guard Rail, Fence, and Bridge Builder; Landscaper; Multiplate Culvert Assembler; Stone Handler; Bituminous Worker (Shoveler, Loader, and Utility Man); Batch Truck Dumper or Cement Handler; Bituminious Worker (Dumper, Ironer, Smoother, and Tamper); Concrete Handler

GROUP 2: Air Tool Operator; Joint Sawer and Filler (Pavement); Vibrator or Tamper Operator (Mechanical Hand Operated); Chain Saw Operator; Demolition Burning Torch Laborer

GROUP 3: Bituminous Worker (Raker and Luteman); Formsetter (Curb, Sidewalk, and Pavement); Strike Off Man

GROUP 4: Line and Grade Specialist

GROUP 5: Blaster; Powderman

GROUP 6: Flagperson and Traffic Control Person

-----

PAIN0106-008 05/01/2017

ASHLAND, BAYFIELD, BURNETT, AND DOUGLAS COUNTIES

	I	Rates	Fringes
Painters:			
New:	5.33	22.22	4= 0=
•	Roller\$		17.27
Spray,	Sandblast, Steel\$	30.93	17.27
Repaint	:		
Brush,	Roller\$	28.83	17.27
Spray,	Sandblast, Steel\$	29.43	17.27

PAIN0108-002 06/01/2019

RACINE COUNTY

Rates Fringes

### Painters:

Brush, Roller	\$ 36.08	20.36
Spray & Sandblast	\$ 37.08	20.36

PAIN0259-002 05/01/2008

BARRON, CHIPPEWA, DUNN, EAU CLAIRE, PEPIN, PIERCE, POLK, RUSK, SAWYER, ST. CROIX, AND WASHBURN COUNTIES

	Rates	Fringes
PAINTER	\$ 24.11	12.15
PAIN0259-004 05/01/2015		

BUFFALO, CRAWFORD, JACKSON, LA CROSSE, MONROE, TREMPEALEAU, AND VERNON COUNTIES

	Rates	Fringes
PAINTER	\$ 22.03	12.45
PAIN0781-002 06/01/2019		

JEFFERSON, MILWAUKEE, OZAUKEE, WASHINGTON, AND WAUKESHA COUNTIES

l l	Rates	Fringes
Painters:		
Bridge\$	33.30	23.86
Brush\$	32.95	23.86
Spray & Sandblast\$	33.70	23.86

PAIN0802-002 06/01/2019

COLUMBIA, DANE, DODGE, GRANT, GREEN, IOWA, LAFAYETTE, RICHLAND, ROCK, AND SAUK COUNTIES

	Rates	Fringes
PAINTER		
Brush	\$ 30.93	18.44

# PREMIUM PAY:

Structural Steel, Spray, Bridges = \$1.00 additional per hour.

-----

# PAIN0802-003 06/01/2019

ADAMS, BROWN, CALUMET, CLARK, DOOR, FOND DU LAC, FOREST, GREEN LAKE, IRON, JUNEAU, KEWAUNEE, LANGLADE, LINCOLN, MANITOWOC, MARATHON, MARINETTE, MARQUETTE, MENOMINEE, OCONTO, ONEIDA, OUTAGAMIE, PORTAGE, PRICE, SHAWANO, SHEBOYGAN, TAYLOR, VILAS, WAUSHARA, WAUPACA, WINNEBAGO, AND WOOD COUNTIES

	Rates	Fringes			
PAINTER	.\$ 30.93	18.58			
PAIN0934-001 06/01/2017					
KENOSHA AND WALWORTH COUNTIES					
	Rates	Fringes			
Painters: Brush Spray Structural Steel	.\$ 34.74	18.95 18.95 18.95			
PAIN1011-002 06/02/2019					
FLORENCE COUNTY					
	Rates	Fringes			
Painters:	•	13.33			
PLAS0599-010 06/01/2017					
	Rates	Fringes			
CEMENT MASON/CONCRETE FINISHER Area 1	.\$ 35.07 .\$ 35.61 .\$ 34.70 .\$ 36.27	17.17 19.75 19.40 20.51 18.73			
Area 6	.\$ 32.02	22.99			

# AREA DESCRIPTIONS

AREA 1: BAYFIELD, DOUGLAS, PRICE, SAWYER, AND WASHBURN COUNTIES

AREA 2: ADAMS, ASHLAND, BARRON, BROWN, BURNETT, CALUMET, CHIPPEWA, CLARK, COLUMBIA, DODGE, DOOR, DUNN, FLORENCE, FOND DU LAC, FOREST, GREEN LAKE, IRON, JEFFERSON, KEWAUNEE, LANGLADE, LINCOLN, MANITOWOC, MARATHON, MARINETTE, MARQUETTE, MENOMINEE, OCONTO, ONEIDA, OUTAGAMIE, POLK, PORTAGE, RUSK, ST CROIX, SAUK, SHAWANO, SHEBOYGAN, TAYLOR, VILAS, WALWORTH, WAUPACA, WAUSHARA, WINNEBAGO, AND WOOD COUNTIES

AREA 3: BUFFALO, CRAWFORD, EAU CLAIRE, JACKSON, JUNEAU, LA CROSSE MONROE, PEPIN, PIERCE, RICHLAND, TREMPEALEAU, AND VERNON COUNTIES

AREA 4: MILWAUKEE, OZAUKEE, WASHINGTON, AND WAUKESHA COUNTIES

AREA 5: DANE, GRANT, GREEN, IOWA, LAFAYETTE, AND ROCK COUNTIES

AREA 6: KENOSHA AND RACINE COUNTIES

-----

<sup>\*</sup> TEAM0039-001 06/01/2020

	Rates	Fringes
TRUCK DRIVER  1 & 2 Axles  3 or more Axles; Euclids, Dumptor & Articulated,	\$ 31.07	22.94
Truck Mechanic	\$ 31.22	22.94
WELL DRILLER	\$ 16.52	3.70

WELDERS - Receive rate prescribed for craft performing operation to which welding is incidental.

Note: Executive Order (EO) 13706, Establishing Paid Sick Leave for Federal Contractors applies to all contracts subject to the Davis-Bacon Act for which the contract is awarded (and any solicitation was issued) on or after January 1, 2017. If this contract is covered by the EO, the contractor must provide employees with 1 hour of paid sick leave for every 30 hours they work, up to 56 hours of paid sick leave each year. Employees must be permitted to use paid sick leave for their own illness, injury or other health-related needs, including

preventive care; to assist a family member (or person who is like family to the employee) who is ill, injured, or has other health-related needs, including preventive care; or for reasons resulting from, or to assist a family member (or person who is like family to the employee) who is a victim of, domestic violence, sexual assault, or stalking. Additional information on contractor requirements and worker protections under the EO is available at www.dol.gov/whd/govcontracts.

Unlisted classifications needed for work not included within the scope of the classifications listed may be added after award only as provided in the labor standards contract clauses (29CFR 5.5 (a) (1) (ii)).

-----

The body of each wage determination lists the classification and wage rates that have been found to be prevailing for the cited type(s) of construction in the area covered by the wage determination. The classifications are listed in alphabetical order of ""identifiers"" that indicate whether the particular rate is a union rate (current union negotiated rate for local), a survey rate (weighted average rate) or a union average rate (weighted union average rate).

### Union Rate Identifiers

A four letter classification abbreviation identifier enclosed in dotted lines beginning with characters other than ""SU"" or ""UAVG"" denotes that the union classification and rate were prevailing for that classification in the survey. Example: PLUM0198-005 07/01/2014. PLUM is an abbreviation identifier of the union which prevailed in the survey for this classification, which in this example would be Plumbers. 0198 indicates the local union number or district council number where applicable, i.e., Plumbers Local 0198. The next number, 005 in the example, is an internal number used in processing the wage determination. 07/01/2014 is the effective date of the most current negotiated rate, which in this example is July 1, 2014.

Union prevailing wage rates are updated to reflect all rate changes in the collective bargaining agreement (CBA) governing this classification and rate.

Survey Rate Identifiers

Classifications listed under the ""SU"" identifier indicate that

no one rate prevailed for this classification in the survey and the published rate is derived by computing a weighted average rate based on all the rates reported in the survey for that classification. As this weighted average rate includes all rates reported in the survey, it may include both union and non-union rates. Example: SULA2012-007 5/13/2014. SU indicates the rates are survey rates based on a weighted average calculation of rates and are not majority rates. LA indicates the State of Louisiana. 2012 is the year of survey on which these classifications and rates are based. The next number, 007 in the example, is an internal number used in producing the wage determination. 5/13/2014 indicates the survey completion date for the classifications and rates under that identifier.

Survey wage rates are not updated and remain in effect until a new survey is conducted.

Union Average Rate Identifiers

Classification(s) listed under the UAVG identifier indicate that no single majority rate prevailed for those classifications; however, 100% of the data reported for the classifications was union data. EXAMPLE: UAVG-OH-0010 08/29/2014. UAVG indicates that the rate is a weighted union average rate. OH indicates the state. The next number, 0010 in the example, is an internal number used in producing the wage determination. 08/29/2014 indicates the survey completion date for the classifications and rates under that identifier.

A UAVG rate will be updated once a year, usually in January of each year, to reflect a weighted average of the current negotiated/CBA rate of the union locals from which the rate is based.

-----

### WAGE DETERMINATION APPEALS PROCESS

- 1.) Has there been an initial decision in the matter? This can be:
- \* an existing published wage determination
- \* a survey underlying a wage determination
- \* a Wage and Hour Division letter setting forth a position on a wage determination matter
- $^st$  a conformance (additional classification and rate) ruling

On survey related matters, initial contact, including requests

for summaries of surveys, should be with the Wage and Hour Regional Office for the area in which the survey was conducted because those Regional Offices have responsibility for the Davis-Bacon survey program. If the response from this initial contact is not satisfactory, then the process described in 2.) and 3.) should be followed.

With regard to any other matter not yet ripe for the formal process described here, initial contact should be with the Branch of Construction Wage Determinations. Write to:

Branch of Construction Wage Determinations Wage and Hour Division U.S. Department of Labor 200 Constitution Avenue, N.W. Washington, DC 20210

2.) If the answer to the question in 1.) is yes, then an interested party (those affected by the action) can request review and reconsideration from the Wage and Hour Administrator (See 29 CFR Part 1.8 and 29 CFR Part 7). Write to:

Wage and Hour Administrator U.S. Department of Labor 200 Constitution Avenue, N.W. Washington, DC 20210

The request should be accompanied by a full statement of the interested party's position and by any information (wage payment data, project description, area practice material, etc.) that the requestor considers relevant to the issue.

3.) If the decision of the Administrator is not favorable, an interested party may appeal directly to the Administrative Review Board (formerly the Wage Appeals Board). Write to:

Administrative Review Board U.S. Department of Labor 200 Constitution Avenue, N.W. Washington, DC 20210

4.) All decisions by the Administrative Review Board are final.

\_\_\_\_\_\_

END OF GENERAL DECISION"

# NOTICE TO BIDDERS WAGE RATE DECISION

The wage rate decision of the Department of Labor which has been incorporated in these advertised specifications is incomplete in that the classifications may be omitted from the Department of Labor's decision.


Since the bidder is responsible, independently, for ascertaining area practice with respect to the necessity, or lack of necessity, for the use of these classifications in the prosecution of the work contemplated by this project, no inference may be drawn from the omission of these classifications concerning prevailing area practices relative to their use. Further, this omission will not, per se, be construed as establishing any governmental liability for increased labor cost if it is subsequently determined that such classifications are required.

There may be omissions and/or errors in the federal wage rates. The bidder is responsible for evaluating and determining the correct applicable rate.

If a project includes multiple types of construction (highway, bridge over navigable water, sanitary sewer and water main, building) and there is not a separate wage determination for this type of work included in the proposal, use the wage determination that is in the proposal.

If a project includes multiple types of construction, different wage rate determinations may be inserted into the contract (WI10/Highway = in all WisDOT highway contracts, WI15/Heavy = bridge over navigable water per USDOL and US Coast Guard designation, WI8/Heavy (Sewer & Water Line & Tunnel) = sanitary sewer and water main if the cost is more than 20% of the contract and/or at least \$1,000,000, and Building). If multiple wage rate determinations are inserted into the contract, use the classification in the wage determination for the work being done. Use WI15 wage rates when working on the bridge and/or structure from bank to bank. Use WI8 wage rates when working on any sanitary sewer or water main work. Use Building wage rates for all work done within the footprint of the building. Use WI10 wage rates for all other highway work in the contract and approaches to structures. For example, if a laborer is working within the footprint of a building, use the Laborer rate in the Building wage determination inserted in the contract. If a laborer is working on a bridge/structure within the banks, use the Laborer rate in the WI15/Heavy wage determination if inserted in the contract. If the laborer is working on the highway, use the Laborer rate in the WI10/Highway wage determination.







Page 1 of 9


Proposal ID: 20200915004 Project(s): 1228-28-70

Federal ID(s): WISC 2020412

SECTION: 0001 Contract Items

Proposal Line Number	Item ID  Description	Approximate Quantity and Units	Unit Price	Bid Amount
0002	204.0100 Removing Concrete Pavement	3,248.000 SY		
0004	204.0150 Removing Curb & Gutter	1,830.000 LF		
0006	204.0155 Removing Concrete Sidewalk	462.000 SY		
8000	204.0220 Removing Inlets	1.000 EACH		
0010	204.9060.S Removing (item description) 1000. Removing Luminaries	120.000 EACH	·	·
0012	205.0100 Excavation Common	2,015.000 CY		
0014	213.0100 Finishing Roadway (project) 0001. 1228- 28-70	1.000 EACH	·	·
0016	305.0120 Base Aggregate Dense 1 1/4-Inch	1,396.000 TON		
0018	415.0080 Concrete Pavement 8-Inch	2,358.000 SY		
0020	415.0410 Concrete Pavement Approach Slab	936.000 SY		·
0022	416.0610 Drilled Tie Bars	145.000 EACH		
0024	416.0620 Drilled Dowel Bars	100.000 EACH		·
0026	495.1000.S Cold patch	10.000 TON		
0028	502.3101 Expansion Device 0001. B-40-429	262.000 LF		
0030	502.3200 Protective Surface Treatment	9,583.000 SY		<u>-</u>
0032	502.3210 Pigmented Surface Sealer	9.000 SY		







Page 2 of 9


Proposal ID: 20200915004 Project(s): 1228-28-70

Federal ID(s): WISC 2020412

SECTION: 0001 Contract Items

Proposal Line Number	Item ID  Description	Approximate Quantity and Units	Unit Price	Bid Amount
0034	502.4205 Adhesive Anchors No. 5 Bar	264.000 EACH		·
0036	505.0600  Bar Steel Reinforcement HS Coated Structures	7,690.000 LB		·
0038	509.0301 Preparation Decks Type 1	477.000 SY		·
0040	509.0302 Preparation Decks Type 2	191.000 SY		
0042	509.0310.S Sawing Pavement Deck Preparation Areas	24.000 LF		·
0044	509.0500 Cleaning Decks	4,906.000 SY		
0046	509.0505.S Cleaning Decks to Reapply Concrete Masonry Overlay	625.000 SY		·
0048	509.1000 Joint Repair	120.000 SY		
0050	509.1200 Curb Repair	33.000 LF		<u> </u>
0052	509.1500 Concrete Surface Repair	160.000 SF		
0054	509.2000 Full-Depth Deck Repair	80.000 SY	·	
0056	509.2100.S Concrete Masonry Deck Repair	1.000 CY		
0058	509.2500 Concrete Masonry Overlay Decks	721.000 CY		
0060	509.5100.S Polymer Overlay	19,089.000 SY		
0062	509.9005.S Removing Concrete Masonry Deck Overlay (structure) 0001. B-40-292	625.000 SY		·







Page 3 of 9

Proposal ID: 20200915004 Project(s): 1228-28-70

Federal ID(s): WISC 2020412

SECTION: 0001 Contract Items

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0064	509.9010.S Removing Asphaltic Concrete Deck Overlay (structure) 0001. B-40-292	2,639.000 SY		·
0066	517.0900.S Preparation and Coating of Top Flanges (structure) 0001. B-40-429	LS	LUMP SUM	
0068	517.1010.S Concrete Staining (structure) 4001. B-40- 292	82,031.000 SF		·
0070	517.1010.S Concrete Staining (structure) 4002. B-40- 293	91,194.000 SF	<del></del>	
0072	517.1800.S Structure Repainting Recycled Abrasive (structure) 0001. B-40-429	LS	LUMP SUM	
0074	517.4500.S Negative Pressure Containment and Collection of Waste Materials (structure) 0001. B-40-429	LS	LUMP SUM	
0076	517.6001.S Portable Decontamination Facility	1.000 EACH		
0078	601.0411 Concrete Curb & Gutter 30-Inch Type D	1,830.000 LF	·	·
0080	602.0410 Concrete Sidewalk 5-Inch	3,600.000 SF		
0082	602.0505 Curb Ramp Detectable Warning Field Yellow	104.000 SF	<u></u>	
0084	602.0605 Curb Ramp Detectable Warning Field Radial Yellow	51.000 SF		
0086	608.0412 Storm Sewer Pipe Reinforced Concrete Class IV 12-Inch	20.000 LF	·	
0088	611.0624 Inlet Covers Type H	1.000 EACH		
0090	611.0651 Inlet Covers Type S	1.000 EACH	·	





# Proposal Schedule of Items

Page 4 of 9

Proposal ID: 20200915004 Project(s): 1228-28-70

Federal ID(s): WISC 2020412

SECTION: 0001 Contract Items

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0092	611.3003 Inlets 3-FT Diameter	2.000 EACH		
0094	619.1000 Mobilization	1.000 EACH		
0096	624.0100 Water	30.000 MGAL	<u>-</u>	
0098	625.0100 Topsoil	751.000 SY		
0100	628.1905 Mobilizations Erosion Control	2.000 EACH		
0102	628.1910 Mobilizations Emergency Erosion Control	1.000 EACH		
0104	628.7005 Inlet Protection Type A	6.000 EACH		
0106	628.7015 Inlet Protection Type C	4.000 EACH		
0108	628.7020 Inlet Protection Type D	55.000 EACH		
0110	628.7560 Tracking Pads	1.000 EACH		
0112	629.0210 Fertilizer Type B	1.000 CWT		
0114	630.0200 Seeding Temporary	2.000 LB		
0116	631.1000 Sod Lawn	751.000 SY		
0118	634.0618 Posts Wood 4x6-Inch X 18-FT	13.000 EACH		
0120	634.0818 Posts Tubular Steel 2x2-Inch X 18-FT	2.000 EACH		
0122	637.2210 Signs Type II Reflective H	163.750 SF		
0124	637.2230 Signs Type II Reflective F	8.250 SF		





# Proposal Schedule of Items

Page 5 of 9

Proposal ID: 20200915004 Project(s): 1228-28-70

Federal ID(s): WISC 2020412

SECTION: 0001 Contract Items

Proposal Line Number	Item ID  Description	Approximate Quantity and Units	Unit Price	Bid Amount
0126	638.2602 Removing Signs Type II	16.000 EACH		
0128	638.3000 Removing Small Sign Supports	14.000 EACH		
0130	643.0300 Traffic Control Drums	20,428.000 DAY		
0132	643.0420 Traffic Control Barricades Type III	3,332.000 DAY		
0134	643.0705 Traffic Control Warning Lights Type A	2,448.000 DAY		
0136	643.0715 Traffic Control Warning Lights Type C	3,238.000 DAY		·
0138	643.0800 Traffic Control Arrow Boards	454.000 DAY		
0140	643.0900 Traffic Control Signs	14,539.000 DAY		·
0142	643.0910 Traffic Control Covering Signs Type I	2.000 EACH		
0144	643.1000 Traffic Control Signs Fixed Message	350.000 SF		
0146	643.1050 Traffic Control Signs PCMS	228.000 DAY		
0148	643.4100.S Traffic Control Interim Lane Closure	10.000 EACH		
0150	643.5000 Traffic Control	1.000 EACH		
0152	644.1810 Temporary Pedestrian Barricade	550.000 LF		
0154	646.1020 Marking Line Epoxy 4-Inch	25,952.000 LF		
0156	646.3020 Marking Line Epoxy 8-Inch	2,642.000 LF		·







Page 6 of 9

Proposal ID: 20200915004 Project(s): 1228-28-70

Federal ID(s): WISC 2020412

SECTION: 0001 Contract Items

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0158	646.3545 Marking Line Grooved Wet Ref Contrast Epoxy 8-Inch	2,190.000 LF		·
0160	646.5020 Marking Arrow Epoxy	31.000 EACH	<u> </u>	
0162	646.5120 Marking Word Epoxy	22.000 EACH		
0164	646.6020 Marking Stop Line Epoxy 12-Inch	555.000 LF		
0166	646.6120 Marking Stop Line Epoxy 18-Inch	45.000 LF		
0168	646.7120 Marking Diagonal Epoxy 12-Inch	629.000 LF		<u>.</u>
0170	646.7220 Marking Chevron Epoxy 24-Inch	355.000 LF		
0172	646.7420 Marking Crosswalk Epoxy Transverse Line 6-Inch	1,845.000 LF		
0174	646.8120 Marking Curb Epoxy	269.000 LF		
0176	646.8220 Marking Island Nose Epoxy	4.000 EACH		
0178	650.4000 Construction Staking Storm Sewer	1.000 EACH	<u></u> .	
0180	650.7000 Construction Staking Concrete Pavement	815.000 LF	·	·
0182	650.9910 Construction Staking Supplemental Control (project) 0001. 1228-28-70	LS	LUMP SUM	
0184	652.0125 Conduit Rigid Metallic 2-Inch	36.000 LF		·
0186	655.0144 Cable In Duct 4-4 AWG	300.000 LF		
0188	655.0146 Cable In Duct 4-6 AWG	300.000 LF		





# Proposal Schedule of Items

Page 7 of 9

Proposal ID: 20200915004 Project(s): 1228-28-70

Federal ID(s): WISC 2020412

SECTION: 0001 Contract Items

Proposal Line Number	Item ID  Description	Approximate Quantity and Units	Unit Price	Bid Amount
0190	655.0610 Electrical Wire Lighting 12 AWG	200.000 LF		
0192	659.1125 Luminaires Utility LED C	56.000 EACH		
0194	659.1130 Luminaires Utility LED D	36.000 EACH		<u> </u>
0196	659.1210 Luminaires Underdeck LED B	13.000 EACH		
0198	690.0250 Sawing Concrete	910.000 LF		
0200	715.0415 Incentive Strength Concrete Pavement	1,000.000 DOL	1.00000	1,000.00
0202	ASP.1T0A On-the-Job Training Apprentice at \$5.00/HR	1,500.000 HRS	5.00000	7,500.00
0204	ASP.1T0G On-the-Job Training Graduate at \$5.00/HR	1,500.000 HRS	5.00000	7,500.00
0206	SPV.0060 Special 0003. Temporary Bus Stop Pad	4.000 EACH		·
0208	SPV.0060 Special 1001. Fuse Holders	20.000 EACH		
0210	SPV.0060 Special 1002. Fuses Type FNQ	120.000 EACH		
0212	SPV.0060 Special 1003. Distribution Center Prentive Maintenance	2.000 EACH		·
0214	SPV.0060 Special 1004. Tunnel Luminaries Maintenance 150 Watt HPS	51.000 EACH	·	·
0216	SPV.0060 Special 1005. Tunnel Luminaries Maintenance 200 Watt HPS	89.000 EACH		·
0218	SPV.0060 Special 1006. Tunnel Luminaries Maintenance 250 Watt HPS	12.000 EACH		





# Proposal Schedule of Items

Page 8 of 9

Proposal ID: 20200915004 Project(s): 1228-28-70

Federal ID(s): WISC 2020412

SECTION: 0001 Contract Items

Proposal	Item ID	Approximate	II. ii Bi	D: L4
Line Number	Description	Quantity and Units	Unit Price	Bid Amount
0220	SPV.0060 Special 1007. Tunnel Luminaries Maintenance 400 Watt HPS	168.000 EACH		·
0222	SPV.0060 Special 1008. Group Clean Tunnel Luminaries	320.000 EACH		·
0224	SPV.0060 Special 1009. Group Luminaries Maintenance Sign Light 250 W MV	15.000 EACH	·	·
0226	SPV.0060 Special 4001. Cleaning and Painting Bearings	32.000 EACH		·
0228	SPV.0060 Special 4112. Protect Existing Light Fixtures and Utilities B-40-292	1.000 EACH		
0230	SPV.0060 Special 4122. Protect Existing Light Fixtures and Utilities B-40-293	1.000 EACH		
0232	SPV.0060 Special 4131. Temporary Lighting and Ventilation B-40-292	1.000 EACH		
0234	SPV.0060 Special 4141. Temporary Lighting and Ventilation B-40-293	1.000 EACH		·
0236	SPV.0060 Special 5001. Adjusting TES Manhole Cover	2.000 EACH		
0238	SPV.0060 Special 5002. Adjusting Water Boxes	1.000 EACH		
0240	SPV.0060 Special 5003. Field Facilities Office Space	1.000 EACH		
0242	SPV.0060 Special 5004. Traffic Control Close-Open Freeway Entrance Ramp	2.000 EACH		
0244	SPV.0075 Special 0003. Pavement Cleanup Project 1228-28-70	100.000 HRS		·





# Proposal Schedule of Items

Page 9 of 9

Proposal ID: 20200915004 Project(s): 1228-28-70

Federal ID(s): WISC 2020412

SECTION: 0001 Contract Items

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0246	SPV.0090 Special 0001. Pavement Marking Contrast Epoxy 4-Inch	844.000 LF		
0248	SPV.0090 Special 0002. Pavement Marking Contrast Epoxy 8-Inch	859.000 LF		·
0250	SPV.0090 Special 4002. Ventilation Opening Edge Repair	75.000 LF		
0252	SPV.0105 Special 4105. Remove and Replace Sidewalk Cover Plate	LS	LUMP SUM	
0254	SPV.0105 Special 4205. Slip-Resistant Treatment Of Sidewalk Cover Plate B-40-686	LS	LUMP SUM	
0256	SPV.0105 Special 4305. Slip-Resistant Treatment Of Sidewalk Cover Plate B-40-689	LS	LUMP SUM	
0258	SPV.0165 Special 4202. Shotcrete Surface Repair	1,965.000 SF		
0260	SPV.0180 Special 4301. Cleaning Tunnel Wall and Ceiling	19,238.000 SY		
0262	SPV.0180 Special 4302. Hydro-Demolition of Concrete Masonry Deck Overlay B-40- 293	3,968.000 SY		
	Section: 000	1	Total:	·
			Total Bid:	<u> </u>

# PLEASE ATTACH SCHEDULE OF ITEMS HERE



# **Wisconsin Department of Transportation**

September 8, 2020

### Division of Transportation Systems Development

Bureau of Project Development 4822 Madison Yards Way, 4<sup>th</sup> Floor South Madison, WI 53705

Telephone: (608) 266-1631 Facsimile (FAX): (608) 266-8459

# **NOTICE TO ALL CONTRACTORS:**

# Federal Wage Rate Addendum #01

# Letting of September 15, 2020

Attached is a copy of the revised WI 10 Highway Davis Bacon Prevailing Wage Rates that are included in proposals 01. 02, 04 - 08, and 10 - 17; and WI 15 Heavy Davis Bacon Prevailing Wage Rates that are included in proposals 01 and 13. These wage rates are effective for all proposals they are included in in the September 15, 2020 letting. The updated wage rates are dated August 28, 2020 and are effective on or after September 7, 2020.

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractors.

Sincerely,

Mike Coleman

Proposal Development Specialist Proposal Management Section

"General Decision Number: WI20200010 08/28/2020

Superseded General Decision Number: WI20190010

State: Wisconsin

Construction Type: Highway

Counties: Wisconsin Statewide.

HIGHWAY, AIRPORT RUNWAY & TAXIWAY CONSTRUCTION PROJECTS (does not include bridges over navigable waters; tunnels; buildings in highway rest areas; and railroad construction)

Note: Under Executive Order (EO) 13658, an hourly minimum wage of \$10.80 for calendar year 2020 applies to all contracts subject to the Davis-Bacon Act for which the contract is awarded (and any solicitation was issued) on or after January 1, 2015. If this contract is covered by the EO, the contractor must pay all workers in any classification listed on this wage determination at least \$10.80 per hour (or the applicable wage rate listed on this wage determination, if it is higher) for all hours spent performing on the contract in calendar year 2020. If this contract is covered by the EO and a classification considered necessary for performance of work on the contract does not appear on this wage determination, the contractor must pay workers in that classification at least the wage rate determined through the conformance process set forth in 29 CFR 5.5(a)(1)(ii) (or the EO minimum wage rate, if it is higher than the conformed wage rate). The EO minimum wage rate will be adjusted annually. Please note that this EO applies to the above-mentioned types of contracts entered into by the federal government that are subject to the Davis-Bacon Act itself, but it does not apply to contracts subject only to the Davis-Bacon Related Acts, including those set forth at 29 CFR 5.1(a)(2)-(60). Additional information on contractor requirements and worker protections under the EO is available at www.dol.gov/whd/govcontracts.

Number	Publication Da	ate
	01/03/2020	
	01/24/2020	
	02/28/2020	
	03/06/2020	
	06/05/2020	
	06/12/2020	
	06/19/2020	
	07/17/2020	
	08/28/2020	
	Number	01/03/2020 01/24/2020 02/28/2020 03/06/2020 06/05/2020 06/12/2020 06/19/2020 07/17/2020

# BRWI0001-002 06/03/2019

CRAWFORD, JACKSON, JUNEAU, LA CROSSE, MONROE, TREMPEALEAU, AND VERNON COUNTIES

	Rates	Fringes				
BRICKLAYER	\$ 33.80	24.28				
BRWI0002-002 06/01/2019						
ASHLAND, BAYFIELD, DOUGLAS, AND IRON COUNTIES						
	Rates	Fringes				
BRICKLAYER	\$ 39.94	23.30				
BRWI0002-005 06/01/2019						
ADAMS, ASHLAND, BARRON, BROWN, BURNETT, CALUMET, CHIPPEWA, CLARK, COLUMBIA, DODGE, DOOR, DUNN, FLORENCE, FOND DU LAC, FOREST, GREEN LAKE, IRON, JEFFERSON, KEWAUNEE, LANGLADE, LINCOLN, MANITOWOC, MARATHON, MARINETTE, MARQUETTE, MENOMINEE, OCONTO, ONEIDA, OUTAGAMIE, POLK, PORTAGE, RUSK, ST CROIX, SAUK, SHAWANO, SHEBOYGAN, TAYLOR, VILAS, WALWORTH, WAUPACA, WAUSHARA, WINNEBAGO, AND WOOD COUNTIES						
	Rates	Fringes				
CEMENT MASON/CONCRETE FINISHER.						
CEMENT MASON/CONCRETE FINISHER. BRWI0003-002 06/03/2019						
	\$ 35.51	23.37				
BRWI0003-002 06/03/2019	\$ 35.51	23.37				
BRWI0003-002 06/03/2019	\$ 35.51 , , MARINETTE, Rates	23.37  AND OCONTO COUNTIES				
BRWI0003-002 06/03/2019 BROWN, DOOR, FLORENCE, KEWAUNEE	\$ 35.51 , , MARINETTE, Rates	23.37  AND OCONTO COUNTIES  Fringes				
BRWI0003-002 06/03/2019  BROWN, DOOR, FLORENCE, KEWAUNEE  BRICKLAYER	\$ 35.51 , MARINETTE, Rates \$ 34.18	23.37  AND OCONTO COUNTIES  Fringes				
BRWI0003-002 06/03/2019  BROWN, DOOR, FLORENCE, KEWAUNEE  BRICKLAYER	\$ 35.51 , MARINETTE, Rates \$ 34.18	23.37  AND OCONTO COUNTIES  Fringes				

# BRWI0006-002 06/01/2019

ADAMS, CLARK, FOREST, LANGLADE, LINCOLN, MARATHON, MENOMINEE, ONEIDA, PORTAGE, PRICE, TAYLOR, VILAS AND WOOD COUNTIES

	Rates	Fringes				
BRICKLAYER	.\$ 35.06	23.02				
BRWI0007-002 06/03/2019						
GREEN, LAFAYETTE, AND ROCK COUNTIES						
	Rates	Fringes				
BRICKLAYER	.\$ 35.57	24.22				
BRWI0008-002 06/01/2019						
MILWAUKEE, OZAUKEE, WASHINGTON, AND WAUKESHA COUNTIES						
	Rates	Fringes				
BRICKLAYER	.\$ 38.93	24.22				
BRWI0011-002 06/03/2019						
CALUMET, FOND DU LAC, MANITOWOC, AND SHEBOYGAN COUNTIES						
	Rates	Fringes				
BRICKLAYER	.\$ 34.18	23.90				
BRWI0019-002 06/03/2019						
BARRON, BUFFALO, BURNETT, CHIPPEWA, DUNN, EAU CLAIRE, PEPIN, PIERCE, POLK, RUSK, ST. CROIX, SAWYER AND WASHBURN COUNTIES						
	Rates	Fringes				
BRICKLAYER	.\$ 33.40	24.68				
BRWI0034-002 06/03/2019						
COLUMBIA AND SAUK COUNTIES						

Rates Fringes

BRICKLAYER.....\$ 35.56 24.23

CARP0087-001 05/01/2016

BURNETT (W. of Hwy 48), PIERCE (W. of Hwy 29), POLK (W. of Hwys 35, 48 & 65), AND ST. CROIX (W. of Hwy 65) COUNTIES

	Rates	Fringes
Carpenter & Piledrivermen	\$ 36.85	18.39
CARP0252-002 06/01/2016		

ADAMS, BARRON, BAYFIELD (Eastern 2/3), BROWN, BUFFALO, BURNETT (E. of Hwy 48), CALUMET, CHIPPEWA, CLARK, COLUMBIA, CRAWFORD, DANE, DODGE, DOOR, DUNN, EAU CLAIRE, FLORENCE (except area bordering Michigan State Line), FOND DU LAC, FOREST, GRANT, GREEN, GREEN LAKE, IOWA, IRON, JACKSON, JEFFERSON, JUNEAU, KEWAUNEE, LA CROSSE, LAFAYETTE, LANGLADE, LINCOLN, MANITOWOC, MARATHON, MARINETTE (except N.E. corner), MARQUETTE, MENOMINEE, MONROE, OCONTO, ONEIDA, OUTAGAMIE, PEPIN, PIERCE (E. of Hwys 29 & 65), POLK (E. of Hwys 35, 48 & 65), PORTAGE, PRICE, RICHLAND, ROCK, RUSK, SAUK, SAWYER, SHAWANO, SHEBOYGAN, ST CROIX (E. of Hwy 65), TAYLOR, TREMPEALEAU, VERNON, VILAS, WALWORTH, WASHBURN, WAUPACA, WAUSHARA, WINNEBAGO, AND WOOD COUNTIES

	Rates	Fringes	
CARPENTER			
CARPENTER	\$ 33.56	18.00	
MILLWRIGHT	\$ 35.08	18.35	
PILEDRIVER	\$ 34.12	18.00	
			-

CARP0252-010 06/01/2016

ASHLAND COUNTY

	Rates	Fringes	
Carpenters			
Carpenter	\$ 33.56	18.00	
Millwright	\$ 35.08	18.35	
Pile Driver	\$ 34.12	18.00	

CARP0264-003 06/01/2016

KENOSHA, MILWAUKEE, OZAUKEE, RACINE, WAUKESHA, AND WASHINGTON

# COUNTIES

	Rates	Fringes
CARPENTER		22.11
CARP0361-004 05/01/2018		
BAYFIELD (West of Hwy 63) AND DOL	JGLAS COUNTIES	
	Rates	Fringes
CARPENTER	\$ 36.15	20.43
CARP2337-001 06/01/2016		
ZONE A: MILWAUKEE, OZAUKEE, WAUKE	SHA AND WASHING	TON
ZONE B: KENOSHA & RACINE		
	Rates	Fringes
PILEDRIVERMAN Zone A		22.69 22.69
* ELEC0014-002 06/14/2020		
ASHLAND, BARRON, BAYFIELD, BUFFAL (except Maryville, Colby, Unity, Sherwood), CRAWFORD, DUNN, EAU CL CROSSE, MONROE, PEPIN, PIERCE, PC CROIX, SAWYER, TAYLOR, TREMPEALEA COUNTIES	Sherman, Fremon AIRE, GRANT, IR DLK, PRICE, RICH	t, Lynn & ON, JACKSON, LA ILAND, RUSK, ST
	Rates	Fringes
Electricians:	•	20.98
* ELEC0014-007 07/05/2020		
REMAINING COUNTIES		
	Rates	Fringes
Teledata System Installer Installer/Technician	\$ 27.75	15.14

Low voltage construction, installation, maintenance and removal of teledata facilities (voice, data, and video) including outside plant, telephone and data inside wire, interconnect, terminal equipment, central offices, PABX, fiber optic cable and equipment, micro waves, V-SAT, bypass, CATV, WAN (wide area networks), LAN (local area networks), and ISDN (integrated systems digital network).

-----

ELEC0127-002 06/01/2020

KENOSHA COUNTY

Rates Fringes

Electricians:.....\$ 41.62 30%+12.70

-----

ELEC0158-002 06/03/2019

BROWN, DOOR, KEWAUNEE, MANITOWOC (except Schleswig), MARINETTE(Wausuakee and area South thereof), OCONTO, MENOMINEE (East of a ine 6 miles West of the West boundary of Oconto County), SHAWANO (Except Area North of Townships of Aniwa and Hutchins) COUNTIES

Rates Fringes

Electricians:.....\$ 33.52 29.75%+10.26

\_\_\_\_\_

ELEC0159-003 06/01/2019

COLUMBIA, DANE, DODGE (Area West of Hwy 26, except Chester and Emmet Townships), GREEN, LAKE (except Townships of Berlin, Seneca, and St. Marie), IOWA, MARQUETTE (except Townships of Neshkoka, Crystal Lake, Newton, and Springfield), and SAUK COUNTIES

Rates Fringes

Electricians:.....\$ 40.30 22.24

-----

ELEC0219-004 06/01/2016

FLORENCE COUNTY (Townships of Aurora, Commonwealth, Fern, Florence and Homestead) AND MARINETTE COUNTY (Township of Niagara)

	Rates	Fringes
Electricians: Electrical contracts over \$180,000	.\$ 32.38	18.63
Electrical contracts under \$180,000	.\$ 30.18	18.42
* ELEC0242-005 05/31/2020	· 	
DOUGLAS COUNTY		
	Rates	Fringes
Electricians:	.\$ 39.77	70.69%
* ELEC0388-002 06/01/2020		
ADAMS, CLARK (Colby, Freemont, Ly Sherwood, Unity), FOREST, JUNEAU MARINETTE (Beecher, Dunbar, Good West of a line 6 miles West of the County), ONEIDA, PORTAGE, SHAWANG AND WOOD COUNTIES	J, LANGLADE, LIN man & Pembine), he West boundary	COLN, MARATHON, MENOMINEE (Area of Oconto
	Rates	Fringes
Electricians:		
21000 2014115	.\$ 34.85	26%+11.20
ELEC0430-002 06/01/2020	.\$ 34.85 	26%+11.20
		26%+11.20
ELEC0430-002 06/01/2020		
ELEC0430-002 06/01/2020	Township) Rates	Fringes
ELEC0430-002 06/01/2020  RACINE COUNTY (Except Burlington	Township) Rates	Fringes
ELEC0430-002 06/01/2020  RACINE COUNTY (Except Burlington Electricians:	Township) Rates .\$ 41.86	Fringes 22.66
ELEC0430-002 06/01/2020  RACINE COUNTY (Except Burlington  Electricians:	Township) Rates .\$ 41.86	Fringes 22.66
ELEC0430-002 06/01/2020  RACINE COUNTY (Except Burlington  Electricians:	Township) Rates .\$ 41.86  AND WAUKESHA COURates .\$ 42.84	Fringes 22.66
ELEC0430-002 06/01/2020  RACINE COUNTY (Except Burlington  Electricians:	Township) Rates .\$ 41.86  AND WAUKESHA COURates .\$ 42.84	Fringes  22.66  INTIES  Fringes

including Chester Township), FOND DU LAC, MANITOWOC
(Schleswig), and SHEBOYGAN COUNTIES

	Rates	Fringes	
Electricians:	\$ 36.32	22.51	
ELEC0494-013 06/07/2020			-

DODGE (East of Hwy 26 including Chester Twp, excluding Emmet Twp), FOND DU LAC (Except Waupuin), MILWAUKEE, OZAUKEE, MANITOWOC (Schleswig), WASHINGTON, AND WAUKESHA COUNTIES

	Rates	Fringes
Sound & Communications		
Installer	\$ 21.46	18.52
Technician	\$ 31.34	20.00

Installation, testing, maintenance, operation and servicing of all sound, intercom, telephone interconnect, closed circuit TV systems, radio systems, background music systems, language laboratories, electronic carillion, antenna distribution systems, clock and program systems and low-voltage systems such as visual nurse call, audio/visual nurse call systems, doctors entrance register systems. Includes all wire and cable carrying audio, visual, data, light and radio frequency signals. Includes the installation of conduit, wiremold, or raceways in existing structures that have been occupied for six months or more where required for the protection of the wire or cable, but does not mean a complete conduit or raceway system. work covered does not include the installation of conduit, wiremold or any raceways in any new construction, or the installation of power supply outlets by means of which external electric power is supplied to any of the foregoing equipment or products

. . .

### ELEC0577-003 06/01/2019

CALUMET (except Township of New Holstein), GREEN LAKE (N. part including Townships of Berlin, St Marie, and Seneca), MARQUETTE (N. part including Townships of Crystal Lake, Neshkoro, Newton, and Springfield), OUTAGAMIE, WAUPACA, WAUSHARA, AND WINNEBAGO COUNTIES

	Rates	Fringes
Electricians:		28.50%+10.00
ELEC0890-003 06/01/2020		
DODGE (Emmet Township only), GRE RACINE (Burlington Township), RC		
	Rates	Fringes
Electricians:		
ELEC0953-001 06/02/2019		
	Rates	Fringes
Line Construction: (1) Lineman	.\$ 47.53	21.43
Operator(3) Equipment Operator		19.80 18.40
(4) Heavy Groundman Driver.	.\$ 33.27	16.88
<ul><li>(5) Light Groundman Driver.</li><li>(6) Groundsman</li></ul>	.\$ 26.14	16.11 14.60
ENGI0139-005 06/01/2020		
	Rates	Fringes
Power Equipment Operator	¢ 44 62	22.00
Group 1 Group 2		23.80 23.80
Group 3	.\$ 40.62	23.80
Group 4		23.80
Group 5 Group 6		23.80 23.80
HAZARDOUS WASTE PREMIUMS: EPA Level ""A"" protection - \$3. EPA Level ""B"" protection - \$2 EPA Level ""C"" protection - \$1.	.00 per hou	n

# POWER EQUIPMENT OPERATORS CLASSIFICATIONS

GROUP 1: Cranes, tower cranes, and derricks with or without attachments with a lifting capacity of over 100 tons; or cranes, tower cranes, and derricks with boom, leads and/or jib lengths measuring 176 feet or longer.

GROUP 2: Cranes, tower cranes and derricks with or without attachments with a lifting capacity of 100 tons or less; or cranes, tower cranes, and derricks with boom, leads, and/or jibs lengths measuring 175 feet or under and Backhoes (excavators) weighing 130,000 lbs and over; caisson rigs; pile driver; dredge operator; dredge engineer; Boat Pilot.

GROUP 3: Mechanic or welder - Heavy duty equipment; cranes with a lifting capacity of 25 tons or under; concrete breaker (manual or remote); vibratory/sonic concrete breaker; concrete laser screed; concrete slipform paver; concrete batch plant operator; concrete pvt. spreader heavy duty (rubber tired); concrete spreader & distributor; automatic subgrader (concrete); concrete grinder & planing machine; concrete slipform curb & gutter machine; slipform concrete placer; tube finisher; hydro blaster (10,000 psi & over); bridge paver; concrete conveyor system; concrete pump; Rotec type Conveyor; stabilizing mixer (self-propelled); shoulder widener; asphalt plant engineer; bituminious paver; bump cutter & grooving machine; milling machine; screed (bituminous paver); asphalt heater, planer & scarifier; Backhoes (excavators) weighing under 130,000 lbs; grader or motor patrol; tractor (scraper, dozer, pusher, loader); scraper - rubber tired (single or twin engine); endloader; hydraulic backhoe (tractor type); trenching machine; skid rigs; tractor, side boom (heavy); drilling or boring machine (mechanical heavy); roller over 5 tons; percussion or rotary drilling machine; air track; blaster; loading machine (conveyor); tugger; boatmen; winches & A-frames; post driver; material hoist.

GROUP 4: Greaser, roller steel (5 tons or less); roller (pneumatic tired) - self propelled; tractor (mounted or towed compactors & light equipment); shouldering machine; self- propelled chip spreader; concrete spreader; finishing machine; mechanical float; curing machine; power subgrader; joint sawer (multiple blade) belting machine; burlap machine; texturing machine; tractor endloader (rubber tired) - light; jeep digger; forklift; mulcher; launch operator; fireman, environmental burner

GROUP 5: Air compressor; power pack; vibrator hammer and extractor; heavy equipment, leadman; tank car heaters; stump chipper; curb machine operator; Concrete proportioning plants; generators; mudjack operator; rock breaker; crusher or screening plant; screed (milling machine); automatic belt conveyor and surge bin; pug mill operator; Oiler, pump (over 3 inches); Drilling Machine Tender.

GROUP 6: Off-road material hauler with or without ejector.

-----

IRON0008-002 06/01/2020

BROWN, CALUMET, DOOR, FOND DU LAC, KEWAUNEE, MANITOWOC, MARINETTE, OCONTO, OUTAGAMI, SHAWANO, SHEBOYGAN, AND WINNEBAGO COUNTIES:

Rates Fringes

IRONWORKER.....\$ 37.31 27.62

Paid Holidays: New Year's Day, Memorial Day, July 4th, Labor Day, Thanksgiving Day & Christmas Day.

-----

IRON0008-003 06/01/2020

KENOSHA, MILWAUKEE, OZAUKEE, RACINE, WALWORTH (N.E. 2/3), WASHINGTON, AND WAUKESHA COUNTIES

Rates Fringes

IRONWORKER.....\$ 39.11 27.87

Paid Holidays: New Year's Day, Memorial Day, July 4th, Labor Day, Thanksgiving Day & Christmas Day.

-----

IRON0383-001 06/01/2020

ADAMS, COLUMBIA, CRAWFORD, DANE, DODGE, FLORENCE, FOREST, GRANT, GREENE, (Excluding S.E. tip), GREEN LAKE, IOWA, JEFFERSON, JUNEAU, LA CROSSE, LAFAYETTE, LANGLADE, MARATHON, MARQUETTE, MENOMINEE, MONROE, PORTAGE, RICHLAND, ROCK (Northern area, vicinity of Edgerton and Milton), SAUK, VERNON, WAUPACA, WAUSHARA, AND WOOD COUNTIES

Rates Fringes

IRONWORKER.....\$ 37.10 27.0

-----

IRON0498-005 06/01/2019

GREEN (S.E. 1/3), ROCK (South of Edgerton and Milton), and

# WALWORTH (S.W. 1/3) COUNTIES:

	Rates	Fringes
IRONWORKER	\$ 40.25	40.53
IRON0512-008 06/03/2019		

BARRON, BUFFALO, CHIPPEWA, CLARK, DUNN, EAU CLAIRE, JACKSON, PEPIN, PIERCE, POLK, RUSK, ST CROIX, TAYLOR, AND TREMPEALEAU COUNTIES

	Rates	Fringes	
IRONWORKER	\$ 37.60	29.40	
IRON0512-021 06/03/2019			

ASHLAND, BAYFIELD, BURNETT, DOUGLAS, IRON, LINCOLN, ONEIDA, PRICE, SAWYER, VILAS AND WASHBURN COUNTIES

	Rates	Fringes	
IRONWORKER	\$ 33.19	29.40	
LAB00113-002 06/01/2020			•

### MILWAUKEE AND WAUKESHA COUNTIES

	F	Rates	Fringes
LABORER			
Group	1\$	30.05	22.26
Group	2\$	30.20	22.26
Group	3\$	30.40	22.26
Group	4\$	30.55	22.26
Group	5\$	30.70	22.26
Group	6\$	26.54	22.26

## LABORERS CLASSIFICATIONS

GROUP 1: General Laborer; Tree Trimmer; Conduit Layer; Demolition and Wrecking Laborer; Guard Rail, Fence, and Bridge Builder; Landscaper; Multiplate Culvert Assembler; Stone Handler; Bituminous Worker (Shoveler, Loader, and Utility Man); Batch Truck Dumper or Cement Handler; Bituminous Worker (Dumper, Ironer, Smoother, and Tamper);

## Concrete Handler

GROUP 2: Air Tool Operator; Joint Sawer and Filler (Pavement); Vibrator or Tamper Operator (Mechanical Hand Operated); Chain Saw Operator; Demolition Burning Torch Laborer

GROUP 3: Bituminous Worker (Raker and Luteman); Formsetter (Curb, Sidewalk, and Pavement); Strike Off Man

GROUP 4: Line and Grade Specialist

GROUP 5: Blaster and Powderman

GROUP 6: Flagperson; traffic control person

-----

LAB00113-003 06/01/2020

#### OZAUKEE AND WASHINGTON COUNTIES

	Rates	Fringes
LABORER		
Group 1	\$ 29.30	22.26
Group 2	\$ 29.40	22.26
Group 3	\$ 29.45	22.26
Group 4	\$ 29.65	22.26
Group 5	\$ 29.50	22.26
Group 6	\$ 26.39	22.26

# LABORERS CLASSIFICATIONS

GROUP 1: General Laborer; Tree Trimmer; Conduit Layer; Demolition and Wrecking Laborer; Guard Rail, Fence, and Bridge Builder; Landscaper; Multiplate Culvert Assembler; Stone Handler; Bituminous Worker (Shoveler, Loader, and Utility Man); Batch Truck Dumper or Cement Handler; Bituminous Worker (Dumper, Ironer, Smoother, and Tamper); Concrete Handler

GROUP 2: Air Tool Operator; Joint Sawer and Filler (Pavement); Vibrator or Tamper Operator (Mechanical Hand Operated);

GROUP 3: Bituminous Worker (Raker and Luteman); Formsetter (Curb, Sidewalk, and Pavement); Strike Off Man

GROUP 4: Line and Grade Specialist

GROUP 5: Blaster; powderman

GROUP 6: Flagperson and Traffic Control Person

-----

LAB00113-011 06/01/2020

#### KENOSHA AND RACINE COUNTIES

		Rates	Fringes
LABORER			
Group	1	\$ 29.11	22.26
Group	2	\$ 29.26	22.26
Group	3	\$ 29.46	22.26
Group	4	\$ 29.43	22.26
Group	5	\$ 29.76	22.26
Group	6	\$ 26.25	22.26

#### LABORERS CLASSIFICATIONS:

GROUP 1: General laborer; Tree Trimmer; Conduit Layer; Demolition and Wrecking Laborer; Guard Rail, Fence, and Bridge Builder; Landscaper; Multiplate Culvert Assembler; Stone Handler; Bituminous Worker (Shoveler, Loader, and Utility Man); Batch Truck Dumper or Cement Handler; Bituminous worker (Dumper, Ironer, Smoother, and Tamper); Concrete Handler

GROUP 2: Air Tool Operator; Joint Sawer and Filler (Pavement); Vibrator or Tamper Operator (Mechanical Hand Operated); Chain Saw Operator; Demolition Burning Torch Laborer

GROUP 3: Bituminous Worker (Raker and Luteman); Formsetter (Curb, Sidewalk, and Pavement); Strike Off Man

GROUP 4: Line and Grade Specialist

GROUP 5: Blaster and Powderman

GROUP 6: Flagman; traffic control person

LARONA 40, 002, 05 (04 (2020

LAB00140-002 06/01/2020

ADAMS, ASHLAND, BARRON, BAYFIELD, BROWN, BUFFALO, BURNETT, CALUMET, CHIPPEWA, CLARK, COLUMBIA, CRAWFORD, DODGE, DOOR, DOUGLAS, DUNN, EAU CLAIRE, FLORENCE, FOND DU LAC, FOREST, GRANT, GREEN, GREEN LAKE, IRON, JACKSON, JUNEAU, IOWA,

JEFFERSON, KEWAUNEE, LA CROSSE, LAFAYETTE, LANGLADE, LINCOLN, MANITOWOC, MARATHON, MARINETTE, MARQUETTE, MENOMINEE, MONROE, OCONTO, ONEIDA, OUTAGAMIE, PEPIN, PIERCE, POLK, PORTAGE, PRICE, RICHLAND, ROCK, RUSK, SAUK, SAWYER, SHAWANO, SHEBOYGAN, ST. CROIX, TAYLOR, TREMPEALEAU, VERNON, VILLAS, WALWORTH, WASHBURN, WAUPACA, WAUSHARA, WINNEBAGO, AND WOOD COUNTIES

		Rates	Fringes
LABORER			
Group	1	.\$ 33.72	17.95
Group	2	.\$ 33.82	17.95
Group	3	.\$ 33.87	17.95
Group	4	.\$ 34.07	17.95
Group	5	.\$ 33.92	17.95
Group	6	.\$ 30.35	17.95

### LABORER CLASSIFICATIONS

GROUP 1: General Laborer; Tree Trimmer; Conduit Layer; Demolition and Wrecking Laborer; Guard Rail, Fence, and Bridge Builder; Landscaper; Multiplate Culvert Assembler; Stone Handler; Bitminous Worker (Shoveler, Loader, and Utility Man); Batch Truck Dumper or Cement Handler; Bituminous Worker (Dumper, Ironer, Smoother and Tamper); Concrete Handler

GROUP 2: Air Tool Operator; Joint Sawer and Filler (Pavement); Vibrator or Tamper Operator (Mechanical Hand Operated); Chain Saw Operator, Demolition Burning Torch Laborer

GROUP 3: Bituminous Worker (Raker and Luteman); Formsetter (Curb, Sidewalk and Pavement); Strike Off Man

GROUP 4: Line and Grade Secialist

GROUP 5: Blaster; powderman

GROUP 6: Flagperson; Traffic Control

-----

LAB00464-003 06/01/2020

DANE COUNTY

Rates Fringes

LABORER

Group	1\$	34.00	17.95
Group	2\$	34.10	17.95
Group	3\$	34.15	17.95
Group	4\$	34.35	17.95
Group	5\$	34.20	17.95
Group	6\$	30.35	17.95

#### LABORERS CLASSIFICATIONS:

GROUP 1: General Laborer; Tree Trimmer; Conduit Layer; Demolition and Wrecking Laborer; Guard Rail, Fence, and Bridge Builder; Landscaper; Multiplate Culvert Assembler; Stone Handler; Bituminous Worker (Shoveler, Loader, and Utility Man); Batch Truck Dumper or Cement Handler; Bituminious Worker (Dumper, Ironer, Smoother, and Tamper); Concrete Handler

GROUP 2: Air Tool Operator; Joint Sawer and Filler (Pavement); Vibrator or Tamper Operator (Mechanical Hand Operated); Chain Saw Operator; Demolition Burning Torch Laborer

GROUP 3: Bituminous Worker (Raker and Luteman); Formsetter (Curb, Sidewalk, and Pavement); Strike Off Man

GROUP 4: Line and Grade Specialist

GROUP 5: Blaster; Powderman

GROUP 6: Flagperson and Traffic Control Person

-----

PAIN0106-008 05/01/2017

ASHLAND, BAYFIELD, BURNETT, AND DOUGLAS COUNTIES

	ŀ	Rates	Fringes
Painters:			
New:			
Brush,	Roller\$	30.33	17.27
Spray,	Sandblast, Steel\$	30.93	17.27
Repaint	:		
Brush,	Roller\$	28.83	17.27
Spray,	Sandblast, Steel\$	29.43	17.27

PAIN0108-002 06/01/2019

RACINE COUNTY

	Rates	Fringes
Painters: Brush, Roller	.\$ 37.08	
PAIN0259-002 05/01/2008		
BARRON, CHIPPEWA, DUNN, EAU CLAI SAWYER, ST. CROIX, AND WASHBURN		PIERCE, POLK, RUSK,
	Rates	Fringes
PAINTER	.\$ 24.11	12.15
PAIN0259-004 05/01/2015		
BUFFALO, CRAWFORD, JACKSON, LA OVERNON COUNTIES	ROSSE, MON	ROE, TREMPEALEAU, AND
	Rates	Fringes
PAINTER		
PAIN0781-002 06/01/2019		
JEFFERSON, MILWAUKEE, OZAUKEE, W	ASHINGTON,	AND WAUKESHA COUNTIES
	Rates	Fringes
Painters: Bridge Brush Spray & Sandblast	.\$ 32.95 .\$ 33.70	23.86 23.86 23.86
PAIN0802-002 06/01/2019		
COLUMBIA, DANE, DODGE, GRANT, GR ROCK, AND SAUK COUNTIES	REEN, IOWA,	LAFAYETTE, RICHLAND,
	Rates	Fringes
PAINTER Brush	.\$ 30.93	18.44
PREMIUM PAY: Structural Steel, Spray, Bridg	ges = \$1.	00 additional per

\_\_\_\_\_

# PAIN0802-003 06/01/2019

ADAMS, BROWN, CALUMET, CLARK, DOOR, FOND DU LAC, FOREST, GREEN LAKE, IRON, JUNEAU, KEWAUNEE, LANGLADE, LINCOLN, MANITOWOC, MARATHON, MARINETTE, MARQUETTE, MENOMINEE, OCONTO, ONEIDA, OUTAGAMIE, PORTAGE, PRICE, SHAWANO, SHEBOYGAN, TAYLOR, VILAS, WAUSHARA, WAUPACA, WINNEBAGO, AND WOOD COUNTIES

	Rates	Fringes
PAINTER	\$ 30.93	18.58
PAIN0934-001 06/01/2017		
KENOSHA AND WALWORTH COUNTIES		
	Rates	Fringes
Painters:     Brush	\$ 34.74	18.95 18.95 18.95
FLORENCE COUNTY		
	Rates	Fringes
Painters:	\$ 25.76	13.33
PLAS0599-010 06/01/2017		
	Rates	Fringes

# AREA DESCRIPTIONS

CEMENT MASON/CONCRETE FINISHER

Area 1.....\$ 39.46

Area 2 (BAC).....\$ 35.07

Area 3.....\$ 35.61

Area 4.....\$ 34.70

Area 5.....\$ 36.27

Area 6....\$ 32.02

AREA 1: BAYFIELD, DOUGLAS, PRICE, SAWYER, AND WASHBURN

17.17

19.75

19.40

20.51

18.73

22.99

#### COUNTIES

AREA 2: ADAMS, ASHLAND, BARRON, BROWN, BURNETT, CALUMET, CHIPPEWA, CLARK, COLUMBIA, DODGE, DOOR, DUNN, FLORENCE, FOND DU LAC, FOREST, GREEN LAKE, IRON, JEFFERSON, KEWAUNEE, LANGLADE, LINCOLN, MANITOWOC, MARATHON, MARINETTE, MARQUETTE, MENOMINEE, OCONTO, ONEIDA, OUTAGAMIE, POLK, PORTAGE, RUSK, ST CROIX, SAUK, SHAWANO, SHEBOYGAN, TAYLOR, VILAS, WALWORTH, WAUPACA, WAUSHARA, WINNEBAGO, AND WOOD COUNTIES

AREA 3: BUFFALO, CRAWFORD, EAU CLAIRE, JACKSON, JUNEAU, LA CROSSE MONROE, PEPIN, PIERCE, RICHLAND, TREMPEALEAU, AND VERNON COUNTIES

AREA 4: MILWAUKEE, OZAUKEE, WASHINGTON, AND WAUKESHA COUNTIES

AREA 5: DANE, GRANT, GREEN, IOWA, LAFAYETTE, AND ROCK COUNTIES

AREA 6: KENOSHA AND RACINE COUNTIES

TEAM0039-001 06/01/2020

	Rates	Fringes
TRUCK DRIVER  1 & 2 Axles  3 or more Axles; Euclids, Dumptor & Articulated,	\$ 31.07	22.94
Truck Mechanic	\$ 31.22	22.94
WELL DRILLER	\$ 16.52	3.70

WELDERS - Receive rate prescribed for craft performing operation to which welding is incidental.

-----

Note: Executive Order (EO) 13706, Establishing Paid Sick Leave for Federal Contractors applies to all contracts subject to the Davis-Bacon Act for which the contract is awarded (and any solicitation was issued) on or after January 1, 2017. If this contract is covered by the EO, the contractor must provide employees with 1 hour of paid sick leave for every 30 hours they work, up to 56 hours of paid sick leave each year. Employees must be permitted to use paid sick leave for their

own illness, injury or other health-related needs, including preventive care; to assist a family member (or person who is like family to the employee) who is ill, injured, or has other health-related needs, including preventive care; or for reasons resulting from, or to assist a family member (or person who is like family to the employee) who is a victim of, domestic violence, sexual assault, or stalking. Additional information on contractor requirements and worker protections under the EO is available at www.dol.gov/whd/govcontracts.

Unlisted classifications needed for work not included within the scope of the classifications listed may be added after award only as provided in the labor standards contract clauses (29CFR 5.5 (a) (1) (ii)).

\_\_\_\_\_

The body of each wage determination lists the classification and wage rates that have been found to be prevailing for the cited type(s) of construction in the area covered by the wage determination. The classifications are listed in alphabetical order of ""identifiers"" that indicate whether the particular rate is a union rate (current union negotiated rate for local), a survey rate (weighted average rate) or a union average rate (weighted union average rate).

### Union Rate Identifiers

A four letter classification abbreviation identifier enclosed in dotted lines beginning with characters other than ""SU"" or ""UAVG"" denotes that the union classification and rate were prevailing for that classification in the survey. Example: PLUM0198-005 07/01/2014. PLUM is an abbreviation identifier of the union which prevailed in the survey for this classification, which in this example would be Plumbers. 0198 indicates the local union number or district council number where applicable, i.e., Plumbers Local 0198. The next number, 005 in the example, is an internal number used in processing the wage determination. 07/01/2014 is the effective date of the most current negotiated rate, which in this example is July 1, 2014.

Union prevailing wage rates are updated to reflect all rate changes in the collective bargaining agreement (CBA) governing this classification and rate.

Survey Rate Identifiers

Classifications listed under the ""SU"" identifier indicate that no one rate prevailed for this classification in the survey and the published rate is derived by computing a weighted average rate based on all the rates reported in the survey for that classification. As this weighted average rate includes all rates reported in the survey, it may include both union and non-union rates. Example: SULA2012-007 5/13/2014. SU indicates the rates are survey rates based on a weighted average calculation of rates and are not majority rates. LA indicates the State of Louisiana. 2012 is the year of survey on which these classifications and rates are based. The next number, 007 in the example, is an internal number used in producing the wage determination. 5/13/2014 indicates the survey completion date for the classifications and rates under that identifier.

Survey wage rates are not updated and remain in effect until a new survey is conducted.

Union Average Rate Identifiers

Classification(s) listed under the UAVG identifier indicate that no single majority rate prevailed for those classifications; however, 100% of the data reported for the classifications was union data. EXAMPLE: UAVG-OH-0010 08/29/2014. UAVG indicates that the rate is a weighted union average rate. OH indicates the state. The next number, 0010 in the example, is an internal number used in producing the wage determination. 08/29/2014 indicates the survey completion date for the classifications and rates under that identifier.

A UAVG rate will be updated once a year, usually in January of each year, to reflect a weighted average of the current negotiated/CBA rate of the union locals from which the rate is based.

-----

#### WAGE DETERMINATION APPEALS PROCESS

- 1.) Has there been an initial decision in the matter? This can be:
- \* an existing published wage determination
- \* a survey underlying a wage determination
- \* a Wage and Hour Division letter setting forth a position on a wage determination matter
- \* a conformance (additional classification and rate) ruling

On survey related matters, initial contact, including requests for summaries of surveys, should be with the Wage and Hour Regional Office for the area in which the survey was conducted because those Regional Offices have responsibility for the Davis-Bacon survey program. If the response from this initial contact is not satisfactory, then the process described in 2.) and 3.) should be followed.

With regard to any other matter not yet ripe for the formal process described here, initial contact should be with the Branch of Construction Wage Determinations. Write to:

Branch of Construction Wage Determinations Wage and Hour Division U.S. Department of Labor 200 Constitution Avenue, N.W. Washington, DC 20210

2.) If the answer to the question in 1.) is yes, then an interested party (those affected by the action) can request review and reconsideration from the Wage and Hour Administrator (See 29 CFR Part 1.8 and 29 CFR Part 7). Write to:

Wage and Hour Administrator U.S. Department of Labor 200 Constitution Avenue, N.W. Washington, DC 20210

The request should be accompanied by a full statement of the interested party's position and by any information (wage payment data, project description, area practice material, etc.) that the requestor considers relevant to the issue.

3.) If the decision of the Administrator is not favorable, an interested party may appeal directly to the Administrative Review Board (formerly the Wage Appeals Board). Write to:

Administrative Review Board U.S. Department of Labor 200 Constitution Avenue, N.W. Washington, DC 20210

-----

END OF GENERAL DECISION"

"General Decision Number: WI20200015 08/28/2020

Superseded General Decision Number: WI20190015

State: Wisconsin

Construction Type: Heavy

Counties: Wisconsin Statewide.

HEAVY CONSTRUCTION PROJECTS (Excluding Tunnel, Sewer, and Water Lines).

Note: Under Executive Order (EO) 13658, an hourly minimum wage of \$10.80 for calendar year 2020 applies to all contracts subject to the Davis-Bacon Act for which the contract is awarded (and any solicitation was issued) on or after January 1, 2015. If this contract is covered by the EO, the contractor must pay all workers in any classification listed on this wage determination at least \$10.80 per hour (or the applicable wage rate listed on this wage determination, if it is higher) for all hours spent performing on the contract in calendar year 2020. If this contract is covered by the EO and a classification considered necessary for performance of work on the contract does not appear on this wage determination, the contractor must pay workers in that classification at least the wage rate determined through the conformance process set forth in 29 CFR 5.5(a)(1)(ii) (or the EO minimum wage rate, if it is higher than the conformed wage rate). The EO minimum wage rate will be adjusted annually. Please note that this EO applies to the above-mentioned types of contracts entered into by the federal government that are subject to the Davis-Bacon Act itself, but it does not apply to contracts subject only to the Davis-Bacon Related Acts, including those set forth at 29 CFR 5.1(a)(2)-(60). Additional information on contractor requirements and worker protections under the EO is available at www.dol.gov/whd/govcontracts.

Modification Number	Publication Date
0	01/03/2020
1	01/24/2020
2	02/28/2020
3	03/06/2020
4	06/05/2020
5	06/12/2020
6	06/19/2020
7	07/03/2020
8	07/17/2020
9	07/24/2020

# BOIL0107-001 01/01/2017

BOIL0107-001 01/01/201/		
	Rates	Fringes
BOILERMAKER  Boilermaker	\$ 35.65	29.89
25,000 lbs/hr)		16.00
BRWI0001-002 06/03/2019		
CRAWFORD, JACKSON, JUNEAU, LA CROVERNON COUNTIES	OSSE, MONROE,	TREMPEALEAU, AND
	Rates	Fringes
BRICKLAYER	•	24.28
BRWI0002-002 06/01/2019		
ASHLAND, BAYFIELD, DOUGLAS, AND	IRON COUNTIES	
	Rates	Fringes
BRICKLAYER	•	
BRWI0002-005 06/01/2019		
ADAMS, ASHLAND, BARRON, BROWN, BURNETT, CALUMET, CHIPPEWA, CLARK, COLUMBIA, DODGE, DOOR, DUNN, FLORENCE, FOND DU LAC, FOREST, GREEN LAKE, IRON, JEFFERSON, KEWAUNEE, LANGLADE, LINCOLN, MANITOWOC, MARATHON, MARINETTE, MARQUETTE, MENOMINEE, OCONTO, ONEIDA, OUTAGAMIE, POLK, PORTAGE, RUSK, ST CROIX, SAUK,		

SHAWANO, SHEBOYGAN, TAYLOR, VILAS, WALWORTH, WAUPACA, WAUSHARA, WINNEBAGO, AND WOOD COUNTIES

	Rates	Fringes
CEMENT MASON/CONCRETE FINISHE	ER\$ 35.51	23.37
BRWI0003-002 06/03/2019		
BROWN, DOOR, FLORENCE, KEWAUN	NEE, MARINETTE,	AND OCONTO COUNTIES
	Rates	Fringes

BRICKLAYER		23.90	
BRWI0004-002 06/01/2019			
KENOSHA, RACINE, AND WALWORTH O	COUNTIES		
	Rates	Fringes	
BRICKLAYER	\$ 38.43	25.10	
BRWI0006-002 06/01/2019			
ADAMS, CLARK, FOREST, LANGLADE, ONEIDA, PORTAGE, PRICE, TAYLOR,	-		
	Rates	Fringes	
BRICKLAYER	\$ 35.06	23.02	
BRWI0007-002 06/03/2019			
GREEN, LAFAYETTE, AND ROCK COUN	NTIES		
	Rates	Fringes	
BRICKLAYER			
BRWI0008-002 06/01/2019			
MILWAUKEE, OZAUKEE, WASHINGTON, AND WAUKESHA COUNTIES			
	Rates	Fringes	
BRICKLAYER	\$ 38.93	24.22	
BRWI0009-001 06/03/2019			
GREEN LAKE, MARQUETTE, OUTAGAMI AND WINNEBAGO COUNTIES	E, SHAWANO,	WAUPACA, WASHARA,	
	Rates	Fringes	
BRICKLAYER	•	23.90	
BRWI0011-002 06/03/2019			
CALUMET, FOND DU LAC, MANITOWOO	AND SHEBOY	GAN COUNTIES	

	Rates	Fringes
BRICKLAYER		23.90
BRWI0013-002 06/03/2019		
DANE, GRANT, IOWA, AND RICHLAND	COUNTIES	
	Rates	Fringes
BRICKLAYER	\$ 35.56	24.23
BRWI0019-002 06/03/2019		
BARRON, BUFFALO, BURNETT, CHIPPI PIERCE, POLK, RUSK, ST. CROIX, S		
	Rates	Fringes
BRICKLAYER BRWI0021-002 06/03/2019	\$ 33.40	24.68
DODGE AND JEFFERSON COUNTIES		
	Rates	Fringes
BRICKLAYER	-	24.02
BRWI0034-002 06/03/2019		
COLUMBIA AND SAUK COUNTIES		
	Rates	Fringes
BRICKLAYER	\$ 35.56	24.23
CARP0087-001 05/01/2016		
BURNETT (W. of Hwy 48), PIERCE 35, 48 & 65), AND ST. CROIX (W.		
	Rates	Fringes
Carpenter & Piledrivermen		18.39
CARP0252-002 06/01/2016		

ADAMS, BARRON, BAYFIELD (Eastern 2/3), BROWN, BUFFALO, BURNETT (E. of Hwy 48), CALUMET, CHIPPEWA, CLARK, COLUMBIA, CRAWFORD, DANE, DODGE, DOOR, DUNN, EAU CLAIRE, FLORENCE (except area bordering Michigan State Line), FOND DU LAC, FOREST, GRANT, GREEN, GREEN LAKE, IOWA, IRON, JACKSON, JEFFERSON, JUNEAU, KEWAUNEE, LA CROSSE, LAFAYETTE, LANGLADE, LINCOLN, MANITOWOC, MARATHON, MARINETTE (except N.E. corner), MARQUETTE, MENOMINEE, MONROE, OCONTO, ONEIDA, OUTAGAMIE, PEPIN, PIERCE (E. of Hwys 29 & 65), POLK (E. of Hwys 35, 48 & 65), PORTAGE, PRICE, RICHLAND, ROCK, RUSK, SAUK, SAWYER, SHAWANO, SHEBOYGAN, ST CROIX (E. of Hwy 65), TAYLOR, TREMPEALEAU, VERNON, VILAS, WALWORTH, WASHBURN, WAUPACA, WAUSHARA, WINNEBAGO, AND WOOD COUNTIES

	Rates	Fringes	
CARPENTER			
CARPENTER	\$ 33.56	18.00	
MILLWRIGHT	\$ 35.08	18.35	
PILEDRIVER	\$ 34.12	18.00	

CARP0252-010 06/01/2016

ASHLAND COUNTY

	Rates	Fringes
Carpenters		
Carpenter\$	33.56	18.00
Millwright\$	35.08	18.35
Pile Driver\$	34.12	18.00

CARP0264-003 06/01/2016

KENOSHA, MILWAUKEE, OZAUKEE, RACINE, WAUKESHA, AND WASHINGTON COUNTIES

	Rates	Fringes
CARPENTER	\$ 35.78	22.11
CARP0361-004 05/01/2018		

BAYFIELD (West of Hwy 63) AND DOUGLAS COUNTIES

	Rates	Fringes
CARPENTER	\$ 36.15	20.43

CARP2337-001 06/01/2016

ZONE A: MILWAUKEE, OZAUKEE, WAUKESHA AND WASHINGTON

ZONE B: KENOSHA & RACINE

	Rates	Fringes	
PILEDRIVERMAN			
Zone A	\$ 31.03	22.69	
Zone B	\$ 31.03	22.69	
			· <b>-</b>

CARP2337-003 06/01/2019

	Rates	Fringes
MILLWRIGHT		
Zone A	\$ 33.58	21.53
Zone B	\$ 33.58	21.53

**ZONE DEFINITIONS** 

ZONE A: MILWAUKEE, OZAUKEE, WAUKESHA AND WASHINGTON COUNTIES

ZONE B: KENOSHA & RACINE COUNTIES

ASHLAND, BARRON, BAYFIELD, BUFFALO, BURNETT, CHIPPEWA, CLARK (except Maryville, Colby, Unity, Sherman, Fremont, Lynn & Sherwood), CRAWFORD, DUNN, EAU CLAIRE, GRANT, IRON, JACKSON, LA CROSSE, MONROE, PEPIN, PIERCE, POLK, PRICE, RICHLAND, RUSK, ST CROIX, SAWYER, TAYLOR, TREMPEALEAU, VERNON, AND WASHBURN COUNTIES

	Rates	Fringes
Electricians:	\$ 35.98	20.98

\* ELEC0014-007 07/05/2020

REMAINING COUNTIES

Rates Fringes

Teledata System Installer

<sup>\*</sup> ELEC0014-002 06/14/2020

Low voltage construction, installation, maintenance and removal of teledata facilities (voice, data, and video) including outside plant, telephone and data inside wire, interconnect, terminal equipment, central offices, PABX, fiber optic cable and equipment, micro waves, V-SAT, bypass, CATV, WAN (wide area networks), LAN (local area networks), and ISDN (integrated systems digital network).

.....

ELEC0127-002 06/01/2020

KENOSHA COUNTY

Rates Fringes

Electricians:.....\$ 41.62 30%+12.70

ELEC0158-002 06/03/2019

BROWN, DOOR, KEWAUNEE, MANITOWOC (except Schleswig),
MARINETTE(Wausuakee and area South thereof), OCONTO, MENOMINEE
(East of a ine 6 miles West of the West boundary of Oconto
County), SHAWANO (Except Area North of Townships of Aniwa and
Hutchins) COUNTIES

COLUMBIA, DANE, DODGE (Area West of Hwy 26, except Chester and Emmet Townships), GREEN, LAKE (except Townships of Berlin, Seneca, and St. Marie), IOWA, MARQUETTE (except Townships of Neshkoka, Crystal Lake, Newton, and Springfield), and SAUK COUNTIES

FLORENCE COUNTY (Townships of Aurora, Commonwealth, Fern, Florence and Homestead) AND MARINETTE COUNTY (Township of Niagara)

	Rates	Fringes
Electricians: Electrical contracts over \$180,000	.\$ 32.38	18.63
Electrical contracts under \$180,000	.\$ 30.18	18.42
* ELEC0242-005 05/31/2020		
DOUGLAS COUNTY		
	Rates	Fringes
Electricians:		
* ELEC0388-002 06/01/2020		
ADAMS, CLARK (Colby, Freemont, L Sherwood, Unity), FOREST, JUNEA MARINETTE (Beecher, Dunbar, Good West of a line 6 miles West of t County), ONEIDA, PORTAGE, SHAWAN AND WOOD COUNTIES	U, LANGLADE, LIN man & Pembine), he West boundary	NCOLN, MARATHON, MENOMINEE (Area of Oconto
	Rates	Fringes
Electricians:		26%+11.20
ELEC0430-002 06/01/2020		
RACINE COUNTY (Except Burlington	Township)	
	Rates	Fringes
Electricians:	.\$ 41.86	22.66
ELEC0494-005 06/01/2020		
MILWAUKEE, OZAUKEE, WASHINGTON,	AND WAUKESHA COL	JNTIES
	Rates	Fringes
Electricians:	•	25.54
ELEC0494-006 06/01/2020		

CALUMET (Township of New Holstein), DODGE (East of Hwy 26 including Chester Township), FOND DU LAC, MANITOWOC (Schleswig), and SHEBOYGAN COUNTIES

	Rates	Fringes	
Electricians:	\$ 36.32	22.51	
ELEC0494-013 06/07/2020			_

DODGE (East of Hwy 26 including Chester Twp, excluding Emmet Twp), FOND DU LAC (Except Waupuin), MILWAUKEE, OZAUKEE, MANITOWOC (Schleswig), WASHINGTON, AND WAUKESHA COUNTIES

	Rates	Fringes
Sound & Communications		
Installer	\$ 21.46	18.52
Technician	\$ 31.34	20.00

Installation, testing, maintenance, operation and servicing of all sound, intercom, telephone interconnect, closed circuit TV systems, radio systems, background music systems, language laboratories, electronic carillion, antenna distribution systems, clock and program systems and low-voltage systems such as visual nurse call, audio/visual nurse call systems, doctors entrance register systems. Includes all wire and cable carrying audio, visual, data, light and radio frequency signals. Includes the installation of conduit, wiremold, or raceways in existing structures that have been occupied for six months or more where required for the protection of the wire or cable, but does not mean a complete conduit or raceway system. work covered does not include the installation of conduit, wiremold or any raceways in any new construction, or the installation of power supply outlets by means of which external electric power is supplied to any of the foregoing equipment or products

-----

## ELEC0577-003 06/01/2019

CALUMET (except Township of New Holstein), GREEN LAKE (N. part including Townships of Berlin, St Marie, and Seneca), MARQUETTE (N. part including Townships of Crystal Lake, Neshkoro, Newton, and Springfield), OUTAGAMIE, WAUPACA, WAUSHARA, AND WINNEBAGO COUNTIES

	Rates	Fringes		
Electricians:	\$ 33.15	28.50%+10.00		
ELEC0890-003 06/01/2020				
DODGE (Emmet Township only), GREEN, JEFFERSON, LAFAYETTE, RACINE (Burlington Township), ROCK AND WALWORTH COUNTIES				
	Rates	Fringes		
Electricians:	\$ 37.41	25.95%+11.11		
ELEC0953-001 06/02/2019				
	Rates	Fringes		
Line Construction:				
(1) Lineman(2) Heavy Equipment	\$ 47.53	21.43		
Operator	\$ 42.78	19.80		
(3) Equipment Operator	\$ 38.02	18.40		
(4) Heavy Groundman Driver	\$ 33.27	16.88		
(5) Light Groundman Driver		16.11		
(6) Groundsman	\$ 26.14	14.60		
ENGI0139-001 06/01/2020				

KENOSHA, MILWAUKEE, OZAUKEE, RACINE, WASHINGTON, AND WAUKESHA COUNTIES

I	Rates	Fringes
Power Equipment Operator		
Group 1\$	47.66	23.15
Group 2\$	47.16	23.15
Group 3\$	46.66	23.15
Group 4\$	45.97	23.15
Group 5\$	42.39	23.15
Group 6\$	37.24	23.15

# HAZARDOUS WASTE PREMIUMS:

EPA Level ""A"" Protection: \$3.00 per hour EPA Level ""B"" Protection: \$2.00 per hour EPA Level ""C"" Protection: \$1.00 per hour

POWER EQUIPMENT OPERATORS CLASSIFICATIONS

- GROUP 1: Cranes, Tower Cranes, Pedestal Tower Cranes and Derricks with or w/o attachments with a lifting capacity of over 100 tons; or Cranes, Tower Cranes, Pedestal Tower Cranes and Derricks with boom, leads, and/or jib lengths measuring 176 feet or longer; Self-Erecting Tower Cranes over 4000 lbs lifting capacity; All Cranes with Boom Dollies; Boring Machines (directional); Master Mechanic. \$0.50 additional per hour per 100 tons or 100 ft of boom over 200 ft or lifting capacity of crane over 200 tons to a maximum of 300 tons or 300 ft. Thereafter an increase of \$0.01 per ft or ton, whichever is greater.
- GROUP 2: Cranes, Tower Cranes, Pedestal Tower Cranes and Derricks with or without attachments with a lifting capacity of 100 tons or less; or Cranes, Tower Cranes Portable Tower Cranes, Pedestal Tower Cranes and Derricks with boom, leadsand/or jib lengths measuring 175 feet or less; Backhoes (excavators) 130,000 lbs and over; Caisson Rigs; Pile Drivers; Boring Machines (vertical or horizontal), Versi-Lift, Tri-Lift, Gantry 20,000 lbs & over.
- GROUP 3: Backhoe (excavator) under 130,000 lbs; Self-erecting Tower Crane 4000 lbs & under lifting capacity; Traveling Crane (bridge type); Skid Rigs; Dredge Operator; Mechanic; Concrete Paver (over 27E); Concrete Spreader and Distributor; Forklift/ Telehandler (machinery- moving / steel erection); Hydro Blaster, 10,000 psi and over
- GROUP 4: Material Hoists; Stack Hoists; Hydraulic Backhoe (tractor or truck mounted); Hydraulic Crane, 5 tons or under (tractor or truck mounted); Hoist (tuggers 5 tons & over); Hydro-Excavators/Daylighters; Concrete Pumps Rotec type Conveyors; Tractor/Bulldozer/End Loader (over 40 hp); Motor Patrol; Scraper Operator; Sideboom; Straddle Carrier; Welder; Bituminous Plant and Paver Operator; Roller over 5 tons; Rail Leveling Machine (Railroad); Tie Placer; Tie Extractor; Tie Tamper; Stone Leveler; Rotary Drill Operator and Blaster; Percussion Drill Operator; Air Track Drill and/or Hammers; Gantrys (under 20,000 lbs); Tencher (wheel type or chain type having 8 inch or larger bucket); Milling Machine; Off-Road Material Haulers.
- GROUP 5: Backfiller; Concrete Auto Breaker (large); Concrete Finishing Machines (road type); Rubber Tired Roller; Concrete Batch Hopper; Concrete Conveyor Systems; Grout Pumps; Concrete Mixers (14S or over); Screw Type Pumps and Gypsum Pumps; Tractor, Bulldozer, End Loader (under 40 hp); Trencher (chain type, bucket under 8 inch); Industrial Locomotives; Rollers under 5 tons; Stump Grinder/Chipper

(Large); Timber Equipment; Firemen (pile drivers and derricks); Personnel Hoist, Telehandler over 8000 lbs; Robotic Tool Carrier with or without attachments

GROUP 6: Tampers - Compactors (riding type); Assistant Engineer; A-Frames and Winch Trucks; Concrete Auto Breaker; Hydrohammers (small); Brooms and Sweepers; Hoist (tuggers under 5 tons); Boats (Tug, Safety, Work Barges, Launch); Shouldering Machine Operator; Prestress Machines; Screed Operator; Stone Crushers and Screening Plants; Screed Operators (milling machine), Farm or Industrial Tractor Mounted Equipment; Post Hole Digger; Fireman (asphalt plants); Air Compressors over 400 CFM; Generators, over 150 KW; Augers (vertical and horizontal); Air, Electric, Hydraulic Jacks (slipform); Skid Steer Loaders (with or without attachments); Boiler Operators (temporary heat); Refrigeration Plant/Freeze Machines; Power Pack Vibratory/Ultra Sound Drivers and Extractors; Welding Machines; Heaters (mechanical); Pumps; Winches (small electric); Oiler and Greaser; Rotary Drill Tender; Conveyor; Forklifts/Telehandler 8000 lbs & under; Elevators: Automatic Hoists; Pumps (well points); Combination Small Equipment Operators

ENGI0139-003 06/01/2020

#### **REMAINING COUNTIES**

	Rates	Fringes
Power Equipment Operator		
Group 1	.\$ 42.92	23.15
Group 2	.\$ 41.67	23.15
Group 3	.\$ 39.97	23.15
Group 4	.\$ 39.44	23.15
Group 5	.\$ 37.37	23.15
Group 6	.\$ 35.84	23.15

### HAZARDOUS WASTE PREMIUMS:

EPA Level ""A"" Protection: \$3.00 per hour EPA Level ""B"" Protection: \$2.00 per hour EPA Level ""C"" Protection: \$1.00 per hour

# POWER EQUIPMENT OPERATORS CLASSIFICATIONS

GROUP 1: Cranes, Tower Cranes and Derricks with or without attachments with a lifting capacity of over 100 tons; Cranes, Tower Cranes, and Derricks with boom, leads and/or jib lengths 176 ft or longer.

- GROUP 2: Backhoes (Excavators) weighing 130,00 lbs and over; Cranes, Tower Cranes and Derricks with or without attachments with a lifting capacity of 100 tons or less; Cranes, Tower Cranes, and Derricks with boom, leads, and/or jib lengths 175 ft or less; Caisson Rigs; Pile Driver
- GROUP 3: Backhoes (Excavators) weighing under 130,000 lbs; Travelling Crane (bridge type); Milling Machine; Concrete Paver over 27 E; Concrete Spreader and Distributor; Concrete Laser Screed; Concrete Grinder and Planing Machine; Slipform Curb and Gutter Machine; Boring Machine (Directional); Dredge Operator; Skid Rigs; over 46 meter Concrete Pump.
- GROUP 4: Hydraulic Backhoe (tractor or truck mounted); Hydraulic Crane, 10 tons or less; Tractor, Bulldozer, or End Loader (over 40 hp); Motor Patrol; Scraper Operator; Bituminous Plant and Paver Operator; Screed-Milling Machine; Roller over 5 tons; Concrete pumps 46 meter and under; Grout Pumps; Rotec type machine; Hydro Blaster, 10,000 psi and over; Rotary Drill Operator; Percussion Drilling Machine; Air Track Drill with or without integral hammer; Blaster; Boring Machine (vertical or horizontal); Side Boom; Trencher, wheel type or chain type having 8 inch or larger bucket; Rail Leveling Machine (Railroad); Tie Placer; Tie Extractor; Tie Tamper; Stone Leveler; Straddle Carrier; Material Hoists; Stack Hoist; Man Hoists; Mechanic and Welder; Off Road Material Haulers.
- GROUP 5: Tractor, Bulldozer, or Endloader (under 40 hp); Tampers -Compactors, riding type; Stump Chipper, large; Roller, Rubber Tire; Backfiller; Trencher, chain type (bucket under 8 inch); Concrete Auto Breaker, large; Concrete Finishing Machine (road type); Concrete Batch Hopper; Concrete Conveyor Systems; Concrete Mixers, 14S or over; Pumps, Screw Type and Gypsum); Hydrohammers, small; Brooms and Sweeeprs; Lift Slab Machine; Roller under 5 tons; Industrial Locomotives; Fireman (Pile Drivers and Derricks); Pumps (well points); Hoists, automatic; A-Frames and Winch Trucks; Hoists (tuggers); Boats (Tug, Safety, Work Barges and Launches); Assistant Engineer
- GROUP 6: Shouldering Machine Operator; Farm or Industrial Tractor mounted equipment; Post Hole Digger; Auger (vertical and horizontal); Skid Steer Loader with or without attachments; Robotic Tool Carrier with or without attachments; Power Pack Vibratory/Ultra Sound Driver and Extractor; Fireman (Asphalt Plants); Screed Operator; Stone Crushers and Screening Plants; Air, Electric, Hydraulic

Jacks (Slip Form); Prestress Machines; Air Compressor, 400 CFM or over; Refrigeration Plant/Freese Machine; Boiler Operators (temporary heat); Forklifts; Welding Machines; Generators; Pumps over 3""; Heaters, Mechanical; Combination small equipment operator; Winches, small electric; Oiler; Greaser; Rotary Drill Tender; Conveyor; Elevator Operator

-----

IRON0008-002 06/01/2020

BROWN, CALUMET, DOOR, FOND DU LAC, KEWAUNEE, MANITOWOC, MARINETTE, OCONTO, OUTAGAMI, SHAWANO, SHEBOYGAN, AND WINNEBAGO COUNTIES:

Rates Fringes

IRONWORKER......\$ 37.31 27.62

Paid Holidays: New Year's Day, Memorial Day, July 4th, Labor Day, Thanksgiving Day & Christmas Day.

-----

IRON0008-003 06/01/2020

KENOSHA, MILWAUKEE, OZAUKEE, RACINE, WALWORTH (N.E. 2/3), WASHINGTON, AND WAUKESHA COUNTIES

Paid Holidays: New Year's Day, Memorial Day, July 4th, Labor Day, Thanksgiving Day & Christmas Day.

-----

IRON0383-001 06/01/2020

ADAMS, COLUMBIA, CRAWFORD, DANE, DODGE, FLORENCE, FOREST, GRANT, GREENE, (Excluding S.E. tip), GREEN LAKE, IOWA, JEFFERSON, JUNEAU, LA CROSSE, LAFAYETTE, LANGLADE, MARATHON, MARQUETTE, MENOMINEE, MONROE, PORTAGE, RICHLAND, ROCK (Northern area, vicinity of Edgerton and Milton), SAUK, VERNON, WAUPACA, WAUSHARA, AND WOOD COUNTIES

	Rates	Fringes
IRONWORKER	\$ 37.10	27.06

-----

#### IRON0512-008 06/03/2019

BARRON, BUFFALO, CHIPPEWA, CLARK, DUNN, EAU CLAIRE, JACKSON, PEPIN, PIERCE, POLK, RUSK, ST CROIX, TAYLOR, AND TREMPEALEAU COUNTIES

	Rates	Fringes
IRONWORKER	\$ 37.60	29.40
IRON0512-021 06/03/2019		

ASHLAND, BAYFIELD, BURNETT, DOUGLAS, IRON, LINCOLN, ONEIDA, PRICE, SAWYER, VILAS AND WASHBURN COUNTIES

	Rates	Fringes
IRONWORKER	\$ 33.19	29.40
LAB00113-002 06/01/2020		

#### MILWAUKEE AND WAUKESHA COUNTIES

		Rates	Fringes
LABORER			
Group	1	\$ 30.05	22.26
Group	2	\$ 30.20	22.26
Group	3	\$ 30.40	22.26
Group	4	\$ 30.55	22.26
	5		22.26
=	6		22,26

## LABORERS CLASSIFICATIONS

GROUP 1: General Laborer; Tree Trimmer; Conduit Layer; Demolition and Wrecking Laborer; Guard Rail, Fence, and Bridge Builder; Landscaper; Multiplate Culvert Assembler; Stone Handler; Bituminous Worker (Shoveler, Loader, and Utility Man); Batch Truck Dumper or Cement Handler; Bituminous Worker (Dumper, Ironer, Smoother, and Tamper); Concrete Handler

GROUP 2: Air Tool Operator; Joint Sawer and Filler (Pavement); Vibrator or Tamper Operator (Mechanical Hand Operated); Chain Saw Operator; Demolition Burning Torch Laborer

GROUP 3: Bituminous Worker (Raker and Luteman); Formsetter (Curb, Sidewalk, and Pavement); Strike Off Man

GROUP 4: Line and Grade Specialist

GROUP 5: Blaster and Powderman

GROUP 6: Flagperson; traffic control person

-----

LAB00113-003 06/01/2020

### OZAUKEE AND WASHINGTON COUNTIES

	F	Rates	Fringes
LABORER			
Group	1\$	29.30	22.26
Group	2\$	29.40	22.26
Group	3\$	29.45	22.26
Group	4\$	29.65	22.26
Group	5\$	29.50	22.26
Group	6\$	26.39	22.26

#### LABORERS CLASSIFICATIONS

GROUP 1: General Laborer; Tree Trimmer; Conduit Layer; Demolition and Wrecking Laborer; Guard Rail, Fence, and Bridge Builder; Landscaper; Multiplate Culvert Assembler; Stone Handler; Bituminous Worker (Shoveler, Loader, and Utility Man); Batch Truck Dumper or Cement Handler; Bituminous Worker (Dumper, Ironer, Smoother, and Tamper); Concrete Handler

GROUP 2: Air Tool Operator; Joint Sawer and Filler (Pavement); Vibrator or Tamper Operator (Mechanical Hand Operated);

GROUP 3: Bituminous Worker (Raker and Luteman); Formsetter (Curb, Sidewalk, and Pavement); Strike Off Man

GROUP 4: Line and Grade Specialist

GROUP 5: Blaster; powderman

GROUP 6: Flagperson and Traffic Control Person

------

LAB00113-011 06/01/2020

#### KENOSHA AND RACINE COUNTIES

	ſ	Rates	Fringes
LABORER			
Group	1\$	29.11	22.26
Group	2\$	29.26	22.26
Group	3\$	29.46	22.26
Group	4\$	29.43	22.26
Group	5\$	29.76	22.26
Group	6\$	26.25	22.26

#### LABORERS CLASSIFICATIONS:

GROUP 1: General laborer; Tree Trimmer; Conduit Layer; Demolition and Wrecking Laborer; Guard Rail, Fence, and Bridge Builder; Landscaper; Multiplate Culvert Assembler; Stone Handler; Bituminous Worker (Shoveler, Loader, and Utility Man); Batch Truck Dumper or Cement Handler; Bituminous worker (Dumper, Ironer, Smoother, and Tamper); Concrete Handler

GROUP 2: Air Tool Operator; Joint Sawer and Filler (Pavement); Vibrator or Tamper Operator (Mechanical Hand Operated); Chain Saw Operator; Demolition Burning Torch Laborer

GROUP 3: Bituminous Worker (Raker and Luteman); Formsetter (Curb, Sidewalk, and Pavement); Strike Off Man

GROUP 4: Line and Grade Specialist

GROUP 5: Blaster and Powderman

GROUP 6: Flagman; traffic control person

-----

# LAB00140-002 06/01/2020

ADAMS, ASHLAND, BARRON, BAYFIELD, BROWN, BUFFALO, BURNETT, CALUMET, CHIPPEWA, CLARK, COLUMBIA, CRAWFORD, DODGE, DOOR, DOUGLAS, DUNN, EAU CLAIRE, FLORENCE, FOND DU LAC, FOREST, GRANT, GREEN, GREEN LAKE, IRON, JACKSON, JUNEAU, IOWA, JEFFERSON, KEWAUNEE, LA CROSSE, LAFAYETTE, LANGLADE, LINCOLN, MANITOWOC, MARATHON, MARINETTE, MARQUETTE, MENOMINEE, MONROE, OCONTO, ONEIDA, OUTAGAMIE, PEPIN, PIERCE, POLK, PORTAGE, PRICE, RICHLAND, ROCK, RUSK, SAUK, SAWYER, SHAWANO, SHEBOYGAN, ST. CROIX, TAYLOR, TREMPEALEAU, VERNON, VILLAS, WALWORTH, WASHBURN, WAUPACA, WAUSHARA, WINNEBAGO, AND WOOD COUNTIES

	I	Rates	Fringes
LABORER			
Group	1\$	33.72	17.95
Group	2\$	33.82	17.95
Group	3\$	33.87	17.95
Group	4\$	34.07	17.95
Group	5\$	33.92	17.95
Group	6\$	30.35	17.95

### LABORER CLASSIFICATIONS

GROUP 1: General Laborer; Tree Trimmer; Conduit Layer; Demolition and Wrecking Laborer; Guard Rail, Fence, and Bridge Builder; Landscaper; Multiplate Culvert Assembler; Stone Handler; Bitminous Worker (Shoveler, Loader, and Utility Man); Batch Truck Dumper or Cement Handler; Bituminous Worker (Dumper, Ironer, Smoother and Tamper); Concrete Handler

GROUP 2: Air Tool Operator; Joint Sawer and Filler (Pavement); Vibrator or Tamper Operator (Mechanical Hand Operated); Chain Saw Operator, Demolition Burning Torch Laborer

GROUP 3: Bituminous Worker (Raker and Luteman); Formsetter (Curb, Sidewalk and Pavement); Strike Off Man

GROUP 4: Line and Grade Secialist

GROUP 5: Blaster; powderman

GROUP 6: Flagperson; Traffic Control

-----

LAB00464-003 06/01/2020

### DANE COUNTY

	Ī	Rates	Fringes
LABORER			
Group	1\$	34.00	17.95
Group	2\$	34.10	17.95
Group	3\$	34.15	17.95
Group	4\$	34.35	17.95
Group	5\$	34.20	17.95
Group	6\$	30.35	17.95

### LABORERS CLASSIFICATIONS:

GROUP 1: General Laborer; Tree Trimmer; Conduit Layer; Demolition and Wrecking Laborer; Guard Rail, Fence, and Bridge Builder; Landscaper; Multiplate Culvert Assembler; Stone Handler; Bituminous Worker (Shoveler, Loader, and Utility Man); Batch Truck Dumper or Cement Handler; Bituminious Worker (Dumper, Ironer, Smoother, and Tamper); Concrete Handler

GROUP 2: Air Tool Operator; Joint Sawer and Filler (Pavement); Vibrator or Tamper Operator (Mechanical Hand Operated); Chain Saw Operator; Demolition Burning Torch Laborer

GROUP 3: Bituminous Worker (Raker and Luteman); Formsetter (Curb, Sidewalk, and Pavement); Strike Off Man

GROUP 4: Line and Grade Specialist

GROUP 5: Blaster; Powderman

GROUP 6: Flagperson and Traffic Control Person

-----

PAIN0106-008 05/01/2017

ASHLAND, BAYFIELD, BURNETT, AND DOUGLAS COUNTIES

	F	Rates	Fringes
Painters:			
New:			
Brush,	Roller\$	30.33	17.27
Spray,	Sandblast, Steel\$	30.93	17.27
Repaint	:		
Brush,	Roller\$	28.83	17.27
Spray,	Sandblast, Steel\$	29.43	17.27

PAIN0108-002 06/01/2019

### RACINE COUNTY

	Rates	Fringes
Painters:		
Brush, Roller\$	36.08	20.36
Spray & Sandblast\$	37.08	20.36

# PAIN0259-002 05/01/2008

BARRON,	CHIPPEWA,	DUNN,	EAU CLAI	RE, PEPIN,	PIERCE,	POLK,	RUSK,
SAWYER,	ST. CROIX	, AND W	IASHBURN	COUNTIES			

	Rates	Fringes
PAINTER	•	12.15
PAIN0259-004 05/01/2015		
BUFFALO, CRAWFORD, JACKSON, LA VERNON COUNTIES	CROSSE, MONROI	E, TREMPEALEAU, AND
	Rates	Fringes
PAINTER	\$ 22.03	12.45
PAIN0781-002 06/01/2019		
JEFFERSON, MILWAUKEE, OZAUKEE,	WASHINGTON, AN	ND WAUKESHA COUNTIES
	Rates	Fringes
Painters: Bridge Brush Spray & Sandblast	\$ 32.95	23.86 23.86 23.86
PAIN0802-002 06/01/2019		
COLUMBIA, DANE, DODGE, GRANT, CROCK, AND SAUK COUNTIES	GREEN, IOWA, LA	AFAYETTE, RICHLAND,
	Rates	Fringes
PAINTER Brush	\$ 30.93	18.44
PREMIUM PAY: Structural Steel, Spray, Brid hour.	lges = \$1.00	additional per
PAIN0802-003 06/01/2019		
ADAMS, BROWN, CALUMET, CLARK, [	OOOR, FOND DU I	LAC, FOREST, GREEN

LAKE, IRON, JUNEAU, KEWAUNEE, LANGLADE, LINCOLN, MANITOWOC, MARATHON, MARINETTE, MARQUETTE, MENOMINEE, OCONTO, ONEIDA, OUTAGAMIE, PORTAGE, PRICE, SHAWANO, SHEBOYGAN, TAYLOR, VILAS, WAUSHARA, WAUPACA, WINNEBAGO, AND WOOD COUNTIES

	Rates	Fringes
PAINTER		18.58
PAIN0934-001 06/01/2017		
KENOSHA AND WALWORTH COUNTIES		
	Rates	Fringes
Painters:     Brush	\$ 34.74	18.95 18.95 18.95
FLORENCE COUNTY		
	Rates	Fringes
Painters:	•	13.33
PLAS0599-010 06/01/2017		
	Rates	Fringes
CEMENT MASON/CONCRETE FINISHER Area 1	\$ 35.07 \$ 35.61 \$ 34.70 \$ 36.27	17.17 19.75 19.40 20.51 18.73 22.99

### AREA DESCRIPTIONS

AREA 1: BAYFIELD, DOUGLAS, PRICE, SAWYER, AND WASHBURN COUNTIES

AREA 2: ADAMS, ASHLAND, BARRON, BROWN, BURNETT, CALUMET, CHIPPEWA, CLARK, COLUMBIA, DODGE, DOOR, DUNN, FLORENCE, FOND DU LAC, FOREST, GREEN LAKE, IRON, JEFFERSON, KEWAUNEE, LANGLADE, LINCOLN, MANITOWOC, MARATHON, MARINETTE,

MARQUETTE, MENOMINEE, OCONTO, ONEIDA, OUTAGAMIE, POLK, PORTAGE, RUSK, ST CROIX, SAUK, SHAWANO, SHEBOYGAN, TAYLOR, VILAS, WALWORTH, WAUPACA, WAUSHARA, WINNEBAGO, AND WOOD COUNTIES

AREA 3: BUFFALO, CRAWFORD, EAU CLAIRE, JACKSON, JUNEAU, LA CROSSE MONROE, PEPIN, PIERCE, RICHLAND, TREMPEALEAU, AND VERNON COUNTIES

AREA 4: MILWAUKEE, OZAUKEE, WASHINGTON, AND WAUKESHA COUNTIES

AREA 5: DANE, GRANT, GREEN, IOWA, LAFAYETTE, AND ROCK COUNTIES

AREA 6: KENOSHA AND RACINE COUNTIES

-----

PLUM0011-003 05/07/2018

ASHLAND, BAYFIELD, BURNETT, DOUGLAS, IRON, SAWYER, AND WASHBURN COUNTIES

MILWAUKEE, OZAUKEE, WASHINGTON, AND WAUKESHA COUNTIES

Rates Fringes

DODGE (Watertown), GREEN, JEFFERSON, LAFAYETTE, AND ROCK COUNTIES

COLUMBIA, DANE, IOWA, MARQUETTE, RICHLAND AND SAUK COUNTIES

	Rates	Fringes		
PLUMBER	.\$ 38.82	20.12		
PLUM0111-007 05/28/2018				
MARINETTE COUNTY (Niagara only)				
	Rates	Fringes		
PLUMBER/PIPEFITTER		24.48		
PLUM0118-002 06/01/2020				
KENOSHA, RACINE, AND WALWORTH CO	DUNTIES			
	Rates	Fringes		
Plumber and Steamfitter	.\$ 43.95	24.35		
PLUM0400-003 06/04/2018				
LAC, GREEN LAKE, KEWAUNEE, MANITO Niagara), MENOMINEE, OCONTO, OUT WAUPACA, WAUSHARA, AND WINNEBAGO	AGAMIE, SHAWANO COUNTIES	•		
PLUMBER/PIPEFITTER	.\$ 36.74	19.06		
PLUM0434-002 05/31/2020				
BARON, BUFFALO, CHIPPEWA, CLARK, CRAWFORD, DUNN, EAU CLAIRE, FLORENCE, FOREST, GRANT, JACKSON, JUNEAU, LA CROSSE, LANGLADE, LINCOLN, MARATHON, MONROE, ONEIDA, PEPIN, PIERCE, POLK, PORTAGE, PRICE, RUSK, ST. CROIX, TAYLOR, TREMPEALEAU, VERNON, VILAS, AND WOOD COUNTIES				
	Rates	Fringes		
PIPEFITTER	.\$ 42.70	Fringes 20.47		
PIPEFITTER	.\$ 42.70	· ·		

	Rates	Fringes			
PIPEFITTER	•	25.29			
PLUM0601-009 06/04/2017					
COLUMBIA, DANE, IOWA, MARQUETTE,	RICHLAND AN	D SAUK COUNTIES			
	Rates	Fringes			
PIPEFITTER	.\$ 47.08	20.89			
TEAM0039-002 06/01/2020					
	Rates	Fringes			
TRUCK DRIVER  1 & 2 Axle Trucks  3 or more axles; Euclids	.\$ 31.07	22.94			
or Dumptor, Articulated Truck, Mechanic	.\$ 31.22	22.94			
SUWI2011-001 11/16/2011					
	Rates	Fringes			
WELL DRILLER	.\$ 16.52				
WELDERS - Receive rate prescribed for craft performing operation to which welding is incidental.					

\_\_\_\_\_

Note: Executive Order (EO) 13706, Establishing Paid Sick Leave for Federal Contractors applies to all contracts subject to the Davis-Bacon Act for which the contract is awarded (and any solicitation was issued) on or after January 1, 2017. If this contract is covered by the EO, the contractor must provide employees with 1 hour of paid sick leave for every 30 hours they work, up to 56 hours of paid sick leave each year. Employees must be permitted to use paid sick leave for their own illness, injury or other health-related needs, including preventive care; to assist a family member (or person who is like family to the employee) who is ill, injured, or has other health-related needs, including preventive care; or for reasons resulting from, or to assist a family member (or person who is like family to the employee) who is a victim of, domestic violence, sexual assault, or stalking. Additional information

on contractor requirements and worker protections under the EO is available at www.dol.gov/whd/govcontracts.

Unlisted classifications needed for work not included within the scope of the classifications listed may be added after award only as provided in the labor standards contract clauses (29CFR 5.5 (a) (1) (ii)).

-----

The body of each wage determination lists the classification and wage rates that have been found to be prevailing for the cited type(s) of construction in the area covered by the wage determination. The classifications are listed in alphabetical order of ""identifiers"" that indicate whether the particular rate is a union rate (current union negotiated rate for local), a survey rate (weighted average rate) or a union average rate (weighted union average rate).

### Union Rate Identifiers

A four letter classification abbreviation identifier enclosed in dotted lines beginning with characters other than ""SU"" or ""UAVG"" denotes that the union classification and rate were prevailing for that classification in the survey. Example: PLUM0198-005 07/01/2014. PLUM is an abbreviation identifier of the union which prevailed in the survey for this classification, which in this example would be Plumbers. 0198 indicates the local union number or district council number where applicable, i.e., Plumbers Local 0198. The next number, 005 in the example, is an internal number used in processing the wage determination. 07/01/2014 is the effective date of the most current negotiated rate, which in this example is July 1, 2014.

Union prevailing wage rates are updated to reflect all rate changes in the collective bargaining agreement (CBA) governing this classification and rate.

### Survey Rate Identifiers

Classifications listed under the ""SU"" identifier indicate that no one rate prevailed for this classification in the survey and the published rate is derived by computing a weighted average rate based on all the rates reported in the survey for that classification. As this weighted average rate includes all rates reported in the survey, it may include both union and non-union rates. Example: SULA2012-007 5/13/2014. SU indicates

the rates are survey rates based on a weighted average calculation of rates and are not majority rates. LA indicates the State of Louisiana. 2012 is the year of survey on which these classifications and rates are based. The next number, 007 in the example, is an internal number used in producing the wage determination. 5/13/2014 indicates the survey completion date for the classifications and rates under that identifier.

Survey wage rates are not updated and remain in effect until a new survey is conducted.

Union Average Rate Identifiers

Classification(s) listed under the UAVG identifier indicate that no single majority rate prevailed for those classifications; however, 100% of the data reported for the classifications was union data. EXAMPLE: UAVG-OH-0010 08/29/2014. UAVG indicates that the rate is a weighted union average rate. OH indicates the state. The next number, 0010 in the example, is an internal number used in producing the wage determination. 08/29/2014 indicates the survey completion date for the classifications and rates under that identifier.

A UAVG rate will be updated once a year, usually in January of each year, to reflect a weighted average of the current negotiated/CBA rate of the union locals from which the rate is based.

-----

### WAGE DETERMINATION APPEALS PROCESS

- 1.) Has there been an initial decision in the matter? This can be:
- \* an existing published wage determination
- \* a survey underlying a wage determination
- \* a Wage and Hour Division letter setting forth a position on a wage determination matter
- \* a conformance (additional classification and rate) ruling

On survey related matters, initial contact, including requests for summaries of surveys, should be with the Wage and Hour Regional Office for the area in which the survey was conducted because those Regional Offices have responsibility for the Davis-Bacon survey program. If the response from this initial contact is not satisfactory, then the process described in 2.) and 3.) should be followed.

With regard to any other matter not yet ripe for the formal process described here, initial contact should be with the Branch of Construction Wage Determinations. Write to:

Branch of Construction Wage Determinations Wage and Hour Division U.S. Department of Labor 200 Constitution Avenue, N.W. Washington, DC 20210

2.) If the answer to the question in 1.) is yes, then an interested party (those affected by the action) can request review and reconsideration from the Wage and Hour Administrator (See 29 CFR Part 1.8 and 29 CFR Part 7). Write to:

Wage and Hour Administrator U.S. Department of Labor 200 Constitution Avenue, N.W. Washington, DC 20210

The request should be accompanied by a full statement of the interested party's position and by any information (wage payment data, project description, area practice material, etc.) that the requestor considers relevant to the issue.

3.) If the decision of the Administrator is not favorable, an interested party may appeal directly to the Administrative Review Board (formerly the Wage Appeals Board). Write to:

Administrative Review Board U.S. Department of Labor 200 Constitution Avenue, N.W. Washington, DC 20210

4.) All decisions by the Administrative Review Board are final.

\_\_\_\_\_\_

END OF GENERAL DECISION"



# **Wisconsin Department of Transportation**

September 2, 2020

# **Division of Transportation Systems Development**

Bureau of Project Development 4822 Madison Yards Way, 4<sup>th</sup> Floor South Madison, WI 53705

Telephone: (608) 266-1631 Facsimile (FAX): (608) 266-8459

### **NOTICE TO ALL CONTRACTORS:**

Proposal #04: 1228-28-70, WIS 2020 412

Hillside Interchange

W Wisconsin To W Walnut ST

IH 43

**Milwaukee County** 

# Letting of September 15, 2020

This is Addendum No. 01, which provides for the following:

### Schedule of Items:

	Added Bid Item Quantities					
Bid Item	Item Description		Old	Revised	Proposal	
Did itelli			Quantity	Quantity	Total	
631.0300	Sod Water	MGAL	0	9	9	
649.0150	Temporary Marking Line Removal Tape 4-	LF	0	600	600	
049.0150	Inch	L	U	000	000	

### **Plan Sheets:**

	Added Plan Sheets				
Plan Sheet	Plan Sheet Title (brief description of why sheet was added)				
108 A	Miscellaneous Quantities (Items for "Sod Water" and "Temporary Marking Line Removal Tape 4-Inch" were missed in earlier Plan Set.)				

### Schedule of Items

Attached, dated September 2, 2020, are the revised Schedule of Items Page 9.

### **Plan Sheets**

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:

Added: 108A

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist Proposal Management Section

**END OF ADDENDUM** 

Addendum No. 01 ID 1228-28-70 Added Sheet 108A September 2, 2020

2	649.0150	TEMPORARY MARKING LINE REMOVAL TAPE 4-INCH	FT	000	000	009
			ROADWAY	KILBOURN EXIT	RAMP TUNNEL	TOTAL
2			CATEGORY	1000		

HOSION CONTROL	631.0300			MGAL	5		4		6
				ROADWAY	KILBOURN ON	RAMP TUNNEL	KILBOURN EXIT	RAMP TUNNEL	TOTAL
_				CATEGORY	1000				

MISCELLANEOUS QUANTITIES COUNTY: MILWAUKEE PROJECT NO: 1228-28-70 FILE NAME :



# Proposal Schedule of Items

Page 9 of 9

Federal ID(s): WISC 2020412

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0246	SPV.0090 Special 0001. Pavement Marking Contrast Epoxy 4-Inch	844.000 LF		
0248	SPV.0090 Special 0002. Pavement Marking Contrast Epoxy 8-Inch	859.000 LF		
0250	SPV.0090 Special 4002. Ventilation Opening Edge Repair	75.000 LF		·
0252	SPV.0105 Special 4105. Remove and Replace Sidewalk Cover Plate	LS	LUMP SUM	
0254	SPV.0105 Special 4205. Slip-Resistant Treatment Of Sidewalk Cover Plate B-40-686	LS	LUMP SUM	
0256	SPV.0105 Special 4305. Slip-Resistant Treatment Of Sidewalk Cover Plate B-40-689	LS	LUMP SUM	
0258	SPV.0165 Special 4202. Shotcrete Surface Repair	1,965.000 SF		
0260	SPV.0180 Special 4301. Cleaning Tunnel Wall and Ceiling	19,238.000 SY	·	·
0262	SPV.0180 Special 4302. Hydro-Demolition of Concrete Masonry Deck Overlay B-40- 293	3,968.000 SY		
0264	631.0300 Sod Water	9.000 MGAL	·	
0266	649.0150 Temporary Marking Line Removable Tape 4-Inch	600.000 LF		
	Section: 000	)1	Total:	·

Total Bid: