#### HIGHWAY WORK PROPOSAL

Wisconsin Department of Transportation 06/2017 s.66.0901(7) Wis. Stats

STATE PROJECT

COUNTY

Proposal Number:

Douglas 1198-03-78 WISC 2021105 C Superior, East Second Street; 29th

**FEDERAL** 

Avenue East - 53rd Avenue East

PROJECT DESCRIPTION

**USH 002** 

**HIGHWAY** 

# ADDENDUM REQUIRED

ATTACHED AT BACK

This proposal, submitted by the undersigned bidder to the Wisconsin Department of Transportation, is in accordance with the advertised request for proposals. The bidder is to furnish and deliver all materials, and to perform all work for the improvement of the designated project in the time specified, in accordance with the appended Proposal Requirements and Conditions.

Proposal Guaranty Required: \$100,000.00  Payable to: Wisconsin Department of Transportation	Attach Proposal Guaranty on back of this PAGE.
Bid Submittal Date: January 12, 2021 Time (Local Time): 11:00 am	Firm Name, Address, City, State, Zip Code SAMPLE
Contract Completion Time October 01, 2021	NOT FOR BIDDING PURPOSES
Assigned Disadvantaged Business Enterprise Goal 3%	This contract is exempt from federal oversight.

This certifies that the undersigned bidder, duly sworn, is an authorized representative of the firm named above; that the bidder has examined and carefully prepared the bid from the plans, Highway Work Proposal, and all addenda, and has checked the same in detail before submitting this proposal or bid; and that the bidder or agents, officer, or employees have not, either directly or indirectly, entered into any agreement, participated in any collusion, or otherwise taken any action in restraint of free competitive bidding in connection with this proposal bid.

Type of Work:

Grade, Base, Concrete Pavement, Asphalt Pavement, Curb & Gutter, Signals, Signing, Pavement Marking, Structures B-16-66, 67

Notice of Award Dated

Date Guaranty Returned

# PLEASE ATTACH PROPOSAL GUARANTY HERE

#### **Effective with November 2007 Letting**

#### PROPOSAL REQUIREMENTS AND CONDITIONS

The bidder, signing and submitting this proposal, agrees and declares as a condition thereof, to be bound by the following conditions and requirements.

If the bidder has a corporate relationship with the proposal design engineering company, the bidder declares that it did not obtain any facts, data, or other information related to this proposal from the design engineering company that was not available to all bidders.

The bidder declares that they have carefully examined the site of, and the proposal, plans, specifications and contract forms for the work contemplated, and it is assumed that the bidder has investigated and is satisfied as to the conditions to be encountered, as to the character, quality, and quantities of work to be performed and materials to be furnished, and as to the requirements of the specifications, special provisions and contract. It is mutually agreed that submission of a proposal shall be considered conclusive evidence that the bidder has made such examination.

The bidder submits herewith a proposal guaranty in proper form and amount payable to the party as designated in the advertisement inviting proposals, to be retained by and become the property of the owner of the work in the event the undersigned shall fail to execute the contract and contract bond and return the same to the office of the engineer within fourteen (14) days after having been notified in writing to do so; otherwise to be returned.

The bidder declares that they understand that the estimate of quantities in the attached schedule is approximate only and that the attached quantities may be greater or less in accordance with the specifications.

The bidder agrees to perform the said work, for and in consideration of the payment of the amount becoming due on account of work performed, according to the unit prices bid in the following schedule, and to accept such amounts in full payment of said work.

The bidder declares that all of the said work will be performed at their own proper cost and expense, that they will furnish all necessary materials, labor, tools, machinery, apparatus, and other means of construction in the manner provided in the applicable specifications and the approved plans for the work together with all standard and special designs that may be designed on such plans, and the special provisions in the contract of which this proposal will become a part, if and when accepted. The bidder further agrees that the applicable specifications and all plans and working drawings are made a part hereof, as fully and completely as if attached hereto.

The bidder, if awarded the contract, agrees to begin the work not later than ten (10) days after the date of written notification from the engineer to do so, unless otherwise stipulated in the special provisions.

The bidder declares that if they are awarded the contract, they will execute the contract agreement and begin and complete the work within the time named herein, and they will file a good and sufficient surety bond for the amount of the contract for performance and also for the full amount of the contract for payment.

The bidder, if awarded the contract, shall pay all claims as required by Section 779.14, Statutes of Wisconsin, and shall be subject to and discharge all liabilities for injuries pursuant to Chapter 102 of the Statutes of Wisconsin, and all acts amendatory thereto. They shall further be responsible for any damages to property or injury to persons occurring through their own negligence or that of their employees or agents, incident to the performance of work under this contract, pursuant to the Standard Specifications for Road and Bridge Construction applicable to this contract.

In connection with the performance of work under this contract, the contractor agrees to comply with all applicable state and federal statutes relating to non-discrimination in employment. No otherwise qualified person shall be excluded from employment or otherwise be subject to discrimination in employment in any manner on the basis of age, race, religion, color, gender, national origin or ancestry, disability, arrest or conviction record (in keeping with s.111.32), sexual orientation, marital status, membership in the military reserve, honesty testing, genetic testing, and outside use of lawful products. This provision shall include, but not be limited to the following: employment, upgrading, demotion or transfer; recruitment or recruitment advertising; layoff or termination; rates of pay or other forms of compensation, and selection for training, including apprenticeship. The contractor further agrees to ensure equal opportunity in employment to all applicants and employees and to take affirmative action to attain a representative workforce.

The contractor agrees to post notices and posters setting forth the provisions of the nondiscrimination clause, in a conspicuous and easily accessible place, available for employees and applicants for employment.

If a state public official (section 19.42, Stats.) or an organization in which a state public official holds at least a 10% interest is a party to this agreement, this contract is voidable by the state unless appropriate disclosure is made to the State of Wisconsin Ethics Board.

#### **Effective with August 2015 Letting**

## BID PREPARATION

#### Preparing the Proposal Schedule of Items

#### A General

- (1) Obtain bidding proposals as specified in section 102 of the standard specifications prior to 11:45 AM of the last business day preceding the letting. Submit bidding proposals using one of the following methods:
  - 1. Electronic bid on theinternet.
  - 2. Electronic bid on a printout with accompanying diskette or CD ROM.
  - 3. Paper bid under a waiver of the electronic submittal requirements.
- (2) Bids submitted on a printout with accompanying diskette or CD ROM or paper bids submitted under a waiver of the electronic submittal requirements govern over bids submitted on the internet.
- (3) The department will provide bidding information through the department's web site at: <a href="https://wisconsindot.gov/Pages/doing-bus/contractors/hcci/bid-let.aspx">https://wisconsindot.gov/Pages/doing-bus/contractors/hcci/bid-let.aspx</a>

The contractor is responsible for reviewing this web site for general notices as well as information regarding proposals in each letting. The department will also post special notices of all addenda to each proposal through this web site no later than 4:00 PM local time on the Thursday before the letting. Check the department's web site after 5:00 PM local time on the Thursday before the letting to ensure all addenda have been accounted for before preparing the bid. When bidding using methods 1 and 2 above, check the Bid Express<sup>TM</sup> on-line bidding exchange at <a href="http://www.bidx.com/">http://www.bidx.com/</a> after 5:00 PM local time on the Thursday before the letting to ensure that the latest schedule of items Expedite file (\*.ebs or \*.00x) is used to submit the final bid.

(4) Interested parties can subscribe to the Bid Express<sup>TM</sup> on-line bidding exchange by following the instructions provided at the www.bidx.com web site or by contacting:

Info Tech Inc.
5700 SW 34th Street, Suite 1235
Gainesville, FL 32608-5371
email: mailto:customer.support@bidx.com

- (5) The department will address equipment and process failures, if the bidder can demonstrate that those failures were beyond their control.
- (6) Contractors are responsible for checking on the issuance of addenda and for obtaining the addenda. Notice of issuance of addenda is posted on the department's web site at: <a href="https://wisconsindot.gov/Pages/doing-bus/contractors/hcci/bid-let.aspx">https://wisconsindot.gov/Pages/doing-bus/contractors/hcci/bid-let.aspx</a>

or by calling the department at (608) 266-1631. Addenda can ONLY be obtained from the departments web site listed above or by picking up the addenda at the Bureau of Highway Construction, 4<sup>th</sup> floor, 4822 Madison Yards Way, Madison, WI, during regular business hours

(7) Addenda posted after 5:00 PM on the Thursday before the letting will be emailed to the eligible bidders for that proposal. All eligible bidders shall acknowledge receipt of the addenda whether they are bidding on the proposal or not. Not acknowledging receipt may jeopardize the awarding of the project.

#### **B Submitting Electronic Bids**

#### **B.1** On the Internet

- (1) Do the following before submitting the bid:
  - 1. Have a properly executed annual bid bond on file with the department.

- 2. Have a digital ID on file with and enabled by Info Tech Inc. Using this digital ID will constitute the bidder's signature for proper execution of the bidding proposal.
- (2) In lieu of preparing, delivering, and submitting the proposal as specified in 102.6 and 102.9 of the standard specifications, submit the proposal on the internet as follows:
  - 1. Download the latest schedule of items reflecting all addenda from the Bid Express TM web site.
  - 2. Use Expedite TM software to enter a unit price for every item in the schedule of items.
  - 3. Submit the bid according to the requirements of Expedite<sup>TM</sup> software and the Bid Express<sup>TM</sup> web site. Do not submit a bid on a printout with accompanying diskette or CD ROM or a paper bid. If the bidder does submit a bid on a printout with accompanying diskette or a paper bid in addition to the internet submittal, the department will disregard the internet bid.
  - 4. Submit the bid before the hour and date the Notice to Contractors designates.
  - 5. Do not sign, notarize, and return the bidding proposal described in 102.2 of the standard specifications.
- (3) The department will not consider the bid accepted until the hour and date the Notice to Contractors designates.

#### B.2 On a Printout with Accompanying Diskette or CD ROM

(1) Download the latest schedule of items from the Wisconsin pages of the Bid Express<sup>TM</sup> web site reflecting the latest addenda posted on the department's web site at:

https://wisconsindot.gov/Pages/doing-bus/contractors/hcci/bid-let.aspx

Use Expedite TM software to prepare and print the schedule of items. Provide a valid amount for all price fields. Follow instructions and review the help screens provided on the Bid Express Web site to assure that the schedule of items is prepared properly.

(2) Staple an 8 1/2 by 11 inch printout of the Expedite<sup>TM</sup> generated schedule of items to the other proposal documents submitted to the department as a part of the bidder's sealed bid. As a separate submittal, not in the sealed bid envelop but due at the same time and place as the sealed bid, also provide the Expedite<sup>TM</sup> generated schedule of items on a 3 1/2 inch computer diskette or CD ROM. Label each diskette or CD ROMwith the bidder's name, the 4 character department-assigned bidder identification code from the top of the bidding proposal, and a list of the proposal numbers included on that diskette or CD ROM as indicated in the following example:

**Bidder Name** 

**BN00** 

Proposals: 1, 12, 14, & 22

- (3) If bidding on more than one proposal in the letting, the bidder may include all proposals for that letting on one diskette or CD ROM. Include only submitted proposals with no incomplete or other files on the diskette or CD ROM.
- (4) The bidder-submitted printout of the Expedite<sup>TM</sup> generated schedule of items is the governing contract document and must conform to the requirements of section 102 of the standard specifications. If a printout needs to be altered, cross out the printed information with ink or typewriter and enter the new information and initial it in ink. If there is a discrepancy between the printout and the diskette or CD ROM, the department will analyze the bid using the printout information.
- (5) In addition to the reasons specified in section 102 of the standard specifications, proposals are irregular and the department may reject them for one or more of the following:
  - 1. The check code printed on the bottom of the printout of the Expedite<sup>TM</sup> generated schedule of items is not the same on each page.
  - 2. The check code printed on the printout of the Expedite<sup>TM</sup> generated schedule of items is not the same as the check code for that proposal provided on the diskette or CD ROM.

3. The diskette or CD ROM is not submitted at the time and place the department designates.

#### C Waiver of Electronic Submittal

- (1) The bidder may request a waiver of the electronic submittal requirements. Submit a written request for a waiver in lieu of bids submitted on the internet or on a printout with accompanying diskette or CD ROM. Use the waiver that was included with the paper bid document sent to the bidder or type up a waiver on the bidder's letterhead. The department will waive the electronic submittal requirements for a bidding entity (individual, partnership, joint venture, corporation, or limited liability company) for up to 4 individual proposals in a calendar year. The department may allow additional waivers for equipment malfunctions.
- (2) Submit a schedule of items on paper conforming to section 102 of the standard specifications. The department charges the bidder a \$75 administrative fee per proposal, payable at the time and place the department designates for receiving bids, to cover the costs of data entry. The department will accept a check or money order payable to: "Wisconsin, Dept. of Transportation."
- (3) In addition to the reasons specified in section 102 of the standard specifications, proposals are irregular and the department may reject them for one or more of the following:
  - 1. The bidder fails to provide the written request for waiver of the electronic submittal requirements.
  - 2. The bidder fails to pay the \$75 administrative fee before the time the department designates for the opening of bids unless the bidder requests on the waiver that they be billed for the \$75.
  - 3. The bidder exceeds 4 waivers of electronic submittal requirements within a calendar year.
- (4) In addition to the reasons specified in section 102 of the standard specifications, the department may refuse to issue bidding proposals for future contracts to a bidding entity that owes the department administrative fees for a waiver of electronic submittal requirements.

#### PROPOSAL BID BOND

DT1303 1/2006

Wisconsin Department of Transportation

Proposal Number	Project Number		Letting Date
Name of Principal			
Name of Surety		State in Which Surety is	Organized

We, the above-named Principal and the above-named Surety, are held and firmly bound unto the State of Wisconsin in the sum equal to the Proposal Guaranty for the total bid submitted for the payment to be made; we jointly and severally bind ourselves, our heirs, executors, administrators, successors and assigns. The condition of this obligation is that the Principal has submitted a bid proposal to the State of Wisconsin acting through the Department of Transportation for the improvement designated by the Proposal Number and Letting Date indicated above.

If the Principal is awarded the contract and, within the time and manner required by law after the prescribed forms are presented for signature, enters into a written contract in accordance with the bid, and files the bond with the Department of Transportation to guarantee faithful performance and payment for labor and materials, as required by law, or if the Department of Transportation shall reject all bids for the work described, then this obligation shall be null and void; otherwise, it shall be and remain in full force and effect. In the event of failure of the Principal to enter into the contract or give the specified bond, the Principal shall pay to the Department of Transportation within 10 business days of demand a total equal to the Proposal Guaranty as liquidated damages; the liability of the Surety continues for the full amount of the obligation as stated until the obligation is paid in full.

The Surety, for value received, agrees that the obligations of it and its bond shall not be impaired or affected by any extension of time within which the Department of Transportation may accept the bid; and the Surety does waive notice of any such extension.

IN WITNESS, the Principal and Surety have agreed and have signed by their proper officers and have caused their corporate seals to be affixed this date: **(DATE MUST BE ENTERED)** 

#### **PRINCIPAL**

(Company Name) (Affix Corporate S	eal)		
(Signature and Title)			
(Company Name)			
(Signature and Title)			
(Company Name)			
(Signature and Title)		(Name of Surety) (Affix Seal)	
(Company Name)		(Signature of Attorney-in-Fact)	
(Signature and Title)			
NOTARY FOR P	RINCIPAL	NOTARY FO	OR SURETY
(Date)		(Da	te)
State of Wisconsin	)	State of Wisconsin	)
C	) ss. ounty )		) ss. _County )
On the above date, this instrument was named person(s).	acknowledged before me by the	On the above date, this instrument w named person(s).	as acknowledged before me by the
(Signature, Notary Public,	State of Wisconsin)	(Signature, Notary Publ	ic, State of Wisconsin)
(Print or Type Name, Notary Pu	blic, State of Wisconsin)	(Print or Type Name, Notary	Public, State of Wisconsin)
(Date Commissio	n Expires)	(Date Commis	sion Expires)

Notary Seal Notary Seal

IMPORTANT: A certified copy of Power of Attorney of the signatory agent must be attached to the bid bond.

#### **CERTIFICATE OF ANNUAL BID BOND**

DT1305 8/2003

Wisconsin Department of Transportation

(Date)

Time Period Valid (	From/To)
Name of Surety	
Name of Contracto	r
Certificate Holder	Wisconsin Department of Transportation
	y that an annual bid bond issued by the above-named Surety is currently on file with the partment of Transportation.
	is issued as a matter of information and conveys no rights upon the certificate holder mend, extend or alter the coverage of the annual bid bond.
Cancellation:	Should the above policy be cancelled before the expiration date, the issuing surety will give thirty (30) days written notice to the certificate holder indicated above.

(Signature of Authorized Contractor Representative)

#### March 2010

#### LIST OF SUBCONTRACTORS

Section 66.0901(7), Wisconsin Statutes, provides that as a part of the proposal, the bidder also shall submit a list of the subcontractors the bidder proposes to contract with and the class of work to be performed by each. In order to qualify for inclusion in the bidder's list a subcontractor shall first submit a bid in writing, to the general contractor at least 48 hours prior to the time of the bid closing. The list may not be added to or altered without the written consent of the municipality. A proposal of a bidder is not invalid if any subcontractor and the class of work to be performed by the subcontractor has been omitted from a proposal; the omission shall be considered inadvertent or the bidder will perform the work personally.

No subcontract, whether listed herein or later proposed, may be entered into without the written consent of the Engineer as provided in Subsection 108.1 of the Standard Specifications.

Name of Subcontractor	Class of Work	Estimated Value	
			_
			_
			_

#### **DECEMBER 2000**

## CERTIFICATION REGARDING DEBARMENT, SUSPENSION, AND OTHER RESPONSIBILITY MATTERS - PRIMARY COVERED TRANSACTIONS

#### **Instructions for Certification**

- 1. By signing and submitting this proposal, the prospective contractor is providing the certification set out below.
- 2. The inability of a person to provide the certification required below will not necessarily result in denial of participation in this covered transaction. The prospective contractor shall submit an explanation of why it cannot provide the certification set out below. The certification or explanation will be considered in connection with the department or agency's determination whether to enter into this transaction. However, failure of the prospective contractor to furnish a certification or an explanation shall disqualify such person from participation in this transaction.
- 3. The certification in this clause is a material representation of fact upon which reliance was placed when the department determined to enter into this transaction. If it is later determined that the contractor knowingly rendered an erroneous certification in addition to other remedies available to the Federal Government the department may terminate this transaction for cause or default.
- 4. The prospective contractor shall provide immediate written notice to the department to whom this proposal is submitted if at any time the prospective contractor learns that its certification was erroneous when submitted or has become erroneous by reason of changed circumstances.
- 5. The terms "covered transaction," "debarred," "suspended," "ineligible," "lower tier covered transaction," "participant," "person," "primary covered transaction," "principal," "proposal," and "voluntarily excluded," as used in this clause, have the meanings set out in the Definitions and Coverage sections of the rules implementing Executive Order 12549. You may contact the department to which this proposal is being submitted for assistance in obtaining a copy of those regulations.
- 6. The prospective contractor agrees by submitting this proposal that, should this contract be entered into, it shall not knowingly enter into any lower tier covered transaction with a person who is debarred, suspended, declared ineligible, or voluntarily excluded from participation in this covered transaction, unless authorized by the department entering into this transaction.
- 7. The prospective contractor further agrees by submitting this proposal that it will include the clause titled "Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion-Lower Tier Covered Transaction," which is included as an addendum to PR-1273 "Required Contract Provisions Federal Aid Construction Contracts," without

modification, in all lower tier covered transactions and in all solicitations for lower tier covered transactions.

- 8. The contractor may rely upon a certification of a prospective subcontractor/materials supplier that it is not debarred, suspended, ineligible, or voluntarily excluded from the covered transaction, unless it knows that the certification is erroneous. A contractor may decide the method and frequency by which it determines the eligibility of its principals. Each contractor may, but is not required to, check the Disapproval List (telephone # 608/266/1631).
- 9. Nothing contained in the foregoing shall be construed to require establishment of a system of records in order to render in good faith the certification required by this clause. The knowledge and information of a contractor is not required to exceed that which is normally possessed by a prudent person in the ordinary course of business dealings.
- 10. Except for transactions authorized under paragraph 6 of these instructions, if a contractor in a covered transaction knowingly enters into a lower tier covered transaction with a person who is suspended, debarred, ineligible or voluntarily excluded from participation in this transaction, in addition to other remedies available to the Federal Government, the department may terminate this transaction for cause or default.

Certification Regarding Debarment, Suspension, and Other Responsibility Matters - Primary Covered Transactions

- (1) The prospective contractor certifies to the best of its knowledge and belief, that it and its principals:
  - (a) Are not presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from covered transactions by any Federal department or agency;
  - (b) Have not within a three-year period preceding this proposal been convicted of or had a civil judgment rendered against them for commission of fraud or a criminal offense in connection with obtaining, attempting to obtain, or performing a public (Federal, State or local) transaction or contract under a public transaction; violation of Federal or State antitrust statutes or commission of embezzlement, theft, forgery, bribery, falsification or destruction of records, making false statements or receiving stolen property;
  - (c) Are not presently indicted for or otherwise criminally or civilly charged by a governmental entity (Federal, State or local) with commission of any of the offense enumerated in paragraph (1)(b) of this certification; and
  - (d) Have not within a three-year period preceding this proposal had one or more public transactions (Federal, State or local) terminated for cause or default.
- (2) Where the prospective contractor is unable to certify to any of the statements in this certification, such prospective contractor shall attach an explanation to this proposal.

#### **Special Provisions**

#### **Table of Contents**

	Article Description	Page #
1.	General	3
2.	Scope of Work	3
3.	Prosecution and Progress	3
4.	Traffic.	4
5.	Holiday Work Restrictions	7
6.	Utilities	7
7.	Railroad Insurance and Coordination - BNSF Railway Company	10
3.	Hauling Restrictions.	13
9.	Roadway Maintenance	13
10.	Notice to Contractor – Contamination Beyond Construction Limits	14
11.	Notice to Contractor, Verification of Asbestos Inspection, No Asbestos Fo	ound14
12.	Notice to Contractor, Environmental Commitments and Environmentally S	Sensitive areas14
13.	Notice to Contractor, Environmental Commitments	14
14.	Notice to Contractor – Traffic Signal Equipment Lead Time and Coordina	ation15
15.	Notice to Contractor, Construction Equipment Height Notification – FAA F	Regulations15
16.	Notice to Contractor, Railroad Overhead	15
17.	Construction Over or Adjacent to Navigable Waters.	15
18.	City of Superior (street lighting).	15
19.	Archaeological Site.	16
20.	Environmental.	17
21.	Coordination with Businesses and Residents.	17
22.	Municipality Acceptance of Sanitary Sewer Construction	17
23.	Removing Pavement, Curb & Gutter, and Concrete Sidewalk	17
24.	Removing Concrete Surface Partial Depth, Item 204.0109.S.	17
25.	Removing Traffic Signals USH 2 & 39 <sup>th</sup> Ave, Item 204.9105.S.01	18
26.	Excavation, Hauling, and Disposal of Petroleum-Contaminated Soil, Item	205.0501.S19
27.	Prepare Foundation for Asphaltic Paving.	21
28.	Concrete Pavement 9-Inch, Item 415.0090; Concrete Pavement Repair, Pavement Replacement, Item 416.1720	
29.	HMA Pavement 5 SMA 58-34 V, Item 460.8645 HMA Pavement Test Str 460.0115.S HMA Pavement Test Strip Density, Item 460.0120.S	
30.	QMP HMA Pavement Nuclear Density.	25
31.	Sawing Pavement Deck Preparation Areas, Item 509.0310.S	28
32.	Concrete Masonry Deck Repair, Item 509.2100.S.	29
33.	Polymer Overlay, Item 509.5100.S.	30
34.	Adjusting Manhole Covers.	34
35.	Cover Plates Temporary, Item 611.8120.S	35
36.	Field Office	35

37.	General Requirements for Electrical Work	36
38.	Electrical Service Meter Breaker Pedestal USH 2 & 39th Ave, Item 656.0200.01	36
39.	Traffic Signals, General	36
40.	Temporary Traffic Signals for Intersections USH 2 & 39 <sup>th</sup> Ave, Item 661.0200.01	36
41.	Flashing Beacon Queue Warning System, Item SPV.0045.01	37
42.	Elastomeric Waterproofing Sealer, Item SPV.0060.01	40
43.	Protecting Footing, Item SPV.0060.02	40
44.	Cure and Seal Treatment, Concrete Curb and Gutter, Item SPV.0090.01; Cure and Seal Treatment, Concrete Sidewalk, Item SPV.0165.01.	41
45.	Traffic Signal Cabinet and Controller USH 2 & 39 <sup>th</sup> Ave, Item SPV.0105.01	42
46.	Furnish and Install Emergency Vehicle Preemption System USH 2 & 39th Ave, Item SPV.0105.02	53
47.	Vehicular Video Detection System USH 2 & 39 <sup>th</sup> Ave, Item SPV.0105.03	54
48.	Material Transfer Vehicle, Project 1198-03-78, Item SPV.0105.04.	58
49.	Pigmented Surface Sealer Reseal, Item SPV.0180.01.	59

1198-03-78 2 of 59

#### STSP'S Revised June 29, 2020 SPECIAL PROVISIONS

#### 1. General.

Perform the work under this construction contract for Project 1198-03-78, City of Superior, East Second Street, 29th Avenue East to 53<sup>rd</sup> Avenue East, USH 2, Douglas County, Wisconsin as the plans show and execute the work as specified in the State of Wisconsin, Department of Transportation, Standard Specifications for Highway and Structure Construction, 2021 Edition, as published by the department, and these special provisions.

If all or a portion of the plans and special provisions are developed in the SI metric system and the schedule of prices is developed in the US standard measure system, the department will pay for the work as bid in the US standard system.

100-005 (20200629)

#### 2. Scope of Work.

The work under this contract shall consist of removing concrete surface partial depth, concrete pavement, concrete pavement repair and replacement, asphaltic surface patching, HMA pavement, storm sewer inlet and manhole repair, concrete sidewalk and curb ramp installations, bridge rehabilitations, traffic signal replacement, pavement markings and all incidental items necessary to complete the work as shown on the plans and included in the proposal and contract.

104-005 (20090901)

#### 3. Prosecution and Progress.

Begin work within ten calendar days after the engineer issues a written notice to do so.

Provide the start date to the engineer in writing within a month after executing the contract but at least 14 calendar days before the preconstruction conference. Upon approval, the engineer will issue the notice to proceed within ten calendar days before the approved start date.

To revise the start date, submit a written request to the engineer at least two weeks before the intended start date. The engineer will approve or deny that request based on the conditions cited in the request and its effect on the department's scheduled resources.

The contract time for completion is based on an expedited work schedule and may require extraordinary forces and equipment.

#### Northern Long-eared Bat (Myotis septentrionalis)

Northern Long-eared Bats (NLEB) have the potential to inhabit the project limits because they roost in trees. Roosts may not have been observed on this project, but conditions to support the species exist. The species and all active roosts are protected by the Federal Endangered Species Act. If an individual bat or active roost is encountered during construction operations, stop work and notify the engineer and the WisDOT Regional Environmental Coordinator (REC).

If additional construction activities beyond what was originally specified are required to complete the work, approval from the engineer, following coordination with WisDOT REC, is required prior to initiating these activities.

#### **Migratory Birds**

Swallow and other migratory birds' nests have been observed on or under the existing bridge. All active nests (when eggs or young are present) of migratory birds are protected under the federal Migratory Bird Treaty Act.

The nesting season for swallows and other birds is usually between May 1 and August 30. Either prevent active nests from becoming established or apply for a depredation permit from the US Fish and Wildlife Service for work that may disturb or destroy active nests. The need for a permit may be avoided by removing the existing bridge structure prior to nest occupation by birds or clearing nests from all

1198-03-78 3 of 59

structures before the nests become active in early spring. As a last resort, prevent birds from nesting by installing a suitable netting device on the remaining structure prior to nesting activity. Include the cost for preventing nesting in the cost of the polymer overlay.

#### **Monitoring Wells**

No active groundwater monitoring wells were observed within the construction limits. If active groundwater monitoring wells are encountered during construction, notify engineer and protect them to maintain their integrity. The environmental consultant will determine if monitoring wells need to be maintained. For monitoring wells that do need to be maintained, adjust the wells that do not conflict with structures or curb and gutter to be flush with the final grade. For wells that conflict with the previously mentioned items or if monitoring wells are not required to be maintained, they will be abandoned by others.

If dewatering is required at the above location, conduct the dewatering according to Dewatering section.

#### **Other Work Restrictions**

Do not haul materials of any kind along or across any portion of the highway carrying USH 2 / USH 53, East Second Street traffic, and entirely clear the traveled way of such portions of the highway of equipment, barricades, signs, lights, and any other material that might impede the free flow of traffic during the following periods:

- From noon Friday to 6:00 PM Friday, every Friday after June 11, 2021

Any deviations from the general requirements above are only allowed with the approval of the department engineer and coordination with City of Superior Parks, Recreation and Forestry, 1316 N. 14th St, Rm.200, Superior, WI 54880, phone (715) 395-7270.

#### 4. Traffic.

#### **A Description**

This special provision describes providing for USH 2/ USH 53 (East Second Street) traffic during construction operations. USH 2/ USH 53 (East Second Street) shall be open to traffic during construction operations. The project shall be constructed under traffic. USH 2/ USH 53 (East Second Street) shall be reduced to a single lane in each direction during construction operations. Complete the construction staging operations as shown in the plan or as directed by the department engineer.

During each phase of the project, if a portion of the work is completed, and traffic lanes are available prior to the completion of the phase, traffic lanes shall be opened, and traffic control shall be adjusted to reflect the revised construction traffic flow. Retract drums to a minimum width of 24 feet when feasible or not working.

#### Stage 1

Traffic transitions between 29<sup>th</sup> Avenue East to 31<sup>st</sup> Avenue East and shifts to NB/WB lanes through 37<sup>th</sup> Avenue East. Concrete panel repair, sidewalk, and curb and gutter repair for EB/SB lanes of USH 2/ USH 53 and EB/SB repair and polymer overlay of Structure B-16-0066 over the Nemadji River occurs.

Traffic transitions between 37<sup>th</sup> Avenue East and 38<sup>th</sup> Avenue East. One lane of traffic remains in a NB/WB lane and one lane shifts to a SB/EB lane, allowing traffic to utilize left turn lanes at the intersections. Traffic remains in these lanes through 42<sup>nd</sup> Avenue East. Concrete panel repair, sidewalk, and curb and gutter repair for one lane of EB/SB USH 2/ USH 53, and for one lane of WB/NB USH 2/ USH 53 occurs. Minimize intersection closures, alternate closures, allowing every other intersection to remain open. Traffic Signal at 39<sup>th</sup> Avenue East is removed and replaced. Maintain access at 39<sup>th</sup> Avenue East (South) at all times.

Notify the Duluth Transit Authority when access will not be maintained to 39<sup>th</sup> Avenue East, 2 weeks in advance, so that they may alter their bus route.

Traffic transitions between 42<sup>nd</sup> Avenue East and 43<sup>rd</sup> Avenue East and shifts to NB/WB lanes through 48<sup>th</sup> Avenue East. Concrete panel repair, sidewalk, and curb and gutter repair for EB/SB lanes of USH 2/USH 53 and EB/SB repair and polymer overlay of Structure B-16-0067 over the Bluff Creek occurs.

Traffic transitions between 48<sup>th</sup> Avenue East and 49<sup>th</sup> Avenue East. Traffic shifts to the inside lanes of EB/SB USH 2/ USH 53, and WB/NB USH 2/ USH 53 through the end of the project.

1198-03-78 4 of 59

Concrete panel repair, sidewalk, and curb and gutter repair for the outside lanes USH 2/ USH 53 occurs. Minimize intersection closures, alternate closures, allowing every other intersection to remain open.

**Stage 1A**: USH 2/ USH 53 and 39<sup>th</sup> Avenue East concrete panel repair and curb repair. Repair on USH 2/ USH 53 outside lanes EB/SB and inside lanes WB/NB lanes. Repair south side of 39<sup>th</sup> Avenue East lanes. Traffic signal work.

**Stage 1B**: USH 2/ USH 53 and 39<sup>th</sup> Avenue East concrete panel repair and curb repair. Repair south side of 39<sup>th</sup> Avenue East outside of curb and gutter. Traffic signal work.

#### Stage 2

Traffic transitions between 30<sup>th</sup> Avenue East to 31<sup>st</sup> Avenue East, and shifts to SB/EB lanes through 37<sup>th</sup> Avenue East. Concrete panel repair, sidewalk, and curb and gutter repair for NB/WB lanes of USH 2/USH 53 and NB/WB repair and polymer overlay of Structure B-16-0066 over the Nemadji River occurs.

Traffic transitions between 37<sup>th</sup> Avenue East and 38<sup>th</sup> Avenue East. One lane of traffic remains in a NB/WB lane and one lane shifts to a SB/EB lane, allowing traffic to utilize left turn lanes at the intersections. Traffic remains in these lanes through 42<sup>nd</sup> Avenue East. Concrete panel repair, sidewalk, and curb and gutter repair for one lane of EB/SB USH 2/ USH 53, and for one lane of WB/NB USH 2/ USH 53 occurs. Minimize intersection closures, alternate closures, allowing every other intersection to remain open. Traffic Signal at 39<sup>th</sup> Avenue East not removed and replaced in Stage 1 is completed. Maintain access at 39<sup>th</sup> Avenue East (South) at all times. Notify the Duluth Transit Authority when access will not be maintained to 39<sup>th</sup> Avenue East, 2 weeks in advance, so that they may alter their bus route.

Traffic transitions between 42<sup>nd</sup> Avenue East and 43<sup>rd</sup> Avenue East, and shifts to SB/EB lanes through 48<sup>th</sup> Avenue East. Concrete panel repair, sidewalk, and curb and gutter repair for NB/WB lanes of USH 2/USH 53 and EB/SB repair and polymer overlay of Structure B-16-0067 over the Bluff Creek occurs.

Traffic transitions between 48<sup>th</sup> Avenue East and 49<sup>th</sup> Avenue East. Traffic shifts to the outside lanes of EB/SB USH 2/ USH 53, and WB/NB USH 2/ USH 53 through the end of the project.

Concrete panel repair, sidewalk, and curb and gutter repair for the outside lanes USH 2/ USH 53 occurs. Minimize intersection closures, alternate closures, allowing every other intersection to remain open.

**Stage 2A**: USH 2/ USH 53 and 39<sup>th</sup> Avenue East concrete panel repair and curb repair. Repair on USH 2/ USH 53 outside lanes WB/NB and inside lanes EB/SB lanes. Repair north side of 39<sup>th</sup> Avenue East lanes. Traffic signal work.

**Stage 2B**: USH 2/ USH 53 and 39<sup>th</sup> Avenue East concrete panel repair and curb repair. Repair north side of 39<sup>th</sup> Avenue East outside of curb and gutter. Traffic signal work.

#### Stage 3

Partial Depth concrete removal, overlay with HMA and SMA. One continuous lane in each direction must be open at all times to traveling public. Only cross traffic may be on milled surfaces. Both Asphaltic lifts required before opening to traveling public.

#### **Access**

Maintain local vehicle traffic access to properties within the work zone that do not have alternate access available outside the work zone, at all times, except as allowed herein. Maintain ramped driveway access to all business and private residences at a maximum slope of 15% on existing driveway surface, compacted base aggregate dense, milled concrete surface or finished driveway surface.

Keep all private entrances accessible, unless permission to temporarily close the entrance is obtained from the property owner. Notify any affected property and business owners in writing of any temporary disruptions in access a minimum of one week ahead of such activity. Cooperate with the property owners to provide access whenever possible. Provide reasonable access for any handicapped person whose access is affected by the construction.

Coordinate with each business for the best time to construct driveways and sidewalks so as not to interrupt business operations during open hours. Construct driveway approaches to commercial properties in stages if the property does not have an alternate access available so that at least one access is maintained to each business at all times.

1198-03-78 5 of 59

Do not store vehicles, equipment, or materials on adjacent or intersecting streets beyond the project limits without specific approval of the engineer. Maintain emergency vehicle access to all properties at all times.

Provide one accessible crosswalk across USH 2/ USH 53 (East Second Street) at the following street intersections: 37<sup>th</sup> Avenue East, 39<sup>th</sup> Avenue East, 41<sup>st</sup> Avenue East and 50<sup>th</sup> Avenue East / E 3<sup>rd</sup> Street.

#### Miscellaneous

Use signs and/or barricades to protect hazards in the work zone - such as exposed manholes, inlets, or drop-offs for pedestrians and vehicles.

Place a portable changeable message sign (PCMS) at both ends of the project (31st Avenue East and 53rd Avenue East) one week prior to beginning construction on USH 2/ USH 53 (East Second Street) warning traffic of the road construction starting date.

Relocate each PCMS to approximately one and one-half mile beyond the project limits at the beginning of construction. Sign messages shall inform motorists of traffic control changes, incident management, and/or emergency situations.

#### **Wisconsin Lane Closure System Advance Notification**

Provide the following advance notification to the engineer for incorporation into the Wisconsin Lane Closure System (LCS).

Closure type with height, weight, or width restrictions MINIMUM NOTIFICATION (available width, all lanes in one direction less than 16 feet) Lane and shoulder closures 7 calendar days Full roadway closures 7 calendar days Ramp closures 7 calendar days **Detours** 7 calendar days Closure type without height, weight, or width restrictions MINIMUM NOTIFICATION (available width, all lanes in one direction 16 feet or greater) Lane and shoulder closures 3 business days Ramp closures 3 business days Modifying all closure types 3 business days

TABLE 108-1 CLOSURE TYPE AND REQUIRED MINIMUM ADVANCE NOTIFICATION

Discuss LCS completion dates and provide changes in the schedule to the engineer at weekly project meetings in order to manage closures nearing their completion date.

#### **Temporary Regulatory Speed Limit Reduction**

During engineer-approved regulatory speed limit reductions, install temporary speed limit signs on the inside and outside shoulders of divided roadways to enhance visibility. On two lane two way roadways, install temporary speed limit signs on shoulders. When construction activities impede the location of a post-mounted regulatory speed limit sign, relocate the sign for maximum visibility to motorists. If work last less than 7 days, mount the regulatory speed limit sign on a portable sign support.

Post temporary regulatory speed limit signs in work zone only during continuous worker activity. During periods of no work activity or when the traffic controls are removed from the roadway, cover or remove the temporary speed limit signs.

Coordinate with Regional Traffic Section to identify the construction stages that have approved temporary regulatory speed zones documented in a Temporary Speed Zone Declaration. Primary contact phone number: (715) 836-7276.

Contact the Region Traffic Section at least 14-calendar days before installing the temporary speed zone. After installation of the temporary speed zone is complete, notify the Regional Traffic Section with field locations of temporary speed zones.

1198-03-78 6 of 59

#### 5. Holiday Work Restrictions.

Do not perform work on, nor haul materials of any kind along or across any portion of the highway carrying USH 2 / USH 53, East Second Street traffic, and entirely clear the traveled way and shoulders of such portions of the highway of equipment, barricades, signs, lights, and any other material that might impede the free flow of traffic during the following holiday periods:

- From noon Friday, May 28, 2021 to 6:00 AM Tuesday, June 1, 2021 for Memorial Day;
- From noon Friday, July 2, 2021 to 6:00 AM Tuesday, July 6, 2021 for Independence Day;
- From noon Friday, August 20, 2021 to 6:00 AM Monday, August 23, 2021, for Lake Superior Dragon Boat Festival, Superior Bay off Barkers Island;
- From noon Friday, September 3, 2021 to 6:00 AM Tuesday, September 7, 2021 for Labor Day. stp-107-005 (20181119)

#### 6. Utilities.

This contract comes under the provision of Administrative Rule Trans 220.

stp-107-065 (20080501)

Some of the utility work described below is dependent on prior work being performed by the contractor at a specific site. In such situations, provide the engineer and the affected utility a good faith notice of when the utility is to start work at the site. Provide this notice 14 to 16 calendar days in advance of when the prior work will be completed, and the site will be available to the utility owner. Follow-up with a confirmation notice to the engineer and the utility owner not less than three working days before the site will be ready for the utility owner to begin its work.

It is the contractor's responsibility to coordinate all work with utilities. This includes giving proper notification prior to when utility work is to be performed in conjunction with roadway construction.

**Astrea (f/k/a) Packerland Broadband (Communication Line)** has underground fiber optic facilities behind the curb from Station 214+00 to Station 244+75 LT, running parallel to USH 2/USH 53. This fiber optic facility is in close proximity to the parapet wall work to be performed at the Nemadji River structure and catch basin reconstruction work. No conflicts are anticipated.

Fiber optic crosses USH 2/USH 53 on the south side of 50th Avenue at Station 35+45, below an area where a curb ramp and sidewalks are to be constructed. No conflicts are anticipated.

**CenturyLink (Communication Line)** has buried communication lines at or near the curb ramp, sidewalk and catch basin reconstruction work at 31<sup>st</sup>, 37<sup>th</sup>, 39<sup>th</sup>, 42<sup>nd</sup>, 48<sup>th</sup>, 51<sup>st</sup>, and 53<sup>rd</sup> Avenue. CenturyLink buried communication line is also near parapet wall work planned for the Nemadji River structure. No conflicts are anticipated.

**Charter Communications (Communication Line)** has facilities running parallel to USH 2/USH 53 on the southwest side from 31<sup>st</sup> Avenue to 36<sup>th</sup> Avenue below grade beyond Station 225+50. Aerial fiber optic and coaxial crosses USH 2/USH 53 at 36th Avenue at Station 240+60; Aerial coaxial crosses USH2/USH 53 at 40th Avenue (Station 260+00) and near 51st Avenue (Station 40+25); aerial coaxial and fiber optic crosses USH 2/USH 53 at 52nd Avenue (Station 44+65). No relocations anticipated.

**City of Superior Public Works (Sewer)** has sanitary sewer lines located behind the curb on the northeast side of USH 2/USH 53 between 35<sup>th</sup> Avenue and 36<sup>th</sup> Avenue (Station 238+00 to Station 240+55 LT), from 44<sup>th</sup> Avenue to 46<sup>th</sup> Avenue (Station 4+75 to 14+50 LT), and between 46<sup>th</sup> Avenue and 47<sup>th</sup> Avenue (Station 16+00 to Station 18+65 LT).

Sanitary lines cross at 48<sup>th</sup> Avenue (Station 25+17) and near 52<sup>nd</sup> Avenue (Station 45+01). Sanitary lines also are located on the southwest side of USH 2/USH 53 from 53<sup>rd</sup> Avenue to the south beyond the project limits (Station 50+04 to Station 52+65 RT).

1198-03-78 7 of 59

Sanitary sewer adjustments and reconstructions shall occur under this project as required for the street rehabilitation. Sanitary manholes shall be reconstructed during concrete panel repairs and sanitary manholes adjustments shall occur during Removing Concrete Surface Partial Depth at the following locations: Station 25+17, 30' RT, Station 45+01, 9' LT, Station 50+04, 28' RT, and Station 52+22, 24' RT.

No conflicts are anticipated with any sanitary lines.

**Merit Network Inc. (Communication Line)** has buried fiber facilities throughout the project running parallel and left of the mainline from the beginning of the project at Station 214+00 south to Station 244+70 on the north side of 37th Avenue. This fiber optic facility is in close proximity to the parapet wall work to be performed at the Nemadji River structure and catch basin reconstruction work. No conflict anticipated.

Fiber optic crosses USH 2/USH 53 (East 2nd Street) on the south side of 50th Avenue at Station 35+45. This fiber optic facility is in close proximity to the pavement panel replacement and pedestrian curb ramp work at the intersection. No relocations or conflicts are anticipated.

**Superior Water, Light and Power Company (SWL&P) (Gas/Petroleum)** has gas facilities throughout the project limits. The depth for gas mains is typically 30" to 42". SWL&P will need to be notified 5 working days prior to construction activities occurring at the locations listed. The contractor shall coordinate with SWL&P and SWL&P will provide an inspector on site. No relocations or conflicts are anticipated.

The gas crosses and is under mainline at the following locations:

31st Ave E: Station 214+76, Station 214+82, and Station 215+51

Station 219+94-240+61 RT

Station 240+61

39<sup>th</sup> Ave E: Station 255+28-260+37 RT

Station 259+85 LT

Station 259+85 - 260+88 LT

40<sup>th</sup> Ave E: Station 260+37

Station 261+36-265+53 RT

48<sup>th</sup> Ave E: Station 24+62

Station 33+45 – 44+73

50<sup>th</sup> Ave E: Station 34+73

Station 34+76-36+78 LT

50<sup>th</sup> Ave E: Station 35+42 52<sup>nd</sup> Ave E: Station 44+68

Station 44+71 - 45+10 LT

Station 45+10

**Superior Water, Light and Power Company (SWL&P) (Water)** has water main facilities under USH 2/USH 53 throughout the project limits at 7-11 feet left of centerline with residential connections. Water line valves and service valves are in the mainline concrete. The contractor shall notify SWL&P 5 days prior to construction and SWL&P will arrange for any vertical adjustments required to meet the temporary and permanent pavement elevations. No relocations are expected.

1198-03-78 8 of 59

Water Valves			
215+02 34' LT	259+50 43' RT	269+55 30' RT	36+04 24' LT
219+96 36' LT	259+62 40' LT	271+12 30' LT	36+61 23' LT
224+98 39' LT	262+01 31' RT	271+14 1' RT	36+65 23' RT
225+11 34' LT	262+27 13' LT	272+42 30' LT	36+78 25' LT
245+14 44' RT	262+73 30' LT	272+75 34' RT	37+27 25' LT
245+17 40' RT	262+92 29' RT	273+45 30' LT	38+00 23' RT
245+17 45' LT	263+45 30' RT	273+64 32' RT	39+24 25' LT
245+84 30' LT	263+61 29'LT	274+13 30' LT	39+52 10' RT
246+62 30' RT	263+63 30' LT	274+16 30' RT	40+82 24' LT
245+87 87' RT	263+93 30' LT	274+66 30' RT	42+51 23' LT
246+39 29' LT	264+02 30' RT	275+20 41' RT	43+11 25' LT
246+67 29' LT	264+21 30' RT	0+49 18' LT	44+21 25' LT
246+92 29' LT	264+64 30' LT	0+72 26' LT	45+40 34' LT
247+41 30' RT	264+67 30' RT	1+03 24' LT	45+63 23' RT
247+91 27' LT	265+70 41' RT	1+28 26' RT	46+26 24' LT
248+20 39' RT	265+89 20' LT	1+52 25'LT	46+82 22' RT
248+46 39' RT	266+04 30' LT	2+15 25'RT	47+13 24' LT
248+62 29' LT	266+17 30' RT	2+52 25' RT	47+52 34' RT
249+51 29' LT	366+54 30' LT	2+93 30' LT	47+80 25' LT
249+64 29' RT	266+60 30' RT	3+41 24' LT	47+79 24' RT
249+65 29' LT	267+07 30' RT	3+85 25' LT	49+54 10' RT
251+07 18' LT	267+57 30' RT	4+21 27' LT	49+68 64' RT
251+27 29' RT	267+67 29' RT	5+50 17' LT	49+82 39' LT
251+62 32' LT	267+69 30' LT	25+56 17'LT	50+22 34' LT
252+51 29' LT	268+12 29' LT	29+48 25' LT	50+51 32' LT
253+36 30' LT	268+20 30' RT	30+95 27' LT	51+03 32' LT
253+83 28' LT	268+19 30' RT	31+87 25'LT	51+31 35' LT
255+12 36' LT	268+60 30' RT	31+95 13'LT	
255+18 39' LT	269+02 30' RT	34+53 18' LT	
255+18 40' RT	269+54 30' LT	35+48 28' RT	

Fire hydrants are located throughout and within the construction area.

Fire hydrants at 39<sup>th</sup> Ave E Station 255+06 LT and 41<sup>st</sup> Ave E Station 265+70 LT must be moved during construction.

The contractor shall notify SWL&P 14 to 16 calendar days prior to construction in this area to move hydrants outside of slope intercepts. SWL&P will require one (1) day to move each hydrant.

1198-03-78 9 of 59

FIRE HYDRANT LO			
	STATION	OFFSET	COMMENTS
31ST AVE EAST	214+96	40' LT	
	224+98	41' LT	
37TH AVE EAST	245+10	21' RT	
38TH AVE EAST	251+07	40' LT	
39TH AVE EAST	255+06	40' LT	MOVE REQUIRED
	262+73	38' LT	
41ST AVE EAST	265+70	47' LT	MOVE REQUIRED
42ND AVE EAST	270+90	41' LT	
43RD AVE EAST	0+48	34' LT	
	5+50	37' LT	
48TH AVE EAST	25+53	50' LT	
	29+52	40' LT	
50TH AVE EAST	34+54	42' LT	
	39+55	36' RT	
	44+54	36' RT	
53RD AVE EAST	49+68	49' RT	

Superior Water, Light and Power Company (SWL&P) (Electricity) has electric facilities throughout the project limits.

38<sup>th</sup> Ave E Station 250+72, 52' LT a power pole is located in the sidewalk to be replaced. The pole will need to be relocated during construction.

38<sup>th</sup> Ave E Station 250+71, 38.7' RT a power pole is located in the sidewalk to be replaced. The pole will need to be relocated during construction.

No other relocations anticipated.

The contractor shall notify SWL&P 14 to 16 calendar days prior to construction in this area to move the poles outside of slope intercepts. SWL&P will require one (1) day to move each pole.

#### 7. Railroad Insurance and Coordination - BNSF Railway Company.

#### **A** Description

Comply with standard spec 107.17 for all work affecting BNSF Railway Company property and any existing tracks.

#### A.1 Railroad Insurance Requirements

In addition to standard spec 107.26, provide railroad protective liability insurance coverage as specified in standard spec 107.17.3. Insurance is filed in the name of BNSF Railway Company. Requirements of the standard specifications are changed as follows:<sup>1</sup>

Before the state issues its notice to proceed to the contractor or contractors (collectively, the contractor) awarded the contract for construction involving the project described in this stipulation (the project), the state shall require the contractor to provide certain insurance coverage to protect the railroad (as defined in this section) from loss for property and liability exposures relating to the construction activities on the PROJECT. The manner and process in which this will be accomplished is as detailed below.

1198-03-78 10 of 59

TYPE OF INSURANCE	MINIMUM LIMITS REQUIRED
1. Commercial general liability insurance; shall be endorsed to include blanket contractual liability coverage; shall cover bodily injury and property damage, personal and advertising injury, and fire legal liability. There shall be no endorsements limiting coverage for the work to be performed pursuant to this Stipulation.	\$5,000,000 combined single limits per occurrence with an annual aggregate limit of not less than \$10,000,000.
Workers' compensation and employer's liability coverage.	Workers' compensation limits: statutory limits. Employers' liability limits: Bodily injury by accident \$100,000 each accident Bodily injury by disease \$500,000 each accident \$100,000 each employee
3. Commercial automobile liability insurance; shall cover all owned, non-owned, and hired vehicles used by the CONTRACTOR in carrying out the contract, and shall include coverage for bodily	\$1,000,000 combined single limit per occurrence.
4. Railroad Protective Liability Insurance, issued on a standard ISO form 00 35 10 93 or its equivalent and endorsed to include the Pollution Exclusion Amendment (ISO form CG 28 31 10 93) and the Limited Seepage and Pollution Endorsement. No endorsements restricting FELA coverage may be added.	\$5,000,000 per occurrence \$10,000,000 in the aggregate

<sup>&</sup>lt;sup>1</sup> As used in this section, "STATE" and "COMPANY" have the meanings assigned to them in the Stipulation to which this Exhibit is attached, "FELA" means the Federal Employment Liability Act, and "this Stipulation" means the Stipulation to which this Exhibit is attached.

- 1. The policies for insurance types 1, 2 and 3 may not contain an exclusion for punitive damages.
- 2. The commercial general liability policy shall include an endorsement that removes any restrictions on coverage regarding work being performed within 50 feet of a railroad or railroad property and an endorsement that removes any exclusion related to explosion, collapse or underground hazard.
- 3. The CONTRACTOR must waive its right of recovery against the RAILROAD for all claims and suits against the RAILROAD. In addition, the CONTRACTOR's insurers, through the terms of the policy or policy endorsement, must waive their right of subrogation against the RAILROAD for all claims and suits. The certificates of insurance must reflect the waiver of subrogation endorsement. The CONTRACTOR also must waive its right of recovery, and its insurers must also waive their right of subrogation, against the RAILROAD for loss of the CONTRACTOR's owned or leased property or property under the CONTRACTOR's care, custody or control.
- 4. The CONTRACTOR's insurance policies, except for excess liability/umbrella policies, through policy endorsement, must include wording to the effect that such policies are primary and non-contributing with respect to any insurance carried by the RAILROAD. The certificates of insurance must reflect that such wording is included in the evidenced policies.
- 5. The policies for insurance types 1 and 3, above, must include a severability of interest endorsement. The RAILROAD and Jones Lang LaSalle Global Services- RR, Inc. must be named as an additional insured with respect to work performed under this project. Severability of interest and naming the RAILROAD and Jones Lang LaSalle Global Services- RR, Inc. as additional insured must be indicated on the certificates of insurance.
- 6. The CONTRACTOR shall provide the original Railroad Protective Liability policy to the RAILROAD prior to performing any work on the PROJECT.

1198-03-78 11 of 59

<sup>&</sup>lt;sup>2</sup> The CONTRACTOR may satisfy the requirements for insurance types 1, 2 and 3 through primary insurance coverage or through excess/umbrella policies.

- 7. The CONTRACTOR shall only obtain coverage from insurance companies licensed to do business in the State of Wisconsin that have an AM Best rating of A- and Class VII or better.
- 8. The CONTRACTOR is not allowed to self-insure.
- 9. Prior to performing any work on the PROJECT, the CONTRACTOR shall provide the RAILROAD acceptable certificates of insurance, including original signatures of the authorized representatives evidencing the required coverages, endorsements, and amendments and referencing the RAILROAD's contract audit/folder number (if available), as evidence that required coverages for insurance types 1, 2 and 3 are in force.
- 10. The policies for insurance types 1, 2 and 3 must contain a provision that obligates the insurer to notify the RAILROAD at least 60 calendar days before a cancellation, non- renewal, substitution or material change in coverage, and such provision must be reflected on the insurance certificates.
- 11. The CONTRACTOR shall send the required insurance documentation to the RAILROAD at the following address:

BNSF Risk Management 2500 Lou Menk Drive AOB-1 Fort Worth, TX 76131-2828

- 12. Acceptance by the RAILROAD of a certificate of insurance that does not comply with this section shall not operate as a waiver of the CONTRACTOR's obligation to provide the insurance required by this section.
- 13. If the RAILROAD notifies the STATE that the CONTRACTOR does not have the required insurance, the STATE's engineer shall immediately suspend work on the PROJECT until the matter is resolved.
- 14. The requirements for insurance types 1, 2, and 3 shall apply with equal force whether the CONTRACTOR or a subcontractor, or anyone directly or indirectly employed by either, performs work on the PROJECT. If any portion of the PROJECT work is subcontracted, the CONTRACTOR must require the subcontractor to provide and maintain insurance coverages for insurance types 1, 2, and 3 that meet the requirements of this section, except that the minimum limits required for the subcontractor's commercial general liability policy shall be \$2,000,000 per occurrence and \$4,000,000 in the aggregate.
- 15. The fact that the CONTRACTOR obtains insurance as required by this section shall not release or diminish the CONTRACTOR's liability. Damages recoverable by the RAILROAD will not be limited by the required insurance coverages.
- 16. Upon request from the RAILROAD, the CONTRACTOR will provide a certified duplicate original of any requested policy.
- 17. For purposes of this section references to the RAILROAD mean the COMPANY, Burlington Northern Santa Fe Corporation, and the subsidiaries, successors, assigns and affiliates of each.

Notify evidence of the required coverage, and duration to Daniel Peltier, Manager of Public Projects; 80 44th Avenue NE, Minneapolis, MN 55421; Telephone (763) 782-3495; E-mail <a href="mailto:daniel.peltier@bnsf.com">daniel.peltier@bnsf.com</a> to determine the applicable railroad rules and regulations. Once determined send the RPLI policy to <a href="mailto:bnsf@certfocus.com">bnsf@certfocus.com</a>. Approval of the policy will not take place until the Manager of Public Projects has been contacted.

Also send a copy to the following: Anna Davey, NW and NC Region Railroad Coordinator; 1701 N 4th Street, Superior, WI 54880; Telephone (715) 392-7960; E-mail: <a href="mailto:anna.davey@dot.wi.gov">anna.davey@dot.wi.gov</a>.

Include the following information on the insurance document:

- Project ID: 1198-03-78

- Project Location: Superior, WI

- Route Name: USH 2/East 2nd, Douglas County

- Crossing ID: Allouez Taconite Facility

- Railroad Subdivision: Allouez Taconite Facility

- Railroad Milepost: 0.00

- Work Performed: Install traffic signals, paving and sidewalk

1198-03-78 12 of 59

#### A.2 Train Operation

The BNSF overhead taconite conveyor system runs over USH 2/East 2<sup>nd</sup> Street in an enclosed system.

#### A.3 Names and Addresses of Railroad Representatives for Consultation and Coordination

#### **Construction Contact**

Daniel Peltier, Manager of Public Projects; 80 44<sup>th</sup> Avenue NE, Minneapolis, MN 55421; Telephone (763) 782-3495; E-mail <u>daniel.peltier@bnsf.com</u> for consultation on railroad requirements during construction.

Amend standard spec 108.4 to include the railroad in the distribution of the initial bar chart, and monthly schedule updates. The bar chart shall specifically show work involving coordination with the railroad.

#### **Flagging Contact**

Notify the Construction Contact above a minimum of 40 working days in advance to arrange for a railroad flagger. Reference the Crossing ID, Wisconsin Milepost and Subdivision found in A.1.

#### **Cable Locate Contact**

In addition to contacting Diggers Hotline, contact the BNSF Communications Network Control Center at (800) 533-2891, five working days before the locate is needed. Reference Allouez Taconite Facility over USH 2/E 2<sup>nd</sup> Street and 39<sup>th</sup> Street, Douglas County Wisconsin.

BNSF will only locate railroad owned facilities located in the railroad right-of-way. The railroad does not locate any other utilities.

#### A.4 Work by Railroad

The railroad will perform the work described in this section, except for work described in other special provisions, and will be accomplished without cost to the contractor. None

#### A.5 Temporary Grade Crossing

If a temporary grade crossing is desired, submit a written request to the railroad representative named in A.3 at least 40 days prior to the time needed. Approval is subject to the discretion of the railroad. The department has made no arrangements for a temporary grade crossing.

stp-107-026 (20200629)

#### 8. Hauling Restrictions.

Use only City of Superior designated truck routes for material haul roads. Haul roads are detailed in standard spec 618. City of Superior designated truck routes are available on the city of Superior website: <a href="http://www.ci.superior.wi.us/">http://www.ci.superior.wi.us/</a>.

#### 9. Roadway Maintenance.

Supplement standard spec 104.6.1 and 690 with the following:

Dry brooming of the pavement shall not be allowed.

When engaged in saw cutting or roadway cleaning operations, use equipment having vacuum or water spray mechanisms to eliminate the dispersion of particulate matter into the atmosphere. If vacuum equipment is employed, it must have a suitable self-contained particulate collector to prevent discharge from the collection bin into the atmosphere.

1198-03-78 13 of 59

#### 10. Notice to Contractor – Contamination Beyond Construction Limits.

The department completed testing for soil and ground water contamination for locations within this project where excavation is required. Testing indicated that petroleum-contaminated soil is present at the following sites:

1. Station 255+50 to 260+15 from 25 feet RT of centerline to construction limits RT of centerline.

The contaminated soils at the above sites are expected to be beyond the excavation limits necessary to complete the work under this project. Control construction operations at these locations to ensure that they do not extend beyond the excavation limits indicated in the plans. If contaminated soils are encountered at these sites or elsewhere on the project during excavation, terminate excavation in the area and notify the engineer.

The Hazardous Materials Report is available by contacting: Stephanie J. King, P.E.,1701 N. 4th Street, Superior, WI 54880, phone (715) 392-7874.

stp-107-100 (20050901)

#### 11. Notice to Contractor, Verification of Asbestos Inspection, No Asbestos Found.

John Roelke, License Number All-119523, inspected Structure B-16-0066 for asbestos on July 17, 2018. No regulated Asbestos Containing Material (RACM) was found on this structure. A copy of the inspection report is available from: Stephanie J. King, P.E.,1701 N. 4th Street, Superior, WI 54880, phone (715) 392-7874.

John Roelke, License Number All-119523, inspected Structure B-16-0067 for asbestos on July 17, 2018. No regulated Asbestos Containing Material (RACM) was found on this structure. A copy of the inspection report is available from: Stephanie J. King, P.E. 1701 N. 4th Street, Superior, WI 54880, phone (715) 392-7874.

stp-107-127 (20120615)

#### 12. Notice to Contractor, Environmental Commitments and Environmentally Sensitive areas.

<u>Environmentally Sensitive area:</u> The department completed surveys and investigations for known environmentally sensitive areas located within the vicinity of this project. Surveys and investigations have indicated that environmentally sensitive areas are present at the following sites:

1. Station 214+00-214+70 from 85 feet LT of centerline to 95 feet LT of centerline.

The environmentally sensitive areas at the above sites are expected to be beyond the excavation limits necessary to complete the work under this project. Control construction operations at these locations to ensure that they do not extend beyond the excavation limits indicated in the plans.

Limit staging/stockpiling to paved, gravel or mowed areas. If staging cannot be limited, then additional surveys and investigations for known environmentally sensitive areas are required.

#### 13. Notice to Contractor, Environmental Commitments.

This project is covered by the Broad Incidental Take Permit/Authorization for No/Low Impact Activities. However, suitable habitat for threatened plant species potentially exists within the project limits.

Any staging or stockpile locations should be located within paved or mowed lawn areas to avoid potential impacts to these species. If staging or stockpile locations cannot be located within paved or mowed lawn areas, surveys may need to be conducted to determine the presence of these listed plant species.

1198-03-78 14 of 59

#### 14. Notice to Contractor – Traffic Signal Equipment Lead Time and Coordination.

Note lead time for traffic signal equipment as there is a several months backorder for delivery of monotube traffic signal equipment. The contractor shall provide as much advance notice as possible to the monotube manufacturer. The contractor shall order equipment as soon as possible to assure the equipment is procured in a timely fashion to ensure timely delivery and installation prior to the end of the contract.

#### 15. Notice to Contractor, Construction Equipment Height Notification – FAA Regulations.

Due to the proximity to airports, the use of any tall construction equipment including temporary cranes, with a height of more than 17 feet above ground level will require advance notice to the FAA.

The department will file an initial FAA Obstruction Analysis/Airport Airspace Analysis for tall construction equipment. If the contractor proposes to use equipment taller than 50 feet above ground level; as will be applied for by the department, the contractor must do a reapplication with coordination through WisDOT so a revision can be made to the airspace analysis.

If the contractor exceeds the filed time window April 5, 2021 through November 1, 2021, reapplication would also need to occur. Reapplication should occur three weeks prior to operations so that approvals can be made available prior to work.

The initial FAA Obstruction Analysis/Airport Airspace Analysis and any conditions or requirements will be available prior to construction from the regional office by contacting Stephanie King, Design Project Manager at (715) 392-7874.

FAA Obstruction Evaluation/Airport Airspace Analysis (OE/AAA) website: http://oeaaa.faa.gov/oeaaa/external/portal.jsp

Contact the following Airports one week before utilizing cranes on the project site. Contact Information:

William Amorde,	Brian Madsen
Richard I. Bong Memorial Airport Manager	Director Sky Harbor Regional Airport
4804 Hammond Avenue	5000 Minnesota Ave
Superior, WI 54880	Duluth, MN 55802
(715) 394-0282	(218) 733-0078

#### 16. Notice to Contractor, Railroad Overhead.

Railroad overhead crosses the project at 39th Avenue East at the location of the traffic signal replacement.

Overall heightened attention when working and carefully restore the area around the railroad footings.

The footings shall be reasonably and safely braced and fenced at all times to ensure complete safety during the signal removal and placement and curb ramp installation.

#### 17. Construction Over or Adjacent to Navigable Waters.

The Nemadji River is classified as a federal navigable waterway under standard spec 107.19.

Burr Creek is classified as a state navigable waterway under standard spec 107.19. stp-107-060 (20171130)

#### 18. City of Superior (street lighting).

The city has electric facilities to power the street lights along USH 2/USH 53. Conflicts are anticipated in select locations listed below.

1198-03-78 15 of 59

The underground lines run the length of the project parallel to USH 2 / USH 53:

The anacigioana ii
PULL BOXES
215+63 40' RT
252+27 13' RT
252+27 25' RT
252+27 25' RT
254+97 38' LT
255+20 35' LT
255+24 52' LT
255+31 52' LT
255+31 36' LT
255+7 51' RT
255+55 51' RT
255+64 51' RT
255+87 37' RT
260+05 LT
262+64 43' LT
2+97 29' LT
25+26 48' LT
34+65 40' LT
34+68 40' RT
35+36 40' LT
35+55 45' RT

#### 19. Archaeological Site.

47DG27 (unnamed) site is located approximately Station 215+80 to 217+00, RT and LT of centerline, within the limits shown on the plans.

Notify the Bureau of Technical Services – Environmental Process and Document Section (BTS-EPDS) at (608) 266-0099 at least two weeks before commencement of any ground disturbing activities. BTS-EPDS will determine if a qualified archaeologist will need to be on site during construction of this area.

1198-03-78 16 of 59

Do not use the site for borrow or waste disposal. Do not use the site area not currently capped by asphalt/concrete for the staging of personnel, equipment and/or supplies.

stp-107-220 (20180628)

#### 20. Environmental.

During both preparation and application of the polymer overlays on both structures, contain both slurry and aggregates to avoid either from entering environmentally sensitive areas such as the underlying waterways or associated wetlands. Also, sweep, collect, and dispose of fine materials before using compressed air for cleaning of the decks. Do not dispose of in or near environmentally sensitive areas. Do not discharge any material into waterways, wetland, deck drains, or storm water inlets during work operations including but not limit to, any activity related to deck cleaning preparation, concrete saw cutting, polymer overlay, etc. Properly dispose of all materials in an upland location or as designated by the engineer. On all structures with open railings, cover the railings to prevent polymer overlay material from falling into the waterway below. This is incidental to Polymer Overlay, Item 509.5100.S.

#### 21. Coordination with Businesses and Residents.

The contractor shall arrange and conduct a meeting between the contractor, the department, affected residents, local officials and business people to discuss the project schedule of operations including vehicular and pedestrian access during construction operations. Hold the first meeting at least one week before the start of work under this contract and hold two meetings per month thereafter. The contractor shall arrange for a suitable location for meetings that provides reasonable accommodation for public involvement. The department will prepare and coordinate publication of the meeting notices and mailings for meetings. The contractor shall schedule meetings with at least 2 weeks prior notice to the engineer to allow for these notifications.

stp-108-060 (20141107)

#### 22. Municipality Acceptance of Sanitary Sewer Construction.

Both the department and City of Superior personnel will inspect construction of sanitary sewer under this contract. Final acceptance of the sanitary sewer construction will be by the City of Superior Environmental Services Division of Public Works.

#### 23. Removing Pavement, Curb & Gutter, and Concrete Sidewalk.

Supplement standard spec 204 as follows:

Sawcut concrete pavement and concrete sidewalk into pieces no larger than 8-foot sections and remove using methods approved by the engineer. Payment of the full depth saw cut will be paid for under the bid item Sawing Concrete. During the saw cutting and concrete removal, take extreme care to not damage the adjacent concrete. The contractor will be responsible for any damage to the adjacent concrete.

#### 24. Removing Concrete Surface Partial Depth, Item 204.0109.S.

#### A Description

This special provision describes removing a portion of concrete surfaces as the plans show and conforming to standard spec 204.

B (Vacant)

1198-03-78 17 of 59

#### **C** Construction

#### C.1 Equipment

Use a machine that provides a surface finish acceptable to the engineer. Shroud the machine to prevent discharge of any loosened material into adjacent work areas or live traffic lanes.

Use a machine that is equipped with electronic devices that provide accurate depth, grade and slope control, and acceptable dust control system.

#### C.2 Methods

Remove existing concrete to the depths as shown on the plan by grinding, planing, chipping, sawing, milling, or by using other methods approved by the engineer.

Perform the removal operation in such a manner as to preclude damage to the remaining pavement and results in a reasonable uniform plane surface free of excessive large scarification marks and having a uniform transverse slope.

The sequence of removal operations shall be such that no exposed longitudinal joints 2 inches or more in depth remain during non-working hours. Windrowing or storing of the removed material on the roadway will only be permitted in conjunction with a continuous removal and pick-up operation. During non-working hours, clear the roadway of all materials and equipment.

Removed pavement becomes the property of the contractor. Properly dispose of it as specified in standard spec 204.3.1.3.

#### **D** Measurement

The department will measure Removing Concrete Surface Partial Depth in area by the square foot of surface area removed.

#### **E** Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBERDESCRIPTIONUNIT204.0109.SRemoving Concrete Surface Partial DepthSF

Payment is in full compensation for removing the concrete; and for disposing of materials.

stp-204-041 (20080902)

#### 25. Removing Traffic Signals USH 2 & 39th Ave, Item 204.9105.S.01.

#### **A Description**

This special provision describes removing existing traffic signals at the intersection of USH 2 & 39<sup>th</sup> Avenue conforming to standard spec 204.

#### B (Vacant)

#### **C** Construction

Arrange for the de-energizing of the traffic signals with the local electrical utility after receiving approval from the engineer that the existing traffic signals can be removed.

The City of Superior assumes that all equipment is in good condition and in working order prior to the contractor's removal operation. Prior to removal, inspect and provide a list of any damaged or non-working traffic signal equipment to the engineer. Any equipment not identified as damaged or not working, prior to removal, will be replaced by the contractor at no cost to the City of Superior.

Notify the City of Superior Public Works Department at (715) 395-7334 at least five working days prior to the removal of the traffic signals. Complete the removal work as soon as possible following shut down of this equipment.

Remove all standards and poles per plan from their concrete footings and disassemble out of traffic. Remove the bases from each pole. Remove the signal heads, mast arms, luminaires, wiring / cabling and traffic signal mounting devices from each signal standard, arm or pole. Ensure that access handhole doors and all associated hardware remain intact. Remove the traffic signal cabinet from the concrete footing. Dispose of the underground signal cable, internal wires, and street lighting cable. Deliver the remaining materials to the City of Superior Municipal Services Building at 2301 Hill Avenue, Superior, WI.

1198-03-78 18 of 59

Contact the City of Superior Public Works Department at (715) 395-7334 at least five working days prior to delivery to make arrangements.

#### **D** Measurement

The department will measure Removing Traffic Signals USH 2 & 39<sup>th</sup> Ave, as a single lump sum unit of work for each intersection, acceptably completed.

#### **E** Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER

DESCRIPTION

UNIT
204.9105.S.01

Removing Traffic Signals USH 2 & 39<sup>th</sup> Ave

LS

Payment is full compensation for removing and disassembling traffic signals; for scrapping of some materials; for disposing of scrap material; for delivering the requested materials to the City of Superior Municipal Services Building.

#### 26. Excavation, Hauling, and Disposal of Petroleum-Contaminated Soil, Item 205.0501.S.

#### **A Description**

#### A.1 General

This special provision describes excavating, loading, hauling, and disposing of petroleum-contaminated soil at a licensed bioremediation/disposal facility. The closest licensed facilities are:

Waste Management Timberline Trail RDF N4581 Hutchinson Road Weyerhaeuser, WI 54895 (715) 868-7000

Vonco V Waste Campus 1100 West Gary Street Duluth, Minnesota 55808 (218) 336-5100

Waste Management Voyager Landfill 6830 US-53 Canyon, Minnesota 55717 (218) 345-6302

Perform this work according to standard spec 205 and with pertinent parts of Chapters NR 700-754 of the Wisconsin Administrative Code, as supplemented herein. Per NR 718.07, a solid waste collection and transportation service-operating license is required under NR 502.06 for each vehicle used to transport contaminated soil. If a Minnesota bioremediation/disposal facility is utilized, perform hauling and disposal according to equivalent State of Minnesota requirements.

#### A.2 Notice to the Contractor – Contaminated Soil Locations

The department completed testing for soil contamination within this project where excavation is required. Testing indicated that petroleum-contaminated soil is present or likely to be present at the following location as shown on the plans:

1. Station 255+50 to 260+15, from 25 feet RT of reference line to construction limits RT, from the ground surface to a depth of approximately 10 feet below existing grades.

If contaminated soil is encountered at other locations, terminate excavations in that area and notify the engineer. The excavation management plan for this project has been designed to minimize the off-site disposal of contaminated material. These special provisions, which outline the excavation management plan, have been developed in cooperation with the WDNR. The WDNR's concurrence is on file at the department.

1198-03-78 19 of 59

For further information regarding previous investigation and remediation activities at these locations, contact:

Contact: Mr. Aaron Gustafson, WisDOT Northwest Region Address: 1701 North 4th Street, Superior, WI 54880

Phone: (715) 919-3051 Fax: (715) 392-7863

Email: aaron.gustafson@dot.wi.gov

#### A.3 Coordination

Coordinate work under this contract with the environmental consultant:

Name: GEI Consultants, Inc., Mr. Roger Miller or Mr. Michael DeBraske

Address: 3159 Voyager Drive, Green Bay, WI 54311

Phone: (920) 455-8657 / (920) 455-8655

Fax: (920) 455-8225

E-mail: <a href="mailto:rmiller@geiconsultants.com">rmiller@geiconsultants.com</a>, <a href="mailto:mdebraske@geiconsultants.com">mdebraske@geiconsultants.com</a>,

The role of the environmental consultant will be limited to:

- 1. Determining the locations and limits of contaminated material to be excavated based on analytical results from previous investigations, visual observations, and field-screening of material that is excavated:
- 2. Identifying contaminated material to be hauled to the bioremediation/disposal facility;
- 3. Documenting that activities associated with management of contaminated material are in conformance with state regulations;
- 4. Obtaining the necessary approvals for treatment and disposal of contaminated material.

Provide at least a 14-calendar day notice of the preconstruction conference date to the environmental consultant. At the preconstruction conference, provide a schedule for all excavation activities in the contaminated areas specified above to the environmental consultant. Also notify the environmental consultant at least three calendar days prior to commencement of excavation activities in each of the contaminated areas.

Coordinate with the environmental consultant to ensure that the environmental consultant is present during excavation in contaminated areas. Perform excavation work in these areas on a continuous basis until excavation work is completed.

Identify the licensed bioremediation/disposal facility that will be used for disposal of contaminated material and provide this information to the environmental consultant no later than 30 calendar days prior to commencement of excavation activities in the contaminated areas or at the preconstruction conference, whichever comes first. The environmental consultant will be responsible for obtaining the necessary approvals for disposal of contaminated soils from the bioremediation/disposal facility. Do not transport contaminated soil offsite without prior approval from the environmental consultant.

#### A.4 Health and Safety Requirements

Supplement standard spec 107.1 with the following:

During excavation activities, expect to encounter soil contaminated with gasoline, diesel fuel, or other petroleum related products. Site workers taking part in activities that will result in the reasonable probability of exposure to safety and health hazards associated with hazardous materials shall have completed health and safety training that meets the Occupational Safety and Health Administration (OSHA) requirements for Hazardous Waste Operations and Emergency Response (HAZWOPER), as provided in 29 CFR 1910.120.

Prepare a site-specific Health and Safety Plan, and develop, delineate and enforce the health and safety exclusion zones for each contaminated site location as required by 29 CFR 1910.120. Submit the site-specific health and safety plan and written documentation of up-to-date OSHA training to the engineer prior to the start of work.

#### B (Vacant)

1198-03-78 20 of 59

#### **C** Construction

Supplement standard spec 205.3 with the following:

Control operations in the contaminated areas to minimize the quantity of contaminated material excavated.

The environmental consultant will periodically evaluate material excavated from the contaminated areas. The environmental consultant will evaluate excavated material based on field-screening results, visual observations, and analytical results from previous environmental investigations. Assist the environmental consultant in collecting samples for evaluation using excavation equipment. The sampling frequency shall be a maximum of one sample for every 15 cubic yards excavated.

On the basis of the results of such field-screening, the material will be designated as follows:

- Excavation Common consisting of clean soil and/or clean construction and demolition fill (such as boulders, concrete, reinforced concrete, bituminous pavement, bricks, building stone, and unpainted or untreated wood), which under NR 500.08 are exempt materials, or
- Petroleum-contaminated soil for bioremediation/disposal at the selected licensed bioremediation/disposal facility.

Directly load and haul material designated by the environmental consultant for offsite treatment and disposal at the licensed facility. Use loading and hauling practices that are appropriate to prevent any spills or releases of contaminated material or residues. Prior to transport, sufficiently dewater material designated for off-site treatment and disposal so as not to contain free liquids.

Excavations may extend near or slightly beyond the depths to groundwater; however, due to the low permeability of subsurface materials, significant dewatering is not anticipated. Control activities in the contaminated area to minimize the amount of dewatering required. Allow contaminated water encountered, but not requiring removal as a standard course of construction, to remain in-place. If dewatering is necessary, notify the engineer and obtain any permits necessary prior to discharge or offsite transport of water.

#### **D** Measurement

The department will measure Excavation, Hauling, and Disposal of Petroleum-Contaminated Soil in tons of contaminated soil accepted by the bioremediation/disposal facility as documented by weight tickets generated by the bioremediation/disposal facility. The management of contaminated groundwater shall be considered incidental to the project.

#### **E** Payment

The department will pay for measured quantities at the contract unit price under the following bid items:

ITEM NUMBER

DESCRIPTION

UNIT

205.0501.S

Excavation, Hauling, and Disposal of Petroleum-Contaminated Soil

TON

Payment is full compensation for excavating, segregating, loading, hauling, and treatment via bioremediation or direct landfilling of contaminated soil; obtaining solid waste collection and transportation service operating licenses; assisting in the collection of soil samples for field evaluation; management of contaminated groundwater, if necessary; dewatering of soils prior to transport.

#### 27. Prepare Foundation for Asphaltic Paving.

Prepare the existing pavement foundation according to standard spec 211, as per the special plan detail, and as hereinafter provided.

Delete standard spec 211.3.5.4 and replace with the following:

Remove all surplus crack and joint sealing material from the surface of the pavement and all joint material, including fillers, sealers, and asphalt patching from joints and cracks to a minimum depth of 4 inches or full depth where conditions dictate below the milled surface of the concrete pavement.

Completely remove unstable patches of asphaltic materials used to fill localized pits, depressions, badly spalled, or disintegrated areas of the old pavement. Remove any loose concrete or concrete with incipient spalling within or contiguous to such areas.

1198-03-78 21 of 59

Prior to placement of the HMA pavement and or leveling layer, refill these areas of removal, as described above, to the surface of the concrete pavement. Payment for refilling these areas is paid for under bid item 465.0110 Asphaltic Surface Patching.

Patching material that extends more than 1/2-inch above the milled ground surface shall be corrected before the leveling layer is placed.

#### 28. Concrete Pavement 9-Inch, Item 415.0090; Concrete Pavement Repair, Item 416.1710; Concrete Pavement Replacement, Item 416.1720.

This special provision describes construction of Concrete Pavement, Concrete Pavement Repair and Concrete Pavement Replacement according to standard spec 415, standard spec 416, and standard spec 710. QMP for these items shall be combined and covered under standard spec 716, as shown on the plans, and hereinafter provided.

Supplement standard spec 716.2 with the following:

Concrete mix design shall be the responsibility of the contractor. Provide the concrete mix designs necessary to accommodate the contractor's operations and contractor scheduling according to the traffic provisions and prosecution and progress provisions included in the plan.

Chloride based accelerators shall be allowed in any concrete mixes that are specifically designed to meet opening strength within six hours or less within the time of placement to accommodate lane restrictions as specified in the contract.

QC slump testing is not required for any concrete mixture that has been approved and has at least 700 lbs. of cement per cubic yard.

Random 28-day compressive strength cylinders are not required.

Any chemical admixture(s) to be used, other than air-entraining agents or water reducers from the department's approved list, must be approved in advance by the engineer. The water-cement ratio of the concrete mixture shall not exceed 0.40.

Supplement standard spec 415.3 and 416.3 with the following:

Restrict lane operations as specified in the Traffic Section and the Prosecution and Progress Section. Perform work to cause the least possible inconvenience to traffic.

Remove areas of existing concrete pavement at locations designated in the plans or the engineer directs in the field. Saw the connecting edges as true and perpendicular as possible as specified for sawing pavement in standard spec 690. Remove the pavement without damage to the remaining pavement.

Dispose of removed material as specified in 204.3.1.3.

Prepare the base as specified in standard spec 211 using engineer-approved hand methods. Place the repair to the thickness of the contiguous pavement. In lieu of replacing base that was damaged or removed, the contractor will be allowed to place concrete to fill this area at no additional cost to the department.

Supplement standard spec 415.3.8, 416.3.7 and standard spec 416.3.8.2 with the following:

Deposit concrete to require as little re-handling as possible, place and consolidate by hand with an immersion type vibrator and strike off and finish flush with adjoining surfaces. Any finished surface,

(no plan overlay expected), within the repair that is 1/8 inches higher than the adjoining pavement shall be diamond ground to match elevation, (exceptions noted in paragraph below). Any individual repair that, within its defined boundaries, has any finished surface that is 1/8 inch lower than the adjoining pavement shall be paid at 50% of the bid price within the individual repair. Repair areas greater than 15 feet in length shall meet the Surface Testing and Correction parameters as defined in standard spec 415.3.10.

Concrete Pavement, Concrete Repair or Concrete Replacement areas within the boundaries of subsequent milling operation, (mainline through lanes), will be allowed to have a finished surface

0.25 inches higher or lower than the adjoining pavement surface.

1198-03-78 22 of 59

Unless the plans show, or the engineer directs otherwise, the department will not require ties to the existing adjoining pavement within repairs that are fifteen feet or less in length.

Construct, cure, and protect as specified for concrete pavement repairs in standard spec 416.

Supplement standard spec 415.3.15 and standard spec 416.2.5.2 with the following:

Concrete Pavement, Concrete Repair or Concrete Replacement must attain a minimum compressive strength of 2500 psi before they can be opened to traffic. The opening strength shall be determined by Maturity Methods standard spec 502.3.10.1.3.3 or other engineer approved methods. If cylinders are used, the compressive strength shall be measured by testing concrete cylinders cured in the field on top of the slab, under the curing blanket. At least two cylinders shall be tested in determining the attained strength of concrete repairs for the purpose of opening the pavement to traffic. The average of test results for the two cylinders shall be used to determine compliance, except that neither cylinder may be less than 10 percent below the required strength.

If opening is not controlled by maturity methods or cylinders, cores may be substituted.

# 29. HMA Pavement 5 SMA 58-34 V, Item 460.8645 HMA Pavement Test Strip Volumetrics, Item 460.0115.S HMA Pavement Test Strip Density, Item 460.0120.S.

#### **A Description**

Conform to standard spec 450 and 460 except as modified in this special provision.

B (Vacant)

#### **C** Construction

Add the following to standard spec 450.3.1.3 to require transfer vehicle for SMA:

(2) Use a Material Transfer Vehicle when constructing SMA pavement.

Add the following to standard spec 450.3.1.5 to prohibit rubber-tire roller on SMA:

(3) Do not use a rubber-tired roller for compaction of SMA pavement.

Add the following to standard spec 460.3.3.2 to require and define approval criteria for SMA test strips:

(5) Construct a test strip according to CMM 8-15.13 to correlate nuclear gauges to pavement cores, confirm SMA in-place density using cores and determine mixture air voids. Submit the test strip start time and date to the department in writing at least 5 calendar days in advance of construction of the test strip. The department will assess the contractor \$2,000 for each instance according to Section E of this special provision if paving does not begin within 2 hours of the submitted start time, delaying the test strip. Alterations to the start time and date must be submitted to the department in writing a minimum of 24 hours prior to the start time. The contractor will not be liable for changes in start time related to adverse weather days as defined by standard spec 101.3 or equipment breakdown verified by the department.

Construct the test strip at the beginning of work for each SMA mixture, for each layer and for each thickness. All SMA test strip material produced shall meet the requirements in Tables 460-1 and 460-2 and conform to the JMF limits presented herein except as follows:

Asphaltic content in percent<sup>[1]</sup> - 0.5

VMA in percent<sup>[2]</sup> - 1.0

Air Voids in percent According to the SMA Test Strip Approval Criteria Below

- Asphalt content more than -0.5% below the JMF will be referee tested by BTS using automated extraction according to WisDOT Modified ASTM D8159.
- VMA limits based on minimum requirement for mix design nominal maximum aggregate size in table 460-1 as modified herein.

1198-03-78 23 of 59

The test strip shall remain in place and become part of the completed pavement when acceptably produced, acceptably compacted, and meets finish and smoothness requirements. CMM 8-15 describes the SMA density and volumetric testing tolerances required for the test strip.

(6) The test strip is to be treated as a single/separate lot and will have densities and pay adjustments calculated accordingly. The department will test one of the two split samples for volumetrics to determine test strip approval. If the QV air void sample is outside of the limits for 100% pay (i.e. 3.2 ≤ Va ≤ 5.8), dispute resolution according to CMM 8-36 will determine material conformance and payment for the test strip. If QV and QC test results exceed testing tolerances (0.015 for Gmm or Gmb), both retained split samples will be tested by BTS. In this case, additional investigation shall be conducted to identify the source of the difference between QV and QC data and BTS referee test data will be used to determine material conformance and pay.

Pay adjustments made as part of dispute resolution on test strip material will be limited to the test strip and will not extend to material placed during main production nor will pay adjustments made on main production extend into the test strip. The department will notify the contractor within 24 hours of the start of test strip construction regarding approval to proceed with paving beyond the test strip. The department will evaluate mixture air voids, test strip density, and nuclear gauge to core correlation in determining test strip approval and material conformance according to the following:

Approval / Material Conformance <sup>[1]</sup>	QV Air Voids	Average Density of All Cores <sup>[2]</sup>	Outcome of Test Strip for Contractor
Approved / Material Conforming	3.2 <u>&lt;</u> Va <u>&lt;</u> 5.8	<u>&gt;</u> 93.0 %	Proceed with production
Test Strip Approved / Material Nonconforming	2.8 <u>&lt;</u> Va <u>&lt;</u> 3.2 or 5.8 < Va <u>&lt;</u> 6.2	<u>&gt;</u> 91.0 %	Propose solution and proceed with production. Payment for material will be based on BTS referee tests.
Test Strip Not Approved / Material Nonconforming	2.5 <u>&lt;</u> Va < 2.8 or 6.2 < Va <u>&lt;</u> 6.5	< 91.0 %	Stop production, submit cause and solution, make additional 500-ton test strip. Payment for material will be based on BTS referee tests.
Test Strip and Material are Unacceptable <sup>[3]</sup>	Va < 2.5 or Va > 6.5	< 90.0 %	Stop production, submit cause and solution, make additional 500-ton test strip, and complete new core to nuclear density gauge correlation

- [1] The overall result of each test strip will coincide with the more restrictive result from air voids or density.
- Individual nuclear density test results more than 3.0% below the minimum density requirement must be addressed according to CMM 8-15.11.
- Unacceptable material will be removed and replaced at no additional cost to the department.

  Alternatively, the engineer may allow the material to remain in place with a 50 percent payment factor.

  Material allowed to remain in place requires another test strip prior to additional paying.
- (7) An acceptable core to nuclear density gauge correlation must be completed by both the contractor and department according to CMM 8-15 as part of the test strip.
- (8) A maximum of two test strips will be allowed to remain in place per layer per contract. If the contractor changes the mix design for a given mix type during a contract, no additional compensation will be paid by the department for the required additional test strip and the department will assess the contractor \$2,000 for each additional test strip according to Section E of this special provision.

# **D** Measurement

Add the following to standard spec 460.4:

(2) The department will measure HMA Pavement Test Strip Volumetrics and HMA Pavement Test Strip Density as each unit of work, acceptably completed, as described in CMM 8-15. Material quantities will be determined according to standard spec 450.4.

1198-03-78 24 of 59

# **E** Payment

Replace standard spec 460.5.1 with the following:

The department will pay for measured quantities at the contract unit price under the following bid items:

ITEM NUMBER	DESCRIPTION	UNIT
460.8645	HMA Pavement 5 SMA 58-34 V	TON
460.0115.S	HMA Pavement Test Strip Volumetrics	EACH
460.0120.S	HMA Pavement Test Strip Density	EACH

Payment for SMA is full compensation for providing SMA mixture designs; for preparing foundation; for volumetric and density testing and aggregate source testing; for asphalt binder from recycled sources, for asphalt binder modification or processes, and addition of fibers, fines, or filler.

Payment for HMA Pavement Test Strip Volumetrics is full compensation for volumetric sampling, splitting, and testing; for proper labeling, handling, and retention of split samples.

Payment for HMA Pavement Test Strip Density is full compensation for collecting and measuring of pavement cores, acceptably filling core holes, providing of nuclear gauges and operator(s), and all other work associated with completion of a core-to-gauge correlation, as directed by the engineer.

The department will pay separately for a material transfer vehicle.

Acceptable HMA mixture placed on the project as part of a volumetric or density test strip will be compensated by the appropriate HMA Pavement bid item with any applicable pay adjustments. If a test strip is delayed as defined in standard spec 460.3.3.2(5) as modified herein, the department will assess the contractor \$2,000 for each instance, under the HMA Delayed Test Strip administrative item. If an additional test strip is required because the initial test strip is not approved by the department, or the mix design is changed by the contractor, the department will assess the contractor \$2,000 for each additional test strip (i.e. \$2,000 for each individual volumetrics or density test strip) under the HMA Additional Test Strip administrative item.

stp-460-030 (20191121)

# 30. QMP HMA Pavement Nuclear Density.

# **A Description**

Replace standard spec 460.3.3.2 (1) and standard spec 460.3.3.2 (4) with the following:

- (1) This special provision describes density testing of in-place HMA pavement with the use of nuclear density gauges. Conform to standard spec 460 except as modified in this special provision.
- (2) Provide and maintain a quality control program defined as all activities and documentation of the following:
  - 1. Selection of test sites.
  - 2. Testing.
  - 3. Necessary adjustments in the process.
  - 4. Process control inspection.
- (3) Chapter 8 of the department's construction and materials manual (CMM) provides additional detailed guidance for QMP work and describes required procedures.

# https://wisconsindot.gov/rdwy/cmm/cm-08-00toc.pdf

(4) The department's Materials Reporting System (MRS) software allows contractors to submit data to the department electronically, estimate pay adjustments, and print selected reports. Qualified personnel may obtain MRS software from the department's web site at:

http://www.atwoodsystems.com/

# **B** Materials

#### **B.1 Personnel**

(1) Nuclear gauge owners and personnel using nuclear gauges shall comply with WisDOT requirements according to 460.3.3 and CMM 8-15.

1198-03-78 25 of 59

#### **B.2 Testing**

(1) Conform to ASTM D2950 and CMM 8.15 for density testing and gauge monitoring methods. Conform to CMM 8-15.10.4 for test duration and gauge placement.

### **B.3 Equipment**

#### **B.3.1 General**

- (1) Furnish nuclear gauges according to CMM 8-15.2.
- (2) Furnish nuclear gauges from the department's approved product list at

https://wisconsindot.gov/Pages/doing-bus/eng-consultants/cnslt-rsrces/tools/appr-prod/default.aspx

# **B.3.2 Comparison of Nuclear Gauges**

# **B.3.2.1 Comparison of QC and QV Nuclear Gauges**

(1) Compare QC and QV nuclear gauges according to CMM 8-15.7.

# **B.3.2.2 Comparison Monitoring**

(1) Conduct reference site monitoring for both QC and QV gauges according to CMM 8-15.

# **B.4 Quality Control Testing and Documentation**

# **B.4.1 Lot and Sublot Requirements**

# **B.4.1.1 Mainline Traffic Lanes, Shoulders, and Appurtenances**

- (1) Divide the pavement into lots and sublots for nuclear density testing according to CMM 8-15.10.2.
- (2) Determine required number of tests according to CMM 8-15.10.2.1.
- (3) Determine random testing locations according to CMM 8-15.10.3.

# B.4.1.2 Side Roads, Crossovers, Turn Lanes, Ramps, and Roundabouts

- (1) Divide the pavement into lots and sublots for nuclear density testing according to CMM 8-15.10.2.
- (2) Determine required number of tests according to CMM 8-15.10.2.2.
- (3) Determine random testing locations according to CMM 8-15.10.3.

# **B.4.2 Pavement Density Determination**

# **B.4.2.1 Mainline Traffic Lanes and Appurtenances**

- (1) Calculate the average sublot densities using the individual test results in each sublot.
- (2) If all sublot averages are no more than one percent below the target density, calculate the daily lot density by averaging the results of each random QC test taken on that day's material.
- (3) If any sublot average is more than one percent below the target density, do not include the individual test results from that sublot when computing the lot average density and remove that sublot's tonnage from the daily quantity for incentive. The tonnage from any such sublot is subject to disincentive pay as specified in standard spec 460.5.2.2.

# **B.4.2.2 Mainline Shoulders**

### **B.4.2.2.1 Width Greater Than 5 Feet**

(1) Determine the pavement density as specified in B.4.2.1.

# B.4.2.2.2 Width of 5 Feet or Less

- (1) If all sublot test results are no more than 3.0 percent below the minimum target density, calculate the daily lot density by averaging all individual test results for the day.
- (2) If a sublot test result is more than 3.0 percent below the target density, the engineer may require the unacceptable material to be removed and replaced with acceptable material or allow the nonconforming material to remain in place with a 50 percent pay reduction. Determine the limits of the unacceptable material according to B.4.3.

# B.4.2.3 Side Roads, Crossovers, Turn Lanes, Ramps, and Roundabouts

(1) Determine the pavement density as specified in B.4.2.1.

1198-03-78 26 of 59

#### **B.4.2.4 Documentation**

(1) Document QC density test data as specified in CMM 8.15. Provide the engineer with the data for each lot within 24 hours of completing the QC testing for the lot.

### **B.4.3 Corrective Action**

- (1) Notify the engineer immediately when an individual test is more than 3.0 percent below the specified minimum in standard spec 460.3.3.1. Investigate and determine the cause of the unacceptable test result.
- (2) The engineer may require unacceptable material specified in B.4.3(1) to be removed and replaced with acceptable material or allow the nonconforming material to remain in place with a 50 percent pay reduction. Determine limits of the unacceptable area by measuring density of the layer at 50-foot increments both ahead and behind the point of unacceptable density and at the same offset as the original test site. Continue testing at 50-foot increments until a point of acceptable density is found as specified in standard spec 460.5.2.2(1). Removal and replacement of material may be required if extended testing is in a previously accepted sublot. Testing in a previously accepted sublot will not be used to recalculate a new lot density.
- (3) Compute unacceptable pavement area using the product of the longitudinal limits of the unacceptable density and the full sublot width within the traffic lanes or shoulders.
- (4) Retesting and acceptance of replaced pavement will be as specified in standard spec 105.3.
- (5) Tests indicating density more than 3.0 percent below the specified minimum, and further tests taken to determine the limits of unacceptable area, are excluded from the computations of the sublot and lot densities.
- (6) If 2 consecutive sublot averages within the same paving pass and same target density are more than one percent below the specified target density, notify the engineer and take necessary corrective action. Document the locations of such sublots and the corrective action that was taken.

# **B.5 Department Testing**

# **B.5.1 Verification Testing**

- (1) The department will have a HTCP certified technician, or ACT working under a certified technician, perform verification testing. The department will test randomly at locations independent of the contractor's QC work. The department will perform verification testing at a minimum frequency of 10 percent of the sublots and a minimum of one sublot per mix design. The sublots selected will be within the active work zone. The contractor will supply the necessary traffic control for the department's testing activities.
- (2) The QV tester will test each selected sublot using the same testing requirements and frequencies as the QC tester.
- (3) If the verification sublot average is not more than one percent below the specified minimum target density, use the QC tests for acceptance.
- (4) If the verification sublot average is more than one percent below the specified target density, compare the QC and QV sublot averages. If the QV sublot average is within 1.0 lb/ft³ of the QC sublot average, use the QC tests for acceptance.
- (5) If the first QV/QC sublot average comparison shows a difference of more than 1.0 lb/ft<sup>3</sup> each tester will perform an additional set of tests within that sublot. Combine the additional tests with the original set of tests to compute a new sublot average for each tester. If the new QV and QC sublot averages compare to within 1.0 lb/ft<sup>3</sup>, use the original QC tests for acceptance.
- (6) If the QV and QC sublot averages differ by more than 1.0 lb/ft³ after a second set of tests, resolve the difference with dispute resolution specified in B.6. The engineer will notify the contractor immediately when density deficiencies or testing precision exceeding the allowable differences are observed.

### **B.5.2 Independent Assurance Testing**

(1) Independent assurance is unbiased testing the department performs to evaluate the department's verification and the contractor's QC sampling and testing including personnel qualifications, procedures, and equipment. The department will perform the independent assurance review according to the department's independent assurance program.

# **B.6 Dispute Resolution**

(1) The testers may perform investigation in the work zone by analyzing the testing, calculation, and documentation procedures. The testers may perform gauge comparison according to B.3.2.1.

1198-03-78 27 of 59

- (2) The testers may use comparison monitoring according to B.3.2.2 to determine if one of the gauges is out of tolerance. If a gauge is found to be out of tolerance with its reference value, remove the gauge from the project and use the other gauge's test results for acceptance.
- (3) If the testing discrepancy cannot be identified, the contractor may elect to accept the QV sublot density test results or retesting of the sublot in dispute within 48 hours of paving. Traffic control costs will be split between the department and the contractor.
- (4) If investigation finds that both gauges are in error, the contractor and engineer will reach a decision on resolution through mutual agreement.

# **B.7 Acceptance**

- (1) The department will not accept QMP HMA Pavement Nuclear Density if a non-compared gauge is used for contractor QC tests.
  - C (Vacant)
  - D (Vacant)
  - **E** Payment

# **E.1 QMP Testing**

(1) Costs for all sampling, testing, and documentation required under this special provision are incidental to the work. If the contractor fails to perform the work required under this special provision, the department may reduce the contractor's pay. The department will administer pay reduction under the Non-performance of QMP administrative item.

# **E.2 Disincentive for HMA Pavement Density**

(1) The department will administer density disincentives as specified in standard spec 460.5.2.2.

# E.3 Incentive for HMA Pavement Density

(1) The department will administer density incentives as specified in standard spec 460.5.2.3. stp-460-020 (20181119)

# 31. Sawing Pavement Deck Preparation Areas, Item 509.0310.S.

### **A Description**

This special provision describes sawing around deteriorated areas requiring deck repairs under the Preparation Decks bid items on decks receiving asphalt or polymer overlays and for deck repairs that will not receive an overlay.

# B (Vacant)

### **C** Construction

The department will sound and mark areas of deteriorated concrete that require deck preparation. The engineer may identify and mark additional areas as the work is being performed.

Wet cut a minimum of 1 inch deep and at least 2 inches outside of the marked areas. Bound each marked area by providing cuts aligned parallel and perpendicular to the deck centerline.

Remove sawing sludge after completing each area. Do not allow sludge or resulting residue to enter a live lane of traffic, storm sewer, stream, lake, reservoir, marsh, or wetland. Dispose of sludge at an acceptable material disposal site located off the project limits or, if the engineer allows, within the project limits.

# **D** Measurement

The department will measure Sawing Pavement Deck Preparation Areas by the linear foot, acceptably completed, measured as the total linear feet of bounding cuts.

The department will not measure for payment over-cuts or cuts made beyond what is required to bound engineer-marked deterioration limits.

1198-03-78 28 of 59

### **E** Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER

DESCRIPTION

UNIT
509.0310.S

Sawing Pavement Deck Preparation Areas

LF

Payment is full compensation for making all saw cuts; and for debris disposal.

stp-509-070 (20180628)

# 32. Concrete Masonry Deck Repair, Item 509.2100.S.

# **A Description**

This special provision describes providing concrete masonry on the sawed deck preparation areas of the concrete bridge deck and in full depth deck, curb, and joint repair areas. Conform to standard spec 502 and standard spec 509.

#### **B** Materials

#### **B.1 Neat Cement**

Furnish a neat cement bonding grout. Mix the neat cement in a water-cement ratio approximately equal to 5 gallons of water per 94 pounds of cement.

#### **B.2** Concrete

Furnish grade C, C-FA, C-S, C-IS, C-IP, C-IT, or E concrete conforming to standard spec 501 for deck preparation, full-depth deck repair, curb repair and joint repair areas except as follows:

- 1. The contractor may increase slump of grade E concrete to 3 inches.
- 2. The contractor may use ready-mixed concrete.

Provide QMP for class II ancillary concrete as specified in standard spec 716.

### **C** Construction

# **C.1 Neat Cement**

Immediately before placing the concrete deck patching, coat the prepared surfaces with a neat cement mixture. Ensure the prepared concrete surfaces are moist without any standing water before coating with the neat cement mixture. Brush the neat cement mixture over the prepared concrete surfaces to ensure that all parts receive an even coating, and do not allow excess neat cement to collect in pockets. Apply the neat cement at a rate that ensures the cement does not dry out before being covered with the new concrete.

# **C.2 Placing Concrete**

Place concrete conforming to standard spec 509. As determined by the engineer, consolidate smaller areas by internal vibration, strike them off, and finish the areas with hand floats to produce plane surfaces that conform to the grade and elevation of the adjoining surfaces. Give all deck patching areas a final hand float finish.

#### C.3 Curing Concrete

Cure the concrete masonry deck patching conforming to standard spec 502.2.6(1).

#### **D** Measurement

The department will measure the Concrete Masonry Deck Repair bid item by the cubic yard, acceptably completed.

The department will measure concrete used in deck preparation areas and in full depth deck, curb, and joint repair as part of the Concrete Masonry Deck Repair bid item.

The department will not measure wasted concrete.

# **E** Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBERDESCRIPTIONUNIT509.2100.SConcrete Masonry Deck RepairCY

1198-03-78 29 of 59

Payment is full compensation for furnishing, hauling, preparing, placing, finishing, curing, and protecting all materials.

stp-509-060 (20191121)

# 33. Polymer Overlay, Item 509.5100.S.

# **A** Description

This special provision describes providing two layers of a two-component polymer overlay system to the bridge decks the plans show.

#### **B** Materials

### **B.1 General**

Furnish materials specifically designed for use over concrete bridge decks. Furnish polymer liquid binders from the department's approved product list.

# **B.2 Polymer Resin**

Furnish a polymer resin base and hardener composed of two-component, 100 percent solids, 100 percent reactive, thermosetting compound with the following properties:

Property	Requirements	Test Method
Gel Time <sup>[1]</sup>	15 - 45 minutes @ 73° to 75° F	ASTM C881
Viscosity <sup>[1]</sup>	7 - 70 poises	ASTM D2393, Brookfield RVT, Spindle No. 3, 20 rpm
Shore D Hardness <sup>[2]</sup>	60-75	ASTM D2240
Absorption <sup>[2]</sup>	1% maximum at 24 hr	ASTM D570
Tensile Elongation <sup>[2]</sup>	30% - 70% @ 7 days	ASTM D638
Tensile Strength <sup>[2]</sup>	2000 to 5000 psi @ 7 days	ASTM D638
Chloride Permeability <sup>[2]</sup>	<100 coulombs @ 28 days	AASHTO T277

<sup>[1]</sup> Uncured, mixed polymer binder

Ensure that the polymer resin when mixed with aggregate has the following properties:

Property	Requirement <sup>[1]</sup>	Test Method
Minimum Compressive Strength	1,000 psi @ 8 hrs 5,000 psi @ 24 hrs	ASTM C579 Method B, Modified <sup>[2]</sup>
Thermal Compatibility	No Delaminations	ASTM C884
Minimum Pull-off Strength	250 psi @ 24 hrs	ASTM C1583

<sup>[1]</sup> Based on samples cured or aged and tested at 75°F

1198-03-78 30 of 59

<sup>[2]</sup> Cured, mixed polymer binder

Plastic inserts that will provide 2-inch by 2-inch cubes shall be placed in the oversized brass molds.

# **B.3 Aggregates**

Furnish natural or synthetic aggregate that is non-polishing; clean; free of surface moisture; fractured or angular in shape; free from silt, clay, asphalt, or other organic materials; and conform to the following:

#### **Aggregate Properties**

Property	Requirement	Test Method
Moisture Content <sup>[1]</sup>	1/2 of the measured aggregate absorption, %	ASTM C566
Hardness	≥6.5	Mohs Scale
Fractured Faces	100% with at least 1 fractured face & 80% with at least 2 fractured faces of material retained on No.16	ASTM D5821
Absorption	<u>≤</u> 1%	ASTM C128

<sup>[1]</sup> Sampled and tested by the department before placement.

#### Gradation

Sieve Size	% Passing by Weight
No. 4	100
No. 8	30 – 75
No. 16	0 – 5
No. 30	0 – 1

# **B.4 Approval of Bridge Deck Polymer Overlay System**

A minimum of 20 working days before application, submit product data sheets and specifications from the manufacturer, and a certified report of test or analysis from an independent laboratory to the engineer for approval. The department will sample and test the aggregates for gradation and moisture content before placement. If requested, supply the department with samples of the polymer for the purpose of acceptance testing.

# **B.4.1 Product Data Sheets and Specifications**

Product data sheets and specifications from the manufacture consists of literature from the manufacturer showing general instructions, application recommendations/methods, product properties, general instructions, or any other applicable information.

# **B.4.2 Certified Report of Test or Analysis**

Conform to the following:

<u>Polymer Binder:</u> Submit a certified report of test or analysis from an independent laboratory dated less than 3 years before the date of the project letting showing the polymer binder meets the requirements of section B.2.

<u>Aggregates:</u> Submit a certified report of test or analysis from an independent laboratory dated less than 6 months before the date of the project letting showing the aggregates meet the requirements of section B.3.

#### **C** Construction

# C.1 General

Ensure that the overlay system is 1/4 inch thick or thicker.

Conform to the following:

<u>Field Review:</u> Conduct a field review of the existing deck to identify any possible surface preparation and material compatibility issues.

<u>Pre-Installation Meeting</u>: Conduct a pre-installation meeting with the manufacturer's representative and the engineer before construction. Discuss the field review findings, verification testing of the surface preparation and establish procedures for maintaining optimum working conditions and coordination of work. Furnish the engineer a copy of the recommended procedures and apply the overlay system according to the manufacturer's

1198-03-78 31 of 59

instructions. Supply for the engineer's use for the duration of the project, a Concrete Surface Profile (CSP) chip set of 10 from the International Concrete Repair Institute (ICRI).

<u>Manufacturer's Representative:</u> An experienced manufacturer's representative familiar with the overlay system installation procedures shall be present at all times during surface preparation and overlay placement to provide quality assurance that the work is being performed properly. This requirement may be reduced at the engineer's discretion.

<u>Material Storage</u>: Store and handle materials according to the manufacturer's recommendations. Store resin materials in their original containers in a dry area. Store all aggregates in a dry environment and protect aggregates from contaminants on the job site.

# **C.2 Deck Preparation**

# C.2.1 Deck Repair

Remove all asphaltic patches and unsound or disintegrated areas of the concrete decks as the plans show, or as the engineer directs. Work performed to remove and repair the concrete deck will be paid for under other items.

Use deck patching products that are compatible with the overlay system. Patching materials with magnesium phosphate shall not be used. Place patches after surface is prepared via shot blasting and cleaning as described in Section C.2.2 of this specification. Portland cement concrete patches shall be used for joint repairs and full depth deck repairs with a plan area larger than 4 sf, unless approved otherwise by the Structures Design Section. If rapid-set concrete is used, place patches per the manufacturer's recommendation. If Portland cement concrete is used, place patches per standard spec 509.3.9.1.

Deck patching shall be filled and properly finished prior to overlay placement. Do not place overlay less than 1 hour, or per the manufacturer's recommendation, after placing rapid-set concrete patches in the repair areas. Do not place overlay less than 28 days after placing Portland cement concrete patches in the repair areas.

# C.2.2 Surface Preparation

Determine an acceptable shotblasting machine operation (size of shot, flow of shot, forward speed, and/or number of passes) that provides a surface profile meeting CSP 5 (medium-heavy shotblast) according to the ICRI Technical Guideline No. 310.2. If the engineer requires additional verification of the surface preparation, test the tensile bond strength according to ASTM C1593. The surface preparation will be considered acceptable if the tensile bond strength is greater than or equal to 250 psi or the failure area at a depth of 1/4 inches or more is greater than 50 percent of the test area. Continue adjustment of the shotblasting machine and necessary testing until the surface is acceptable to the engineer or a passing test result is obtained.

Prepare the entire deck using the final accepted adjustments to the shotblasting machine as determined above. Thoroughly blast clean with hand-held equipment any areas inaccessible by the shotblasting equipment. Do not perform surface preparation more than 24 hours before the application of the overlay system.

Protect drains, expansion joints, access hatches, or other appurtenances on the deck from damage by the shot and sand blasting operations and from materials adhering and entering. Tape or form all construction joints to provide a clean straight edge.

Before shot blasting, remove pavement markings within the treatment area using an approved mechanical or blasting method.

Prepare the vertical concrete surfaces adjacent to the deck a minimum of 2" above the overlay according to SSPC-SP 13 (free of contaminants, dust, and loose concrete) by sand blasting, using wire wheels, or other approved method.

Just before overlay placement, clean all dust, debris, and concrete fines from the prepared surfaces including the vertical surfaces with compressed air. When using compressed air, the air stream must be free of oil. Any grease, oil, or other foreign matter that rests on or has absorbed into the concrete shall be removed completely. If prepared surfaces (including the first layer of the polymer overlay) are exposed to rain or dew, lightly sandblast (brush/breeze blast) the exposed surfaces.

The engineer may consider alternate surface preparation methods per the overlay system manufacture's recommendations. The engineer will approve the final surface profile and deck cleanliness before the contractor placing the polymer overlay.

1198-03-78 32 of 59

#### C.2.3 Transitional Area

If the plans show, create a transitional area approaching transverse expansion joints and ends of the deck using an approved mechanical or blasting method. Remove 1/4 inch to 5/16 inch of concrete adjacent to the joint or end of deck and taper a distance of 3 feet.

If the plans show, create a transitional area on the approach pavement. Prep and place the first lift 3 feet beyond the end of the deck the same width as the deck. Prep and place the second lift 6 feet beyond the end of the deck the same width as the deck.

# C.3 Overlay Application

Perform the handling and mixing of the polymer resin and hardening agent in a safe manner to achieve the desired results according to the manufacturer's instructions. Do not apply the overlay system if any of the following exists:

- 1. Ambient air temperature is below 50 F or above 100 F.
- 2. Deck temperature is below 50 F.
- 3. Moisture content in the deck exceeds 4.5 percent when measured by an electronic moisture meter or shows visible moisture after 2 hours when measured in accordance with ASTM D4263.
- 4. Rain is forecasted during the minimum curing periods listed under C.5.
- 5. Materials component temperatures below 65 F or above 99 F.
- 6. Concrete deck age is less than 28 days.
- 7. The deck temperature exceeds 100 F.
- 8. If the gel time is 10 minutes or less at the predicted high air temperature for the day.

After the deck has been shotblasted or during the overlay curing period, only necessary surface preparation and overlay application equipment will be allowed on the deck. Provide appropriate protective measures to prevent contamination from equipment allowed on the deck during preparation and application operations. Begin overlay placement as soon as possible after surface preparation operations.

The polymer overlay shall consist of a two-course application of polymer and aggregate. Each of the two courses shall consist of a layer of polymer covered with a layer of aggregate in sufficient quantity to completely cover the polymer. Apply the polymer and aggregate according to the manufacturer's requirements. Apply the overlay using equipment designed for this purpose. The application machine shall feature positive displacement volumetric metering and be capable of storing and mixing the polymer resins at the proper mix ratio. Disperse the aggregate using a method that provides a uniform, consistent coverage of aggregate and minimizes aggregate rolling or bouncing into final position. First course applications that do not receive enough aggregate before the polymer gels shall be removed and replaced. A second course applied with insufficient aggregate may be left in place, but will require additional applications before opening to traffic.

After completion of each course, cure the overlay according to the manufacturer's instructions. Follow the minimum cure times listed under C.5 or as prescribed by the manufacturer. Remove the excess aggregate from the surface treatment by sweeping, blowing, or vacuuming without tearing or damaging the surface; the material may be re-used if approved by the engineer and manufacturer. Apply all courses of the overlay system before opening the area to traffic. Do not allow equipment or traffic on the treated area until directed by the engineer.

After the first layer of coating has cured to the point where the aggregate cannot be pulled out, apply the second layer. Before applying the second layer, broom and blow off the first layer with compressed air to remove all loose excess aggregate.

Before opening to traffic, clean expansion joints and joint seals of all debris and polymer. A minimum of 3 days following opening to traffic, remove loosened aggregates from the deck, expansion joints, and approach pavement.

1198-03-78 33 of 59

# C.4 Application Rates

Apply the polymer overlay in two separate courses in accordance with the manufacturer's instructions, but not less than the following rate of application.

Course	Minimum Polymer Rate <sup>[1]</sup> (GAL/100 SF)	Aggregate <sup>[2]</sup> (LBS/SY)
1	2.5	10+
2	5.0	14+

The minimum total applications rate is 7.5 GAL/100 SF.

# C.5 Minimum Curing Periods

As a minimum, cure the coating as follows:

	Average temperature of deck, polymer and aggregate components in degrees F							
Course	50-54	55-59	60-64	65-69	70-74	75-79	80-84	85-99
1	6 hrs.	5 hrs.	4 hrs.	3 hrs.	2.5 hrs	2 hrs	1.5 hrs.	1 hr.
2	8 hrs.	6.5 hrs.	6.5 hrs.	5 hrs.	4 hrs.	3 hrs.	3 hrs.	3 hrs.

If faster cure times are desired and achievable, submit to the engineer a certified test report from an independent laboratory showing the material is able to reach a compressive strength of 1000 psi as tested per ASTM C 579 Method B within the temperature ranges and cure times for which the product is proposed to be placed. Establish ambient air, material, and substrate temperatures from the manufacturer for field applications. Field applications will not be allowed below the documented temperatures.

# C.6 Repair of Polymer Overlay

Repair all areas of unbonded, uncured, or damaged polymer overlay for no additional compensation. Submit repair procedures from the manufacturer to the engineer for approval. Absent a manufacturer's repair procedures and with the approval of the engineer, complete repairs according to the following: Saw cut the limits of the area to the top of the concrete; remove the overlay by scarifying, grinding, or other approved methods; shot blast or sand blast and air blast the concrete before placement of polymer overlay; and place the polymer overlay according to section C.3.

### **D** Measurement

The department will measure Polymer Overlay by the square yard, acceptably completed.

# E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBERDESCRIPTIONUNIT509.5100.SPolymer OverlaySY

Payment is full compensation for preparing the surface; for tensile bond testing; for creating the transitional area; for providing the overlay; for cleanup; and for sweeping/vacuuming and disposing of excess materials.

The department will pay separately for deck repairs.

stp-509-030 (20200629)

# 34. Adjusting Manhole Covers.

This special provision describes adjusting manhole covers conforming to standard spec 611 as modified in this special provision.

Adjust manhole covers located in pavement areas in two separate operations. Initially, remove designated manhole covers along with sufficient pavement to permit installation of temporary cover plate over the opening. Fill the excavated area with asphaltic pavement mixture, which shall remain in place until contract milling and paving operations permit setting the manhole frames to grade. During the second phase, remove the asphaltic pavement mixture surrounding the manhole plus the temporary

1198-03-78 34 of 59

<sup>[2]</sup> Application of aggregate shall be of sufficient quantity to completely cover the polymer.

cover plate, and set the manhole cover to final grade. The department will measure and pay for the items of asphaltic pavement mixture, temporary cover plate, milling, and paving separately. Remove and replace all loose or deteriorated brick and mortar joints, mortar pipe connections that are not flush with the manhole, clean out the manhole, and apply a 1-inch mortar back plaster to the entire interior of the manhole at locations the plans show or as the engineer directs. Payment for replacing damaged rings or adding adjustment rings is incidental to the adjusting manhole cover.

Revise standard spec 611.3.7 by deleting the last paragraph.

Set the manhole frames so that they comply with the surface requirements of standard spec 450.3.2.9. At the completion of the paving, a 6-foot straightedge shall be placed over the centerline of each manhole frame parallel to the direction of traffic. A measurement shall be made at each side of the frame. The two measurements shall be averaged. If this average is greater than 5/8 inches, reset the manhole frame to the correct plane and elevation. If this average is 5/8 inches or less but greater than 3/8 inches, the manhole frame shall be allowed to remain in place but shall be paid for at 50 percent of the contract unit price.

If the manhole frame is higher than the adjacent pavement, the two measurements shall be made at each end of the straightedge. These two measurements shall be averaged. The same criteria for acceptance and payment as above, shall apply.

# 35. Cover Plates Temporary, Item 611.8120.S.

### **A Description**

This special provision describes providing and removing steel plates to cover and support asphaltic pavement and traffic loading at manholes, inlets and similar structures during milling and paving operations.

### **B** Materials

Provide a 0.25 inch minimum thickness steel plate that extends to the outside edge of the existing masonry.

# C (Vacant)

#### **D** Measurement

The department will measure Cover Plates Temporary as each individual unit, acceptably completed.

# **E** Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER

DESCRIPTION

UNIT

611.8120.S

Cover Plates Temporary

EACH

Payment is full compensation for furnishing, installing, and removing the cover plates.

The steel plates shall become the property of the contractor when no longer needed in the contract work. stp-611-006 (20151210)

# 36. Field Office.

Add the following to standard spec 642:

For field offices without handwashing facilities, provide and maintain a portable handwashing station at every project field office. The station shall include a hands-free sink with foot pump-operated faucet, soap dispenser, paper towel dispenser, fresh water supply, and collection tank for gray water. Regularly service and maintain the handwashing station and all supplies as needed, and properly dispose of all materials. Costs associated with the handwashing station are incidental to the field office bid item.

stp-642-010 (20200629)

1198-03-78 35 of 59

# 37. General Requirements for Electrical Work.

Replace standard spec 651.3.3 (3) with the following:

Notify the engineer and request a signal inspection at least 5 business days before the date of the requested inspection. In the event of deficiencies, request a re-inspection when the work is corrected. The engineer will not authorize turn-on until the contractor corrects deficiencies.

Electrical item inspections are required at the following times: after the staking of all electrical underground items, before the pouring of all lighting, signal, and cabinet bases; before cable and wire are pulled; during field terminations at signal and lighting bases; and prior to the installation of any poles, standards, or other above ground electrical items.

Request electrical inspections of the completed signal and lighting work to the engineer at least five working days prior to the time of the required inspection. Notify the City of Superior Public Works Department at (715) 395-7334 and notify the Northwest Region – Eau Claire Office Electrical Field Unit at (715) 577-0662 to coordinate the inspections.

# 38. Electrical Service Meter Breaker Pedestal USH 2 & 39th Ave, Item 656.0200.01

Add the following to standard spec 656.2.3 (1):

The contractor will be responsible for the electric service installation request. Notify the City of Superior Public Works Department at (715) 395-7334 when application is submitted to the utility company.

Electric utility company service installation and energy cost will be billed to and paid for by the maintaining authority.

Install the cabinet base and meter breaker pedestal first, so the electric utility company can install the service lateral. Finish grade the service trench, replace topsoil that is lost or contaminated with other materials, fertilize, seed, and mulch all areas that are disturbed by the electric utility company.

Add the following to standard spec 656.5 (3):

Payment for grading the service trench, replacing topsoil, fertilizer, seed, and mulch will be incidental to this work unless the bid items are in the contract and then they will be paid for at the contract price.

# 39. Traffic Signals, General

Note that failure to comply with the state standards and specifications may result in the cost of the corrections to be made at the contractor's expense. Also, any additional disruption of state-owned facilities shall be repaired or relocated as needed at the contractor's expense.

Notify the City of Superior Public Works Department at (715) 395-7334 and the Northwest Region – Eau Claire Office Electrical Field Unit at (715) 577-0662 at least three weeks prior to the beginning of the traffic signal work.

Prior to ordering monotube equipment, the monotube locations shall be staked to confirm arm lengths with the engineer in the field. Note that there is a several month backorder for delivery of monotube traffic signal equipment. Provide as much advance notice as possible to the monotube manufacturer to ensure timely delivery.

# 40. Temporary Traffic Signals for Intersections USH 2 & 39th Ave, Item 661.0200.01.

Add the following to standard spec 661.2.1:

(6) All wood poles shall be plumb and level.

Replace standard spec 661.3.1(2) with the following:

(2) Request a signal inspection of the complete temporary traffic signal installation. Make this request to the engineer at least five working days before the requested inspection. Notify the Northwest Region – Eau Claire Office Electrical Field Unit at (715) 577-0662 to coordinate the inspection. The department's region electrical personnel will perform the inspection.

1198-03-78 36 of 59

Add the following to standard spec 661.3.1.4:

(4) Arrange for monthly inspections with the engineer to check the height of the span wire above the roadways. Ensure the bottom of the traffic signal heads remain within the minimum and maximum heights allowed above the roadway. Make all height adjustments within 24-hours of an inspection indicating that adjustments are required. Notify the engineer in writing upon completion of all necessary adjustments. Maintain a written log to properly document the date of each monthly inspection, the heights above the roadway, the roadway clearance after adjustments have been made and acceptance by the engineer. Provide to the engineer all documentation related to the monthly span wire height checks and all records related to maintenance performed on the temporary traffic signal installations to the engineer.

Replace standard spec 661.5 (2) with the following:

- (2) Payment for the Temporary Traffic Signals for Intersections bid item is full compensation for providing, operating, maintaining, and repairing the complete temporary installation; and for removal. Payment also includes the following:
  - 1. Furnishing and installing replacement equipment.
  - 2. The cost of delivery and pick-up of the cabinet assemblies.
  - 3. Removal of service and site restoration.
  - 4. Inspection and documentation

# 41. Flashing Beacon Queue Warning System, Item SPV.0045.01

# A Description

This special provision describes providing, repositioning, operating, maintaining, monitoring, calibrating, testing and removing a flashing beacon queue warning system capable of measuring vehicular speeds at a downstream section of a roadway, and activating the system.

#### **B** Materials

Provide flashing beacon queue warning system components and software that is National Transportation Communications for ITS Protocol (NCTIP) compliant.

### **B.1 Portable Traffic Sensors (PTS)**

Provide one PTS that is nonintrusive and capable of capturing vehicle speed (mph). Integrate the sensor with a modem to communicate with the automated system manager.

### B.2 Static Traffic Control Signs with Temporary Flashing Beacon Signs (FBS)

Provide static traffic control signs with temporary flashing beacon signs conforming to standard spec 658.2(2) for Traffic Signal Faces. Ensure each FBS is integrated with a modem, and other equipment (e.g., automated system manager) mounted on it, and acts as a single device for communicating with similarly integrated devices and displaying real-time traffic conditions.

# **B.3 Automated System Manager**

Provide an ASM that assesses current traffic data captured by the PTS and activates/deactivates the FBS based on predetermined speed thresholds.

# **B.4 System Communications**

Ensure flashing beacon queue warning system communications meet the following requirements:

- 1. Perform required configuration of the flashing beacon queue warning system's communication system automatically during system initialization.
- 2. Communication between the server and any individual FBS or PTS are independent through the full range of deployed locations, and do not rely upon communications with any other FBS or PTS.
- 3. Incorporate an error detection/correction mechanism into the flashing beacon queue warning system communication system to ensure the integrity of all traffic condition data.

1198-03-78 37 of 59

# **B.5 System Acceptance**

Submit vendor verification to the engineer and Bureau of Traffic Operations (<a href="mailto:DOTBTOworkzone@dot.wi.gov">DOTBTOworkzone@dot.wi.gov</a>) 14 calendar days before the pre-construction meeting that the system will adequately perform the functions specified in this special provision. Adequate verification includes past successful performance of the system, literature and references from successful use of the system by other agencies, and/or demonstration of the system.

Provide contact information for a designated representative responsible for monitoring the performance of the system and for making modifications to the operational settings as the engineer directs. Provide all testing and calibration equipment.

### **C** Construction

### C.1 General

Install and reposition flashing beacon queue warning system per plan or as the engineer directs. Provide plan to the engineer and Bureau of Traffic Operations (<a href="mailto:DOTBTOworkzone@dot.wi.gov">DOTBTOworkzone@dot.wi.gov</a>) 14 calendar days before the pre-construction meeting.

PTS may be mounted on FBS, arrow board or other trailer devices, delineated by 5 drums.

Install one PTS approximately 800 feet upstream of the stop bar at the intersection of USH 2/53 and 39<sup>th</sup> Avenue.

Install FBS at the following locations, delineated by 5 drums:

- 1. Place first FBS 2000 feet upstream of stop bar at the intersection of USH 2/53 and 39<sup>th</sup> Avenue.
- 2. Place second FBS 3900 feet upstream of stop bar at the intersection of USH 2/53 and 39th Avenue.

Number the devices in chronological order so they are visible from the shoulder with 6-inch white high reflective sheeting.

Provide technical personnel for all system calibration, operation, maintenance, and timely on-call support services.

Promptly correct the system within 24 hours of becoming aware of a deficiency in the operation or individual part of the system. A minimum of three days before deployment, place the flashing beacon queue warning system and demonstrate to the Department that the flashing beacon queue warning system is operational.

Maintain the flashing beacon queue warning system for the duration of the project. Ensure the system operates continuously (24 hours, 7 days a week) in the automated mode throughout the duration of the project.

Remove the system upon completion.

### C.2 Reports

Provide an electronic copy of a weekly summary report of all data via email to the engineer. Ensure the report includes, at a minimum, the average speed per sensor, time in congestive state per sensor and number of triggers per day.

# C.3 Meetings

Attend mandatory in-person pre-construction meetings with the department. Attend additional meetings as deemed necessary by the department. These meetings may be held in person or via teleconference, as scheduled by the department.

### **C.4 Programming**

# C.4.1 General

Program the flashing beacon queue warning system to ensure that the following general operations are performed:

- 1. Provide a password protected login to the ASM, website and all other databases.
- 2. Automatic setting of the FBS to reflect current traffic flow status updated every 60 seconds for congestion. Ensure to remove a congestion message when 180 seconds of average traffic speeds above the current level are observed, or utilize a customized frequency as determined by the engineer.

1198-03-78 38 of 59

- 3. The FBS activate based on pre-determined speed thresholds from the PTS.
  - FBS's shall activate based on traffic speeds at the PTS located approximately 800 feet upstream of the stop bar at the intersection of USH 2/53 and 39th Avenue.
- 4. Provide real-time data from the ASM to a website with a full color mapping feature and refresh every 60 seconds. Make data on website available to the department staff at all times for the duration of the work zone activity. Ensure website includes:
  - Vehicle speeds
  - FBS triggers
  - Device locations
- 5. Archive all traffic data in a Microsoft Excel format with date and time stamps.
- 6. Configure the website to quantify system failures which includes communication disruption between any devices in the system configuration, FBS malfunctioning, PTS malfunction, loss of power, low battery, etc.
- 7. Automatically generate and send an email alert any time a user specified queue is detected by the system.
- 8. Ensure the system autonomously restarts in case of any power failure.

# C.4.2 System Operation Strategy

Arrange for the vendor/manufacturer to coordinate system operation, detection, and trends/thresholds with the engineer.

The sequences below are a minimum requirement, but can be adjusted at the discretion of the engineer, are as follows:

#### Free Flow:

If the current PTS speed is at or above 15 mph, the FBS's will not flash.

# Slow or Stopped Traffic:

If the current PTS speed is between the 14 mph and 0 mph (for example, 12 mph), the FBS's shall flash.

# C.5 Calibration and Testing

At the beginning of the project and perform a successful field test and calibration at the flashing beacon queue warning system location to verify the system is detecting accurate vehicle speeds, and accurately relaying the information to the ASM and the FBS.

Send email of successful calibration and testing to the engineer.

### **D** Measurement

The department will measure Flashing Beacon Queue Warning System by the day, acceptably completed, measured as each complete system per roadway.

# **E** Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBERDESCRIPTIONUNITSPV.0045.01Flashing Beacon Queue Warning SystemDAY

Payment is full compensation for providing, repositioning, operating, maintaining, monitoring, calibrating, testing, and removing the complete system consisting of FBS, PTS, ASM, and system communications.

Failure to correct a deficiency to the FBS, PTS, or ASM within 24 hours after notification from the engineer or the department will result in a one-day deduction of the measured quantity for each day in which the deficiency is not corrected.

Failure to correct the website within 24 hours after notification from the engineer will result in a 10% reduction of the day quantity for each day the website is down.

The engineer will have sole discretion to assess the deductions for an improperly working flashing beacon queue warning system.

1198-03-78 39 of 59

# 42. Elastomeric Waterproofing Sealer, Item SPV.0060.01.

# A Description

This special provision describes furnishing and installing elastomeric waterproofing sealer on sanitary or storm manholes, and catch basins as located on the plans and as hereinafter provided.

#### **B** Materials

Elastomeric waterproofing sealer shall be a single component moisture curing polyurethane applied to form a continuous membrane, as detailed in Section 8.42.1 of the Standard Specifications for Sewer and Water Construction in Wisconsin, Sixth Edition with Addendum No.1 and No.2.

#### **C** Construction

All masonry work shall be cured a minimum of 24 hours prior to applying an elastomeric waterproofing seal. All surfaces shall be cleaned and primed according to the manufacturer's recommendation.

Elastomeric waterproofing sealer shall be applied so that it forms a continuous membrane, 100-mil thick, extending from a point 4 inches below the chimney to a point 2 inches above the frame flange. The engineer reserves the right to require bond breaker (duct tape) be placed completely around the manhole circumference and centered over the mortar joint between the frame and chimney or cone.

#### **D** Measurement

The department will measure Elastomeric Waterproofing Sealer by each manhole and catch basin onto which the elastomeric waterproofing sealer is applied, acceptably completed.

# **E** Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER

DESCRIPTION

UNIT

SPV.0060.01

Elastomeric Waterproofing Sealer

EACH

Payment is full compensation for all materials and personnel to complete the application of the elastomeric waterproofing sealer to the manhole, including, but not limited to, any necessary excavation and backfill.

# 43. Protecting Footing, Item SPV.0060.02.

# **A Description**

This work consists of installation, inspection, maintenance, and removal of footing protection measures.

#### **B** Materials

Furnish notched metal "T" or "U" shaped fence posts weighing 1 1/3 pounds per foot or more.

Furnish select 2x4 dimensional lumber.

Furnish fence fabric meeting the following requirements:

Color: International orange (UV stabilized)

Roll Height: 4 feet

Mesh Opening: 1-inch min to 3-inch max

Resin/Construction: High density polyethylene mesh

Tensile Yield: Avg. 2000 lb per 4-ft. width (ASTM D638)

Ultimate Tensile Strength: Avg. 3000 lb per 4-ft. width (ASTM D638)

Elongation at Break (%): Greater than 100% (ASTM D638)

Chemical Resistance: Inert to most chemicals and acids

1198-03-78 40 of 59

#### **C** Construction

Under the bid item Protecting Footing, fence and protect footing at Station 255+76 as shown in the Plan and/or as designated by the engineer in the field.

The engineer may add, delete or revise the areas that require protection at any time prior to or during the project construction period. The contractor shall install all protection measures before the commencement of any construction activities and be reviewed on site by the engineer in the field.

Securely support the fence so it is in a vertical position without sagging. Locate and place the fence supports so they are not a safety hazard.

The contractor shall periodically inspect the protection fencing and repair any deficiencies. If the footing under protection is damaged, the contractor shall notify the engineer in the field immediately.

Removal of footing protection fence shall occur after work has completed.

# **D** Measurement

The department will measure Protecting Footing as each footing, acceptably protected.

# **E** Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBERDESCRIPTIONUNITSPV.0060.02Protecting FootingEACH

Payment is full compensation for installation, inspection, maintenance and removal of fence as provided herein, including clean up after the work is complete.

# 44. Cure and Seal Treatment, Concrete Curb and Gutter, Item SPV.0090.01; Cure and Seal Treatment, Concrete Sidewalk, Item SPV.0165.01.

### **A** Description

This special provision describes treating all newly constructed concrete curb and gutter and concrete sidewalks with a surface cure and seal treatment as shown on plans, and as hereinafter provided.

# **B** Materials

Materials shall conform to a clear treating material listed on the current approved WISDOT product list for "Cure and Seal Compounds for Non-Trafficked Surfaces on Structural Masonry".

# **C** Construction

Application rates for the treating material shall be according to the manufacturer's specifications

#### **D** Measurement

The department will measure the Cure and Seal Treatment, Concrete Curb and Gutter by the linear foot, acceptably completed.

The department will measure the Cure and Seal Treatment: Concrete Sidewalk by the square foot, acceptably completed.

# **E** Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0090.01	Cure and Seal Treatment, Concrete Curb and Gutter	LF
SPV.0165.01	Cure and Seal Treatment, Concrete Sidewalk	SF

Payment is full compensation for cure and seal treatment for concrete sidewalk and concrete curb and gutter.

1198-03-78 41 of 59

# 45. Traffic Signal Cabinet and Controller USH 2 & 39th Ave, Item SPV.0105.01.

# A Description

This special provision describes furnishing and installing a fully equipped and operational NEMA TS2 Type 1 traffic signal control cabinet.

#### **B** Materials

#### **B.1 General**

Furnish and install equipment and assemble the cabinet conforming to the latest revision of NEMA Standards Publication TS 2-2003, *Traffic Controller Assemblies with NTCIP Requirements*, National Electrical Manufacturers Association, hereinafter called NEMA TS2 Standard, except where modified in this specification. All work shall conform to the Wisconsin State Electrical Code (WSEC). All work shall conform to standard spec 651, 2020 Edition, as supplemented or modified in this specification.

Provide cabinets designed for TS2 Type 1 operation. Pre-wire cabinets for a minimum of sixteen phases as specified herein.

The traffic signal controller shall be an Econolite ASC/3.

Furnish and install at no extra cost any equipment and materials not specifically described but required in order to perform the intended functions in the cabinet.

Install the cabinet on the foundation and terminate all connections. Test for correct operation.

Provide the project plans and specifications to the traffic signal controller and cabinet supplier at least 18 weeks prior to scheduled field installation. Coordinate with the traffic signal controller and cabinet supplier to schedule the cabinet delivery date and time to the project site location. Notify the City of Superior Public Works Department at (715) 395-7334 at least five working days prior to cabinet delivery.

Coordinate directly with the traffic signal controller and cabinet supplier to schedule the cabinet acceptance testing. Notify the City of Superior Public Works Department at (715) 395-7334 and participate in the acceptance testing. The City of Superior has the final determination of the cabinet acceptance testing date and time. The acceptance testing procedures will be provided by the City of Superior.

The owner will not be responsible for project delays and costs due to the delays of delivery by the supplier or by the failure of the traffic signal controller and cabinet to pass acceptance testing.

Provide all other needed materials in conformance with standard spec 651.2, 652.2, 653.2, 654.2, 655.2, 656.2, 657.2, 658.2 and 659.2.

### **B.2 Cabinet**

# **B.2.1 Cabinet Design**

Furnish a door-in-door ground mounted (without anchor bolts) aluminum cabinet of clean-cut design and appearance. Provide a cabinet of minimum size 44 inches wide, minimum 24 inches deep, and minimum 52 inches to maximum 60 inches high. The size of the cabinet shall provide ample space for housing the controller, all of the associated devices which are to be furnished with the controller, all other auxiliary devices herein specified, and all equipment to be furnished as listed in the materials section of this specification.

The cabinet shall comply with the environmental and operating standards outlined in the NEMA TS2 Standard. The cabinet shall provide reasonable vandalism protection. The cabinet shall have a NEMA 3R rating.

Construct the cabinet from type 5052-H32 aluminum with a minimum thickness of 0.125 inches. Furnish the cabinet with a natural, uncoated, aluminum finish inside and outside. Continuously weld all seams. The surface shall be smooth, free of marks and scratches. Use stainless steel for all external hardware.

On the top of the cabinet, incorporate a 1-inch slope toward the rear to prevent rain accumulation. Incorporate a rain channel into the design of the main door opening to prevent liquids from entering the enclosure.

Include an exhaust plenum with a vent screen into the roof of the cabinet. Perforations in the vent screen shall not exceed 0.125 inches in diameter.

Equip the lower section of the cabinet door with a louvered air entrance. The air inlet shall be large enough to allow sufficient air flow per the rated fan capacity. Louvers must satisfy the NEMA rod entry

1198-03-78 42 of 59

test for Type 3R ventilated enclosures. Secure a washable, fiberglass, removable air filter to the air entrance. The filter shall fit snugly against the cabinet door wall.

Attach an aluminum, easily removable, gasketed cover over the air filter and louver.

### **B.2.2 Doors**

The cabinet door opening shall be a minimum of 80 percent of the front surface of the cabinet. The main door and police door-in-door shall each close against a weatherproof and dust-proof, closed-cell neoprene gasket seal. The gasket material for the main door shall be a minimum of 0.188 inches thick by 1.00 inch wide. The gasket material for the police door shall be a minimum of 0.188 inches thick by 0.500 inches wide. Permanently bond the gaskets to the cabinet.

Equip the main door with a three-point latching mechanism. The upper and lower locking points of the latching mechanism shall each have a pair of nylon rollers. The handle on the main door shall utilize a shank of stainless steel 3/4 inches minimum diameter. The handle shall include a hasp for the attachment of an optional padlock. The cabinet door handle may turn either clockwise or counterclockwise to open and shall not extend outwards past the edge of the door at any time. Position the lock assembly so the key will not cause any interference with the handle, or a person's hand on the handle, when opening the cabinet door.

Include on the main door a solid stainless steel rod stop and catch mechanism capable of rigidly holding the door open at approximately 90, 120, and 180 degrees under windy conditions. The operator must be able to engage and disengage the catch with a shoed or booted foot.

The main door hinge shall be a one-piece, continuous piano hinge with a minimum 0.25 inch stainless steel pin running the entire length of the right side of the door (right-handed). Attach the hinge in such a manner that no rivets or bolts are exposed.

Equip the main door with a brass Corbin tumbler lock No. 2, swing away dust cap, and provide two keys No. 2. Equip the police door-in-door with a standard police lock and provide one key.

Electrically bond the door to the rest of the cabinet with a braided copper grounding conductor. The length of the grounding conductor shall allow the door to swing fully open, without using the stop bar, without stretching or breaking the grounding conductor. The grounding conductor shall not interfere with normal door operation.

Provide a door switch for the main cabinet door. When the door is opened the switch shall send a signal to the controller sufficient for the controller to log an alarm.

# **B.2.3 Shelves and Mounting**

Mount a minimum of three vertical "C" channels, compatible with Unistrut channel nuts, on each interior side wall of the cabinet for the purpose of mounting the cabinet components. The channels shall accommodate spring mounted nuts or studs. Install three vertical "C" channels or three slotted rails on the interior back wall of the cabinet. All mounting channels and rails shall extend to within 7 inches of the top and bottom of the cabinets and shall be of sufficient strength to rigidly hold specified shelves and equipment.

Provide two full-width, 11-inch deep, fully adjustable, aluminum shelves to support the controller and other equipment. Mount the lower shelf at a height above the bottom of the cabinet such that the shelf and attached drawer does not interfere with the ability to tilt the terminal facility forward on its hinges for maintenance purposes. Mount the top shelf at least 13 inches above the surface of the lower shelf.

Locate the controller and MMU on the top shelf. Locate the loop detector racks and other auxiliary equipment on the lower shelf. The power supply may be mounted on either shelf.

Provide an under-shelf drawer under the lower shelf. The drawer shall be approximately 20 inches wide and the full depth of the shelf. The drawer shall operate easily and smoothly and shall have a stop to prevent inadvertently pulling the drawer out of its support. Design the stop to allow purposeful complete removal of the drawer without the use of tools.

### **B.2.4 Auxiliary Cabinet Equipment**

Ventilate the cabinet by means of a 120 VAC, 60HZ, tube axial compact type fan located in the top of the cabinet plenum. The fan's free delivery airflow shall be equal to or greater than 100 cubic feet per minute. The magnetic field of the fan motor shall not affect the performance of control equipment. The fan bearings shall operate freely. The fan unit shall not crack, creep, warp, or have bearing failure within a seven year duty cycle. The maximum noise level shall be less than 40 decibels. The fan unit shall be corrosion resistant. The thermostat's turn on setting shall be adjustable from 90 to 120 degrees F. The fan

1198-03-78 43 of 59

shall run until the cabinet temperature decreases below the turn-on temperature setting by approximately 30 degrees F. The fan shall be fused.

Mount an incandescent lamp and socket in the cabinet to sufficiently illuminate the field terminals. Wire the lamp to a 15-amp ON/OFF toggle switch mounted on the rear cover of the police panel as specified in the Cabinet Switches section of this specification.

Provide a 250 watt element heater. Install the heater on the face of the aluminum, louvered air filter cover such that feed air is supplied through the cover. Provide a protective, ventilated cover over the heater. Provide a cord and twist-off plug to an electrical receptacle on the cabinet door. Provide a thermostat with an adjustable setting from 0 to 100 degrees F. Install the thermostat on the interior ceiling of the cabinet well away from the cabinet light or any heat source. Provide a thermal limit switch to prevent the heater's protective cover from exceeding 170 degrees F.

### **B.3 Terminals and Facilities**

# **B.3.1 Terminal Facility**

The terminal facility panel shall be constructed from 5052-H32 brushed aluminum of 0.125 inches minimum thickness and formed so as to eliminate any flexing when plug- in components are installed.

Mount the bottom of the terminal facility a minimum of 9 inches from the bottom of the cabinet. Hinge the terminal facility at the bottom to allow easy access with simple tools to all wiring on the rear of the panel. It shall not be necessary to remove the lower shelf, the shelf drawer, or any shelf-mounted equipment to hinge down the terminal facility. Provide sufficient slack in the load bay wiring to allow for dropping the load bay.

Fully wire the terminal facility with 16 load switch sockets: 8 phases of vehicular, 4 phases of pedestrian, and 4 phases of overlap operation; 8 flash transfer relay sockets; 1 flasher socket; and 2 terminal facility BIU rack slots. The use of printed circuit boards is not acceptable on the terminal facility, except printed circuit boards are acceptable for the BIU interface with the load bay. Position the 16 load switch sockets in two horizontal rows of 8 sockets each. Support the load switches and flasher by a bracket or shelf extending at least 3 inches from the terminal facility.

Label all terminals, load switches, and flash transfer relay sockets. Label reference designators by silk-screening on the front and rear of the terminal facility to match drawing designations.

Provide rack mounted BIU's. Provide a dual-row, 64-pin female DIN 41612 Type B connector for each BIU rack position. Provide card guides for both edges of the BIU. Terminal and facilities BIU mounting shall be an integral part of the terminal facility.

Provide two 16-channel, 8-position, TS2 detector racks, with an integrally mounted BIU mounting. The rack shall be addressable. Power the detector rack by the cabinet power supply. Fasten the loop detector rack towards the left side of the lower shelf.

For BIU rack connectors, provide pre-wired address pins or jumper plugs corresponding to the requirements of the NEMA TS2 Standard. The address pins or jumper plugs shall control the BIU mode of operation. BIUs shall be capable of being interchanged with no additional programming.

For the terminal facility, contain all field wires within one or two rows of horizontally-mounted Marathon heavy duty terminal blocks. Terminate all field output circuits on an unfused terminal block with a minimum rating of 10 amps. Use mechanical connector lugs rated for copper wire. Angle the lower section of the terminal block out from the back of the cabinet at approximately a 45 degree angle.

Identify all field input/output (I/O) terminals by permanent alphanumeric labels. All labels shall use standard nomenclature per the NEMA TS2 Standard.

All field flash sequence programming at the field terminals shall be able to be accomplished with the use of only a screwdriver.

Wire field terminal blocks to use three positions per vehicle or overlap phase (green, yellow, red).

Wire one RC network in parallel with each flash transfer relay coil.

Permanently label all logic-level, NEMA-controller and MMU input and output terminations on the terminal facility. Identity the function of each terminal position on the cabinet drawings.

Terminal blocks for DC signal interfacing shall have a number 6-32 x 7/32 inch screw as minimum. Functions to be terminated shall be as specified in the listing of Input/ Output Terminals in Section 5 of the NEMA TS2 Standard.

1198-03-78 44 of 59

Conform all terminal facility and cabinet wiring to the WSEC. The green/ walk, yellow, and red/don't walk load switch outputs shall be minimum 16 gauge wire. The MMU (other than AC power), controller I/O, and logic ground shall be minimum 22 gauge wire. All wire colors shall be consistent.

# **B.3.2 Auxiliary Panels**

### **B.3.2.1 Vehicle Detection Interface Panel**

Provide a 32-position interface panel or two 16-position panels. Each interface panel shall allow for the connection of 32 or 16 independent field loops, respectively. The panels shall have barrier strip type terminals using 8-32 screws and be rated for 20 inch pounds of torque.

Provide a ground bus terminal between each loop pair terminal to provide a termination for the loop lead-in cable ground wire. Secure the interface panels to a mounting plate attached to the left interior side wall of the cabinet. Provide a cable consisting of 20 AWG twisted pair wires to enable connection to and from the interface panel to a detector rack. The twisted pair wires shall be color-coded wires. Provide a cable of sufficient length to allow the detector rack to be placed on either shelf.

Identify all termination points by a unique number silk screened on the panel.

# **B.3.2.2 Intersection Lighting**

Provide an intersection lighting control panel as described. The intersection lighting control panel shall consist of an aluminum panel 0.125 inches thick and approximately 5 inches by 10 inches. Determine the actual panel size by the cabinet's mounting rail placement. Attach to the panel a 2 pole-30 amp contactor-120vac coil (Square D #8910DPA32V02 or equal), and a heavy duty six position terminal block (Marathon DJ1606 or equal). Use wire sizes 10AWG for power and load wiring, and 16AWG for control wires. Wire the terminal strip as follows:

- Control coil
  - L1 in
  - L2 in
- Neutral in and control coil
  - L1 out
  - L2 out

Protect each output by a MOV (V150LA20A) wired between the output and neutral. Include a photo control (Intermatic #K4021C or equal). Mount the photo control just above the cabinet door and approximately 12 inches from the right side of the cabinet. Wire the photo control to a 3 position terminal strip using 16AWG wire color coded to match the photo control wiring connected to the intersection lighting control panel.

# **B.3.3 Conductors and Cabling**

All conductors in the cabinet shall be copper 22 AWG or larger. All 14 AWG and smaller wire shall conform to MIL-W-16878/1, Type B, 600V, 19-strand tinned copper. The wire shall have a minimum of 0.010 inches thick PVC insulation without clear nylon jacket and rated to 105 degrees Celsius. All 12 AWG and larger wire shall be UL or NRTL listed THHN/THWN 90 degrees Celsius, 600V, 0.020 inches thick PVC insulation, and clear nylon jacketed.

Provide controller and MMU cables of sufficient length to allow the units to be placed on either cabinet shelf in the operating mode. Connecting cables shall be sleeved in a braided nylon mesh. Exposed tie-wraps and interwoven cables are unacceptable.

Provide the cabinet configuration with enough SDLC RS-485 Port 1 communication cables to allow full capabilities of that cabinet. Each communication cable connector shall be a 15-pin metal shell D subminiature type. The cable shall be a shielded cable suitable for RS-485 communications. Secure all connecting cables and wire runs by mechanical clamps. Stick-on type clamps are not acceptable.

Pre-wire the terminal facility for a Type 16 MMU. All wiring shall be neat in appearance. Stow excess cable behind the terminal facility or below the shelves in order to allow easy access to the terminal facility and cabinet components. All cabinet wiring shall be continuous from its point of origin to its termination point. Butt type connections/splices are not acceptable.

Wire the grounding system in the cabinet into three separate circuits: AC Neutral, Earth Ground, and Logic Ground.

1198-03-78 45 of 59

Optoisolate all pedestrian pushbutton inputs from the field to the controller through the BIU and operate at 12 VAC.

Hook or loop all wire, size 16 AWG or smaller, at solder joints around the eyelet or terminal block post prior to soldering to ensure circuit integrity. Lap joint soldering is not acceptable.

### **B.3.4 Cabinet Switches**

Locate the following switches on a maintenance panel on the inside of the cabinet door:

- Controller On/Off
- · Cabinet Light
- · Stop Time (Three Position)
- Manual Detector Switches (Three Position)

Position	Switch	<u>Label Function</u>
Upper	Stop Time	Place stop time on the controller
Center	Run	Remove the stop time input to the controller
Lower	Normal	Connects the MMU to the controller stop time input

Locate the following switches behind the police access door:

- · Signal/Off
- Flash/Normal
- Hand/ Auto
- Coiled hand control and cable

The above switches shall function as follows:

- Off: Signals Dark
- · Signal: Signals On and operating as follows:
- · Flash: Signals Flash
- Normal: Normal signal operation
- Hand: Signals advance by use of hand control
- Auto: Signal advance by programmed operation.

Provide manual detector switches. Provide a minimum of 16 vehicle detector switches, and four pedestrian detector switches. The switches shall be spring loaded and automatically return to the center position. Wire the vehicle detector switches to detector BIU slot 1. Wire the pedestrian switches to the T&F BIU slot 1. The switches shall operate as follows:

<u>Position</u>	Function Up
Up	Detector Disabled
Center	Center Detector Enabled
Down	Down Detector Called

### **B.4 Power Panel**

#### **B.4.1 Power Panel Design**

The power panel shall consist of a separate module, securely fastened to the interior right side wall of the cabinet. Wire the power panel to provide the necessary power to the cabinet, controller, MMU, cabinet power supply, and all auxiliary equipment. Manufacture the power panel from 0.090-inch, 5052-H32 aluminum. Panel layout shall facilitate field inspection and maintenance accessibility without excessive disassembly or special tools.

Provide a light, tough, transparent, weather-resistant, non-yellowing, thermoplastic cover, rigidly mounted over the full power panel, with access holes for circuit breakers and other equipment, and open on the sides for ventilation.

#### B.4.2 Bus Bar

Provide a minimum 20-position neutral bus bar capable of connecting three #12 AWG wires per position.

1198-03-78 46 of 59

#### **B.4.3 Circuit Breakers**

House in the power panel the following vertically mounted, single pole, 120 volts AC, 60 Hertz, circuit breakers, with the ON position being up:

- One 30-amp signal breaker. This breaker shall supply power for all cabinet functions not powered through one of the other breakers or fuses listed below. This breaker shall feed a signal bus supplied through a solid state bus relay and a radio interference line filter. The bus relay, in all cases, shall be a solid state contactor and shall not be jack mounted. Breakers shall be thermal magnetic type, UL or NRTL listed, with a minimum of 22,000 amp interrupting capacity.
- One 30-amp breaker for streetlighting.
- One 15-amp auxiliary breaker. This breaker shall supply power to the fan and heater.
- One 10-amp breaker. This breaker shall supply power for control equipment: controller, MMU, and cabinet power supply.
- One 20-amp circuit breaker for future use.

Power the cabinet light through the GFI fuse, not a circuit breaker.

# **B.4.4 Radio Interference Suppressor**

Equip each control cabinet with a single radio interference suppressor (RIS) of sufficient ampere rating to handle the load requirements. Install the RIS at the input power point. The RIS shall minimize interference in both the broadcast and the aircraft frequencies and shall provide a maximum attenuation of 50 DB over a frequency range from 200 KHZ to 75 MHZ, when used in connection with normal installations. The RIS shall be hermetically sealed in a substantial metal case filled with a suitable insulating compound. The terminals shall be nickel-plated brass studs of sufficient external length to provide space to connect two #8 AWG wires and shall be so mounted that they cannot be turned in the case. Ungrounded terminals shall be properly insulated from each other and shall maintain a surface leakage distance of not less than 6.35 mm between any exposed current conductor and any other metallic parts. The terminals shall have an insulation factor of 100-200 megohms dependent upon external conditions. The RIS shall be rated at minimum 50 amperes. Design the RIS for operation on 115 VAC +/- 10%, 60HZ, singlephase circuits, and to meet the standards of UL or a NRTL and Radio Manufacturer's Association.

### **B.4.5 Bus Relay**

Provide a normally-open, 60 amp, solid state relay.

#### **B.4.6 Surge Protector**

Install a plug-in type EDCO SHA-1250, or Atlantic/Pacific approved equal, surge protector across the load terminal of the 10-amp circuit breaker. Install a General Electric Varistor, catalog #V130PA20A, at the load terminals of the circuit breaker from the hot line to the grounded current carrying neutral conductor

### **B.4.7 Power Receptacles**

Mount a 120 VAC 20 amp, NEMA 5-20R GFCI convenience outlet at each of these two locations:

- On the interior right side wall above the power panel. The outlet shall be fully operational and fuse protected.
- Near the power panel where it will not interfere with power panel maintenance. This outlet is to be wired by field installation personnel.

# **B.4.8 Suppressors and RC Network**

Provide a suppressor for each 120 VAC circuit that serves an inductive device, such as a fan motor or a mechanical relay, to protect the controller's solid state devices from excessive voltage surges. Such suppressors shall be in addition to the surge protector at the input power point.

Wire one RC network in parallel with each inductive device.

### **B.5 Auxiliary Devices**

# **B.5.1 Load Switches**

Provide 16 solid state load switches conforming to the requirements of section 6.2 of the NEMA TS2 Standard.

# **B.5.2 Flashers**

Provide one solid state flasher conforming to the requirements of section 6.3 of the NEMA TS2 Standard.

1198-03-78 47 of 59

# **B.5.3 Flash Transfer Relays**

Provide four flash transfer relays conforming to the requirements of section 6.4 of the NEMA TS2 Standard.

# **B.5.4 Inductive Loop Detector Units**

Provide inductive loop detector units conforming to the requirements of section 6.5 of the NEMA TS2 Standard for 2-channel, rack mount detector units, type C

# **B.5.5 Cabinet Power Supply**

Provide one cabinet power supply with each cabinet conforming to the requirements of section 5.3.5 of the NEMA TS2 Standard. Provide LED indicators for the 12 VDC, 12 VAC, and 24 VDC outputs. Provide jack plugs on the front panel for access to the +24 VDC for test purposes.

# **B.6 Bus Interface Units (BIU)**

Provide three BIUs conforming to the requirements of section 8 of the NEMA TS2 Standard. Provide two BIUs with the main panel and one BIU with one of the detector racks.

# **B.7 Malfunction Management Unit (MMU)**

Provide one shelf-mountable, 16 channel, solid-state MMU with Ethernet capability. The MMU shall meet the requirements of Section 4 of the NEMA TS2 Standard. The MMU shall be capable of the following:

- · Detecting inputs of Green (Walk), Yellow, or Red (Don't Walk) on the same channel.
- Determining if the field signal input states detected as active or inactive by the MMU correspond with the data provided by the Controller Unit.
- Monitoring and optional external watchdog output from a Controller Unit or other external cabinet device.
- Monitoring an intersection with up to four approaches using the Flashing Yellow Arrow (for protected/permissive left and right turn movements).
- Event logging for the following; AC Line log, Prior/Previous Faults log, and Monitor Reset Log. All log entries shall include a date and time stamp.
- All monitor functions shall be capable of being programmed through the front panel, without the need for computers or special programs cards.
- A built-in Diagnostic Wizard shall be provided that displays detailed diagnostic information regarding the fault being analyzed. This mode shall provide a concise view of the signal states involved in the fault, pinpoint faulty signal inputs, and provide guidance on how the technician should isolate the cause of the malfunction.
- The MMU shall have an LCD display that allows for viewing of log files and field indications, as well as the viewing and setting of date and time and configuration parameters.

### **B.8 Traffic Signal Controller**

The traffic signal controller provided shall be an Econolite ASC/3, compatible with the NEMA TS2 Type 1 specifications.

#### **B.8.1 Firmware**

Provide installed in the controller current, fully operational, controller firmware and software sufficient for the controller to perform all functions shown on the plans, sequence of operation plan sheet, specifications, and signal timing plan for the local intersection. Provide all software licenses.

The firmware and software shall be compatible with and able to fully communicate with:

- All phase sequences used by the city, including flashing yellow for both left and right turns.
- Communications, closed loop, and on-street control software designed for use with the provided controller and provided under separate bid items.
- · Both the controller and the MMU.
- · City PC laptop and desktop computers with Windows XP and Windows 7 operating systems.
- · The supplier's multi-level central operation software programs for potential future Application.

### **B.8.2 Features/Functions**

1198-03-78 48 of 59

#### B.8.2.1 General

Provide shelf-mounted controller units.

Provide intersection controller units with up to 16-phase operation plus 16 programmable overlaps regardless of whether or not preemption, coordination, or other special programming is used.

Provide a four-ring, programmable for both single and dual entry concurrent timing, nine- phase frame or equivalent. Provide volume density timing for eight phases and pedestrian timing for all phases. Provide MUTCD flash capability. All controls shall be according to the NEMA TS2 Standard.

All controller timing parameters shall be fully programmable from the front panel keyboard inputs, and memory storage features shall be non-volatile under power-off conditions for at least thirty days. A security code must be entered before any timing parameters can be changed. The locking, non-locking detection mode and per phase recall shall also be accessible on the front panel.

Provide a data key port on the controller to load and store intersection programming.

Internally buffer all logic circuit inputs to withstand transients and noise, such as might result from normal usage, without damage to any mechanism components.

# **B.8.2.2 Front Panel Display**

Provide a display panel on the front panel consisting of a backlit alphanumeric LCD display. The face of the display shall be scratch, chemical, and solvent resistant. The operator shall access the controller through a menu system. By selecting various menu options, real time operational status or stored parameter tables shall be presented to the operator.

Show on the LCD display, in addition to information required elsewhere:

- The status of each signal phase on.
- The interval status.
- · Phase termination information.
- The presence of vehicular and pedestrian calls for each phase.

# **B.8.2.3 Timing**

The passage timer shall time concurrently with the minimum green timer, such that the duration of the minimum green time is directly adjustable and is independent of the passage time setting.

In the dual-ring application, no more than two phases shall be permitted to time concurrently, and no more than one phase per ring. Provide barrier protection against concurrent timing of two conflicting phases; no phases assigned to one side of the barrier shall be permitted to time concurrently, if a conflict will occur. Service calls on a single entry basis. Both rings shall cross the barrier simultaneously according to the following logic:

- Phases timing concurrently shall terminate simultaneously if both have a gap-out due to excessive time between actuations.
- · Phases timing concurrently shall terminate simultaneously if both have a maximum timeout.
- Phases timing concurrently shall terminate simultaneously if one has a gap-out and the other has a maximum time-out.

In the event that one phase has not achieved a gap-out or maximum time-out, the other gapped-out phase shall be permitted to leave the gapped-out condition and retime an extension when an actuation is received.

Controllers shall not accept any operator input or stored timing parameters that would result in intervals shorter than the following:

- Yellow clearance 3.0 seconds
- Standard minimum walk 4.0 seconds
- Preemption minimum walk = 0.0 seconds
- Minimum pedestrian clearance 6.0 seconds

At the beginning of each of the above intervals, the controller shall check the previously stored data against these minimums. If an operator attempts to load an incorrect timing parameter the controller unit

1198-03-78 49 of 59

shall output a unique error code on the front panel display. As an alternate to minimum timing control a coded keyboard entry security feature may be provided.

# **B.8.2.4 Manual (Police) Control**

If manual control is used, actuation of the manual control shall permit manual advance of the Walk, Pedestrian Clearance, and Green interval terminations only. Manual termination of Yellow or All-Red clearance intervals shall not be permitted.

#### **B.8.2.5 Coordination**

The controller shall be capable of operation in progressive coordination systems and mutual coordination and shall contain, but not be limited to, the following external inputs, with all functions brought out:

Vehicle/Pedestrian Detectors (per phase)
Pedestrian Omit (per phase)

Phase Omit (per phase) Hold (per phase)

Omit Red Clearance (per ring)
Internal Maximum Inhibit (per ring)
Maximum II (per ring)

Red Rest (per ring) Stop Timing (per ring) Force-Off (per ring)

Select Minimum Recall (per controller)
Manual Control (per controller)

Semi-Modes (per controller) External Start (per controller)

### **B.8.2.6 Diagnostic Program**

Provide a diagnostic program prepared by the manufacturer of the controller unit which will demonstrate the proper operation of all of the inputs, outputs, controls and indicators in the controller, and have visual confirmation on the front panel. The diagnostic program shall be resident in each controller. The controller shall continuously run a diagnostic routine in the background to assure unit integrity.

# **B.8.2.7 Message Logging**

Provide user programmable, data logging of local events or alarm events including, but not limited to: Conflict Flash, Remote Flash, Local Flash, Controller Voltage Monitor, Detector Failure, On Line and Data Change. The time and date shall be recorded as a part of the message logged. The logging function shall be resident in the controller unit. The logging function shall be viewed from the front panel LCD display. If the logging function cannot be viewed from the front panel LCD display, it shall be performed by supplemental auxiliary equipment supplied with this specification.

# **B.8.2.8 Closed Loop Operation**

The controller shall be able to be used in a closed loop system using twisted pair copper, single mode fiber, multimode fiber, or wireless radio to connect to compatible equipment.

# **B.8.2.9 RS-232 Interface and Ethernet Port**

Provide a RS-232C interface and connector for interconnecting to a conflict monitor, printer, another like controller unit, or a local personal computer, as well as a remote personal computer through an external modem. A modem is not required to be provided with this specification. Include Ethernet communications capability as a standard feature and provide an Ethernet port. Ports shall be on the front panel of the controller.

# **B.9 Documentation**

# **B.9.1 Cabinet Intersection Wiring Diagram**

For each individual cabinet ordered, within 10 calendar days after receipt of the procurement order, furnish to the city engineer two sets of 22X34-inch detailed printed cabinet intersection wiring diagrams for information only.

1198-03-78 50 of 59

At the time of the cabinet delivery, furnish to the city engineer two sets of printed 22X34-inch cabinet intersection wiring diagrams per cabinet. Printing the 22X34-inch sheet in smaller sizes is not acceptable. Leave a third drawing in the under-shelf drawer in the signal cabinet. After cabinet acceptance is complete, if any cabinet wiring changes were made, revise the cabinet wiring diagrams, leave one drawing in the under-shelf drawer in the signal cabinet, and furnish to the city engineer two sets of as-built printed cabinet wiring diagrams per cabinet. If no changes were made from time of cabinet delivery, notify the city engineer in writing.

# **B.910.2 MMU and Controller Programming**

At the time of cabinet delivery, furnish to the city engineer two printed copies of the MMU programming and two copies of the signal timing in the traffic signal controller. Leave a third copy in the under-shelf drawer in the signal cabinet. After cabinet acceptance is complete, if any MMU or controller timing changes were made, revise the documents, leave one copy in the under-shelf drawer in the signal cabinet, and furnish to the city engineer two copies per cabinet. If no changes were made from time of cabinet delivery, notify the city engineer in writing.

### **B.9.3 Manuals**

At the time of the cabinet delivery, furnish to the city engineer one set of installation, operations, and maintenance manuals per cabinet including each type of equipment in the cabinet. The manuals shall as a minimum include the following information:

- · Table of contents
- Operating procedure
- Step-by-step maintenance and trouble-shooting information for the entire assembly Schematic diagrams.
- · Pictorial diagrams of parts locations Itemized parts lists with parts numbers.
- Theory of operation
- · Maintenance checklists

The itemized parts lists shall include the manufacturer's name and parts number for all components (such as IC, diodes, switches, relays, etc.) used. The list shall include cross references to parts numbers of other manufacturers who make the same replacement parts.

For each of the traffic signal controller and MMU, in addition to the above manual requirements, furnish one reference manual for the processor and components proposed to perform the controller and MMU functions. Include a complete set of schematics for the controller, MMU, and any auxiliary circuit boards either in the reference manual or in a separate volume. In addition, furnish a written narrative describing the controller and MMU operation and front panel configuration, and a conceptual flow chart illustrating the control logic for comparison with these specifications. The narrative shall include a discussion of any limitation or exceptions to the performance described in these specifications, and a discussion of any control capabilities provided in addition to that required in these specifications.

# **B.11 Cabinet Delivery**

Provide the traffic signal specifications and plans, including the sequence of operation, to the cabinet vendor. The vendor shall determine the required cabinet equipment and assembly requirements from the plans and specifications and provide the city engineer a list of procurement items. The city engineer will approve or request resubmittal of the procurement items list prior to the cabinet being built.

Provide the list of procurement items to the city engineer a minimum of 30 days before the cabinet is scheduled to be installed in the field. The vendor is responsible for coordinating with the project construction contractor to determine the scheduled cabinet installation date. Cabinets shall be completed, delivered, and accepted within 50 calendar days after the city engineer approves the procurement item list

If the city makes a modification to any cabinet order before the entire cabinet is completely built in the vendor's shop, the delivery time does not change. If the city accepts a vendor requested cabinet order or other modification at any time, the delivery time does not change. All cabinet modifications will be made without additional cost to the city, except if an additional equipment item is added at the city's request and the additional item is not to remedy any contractor or vendor error.

Deliver the fully wired and equipped cabinets to the intersection where the cabinet will be installed, or other site as designated by the city or the project construction contractor. The contractor is responsible for arranging the unloading of the cabinet.

1198-03-78 51 of 59

When the city exercises its right to test a cabinet as described in the Acceptance Testing section of this specification, deliver the cabinet to the location specified by the city engineer. When the testing is complete, pick up the cabinet from the shop within three business days of notification.

The contractor is notified that delivery times and schedules may be changed or delayed at any time for any reason. The contractor may be required to store completed cabinets at their facility for extended periods of time.

# **B.12 Acceptance Testing**

Complete on-site traffic signal acceptance testing in the presence of the city. The acceptance testing will occur after the signal cabinet is fully installed at the project intersection and before the traffic signal is turned on. The construction contractor and the city will determine the time for the acceptance testing. In addition to the cabinet as specified in this specification, add-on accessory items, traffic signal interconnect, system communication, and closed loop system operation are included in the acceptance testing.

Provide an IMSA certified Traffic Signal Bench Technician, Level II or an IMSA certified Traffic Signal Field Technician, Level II with a minimum of three years' experience in construction and operation of traffic signal cabinets similar to the cabinets specified in this specification. Alternatively, provide a technician or electrician with a minimum of three years' experience in construction and operation of traffic signal cabinets similar to the cabinets specified in this specification. The technician or electrician shall be on-site during the entire acceptance testing and shall be capable and equipped to make in-field revisions/ repairs to the signal cabinet and controller to conform to this specification.

Upon successful completion of the acceptance testing as determined by the city, a 30-day conditional acceptance of the signal cabinet will be provided to the contractor. Should the cabinet within the 30-day conditional acceptance period fail to perform in any way as determined by the city, the contractor shall repair the cabinet to bring it into conformance with this specification and the acceptance testing shall be repeated. Repair times shall conform to the warranty service response times in this specification. The acceptance testing shall be repeated. Upon successful completion of the retesting, a new 30-day conditional acceptance period shall begin. After the signal cabinet runs 30 days without failure, the cabinet will be fully accepted by the city. The contractor will be allowed up to two 30-day conditional acceptance periods. If the cabinet fails during the second 30-day period, an entirely new cabinet shall be furnished and installed in the field by the contractor at no cost to the city and a new acceptance testing procedure shall begin. Cabinet replacement times shall conform to the warranty service response times in this specification. The original cabinet becomes the property of the contractor.

The city reserves the right to perform its own tests on the traffic signal cabinet at any time using the city's control equipment. Should an individual traffic signal cabinet be found to not meet the requirements of these specifications, the contractor shall pick up the traffic signal cabinet from the city or from the field, perform at their shop repairs / revisions as necessary to bring the traffic signal cabinet into conformance with these specifications, and deliver the repaired / revised traffic signal cabinet back to the designated location, all at no additional cost to the city.

### **B.13 Certification**

Provide a written certification with the cabinet delivery that the equipment meets the requirements of the plans and specifications and will fully run the sequence of operation and the signal timing, including closed loop system operation if applicable. The certification shall be on the contractor's company letterhead, shall be addressed to both the department and the construction contractor, and shall be signed by a company officer authorized to legally obligate the company.

# **B.14 Warranty**

The contractor shall certify that the equipment meets the required specification and shall supply a complete catalog description. The following documents shall also be provided:

- A warranty statement which stipulates that equipment to be supplied shall be warranted by the manufacturer for two years from the date of purchase.
- · Operations manuals
- Maintenance manuals
- Schematic diagrams
- Component and equipment locations within the cabinet.
- Controller Operation

1198-03-78 52 of 59

Consistent with customary trade practices, the manufacturer shall furnish a warranty for all electrical or mechanical equipment described herein. The contractor shall turn such warranty over to the owner for potential dealing with the guarantor.

During the installation and testing of the controller, the contractor shall provide, at his own expense, a competent representative to oversee, direct and manage the installation and testing of the controller. In the final stages of the installation and testing, the manufacturer's representative shall be available at the job site for consultation until such time as the controller operation is tested and accepted.

#### C Construction

Perform work according to standard spec 651.3, 652.3, 653.3, 654.3, 655.3, 656.3, 657.3, 658.3 and 659.3 except as specified below.

All components shall be assembled, mounted, and connected in the traffic signal control cabinet per the plans. The controller shall be firmly mounted to the concrete pad. The assembled controller and cabinet shall be adjusted, tested, and demonstrated to be operating properly before acceptance.

Request a signal inspection of the completed signal installation to the engineer at least five working days prior to the time of the requested inspection. City of Superior personnel will perform the inspection.

### **D** Measurement

The department will measure Furnish and Install Traffic Signal Controller and Cabinet USH 2 & 39<sup>th</sup> Ave as a single lump sum unit of work, acceptably completed.

### **E** Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER

DESCRIPTION

UNIT

SPV.0105.01

Traffic Signal Controller and Cabinet USH 2 & 39<sup>th</sup> Ave

LS

Payment is full compensation for furnishing and installing the traffic signal controller and cabinet, testing and set up, and making the signal system fully operational.

# 46. Furnish and Install Emergency Vehicle Preemption System USH 2 & 39<sup>th</sup> Ave, Item SPV.0105.02.

# **A Description**

This special provision includes furnishing and installing an emergency vehicle preemption (EVP) system for the permanent traffic signal installation as shown on the plans.

### **B** Materials

The EVP Receivers shall be a GTT Opticom Model #711, or approved equal.

The EVP Processor shall be a GTT Opticom Model #764 Phase Selector, or approved equal.

# **C** Construction

Install equipment according to manufacturer's instructions to provide a fully operational system. Make connections in the signal cabinet and program the signal controller according to the preemption sequence in the plans.

Coordinate with the City of Superior to arrange testing of each receiver and the overall preemption system using city emergency vehicles under realistic conditions. Adjust detectors and other system equipment to provide the specified detection ability.

### **D** Measurement

The department will measure Furnish and Install Emergency Vehicle Preemption System USH 2 & 39<sup>th</sup> Ave as a single lump sum unit of work, acceptably completed.

### **E** Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBERDESCRIPTIONUNITSPV.0105.02Furnish and Install Emergency Vehicle Preemption System USH 2 & 39th AveLS

1198-03-78 53 of 59

Payment is full compensation for furnishing and installing the emergency vehicle preemption system, testing and set up, and making the EVP system fully operational.

# 47. Vehicular Video Detection System USH 2 & 39th Ave, Item SPV.0105.03.

# A Description

This work shall consist of furnishing, installing and placing into operation a vehicular video detection system (VVDS) as shown on the plans, and as directed by the engineer in the field. The VVDS shall be a four-camera system.

# **B** Materials

This specification sets forth the minimum requirements for a system that detects vehicles on a roadway by processing video images and providing detection outputs to a traffic signal controller. The materials shall also include all brackets, mounting hardware, cable, terminations, interface panels, detector racks, processors, and all other incidentals for the installation of the video detection equipment. This equipment shall meet the NEMA environmental, power and surge ratings as set forth in NEMA TS2 specifications.

All video detection equipment, components, and terminations supplied under this item shall be fully compatible with Eagle EPAC 300 M51 and Econolite ASC/3 traffic signal controllers. The Vehicular Video Detection System shall be able to transmit and receive data by means of a hybrid single mode/multimode fiber optic cable. The system architecture shall fully support Ethernet networking of system components. All required interface equipment needed for transmitting and receiving data and video shall be provided for with the VVDS.

Some of the video cameras may be required to be mounted on a riser attached to a trombone or monotube arm. This item includes furnishing and installing risers as necessary and indicated on the plans.

The Video Vehicle Detection System shall be the Autoscope Vision system including all associated hardware and software to create a fully functioning vehicle detection system.

### **B.1 Hardware**

The machine vision system hardware shall consist of three components: 1) a color, zoom, Machine Vision Processor (MVP) sensor 2) a modular cabinet interface unit 3) a communication interface panel. Additionally, an optional personal computer (PC) shall host the server and client applications that are used to program and monitor the system components. The real-time performance shall be observed by viewing the video output from the sensor with overlaid flashing detectors to indicate the current detection state (on/off). The MVP sensor shall optionally store cumulative traffic statistics internally in non-volatile memory for later retrieval and analysis.

The MVP shall communicate to the modular cabinet interface unit via the communications interface panel and the software applications using the industry standard TCP/IP network protocol. The MVP shall have a built-in, Ethernet-ready, Internet Protocol (IP) address and shall be addressable with no plug in devices or converters required. The MVP shall provide standard MPEG-4 streaming digital video.

The communication interface panel shall provide four sets of three electrical terminations for three wire power cables for up to eight MVP sensors that may be mounted on a pole or mast arm with a traffic signal cabinet or junction box. The communications interface panel shall provide single-point Ethernet connectivity via RJ45 connector for communication to and between the modular cabinet interface module and the MVP sensors.

# **B.2 Machine Vision Processor Sensor**

The MVP sensor shall be an integrated imaging color CCD array with zoom lens optics, high-speed, dualcore image processing hardware bundled into a sealed enclosure. The CCD array shall be directly controlled by the dual-core processor, thus providing high-quality video for detection that has virtually no noise to degrade detection performance. It shall be possible to zoom the lens as required for setup and operation. It shall provide JPEG video compression as well as standard MPEG-4 digital streaming video with flashing detector overlay. The MVP shall provide direct real-time iris and shutter speed control. The MVP image sensor shall be equipped with an integrated 22x zoom lens that can be changed using either configuration computer software. The digital streaming video output and all data communications shall be transmitted over the three-wire power cable.

1198-03-78 54 of 59

#### **B.3 Modular Cabinet Interface Unit**

The modular cabinet interface unit shall provide the hardware and software means for up to 8 MVP sensors to communicate real-time detection states and alarms to a local traffic signal controller. It shall comply with the electrical and protocol specifications of the detector rack standards. The card shall have 1500 Vrms isolation between rack logic ground and street wiring. The modular cabinet interface unit shall be a simple interface card that plugs directly into a 170 input file rack or a NEMA type C or D detector rack. The modular cabinet interface unit shall occupy only 2 slots of the detector rack. The modular cabinet interface unit shall accept up to 16 phase inputs and shall provide up to 24 detector outputs.

#### **B.4 Communications Interface Panel**

The communications interface panel shall support up to eight MVPs. The communications interface panel shall accept 110/220 VAC, 50/60 Hz power and provide predefined wire termination blocks for MVP power connections, a Broadband-over-Power-Line (BPL) transceiver to support up to 10MB/s interdevice communications, electrical surge protectors to isolate the modular cabinet interface unit and MVP sensors, and an interface connector to cable directly to the modular cabinet interface unit.

The interface panel shall provide power for up to eight MVP sensors, taking local line voltage 110/220 VAC, 50/60 Hz and producing 110/220 VAC, 50/60 Hz, at about 30 watts to each MVP sensor. Two ½-amp SLO-BLO fuses shall protect the communications interface panel.

### **B.5 Functional Requirements**

The vision sensor shall be able to be programmed with a variety of detector types that perform specific functions selectable by software. Detector types shall include stopline detectors capable of providing presence of moving vehicle detection based upon phase status, presence detectors, directional presence and input detectors. Additionally, phase green or red shall be displayed.

The unit shall monitor video contrast and apply video-loss timing parameters to the output by implementing minimum, maximum, or user defined fixed time recall for the assigned phase(s). The detector shall be capable of having Boolean logic applied to multiple detectors or a minimum number of detectors out of a total present, prior to placing a call.

#### **B.6 Minimum Detector Requirements**

Minimum detector requirements shall include the following:

- Count detection provide bi-directional vehicle counts, occupancy, and headway, and provide means to output these traffic volume statistics.
- Speed and classification detection define vehicle by speed, classification and length, with a minimum of 3 different categories for each.
- Presence detection indicate presence of a vehicle, stopped vehicle, or a vehicle traveling in the wrong direction.
- · Detector function combination monitor outputs of multiple detectors via Boolean logic functions.
- Label display provide information on the video output and pass input information to other detectors.
- Detector Station collect and report traffic data gathered over specified time intervals including 1,
   5, 10, 15, 30, 60-minute intervals and per cycle.
- Incident detection monitor traffic parameters for conditions that indicate an incident has
  occurred, such as an accident or a stalled vehicle that results in a sudden reduction in roadway
  capacity or throughput.
- Schedulers define plans that can be used by other detectors to specify different parameters for each time-of-day plan.
- Contrast Loss detection monitor the quality of the video image that the vision sensor is processing.
- Speed Alarm generate alarm outputs based on user-defined algorithms based on vehicle speed.

1198-03-78 55 of 59

#### **B.7 Power**

The vision sensor shall operate on 110/220 VAC 50/60 Hz at a maximum of 25 watts. The camera and processor electronics shall consume a maximum of 10 watts. The remaining 15 watts shall support an enclosure heater.

# **B.8 Sensor Operations Log**

The vision sensor shall maintain a non-volatile operations log, which minimally contains:

- Revision numbers for the current vision sensor hardware and software components in operation.
- · Title and comments for the detector configuration.
- Date and time the last detector configuration was downloaded to the vision sensor. Date and time the operation log was last cleared.
- Date and time communications were opened or closed with the vision sensor. Date and time of last power up.
- Time stamped, self-diagnosed hardware and software errors that shall aid in system maintenance and troubleshooting.

### **B.9 Sensor Vehicle Detection Performance**

The real time detection performance of the vision sensor shall be optimized by following the guidelines for the traffic application including vision sensor mounting location; the number of traffic lanes to monitor; the sizing, placement, and orientation of vehicle detectors; traffic approaching and/or departing from the sensor's field of view; and minimizing the effects of lane changing maneuvers.

### **B.10 Detection Zone Placement**

The video detection system shall provide flexible detection zone placement anywhere and at any orientation within the field of view of the vision sensor. Preferred detector configurations shall be detection zones placed across lanes of traffic for optimal count accuracy, detection zones placed parallel to lanes of traffic for optimal presence detection accuracy of moving or stopped vehicles. A single detection zone shall be able to replace one or more conventional detector loops connected in series. Detection zones shall be able to be overlapped for optimal road coverage. In addition, selective groups of detectors shall be able to be logically combined into a single output by using optional delay and extend timing and signal state information. Optimal detection shall be achieved when the vision sensor placement provides an unobstructed view of each traffic lane where vehicle detection is required.

# **B.11 Detection Zone Programming**

Placement of detection zones shall be by means of a PC with a Windows operating system, a keyboard, and a mouse. The PC monitor shall be able to show the detection zones superimposed on images of traffic scenes.

The detection zones shall be created by using a mouse to draw detection zones on the PC monitor. Using the mouse and keyboard it shall be possible to place, size, and orient detection zones to provide optimal road coverage for vehicle detection. It shall be possible to download detector configurations from the PC to the MVP sensor and cabinet interface module, to retrieve the detector configuration that is currently running in the MVP sensor, and to back up detector configurations by saving them to the PC fixed disks or other removable storage media.

The supervisor computer's mouse and keyboard shall be used to edit previously defined detector configurations to permit adjustment of the detection zone size and placement, to add detectors for additional traffic applications, or to reprogram the MVP sensor for different traffic applications or changes in installation site geometry or traffic rerouting.

# **B.12 Optimal Detection**

The video detection system shall provide optimal detection of vehicle passage and presence when the vision sensor is mounted 30 feet or higher above the roadway, the image sensor is adjacent to the desired coverage area and the distance to the farthest detection zone locations is not greater than ten times the mounting height of the vision sensor.

The vision sensor shall be able to view either approaching or departing traffic or both in the same field of view. The vision sensor, when placed at a mounting height that minimizes vehicle image occlusion and equipped with a lens to match the width of the road shall be able to monitor a minimum of six traffic lanes simultaneously.

1198-03-78 56 of 59

#### **B.13 Detection Zone Operations**

The vision sensor's real-time detection operation shall be verifiable through the following means:

View the video output of the sensor with any standard video display device (monitor).

The video output of the vision sensor (differential twisted pair) shall be capable of selectively transmitting:

- Camera video only.
- Analog video overlaid with the current real-time detection state of each detector.
- Camera video with overlaid, scaled crosshairs that are used for aiming the sensor (during installation).

Individual detectors shall have the option of being hidden.

Electrically monitor assigned contact closure pinouts from a detector port master such as a detector rack interface card. Each pin of an interface card shall have one associated LED output to reflect its output state.

View the associated output LED state on the detector port master:

- · An LED shall be ON when its assigned detector output or signal controller phase input is on.
- An LED shall be OFF when its assigned detector or signal controller input is off.

# **B.14 Count Detection Performance**

Using a vision sensor installed within the optimal viewing specifications described above for count station traffic applications the system shall be able to accurately count vehicles with at least 96% accuracy under normal operating conditions (day and night) and at least 93% accuracy under adverse conditions. Adverse conditions are combinations of weather and lighting conditions that result from shadows, fog, rain, snow, etc. The data shall be optionally stored internally in non-volatile memory for later retrieval and analysis.

#### **B.15 Demand Presence Detection Performance**

Using a vision sensor installed within the optimal viewing specifications described above for intersection control applications the system shall be able to accurately provide demand presence detection. The demand presence accuracy shall be based on the ability to enable a protected turning movement on an intersection stop line, when a demand exists. The probability of not detecting a vehicle for demand presence shall be less than 1%error under all operating conditions. In the presence of adverse conditions, the vision sensor shall minimize extraneous (false) protected movement calls to less than 7%.

### **B.16 Speed Detection Performance**

The vision sensor shall accurately measure average (arithmetic mean) speed of multiple vehicles with more than 98% accuracy under all operating conditions for approaching and departing traffic. The average speed measurement shall include more than ten vehicles in the sample to ensure statistical significance. Optimal speed detection performance requires the sensor location to follow the specifications described above for count station traffic applications with the exception that the sensor must be higher than 40 feet. The vision sensor shall accurately measure individual vehicle speeds with more than 95% accuracy under all operating conditions for vehicles approaching the sensor (viewing the rear end of the vehicles). These specifications shall apply to vehicles that travel through both the count and speed detector pair and shall not include partial detection situations created by lane changing maneuvers.

#### C Construction

The Vehicular Video Detection System shall be installed by supplier factory-certified installers and as recommended by the supplier and documented in installation materials provided by the supplier.

The camera shall be mounted at the end of the luminaire arm. The cable shall be secured to the luminaire arms with a maximum of 3 feet between secured points. The cable shall be fed through the cap of the luminaire pole and sealed. Slack shall be provided in the cable at the camera and at the pole sufficient for drip loops.

#### C.1 Sensor Electrical

The video output of the vision sensor shall be isolated from earth ground. All video connections from the sensor to the interface panel shall also be isolated from earth ground. The video output communication,

1198-03-78 57 of 59

and power stages of the sensor shall include transient protection to prevent damage to the sensor due to voltage transients occurring on the cable leading from the vision sensor to other field terminations. Connections for video communications and power shall be made to the image sensor using a single 18-pin circular metal shell connector (Bendix PT07C-14-18P or equivalent). The mating cable shall use a right angle shell. The vision sensor shall have passed requirements for and received the CE mark. The power to the sensor shall be fused in the controller cabinet. Cable used between the vision sensor and the traffic control cabinet interface shall be a continuous unbroken run. This cable shall follow all local electrical codes and be suitable for installation in conduit or overhead with appropriate span wire.

# **C.2 Auxilliary Equipment**

The system shall be supplied with a color 10-inch monitor to display a camera field of view with detection areas overlaid. This monitor shall include sufficient cable and terminals to either be used in the controller cabinet or from within the engineer or technician's vehicle. The input to the monitor shall be selectable from any of the cameras in the system via a quad video processor. All camera field-of-view displays shall also be viewable in real time with the use of a laptop computer connected to the video detection system.

# **C.3 Training and Support**

The supplier of the video detection system shall provide two days of training to maintenance and engineering personnel in the operation, setup, and maintenance of the video detection system.

The supplier shall maintain an ongoing program of technical support for the video detection system. This technical support shall be available via telephone, or via personnel sent to the installation site upon placement of an acceptable order at the supplier's then current pricing and terms of sale for on-site technical support services.

The supplier shall provide a two-year warranty on the video detection system from the date of installation. During the warranty period, technical support shall be available from the supplier via telephone within four hours of the time a call is made by a user, and this support shall be available from factory-certified personnel or factory-certified installers. Updates to the video detection system software shall be available from the supplier without charge.

#### **D** Measurement

The department will measure Vehicular Video Detection System USH 2 & 39<sup>th</sup> Ave as a single lump sum unit of work, acceptably completed.

# **E** Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER

DESCRIPTION

UNIT

SPV.0105.03

Vehicular Video Detection System USH 2 & 39<sup>th</sup> Ave

LS

Payment is full compensation for furnishing and installing the vehicular video detection system, testing and set up, and making the detection system fully operational.

# 48. Material Transfer Vehicle, Project 1198-03-78, Item SPV.0105.04.

# **A Description**

This special provision describes furnishing Material Transfer Vehicle (MTV) and an operator for use on this project during HMA upper layer paving operations, as shown in the plans or as directed by the engineer, and as hereinafter provided.

#### **B** Materials

The MTV shall be self-propelled, remix and maintain constant temperature, and continually feed the paver hopper. The storage capacity shall be adequate to provide continuous forward movement of the paver. The paver speed shall be coordinated to match the delivery of material and capacity of the MTV to limit stopping of the paver.

# **C** Construction

An operator shall remain with the vehicle at all times during moving operations and the paver's hopper shall remain full at all times to avoid segregation of coarse aggregates. No placement of HMA upper layer pavement shall be allowed without the use of the MTV.

1198-03-78 58 of 59

#### **D** Measurement

The department will measure Material Transfer Vehicle by a single lump sum, acceptably completed.

# **E** Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER **DESCRIPTION UNIT** LS

SPV.0105.04. Material Transfer Vehicle, Project 1198-03-78

Payment is full compensation for deploying the equipment and its operator.

#### 49. Pigmented Surface Sealer Reseal, Item SPV.0180.01.

#### **A Description**

This special provision describes resealing existing parapets on structures with protective surface sealer.

# **B** Materials

Furnish a gray commercial pigmented surface sealer selected from the department's approved products list.

#### **C** Construction

Apply pigmented surface sealer to the inside and top faces of parapets, including parapets on abutment wings if present. Use gray sealer unless the contract specifies a different color. Do not seal surfaces where the contract requires staining or other treatment.

Ensure that the concrete is surface-dry for a minimum of one day before application. Delay application if rain is expected or protect from rain for up to 12 hours after application.

Ensure that the concrete is clean. Air blast immediately before applying the pigmented surface sealer to remove all dust or loose particles. Also ensure that application equipment is clean and functioning properly.

Use the manufacturer's recommended methods. Apply at the rate the manufacturer recommends unless that rate causes running.

Do not open the bridge to service until areas are dry enough without causing damage to the treatment.

#### **D** Measurement

The department will measure Pigmented Surface Sealer Reseal by the square yard, acceptably completed.

# **E** Payment

The department will pay for measured quantities at the contract unit price under the following bid item: ITEM NUMBER DESCRIPTION UNIT SPV.0180.01 Pigmented Surface Sealer Reseal SY

Payment is full compensation for resealing, including surface preparation and cleaning.

59 of 59 1198-03-78

# ADDITIONAL SPECIAL PROVISION 1 (ASP 1) FOR TRANSPORTATION ALLIANCE FOR NEW SOLUTIONS (TrANS) PROGRAM EMPLOYMENT PLACEMENTS AND APPRENTICESHIPS

The Safe, Accountable, Flexible, Efficient Transportation Equity Act: A Legacy for Users (SAFETEA-LU), Section 5204(e) – Surface Transportation Workforce Development Training and Education, provides for 100 percent Federal funding if the core program funds are used for training, education, or workforce development purposes, including "pipeline" activities. The core programs includes: Congestion Mitigation and Air Quality Improvement (CMAQ) Program, Highway Bridge Program (HBP), Interstate Maintenance (IM), National Highway System (NHS), and Surface Transportation Program (STP). These workforce development activities cover surface transportation workers, including OJT/SS programs for women and minorities as authorized in 23 U.S.C. §140(b).

*TrANS* is an employment program originally established in 1995 in Southeastern Wisconsin. Currently TrANS has expanded to include TrANS program locations to serve contractors in Southeast (Milwaukee and surrounding counties), Southcentral (Dane County and surrounding counties including Rock County), and most Northeastern Wisconsin counties from locations in Keshena, Rhinelander and surrounding far Northern areas. TrANS attempts to meet contractor's needs in other geographic locations as possible. It is an industry driven plan of services to address the outreach, preparation, placement and retention of women, minorities and non-minorities as laborers and apprentices in the highway skilled trades. These candidate preparation and contractor coordination services are provided by community based organizations. For a list of the TrANS Coordinators contact the Disadvantaged Business Enterprise Office at (414) 438-4583 in Milwaukee or (608) 266-6961 in Madison. These services are provided to you at no cost.

#### I. BASIC CONCEPTS

Training reimbursements to employing contractors for new placements, rehires or promotions to apprentice of TrANS Program graduates will be made as follows:

- 1) On-the-Job Training, Item ASP.1T0G, ASP 1 Graduate. At the rate of \$5.00 per hour on federal aid projects when TrANS graduates are initially hired, or seasonally rehired, as unskilled laborers or the equivalent.
  - <u>Eligibility and Duration:</u> To the employing contractor, for up to 2000 hours from the point of initial hire as a TrANS program placement.
  - <u>Contract Goal:</u> To maintain the intent of the Equal Employment Opportunity program, it is a goal that <u>3</u> (number) TrANS Graduate(s) be utilized on this contract.
- 2) On-the-Job Training, Item ASP.1T0A, ASP 1 Apprentice. At the rate of \$5.00 per hour on federal aid projects at the point when an employee who came out of the TrANS Program is subsequently entered into an apprenticeship contract in an underutilized skilled trade (this will include the Skilled Laborer Apprenticeship when that standard is implemented).

<u>Eligibility and Duration:</u> To the employing contractor, for the length of time the TrANS graduate is in apprentice status.

<u>Contract Goal:</u> To maintain the intent of the Equal Employment Opportunity program, it is a goal that <u>3</u> (number) TrANS Apprentice(s) be utilized on this contract.

- The maximum duration of reimbursement is two years as a TrANS graduate plus time in apprentice status.
- 4) If a TrANS program is not available in the contractor's area and another training program is utilized, payment of On-the-Job Training hours may be approved by the Wisconsin Department of Transportation (WisDOT) if the training program meets the established acceptance criteria. Only On-the-Job Training Hours accumulated after WisDOT approval will be reimbursed as specified under Items ASP.1T0G and ASP.1T0A. For more information, contact the Disadvantaged Business Enterprise Office at the phone numbers listed above.
- 5) WisDOT reserves the right to deny payments under items ASP.1T0G and ASP.1T0A if the contractor either fails to provide training or there is evidence of a lack of good faith in meeting the requirements of this training special provision.

#### II. RATIONALE AND SPECIAL NOTE

The \$5.00 per hour now being paid for TrANS placements is intended to cover the duration of two years to allow for reaching entry-level laborer status. An additional incentive, the \$5.00 rate, would promote movement into the underutilized skilled trades' apprenticeships and applies until the individual completes their apprenticeship. These incentives benefit TrANS candidates by giving them a better opportunity to enter a skilled trade; benefits contractors who will be assisted in meeting their EEO profiles and goals; and benefits the public who will see the program reinforce larger public-private employment reform in Wisconsin. The pool of TrANS graduates was created for the purpose of addressing underutilization in the skilled trades, an objective that is further reinforced by a parallel retention pilot program, known as the Companywide Reporting. Whether or not reimbursement is involved, the WisDOT reassures contractors who are in the Companywide Program that TrANS placements still contribute toward fulfilling the new hire goal of 50% women and minorities. Based on data administered by United States Department of Labor (US DOL), the highway skilled trades remain underutilized for women statewide (less than 6.9%); and for minorities in all counties (% varies by county).

<u>NOTE</u>: Unless using other advancement strategies, contractors are encouraged to use some or all of this monetary incentive to offset the cut in hourly wages an individual may incur when entering an apprenticeship if the full general laborer hourly rate has been previously paid. No special accounting measures are required.

#### III. IMPLEMENTATION

The implementation of ASP 1 is intended to cover only the amount of time it takes for underutilization to be resolved across the trades. This will be measured annually at the county and/or state levels using data administered by WisDWD in relation to goals set by the USDOL-

OFCCP. With appropriate state and federal approvals, we may also do some measurement at the company level.

It is the contractor's responsibility to note on their Certified Payrolls if their employee is a TrANS graduate or a TrANS apprentice. The District EEO Coordinators utilize the information on the Certified Payrolls to track the hours accumulated by TrANS Graduates and TrANS apprentices on WisDOT contracts. Payment under this ASP 1 is made based on the hours recorded off of the Certified Payrolls. Tracking may eventually include improved linkages with the WisDWD apprentice database, information from company and committee level sources.

TrANS is nondiscriminatory by regulation, and is a tool for optional use by contractors to address the underutilization of women and minorities as laborers and apprentices in our industry's skilled trades.

#### IV. TRANS TRAINING

As part of the contractor's equal employment opportunity affirmative action program, training shall be provided to employees enrolled in apprenticeship and on-the-job training programs as follows:

The contractor shall provide on-the-job training aimed at developing full journey workers in the type of trade or job classifications involved. In the event the contractor subcontracts a portion of the contract work, the contractor shall determine how many, if any, of the trainees are to be trained by the subcontractor provided, however, that the contractor shall retain the primary responsibility for meeting the training requirements imposed by this special provision. The contractor shall also insure that this training special provision is made applicable to such subcontract.

Training and upgrading of minorities and women toward journey workers status is a primary objective of this training special provision. Accordingly, the contractor shall make every effort to enroll minority trainees and women (e.g., by conducting systematic and direct recruitment through public and private sources likely to yield minority trainees and women trainees); to the extent such persons are available within a reasonable area of recruitment. The contractor will be given an opportunity and will be responsible for demonstrating the steps that they have taken in pursuance thereof, prior to determination as to whether the contractor is in compliance with this training special provision. This training commitment is not intended, and shall not be used, to discriminate against any applicant for training, whether a member of a minority group or not.

No employee shall be employed as a trainee in any classification in which they have successfully completed a training course leading to journey workers status or in which they have been employed as a journey worker. The contractor should satisfy this requirement by including appropriate questions in the employee application or by other suitable means. Regardless of the method used, the contractor's records should document the findings in each case.

#### V. APPRENTICESHIP TRAINING

The Federal Highway Administration's (FHWA) policy is to require full use of all available training and skill improvement opportunities to assure increased participation of minority groups, disadvantaged persons and women in all phases of the highway construction industry. The FHWA On-the-Job Training (OJT) Program requires the State transportation agencies (STAs) to establish apprenticeships and training programs targeted to move women, minorities, and disadvantaged individuals into journey-level positions to ensure that a competent workforce is available to meet highway construction hiring needs, and to address the historical under-representation of members of these groups in highway construction skilled crafts.

The OJT Supportive Services (OJT/SS) Program was established in Title 23 Code of Federal Regulations (CFR), Part 230) to supplement the OJT program and support STA training programs by providing services to highway construction contractors and assistance to highway construction apprentices and trainees. The primary objectives of OJT/SS are:

- (1) To increase the overall effectiveness of the State highway agencies' approved training programs.
- (2) To seek other ways to increase the training opportunities for women, minorities, and disadvantaged individuals.

The STAs are responsible for establishing procedures, subject to the availability of Surface Transportation and Bridge Funds under 23 U.S.C. §140(b) (Nondiscrimination), for the provision of supportive services with respect to training programs approved under 23 CFR, Part 230(a) (Equal Employment Opportunity on Federal and Federal-aid Construction Contracts – including Supportive Services).

The contractor and subcontractor shall maintain records to demonstrate compliance with these apprenticeship requirements. Reasonable exemptions and modifications to and from any or all of these requirements will be determined by the Wisconsin Department of Transportation-Civil Rights Office. A request for an exemption or modification, with justification, shall be made in writing, addressed to WisDOT Civil Rights Office, 4802 Sheboygan Avenue, P.O. Box 7965, Rm. 451, Madison, WI 53707.

#### **ADDITIONAL SPECIAL PROVISION 3**

#### DISADVANTAGED BUSINESS ENTERPRISE (DBE) PROGRAM IMPLEMENTATION

#### **Authority**

Wisconsin Department of Transportation (WisDOT) is a recipient of funds from the US Department of Transportation's Federal Highway Administration. The DBE program is a federal program applicable on all contracts administered by WisDOT that include federal-aid highway funds. The authority for the DBE program is the Transportation Bill as approved by Congress periodically. DBE program guidance and requirements are outlined in the Code of Federal Regulations at 49 CFR Part 26. This contract is subject to DBE provisions because it is financed with federal-aid-highway funds. Additionally, this contract is subject to the *State of Wisconsin Standard Specifications for Highway and Structure Construction* and all applicable contract documents.

#### Requirements

Pursuant to the federal DBE program regulation at 49 CFR Part 26, a contractor's failure to comply with any provision of the DBE program regulatory provisions will be considered a material breach of contract. This is nonnegotiable.

If a contractor fails to carry out the DBE program requirements and/or the Required Contract Provisions for Federal Aid Contracts (FHWA 1273) referenced in this document, sanctions will be assessed depending upon the facts, reasoning, severity, and remedial efforts of the contractor that may include: termination of contract, withholding payment, assessment of monetary sanctions, and/or suspension/debarment proceedings that could result in the disqualification of the contractor from bidding for a designated period of time.

- (1) At time of bid, ALL prime contractors shall submit Form DT1506 (Commitment to Subcontract to DBE), and signed Attachments A. If the assigned DBE contract goal is not met, Form DT1202 (Documentation of Good Faith Effort) is due at time of bid. Supplemental DT1202 documentation is due within 24-hours of bid closing, submitted to the DBE Alert email box. Any change to DBE commitments thereafter must follow Modification of DBE Subcontracting Commitment (Section 9).
- (2) The Department requires this list of DBE subcontractors from all bidders at time of bid to ensure the lowest possible cost to taxpayers and fairness to other bidders and subcontractors. Bid Shopping is prohibited.
- (3) The contractor shall utilize the specific DBE firms listed on the approved Form, DT1506, to perform the work and/or supply the materials for which the DBE firm is listed unless the contractor obtains written consent from WisDOT. The contractor shall not be entitled to payment for any work or materials on the approved DT1506 that is not performed or supplied by the listed DBE without WisDOT's written consent.

#### Description

The Wisconsin Department of Transportation is committed to the compliant administration of the DBE Program. The DBE provisions work in tandem with FHWA 1273 and WisDOT's Standard Specifications and Construction Materials Manual. The WisDOT Secretary is signatory to assurances of department-wide compliance.

The department assigns the contract DBE goal as a percentage of work items that could be performed by certified DBE firms on the contract. The assigned DBE goal is expressed on the bid proposal as a percentage applicable to the total contract bid amount.

(1) WisDOT identifies the assigned DBE goal in its contract advertisements and posts the contract DBE goal on the cover of the bidding proposal. The contractor can meet the assigned contract DBE goal by subcontracting work to a DBE firm or by procuring services or materials from a DBE firm.

- (2) Under the contract, the prime contractor should inform, advise, and develop participating DBE firms to be more knowledgeable contractors who are prepared to successfully complete their contractual agreement through the proactive provision of assistance in the following areas:
  - § Produce accurate and complete quotes
  - § Understand highway plans applicable to their work
  - § Understand specifications and contract requirements applicable to their work
  - § Understand contracting reporting requirements
- (3) The department encourages contractors to assist DBE subcontractors more formally by participating in WisDOT's Business Development program as a mentor, coach, or resource. For comprehensive information on the Disadvantaged Business Enterprise Program, visit WisDOT's Civil Rights and Compliance Section website at: <a href="http://wisconsindot.gov/Pages/doing-bus/civil-rights/dbe/default.aspx">http://wisconsindot.gov/Pages/doing-bus/civil-rights/dbe/default.aspx</a>

#### 1. Definitions

Interpret these terms, used throughout this additional special provision, as follows:

- a. Assigned DBE Contract Goal: The percentage shown on the cover of the Highway Work Proposal that represents the feasible level of DBE participation for each contract. The goal is calculated using the Engineer's Estimate and DBE Interest Report. Goal assignment includes review of FHWA funds, analyzes bid items for subcontract opportunity and compatibility with DBE certified firm work codes. Additional factors considered include proximity, proportion, and regulations.
- b. **Bid Shopping:** In construction law, bid shopping is the practice of divulging a subcontractor's bid to another prospective contractor(s) before or after the award of a contract to secure a lower bid.
- c. DBE: Disadvantaged Business Enterprise- for-profit small business concern where socially and economically disadvantaged individuals own at least a 51% interest and control management and daily business operations.
- d. DBE Commitment: The DBE Commitment is identified in the Commitment to Subcontract to DBE (Form DT1506) and is expressed as the amount of DBE participation the prime contractor has secured. The DT1506, a contract document completed by the bidder, is required to be considered a responsive bidder on an FHWA-funded contract that has an assigned DBE goal.
- e. **DBE Utilization:** The actual participation of a DBE subcontractor on a project. WisDOT verifies DBE utilization through review of Form DT1506, payments to subcontractors, and contract documentation. The Prime Contractor receives DBE credit for payments made to the DBE firms performing the work listed on the approved Form DT1506, and those submitted after approved commitment with Attachment A.
- f. **Good Faith Effort:** Legal term describing a diligent and honest effort taken by a reasonable person under the same set of facts or circumstances. For DBE subcontracting, the bidder must show that it took all necessary and reasonable steps to achieve the assigned DBE goal by the scope, intensity, and appropriateness of effort that could reasonably be expected for a contractor to obtain sufficient DBE participation.
- g. **Manufacturer:** A firm that operates or maintains a factory or establishment that produces, on the premises, the materials, supplies, articles, or equipment required under the contract.
- h. **Reasonable Price:** Contractors are expected to assess reasonable price by analyzing the contract scope for DBE subcontract feasibility and comparing common line items in DBE and non-DBE subcontract quotes for the same work. Per federal regulation, reasonable price is not necessarily the lowest price.

- i. Supplier: A firm that owns, operates, or maintains a store, warehouse, or other establishment in which the materials, supplies, articles, or equipment required under the contract are bought, kept in stock, and regularly sold or leased to the public.
- j. **Tied quote:** Subcontractor quote that groups multiple bid/line items at a bundled/package price with a notation that the items within the quote shall not be separated.

#### 2. WisDOT DBE Program Compliance

#### a. Documentation Submittal

The Commitment to Subcontract to DBE (Form DT1506) and signed Attachments A shall be submitted at bid by ALL prime contractors. If the assigned DBE contract goal is not met, Documentation of Good Faith Effort (Form DT1202) is due at time of bid. Supplemental DT1202 documentation is due within 24-hours of bid closing, submitted to the DBE Alert email box.

Naming conventions: When emailing files, please use the following language to identify your submission-"Project #, Proposal #, Let date, Business Name, GFE" Email: DBE\_Alert@dot.wi.gov

The DBE Office will not certify Good Faith Effort and the Bureau of Project Development will consider the bid nonresponsive if the contractor fails to furnish the Form DT1506, Attachments A, and Form DT1202 if applicable, as required. See sample forms in the Appendix.

#### b. Verification of DBE Commitment

The documentation related to DBE subcontract commitment submitted prior to contract award is evaluated as follows:

#### (1) DBE Goal Met

If the bidder indicates that the contract DBE goal is met, the department will evaluate Form DT1506 and Attachments A to verify the actual DBE percentage calculation. If the DBE commitment is verified, the contract is eligible for award with respect to the DBE commitment.

#### (2) DBE Goal Not Met

- a) If the bidder indicates a bid percentage on Form DT1506 that does not meet the assigned DBE contract goal, the bidder must request alternative evaluation of good faith effort through submission of Form DT1202 (Documentation of Good Faith Effort) at the time of bid including narrative description. Supplementary documentation of good faith effort that supports the DT1202 submission is due within 24-hours of bid submission and prior to bid posting. The department will review the bidder's DBE commitment and evaluate the bidder's good faith efforts submission.
- b) Following evaluation of the bidder's Good Faith Effort documentation the bidder will be notified that the department intends to:
  - 1. *Approve* the request (adequate documentation of GFE has been submitted)- no conditions placed on the contract with respect to the DBE commitment;
  - 2. Deny the request (inadequate documentation of GFE has been submitted)- the contract is viewed as non-responsive per Wisconsin Standard Specifications for Highway and Structure Construction and will not be executed.
- c) If the department denies the bidder's request, the contract is ineligible for award. The department will provide a written explanation for denying the request to the bidder. The bidder may appeal the department's denial (see Section 4).

Supplemental good faith effort documentation must be submitted to the DBE Office by email at: DBE\_Alert@dot.wi.gov or by postal mail - ATTN: DBE Office, PO Box 7986, Madison, WI 53707-7986. Email naming convention: "Project #, Proposal #, Let date, Business Name, GFE"

#### 3. Department's Criteria for Good Faith Effort Documentation

The Federal-aid Construction Contract Provision, referenced as FHWA-1273, explicitly states that the prime contractor shall be responsible for all work performed on the contract by piecework, station work, or subcontract. The contractor shall take all necessary and reasonable steps to ensure nondiscrimination in the administration of the contract including assurances of equal employment opportunity laws, DBE regulations, and affirmative action. Compliance encompasses responsible and responsive action, documentation, and good faith effort.

Contractually, all contractors, subcontractors, and service providers on the contract are bound by FHWA 1273 and DBE program provisions. **Prime contractors should encourage subcontractors to utilize DBE firms whenever possible to contribute to the assigned DBE contract goal.** 

Bidders are required to document good faith effort. Per 49 CFR Part 26.53, good faith effort is demonstrated in one of two ways. The bidder:

- (1) Documents that it has obtained enough DBE participation to meet the goal; OR
- (2) Documents that it made adequate good faith efforts to meet the goal, even though it did not succeed

Appendix A of 49 CFR Part 26 provides guidance concerning good faith efforts. WisDOT evaluates good faith effort on a contract basis just as each contract award is evaluated individually.

The efforts employed by the bidder should be those that WisDOT can reasonably expect a bidder to take to actively and aggressively obtain DBE participation sufficient to meet the DBE contract goal. The department will only approve demonstration of good faith effort if the bidder documents the quality, quantity, and intensity of the variety of activities undertaken that are commensurate with expected efforts to meet the stated goal.

The department, in conjunction with industry stakeholders, has developed the following guidance for contractor good faith effort activity. The guidance and the attached appendices provide a framework for the actions required by all parties in the processing and evaluation of bidder's total efforts to achieve the project specific DBE goal prior to the bid letting date.

- a. Solicitation guidance for Prime Contractors:
  - (1) Document all efforts and decisions made toward achieving the DBE goal on the contract. The bidder should use WisDOT-approved DBE outreach tools, including the UCP DBE Directory and the Bid Express Small Business Network to foster DBE participation on all applicable contracts.
  - (2) As needed, request assistance with DBE outreach and follow-up by contacting the department's DBE Support Services Office by phone or email request at least 14 days prior to the bid letting date. Phone numbers are (414) 438-4584 and/or (608) 267-3849; Fax: (414) 438-5392; E-mail: DBE Alert@dot.wi.gov
  - (3) Participate in and document a substantive conversation with at least one DBE firm per Let, to discuss questions, concerns, and any other contract related matters that may be applicable to the DBE firm. Guidelines for this conversation are provided in Appendix A of ASP-3.
  - (4) Request quotes by identifying potential items to subcontract and solicit. In their initial contacts, contractors are strongly encouraged to include a single page, detailed list of items for which they are accepting quotes, by project, within a letting. See attached sample entitled "Sample Contractor Solicitation Letter" in Appendix B. Prime contractors should also indicate a willingness to accept quotes in areas they are planning to perform themselves, as required by federal rules. In some cases, it might be appropriate to use DBE firms to do work in a prime contractor's area of specialization.

- i. Solicit quotes from certified DBE firms who match possible items to subcontract using all reasonable and available means. Additionally, forward copies of solicitations highlighting the work areas for which quotes are being sought to DBE Alert@dot.wi.gov
- ii. Acceptable outreach tools include SBN (Small Business Network, see Appendix C): <a href="https://www.bidx.com/wi/main">https://www.bidx.com/wi/main</a>, postal mail, email, fax, and phone.
  - a. Contractors must ask DBE firms for a response in their solicitations. See *Sample Contractor Solicitation Letter*, Appendix B. This letter may be included as an attachment to the sub-quote request.
  - b. Solicit quotes at least 10 calendar days prior to the letting date to allow DBE firms sufficient time to respond. Prime contractors should contact DBE firms early, asking if they need help organizing their quote, assistance confirming equipment needs, or other assistance supporting their submission of a competitive quote for their services.
  - c. A follow up solicitation should take place within 5 calendar days of the letting date. Email and/or SBN are the preferred method for the solicitation.
- iii. Upon request, provide interested DBE firms with adequate information about plans, specifications, and the requirements of the contract by letter, information session, email, phone call, and/or referral.
- iv. When potential exists, the contractor should advise interested DBE firms on how to obtain bonding, line of credit, or insurance if requested.
- v. Document DBE firm's interest in quoting by taking appropriate steps to follow up initial solicitation with:
  - a. Email to all prospective DBE firms in relevant work areas
  - b. Phone call log to DBE firms who express interest via written response or call
  - c. Fax/letter confirmation
  - d. Signed copy of record of subcontractor outreach effort

#### b. Guidance for Evaluating DBE quotes

- (1) Quote evaluation practices required to evaluate DBE quotes:
  - i. Reasonable Price: Contractors are expected to assess reasonable price by analyzing the contract scope for DBE subcontract feasibility and comparing common line items in DBE and non-DBE subcontract quotes for the same work. Per federal regulation, reasonable price is not necessarily the lowest price. See 49 CFR Part 26, Appendix A. IV.D(2).
- (2) Documentation submitted by the prime of the following evaluation is required to evaluate DBE quotes by contractors:
  - i. Evaluation of DBE firm's ability to perform "possible items to subcontract" using legitimate reasons, including but not limited to, *a discussion* between the prime and DBE firm regarding its capabilities prior to the bid letting. If lack of capacity is the reason for not utilizing the DBE firm's quote, the prime is required to contact the DBE by phone and email regarding their ability to perform the work indicated in the UCP directory listed as their work area by NAICS code. Only the work area indicated by the NAICS code(s) listed in the UCP directory can be counted toward DBE credit. Documentation of the conversation is required.
    - In striving to meet an assigned DBE contract goal, contractors are expected to use DBE quotes that are responsive and reasonable. This includes DBE quotes that are not the low quote.
    - Additional evaluation Evaluation of DBE quotes with <u>tied bid items</u>. Typically, this type of quoting represents a cost saving but is not clearly stated as a discount. Tied quotes are usually presented as an 'all or none' quote. When non-DBE subcontractors submit tied bid items in their quotes, the DBE firm's quote may not appear competitive. In such a case, the following steps are taken in comparing the relevant quotes. These are qualitative examples:
      - i Compare bid items common to both quotes, noting the reasonableness in the price comparison.

ii Review quotes from other firms for the bid items not quoted by the DBE firm to see if combining both can provide the same competitive advantage that the tied bid items offered.

See Appendix D – Good Faith Effort Evaluation Measures and Appendix E - Good Faith Effort Best Practices.

- c. Requesting Good Faith Effort Evaluation: <u>At the time of bid</u>- if the DBE goal is not met in full, the prime contractor must request alternative Good Faith Effort Evaluation using form DT1202- Documentation of Good Faith Effort. Supplementary documentation of good faith effort that supports the DT1202 submission is due within 24-hours of bid submission and prior to bid posting. Supporting documentation for the DT1202 is to include the following:
  - (1) Solicitation Documentation: The names, addresses, email addresses, and telephone numbers of DBE firms contacted along with the dates of both initial and follow-up contact; electronic copies of all written solicitations to DBE firms. A printed copy of SBN solicitation is acceptable.
  - (2) Selected Work Items Documentation: Identify economically feasible work units to be performed by DBEs to include activities such as: list of work items to be performed; breaking up of large work items into smaller tasks or quantities; flexible time frames for performance and delivery schedules.
  - (3) Documentation of Project Information provided to interested DBEs: A description of information provided to the DBE firms regarding the plans, specifications, and estimated quantities for portions of the work to be performed by that DBE firm.
  - (4) Documentation of Negotiation with Interested DBEs: Provide sufficient evidence to demonstrate that good faith negotiations took place. Merely sending out solicitations requesting bids from DBEs does not constitute sufficient good faith efforts.
  - (5) Documentation of Sound Reasoning for Rejecting DBEs and copies of each quote received from a DBE firm and, if rejected, copies of quotes from non-DBEs for same items.
  - (6) Documentation of Assistance to Interested DBEs- Bonding, Credit, Insurance, Equipment, Supplies/Materials
  - (7) Documentation of outreach to Minority, Women, and Community Organizations and other DBE Business Development Support: Contact organizations and agencies for assistance in contacting, recruiting, and providing support to DBE subcontractors, suppliers, manufacturers, and truckers at least 14 days before bid opening. Participate in or host activities such as networking events, mentor-protégé programs, small business development workshops, and others consistent with DBE support.

Naming conventions: When emailing files, please use the following language to identify your submission-"Project #, Proposal #, Let date, Business Name, GFE" Email: DBE\_Alert@dot.wi.gov

If the Good Faith Effort documentation is deemed adequate, the request will be approved and the DBE office will promptly notify the Prime Contractor and Bureau of Project Development.

If the DBE Office denies the request, the Prime Contractor will receive written correspondence outlining the reasons. The department encourages the Prime Contractor to communicate with DBE staff to clarify any questions related to meeting goals and/or contractor demonstration of good faith efforts.

If the contract is awarded, the Prime Contractor must obtain written consent from the DBE Office to change or replace any DBE firm listed on the approved Form DT1506. No contractor, prime or subsequent tier, shall be paid for completing work assigned to a DBE subcontractor on an approved DT1506 <u>unless</u> WisDOT has granted permission for the reduction, replacement, or termination of the assigned DBE in writing. If a prime contractor or a subcontractor on any tier uses its own forces to perform work assigned to a DBE on an approved DBE commitment, **they will not be paid for the work**. Any changes to DBE commitment after the approval of Form DT1506 must be reviewed and approved by the DBE Office prior to the change (see Section 9).

#### 4. Bidder's Documentation of Good Faith Effort Evaluation Request Appeal Process

A bidder can appeal the department's decision to deny the bidder's demonstration of Good Faith Effort through Administrative Reconsideration. The bidder must provide a written justification refuting the specific reasons for denial as stated in the department's denial notice. The bidder may meet in person with the department if so requested. Failure to appeal within 5 business days after receiving the department's written notice denying the request constitutes a forfeiture of the bidder's right of appeal. Receipt of appeal is confirmed by email date stamp or certified mail signed by WisDOT staff. A contract will not be executed without documentation that the DBE provisions have been fulfilled.

The department will appoint a representative who did not participate in the original good faith effort determination, to assess the bidder's appeal. The department will issue a written decision within 5 business days after the bidder presents all written and oral information. In that written decision, the department will explain the basis for finding that the bidder did or did not demonstrate an adequate good faith effort to meet the contract DBE goal. The department's decision is final.

#### 5. Determining DBE Eligibility

#### **Directory of DBE firms**

- a. The only resource for DBE firms certified in the State of Wisconsin is the Wisconsin Unified Certification Program (UCP) DBE Directory. WisDOT maintains a current list of certified DBE firms at: <a href="http://wisconsindot.gov/Documents/doing-bus/civil-rights/dbe/dbe-ucp-directory.xlsx">http://wisconsindot.gov/Documents/doing-bus/civil-rights/dbe/dbe-ucp-directory.xlsx</a>
- b. The DBE Program office is available to assist with contracting DBE firms:(608) 267-3849.
- c. DBE firms are certified based on various factors including the federal standards from the Small Business Administration that assigns a North American Industrial Classification (NAICS) Codes. DBE firms are only eligible for credit when performing work in their assigned NAICS code(s). If a DBE subcontractor performs work that is not with its assigned NAICS code, the prime contractor should contact the DBE Office to inquire about compatibility with the Business Development Program.

#### 6. Counting DBE Participation

#### **Assessing DBE Work**

The department will only count the DBE usage towards the contract DBE goal if the DBE firm is certified as a DBE by one of the UCP agencies. The department only counts the value of the work a DBE actually performs towards the DBE goal. The department assesses the DBE work as follows:

- a. The department counts work performed by the DBE firm's own resources. The department includes the cost of materials and supplies the DBE firm obtains for the work. The department also includes the cost of equipment the DBE firm leases for the work. The department will not include the cost of materials, supplies, or equipment the DBE firm purchases or leases from the prime contractor or its affiliate, with the exception of non-project specific leases the DBE has in place before the work is advertised.
- b. The department counts fees and commissions the DBE subcontractor charges for providing bona fide professional, technical, consultant, or managerial services. The department also counts fees and commissions the DBE charges for providing bonds or insurance. The department will only count costs the program engineer deems reasonable based on experience or prevailing market rates.
- If a DBE firm subcontracts work, the department counts the value of the work subcontracted to a DBE subcontractor.

- d. The contractor shall maintain records and may be required to furnish periodic reports documenting its performance under this item.
- e. It is the Prime Contractor's responsibility to determine whether the work that is committed and/or contracted to a DBE firm can be counted for DBE credit by referencing the work type and NAICS code listed for the DBE firm on the Wisconsin UCP DBE Directory.
- f. It is the Prime Contractor's responsibility to assess the DBE firm's ability to perform the work for which it is committing/contracting the DBE to do. Note that the department encourages the Prime Contractor to assist and develop DBE firms to become fully knowledgeable contractors to successfully perform on its contracts.
- g. The Prime Contractor shall inform the DBE office via email of all DBE subcontractors added to the project following execution of the contract. The Prime Contractor may omit submission of another form DT1506, but must submit signed Attachment A forms for additional DBE firms.
- h. See Section 7 for DBE credit evaluation for Trucking and Section 8 for DBE credit evaluation for Manufacturers, Suppliers, and Brokers

Naming conventions: When emailing files, please use the following language to identify your submission-"Project #, Proposal #, Let date, Business Name, Attachment A" Email: DBE Alert@dot.wi.gov

\*Note: A sublet request is required for DBE work, regardless of subcontract tier, and also for reporting materials or supplies furnished by a DBE.

- Sublet Requests via form DT1925 or WS1925 are required for 1st Tier DBEs
- For all 2nd Tier and below notification of DBE sublet is indicated by the contractor entering them in CRCS

#### 7. Credit Evaluation for Trucking

All bidders are expected to adhere to the department's current trucking policy posted on the HCCI website at: http://wisconsindot.gov/Documents/doing-bus/civil-rights/dbe/trucking-utilization-policy.pdf

The prime contractor is responsible for ensuring that all subcontractors including trucking firms, receive Form FHWA 1273: https://www.fhwa.dot.gov/programadmin/contracts/1273/1273.pdf

See Section 8 for Broker credit.

#### 8. Credit Evaluation for Manufacturers, Suppliers, Brokers

The department will calculate the amount of DBE credit awarded to a prime using a DBE firm for the provisions of materials and supplies on a contract-by-contract basis. The department will count the material and supplies that a DBE firm provides under the contract for DBE credit based on whether the DBE firm is a manufacturer, supplier, or broker. Generally, DBE credit is determined through evaluation of the DBE owner's role, responsibility, and contribution to the transaction. Maximum DBE credit is awarded when the DBE firm manufactures materials or supplies. DBE credit decreases when the DBE firm solely supplies materials, and minimal credit is allotted when the DBE firm's role is administrative or transactional. It is the bidder's responsibility to confirm that the DBE firm is considered a supplier or a manufacturer before listing them on Commitment to Subcontract to DBE form DT1506.

- a. Manufacturers
  - (1) A manufacturer is a firm that operates or maintains a factory or establishment that produces, on the premises, the materials, supplies, articles, or equipment required under the contract and of the general character described by the specifications.

- (2) If the materials or supplies are obtained from a DBE manufacturer, **100%** percent of the cost of the materials or supplies counts toward DBE goals.
- b. Regular Dealers of Material and/or Supplies
  - (1) Supplies purchased in bulk from DBE firms at the beginning of the season may be credited to current contracts if submitted with appropriate documentation to the DBE office.
  - (2) A regular dealer is a firm that owns, operates, or maintains a store, warehouse, or other establishment in which the materials, supplies, articles or equipment of the general character described by the specifications and required under the contract are bought, kept in stock, and regularly sold or leased to the public in the usual course of business.
  - (3) If the materials or supplies are purchased from a DBE regular dealer, count **60%** percent of the cost of the materials or supplies toward DBE goals.
  - (4) At a minimum, a regular dealer must meet the following criteria to be counted for DBE credit:
    - i. The DBE firm must be an established, regular business that engages, as its principal business and under its own name, in the purchase and sale or lease of the products in question.
    - ii. The DBE firm must both own and operate distribution equipment for the product--bulk items such as petroleum products, steel, cement, gravel, stone, or asphalt. If some of the distribution equipment is leased, the lease agreement must accompany the DBE Commitment form for evaluation of the dealer's control before the DBE office approves the DBE credit.
  - (5) When DBE suppliers are contracted, additional documentation must accompany form DT1506 and Attachment A forms. An invoice or bill-of-sale that includes names of the bidder and the DBE supplier, along with documentation of the calculations used as the basis for the purchase agreement, subcontract, or invoice. WisDOT recognizes that the amount on the Attachment A form may be more or less than the amount on the invoice per b.(1) above.
    - The bidder should respond to the following questions and include with submission of form DT1506:
      - a. What is the product or material?
      - b. Is this item in the prime's inventory or was the item purchased when contract was awarded?
      - c. Which contract line items were referenced to develop this quote?
      - d. What is the amount of material or product used on the project?
- c. Brokers, Transaction Expediters, Packagers, Manufacturers' Representatives
  - (1) No portion of the cost of the materials, supplies, services themselves will count for DBE credit. However, WisDOT will evaluate the fees or commissions charged when a prime purchases materials, supplies, or services from a DBE certified firm which is neither a manufacturer nor a regular dealer, namely: brokers, packagers, manufacturers' representatives, or other persons who arrange or expedite transactions.
  - (2) Brokerage fees are calculated as **10%** of the purchase amount.
  - (3) WisDOT may count the amount of fees or commissions charged for assistance in the procurement of the materials and supplies, fees, or transportation charges for the delivery of materials or supplies required on a job site.
  - (4) Evaluation of DBE credit includes review of the contract need for the item/service, the sub-contract or invoice for the item/service, and a comparison of the fees customarily allowed for similar services to determine whether they are reasonable.

#### 9. DBE Commitment Modification Policy (Formerly "DBE Replacement Policy")

#### A. Issuing a Contract Change Order

Any changes or modifications to the contract once executed are considered contract modifications and as such require a change order. In addition, the DBE office must provide consent for reduction, termination, or replacement of subcontractors approved on the DT1506 *in advance* of the modification for the prime contractor to receive payment for work or supplies. Additions to the DBE commitment do not require advance notification of the DBE office. (see D below)

#### **Contractor Considerations**

- A prime contractor cannot modify the DBE commitment through reduction in participation, termination, or replacement of a DBE subcontractor listed on the approved DT1506 without prior written consent from the DBE Office. This includes, but is not limited to, instances in which a prime contractor seeks to perform work originally designated for a DBE subcontractor with its own forces or those of an affiliate, a non-DBE firm, or with another DBE firm.
- 2. If a prime contractor reduces participation, replaces, or terminates a DBE subcontractor who has been approved for DBE credit toward its contract, the prime is required to provide documentation supporting its inability to fulfill the contractual commitment made to the department regarding the DBE utilization.
- 3. The Prime Contractor is required to demonstrate efforts to find another DBE subcontractor to perform at least the same amount of work under the contract as the DBE subcontractor that was terminated, to the extent needed to meet the assigned DBE contract goal.
- 4. When additional opportunity is available by contract modifications, the Prime Contractor must utilize DBE subcontractors that were committed to equal work items, in the original contract.
- 5. In circumstances when a DBE subcontractor fails to complete its work on the contract for any reason, or is terminated from a contract, the Prime Contractor must undertake efforts to maintain its commitment to the assigned DBE goal.
- 6. The DBE subcontractor should communicate with the Prime Contractor regarding its schedule and capacity in the context of the contract. If the DBE firm anticipates that it cannot fulfill its subcontract, they shall advise the Prime Contractor and suggest a DBE subcontractor that may replace their services and provide written consent to be released from its subcontract.
  - (a) Before the Prime Contractor can request modification to the approved DT1506, the Prime Contractor must:
    - i. Make every effort to fulfill the DBE commitment by working with the listed DBE subcontractor to ensure that the firm is fully knowledgeable of the Prime Contractor's expectations for successful performance on the contract. Document these efforts in writing.
    - ii. If those efforts fail, provide written notice to the DBE subcontractor of the Prime Contractor's intent to request to modify the commitment through reduction in participation, termination, and/or replacement of the subcontractor including the reason(s) for pursuing this action.
    - iii. Copy the DBE Office on all correspondence related to changing a DBE subcontractor who has been approved for DBE credit on a contract, including preparation and coordination efforts.
    - iv. Clearly state the amount of time the DBE firm has to remedy and/or respond to the notice of intent to replace/terminate. The DBE must be allowed five days from the date notice was received as indicated by email time stamp or signed certified mail, to respond, in writing. **EXCEPTION:** The Prime Contractor must provide a verifiable reason for a response period shorter than five days. For example, a WisDOT project engineer or project manager confirms that WisDOT has eliminated an item the DBE subcontractor was contracted for.
    - v. The DBE subcontractor must acknowledge the contract modification with written response to the Prime Contractor and the DBE Office. If objecting to the subcontract modification, the DBE subcontractor must outline the basis for objection to the proposed modification, providing sound reasoning for WisDOT to reject the prime's request.

#### **B.** Request to Modify DBE Subcontracting Commitment

The written request referenced above may be delivered by email or fax. The request must contain the following:

- 1. Project ID number
- 2. WisDOT Contract Project Engineer's name and contact information

- 3. DBE subcontractor name and work type and/or NAICS code
- 4. Contract's progress schedule
- 5. Reason(s) for requesting that the DBE subcontractor be replaced or terminated
- 6. Attach/include all communication with the DBE subcontractor to deploy/address/resolve work completion

Naming conventions: When emailing files, please use the following language to identify your submission-"Project #, Proposal #, Let date, Business Name, MODIFICATION" Email: DBE\_Alert@dot.wi.gov + Project Engineer

WisDOT will review the request and any supporting documentation submitted to evaluate if the circumstance and the reasons constitute good cause for replacing or terminating the approved DBE subcontractor.

Good Causes to Replace a DBE subcontractor according to the federal DBE program guidelines {49 CFR part 26.53}

- The listed DBE subcontractor fails or refuses to execute a written contract
- The listed DBE subcontractor fails or refuses to perform the work of its subcontract in a way consistent
  with normal industry standards. Provided, however, that good cause does not exist if the failure or
  refusal of the DBE subcontractor to perform its work on the subcontract results from the bad faith or
  discriminatory action of the prime contractor
- The listed DBE subcontractor fails or refuses to meet the prime contractor's reasonable, nondiscriminatory bond requirements
- The listed DBE subcontractor becomes bankrupt, insolvent, or exhibits credit unworthiness
- The listed DBE subcontractor is ineligible to work on public works projects because of suspension and debarment proceedings pursuant 2 CFR Parts 180, 215, and 1,200 or applicable state law
- The prime has determined that the listed DBE subcontractor is not a responsible contractor
- The listed DBE subcontractor voluntarily withdraws from the project and provides written notice of its withdrawal
- The listed DBE subcontractor is ineligible to receive DBE credit for the type of work required
- A DBE firm owner dies or becomes disabled with the result that the listed DBE subcontractor is unable to complete its work on the contract

#### C. Evaluation and Response to the Request

WisDOT's timely response to the Prime Contractor's request for modification of the approved DBE subcontracting commitment will be provided to the prime and the WisDOT project engineer via email.

If WisDOT determines that the Prime Contractor's basis for reduction in participation, replacement, or termination of the DBE subcontractor is not consistent with the good cause guidelines, the DBE office will provide a response via email within 48-hours of receipt of request from the Prime Contractor as indicated by email time stamp. The communication will include: the requirement to utilize the committed DBE, actions to support the completion of the contractual commitment, a list of available WisDOT support services, and administrative remedies, including withholding payment to the prime, that may be invoked for failure to comply with federal DBE guidelines for DBE replacement.

The WisDOT contact for all actions related to modification of the approved Form DT1506 is the DBE Program Engineer who can be reached at DBE\_Alert@dot.wi.gov or (608) 264-9528.

#### D. DBE Utilization beyond the approved DBE Commitment (Form DT1506)

When the prime or a subcontractor increases the scope of work for an approved DBE subcontractor or adds a DBE subcontractor who was not on the approved form DT1506 at any time after contract execution, this is referred to as voluntary DBE contract goal achievement. The contractor must follow these steps to ensure that the participation is accurately credited toward the DBE goal:

- a. Forward a complete, signed Attachment A form to the DBE Office. A complete Attachment A includes DBE subcontractor contact information, signatures, subcontract value, and description of the work areas to be performed by the DBE. The DBE Office will verify the DBE participation and revise the DT1506 based on the email/discussion and the new Attachment A.
- b. When adding to an existing DBE commitment, submit a new Attachment A to the DBE Alert mailbox
- c. OR Submit a final Attachment A to DBE Alert during the Finals Process when Compliance receives notice of "Substantially Complete"

Naming conventions: When emailing files, please use the following language to identify your submission-"Project #, Proposal #, Let date, Business Name, New Attachment A" Email: DBE\_Alert@dot.wi.gov

#### Special note on trucking

- DBE truckers added to the sublets in CRCS will be approved without DBE credit (You will see a "N" in CRCS instead of "Y")
- Prime Contractors may enter a "place holder" e.g. \$1000.00, for DBE Trucking in CRCS if the full amount of trucking is unknown for sublet purposes only
- The hiring contractor may obtain the Attachment A with DBE signature included but the **Prime Contractor** must sign the Attachment A before submitting

#### 10. Commercially Useful Function

- a. Commercially Useful Function (CUF) is evaluated after the contract has been executed, while the DBE certified firm is performing contracted work items.
- b. The department uses Form DT1011, DBE Commercially Useful Function Review and Certification to evaluate if the DBE is performing a commercially useful function. WisDOT counts expenditures of a DBE toward the DBE goal only if the DBE is performing a commercially useful function on that contract.
- c. A DBE firm is performing a commercially useful function if the following conditions are met:
  - (1) For contract work, the DBE is responsible for executing a distinct portion of the work and is carrying out its responsibilities by actually performing, managing, and supervising that work.
  - (2) For materials and supplies, the DBE is responsible for negotiating price, determining quality and quantity, ordering, and paying for those materials and supplies.

#### 11. Credit Evaluation for DBE Primes

WisDOT calculates DBE credit based on the amount and type of work performed by DBE certified firms for work submitted with required documentation. If the prime contractor is a DBE certified firm, the department will only count the work that the DBE prime performs with its own forces for DBE neutral credit. The department will also calculate DBE credit for work performed by any other DBE certified subcontractor, DBE certified supplier, and DBE certified manufacturer on the contract in each firm's approved NAICS code/work areas that are submitted with required documentation. Crediting for manufacturers and suppliers is calculated consistent with Section 8 of this document and 49 CFR Part 26.

#### 12. Joint Venture

If a DBE performs as a participant in a joint venture, the department will only count the portion of the total dollar value of the contract equal to the portion of the work that the DBE performs with its own forces, for DBE credit.

#### 13. Mentor-Protégé

- a. If a DBE performs as a participant in a mentor-protégé agreement, the department will credit the portion of the work performed by the DBE protégé firm.
- b. DBE credit is evaluated and confirmed by the DBE Office for any contracts on which the mentor-protégé team identifies itself to the DBE Office as a current participant of the Mentor-Protégé Program.
- c. Refer to WisDOT's Mentor-Protégé guidelines for guidance on the number of contracts and amount of DBE credit allowed on WisDOT projects.

#### 14. Use of Joint Checks

The use of joint checks is allowable if it is a commonly recognized business practice in the material industry. A joint check is defined as a two-party check between a DBE subcontractor, a prime contractor, and the regular dealer or materials supplier who is neither the prime nor an affiliate of the prime. Typically, the prime contractor issues one check as payor to the DBE subcontractor and to the supplier jointly (to guarantee payment to the supplier) as payment for the material/supplies used by the DBE firm in cases where the DBE subcontractor and materials have been approved for DBE credit. The DBE subcontractor gains the opportunity to establish a direct contracting relationship with the supplier to potentially facilitate a business rapport that results in a line of credit or increased partnering opportunities.

The cost of material and supplies purchased by the DBE firm is part of the value of work performed by the DBE to be counted toward the goal. To receive credit, the DBE firm must be responsible for negotiating price, determining quality and quantity, ordering the materials, and installing (where applicable) and "paying for the material itself." See 49 CFR 26.55(c)(1).

The approval to use joint checks constitutes a commitment to provide further information to WisDOT, upon request by staff. WisDOT will allow the use of joint checks when the following conditions are met:

- a. The Prime Contractor must request permission to use joint checks from the DBE Office by submitting the Application to Use Joint Checks.
  - (1) Request should be made when Form DT1506 or when the Request to Sublet is submitted; the request will not be considered if submitted after the DBE Subcontractor starts its work.
  - (2) Approval/Permission must be granted prior to the issuance of any joint checks.
  - (3) The payment schedule for the supplier must be presented to the DBE office before the first check is issued.
  - (4) The joint check for supplies must be strictly for the cost of approved supplies.
- b. The DBE subcontractor is responsible for furnishing and/or installing the material/work item and is not an 'extra participant' in the transaction. The DBE firm's role in the transaction cannot be limited solely to signing the check(s) to release payment to the material supplier. At a minimum, the DBE subcontractor's tasks should include the following:
  - (1) The DBE subcontractor (not the prime/payor) negotiates the quantities, price, and delivery of materials.
  - (2) The DBE subcontractor consents to sign/release the check to the supplier by signing the Application to Use Joint Checks after establishing the conditions and documentation of payment within the subcontract terms or in a separate written document.
- c. The Prime contractor/payor acts solely as a guarantor.
  - (1) The Prime Contractor agrees to furnish the check used for the payment of materials/supplies under the contract.

(2) The prime contractor/payor cannot require the subcontractor to use a specific supplier or the prime contractor's negotiated unit price.

#### 15. Payment

Costs for conforming to this Additional Special Provision (ASP) and any associated DBE requirements are incidental to the contract.

## Appendix A Substantive Conversation Guidelines

The substantive conversation is critical to all bidders' demonstration of good faith effort to meet the DBE goal prior to bid opening. Relationship building between primes and subcontractors is crucial to DBE goal attainment. Responsible bidders seek to build rapport with potential DBE subcontractors to understand capacity, areas of expertise, and assess contracting feasibility. Bidders who compete for WisDOT contracts are specialty contractors responding to a growing and changing contract environment. Just as these specialists are responsible for care of the roads, they are likewise responsible for contributing to the health of the industry. The substantive conversation drives collaboration that will build industry health and capacity. The following is intended to provide guidance for such discussions but is not an exhaustive list. Contractors are encouraged to incorporate their existing strategies for cultivating business relationships as well.

## <u>Prior to Bid Opening- this discussion should happen as early as possible (WisDOT advertisements are released 5 weeks prior to each Let)</u>

- Determine DBE subcontractor's interest in quoting
- If response indicates inexperience with quoting- offer support/assistance to the DBE in understanding the industry including fundamentals a subcontractor needs to know, required reading and/or resources.
- Assess their interest and experience in the road construction industry by asking questions such as:
  - 1. Have you competed for other WisDOT contracts? Ratio of competed/to wins
  - 2. Have you performed on any transportation industry contracts (locally or with other states)?
  - 3. What the largest contract you've completed?
  - 4. Have you worked in the industry: apprentice, journeyman, safety, inspection etc.?
  - 5. Does this project fit into your schedule? Are you working on any contracts now?
  - 6. Have you reviewed a copy of the plans? Are you comfortable performing within the scope and quantity considerations of this contract?
  - 7. What region do you work in? Home base?
  - 8. Which line items are you considering?
  - 9. Have you read/are you familiar with WisDOT Standard Specifications? Construction Material Manual?
  - 10. Do you understand where your work fits in the project schedule, project phases?

#### Following Bid Opening- this discussion can happen at any time

- 1. After reviewing their quote, note the following in your discussion:
- Does the quote look complete? Irregular?
- · Are there errors in the quote? Are items very high or very low?
- In general, does the quote look competitive?
- 2. Questions and Advice for the bidder to share with the potential DBE subcontractor:
- · What line items would typically be in a competitive quote for a subcontractor of their specialty?
- How many employees and what is their role/experience/expertise in your firm?
- Do you have resources for labor (union member, family-based, community-resourced) and capital (banking relationship, bond agent, CPA)?
- · Where have you worked: cities, states, government, commercial, residential/private sector, etc. Explain similarities or differences.
- Refer them to reliable, trusted, industry resources that can educate or connect them to relevant resources, education/certification resources, more appropriate contract opportunities.
- Discussion about prime contract and subcontract liability, critical path items, contract quantities, schedule risks, and potential profit/loss (for upcoming known projects or in general).
- · Discussion of bonding, insurance, and overall business risk considerations.

# APPENDIX B Sample Contractor Solicitation Letter Page 1 This sample is provided as a guide not a requirement

#### **GFESAMPLE MEMORANDUM**

TO: DBE FIRMS

FROM: POTENTIAL PRIME CONTRACTOR OR MAJOR SUBCONTRACTOR

SUBJECT: REQUEST FOR DBE QUOTES

**LET DATE & TIME** 

DATE: MONTH DAY YEAR
CC: DBE OFFICE ENGINEER

Our company is considering bidding on the projects indicated on the next page, as a prime and/or a subcontractor for the Wisconsin Department of Transportation Month- date -year Letting. Page 2 lists the projects and work items that we may subcontract for this letting. We are interested in obtaining subcontractor quotes for these projects and work categories. Also note that we are willing to accept quotes in areas we may be planning to perform ourselves as required by federal rules.

Please review page 2, respond whether you plan to quote, highlight the projects and work items you are interested in performing and return it via fax or email within 3 days. Plans, specifications and addenda are available through WisDOT at the DBE Support Services office or at the Highway Construction Contract Information (HCCI) site at <a href="http://roadwaystandards.dot.wi.gov/hcci/">http://roadwaystandards.dot.wi.gov/hcci/</a>

Your quote should include all of the costs required to complete the items you propose to perform including labor, equipment, material, and related bonding or insurance. The quote should note items that you are DBE certified to perform, tied items, and any special terms. Page 2, with the indicated projects and items you plan to quote, should be used as a cover sheet for your quote.

Please make every effort to have your quotes into our office by time deadline the prior to the letting date. <u>Make sure</u> the correct letting date, project ID and proposal number, unit price and extension are included in your quote. We prefer quotes be sent via SBN but prime's alternatives are acceptable. Our office hours are include hours and days.

Please call our office as soon as possible prior to the letting if you need information/clarification to prepare your quote at contact number.

If you wish to discuss or evaluate your quote in more detail, contact us after the contract is awarded. Status of the contract can be checked at WisDOT's HCCl site at <a href="http://roadwaystandards.dot.wi.gov/hcci/">http://roadwaystandards.dot.wi.gov/hcci/</a> All questions should be directed to:

Project Manager, John Doe, Phone:

(000) 123-4567

Email: Joe@joetheplumber.com

Fax: (000) 123- 4657

### **Sample Contractor Solicitation Letter Page 2**

This sample is provided as a guide not a requirement

#### REQUEST FOR QUOTE

Prime's Name:							
Letting Date: Project ID:							
Please check all that apply  Yes, we will be quoti  No, we are not intere  Please take our nam	ested in o	quoting o	n the letti	ng or its i		renced be	low
We have questions a	about qu	oting this	letting. F	Please ha	ive some	one conta	ct me at this nu
Prime Contractor 's Con Person	ntact					DBE	
Contractor Contact Person Phone:  ax:  mail:							
Proposal No.	ease cire	cie the jo	3	4	5	quoting b	elow 7
County							
VORK DESCRIPTION:							
Clearing and Grubbing	Χ		Х	Х		Х	Х
Dump Truck Hauling	Х		Х	Х		Х	X
Curb & Gutter/Sidewalk, Etc.	X		Х	X		Χ	X
Erosion Control Items	Χ		Х	Х		Х	X
Signs and Posts/Markers	Χ		X	Χ		Χ	X
Traffic Control		Х	Х	X		X	X
Electrical Work/Traffic Signals		Х	Х	X		X	
Pavement Marking		X	Х	Х	X	X	X
Sawing Pavement		X	Х	Х	Х	X	X
QMP, Base	Х	Х		X	Х	Х	X
Pipe Underdrain	Х			Х			
Beam Guard				X	X	Χ	X
Concrete Staining							X

Trees/Shrubs	Χ			Х

Again please make every effort to have your quotes into our office by time deadline prior to the letting date.

We prefer quotes be sent via SBN but prime's preferred alternatives are acceptable.

If there are further questions please direct them to the prime contractor's contact person at phone number.

## Appendix C Small Business Network (SBN) Overview

The Small Business Network is a part of the Bid Express® service that was created to ensure that prime bidders have a centralized online location to find subs - including small and disadvantaged business enterprises (DBEs). It is available for prime bidders to use as part of their Basic Service subscription. Within the Small Business Network, **Prime Contractors** can:

#### 1. Easily select proposals, work types and items:

a. After adding applicable work types, select items that you wish to quote. Enter the sub-quote quantities and add comments, if desired. Adding or removing items and work types can be done quickly. If needed, you can save the sub-quote for later completion.

#### 2. Create sub-quotes for the subcontracting community:

- a. Create sub-quotes with ease using the intuitive sub-quote creator. In seven short steps, you can rapidly create a custom sub-quote directed to all subcontractors that bid on the applicable work types. Steps include: provide contact information and sub-quote expiration date, select letting and proposal, add work types and items, specify terms and conditions, upload attachments, and select vendors.
- b. Create a sub-quote to send to subcontractors or suppliers that lists the items in a proposal that you want quoted
- c. Create an unlimited number of sub-quotes for items you want quoted, and optionally mark them as a DBE preferred request.
- d. Add attachments to sub-quotes.

#### 3. View sub-quote requests & responses:

- a. After logging into the Bid Express service, you can quickly review all of your sub-quote requests and all unsolicited sub-quote requests from subcontractors. To simplify the Small Business Network home screen, sub-quote requests can be hidden with one click if they are not applicable.
- b. View or receive unsolicited sub-quotes that subcontractors have posted, complete with terms, conditions and pricing.

#### 4. View Record of Subcontractor Outreach Effort:

- a. For each sub-quote produced, a *Record of Subcontractor Outreach Effort* is generated that shows the response statistics for a particular sub-quote. If accepted by the letting agency, this report may serve as proof of a "Good Faith" effort in reaching out to the DBE community.
- b. Easily locate pre-gualified and certified small and disadvantaged businesses.
- c. Advertise to small and disadvantaged businesses more efficiently and cost effectively.
- d. Document your interactions with subs/DBEs by producing an Outreach Report (may be accepted as proof of DBE outreach at the discretion of each agency).

The Small Business Network is a part of the Bid Express® service that was created to ensure that small businesses have a centralized area to access information about upcoming projects. It can help small businesses learn more about opportunities, compete more effectively, network with other contractors and subcontractors, and win more jobs. **DBE firms can:** 

#### 1. View and reply to sub-quote requests from primes:

a. After logging into the Bid Express service, you can quickly review all incoming sub-quote requests and all unsolicited sub-quotes created by your company. Receive notifications by selected work type. To simplify on the Small Business Network home screen, sub-quote requests can be filtered by work types relevant to your interests or hidden with one click if they are not applicable.

#### 2. Select items when responding to sub-quote requests from primes:

- a. You have the freedom to choose and price any number of items when responding to a sub-quote request. Quantities can be modified, and per-item comments are also available.
- b. View requests for sub-quotes for work that primes have posted for projects they are bidding, add your pricing, terms, and conditions, and submit completed sub-quotes to the requesting primes. c. Add attachments to a sub-quote.

#### 3. Create and send unsolicited sub-quotes to specific contractors:

a. Create unsolicited sub-quotes with ease using the intuitive sub-quote creator. In eight short steps, you can rapidly create a custom sub-quote directed at any number of specific vendors of your choosing. Steps include: provide contact information and sub-quote expiration date, select letting and proposal, add work types and items, specify terms and conditions, upload attachments, and select vendors.

#### 4. Easily select and price items for unsolicited sub-quotes:

- a. After adding applicable work types, select items that you wish to quote. The extended price calculates automatically, cutting out costly calculation errors. Comments can be provided on a peritem basis as well.
- b. Create an unsolicited sub-quote that lists the items from a proposal that you want to quote, include pricing, terms and conditions, and send it to selected prime/plan holder.
- c. Add attachments to a sub-quote.
- d. Add unsolicited work items to sub-quotes that you are responding to.

#### 5. Easy Access to Valuable Information

- a. Receive a confirmation that your sub-quote was opened by a prime.
- b. View Bid Tab Analysis data from past bids, including the high, average and low prices of items.
- c. View important notices and publications from DOT targeted to small and disadvantaged businesses.

#### Accessing Small Business Network for WisDOT contracting opportunities

- a. If you are a contractor not yet subscribing to the Bid Express service, go to www.bidx.com and select "Order Bid Express." The Small Business Network is a part of the Bid Express Basic Service.
- b. DBE firms can request a Bid Express Small Business Network Account at no cost by calling 414-438-4588.

#### APPENDIX D

#### Good Faith Effort Evaluation Measures by categories referenced in DBE regulations

Bidders must demonstrate that they took all necessary and reasonable steps to achieve the assigned DBE contract goal. For each contract, all bidders must submit documentation indicating the goal has been met <u>or</u> if falling short of meeting the assigned goal, must request a DBE Goal Waiver and document all efforts employed to secure DBE subcontractor participation on Form DT1202.

DBE staff analyze the bidder's documented good faith efforts to determine if action taken was sufficient to meet the goal. Sufficiency is measured contract-by-contract. WisDOT evaluates active and aggressive efforts, quality, quantity, scope, intensity, and appropriateness of the bidder's efforts as a scale of the principles of Good Faith outlined in 49 CFR Part 26, Appendix A. Additional emphasis is placed on the bidder's demonstration of timely submission of documentation and communication with DBE subcontractors, and business development initiatives undertaken to support DBE firm growth.

The following is a sample of good faith effort activities that are rated according to the accompanying rubric. Contractors are encouraged to identify additional activities that align with their business type(s).

- Personal, tailored solicitation to firms that specialize in work types planned or desired for subcontracting
- Follow up to initial solicitation via email or phone
- Substantive conversation including topics such as contract liability, critical path work items, schedule risks, and potential profit/loss
- SBN utilization including posting quotes
- · Review and response to DBE quotes including provision of information about plans, specifications, and requirements as applicable
- Documentation requesting subcontractors support DBE goal by solicitation and inclusion of DBE subcontractor quotes
- Responsive and timely submission of organized documentation
- Analysis of number of DBE firms who do work types that you typically subcontract
- Analysis of number of DBE firms who reside in geographical areas where prime seeks work
- Analysis of firms who express interest in bidding/quoting including the number of firms who declined your solicitation.
- Reference check of DBE subcontractor work or training (documentation of guestions and response required)
- Number of different efforts undertaken to meet the assigned DBE goal as documented in accompanying Form DT1202
- Submission of all DBE quotes received matched with a variety of work to be performed by DBEs
- Number and names of DBE firms provided written advice, or referral to industry-specific business development resources
- · Overall pattern of DBE utilization on all WisDOT contracts which may include contracting with municipalities
- Documentation of resources expended to meet assigned DBE goal (#of hours, staff titles, average pay rate, actions taken)
- Analysis of subcontractable work items to be completed by prime beyond prime contractor's 30%
- Risk analysis of work items that are typically in tied quotes that could be unbundled
- · List of contract work items in smallest economically feasible units, identifying schedule impact
- Submission of a Gap Analysis identifying DBE skillset and/or industry needs
- Staff training in EEO and Civil Rights laws as documented in training logs
- Written Capacity Assessment completed with DBE firm documenting its ability to perform the work quoted
- DBE engagement efforts beyond simple solicitation that include a substantive discussion, initiated as early in the acquisition process as possible (points added for each day prior to letting)
- Outreach and marketing efforts with minority, women, and veteran-focused organizations at least 10 days prior to bid opening
- Active involvement in WisDOT's Business Development Program, TrANS training, facilitated networking efforts, workshops
- Customized teaching/training efforts for future opportunities with DBE subcontractor, contract specific and/or annually
- · Introduction and reference provided for DBE subcontractor to a prime who has not previously contracted with the DBE firm
- Prime utilization of a DBE subcontractor the prime has not contracted with previously
- Written referral/recommendation to bond/insurance agents, manufacturer, supplier
- Documented efforts fostering DBE participation through administrative and/or technical assistance
- Evidence of negotiation with the DBE firm about current and future Let opportunities
- · Recommendation of local and state services that support small business and access to opportunity: DOA, SBA, WEDC, WPI, etc.
- Advice on bonding, lines of credit, or insurance as required to complete the items quoted and contract requirements

	Active & Aggressive Category	Quality Category	Quantity Category	Scope & Intensity Category	Timing Category	Business Develop't Efforts	Total=
Solicitation Documentation							
Selected Work Items Documentation							
Documentation of Project Information provided to Interested DBEs							
Documentation of Negotiation with Interested DBEs							
Documentation of Sound Reason for Rejecting DBEs							
Documentation of Assistance to Interested DBEs- bonding, credit, insurance, equipment, supplies/materials							
Documentation of Outreach to Minority, Women, and Community organizations and other DBE Business Development Support							
Documentation of other GFE activities							
Overall Total=							

ACTIVE & AGGRESSIVE: Demonstrated through engaged and assertive activity

QUALITY: Demonstrated through essential character of conscientious and serious activity

**QUANTITY:** Demonstrated through a measurable number of activities

SCOPE & INTENSITY: Demonstrated through a rigorous approach to an appropriate and purposeful range of activities

**TIMING:** Demonstrated through engagement efforts beyond simple solicitation, initiated early in the process **BUSINESS DEVELOPMENT INITIATIVES:** Demonstrated by efforts to support business growth and health of DBEs

#### Rating Scale

- Each qualifying activity is worth 5 points per Category
- Documented efforts must receive 55 points or more to qualify for Phase 2 GFE evaluation
  - Pro Forma efforts= 0-50 points
     Perfunctory effort characterized by routine or superficial activities
  - Bona Fide= 55+ points
     Genuine effort characterized by sincere and earnest activities

#### **GFE EVALUATION – PHASE 2**

#### **DBE Office completes:**

- · Review of quote comparisons submitted by Prime
- · Bid analysis to confirm is any bid submitted met the DBE goal
- · Team review of combined efforts documented in Phase 1 and 2 by apparent low bidder

#### **APPENDIX E**

#### **Good Faith Effort Best Practices**

This list is not a set of requirements; it is a list of potential strategies

#### **Primes**

- Ø Prime contractor open houses inviting DBE firms to see the bid "war room" or providing technical assistance.
- Ø Participate in speed networking and mosaic exercises as arranged by DBE office.
- Ø Host information sessions not directly associated with a bid letting.
- Ø Participate in a formal mentor protégé or joint venture with a DBE firm.
- Ø Participate in WisDOT advisory committees i.e. TRANSAC, or Mega Project committee meetings.
- Ø Facilitate a small group DBE 'training session' clarifying how your firm prepares for bid letting, evaluates subcontractors, preferred qualifications, and communication methods.
- Ø Encourage subcontractors to solicit and highlight DBE participation in their quotes to you.
- Ø Quality of communication, not quantity creates the best results. Contractors should be thorough in communicating with DBE firms before the bid and provide any assistance requested to assure best possible bid.

#### **DBE**

- Ø DBE firms should contact primes as soon as possible with questions regarding their quotes or bid; seven days prior is optimal.
- Ø Continually check for contract addendums on the HCCI website through the Thursday prior to letting to stay abreast of changes.
- Ø Review the status of contracts on the HCCI website reviewing the 'apparent low bidder' list and bid tabs at a minimum.
- Ø Prepare a portfolio or list of related projects and prime and supplier references; be sure to note transportation related projects of similar size and scope, firm expertise and staffing.
- Ø Participate in DBE office assessment programs.
- Ø Participate on advisory and mega-project committees.
- Ø Sign up to receive the DBE Contracting Update.
- Ø Consider membership in relevant industry or contractor organizations.
- Ø Active participation is a must. Quote as many projects as you can reasonably work on; quoting the primes and bidding as a prime with the department are the only ways to get work.

# APPENDIX F Good Faith Effort Evaluation Guidance Appendix A of 49 CFR Part 26

I. When, as a recipient, you establish a contract goal on a DOT-assisted contract for procuring construction, equipment, services, or any other purpose, a bidder must, in order to be responsible and/or responsive, make sufficient good faith efforts to meet the goal. The bidder can meet this requirement in either of two ways. First, the bidder can meet the goal, documenting commitments for participation by DBE firms sufficient for this purpose. Second, even if it doesn't meet the goal, the bidder can document adequate good faith efforts. This means that the bidder must show that it took all necessary and reasonable steps to achieve a DBE goal or other requirement of this part which, by their scope, intensity, and appropriateness to the objective, could reasonably be expected to obtain sufficient DBE participation, even if they were not fully successful.

II. In any situation in which you have established a contract goal, Part 26 requires you to use the good faith efforts mechanism of this part. As a recipient, you have the responsibility to make a fair and reasonable judgment whether a bidder that did not meet the goal made adequate good faith efforts. It is important for you to consider the quality, quantity, and intensity of the different kinds of efforts that the bidder has made, based on the regulations and the guidance in this Appendix.

The efforts employed by the bidder should be those that one could reasonably expect a bidder to take if the bidder were actively and aggressively trying to obtain DBE participation sufficient to meet the DBE contract goal. Mere pro forma efforts are not good faith efforts to meet the DBE contract requirements. We emphasize, however, that your determination concerning the sufficiency of the firm's good faith efforts is a judgment call. Determinations should not be made using quantitative formulas.

- III. The department also strongly cautions you against requiring that a bidder meet a contract goal (i.e., obtain a specified amount of DBE participation) in order to be awarded a contract, even though the bidder makes an adequate good faith efforts showing. This rule specifically prohibits you from ignoring bona fide good faith efforts.
- IV. The following is a list of types of actions which you should consider as part of the bidder's good faith efforts to obtain DBE participation. It is not intended to be a mandatory checklist, nor is it intended to be exclusive or exhaustive. Other factors or types of efforts may be relevant in appropriate cases.
- A. (1) Conducing market research to identify small business contractors and suppliers and soliciting through all reasonable and available means the interest of all certified DBEs that have the capability to perform the work of the contract. This may include attendance at pre-bid and business matchmaking meetings and events, advertising and/or written notices, posting of Notices of Sources Sought and/or Requests for Proposals, written notices or emails to all DBEs listed in the State's directory of transportation firms that specialize in the areas of work desired (as noted in the DBE directory) and which are located in the area or surrounding areas of the project.
- (2) The bidder should solicit this interest as early in the acquisition process as practicable to allow the DBEs to respond to the solicitation and submit a timely offer for the subcontract. The bidder should determine with certainty if the DBEs are interested by taking appropriate steps to follow up initial solicitations.
- B. Selecting portions of the work to be performed by DBEs in order to increase the likelihood that the DBE goals will be achieved. This includes, where appropriate, breaking out contract work items into economically feasible units (for example, smaller tasks or quantities) to facilitate DBE participation, even when the prime

contractor might otherwise prefer to perform these work items with its own forces. This may include, where possible, establishing flexible timeframes for performance and delivery schedules in a manner that encourages and facilitates DBE participation.

- C. Providing interested DBEs with adequate information about the plans, specifications, and requirements of the contract in a timely manner to assist them in responding to a solicitation with their offer for the subcontract.
- D. (1) Negotiating in good faith with interested DBEs. It is the bidder's responsibility to make a portion of the work available to DBE subcontractors and suppliers and to select those portions of the work or material needs consistent with the available DBE subcontractors and suppliers, so as to facilitate DBE participation. Evidence of such negotiation includes the names, addresses, and telephone numbers of DBEs that were considered; a description of the information provided regarding the plans and specifications for the work selected for subcontracting; and evidence as to why additional Agreements could not be reached for DBEs to perform the work.
- (2) A bidder using good business judgment would consider a number of factors in negotiating with subcontractors, including DBE subcontractors, and would take a firm's price and capabilities as well as contract goals into consideration. However, the fact that there may be some additional costs involved in finding and using DBEs is not in itself sufficient reason for a bidder's failure to meet the contract DBE goal, as long as such costs are reasonable. Also, the ability or desire of a prime contractor to perform the work of a contract with its own organization does not relieve the bidder of the responsibility to make good faith efforts. Prime contractors are not, however, required to accept higher quotes from DBEs if the price difference is excessive or unreasonable.
- E. (1) Not rejecting DBEs as being unqualified without sound reasons based on a thorough investigation of their capabilities. The contractor's standing within its industry, membership in specific groups, organizations, or associations and political or social affiliations (for example union vs. non-union status) are not legitimate causes for the rejection or non-solicitation of bids in the contractor's efforts to meet the project goal. Another practice considered an insufficient good faith effort is the rejection of the DBE because its quotation for the work was not the lowest received. However, nothing in this paragraph shall be construed to require the bidder or prime contractor to accept unreasonable quotes in order to satisfy contract goals.
- (2) A prime contractor's inability to find a replacement DBE at the original price is not alone sufficient to support a finding that good faith efforts have been made to replace the original DBE. The fact that the contractor has the ability and/or desire to perform the contract work with its own forces does not relieve the contractor of the obligation to make good faith efforts to find a replacement DBE, and it is not a sound basis for rejecting a prospective replacement DBE's reasonable quote.
- F. Making efforts to assist interested DBEs in obtaining bonding, lines of credit, or insurance as required by the recipient or contractor.
- G. Making efforts to assist interested DBEs in obtaining necessary equipment, supplies, materials, or related assistance or services.
- H. Effectively using the services of available minority/women community organizations; minority/women contractors' groups; local, State, and Federal minority/women business assistance offices; and other organizations as allowed on a case-by-case basis to provide assistance in the recruitment and placement of DBEs.

V. In determining whether a bidder has made good faith efforts, it is essential to scrutinize its documented efforts. At a minimum, you must review the performance of other bidders in meeting the contract goal. For example, when the apparent successful bidder fails to meet the contract goal, but others meet it, you may reasonably raise the question of whether, with additional efforts, the apparent successful bidder could have met the goal. If the apparent successful bidder fails to meet the goal, but meets or exceeds the average DBE participation obtained by other bidders, you may view this, in conjunction with other factors, as evidence of the apparent successful bidder having made good faith efforts. As provided in §26.53(b)(2)((vi), you must also require the contractor to submit copies of each DBE and non-DBE subcontractor quote submitted to the bidder when a non-DBE subcontractor was selected over a DBE for work on the contract to review whether DBE prices were substantially higher; and contact the DBEs listed on a contractor's solicitation to inquire as to whether they were contacted by the prime. Pro forma mailings to DBEs requesting bids are not alone sufficient to satisfy good faith efforts under the rule.

VI. A promise to use DBEs after contract award is not considered to be responsive to the contract solicitation or to constitute good faith efforts.

[79 FR 59600, Oct. 2, 2014]

# APPENDIX G (SAMPLE) Forms DT1506 and DT1202

COM	MITME	NT TO SUBCONTRACT TO DE	3E							Wisconsin De	epartment of Transportation
DT1506	6/2020	20 s.84.06(2) Wis. Stats.				Projec	ct(s):				
Primo C	ontractor:										
Fillile C	County:							Letti	ng Date:		
This contract requires that a specified percentage of the work be subcontral disadvantaged business enterprise and that this information be submittee						Т	otal \		of Prime		
in ASP-3. Completion of the following information indicates your intent in these contract requirements.									Contract:		
tnese coi	ntract requ	irements.							Goal %: Goal \$:	\$	
						וטטו	L COII	uact	Juai Ş.	٦	Goal met
This for	m must b	e completed and returned for THIS co	ntract. S	ee reverse si	de for instruction	ns.					
Α	V	NAME OF DBE SUBCONTRACTOR		TYPE OF V	VORK		S	UBCO	NTRACT	\$ VALUE	Government Use Only Adjusted Amounts
			A (\$)	\$		T	OTAL	%		#DIV/0!	
		SUBTOTAL DBE \$ VALUE	V (\$)	\$	-	T	OTAL	%		#DIV/0!	
Α	A V NAME OF DBE SUPPLIER AND/OR			TYPE OF MATERIAL		SUBCONTRACT \$ \			NTRACT	\$ VALUE Government Use Only Adjusted Amounts	
		MANUFACTURER (see #3 on Instructions)									
			A (\$)	\$		T	OTAL	%		#DIV/0!	
		SUBTOTAL DBE \$ VALUE	V (\$)	**		TOTAL %		#DIV/0!			
					EST. # OF	E	T #	OF TR	IICKE		Government Use Only
Α	V	NAME OF DBE TRUCKING FIRM	MATER	IIAL HAULED	TON/C.Y.	REQ'D		\$ VALUE	Adjusted Amounts		
						0=		L=			
						0=		L=			
						0=		L=			
						0=		L=			
			A (\$)	\$	-			TAL 9		#DIV/0!	
		SUBTOTAL DBE \$ VALUE	V (\$)	\$	-	TOTAL %			#DIV/0!		
			A (\$)	\$	-			TAL 9			
		GRAND TOTAL DBE \$ VALUE	V (\$)	\$	-	TOTAL %					
Loodify th	ot orronge	monto have been made for the foregoing week	le with the		tractors   further	undara				-	into mont or
		ments have been made for the foregoing work will result in appropriate sanctions, which may									
	0.	- Owned Touris Head on During		Governme	nt Use Only App	roved /	Amou	nts	x		
O = Owned Trucks Used on Project L = Leased Trucks Used on Project		A \$		%				(Authorize	d Agent)		
	-	···- <b>-</b>		V \$		%				Dat	e
				Total \$		%				submission method:	DBE_Alert@dot.wi.gov
A = Assigned (DBE Conscious) V = Voluntary (DBE Neutral)			Signature:				Or:  Mail to: Wisconsin Department of Transp		ent of Transportation		
			Date:					DBE Programs Office			
					iver granted: <b>Yes</b>		No	Π		PO Box 7986 Madison,WI 5370	7-7986
				Proposal N						,	

Ins	tructions	For Completing Commitment To Subcontract To DBE Form:
1	(DBE Co	lance with the DBE Regulations (49 CFR part 26), WisDOT is tracking Assigned Goals for DBE's inscious) and Voluntary Usage of DBE Firms (DBE Neutral). DBE participation reported on this be used to periodically adjust (DBE Conscious and DBE Neutral) components of WisDOT's overal BE goal.
2	used to r above as to meet t amount a	DBE firm listed on this form, place an "x" in the appropriate column to indicate whether it will be neet the Assigned Goal (A) and/or whether it is used on a Voluntary basis (V). Any achievement signed goals should be reported as a voluntary achievement. If you indicate that a firm will be used both assigned and voluntary goals, indicate the dollar amount attributable to assigned goals and the attributable to the voluntary goal. Our objective is to capture all DBE achievement you generate. The is an example:
	a. b.	The total contract amount is \$100,000 and the DBE goal is 10% or \$10,000 in DBE participation If \$10,000 is the subcontract dollar value to ADBE Landscaping Co. then \$10,000 would be
	c.	Assigned (DBE Conscious) and you would place an "x" in the "A" column  If \$15,000 is the subcontract dollar value to ADBE Landscaping Co. then \$10,000 would be Assigned (DBE Conscious) and you would place an "x" in the "A" column and ADBE Landscaping Co. would be listed on the next line for \$5,000 which would be Voluntary (DBE Neutral) and an "x" would be placed in the "V" column
3	supplies. DBE goa a 10 perc to find o	Introduction of the context of the DBE goal if the DBE is a manufacturer of their materials or arthment will give full credit toward the DBE goal if the DBE is a manufacturer of their materials or The department will give 60 percent credit or brokerage fee set by industry's standard toward the all if the DBE is merely a supplier of these materials or supplies. Drop shipment by a supplier will earn ent DBE credit. It is the Prime Contractor's responsibility to use the Bidder's List or UCP Directory at if the DBE is considered a supplier or a manufacturer before listing them on Commitment to ract to DBE form. WisDOT will apply the appropriate credit when approving the form.
4		npleting the form, if it does not indicate that the DBE goal has been met or exceeded, please and supply the necessary documentation on the Documentation of Good Faith Effort form
Ins	tructions	For Completing Attachment A Form:
5	Section 2 on the co	26.53 (49 CFR part 26) requires written confirmation of participation from each DBE firm to be used ontract. Please submit one copy of a completed Attachment A, Confirmation of Participation form, DBE firm to be used on this contract. Each form must be signed by the Prime Contractor, the hiring or (if applicable) and the DBE Firm specified on the form.
6	DBE cre	diting for the trucking industry is achieved in the following manner:
	a. b.	A minimum of one truck owned by the DBE must be used on the contract. Full DBE credit is given for owned trucks and trucks leased from another DBE.
	d.	Trucks leased from non-DBE firms will be given DBE credit of 10% of the subcontract value.  All trucks used for credit must be listed and approved on the DBE firm's Schedule of  Owned/Leased Vehicles for DBE Credit and/or a WisDOT approved trucking utilization plan.
	DB	the Prime Contractor's and the DBE firm's responsibility to ensure that utilization of trucks and the Ecredit earned is in accordance with the above and will yield the subcontract dollar value listed on Commitment to Subcontract to DBE form.
Plea	ase submit	documents to: DBE_Alert@dot.wi.gov
	tify Project	#, Proposal#, Let date, Business Name, DT1506 and/or Attachment A in the <b>email subject line</b>

CONFIRMATI	ON OF PART	CIPATION						
Project I.D.:				Proposal Number:				
Letting Date:				Total \$ Value of Pri	ime Contract:			
Letting Date.				Total & Value of 1	ille Collitact.			
Name of DBE	Firm Participa	ting in this Co	ntract:					
	·							
Name of the Prime/Subcontractor who hired the DBE Firm: (list all names of tiers if more than one)								
Type of Work	or Type of Mat	erial Supplied:						
Total Subcont	ract Value:							
ļ				D: C				
_				Prime Contractor Repre	sentative's bignat	ure		
FOR PRIME CO	INTRACTORS C	INLY:		Prime Contractor Representative's Name (Print Name)				
	e arrangements wit							
	of work listed or sup alue listed above.	ipiy trie materianin	IICated above to	Prime Contractor (Print 0	Company Name)			
-								
1				Date				
1								
				Participating DBE Firm Representative's Signature				
	ATING DBE FIR							
	e arrangements wil							
Contractor to perform the type of work or supply the material indicated above for the subcontract value listed above.				Participating DBE Firm Representative's Name (Print Name)				
FOR DBE TRUCKING FIRMS ONLY:  I certify that I will utilize, for DBE credit, only trucks listed on my WisDOT			D					
			Participating DBE Firm (Print Company Name)					
approved Schedule of Owned/Leased Vehicles for DBE Credit form and I will be utilizing the number of trucks and material hauled as listed below.				Date				
	<del></del>			Date				
# Owne	d Trucks	# Lease	d Trucks	# Estimated T	ons/C.Y.	Material(s) Hauled		
						(-)		

Official Form DT1506 can be found here: <a href="www.wisconsindot.gov/DBEcontracting">www.wisconsindot.gov/DBEcontracting</a>



#### DOCUMENTATION-OF-GOOD-FAITH-EFFORT-

Wisconsin-Department-of-Transportation

V	DT12023/2020	Transportatio
++		

Project ID	Proposal-No.	Letting	
Prime Contractor	County		
Person-Submitting Document	Telephone-Number		
Address			

All-bidders-must-undertake-necessary-and-reasonable-steps-to-achieve-the-assigned-DBE-contract-goal-perfederal regulatory guidance at 49 CFR Part 26. Bidders use this form to document all efforts employed to meet the assigned goal as a record of contractor good faith efforts (GFE). Refer to ASP3 or 49 CFR Part 26 for guidance-on-actions-that-demonstrate-good-faith-effort.

It is critical to list all efforts, attach documentation, and follow the instructions to complete this submission. Documentation-of-good-faith-effort-includes-copies-of-each-DBE-and-non-DBE-subcontractor-quote-submitted-tothe bidder for the same line items. Utilize the sample documentation logs to document and organize efforts...

Submit-good faith effort documentation per ASP-3 guidelines.

Instructions: Provide a narrative description of all activities pursued to demonstrate good faith efforts, any corresponding documentation, and applicable explanation on separate pages. Include the following items, organized-in-the-order-listed-below.

#### 1.→ Solicitation Documentation:

- a.→ Purpose: To identify all reasonable and available activities the bidder performed to solicit the interest-of-all-certified-DBEs-who-have-the-capacity-and-ability-to-perform-work-on-the-project.-Allsolicitation-efforts-should-begin-as-early-as-possible-to-ensure-DBEs-have-ample-time-torespond-and-ask-questions.
- b.→ Action: Identify and list-all-activities engaged in to solicit-DBEs using all reasonable and available means such as written notice and follow-up communications; substantiveconversations; pre-bid-meetings; networking-events; market-research; advertising.

#### 2.→ Selected·Work·Items·Documentation:

- a.→ Purpose: To ensure that all work items are broken out into economically feasible units to facilitate DBE-participation. This must occur even when you prefer to perform the work yourself.
- b.→ Action: Identify economically feasible work units to be performed by DBEs to include activities such as: list of work items to be performed; breaking up of large work items into smaller tasks or quantities; flexible time frames for performance and delivery schedules.

#### 3.→ Documentation of Project Information provided to Interested DBEs:

- a.→ Purpose: To provide interested DBEs with adequate information about the plans, specifications, and any other contractual requirements in a timely manner to assist DBEs in response to solicitation.
- b. Action: Provide DBEs access to plans, specifications, and other contract requirements. Early solicitation allows ample opportunity to provide project information, links to Let advertisements, and-substantive-engagement-with-DBEs.

#### 4.→ Documentation of Negotiation with Interested DBEs:

- a.→ Purpose: To ensure that negotiations with interested DBEs were made in good faith providing evidence as to why agreements could not be reached for DBEs to perform work.
- b. Action: Provide-sufficient evidence to demonstrate that good-faith negotiations took-place. Merely-sending-out-solicitations requesting-bids from DBEs does not constitute sufficient good-faith efforts. A bidder-using good-business judgment-considers a number of factors in negotiating with all subcontractors, and the firm's price and capabilities in addition to contract goals are taken into consideration. However, the fact that there may be some additional costs involved in finding and using DBEs is not in itself sufficient reason for failing to meet the DBE goal as long as costs are reasonable. (see 49 CFR Part 26 Appendix A)

#### 5.→ Documentation·of·Sound·Reason·for·Rejecting·DBEs:

- a.→ Purpose: To ensure that bidders avoid rejecting DBEs as unqualified without sound reasons. Reasons for rejection must be based on thorough investigation of DBE capabilities.
- b. Action: Provide-sufficient evidence to demonstrate that DBE-was rejected for sound reasons such as past performance, relevant business experience and stability, safety record, business ethic and integrity, technical capacity, other tangible factors.

#### 6.→ Documentation·of·Assistance·to·Interested·DBEs-·Bonding,·Credit,·Insurance,·Equipment,· Supplies/Materials:·

- a.→ Purpose: To assist interested DBEs in obtaining bonds, lines of credit, insurance, equipment, supplies, materials, and other assistance or services.
- b.→ Action: Assist-interested DBEs in obtaining bonding, lines of credit or insurance, and provide technical assistance or information related to plans, specifications, and project requirements. Assist DBEs in obtaining equipment, supplies, materials or other services related to meeting project requirements (excluding supplies or equipment the DBE purchases from the prime).

### 7.→ Documentation of outreach to Minority, Women, and Community Organizations and other DBE Business Development Support:

- a.→ Purpose: To effectively use the services of minority, women, and community organizations as well as contractors' groups, local, state, and federal business assistance offices and organization that provide assistance in recruiting and supporting DBEs, as well as participation in activities that support DBE business development.
- b.→ Action: Contact organizations and agencies for assistance in contacting, recruiting, and providing support to DBE subcontractors, suppliers, manufacturers, and truckers at least 14 days before bid opening. Participate in or host activities such as networking events, mentor-protégé programs, small business development workshops, and others consistent with DBE support.

Return to: Wisconsin-Department of Transportation DBE-Program-Office PO-Box-7965 Madison, WI-53707-7965 DBE\_Alert@dot.wi.gov

	certify that I have utilized comprehensive good faith efforts to solicit and utilize DBE firms to meet the DBE participation requirements of this contract proposal, as demonstrated by my responses and as specified in Additional Special Provision 3 (ASP-3).									
į	I-certify that the information given in the Documentation of Good Faith Efforts is t	true-and-correct-to-the-best-of-my-knowledge-and-belief.··								
	l-further-understand-that-any-willful-falsification,-fraudulent-statement,-or-misrep involve-debarment-and/or-prosecution-under-applicable-state-(Trans-504)-and-Fe									
į										
		(Bidder/Authorized Representative Signature)								
į	90.00	8								
į		(Print-Name)								
į	99.99									
į		(Title)								
į										

## Good·Faith·Effort·-·Sample·Documentation·Logs

The sample logs below are provided as guides rather than exhaustive list. See ASP3, Appendix A for additional examples of demonstrable good faith efforts. Attach documentation for each activity listed.

Acceptable-forms-of-documentation-include-copies-of-solicitations-sent-to-DBEs, notes-from-substantive-conversations-and-negotiations-with-DBEs, copies-of-advertisements-placed, email-communications, all-quotes-received-from-DBEs-and-from-all-subcontractors-who-were-considered-alongside-DBE-quotes, proof-of-attendance-at-applicable-networking-events; flyers-for-events-or-workshops-for-DBEs-offered-by-the-prime, and-other-physical-records-of-good-faith-efforts-activities.

### SOLICITATION-LOG-

Date	Activity Name-of-DBE-Solicited		Follow-up	
4/1/2020 Sent·May·Let·solicitation		Winterland · Electric	Spoke-with-Mark-Winterland-on-4/15/20-to-ask-if-	
			he-would-quote-	

## SELECTED WORK-ITEMS-SOLICITED LOG

Work-Type	DBE-Firm	Contact-Person	Date	Contact·Mode
Payament Markins	ABC-Marking	Leslie·Lynch	4/1/2020	Email; phone
Pavement·Marking	#1-Marking-Co.	Mark-Smart	4/1/2020	Email;·left·VM
Flactrical	Winterland·Electric	Tabitha-Tinker	4/3/2020	Email,·left·VM
Electrical	Superstar-Wiring	Jose·Huascar	4/3/2020	Email; phone

## INFORMATION-PROVIDED-LOG

Request- Date	DBE-Firm	Information·Requested·&·Provided	Response- Date
4/1/2020	Winterland Electric	Requested-info-on-electrical-requirements;-provided- plan-and-link-to-specs	4/3/2020
4/21/2020	Absolute-Construction	Wanted to know how and when supplies are paid for by WisDOT; referred to spec that covers stockpiling	4/21/2020

## NEGOTIATIONS:LOG

Date	DBE-Firm Contact-Name		Work-Type	Quotes- Rec'd?	Considere d-for- project?	If-not-selected, why?
4/12/2020	4/12/2020 ABC-Landscape John-Dean		Erosion-Control	Yes	No	Cannot-perform-all-items
4/17/2020	4/17/2020 Wild-Ferns Sandy-Lynn		Erosion-Control	Yes	Yes	
4/20/2020	#1-Marking	Mark-Smart	Electrical	Yes	Yes	

#### ASSISTANCE-LOG

Date	DBE-Firm Contact-Person		Assistance-Provided	
4/1/2020	ABC-Sawing	Jackie-Swiggle	Informed·DBE·on·how·to·obtain·bonding	
4/17/2020	Supreme-Construction		Provided-contact-for-wholesale-supply- purchase	

## OUTREACH-&-BUSINESS-DEVELOPMENT-LOG

Date	Agency/Organization- Contacted	Contact-Person	Assistance Requested
4/1/2020 Women-in-Construction		LaTonya·Klein	Contact-information-for-woman-owned-suppliers
4/28/2020	WBIC	Sam-Smith	Asked-for-information-to-provide-to-DBE-regarding- financing-programs-through-WBIC

Official Form DT1202 can be found here: <a href="www.wisconsindot.gov/DBEcontracting">www.wisconsindot.gov/DBEcontracting</a>

## ADDITIONAL SPECIAL PROVISION 4

This special provision does not limit the right of the department, prime contractor, or subcontractors at any tier to withhold payment for work not acceptably completed or work subject to an unresolved contract dispute.

## **Payment to First-Tier Subcontractors**

Within 10 calendar days of receiving a progress payment for work completed by a subcontractor, pay the subcontractor for that work. The prime contractor may withhold payment to a subcontractor if, within 10 calendar days of receipt of that progress payment, the prime contractor provides written notification to the subcontractor and the department documenting "just cause" for withholding payment.

The prime contractor is not allowed to withhold retainage from payments due subcontractors.

## **Payment to Lower-Tier Subcontractors**

Ensure that subcontracting agreements at all tiers provide prompt payment rights to lower-tier subcontractors that parallel those granted first-tier subcontractors in this provision.

# Additional Special Provision 6 ASP 6 - Modifications to the standard specifications

Make the following revisions to the standard specifications:

## 102.1 Prequalifying Bidders

Replace paragraph two with the following effective with the October 2020 letting:

(2) Furnish a dated prequalification statement on the department's form at least 10 business days before the time set for the letting to close.

## 102.6 Preparing the Proposal

Replace the entire text with the following effective with the October 2020 letting:

#### 102.6.1 General

- (1) Submit completed proposals on the department's bidding proposal described in 102.2. Submit legible information only. Write everything in ink, by typewriter, or by computer-controlled printer. Provide all dollar amounts in dollars and cents, in numerals. Attach all addenda to the submitted proposal.
- (2) Properly execute the proposal. Place the required signatures, in ink, in the space provided on the bidding proposal as indicated below:

### **ENTITY SUBMITTING PROPOSAL**

## **REQUIRED SIGNATURE**

Individual The individual or a duly authorized agent.

Partnership A partner or a duly authorized agent.

**Joint venture** A member or a duly authorized agent of at least one of the joint venture

firms.

**Corporation** An authorized officer or duly authorized agent of the corporation. Also show

the name of the state chartering that corporation and affix the corporate

seal.

Limited liability company A manager, a member, or a duly authorized agent.

- (3) Instead of using the schedule of items provided on the department's bidding proposal, the bidder may submit a substitute schedule with the proposal. Use a format for the substitute schedule conforming to the department's guidelines for approval of a bidder-generated schedule of items. Obtain the department's written approval before using a substitute schedule.
- (4) Provide a unit price for each bid item listed in the schedule of items. Calculate and show, in the bid amount column, the products of the respective unit prices and quantities. For a lump sum bid item, show the same price in the unit price column and in the bid amount column pertaining to that bid item. Show the total bid obtained by adding the values entered in the bid amount column for the listed bid items.
- (5) If a unit price or lump sum bid already entered in the proposal needs to be altered, cross out the entered unit price or lump sum bid with ink or typewriter and enter the new price above or below and initial it in ink.
- (6) A change that the bidder makes in the proposal is not an alteration if the bidder makes that change as directed in a specific instruction contained in an addendum.

## 102.6.2 Disadvantaged Business Enterprise (DBE) Commitment

- (1) Before the letting is closed, submit the following documentation for proposals with a DBE goal:
  - 1. Commitment to subcontract to DBE on department form DT1506.
  - 2. Attachment A for each subcontractor listed on the DT1506.
  - 3. If the DBE goal is not attained, certificate of good faith efforts on department form DT1202.
- (2) Within 24 hours after the letting is closed, email all supplemental documentation for the DT1202 verifying efforts made to attain the DBE goal to DBE\_Alert@dot.wi.gov.

### 102.7.3 Department Will Reject

Replace paragraph one with the following effective with the January 2021 letting:

- (1) Proposals are irregular and the department will reject and will not post them if the bidder:
  - 1. Does not furnish the required proposal guaranty in the proper form and amount as specified in 102.8.
  - Does not submit a unit price for each bid item listed, except for lump sum bid items where the bidder may show the price in the bid amount column for that bid item.
  - 3. Includes conditions or qualifications not provided for in the department-supplied bidding proposal.
  - 4. Submits a bid on a bidding proposal issued to a different bidder without obtaining departmental authorization to do so
  - 5. Submits a bid that contains unauthorized revisions in the name of the party to whom the bidding proposal was issued.
  - 6. Submits a schedule of items with illegibly printed bid item numbers, descriptions, or unit prices.
  - 7. Submits a schedule of items for the wrong contract.
  - 8. Submits a bidder-generated schedule of items with an incorrect bid item number and incorrect description for a single bid item.
  - 9. Omits a bid item or bid items on a bidder-generated schedule of items.
  - 10. Submits a materially unbalanced bid.
  - 11. Does not sign the proposal.
  - 12. Does not submit the DBE forms and required supplemental documentation of the good faith efforts as specified in 102.6.2.

## 102.12 Public Opening of Proposals

Replace paragraph one with the following effective with the October 2020 letting:

(1) The letting will close at the time and place indicated in the notice to contractors. The department will publicly open and post the total bid for each proposal on the Bid Express web site beginning at noon on the day after the letting is closed except as specified in 102.7.3 and 102.8. If a proposal has no total bid shown, the department will not post the bid. After verification for accuracy under 103.1, the department will post bid totals on the HCCI web site.

https://wisconsindot.gov/Pages/doing-bus/contractors/hcci/bid-let.aspx

### 103.1 Consideration of Proposals

Replace paragraph one with the following effective with the October 2020 letting:

- (1) Following the public opening of the proposals received, the department will compare them based on the summation of the products of the quantities of work listed and the contract unit prices offered. In case of discrepancies, errors, or omissions, the department will make corrections as specified in 102.7.1. In awarding contracts, the department, in addition to considering the amounts stated in the proposals, may consider one or more of the following:
  - 1. The responsibility of the various bidders as determined from a study of the data required under 102.1.
  - 2. The responsiveness of the bid as determined under 102.6.
  - 3. Information from other investigations that the department may make.

## 107.17.1 General

Replace paragraph four with the following effective with the November 2020 letting:

- (4) Comply with the railroad's rules and regulations regarding operations on or near the railroad right-of-way as follows:
  - When working on the railroad right-of-way.
  - When working within 25 feet of the track centerline or adjacent facilities, including equipment or extensions of equipment that can fall within 25 feet of the track centerline or adjacent facilities.

If the railroad's chief engineering officer requires, arrange with the railroad to obtain the services of qualified railroad employees to protect railroad traffic through the work area. Bear the cost of these services and pay the railroad directly. Notify the railroad's representative, specified in the project special provisions, in writing at least 40 business days before starting work near a track. Provide the specific time planned to start the operations.

#### 109.6.3.3 Retainage

Delete paragraph two effective with the December 2020 letting:

## 450.2.1 Acronyms and Definitions

Add the following definitions to 450.2.1(2) effective with the November 2020 letting:

**Butt Joint** A transverse joint between existing and newly paved surfaces, formed by

milling or sawing a vertical notch into the existing surface and then paving

against the notch.

Echelon Paving Paving two or more adjacent lanes with adjacent pavers offset from each

other by 200 feet or less.

Notched Wedge Joint A longitudinal joint consisting of a wedge placed at the edge of the initially

paved lane with an overlapping wedge placed on the subsequent lane.

Tandem Paving Paving two or more adjacent lanes with adjacent pavers offset from each

other by more than 200 feet.

Vertical Joint A longitudinal joint between 2 paved lanes with a vertical or nearly vertical

interface between the adjacent mats.

## 450.3.2.8 Jointing

Replace paragraph two with the following with the November 2020 letting:

(2) Where placing against existing HMA pavement, saw or mill the existing mat to form a full-depth joint.

Replace paragraphs five and six with the following effective with the November 2020 letting:

- (5) At the prepave meeting, submit documentation to the engineer that includes the brand name and model of each extruding and compacting device proposed for notched wedge joint construction. Alternatively, submit pictures of fabricated wedging and compacting devices. Do not use devices before engineer approval.
- (6) For notched wedge joints, construct and shape the wedge for each layer using the engineer-approved extruding device and compacting device that will provide a uniform slope and will not restrict the main screed. Compact the wedge with a weighted roller wheel or vibratory plate compactor the same width as the wedge. Clean and apply tack coat to the wedge surface and both notches before placing the adjacent lane.
- (7) For butt and vertical joints, clean and apply tack coat to promote bonding and seal the joint.
- (8) If paving in echelon, the contractor may use a vertical or notched wedge joint. Joints paved in echelon need not be tack coated.

## 460.2.2.3 Aggregate Gradation Master Range

Replace table 460-1 with the following effective with the November 2020 letting:

TABLE 460-1 AGGREGATE GRADATION MASTER RANGE AND VMA REQUIREMENTS

	PERCENT PASSING DESIGNATED SIEVES									
SIEVE	NOMINAL SIZE									
SILVE	No. 1 (37.5 mm)	No. 2 (25.0 mm)	No.3 (19.0 mm)	No. 4 (12.5 mm)	No. 5 (9.5 mm)	No. 6 (4.75 mm)	SMA No. 4 (12.5 mm)	SMA No. 5 (9.5 mm)		
50.0-mm	100									
37.5-mm	90 - 100	100								
25.0-mm	90 max	90 - 100	100							
19.0-mm		90 max	90 - 100	100			100			
12.5-mm			90 max	90 - 100	100		90 - 97	100		
9.5-mm				90 max	90 - 100	100	58 - 80	90 - 100		
4.75-mm					90 max	90 - 100	25 - 35	35 - 45		
2.36-mm	15 - 41	19 - 45	23 - 49	28 - 58	32 - 67	90 max	15 - 25	18 - 28		
1.18-mm						30 - 55				
0.60-mm							18 max	18 max		
0.075-mm	0 - 6.0	1.0 - 7.0	2.0 - 8.0	2.0 - 10.0	2.0 - 10.0	6.0 - 13.0	8.0 - 11.0	8.0 - 12.0		
% VMA	11.0 min	12.0 min	13.0 min	14.0 min <sup>[1]</sup>	15.0 min <sup>[2]</sup>	16.0 - 17.5	16.0 min	17.0 min		

<sup>[1] 14.5</sup> for LT and MT mixes.

### 522.2 Materials

Replace paragraph three with the following effective with the January 2021 letting:

- (3) Manufacture precast reinforced concrete pipe, cattle pass, and apron endwalls in a plant listed under precast concrete fabricators on the APL. Conform to the specified AASHTO standard materials requirements except as follows:
  - The contractor may use cement conforming to 501.2.1 or may substitute for portland cement at the time of batching conforming to 501.2.6 for fly ash, 501.2.7 for slag, or 501.2.8 for other pozzolans. In either case the maximum total supplementary cementitious content is limited to 30 percent of the total cementitious content by weight.

## 532.2.1 General

Replace paragraph one with the following effective with the November 2020 letting:

(1) Furnish structural steel conforming to ASTM as follows:

<= 1/2 inch thick structural tube and pipe	ASTM A500 grade C
> 1/2 inch thick structural tube and pipe	API 5L PSL 2 grade 46 or ASTM 1085
Tapered vertical supports	ASTM A595 grade A or ASTM A572 grade 55
Multi-sided or greater than 26-inch diameter round tapered poles.	ASTM A572 grade 65
Structural angles and plates	ASTM A709 grade 36

<sup>[2] 15.5</sup> for LT and MT mixes.

## 532.3.8 Acceptance and Inspection

Add the following new subsection effective with the November 2020 letting:

## 532.3.8 Acceptance and Inspection

- (1) Demonstrate to the engineer that electrical and mechanical systems for each high mast tower installation are fully operational. The department will not accept an installation until the engineer is satisfied that it functions properly.
- (2) Inspect completed "S" or "L" designated structures before opening to public traffic conforming to the BOS structure inspection manual part 4 for sign, signal, and high mast towers available at:

https://wisconsindot.gov/Pages/doing-bus/eng-consultants/cnslt-rsrces/strct/inspection-manual.aspx

Ensure that a department-certified active team leader for sign/signal inspections, listed on the department's highway structures information system (HSIS) website, performs inspections. Conform to the following:

- Notify the engineer at least 5 business days before inspection.
- Ensure that the team leader performing inspections submits the signed inspection reports and provides punch list items as maintenance items in the inspection report to the engineer within one business day after completing each inspection. Submit that signed final inspection report to the engineer and HSIS at:

https://wisconsindot.gov/Pages/doing-bus/eng-consultants/cnslt-rsrces/strct/hsi.aspx

- Notify the engineer and region ancillary structure project manager upon completion of the punch list items.

#### 550.2.1 Steel Piles and Pile Shells

Replace paragraph three with the following effective with the November 2020 letting:

(3) For steel pipe sections and steel pile shells for cast-in-place concrete piles, use ASTM A252 grade 3 steel.

#### 608.2.1 Pipe

Replace paragraph three with the following effective with the January 2021 letting:

- (3) Manufacture precast reinforced concrete pipe for storm sewer in a plant listed under precast concrete fabricators on the APL. Conform to the specified AASHTO materials requirements for the class of precast concrete pipe specified except as follows:
  - The contractor may use cement conforming to 501.2.1 or may substitute for portland cement at the time of batching conforming to 501.2.6 for fly ash, 501.2.7 for slag, or 501.2.8 for other pozzolans. In either case the maximum total supplementary cementitious content is limited to 30 percent of the total cementitious content by weight.

#### 611.2 Materials

Replace paragraph three with the following effective with the January 2021 letting:

- (3) For precast structures conform to AASHTO M199 for circular structures and ASTM C913 for square and rectangular structures. Manufacture in a plant listed under precast concrete fabricators on the APL. Conform to the specified AASHTO materials requirements for the structure specified except as follows:
  - Use concrete with 470 pounds or more cementitious material per cubic yard.
  - The contractor may use cement conforming to 501.2.1 or may substitute for portland cement at the time of batching conforming to 501.2.6 for fly ash, 501.2.7 for slag, or 501.2.8 for other pozzolans. In either case the maximum total supplementary cementitious content is limited to 30 percent of the total cementitious content by weight.
  - For wet cast use air-entrained concrete with 7.0 percent +/- 1.5 percent air content.

## 614.3.2.1 Installing Posts

Replace paragraphs four and five with the following effective with the December 2020 letting:

- (4) For bid items 614.0220, 0230, and 2500; do not trim posts before installation and mark one face of each post as follows:
  - Draw an embedment depth line.
  - Above the embedment line, write the post length.
  - Posts 3 through 8 of bid item 614.0220 do not require marking.

Install posts with the markings on the roadway side. Ensure the markings remain on the posts until guardrail final acceptance.

- (5) Ensure that posts are at least the minimum length and minimum embedment the plans show before cutting post tops to the finished elevation. After installation, the engineer may direct the contractor to remove and reinstall up to 5% of the posts to verify they were placed to the required plan depth. If a post is embedded less than the required plan depth, the engineer may direct additional sampling. Re-install sampled posts at the locations and to the depths the plans show. Replace posts and other components that are damaged during sampling.
- (6) Provide offset block-mounted reflectors as the plans show.

## 650.3.7 Structure Layout Staking

Replace the entire text with the following effective with the January 2021 letting:

- (1) Set construction stakes or marks on a line offset from the structure centerline or on a reference line, whichever is appropriate, for both roadway and substructure units. Establish the plan horizontal and vertical positions to the required accuracy. Also, set and maintain stakes and marks as necessary to support the method of operations. Locate stakes and marks to within 0.02 feet of the true horizontal position, and establish the grade elevation to within 0.01 feet of true vertical position.
- (2) For girder bridges, the department will compute deck grades with contractor-supplied girder elevation data.
- (3) For slab span bridges, the department will compute slab grades using contractor-supplied falsework settlement and deflection data at tenth points along slab edges, the crown, and reference line locations. Before releasing falsework, survey top-of-slab elevations at the centerline of the abutments and at the 5/10th point along slab edges, the crown, and reference line locations to verify the camber.

## 710.2 Small Quantities

Replace paragraph one with the following effective with the November 2020 letting:

- (1) For contracts with only small quantities of material subject to testing, as defined under specific contract QMP provisions, modify the requirements of 710 as follows:
  - 1. The contractor may submit an abbreviated quality control plan as allowed in 701.1.2.3.
  - 2. The engineer may accept aggregate based on documented previous testing and non-random start-up gradation testing as allowed in 710.5.6.1.

## 710.4 Concrete Mixes

Replace paragraph two with the following effective with the January 2021 letting:

- (2) At least 3 business days before producing concrete, document that materials conform to 501 unless the engineer allows or individual QMP specifications provide otherwise. Include the following:
  - 1. For mixes: quantities per cubic yard expressed as SSD weights and net water, water to cementitious material ratio, and air content.
  - 2. For cementitious materials and admixtures: type, brand, and source.
  - For aggregates: absorption, SSD bulk specific gravity, wear, soundness, freeze thaw test results if required, and air correction factor. Also include proposed combined gradation limits and target individual gradations, including P200 limits..

### 710.5.6 Aggregate Testing

Replace the entire text with the following effective with the January 2021 letting:

#### 710.5.6.1 General

- (1) Test aggregate gradations during concrete production. The department will accept non-random start-up testing during concrete production for the following:
  - Small quantities, as defined in 715.1.1.2, of class I concrete placed under 715.
  - Less than 400 cubic yards of class II ancillary concrete placed under the contract.

## 710.5.6.2 Gradation Testing During Concrete Production

- (1) Test aggregate gradation during concrete production batching either at a central mix batch plant or at a ready mix plant. The contractor's concrete production QC tests can be used for the same mix design on multiple contracts.
- (2) Conform to combined gradation limits either calculated using department form WS3012 or custom limits approved as a part of the contractor's quality control plan. For class II concrete, also conform to the additional combined gradation requirements specified for class I concrete in 715.2.2.
- (3) Determine the complete gradation using a washed analysis for both fine and coarse aggregates. Report results for the 1 1/2", 1", 3/4", 1/2", 3/8", #4, #8, #16, #30, #50, #100, and #200 sieves.
- (4) Contractor QC testing frequency is based on the cumulative plant production for each mix design across multiple WisDOT contracts.

TABLE 710-1 PLANT PRODUCTION QC GRADATION TESTING FREQUENCY

Daily Plant Production Rate for WisDOT Work	Minimum QC Frequency per Stockpile		
250 cubic yards or less	one test per cumulative total of 250 cubic yards		
more than 250 through 1000 cubic yards	one test per day		
more than 1000 cubic yards	two tests per day		

(5) Department QV testing frequency is based on the quantity of each mix design placed under each individual WisDOT contract.

TABLE 710-2 CONTRACT PLACEMENT QV GRADATION TESTING FREQUENCY

Anticipated Daily Placement Rate Each WisDOT Contract	Minimum QV Frequency per Stockpile	
less than or equal to 1000 cubic yards	one test per 5 days of placement	
more than 1000 cubic yards	two tests per 5 days of placement	

## 715.2.2 Combined Aggregate Gradation

Replace the entire text with the following effective with the January 2021 letting:

- (1) Ensure that the combined aggregate gradation conforms to the following, expressed as weight percentages of the total aggregate:
  - 1. One hundred percent passes the 2-inch sieve.
  - 2. For mixes containing size No. 2 stone, the percent passing the 1-inch sieve is less than or equal to 89. The engineer may waive this requirement if the clear spacing between reinforcing bars is less than 2 inches.
  - 3. The percent passing the No. 4 sieve is less than or equal to 42, except if the coarse aggregate is completely composed of crushed stone, up to 47 percent may pass the No. 4 sieve. For pavement, coarse aggregate may be completely composed of crushed concrete, in which case up to 47 percent may pass the No. 4 sieve.
  - 4. The percent passing the No. 200 sieve is less than or equal to 2.3 percent.

#### 716.2.1 Class II Concrete

Replace paragraphs four through six with the following effective with the November 2020 letting:

- (4) Provide concrete with a 28-day compressive strength that equals or exceeds the following:
  - If the contract specifies f'c, then f'c.
  - If the contract does not specify f'c, then 3000 psi.

## **ERRATA**

## 101.3 Definitions

Adopt AASHTO change order definition.

**Change order** A written order to the contractor detailing changes to the specified work quantities or modifications within the scope of the original contract..

Delete existing contract change order, contract modification, and contract revision definitions.

## 460.2.7(1) HMA Mixture Design

Correct table 460-2 errata by eliminating plasticity index requirements for LT, MT, and HT mixes.

#### **TABLE 460-2 MIXTURE REQUIREMENTS**

Mixture type	LT	MT	HT	SMA
LA Wear (AASHTO T96)				
100 revolutions(max % loss)	13	13	13	13
500 revolutions(max % loss)	50	45	45	35
Soundness (AASHTO T104) (sodium sulfate, max % loss)	12	12	12	12
Freeze/Thaw (AASHTO T103 as modified in CMM 860.2.7) (specified counties, max % loss)	18	18	18	18
Fractured Faces (ASTM D5821 as modified in CMM 860.7.2) (one face/2 face, % by count)	65/	75 / 60	98 / 90	100/90
Flat & Elongated (ASTM D4791) (max %, by weight)	5 (5:1 ratio)	5 (5:1 ratio)	5 (5:1 ratio)	20 (3:1 ratio)
Fine Aggregate Angularity (AASHTO T304, method A, min)	40 <sup>[1]</sup>	43 <sup>[1]</sup>	45	45
Sand Equivalency (AASHTO T176, min)	40	40 <sup>[2]</sup>	45	50
Clay Lumps and Friable Particle in Aggregate (AASHTO T112)	<= 1%	<= 1%	<= 1%	<= 1%
Plasticity Index of Material Added to Mix Design as Mineral Filler (AASHTO T89/90)				<= 4
Gyratory Compaction				
Gyrations for Nini	6	7	8	7
Gyrations for Ndes	40	75	100	65
Gyrations for Nmax	60	115	160	100
Air Voids, %Va (%Gmm Ndes)	4.0 (96.0)	4.0 (96.0)	4.0 (96.0)	4.5 (95.5)
% Gmm Nini	<= 91.5 <sup>[3]</sup>	<= 89.0 <sup>[3]</sup>	<= 89.0	
% Gmm Nmax	<= 98.0	<= 98.0	<= 98.0	<= 98.0
Dust to Binder Ratio <sup>[4]</sup> (% passing 0.075/Pbe)	0.6 - 1.2 <sup>[5]</sup>	0.6 - 1.2 <sup>[5]</sup>	0.6 - 1.2 <sup>[5]</sup>	1.2 - 2.0
Voids filled with Binder (VFB or VFA, %)	68 - 80 <sup>[6] [8]</sup>	65 - 75 <sup>[6] [7] [9]</sup>	65 - 75 <sup>[6] [7] [9]</sup>	70 - 80
Tensile Strength Ratio (TSR) (AASHTO T283)[10] [11]				
no antistripping additive	0.75 min	0.75 min	0.75 min	0.80 min
with antistripping additive	0.80 min	0.80 min	0.80 min	0.80 min
Draindown (AASHTO T305) (%)				<= 0.30
Minimum Effective Asphalt Content, Pbe (%)				5.5

<sup>[1]</sup> For No 6 (4.75 mm) nominal maximum size mixes, the specified fine aggregate angularity is 43 for LT and 45 MT mixes.

<sup>[2]</sup> For No 6 (4.75 mm) nominal maximum size mixes, the specified sand equivalency is 43 for MT mixes.

<sup>[3]</sup> The percent maximum density at initial compaction is only a guideline.

<sup>[4]</sup> For a gradation that passes below the boundaries of the caution zone (ref. AASHTO M323), the dust to binder ratio limits are 0.6 - 1.6.

<sup>[5]</sup> For No 6 (4.75 mm) nominal maximum size mixes, the specified dust to binder ratio limits are 1.0 - 2.0 for LT mixes and 1.5 - 2.0 for MT and HT mixes.

<sup>&</sup>lt;sup>[6]</sup> For No. 6 (4.75mm) nominal maximum size mixes, the specified VFB is 67 - 79 percent for LT mixes and 66 - 77 percent for MT and HT mixes.

<sup>[7]</sup> For No. 5 (9.5mm) and No. 4 (12.5 mm) nominal maximum size mixtures, the specified VFB range is 70 - 76 percent.

<sup>[8]</sup> For No. 2 (25.0mm) nominal maximum size mixes, the specified VFB lower limit is 67 percent.

<sup>[9]</sup> For No. 1 (37.5mm) nominal maximum size mixes, the specified VFB lower limit is 67 percent.

<sup>[10]</sup> WisDOT eliminates freeze-thaw conditioning cycles from the TSR test procedure.

<sup>[11]</sup> Run TSR at asphalt content corresponding to 3.0% air void regressed design, or 4.5% air void design for SMA, using distilled water for testing.

### 513.2.1(2) General

Correct errata by changing the CMM reference from 875.2 to 875.4.

(2) Conform to the department's certification method of acceptance, as defined in CMM 875.4, for railing and railing components. Furnish a certificate of compliance for miscellaneous hardware.

### 531.1(1) Description

Correct errata by adding structural steel sign supports constructed under 635.

- (1) This section describes constructing drilled shaft foundations for the following:
  - Overhead sign structures constructed under 532.
  - High mast light towers constructed under 532.
  - Structural steel sign supports constructed under 635.
  - Camera poles constructed under 677.

## 635.3.1(1) Structural Steel Sign Supports

Correct errata by adding "type NS" concrete footings.

(1) Locate and erect the supports as specified for placement and orientation in 637.3.3.2. Construct Type NS concrete footings conforming to 531.

#### 654.5(2) Payment

Correct errata by changing excavating to drilling.

(2) Payment for the Bases bid items is full compensation for providing concrete bases; for embedded conduit and electrical components; for anchor templates, rods, nuts, and washers; for bar steel reinforcement; and for drilling and backfilling.

## **ADDITIONAL SPECIAL PROVISION 7**

- A. Reporting 1<sup>st</sup> Tier and DBE Payments During Construction
  - 1. Comply with reporting requirements specified in the department's Civil Rights Compliance, Contractor's User Manual, Sublets and Payments.
  - 2. Report payments to all DBE firms within 10 calendar days of receipt of a progress payment by the department or a contractor for work performed, materials furnished, or materials stockpiled by a DBE firm. Report the payment as specified in A(1) for all work satisfactorily performed and for all materials furnished or stockpiled.
  - 3. Report payments to all first tier subcontractor relationships within 10 calendar days of receipt of a progress payment by the department for work performed. Report the payment as specified in A(1) for all work satisfactorily performed.
  - 4. All tiers shall report payments as necessary to comply with the DBE payment requirement as specified in A(2).
  - 5. Require all first tier relationships, DBE firms and all other tier relationships necessary to comply with the DBE payment requirement in receipt of a progress payment by contractor to acknowledge receipt of payment as specified in A(1), (2), (3) and (4).
  - 6. All agreements made by a contractor shall include the provisions in A(1), (2), (3), (4) and (5), and shall be binding on all first tier subcontractor relationships and all contractors and subcontractors utilizing DBE firms on the project.
- B. Costs for conforming to this special provision are incidental to the contract.

NOTE: CRCS Prime Contractor payment is currently not automated and will need to be manually loaded into the Civil Rights Compliance System. Copies of prime contractor payments received (check or ACH) will have to be forwarded to <a href="mailto:paul.ndon@dot.wi.gov">paul.ndon@dot.wi.gov</a> within 5 days of payment receipt to be logged manually.

\*\*\*Additionally, for information on Subcontractor Sublet assignments, Subcontractor Payments and Payment Tracking, please refer to the CRCS Payment and Sublets manual at:

 $\underline{https://wisconsindot.gov/Documents/doing-bus/civil-rights/labornwage/crcs-payments-sublets-\underline{manual.pdf}}$ 

## **ADDITIONAL SPECIAL PROVISION 9**

## **Electronic Certified Payroll or Labor Data Submittal**

(1) Use the department's Civil Rights Compliance System (CRCS) to electronically submit certified payroll reports for contracts with federal funds and labor data for contracts with state funds only. Details are available online through the department's highway construction contractor information (HCCI) site on the Labor, Wages, and EEO Information page at:

https://wisconsindot.gov/Pages/doing-bus/civil-rights/labornwage/default.aspx

- (2) Ensure that all tiers of subcontractors, including all trucking firms, either submit their weekly certified payroll reports (contracts with federal funds) or labor data (contracts with state funds only) electronically through CRCS. These payrolls or labor data are due within seven calendar days following the close of the payroll period. Every firm providing physical labor towards completing the project is a subcontractor under this special provision.
- (3) Upon receipt of contract execution, promptly make all affected firms aware of the requirements under this special provision and arrange for them to receive CRCS training as they are about to begin their submittals. The department will provide training either in a classroom setting at one of our regional offices or by telephone. Contact Paul Ndon at (414) 438-4584 to schedule the training.
- (4) The department will reject all paper submittals for information required under this special provision. All costs for conforming to this special provision are incidental to the contract.
- (5) Firms wishing to export payroll/labor data from their computer system into CRCS should have their payroll coordinator contact Paul Ndon at <a href="mailto:paul.ndon@dot.wi.gov">paul.ndon@dot.wi.gov</a>. Not every contractor's payroll system is capable of producing export files. For details, see Section 4.8 CPR Auto Submit (Data Mapping) on pages 49-50; 66-71 of the CRCS Payroll Manual at:

https://wisconsindot.gov/Documents/doing-bus/civil-rights/labornwage/crcs-payroll-manual.pdf

## REQUIRED CONTRACT PROVISIONS FEDERAL-AID CONSTRUCTION CONTRACTS

- I. General
- II. Nondiscrimination
- III. Nonsegregated Facilities
- IV. Davis-Bacon and Related Act Provisions
- V. Contract Work Hours and Safety Standards Act
- VI. Subletting or Assigning the Contract
- VII. Safety: Accident Prevention
- VIII. False Statements Concerning Highway Projects
- IX. Implementation of Clean Air Act and Federal Water Pollution Control Act
- Compliance with Governmentwide Suspension and Debarment Requirements
- Certification Regarding Use of Contract Funds for Lobbying

#### **ATTACHMENTS**

A. Employment and Materials Preference for Appalachian Development Highway System or Appalachian Local Access Road Contracts (included in Appalachian contracts only)

#### I. GENERAL

1. Form FHWA-1273 must be physically incorporated in each construction contract funded under Title 23 (excluding emergency contracts solely intended for debris removal). The contractor (or subcontractor) must insert this form in each subcontract and further require its inclusion in all lower tier subcontracts (excluding purchase orders, rental agreements and other agreements for supplies or services).

The applicable requirements of Form FHWA-1273 are incorporated by reference for work done under any purchase order, rental agreement or agreement for other services. The prime contractor shall be responsible for compliance by any subcontractor, lower-tier subcontractor or service provider.

Form FHWA-1273 must be included in all Federal-aid designbuild contracts, in all subcontracts and in lower tier subcontracts (excluding subcontracts for design services, purchase orders, rental agreements and other agreements for supplies or services). The design-builder shall be responsible for compliance by any subcontractor, lower-tier subcontractor or service provider.

Contracting agencies may reference Form FHWA-1273 in bid proposal or request for proposal documents, however, the Form FHWA-1273 must be physically incorporated (not referenced) in all contracts, subcontracts and lower-tier subcontracts (excluding purchase orders, rental agreements and other agreements for supplies or services related to a construction contract).

2. Subject to the applicability criteria noted in the following sections, these contract provisions shall apply to all work performed on the contract by the contractor's own organization and with the assistance of workers under the contractor's immediate superintendence and to all work performed on the contract by piecework, station work, or by subcontract.

- 3. A breach of any of the stipulations contained in these Required Contract Provisions may be sufficient grounds for withholding of progress payments, withholding of final payment, termination of the contract, suspension / debarment or any other action determined to be appropriate by the contracting agency and FHWA.
- 4. Selection of Labor: During the performance of this contract, the contractor shall not use convict labor for any purpose within the limits of a construction project on a Federal-aid highway unless it is labor performed by convicts who are on parole, supervised release, or probation. The term Federal-aid highway does not include roadways functionally classified as local roads or rural minor collectors.

#### II. NONDISCRIMINATION

The provisions of this section related to 23 CFR Part 230 are applicable to all Federal-aid construction contracts and to all related construction subcontracts of \$10,000 or more. The provisions of 23 CFR Part 230 are not applicable to material supply, engineering, or architectural service contracts.

In addition, the contractor and all subcontractors must comply with the following policies: Executive Order 11246, 41 CFR 60, 29 CFR 1625-1627, Title 23 USC Section 140, the Rehabilitation Act of 1973, as amended (29 USC 794), Title VI of the Civil Rights Act of 1964, as amended, and related regulations including 49 CFR Parts 21, 26 and 27; and 23 CFR Parts 200, 230, and 633.

The contractor and all subcontractors must comply with: the requirements of the Equal Opportunity Clause in 41 CFR 60-1.4(b) and, for all construction contracts exceeding \$10,000, the Standard Federal Equal Employment Opportunity Construction Contract Specifications in 41 CFR 60-4.3.

Note: The U.S. Department of Labor has exclusive authority to determine compliance with Executive Order 11246 and the policies of the Secretary of Labor including 41 CFR 60, and 29 CFR 1625-1627. The contracting agency and the FHWA have the authority and the responsibility to ensure compliance with Title 23 USC Section 140, the Rehabilitation Act of 1973, as amended (29 USC 794), and Title VI of the Civil Rights Act of 1964, as amended, and related regulations including 49 CFR Parts 21, 26 and 27; and 23 CFR Parts 200, 230, and 633.

The following provision is adopted from 23 CFR 230, Appendix A, with appropriate revisions to conform to the U.S. Department of Labor (US DOL) and FHWA requirements.

1. Equal Employment Opportunity: Equal employment opportunity (EEO) requirements not to discriminate and to take affirmative action to assure equal opportunity as set forth under laws, executive orders, rules, regulations (28 CFR 35, 29 CFR 1630, 29 CFR 1625-1627, 41 CFR 60 and 49 CFR 27) and orders of the Secretary of Labor as modified by the provisions prescribed herein, and imposed pursuant to 23 U.S.C. 140 shall constitute the EEO and specific affirmative action standards for the contractor's project activities under

this contract. The provisions of the Americans with Disabilities Act of 1990 (42 U.S.C. 12101 et seq.) set forth under 28 CFR 35 and 29 CFR 1630 are incorporated by reference in this contract. In the execution of this contract, the contractor agrees to comply with the following minimum specific requirement activities of EEO:

- a. The contractor will work with the contracting agency and the Federal Government to ensure that it has made every good faith effort to provide equal opportunity with respect to all of its terms and conditions of employment and in their review of activities under the contract.
- b. The contractor will accept as its operating policy the following statement:

"It is the policy of this Company to assure that applicants are employed, and that employees are treated during employment, without regard to their race, religion, sex, color, national origin, age or disability. Such action shall include: employment, upgrading, demotion, or transfer; recruitment or recruitment advertising; layoff or termination; rates of pay or other forms of compensation; and selection for training, including apprenticeship, pre-apprenticeship, and/or on-the-job training."

- 2. EEO Officer: The contractor will designate and make known to the contracting officers an EEO Officer who will have the responsibility for and must be capable of effectively administering and promoting an active EEO program and who must be assigned adequate authority and responsibility to do so
- 3. Dissemination of Policy: All members of the contractor's staff who are authorized to hire, supervise, promote, and discharge employees, or who recommend such action, or who are substantially involved in such action, will be made fully cognizant of, and will implement, the contractor's EEO policy and contractual responsibilities to provide EEO in each grade and classification of employment. To ensure that the above agreement will be met, the following actions will be taken as a minimum:
- a. Periodic meetings of supervisory and personnel office employees will be conducted before the start of work and then not less often than once every six months, at which time the contractor's EEO policy and its implementation will be reviewed and explained. The meetings will be conducted by the EEO Officer.
- b. All new supervisory or personnel office employees will be given a thorough indoctrination by the EEO Officer, covering all major aspects of the contractor's EEO obligations within thirty days following their reporting for duty with the contractor.
- c. All personnel who are engaged in direct recruitment for the project will be instructed by the EEO Officer in the contractor's procedures for locating and hiring minorities and women.
- d. Notices and posters setting forth the contractor's EEO policy will be placed in areas readily accessible to employees, applicants for employment and potential employees.
- e. The contractor's EEO policy and the procedures to implement such policy will be brought to the attention of employees by means of meetings, employee handbooks, or other appropriate means.

- **4. Recruitment:** When advertising for employees, the contractor will include in all advertisements for employees the notation: "An Equal Opportunity Employer." All such advertisements will be placed in publications having a large circulation among minorities and women in the area from which the project work force would normally be derived.
- a. The contractor will, unless precluded by a valid bargaining agreement, conduct systematic and direct recruitment through public and private employee referral sources likely to yield qualified minorities and women. To meet this requirement, the contractor will identify sources of potential minority group employees, and establish with such identified sources procedures whereby minority and women applicants may be referred to the contractor for employment consideration.
- b. In the event the contractor has a valid bargaining agreement providing for exclusive hiring hall referrals, the contractor is expected to observe the provisions of that agreement to the extent that the system meets the contractor's compliance with EEO contract provisions. Where implementation of such an agreement has the effect of discriminating against minorities or women, or obligates the contractor to do the same, such implementation violates Federal nondiscrimination provisions.
- c. The contractor will encourage its present employees to refer minorities and women as applicants for employment. Information and procedures with regard to referring such applicants will be discussed with employees.
- **5. Personnel Actions:** Wages, working conditions, and employee benefits shall be established and administered, and personnel actions of every type, including hiring, upgrading, promotion, transfer, demotion, layoff, and termination, shall be taken without regard to race, color, religion, sex, national origin, age or disability. The following procedures shall be followed:
- a. The contractor will conduct periodic inspections of project sites to insure that working conditions and employee facilities do not indicate discriminatory treatment of project site personnel.
- b. The contractor will periodically evaluate the spread of wages paid within each classification to determine any evidence of discriminatory wage practices.
- c. The contractor will periodically review selected personnel actions in depth to determine whether there is evidence of discrimination. Where evidence is found, the contractor will promptly take corrective action. If the review indicates that the discrimination may extend beyond the actions reviewed, such corrective action shall include all affected persons.
- d. The contractor will promptly investigate all complaints of alleged discrimination made to the contractor in connection with its obligations under this contract, will attempt to resolve such complaints, and will take appropriate corrective action within a reasonable time. If the investigation indicates that the discrimination may affect persons other than the complainant, such corrective action shall include such other persons. Upon completion of each investigation, the contractor will inform every complainant of all of their avenues of appeal.

#### 6. Training and Promotion:

a. The contractor will assist in locating, qualifying, and increasing the skills of minorities and women who are

applicants for employment or current employees. Such efforts should be aimed at developing full journey level status employees in the type of trade or job classification involved.

- b. Consistent with the contractor's work force requirements and as permissible under Federal and State regulations, the contractor shall make full use of training programs, i.e., apprenticeship, and on-the-job training programs for the geographical area of contract performance. In the event a special provision for training is provided under this contract, this subparagraph will be superseded as indicated in the special provision. The contracting agency may reserve training positions for persons who receive welfare assistance in accordance with 23 U.S.C. 140(a).
- c. The contractor will advise employees and applicants for employment of available training programs and entrance requirements for each.
- d. The contractor will periodically review the training and promotion potential of employees who are minorities and women and will encourage eligible employees to apply for such training and promotion.
- 7. Unions: If the contractor relies in whole or in part upon unions as a source of employees, the contractor will use good faith efforts to obtain the cooperation of such unions to increase opportunities for minorities and women. Actions by the contractor, either directly or through a contractor's association acting as agent, will include the procedures set forth below:
- a. The contractor will use good faith efforts to develop, in cooperation with the unions, joint training programs aimed toward qualifying more minorities and women for membership in the unions and increasing the skills of minorities and women so that they may qualify for higher paying employment.
- b. The contractor will use good faith efforts to incorporate an EEO clause into each union agreement to the end that such union will be contractually bound to refer applicants without regard to their race, color, religion, sex, national origin, age or disability.
- c. The contractor is to obtain information as to the referral practices and policies of the labor union except that to the extent such information is within the exclusive possession of the labor union and such labor union refuses to furnish such information to the contractor, the contractor shall so certify to the contracting agency and shall set forth what efforts have been made to obtain such information.
- d. In the event the union is unable to provide the contractor with a reasonable flow of referrals within the time limit set forth in the collective bargaining agreement, the contractor will, through independent recruitment efforts, fill the employment vacancies without regard to race, color, religion, sex, national origin, age or disability; making full efforts to obtain qualified and/or qualifiable minorities and women. The failure of a union to provide sufficient referrals (even though it is obligated to provide exclusive referrals under the terms of a collective bargaining agreement) does not relieve the contractor from the requirements of this paragraph. In the event the union referral practice prevents the contractor from meeting the obligations pursuant to Executive Order 11246, as amended, and these special provisions, such contractor shall immediately notify the contracting agency.
- 8. Reasonable Accommodation for Applicants / Employees with Disabilities: The contractor must be familiar

with the requirements for and comply with the Americans with Disabilities Act and all rules and regulations established there under. Employers must provide reasonable accommodation in all employment activities unless to do so would cause an undue hardship.

- 9. Selection of Subcontractors, Procurement of Materials and Leasing of Equipment: The contractor shall not discriminate on the grounds of race, color, religion, sex, national origin, age or disability in the selection and retention of subcontractors, including procurement of materials and leases of equipment. The contractor shall take all necessary and reasonable steps to ensure nondiscrimination in the administration of this contract.
- a. The contractor shall notify all potential subcontractors and suppliers and lessors of their EEO obligations under this contract.
- b. The contractor will use good faith efforts to ensure subcontractor compliance with their EEO obligations.

#### 10. Assurance Required by 49 CFR 26.13(b):

- a. The requirements of 49 CFR Part 26 and the State DOT's U.S. DOT-approved DBE program are incorporated by reference.
- b. The contractor or subcontractor shall not discriminate on the basis of race, color, national origin, or sex in the performance of this contract. The contractor shall carry out applicable requirements of 49 CFR Part 26 in the award and administration of DOT-assisted contracts. Failure by the contractor to carry out these requirements is a material breach of this contract, which may result in the termination of this contract or such other remedy as the contracting agency deems appropriate.
- 11. Records and Reports: The contractor shall keep such records as necessary to document compliance with the EEO requirements. Such records shall be retained for a period of three years following the date of the final payment to the contractor for all contract work and shall be available at reasonable times and places for inspection by authorized representatives of the contracting agency and the FHWA.
- a. The records kept by the contractor shall document the following:
- (1) The number and work hours of minority and nonminority group members and women employed in each work classification on the project;
  - (2) The progress and efforts being made in cooperation with unions, when applicable, to increase employment opportunities for minorities and women; and
  - (3) The progress and efforts being made in locating, hiring, training, qualifying, and upgrading minorities and women;
- b. The contractors and subcontractors will submit an annual report to the contracting agency each July for the duration of the project, indicating the number of minority, women, and non-minority group employees currently engaged in each work classification required by the contract work. This information is to be reported on <a href="Form FHWA-1391">Form FHWA-1391</a>. The staffing data should represent the project work force on board in all or any part of the last payroll period preceding the end of July. If on-the-job training is being required by special provision, the contractor

will be required to collect and report training data. The employment data should reflect the work force on board during all or any part of the last payroll period preceding the end of July.

#### **III. NONSEGREGATED FACILITIES**

This provision is applicable to all Federal-aid construction contracts and to all related construction subcontracts of \$10,000 or more.

The contractor must ensure that facilities provided for employees are provided in such a manner that segregation on the basis of race, color, religion, sex, or national origin cannot result. The contractor may neither require such segregated use by written or oral policies nor tolerate such use by employee custom. The contractor's obligation extends further to ensure that its employees are not assigned to perform their services at any location, under the contractor's control, where the facilities are segregated. The term "facilities" includes waiting rooms, work areas, restaurants and other eating areas, time clocks, restrooms, washrooms, locker rooms, and other storage or dressing areas, parking lots, drinking fountains, recreation or entertainment areas, transportation, and housing provided for employees. The contractor shall provide separate or single-user restrooms and necessary dressing or sleeping areas to assure privacy between sexes.

#### IV. DAVIS-BACON AND RELATED ACT PROVISIONS

This section is applicable to all Federal-aid construction projects exceeding \$2,000 and to all related subcontracts and lower-tier subcontracts (regardless of subcontract size). The requirements apply to all projects located within the right-of-way of a roadway that is functionally classified as Federal-aid highway. This excludes roadways functionally classified as local roads or rural minor collectors, which are exempt. Contracting agencies may elect to apply these requirements to other projects.

The following provisions are from the U.S. Department of Labor regulations in 29 CFR 5.5 "Contract provisions and related matters" with minor revisions to conform to the FHWA-1273 format and FHWA program requirements.

#### 1. Minimum wages

a. All laborers and mechanics employed or working upon the site of the work, will be paid unconditionally and not less often than once a week, and without subsequent deduction or rebate on any account (except such payroll deductions as are permitted by regulations issued by the Secretary of Labor under the Copeland Act (29 CFR part 3)), the full amount of wages and bona fide fringe benefits (or cash equivalents thereof) due at time of payment computed at rates not less than those contained in the wage determination of the Secretary of Labor which is attached hereto and made a part hereof, regardless of any contractual relationship which may be alleged to exist between the contractor and such laborers and mechanics.

Contributions made or costs reasonably anticipated for bona fide fringe benefits under section 1(b)(2) of the Davis-Bacon Act on behalf of laborers or mechanics are considered wages paid to such laborers or mechanics, subject to the provisions

of paragraph 1.d. of this section; also, regular contributions made or costs incurred for more than a weekly period (but not less often than quarterly) under plans, funds, or programs which cover the particular weekly period, are deemed to be constructively made or incurred during such weekly period. Such laborers and mechanics shall be paid the appropriate wage rate and fringe benefits on the wage determination for the classification of work actually performed, without regard to skill, except as provided in 29 CFR 5.5(a)(4). Laborers or mechanics performing work in more than one classification may be compensated at the rate specified for each classification for the time actually worked therein: Provided, That the employer's payroll records accurately set forth the time spent in each classification in which work is performed. The wage determination (including any additional classification and wage rates conformed under paragraph 1.b. of this section) and the Davis-Bacon poster (WH-1321) shall be posted at all times by the contractor and its subcontractors at the site of the work in a prominent and accessible place where it can be easily seen by the workers.

- b.(1) The contracting officer shall require that any class of laborers or mechanics, including helpers, which is not listed in the wage determination and which is to be employed under the contract shall be classified in conformance with the wage determination. The contracting officer shall approve an additional classification and wage rate and fringe benefits therefore only when the following criteria have been met:
  - (i) The work to be performed by the classification requested is not performed by a classification in the wage determination; and
  - (ii) The classification is utilized in the area by the construction industry; and
  - (iii) The proposed wage rate, including any bona fide fringe benefits, bears a reasonable relationship to the wage rates contained in the wage determination.
  - (2) If the contractor and the laborers and mechanics to be employed in the classification (if known), or their representatives, and the contracting officer agree on the classification and wage rate (including the amount designated for fringe benefits where appropriate), a report of the action taken shall be sent by the contracting officer to the Administrator of the Wage and Hour Division, Employment Standards Administration, U.S. Department of Labor, Washington, DC 20210. The Administrator, or an authorized representative, will approve, modify, or disapprove every additional classification action within 30 days of receipt and so advise the contracting officer or will notify the contracting officer within the 30-day period that additional time is necessary.
- (3) In the event the contractor, the laborers or mechanics to be employed in the classification or their representatives, and the contracting officer do not agree on the proposed classification and wage rate (including the amount designated for fringe benefits, where appropriate), the contracting officer shall refer the questions, including the views of all interested parties and the recommendation of the contracting officer, to the Wage and Hour Administrator for determination. The Wage and Hour Administrator, or an authorized representative, will issue a determination within 30 days of receipt and so advise the contracting officer or

will notify the contracting officer within the 30-day period that additional time is necessary.

- (4) The wage rate (including fringe benefits where appropriate) determined pursuant to paragraphs 1.b.(2) or 1.b.(3) of this section, shall be paid to all workers performing work in the classification under this contract from the first day on which work is performed in the classification.
- c. Whenever the minimum wage rate prescribed in the contract for a class of laborers or mechanics includes a fringe benefit which is not expressed as an hourly rate, the contractor shall either pay the benefit as stated in the wage determination or shall pay another bona fide fringe benefit or an hourly cash equivalent thereof.
- d. If the contractor does not make payments to a trustee or other third person, the contractor may consider as part of the wages of any laborer or mechanic the amount of any costs reasonably anticipated in providing bona fide fringe benefits under a plan or program, Provided, That the Secretary of Labor has found, upon the written request of the contractor, that the applicable standards of the Davis-Bacon Act have been met. The Secretary of Labor may require the contractor to set aside in a separate account assets for the meeting of obligations under the plan or program.

#### 2. Withholding

The contracting agency shall upon its own action or upon written request of an authorized representative of the Department of Labor, withhold or cause to be withheld from the contractor under this contract, or any other Federal contract with the same prime contractor, or any other federallyassisted contract subject to Davis-Bacon prevailing wage requirements, which is held by the same prime contractor, so much of the accrued payments or advances as may be considered necessary to pay laborers and mechanics, including apprentices, trainees, and helpers, employed by the contractor or any subcontractor the full amount of wages required by the contract. In the event of failure to pay any laborer or mechanic, including any apprentice, trainee, or helper, employed or working on the site of the work, all or part of the wages required by the contract, the contracting agency may, after written notice to the contractor, take such action as may be necessary to cause the suspension of any further payment, advance, or guarantee of funds until such violations have ceased.

## 3. Payrolls and basic records

a. Payrolls and basic records relating thereto shall be maintained by the contractor during the course of the work and preserved for a period of three years thereafter for all laborers and mechanics working at the site of the work. Such records shall contain the name, address, and social security number of each such worker, his or her correct classification, hourly rates of wages paid (including rates of contributions or costs anticipated for bona fide fringe benefits or cash equivalents thereof of the types described in section 1(b)(2)(B) of the Davis-Bacon Act), daily and weekly number of hours worked, deductions made and actual wages paid. Whenever the Secretary of Labor has found under 29 CFR 5.5(a)(1)(iv) that the wages of any laborer or mechanic include the amount of any costs reasonably anticipated in providing benefits under a plan or program described in section 1(b)(2)(B) of the Davis-

Bacon Act, the contractor shall maintain records which show that the commitment to provide such benefits is enforceable, that the plan or program is financially responsible, and that the plan or program has been communicated in writing to the laborers or mechanics affected, and records which show the costs anticipated or the actual cost incurred in providing such benefits. Contractors employing apprentices or trainees under approved programs shall maintain written evidence of the registration of apprenticeship programs and certification of trainee programs, the registration of the apprentices and trainees, and the ratios and wage rates prescribed in the applicable programs.

- b.(1) The contractor shall submit weekly for each week in which any contract work is performed a copy of all payrolls to the contracting agency. The payrolls submitted shall set out accurately and completely all of the information required to be maintained under 29 CFR 5.5(a)(3)(i), except that full social security numbers and home addresses shall not be included on weekly transmittals. Instead the payrolls shall only need to include an individually identifying number for each employee ( e.g., the last four digits of the employee's social security number). The required weekly payroll information may be submitted in any form desired. Optional Form WH-347 is available for this purpose from the Wage and Hour Division Web site at http://www.dol.gov/esa/whd/forms/wh347instr.htm or its successor site. The prime contractor is responsible for the submission of copies of payrolls by all subcontractors. Contractors and subcontractors shall maintain the full social security number and current address of each covered worker, and shall provide them upon request to the contracting agency for transmission to the State DOT, the FHWA or the Wage and Hour Division of the Department of Labor for purposes of an investigation or audit of compliance with prevailing wage requirements. It is not a violation of this section for a prime contractor to require a subcontractor to provide addresses and social security numbers to the prime contractor for its own records, without weekly submission to the contracting agency...
- (2) Each payroll submitted shall be accompanied by a "Statement of Compliance," signed by the contractor or subcontractor or his or her agent who pays or supervises the payment of the persons employed under the contract and shall certify the following:
  - (i) That the payroll for the payroll period contains the information required to be provided under §5.5 (a)(3)(ii) of Regulations, 29 CFR part 5, the appropriate information is being maintained under §5.5 (a)(3)(i) of Regulations, 29 CFR part 5, and that such information is correct and complete;
  - (ii) That each laborer or mechanic (including each helper, apprentice, and trainee) employed on the contract during the payroll period has been paid the full weekly wages earned, without rebate, either directly or indirectly, and that no deductions have been made either directly or indirectly from the full wages earned, other than permissible deductions as set forth in Regulations, 29 CFR part 3;
  - (iii) That each laborer or mechanic has been paid not less than the applicable wage rates and fringe benefits or cash equivalents for the classification of work performed, as specified in the applicable wage determination incorporated into the contract.

- (3) The weekly submission of a properly executed certification set forth on the reverse side of Optional Form WH–347 shall satisfy the requirement for submission of the "Statement of Compliance" required by paragraph 3.b.(2) of this section.
- (4) The falsification of any of the above certifications may subject the contractor or subcontractor to civil or criminal prosecution under section 1001 of title 18 and section 231 of title 31 of the United States Code.
- c. The contractor or subcontractor shall make the records required under paragraph 3.a. of this section available for inspection, copying, or transcription by authorized representatives of the contracting agency, the State DOT, the FHWA, or the Department of Labor, and shall permit such representatives to interview employees during working hours on the job. If the contractor or subcontractor fails to submit the required records or to make them available, the FHWA may, after written notice to the contractor, the contracting agency or the State DOT, take such action as may be necessary to cause the suspension of any further payment, advance, or guarantee of funds. Furthermore, failure to submit the required records upon request or to make such records available may be grounds for debarment action pursuant to 29 CFR 5.12.

#### 4. Apprentices and trainees

a. Apprentices (programs of the USDOL).

Apprentices will be permitted to work at less than the predetermined rate for the work they performed when they are employed pursuant to and individually registered in a bona fide apprenticeship program registered with the U.S. Department of Labor, Employment and Training Administration, Office of Apprenticeship Training, Employer and Labor Services, or with a State Apprenticeship Agency recognized by the Office, or if a person is employed in his or her first 90 days of probationary employment as an apprentice in such an apprenticeship program, who is not individually registered in the program, but who has been certified by the Office of Apprenticeship Training, Employer and Labor Services or a State Apprenticeship Agency (where appropriate) to be eligible for probationary employment as an apprentice.

The allowable ratio of apprentices to journeymen on the job site in any craft classification shall not be greater than the ratio permitted to the contractor as to the entire work force under the registered program. Any worker listed on a payroll at an apprentice wage rate, who is not registered or otherwise employed as stated above, shall be paid not less than the applicable wage rate on the wage determination for the classification of work actually performed. In addition, any apprentice performing work on the job site in excess of the ratio permitted under the registered program shall be paid not less than the applicable wage rate on the wage determination for the work actually performed. Where a contractor is performing construction on a project in a locality other than that in which its program is registered, the ratios and wage rates (expressed in percentages of the journeyman's hourly rate) specified in the contractor's or subcontractor's registered program shall be observed.

Every apprentice must be paid at not less than the rate specified in the registered program for the apprentice's level of progress, expressed as a percentage of the journeymen hourly rate specified in the applicable wage determination. Apprentices shall be paid fringe benefits in accordance with the provisions of the apprenticeship program. If the apprenticeship program does not specify fringe benefits, apprentices must be paid the full amount of fringe benefits listed on the wage determination for the applicable classification. If the Administrator determines that a different practice prevails for the applicable apprentice classification, fringes shall be paid in accordance with that determination.

In the event the Office of Apprenticeship Training, Employer and Labor Services, or a State Apprenticeship Agency recognized by the Office, withdraws approval of an apprenticeship program, the contractor will no longer be permitted to utilize apprentices at less than the applicable predetermined rate for the work performed until an acceptable program is approved.

b. Trainees (programs of the USDOL).

Except as provided in 29 CFR 5.16, trainees will not be permitted to work at less than the predetermined rate for the work performed unless they are employed pursuant to and individually registered in a program which has received prior approval, evidenced by formal certification by the U.S. Department of Labor, Employment and Training Administration.

The ratio of trainees to journeymen on the job site shall not be greater than permitted under the plan approved by the Employment and Training Administration.

Every trainee must be paid at not less than the rate specified in the approved program for the trainee's level of progress, expressed as a percentage of the journeyman hourly rate specified in the applicable wage determination. Trainees shall be paid fringe benefits in accordance with the provisions of the trainee program. If the trainee program does not mention fringe benefits, trainees shall be paid the full amount of fringe benefits listed on the wage determination unless the Administrator of the Wage and Hour Division determines that there is an apprenticeship program associated with the corresponding journeyman wage rate on the wage determination which provides for less than full fringe benefits for apprentices. Any employee listed on the payroll at a trainee rate who is not registered and participating in a training plan approved by the Employment and Training Administration shall be paid not less than the applicable wage rate on the wage determination for the classification of work actually performed. In addition, any trainee performing work on the job site in excess of the ratio permitted under the registered program shall be paid not less than the applicable wage rate on the wage determination for the work actually performed.

In the event the Employment and Training Administration withdraws approval of a training program, the contractor will no longer be permitted to utilize trainees at less than the applicable predetermined rate for the work performed until an acceptable program is approved.

c. Equal employment opportunity. The utilization of apprentices, trainees and journeymen under this part shall be in conformity with the equal employment opportunity requirements of Executive Order 11246, as amended, and 29 CFR part 30.

d. Apprentices and Trainees (programs of the U.S. DOT).

Apprentices and trainees working under apprenticeship and skill training programs which have been certified by the Secretary of Transportation as promoting EEO in connection with Federal-aid highway construction programs are not subject to the requirements of paragraph 4 of this Section IV. The straight time hourly wage rates for apprentices and trainees under such programs will be established by the particular programs. The ratio of apprentices and trainees to journeymen shall not be greater than permitted by the terms of the particular program.

- **5. Compliance with Copeland Act requirements.** The contractor shall comply with the requirements of 29 CFR part 3, which are incorporated by reference in this contract.
- **6. Subcontracts.** The contractor or subcontractor shall insert Form FHWA-1273 in any subcontracts and also require the subcontractors to include Form FHWA-1273 in any lower tier subcontracts. The prime contractor shall be responsible for the compliance by any subcontractor or lower tier subcontractor with all the contract clauses in 29 CFR 5.5.
- **7. Contract termination: debarment.** A breach of the contract clauses in 29 CFR 5.5 may be grounds for termination of the contract, and for debarment as a contractor and a subcontractor as provided in 29 CFR 5.12.
- **8. Compliance with Davis-Bacon and Related Act requirements.** All rulings and interpretations of the Davis-Bacon and Related Acts contained in 29 CFR parts 1, 3, and 5 are herein incorporated by reference in this contract.
- 9. Disputes concerning labor standards. Disputes arising out of the labor standards provisions of this contract shall not be subject to the general disputes clause of this contract. Such disputes shall be resolved in accordance with the procedures of the Department of Labor set forth in 29 CFR parts 5, 6, and 7. Disputes within the meaning of this clause include disputes between the contractor (or any of its subcontractors) and the contracting agency, the U.S. Department of Labor, or the employees or their representatives.

## 10. Certification of eligibility.

- a. By entering into this contract, the contractor certifies that neither it (nor he or she) nor any person or firm who has an interest in the contractor's firm is a person or firm ineligible to be awarded Government contracts by virtue of section 3(a) of the Davis-Bacon Act or 29 CFR 5.12(a)(1).
- b. No part of this contract shall be subcontracted to any person or firm ineligible for award of a Government contract by virtue of section 3(a) of the Davis-Bacon Act or 29 CFR 5.12(a)(1).
- c. The penalty for making false statements is prescribed in the U.S. Criminal Code, 18 U.S.C. 1001.

## V. CONTRACT WORK HOURS AND SAFETY STANDARDS ACT

The following clauses apply to any Federal-aid construction contract in an amount in excess of \$100,000 and subject to the overtime provisions of the Contract Work Hours and Safety Standards Act. These clauses shall be inserted in addition to the clauses required by 29 CFR 5.5(a) or 29 CFR 4.6. As used in this paragraph, the terms laborers and mechanics include watchmen and guards.

- 1. Overtime requirements. No contractor or subcontractor contracting for any part of the contract work which may require or involve the employment of laborers or mechanics shall require or permit any such laborer or mechanic in any workweek in which he or she is employed on such work to work in excess of forty hours in such workweek unless such laborer or mechanic receives compensation at a rate not less than one and one-half times the basic rate of pay for all hours worked in excess of forty hours in such workweek.
- 2. Violation; liability for unpaid wages; liquidated damages. In the event of any violation of the clause set forth in paragraph (1.) of this section, the contractor and any subcontractor responsible therefor shall be liable for the unpaid wages. In addition, such contractor and subcontractor shall be liable to the United States (in the case of work done under contract for the District of Columbia or a territory, to such District or to such territory), for liquidated damages. Such liquidated damages shall be computed with respect to each individual laborer or mechanic, including watchmen and guards, employed in violation of the clause set forth in paragraph (1.) of this section, in the sum of \$10 for each calendar day on which such individual was required or permitted to work in excess of the standard workweek of forty hours without payment of the overtime wages required by the clause set forth in paragraph (1.) of this section.
- 3. Withholding for unpaid wages and liquidated damages. The FHWA or the contacting agency shall upon its own action or upon written request of an authorized representative of the Department of Labor withhold or cause to be withheld, from any moneys payable on account of work performed by the contractor or subcontractor under any such contract or any other Federal contract with the same prime contractor, or any other federally-assisted contract subject to the Contract Work Hours and Safety Standards Act, which is held by the same prime contractor, such sums as may be determined to be necessary to satisfy any liabilities of such contractor or subcontractor for unpaid wages and liquidated damages as provided in the clause set forth in paragraph (2.) of this section
- **4. Subcontracts.** The contractor or subcontractor shall insert in any subcontracts the clauses set forth in paragraph (1.) through (4.) of this section and also a clause requiring the subcontractors to include these clauses in any lower tier subcontracts. The prime contractor shall be responsible for compliance by any subcontractor or lower tier subcontractor with the clauses set forth in paragraphs (1.) through (4.) of this section.

#### VI. SUBLETTING OR ASSIGNING THE CONTRACT

This provision is applicable to all Federal-aid construction contracts on the National Highway System.

- 1. The contractor shall perform with its own organization contract work amounting to not less than 30 percent (or a greater percentage if specified elsewhere in the contract) of the total original contract price, excluding any specialty items designated by the contracting agency. Specialty items may be performed by subcontract and the amount of any such specialty items performed may be deducted from the total original contract price before computing the amount of work required to be performed by the contractor's own organization (23 CFR 635.116).
- a. The term "perform work with its own organization" refers to workers employed or leased by the prime contractor, and equipment owned or rented by the prime contractor, with or without operators. Such term does not include employees or equipment of a subcontractor or lower tier subcontractor, agents of the prime contractor, or any other assignees. The term may include payments for the costs of hiring leased employees from an employee leasing firm meeting all relevant Federal and State regulatory requirements. Leased employees may only be included in this term if the prime contractor meets all of the following conditions:
- the prime contractor maintains control over the supervision of the day-to-day activities of the leased employees;
- (2) the prime contractor remains responsible for the quality of the work of the leased employees;
- (3) the prime contractor retains all power to accept or exclude individual employees from work on the project; and
  - (4) the prime contractor remains ultimately responsible for the payment of predetermined minimum wages, the submission of payrolls, statements of compliance and all other Federal regulatory requirements.
- b. "Specialty Items" shall be construed to be limited to work that requires highly specialized knowledge, abilities, or equipment not ordinarily available in the type of contracting organizations qualified and expected to bid or propose on the contract as a whole and in general are to be limited to minor components of the overall contract.
- 2. The contract amount upon which the requirements set forth in paragraph (1) of Section VI is computed includes the cost of material and manufactured products which are to be purchased or produced by the contractor under the contract provisions.
- 3. The contractor shall furnish (a) a competent superintendent or supervisor who is employed by the firm, has full authority to direct performance of the work in accordance with the contract requirements, and is in charge of all construction operations (regardless of who performs the work) and (b) such other of its own organizational resources (supervision, management, and engineering services) as the contracting officer determines is necessary to assure the performance of the contract.
- 4. No portion of the contract shall be sublet, assigned or otherwise disposed of except with the written consent of the contracting officer, or authorized representative, and such consent when given shall not be construed to relieve the contractor of any responsibility for the fulfillment of the contract. Written consent will be given only after the contracting agency has assured that each subcontract is

evidenced in writing and that it contains all pertinent provisions and requirements of the prime contract.

5. The 30% self-performance requirement of paragraph (1) is not applicable to design-build contracts; however, contracting agencies may establish their own self-performance requirements.

#### VII. SAFETY: ACCIDENT PREVENTION

- This provision is applicable to all Federal-aid construction contracts and to all related subcontracts.
- 1. In the performance of this contract the contractor shall comply with all applicable Federal, State, and local laws governing safety, health, and sanitation (23 CFR 635). The contractor shall provide all safeguards, safety devices and protective equipment and take any other needed actions as it determines, or as the contracting officer may determine, to be reasonably necessary to protect the life and health of employees on the job and the safety of the public and to protect property in connection with the performance of the work covered by the contract.
- 2. It is a condition of this contract, and shall be made a condition of each subcontract, which the contractor enters into pursuant to this contract, that the contractor and any subcontractor shall not permit any employee, in performance of the contract, to work in surroundings or under conditions which are unsanitary, hazardous or dangerous to his/her health or safety, as determined under construction safety and health standards (29 CFR 1926) promulgated by the Secretary of Labor, in accordance with Section 107 of the Contract Work Hours and Safety Standards Act (40 U.S.C. 3704).
- 3. Pursuant to 29 CFR 1926.3, it is a condition of this contract that the Secretary of Labor or authorized representative thereof, shall have right of entry to any site of contract performance to inspect or investigate the matter of compliance with the construction safety and health standards and to carry out the duties of the Secretary under Section 107 of the Contract Work Hours and Safety Standards Act (40 U.S.C.3704).

## VIII. FALSE STATEMENTS CONCERNING HIGHWAY PROJECTS

This provision is applicable to all Federal-aid construction contracts and to all related subcontracts.

In order to assure high quality and durable construction in conformity with approved plans and specifications and a high degree of reliability on statements and representations made by engineers, contractors, suppliers, and workers on Federal-aid highway projects, it is essential that all persons concerned with the project perform their functions as carefully, thoroughly, and honestly as possible. Willful falsification, distortion, or misrepresentation with respect to any facts related to the project is a violation of Federal law. To prevent any misunderstanding regarding the seriousness of these and similar acts, Form FHWA-1022 shall be posted on each Federal-aid highway project (23 CFR 635) in one or more places where it is readily available to all persons concerned with the project:

18 U.S.C. 1020 reads as follows:

"Whoever, being an officer, agent, or employee of the United States, or of any State or Territory, or whoever, whether a person, association, firm, or corporation, knowingly makes any false statement, false representation, or false report as to the character, quality, quantity, or cost of the material used or to be used, or the quantity or quality of the work performed or to be performed, or the cost thereof in connection with the submission of plans, maps, specifications, contracts, or costs of construction on any highway or related project submitted for approval to the Secretary of Transportation; or

Whoever knowingly makes any false statement, false representation, false report or false claim with respect to the character, quality, quantity, or cost of any work performed or to be performed, or materials furnished or to be furnished, in connection with the construction of any highway or related project approved by the Secretary of Transportation; or

Whoever knowingly makes any false statement or false representation as to material fact in any statement, certificate, or report submitted pursuant to provisions of the Federal-aid Roads Act approved July 1, 1916, (39 Stat. 355), as amended and supplemented;

Shall be fined under this title or imprisoned not more than 5 years or both."

## IX. IMPLEMENTATION OF CLEAN AIR ACT AND FEDERAL WATER POLLUTION CONTROL ACT

This provision is applicable to all Federal-aid construction contracts and to all related subcontracts.

By submission of this bid/proposal or the execution of this contract, or subcontract, as appropriate, the bidder, proposer, Federal-aid construction contractor, or subcontractor, as appropriate, will be deemed to have stipulated as follows:

- 1. That any person who is or will be utilized in the performance of this contract is not prohibited from receiving an award due to a violation of Section 508 of the Clean Water Act or Section 306 of the Clean Air Act.
- 2. That the contractor agrees to include or cause to be included the requirements of paragraph (1) of this Section X in every subcontract, and further agrees to take such action as the contracting agency may direct as a means of enforcing such requirements.

# X. CERTIFICATION REGARDING DEBARMENT, SUSPENSION, INELIGIBILITY AND VOLUNTARY EXCLUSION

This provision is applicable to all Federal-aid construction contracts, design-build contracts, subcontracts, lower-tier subcontracts, purchase orders, lease agreements, consultant contracts or any other covered transaction requiring FHWA approval or that is estimated to cost \$25,000 or more – as defined in 2 CFR Parts 180 and 1200.

#### 1. Instructions for Certification – First Tier Participants:

- a. By signing and submitting this proposal, the prospective first tier participant is providing the certification set out below.
- b. The inability of a person to provide the certification set out below will not necessarily result in denial of participation in this

covered transaction. The prospective first tier participant shall submit an explanation of why it cannot provide the certification set out below. The certification or explanation will be considered in connection with the department or agency's determination whether to enter into this transaction. However, failure of the prospective first tier participant to furnish a certification or an explanation shall disqualify such a person from participation in this transaction.

- c. The certification in this clause is a material representation of fact upon which reliance was placed when the contracting agency determined to enter into this transaction. If it is later determined that the prospective participant knowingly rendered an erroneous certification, in addition to other remedies available to the Federal Government, the contracting agency may terminate this transaction for cause of default.
- d. The prospective first tier participant shall provide immediate written notice to the contracting agency to whom this proposal is submitted if any time the prospective first tier participant learns that its certification was erroneous when submitted or has become erroneous by reason of changed circumstances.
- e. The terms "covered transaction," "debarred,"
  "suspended," "ineligible," "participant," "person," "principal,"
  and "voluntarily excluded," as used in this clause, are defined
  in 2 CFR Parts 180 and 1200. "First Tier Covered
  Transactions" refers to any covered transaction between a
  grantee or subgrantee of Federal funds and a participant (such
  as the prime or general contract). "Lower Tier Covered
  Transactions" refers to any covered transaction under a First
  Tier Covered Transaction (such as subcontracts). "First Tier
  Participant" refers to the participant who has entered into a
  covered transaction with a grantee or subgrantee of Federal
  funds (such as the prime or general contractor). "Lower Tier
  Participant" refers any participant who has entered into a
  covered transaction with a First Tier Participant or other Lower
  Tier Participants (such as subcontractors and suppliers).
- f. The prospective first tier participant agrees by submitting this proposal that, should the proposed covered transaction be entered into, it shall not knowingly enter into any lower tier covered transaction with a person who is debarred, suspended, declared ineligible, or voluntarily excluded from participation in this covered transaction, unless authorized by the department or agency entering into this transaction.
- g. The prospective first tier participant further agrees by submitting this proposal that it will include the clause titled "Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion-Lower Tier Covered Transactions," provided by the department or contracting agency, entering into this covered transaction, without modification, in all lower tier covered transactions and in all solicitations for lower tier covered transactions exceeding the \$25,000 threshold.
- h. A participant in a covered transaction may rely upon a certification of a prospective participant in a lower tier covered transaction that is not debarred, suspended, ineligible, or voluntarily excluded from the covered transaction, unless it knows that the certification is erroneous. A participant is responsible for ensuring that its principals are not suspended, debarred, or otherwise ineligible to participate in covered transactions. To verify the eligibility of its principals, as well as the eligibility of any lower tier prospective participants, each participant may, but is not required to, check the Excluded Parties List System website (https://www.epls.gov/), which is compiled by the General Services Administration.

- i. Nothing contained in the foregoing shall be construed to require the establishment of a system of records in order to render in good faith the certification required by this clause. The knowledge and information of the prospective participant is not required to exceed that which is normally possessed by a prudent person in the ordinary course of business dealings.
- j. Except for transactions authorized under paragraph (f) of these instructions, if a participant in a covered transaction knowingly enters into a lower tier covered transaction with a person who is suspended, debarred, ineligible, or voluntarily excluded from participation in this transaction, in addition to other remedies available to the Federal Government, the department or agency may terminate this transaction for cause or default.

\* \* \* \* \*

# 2. Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion – First Tier Participants:

- a. The prospective first tier participant certifies to the best of its knowledge and belief, that it and its principals:
- (1) Are not presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from participating in covered transactions by any Federal department or agency;
- (2) Have not within a three-year period preceding this proposal been convicted of or had a civil judgment rendered against them for commission of fraud or a criminal offense in connection with obtaining, attempting to obtain, or performing a public (Federal, State or local) transaction or contract under a public transaction; violation of Federal or State antitrust statutes or commission of embezzlement, theft, forgery, bribery, falsification or destruction of records, making false statements, or receiving stolen property;
- (3) Are not presently indicted for or otherwise criminally or civilly charged by a governmental entity (Federal, State or local) with commission of any of the offenses enumerated in paragraph (a)(2) of this certification; and
- (4) Have not within a three-year period preceding this application/proposal had one or more public transactions (Federal, State or local) terminated for cause or default.
- b. Where the prospective participant is unable to certify to any of the statements in this certification, such prospective participant shall attach an explanation to this proposal.

#### 2. Instructions for Certification - Lower Tier Participants:

(Applicable to all subcontracts, purchase orders and other lower tier transactions requiring prior FHWA approval or estimated to cost \$25,000 or more - 2 CFR Parts 180 and 1200)

- a. By signing and submitting this proposal, the prospective lower tier is providing the certification set out below.
- b. The certification in this clause is a material representation of fact upon which reliance was placed when this transaction was entered into. If it is later determined that the prospective lower tier participant knowingly rendered an erroneous certification, in addition to other remedies available to the Federal Government, the department, or agency with which

this transaction originated may pursue available remedies, including suspension and/or debarment.

- c. The prospective lower tier participant shall provide immediate written notice to the person to which this proposal is submitted if at any time the prospective lower tier participant learns that its certification was erroneous by reason of changed circumstances.
- d. The terms "covered transaction," "debarred,"
  "suspended," "ineligible," "participant," "person," "principal,"
  and "voluntarily excluded," as used in this clause, are defined
  in 2 CFR Parts 180 and 1200. You may contact the person to
  which this proposal is submitted for assistance in obtaining a
  copy of those regulations. "First Tier Covered Transactions"
  refers to any covered transaction between a grantee or
  subgrantee of Federal funds and a participant (such as the
  prime or general contract). "Lower Tier Covered Transactions"
  refers to any covered transaction under a First Tier Covered
  Transaction (such as subcontracts). "First Tier Participant"
  refers to the participant who has entered into a covered
  transaction with a grantee or subgrantee of Federal funds
  (such as the prime or general contractor). "Lower Tier
  Participant" refers any participant who has entered into a
  covered transaction with a First Tier Participant or other Lower
  Tier Participants (such as subcontractors and suppliers).
- e. The prospective lower tier participant agrees by submitting this proposal that, should the proposed covered transaction be entered into, it shall not knowingly enter into any lower tier covered transaction with a person who is debarred, suspended, declared ineligible, or voluntarily excluded from participation in this covered transaction, unless authorized by the department or agency with which this transaction originated.
- f. The prospective lower tier participant further agrees by submitting this proposal that it will include this clause titled "Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion-Lower Tier Covered Transaction," without modification, in all lower tier covered transactions and in all solicitations for lower tier covered transactions exceeding the \$25,000 threshold.
- g. A participant in a covered transaction may rely upon a certification of a prospective participant in a lower tier covered transaction that is not debarred, suspended, ineligible, or voluntarily excluded from the covered transaction, unless it knows that the certification is erroneous. A participant is responsible for ensuring that its principals are not suspended, debarred, or otherwise ineligible to participate in covered transactions. To verify the eligibility of its principals, as well as the eligibility of any lower tier prospective participants, each participant may, but is not required to, check the Excluded Parties List System website (<a href="https://www.epls.gov/">https://www.epls.gov/</a>), which is compiled by the General Services Administration.
- h. Nothing contained in the foregoing shall be construed to require establishment of a system of records in order to render in good faith the certification required by this clause. The knowledge and information of participant is not required to exceed that which is normally possessed by a prudent person in the ordinary course of business dealings.
- i. Except for transactions authorized under paragraph e of these instructions, if a participant in a covered transaction knowingly enters into a lower tier covered transaction with a person who is suspended, debarred, ineligible, or voluntarily excluded from participation in this transaction, in addition to other remedies available to the Federal Government, the

department or agency with which this transaction originated may pursue available remedies, including suspension and/or debarment.

\* \* \* \* \*

# Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion--Lower Tier Participants:

- 1. The prospective lower tier participant certifies, by submission of this proposal, that neither it nor its principals is presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from participating in covered transactions by any Federal department or agency.
- 2. Where the prospective lower tier participant is unable to certify to any of the statements in this certification, such prospective participant shall attach an explanation to this proposal.

\* \* \* \* :

## XI. CERTIFICATION REGARDING USE OF CONTRACT FUNDS FOR LOBBYING

This provision is applicable to all Federal-aid construction contracts and to all related subcontracts which exceed \$100,000 (49 CFR 20).

- 1. The prospective participant certifies, by signing and submitting this bid or proposal, to the best of his or her knowledge and belief. that:
- a. No Federal appropriated funds have been paid or will be paid, by or on behalf of the undersigned, to any person for influencing or attempting to influence an officer or employee of any Federal agency, a Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress in connection with the awarding of any Federal contract, the making of any Federal grant, the making of any Federal loan, the entering into of any cooperative agreement, and the extension, continuation, renewal, amendment, or modification of any Federal contract, grant, loan, or cooperative agreement.
- b. If any funds other than Federal appropriated funds have been paid or will be paid to any person for influencing or attempting to influence an officer or employee of any Federal agency, a Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress in connection with this Federal contract, grant, loan, or cooperative agreement, the undersigned shall complete and submit Standard Form-LLL, "Disclosure Form to Report Lobbying," in accordance with its instructions.
- 2. This certification is a material representation of fact upon which reliance was placed when this transaction was made or entered into. Submission of this certification is a prerequisite for making or entering into this transaction imposed by 31 U.S.C. 1352. Any person who fails to file the required certification shall be subject to a civil penalty of not less than \$10,000 and not more than \$100,000 for each such failure.
- 3. The prospective participant also agrees by submitting its bid or proposal that the participant shall require that the language of this certification be included in all lower tier subcontracts, which exceed \$100,000 and that all such recipients shall certify and disclose accordingly.

# ATTACHMENT A - EMPLOYMENT AND MATERIALS PREFERENCE FOR APPALACHIAN DEVELOPMENT HIGHWAY SYSTEM OR APPALACHIAN LOCAL ACCESS ROAD CONTRACTS

This provision is applicable to all Federal-aid projects funded under the Appalachian Regional Development Act of 1965.

- 1. During the performance of this contract, the contractor undertaking to do work which is, or reasonably may be, done as on-site work, shall give preference to qualified persons who regularly reside in the labor area as designated by the DOL wherein the contract work is situated, or the subregion, or the Appalachian counties of the State wherein the contract work is situated, except:
- a. To the extent that qualified persons regularly residing in the area are not available.
- b. For the reasonable needs of the contractor to employ supervisory or specially experienced personnel necessary to assure an efficient execution of the contract work.
- c. For the obligation of the contractor to offer employment to present or former employees as the result of a lawful collective bargaining contract, provided that the number of nonresident persons employed under this subparagraph (1c) shall not exceed 20 percent of the total number of employees employed by the contractor on the contract work, except as provided in subparagraph (4) below.
- 2. The contractor shall place a job order with the State Employment Service indicating (a) the classifications of the laborers, mechanics and other employees required to perform the contract work, (b) the number of employees required in each classification, (c) the date on which the participant estimates such employees will be required, and (d) any other pertinent information required by the State Employment Service to complete the job order form. The job order may be placed with the State Employment Service in writing or by telephone. If during the course of the contract work, the information submitted by the contractor in the original job order is substantially modified, the participant shall promptly notify the State Employment Service.
- 3. The contractor shall give full consideration to all qualified job applicants referred to him by the State Employment Service. The contractor is not required to grant employment to any job applicants who, in his opinion, are not qualified to perform the classification of work required.
- 4. If, within one week following the placing of a job order by the contractor with the State Employment Service, the State Employment Service is unable to refer any qualified job applicants to the contractor, or less than the number requested, the State Employment Service will forward a certificate to the contractor indicating the unavailability of applicants. Such certificate shall be made a part of the contractor's permanent project records. Upon receipt of this certificate, the contractor may employ persons who do not normally reside in the labor area to fill positions covered by the certificate, notwithstanding the provisions of subparagraph (1c) above.
- 5. The provisions of 23 CFR 633.207(e) allow the contracting agency to provide a contractual preference for the use of mineral resource materials native to the Appalachian region.

6. The contractor shall include the provisions of Sections 1 through 4 of this Attachment A in every subcontract for work which is, or reasonably may be, done as on-site work.

## **Non-discrimination Provisions**

During the performance of this contract, the contractor, for itself, its assignees, and successors in interest (hereinafter referred to as the "contractor") agrees as follows:

- **1. Compliance with Regulations:** The contractor (hereinafter includes consultants) will comply with the Acts and the Regulations relative to Non-discrimination in Federally-assisted programs of the U.S. Department of Transportation, Federal Highway Administration, as they may be amended from time to time, which are herein incorporated by reference and made a part of this contract.
- **2. Non-discrimination:** The contractor, with regard to the work performed by it during the contract, will not discriminate on the grounds of race, color, or national origin in the selection and retention of subcontractors, including procurements of materials and leases of equipment. The contractor will not participate directly or indirectly in the discrimination prohibited by the Acts and the Regulations, including employment practices when the contract covers any activity, project, or program set forth in Appendix B of 49 CFR Part 21.
- **3. Solicitations for Subcontracts, Including Procurements of Materials and Equipment:** In all solicitations, either by competitive bidding, or negotiation made by the contractor for work to be performed under a subcontract, including procurements of materials, or leases of equipment, each potential subcontractor or supplier will be notified by the contractor of the contractor's obligations under this contract and the Acts and the Regulations relative to Non-discrimination on the grounds of race, color, or national origin.
- **4. Information and Reports:** The contractor will provide all information and reports required by the Acts, the Regulations, and directives issued pursuant thereto and will permit access to its books, records, accounts, other sources of information, and its facilities as may be determined by the Recipient or the Federal Highway Administration to be pertinent to ascertain compliance with such Acts, Regulations, and instructions. Where any information required of a contractor is in the exclusive possession of another who fails or refuses to furnish the information, the contractor will so certify to the Recipient or the Federal Highway Administration, as appropriate, and will set forth what efforts it has made to obtain the information.
- **5. Sanctions for Noncompliance:** In the event of a contractor's noncompliance with the Non-discrimination provisions of this contract, the Recipient will impose such contract sanctions as it or the Federal Highway Administration may determine to be appropriate, including, but not limited to:
  - a. Withholding payments to the contractor under the contract until the contractor complies; and/or
  - b. Cancelling, terminating, or suspending a contract, in whole or in part.

**6. Incorporation of Provisions:** The contractor will include the provisions of paragraphs one through six in every subcontract, including procurements of materials and leases of equipment, unless exempt by the Acts, the Regulations and directives issued pursuant thereto. The contractor will take action with respect to any subcontract or procurement as the Recipient or the Federal Highway Administration may direct as a means of enforcing such provisions including sanctions for noncompliance. Provided, that if the contractor becomes involved in, or is threatened with litigation by a subcontractor, or supplier because of such direction, the contractor may request the Recipient to enter into any litigation to protect the interests of the Recipient. In addition, the contractor may request the United States to enter into the litigation to protect the interests of the United States.

During the performance of this contract, the contractor, for itself, its assignees, and successors in interest (hereinafter referred to as the "contractor") agrees to comply with the following non-discrimination statutes and authorities; including but not limited to:

## **Pertinent Non-Discrimination Authorities:**

- Title VI of the Civil Rights Act of 1964 (42 U.S.C. § 2000d et seq., 78 stat. 252), (prohibits discrimination on the basis of race, color, national origin); and 49 CFR Part 21.
- The Uniform Relocation Assistance and Real Property Acquisition Policies Act of 1970, (42 U.S.C. § 4601), (prohibits unfair treatment of persons displaced or whose property has been acquired because of Federal or Federal-aid programs and projects);
- Federal-Aid Highway Act of 1973, (23 U.S.C. § 324 et seq.), (prohibits discrimination on the basis of sex);
- Section 504 of the Rehabilitation Act of 1973, (29 U.S.C. § 794 et seq.), as amended, (prohibits discrimination on the basis of disability); and 49 CFR Part 27;
- The Age Discrimination Act of 1975, as amended, (42 U.S.C. § 6101 et seq.), (prohibits discrimination on the basis of age);
- Airport and Airway Improvement Act of 1982, (49 USC § 471, Section 47123), as amended, (prohibits discrimination based on race, creed, color, national origin, or sex);
- The Civil Rights Restoration Act of 1987, (PL 100-209), (Broadened the scope, coverage and applicability of Title VI of the Civil Rights Act of 1964, The Age Discrimination Act of 1975 and Section 504 of the Rehabilitation Act of 1973, by expanding the definition of the terms "programs or activities" to include all of the programs or activities of the Federal-aid recipients, sub-recipients and contractors, whether such programs or activities are Federally funded or not);
- Titles II and III of the Americans with Disabilities Act, which prohibit discrimination on the basis of disability in the operation of public entities, public and private transportation systems, places of public accommodation, and certain testing entities (42 U.S.C. §§ 12131-12189) as implemented by Department of Transportation regulations at 49 C.F.R. parts 37 and 38;
- The Federal Aviation Administration's Non-discrimination statute (49 U.S.C. § 47123) (prohibits discrimination on the basis of race, color, national origin, and sex);

- Executive Order 12898, Federal Actions to Address Environmental Justice in Minority Populations and Low-Income Populations, which ensures Non-discrimination against minority populations by discouraging programs, policies, and activities with disproportionately high and adverse human health or environmental effects on minority and low-income populations;
- Executive Order 13166, Improving Access to Services for Persons with Limited English Proficiency, and resulting agency guidance, national origin discrimination includes discrimination because of Limited English proficiency (LEP). To ensure compliance with Title VI, you must take reasonable steps to ensure that LEP persons have meaningful access to your programs (70 Fed. Reg. at 74087 to 74100);
- Title IX of the Education Amendments of 1972, as amended, which prohibits you from discriminating because of sex in education programs or activities (20 U.S.C. 1681 et seq).

## **SEPTEMBER 2002**

# NOTICE OF REQUIREMENT FOR AFFIRMATIVE ACTION TO ENSURE EQUAL EMPLOYMENT OPPORTUNITY (EXECUTIVE ORDER 11246)

- 1. The Offeror's or Bidder's attention is called to the "Employment Practices" and "Equal Opportunity Clause" set forth in the Required Contract Provisions, FHWA 1273.
- 2. The goals and timetables for minority and female participation expressed in percentage terms for the contractor's aggregate work force in each trade, on all construction work in the covered area, are as follows:

## Goals for Minority Participation for Each Trade:

_County_	<u>%</u>	_County_	_%_	_County_	<u>%</u>
Adams	1.7	Iowa	1.7	Polk	2.2
Ashland	1.2	Iron	1.2	Portage	0.6
Barron	0.6	Jackson	0.6	Price	0.6
Bayfield	1.2	Jefferson	7.0	Racine	8.4
Brown	1.3	Juneau	0.6	Richland	1.7
Buffalo	0.6	Kenosha	3.0	Rock	3.1
Burnett	2.2	Kewaunee	1.0	Rusk	0.6
Calumet	0.9	La Crosse	0.9	St. Croix	2.9
Chippewa	0.5	Lafayette	0.5	Sauk	1.7
Clark	0.6	Langlade	0.6	Sawyer	0.6
Columbia	1.7	Lincoln	0.6	Shawano	1.0
Crawford	0.5	Manitowoc	1.0	Sheboygan	7.0
Dane	2.2	Marathon	0.6	Taylor	0.6
Dodge	7.0	Marinette	1.0	Trempealeau	0.6
Door	1.0	Marquette	1.7	Vernon	0.6
Douglas	1.0	Menominee	1.0	Vilas	0.6
Dunn	0.6	Milwaukee	8.0	Walworth	7.0
Eau Claire	0.5	Monroe	0.6	Washburn	0.6
Florence	1.0	Oconto	1.0	Washington	8.0
Fond du Lac	1.0	Oneida	0.6	Waukesha	8.0
Forest	1.0	Outagamie	0.9	Waupaca	1.0
Grant	0.5	Ozaukee	8.0	Waushara	1.0
Green	1.7	Pepin	0.6	Winnebago	0.9
Green Lake	1.0	Pierce	2.2	Wood	0.6

## Goals for female participation for each trade: 6.9%

These goals are applicable to all the contractor's construction work, (whether or not it is federal or federally assisted), performed in the covered area. If the contractor performs construction work in the geographical area located outside of the covered area, it shall apply the goals established for such geographical area where the work is actually performed. With regard to this second area, the contractor also is subject to the goals for both its federally involved and nonfederally involved construction.

The contractor's compliance with the Executive Order and the Regulations in 41 CFR Part 60-4 shall be based on its implementation of the Equal Opportunity Clause, specific affirmative action obligations required by the specifications set forth in 41 CFR 60-4.3(a), and its efforts to meet the goals. The hours of minority and female employment and training must be substantially uniform throughout the length of the contract, and in each trade, and the contractor shall make a good faith effort to employ minorities and women evenly on each of its projects. The transfer of minority or female employees or trainees from contractor to contractor or from project to project for the sole purpose of meeting the contractor's goals shall be a violation of the contract, the Executive Order and the Regulations in 41 CFR Part 60-4. Compliance with the goals will be measured against the total work hours performed.

3. The contractor shall provide written notification to the Director of the Office of Federal Contract Compliance Programs within ten (10) working days of award of any construction subcontract in excess of \$10,000.00 at any tier for construction work under the contract resulting from this solicitation. The notification shall list the name, address and telephone number of the subcontractor, employer identification number of the subcontractor; estimated dollar amount of the subcontract; estimated starting and completion dates of the subcontract; and the geographical area in which the subcontract is to be performed.

As referred to in this section, the Director means:

Director Office of Federal Contract Compliance Programs Ruess Federal Plaza 310 W. Wisconsin Ave., Suite 1115 Milwaukee, WI 53202

The "Employer Identification Number" means the Federal Social Security number used on the Employer's Quarterly Federal Tax Return, U.S. Treasury Department Form 941.

4. As used in this notice, and in the contract resulting from solicitation, the "covered area" is the county(ies) in Wisconsin to which this proposal applies.

## **APRIL 2013**

## ADDITIONAL FEDERAL-AID PROVISIONS

## NOTICE TO ALL BIDDERS

To report bid rigging activities call:

## 1-800-424-9071

The U.S. Department of Transportation (DOT) operates the above toll-free "hotline" Monday through Friday, 8:00 a.m. to 5:00 p.m., Eastern Time. Anyone with knowledge of possible bid rigging, bidding collusion, or other fraudulent activities should use the "hotline" to report such activities.

The "hotline" is part of the DOT's continuing effort to identify and investigate highway construction contract fraud and abuse and is operated under the direction of the DOT Inspector General. All information will be treated confidentially and caller anonymity will be respected.

## **Effective November 2020 letting**

### **BUY AMERICA PROVISION**

All steel and iron materials permanently incorporated in this project shall be domestic products and all manufacturing and coating processes for these materials from smelting forward in the manufacturing process must have occurred within the United States. Coating includes epoxy coating, galvanizing, painting and any other coating that protects or enhances the value of a material subject to the requirements of Buy America. The exemption of this requirement is the minimal use of foreign materials if the total cost of such material permanently incorporated in the product does not exceed one-tenth of one percent (1/10 of 1%) of the total contract cost or \$2,500.00, whichever is greater. For purposes of this paragraph, the cost is that shown to be the value of the subject products as they are delivered to the project. The contractor shall take actions and provide documentation conforming to CMM 2-28.5 to ensure compliance with this "Buy America" provision.

https://wisconsindot.gov/rdwy/cmm/cm-02-28.pdf

Upon completion of the project certify to the engineer, in writing using department form DT4567, that all steel, iron, and coating processes for steel or iron incorporated into the contract work conform to these "Buy America" provisions. Attach a list of exemptions and their associated costs to the certification form. Department form DT4567 is available at:

https://wisconsindot.gov/Documents/formdocs/dt4567.docx

1 of 1

## Cargo Preference Act Requirement

All Federal-aid projects shall comply with 46 CFR 381.7 (a) – (b) as follows:

- (a) Agreement Clauses. "Use of United States-flag vessels:"
- (1) Pursuant to Pub. L. 664 (43 U.S.C. 1241(b)) at least 50 percent of any equipment, materials or commodities procured, contracted for or otherwise obtained with funds granted, guaranteed, loaned, or advanced by the U.S. Government under this agreement, and which may be transported by ocean vessel, shall be transported on privately owned United States-flag commercial vessels, if available.
- (2) Within 20 days following the date of loading for shipments originating within the United States or within 30 working days following the date of loading for shipments originating outside the United States, a legible copy of a rated, 'on-board' commercial ocean bill-of-lading in English for each shipment of cargo described in paragraph (a)(1) of this section shall be furnished to both the Contracting Officer (through the prime contractor in the case of subcontractor bills-of-lading) and to the Division of National Cargo, Office of Market Development, Maritime Administration, Washington, DC 20590."
- (b) Contractor and Subcontractor Clauses. "Use of United States-flag vessels: The contractor agrees—"
- (1) To utilize privately owned United States-flag commercial vessels to ship at least 50 percent of the gross tonnage (computed separately for dry bulk carriers, dry cargo liners, and tankers) involved, whenever shipping any equipment, material, or commodities pursuant to this contract, to the extent such vessels are available at fair and reasonable rates for United States-flag commercial vessels.
- (2) To furnish within 20 days following the date of loading for shipments originating within the United States or within 30 working days following the date of loading for shipments originating outside the United States, a legible copy of a rated, 'on-board' commercial ocean bill-of-lading in English for each shipment of cargo described in paragraph (b) (1) of this section to both the Contracting Officer (through the prime contractor in the case of subcontractor bills-of-lading) and to the Division of National Cargo, Office of Market Development, Maritime Administration, Washington, DC 20590.
- (3) To insert the substance of the provisions of this clause in all subcontracts issued pursuant to this contract.

## WISCONSIN DEPARTMENT OF TRANSPORTATION DIVISION OF TRANSPORTATION AND SYSTEM DEVELOPMENT

## SUPPLEMENTAL REQUIRED CONTRACT PROVISIONS FOR PROJECTS WITH FEDERAL AID

## I. PREVAILING WAGE RATES

The attached U.S. Department of Labor (Davis-Bacon Minimum Wage Rates) furnishes the minimum prevailing wage rates pursuant to the Davis-Bacon and Related Acts. The wage rates shown are the minimum rates required by the contract to be paid during its life, however this is not a representation that labor can be obtained at these rates. It is the responsibility of bidders to inform themselves as to the local labor conditions and prospective changes or adjustments of wage rates. No increase in the contract price will be allowed or authorized on account of the payment of wage rates in excess of those listed herein.

## II. COVERAGE OF TRUCK DRIVERS

Truck drivers are covered by Davis-Bacon Minimum Wage Rates in the following circumstances:

- Drivers of a contractor or subcontractor for time spent working on the site
  of the work.
- Drivers of a contractor or subcontractor for time spent loading and/or unloading materials and supplies on the site of the work, if such time is not de minimis. https://www.dol.gov/whd/FOH/FOH Ch15.pdf
- Truck drivers transporting materials or supplies between a facility that is deemed part of the site of the work and the actual construction site.
- Truck drivers transporting portions of the building or work between a site
  established specifically for the performance of the contract where a
  significant portion of such building or work is constructed and the physical
  place where the building or work called for in the contract will remain.

Truck drivers are not covered by Davis-Bacon Minimum Wage Rates in the following circumstances:

- Material delivery truck drivers while off the site of the work.
- Drivers of a contractor or subcontractor traveling between a Davis-Bacon job and a commercial supply facility while they are off the site of the work."
- Truck drivers whose time spent on the site of the work is de minimis, such as only a few minutes at a time merely to pick up or drop off materials or supplies.

Details are available online at:

https://www.dol.gov/whd/recovery/pwrb/Tab9.pdf https://wisconsindot.gov/Pages/doing-bus/civil-rights/labornwage/trckng.aspx

# III. POSTINGS AT THE SITE OF THE WORK

In addition to the required postings furnished by the department, the contractor shall post the following in at least one conspicuous and accessible place at the site of work:

a. A copy of the contractor's Equal Employment Opportunity Policy.

All required documents shall be posted by the first day of work and be accurate and complete. Postings must be readable, in an area where they will be noticed, and maintained until the last day of work.

### IV. RESOURCES

Required information regarding compliance with federal provisions is found in the following resources:

- · FHWA-1273 included in this contract
- U.S. Department of Labor Prevailing Wage Resource Book
- · U.S. Department of Labor Field Operations Handbook
- U.S. Code of Federal Regulations
- Any applicable law, Act, or Executive Order enacted by the federal government at the time of the letting of this contract

"General Decision Number: WI20200010 10/02/2020

Superseded General Decision Number: WI20190010

State: Wisconsin

Construction Type: Highway

Counties: Wisconsin Statewide.

HIGHWAY, AIRPORT RUNWAY & TAXIWAY CONSTRUCTION PROJECTS (does not include bridges over navigable waters; tunnels; buildings in highway rest areas; and railroad construction)

Note: Under Executive Order (EO) 13658, an hourly minimum wage of \$10.80 for calendar year 2020 applies to all contracts subject to the Davis-Bacon Act for which the contract is awarded (and any solicitation was issued) on or after January 1, 2015. If this contract is covered by the EO, the contractor must pay all workers in any classification listed on this wage determination at least \$10.80 per hour (or the applicable wage rate listed on this wage determination, if it is higher) for all hours spent performing on the contract in calendar year 2020. If this contract is covered by the EO and a classification considered necessary for performance of work on the contract does not appear on this wage determination, the contractor must pay workers in that classification at least the wage rate determined through the conformance process set forth in 29 CFR 5.5(a)(1)(ii) (or the EO minimum wage rate, if it is higher than the conformed wage rate). The EO minimum wage rate will be adjusted annually. Please note that this EO applies to the above-mentioned types of contracts entered into by the federal government that are subject to the Davis-Bacon Act itself, but it does not apply to contracts subject only to the Davis-Bacon Related Acts, including those set forth at 29 CFR 5.1(a)(2)-(60). Additional information on contractor requirements and worker protections under the EO is available at www.dol.gov/whd/govcontracts.

Modification	Number	Publication	Date
0		01/03/2020	
1		01/24/2020	
2		02/28/2020	
3		03/06/2020	
4		06/05/2020	
5		06/12/2020	
6		06/19/2020	
7		07/17/2020	
8		08/28/2020	

9	09/11/2020
10	09/18/2020
11	10/02/2020

BRWI0001-002 06/03/2019

CRAWFORD, JACKSON, JUNEAU, LA CROSSE, MONROE, TREMPEALEAU, AND VERNON COUNTIES

	Rates	Fringes
BRICKLAYER		24.28
BRWI0002-002 06/01/2019		
ASHLAND, BAYFIELD, DOUGLAS, AND	IRON COUNTIES	
	Rates	Fringes
BRICKLAYER	\$ 39.94	23.30
BRWI0002-005 06/01/2019		

ADAMS, ASHLAND, BARRON, BROWN, BURNETT, CALUMET, CHIPPEWA, CLARK, COLUMBIA, DODGE, DOOR, DUNN, FLORENCE, FOND DU LAC, FOREST, GREEN LAKE, IRON, JEFFERSON, KEWAUNEE, LANGLADE, LINCOLN, MANITOWOC, MARATHON, MARINETTE, MARQUETTE, MENOMINEE, OCONTO, ONEIDA, OUTAGAMIE, POLK, PORTAGE, RUSK, ST CROIX, SAUK, SHAWANO, SHEBOYGAN, TAYLOR, VILAS, WALWORTH, WAUPACA, WAUSHARA, WINNEBAGO, AND WOOD COUNTIES

	Rates	Fringes
CEMENT MASON/CONCRETE FINISHER	.\$ 35.51	23.37
BRWI0003-002 06/03/2019		
BROWN, DOOR, FLORENCE, KEWAUNEE,	MARINETTE,	AND OCONTO COUNTIES
	Rates	Fringes
BRICKLAYER	.\$ 34.18	23.90
BRWI0004-002 06/01/2019		
KENOSHA, RACINE, AND WALWORTH CO	UNTIES	

Rates Fringes

BRICKLAYER	\$ 38.43	25.10	
BRWI0006-002 06/01/2019			
ADAMS, CLARK, FOREST, LANGLADE, ONEIDA, PORTAGE, PRICE, TAYLOR,			
	Rates	Fringes	
BRICKLAYER BRWI0007-002 06/03/2019		23.02	
GREEN, LAFAYETTE, AND ROCK COUN	TIES		
	Rates	Fringes	
BRICKLAYER	\$ 35.57	24.22	
BRWI0008-002 06/01/2019			
MILWAUKEE, OZAUKEE, WASHINGTON,	AND WAUKESHA	COUNTIES	
	Rates	Fringes	
BRICKLAYER			
BRWI0011-002 06/03/2019			
CALUMET, FOND DU LAC, MANITOWOC, AND SHEBOYGAN COUNTIES			
	Rates	Fringes	
BRICKLAYER		23.90	
BRWI0019-002 06/03/2019			
BARRON, BUFFALO, BURNETT, CHIPPEWA, DUNN, EAU CLAIRE, PEPIN, PIERCE, POLK, RUSK, ST. CROIX, SAWYER AND WASHBURN COUNTIES			
	Rates	Fringes	
BRICKLAYER BRWI0034-002 06/03/2019	•	24.68	
COLUMBIA AND SAUK COUNTIES			

	Rates	Fringes
BRICKLAYER	\$ 35.56	24.23

CARP0087-001 05/01/2016

BURNETT (W. of Hwy 48), PIERCE (W. of Hwy 29), POLK (W. of Hwys 35, 48 & 65), AND ST. CROIX (W. of Hwy 65) COUNTIES

	Rates	Fringes	
Carpenter & Piledrivermen	\$ 36.85	18.39	
CARROSES 003 06 /01 /3016			

CARP0252-002 06/01/2016

ADAMS, BARRON, BAYFIELD (Eastern 2/3), BROWN, BUFFALO, BURNETT (E. of Hwy 48), CALUMET, CHIPPEWA, CLARK, COLUMBIA, CRAWFORD, DANE, DODGE, DOOR, DUNN, EAU CLAIRE, FLORENCE (except area bordering Michigan State Line), FOND DU LAC, FOREST, GRANT, GREEN, GREEN LAKE, IOWA, IRON, JACKSON, JEFFERSON, JUNEAU, KEWAUNEE, LA CROSSE, LAFAYETTE, LANGLADE, LINCOLN, MANITOWOC, MARATHON, MARINETTE (except N.E. corner), MARQUETTE, MENOMINEE, MONROE, OCONTO, ONEIDA, OUTAGAMIE, PEPIN, PIERCE (E. of Hwys 29 & 65), POLK (E. of Hwys 35, 48 & 65), PORTAGE, PRICE, RICHLAND, ROCK, RUSK, SAUK, SAWYER, SHAWANO, SHEBOYGAN, ST CROIX (E. of Hwy 65), TAYLOR, TREMPEALEAU, VERNON, VILAS, WALWORTH, WASHBURN, WAUPACA, WAUSHARA, WINNEBAGO, AND WOOD COUNTIES

F	Rates	Fringes
CARPENTER		
CARPENTER\$	33.56	18.00
MILLWRIGHT\$	35.08	18.35
PILEDRIVER\$	34.12	18.00

# CARP0252-010 06/01/2016

## ASHLAND COUNTY

	Rates	Fringes
Carpenters		
Carpenter	.\$ 33.56	18.00
Millwright	.\$ 35.08	18.35
Pile Driver	.\$ 34.12	18.00

# CARP0264-003 06/01/2016

KENOSHA, MILWAUKEE, OZAUKEE, RACINE, WAUKESHA, AND WASHINGTON COUNTIES

	Rates	Fringes	
CARPENTER	\$ 35.78	22.11	
CARP0361-004 05/01/2018			
BAYFIELD (West of Hwy 63) AND DOUGLAS COUNTIES			
	Rates	Fringes	
CARPENTER	•	20.43	
CARRADA - 0.0 / 0.1 / 2.0 / 6			

CARP2337-001 06/01/2016

ZONE A: MILWAUKEE, OZAUKEE, WAUKESHA AND WASHINGTON

ZONE B: KENOSHA & RACINE

**REMAINING COUNTIES** 

	Rates	Fringes
PILEDRIVERMAN		
Zone A	\$ 31.03	22.69
Zone B	\$ 31.03	22.69
ELEC0014-002 06/14/2020		

ASHLAND, BARRON, BAYFIELD, BUFFALO, BURNETT, CHIPPEWA, CLARK (except Maryville, Colby, Unity, Sherman, Fremont, Lynn & Sherwood), CRAWFORD, DUNN, EAU CLAIRE, GRANT, IRON, JACKSON, LA CROSSE, MONROE, PEPIN, PIERCE, POLK, PRICE, RICHLAND, RUSK, ST CROIX, SAWYER, TAYLOR, TREMPEALEAU, VERNON, AND WASHBURN COUNTIES

	Rates	Fringes
Electricians:	\$ 35.98	20.98
ELEC0014-007 07/05/2020		

Rates Fringes

Teledata System Installer Installer/Technician.....\$ 27.75

15.14

Low voltage construction, installation, maintenance and removal of teledata facilities (voice, data, and video) including outside plant, telephone and data inside wire, interconnect, terminal equipment, central offices, PABX, fiber optic cable and equipment, micro waves, V-SAT, bypass, CATV, WAN (wide area networks), LAN (local area networks), and ISDN (integrated systems digital network).

ELEC0127-002 06/01/2020

KENOSHA COUNTY

Rates Fringes

Electricians:.....\$ 41.62 30%+12.70

\_\_\_\_\_\_

BROWN, DOOR, KEWAUNEE, MANITOWOC (except Schleswig), MARINETTE(Wausuakee and area South thereof), OCONTO, MENOMINEE (East of a ine 6 miles West of the West boundary of Oconto County), SHAWANO (Except Area North of Townships of Aniwa and Hutchins) COUNTIES

> Rates Fringes

ELECTRICIAN.....\$ 34.77 29.75%+10.26 \_\_\_\_\_\_

ELEC0159-003 08/02/2020

COLUMBIA, DANE, DODGE (Area West of Hwy 26, except Chester and Emmet Townships), GREEN, LAKE (except Townships of Berlin, Seneca, and St. Marie), IOWA, MARQUETTE (except Townships of Neshkoka, Crystal Lake, Newton, and Springfield), and SAUK COUNTIES

Rates Fringes

ELECTRICIAN.....\$ 41.86

ELEC0219-004 06/01/2019

FLORENCE COUNTY (Townships of Aurora, Commonwealth, Fern,

<sup>\*</sup> ELEC0158-002 06/01/2020

Florence and Homestead) AND MARINETTE COUNTY (Township of Niagara)

	Rates	Fringes	
Electricians: Electrical contracts over \$180,000 Electrical contracts under	\$ 33.94	21.80	
\$180,000	\$ 31.75	21.73	
* ELEC0242-005 05/31/2020			
DOUGLAS COUNTY			
	Rates	Fringes	
Electricians:		28.11	
ELEC0388-002 06/01/2020			
ADAMS, CLARK (Colby, Freemont, Lynn, Mayville, Sherman, Sherwood, Unity), FOREST, JUNEAU, LANGLADE, LINCOLN, MARATHON, MARINETTE (Beecher, Dunbar, Goodman & Pembine), MENOMINEE (Area West of a line 6 miles West of the West boundary of Oconto County), ONEIDA, PORTAGE, SHAWANO (Aniwa and Hutchins), VILAS AND WOOD COUNTIES			
	Rates	Fringes	
Electricians:	•	26%+11.20	
ELEC0430-002 06/01/2020			
RACINE COUNTY (Except Burlington	Township)		
	Rates	Fringes	
Electricians:	•	22.66	
ELEC0494-005 06/01/2020			
MILWAUKEE, OZAUKEE, WASHINGTON, AND WAUKESHA COUNTIES			
	Datas		
	Rates	Fringes	

### ELEC0494-006 06/01/2020

CALUMET (Township of New Holstein), DODGE (East of Hwy 26 including Chester Township), FOND DU LAC, MANITOWOC (Schleswig), and SHEBOYGAN COUNTIES

	Rates	Fringes
Electricians:	.\$ 36.32	22.51
ELEC0494-013 06/07/2020		

DODGE (East of Hwy 26 including Chester Twp, excluding Emmet Twp), FOND DU LAC (Except Waupuin), MILWAUKEE, OZAUKEE, MANITOWOC (Schleswig), WASHINGTON, AND WAUKESHA COUNTIES

	Rates	Fringes
Sound & Communications		
Installer	\$ 21.46	18.52
Technician	\$ 31.34	20.00

Installation, testing, maintenance, operation and servicing of all sound, intercom, telephone interconnect, closed circuit TV systems, radio systems, background music systems, language laboratories, electronic carillion, antenna distribution systems, clock and program systems and low-voltage systems such as visual nurse call, audio/visual nurse call systems, doctors entrance register systems. Includes all wire and cable carrying audio, visual, data, light and radio frequency signals. Includes the installation of conduit, wiremold, or raceways in existing structures that have been occupied for six months or more where required for the protection of the wire or cable, but does not mean a complete conduit or raceway system. work covered does not include the installation of conduit, wiremold or any raceways in any new construction, or the installation of power supply outlets by means of which external electric power is supplied to any of the foregoing equipment or products

FLECOE77, 002, 06 /01 /2010

### ELEC0577-003 06/01/2019

CALUMET (except Township of New Holstein), GREEN LAKE (N. part including Townships of Berlin, St Marie, and Seneca), MARQUETTE (N. part including Townships of Crystal Lake, Neshkoro, Newton, and Springfield), OUTAGAMIE, WAUPACA, WAUSHARA, AND WINNEBAGO

# COUNTIES

	Rates	Fringes	
Electricians:	\$ 33.15	28.50%+10.00	
ELEC0890-003 06/01/2020			
DODGE (Emmet Township only), GREE RACINE (Burlington Township), ROC			
	Rates	Fringes	
Electricians:	\$ 37.41	25.95%+11.11	
ELEC0953-001 06/02/2019			
	Rates	Fringes	
Line Construction: (1) Lineman	\$ 47.53	21.43	
Operator		19.80	
(3) Equipment Operator		18.40	
<ul><li>(4) Heavy Groundman Driver</li><li>(5) Light Groundman Driver</li></ul>		16.88 16.11	
(6) Groundsman		14.60	
ENGI0139-005 06/01/2020			
	Rates	Fringes	
Power Equipment Operator			
Group 1	\$ 41.62	23.80	
Group 2	\$ 41.12	23.80	
Group 3		23.80	
Group 4		23.80	
Group 5		23.80	
Group 6	<b>34.1</b> /	23.80	
HAZARDOUS WASTE PREMIUMS: EPA Level ""A"" protection - \$3.0 EPA Level ""B"" protection - \$2. EPA Level ""C"" protection - \$1.0	00 per hour		
POWER EQUIPMENT OPERATORS CLASSIFICATIONS			

GROUP 1: Cranes, tower cranes, and derricks with or without

attachments with a lifting capacity of over 100 tons; or cranes, tower cranes, and derricks with boom, leads and/or jib lengths measuring 176 feet or longer.

GROUP 2: Cranes, tower cranes and derricks with or without attachments with a lifting capacity of 100 tons or less; or cranes, tower cranes, and derricks with boom, leads, and/or jibs lengths measuring 175 feet or under and Backhoes (excavators) weighing 130,000 lbs and over; caisson rigs; pile driver; dredge operator; dredge engineer; Boat Pilot.

GROUP 3: Mechanic or welder - Heavy duty equipment; cranes with a lifting capacity of 25 tons or under; concrete breaker (manual or remote); vibratory/sonic concrete breaker; concrete laser screed; concrete slipform paver; concrete batch plant operator; concrete pvt. spreader heavy duty (rubber tired); concrete spreader & distributor; automatic subgrader (concrete); concrete grinder & planing machine; concrete slipform curb & gutter machine; slipform concrete placer; tube finisher; hydro blaster (10,000 psi & over); bridge paver; concrete conveyor system; concrete pump; Rotec type Conveyor; stabilizing mixer (self-propelled); shoulder widener; asphalt plant engineer; bituminious paver; bump cutter & grooving machine; milling machine; screed (bituminous paver); asphalt heater, planer & scarifier; Backhoes (excavators) weighing under 130,000 lbs; grader or motor patrol; tractor (scraper, dozer, pusher, loader); scraper - rubber tired (single or twin engine); endloader; hydraulic backhoe (tractor type); trenching machine; skid rigs; tractor, side boom (heavy); drilling or boring machine (mechanical heavy); roller over 5 tons; percussion or rotary drilling machine; air track; blaster; loading machine (conveyor); tugger; boatmen; winches & A-frames; post driver; material hoist.

GROUP 4: Greaser, roller steel (5 tons or less); roller (pneumatic tired) - self propelled; tractor (mounted or towed compactors & light equipment); shouldering machine; self- propelled chip spreader; concrete spreader; finishing machine; mechanical float; curing machine; power subgrader; joint sawer (multiple blade) belting machine; burlap machine; texturing machine; tractor endloader (rubber tired) - light; jeep digger; forklift; mulcher; launch operator; fireman, environmental burner

GROUP 5: Air compressor; power pack; vibrator hammer and extractor; heavy equipment, leadman; tank car heaters; stump chipper; curb machine operator; Concrete proportioning plants; generators; mudjack operator; rock breaker; crusher or screening plant; screed (milling

machine); automatic belt conveyor and surge bin; pug mill operator; Oiler, pump (over 3 inches); Drilling Machine Tender.

GROUP 6: Off-road material hauler with or without ejector.

-----

IRON0008-002 06/01/2020

BROWN, CALUMET, DOOR, FOND DU LAC, KEWAUNEE, MANITOWOC, MARINETTE, OCONTO, OUTAGAMI, SHAWANO, SHEBOYGAN, AND WINNEBAGO COUNTIES:

Rates Fringes

IRONWORKER.....\$ 37.31 27.62

Paid Holidays: New Year's Day, Memorial Day, July 4th, Labor Day, Thanksgiving Day & Christmas Day.

-----

IRON0008-003 06/01/2020

KENOSHA, MILWAUKEE, OZAUKEE, RACINE, WALWORTH (N.E. 2/3), WASHINGTON, AND WAUKESHA COUNTIES

Rates Fringes

IRONWORKER.....\$ 39.11 27.87

Paid Holidays: New Year's Day, Memorial Day, July 4th, Labor Day, Thanksgiving Day & Christmas Day.

\_\_\_\_\_

IRON0383-001 06/01/2020

ADAMS, COLUMBIA, CRAWFORD, DANE, DODGE, FLORENCE, FOREST, GRANT, GREENE, (Excluding S.E. tip), GREEN LAKE, IOWA, JEFFERSON, JUNEAU, LA CROSSE, LAFAYETTE, LANGLADE, MARATHON, MARQUETTE, MENOMINEE, MONROE, PORTAGE, RICHLAND, ROCK (Northern area, vicinity of Edgerton and Milton), SAUK, VERNON, WAUPACA, WAUSHARA, AND WOOD COUNTIES

	Rates	Fringes	
IRONWORKER	\$ 37.10	27.06	

### IRON0498-005 06/01/2019

GREEN (S.E. 1/3), ROCK (South of Edgerton and Milton), and WALWORTH (S.W. 1/3) COUNTIES:

	Rates	Fringes
IRONWORKER	\$ 40.25	40.53
IRON0512-008 06/03/2019		

BARRON, BUFFALO, CHIPPEWA, CLARK, DUNN, EAU CLAIRE, JACKSON, PEPIN, PIERCE, POLK, RUSK, ST CROIX, TAYLOR, AND TREMPEALEAU COUNTIES

	Rates	Fringes
IRONWORKER	\$ 37.60	29.40
IRON0512-021 06/03/2019		

ASHLAND, BAYFIELD, BURNETT, DOUGLAS, IRON, LINCOLN, ONEIDA, PRICE, SAWYER, VILAS AND WASHBURN COUNTIES

	Rates	Fringes
IRONWORKER	\$ 33.19	29.40
LAB00113-002 06/01/2020		

# MILWAUKEE AND WAUKESHA COUNTIES

	F	Rates	Fringes
LABORER			
•	1\$		22.26
Group	2\$	30.20	22.26
Group	3\$	30.40	22.26
Group	4\$	30.55	22.26
Group	5\$	30.70	22.26
Group	6\$	26.54	22.26

# LABORERS CLASSIFICATIONS

GROUP 1: General Laborer; Tree Trimmer; Conduit Layer; Demolition and Wrecking Laborer; Guard Rail, Fence, and Bridge Builder; Landscaper; Multiplate Culvert Assembler; Stone Handler; Bituminous Worker (Shoveler, Loader, and Utility Man); Batch Truck Dumper or Cement Handler; Bituminous Worker (Dumper, Ironer, Smoother, and Tamper); Concrete Handler

GROUP 2: Air Tool Operator; Joint Sawer and Filler (Pavement); Vibrator or Tamper Operator (Mechanical Hand Operated); Chain Saw Operator; Demolition Burning Torch Laborer

GROUP 3: Bituminous Worker (Raker and Luteman); Formsetter (Curb, Sidewalk, and Pavement); Strike Off Man

GROUP 4: Line and Grade Specialist

GROUP 5: Blaster and Powderman

GROUP 6: Flagperson; traffic control person

-----

LAB00113-003 06/01/2020

#### OZAUKEE AND WASHINGTON COUNTIES

	Rates	Fringes
LABORER		
Group	1\$ 29.3	0 22.26
Group	2\$ 29.4	0 22.26
Group	3\$ 29.4	5 22.26
Group	4\$ 29.6	5 22.26
Group	5\$ 29.5	0 22.26
Group	6\$ 26.3	9 22.26

### LABORERS CLASSIFICATIONS

GROUP 1: General Laborer; Tree Trimmer; Conduit Layer; Demolition and Wrecking Laborer; Guard Rail, Fence, and Bridge Builder; Landscaper; Multiplate Culvert Assembler; Stone Handler; Bituminous Worker (Shoveler, Loader, and Utility Man); Batch Truck Dumper or Cement Handler; Bituminous Worker (Dumper, Ironer, Smoother, and Tamper); Concrete Handler

GROUP 2: Air Tool Operator; Joint Sawer and Filler (Pavement); Vibrator or Tamper Operator (Mechanical Hand Operated);

GROUP 3: Bituminous Worker (Raker and Luteman); Formsetter (Curb, Sidewalk, and Pavement); Strike Off Man

GROUP 4: Line and Grade Specialist

GROUP 5: Blaster; powderman

GROUP 6: Flagperson and Traffic Control Person

-----

LABO0113-011 06/01/2020

# KENOSHA AND RACINE COUNTIES

	Rates	Fringes
LABORER		
Group 1	\$ 29.11	22.26
Group 2	\$ 29.26	22.26
Group 3	\$ 29.46	22.26
Group 4	\$ 29.43	22.26
Group 5	\$ 29.76	22.26
Group 6	\$ 26.25	22.26

#### LABORERS CLASSIFICATIONS:

GROUP 1: General laborer; Tree Trimmer; Conduit Layer; Demolition and Wrecking Laborer; Guard Rail, Fence, and Bridge Builder; Landscaper; Multiplate Culvert Assembler; Stone Handler; Bituminous Worker (Shoveler, Loader, and Utility Man); Batch Truck Dumper or Cement Handler; Bituminous worker (Dumper, Ironer, Smoother, and Tamper); Concrete Handler

GROUP 2: Air Tool Operator; Joint Sawer and Filler (Pavement); Vibrator or Tamper Operator (Mechanical Hand Operated); Chain Saw Operator; Demolition Burning Torch Laborer

GROUP 3: Bituminous Worker (Raker and Luteman); Formsetter (Curb, Sidewalk, and Pavement); Strike Off Man

GROUP 4: Line and Grade Specialist

GROUP 5: Blaster and Powderman

GROUP 6: Flagman; traffic control person

\_\_\_\_\_\_

LABO0140-002 06/01/2020

ADAMS, ASHLAND, BARRON, BAYFIELD, BROWN, BUFFALO, BURNETT,

CALUMET, CHIPPEWA, CLARK, COLUMBIA, CRAWFORD, DODGE, DOOR, DOUGLAS, DUNN, EAU CLAIRE, FLORENCE, FOND DU LAC, FOREST, GRANT, GREEN, GREEN LAKE, IRON, JACKSON, JUNEAU, IOWA, JEFFERSON, KEWAUNEE, LA CROSSE, LAFAYETTE, LANGLADE, LINCOLN, MANITOWOC, MARATHON, MARINETTE, MARQUETTE, MENOMINEE, MONROE, OCONTO, ONEIDA, OUTAGAMIE, PEPIN, PIERCE, POLK, PORTAGE, PRICE, RICHLAND, ROCK, RUSK, SAUK, SAWYER, SHAWANO, SHEBOYGAN, ST. CROIX, TAYLOR, TREMPEALEAU, VERNON, VILLAS, WALWORTH, WASHBURN, WAUPACA, WAUSHARA, WINNEBAGO, AND WOOD COUNTIES

		Rates	Fringes
LABORER			
Group	1	\$ 33.72	17.95
Group	2	\$ 33.82	17.95
Group	3	\$ 33.87	17.95
Group	4	\$ 34.07	17.95
Group	5	\$ 33.92	17.95
Group	6	\$ 30.35	17.95

#### LABORER CLASSIFICATIONS

GROUP 1: General Laborer; Tree Trimmer; Conduit Layer; Demolition and Wrecking Laborer; Guard Rail, Fence, and Bridge Builder; Landscaper; Multiplate Culvert Assembler; Stone Handler; Bitminous Worker (Shoveler, Loader, and Utility Man); Batch Truck Dumper or Cement Handler; Bituminous Worker (Dumper, Ironer, Smoother and Tamper); Concrete Handler

GROUP 2: Air Tool Operator; Joint Sawer and Filler (Pavement); Vibrator or Tamper Operator (Mechanical Hand Operated); Chain Saw Operator, Demolition Burning Torch Laborer

GROUP 3: Bituminous Worker (Raker and Luteman); Formsetter (Curb, Sidewalk and Pavement); Strike Off Man

GROUP 4: Line and Grade Secialist

GROUP 5: Blaster; powderman

GROUP 6: Flagperson; Traffic Control

\_\_\_\_\_\_

LAB00464-003 06/01/2020

DANE COUNTY

	Ra	ites	Fringes
LABORER			
Group	1\$ 3	34.00	17.95
Group	2\$ 3	34.10	17.95
Group	3\$ 3	34.15	17.95
Group	4\$ 3	34.35	17.95
Group	5\$ 3	34.20	17.95
Group	6\$ 3	30.35	17.95

#### LABORERS CLASSIFICATIONS:

GROUP 1: General Laborer; Tree Trimmer; Conduit Layer; Demolition and Wrecking Laborer; Guard Rail, Fence, and Bridge Builder; Landscaper; Multiplate Culvert Assembler; Stone Handler; Bituminous Worker (Shoveler, Loader, and Utility Man); Batch Truck Dumper or Cement Handler; Bituminious Worker (Dumper, Ironer, Smoother, and Tamper); Concrete Handler

GROUP 2: Air Tool Operator; Joint Sawer and Filler (Pavement); Vibrator or Tamper Operator (Mechanical Hand Operated); Chain Saw Operator; Demolition Burning Torch Laborer

GROUP 3: Bituminous Worker (Raker and Luteman); Formsetter (Curb, Sidewalk, and Pavement); Strike Off Man

GROUP 4: Line and Grade Specialist

GROUP 5: Blaster; Powderman

GROUP 6: Flagperson and Traffic Control Person

-----

PAIN0106-008 05/01/2017

ASHLAND, BAYFIELD, BURNETT, AND DOUGLAS COUNTIES

	F	Rates	Fringes
Painters:			
New:			
Brush,	Roller\$	30.33	17.27
Spray,	Sandblast, Steel\$	30.93	17.27
Repaint	•		
Brush,	Roller\$	28.83	17.27
Spray,	Sandblast, Steel\$	29.43	17.27

PAIN0108-002 06/01/2019

# RACINE COUNTY

	Rates	Fringes
Painters: Brush, Roller Spray & Sandblast	\$ 37.08	20.36 20.36
PAIN0259-002 05/01/2008		
BARRON, CHIPPEWA, DUNN, EAU CLAIF SAWYER, ST. CROIX, AND WASHBURN O		PIERCE, POLK, RUSK,
	Rates	Fringes
PAINTER	\$ 24.11	12.15
PAIN0259-004 05/01/2015		
BUFFALO, CRAWFORD, JACKSON, LA CF VERNON COUNTIES	ROSSE, MONR	OE, TREMPEALEAU, AND
	Rates	Fringes
PAINTER	•	
PAIN0781-002 06/01/2019		
JEFFERSON, MILWAUKEE, OZAUKEE, WA	ASHINGTON,	AND WAUKESHA COUNTIES
	Rates	Fringes
Painters:     Bridge	\$ 32.95	23.86 23.86 23.86
COLUMBIA, DANE, DODGE, GRANT, GRE ROCK, AND SAUK COUNTIES	EEN, IOWA,	LAFAYETTE, RICHLAND,
	Rates	Fringes
PAINTER Brush	\$ 30.93	18.44

### PREMIUM PAY:

Structural Steel, Spray, Bridges = \$1.00 additional per hour

\_\_\_\_\_

PAIN0802-003 06/01/2019

ADAMS, BROWN, CALUMET, CLARK, DOOR, FOND DU LAC, FOREST, GREEN LAKE, IRON, JUNEAU, KEWAUNEE, LANGLADE, LINCOLN, MANITOWOC, MARATHON, MARINETTE, MARQUETTE, MENOMINEE, OCONTO, ONEIDA, OUTAGAMIE, PORTAGE, PRICE, SHAWANO, SHEBOYGAN, TAYLOR, VILAS, WAUSHARA, WAUPACA, WINNEBAGO, AND WOOD COUNTIES

WAUSHAKA, WAUPACA, WINNEBAGO, AND WOOD COUNTIES			
	Rates	Fringes	
PAINTER		18.58	
PAIN0934-001 06/01/2017			
KENOSHA AND WALWORTH COUNTIES			
	Rates	Fringes	
Painters: Brush Spray Structural Steel	.\$ 34.74	18.95 18.95 18.95	
PAIN1011-002 06/02/2019			
FLORENCE COUNTY			
	Rates	Fringes	
Painters:	.\$ 25.76	13.33	

PLAS0599-010 06/01/2017

	Rates	Fringes
CEMENT MASON/CONCRETE FINISHER		
Area 1	\$ 39.46	17.17
Area 2 (BAC)	\$ 35.07	19.75
Area 3	\$ 35.61	19.40
Area 4	\$ 34.70	20.51
Area 5	\$ 36.27	18.73
Area 6	\$ 32.02	22.99

#### AREA DESCRIPTIONS

AREA 1: BAYFIELD, DOUGLAS, PRICE, SAWYER, AND WASHBURN COUNTIES

AREA 2: ADAMS, ASHLAND, BARRON, BROWN, BURNETT, CALUMET, CHIPPEWA, CLARK, COLUMBIA, DODGE, DOOR, DUNN, FLORENCE, FOND DU LAC, FOREST, GREEN LAKE, IRON, JEFFERSON, KEWAUNEE, LANGLADE, LINCOLN, MANITOWOC, MARATHON, MARINETTE, MARQUETTE, MENOMINEE, OCONTO, ONEIDA, OUTAGAMIE, POLK, PORTAGE, RUSK, ST CROIX, SAUK, SHAWANO, SHEBOYGAN, TAYLOR, VILAS, WALWORTH, WAUPACA, WAUSHARA, WINNEBAGO, AND WOOD COUNTIES

AREA 3: BUFFALO, CRAWFORD, EAU CLAIRE, JACKSON, JUNEAU, LA CROSSE MONROE, PEPIN, PIERCE, RICHLAND, TREMPEALEAU, AND VERNON COUNTIES

AREA 4: MILWAUKEE, OZAUKEE, WASHINGTON, AND WAUKESHA COUNTIES

AREA 5: DANE, GRANT, GREEN, IOWA, LAFAYETTE, AND ROCK COUNTIES

AREA 6: KENOSHA AND RACINE COUNTIES

\_\_\_\_\_

TEAM0039-001 06/01/2020

	Rates	Fringes
TRUCK DRIVER  1 & 2 Axles  3 or more Axles; Euclids, Dumptor & Articulated,	\$ 31.07	22.94
Truck Mechanic	\$ 31.22	22.94
WELL DRILLER	\$ 16.52	3.70

WELDERS - Receive rate prescribed for craft performing operation to which welding is incidental.

\_\_\_\_\_\_

Note: Executive Order (EO) 13706, Establishing Paid Sick Leave for Federal Contractors applies to all contracts subject to the Davis-Bacon Act for which the contract is awarded (and any solicitation was issued) on or after January 1, 2017. If this contract is covered by the EO, the contractor must provide

employees with 1 hour of paid sick leave for every 30 hours they work, up to 56 hours of paid sick leave each year. Employees must be permitted to use paid sick leave for their own illness, injury or other health-related needs, including preventive care; to assist a family member (or person who is like family to the employee) who is ill, injured, or has other health-related needs, including preventive care; or for reasons resulting from, or to assist a family member (or person who is like family to the employee) who is a victim of, domestic violence, sexual assault, or stalking. Additional information on contractor requirements and worker protections under the EO is available at www.dol.gov/whd/govcontracts.

Unlisted classifications needed for work not included within the scope of the classifications listed may be added after award only as provided in the labor standards contract clauses (29CFR 5.5 (a) (1) (ii)).

-----

The body of each wage determination lists the classification and wage rates that have been found to be prevailing for the cited type(s) of construction in the area covered by the wage determination. The classifications are listed in alphabetical order of ""identifiers"" that indicate whether the particular rate is a union rate (current union negotiated rate for local), a survey rate (weighted average rate) or a union average rate (weighted union average rate).

### Union Rate Identifiers

A four letter classification abbreviation identifier enclosed in dotted lines beginning with characters other than ""SU"" or ""UAVG"" denotes that the union classification and rate were prevailing for that classification in the survey. Example: PLUM0198-005 07/01/2014. PLUM is an abbreviation identifier of the union which prevailed in the survey for this classification, which in this example would be Plumbers. 0198 indicates the local union number or district council number where applicable, i.e., Plumbers Local 0198. The next number, 005 in the example, is an internal number used in processing the wage determination. 07/01/2014 is the effective date of the most current negotiated rate, which in this example is July 1, 2014.

Union prevailing wage rates are updated to reflect all rate changes in the collective bargaining agreement (CBA) governing this classification and rate.

# Survey Rate Identifiers

Classifications listed under the ""SU"" identifier indicate that no one rate prevailed for this classification in the survey and the published rate is derived by computing a weighted average rate based on all the rates reported in the survey for that classification. As this weighted average rate includes all rates reported in the survey, it may include both union and non-union rates. Example: SULA2012-007 5/13/2014. SU indicates the rates are survey rates based on a weighted average calculation of rates and are not majority rates. LA indicates the State of Louisiana. 2012 is the year of survey on which these classifications and rates are based. The next number, 007 in the example, is an internal number used in producing the wage determination. 5/13/2014 indicates the survey completion date for the classifications and rates under that identifier.

Survey wage rates are not updated and remain in effect until a new survey is conducted.

Union Average Rate Identifiers

Classification(s) listed under the UAVG identifier indicate that no single majority rate prevailed for those classifications; however, 100% of the data reported for the classifications was union data. EXAMPLE: UAVG-OH-0010 08/29/2014. UAVG indicates that the rate is a weighted union average rate. OH indicates the state. The next number, 0010 in the example, is an internal number used in producing the wage determination. 08/29/2014 indicates the survey completion date for the classifications and rates under that identifier.

A UAVG rate will be updated once a year, usually in January of each year, to reflect a weighted average of the current negotiated/CBA rate of the union locals from which the rate is based.

-----

# WAGE DETERMINATION APPEALS PROCESS

- 1.) Has there been an initial decision in the matter? This can be:
- \* an existing published wage determination
- \* a survey underlying a wage determination
- \* a Wage and Hour Division letter setting forth a position on

- a wage determination matter
- \* a conformance (additional classification and rate) ruling

On survey related matters, initial contact, including requests for summaries of surveys, should be with the Wage and Hour Regional Office for the area in which the survey was conducted because those Regional Offices have responsibility for the Davis-Bacon survey program. If the response from this initial contact is not satisfactory, then the process described in 2.) and 3.) should be followed.

With regard to any other matter not yet ripe for the formal process described here, initial contact should be with the Branch of Construction Wage Determinations. Write to:

Branch of Construction Wage Determinations Wage and Hour Division U.S. Department of Labor 200 Constitution Avenue, N.W. Washington, DC 20210

2.) If the answer to the question in 1.) is yes, then an interested party (those affected by the action) can request review and reconsideration from the Wage and Hour Administrator (See 29 CFR Part 1.8 and 29 CFR Part 7). Write to:

Wage and Hour Administrator U.S. Department of Labor 200 Constitution Avenue, N.W. Washington, DC 20210

The request should be accompanied by a full statement of the interested party's position and by any information (wage payment data, project description, area practice material, etc.) that the requestor considers relevant to the issue.

3.) If the decision of the Administrator is not favorable, an interested party may appeal directly to the Administrative Review Board (formerly the Wage Appeals Board). Write to:

Administrative Review Board U.S. Department of Labor 200 Constitution Avenue, N.W. Washington, DC 20210

4.) All decisions by the Administrative Review Board are final.

\_\_\_\_\_\_

"General Decision Number: WI20200015 10/02/2020

Superseded General Decision Number: WI20190015

State: Wisconsin

Construction Type: Heavy

Counties: Wisconsin Statewide.

HEAVY CONSTRUCTION PROJECTS (Excluding Tunnel, Sewer, and Water Lines).

Note: Under Executive Order (EO) 13658, an hourly minimum wage of \$10.80 for calendar year 2020 applies to all contracts subject to the Davis-Bacon Act for which the contract is awarded (and any solicitation was issued) on or after January 1, 2015. If this contract is covered by the EO, the contractor must pay all workers in any classification listed on this wage determination at least \$10.80 per hour (or the applicable wage rate listed on this wage determination, if it is higher) for all hours spent performing on the contract in calendar year 2020. If this contract is covered by the EO and a classification considered necessary for performance of work on the contract does not appear on this wage determination, the contractor must pay workers in that classification at least the wage rate determined through the conformance process set forth in 29 CFR 5.5(a)(1)(ii) (or the EO minimum wage rate, if it is higher than the conformed wage rate). The EO minimum wage rate will be adjusted annually. Please note that this EO applies to the above-mentioned types of contracts entered into by the federal government that are subject to the Davis-Bacon Act itself, but it does not apply to contracts subject only to the Davis-Bacon Related Acts, including those set forth at 29 CFR 5.1(a)(2)-(60). Additional information on contractor requirements and worker protections under the EO is available at www.dol.gov/whd/govcontracts.

Modification	Number	Publication Date
0		01/03/2020
1		01/24/2020
2		02/28/2020
3		03/06/2020
4		06/05/2020
5		06/12/2020
6		06/19/2020
7		07/03/2020
8		07/17/2020
9		07/24/2020

10	08/28/2020
11	09/11/2020
12	09/18/2020
13	10/02/2020

BOIL0107-001 01/01/2017

	Rates	Fringes
BOILERMAKER		
Boilermaker	\$ 35.65	29.89
Small Boiler Repair (under	•	
25,000 lbs/hr)	\$ 26.91	16.00

BRWI0001-002 06/03/2019

CRAWFORD, JACKSON, JUNEAU, LA CROSSE, MONROE, TREMPEALEAU, AND VERNON COUNTIES

	Rates	Fringes
BRICKLAYER	\$ 33.80	24.28
BRWI0002-002 06/01/2019		

ASHLAND, BAYFIELD, DOUGLAS, AND IRON COUNTIES

	Rates	Fringes
BRICKLAYER	.\$ 39.94	23.30
BRWI0002-005 06/01/2019		

ADAMS, ASHLAND, BARRON, BROWN, BURNETT, CALUMET, CHIPPEWA, CLARK, COLUMBIA, DODGE, DOOR, DUNN, FLORENCE, FOND DU LAC, FOREST, GREEN LAKE, IRON, JEFFERSON, KEWAUNEE, LANGLADE, LINCOLN, MANITOWOC, MARATHON, MARINETTE, MARQUETTE, MENOMINEE, OCONTO, ONEIDA, OUTAGAMIE, POLK, PORTAGE, RUSK, ST CROIX, SAUK, SHAWANO, SHEBOYGAN, TAYLOR, VILAS, WALWORTH, WAUPACA, WAUSHARA, WINNEBAGO, AND WOOD COUNTIES

	Rates	Fringes
CEMENT MASON/CONCRETE FINISHER.	\$ 35.51	23.37
BRWI0003-002 06/03/2019		

BROWN, DOOR, FLORENCE, KEWAUNEE, MARINETTE, AND OCONTO COUNTIES

	Rates	Fringes
BRICKLAYER	\$ 34.18	23.90
BRWI0004-002 06/01/2019		
KENOSHA, RACINE, AND WALWORTH C	OUNTIES	
	Rates	Fringes
BRICKLAYER	•	25.10
BRWI0006-002 06/01/2019		
ADAMS, CLARK, FOREST, LANGLADE, ONEIDA, PORTAGE, PRICE, TAYLOR,	-	
	Rates	Fringes
BRICKLAYER	\$ 35.06	23.02
BRWI0007-002 06/03/2019		
GREEN, LAFAYETTE, AND ROCK COUN	TIES	
	Rates	Fringes
BRICKLAYER		24.22
BRWI0008-002 06/01/2019		
MILWAUKEE, OZAUKEE, WASHINGTON,	AND WAUKES	HA COUNTIES
	Rates	Fringes
BRICKLAYER		24.22
BRWI0009-001 06/03/2019		
GREEN LAKE, MARQUETTE, OUTAGAMI AND WINNEBAGO COUNTIES	E, SHAWANO,	WAUPACA, WASHARA,
	Rates	Fringes
BRICKLAYER	•	23.90
BRWI0011-002 06/03/2019		

CALUMET,	FOND	DU	LAC,	MANITOWOC,	AND	SHEBOYGAN	COUNTIES
----------	------	----	------	------------	-----	-----------	----------

CALONET, TOND DO LAC, MANITOWOC,	AND SHEDO	TIGAN COUNTIES
	Rates	Fringes
BRICKLAYER		
BRWI0013-002 06/03/2019		
DANE, GRANT, IOWA, AND RICHLAND	COUNTIES	
	Rates	Fringes
BRICKLAYER	.\$ 35.56	24.23
BRWI0019-002 06/03/2019		
BARRON, BUFFALO, BURNETT, CHIPPEI PIERCE, POLK, RUSK, ST. CROIX, SA		
	Rates	Fringes
BRICKLAYER	.\$ 33.40	24.68
BRWI0021-002 06/03/2019		
DODGE AND JEFFERSON COUNTIES		
	Rates	Fringes
BRICKLAYER	.\$ 35.75	24.02
BRWI0034-002 06/03/2019		
COLUMBIA AND SAUK COUNTIES		
	Rates	Fringes
BRICKLAYER		24.23
CARP0087-001 05/01/2016		
BURNETT (W. of Hwy 48), PIERCE (N. 635, 48 & 65), AND ST. CROIX (W. 635)		

Carpenter & Piledrivermen......\$ 36.85

Rates Fringes

18.39

-----

#### CARP0252-002 06/01/2016

ADAMS, BARRON, BAYFIELD (Eastern 2/3), BROWN, BUFFALO, BURNETT (E. of Hwy 48), CALUMET, CHIPPEWA, CLARK, COLUMBIA, CRAWFORD, DANE, DODGE, DOOR, DUNN, EAU CLAIRE, FLORENCE (except area bordering Michigan State Line), FOND DU LAC, FOREST, GRANT, GREEN, GREEN LAKE, IOWA, IRON, JACKSON, JEFFERSON, JUNEAU, KEWAUNEE, LA CROSSE, LAFAYETTE, LANGLADE, LINCOLN, MANITOWOC, MARATHON, MARINETTE (except N.E. corner), MARQUETTE, MENOMINEE, MONROE, OCONTO, ONEIDA, OUTAGAMIE, PEPIN, PIERCE (E. of Hwys 29 & 65), POLK (E. of Hwys 35, 48 & 65), PORTAGE, PRICE, RICHLAND, ROCK, RUSK, SAUK, SAWYER, SHAWANO, SHEBOYGAN, ST CROIX (E. of Hwy 65), TAYLOR, TREMPEALEAU, VERNON, VILAS, WALWORTH, WASHBURN, WAUPACA, WAUSHARA, WINNEBAGO, AND WOOD COUNTIES

ı	Rates	Fringes
CARPENTER		
CARPENTER\$	33.56	18.00
MILLWRIGHT\$	35.08	18.35
PILEDRIVER\$	34.12	18.00

CARP0252-010 06/01/2016

ASHLAND COUNTY

	Rates	Fringes
Carpenters		
Carpenter	\$ 33.56	18.00
Millwright	\$ 35.08	18.35
Pile Driver	\$ 34.12	18.00
Millwright	\$ 35.08	18.35

CARP0264-003 06/01/2016

KENOSHA, MILWAUKEE, OZAUKEE, RACINE, WAUKESHA, AND WASHINGTON COUNTIES

	Rates	Fringes	
CARPENTER	\$ 35.78	22.11	
CARP0361-004 05/01/2018			-

BAYFIELD (West of Hwy 63) AND DOUGLAS COUNTIES

	Rates	Fringes	
CARPENTER	\$ 36.15	20.43	
CARD2227 001 06/01/2016			

CARP2337-001 06/01/2016

ZONE A: MILWAUKEE, OZAUKEE, WAUKESHA AND WASHINGTON

ZONE B: KENOSHA & RACINE

	Rates	Fringes
PILEDRIVERMAN  Zone A		22.69 22.69
CARP2337-003 06/01/2019		
	Rates	Fringes
MILLWRIGHT		
Zone A	\$ 33.58	21.53
Zone B	\$ 33.58	21.53

**ZONE DEFINITIONS** 

ZONE A: MILWAUKEE, OZAUKEE, WAUKESHA AND WASHINGTON COUNTIES

ZONE B: KENOSHA & RACINE COUNTIES

-----

ELEC0014-002 06/14/2020

ASHLAND, BARRON, BAYFIELD, BUFFALO, BURNETT, CHIPPEWA, CLARK (except Maryville, Colby, Unity, Sherman, Fremont, Lynn & Sherwood), CRAWFORD, DUNN, EAU CLAIRE, GRANT, IRON, JACKSON, LA CROSSE, MONROE, PEPIN, PIERCE, POLK, PRICE, RICHLAND, RUSK, ST CROIX, SAWYER, TAYLOR, TREMPEALEAU, VERNON, AND WASHBURN COUNTIES

	Rates	Fringes
Electricians:	\$ 35.98	20.98
ELEC0014-007 07/05/2020		

REMAINING COUNTIES

Rates Fringes

Teledata System Installer

Installer/Technician.....\$ 27.75

15.14

Low voltage construction, installation, maintenance and removal of teledata facilities (voice, data, and video) including outside plant, telephone and data inside wire, interconnect, terminal equipment, central offices, PABX, fiber optic cable and equipment, micro waves, V-SAT, bypass, CATV, WAN (wide area networks), LAN (local area networks), and ISDN (integrated systems digital network).

-----

ELEC0127-002 06/01/2020

KENOSHA COUNTY

Rates Fringes

Electricians:.....\$ 41.62 30%+12.70

-----

BROWN, DOOR, KEWAUNEE, MANITOWOC (except Schleswig), MARINETTE(Wausuakee and area South thereof), OCONTO, MENOMINEE (East of a ine 6 miles West of the West boundary of Oconto County), SHAWANO (Except Area North of Townships of Aniwa and Hutchins) COUNTIES

Rates Fringes

ELECTRICIAN.....\$ 34.77 29.75%+10.26

ELEC0159-003 08/02/2020

COLUMBIA, DANE, DODGE (Area West of Hwy 26, except Chester and Emmet Townships), GREEN, LAKE (except Townships of Berlin, Seneca, and St. Marie), IOWA, MARQUETTE (except Townships of Neshkoka, Crystal Lake, Newton, and Springfield), and SAUK COUNTIES

Rates Fringes

ELECTRICIAN.....\$ 41.86 22.67

-----

ELEC0219-004 06/01/2019

<sup>\*</sup> ELEC0158-002 06/01/2020

FLORENCE COUNTY (Townships of Aurora, Commonwealth, Fern, Florence and Homestead) AND MARINETTE COUNTY (Township of Niagara)

	Rates	Fringes
Electricians: Electrical contracts over \$180,000	\$ 33.94	21.80
\$180,000	\$ 31.75	21.73
* ELEC0242-005 05/31/2020		
DOUGLAS COUNTY		
	Rates	Fringes
Electricians:	\$ 39.77	28.11
ELEC0388-002 06/01/2020		
ADAMS, CLARK (Colby, Freemont, Ly Sherwood, Unity), FOREST, JUNEAU MARINETTE (Beecher, Dunbar, Goodn West of a line 6 miles West of the County), ONEIDA, PORTAGE, SHAWANG AND WOOD COUNTIES	J, LANGLADE, LIN nan & Pembine), ne West boundary	COLN, MARATHON, MENOMINEE (Area of Oconto
	Rates	Fringes
Electricians:	\$ 34.85	26%+11.20
ELEC0430-002 06/01/2020		
RACINE COUNTY (Except Burlington	Township)	
	Rates	Fringes
Electricians:	\$ 41.86	22.66
ELEC0494-005 06/01/2020		
MILWAUKEE, OZAUKEE, WASHINGTON, A	AND WAUKESHA COU	NTIES
	Rates	Fringes
Electricians:	.\$ 42.84	25.54

\_\_\_\_\_

## ELEC0494-006 06/01/2020

CALUMET (Township of New Holstein), DODGE (East of Hwy 26 including Chester Township), FOND DU LAC, MANITOWOC (Schleswig), and SHEBOYGAN COUNTIES

	Rates	Fringes
Electricians:	.\$ 36.32	22.51
ELEC0494-013 06/07/2020		

DODGE (East of Hwy 26 including Chester Twp, excluding Emmet Twp), FOND DU LAC (Except Waupuin), MILWAUKEE, OZAUKEE, MANITOWOC (Schleswig), WASHINGTON, AND WAUKESHA COUNTIES

	Rates	Fringes
Sound & Communications		
Installer	\$ 21.46	18.52
Technician	\$ 31.34	20.00

Installation, testing, maintenance, operation and servicing of all sound, intercom, telephone interconnect, closed circuit TV systems, radio systems, background music systems, language laboratories, electronic carillion, antenna distribution systems, clock and program systems and low-voltage systems such as visual nurse call, audio/visual nurse call systems, doctors entrance register systems. Includes all wire and cable carrying audio, visual, data, light and radio frequency signals. Includes the installation of conduit, wiremold, or raceways in existing structures that have been occupied for six months or more where required for the protection of the wire or cable, but does not mean a complete conduit or raceway system. work covered does not include the installation of conduit, wiremold or any raceways in any new construction, or the installation of power supply outlets by means of which external electric power is supplied to any of the foregoing equipment or products

\_\_\_\_\_

#### ELEC0577-003 06/01/2019

CALUMET (except Township of New Holstein), GREEN LAKE (N. part including Townships of Berlin, St Marie, and Seneca), MARQUETTE (N. part including Townships of Crystal Lake, Neshkoro, Newton,

and Springfield), OUTAGAMIE, WAUPACA, WAUSHARA, AND WINNEBAGO COUNTIES

	Rates	Fringes		
Electricians:				
ELEC0890-003 06/01/2020				
DODGE (Emmet Township only), GREEN, JEFFERSON, LAFAYETTE, RACINE (Burlington Township), ROCK AND WALWORTH COUNTIES				
	Rates	Fringes		
Electricians:	.\$ 37.41	25.95%+11.11		
ELEC0953-001 06/02/2019				
	Rates	Fringes		
Line Construction: (1) Lineman	.\$ 47.53	21.43		
Operator		19.80		
<ul><li>(3) Equipment Operator</li><li>(4) Heavy Groundman Driver.</li></ul>		18.40 16.88		
(5) Light Groundman Driver.		16.11		
(6) Groundsman		14.60		

ENGI0139-001 06/01/2020

KENOSHA, MILWAUKEE, OZAUKEE, RACINE, WASHINGTON, AND WAUKESHA COUNTIES

	Rates	Fringes
Power Equipment Operator		
Group 1	\$ 47.66	23.15
Group 2	\$ 47.16	23.15
Group 3	\$ 46.66	23.15
Group 4	\$ 45.97	23.15
Group 5	\$ 42.39	23.15
Group 6	\$ 37.24	23.15

HAZARDOUS WASTE PREMIUMS:

EPA Level ""A"" Protection: \$3.00 per hour EPA Level ""B"" Protection: \$2.00 per hour

# POWER EQUIPMENT OPERATORS CLASSIFICATIONS

GROUP 1: Cranes, Tower Cranes, Pedestal Tower Cranes and Derricks with or w/o attachments with a lifting capacity of over 100 tons; or Cranes, Tower Cranes, Pedestal Tower Cranes and Derricks with boom, leads, and/or jib lengths measuring 176 feet or longer; Self-Erecting Tower Cranes over 4000 lbs lifting capacity; All Cranes with Boom Dollies; Boring Machines (directional); Master Mechanic. \$0.50 additional per hour per 100 tons or 100 ft of boom over 200 ft or lifting capacity of crane over 200 tons to a maximum of 300 tons or 300 ft. Thereafter an increase of \$0.01 per ft or ton, whichever is greater.

GROUP 2: Cranes, Tower Cranes, Pedestal Tower Cranes and Derricks with or without attachments with a lifting capacity of 100 tons or less; or Cranes, Tower Cranes Portable Tower Cranes, Pedestal Tower Cranes and Derricks with boom, leadsand/or jib lengths measuring 175 feet or less; Backhoes (excavators) 130,000 lbs and over; Caisson Rigs; Pile Drivers; Boring Machines (vertical or horizontal), Versi-Lift, Tri-Lift, Gantry 20,000 lbs & over.

GROUP 3: Backhoe (excavator) under 130,000 lbs; Self-erecting Tower Crane 4000 lbs & under lifting capacity; Traveling Crane (bridge type); Skid Rigs; Dredge Operator; Mechanic; Concrete Paver (over 27E); Concrete Spreader and Distributor; Forklift/ Telehandler (machinery- moving / steel erection); Hydro Blaster, 10,000 psi and over

GROUP 4: Material Hoists; Stack Hoists; Hydraulic Backhoe (tractor or truck mounted); Hydraulic Crane, 5 tons or under (tractor or truck mounted); Hoist (tuggers 5 tons & over); Hydro-Excavators/Daylighters; Concrete Pumps Rotec type Conveyors; Tractor/Bulldozer/End Loader (over 40 hp); Motor Patrol; Scraper Operator; Sideboom; Straddle Carrier; Welder; Bituminous Plant and Paver Operator; Roller over 5 tons; Rail Leveling Machine (Railroad); Tie Placer; Tie Extractor; Tie Tamper; Stone Leveler; Rotary Drill Operator and Blaster; Percussion Drill Operator; Air Track Drill and/or Hammers; Gantrys (under 20,000 lbs); Tencher (wheel type or chain type having 8 inch or larger bucket); Milling Machine; Off-Road Material Haulers.

GROUP 5: Backfiller; Concrete Auto Breaker (large); Concrete Finishing Machines (road type); Rubber Tired Roller; Concrete Batch Hopper; Concrete Conveyor Systems; Grout Pumps; Concrete Mixers (14S or over); Screw Type Pumps and

Gypsum Pumps; Tractor, Bulldozer, End Loader (under 40 hp); Trencher (chain type, bucket under 8 inch); Industrial Locomotives; Rollers under 5 tons; Stump Grinder/Chipper (Large); Timber Equipment; Firemen (pile drivers and derricks); Personnel Hoist, Telehandler over 8000 lbs; Robotic Tool Carrier with or without attachments

GROUP 6: Tampers - Compactors (riding type); Assistant Engineer; A-Frames and Winch Trucks; Concrete Auto Breaker; Hydrohammers (small); Brooms and Sweepers; Hoist (tuggers under 5 tons); Boats (Tug, Safety, Work Barges, Launch); Shouldering Machine Operator; Prestress Machines; Screed Operator; Stone Crushers and Screening Plants; Screed Operators (milling machine), Farm or Industrial Tractor Mounted Equipment; Post Hole Digger; Fireman (asphalt plants); Air Compressors over 400 CFM; Generators, over 150 KW; Augers (vertical and horizontal); Air, Electric, Hydraulic Jacks (slipform); Skid Steer Loaders (with or without attachments); Boiler Operators (temporary heat); Refrigeration Plant/Freeze Machines; Power Pack Vibratory/Ultra Sound Drivers and Extractors; Welding Machines; Heaters (mechanical); Pumps; Winches (small electric); Oiler and Greaser; Rotary Drill Tender; Conveyor; Forklifts/Telehandler 8000 lbs & under; Elevators: Automatic Hoists; Pumps (well points); Combination Small Equipment Operators

ENGI0139-003 06/01/2020

## REMAINING COUNTIES

	Rates	Fringes
Power Equipment Operator		
Group 1	\$ 42.92	23.15
Group 2	\$ 41.67	23.15
Group 3	\$ 39.97	23.15
Group 4	\$ 39.44	23.15
Group 5	\$ 37.37	23.15
Group 6	\$ 35.84	23.15

# HAZARDOUS WASTE PREMIUMS:

EPA Level ""A"" Protection: \$3.00 per hour EPA Level ""B"" Protection: \$2.00 per hour EPA Level ""C"" Protection: \$1.00 per hour

POWER EQUIPMENT OPERATORS CLASSIFICATIONS

GROUP 1: Cranes, Tower Cranes and Derricks with or without

attachments with a lifting capacity of over 100 tons; Cranes, Tower Cranes, and Derricks with boom, leads and/or jib lengths 176 ft or longer.

- GROUP 2: Backhoes (Excavators) weighing 130,00 lbs and over; Cranes, Tower Cranes and Derricks with or without attachments with a lifting capacity of 100 tons or less; Cranes, Tower Cranes, and Derricks with boom, leads, and/or jib lengths 175 ft or less; Caisson Rigs; Pile Driver
- GROUP 3: Backhoes (Excavators) weighing under 130,000 lbs; Travelling Crane (bridge type); Milling Machine; Concrete Paver over 27 E; Concrete Spreader and Distributor; Concrete Laser Screed; Concrete Grinder and Planing Machine; Slipform Curb and Gutter Machine; Boring Machine (Directional); Dredge Operator; Skid Rigs; over 46 meter Concrete Pump.
- GROUP 4: Hydraulic Backhoe (tractor or truck mounted); Hydraulic Crane, 10 tons or less; Tractor, Bulldozer, or End Loader (over 40 hp); Motor Patrol; Scraper Operator; Bituminous Plant and Paver Operator; Screed-Milling Machine; Roller over 5 tons; Concrete pumps 46 meter and under; Grout Pumps; Rotec type machine; Hydro Blaster, 10,000 psi and over; Rotary Drill Operator; Percussion Drilling Machine; Air Track Drill with or without integral hammer; Blaster; Boring Machine (vertical or horizontal); Side Boom; Trencher, wheel type or chain type having 8 inch or larger bucket; Rail Leveling Machine (Railroad); Tie Placer; Tie Extractor; Tie Tamper; Stone Leveler; Straddle Carrier; Material Hoists; Stack Hoist; Man Hoists; Mechanic and Welder; Off Road Material Haulers.
- GROUP 5: Tractor, Bulldozer, or Endloader (under 40 hp); Tampers -Compactors, riding type; Stump Chipper, large; Roller, Rubber Tire; Backfiller; Trencher, chain type (bucket under 8 inch); Concrete Auto Breaker, large; Concrete Finishing Machine (road type); Concrete Batch Hopper; Concrete Conveyor Systems; Concrete Mixers, 14S or over; Pumps, Screw Type and Gypsum); Hydrohammers, small; Brooms and Sweeeprs; Lift Slab Machine; Roller under 5 tons; Industrial Locomotives; Fireman (Pile Drivers and Derricks); Pumps (well points); Hoists, automatic; A-Frames and Winch Trucks; Hoists (tuggers); Boats (Tug, Safety, Work Barges and Launches); Assistant Engineer
- GROUP 6: Shouldering Machine Operator; Farm or Industrial Tractor mounted equipment; Post Hole Digger; Auger (vertical and horizontal); Skid Steer Loader with or without attachments; Robotic Tool Carrier with or without

attachments; Power Pack Vibratory/Ultra Sound Driver and Extractor; Fireman (Asphalt Plants); Screed Operator; Stone Crushers and Screening Plants; Air, Electric, Hydraulic Jacks (Slip Form); Prestress Machines; Air Compressor, 400 CFM or over; Refrigeration Plant/Freese Machine; Boiler Operators (temporary heat); Forklifts; Welding Machines; Generators; Pumps over 3""; Heaters, Mechanical; Combination small equipment operator; Winches, small electric; Oiler; Greaser; Rotary Drill Tender; Conveyor; Elevator Operator

-----

#### IRON0008-002 06/01/2020

BROWN, CALUMET, DOOR, FOND DU LAC, KEWAUNEE, MANITOWOC, MARINETTE, OCONTO, OUTAGAMI, SHAWANO, SHEBOYGAN, AND WINNEBAGO COUNTIES:

Rates Fringes

IRONWORKER.....\$ 37.31 27.62

Paid Holidays: New Year's Day, Memorial Day, July 4th, Labor Day, Thanksgiving Day & Christmas Day.

-----

IRON0008-003 06/01/2020

KENOSHA, MILWAUKEE, OZAUKEE, RACINE, WALWORTH (N.E. 2/3), WASHINGTON, AND WAUKESHA COUNTIES

Rates Fringes

IRONWORKER.....\$ 39.11 27.87

Paid Holidays: New Year's Day, Memorial Day, July 4th, Labor Day, Thanksgiving Day & Christmas Day.

-----

#### IRON0383-001 06/01/2020

ADAMS, COLUMBIA, CRAWFORD, DANE, DODGE, FLORENCE, FOREST, GRANT, GREENE, (Excluding S.E. tip), GREEN LAKE, IOWA, JEFFERSON, JUNEAU, LA CROSSE, LAFAYETTE, LANGLADE, MARATHON, MARQUETTE, MENOMINEE, MONROE, PORTAGE, RICHLAND, ROCK (Northern area, vicinity of Edgerton and Milton), SAUK, VERNON, WAUPACA, WAUSHARA, AND WOOD COUNTIES

Rates	Fringes

IRONWORKER.....\$ 37.10 27.06

IRON0512-008 06/03/2019

BARRON, BUFFALO, CHIPPEWA, CLARK, DUNN, EAU CLAIRE, JACKSON, PEPIN, PIERCE, POLK, RUSK, ST CROIX, TAYLOR, AND TREMPEALEAU COUNTIES

	Rates	Fringes
IRONWORKER	.\$ 37.60	29.40
IRON0512-021 06/03/2019		

ASHLAND, BAYFIELD, BURNETT, DOUGLAS, IRON, LINCOLN, ONEIDA, PRICE, SAWYER, VILAS AND WASHBURN COUNTIES

	Rates	Fringes
IRONWORKER	\$ 33.19	29.40
LAB00113-002 06/01/2020		

#### MILWAUKEE AND WAUKESHA COUNTIES

	Rates	Fringes
LABORER		
Group	1\$ 30.05	22.26
Group	2\$ 30.20	22.26
Group	3\$ 30.40	22.26
Group	4\$ 30.55	22.26
Group	5\$ 30.70	22.26
Group	6\$ 26.54	22.26

## LABORERS CLASSIFICATIONS

GROUP 1: General Laborer; Tree Trimmer; Conduit Layer; Demolition and Wrecking Laborer; Guard Rail, Fence, and Bridge Builder; Landscaper; Multiplate Culvert Assembler; Stone Handler; Bituminous Worker (Shoveler, Loader, and Utility Man); Batch Truck Dumper or Cement Handler; Bituminous Worker (Dumper, Ironer, Smoother, and Tamper); Concrete Handler

GROUP 2: Air Tool Operator; Joint Sawer and Filler

(Pavement); Vibrator or Tamper Operator (Mechanical Hand Operated); Chain Saw Operator; Demolition Burning Torch Laborer

GROUP 3: Bituminous Worker (Raker and Luteman); Formsetter (Curb, Sidewalk, and Pavement); Strike Off Man

GROUP 4: Line and Grade Specialist

GROUP 5: Blaster and Powderman

GROUP 6: Flagperson; traffic control person

-----

LAB00113-003 06/01/2020

#### OZAUKEE AND WASHINGTON COUNTIES

	ı	Rates	Fringes
LABORER			
Group	1\$	29.30	22.26
Group	2\$	29.40	22.26
Group	3\$	29.45	22.26
Group	4\$	29.65	22.26
Group	5\$	29.50	22.26
Group	6\$	26.39	22.26

#### LABORERS CLASSIFICATIONS

GROUP 1: General Laborer; Tree Trimmer; Conduit Layer; Demolition and Wrecking Laborer; Guard Rail, Fence, and Bridge Builder; Landscaper; Multiplate Culvert Assembler; Stone Handler; Bituminous Worker (Shoveler, Loader, and Utility Man); Batch Truck Dumper or Cement Handler; Bituminous Worker (Dumper, Ironer, Smoother, and Tamper); Concrete Handler

GROUP 2: Air Tool Operator; Joint Sawer and Filler (Pavement); Vibrator or Tamper Operator (Mechanical Hand Operated);

GROUP 3: Bituminous Worker (Raker and Luteman); Formsetter (Curb, Sidewalk, and Pavement); Strike Off Man

GROUP 4: Line and Grade Specialist

GROUP 5: Blaster; powderman

GROUP 6: Flagperson and Traffic Control Person

-----

#### LAB00113-011 06/01/2020

#### KENOSHA AND RACINE COUNTIES

	I	Rates	Fringes
LABORER			
Group	1\$	29.11	22.26
Group	2\$	29.26	22.26
Group	3\$	29.46	22.26
Group	4\$	29.43	22.26
Group	5\$	29.76	22.26
Group	6\$	26.25	22.26

#### LABORERS CLASSIFICATIONS:

GROUP 1: General laborer; Tree Trimmer; Conduit Layer; Demolition and Wrecking Laborer; Guard Rail, Fence, and Bridge Builder; Landscaper; Multiplate Culvert Assembler; Stone Handler; Bituminous Worker (Shoveler, Loader, and Utility Man); Batch Truck Dumper or Cement Handler; Bituminous worker (Dumper, Ironer, Smoother, and Tamper); Concrete Handler

GROUP 2: Air Tool Operator; Joint Sawer and Filler (Pavement); Vibrator or Tamper Operator (Mechanical Hand Operated); Chain Saw Operator; Demolition Burning Torch Laborer

GROUP 3: Bituminous Worker (Raker and Luteman); Formsetter (Curb, Sidewalk, and Pavement); Strike Off Man

GROUP 4: Line and Grade Specialist

GROUP 5: Blaster and Powderman

GROUP 6: Flagman; traffic control person

\_\_\_\_\_

#### LAB00140-002 06/01/2020

ADAMS, ASHLAND, BARRON, BAYFIELD, BROWN, BUFFALO, BURNETT, CALUMET, CHIPPEWA, CLARK, COLUMBIA, CRAWFORD, DODGE, DOOR, DOUGLAS, DUNN, EAU CLAIRE, FLORENCE, FOND DU LAC, FOREST, GRANT, GREEN, GREEN LAKE, IRON, JACKSON, JUNEAU, IOWA, JEFFERSON, KEWAUNEE, LA CROSSE, LAFAYETTE, LANGLADE, LINCOLN, MANITOWOC, MARATHON, MARINETTE, MARQUETTE, MENOMINEE, MONROE, OCONTO, ONEIDA, OUTAGAMIE, PEPIN, PIERCE, POLK, PORTAGE, PRICE,

RICHLAND, ROCK, RUSK, SAUK, SAWYER, SHAWANO, SHEBOYGAN, ST. CROIX, TAYLOR, TREMPEALEAU, VERNON, VILLAS, WALWORTH, WASHBURN, WAUPACA, WAUSHARA, WINNEBAGO, AND WOOD COUNTIES

	F	Rates	Fringes
LABORER			
Group	1\$	33.72	17.95
Group	2\$	33.82	17.95
Group	3\$	33.87	17.95
Group	4\$	34.07	17.95
Group	5\$	33.92	17.95
Group	6\$	30.35	17.95

#### LABORER CLASSIFICATIONS

GROUP 1: General Laborer; Tree Trimmer; Conduit Layer; Demolition and Wrecking Laborer; Guard Rail, Fence, and Bridge Builder; Landscaper; Multiplate Culvert Assembler; Stone Handler; Bitminous Worker (Shoveler, Loader, and Utility Man); Batch Truck Dumper or Cement Handler; Bituminous Worker (Dumper, Ironer, Smoother and Tamper); Concrete Handler

GROUP 2: Air Tool Operator; Joint Sawer and Filler (Pavement); Vibrator or Tamper Operator (Mechanical Hand Operated); Chain Saw Operator, Demolition Burning Torch Laborer

GROUP 3: Bituminous Worker (Raker and Luteman); Formsetter (Curb, Sidewalk and Pavement); Strike Off Man

GROUP 4: Line and Grade Secialist

GROUP 5: Blaster; powderman

GROUP 6: Flagperson; Traffic Control

-----

LAB00464-003 06/01/2020

DANE COUNTY

	Rates	Fringes
LABORER		
Group	1\$ 34.00	17.95
Group	2\$ 34.10	17.95
Group	3\$ 34.15	17.95

Group 4	\$ 34.35	17.95
Group 5	\$ 34.20	17.95
Group 6	\$ 30.35	17.95

#### LABORERS CLASSIFICATIONS:

GROUP 1: General Laborer; Tree Trimmer; Conduit Layer; Demolition and Wrecking Laborer; Guard Rail, Fence, and Bridge Builder; Landscaper; Multiplate Culvert Assembler; Stone Handler; Bituminous Worker (Shoveler, Loader, and Utility Man); Batch Truck Dumper or Cement Handler; Bituminious Worker (Dumper, Ironer, Smoother, and Tamper); Concrete Handler

GROUP 2: Air Tool Operator; Joint Sawer and Filler (Pavement); Vibrator or Tamper Operator (Mechanical Hand Operated); Chain Saw Operator; Demolition Burning Torch Laborer

GROUP 3: Bituminous Worker (Raker and Luteman); Formsetter (Curb, Sidewalk, and Pavement); Strike Off Man

GROUP 4: Line and Grade Specialist

GROUP 5: Blaster; Powderman

GROUP 6: Flagperson and Traffic Control Person

-----

PAIN0106-008 05/01/2017

ASHLAND, BAYFIELD, BURNETT, AND DOUGLAS COUNTIES

	I	Rates	Fringes
Painters:			
New:			
	Roller\$	30 33	17.27
•	Sandblast, Steel\$		17.27
Repaint	-		_, , _,
•	Roller\$	28.83	17.27
	Sandblast, Steel\$		17.27

PAIN0108-002 06/01/2019

RACINE COUNTY

Rates Fringes

Painters:

Brush, Roller Spray & Sandblast		20.36 20.36
PAIN0259-002 05/01/2008		
BARRON, CHIPPEWA, DUNN, EAU CLAI SAWYER, ST. CROIX, AND WASHBURN		PIERCE, POLK, RUSK,
	Rates	Fringes
PAINTER		
PAIN0259-004 05/01/2015		
BUFFALO, CRAWFORD, JACKSON, LA C VERNON COUNTIES	ROSSE, MONR	OE, TREMPEALEAU, AND
	Rates	Fringes
PAINTER	•	12.45
PAIN0781-002 06/01/2019		
JEFFERSON, MILWAUKEE, OZAUKEE, W	ASHINGTON,	AND WAUKESHA COUNTIES
	Rates	Fringes
Painters: Bridge Brush Spray & Sandblast	.\$ 32.95 .\$ 33.70	23.86 23.86 23.86
PAIN0802-002 06/01/2019  COLUMBIA, DANE, DODGE, GRANT, GR ROCK, AND SAUK COUNTIES	EEN, IOWA,	LAFAYETTE, RICHLAND,
	Rates	Fringes
PAINTER Brush	.\$ 30.93	18.44
PREMIUM PAY: Structural Steel, Spray, Bridg hour.	es = \$1.0	0 additional per

## PAIN0802-003 06/01/2019

ADAMS, BROWN, CALUMET, CLARK, DOOR, FOND DU LAC, FOREST, GREEN LAKE, IRON, JUNEAU, KEWAUNEE, LANGLADE, LINCOLN, MANITOWOC, MARATHON, MARINETTE, MARQUETTE, MENOMINEE, OCONTO, ONEIDA, OUTAGAMIE, PORTAGE, PRICE, SHAWANO, SHEBOYGAN, TAYLOR, VILAS, WAUSHARA, WAUPACA, WINNEBAGO, AND WOOD COUNTIES

	Rates	Fringes
PAINTER		18.58
PAIN0934-001 06/01/2017		
KENOSHA AND WALWORTH COUNTIES		
	Rates	Fringes
Painters:     Brush	\$ 34.74	18.95 18.95 18.95
FLORENCE COUNTY		
	Rates	Fringes
Painters:	\$ 25.76	13.33
PLAS0599-010 06/01/2017		
	Rates	Fringes
CEMENT MASON/CONCRETE FINISHER Area 1	\$ 35.07 \$ 35.61 \$ 34.70 \$ 36.27	17.17 19.75 19.40 20.51 18.73 22.99

AREA 2: ADAMS, ASHLAND, BARRON, BROWN, BURNETT, CALUMET,

AREA 1: COUNTIES BAYFIELD, DOUGLAS, PRICE, SAWYER, AND WASHBURN

CHIPPEWA, CLARK, COLUMBIA, DODGE, DOOR, DUNN, FLORENCE, FOND DU LAC, FOREST, GREEN LAKE, IRON, JEFFERSON, KEWAUNEE, LANGLADE, LINCOLN, MANITOWOC, MARATHON, MARINETTE, MARQUETTE, MENOMINEE, OCONTO, ONEIDA, OUTAGAMIE, POLK, PORTAGE, RUSK, ST CROIX, SAUK, SHAWANO, SHEBOYGAN, TAYLOR, VILAS, WALWORTH, WAUPACA, WAUSHARA, WINNEBAGO, AND WOOD COUNTIES

AREA 3: BUFFALO, CRAWFORD, EAU CLAIRE, JACKSON, JUNEAU, LA CROSSE MONROE, PEPIN, PIERCE, RICHLAND, TREMPEALEAU, AND VERNON COUNTIES

AREA 4: MILWAUKEE, OZAUKEE, WASHINGTON, AND WAUKESHA COUNTIES

AREA 5: DANE, GRANT, GREEN, IOWA, LAFAYETTE, AND ROCK COUNTIES

AREA 6: KENOSHA AND RACINE COUNTIES

-----

PLUM0011-003 05/07/2018

ASHLAND, BAYFIELD, BURNETT, DOUGLAS, IRON, SAWYER, AND WASHBURN COUNTIES

Rates Fringes

PLUMBER......\$ 40.63 20.72

PLUM0075-002 06/01/2016

MILWAUKEE, OZAUKEE, WASHINGTON, AND WAUKESHA COUNTIES

Rates Fringes

PLUMBER.....\$ 40.27 21.47

PLUM0075-004 06/01/2016

DODGE (Watertown), GREEN, JEFFERSON, LAFAYETTE, AND ROCK COUNTIES

PLUM0075-009 06/01/2016

COLUMBIA, DANE, IOWA, MARQUETTE, RICHLAND AND SAUK COUNTIES

Rates Fringes PLUMBER.....\$ 38.82 20.12 PLUM0111-007 05/28/2018 MARINETTE COUNTY (Niagara only)

Fringes PLUMBER/PIPEFITTER.....\$ 33.33 PLUM0118-002 06/01/2020

Rates

KENOSHA, RACINE, AND WALWORTH COUNTIES

Rates Fringes Plumber and Steamfitter..... \$43.95 24.35 \_\_\_\_\_\_ PLUM0400-003 06/04/2018

ADAMS, BROWN, CALUMET, DODGE (except Watertown), DOOR, FOND DU LAC, GREEN LAKE, KEWAUNEE, MANITOWOC, MARINETTE (except Niagara), MENOMINEE, OCONTO, OUTAGAMIE, SHAWANO, SHEBOYGAN, WAUPACA, WAUSHARA, AND WINNEBAGO COUNTIES

Rates Fringes PLUMBER/PIPEFITTER.....\$ 36.74 19.06 PLUM0434-002 05/31/2020

BARON, BUFFALO, CHIPPEWA, CLARK, CRAWFORD, DUNN, EAU CLAIRE, FLORENCE, FOREST, GRANT, JACKSON, JUNEAU, LA CROSSE, LANGLADE, LINCOLN, MARATHON, MONROE, ONEIDA, PEPIN, PIERCE, POLK, PORTAGE, PRICE, RUSK, ST. CROIX, TAYLOR, TREMPEALEAU, VERNON, VILAS, AND WOOD COUNTIES

Fringes Rates PIPEFITTER.....\$ 42.70 -----PLUM0601-003 06/03/2019

DODGE (Watertown), GREEN, JEFFERSON, LAFAYETTE, MILWAUKEE, OZAUKEE, ROCK, WASHINGTON AND WAUKESHA COUNTIES

	Rates	Fringes		
PIPEFITTER	•	25.29		
PLUM0601-009 06/04/2017				
COLUMBIA, DANE, IOWA, MARQUETTE,	RICHLAND AND SA	AUK COUNTIES		
	Rates	Fringes		
PIPEFITTER	.\$ 47.08	20.89		
TEAM0039-002 06/01/2020				
	Rates	Fringes		
TRUCK DRIVER  1 & 2 Axle Trucks  3 or more axles; Euclids or Dumptor, Articulated	.\$ 31.07	22.94		
Truck, Mechanic	.\$ 31.22	22.94		
SUWI2011-001 11/16/2011				
	Rates	Fringes		
WELL DRILLER	•			
WELDERS - Receive rate prescribed for craft performing operation to which welding is incidental.				

Note: Executive Order (EO) 13706, Establishing Paid Sick Leave for Federal Contractors applies to all contracts subject to the Davis-Bacon Act for which the contract is awarded (and any solicitation was issued) on or after January 1, 2017. If this contract is covered by the EO, the contractor must provide employees with 1 hour of paid sick leave for every 30 hours they work, up to 56 hours of paid sick leave each year. Employees must be permitted to use paid sick leave for their own illness, injury or other health-related needs, including preventive care; to assist a family member (or person who is like family to the employee) who is ill, injured, or has other health-related needs, including preventive care; or for reasons

\_\_\_\_\_\_

resulting from, or to assist a family member (or person who is like family to the employee) who is a victim of, domestic violence, sexual assault, or stalking. Additional information on contractor requirements and worker protections under the EO is available at www.dol.gov/whd/govcontracts.

Unlisted classifications needed for work not included within the scope of the classifications listed may be added after award only as provided in the labor standards contract clauses (29CFR 5.5 (a) (1) (ii)).

-----

The body of each wage determination lists the classification and wage rates that have been found to be prevailing for the cited type(s) of construction in the area covered by the wage determination. The classifications are listed in alphabetical order of ""identifiers"" that indicate whether the particular rate is a union rate (current union negotiated rate for local), a survey rate (weighted average rate) or a union average rate (weighted union average rate).

#### Union Rate Identifiers

A four letter classification abbreviation identifier enclosed in dotted lines beginning with characters other than ""SU"" or ""UAVG"" denotes that the union classification and rate were prevailing for that classification in the survey. Example: PLUM0198-005 07/01/2014. PLUM is an abbreviation identifier of the union which prevailed in the survey for this classification, which in this example would be Plumbers. 0198 indicates the local union number or district council number where applicable, i.e., Plumbers Local 0198. The next number, 005 in the example, is an internal number used in processing the wage determination. 07/01/2014 is the effective date of the most current negotiated rate, which in this example is July 1, 2014.

Union prevailing wage rates are updated to reflect all rate changes in the collective bargaining agreement (CBA) governing this classification and rate.

## Survey Rate Identifiers

Classifications listed under the ""SU"" identifier indicate that no one rate prevailed for this classification in the survey and the published rate is derived by computing a weighted average rate based on all the rates reported in the survey for that classification. As this weighted average rate includes all rates reported in the survey, it may include both union and non-union rates. Example: SULA2012-007 5/13/2014. SU indicates the rates are survey rates based on a weighted average calculation of rates and are not majority rates. LA indicates the State of Louisiana. 2012 is the year of survey on which these classifications and rates are based. The next number, 007 in the example, is an internal number used in producing the wage determination. 5/13/2014 indicates the survey completion date for the classifications and rates under that identifier.

Survey wage rates are not updated and remain in effect until a new survey is conducted.

Union Average Rate Identifiers

Classification(s) listed under the UAVG identifier indicate that no single majority rate prevailed for those classifications; however, 100% of the data reported for the classifications was union data. EXAMPLE: UAVG-OH-0010 08/29/2014. UAVG indicates that the rate is a weighted union average rate. OH indicates the state. The next number, 0010 in the example, is an internal number used in producing the wage determination. 08/29/2014 indicates the survey completion date for the classifications and rates under that identifier.

A UAVG rate will be updated once a year, usually in January of each year, to reflect a weighted average of the current negotiated/CBA rate of the union locals from which the rate is based.

-----

#### WAGE DETERMINATION APPEALS PROCESS

- 1.) Has there been an initial decision in the matter? This can be:
- \* an existing published wage determination
- \* a survey underlying a wage determination
- \* a Wage and Hour Division letter setting forth a position on a wage determination matter
- \* a conformance (additional classification and rate) ruling

On survey related matters, initial contact, including requests for summaries of surveys, should be with the Wage and Hour Regional Office for the area in which the survey was conducted because those Regional Offices have responsibility for the Davis-Bacon survey program. If the response from this initial contact is not satisfactory, then the process described in 2.) and 3.) should be followed.

With regard to any other matter not yet ripe for the formal process described here, initial contact should be with the Branch of Construction Wage Determinations. Write to:

Branch of Construction Wage Determinations Wage and Hour Division U.S. Department of Labor 200 Constitution Avenue, N.W. Washington, DC 20210

2.) If the answer to the question in 1.) is yes, then an interested party (those affected by the action) can request review and reconsideration from the Wage and Hour Administrator (See 29 CFR Part 1.8 and 29 CFR Part 7). Write to:

Wage and Hour Administrator U.S. Department of Labor 200 Constitution Avenue, N.W. Washington, DC 20210

The request should be accompanied by a full statement of the interested party's position and by any information (wage payment data, project description, area practice material, etc.) that the requestor considers relevant to the issue.

3.) If the decision of the Administrator is not favorable, an interested party may appeal directly to the Administrative Review Board (formerly the Wage Appeals Board). Write to:

Administrative Review Board U.S. Department of Labor 200 Constitution Avenue, N.W. Washington, DC 20210

4.) All decisions by the Administrative Review Board are final.

END OF GENERAL DECISION"

# NOTICE TO BIDDERS WAGE RATE DECISION

The wage rate decision of the Department of Labor which has been incorporated in these advertised specifications is incomplete in that the classifications may be omitted from the Department of Labor's decision.

Since the bidder is responsible, independently, for ascertaining area practice with respect to the necessity, or lack of necessity, for the use of these classifications in the prosecution of the work contemplated by this project, no inference may be drawn from the omission of these classifications concerning prevailing area practices relative to their use. Further, this omission will not, per se, be construed as establishing any governmental liability for increased labor cost if it is subsequently determined that such classifications are required.

There may be omissions and/or errors in the federal wage rates. The bidder is responsible for evaluating and determining the correct applicable rate.

If a project includes multiple types of construction (highway, bridge over navigable water, sanitary sewer and water main, building) and there is not a separate wage determination for this type of work included in the proposal, use the wage determination that is in the proposal.

If a project includes multiple types of construction, different wage rate determinations may be inserted into the contract (WI10/Highway = in all WisDOT highway contracts, WI15/Heavy = bridge over navigable water per USDOL and US Coast Guard designation, WI8/Heavy (Sewer & Water Line & Tunnel) = sanitary sewer and water main if the cost is more than 20% of the contract and/or at least \$1,000,000, and Building). If multiple wage rate determinations are inserted into the contract, use the classification in the wage determination for the work being done. Use WI15 wage rates when working on the bridge and/or structure from bank to bank. Use WI8 wage rates when working on any sanitary sewer or water main work. Use Building wage rates for all work done within the footprint of the building. Use WI10 wage rates for all other highway work in the contract and approaches to structures. For example, if a laborer is working within the footprint of a building, use the Laborer rate in the Building wage determination inserted in the contract. If a laborer is working on a bridge/structure within the banks, use the Laborer rate in the WI15/Heavy wage determination if inserted in the contract. If the laborer is working on the highway, use the Laborer rate in the WI10/Highway wage determination.







Page 1 of 10


**Proposal ID:** 20210112035 **Project(s):** 1198-03-78

Federal ID(s): WISC 2021105

**SECTION:** 0001 Roadway Construction

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0002	204.0100 Removing Concrete Pavement	975.000 SY	<u> </u>	
0004	204.0105 Removing Pavement Butt Joints	320.000 SY	·	
0006	204.0109.S Removing Concrete Surface Partial Depth	525,240.000 SF	·	
8000	204.0110 Removing Asphaltic Surface	1,871.000 SY	·	
0010	204.0150 Removing Curb & Gutter	1,943.000 LF		
0012	204.0155 Removing Concrete Sidewalk	3,157.000 SY		·
0014	204.0157 Removing Concrete Barrier	188.000 LF		
0016	204.0195 Removing Concrete Bases	7.000 EACH		·
0018	204.9105.S Removing (item description) 01. Traffic Signal USH 2 & 39th Ave	LS	LUMP SUM	
0020	205.0100 Excavation Common	660.000 CY		
0022	205.0501.S Excavation, Hauling, and Disposal of Petroleum Contaminated Soil	80.000 TON		
0024	210.1100 Backfill Structure Type A	34.000 CY		
0026	211.0100 Prepare Foundation for Asphaltic Paving (project) 01. 1198-03-78	LS	LUMP SUM	
0028	213.0100 Finishing Roadway (project) 01. 1198-03- 78	1.000 EACH	·	
0030	305.0110 Base Aggregate Dense 3/4-Inch	1,107.000 TON		







Page 2 of 10


**Proposal ID:** 20210112035 **Project(s):** 1198-03-78

Federal ID(s): WISC 2021105

**SECTION:** 0001 Roadway Construction

Proposal Line Number	Item ID  Description	Approximate Quantity and Units	Unit Price	Bid Amount
0032	310.0110 Base Aggregate Open-Graded	2,195.000 TON	<u> </u>	·
0034	415.0090 Concrete Pavement 9-Inch	443.000 SY		
0036	415.0410 Concrete Pavement Approach Slab	640.000 SY	·	
0038	416.0160 Concrete Driveway 6-Inch	213.000 SY		
0040	416.0610 Drilled Tie Bars	7,386.000 EACH		
0042	416.0620 Drilled Dowel Bars	8,212.000 EACH		
0044	416.1710 Concrete Pavement Repair	3,083.000 SY		
0046	416.1720 Concrete Pavement Replacement	9,370.000 SY		
0048	455.0605 Tack Coat	7,145.000 GAL		
0050	460.0115.S HMA Pavement Test Strips Volumetrics	1.000 EACH	50,000.00000	50,000.00
0052	460.0120.S HMA Pavement Test Strips Density	1.000 EACH		
0054	460.2000 Incentive Density HMA Pavement	5,910.000 DOL	1.00000	5,910.00
0056	460.7645 HMA Pavement 5 HT 58-34 V	4,290.000 TON	<u></u>	
0058	460.8645 HMA Pavement 5 SMA 58-34 V	4,950.000 TON		
0060	465.0105 Asphaltic Surface	51.000 TON	<u> </u>	
0062	465.0110 Asphaltic Surface Patching	505.000 TON		
0064	502.0100 Concrete Masonry Bridges	3.000 CY		





Page 3 of 10



## **Proposal Schedule of Items**


**Project(s):** 1198-03-78

**Proposal ID:** 20210112035 Federal ID(s): WISC 2021105

SECTION: 0001 Roadway Construction

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0066	505.0600 Bar Steel Reinforcement HS Coated Structures	70.000 LB	·	
0068	509.0301 Preparation Decks Type 1	264.000 SY		
0070	509.0302 Preparation Decks Type 2	139.000 SY		
0072	509.0310.S Sawing Pavement Deck Preparation Areas	376.000 LF	·	
0074	509.1500 Concrete Surface Repair	55.000 SF		
0076	509.2100.S Concrete Masonry Deck Repair	35.500 CY		
0078	509.5100.S Polymer Overlay	3,000.000 SY		
0800	601.0409 Concrete Curb & Gutter 30-Inch Type A	1,980.000 LF		
0082	601.0600 Concrete Curb Pedestrian	48.000 LF		
0084	602.0405 Concrete Sidewalk 4-Inch	13,690.000 SF		
0086	602.0415 Concrete Sidewalk 6-Inch	13,636.000 SF		
8800	602.0515 Curb Ramp Detectable Warning Field Natural Patina	492.000 SF	·	
0090	603.0405 Concrete Barrier Transition Section 32- Inch	188.000 LF	·	
0092	611.0410 Reconstructing Catch Basins	21.000 EACH		
0094	611.0420 Reconstructing Manholes	12.000 EACH		
0096	611.8110 Adjusting Manhole Covers	7.000 EACH		







Page 4 of 10

**Proposal ID:** 20210112035 **Project(s):** 1198-03-78

Federal ID(s): WISC 2021105

**SECTION:** 0001 Roadway Construction

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0098	611.8115 Adjusting Inlet Covers	27.000 EACH		
0100	611.8120.S Cover Plates Temporary	136.000 EACH		
0102	619.1000 Mobilization	1.000 EACH	<u> </u>	
0104	624.0100 Water	25.000 MGAL		<u> </u>
0106	625.0100 Topsoil	1,882.000 SY		
0108	628.1905 Mobilizations Erosion Control	3.000 EACH		<u> </u>
0110	628.1910  Mobilizations Emergency Erosion Control	2.000 EACH	<u></u>	
0112	628.2006 Erosion Mat Urban Class I Type A	1,882.000 SY		
0114	628.7015 Inlet Protection Type C	68.000 EACH	<u></u>	
0116	629.0210 Fertilizer Type B	1.200 CWT	<u> </u>	
0118	630.0130 Seeding Mixture No. 30	51.000 LB	<u></u>	
0120	630.0500 Seed Water	43.000 MGAL		
0122	634.0616 Posts Wood 4x6-Inch X 16-FT	2.000 EACH	<u> </u>	<u> </u>
0124	634.0814 Posts Tubular Steel 2x2-Inch X 14-FT	1.000 EACH		
0126	637.2210 Signs Type II Reflective H	12.000 SF	<u> </u>	
0128	638.2102 Moving Signs Type II	20.000 EACH		
0130	638.4000 Moving Small Sign Supports	19.000 EACH		







Page 5 of 10

**Proposal ID:** 20210112035 **Project(s):** 1198-03-78

Federal ID(s): WISC 2021105

**SECTION:** 0001 Roadway Construction

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0132	642.5001 Field Office Type B	1.000 EACH	·	·
0134	643.0300 Traffic Control Drums	75,692.000 DAY		
0136	643.0420 Traffic Control Barricades Type III	6,636.000 DAY	·	·
0138	643.0500 Traffic Control Flexible Tubular Marker Posts	304.000 EACH		·
0140	643.0600 Traffic Control Flexible Tubular Marker Bases	304.000 EACH		
0142	643.0705 Traffic Control Warning Lights Type A	13,272.000 DAY		<u></u>
0144	643.0715 Traffic Control Warning Lights Type C	7,848.000 DAY		<u></u>
0146	643.0800 Traffic Control Arrow Boards	488.000 DAY	<u> </u>	<u> </u>
0148	643.0900 Traffic Control Signs	13,464.000 DAY		<u></u>
0150	643.0920 Traffic Control Covering Signs Type II	7.000 EACH		<u></u>
0152	643.1000 Traffic Control Signs Fixed Message	400.000 SF		
0154	643.1050 Traffic Control Signs PCMS	368.000 DAY		·
0156	643.5000 Traffic Control	1.000 EACH		
0158	644.1430 Temporary Pedestrian Surface Plate	800.000 SF		<u> </u>
0160	644.1601 Temporary Pedestrian Curb Ramp	272.000 DAY		
0162	644.1810 Temporary Pedestrian Barricade	3,500.000 LF		·







Page 6 of 10


**Proposal ID:** 20210112035 **Project(s):** 1198-03-78

Federal ID(s): WISC 2021105

**SECTION:** 0001 Roadway Construction

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0164	646.1020 Marking Line Epoxy 4-Inch	57,125.000 LF		<u> </u>
0166	646.3020 Marking Line Epoxy 8-Inch	554.000 LF	·	<u> </u>
0168	646.5020 Marking Arrow Epoxy	19.000 EACH		
0170	646.6120 Marking Stop Line Epoxy 18-Inch	130.000 LF	·	
0172	646.7420 Marking Crosswalk Epoxy Transverse Line 6-Inch	1,306.000 LF	·	·
0174	646.8020 Marking Corrugated Median Epoxy	120.000 SF		
0176	646.8220 Marking Island Nose Epoxy	7.000 EACH	·	
0178	646.9000 Marking Removal Line 4-Inch	2,880.000 LF		
0180	646.9100 Marking Removal Line 8-Inch	200.000 LF		
0182	646.9300 Marking Removal Special Marking	5.000 EACH	·	·
0184	649.0150 Temporary Marking Line Removable Tape 4-Inch	32,324.000 LF	·	
0186	650.5500 Construction Staking Curb Gutter and Curb & Gutter	2,028.000 LF	·	
0188	650.8000 Construction Staking Resurfacing Reference	11,400.000 LF	·	·
0190	650.9000 Construction Staking Curb Ramps	50.000 EACH		
0192	650.9910 Construction Staking Supplemental Control (project) 01. 1198-03-78	LS	LUMP SUM	







Page 7 of 10

**Proposal ID:** 20210112035 **Project(s):** 1198-03-78

Federal ID(s): WISC 2021105

**SECTION:** 0001 Roadway Construction

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0194	652.0225 Conduit Rigid Nonmetallic Schedule 40 2-Inch	71.000 LF		
0196	652.0235 Conduit Rigid Nonmetallic Schedule 40 3-Inch	195.000 LF	·	<del>.</del>
0198	652.0615 Conduit Special 3-Inch	653.000 LF	·	
0200	653.0164 Pull Boxes Non-Conductive 24x42-Inch	8.000 EACH		
0202	653.0900 Adjusting Pull Boxes	2.000 EACH		
0204	653.0905 Removing Pull Boxes	27.000 EACH		<u> </u>
0206	654.0101 Concrete Bases Type 1	5.000 EACH		<u> </u>
0208	654.0102 Concrete Bases Type 2	2.000 EACH		
0210	654.0113 Concrete Bases Type 13	1.000 EACH		
0212	654.0120 Concrete Bases Type 10-Special	1.000 EACH		
0214	654.0217 Concrete Control Cabinet Bases Type 9 Special	1.000 EACH	·	
0216	655.0230 Cable Traffic Signal 5-14 AWG	702.000 LF		
0218	655.0240 Cable Traffic Signal 7-14 AWG	188.000 LF		
0220	655.0260 Cable Traffic Signal 12-14 AWG	1,281.000 LF		<u> </u>
0222	655.0305 Cable Type UF 2-12 AWG Grounded	567.000 LF		
0224	655.0515 Electrical Wire Traffic Signals 10 AWG	966.000 LF		







Page 8 of 10


**Proposal ID:** 20210112035 **Project(s):** 1198-03-78

Federal ID(s): WISC 2021105

**SECTION:** 0001 Roadway Construction

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0226	655.0610 Electrical Wire Lighting 12 AWG	528.000 LF		<u> </u>
0228	655.0630 Electrical Wire Lighting 4 AWG	800.000 LF		
0230	655.0900 Traffic Signal EVP Detector Cable	852.000 LF	·	
0232	656.0200 Electrical Service Meter Breaker Pedestal (location) 01. USH 2 & 39th Ave	LS	LUMP SUM	
0234	657.0100 Pedestal Bases	5.000 EACH	·	
0236	657.0255 Transformer Bases Breakaway 11 1/2- Inch Bolt Circle	2.000 EACH	·	·
0238	657.0310 Poles Type 3	2.000 EACH	<u> </u>	
0240	657.0352 Poles Type 10-Special	1.000 EACH		
0242	657.0360 Poles Type 13	1.000 EACH		
0244	657.0420 Traffic Signal Standards Aluminum 13-FT	2.000 EACH		
0246	657.0425 Traffic Signal Standards Aluminum 15-FT	2.000 EACH		
0248	657.0430 Traffic Signal Standards Aluminum 10-FT	1.000 EACH		
0250	657.0546 Monotube Arms 45-FT-Special	1.000 EACH		
0252	657.0550 Monotube Arms 50-FT	1.000 EACH		
0254	657.0590 Trombone Arms 20-FT	2.000 EACH		
0256	657.0704 Luminaire Arms Truss Type 4-Inch Clamp 10-FT	2.000 EACH	·	







Page 9 of 10

**Proposal ID:** 20210112035 **Project(s):** 1198-03-78

Federal ID(s): WISC 2021105

**SECTION:** 0001 Roadway Construction

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0258	657.0810 Luminaire Arms Steel 10-FT	2.000 EACH		·
0260	658.0173 Traffic Signal Face 3S 12-Inch	12.000 EACH		·
0262	658.0174 Traffic Signal Face 4S 12-Inch	4.000 EACH	·	
0264	658.0416 Pedestrian Signal Face 16-Inch	8.000 EACH	·	
0266	658.0500 Pedestrian Push Buttons	8.000 EACH	·	
0268	658.5069 Signal Mounting Hardware (location) 01. USH 2 & 39th Avenue	LS	LUMP SUM	
0270	659.1115 Luminaires Utility LED A	4.000 EACH		·
0272	661.0200 Temporary Traffic Signals for Intersections (location) 01. USH 2 & 39th Ave	LS	LUMP SUM	·
0274	690.0150 Sawing Asphalt	514.000 LF		
0276	690.0250 Sawing Concrete	44,108.000 LF		
0278	715.0415 Incentive Strength Concrete Pavement	500.000 DOL	1.00000	500.00
0280	740.0440 Incentive IRI Ride	17,280.000 DOL	1.00000	17,280.00
0282	ASP.1T0A On-the-Job Training Apprentice at \$5.00/HR	2,400.000 HRS	5.00000	12,000.00
0284	ASP.1T0G On-the-Job Training Graduate at \$5.00/HR	990.000 HRS	5.00000	4,950.00
0286	SPV.0045 Special 01. Flashing Beacon Queue Warning System	166.000 DAY	<u> </u>	



12/02/2020 16:53:45



## **Proposal Schedule of Items**

Page 10 of 10

**Proposal ID:** 20210112035 **Project(s):** 1198-03-78

Federal ID(s): WISC 2021105

**SECTION:** 0001 Roadway Construction

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0288	SPV.0060 Special 01. Elastomeric Waterproofing Sealer	66.000 EACH	·	·
0290	SPV.0060 Special 02. Protecting Footing	1.000 EACH		
0292	SPV.0090 Special 01. Cure and Seal Treatment, Concrete Curb and Gutter	2,028.000 LF	·	
0294	SPV.0105 Special 01. Traffic Signal Cabinet And Controller USH 2 39th Ave	LS	LUMP SUM	
0296	SPV.0105 Special 02. Furnish and Install Emergency Vehicle Preemption System USH 2 & 39th Ave	LS	LUMP SUM	
0298	SPV.0105 Special 03. Vehicle Video Detection System USH 2 & 39th Ave	LS	LUMP SUM	
0300	SPV.0105 Special 04. Material Transfer Vehicle	LS	LUMP SUM	
0302	SPV.0165 Special 01. Cure and Seal Treatment, Concrete Sidewalk	27,326.000 SF		
0304	SPV.0180 Special 01. Pigmented Surface Sealer Reseal	329.000 SY		·
	Section: 000	01	Total:	

Total Bid:	

## PLEASE ATTACH ADDENDA HERE



## **Wisconsin Department of Transportation**

January 4, 2021

#### Division of Transportation Systems Development

Bureau of Project Development 4822 Madison Yards Way, 4<sup>th</sup> Floor South Madison, WI 53705

Telephone: (608) 266-1631 Facsimile (FAX): (608) 266-8459

## **NOTICE TO ALL CONTRACTORS:**

## Federal Wage Rate Addendum #01

## Letting of January 12, 2021

Attached is a copy of the revised WI 10 Highway Davis Bacon Prevailing Wage Rates that are included in proposals 01-03, 05, 07-09, 13-15, 17-24, 27-30, and 32-40; WI 8 Heavy (Sewer & Water Line & Tunnel) Davis Bacon Prevailing Wage Rates that are included in proposal 14; and WI 15 Heavy Davis Bacon Prevailing Wage Rates that are included in proposals 24 and 35. These wage rates are effective for all proposals they are included in in the January 12, 2021 letting. The updated wage rates are dated January 1, 2021 and are effective on or after January 11, 2021.

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractors.

Sincerely,

Mike Coleman

Proposal Development Specialist Proposal Management Section

"General Decision Number: WI20210010 01/01/2021

Superseded General Decision Number: WI20200010

State: Wisconsin

Construction Type: Highway

Counties: Wisconsin Statewide.

HIGHWAY, AIRPORT RUNWAY & TAXIWAY CONSTRUCTION PROJECTS (does not include bridges over navigable waters; tunnels; buildings in highway rest areas; and railroad construction)

Note: Under Executive Order (EO) 13658, an hourly minimum wage of \$10.95 for calendar year 2021 applies to all contracts subject to the Davis-Bacon Act for which the contract is awarded (and any solicitation was issued) on or after January 1, 2015. If this contract is covered by the EO, the contractor must pay all workers in any classification listed on this wage determination at least \$10.95 per hour (or the applicable wage rate listed on this wage determination, if it is higher) for all hours spent performing on the contract in calendar year 2021. If this contract is covered by the EO and a classification considered necessary for performance of work on the contract does not appear on this wage determination, the contractor must pay workers in that classification at least the wage rate determined through the conformance process set forth in 29 CFR 5.5(a)(1)(ii) (or the EO minimum wage rate, if it is higher than the conformed wage rate). The EO minimum wage rate will be adjusted annually. Please note that this EO applies to the above-mentioned types of contracts entered into by the federal government that are subject to the Davis-Bacon Act itself, but it does not apply to contracts subject only to the Davis-Bacon Related Acts, including those set forth at 29 CFR 5.1(a)(2)-(60). Additional information on contractor requirements and worker protections under the EO is available at www.dol.gov/whd/govcontracts.

Modification Number Publication Date 0 01/01/2021

BRWI0001-002 06/03/2019

CRAWFORD, JACKSON, JUNEAU, LA CROSSE, MONROE, TREMPEALEAU, AND VERNON COUNTIES

	Rates	Fringes	
BRICKLAYER	.\$ 33.80	24.28	
* BRWI0002-002 06/01/2020			
ASHLAND, BAYFIELD, DOUGLAS, AND	IRON COUNTIES		
	Rates	Fringes	
BRICKLAYER	.\$ 42.77	23.47	
BRWI0002-005 06/01/2019			
ADAMS, ASHLAND, BARRON, BROWN, BURNETT, CALUMET, CHIPPEWA, CLARK, COLUMBIA, DODGE, DOOR, DUNN, FLORENCE, FOND DU LAC, FOREST, GREEN LAKE, IRON, JEFFERSON, KEWAUNEE, LANGLADE, LINCOLN, MANITOWOC, MARATHON, MARINETTE, MARQUETTE, MENOMINEE, OCONTO, ONEIDA, OUTAGAMIE, POLK, PORTAGE, RUSK, ST CROIX, SAUK, SHAWANO, SHEBOYGAN, TAYLOR, VILAS, WALWORTH, WAUPACA, WAUSHARA, WINNEBAGO, AND WOOD COUNTIES			
	Rates	Fringes	
CEMENT MASON/CONCRETE FINISHER	.\$ 35.51	23.37	
* BRWI0003-002 06/01/2020	MADINETTE AND	OCONTO COUNTIES	
BROWN, DOOR, FLORENCE, KEWAUNEE,			
	Rates	J	
BRICKLAYER BRWI0004-002 06/01/2019	•	24.40	
KENOSHA, RACINE, AND WALWORTH CO	DUNTIES		
	Rates	Fringes	
BRICKLAYER	.\$ 38.43	25.10	
BRWI0006-002 06/01/2019			
ADAMS, CLARK, FOREST, LANGLADE, ONEIDA, PORTAGE, PRICE, TAYLOR,	=	=	

	Rates	Fringes	
BRICKLAYER	\$ 35.06	23.02	
BRWI0007-002 06/03/2019			
GREEN, LAFAYETTE, AND ROCK COUNT	ΓΙΕS		
	Rates	Fringes	
BRICKLAYER	•	24.22	
BRWI0008-002 06/01/2019			
MILWAUKEE, OZAUKEE, WASHINGTON,	AND WAUKESHA COL	JNTIES	
	Rates	Fringes	
BRICKLAYER	\$ 38.93		
* BRWI0011-002 06/01/2020			
CALUMET, FOND DU LAC, MANITOWOC	, AND SHEBOYGAN (	COUNTIES	
	Rates	Fringes	
BRICKLAYER	·	24.40	
* BRWI0019-002 06/01/2020			
BARRON, BUFFALO, BURNETT, CHIPPEWA, DUNN, EAU CLAIRE, PEPIN, PIERCE, POLK, RUSK, ST. CROIX, SAWYER AND WASHBURN COUNTIES			
	Rates	Fringes	
BRICKLAYER		25.22	
COLUMBIA AND SAUK COUNTIES			
	Rates	Fringes	
BRICKLAYER		24.23	
CARP0087-001 05/01/2016			
BURNETT (W. of Hwy 48), PIERCE (W. of Hwy 29), POLK (W. of Hwys 35, 48 & 65), AND ST. CROIX (W. of Hwy 65) COUNTIES			

	Rates	Fringes
Carpenter & Piledrivermen	\$ 36.85	18.39
CARP0252-002 06/01/2016		

ADAMS, BARRON, BAYFIELD (Eastern 2/3), BROWN, BUFFALO, BURNETT (E. of Hwy 48), CALUMET, CHIPPEWA, CLARK, COLUMBIA, CRAWFORD, DANE, DODGE, DOOR, DUNN, EAU CLAIRE, FLORENCE (except area bordering Michigan State Line), FOND DU LAC, FOREST, GRANT, GREEN, GREEN LAKE, IOWA, IRON, JACKSON, JEFFERSON, JUNEAU, KEWAUNEE, LA CROSSE, LAFAYETTE, LANGLADE, LINCOLN, MANITOWOC, MARATHON, MARINETTE (except N.E. corner), MARQUETTE, MENOMINEE, MONROE, OCONTO, ONEIDA, OUTAGAMIE, PEPIN, PIERCE (E. of Hwys 29 & 65), POLK (E. of Hwys 35, 48 & 65), PORTAGE, PRICE, RICHLAND, ROCK, RUSK, SAUK, SAWYER, SHAWANO, SHEBOYGAN, ST CROIX (E. of Hwy 65), TAYLOR, TREMPEALEAU, VERNON, VILAS, WALWORTH, WASHBURN, WAUPACA, WAUSHARA, WINNEBAGO, AND WOOD COUNTIES

	Rates	Fringes
CARPENTER		
CARPENTER	.\$ 33.56	18.00
MILLWRIGHT	.\$ 35.08	18.35
PILEDRIVER	.\$ 34.12	18.00

## CARP0252-010 06/01/2016

## ASHLAND COUNTY

	Rates	Fringes	
Carpenters			
Carpenter	\$ 33.56	18.00	
Millwright	\$ 35.08	18.35	
Pile Driver	\$ 34.12	18.00	

## CARP0264-003 06/01/2016

KENOSHA, MILWAUKEE, OZAUKEE, RACINE, WAUKESHA, AND WASHINGTON COUNTIES

	Rates	Fringes
CARPENTER	\$ 35.78	22.11

-----

CARP0361-004 05/01/2018

BAYFIELD (West of Hwy 63) AND DOUGLAS COUNTIES

Rates	Fringes
-------	---------

CARPENTER.....\$ 36.15 20.43

-----

CARP2337-001 06/01/2016

ZONE A: MILWAUKEE, OZAUKEE, WAUKESHA AND WASHINGTON

ZONE B: KENOSHA & RACINE

	Rates	Fringes
PILEDRIVERMAN		
Zone A	\$ 31.03	22.69
Zone B	\$ 31.03	22.69

ELEC0014-002 06/14/2020

ASHLAND, BARRON, BAYFIELD, BUFFALO, BURNETT, CHIPPEWA, CLARK (except Maryville, Colby, Unity, Sherman, Fremont, Lynn & Sherwood), CRAWFORD, DUNN, EAU CLAIRE, GRANT, IRON, JACKSON, LA CROSSE, MONROE, PEPIN, PIERCE, POLK, PRICE, RICHLAND, RUSK, ST CROIX, SAWYER, TAYLOR, TREMPEALEAU, VERNON, AND WASHBURN COUNTIES

	Rates	Fringes
Electricians:	\$ 35.98	20.98
ELEC0014-007 07/05/2020		

REMAINING COUNTIES

	Rates	Fringes
Teledata System Installer		
<pre>Installer/Technician</pre>	\$ 27.75	15.14

Low voltage construction, installation, maintenance and removal of teledata facilities (voice, data, and video) including outside plant, telephone and data inside wire, interconnect, terminal equipment, central offices, PABX, fiber optic cable and equipment, micro waves, V-SAT,

bypass, CATV, WAN (wide area networks), LAN (local area networks), and ISDN (integrated systems digital network). \_\_\_\_\_\_ ELEC0127-002 06/01/2020 KENOSHA COUNTY Rates Fringes Electricians:.....\$ 41.62 30%+12.70 \_\_\_\_\_\_ ELEC0158-002 06/01/2020 BROWN, DOOR, KEWAUNEE, MANITOWOC (except Schleswig), MARINETTE(Wausuakee and area South thereof), OCONTO, MENOMINEE (East of a ine 6 miles West of the West boundary of Oconto County), SHAWANO (Except Area North of Townships of Aniwa and Hutchins) COUNTIES Rates Fringes ELECTRICIAN.....\$ 34.77 29.75%+10.26 \_\_\_\_\_ ELEC0159-003 08/02/2020 COLUMBIA, DANE, DODGE (Area West of Hwy 26, except Chester and Emmet Townships), GREEN, LAKE (except Townships of Berlin, Seneca, and St. Marie), IOWA, MARQUETTE (except Townships of Neshkoka, Crystal Lake, Newton, and Springfield), and SAUK COUNTIES Rates Fringes ELECTRICIAN.....\$ 41.86 \_\_\_\_\_\_ ELEC0219-004 06/01/2019 FLORENCE COUNTY (Townships of Aurora, Commonwealth, Fern, Florence and Homestead) AND MARINETTE COUNTY (Township of Niagara) Rates Fringes Electricians: Electrical contracts over \$180,000.....\$ 33.94 21.80

Electrical contracts under \$180,000	.\$ 31.75	21.73	
ELEC0242-005 05/31/2020			
DOUGLAS COUNTY			
	Rates	Fringes	
Electricians:	.\$ 39.77	28.11	
ELEC0388-002 06/01/2020			
ADAMS, CLARK (Colby, Freemont, Lynn, Mayville, Sherman, Sherwood, Unity), FOREST, JUNEAU, LANGLADE, LINCOLN, MARATHON, MARINETTE (Beecher, Dunbar, Goodman & Pembine), MENOMINEE (Area West of a line 6 miles West of the West boundary of Oconto County), ONEIDA, PORTAGE, SHAWANO (Aniwa and Hutchins), VILAS AND WOOD COUNTIES			
	Rates	Fringes	
Electricians:	.\$ 34.85	26%+11.20	
ELEC0430-002 06/01/2020			
RACINE COUNTY (Except Burlington	Township)		
	Rates	Fringes	
Electricians:	.\$ 41.86	22.66	
ELEC0494-005 06/01/2020			
MILWAUKEE, OZAUKEE, WASHINGTON, A	AND WAUKESHA COL	JNTIES	
	Rates	Fringes	
Electricians:		25.54	
ELEC0494-006 06/01/2020			
CALUMET (Township of New Holstein including Chester Township), FONI (Schleswig), and SHEBOYGAN COUNTY	D'DU LAC, MANITO	-	

Rates Fringes

Electricians:	\$ 36.3	2 22.51	

ELEC0494-013 06/07/2020

DODGE (East of Hwy 26 including Chester Twp, excluding Emmet Twp), FOND DU LAC (Except Waupuin), MILWAUKEE, OZAUKEE, MANITOWOC (Schleswig), WASHINGTON, AND WAUKESHA COUNTIES

	Rates	Fringes
Sound & Communications		
Installer	\$ 21.46	18.52
Technician	\$ 31.34	20.00

Installation, testing, maintenance, operation and servicing of all sound, intercom, telephone interconnect, closed circuit TV systems, radio systems, background music systems, language laboratories, electronic carillion, antenna distribution systems, clock and program systems and low-voltage systems such as visual nurse call, audio/visual nurse call systems, doctors entrance register systems. Includes all wire and cable carrying audio, visual, data, light and radio frequency signals. Includes the installation of conduit, wiremold, or raceways in existing structures that have been occupied for six months or more where required for the protection of the wire or cable, but does not mean a complete conduit or raceway system. work covered does not include the installation of conduit, wiremold or any raceways in any new construction, or the installation of power supply outlets by means of which external electric power is supplied to any of the foregoing equipment or products

CALUMET (except Township of New Holstein), GREEN LAKE (N. part including Townships of Berlin, St Marie, and Seneca), MARQUETTE (N. part including Townships of Crystal Lake, Neshkoro, Newton, and Springfield), OUTAGAMIE, WAUPACA, WAUSHARA, AND WINNEBAGO COUNTIES

	Rates	Fringes	
Electricians:	\$ 34.23	29.50%+10.00	
ELEC0890-003 06/01/2020			

<sup>\*</sup> ELEC0577-003 06/01/2020

DODGE (Emmet Township only), GREEN, JEFFERSON, LAFAYETTE, RACINE (Burlington Township), ROCK AND WALWORTH COUNTIES

	Rates	Fringes
Electricians:\$		.95%+11.11
ELEC0953-001 06/02/2019		
	Rates	Fringes
Line Construction: (1) Lineman	5 47.53	21.43
<pre>(2) Heavy Equipment Operator (3) Equipment Operator\$</pre>		19.80 18.40
<ul><li>(4) Heavy Groundman Driver\$</li><li>(5) Light Groundman Driver\$</li><li>(6) Groundsman\$</li></ul>	30.89	16.88 16.11 14.60
ENGI0139-005 06/01/2020		
	Rates	Fringes
Power Equipment Operator		
Group 1 Group 2		23.80 23.80
Group 3		23.80
Group 4		23.80
Group 5\$		23.80
Group 6	34.17	23.80
HAZARDOUS WASTE PREMIUMS: EPA Level ""A"" protection - \$3.00 EPA Level ""B"" protection - \$2.00 EPA Level ""C"" protection - \$1.00	00 per hour	

## POWER EQUIPMENT OPERATORS CLASSIFICATIONS

GROUP 1: Cranes, tower cranes, and derricks with or without attachments with a lifting capacity of over 100 tons; or cranes, tower cranes, and derricks with boom, leads and/or jib lengths measuring 176 feet or longer.

GROUP 2: Cranes, tower cranes and derricks with or without attachments with a lifting capacity of 100 tons or less; or cranes, tower cranes, and derricks with boom, leads, and/or jibs lengths measuring 175 feet or under and Backhoes (excavators) weighing 130,000 lbs and over; caisson rigs;

pile driver; dredge operator; dredge engineer; Boat Pilot.

GROUP 3: Mechanic or welder - Heavy duty equipment; cranes with a lifting capacity of 25 tons or under; concrete breaker (manual or remote); vibratory/sonic concrete breaker; concrete laser screed; concrete slipform paver; concrete batch plant operator; concrete pvt. spreader heavy duty (rubber tired); concrete spreader & distributor; automatic subgrader (concrete); concrete grinder & planing machine; concrete slipform curb & gutter machine; slipform concrete placer; tube finisher; hydro blaster (10,000 psi & over); bridge paver; concrete conveyor system; concrete pump; Rotec type Conveyor; stabilizing mixer (self-propelled); shoulder widener; asphalt plant engineer; bituminious paver; bump cutter & grooving machine; milling machine; screed (bituminous paver); asphalt heater, planer & scarifier; Backhoes (excavators) weighing under 130,000 lbs; grader or motor patrol; tractor (scraper, dozer, pusher, loader); scraper - rubber tired (single or twin engine); endloader; hydraulic backhoe (tractor type); trenching machine; skid rigs; tractor, side boom (heavy); drilling or boring machine (mechanical heavy); roller over 5 tons; percussion or rotary drilling machine; air track; blaster; loading machine (conveyor); tugger; boatmen; winches & A-frames; post driver; material hoist.

GROUP 4: Greaser, roller steel (5 tons or less); roller (pneumatic tired) - self propelled; tractor (mounted or towed compactors & light equipment); shouldering machine; self- propelled chip spreader; concrete spreader; finishing machine; mechanical float; curing machine; power subgrader; joint sawer (multiple blade) belting machine; burlap machine; texturing machine; tractor endloader (rubber tired) - light; jeep digger; forklift; mulcher; launch operator; fireman, environmental burner

GROUP 5: Air compressor; power pack; vibrator hammer and extractor; heavy equipment, leadman; tank car heaters; stump chipper; curb machine operator; Concrete proportioning plants; generators; mudjack operator; rock breaker; crusher or screening plant; screed (milling machine); automatic belt conveyor and surge bin; pug mill operator; Oiler, pump (over 3 inches); Drilling Machine Tender.

GROUP 6: Off-road material hauler with or without ejector.

\_\_\_\_\_

BROWN, CALUMET, DOOR, FOND DU LAC, KEWAUNEE, MANITOWOC, MARINETTE, OCONTO, OUTAGAMI, SHAWANO, SHEBOYGAN, AND WINNEBAGO COUNTIES:

	Rates	Fringes
IRONWORKER	.\$ 37.31	27.62
Paid Holidays: New Year's Day, Day, Thanksgiving Day & Christ		uly 4th, Labor
IRON0008-003 06/01/2020		
KENOSHA, MILWAUKEE, OZAUKEE, RAC WASHINGTON, AND WAUKESHA COUNTIE	· ·	.E. 2/3),
	Rates	Fringes
IRONWORKER	.\$ 39.11	27.87
Paid Holidays: New Year's Day, Day, Thanksgiving Day & Christ		uly 4th, Labor
IRON0383-001 06/01/2020		
ADAMS, COLUMBIA, CRAWFORD, DANE, GRANT, GREENE, (Excluding S.E. t JEFFERSON, JUNEAU, LA CROSSE, LA MARQUETTE, MENOMINEE, MONROE, PO area, vicinity of Edgerton and M WAUSHARA, AND WOOD COUNTIES	ip), GREEN LAKE, FAYETTE, LANGLAD RTAGE, RICHLAND,	IOWA, E, MARATHON, ROCK (Northern
	Rates	Fringes
IRONWORKER	.\$ 37.10	27.06
IRON0498-005 06/01/2019		
GREEN (S.E. 1/3), ROCK (South of WALWORTH (S.W. 1/3) COUNTIES:	Edgerton and Mi	lton), and
	Rates	Fringes
IRONWORKER	.\$ 40.25	40.53

-----

### IRON0512-008 06/03/2019

BARRON, BUFFALO, CHIPPEWA, CLARK, DUNN, EAU CLAIRE, JACKSON, PEPIN, PIERCE, POLK, RUSK, ST CROIX, TAYLOR, AND TREMPEALEAU COUNTIES

	Rates	Fringes
IRONWORKER	\$ 37.60	29.40
IRON0512-021 06/03/2019		

ASHLAND, BAYFIELD, BURNETT, DOUGLAS, IRON, LINCOLN, ONEIDA, PRICE, SAWYER, VILAS AND WASHBURN COUNTIES

	Rates	Fringes
IRONWORKER	\$ 33.19	29.40
LAB00113-002 06/01/2020		

### MILWAUKEE AND WAUKESHA COUNTIES

		Rates	Fringes
LABORER			
Group	1	\$ 30.05	22.26
Group	2	\$ 30.20	22.26
Group	3	\$ 30.40	22.26
Group	4	\$ 30.55	22.26
Group	5	\$ 30.70	22.26
	6		22.26

## LABORERS CLASSIFICATIONS

GROUP 1: General Laborer; Tree Trimmer; Conduit Layer; Demolition and Wrecking Laborer; Guard Rail, Fence, and Bridge Builder; Landscaper; Multiplate Culvert Assembler; Stone Handler; Bituminous Worker (Shoveler, Loader, and Utility Man); Batch Truck Dumper or Cement Handler; Bituminous Worker (Dumper, Ironer, Smoother, and Tamper); Concrete Handler

GROUP 2: Air Tool Operator; Joint Sawer and Filler (Pavement); Vibrator or Tamper Operator (Mechanical Hand Operated); Chain Saw Operator; Demolition Burning Torch Laborer

GROUP 3: Bituminous Worker (Raker and Luteman); Formsetter (Curb, Sidewalk, and Pavement); Strike Off Man

GROUP 4: Line and Grade Specialist

GROUP 5: Blaster and Powderman

GROUP 6: Flagperson; traffic control person

-----

LAB00113-003 06/01/2020

## OZAUKEE AND WASHINGTON COUNTIES

	F	Rates	Fringes
LABORER			
Group	1\$	29.30	22.26
Group	2\$	29.40	22.26
Group	3\$	29.45	22.26
Group	4\$	29.65	22.26
Group	5\$	29.50	22.26
Group	6\$	26.39	22.26

#### LABORERS CLASSIFICATIONS

GROUP 1: General Laborer; Tree Trimmer; Conduit Layer; Demolition and Wrecking Laborer; Guard Rail, Fence, and Bridge Builder; Landscaper; Multiplate Culvert Assembler; Stone Handler; Bituminous Worker (Shoveler, Loader, and Utility Man); Batch Truck Dumper or Cement Handler; Bituminous Worker (Dumper, Ironer, Smoother, and Tamper); Concrete Handler

GROUP 2: Air Tool Operator; Joint Sawer and Filler (Pavement); Vibrator or Tamper Operator (Mechanical Hand Operated);

GROUP 3: Bituminous Worker (Raker and Luteman); Formsetter (Curb, Sidewalk, and Pavement); Strike Off Man

GROUP 4: Line and Grade Specialist

GROUP 5: Blaster; powderman

GROUP 6: Flagperson and Traffic Control Person

------

LAB00113-011 06/01/2020

#### KENOSHA AND RACINE COUNTIES

	I	Rates	Fringes
LABORER			
Group	1\$	29.11	22.26
Group	2\$	29.26	22.26
Group	3\$	29.46	22.26
Group	4\$	29.43	22.26
Group	5\$	29.76	22.26
Group	6\$	26.25	22.26

#### LABORERS CLASSIFICATIONS:

GROUP 1: General laborer; Tree Trimmer; Conduit Layer; Demolition and Wrecking Laborer; Guard Rail, Fence, and Bridge Builder; Landscaper; Multiplate Culvert Assembler; Stone Handler; Bituminous Worker (Shoveler, Loader, and Utility Man); Batch Truck Dumper or Cement Handler; Bituminous worker (Dumper, Ironer, Smoother, and Tamper); Concrete Handler

GROUP 2: Air Tool Operator; Joint Sawer and Filler (Pavement); Vibrator or Tamper Operator (Mechanical Hand Operated); Chain Saw Operator; Demolition Burning Torch Laborer

GROUP 3: Bituminous Worker (Raker and Luteman); Formsetter (Curb, Sidewalk, and Pavement); Strike Off Man

GROUP 4: Line and Grade Specialist

GROUP 5: Blaster and Powderman

GROUP 6: Flagman; traffic control person

-----

# LABO0140-002 06/01/2020

ADAMS, ASHLAND, BARRON, BAYFIELD, BROWN, BUFFALO, BURNETT, CALUMET, CHIPPEWA, CLARK, COLUMBIA, CRAWFORD, DODGE, DOOR, DOUGLAS, DUNN, EAU CLAIRE, FLORENCE, FOND DU LAC, FOREST, GRANT, GREEN, GREEN LAKE, IRON, JACKSON, JUNEAU, IOWA, JEFFERSON, KEWAUNEE, LA CROSSE, LAFAYETTE, LANGLADE, LINCOLN, MANITOWOC, MARATHON, MARINETTE, MARQUETTE, MENOMINEE, MONROE, OCONTO, ONEIDA, OUTAGAMIE, PEPIN, PIERCE, POLK, PORTAGE, PRICE, RICHLAND, ROCK, RUSK, SAUK, SAWYER, SHAWANO, SHEBOYGAN, ST. CROIX, TAYLOR, TREMPEALEAU, VERNON, VILLAS, WALWORTH, WASHBURN, WAUPACA, WAUSHARA, WINNEBAGO, AND WOOD COUNTIES

	I	Rates	Fringes
LABORER			
Group	1\$	33.72	17.95
Group	2\$	33.82	17.95
Group	3\$	33.87	17.95
Group	4\$	34.07	17.95
Group	5\$	33.92	17.95
Group	6\$	30.35	17.95

#### LABORER CLASSIFICATIONS

GROUP 1: General Laborer; Tree Trimmer; Conduit Layer; Demolition and Wrecking Laborer; Guard Rail, Fence, and Bridge Builder; Landscaper; Multiplate Culvert Assembler; Stone Handler; Bitminous Worker (Shoveler, Loader, and Utility Man); Batch Truck Dumper or Cement Handler; Bituminous Worker (Dumper, Ironer, Smoother and Tamper); Concrete Handler

GROUP 2: Air Tool Operator; Joint Sawer and Filler (Pavement); Vibrator or Tamper Operator (Mechanical Hand Operated); Chain Saw Operator, Demolition Burning Torch Laborer

GROUP 3: Bituminous Worker (Raker and Luteman); Formsetter (Curb, Sidewalk and Pavement); Strike Off Man

GROUP 4: Line and Grade Secialist

GROUP 5: Blaster; powderman

GROUP 6: Flagperson; Traffic Control

-----

LAB00464-003 06/01/2020

### DANE COUNTY

	Ī	Rates	Fringes
LABORER			
Group	1\$	34.00	17.95
Group	2\$	34.10	17.95
Group	3\$	34.15	17.95
Group	4\$	34.35	17.95
Group	5\$	34.20	17.95
Group	6\$	30.35	17.95

#### LABORERS CLASSIFICATIONS:

GROUP 1: General Laborer; Tree Trimmer; Conduit Layer; Demolition and Wrecking Laborer; Guard Rail, Fence, and Bridge Builder; Landscaper; Multiplate Culvert Assembler; Stone Handler; Bituminous Worker (Shoveler, Loader, and Utility Man); Batch Truck Dumper or Cement Handler; Bituminious Worker (Dumper, Ironer, Smoother, and Tamper); Concrete Handler

GROUP 2: Air Tool Operator; Joint Sawer and Filler (Pavement); Vibrator or Tamper Operator (Mechanical Hand Operated); Chain Saw Operator; Demolition Burning Torch Laborer

GROUP 3: Bituminous Worker (Raker and Luteman); Formsetter (Curb, Sidewalk, and Pavement); Strike Off Man

GROUP 4: Line and Grade Specialist

GROUP 5: Blaster; Powderman

GROUP 6: Flagperson and Traffic Control Person

-----

PAIN0106-008 05/01/2017

ASHLAND, BAYFIELD, BURNETT, AND DOUGLAS COUNTIES

	F	Rates	Fringes
Painters:			
New:			
Brush,	Roller\$	30.33	17.27
Spray,	Sandblast, Steel\$	30.93	17.27
Repaint	:		
Brush,	Roller\$	28.83	17.27
Spray,	Sandblast, Steel\$	29.43	17.27

PAIN0108-002 06/01/2019

# RACINE COUNTY

	Rates	Fringes
Painters:		
Brush, Roller\$	36.08	20.36
Spray & Sandblast\$	37.08	20.36

# PAIN0259-002 05/01/2008

BARRON,	CHIPPEWA,	DUNN,	EAU CLAI	RE, PEPIN,	PIERCE,	POLK,	RUSK,
SAWYER,	ST. CROIX	, AND W	IASHBURN	COUNTIES			

	Rates	Fringes
PAINTER	•	12.15
PAIN0259-004 05/01/2015		
BUFFALO, CRAWFORD, JACKSON, LA VERNON COUNTIES	CROSSE, MONROI	E, TREMPEALEAU, AND
	Rates	Fringes
PAINTER	\$ 22.03	12.45
PAIN0781-002 06/01/2019		
JEFFERSON, MILWAUKEE, OZAUKEE,	WASHINGTON, AN	ND WAUKESHA COUNTIES
	Rates	Fringes
Painters: Bridge Brush Spray & Sandblast	\$ 32.95	23.86 23.86 23.86
PAIN0802-002 06/01/2019		
COLUMBIA, DANE, DODGE, GRANT, CROCK, AND SAUK COUNTIES	GREEN, IOWA, LA	AFAYETTE, RICHLAND,
	Rates	Fringes
PAINTER Brush	\$ 30.93	18.44
PREMIUM PAY: Structural Steel, Spray, Brid hour.	lges = \$1.00	additional per
PAIN0802-003 06/01/2019		
ADAMS, BROWN, CALUMET, CLARK, [	OOOR, FOND DU I	LAC, FOREST, GREEN

LAKE, IRON, JUNEAU, KEWAUNEE, LANGLADE, LINCOLN, MANITOWOC, MARATHON, MARINETTE, MARQUETTE, MENOMINEE, OCONTO, ONEIDA, OUTAGAMIE, PORTAGE, PRICE, SHAWANO, SHEBOYGAN, TAYLOR, VILAS, WAUSHARA, WAUPACA, WINNEBAGO, AND WOOD COUNTIES

	Rates	Fringes
PAINTER		18.58
PAIN0934-001 06/01/2017		
KENOSHA AND WALWORTH COUNTIES		
	Rates	Fringes
Painters:     Brush	\$ 34.74	18.95 18.95 18.95
FLORENCE COUNTY		
	Rates	Fringes
Painters:	•	13.33
PLAS0599-010 06/01/2017		
	Rates	Fringes
CEMENT MASON/CONCRETE FINISHER Area 1	\$ 35.07 \$ 35.61 \$ 34.70 \$ 36.27	17.17 19.75 19.40 20.51 18.73 22.99

# AREA DESCRIPTIONS

AREA 1: BAYFIELD, DOUGLAS, PRICE, SAWYER, AND WASHBURN COUNTIES

AREA 2: ADAMS, ASHLAND, BARRON, BROWN, BURNETT, CALUMET, CHIPPEWA, CLARK, COLUMBIA, DODGE, DOOR, DUNN, FLORENCE, FOND DU LAC, FOREST, GREEN LAKE, IRON, JEFFERSON, KEWAUNEE, LANGLADE, LINCOLN, MANITOWOC, MARATHON, MARINETTE,

MARQUETTE, MENOMINEE, OCONTO, ONEIDA, OUTAGAMIE, POLK, PORTAGE, RUSK, ST CROIX, SAUK, SHAWANO, SHEBOYGAN, TAYLOR, VILAS, WALWORTH, WAUPACA, WAUSHARA, WINNEBAGO, AND WOOD COUNTIES

AREA 3: BUFFALO, CRAWFORD, EAU CLAIRE, JACKSON, JUNEAU, LA CROSSE MONROE, PEPIN, PIERCE, RICHLAND, TREMPEALEAU, AND VERNON COUNTIES

AREA 4: MILWAUKEE, OZAUKEE, WASHINGTON, AND WAUKESHA COUNTIES

AREA 5: DANE, GRANT, GREEN, IOWA, LAFAYETTE, AND ROCK COUNTIES

AREA 6: KENOSHA AND RACINE COUNTIES

\_\_\_\_\_

# TEAM0039-001 06/01/2020

	Rates	Fringes
TRUCK DRIVER  1 & 2 Axles  3 or more Axles; Euclids, Dumptor & Articulated,	\$ 31.07	22.94
Truck Mechanic	\$ 31.22	22.94
WELL DRILLER	\$ 16.52	3.70

WELDERS - Receive rate prescribed for craft performing operation to which welding is incidental.

\_\_\_\_\_\_

Note: Executive Order (EO) 13706, Establishing Paid Sick Leave for Federal Contractors applies to all contracts subject to the Davis-Bacon Act for which the contract is awarded (and any solicitation was issued) on or after January 1, 2017. If this contract is covered by the EO, the contractor must provide employees with 1 hour of paid sick leave for every 30 hours they work, up to 56 hours of paid sick leave each year. Employees must be permitted to use paid sick leave for their own illness, injury or other health-related needs, including preventive care; to assist a family member (or person who is like family to the employee) who is ill, injured, or has other health-related needs, including preventive care; or for reasons resulting from, or to assist a family member (or person who is like family to the employee) who is a victim of, domestic

violence, sexual assault, or stalking. Additional information on contractor requirements and worker protections under the EO is available at www.dol.gov/whd/govcontracts.

Unlisted classifications needed for work not included within the scope of the classifications listed may be added after award only as provided in the labor standards contract clauses (29CFR 5.5 (a) (1) (ii)).

-----

The body of each wage determination lists the classification and wage rates that have been found to be prevailing for the cited type(s) of construction in the area covered by the wage determination. The classifications are listed in alphabetical order of ""identifiers"" that indicate whether the particular rate is a union rate (current union negotiated rate for local), a survey rate (weighted average rate) or a union average rate (weighted union average rate).

#### Union Rate Identifiers

A four letter classification abbreviation identifier enclosed in dotted lines beginning with characters other than ""SU"" or ""UAVG"" denotes that the union classification and rate were prevailing for that classification in the survey. Example: PLUM0198-005 07/01/2014. PLUM is an abbreviation identifier of the union which prevailed in the survey for this classification, which in this example would be Plumbers. 0198 indicates the local union number or district council number where applicable, i.e., Plumbers Local 0198. The next number, 005 in the example, is an internal number used in processing the wage determination. 07/01/2014 is the effective date of the most current negotiated rate, which in this example is July 1, 2014.

Union prevailing wage rates are updated to reflect all rate changes in the collective bargaining agreement (CBA) governing this classification and rate.

## Survey Rate Identifiers

Classifications listed under the ""SU"" identifier indicate that no one rate prevailed for this classification in the survey and the published rate is derived by computing a weighted average rate based on all the rates reported in the survey for that classification. As this weighted average rate includes all rates reported in the survey, it may include both union and

non-union rates. Example: SULA2012-007 5/13/2014. SU indicates the rates are survey rates based on a weighted average calculation of rates and are not majority rates. LA indicates the State of Louisiana. 2012 is the year of survey on which these classifications and rates are based. The next number, 007 in the example, is an internal number used in producing the wage determination. 5/13/2014 indicates the survey completion date for the classifications and rates under that identifier.

Survey wage rates are not updated and remain in effect until a new survey is conducted.

Union Average Rate Identifiers

Classification(s) listed under the UAVG identifier indicate that no single majority rate prevailed for those classifications; however, 100% of the data reported for the classifications was union data. EXAMPLE: UAVG-OH-0010 08/29/2014. UAVG indicates that the rate is a weighted union average rate. OH indicates the state. The next number, 0010 in the example, is an internal number used in producing the wage determination. 08/29/2014 indicates the survey completion date for the classifications and rates under that identifier.

A UAVG rate will be updated once a year, usually in January of each year, to reflect a weighted average of the current negotiated/CBA rate of the union locals from which the rate is based.

-----

#### WAGE DETERMINATION APPEALS PROCESS

- 1.) Has there been an initial decision in the matter? This can be:
- \* an existing published wage determination
- \* a survey underlying a wage determination
- \* a Wage and Hour Division letter setting forth a position on a wage determination matter
- \* a conformance (additional classification and rate) ruling

On survey related matters, initial contact, including requests for summaries of surveys, should be with the Wage and Hour Regional Office for the area in which the survey was conducted because those Regional Offices have responsibility for the Davis-Bacon survey program. If the response from this initial contact is not satisfactory, then the process described in 2.)

and 3.) should be followed.

With regard to any other matter not yet ripe for the formal process described here, initial contact should be with the Branch of Construction Wage Determinations. Write to:

Branch of Construction Wage Determinations Wage and Hour Division U.S. Department of Labor 200 Constitution Avenue, N.W. Washington, DC 20210

2.) If the answer to the question in 1.) is yes, then an interested party (those affected by the action) can request review and reconsideration from the Wage and Hour Administrator (See 29 CFR Part 1.8 and 29 CFR Part 7). Write to:

Wage and Hour Administrator U.S. Department of Labor 200 Constitution Avenue, N.W. Washington, DC 20210

The request should be accompanied by a full statement of the interested party's position and by any information (wage payment data, project description, area practice material, etc.) that the requestor considers relevant to the issue.

3.) If the decision of the Administrator is not favorable, an interested party may appeal directly to the Administrative Review Board (formerly the Wage Appeals Board). Write to:

Administrative Review Board U.S. Department of Labor 200 Constitution Avenue, N.W. Washington, DC 20210

4.) All decisions by the Administrative Review Board are final.

\_\_\_\_\_\_

END OF GENERAL DECISION

"

"General Decision Number: WI20210008 01/01/2021

Superseded General Decision Number: WI20200008

State: Wisconsin

Construction Types: Heavy (Sewer and Water Line and Tunnel)

Counties: Wisconsin Statewide.

TUNNEL, SEWER & WATER LINE CONSTRUCTION PROJECTS

Note: Under Executive Order (EO) 13658, an hourly minimum wage of \$10.95 for calendar year 2021 applies to all contracts subject to the Davis-Bacon Act for which the contract is awarded (and any solicitation was issued) on or after January 1, 2015. If this contract is covered by the EO, the contractor must pay all workers in any classification listed on this wage determination at least \$10.95 per hour (or the applicable wage rate listed on this wage determination, if it is higher) for all hours spent performing on the contract in calendar year 2021. If this contract is covered by the EO and a classification considered necessary for performance of work on the contract does not appear on this wage determination, the contractor must pay workers in that classification at least the wage rate determined through the conformance process set forth in 29 CFR 5.5(a)(1)(ii) (or the EO minimum wage rate, if it is higher than the conformed wage rate). The EO minimum wage rate will be adjusted annually. Please note that this EO applies to the above-mentioned types of contracts entered into by the federal government that are subject to the Davis-Bacon Act itself, but it does not apply to contracts subject only to the Davis-Bacon Related Acts, including those set forth at 29 CFR 5.1(a)(2)-(60). Additional information on contractor requirements and worker protections under the EO is available at www.dol.gov/whd/govcontracts.

Modification Number Publication Date 0 01/01/2021

BRWI0001-002 06/03/2019

CRAWFORD, JACKSON, JUNEAU, LA CROSSE, MONROE, TREMPEALEAU, AND VERNON COUNTIES

	Rates	Fringes
BRICKLAYER	\$ 33.80	24.28
* BRWI0002-002 06/01/2020		
ASHLAND, BAYFIELD, DOUGLAS, AND	IRON COUNTIES	
	Rates	Fringes
BRICKLAYER	•	23.47
BRWI0002-005 06/01/2019		
ADAMS, ASHLAND, BARRON, BROWN, CLARK, COLUMBIA, DODGE, DOOR, DOFFER, GREEN LAKE, IRON, JEFFER LINCOLN, MANITOWOC, MARATHON, MARATHON, OCONTO, ONEIDA, OUTAGAMIE, POLK SHAWANO, SHEBOYGAN, TAYLOR, VILAWINNEBAGO, AND WOOD COUNTIES	JNN, FLORENCE, FOR RSON, KEWAUNEE, I ARINETTE, MARQUE , PORTAGE, RUSK,	OND DU LAC, LANGLADE, ITE, MENOMINEE, ST CROIX, SAUK,
	Rates	Fringes
CEMENT MASON/CONCRETE FINISHER.  * BRWI0003-002 06/01/2020	\$ 35.51	23.37
BROWN, DOOR, FLORENCE, KEWAUNEE	, MARINETTE, AND	OCONTO COUNTIES
	Rates	Fringes
BRICKLAYER	\$ 35.68	24.40
BRWI0004-002 06/01/2019	NINTTEC	
KENOSHA, RACINE, AND WALWORTH CO		
	Rates	Fringes
BRICKLAYER	\$ 38.43 	25.10 
BRWI0006-002 06/01/2019		
ADAMS, CLARK, FOREST, LANGLADE, ONEIDA, PORTAGE, PRICE, TAYLOR,		=

Rates

Fringes

BRICKLAYER		
BRWI0007-002 06/03/2019		
GREEN, LAFAYETTE, AND ROCK COUNT	ΓIES	
	Rates	Fringes
BRICKLAYER	\$ 35.57	24.22
BRWI0008-002 06/01/2019		
MILWAUKEE, OZAUKEE, WASHINGTON,	AND WAUKES	HA COUNTIES
	Rates	Fringes
BRICKLAYER		24.22
* BRWI0009-001 06/01/2020		
GREEN LAKE, MARQUETTE, OUTAGAMINAND WINNEBAGO COUNTIES	E, SHAWANO,	WAUPACA, WASHARA,
	Rates	Fringes
BRICKLAYER	•	
* BRWI0011-002 06/01/2020		
CALUMET, FOND DU LAC, MANITOWOC	, AND SHEBO	YGAN COUNTIES
	Rates	Fringes
BRICKLAYER		
BRWI0013-002 06/03/2019		
DANE, GRANT, IOWA, AND RICHLAND	COUNTIES	
	Rates	Fringes
BRICKLAYER	\$ 35.56	24.23
* BRWI0019-002 06/01/2020		
BARRON, BUFFALO, BURNETT, CHIPPI PIERCE, POLK, RUSK, ST. CROIX, S		

	Rates	Fringes
BRICKLAYER	.\$ 34.86	25.22
* BRWI0021-002 06/01/2020		
DODGE AND JEFFERSON COUNTIES		
	Rates	Fringes
BRICKLAYER	.\$ 36.80	24.97
BRWI0034-002 06/03/2019		
COLUMBIA AND SAUK COUNTIES		
	Rates	Fringes
BRICKLAYER	.\$ 35.56	24.23
CARP0087-001 05/01/2016		
BURNETT (W. of Hwy 48), PIERCE (35, 48 & 65), AND ST. CROIX (W.		•

ADAMS, BARRON, BAYFIELD (Eastern 2/3), BROWN, BUFFALO, BURNETT (E. of Hwy 48), CALUMET, CHIPPEWA, CLARK, COLUMBIA, CRAWFORD, DANE, DODGE, DOOR, DUNN, EAU CLAIRE, FLORENCE (except area bordering Michigan State Line), FOND DU LAC, FOREST, GRANT, GREEN, GREEN LAKE, IOWA, IRON, JACKSON, JEFFERSON, JUNEAU, KEWAUNEE, LA CROSSE, LAFAYETTE, LANGLADE, LINCOLN, MANITOWOC, MARATHON, MARINETTE (except N.E. corner), MARQUETTE, MENOMINEE, MONROE, OCONTO, ONEIDA, OUTAGAMIE, PEPIN, PIERCE (E. of Hwys 29 & 65), POLK (E. of Hwys 35, 48 & 65), PORTAGE, PRICE, RICHLAND, ROCK, RUSK, SAUK, SAWYER, SHAWANO, SHEBOYGAN, ST CROIX (E. of Hwy 65), TAYLOR, TREMPEALEAU, VERNON, VILAS, WALWORTH, WASHBURN, WAUPACA, WAUSHARA, WINNEBAGO, AND WOOD COUNTIES

Rates Fringes

CARPENTER		
CARPENTERMILLWRIGHT		18.00 18.35
PILEDRIVER	\$ 34.12	18.00
CARP0252-010 06/01/2016		
ASHLAND COUNTY		
	Rates	Fringes
Carpenters		
Carpenter		18.00 18.35
Pile Driver	\$ 34.12	18.00
CARP0264-003 06/01/2016		
KENOSHA, MILWAUKEE, OZAUKEE, RACI	INE, WAUKESHA, A	AND WASHINGTON
	Rates	Fringes
CARPENTER	\$ 35.78	22.11
CARP0361-004 05/01/2018		
BAYFIELD (West of Hwy 63) AND DOL	JGLAS COUNTIES	
	Rates	Fringes
CARPENTER		20.43
CARP2337-001 06/01/2016		
ZONE A: MILWAUKEE, OZAUKEE, WAUKE	SHA AND WASHING	STON
ZONE B: KENOSHA & RACINE		
	Rates	Fringes
	Races	TT INGCS
PILEDRIVERMAN  Zone A	\$ 31.03	22.69
Zone B		22.69
CARP2337-003 06/01/2019		
	Rates	Fringes

MILLWRIGHT

Zone A.....\$ 33.58 21.53 Zone B.....\$ 33.58 21.53

ZONE DEFINITIONS

ZONE A: MILWAUKEE, OZAUKEE, WAUKESHA AND WASHINGTON COUNTIES

ZONE B: KENOSHA & RACINE COUNTIES

-----

ELEC0014-002 06/14/2020

ASHLAND, BARRON, BAYFIELD, BUFFALO, BURNETT, CHIPPEWA, CLARK (except Maryville, Colby, Unity, Sherman, Fremont, Lynn & Sherwood), CRAWFORD, DUNN, EAU CLAIRE, GRANT, IRON, JACKSON, LA CROSSE, MONROE, PEPIN, PIERCE, POLK, PRICE, RICHLAND, RUSK, ST CROIX, SAWYER, TAYLOR, TREMPEALEAU, VERNON, AND WASHBURN COUNTIES

	Rates	Fringes
Electricians:	.\$ 35.98	20.98

ELEC0127-002 06/01/2020

KENOSHA COUNTY

	Rates	Fringes
Electricians:	.\$ 41.62	30%+12.70
ELEC0158-002 06/01/2020		

BROWN, DOOR, KEWAUNEE, MANITOWOC (except Schleswig), MARINETTE(Wausuakee and area South thereof), OCONTO, MENOMINEE (East of a ine 6 miles West of the West boundary of Oconto County), SHAWANO (Except Area North of Townships of Aniwa and Hutchins) COUNTIES

	Rates	Fringes
ELECTRICIAN	.\$ 34.77	29.75%+10.26
ELEC0159-003 08/02/2020		

COLUMBIA, DANE, DODGE (Area West of Hwy 26, except Chester and

Emmet Townships), GREEN, LAKE (except Townships of Berlin, Seneca, and St. Marie), IOWA, MARQUETTE (except Townships of Neshkoka, Crystal Lake, Newton, and Springfield), and SAUK COUNTIES

	Rates	Fringes
ELECTRICIAN	\$ 41.86	22.67
ELEC0219-004 06/01/2019		

FLORENCE COUNTY (Townships of Aurora, Commonwealth, Fern, Florence and Homestead) AND MARINETTE COUNTY (Township of Niagara)

	Rates	Fringes
Electricians:		
Electrical contracts over	r	
\$180,000	\$ 33.94	21.80
Electrical contracts und	er	
\$180,000	\$ 31.75	21.73
ELEC0242-005 05/31/2020		

DOUGLAS COUNTY

	Rates	Fringes
Electricians:	\$ 39.77	28.11
ELEC0388-002 06/01/2020		

ADAMS, CLARK (Colby, Freemont, Lynn, Mayville, Sherman, Sherwood, Unity), FOREST, JUNEAU, LANGLADE, LINCOLN, MARATHON, MARINETTE (Beecher, Dunbar, Goodman & Pembine), MENOMINEE (Area West of a line 6 miles West of the West boundary of Oconto County), ONEIDA, PORTAGE, SHAWANO (Aniwa and Hutchins), VILAS AND WOOD COUNTIES

	Rates	Fringes
Electricians:	\$ 34.85	26%+11.20
ELEC0430-002 06/01/2020		

RACINE COUNTY (Except Burlington Township)

	Rates	Fringes
Electricians:		22.66
ELEC0494-005 06/01/2020		
MILWAUKEE, OZAUKEE, WASHINGTON	, AND WAUKESH	HA COUNTIES
	Rates	Fringes
Electricians:	\$ 42.84	25.54
ELEC0494-006 06/01/2020		
CALUMET (Township of New Holst including Chester Township), F (Schleswig), and SHEBOYGAN COU	OND DU LAC, N	•
	Rates	Fringes
Electricians:	\$ 36.32	22.51
* ELEC0577-003 06/01/2020		
CALUMET (except Township of New Holstein), GREEN LAKE (N. part including Townships of Berlin, St Marie, and Seneca), MARQUETTE (N. part including Townships of Crystal Lake, Neshkoro, Newton, and Springfield), OUTAGAMIE, WAUPACA, WAUSHARA, AND WINNEBAGO COUNTIES		
	Rates	Fringes
Electricians:	\$ 34.23	
ELEC0890-003 06/01/2020		
DODGE (Emmet Township only), GREEN, JEFFERSON, LAFAYETTE, RACINE (Burlington Township), ROCK AND WALWORTH COUNTIES		
	Rates	Fringes
Electricians:	\$ 37.41	25.95%+11.11
ENGI0139-003 06/01/2020		
REMAINING COUNTIES		

	Rates	Fringes
Power Equipment Operator		
Group 1	.\$ 42.92	23.15
Group 2	.\$ 41.67	23.15
Group 3	.\$ 39.97	23.15
Group 4	.\$ 39.44	23.15
Group 5	.\$ 37.37	23.15
Group 6	.\$ 35.84	23.15

# HAZARDOUS WASTE PREMIUMS:

EPA Level ""A"" Protection: \$3.00 per hour EPA Level ""B"" Protection: \$2.00 per hour EPA Level ""C"" Protection: \$1.00 per hour

# POWER EQUIPMENT OPERATORS CLASSIFICATIONS

GROUP 1: Cranes, Tower Cranes and Derricks with or without attachments with a lifting capacity of over 100 tons; Cranes, Tower Cranes, and Derricks with boom, leads and/or jib lengths 176 ft or longer.

GROUP 2: Backhoes (Excavators) weighing 130,00 lbs and over; Cranes, Tower Cranes and Derricks with or without attachments with a lifting capacity of 100 tons or less; Cranes, Tower Cranes, and Derricks with boom, leads, and/or jib lengths 175 ft or less; Caisson Rigs; Pile Driver

GROUP 3: Backhoes (Excavators) weighing under 130,000 lbs; Travelling Crane (bridge type); Milling Machine; Concrete Paver over 27 E; Concrete Spreader and Distributor; Concrete Laser Screed; Concrete Grinder and Planing Machine; Slipform Curb and Gutter Machine; Boring Machine (Directional); Dredge Operator; Skid Rigs; over 46 meter Concrete Pump.

GROUP 4: Hydraulic Backhoe (tractor or truck mounted);
Hydraulic Crane, 10 tons or less; Tractor, Bulldozer, or
End Loader (over 40 hp); Motor Patrol; Scraper Operator;
Bituminous Plant and Paver Operator; Screed-Milling
Machine; Roller over 5 tons; Concrete pumps 46 meter and
under; Grout Pumps; Rotec type machine; Hydro Blaster,
10,000 psi and over; Rotary Drill Operator; Percussion
Drilling Machine; Air Track Drill with or without integral
hammer; Blaster; Boring Machine (vertical or horizontal);
Side Boom; Trencher, wheel type or chain type having 8 inch
or larger bucket; Rail Leveling Machine (Railroad); Tie
Placer; Tie Extractor; Tie Tamper; Stone Leveler; Straddle
Carrier; Material Hoists; Stack Hoist; Man Hoists; Mechanic

and Welder; Off Road Material Haulers.

GROUP 5: Tractor, Bulldozer, or Endloader (under 40 hp); Tampers -Compactors, riding type; Stump Chipper, large; Roller, Rubber Tire; Backfiller; Trencher, chain type (bucket under 8 inch); Concrete Auto Breaker, large; Concrete Finishing Machine (road type); Concrete Batch Hopper; Concrete Conveyor Systems; Concrete Mixers, 14S or over; Pumps, Screw Type and Gypsum); Hydrohammers, small; Brooms and Sweeeprs; Lift Slab Machine; Roller under 5 tons; Industrial Locomotives; Fireman (Pile Drivers and Derricks); Pumps (well points); Hoists, automatic; A-Frames and Winch Trucks; Hoists (tuggers); Boats (Tug, Safety, Work Barges and Launches); Assistant Engineer

GROUP 6: Shouldering Machine Operator; Farm or Industrial Tractor mounted equipment; Post Hole Digger; Auger (vertical and horizontal); Skid Steer Loader with or without attachments; Robotic Tool Carrier with or without attachments; Power Pack Vibratory/Ultra Sound Driver and Extractor; Fireman (Asphalt Plants); Screed Operator; Stone Crushers and Screening Plants; Air, Electric, Hydraulic Jacks (Slip Form); Prestress Machines; Air Compressor, 400 CFM or over; Refrigeration Plant/Freese Machine; Boiler Operators (temporary heat); Forklifts; Welding Machines; Generators; Pumps over 3""; Heaters, Mechanical; Combination small equipment operator; Winches, small electric; Oiler; Greaser; Rotary Drill Tender; Conveyor; Elevator Operator

-----

## ENGI0139-007 06/01/2020

DODGE, FOND DU LAC, JEFFERSON, KENOSHA, MILWAUKEE, OZAUKEE, RACINE, SHEBOYGAN, WALWORTH, WASHINGTON, AND WAUKESHA COUNTIES

	Rates	Fringes
Power Equipment Operator		
Group 1	\$ 41.64	23.25
Group 2	\$ 40.86	23.25
Group 3	\$ 39.91	23.25
Group 4		23.25
Group 5		23.25

### HAZARDOUS WASTE PREMIUMS:

EPA Level ""A"" Protection: \$3.00 per hour EPA Level ""B"" Protection: \$2.00 per hour EPA Level ""C"" Protection: \$1.00 per hour

- GROUP 1: Cranes, Tower Cranes, and Derricks with or without attachments, with a lifting capacity of over 100 tons; or Cranes, Tower Cranes, and Derricks with boom, leads, and/or jib lengths measuring 176 feet or longer; Backhoes (Excavators) 130,000 lbs and over; Caisson Rigs and Pile Drivers
- GROUP 2: Cranes, Tower Cranes and Derricks with or without attachments with a lifting capacity of 100 tons or under; or Cranes, Tower Cranes, and Derricks with boom, lead, and\or jib lengths measuring 175 feet or under; Backhoes (Excavators) under 130,000 lbs; Skid Rigs; Dredge Operator: Traveling Crane (Bridge type); Concrete Paver over 27 E; Concrete Spreader and Distributor; Concrete Pumps and Boring Machines (directional)
- GROUP 3: Material Hoists; Stack Hoists; Tractor or Truck mounted Hydraulic Backhoe; Tractor or Truck Mounted Hydraulic Crane, 5 tons or under; Manhoist; Tractor over 40 hp; Bulldozer over 40 hp; Endloader over 40 hp; Forklift, 25 ft and over; Motor Patrol; Scraper Operator; Sideboom; Straddle Carrier; Mechanic and Welder; Bituminous Plant and Paver Operator; Roller over 5 tons; Percussion Drill Operator; Rotary Drill Operator; Blaster; Air Track Drill; Trencher (wheel type or chain type having over 8 inch bucket); Elevator; Milling Machine and Boring Machine (horizontal or vertical); Backhoe Mounted Compactor
- GROUP 4: Backfiller; Concrete Auto Breaker (large); Concrete Finishing Machine (road type); Roller, Rubber Tire; Concrete Batch Hopper; Concrete Conveyor System; Concrete Mixers (14S or over); Screw type Pumps and Gypsum Pumps; Grout Pumps; Tractor, Bulldozer, End Loader, under 40 hp; Pumps (well points); Trencher (chain type 8 inch or smaller bucket; Industrial Locomotives; Roller under 5 tons; Fireman (Piledrivers and Derricks); Robotic Tool Carrier with or without attachments.
- GROUP 5: Hoists (Automatic); Forklift, 12 ft to 25 ft; Tamper-Compactors, riding type; A-Frame andWinch Trucks; Concrete Auto Breaker; Hydrohammer, small; Brooms and Sweepers; Hoist (Tuggers); Stump Chipper, large; Boats (Tug, Safety, Work Barges and Launch); Shouldering Machine Operator; Screed Operator; Farm or Industrial Tractor; Post Hole Digger; Stone Crushers and Screening Plants; Firemen (Asphalt Plants); Air Compressor (400 CFM or over); Augers (vertical and horizontal); Generators, 150 KW and over; Air, Electric Hydraulic Jacks (Slipform); Prestress

Machines; Skid Steer Loader with or without attachments; Boiler operators (temporary heat); Forklift, 12 ft and under; Screed Operator Milling Machine; Refrigeration Plant/Freeze Machine; Power Pack Vibratory/Ultra Sound Driver and Extractor; Generators under 150 KW; Combination small equipment operator; Compressors under 400 CFM; Welding Machines; Heaters, Mechanical; Pumps; Winches, Small Electric; Oiler and Greaser; Conveyor; High pressure utility locating machine (daylighting machine).

-----

### IRON0008-002 06/01/2020

BROWN, CALUMET, DOOR, FOND DU LAC, KEWAUNEE, MANITOWOC, MARINETTE, OCONTO, OUTAGAMI, SHAWANO, SHEBOYGAN, AND WINNEBAGO COUNTIES:

Rates Fringes

IRONWORKER.....\$ 37.31 27.62

Paid Holidays: New Year's Day, Memorial Day, July 4th, Labor Day, Thanksgiving Day & Christmas Day.

-----

IRON0008-003 06/01/2020

KENOSHA, MILWAUKEE, OZAUKEE, RACINE, WALWORTH (N.E. 2/3), WASHINGTON, AND WAUKESHA COUNTIES

Rates Fringes

IRONWORKER.....\$ 39.11 27.87

Paid Holidays: New Year's Day, Memorial Day, July 4th, Labor Day, Thanksgiving Day & Christmas Day.

-----

# IRON0383-001 06/01/2020

ADAMS, COLUMBIA, CRAWFORD, DANE, DODGE, FLORENCE, FOREST, GRANT, GREENE, (Excluding S.E. tip), GREEN LAKE, IOWA, JEFFERSON, JUNEAU, LA CROSSE, LAFAYETTE, LANGLADE, MARATHON, MARQUETTE, MENOMINEE, MONROE, PORTAGE, RICHLAND, ROCK (Northern area, vicinity of Edgerton and Milton), SAUK, VERNON, WAUPACA, WAUSHARA, AND WOOD COUNTIES

	Rates	Fringes
IRONWORKER	.\$ 37.10	27.06
IRON0498-005 06/01/2019		
GREEN (S.E. 1/3), ROCK (South of WALWORTH (S.W. 1/3) COUNTIES:	Edgerton and Mi	ilton), and
	Rates	Fringes
IRONWORKER	.\$ 40.25	40.53
IRON0512-008 06/03/2019		
BARRON, BUFFALO, CHIPPEWA, CLARK PEPIN, PIERCE, POLK, RUSK, ST CR COUNTIES	-	
	Rates	Fringes
IRONWORKER	.\$ 37.60	29.40
ASHLAND, BAYFIELD, BURNETT, DOUG PRICE, SAWYER, VILAS AND WASHBU		DLN, ONEIDA,
	Rates	Fringes
IRONWORKER		29.40
MILWAUKEE, OZAUKEE, WASHINGTON,	AND WAUKESHA COL	JNTIES
	Rates	Fringes
Laborers: (Open Cut) Group 1	.\$ 18.65 .\$ 22.19 .\$ 31.56 .\$ 31.70 .\$ 31.76	21.08 21.08 21.08 21.08 21.08 21.08 21.08 21.08

Group 9.....\$ 38.23 21.08

LABORERS CLASSIFICATIONS [OPEN CUT]

GROUP 1: Yard Laborer

GROUP 2: Landscaper

GROUP 3: Flag Person

GROUP 4: Paving Laborer

GROUP 5: General Laborer on Surface; Top Man

GROUP 6: Mud Mixer

GROUP 7: Mucker; Form Stripper; Bottom Digger and Misc; Bottom Man and Welder on Surface

GROUP 8: Concrete Manhole Builder; Caisson Worker; Miner; Pipe Layer; Rock Driller and Joint Man; Timber Man and Concrete Brusher; Bracer in Trench Behind Machine & Tight Sheeting; Concrete Formsetter and Shoveler; Jackhammer Operator

GROUP 9: Blaster

\_\_\_\_\_\_

LAB00113-005 06/01/2020

SEWER, TUNNEL & UNDERGROUND

KENOSHA AND RACINE COUNTIES

	Rate	es l	ringes
			_
Laborers:			
Group	1\$ 23.	. 05	21.08
Group	2\$ 28.	. 98	21.08
Group	3\$ 32.	. 34	21.08
Group	4\$ 34.	. 11	21.08

TUNNEL WORK UNDER COMPRESSED AIR: 0-15 lbs add \$1.00, 15-30 lbs add \$2.00, over 30 lbs add \$3.00

LABORERS CLASSIFICATIONS

GROUP 1: Flagperson

GROUP 2: Top Man, General Laborer, Wellpoint Installation, Wire Mesh and Reinforcement, Concrete Worker, Form Stripper, Strike-off Work

GROUP 3: Machine and Equipment Operator, Sheeting, Form Setting, Patch Finisher, Bottom Man, Joint Sawer, Gunnite Man, Manhole Builder, Welder-Torchman, Blaster, Caulker, Bracer, Bull Float, Conduit Worker, Mucker and Car Pusher, Raker and Luteman, Hydraulic Jacking of Shields, Shield Drivers, Mining Machine, Lock Tenders, Mucking Machine Operator, Motor Men & Gauge Tenders and operation of incidental Mechanical Equipment and all Power Driven Tools

GROUP 4: Pipelayer, Miner and Laser Operator

-----

LAB00113-008 06/01/2020

MILWAUKEE, OZAUKEE, WASHINGTON & WAUKESHA COUNTIES

	Rates	Fringes
Laborers: (Tunnel-Free Air)		
Group 1	\$ 22.19	21.08
Group 2	\$ 31.70	21.08
Group 3	\$ 31.76	21.08
Group 4	\$ 34.77	21.08
Group 5	\$ 34.91	21.08
Group 6	\$ 37.59	21.08
Group 7	\$ 38.23	21.08

# LABORERS CLASSIFICATIONS [TUNNEL - FREE AIR]:

GROUP 1: Flagperson

GROUP 2: General Laborer on surface; Tower Man

GROUP 3: Saw Man; Top Man

GROUP 4: Form Stripper; Car Pusher

GROUP 5: Mucker; Dinkey; Welder (rate on surface)

GROUP 6: Concrete Manhole Builder; Mucking Machine; Miner; Mining Machine; Welder; Rock Driller; Concrete Buster; Jack Hammer Operator; Caisson Worker; Pipelayer and Joint Man; Bracerman

GROUP 7: Blaster

# \* LAB00113-009 06/01/2020

# MILWAUKEE, OZAUKEE, WASHINGTON & WAUKESHA COUNTIES

	Rates	Fringes
Laborers: (Tunnel - *COMPRESSED AIR 0 - 15 lbs.)		
Group 1	\$ 22.19	21.08
Group 2	\$ 31.70	21.08
Group 3	\$ 35.31	21.08
Group 4	\$ 36.11	21.08
Group 5	\$ 36.23	21.08
Group 6	\$ 38.93	21.08
Group 7	\$ 39.55	21.08

# LABORERS CLASSIFICATIONS [TUNNEL - COMPRESSED AIR]:

GROUP 1: Flagperson

GROUP 2: General Laborer on surface

GROUP 3: Lock Tender on surface

GROUP 4: Form Stripper; Car Pusher

GROUP 5: Mucker; Dinkey

GROUP 6: Mucking Machine; Miner; Mining Machine; Welder & Rock Driller; Lock Tender in tunnel; Concrete Buster; Jack Hammer Operator; Caisson Worker; Pielayer and Joint Man; Bracerman; Nozzle Man on Gunite; Timber Man; Concrete Brusher

GROUP 7: Blaster

NOTE: Hazardous & Toxic Waste Removal: add \$0.15 per hour.

-----

LABO0140-005 06/01/2020

ADAMS, ASHLAND, BARRON, BROWN, BUFFALO, CALUMET, CHIPPEWA, CLARK, COLUMBIA, CRAWFORD, DODGE, DOOR, DUNN, EAU CLAIRE, FLORENCE, FOND DU LAC, FOREST, GRANT, GREEN, GREEN LAKE, IOWA, JACKSON, JEFFERSON, JUNEAU, LACROSSE, LAFAYETTE, LANGLADE,

<sup>\*</sup>Compressed Air 15 - 30 lbs add \$2.00 to all classifications

<sup>\*</sup>Compressed Air over 30 lbs add \$3.00 to all classifications

LINCOLN, MANITOWOC, MARATHON, MARINETTE, MARQUETTE, MENOMINEE, MONROE, OCONTO, ONEIDA, OUTAGAMIE, PEPIN, PIERCE, POLK, PORTAGE, PRICE, RICHLAND, ROCK, RUSK, ST CROIX, SAUK, SAWYER, SHAWANO, SHEBOYGAN, TAYLOR, TREMMPEALEAU, VERNON, VILAS, WALWWORTH, WASHBURN, WAUPACA, WAUSHARA, WINNEBAGO, AND WOOD COUNTIES

	Rates	Fringes
LABORER (SEWER & WATER)		
Group 1	\$ 29.33	17.88
Group 2	\$ 31.18	17.88
Group 3	\$ 31.48	17.88
Group 4	\$ 32.13	17.88

FOR ALL TUNNEL WORK UNDER COMPRESSED AIR: 0-15 lbs add \$1.00, 15-30 lbs add \$2.00, over 30 lbs add \$3.00

#### LABORER CLASSIFICATIONS:

## GROUP 1: Flagperson

GROUP 2: General Laborer, Wellpoint Installation; Form Stripper; Strike Off worker

GROUP 3: Sheeting Formsetting; Patch Finisher; Bottom Man; Joint Sawer; Gunnite Man; Manhole Builder; Welder; Torchman; Blaster; Caulker Bracer; Bull Float; Mucker and Car Pusher; Raker and Luteman; Hydraulic jacking of shields, Shield Drivers; Mining Machine; Lock Tenders; Mucking Machine Operators; Motor Men and Gauge Tenders; Power Tool Operators

GROUP 4: Pipelayer, Miner, and Laser Operator

-----

LAB00464-002 06/01/2020

### DANE AND DOUGLAS COUNTIES

	Rates	Fringes
LABORER		
Group 1	\$ 29.23	17.88
Group 2	\$ 31.43	17.88
Group 3	\$ 31.63	17.88
Group 4	\$ 32.38	17.88

FOR ALL TUNNEL WORK UNDER COMPRESSED AIR: 0 - 15 lbs add

\$1.00, 15- 30 lbs add \$2.00, over 30 lbs add \$3.00

# LABORERS CLASSIFICATIONS:

# GROUP 1: Flagperson

GROUP 2: General Laborer; Wellpoint Installation; Concrete Worker; Form Stripper; Strike Off worker

GROUP 3: Sheeting Formsetting; Patch Finisher; Bottom Man; Joint Sawer; Gunnite Man; Manhole Builder; Welder; Torchman; Blaster; Caulker Bracer; Bull Float; Mucker and Car Pusher; Raker and Luteman; Hydraulic jacking of shields, Shield Dirvers; Mining Machine; Lock Tenders; Mucking Machine Operators; Motor Men and Gauge Tenders; Power Tool Operators

GROUP 4: Pipelayer, Miner, and Laser Operator

\_\_\_\_\_

LAB01091-010 06/01/2020

BAYFIELD, BURNETT, IRON, SAWYER, AND WASHBURN COUNTIES

	Rates	Fringes
Laborers: (SEWER & WATER)		
Group 1	\$ 29.02	17.88
Group 2	\$ 31.08	17.88
Group 3	\$ 31.28	17.88
Group 4	\$ 32.03	17.88

FOR ALL TUNNEL WORK UNDER COMPRESSED AIR:

0 - 15 lbs add \$1.00, 15-30 lbs add \$2.00, over 30 lbs add \$3.00

# LABORERS CLASSIFICATIONS:

## GROUP 1: Flagperson

GROUP 2: Laborers, Wellpoint Installation; Form Stripper; Strike Off worker

GROUP 3: Sheeting Formsetting; Patch Finisher; Bottom Man; Joint Sawer; Gunnite Man; Manhole Builder; Welder; Torchman; Blaster; Caulker Bracer; Bull Float; Mucker and Car Pusher; Raker and Luteman; Hydraulic jacking of shields, Shield Dirvers; Mining Machine; Lock Tenders;

Mucking Machine Operators; Motor Men and Gauge Tenders; Power Tool Operators

GROUP 4: Pipelayer, Miner, and Laser Operator

-----

PLAS0599-010 06/01/2017

	Rates	Fringes
CEMENT MASON/CONCRETE FINISHER		
Area 1	.\$ 39.46	17.17
Area 2 (BAC)	.\$ 35.07	19.75
Area 3	.\$ 35.61	19.40
Area 4	.\$ 34.70	20.51
Area 5	.\$ 36.27	18.73
Area 6	.\$ 32.02	22.99

### AREA DESCRIPTIONS

AREA 1: BAYFIELD, DOUGLAS, PRICE, SAWYER, AND WASHBURN COUNTIES

AREA 2: ADAMS, ASHLAND, BARRON, BROWN, BURNETT, CALUMET, CHIPPEWA, CLARK, COLUMBIA, DODGE, DOOR, DUNN, FLORENCE, FOND DU LAC, FOREST, GREEN LAKE, IRON, JEFFERSON, KEWAUNEE, LANGLADE, LINCOLN, MANITOWOC, MARATHON, MARINETTE, MARQUETTE, MENOMINEE, OCONTO, ONEIDA, OUTAGAMIE, POLK, PORTAGE, RUSK, ST CROIX, SAUK, SHAWANO, SHEBOYGAN, TAYLOR, VILAS, WALWORTH, WAUPACA, WAUSHARA, WINNEBAGO, AND WOOD COUNTIES

AREA 3: BUFFALO, CRAWFORD, EAU CLAIRE, JACKSON, JUNEAU, LA CROSSE MONROE, PEPIN, PIERCE, RICHLAND, TREMPEALEAU, AND VERNON COUNTIES

AREA 4: MILWAUKEE, OZAUKEE, WASHINGTON, AND WAUKESHA COUNTIES

AREA 5: DANE, GRANT, GREEN, IOWA, LAFAYETTE, AND ROCK COUNTIES

AREA 6: KENOSHA AND RACINE COUNTIES

-----

TEAM0039-001 06/01/2020

Rates Fringes

TRUCK DRIVER

1 & 2 Axles	\$ 31.07	22.94
<pre>3 or more Axles;</pre>	Euclids,	
Dumptor & Articul	Lated,	
Truck Mechanic	\$ 31.22	22.94
WELL DRILLER	\$ 16.52	3.70

WELDERS - Receive rate prescribed for craft performing operation to which welding is incidental.

\_\_\_\_\_

Note: Executive Order (EO) 13706, Establishing Paid Sick Leave for Federal Contractors applies to all contracts subject to the Davis-Bacon Act for which the contract is awarded (and any solicitation was issued) on or after January 1, 2017. If this contract is covered by the EO, the contractor must provide employees with 1 hour of paid sick leave for every 30 hours they work, up to 56 hours of paid sick leave each year. Employees must be permitted to use paid sick leave for their own illness, injury or other health-related needs, including preventive care; to assist a family member (or person who is like family to the employee) who is ill, injured, or has other health-related needs, including preventive care; or for reasons resulting from, or to assist a family member (or person who is like family to the employee) who is a victim of, domestic violence, sexual assault, or stalking. Additional information on contractor requirements and worker protections under the EO is available at www.dol.gov/whd/govcontracts.

Unlisted classifications needed for work not included within the scope of the classifications listed may be added after award only as provided in the labor standards contract clauses (29CFR 5.5 (a) (1) (ii)).

-----

The body of each wage determination lists the classification and wage rates that have been found to be prevailing for the cited type(s) of construction in the area covered by the wage determination. The classifications are listed in alphabetical order of ""identifiers"" that indicate whether the particular rate is a union rate (current union negotiated rate for local), a survey rate (weighted average rate) or a union average rate (weighted union average rate).

Union Rate Identifiers

A four letter classification abbreviation identifier enclosed in dotted lines beginning with characters other than ""SU"" or ""UAVG"" denotes that the union classification and rate were prevailing for that classification in the survey. Example: PLUM0198-005 07/01/2014. PLUM is an abbreviation identifier of the union which prevailed in the survey for this classification, which in this example would be Plumbers. 0198 indicates the local union number or district council number where applicable, i.e., Plumbers Local 0198. The next number, 005 in the example, is an internal number used in processing the wage determination. 07/01/2014 is the effective date of the most current negotiated rate, which in this example is July 1, 2014.

Union prevailing wage rates are updated to reflect all rate changes in the collective bargaining agreement (CBA) governing this classification and rate.

## Survey Rate Identifiers

Classifications listed under the ""SU"" identifier indicate that no one rate prevailed for this classification in the survey and the published rate is derived by computing a weighted average rate based on all the rates reported in the survey for that classification. As this weighted average rate includes all rates reported in the survey, it may include both union and non-union rates. Example: SULA2012-007 5/13/2014. SU indicates the rates are survey rates based on a weighted average calculation of rates and are not majority rates. LA indicates the State of Louisiana. 2012 is the year of survey on which these classifications and rates are based. The next number, 007 in the example, is an internal number used in producing the wage determination. 5/13/2014 indicates the survey completion date for the classifications and rates under that identifier.

Survey wage rates are not updated and remain in effect until a new survey is conducted.

### Union Average Rate Identifiers

Classification(s) listed under the UAVG identifier indicate that no single majority rate prevailed for those classifications; however, 100% of the data reported for the classifications was union data. EXAMPLE: UAVG-OH-0010 08/29/2014. UAVG indicates that the rate is a weighted union average rate. OH indicates the state. The next number, 0010 in the example, is an internal number used in producing the wage determination. 08/29/2014 indicates the survey completion date for the classifications and rates under that identifier.

A UAVG rate will be updated once a year, usually in January of each year, to reflect a weighted average of the current negotiated/CBA rate of the union locals from which the rate is based.

-----

### WAGE DETERMINATION APPEALS PROCESS

- 1.) Has there been an initial decision in the matter? This can be:
- \* an existing published wage determination
- \* a survey underlying a wage determination
- \* a Wage and Hour Division letter setting forth a position on a wage determination matter
- \* a conformance (additional classification and rate) ruling

On survey related matters, initial contact, including requests for summaries of surveys, should be with the Wage and Hour Regional Office for the area in which the survey was conducted because those Regional Offices have responsibility for the Davis-Bacon survey program. If the response from this initial contact is not satisfactory, then the process described in 2.) and 3.) should be followed.

With regard to any other matter not yet ripe for the formal process described here, initial contact should be with the Branch of Construction Wage Determinations. Write to:

Branch of Construction Wage Determinations Wage and Hour Division U.S. Department of Labor 200 Constitution Avenue, N.W. Washington, DC 20210

2.) If the answer to the question in 1.) is yes, then an interested party (those affected by the action) can request review and reconsideration from the Wage and Hour Administrator (See 29 CFR Part 1.8 and 29 CFR Part 7). Write to:

Wage and Hour Administrator U.S. Department of Labor 200 Constitution Avenue, N.W. Washington, DC 20210

The request should be accompanied by a full statement of the

interested party's position and by any information (wage payment data, project description, area practice material, etc.) that the requestor considers relevant to the issue.

3.) If the decision of the Administrator is not favorable, an interested party may appeal directly to the Administrative Review Board (formerly the Wage Appeals Board). Write to:

Administrative Review Board U.S. Department of Labor 200 Constitution Avenue, N.W. Washington, DC 20210

4.) All decisions by the Administrative Review Board are final.

\_\_\_\_\_\_

END OF GENERAL DECISION

"

"General Decision Number: WI20210015 01/01/2021

Superseded General Decision Number: WI20200015

State: Wisconsin

Construction Type: Heavy

Counties: Wisconsin Statewide.

HEAVY CONSTRUCTION PROJECTS (Excluding Tunnel, Sewer, and Water

Lines).

Note: Under Executive Order (EO) 13658, an hourly minimum wage of \$10.95 for calendar year 2021 applies to all contracts subject to the Davis-Bacon Act for which the contract is awarded (and any solicitation was issued) on or after January 1, 2015. If this contract is covered by the EO, the contractor must pay all workers in any classification listed on this wage determination at least \$10.95 per hour (or the applicable wage rate listed on this wage determination, if it is higher) for all hours spent performing on the contract in calendar year 2021. If this contract is covered by the EO and a classification considered necessary for performance of work on the contract does not appear on this wage determination, the contractor must pay workers in that classification at least the wage rate determined through the conformance process set forth in 29 CFR 5.5(a)(1)(ii) (or the EO minimum wage rate, if it is higher than the conformed wage rate). The EO minimum wage rate will be adjusted annually. Please note that this EO applies to the above-mentioned types of contracts entered into by the federal government that are subject to the Davis-Bacon Act itself, but it does not apply to contracts subject only to the Davis-Bacon Related Acts, including those set forth at 29 CFR 5.1(a)(2)-(60). Additional information on contractor requirements and worker protections under the EO is available at www.dol.gov/whd/govcontracts.

Modification Number Publication Date 0 01/01/2021

BOIL0107-001 01/01/2017

	Rates	Fringes
BOILERMAKER		
Roilermaker	\$ 35 65	29 89

Small Boiler Repair (under 25,000 lbs/hr)		16.00	
BRWI0001-002 06/03/2019			
CRAWFORD, JACKSON, JUNEAU, LA CR VERNON COUNTIES	OSSE, MONROE,	TREMPEALEAU, AND	
	Rates	Fringes	
BRICKLAYER	.\$ 33.80	24.28	
* BRWI0002-002 06/01/2020			
ASHLAND, BAYFIELD, DOUGLAS, AND	IRON COUNTIES		
	Rates	Fringes	
BRICKLAYER		23.47	
BRWI0002-005 06/01/2019			
ADAMS, ASHLAND, BARRON, BROWN, BURNETT, CALUMET, CHIPPEWA, CLARK, COLUMBIA, DODGE, DOOR, DUNN, FLORENCE, FOND DU LAC, FOREST, GREEN LAKE, IRON, JEFFERSON, KEWAUNEE, LANGLADE, LINCOLN, MANITOWOC, MARATHON, MARINETTE, MARQUETTE, MENOMINEE, OCONTO, ONEIDA, OUTAGAMIE, POLK, PORTAGE, RUSK, ST CROIX, SAUK, SHAWANO, SHEBOYGAN, TAYLOR, VILAS, WALWORTH, WAUPACA, WAUSHARA, WINNEBAGO, AND WOOD COUNTIES			
	Rates	Fringes	
CEMENT MASON/CONCRETE FINISHER	.\$ 35.51	23.37	
* BRWI0003-002 06/01/2020			
BROWN, DOOR, FLORENCE, KEWAUNEE,	MARINETTE, AN	D OCONTO COUNTIES	
	Rates	Fringes	
BRICKLAYER		24.40	
BRWI0004-002 06/01/2019	<b></b>		
KENOSHA, RACINE, AND WALWORTH CO	UNTIES		

Rates

Fringes

BRICKLAYER	-	25.10	
BRWI0006-002 06/01/2019			
ADAMS, CLARK, FOREST, LANGLADE, ONEIDA, PORTAGE, PRICE, TAYLOR,	•	-	
	Rates	Fringes	
BRICKLAYER	\$ 35.06	23.02	
BRWI0007-002 06/03/2019			
GREEN, LAFAYETTE, AND ROCK COUN	TIES		
	Rates	Fringes	
BRICKLAYER	\$ 35.57	24.22	
BRWI0008-002 06/01/2019			
MILWAUKEE, OZAUKEE, WASHINGTON,	AND WAUKESH	HA COUNTIES	
	Rates	Fringes	
BRICKLAYER	•	24.22	
* BRWI0009-001 06/01/2020			
GREEN LAKE, MARQUETTE, OUTAGAMIE, SHAWANO, WAUPACA, WASHARA, AND WINNEBAGO COUNTIES			
	Rates	Fringes	
BRICKLAYER			
* BRWI0011-002 06/01/2020			
CALUMET, FOND DU LAC, MANITOWOC	, AND SHEBOY	GAN COUNTIES	
	Rates	Fringes	
BRICKLAYER	\$ 35.68	24.40	
BRWI0013-002 06/03/2019			
DANE, GRANT, IOWA, AND RICHLAND	COUNTIES		

	Rates	Fringes
BRICKLAYER	\$ 35.56	24.23
* BRWI0019-002 06/01/2020		

BARRON, BUFFALO, BURNETT, CHIPPEWA, DUNN, EAU CLAIRE, PEPIN, PIERCE, POLK, RUSK, ST. CROIX, SAWYER AND WASHBURN COUNTIES

	Rates	Fringes
BRICKLAYER	\$ 34.86	25.22
* BRWT0021_002_06/01/2020		

\* BRWI0021-002 06/01/2020

DODGE AND JEFFERSON COUNTIES

	Rates	Fringes
BRICKLAYER	.\$ 36.80	24.97
BRWI0034-002 06/03/2019		

COLUMBIA AND SAUK COUNTIES

	Rates	Fringes	
BRICKLAYER	\$ 35.56	24.23	
CARP0087-001 05/01/2016			

BURNETT (W. of Hwy 48), PIERCE (W. of Hwy 29), POLK (W. of Hwys 35, 48 & 65), AND ST. CROIX (W. of Hwy 65) COUNTIES

	Rates	Fringes
Carpenter & Piledrivermen	\$ 36.85	18.39
CARP0252-002 06/01/2016		

ADAMS, BARRON, BAYFIELD (Eastern 2/3), BROWN, BUFFALO, BURNETT (E. of Hwy 48), CALUMET, CHIPPEWA, CLARK, COLUMBIA, CRAWFORD, DANE, DODGE, DOOR, DUNN, EAU CLAIRE, FLORENCE (except area bordering Michigan State Line), FOND DU LAC, FOREST, GRANT, GREEN, GREEN LAKE, IOWA, IRON, JACKSON, JEFFERSON, JUNEAU, KEWAUNEE, LA CROSSE, LAFAYETTE, LANGLADE, LINCOLN, MANITOWOC, MARATHON, MARINETTE (except N.E. corner), MARQUETTE, MENOMINEE, MONROE, OCONTO, ONEIDA, OUTAGAMIE, PEPIN, PIERCE (E.

of Hwys 29 & 65), POLK (E. of Hwys 35, 48 & 65), PORTAGE, PRICE, RICHLAND, ROCK, RUSK, SAUK, SAWYER, SHAWANO, SHEBOYGAN, ST CROIX (E. of Hwy 65), TAYLOR, TREMPEALEAU, VERNON, VILAS, WALWORTH, WASHBURN, WAUPACA, WAUSHARA, WINNEBAGO, AND WOOD COUNTIES

	Rates	Fringes	
CARPENTER			
CARPENTER	\$ 33.56	18.00	
MILLWRIGHT	\$ 35.08	18.35	
PILEDRIVER	\$ 34.12	18.00	
CARP0252-010 06/01/2016			

## ASHLAND COUNTY

F	Rates	Fringes
Carpenters		
Carpenter\$	33.56	18.00
Millwright\$	35.08	18.35
Pile Driver\$	34.12	18.00

CARP0264-003 06/01/2016

KENOSHA, MILWAUKEE, OZAUKEE, RACINE, WAUKESHA, AND WASHINGTON COUNTIES

	Rates	Fringes
CARPENTER	\$ 35.78	22.11
CARP0361-004 05/01/2018		

BAYFIELD (West of Hwy 63) AND DOUGLAS COUNTIES

	Rates	Fringes
CARPENTER	\$ 36.15	20.43
CARRARA 001 06 /01 /2016		

CARP2337-001 06/01/2016

ZONE A: MILWAUKEE, OZAUKEE, WAUKESHA AND WASHINGTON

ZONE B: KENOSHA & RACINE

	Rates	Fringes
PILEDRIVERMAN  Zone A Zone B		22.69 22.69
CARP2337-003 06/01/2019		
	Rates	Fringes
MILLWRIGHT  Zone A Zone B		21.53 21.53
ZONE DEFINITIONS		
ZONE A: MILWAUKEE, OZAUKEE, WAL	KESHA AND WASHING	GTON COUNTIES

ELEC0014-002 06/14/2020

ZONE B: KENOSHA & RACINE COUNTIES

ASHLAND, BARRON, BAYFIELD, BUFFALO, BURNETT, CHIPPEWA, CLARK (except Maryville, Colby, Unity, Sherman, Fremont, Lynn & Sherwood), CRAWFORD, DUNN, EAU CLAIRE, GRANT, IRON, JACKSON, LA CROSSE, MONROE, PEPIN, PIERCE, POLK, PRICE, RICHLAND, RUSK, ST CROIX, SAWYER, TAYLOR, TREMPEALEAU, VERNON, AND WASHBURN COUNTIES

	Rates	Fringes
Electricians:	\$ 35.98	20.98
ELEC0014-007 07/05/2020		

REMAINING COUNTIES

F	Rates	Fringes
Teledata System Installer		
<pre>Installer/Technician\$</pre>	27.75	15.14

Low voltage construction, installation, maintenance and removal of teledata facilities (voice, data, and video) including outside plant, telephone and data inside wire, interconnect, terminal equipment, central offices, PABX, fiber optic cable and equipment, micro waves, V-SAT, bypass, CATV, WAN (wide area networks), LAN (local area

networks), and ISDN (integrated systems digital network). ELEC0127-002 06/01/2020 KENOSHA COUNTY Rates Fringes Electricians:.....\$ 41.62 30%+12.70 \_\_\_\_\_\_ ELEC0158-002 06/01/2020 BROWN, DOOR, KEWAUNEE, MANITOWOC (except Schleswig), MARINETTE(Wausuakee and area South thereof), OCONTO, MENOMINEE (East of a ine 6 miles West of the West boundary of Oconto County), SHAWANO (Except Area North of Townships of Aniwa and Hutchins) COUNTIES Rates Fringes ELECTRICIAN.....\$ 34.77 29.75%+10.26 ELEC0159-003 08/02/2020 COLUMBIA, DANE, DODGE (Area West of Hwy 26, except Chester and Emmet Townships), GREEN, LAKE (except Townships of Berlin, Seneca, and St. Marie), IOWA, MARQUETTE (except Townships of Neshkoka, Crystal Lake, Newton, and Springfield), and SAUK COUNTIES Rates Fringes ELECTRICIAN.....\$ 41.86 ELEC0219-004 06/01/2019 FLORENCE COUNTY (Townships of Aurora, Commonwealth, Fern, Florence and Homestead) AND MARINETTE COUNTY (Township of Niagara) Rates Fringes Electricians: Electrical contracts over 21.80 \$180,000.....\$ 33.94 Electrical contracts under

\$180,000	.\$ 31.75	21.73	
ELEC0242-005 05/31/2020			
DOUGLAS COUNTY			
	Rates	Fringes	
Electricians:	.\$ 39.77	28.11	
ADAMS, CLARK (Colby, Freemont, Lynn, Mayville, Sherman, Sherwood, Unity), FOREST, JUNEAU, LANGLADE, LINCOLN, MARATHON, MARINETTE (Beecher, Dunbar, Goodman & Pembine), MENOMINEE (Area West of a line 6 miles West of the West boundary of Oconto County), ONEIDA, PORTAGE, SHAWANO (Aniwa and Hutchins), VILAS AND WOOD COUNTIES			
	Rates	Fringes	
Electricians:	.\$ 34.85	26%+11.20	
ELEC0430-002 06/01/2020			
RACINE COUNTY (Except Burlington	Township)		
	Rates	Fringes	
Electricians:	.\$ 41.86	22.66	
ELEC0494-005 06/01/2020			
MILWAUKEE, OZAUKEE, WASHINGTON,	AND WAUKESHA COL	JNTIES	
	Rates	Fringes	
Electricians:	.\$ 42.84	25.54	
ELEC0494-006 06/01/2020			
CALUMET (Township of New Holstein), DODGE (East of Hwy 26 including Chester Township), FOND DU LAC, MANITOWOC (Schleswig), and SHEBOYGAN COUNTIES			
	Rates	Fringes	
Electricians:	.\$ 36.32	22.51	

#### ELEC0494-013 06/07/2020

DODGE (East of Hwy 26 including Chester Twp, excluding Emmet Twp), FOND DU LAC (Except Waupuin), MILWAUKEE, OZAUKEE, MANITOWOC (Schleswig), WASHINGTON, AND WAUKESHA COUNTIES

	Rates	Fringes
Sound & Communications		
Installer	.\$ 21.46	18.52
Technician	.\$ 31.34	20.00

Installation, testing, maintenance, operation and servicing of all sound, intercom, telephone interconnect, closed circuit TV systems, radio systems, background music systems, language laboratories, electronic carillion, antenna distribution systems, clock and program systems and low-voltage systems such as visual nurse call, audio/visual nurse call systems, doctors entrance register systems. Includes all wire and cable carrying audio, visual, data, light and radio frequency signals. Includes the installation of conduit, wiremold, or raceways in existing structures that have been occupied for six months or more where required for the protection of the wire or cable, but does not mean a complete conduit or raceway system. work covered does not include the installation of conduit, wiremold or any raceways in any new construction, or the installation of power supply outlets by means of which external electric power is supplied to any of the foregoing equipment or products

-----

#### \* ELEC0577-003 06/01/2020

CALUMET (except Township of New Holstein), GREEN LAKE (N. part including Townships of Berlin, St Marie, and Seneca), MARQUETTE (N. part including Townships of Crystal Lake, Neshkoro, Newton, and Springfield), OUTAGAMIE, WAUPACA, WAUSHARA, AND WINNEBAGO COUNTIES

	Rates	Fringes
Electricians:	.\$ 34.23	29.50%+10.00
ELEC0890-003 06/01/2020		

DODGE (Emmet Township only), GREEN, JEFFERSON, LAFAYETTE,

	Rates	Fringes
Electricians:	.\$ 37.41	25.95%+11.11
ELEC0953-001 06/02/2019		
	Rates	Fringes
Line Construction:  (1) Lineman	.\$ 42.78 .\$ 38.02 .\$ 33.27	21.43 19.80 18.40 16.88 16.11
(6) Groundsman		14.60

ENGI0139-001 06/01/2020

KENOSHA, MILWAUKEE, OZAUKEE, RACINE, WASHINGTON, AND WAUKESHA COUNTIES

	Rates	Fringes
Power Equipment Operator		
Group 1	\$ 47.66	23.15
Group 2	\$ 47.16	23.15
Group 3	\$ 46.66	23.15
Group 4	\$ 45.97	23.15
Group 5		23.15
Group 6		23.15

#### HAZARDOUS WASTE PREMIUMS:

EPA Level ""A"" Protection: \$3.00 per hour EPA Level ""B"" Protection: \$2.00 per hour EPA Level ""C"" Protection: \$1.00 per hour

## POWER EQUIPMENT OPERATORS CLASSIFICATIONS

GROUP 1: Cranes, Tower Cranes, Pedestal Tower Cranes and Derricks with or w/o attachments with a lifting capacity of over 100 tons; or Cranes, Tower Cranes, Pedestal Tower Cranes and Derricks with boom, leads, and/or jib lengths measuring 176 feet or longer; Self-Erecting Tower Cranes over 4000 lbs lifting capacity; All Cranes with Boom Dollies; Boring Machines (directional); Master Mechanic.

- \$0.50 additional per hour per 100 tons or 100 ft of boom over 200 ft or lifting capacity of crane over 200 tons to a maximum of 300 tons or 300 ft. Thereafter an increase of \$0.01 per ft or ton, whichever is greater.
- GROUP 2: Cranes, Tower Cranes, Pedestal Tower Cranes and Derricks with or without attachments with a lifting capacity of 100 tons or less; or Cranes, Tower Cranes Portable Tower Cranes, Pedestal Tower Cranes and Derricks with boom, leadsand/or jib lengths measuring 175 feet or less; Backhoes (excavators) 130,000 lbs and over; Caisson Rigs; Pile Drivers; Boring Machines (vertical or horizontal), Versi-Lift, Tri-Lift, Gantry 20,000 lbs & over.
- GROUP 3: Backhoe (excavator) under 130,000 lbs;Self-erecting Tower Crane 4000 lbs & under lifting capacity;Traveling Crane (bridge type); Skid Rigs; Dredge Operator; Mechanic; Concrete Paver (over 27E); Concrete Spreader and Distributor; Forklift/ Telehandler (machinery- moving / steel erection); Hydro Blaster, 10,000 psi and over
- GROUP 4: Material Hoists; Stack Hoists; Hydraulic Backhoe (tractor or truck mounted); Hydraulic Crane, 5 tons or under (tractor or truck mounted); Hoist (tuggers 5 tons & over); Hydro-Excavators/Daylighters; Concrete Pumps Rotec type Conveyors; Tractor/Bulldozer/End Loader (over 40 hp); Motor Patrol; Scraper Operator; Sideboom; Straddle Carrier; Welder; Bituminous Plant and Paver Operator; Roller over 5 tons; Rail Leveling Machine (Railroad); Tie Placer; Tie Extractor; Tie Tamper; Stone Leveler; Rotary Drill Operator and Blaster; Percussion Drill Operator; Air Track Drill and/or Hammers; Gantrys (under 20,000 lbs); Tencher (wheel type or chain type having 8 inch or larger bucket); Milling Machine; Off-Road Material Haulers.
- GROUP 5: Backfiller; Concrete Auto Breaker (large); Concrete Finishing Machines (road type); Rubber Tired Roller; Concrete Batch Hopper; Concrete Conveyor Systems; Grout Pumps; Concrete Mixers (14S or over); Screw Type Pumps and Gypsum Pumps; Tractor, Bulldozer, End Loader (under 40 hp); Trencher (chain type, bucket under 8 inch); Industrial Locomotives; Rollers under 5 tons; Stump Grinder/Chipper (Large); Timber Equipment; Firemen (pile drivers and derricks); Personnel Hoist, Telehandler over 8000 lbs; Robotic Tool Carrier with or without attachments
- GROUP 6: Tampers Compactors (riding type); Assistant Engineer; A-Frames and Winch Trucks; Concrete Auto Breaker; Hydrohammers (small); Brooms and Sweepers; Hoist (tuggers under 5 tons); Boats (Tug, Safety, Work Barges, Launch);

Shouldering Machine Operator; Prestress Machines; Screed Operator; Stone Crushers and Screening Plants; Screed Operators (milling machine), Farm or Industrial Tractor Mounted Equipment; Post Hole Digger; Fireman (asphalt plants); Air Compressors over 400 CFM; Generators, over 150 KW; Augers (vertical and horizontal); Air, Electric, Hydraulic Jacks (slipform); Skid Steer Loaders (with or without attachments); Boiler Operators (temporary heat); Refrigeration Plant/Freeze Machines; Power Pack Vibratory/Ultra Sound Drivers and Extractors; Welding Machines; Heaters (mechanical); Pumps; Winches (small electric); Oiler and Greaser; Rotary Drill Tender; Conveyor; Forklifts/Telehandler 8000 lbs & under; Elevators: Automatic Hoists; Pumps (well points); Combination Small Equipment Operators

-----

ENGI0139-003 06/01/2020

#### **REMAINING COUNTIES**

	Rates	Fringes
Power Equipment Operator		
Group 1	\$ 42.92	23.15
Group 2	\$ 41.67	23.15
Group 3	\$ 39.97	23.15
Group 4	\$ 39.44	23.15
Group 5	\$ 37.37	23.15
Group 6	\$ 35.84	23.15

#### HAZARDOUS WASTE PREMIUMS:

EPA Level ""A"" Protection: \$3.00 per hour EPA Level ""B"" Protection: \$2.00 per hour EPA Level ""C"" Protection: \$1.00 per hour

#### POWER EQUIPMENT OPERATORS CLASSIFICATIONS

GROUP 1: Cranes, Tower Cranes and Derricks with or without attachments with a lifting capacity of over 100 tons; Cranes, Tower Cranes, and Derricks with boom, leads and/or jib lengths 176 ft or longer.

GROUP 2: Backhoes (Excavators) weighing 130,00 lbs and over; Cranes, Tower Cranes and Derricks with or without attachments with a lifting capacity of 100 tons or less; Cranes, Tower Cranes, and Derricks with boom, leads, and/or jib lengths 175 ft or less; Caisson Rigs; Pile Driver

GROUP 3: Backhoes (Excavators) weighing under 130,000 lbs;

Travelling Crane (bridge type); Milling Machine; Concrete Paver over 27 E; Concrete Spreader and Distributor; Concrete Laser Screed; Concrete Grinder and Planing Machine; Slipform Curb and Gutter Machine; Boring Machine (Directional); Dredge Operator; Skid Rigs; over 46 meter Concrete Pump.

GROUP 4: Hydraulic Backhoe (tractor or truck mounted); Hydraulic Crane, 10 tons or less; Tractor, Bulldozer, or End Loader (over 40 hp); Motor Patrol; Scraper Operator; Bituminous Plant and Paver Operator; Screed-Milling Machine; Roller over 5 tons; Concrete pumps 46 meter and under; Grout Pumps; Rotec type machine; Hydro Blaster, 10,000 psi and over; Rotary Drill Operator; Percussion Drilling Machine; Air Track Drill with or without integral hammer; Blaster; Boring Machine (vertical or horizontal); Side Boom; Trencher, wheel type or chain type having 8 inch or larger bucket; Rail Leveling Machine (Railroad); Tie Placer; Tie Extractor; Tie Tamper; Stone Leveler; Straddle Carrier; Material Hoists; Stack Hoist; Man Hoists; Mechanic and Welder; Off Road Material Haulers.

GROUP 5: Tractor, Bulldozer, or Endloader (under 40 hp); Tampers -Compactors, riding type; Stump Chipper, large; Roller, Rubber Tire; Backfiller; Trencher, chain type (bucket under 8 inch); Concrete Auto Breaker, large; Concrete Finishing Machine (road type); Concrete Batch Hopper; Concrete Conveyor Systems; Concrete Mixers, 14S or over; Pumps, Screw Type and Gypsum); Hydrohammers, small; Brooms and Sweeeprs; Lift Slab Machine; Roller under 5 tons; Industrial Locomotives; Fireman (Pile Drivers and Derricks); Pumps (well points); Hoists, automatic; A-Frames and Winch Trucks; Hoists (tuggers); Boats (Tug, Safety, Work Barges and Launches); Assistant Engineer

GROUP 6: Shouldering Machine Operator; Farm or Industrial Tractor mounted equipment; Post Hole Digger; Auger (vertical and horizontal); Skid Steer Loader with or without attachments; Robotic Tool Carrier with or without attachments; Power Pack Vibratory/Ultra Sound Driver and Extractor; Fireman (Asphalt Plants); Screed Operator; Stone Crushers and Screening Plants; Air, Electric, Hydraulic Jacks (Slip Form); Prestress Machines; Air Compressor, 400 CFM or over; Refrigeration Plant/Freese Machine; Boiler Operators (temporary heat); Forklifts; Welding Machines; Generators; Pumps over 3""; Heaters, Mechanical; Combination small equipment operator; Winches, small electric; Oiler; Greaser; Rotary Drill Tender; Conveyor; Elevator Operator

-----

#### IRON0008-002 06/01/2020

BROWN, CALUMET, DOOR, FOND DU LAC, KEWAUNEE, MANITOWOC, MARINETTE, OCONTO, OUTAGAMI, SHAWANO, SHEBOYGAN, AND WINNEBAGO COUNTIES:

	Rates	Fringes
IRONWORKER	.\$ 37.31	27.62
Paid Holidays: New Year's Day, Day, Thanksgiving Day & Christ		uly 4th, Labor
IRON0008-003 06/01/2020		
KENOSHA, MILWAUKEE, OZAUKEE, RAC WASHINGTON. AND WAUKESHA COUNTIE	•	.E. 2/3),

WASHINGTON, AND WAUKESHA COUNTIES

ı	Rates	Fringes
IRONWORKER\$	39.11	27.87

Paid Holidays: New Year's Day, Memorial Day, July 4th, Labor Day, Thanksgiving Day & Christmas Day.

IRON0383-001 06/01/2020

ADAMS, COLUMBIA, CRAWFORD, DANE, DODGE, FLORENCE, FOREST, GRANT, GREENE, (Excluding S.E. tip), GREEN LAKE, IOWA, JEFFERSON, JUNEAU, LA CROSSE, LAFAYETTE, LANGLADE, MARATHON, MARQUETTE, MENOMINEE, MONROE, PORTAGE, RICHLAND, ROCK (Northern area, vicinity of Edgerton and Milton), SAUK, VERNON, WAUPACA, WAUSHARA, AND WOOD COUNTIES

	Rates	Fringes
IRONWORKER	.\$ 37.10	27.06
IRON0512-008 06/03/2019		

BARRON, BUFFALO, CHIPPEWA, CLARK, DUNN, EAU CLAIRE, JACKSON, PEPIN, PIERCE, POLK, RUSK, ST CROIX, TAYLOR, AND TREMPEALEAU COUNTIES

	Rates	Fringes
IRONWORKER	\$ 37.60	29.40

IRON0512-021 06/03/2019

ASHLAND, BAYFIELD, BURNETT, DOUGLAS, IRON, LINCOLN, ONEIDA, PRICE, SAWYER, VILAS AND WASHBURN COUNTIES

	Rates	Fringes
IRONWORKER	.\$ 33.19	29.40
LAB00113-002 06/01/2020		

#### MILWAUKEE AND WAUKESHA COUNTIES

	I	Rates	Fringes
LABORER			
Group	1\$	30.05	22.26
Group	2\$	30.20	22.26
Group	3\$	30.40	22.26
Group	4\$	30.55	22.26
Group	5\$	30.70	22.26
Group	6\$	26.54	22.26

#### LABORERS CLASSIFICATIONS

GROUP 1: General Laborer; Tree Trimmer; Conduit Layer; Demolition and Wrecking Laborer; Guard Rail, Fence, and Bridge Builder; Landscaper; Multiplate Culvert Assembler; Stone Handler; Bituminous Worker (Shoveler, Loader, and Utility Man); Batch Truck Dumper or Cement Handler; Bituminous Worker (Dumper, Ironer, Smoother, and Tamper); Concrete Handler

GROUP 2: Air Tool Operator; Joint Sawer and Filler (Pavement); Vibrator or Tamper Operator (Mechanical Hand Operated); Chain Saw Operator; Demolition Burning Torch Laborer

GROUP 3: Bituminous Worker (Raker and Luteman); Formsetter (Curb, Sidewalk, and Pavement); Strike Off Man

GROUP 4: Line and Grade Specialist

GROUP 5: Blaster and Powderman

GROUP 6: Flagperson; traffic control person

-----

LAB00113-003 06/01/2020

#### OZAUKEE AND WASHINGTON COUNTIES

	ı	Rates	Fringes
LABORER			
Group	1\$	29.30	22.26
Group	2\$	29.40	22.26
Group	3\$	29.45	22.26
Group	4\$	29.65	22.26
Group	5\$	29.50	22.26
Group	6\$	26.39	22.26

#### LABORERS CLASSIFICATIONS

GROUP 1: General Laborer; Tree Trimmer; Conduit Layer; Demolition and Wrecking Laborer; Guard Rail, Fence, and Bridge Builder; Landscaper; Multiplate Culvert Assembler; Stone Handler; Bituminous Worker (Shoveler, Loader, and Utility Man); Batch Truck Dumper or Cement Handler; Bituminous Worker (Dumper, Ironer, Smoother, and Tamper); Concrete Handler

GROUP 2: Air Tool Operator; Joint Sawer and Filler (Pavement); Vibrator or Tamper Operator (Mechanical Hand Operated);

GROUP 3: Bituminous Worker (Raker and Luteman); Formsetter (Curb, Sidewalk, and Pavement); Strike Off Man

GROUP 4: Line and Grade Specialist

GROUP 5: Blaster; powderman

GROUP 6: Flagperson and Traffic Control Person

-----

LAB00113-011 06/01/2020

#### KENOSHA AND RACINE COUNTIES

	F	Rates	Fringes
LABORER			
Group	1\$	29.11	22.26
Group	2\$	29.26	22.26

Group 3\$ 29.46	22.26
Group 4\$ 29.43	22.26
Group 5\$ 29.76	22.26
Group 6\$ 26.25	22.26

#### LABORERS CLASSIFICATIONS:

GROUP 1: General laborer; Tree Trimmer; Conduit Layer; Demolition and Wrecking Laborer; Guard Rail, Fence, and Bridge Builder; Landscaper; Multiplate Culvert Assembler; Stone Handler; Bituminous Worker (Shoveler, Loader, and Utility Man); Batch Truck Dumper or Cement Handler; Bituminous worker (Dumper, Ironer, Smoother, and Tamper); Concrete Handler

GROUP 2: Air Tool Operator; Joint Sawer and Filler (Pavement); Vibrator or Tamper Operator (Mechanical Hand Operated); Chain Saw Operator; Demolition Burning Torch Laborer

GROUP 3: Bituminous Worker (Raker and Luteman); Formsetter (Curb, Sidewalk, and Pavement); Strike Off Man

GROUP 4: Line and Grade Specialist

GROUP 5: Blaster and Powderman

GROUP 6: Flagman; traffic control person

\_\_\_\_\_

#### LAB00140-002 06/01/2020

ADAMS, ASHLAND, BARRON, BAYFIELD, BROWN, BUFFALO, BURNETT, CALUMET, CHIPPEWA, CLARK, COLUMBIA, CRAWFORD, DODGE, DOOR, DOUGLAS, DUNN, EAU CLAIRE, FLORENCE, FOND DU LAC, FOREST, GRANT, GREEN, GREEN LAKE, IRON, JACKSON, JUNEAU, IOWA, JEFFERSON, KEWAUNEE, LA CROSSE, LAFAYETTE, LANGLADE, LINCOLN, MANITOWOC, MARATHON, MARINETTE, MARQUETTE, MENOMINEE, MONROE, OCONTO, ONEIDA, OUTAGAMIE, PEPIN, PIERCE, POLK, PORTAGE, PRICE, RICHLAND, ROCK, RUSK, SAUK, SAWYER, SHAWANO, SHEBOYGAN, ST. CROIX, TAYLOR, TREMPEALEAU, VERNON, VILLAS, WALWORTH, WASHBURN, WAUPACA, WAUSHARA, WINNEBAGO, AND WOOD COUNTIES

	Rates	Fringes
LABORER		
Group	1\$ 33.72	17.95
Group	2\$ 33.82	17.95
Group	3\$ 33.87	7 17.95

Group 4	\$ 34.07	17.95
Group 5	\$ 33.92	17.95
Group 6	\$ 30.35	17.95

#### LABORER CLASSIFICATIONS

GROUP 1: General Laborer; Tree Trimmer; Conduit Layer; Demolition and Wrecking Laborer; Guard Rail, Fence, and Bridge Builder; Landscaper; Multiplate Culvert Assembler; Stone Handler; Bitminous Worker (Shoveler, Loader, and Utility Man); Batch Truck Dumper or Cement Handler; Bituminous Worker (Dumper, Ironer, Smoother and Tamper); Concrete Handler

GROUP 2: Air Tool Operator; Joint Sawer and Filler (Pavement); Vibrator or Tamper Operator (Mechanical Hand Operated); Chain Saw Operator, Demolition Burning Torch Laborer

GROUP 3: Bituminous Worker (Raker and Luteman); Formsetter (Curb, Sidewalk and Pavement); Strike Off Man

GROUP 4: Line and Grade Secialist

GROUP 5: Blaster; powderman

GROUP 6: Flagperson; Traffic Control

LAB00464-003 06/01/2020

DANE COUNTY

		Rates	Fringes
LABORER			
Group	1	\$ 34.00	17.95
Group	2	\$ 34.10	17.95
Group	3	\$ 34.15	17.95
Group	4	\$ 34.35	17.95
Group	5	\$ 34.20	17.95
Group	6	\$ 30.35	17.95

#### LABORERS CLASSIFICATIONS:

GROUP 1: General Laborer; Tree Trimmer; Conduit Layer; Demolition and Wrecking Laborer; Guard Rail, Fence, and Bridge Builder; Landscaper; Multiplate Culvert Assembler; Stone Handler; Bituminous Worker (Shoveler, Loader, and Utility Man); Batch Truck Dumper or Cement Handler;

Bituminious Worker (Dumper, Ironer, Smoother, and Tamper); Concrete Handler

GROUP 2: Air Tool Operator; Joint Sawer and Filler (Pavement); Vibrator or Tamper Operator (Mechanical Hand Operated); Chain Saw Operator; Demolition Burning Torch Laborer

GROUP 3: Bituminous Worker (Raker and Luteman); Formsetter (Curb, Sidewalk, and Pavement); Strike Off Man

GROUP 4: Line and Grade Specialist

GROUP 5: Blaster; Powderman

GROUP 6: Flagperson and Traffic Control Person

\_\_\_\_\_

PAIN0106-008 05/01/2017

ASHLAND, BAYFIELD, BURNETT, AND DOUGLAS COUNTIES

	Ī	Rates	Fringes
Painters:			
New:			
Brush,	Roller\$	30.33	17.27
Spray,	Sandblast, Steel\$	30.93	17.27
Repaint	:		
Brush,	Roller\$	28.83	17.27
Spray,	Sandblast, Steel $\$$	29.43	17.27

PAIN0108-002 06/01/2019

RACINE COUNTY

R	lates	Fringes
Painters:		
Brush, Roller\$	36.08	20.36
Spray & Sandblast\$	37.08	20.36

PAIN0259-002 05/01/2008

BARRON, CHIPPEWA, DUNN, EAU CLAIRE, PEPIN, PIERCE, POLK, RUSK, SAWYER, ST. CROIX, AND WASHBURN COUNTIES

Rates Fringes

PAINTER	•	
PAIN0259-004 05/01/2015		
BUFFALO, CRAWFORD, JACKSON, L VERNON COUNTIES	A CROSSE, MONR	OE, TREMPEALEAU, AND
	Rates	Fringes
PAINTER	•	12.45
PAIN0781-002 06/01/2019		
JEFFERSON, MILWAUKEE, OZAUKEE	, WASHINGTON,	AND WAUKESHA COUNTIES
	Rates	Fringes
Painters: Bridge Brush Spray & Sandblast	\$ 32.95	23.86 23.86 23.86
PAIN0802-002 06/01/2019		
COLUMBIA, DANE, DODGE, GRANT, ROCK, AND SAUK COUNTIES	GREEN, IOWA,	LAFAYETTE, RICHLAND,
	Rates	Fringes
PAINTER Brush	\$ 30.93	18.44
PREMIUM PAY: Structural Steel, Spray, Br hour.	idges = \$1.0	0 additional per
PAIN0802-003 06/01/2019		
ADAMS, BROWN, CALUMET, CLARK,	DOOR, FOND DU	LAC, FOREST, GREEN

LAKE, IRON, JUNEAU, KEWAUNEE, LANGLADE, LINCOLN, MANITOWOC, MARATHON, MARINETTE, MARQUETTE, MENOMINEE, OCONTO, ONEIDA, OUTAGAMIE, PORTAGE, PRICE, SHAWANO, SHEBOYGAN, TAYLOR, VILAS, WAUSHARA, WAUPACA, WINNEBAGO, AND WOOD COUNTIES

Rates

Fringes

PAINTER		\$ 30.93	18.58
PAIN0934-001	06/01/2017		

#### KENOSHA AND WALWORTH COUNTIES

	Rates	Fringes	
Painters:			
Brush	\$ 33.74	18.95	
Spray	\$ 34.74	18.95	
Structural Steel	\$ 33.89	18.95	

#### PAIN1011-002 06/02/2019

#### FLORENCE COUNTY

	Rates	Fringes	
Painters:	\$ 25.76	13.33	
DI ASAEGO 010 06/01/2017			-

#### PLAS0599-010 06/01/2017

Rates	Fringes
\$ 39.46	17.17
\$ 35.07	19.75
\$ 35.61	19.40
\$ 34.70	20.51
\$ 36.27	18.73
\$ 32.02	22.99
	\$ 39.46 \$ 35.07 \$ 35.61 \$ 34.70 \$ 36.27

#### AREA DESCRIPTIONS

AREA 1: BAYFIELD, DOUGLAS, PRICE, SAWYER, AND WASHBURN COUNTIES

AREA 2: ADAMS, ASHLAND, BARRON, BROWN, BURNETT, CALUMET, CHIPPEWA, CLARK, COLUMBIA, DODGE, DOOR, DUNN, FLORENCE, FOND DU LAC, FOREST, GREEN LAKE, IRON, JEFFERSON, KEWAUNEE, LANGLADE, LINCOLN, MANITOWOC, MARATHON, MARINETTE, MARQUETTE, MENOMINEE, OCONTO, ONEIDA, OUTAGAMIE, POLK, PORTAGE, RUSK, ST CROIX, SAUK, SHAWANO, SHEBOYGAN, TAYLOR, VILAS, WALWORTH, WAUPACA, WAUSHARA, WINNEBAGO, AND WOOD COUNTIES

AREA 3: BUFFALO, CRAWFORD, EAU CLAIRE, JACKSON, JUNEAU, LA CROSSE MONROE, PEPIN, PIERCE, RICHLAND, TREMPEALEAU, AND VERNON COUNTIES

AREA 4: MILWAUKEE, OZAUKEE, WAS	HINGTON, AND I	WAUKESHA COUNTIES
AREA 5: DANE, GRANT, GREEN, IO COUNTIES	WA, LAFAYETTE	, AND ROCK
AREA 6: KENOSHA AND RACINE COUNT	IES	
PLUM0011-003 05/07/2018		
ASHLAND, BAYFIELD, BURNETT, DOUGL COUNTIES	AS, IRON, SAW	YER, AND WASHBURN
	Rates	Fringes
PLUMBER	\$ 40.63	20.72
PLUM0075-002 06/01/2016		
MILWAUKEE, OZAUKEE, WASHINGTON, A	ND WAUKESHA C	OUNTIES
	Rates	Fringes
PLUMBER	•	21.47
PLUM0075-004 06/01/2016		
DODGE (Watertown), GREEN, JEFFERS COUNTIES	ON, LAFAYETTE	, AND ROCK
	Rates	Fringes
PLUMBER		21.47
PLUM0075-009 06/01/2016		
COLUMBIA, DANE, IOWA, MARQUETTE,	RICHLAND AND	SAUK COUNTIES
	Rates	Fringes
PLUMBER	\$ 38.82	20.12
PLUM0111-007 05/28/2018		
MARINETTE COUNTY (Niagara only)		

	Rates	Fringes
PLUMBER/PIPEFITTER		24.48
PLUM0118-002 06/01/2020		
KENOSHA, RACINE, AND WALWORTH CO	OUNTIES	
	Rates	Fringes
Plumber and Steamfitter	\$ 43.95	24.35
PLUM0400-003 06/04/2018		
ADAMS, BROWN, CALUMET, DODGE (ex- LAC, GREEN LAKE, KEWAUNEE, MANITO Niagara), MENOMINEE, OCONTO, OU WAUPACA, WAUSHARA, AND WINNEBAGO	OWOC, MARINETTE TAGAMIE, SHAWANO	(except
	Rates	Fringes
PLUMBER/PIPEFITTER	\$ 36.74	19.06
PLUM0434-002 05/31/2020		
BARON, BUFFALO, CHIPPEWA, CLARK FLORENCE, FOREST, GRANT, JACKSON LINCOLN, MARATHON, MONROE, ONEIN PORTAGE, PRICE, RUSK, ST. CROIX VILAS, AND WOOD COUNTIES	N, JUNEAU, LA CR DA, PEPIN, PIERC	OSSE, LANGLADE, E, POLK,
	Rates	Fringes
PIPEFITTER	\$ 42.70	20.47
* PLUM0601-003 06/01/2020		
DODGE (Watertown), GREEN, JEFFE OZAUKEE, ROCK, WASHINGTON AND W	-	<del>-</del>
	Rates	Fringes
PIPEFITTER	\$ 47.79	26.57
* PLUM0601-009 06/01/2020		

COLUMBIA, DANE, IOWA, MARQUETTE, RICHLAND AND SAUK COUNTIES

	Rates	Fringes	
PIPEFITTER	\$ 49.53	24.82	
TEAM0039-002 06/01/2020			
	Rates	Fringes	
TRUCK DRIVER  1 & 2 Axle Trucks  3 or more axles; Euclids or Dumptor, Articulated	\$ 31.07	22.94	
Truck, Mechanic	\$ 31.22	22.94	
SUWI2011-001 11/16/2011			
	Rates	Fringes	
WELL DRILLER	•		
WELDERS - Receive rate prescribed for craft performing			

\_\_\_\_\_

operation to which welding is incidental.

Note: Executive Order (EO) 13706, Establishing Paid Sick Leave for Federal Contractors applies to all contracts subject to the Davis-Bacon Act for which the contract is awarded (and any solicitation was issued) on or after January 1, 2017. If this contract is covered by the EO, the contractor must provide employees with 1 hour of paid sick leave for every 30 hours they work, up to 56 hours of paid sick leave each year. Employees must be permitted to use paid sick leave for their own illness, injury or other health-related needs, including preventive care; to assist a family member (or person who is like family to the employee) who is ill, injured, or has other health-related needs, including preventive care; or for reasons resulting from, or to assist a family member (or person who is like family to the employee) who is a victim of, domestic violence, sexual assault, or stalking. Additional information on contractor requirements and worker protections under the EO is available at www.dol.gov/whd/govcontracts.

Unlisted classifications needed for work not included within the scope of the classifications listed may be added after award only as provided in the labor standards contract clauses (29CFR 5.5 (a) (1) (ii)).

.....

The body of each wage determination lists the classification and wage rates that have been found to be prevailing for the cited type(s) of construction in the area covered by the wage determination. The classifications are listed in alphabetical order of ""identifiers"" that indicate whether the particular rate is a union rate (current union negotiated rate for local), a survey rate (weighted average rate) or a union average rate (weighted union average rate).

#### Union Rate Identifiers

A four letter classification abbreviation identifier enclosed in dotted lines beginning with characters other than ""SU"" or ""UAVG"" denotes that the union classification and rate were prevailing for that classification in the survey. Example: PLUM0198-005 07/01/2014. PLUM is an abbreviation identifier of the union which prevailed in the survey for this classification, which in this example would be Plumbers. 0198 indicates the local union number or district council number where applicable, i.e., Plumbers Local 0198. The next number, 005 in the example, is an internal number used in processing the wage determination. 07/01/2014 is the effective date of the most current negotiated rate, which in this example is July 1, 2014.

Union prevailing wage rates are updated to reflect all rate changes in the collective bargaining agreement (CBA) governing this classification and rate.

# Survey Rate Identifiers

Classifications listed under the ""SU"" identifier indicate that no one rate prevailed for this classification in the survey and the published rate is derived by computing a weighted average rate based on all the rates reported in the survey for that classification. As this weighted average rate includes all rates reported in the survey, it may include both union and non-union rates. Example: SULA2012-007 5/13/2014. SU indicates the rates are survey rates based on a weighted average calculation of rates and are not majority rates. LA indicates the State of Louisiana. 2012 is the year of survey on which these classifications and rates are based. The next number, 007 in the example, is an internal number used in producing the wage determination. 5/13/2014 indicates the survey completion date for the classifications and rates under that identifier.

Survey wage rates are not updated and remain in effect until a new survey is conducted.

Union Average Rate Identifiers

Classification(s) listed under the UAVG identifier indicate that no single majority rate prevailed for those classifications; however, 100% of the data reported for the classifications was union data. EXAMPLE: UAVG-OH-0010 08/29/2014. UAVG indicates that the rate is a weighted union average rate. OH indicates the state. The next number, 0010 in the example, is an internal number used in producing the wage determination. 08/29/2014 indicates the survey completion date for the classifications and rates under that identifier.

A UAVG rate will be updated once a year, usually in January of each year, to reflect a weighted average of the current negotiated/CBA rate of the union locals from which the rate is based.

-----

#### WAGE DETERMINATION APPEALS PROCESS

- 1.) Has there been an initial decision in the matter? This can be:
- \* an existing published wage determination
- \* a survey underlying a wage determination
- \* a Wage and Hour Division letter setting forth a position on a wage determination matter
- \* a conformance (additional classification and rate) ruling

On survey related matters, initial contact, including requests for summaries of surveys, should be with the Wage and Hour Regional Office for the area in which the survey was conducted because those Regional Offices have responsibility for the Davis-Bacon survey program. If the response from this initial contact is not satisfactory, then the process described in 2.) and 3.) should be followed.

With regard to any other matter not yet ripe for the formal process described here, initial contact should be with the Branch of Construction Wage Determinations. Write to:

Branch of Construction Wage Determinations Wage and Hour Division U.S. Department of Labor

200 Constitution Avenue, N.W. Washington, DC 20210

2.) If the answer to the question in 1.) is yes, then an interested party (those affected by the action) can request review and reconsideration from the Wage and Hour Administrator (See 29 CFR Part 1.8 and 29 CFR Part 7). Write to:

Wage and Hour Administrator U.S. Department of Labor 200 Constitution Avenue, N.W. Washington, DC 20210

The request should be accompanied by a full statement of the interested party's position and by any information (wage payment data, project description, area practice material, etc.) that the requestor considers relevant to the issue.

3.) If the decision of the Administrator is not favorable, an interested party may appeal directly to the Administrative Review Board (formerly the Wage Appeals Board). Write to:

Administrative Review Board U.S. Department of Labor 200 Constitution Avenue, N.W. Washington, DC 20210

4.) All decisions by the Administrative Review Board are final.

\_\_\_\_\_\_

END OF GENERAL DECISION

"



# **Wisconsin Department of Transportation**

December 14, 2020

# **Division of Transportation Systems Development**

Bureau of Project Development 4822 Madison Yards Way, 4<sup>th</sup> Floor South Madison, WI 53705

Telephone: (608) 266-1631 Facsimile (FAX): (608) 266-8459

#### NOTICE TO ALL CONTRACTORS:

Proposal #35: 1198-03-78, WISC 2021 105

C Superior, East Second Street 29<sup>th</sup> Avenue East – 53<sup>rd</sup> Avenue East

USH 2

**Douglas County** 

# Letting of January 12, 2021

This is Addendum No. 01, which provides for the following:

### **Schedule of Items:**

	Revised Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total	
460.0115.S	HMA Pavement Test Strips Volumetrics *	Each	1	0	1	

<sup>\*</sup> Note: The above listed bid item inadvertently shows as a pre-established bid price. This is in error. This addendum removes the pre-established bid price.

#### Schedule of Items

Attached, dated December 14, 2020, are the revised Schedule of Items Page 2.

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.


Sincerely,

Mike Coleman

Proposal Development Specialist Proposal Management Section

**END OF ADDENDUM** 







# Proposal Schedule of Items

Page 2 of 10

Federal ID(s): WISC 2021105

SECTION: 0001 Roadway Construction

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID  Description	Approximate Quantity and Units	Unit Price	Bid Amount
0032	310.0110 Base Aggregate Open-Graded	2,195.000 TON	·	
0034	415.0090 Concrete Pavement 9-Inch	443.000 SY		
0036	415.0410 Concrete Pavement Approach Slab	640.000 SY		·
0038	416.0160 Concrete Driveway 6-Inch	213.000 SY		
0040	416.0610 Drilled Tie Bars	7,386.000 EACH	<u></u>	
0042	416.0620 Drilled Dowel Bars	8,212.000 EACH	·	
0044	416.1710 Concrete Pavement Repair	3,083.000 SY	·	
0046	416.1720 Concrete Pavement Replacement	9,370.000 SY	·	
0048	455.0605 Tack Coat	7,145.000 GAL	·	
0050	460.0115.S HMA Pavement Test Strips Volumetrics	1.000 EACH	·	
0052	460.0120.S HMA Pavement Test Strips Density	1.000 EACH	·	
0054	460.2000 Incentive Density HMA Pavement	5,910.000 DOL	1.00000	5,910.00
0056	460.7645 HMA Pavement 5 HT 58-34 V	4,290.000 TON	·	
0058	460.8645 HMA Pavement 5 SMA 58-34 V	4,950.000 TON	·	
0060	465.0105 Asphaltic Surface	51.000 TON	·	
0062	465.0110 Asphaltic Surface Patching	505.000 TON		
0064	502.0100 Concrete Masonry Bridges	3.000 CY		



# **Wisconsin Department of Transportation**

January 7, 2021

# **Division of Transportation Systems Development**

Bureau of Project Development 4822 Madison Yards Way, 4<sup>th</sup> Floor South Madison, WI 53705

Telephone: (608) 266-1631 Facsimile (FAX): (608) 266-8459

#### **NOTICE TO ALL CONTRACTORS:**

Proposal #35: 1198-03-78, WISC 2021 105

C Superior East Second Street

29th Avenue East – 53rd Avenue East

USH 2

**Douglas County** 

# Letting of January 12, 2021

This is Addendum No. 02, which provides for the following:

## **Special Provisions:**

Revised Special Provisions			
Article No.	Description		
34	Adjusting Manhole Covers		

### Schedule of Items:

	Revised Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total	
649.0150	Temporary Marking Line Removable Tape 4-Inch	LF	32,324	1200	33,524	

# **Plan Sheets:**

Revised Plan Sheets				
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)			
153	Miscellaneous Quantities (Revised TC Marking Table)			

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist Proposal Management Section

# ADDENDUM NO. 02 1198-03-78 January 7, 2021

#### **Special Provisions**

#### 34. Adjusting Manhole Covers.

Replace paragraph two with the following:

Adjust manhole covers located in overlay areas after initial partial depth removal of concrete surface is done surrounding the casting. Once concrete surface has been removed, saw cut a square shape within the remaining concrete pavement around the manhole for removal of casting and surrounding pavement. Adjust the casting to finished grade, after the surface is completed. Utilize forms to create a square segment of concrete pavement, surrounding the manhole casting, filling in the void in underlying concrete pavement, and up to the level of the finished paving grade. Final asphalt paving shall be installed up to and around these raised concrete pads at each manhole. The department will measure and pay for the items of asphaltic pavement mixture, temporary cover plate, milling, and concrete pavement as Concrete Pavement Repair separately. Remove and replace all loose or deteriorated brick and mortar joints, mortar pipe connections that are not flush with the manhole, clean out the manhole, and apply a 1-inch mortar back plaster to the entire interior of the manhole at locations the plans show or as the engineer directs. Payment for cleaning, mortar, and replacing damaged rings or adding adjustment rings is incidental to the adjusting manhole cover.


#### Schedule of Items

Attached, dated January 7, 2021, are the revised Schedule of Items Page 6.

#### Plan Sheets

The following  $8\frac{1}{2}$  x 11-inch sheets are attached and made part of the plans for this proposal: Revised: 153.

**END OF ADDENDUM** 





01/07/2021 14:00:11



# Proposal Schedule of Items

Page 6 of 10

Federal ID(s): WISC 2021105

SECTION: 0001 Roadway Construction

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0164	646.1020 Marking Line Epoxy 4-Inch	57,125.000 LF		
0166	646.3020 Marking Line Epoxy 8-Inch	554.000 LF		
0168	646.5020 Marking Arrow Epoxy	19.000 EACH		
0170	646.6120 Marking Stop Line Epoxy 18-Inch	130.000 LF		
0172	646.7420 Marking Crosswalk Epoxy Transverse Line 6-Inch	1,306.000 LF		
0174	646.8020 Marking Corrugated Median Epoxy	120.000 SF		
0176	646.8220 Marking Island Nose Epoxy	7.000 EACH		
0178	646.9000 Marking Removal Line 4-Inch	2,880.000 LF		
0180	646.9100 Marking Removal Line 8-Inch	200.000 LF		<u> </u>
0182	646.9300 Marking Removal Special Marking	5.000 EACH	·	
0184	649.0150 Temporary Marking Line Removable Tape 4-Inch	33,524.000 LF		
0186	650.5500 Construction Staking Curb Gutter and Curb & Gutter	2,028.000 LF		
0188	650.8000 Construction Staking Resurfacing Reference	11,400.000 LF	·	
0190	650.9000 Construction Staking Curb Ramps	50.000 EACH		
0192	650.9910 Construction Staking Supplemental Control (project) 01. 1198-03-78	LS	LUMP SUM	