

MONOTUBE STRUCTURE NUMBERS	
SB2	S-70-0332
SB5	S-70-0333
SB8	S-70-0334
SB11	S-70-0335


GENERAL NOTES

THE LOCATION OF EXISTING AND PROPOSED UTILITY INSTALLATIONS AS SHOWN ON THE PLANS ARE APPROXIMATE. THERE MAY BE OTHER UTILITY INSTALLATIONS WITHIN THE PROJECT AREA THAT ARE NOT SHOWN. THE CONTRACTOR SHALL VERIFY THE LOCATIONS OF ALL UTILITIES PRIOR TO CONSTRUCTION.

CONFIGURATION WITH HEAD NUMBERS			
3-V (R) (Y) (G)	3, 4, 5 8, 9, 10 11, 12, 13 14, 15, 16	3-VLFY (R) (Y) (G)	1, 2
4-VLFY (R) (Y) (G)	6, 7	1-P (P)	17, 18 19, 20 21, 22 23, 24

LEGEND	
PULL BOX 24" X 42"	⊕
SIGNAL STANDARD, PEDESTAL BASE	⊕
PEDESTRIAN SIGNAL W/PUSH BUTTON	⊕ B
SIGNAL POLE, MONOTUBE ARM	⊕ 40'
CONTROL CABINET BASE	⊕
3" CONDUIT (2" from PB to T1 concrete base)	---
SIGNAL HEAD NUMBER MOUNTING CONFIGURATION	3 (R) (Y) (G)
MICROWAVE DETECTOR	⊕
LOOP DETECTOR (in 1" conduit)	⊕ 43 2T 6' 30"
LUMINAIRE (under permit to local municipality)	⊕
WisDOT Lighting (L70-2012)	⊕

START CROSSING Watch For Vehicles DON'T START Finish Crossing If Started TIME REMAINING To Finish Crossing DON'T CROSS TO CROSS PUSH BUTTON	Install on SB6, SB12 & SB13
START CROSSING Watch For Vehicles DON'T START Finish Crossing If Started TIME REMAINING To Finish Crossing DON'T CROSS TO CROSS PUSH BUTTON	Install on SB3, SB6, SB9, SB12 & SB14




Updated 9-27-2017
(Add Pavement Marking on Valley Rd)

R E V I S I O N			
Rev. No.	New TS2 Cabinet, Add Monotubes, FYA & Ped Phases 2 and 8		
	APPROVAL RECOMMENDED		APPROVED
	REGION		CENTRAL OFFICE
	Date	By	Date By
4	9-8-14	RJS	9-9-14 JLB
2-15-12	New Cabinet (EPAC) & Change to All Red Emergency Flash		
8-12-04	Add Pedestrian Phases 4 & 6		
9-6-96	Add Phase 1 & Upgrade Cabinet		

TRAFFIC CONTROL SIGNAL	
STH 47 & CTH P/Valley Rd CITY OF MENASHA WINNEBAGO COUNTY	
SIGNAL NO. 70-0192	CONTROLLER TYPE: ECONOLITE
WISCONSIN DEPARTMENT OF TRANSPORTATION	
APPROVAL RECOMMENDED Date 3-29-89	Gerald R. Kurtz REGION TRAFFIC ENGINEER
APPROVED Date 4-19-89	H. O. Price STATE TRAFFIC ENGINEER
REGION CONTACT: RJS DESIGNED BY: RJS REVISED BY: RJS	PAGE 1 OF 2

	HEAD NUMBERS	FLASH
Ø1	6, 7	R
Ø2	3, 4, 5	R
Ø3		
Ø4	11, 12, 13	R
Ø5		
Ø6	8, 9, 10	R
Ø7		
Ø8	14, 15, 16	R
Ø2P	17, 18	
Ø4P	19, 20	
Ø6P	21, 22	
Ø8P	23, 24	
OLE	6, 7	-
OLF		
OLG	1, 2	-
OLH		


RING 1

NOT
USED

Ø3

Ø4

RING 2

NOT
USED

Ø7

Ø8

BARRIER

CONTROLLER LOGIC

PHASE NUMBER	PHASE LOCKING	DUAL ENTRY W / Ø	PHASE RECALL	PHASE ACTIVE
1				x
2			MIN	x
3				
4		8		x
5				
6			MIN	x
7				
8		4		x

EMERGENCY VEHICLE PREEMPTION
maintained by the City of Appleton

EMERGENCY VEHICLE DETECTOR	3	4	5	6
MOVEMENT				
PHASE	1+6	4+8	2+6	4+8
GTT CHANNEL	A	B	C	D

TYPE OF INTERCONNECT/COMMUNICATION	
CELL MODEM	
CLOSED LOOP	
TWISTED PAIR*	
FIBER OPTIC*	
FIBER OPTIC (ETHERNET)	
RADIO	

TYPE OF COORDINATION	
NONE	
TBC	x
TRAFFIC RESPONSIVE	
ADAPTIVE	
*LOCATION OF MASTER CONTROLLER NO:	S-000
SIGNAL SYSTEM #:	SS-0000

TYPE OF LIGHTING	
BY OTHER AGENCY	
IN TRAFFIC SIGNAL CABINET	x
IN SEPARATE DOT LIGHTING CABINET	

TYPE OF PRE-EMPT	
NONE	
RAILROAD	
EMERGENCY VEHICLE	
GTT	x
TOMAR	
HARDWIRE	
3M	
LIFT BRIDGE	
QUEUE DETECTOR	

DETECTOR LOGIC

RACK # 1

DETECTOR CHANNEL	3	1	7	5	11	9	15	13
PLAN LOOP DETECTOR *(S)		11		21		42		81
ASSIGNED PHASE		1		2		4		8
OPERATION MODE		Veh		Veh		Veh		Veh
SWITCH TO PHASE								
EXTEND								
DELAY					Yes		Yes	
DETECTOR CHANNEL	4	2	8	6	12	10	16	14
PLAN LOOP DETECTOR *(S)		61		22		43		82
ASSIGNED PHASE		6		2		4		8
OPERATION MODE		Veh		Veh		Veh		Veh
SWITCH TO PHASE								
EXTEND								
DELAY								

RACK # 2

DETECTOR CHANNEL	19	17	23	21	27	25	31	29
PLAN LOOP DETECTOR *(S)								
ASSIGNED PHASE								
OPERATION MODE								
SWITCH TO PHASE								
EXTEND								
DELAY								
DETECTOR CHANNEL	20	18	24	22	28	26	32	30
PLAN LOOP DETECTOR *(S)								
ASSIGNED PHASE								
OPERATION MODE								
SWITCH TO PHASE								
EXTEND								
DELAY								

GENERAL NOTES:

1. PROVIDE FOR HAND CONTROL.

Updated 9-27-2017
(Add Pavement Marking on Valley Rd)

STH 47 & CTH P/Valley Rd
CITY OF MENASHA
WINNEBAGO COUNTY

SIGNAL NO. 192

CABINET: TS2 CONTROLLER: ECONOLITE

DATE: 9-9-2014 PAGE NO. 2 OF 2