

LANDSCAPE SUMMARY

	62505 SALVAGED TOPSOIL	63009 SEED #20	63003 SEED TEMPORARY	62905 FERTILIZER TYPE B	62702 MULCH	
LOCATION	m2	kg	kg	kg	m2	REMARKS
B-44-71	200	3	1	7	200	TO RESTORE DISTURBED ABUTMENT SLOPES
B-44-73	200	3	1	7	200	TO RESTORE DISTURBED ABUTMENT SLOPES
B-44-74	200	3	1	7	200	TO RESTORE DISTURBED ABUTMENT SLOPES
TOTAL	600	9	3	21	600	

QUALITATIVE MANAGEMENT PROGRAM SUMMARY

	90501 READY MIX CONC. MASONRY FOR BRIDGES	90502 INCENTIVE FOR CONC. MASONRY COMP. STRENGTH	
LOCATION	m3	DOLLAR	REMARKS
B-44-71	342	4,104	CATEGORY 0020
B-44-73	377	4,524	CATEGORY 0030
B-44-74	377	4,524	CATEGORY 0040
TOTALS	1,096	13,152	

CONSTRUCTION STAKING SUMMARY

		<u>CONSTRUCTION STAKING, STRUCTURE LAYOUT</u>							
		90005A		90005B		90005C			
		STRUCTURE		STRUCTURE		STRUCTURE			
		B-44-71		B-44-73		B-44-74			
		EACH		EACH		EACH			
STATION TO	STATION	LOCATION	STRUCTURE					REMARKS	
38+122.58	- 38+152.50	USH 41 SOUTHBOUND	B-44-71	1				CATEGORY 0020	
40+296.60	- 40+328.50	USH 41 SOUTHBOUND	B-44-73		1			CATEGORY 0030	
40+306.07	- 40+337.97	USH 41 NORTHBOUND	B-44-74			1		CATEGORY 0040	
TOTAL				1	1	1			

NOTE:

FOR ALL OTHER QUANTITIES, PLEASE SEE THE SUMMARY OF ESTIMATED QUANTITIES FOUND IN EACH OF THE ATTACHED STRUCTURE PLANS.