

3

DATE 12AUG08		ESTIMATE OF QUANTITIES			
LINE				1154-01-76	
NUMBER	ITEM	ITEM DESCRIPTION	UNIT	TOTAL	QUANTITY
0010	201.0105	CLEARING	STA	60.000	60.000
0020	201.0205	GRUBBING	STA	60.000	60.000
0030	203.0100	REMOVING SMALL PIPE CULVERTS	EACH	53.000	53.000
0040	203.0200	REMOVING OLD STRUCTURE (STATION) 01. STA 809+25	LS	1.000	1.000
0050	204.0100	REMOVING PAVEMENT	SY	41,434.000	41,434.000
0060	204.0150	REMOVING CURB & GUTTER	LF	1,054.000	1,054.000
0070	204.0155	REMOVING CONCRETE SIDEWALK	SY	12.000	12.000
0080	204.0165	REMOVING GUARDRAIL	LF	671.000	671.000
0090	204.0170	REMOVING FENCE	LF	728.000	728.000
0100	204.0180	REMOVING MARKER POSTS	EACH	33.000	33.000
0110	204.0185	REMOVING MASONRY	CY	28.000	28.000
0120	204.0210	REMOVING MANHOLES	EACH	4.000	4.000
0130	204.0220	REMOVING INLETS	EACH	5.000	5.000
0140	204.0225	REMOVING SEPTIC TANKS	EACH	1.000	1.000
0150	204.0235	REMOVING BUILDINGS (PARCEL) 01. PARCEL 13	LS	1.000	1.000
0160	204.0240	SITE CLEARANCE (PARCEL) 01. PARCEL 13	LS	1.000	1.000
0170	204.0245	REMOVING STORM SEWER (SIZE) 01. 12-INCH	LF	320.000	320.000
0180	204.0245	REMOVING STORM SEWER (SIZE) 02. 21-INCH	LF	15.000	15.000
0190	204.0245	REMOVING STORM SEWER (SIZE) 03. 24-INCH	LF	700.000	700.000
0200	204.0265	ABANDONING WELLS	EACH	1.000	1.000
0210	204.0280	SEALING PIPES	EACH	5.000	5.000
0220	204.0291.S	ABANDONING SEWER	CY	90.000	90.000
0230	204.9060.S	REMOVING (ITEM DESCRIPTION) 01. CRASH CUSHION	EACH	2.000	2.000
0240	204.9090.S	REMOVING (ITEM DESCRIPTION) 01. REMOVING CONCRETE BARRIER PRECAST	LF	1,000.000	1,000.000
0250	205.0100	EXCAVATION COMMON	CY	71,243.000	71,243.000
0260	208.0100	BORROW	CY	122,744.000	122,744.000
0270	208.1100	SELECT BORROW	CY	33,540.000	33,540.000
0280	213.0100	FINISHING ROADWAY (PROJECT) 01. 1154-01-76	EACH	1.000	1.000
0290	305.0110	BASE AGGREGATE DENSE 3/4-INCH	TON	66,979.000	66,979.000
0300	305.0120	BASE AGGREGATE DENSE 1 1/4-INCH	TON	188,236.000	188,236.000
0310	415.0080	CONCRETE PAVEMENT 8-INCH	SY	47,670.000	47,670.000
0320	415.0100	CONCRETE PAVEMENT 10-INCH	SY	168,167.000	168,167.000
0330	415.2000.S	INCENTIVE STRENGTH CONCRETE PAVEMENT	DOL	49,638.000	49,638.000
0340	416.0160	CONCRETE DRIVEWAY 6-INCH	SY	380.000	380.000
0350	416.0610	DRILLED TIE BARS	EACH	544.000	544.000
0360	416.0620	DRILLED DOWEL BARS	EACH	122.000	122.000
0370	416.0805	CONCRETE PAVEMENT GAPS	EACH	7.000	7.000
0380	440.4410.S	INCENTIVE IRI RIDE	DOL	44,417.000	44,417.000
0390	455.0105	ASPHALTIC MATERIAL PG58-28	TON	1,044.000	1,044.000
0400	455.0115	ASPHALTIC MATERIAL PG64-22	TON	55.000	55.000
0410	455.0120	ASPHALTIC MATERIAL PG64-28	TON	31.000	31.000
0420	455.0605	TACK COAT	GAL	2,139.000	2,139.000
0430	460.1100	HMA PAVEMENT TYPE E-0.3	TON	16,271.000	16,271.000
0440	460.1103	HMA PAVEMENT TYPE E-3	TON	3,299.000	3,299.000
0450	460.2000	INCENTIVE DENSITY HMA PAVEMENT	DOL	12,532.000	12,532.000
0460	465.0120	ASPHALTIC SURFACE DRIVEWAYS AND FIELD ENTRANCES	TON	100.000	100.000
0470	465.0125	ASPHALTIC SURFACE TEMPORARY	TON	465.000	465.000
0480	465.0315	ASPHALTIC FLUMES	SY	154.000	154.000
0490	465.0400	ASPHALTIC SHOULDER RUMBLE STRIP	LF	82,718.000	82,718.000

3

3

DATE 12AUG08		ESTIMATE OF QUANTITIES			
LINE				1154-01-76	
NUMBER	ITEM	ITEM DESCRIPTION	UNIT	TOTAL	QUANTITY
0500	520.0112	CULVERT PIPE CLASS III 12-INCH	LF	68.000	68.000
0510	520.0115	CULVERT PIPE CLASS III 15-INCH	LF	96.000	96.000
0520	520.1012	APRON ENDWALLS FOR CULVERT PIPE 12-INCH	EACH	6.000	6.000
0530	520.1015	APRON ENDWALLS FOR CULVERT PIPE 15-INCH	EACH	4.000	4.000
0540	520.8000.S	CULVERT PIPE CONCRETE COLLAR	EACH	11.000	11.000
0550	521.0118	CULVERT PIPE CORRUGATED STEEL 18-INCH	LF	286.000	286.000
0560	521.1018	APRON ENDWALLS FOR CULVERT PIPE STEEL 18-INCH	EACH	14.000	14.000
0570	522.0118	CULVERT PIPE REINFORCED CONCRETE CLASS III 18-INCH	LF	164.000	164.000
0580	522.0124	CULVERT PIPE REINFORCED CONCRETE CLASS III 24-INCH	LF	160.000	160.000
0590	522.0136	CULVERT PIPE REINFORCED CONCRETE CLASS III 36-INCH	LF	146.000	146.000
0600	522.0148	CULVERT PIPE REINFORCED CONCRETE CLASS III 48-INCH	LF	202.000	202.000
0610	522.0336	CULVERT PIPE REINFORCED CONCRETE CLASS IV 36-INCH	LF	308.000	308.000
0620	522.1012	APRON ENDWALLS FOR CULVERT PIPE REINFORCED CONCRETE 12-INCH	EACH	7.000	7.000
0630	522.1015	APRON ENDWALLS FOR CULVERT PIPE REINFORCED CONCRETE 15-INCH	EACH	2.000	2.000
0640	522.1018	APRON ENDWALLS FOR CULVERT PIPE REINFORCED CONCRETE 18-INCH	EACH	6.000	6.000
0650	522.1024	APRON ENDWALLS FOR CULVERT PIPE REINFORCED CONCRETE 24-INCH	EACH	3.000	3.000
0660	522.1027	APRON ENDWALLS FOR CULVERT PIPE REINFORCED CONCRETE 27-INCH	EACH	1.000	1.000
0670	522.1036	APRON ENDWALLS FOR CULVERT PIPE REINFORCED CONCRETE 36-INCH	EACH	10.000	10.000
0680	522.1048	APRON ENDWALLS FOR CULVERT PIPE REINFORCED CONCRETE 48-INCH	EACH	2.000	2.000
0690	523.0134	CULVERT PIPE REINFORCED CONCRETE HORIZONTAL ELLIPTICAL CLASS HE-III 34X53-INCH	LF	508.000	508.000
0700	523.0138	CULVERT PIPE REINFORCED CONCRETE HORIZONTAL ELLIPTICAL CLASS HE-III 38X60-INCH	LF	150.000	150.000
0710	523.0534	APRON ENDWALLS FOR CULVERT PIPE REINFORCED CONCRETE HORIZONTAL ELLIPTICAL 34X53-INCH	EACH	6.000	6.000
0720	523.0538	APRON ENDWALLS FOR CULVERT PIPE REINFORCED CONCRETE HORIZONTAL ELLIPTICAL 38X60-INCH	EACH	1.000	1.000
0730	601.0105	CONCRETE CURB TYPE A	LF	810.000	810.000
0740	601.0409	CONCRETE CURB & GUTTER 30-INCH TYPE A	LF	10,321.000	10,321.000
0750	601.0411	CONCRETE CURB & GUTTER 30-INCH TYPE D	LF	870.000	870.000
0760	601.0413	CONCRETE CURB & GUTTER 6-INCH SLOPED 30-INCH TYPE G	LF	1,500.000	1,500.000
0770	601.0555	CONCRETE CURB AND GUTTER 6-INCH SLOPED 36-INCH TYPE A	LF	1,973.000	1,973.000
0780	601.0557	CONCRETE CURB AND GUTTER 6-INCH SLOPED 36-INCH TYPE D	LF	458.000	458.000
0790	601.0580	CONCRETE CURB & GUTTER 4-INCH SLOPED 36-INCH TYPE R	LF	1,030.000	1,030.000
0800	602.0405	CONCRETE SIDEWALK 4-INCH	SF	6,550.000	6,550.000

3

3

DATE 12AUG08		ESTIMATE OF QUANTITIES			
LINE				1154-01-76	
NUMBER	ITEM	ITEM DESCRIPTION	UNIT	TOTAL	QUANTITY
0810	602.0505	CURB RAMP DETECTABLE WARNING FIELD YELLOW	SF	72.000	72.000
0820	603.0105	CONCRETE BARRIER SINGLE-FACED 32-INCH	LF	7,141.000	7,141.000
0830	603.0205	CONCRETE BARRIER DOUBLE-FACED 32-INCH	LF	1,171.000	1,171.000
0840	603.0405	CONCRETE BARRIER TRANSITION SECTION 32-INCH	LF	75.000	75.000
0850	604.0600	SLOPE PAVING SELECT CRUSHED MATERIAL	SY	244.000	244.000
0860	606.0100	RIPRAP LIGHT	CY	19.000	19.000
0870	606.0200	RIPRAP MEDIUM	CY	171.000	171.000
0880	608.0318	STORM SEWER PIPE REINFORCED CONCRETE CLASS III 18-INCH	LF	366.000	366.000
0890	608.0321	STORM SEWER PIPE REINFORCED CONCRETE CLASS III 21-INCH	LF	654.000	654.000
0900	608.0324	STORM SEWER PIPE REINFORCED CONCRETE CLASS III 24-INCH	LF	32.000	32.000
0910	608.0327	STORM SEWER PIPE REINFORCED CONCRETE CLASS III 27-INCH	LF	576.000	576.000
0920	608.0412	STORM SEWER PIPE REINFORCED CONCRETE CLASS IV 12-INCH	LF	756.000	756.000
0930	608.0415	STORM SEWER PIPE REINFORCED CONCRETE CLASS IV 15-INCH	LF	166.000	166.000
0940	608.0418	STORM SEWER PIPE REINFORCED CONCRETE CLASS IV 18-INCH	LF	14.000	14.000
0950	611.0201	MANHOLES TYPE 1	EACH	6.000	6.000
0960	611.0210	MANHOLES TYPE 3	EACH	1.000	1.000
0970	611.0301	INLETS TYPE 1	EACH	2.000	2.000
0980	611.0302	INLETS TYPE 2	EACH	6.000	6.000
0990	611.0303	INLETS TYPE 3	EACH	35.000	35.000
1000	611.0305	INLETS TYPE 8	EACH	4.000	4.000
1010	611.0307	INLETS TYPE 9	EACH	4.000	4.000
1020	611.0530	MANHOLE COVERS TYPE J	EACH	13.000	13.000
1030	611.0606	INLET COVERS TYPE B	EACH	2.000	2.000
1040	611.0612	INLET COVERS TYPE C	EACH	2.000	2.000
1050	611.0624	INLET COVERS TYPE H	EACH	20.000	20.000
1060	611.0627	INLET COVERS TYPE HM	EACH	4.000	4.000
1070	611.0630	INLET COVERS TYPE HM-GJ	EACH	2.000	2.000
1080	611.0636	INLET COVERS TYPE HM-S	EACH	7.000	7.000
1090	611.0639	INLET COVERS TYPE H-S	EACH	15.000	15.000
1100	611.0642	INLET COVERS TYPE MS	EACH	12.000	12.000
1110	611.0652	INLET COVERS TYPE T	EACH	6.000	6.000
1120	611.0654	INLET COVERS TYPE V	EACH	44.000	44.000
1130	611.8110	ADJUSTING MANHOLE COVERS	EACH	15.000	15.000
1140	614.0115	ANCHORAGES FOR STEEL PLATE BEAM GUARD TYPE 2	EACH	4.000	4.000
1150	614.0200	STEEL THRIE BEAM STRUCTURE APPROACH	LF	334.000	334.000
1160	614.0305	STEEL PLATE BEAM GUARD CLASS A	LF	5,203.000	5,203.000
1170	614.0370	STEEL PLATE BEAM GUARD ENERGY ABSORBING TERMINAL	EACH	12.000	12.000
1180	614.0620.S	MARKER POSTS CULVERT END FLEXIBLE	EACH	57.000	57.000
1190	614.0700	SAND BARRELS	EACH	14.000	14.000
1200	616.0100	FENCE WOVEN WIRE (HEIGHT) 01. 4-FOOT	LF	56,780.000	56,780.000
1210	618.0100	MAINTENANCE AND REPAIR OF HAUL ROADS (PROJECT) 01. 1154-01-76	EACH	1.000	1.000
1220	619.1000	MOBILIZATION	EACH	1.000	1.000
1230	620.0300	CONCRETE MEDIAN SLOPED NOSE	SF	781.000	781.000
1240	624.0100	WATER	MGAL	168.350	168.350

3

3

DATE 12AUG08		ESTIMATE OF QUANTITIES			
LINE				1154-01-76	
NUMBER	ITEM	ITEM DESCRIPTION	UNIT	TOTAL	QUANTITY
1250	625.0500	SALVAGED TOPSOIL	SY	168,000.000	168,000.000
1260	627.0200	MULCHING	SY	154,100.000	154,100.000
1270	628.1504	SILT FENCE	LF	10,430.000	10,430.000
1280	628.1520	SILT FENCE MAINTENANCE	LF	6,110.000	6,110.000
1290	628.1550	SILT SCREEN	LF	20.000	20.000
1300	628.1905	MOBILIZATIONS EROSION CONTROL	EACH	5.000	5.000
1310	628.1910	MOBILIZATIONS EMERGENCY EROSION CONTROL	EACH	7.000	7.000
1320	628.2002	EROSION MAT CLASS I TYPE A	SY	17,200.000	17,200.000
1330	628.2004	EROSION MAT CLASS I TYPE B	SY	490.000	490.000
1340	628.2006	EROSION MAT URBAN CLASS I TYPE A	SY	1,040.000	1,040.000
1350	628.6505	SOIL STABILIZER TYPE A	ACRE	0.230	0.230
1360	628.7005	INLET PROTECTION TYPE A	EACH	58.000	58.000
1370	628.7015	INLET PROTECTION TYPE C	EACH	23.000	23.000
1380	628.7020	INLET PROTECTION TYPE D	EACH	24.000	24.000
1390	628.7550	CULVERT PIPE DITCH CHECKS	EACH	27.000	27.000
1400	629.0210	FERTILIZER TYPE B	CWT	125.000	125.000
1410	630.0120	SEEDING MIXTURE NO. 20	LB	2,990.000	2,990.000
1420	630.0130	SEEDING MIXTURE NO. 30	LB	1,085.000	1,085.000
1430	630.0200	SEEDING TEMPORARY	LB	4,500.000	4,500.000
1440	631.0300	SOD WATER	MGAL	0.700	0.700
1450	631.1200	SOD EROSION CONTROL SANDY SOIL	SY	35.000	35.000
1460	632.0101	TREES (SPECIES, ROOT, SIZE) 01. WASHINGTON HAWTHORNE B&B 1.5" CAL	EACH	1.000	1.000
1470	632.0101	TREES (SPECIES, ROOT, SIZE) 02. AMERICAN HORNBEAM B&B 2" CAL	EACH	1.000	1.000
1480	632.0201	SHRUBS (SPECIES, ROOT, SIZE) 01. VERNAL WITCHHAZEL B&B 36"	EACH	12.000	12.000
1490	632.0201	SHRUBS (SPECIES, ROOT, SIZE) 02. MINIATURE SNOWFLAKE MOCKORANGE CG 24	EACH	30.000	30.000
1500	632.0201	SHRUBS (SPECIES, ROOT, SIZE) 03. PALIBIN LILAC CG 36"	EACH	17.000	17.000
1510	632.0201	SHRUBS (SPECIES, ROOT, SIZE) 04. MEADOW	EACH	44.000	44.000
1520	632.0201	ROSE CG 24" SHRUBS (SPECIES, ROOT, SIZE) 05. BAILEY'S COMPACT AMERICAN CRANBERRYBUSH VIBURNUM B&B 36"	EACH	14.000	14.000
1530	632.0201	SHRUBS (SPECIES, ROOT, SIZE) 06. SHRUBS FRAGRANT SUMAC CG 12"	EACH	103.000	103.000
1540	632.9101	LANDSCAPE PLANTING SURVEILLANCE AND CARE CYCLES	EACH	6.000	6.000
1550	633.0100	DELINEATOR POSTS STEEL	EACH	404.000	404.000
1560	633.0500	DELINEATORS	EACH	506.000	506.000
1570	633.1100	DELINEATORS TEMPORARY	EACH	76.000	76.000
1580	634.0612	POSTS WOOD 4X6-INCH X 12-FT	EACH	10.000	10.000
1590	634.0614	POSTS WOOD 4X6-INCH X 14-FT	EACH	97.000	97.000
1600	634.0616	POSTS WOOD 4X6-INCH X 16-FT	EACH	38.000	38.000
1610	634.0618	POSTS WOOD 4X6-INCH X 18-FT	EACH	35.000	35.000
1620	635.0200	SIGN SUPPORTS STRUCTURAL STEEL HS	LB	4,995.000	4,995.000
1630	636.0100	SIGN SUPPORTS CONCRETE MASONRY	CY	8.800	8.800
1640	636.1000	SIGN SUPPORTS STEEL REINFORCEMENT HS	LB	528.000	528.000
1650	637.0101	SIGNS TYPE I	SF	813.500	813.500
1660	637.0202	SIGNS REFLECTIVE TYPE II	SF	1,848.350	1,848.350
1670	638.2101	MOVING SIGNS TYPE I	EACH	1.000	1.000
1680	638.2102	MOVING SIGNS TYPE II	EACH	5.000	5.000
1690	638.2602	REMOVING SIGNS TYPE II	EACH	143.000	143.000

3

3

DATE 12AUG08		ESTIMATE OF QUANTITIES			
LINE					1154-01-76
NUMBER	ITEM	ITEM DESCRIPTION	UNIT	TOTAL	QUANTITY
1700	638.3000	REMOVING SMALL SIGN SUPPORTS	EACH	91.000	91.000
1710	642.5401	FIELD OFFICE TYPE D	EACH	1.000	1.000
1720	643.0200	TRAFFIC CONTROL SURVEILLANCE AND MAINTENANCE (PROJECT) 01. 1154-01-76	DAYS	215.000	215.000
1730	643.0300	TRAFFIC CONTROL DRUMS	DAYS	30,645.000	30,645.000
1740	643.0420	TRAFFIC CONTROL BARRICADES TYPE III	DAYS	7,950.000	7,950.000
1750	643.0500	TRAFFIC CONTROL FLEXIBLE TUBULAR MARKER POSTS	EACH	310.000	310.000
1760	643.0600	TRAFFIC CONTROL FLEXIBLE TUBULAR MARKER BASES	EACH	310.000	310.000
1770	643.0705	TRAFFIC CONTROL WARNING LIGHTS TYPE A	DAYS	13,250.000	13,250.000
1780	643.0715	TRAFFIC CONTROL WARNING LIGHTS TYPE C	DAYS	6,970.000	6,970.000
1790	643.0800	TRAFFIC CONTROL ARROW BOARDS	DAYS	520.000	520.000
1800	643.0900	TRAFFIC CONTROL SIGNS	DAYS	12,675.000	12,675.000
1810	643.0905.S	TRAFFIC CONTROL COVERING SIGNS	EACH	15.000	15.000
1820	643.1050.S	TRAFFIC CONTROL SIGNS PORTABLE CHANGEABLE MESSAGE	DAY	118.000	118.000
1830	643.2000	TRAFFIC CONTROL DETOUR (PROJECT) 01. 1154-01-76	EACH	1.000	1.000
1840	643.3000	TRAFFIC CONTROL DETOUR SIGNS	DAYS	16,975.000	16,975.000
1850	645.0111	GEOTEXTILE FABRIC TYPE DF SCHEDULE A	SY	1,200.000	1,200.000
1860	645.0120	GEOTEXTILE FABRIC TYPE HR	SY	437.000	437.000
1870	645.0130	GEOTEXTILE FABRIC TYPE R	SY	90.000	90.000
1880	646.0106	PAVEMENT MARKING EPOXY 4-INCH	LF	162,070.000	162,070.000
1890	646.0126	PAVEMENT MARKING EPOXY 8-INCH	LF	1,620.000	1,620.000
1900	646.0156	PAVEMENT MARKING EPOXY 18-INCH	LF	150.000	150.000
1910	646.0600	REMOVING PAVEMENT MARKINGS	LF	37,530.000	37,530.000
1920	646.0841.S	PAVEMENT MARKING GROOVED WET REFLECTIVE CONTRAST TAPE 4-INCH	LF	14,000.000	14,000.000
1930	646.0843.S	PAVEMENT MARKING GROOVED WET REFLECTIVE CONTRAST TAPE 8-INCH	LF	9,350.000	9,350.000
1940	647.0166	PAVEMENT MARKING ARROWS EPOXY TYPE 2	EACH	6.000	6.000
1950	647.0456	PAVEMENT MARKING CURB EPOXY	LF	290.000	290.000
1960	647.0566	PAVEMENT MARKING STOP LINE EPOXY 18-INCH	LF	135.000	135.000
1970	647.0576	PAVEMENT MARKING STOP LINE EPOXY 24-INCH	LF	12.000	12.000
1980	647.0606	PAVEMENT MARKING ISLAND NOSE EPOXY	EACH	9.000	9.000
1990	647.0726	PAVEMENT MARKING DIAGONAL EPOXY 12-INCH	LF	329.000	329.000
2000	647.0796	PAVEMENT MARKING CROSSWALK EPOXY 24-INCH	LF	80.000	80.000
2010	648.0100	LOCATING NO-PASSING ZONES	MI	1.500	1.500
2020	649.0100	TEMPORARY PAVEMENT MARKING 4-INCH	LF	55,600.000	55,600.000
2030	649.0400	TEMPORARY PAVEMENT MARKING REMOVABLE TAPE 4-INCH	LF	7,500.000	7,500.000
2040	649.2100	TEMPORARY RAISED PAVEMENT MARKERS	EACH	340.000	340.000
2050	650.4000	CONSTRUCTION STAKING STORM SEWER SYSTEM	EACH	66.000	66.000
2060	650.4500	CONSTRUCTION STAKING SUBGRADE	LF	20,843.000	20,843.000
2070	650.5000	CONSTRUCTION STAKING BASE	LF	10,055.000	10,055.000
2080	650.5500	CONSTRUCTION STAKING CURB GUTTER AND CURB & GUTTER	LF	4,293.000	4,293.000
2090	650.6000	CONSTRUCTION STAKING PIPE CULVERTS	EACH	26.000	26.000
2100	650.7000	CONSTRUCTION STAKING CONCRETE PAVEMENT	LF	75,619.000	75,619.000
2110	650.7500	CONSTRUCTION STAKING CONCRETE BARRIER	LF	8,387.000	8,387.000
2120	650.9920	CONSTRUCTION STAKING SLOPE STAKES	LF	14,823.000	14,823.000
2130	652.0225	CONDUIT RIGID NONMETALLIC SCHEDULE 40 2-INCH	LF	3,010.000	3,010.000

3

3

DATE 12AUG08		ESTIMATE OF QUANTITIES			
LINE				1154-01-76	
NUMBER	ITEM	ITEM DESCRIPTION	UNIT	TOTAL	QUANTITY
2140	652.0235	CONDUIT RIGID NONMETALLIC SCHEDULE 40 3-INCH	LF	1,500.000	1,500.000
2150	653.0140	PULL BOXES STEEL 24X42-INCH	EACH	20.000	20.000
2160	654.0105	CONCRETE BASES TYPE 5	EACH	35.000	35.000
2170	654.0215	CONCRETE CONTROL CABINET BASES TYPE 9	EACH	2.000	2.000
2180	655.0610	ELECTRICAL WIRE LIGHTING 12 AWG	LF	16,170.000	16,170.000
2190	655.0615	ELECTRICAL WIRE LIGHTING 10 AWG	LF	8,355.000	8,355.000
2200	657.0255	TRANSFORMER BASES STANDARD 11 1/2-INCH BOLT CIRCLE	EACH	35.000	35.000
2210	657.0320	POLES TYPE 5	EACH	35.000	35.000
2220	657.0710	LUMINAIRE ARMS TRUSS TYPE 4 1/2-INCH CLAMP 12-FT	EACH	35.000	35.000
2230	659.0115	LUMINAIRES UTILITY HPS 150 WATTS	EACH	35.000	35.000
2240	690.0100	SAWING EXISTING PAVEMENT	LF	6,761.000	6,761.000
2250	690.0200	SAWING CONCRETE PAVEMENT FULL DEPTH	LF	4,467.000	4,467.000
2260	ASP.1T0A	ON-THE-JOB TRAINING APPRENTICE AT \$5.00/HR	HRS	800.000	800.000
2270	ASP.1T0G	ON-THE-JOB TRAINING GRADUATE AT \$5.00/HR	HRS	3,000.000	3,000.000
2280	SPV.0060	SPECIAL 01. APRON ENDWALLS FOR CULVERT PIPE REINFORCED CONCRETE SPECIAL 18-INCH	EACH	5.000	5.000
2290	SPV.0060	SPECIAL 04. MANHOLES TYPE 5 SPECIAL	EACH	6.000	6.000
2300	SPV.0060	SPECIAL 05. INLETS TYPE 3 SADDLE	EACH	4.000	4.000
2310	SPV.0060	SPECIAL 06. ADJUSTING WATERMAIN VALVE BOXES	EACH	15.000	15.000
2320	SPV.0060	SPECIAL 07. STORM SEWER OPENINGS	EACH	1.000	1.000
2330	SPV.0165	SPECIAL 01. STAMPED COLORED CONCRETE SIDEWALK 4-INCH	SF	18,200.000	18,200.000
2340	SPV.0180	SPECIAL 01. STAMPED COLORED CONCRETE PAVEMENT 12-INCH	SY	655.000	655.000
2350	SPV.0195	SPECIAL 01. COARSE AGGREGATE SPECIAL	TON	260.000	260.000
2360	SPV.0195	SPECIAL 02. LIMESTONE SCREENINGS 3/8-INCH	TON	3,288.000	3,288.000

3