

DATE 02/11/94

ESTIMATE OF QUANTITIES



ITEM	ITEM DESCRIPTION	UNIT	TOTAL	1410-02-70 QUANTITY
20102	CLEARING	I.D.	152.00	152.00
20105	GRUBBING	I.D.	152.00	152.00
20351	REMOVING OLD BRIDGE, STATION 6+34.5	L.S.	1.00	1.00
20401	REMOVING PAVEMENT	S.Y.	1,455.00	1,455.00
20402	REMOVING ASPHALTIC SURFACE	S.Y.	1,530.00	1,530.00

20405	REMOVING CURB AND GUTTER	L.F.	22.00	22.00
20411	REMOVING GUARDRAIL	L.F.	305.00	305.00
20419	REMOVING ASPHALTIC SURFACE, BUTT JOINTS	S.Y.	427.00	427.00
20420	REMOVING ASPHALTIC PAVEMENT, MILLING	S.Y.	520.00	520.00
20503	UNCLASSIFIED EXCAVATION	C.Y.	909.00	909.00

20610	EXCAVATION FOR STRUCTURES, BRIDGES B-66-106	L.S.	1.00	1.00
20801	BORROW EXCAVATION	C.Y.	5,986.00	5,986.00
21301	FINISHING ROADWAY	L.S.	1.00	1.00
30404	CRUSHED AGGREGATE BASE COURSE	TON	2,564.00	2,564.00
40204	ASPHALTIC MATERIAL FOR TACK COAT	GAL.	190.00	190.00

40501	ASPHALTIC MATERIAL FOR PLANT MIXES	TON	145.00	145.00
40712	ASPHALTIC CONCRETE PAVEMENT, TYPE HV	TON	1,545.00	1,545.00
40713	ASPHALTIC CONCRETE PAVEMENT, TYPE MV	TON	868.00	868.00
50201	CONCRETE MASONRY, BRIDGES	C.Y.	298.00	298.00
50230	PROTECTIVE SURFACE TREATMENT	GAL.	30.00	30.00

50303	PRESTRESSED GIRDER, I TYPE, 36-INCH	L.F.	660.00	660.00
50504	HIGH-STRENGTH BAR STEEL REINFORCEMENT, BRIDGES	LB.	9,550.00	9,550.00
50511	COATED HIGH-STRENGTH BAR STEEL REINFORCEMENT, BRIDGES	LB.	23,740.00	23,740.00
50626	NON-LAMINATED ELASTOMERIC BEARING PADS	EACH	20.00	20.00
50640	STEEL DIAPHRAGMS, STRUCTURE B-66-106	EACH	9.00	9.00

51121	STEEL PILING, DELIVERED AND DRIVEN, HP 10-INCH 42 POUND	L.F.	440.00	440.00
-------	--	------	--------	--------

Sheet 3

1410-02-70
QUANTITY

ITEM	ITEM DESCRIPTION	UNIT	TOTAL	1410-02-70 QUANTITY
52007	CULVERT PIPE, CLASS III, 30-INCH	L.F.	50.00	50.00
52065	APRON ENDWALLS FOR CULVERT PIPE, 30-INCH	EACH	2.00	2.00
52231	REINFORCED CONCRETE CULVERT PIPE, CLASS IV, 30-INCH	L.F.	370.00	370.00
52266	REINFORCED CONCRETE APRON ENDWALLS FOR CULVERT PIPE, 30-INCH	EACH	2.00	2.00
52601	TEMPORARY STRUCTURE, STATION STA 6+10	L.S.	1.00	1.00
60133	CONCRETE CURB AND GUTTER, 30-INCH, TYPE D	L.F.	30.00	30.00
60170	CONCRETE CURB AND GUTTER, 36-INCH, TYPE D	L.F.	155.00	155.00
60205	CONCRETE SIDEWALK, 5-INCH	S.F.	50.00	50.00
60305	TEMPORARY PRECAST CONCRETE BARRIER, DELIVERED	L.F.	1,330.00	1,330.00
60307	TEMPORARY PRECAST CONCRETE BARRIER, INSTALLED	L.F.	2,460.00	2,460.00
60602	HEAVY RIPRAP	C.Y.	315.00	315.00
61182	ADJUSTING MANHOLE COVERS	EACH	3.00	3.00
61211	PIPE UNDERDRAIN, UNPERFORATED, 6-INCH	L.F.	16.00	16.00
61236	PIPE UNDERDRAIN, WRAPPED, 6-INCH	L.F.	150.00	150.00
61407	STEEL THRIE BEAM STRUCTURE APPROACH	L.F.	81.00	81.00
61408	STEEL PLATE BEAM GUARD, CLASS A	L.F.	194.00	194.00
61412	ANCHORAGES FOR STEEL PLATE BEAM GUARD, TYPE 1	EACH	4.00	4.00
61801	MAINTENANCE AND REPAIR OF HAUL ROADS	L.S.	1.00	1.00
61910	MOBILIZATION	L.S.	1.00	1.00
62203	ASPHALTIC FLUMES	S.Y.	38.00	38.00
62505	SALVAGED TOPSOIL	S.Y.	5,360.00	5,360.00
62702	MULCHING	S.Y.	3,406.00	3,406.00
62811	EROSION BALES, DELIVERED	EACH	117.00	117.00
62812	EROSION BALES, INSTALLED	EACH	117.00	117.00
62815	SILT FENCE, DELIVERED	L.F.	2,100.00	2,100.00

Sheet 3.1

ITEM	ITEM DESCRIPTION	UNIT	TOTAL	1410-02-70 QUANTITY
------	------------------	------	-------	------------------------

62816	SILT FENCE, INSTALLED	L.F.	2,100.00	2,100.00
-------	--------------------------	------	----------	----------

62817	SILT FENCE MAINTENANCE	L.F.	6,300.00	6,300.00
-------	---------------------------	------	----------	----------

62819	MOBILIZATIONS, EROSION CONTROL	EACH	2.00	2.00
-------	-----------------------------------	------	------	------

62902	FERTILIZER, TYPE A	CWT.	3.40	3.40
-------	--------------------	------	------	------

63002	SEEDING	LB.	30.00	30.00
-------	---------	-----	-------	-------

63004	SEEDING, WETLANDS	LB.	25.00	25.00
-------	-------------------	-----	-------	-------

63101	SODDING	S.Y.	1,960.00	1,960.00
-------	---------	------	----------	----------

63201	TREES, ASH GREEN, 2-INCH CAL., B&B,	EACH	4.00	4.00
-------	--	------	------	------

63202	TREES, ASH, WHITE, 2-INCH CAL., B&B	EACH	4.00	4.00
-------	--	------	------	------

63401	WOOD POSTS, 4X4-INCH X 10-FT.	EACH	6.00	6.00
-------	----------------------------------	------	------	------

63412	WOOD POSTS, 4X6-INCH X 16-FT.	EACH	11.00	11.00
-------	----------------------------------	------	-------	-------

63702	SIGNS, TYPE II, REFLECTIVE	S.F.	6.00	6.00
-------	-------------------------------	------	------	------

63822	MOVING SIGNS, TYPE II	EACH	15.00	15.00
-------	--------------------------	------	-------	-------

64202	FIELD OFFICE, TYPE B	L.S.	1.00	1.00
-------	-------------------------	------	------	------

64301	TRAFFIC CONTROL	L.S.	1.00	1.00
-------	-----------------	------	------	------

64313	TRAFFIC CONTROL, DRUMS	DAYS	6,401.00	6,401.00
-------	---------------------------	------	----------	----------

64318	TRAFFIC CONTROL, BARRICADES, TYPE III	DAYS	1,066.00	1,066.00
-------	---	------	----------	----------

64321	TRAFFIC CONTROL, WARNING LIGHTS, TYPE A	DAYS	4,091.00	4,091.00
-------	---	------	----------	----------

64323	TRAFFIC CONTROL, WARNING LIGHTS, TYPE C	DAYS	6,401.00	6,401.00
-------	---	------	----------	----------

64326	TRAFFIC CONTROL, SIGNS	DAYS	3,353.00	3,353.00
-------	---------------------------	------	----------	----------

64406	PAVEMENT MARKING, EPOXY, 4-INCH	L.F.	5,180.00	5,180.00
-------	------------------------------------	------	----------	----------

64481	TEMPORARY PAVEMENT MARKING, REMOVABLE TAPE	L.F.	611.00	611.00
-------	--	------	--------	--------

64484	TEMPORARY PAVEMENT MARKING	L.F.	10,590.00	10,590.00
-------	-------------------------------	------	-----------	-----------

64487	REMOVING PAVEMENT MARKINGS	L.F.	845.00	845.00
-------	-------------------------------	------	--------	--------

64490	PAVEMENT MARKING, DIAGONAL, EPOXY, 12-INCH	L.F.	390.00	390.00
-------	--	------	--------	--------

64497	LOCATING NO-PASSING ZONES	MI.	.25	.25
-------	------------------------------	-----	-----	-----

64506	GEOTEXTILE FABRIC, TYPE HR	S.Y.	469.00	469.00
-------	-------------------------------	------	--------	--------

Sheet 3.2

ITEM	ITEM DESCRIPTION	UNIT	TOTAL	1410-02-70 QUANTITY
64601	SAWING EXISTING PAVEMENT	L.F.	1,935.00	1,935.00
64602	SAWING CONCRETE PAVEMENT, FULL DEPTH	L.F.	48.00	48.00
90001	MODIFIED TUBULAR RAILING TYPE F	L.S.	1.00	1.00
90002	MOVING NON-STANDARD SIGNS	EACH	3.00	3.00
90003	SIGNS, FIXED MESSAGE	S.F.	22.50	22.50

Sheet 3.3

90004	TURBIDITY BARRIER, 4 FT., DELIVERED	L.F.	285.00	285.00
90005	TURBIDITY BARRIER, 4 FT., INSTALLED	L.F.	285.00	285.00
90006	MOVING ALLENTON SIGN	L.S.	1.00	1.00
90402	QUALITY MANAGEMENT PROGRAM, ASPHALTIC MIXTURE	TON	2,413.00	2,413.00
90637	SAFETY FENCE	L.F.	480.00	480.00
90643	SAND BAGS	EACH	30.00	30.00