

11, 12, 13, 14, 15, 16, 17, 18, 19, 20, LEVELS ON -

PAVEMENT MARKING, EPOXY (L.F.)

LOCATION	4" WHITE EDGE LINE	4" YELLOW CENTER LINE	4" WHITE DASHED	12" WHITE DIAGONAL	TOTALS
54+78.3-11+65	2482	2623	75	390	5180
5+50-7+00				390	390

SAFETY FENCE

STATION	LOCATION	L.F.
2+60 TO 6+10 (RT)	TLE LIMIT	480
TOTAL		480

STATE PROJECT NUMBER

1410-02-70

SHEET NO.

313

MISCELLANEOUS QUANTITIES

STH 33WASHINGTON COUNTY

TEMPORARY PAVEMENT MARKING,
REMOVABLE TAPE

LOCATION	TYPE	LF
BYPASS I	4" DOUBLE YELLOW	250
STA. 54+78 - 2+25 (STAGE III)	4" DOUBLE YELLOW	361
TOTAL		611

TURBIDITY BARRIER, 4 FT.

LOCATION	DELIVERED L.F.	INSTALLED L.F.
EAST ABUTMENT	135	135
WEST ABUTMENT	150	150
TOTAL	285	285

PLANT DATA CHART
(DECIDUOUS TALL GROWING TREES)

SYMBOL	COMMON NAME	AVG. MATURE HEIGHT	SIZE WHEN PLANTED	ROOT ZONE MODE	MIN. BALL/POT DIAM.	MIN. BALL/POT DEPTH	MIN. HOLE DIAM	MIN. HOLE DEPTH	BRACE OR GUY	FERT UNITS REOD.	RODENT PROTCT REOD.	MULCH RING DIAM.	QUANTITY
WA	ASH, WHITE	60'	2" CAL.	B&B	24"	16"	36"	16"	GUY	4	YES	48"	4
WG	ASH, GREEN	60'	2" CAL.	B&B	24"	16"	36"	16"	GUY	4	YES	48"	4

* B&B - BALLED AND BURLAPED

TRAFFIC CONTROL (DAYS)

	STAGE I	STAGE II	STAGE III	STAGE IV	TOTALS
DRUMS	624	3835	1612	330	6401
BARRICADES	0	910	156	0	1066
TYPE III					
WARNING LIGHTS	112	2405	494	1080	4091
TYPE A					
WARNING LIGHTS	624	3835	1612	330	6401
TYPE C					
SIGNS	176	1365	312	1500	3353

SILT FENCE

LOCATION	SILT FENCE DELIVERED (L.F.)	SILT FENCE INSTALLED (L.F.)	SILT FENCE MAINTENANCE (L.F.)
54+78.3-6+08 (LT)	755	755	2265
6+63-8100 (LR)	360	360	1080
0+00-2+30 (RT)	365	365	1095
3+00-6+08 (RT)	380	380	1140
6+63-10+00 (RT)	240	240	720
TOTALS	2100	2100	6300

FIXED AND SPECIAL SIGNS

SIGN CODE	SIGN MESSAGE	SIZE (INCHES)	FIXED MESSAGE SIGN (SF)	MOVING NON-STANDARD SIGNS	MOVING ALLEN TON SIGN	WOOD POST 4X6-INCH 16'
FIXED	ACCESS TO WATER TREATMENT FACILITY	60" X 54"	22.5			2
ALLEN TON LIONS				1	1	
AMERICAN LEGION				1		
RIVEREDGE PARK				1		
TOTALS			22.5	3	1	2

TEMPORARY PAVEMENT MARKING

LOCATION	TYPE	LF
BYPASS I	4" DOUBLE YELLOW	1650
MAINLINE I (STAGE II)	4" DOUBLE YELLOW	1880
EDGE LINE	4" WHITE	1880
MAINLINE I (STAGE IV)	4" DOUBLE YELLOW	2590
EDGE LINE	4" WHITE	2590
TOTAL		10590

REMOVING ASPHALTIC PAVEMENT, MILLING

LOCATION	S.Y.
9+68 - 11+63	520
TOTAL	520

SIGNS AND MOVING SIGNS

SIGN CODE	SIGN MESSAGE	SIZE (INCHES)	MOVING SIGNS TYPE II (EACH)	SIGNS TYPE II REFLECTIVE (SF)	WOOD POST 4X4-INCH 10'	WOOD POST 4X6-INCH 16'	REMARKS
J1-1	JCT COUNTY W		1			1	JCT AND COUNTY W SIGNS TO BE PLACED ON ONE
W5-52L	OBJECT MARKER (LT)		2		2		
W5-52R	OBJECT MARKER (RT)		2		2		
R1-1	ALLEN TON INC. STOP		1			2	
	NEW PLAT ST. MAIN ST.		1				SALVAGE EXISTING STEEL POST.
R2-1	SPEED LIMIT 30		1			1	
R2-1	SPEED LIMIT 45		1			1	
W14-3	NO PASSING ZONE		2			2	
W1-4L	REVERSE TURN		1			1	
R7-1R	NO PARKING (RT, ARROW)	18" X 24"		3.0	1		
R7-1L	NO PARKING (LT, ARROW)	18" X 24"		3.0	1		
TOTALS			15	6.0	6	9	

EROSION BALES, SANDBAGS

LOCATION	EROSION BALES DELIVERED (EACH)	EROSION BALES INSTALLED (EACH)	SANDBAGS EACH)
UNDISTRIBUTED	117	117	30
TOTAL	117	117	30

TEMPORARY PRECAST CONCRETE BARRIER

STAGE	DELIVERED (L.F.)	INSTALLED (L.F.)
I	390	390
II	940	1330
III	0	740
IV	0	0
TOTALS	1330	2460