

Project 1440-39-30/60
STH 23
FOND DU LAC - PLYMOUTH
USH 151 - CTH UU
FOND DU LAC COUNTY

	PHOTOLOG	LENGTH FT	MAINLINE WIDTH FT	PAVED FT	PROPOSED SHOULDER		PAVED FT	GRAVEL FT	ASSUMING		2" REMOVING ASPH SURF MILLING 204.0120 SY	REMOVING GUARDRAIL 204.0165 LF	STEEL PLATE BEAM GUARD, CLASS A 614.0305 LF	ASSUMING THE ENTIRE LENGTH SHOULDERS 6" BASE AGGREGATE DENSE 3/4" 305.0110 TON	ASSUMING 15% CONCRETE REPAIR 416.1710 SY	CONTINUOUS DIAMOND GRIND 420.1000 SY	0.06 GAL/SY TACK 455.0605 GAL	2" HMA PAVEMENT 4 MT 58-28 S 460.6224 TON	ASPHALTIC SHLD RUMBLE STRIP 465.0400 LF	ASPH CNTR RUMBLE STRIP 465.0475 LF	PAVT MARK EPOXY 4" 646.0106 LF	GROOVED, WET REFLECTIVE EPOXY PAVT MARKING LF
					LEFT GRAVEL FT	RIGHT GRAVEL FT			ASSUMING REMOVING CURB & GUTTER 204.0150 LF	ASSUMING CURB & GUTTER 30IN TYPE D 601.0411 FT												
EB	2713	2792	4171.2	24		10	2				4,635			386	1,668	11,123	278	556		0	10,428	0
	2792	2844	2745.6	24		8	0				2,441			0	1,098	7,322	146	293			6,864	
	2844	2896	2745.6	24		4	4				1,220			508	1,098	7,322	73	146			6,864	
	2896	2922	1372.8	12		3	3				458			191	275	1,830	27	55			3,432	
WB											8,753			1,085	4,140	27,597	525	1,050			27,588	
TOTALS		11,035	2.09 MI						250	250	17,506 18,381 ADD'L 5%	0	0	2,171	8,279	55,194	1,050	2,101 2,206 ADD'L 5%	0	0	55,176	0