

REMOVING PAVEMENT BUTT JOINTS

(204.0105) REMOVING PAVEMENT BUTT JOINTS		
STATION (TO STATION)	LOCATION	(SY)
597+20.89	STH 96 LT - LEONA ST	62
605+54.6	STH 96 RT - GRANDVIEW RD	62
608+50.7	STH 96 RT - GREEN GROVE RD	62
624+80	STH 96 RT - POTATO POINT RD	48
654+67.1	STH 96 LT - FRENCH RD	43
658+41.3	STH 96 RT - FOX POINT DR.	48
665+69	STH 96 RT - FOX POINT DR.	48
729+34 - 729+81	STH 96 LT & RT - MAIN RD	256
TOTAL		629

REMOVING ASPHALTIC SURFACE BUTT JOINTS

(204.0115) REMOVING ASPHALTIC SURFACE BUTT JOINTS		
STATION (TO STATION)	LOCATION	(SY)
596+23 - 596+73	STH 96 LT & RT	267
722+50	WASHINGTON ST.	189
TOTAL		456

REMOVING GUARDRAIL

(204.0165) REMOVING GUARDRAIL		
STATION (TO STATION)	LOCATION	(LF)
707+57 - 711+25	STH 96 RT	397
711+50 - 712+34	STH 96 RT	110
720+62 - 722+10	STH 96 LT	180
721+15 - 721+70	STH 96 LT	55
723+41	STH 96 RT	50
726+91	STH 96 RT	50
TOTAL		842

EARTHWORK SUMMARY

		(205.0100) EXCAVATION COMMON	FILL	WASTE	REMARKS
STATION (TO STATION)	LOCATION	(CY)	(CY)	(CY)	
596+23 - 705+00	STH 96 LT & RT	147	60	87	REMOVING CURB & GUTTER AREA
686+00 - 704+50	STH 96 LT	530	211	319	DITCH SECTION
TOTAL		677	271	406	

REMOVING CONCRETE SURFACE PARTIAL DEPTH

REMOVING CURB & GUTTER

(204.0150)
REMOVING
CURB & GUTTER

STATION TO	STATION	LOCATION	(LF)	REMARKS
600+95	- 601+14	STH 96 LT	19	CATCH BASIN AREA
604+85	- 604+95	STH 96 RT	10	CATCH BASIN AREA
604+85	- 604+99	STH 96 LT	14	CATCH BASIN AREA
604+93	- 605+09	STH 96 RT	19	RT. RADIUS OF GRANDVIEW RD.
607+78	- 607+93	STH 96 RT	15	CATCH BASIN AREA
607+80	- 607+95	STH 96 LT	15	CATCH BASIN AREA
607+87	- 608+08	STH 96 RT	19	RT. RADIUS OF GREEN GROVE RD.
611+88	- 612+06	STH 96 RT	18	CATCH BASIN AREA
612+97	- 613+07	STH 96 RT	10	CATCH BASIN AREA
612+95	- 613+18	STH 96 LT	23	CATCH BASIN AREA
612+96	- 613+18	STH 96 LT	22	C & G
617+46	- 617+55	STH 96 RT	9	CATCH BASIN AREA
617+46	- 617+54	STH 96 LT	8	CATCH BASIN AREA
619+92	- 620+07	STH 96 RT	15	CATCH BASIN AREA
619+96	- 620+05	STH 96 LT	9	CATCH BASIN AREA
624+10	- 624+28	STH 96 RT	18	CATCH BASIN AREA
626+66	- 626+74	STH 96 LT	8	CATCH BASIN AREA
626+98	- 627+04	STH 96 RT	6	CATCH BASIN AREA
630+43	- 630+53	STH 96 RT	10	CATCH BASIN AREA
630+46	- 630+56	STH 96 LT	10	CATCH BASIN AREA
634+07	- 634+16	STH 96 LT	9	CATCH BASIN AREA
640+44	- 640+54	STH 96 RT	10	CATCH BASIN AREA
640+46	- 640+54	STH 96 LT	8	CATCH BASIN AREA
643+97	- 644+03	STH 96 RT	6	CATCH BASIN AREA
643+94	- 644+05	STH 96 LT	11	CATCH BASIN AREA
646+58	- 646+71	STH 96 LT	13	CATCH BASIN AREA
646+61	- 646+69	STH 96 RT	8	CATCH BASIN AREA
648+50	- 649+80	STH 96 LT	130	C & G

REMOVING SMALL PIPE CULVERTS

		(203.0100) REMOVING SMALL PIPE CULVERTS (EACH)	REMARKS
STATION	LOCATION		
691+30	STH 96 LT	1	15 - INCH CMCP
TOTAL		1	

CLEARING & GRUBBING

		(201.0120) CLEARING (ID)	(201.0220) GRUBBING (ID)
STATION	LOCATION		
648+78	STH 96, 220' LT	12	12
648+81	STH 96, 216' RT	12	12
666+48	STH 96, 198' RT	8	8
666+68	STH 96, 228' RT	6	6
666+73	STH 96, 245' RT	16	16
666+78	STH 96, 227' RT	16	16
TOTAL		70	70

SEALING PIPES

		(204.0280) SEALING PIPES (EACH)	REMARKS
STATION	LOCATION		
648+73	STH 96 RT	1	EXIST. 18-INCH CSP
648+78	STH 96 RT	2	EXIST. 8-INCH RCSP
648+85	STH 96 RT	1	EXIST. 8-INCH CSP
648+95	STH 96 RT	1	EXIST. 8-INCH CSP
649+35	STH 96 LT & RT	2	EXIST. 8-INCH CSP
667+09	STH 96 RT	1	18-INCH CMP
692+45	STH 96 LT	1	15-INCH CMP
702+19	STH 96 LT	1	EXIST. 18-INCH RCSP
TOTAL		10	

GRADING, SHAPING & FINISHING FOR BARRIER TERMINALS

||
||
||

SHAPING SHOULDERS

			(305.0500) SHAPING SHOULDERS (STA)
STATION TO	STATION	LOCATION	
686+10 -	726+84	STH 96 LT	41
705+00 -	729+81	STH 96 RT	25
TOTAL			66

PAVEMENT TIES

			* (416.0610) PAVEMENT TIES (LF)		REMARKS
STATION TO	STATION	LOCATION			
596+98 -	729+37	STH 96 LT & RT	1,103		SEE BASE PATCHING
600+95 -	729+32	STH 96 LT & RT	613		SEE CURB & GUTTER
TOTAL			1,716		

* QUANTITIES ARE SUMMARIZED ELSEWHERE

PAVEMENT DOWEL BARS

			* (416.0620) PAVEMENT DOWEL BARS (EACH)		REMARKS
STATION TO	STATION	LOCATION			
596+98 -	729+37	STH 96 LT & RT	12,241		SEE BASE PATCHING
TOTAL			12,241		

* QUANTITIES ARE SUMMARIZED ELSEWHERE

BASE AGGREGATE ITEMS

			(305.0110) BASE AGGREGATE 3/4-INCH (TON)	(305.0120) BASE AGGREGATE 1 1/4-INCH (TON)	* (624.0100) WATER (MGAL)	(301.0100.S) OMP BASE AGGREGATE (TON)	REMARKS
STATION TO	STATION	LOCATION					
596+23 -	705+00	STH 96 LT & RT	-	201	2		

HMA SUMMARY

STATION (TO STATION)	LOCATION	(460.1100) HMA PAVEMENT TYPE E-0.3 (TON)	(460.1101) HMA PAVEMENT TYPE E-1 (TON)	(455.0105) ASPHALTIC MATERIAL PG58-28 (TON)	(465.0120) ASPHALTIC SURFACE DRIVEWAYS & FIELD ENTRANCES (TON)	(465.0125) ASPHALTIC SURFACE TEMPORARY (TON)	(455.0605) TACK COAT (GAL)	(460.3000) QMP HMA MIXTURE (TON)	(460.4100.S) REHEATING HMA LONG. JOINTS (STA)	REMARKS
596+23 - 729+81	STH 96 RT & LT	-	10,814	637	-	-	5,345	10,814	-	-
686+10 - 726+84	STH 96 LT SHOULDER	465	-	27	-	-	160	465	-	EXISTING SHOULDER AT GUARDRAIL
705+00 - 729+81	STH 96 RT SHOULDER	282	-	17	-	-	110	282	-	EXISTING SHOULDER AT GUARDRAIL
597+20.89	LEONA ST.	-	13	0.8	-	-	5	13	-	-
605+54.6	GRANDVIEW RD	-	13	0.8	-	-	5	13	-	-
608+50.7	GREEN GROVE RD	-	13	0.8	-	-	5	13	-	-
624+80	POTATO POINT RD	-	10	0.6	-	-	4	10	-	-
654+67.1	FRENCH RD	-	9	0.5	-	-	3	9	-	-
658+41.3	FOX POINT DR.	-	10	0.6	-	-	4	10	-	-
665+69	FOX POINT DR.	-	10	0.6	-	-	4	10	-	-
722+27	HISTORICAL MARKER	55	-	2.3	-	-	10	55	-	-
722+50	WASHINGTON ST.	-	23	1.4	-	-	4	23	-	-
665+76 - 667+21	FOX POINT DR.	-	-	-	44	-	-	-	-	DRIVEWAY AT 79 FOX POINT DRIVE
596+23 - 729+81	STH 96	-	-	-	-	-	-	-	402	-
UNDISTRIBUTED	STH 96	-	-	-	-	10	-	-	-</	

CONCRETE PAVEMENT AND BASE PATCHING CONCRETE SUMMARY

STATION (TO STATION)	LOCATION STH 96				SIZE Ft. x Ft.	(390.0303)	(390.0403)	(415.0090)	* (416.0610)	* (416.0620)	* (690.0200)	REMARKS
	WB DRIVING LANE	WB PASSING LANE	EB PASSING LANE	EB DRIVING LANE		BASE PATCHING CONCRETE (SY)	BASE PATCHING CONCRETE SHES (SY)	CONCRETE PAVEMENT 9-INCH (SY)	PAVEMENT TIES (EACH)	PAVEMENT DOWEL BARS (EACH)	SAWING CONCRETE PAVEMENT FULL DEPTH (LF)	
596+98	X	X	X	X	8x48	-	43	-	9	64	114	STORM SEWER REPLACEMENT AREA
597+14	X	X			6x24	-	16	-	2	32	60	INTERSECTION OF LEONA ST.
597+52	X	X			6x24	-	16	-	2	32	60	INTERSECTION OF LEONA ST.
597+55			X	X	6x24	-	16	-	2	32	60	INTERSECTION OF LEONA ST.
597+70	X	X	X		6x36	-	24	-	4	48	90	INTERSECTION OF LEONA ST.
598+45			X	X	6x24	16	-	-	2	32	60	-
599+02	X	X	X		6x36	24	-	-	4	48	90	-
599+59	X	X		X	6x36	24	-	-	2	48	96	-
600+43	X	X	X		6x36	24	-	-	4	48	90	-
601+00	X	X	X	X	8x48	-	43	-	9	64	114	STORM SEWER REPLACEMENT AREA
601+57		X			6x12	8	-</					

CONCRETE PAVEMENT AND BASE PATCHING CONCRETE SUMMARY

STATION (TO STATION)	LOCATION STH 96				SIZE Ft. x Ft.	(390.0303) BASE PATCHING CONCRETE (SY)	(390.0403) BASE PATCHING CONCRETE SHES (SY)	(415.0090) CONCRETE PAVEMENT 9-INCH (SY)	* (416.0610) PAVEMENT TIES (EACH)	* (416.0620) PAVEMENT DOWEL BARS (EACH)	* (690.0200) SAWING CONCRETE PAVEMENT FULL DEPTH (LF)	REMARKS
	WB DRIVING LANE	WB PASSING LANE	EB PASSING LANE	EB DRIVING LANE								
669+43			X	X	6x24	16	-	-	2	32	60	-
669+63			X	X	6x24	16	-	-	2	32	60	-
669+95	X	X	X		6x36	24	-	-	4	48	90	-
670+21		X	X		6x24	16	-	-	2	32	66	-
670+40				X	6x12	8	-	-	-	16	36	-
670+59	X	X		X	6x36	24	-	-	2	48	96	-
670+65	X				6x12	8	-	-	-	16	36	-
671+25	X	X	X		6x36	24	-	-	4	48	90	-
671+43			X	X	6x24	16	-	-	2	32	60	-
671+61	X	X			6x24	16	-	-	2	32	60	-
671+89		X			6x12	8	-	-	-	16	36	-

SAWING EXISTING PAVEMENT

STATION (TO STATION)	LOCATION	(690.0100) SAWING EXISTING PAV'T (LF)	(690.0200) SAWING CONCRETE PAV'T FULL DEPTH (LF)	REMARKS
596+23	STH 96 LT & RT	48	-	-
597+20.89	STH 96 LT - LEONA ST.	48	-	-
605+54.6	STH 96 RT - GRANDVIEW RD	48	-	-
608+50.7	STH 96 RT - GREEN GROVE RD	48	-	-
624+80	STH 96 RT - POTATO POINT R	41	-	-
654+67.1	STH 96 LT - FRENCH RD	30	-	-
658+41.3	STH 96 RT - FOX POINT DR.	43	-	-
665+69	STH 96 RT - FOX POINT DR.	43	-	-
722+50	WASHINGTON ST.	50	-	-
729+81	STH 96 LT & RT	42	-	-
600+95 - 702+26	STH 96 LT & RT	-	1,500	CURB AND GUTTER REMOVAL
595+33 - 729+37	STH 96 LT & RT	-	23,110	BASE PATCHING
665+78	STH 96 RT	22	-	DRIVEWAY 79 FOX POINT DRIVE
TOTAL		463	24,610	

