

Project 4110-30-00
USH 45
CITY OF FOND DU LAC
MERRILL AVENUE - JOHNSON AVENUE
FOND DU LAC COUNTY

RP	STATION	Photolog	LENGTH FT	EXISTING								PROPOSED								EXISTING FACE TO FACE FT	PROPOSED FACE TO FACE FT	REMOVING PAVEMENT 204.0100 SY	REMOVING CURB & GUTTER 204.0150 FT	REMOVING CONC SIDEWALK 204.0155 SY	COMMON EXCAVATION 205.0100 CY	305.0120						16" BREAKER RUN TON	415.0900 CONCRETE PAVT 9-IN SY	601.0411 CONCRETE C&G 30", TYPE D LF	602.0405 CONCRETE SIDEWALK 4-IN SF	608.0324 SS PIPE REINFORCED CONC CLASS III LF	611.0201 MANHOLES TYPE 1 EA	611.0530 MH COVERS TYPE J EA	611.0303 INLETS TYPE 3 EA	611.0624 INLET COVERS TYPE H EA	PAVT MARK EPOXY 4 " 646.0106 LF
				MAINLINE WIDTH FT	PARKING				MAINLINE WIDTH FT	BIKE LANE(S) FT	PARKING				6" CABG (MAINLINE) CF	6" CABG (MAINLINE) CY	6" CABG (MAINLINE) TON	CABC (SHLD) CF	CABC (SHLD) CY							CABC (SHLD) TON															
					PAVED FT	GRAVEL FT	PAVED FT	GRAVEL FT			PAVED FT	GRAVEL FT	PAVED FT	GRAVEL FT																											
MERRIL - REES	(-)1+00 TO 4+50	2404	2414.5	554	48	4.75	0.00	4.75	0.00	36	8	6.00	0.00	6.00	0.00	60.00	61.00	3,542	1,109	1,170	2,505	16,909	626	1,253	0	0	0	2,683	3,450	1,109	6,098	632	1	1	4	4	2,218				
REES - JOHNSON	4+50 TO 9+00	2414.5	2423	449	58	0.00	0.00	0.00	0.00	60	8	0.00	0.00	0.00	0.00	60.00	73.00	2,867	898	947	2,427	16,381	607	1,213	0	0	0	2,637	3,391	898	4,937	525	1	1	3	3	1,795				
TOTALS				1,003														6,409	2,006	2,118	4,932	2,466						0	5,320	6,841	2,006	11,035	1,157	3	3	8	8	4,013			
0.19 mi																																									

NOTE:

PAVT CALCS ARE BASED ON ASSUMPTIONS MADE WITHIN THE SCOPING PROCESS; A PAVEMENT DESIGN IS REQUIRED
LANE WIDTHS/NUMBER OF LANES ARE ALSO AN ASSUMPTION