

## **NOTES TO CONSTRUCTION**

**PROJECT I.D. 8357-01-72  
T Russell, Little Sand Bay Road  
Old CTH K - Termini  
Local Street  
Bayfield County**

- 1) Proper erosion control measures must be used and maintained during all phases of construction. An erosion control implementation plan (ECIP) must be developed by the contractor and submitted to the WisDNR at:

Attn: Shawn Haseleu  
810 W. Maple Street  
Spooner, WI 54801

The ECIP must be developed by the contractor and submitted 14 days prior to the preconstruction conference.

- 2) If erosion mat is used along stream banks, WisDNR recommends that biodegradable non-netted mat be used. The contractor should restrict the removal of vegetative cover and exposure of bare ground to the minimum amounts necessary to complete construction. Restoration of disturbed soils should take place as soon as conditions permit.