

HIGHWAY WORK PROPOSALWisconsin Department of Transportation
DT1502 4/2004 s.66.29(7) Wis. Stats.

Proposal Number:

18

<u>COUNTY</u>	<u>STATE PROJECT ID</u>	<u>FEDERAL PROJECT ID</u>	<u>PROJECT DESCRIPTION</u>	<u>HIGHWAY</u>
Racine	3180-10-70		Burlington Bypass STH 83 (South) to STH 36/83 (North) Paving	STH 11

**ADDENDUM
REQUIRED
ATTACHED AT BACK**

This proposal, submitted by the undersigned bidder to the Wisconsin Department of Transportation, is in accordance with the advertised request for proposals. The bidder is to furnish and deliver all materials, and to perform all work for the improvement of the designated project in the time specified, in accordance with the appended Proposal Requirements and Conditions.

Proposal Guaranty Required, \$ 100,000.00 Payable to: Wisconsin Department of Transportation	Attach Proposal Guaranty on back of this PAGE.
Bid Submittal Due Date: July 10, 2007 Time (Local Time): 9:00 AM	Firm Name, Address, City, State, Zip Code
Contract Completion Time October 31, 2008	SAMPLE NOT FOR BIDDING PURPOSES
Assigned Disadvantaged Business Enterprise Goal %	This contract is exempt from federal oversight.

This certifies that the undersigned bidder, duly sworn, is an authorized representative of the firm named above; that the bidder has examined and carefully prepared the bid from the plans, Highway Work Proposal, and all addenda, and has checked the same in detail before submitting this proposal or bid; and that the bidder or agents, officer, or employees have not, either directly or indirectly, entered into any agreement, participated in any collusion, or otherwise taken any action in restraint of free competitive bidding in connection with this proposal bid.

Do not sign, notarize, or submit this Highway Work Proposal when submitting an electronic bid on the Internet.

Subscribed and sworn to before me this date _____

(Signature, Notary Public, State of Wisconsin)_____
(Print or Type Name, Notary Public, State Wisconsin)_____
(Date Commission Expires)

Notary Seal

(Bidder Signature)_____
(Print or Type Bidder Name)_____
(Bidder Title)**For Department Use Only**

Type of Work Grading, paving, drainage structures, dense graded base, concrete curb and gutter, asphaltic concrete pavement, traffic signals, Structures B-51-95 and B-51-101, box culvert extension C-51-22, and incidentals.	
Notice of Award Dated	Date Guaranty Returned

**PLEASE ATTACH
PROPOSAL GUARANTY HERE**

Effective with August 2005 Letting

PROPOSAL REQUIREMENTS AND CONDITIONS

The bidder, signing and submitting this proposal, agrees and declares as a condition thereof, to be bound by the following conditions and requirements.

The bidder declares that they have carefully examined the site of, and the proposal, plans, specifications and contract forms for the work contemplated, and it is assumed that the bidder has investigated and is satisfied as to the conditions to be encountered, as to the character, quality, and quantities of work to be performed and materials to be furnished, and as to the requirements of the specifications, special provisions and contract. It is mutually agreed that submission of a proposal shall be considered conclusive evidence that the bidder has made such examination.

The bidder submits herewith a proposal guaranty in proper form and amount payable to the party as designated in the advertisement inviting proposals, to be retained by and become the property of the owner of the work in the event the undersigned shall fail to execute the contract and contract bond and return the same to the office of the engineer within fourteen (14) days after having been notified in writing to do so; otherwise to be returned.

The bidder declares that they understand that the estimate of quantities in the attached schedule is approximate only and that the attached quantities may be greater or less in accordance with the specifications.

The bidder agrees to perform the said work, for and in consideration of the payment of the amount becoming due on account of work performed, according to the unit prices bid in the following schedule, and to accept such amounts in full payment of said work.

The bidder declares that all of the said work will be performed at their own proper cost and expense, that they will furnish all necessary materials, labor, tools, machinery, apparatus, and other means of construction in the manner provided in the applicable specifications and the approved plans for the work together with all standard and special designs that may be designed on such plans, and the special provisions in the contract of which this proposal will become a part, if and when accepted. The bidder further agrees that the applicable specifications and all plans and working drawings are made a part hereof, as fully and completely as if attached hereto.

The bidder, if awarded the contract, agrees to begin the work not later than ten (10) days after the date of written notification from the engineer to do so, unless otherwise stipulated in the special provisions.

The bidder declares that if they are awarded the contract, they will execute the contract agreement and begin and complete the work within the time named herein, and they will file a good and sufficient surety bond for the amount of the contract for performance and also for the full amount of the contract for payment.

The bidder, if awarded the contract, shall pay all claims as required by Section 779.14, Statutes of Wisconsin, and shall be subject to and discharge all liabilities for injuries pursuant to Chapter 102 of the Statutes of Wisconsin, and all acts amendatory thereto. They shall further be responsible for any damages to property or injury to persons occurring through their own negligence or that of their employees or agents, incident to the performance of work under this contract, pursuant to the Standard Specifications for Road and Bridge Construction applicable to this contract.

In connection with the performance of work under this contract, the contractor agrees to comply with all applicable state and federal statutes relating to non-discrimination in employment. No otherwise qualified person shall be excluded from employment or otherwise be subject to discrimination in employment in any manner on the basis of age, race, religion, color, gender, national origin or ancestry, disability, arrest or conviction record (in keeping with s.111.32), sexual orientation, marital status, membership in the military reserve, honesty testing, genetic testing, and outside use of lawful products. This provision shall include, but not be limited to the following: employment, upgrading, demotion or transfer; recruitment or recruitment advertising; layoff or termination; rates of pay or other forms of compensation, and selection for training, including apprenticeship. The contractor further agrees to ensure equal opportunity in employment to all applicants and employees and to take affirmative action to attain a representative workforce.

The contractor agrees to post notices and posters setting forth the provisions of the nondiscrimination clause, in a conspicuous and easily accessible place, available for employees and applicants for employment.

If a state public official (section 19.42, Stats.) or an organization in which a state public official holds at least a 10% interest is a party to this agreement, this contract is voidable by the state unless appropriate disclosure is made to the State of Wisconsin Ethics Board.

BID PREPARATION

Preparing the Proposal Schedule of Items

A General

- (1) Obtain bidding proposals as specified in **section 102** of the standard specifications. Submit bidding proposals using one of the following methods:
 1. Electronic bid on the internet.
 2. Electronic bid on a printout with accompanying diskette.
 3. Paper bid under a waiver of the electronic submittal requirements.
- (2) Bids submitted on a printout with accompanying diskette or paper bids submitted under a waiver of the electronic submittal requirements govern over bids submitted on the internet.
- (3) The department will provide bidding information through the department's web site at <http://www.dot.wisconsin.gov/business/engrserv/bid-letting-information.htm>. The contractor is responsible for reviewing this web site for general notices as well as information regarding proposals in each letting. The department will also post special notices of all addenda to each proposal through this web site no later than 4:00 P.M. local time on the Thursday before the letting. Check the department's web site after 5:00 P.M. local time on the Thursday before the letting to ensure all addenda have been accounted for before preparing the bid. When bidding using methods 1 and 2 above, check the Bid Express™ on-line bidding exchange at <http://www.bidx.com/> after 5:00 P.M. local time on the Thursday before the letting to ensure that the latest schedule of items Expedite file (*.ebs or *.00x) is used to submit the final bid.
- (4) Interested parties can subscribe to the Bid Express™ on-line bidding exchange by following the instructions provided at the www.bidx.com web site or by contacting:

Info Tech Inc.
5700 SW 34th Street, Suite 1235
Gainesville, FL 32608-5371
email: <mailto:customer.support@bidx.com>

- (5) The department will address equipment and process failures, if the bidder can demonstrate that those failures were beyond their control.
- (6) Contractors are responsible for checking on the issuance of addenda and for obtaining the addenda. Notice of issuance of addenda is posted on the department's web site at <http://www.dot.wisconsin.gov/business/engrserv/bid-letting-information.htm> or by calling the department at (608) 266-1631. Addenda can ONLY be obtained from the departments web site listed above or by picking up the addenda at the Bureau of Highway Construction, Room 601, 4802 Sheboygan Avenue, Madison, WI, during regular business hours.

B Submitting Electronic Bids


B.1 On the Internet

- (1) Do the following before submitting the bid:
 1. Have a properly executed annual bid bond on file with the department.
 2. Have a digital ID on file with and enabled by Info Tech Inc. Using this digital ID will constitute the bidder's signature for proper execution of the bidding proposal.
- (2) In lieu of preparing, delivering, and submitting the proposal as specified in **102.6** and **102.9** of the standard specifications, submit the proposal on the internet as follows:
 1. Download the latest schedule of items reflecting all addenda from the Bid Express™ web site.
 2. Use Expedite™ software to enter a unit price for every item in the schedule of items.

3. Submit the bid according to the requirements of Expedite™ software and the Bid Express™ web site. Do not submit a bid on a printout with accompanying diskette or a paper bid. If the bidder does submit a bid on a printout with accompanying diskette or a paper bid in addition to the internet submittal, the department will disregard the internet bid.
 4. Submit the bid before the hour and date the Notice to Contractors designates.
 5. Do not sign, notarize, and return the bidding proposal described in 102.2 of the standard specifications.
- (3) The department will not consider the bid accepted until the hour and date the Notice to Contractors designates.

B.2 On a Printout with Accompanying Diskette

- (1) Download the latest schedule of items from the Wisconsin pages of the Bid Express™ web site reflecting the latest addenda posted on the department's web site at <http://www.dot.wisconsin.gov/business/engrserv/bid-letting-information.htm>. Use Expedite™ software to prepare and print the schedule of items. Provide a valid amount for all price fields. Follow instructions and review the help screens provided on the Bid Express™ web site to assure that the schedule of items is prepared properly.
- (2) Staple an 8 1/2 by 11 inch printout of the Expedite™ generated schedule of items to the other proposal documents submitted to the department as a part of the bidder's sealed bid. As a separate submittal not in the sealed bid envelop but due at the same time and place as the sealed bid, also provide the Expedite™ generated schedule of items on a 3 1/2 inch computer diskette. Label each diskette with the bidder's name, the 4 character department-assigned bidder identification code from the top of the bidding proposal, and a list of the proposal numbers included on that diskette as indicated in the following example:



- (3) If bidding on more than one proposal in the letting, the bidder may include all proposals for that letting on one diskette. Include only submitted proposals with no incomplete or other files on the diskette.
- (4) The bidder-submitted printout of the Expedite™ generated schedule of items is the governing contract document and must conform to the requirements of section 102 of the standard specifications. If a printout needs to be altered, cross out the printed information with ink or typewriter and enter the new information and initial it in ink. If there is a discrepancy between the printout and the diskette, the department will analyze the bid using the printout information.
- (5) In addition to the reasons specified in section 102 of the standard specifications, proposals are irregular and the department may reject them for one or more of the following:
 1. The check code printed on the bottom of the printout of the Expedite™ generated schedule of items is not the same on each page.

2. The check code printed on the printout of the Expedite™ generated schedule of items is not the same as the check code for that proposal provided on the diskette.
3. The diskette is not submitted at the time and place the department designates.

C Waiver of Electronic Submittal

- (1) The bidder may request a waiver of the electronic submittal requirements. Submit a written request for a waiver in lieu of bids submitted on the internet or on a printout with accompanying diskette. The department will waive the electronic submittal requirements for a bidding entity (individual, partnership, joint venture, corporation, or limited liability company) for up to 4 individual proposals in a calendar year. The department may allow additional waivers for equipment malfunctions.
- (2) Submit a schedule of items on paper conforming to [section 102](#) of the standard specifications. The department charges the bidder a \$75 administrative fee per proposal, payable at the time and place the department designates for receiving bids, to cover the costs of data entry. The department will accept a check or money order payable to: "Wisconsin, Dept. of Transportation."
- (3) In addition to the reasons specified in [section 102](#) of the standard specifications, proposals are irregular and the department may reject them for one or more of the following:
 1. The bidder fails to provide the written request for waiver of the electronic submittal requirements.
 2. The bidder fails to pay the \$75 administrative fee before the time the department designates for the opening of bids.
 3. The bidder exceeds 4 waivers of electronic submittal requirements within a calendar year.
- (4) In addition to the reasons specified in [section 102](#) of the standard specifications, the department may refuse to issue bidding proposals for future contracts to a bidding entity that owes the department administrative fees for a waiver of electronic submittal requirements.

PROPOSAL BID BOND

DT1303 1/2006

Wisconsin Department of Transportation

Proposal Number	Project Number	Letting Date
Name of Principal		
Name of Surety	State in Which Surety is Organized	

We, the above-named Principal and the above-named Surety, are held and firmly bound unto the State of Wisconsin in the sum equal to the Proposal Guaranty for the total bid submitted for the payment to be made; we jointly and severally bind ourselves, our heirs, executors, administrators, successors and assigns. The condition of this obligation is that the Principal has submitted a bid proposal to the State of Wisconsin acting through the Department of Transportation for the improvement designated by the Proposal Number and Letting Date indicated above.

If the Principal is awarded the contract and, within the time and manner required by law after the prescribed forms are presented for signature, enters into a written contract in accordance with the bid, and files the bond with the Department of Transportation to guarantee faithful performance and payment for labor and materials, as required by law, or if the Department of Transportation shall reject all bids for the work described, then this obligation shall be null and void; otherwise, it shall be and remain in full force and effect. In the event of failure of the Principal to enter into the contract or give the specified bond, the Principal shall pay to the Department of Transportation **within 10 business days of demand** a total equal to the Proposal Guaranty as liquidated damages; the liability of the Surety continues for the full amount of the obligation as stated until the obligation is paid in full.

The Surety, for value received, agrees that the obligations of it and its bond shall not be impaired or affected by any extension of time within which the Department of Transportation may accept the bid; and the Surety does waive notice of any such extension.

IN WITNESS, the Principal and Surety have agreed and have signed by their proper officers and have caused their corporate seals to be affixed this date: **(DATE MUST BE ENTERED)**

PRINCIPAL

(Company Name) **(Affix Corporate Seal)**

(Signature and Title)

(Company Name)

(Signature and Title)

(Company Name)

(Signature and Title)

(Company Name)

(Signature and Title)

NOTARY FOR PRINCIPAL

(Date)

State of Wisconsin)
) ss.
_____ County)

On the above date, this instrument was acknowledged before me by the named person(s).

(Signature, Notary Public, State of Wisconsin)

(Print or Type Name, Notary Public, State of Wisconsin)

(Date Commission Expires)

Notary Seal

(Name of Surety) **(Affix Seal)**

(Signature of Attorney-in-Fact)

NOTARY FOR SURETY

(Date)

State of Wisconsin)
) ss.
_____ County)

On the above date, this instrument was acknowledged before me by the named person(s).

(Signature, Notary Public, State of Wisconsin)

(Print or Type Name, Notary Public, State of Wisconsin)

(Date Commission Expires)

Notary Seal

IMPORTANT: A certified copy of Power of Attorney of the signatory agent must be attached to the bid bond.

CERTIFICATE OF ANNUAL BID BOND

DT1305 8/2003

Wisconsin Department of Transportation

Time Period Valid (From/To)	
Name of Surety	
Name of Contractor	
Certificate Holder	Wisconsin Department of Transportation

This is to certify that an annual bid bond issued by the above-named Surety is currently on file with the Wisconsin Department of Transportation.

This certificate is issued as a matter of information and conveys no rights upon the certificate holder and does not amend, extend or alter the coverage of the annual bid bond.

Cancellation: Should the above policy be cancelled before the expiration date, the issuing surety will give thirty (30) days written notice to the certificate holder indicated above.

(Signature of Authorized Contractor Representative)

(Date)

FEBRUARY 1999

LIST OF SUBCONTRACTORS

Section 66.29(7), Wisconsin Statutes, provides that a bidder, as a part of his proposal, shall submit a list of the subcontractors he proposes to contract with and the class of work to be performed by each, provided that to qualify for such listing each subcontractor must first submit his bid in writing to the general contractor at least 48 hours prior to the time of bid closing. It further provides that a proposal of a bidder shall not be invalid if any subcontractor, and the class of work to be performed by such subcontractor, has been omitted from a proposal.

No subcontract, whether listed herein or later proposed, may be entered into without the written consent of the Engineer as provided in Subsection 108.1 of the Standard Specifications.

Name of Subcontractor	Class of Work	Estimated Value
_____	_____	_____
_____	_____	_____
_____	_____	_____
_____	_____	_____
_____	_____	_____
_____	_____	_____
_____	_____	_____

DECEMBER 2000

**CERTIFICATION REGARDING DEBARMENT, SUSPENSION, AND OTHER
RESPONSIBILITY MATTERS - PRIMARY COVERED TRANSACTIONS**

Instructions for Certification

1. By signing and submitting this proposal, the prospective contractor is providing the certification set out below.
2. The inability of a person to provide the certification required below will not necessarily result in denial of participation in this covered transaction. The prospective contractor shall submit an explanation of why it cannot provide the certification set out below. The certification or explanation will be considered in connection with the department or agency's determination whether to enter into this transaction. However, failure of the prospective contractor to furnish a certification or an explanation shall disqualify such person from participation in this transaction.
3. The certification in this clause is a material representation of fact upon which reliance was placed when the department determined to enter into this transaction. If it is later determined that the contractor knowingly rendered an erroneous certification in addition to other remedies available to the Federal Government the department may terminate this transaction for cause or default.
4. The prospective contractor shall provide immediate written notice to the department to whom this proposal is submitted if at any time the prospective contractor learns that its certification was erroneous when submitted or has become erroneous by reason of changed circumstances.
5. The terms "covered transaction," "debarred," "suspended," "ineligible," "lower tier covered transaction," "participant," "person," "primary covered transaction," "principal," "proposal," and "voluntarily excluded," as used in this clause, have the meanings set out in the Definitions and Coverage sections of the rules implementing Executive Order 12549. You may contact the department to which this proposal is being submitted for assistance in obtaining a copy of those regulations.
6. The prospective contractor agrees by submitting this proposal that, should this contract be entered into, it shall not knowingly enter into any lower tier covered transaction with a person who is debarred, suspended, declared ineligible, or voluntarily excluded from participation in this covered transaction, unless authorized by the department entering into this transaction.
7. The prospective contractor further agrees by submitting this proposal that it will include the clause titled "Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion-Lower Tier Covered Transaction," which is included as an addendum to PR-1273 - "Required Contract Provisions Federal Aid Construction Contracts," without

modification, in all lower tier covered transactions and in all solicitations for lower tier covered transactions.

8. The contractor may rely upon a certification of a prospective subcontractor/materials supplier that it is not debarred, suspended, ineligible, or voluntarily excluded from the covered transaction, unless it knows that the certification is erroneous. A contractor may decide the method and frequency by which it determines the eligibility of its principals. Each contractor may, but is not required to, check the Disapproval List (telephone # 608/266/1631).
9. Nothing contained in the foregoing shall be construed to require establishment of a system of records in order to render in good faith the certification required by this clause. The knowledge and information of a contractor is not required to exceed that which is normally possessed by a prudent person in the ordinary course of business dealings.
10. Except for transactions authorized under paragraph 6 of these instructions, if a contractor in a covered transaction knowingly enters into a lower tier covered transaction with a person who is suspended, debarred, ineligible or voluntarily excluded from participation in this transaction, in addition to other remedies available to the Federal Government, the department may terminate this transaction for cause or default.

Certification Regarding Debarment, Suspension, and Other Responsibility Matters - Primary Covered Transactions

- (1) The prospective contractor certifies to the best of its knowledge and belief, that it and its principals:
 - (a) Are not presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from covered transactions by any Federal department or agency;
 - (b) Have not within a three-year period preceding this proposal been convicted of or had a civil judgment rendered against them for commission of fraud or a criminal offense in connection with obtaining, attempting to obtain, or performing a public (Federal, State or local) transaction or contract under a public transaction; violation of Federal or State antitrust statutes or commission of embezzlement, theft, forgery, bribery, falsification or destruction of records, making false statements or receiving stolen property;
 - (c) Are not presently indicted for or otherwise criminally or civilly charged by a governmental entity (Federal, State or local) with commission of any of the offense enumerated in paragraph (1)(b) of this certification; and
 - (d) Have not within a three-year period preceding this proposal had one or more public transactions (Federal, State or local) terminated for cause or default.
- (2) Where the prospective contractor is unable to certify to any of the statements in this certification, such prospective contractor shall attach an explanation to this proposal.

Special Provisions

Table of Contents

Article	Description	Page #
1.	General.....	3
2.	Scope of Work.	3
3.	Prosecution and Progress.	3
4.	Traffic.	5
5.	Holiday Work Restrictions.	9
6.	Utilities.....	10
7.	Construction Over or Adjacent to Navigable Waters.	14
8.	Erosion Control.....	14
9.	Information to Bidders Wetlands.....	14
10.	Hauling Restrictions.....	15
11.	Other Contracts.	15
12.	Project Meetings.	16
13.	Temporary Items to Remain After Construction.	16
14.	Removing Pavement.	17
15.	Removing Retaining Wall, Item 204.9060.S.01.	17
16.	Grading, Shaping and Finishing for Barrier Terminals, Item 205.9006.S.....	18
17.	Backfill Granular.	18
18.	QMP Base Aggregate, Item 301.0100.S.....	18
19.	Base Aggregate Dense 1 1/4-Inch for Lower Base Layers.....	30
20.	QMP Concrete Ancillary.	30
21.	QMP Concrete Pavement, Item 415.3000.S; Incentive Strength Concrete Pavement, Item 415.2000.S.	36
22.	QMP HMA Pavement Nuclear Density, Item 460.2500.S.	51
23.	QMP Concrete Structures; Incentive Strength Concrete Structures, Item 502.0400.S.	57
24.	Culvert Pipe.	73
25.	Concrete Barrier Temporary Precast Contractor Furnished & Delivered.	74
26.	Steel Thrie Beam Bullnose Terminal, Item 614.0220.S; Steel Thrie Beam, Item 614.0230.S.	74
27.	Steel Plate Beam Guard Class A.....	76
28.	Marker Posts Culvert End Flexible, Item 614.0620.S.	76
29.	Stone or Rock Ditch Checks, Item 628.7560.S.	77
30.	Proving Period, Signs and Sign Posts.	78
31.	Signs Reflective Type II.	79
32.	Field Facilities.....	79
33.	Traffic Control.	80
34.	Traffic Control Covering Signs, Item 643.0905.S.....	81
35.	Traffic Control Signs Portable Changeable Message, Item 643.1050.S.....	82
36.	Pavement Marking Wet Reflective Tape 4-Inch, Item 646.0871.S.....	87

37.	Construction Staking Base, Item 650.5000.....	88
38.	Electrical Service Meter Breaker Pedestal STH 11/36/83 and STH 83, Item 656.0200.01; STH 11 and STH 36/83, Item 656.0200.02.	88
39.	QMP Subgrade, Item SPV.0035.01.	89
40.	Concrete Base, Type 9, Monotube, Item SPV.0060.01.	97
41.	Apron Endwalls for Underdrain Reinforced Concrete 12-Inch, Item SPV.0060.02.	97
42.	Cover Signs, Type I, Item SPV.0060.03.....	97
43.	Erosion Control Filter Bags, Item SPV.0060.04.....	98
44.	Sand Bags, Item SPV.0060.05.....	99
45.	Traffic Signals and Street Lighting, STH 11/36/83 and STH 83, Item SPV.0105.01; STH 11 and STH 36/83, Item SPV.0105.02.	100
46.	Temporary Diversion Channel, Item SPV.0105.03.....	101
47.	Architectural Surface Treatment, Item SPV.0165.01.	102
48.	Concrete Staining, Item SPV.0165.02.	104
49.	Covering Signs Type II, Item SPV.0165.03.	106
50.	Test Rolling, Item SPV.0170.01.	107
51.	Geotextile Fabric Type FF, Item SPV.0180.01.	108
52.	Washed Stone, Item SPV.0195.01.....	108

SPECIAL PROVISIONS

1. General.

Perform the work under this construction contract for Project 3180-10-70, STH 83 (South) to STH 36/83 (North), STH 11, Racine County, Wisconsin as the plans show and execute the work as specified in the State of Wisconsin, Department of Transportation, Standard Specifications for Highway and Structure Construction, 2003 Edition, the Supplemental Specifications 2006 Edition, and these special provisions including the Additional Special Provisions (ASPs). The department considers only standard specifications, supplemental specifications and interim supplemental specifications issued directly from the department as valid for this contract.

If all or a portion of the plans and special provisions are developed in the SI metric system and the schedule of prices is developed in the US standard measure system, the department will pay for the work as bid in the US standard system.
(100906)

2. Scope of Work.

The work under this contract shall consist of grading, paving, drainage structures, dense graded base, concrete curb and gutter, asphaltic concrete pavement, traffic signals, Structures B-51-95, B-51-101, C-51-22, and all incidental items necessary to complete the work as shown on the plans and included in the proposal and contract.
(082003) 104-005

3. Prosecution and Progress.

Begin work within ten calendar days after the engineer issues a written notice to proceed.

Provide the start date to the engineer in writing within a month after executing the contract but at least 14 calendar days before the preconstruction conference. Upon approval, the engineer will issue the notice to proceed within ten calendar days before the approved start date.

To revise the start date, submit a written request to the engineer at least two weeks before the intended start date. The engineer will approve or deny that request based on the conditions cited in the request and its effect on the department's scheduled resources.

When in the fall of 2007, weather conditions or seasonal restrictions preclude the satisfactory performance of further work under this contract, the engineer will, in writing, suspend operations until the spring of 2008. Resume construction operations in the spring

of 2008 within ten days after the date on which a written order to do so has been issued by the engineer.

The schedule of operations shall conform to construction staging as described in the plans, unless the engineer approves modifications in the plans in writing. A general description of construction staging plans is as follows:

Construct driveway approaches as shown on the plans. Inform property owners and tenants at least 48 hours prior to removing a driveway approach that severs that property. Schedule driveway approach removal and replacement so that the time lapse between removal and replacement is minimal.

If the contractor can make other access arrangements, agreed in writing and signed by the contractor and the property owner serviced by the driveway, other arrangements will be allowed when approved by the engineer.

Submit all traffic control change requests to the engineer at least 24 hours prior to an actual traffic control change. A request does not constitute approval.

Modify 108.11 of the standard specifications by adding the following to the end of the subsection:

Each day shall be defined as a twenty-four hour period beginning at 12:01 AM.

Supplement 108.11 as follows:

Interim Completion Date, June 1, 2008.

If the contractor fails to complete all of the work necessary to open STH 83 to through traffic on a paved surface finished or temporary from Hidden Creek Lane to the north construction limit prior to 12:01 AM June 1, 2008, the department will assess the contractor \$ 1000 in interim liquidated damages for each calendar day that all of the work necessary to open STH 83 to through traffic on a paved surface finished or temporary from Hidden Creek Lane to the north construction limit is not completed after 12:01 AM June 1, 2008. An entire calendar day will be charged for any period of time within a calendar day that the road remains closed beyond 12:01 AM.

Interim Completion Date, August 1, 2008.

If the contractor fails to complete the contract work necessary to open Brever and Ketterhagen Roads to through traffic prior to 12:01 AM August 1, 2008, the department will assess the contractor \$ 1000 in interim liquidated damages for each calendar day that Brever Road or Ketterhagen Road, or both, remain closed after 12:01 AM August 1, 2008. An entire calendar day will be charged for any period of time within a calendar day that Brever Road or Ketterhagen Road, or both, remain closed beyond 12:01 A.M.

Interim Completion Date, October 17, 2008.

If the contractor fails to complete the contract work necessary to open STH 83 to through traffic prior to 12:01 AM October 17, 2008, the department will assess the contractor \$ 1000 in interim liquidated damages for each calendar day that the roadway remains closed after 12:01 AM October 17, 2008. An entire calendar day will be charged for any period of time within a calendar day that the road remains closed beyond 12:01 AM.

The department will not grant time extensions to the interim completion dates specified above for the following:

1. Severe weather as specified in 108.10.2.2.
2. Labor disputes that are not industry wide.
3. Delays in material deliveries.

If contract time expires before completing all work specified in the contract, additional liquidated damages will be affixed in accordance with 108.11 of the standard specifications.

4. Traffic.

Accomplish the construction sequence, including the associated traffic control and detours, as detailed on the plans and described herein.

Detours

Detour traffic as shown on the plans. Install required traffic control and detour signs as shown on the plans prior to commencing stage construction and remove after completion of the project. Cover advance-warning signs and detour signs until work begins.

Property Owner Access

Construct commercial property driveway approaches in stages or provide temporary access at all times during the life of the contract.

Conduct construction operations in such a manner as to provide access to emergency vehicles at all times.

Do not park or store vehicles, equipment and materials within 50 feet from the edge of any active traffic lane.

Employ such flag persons, signs, barricades and drums as may be necessary to safeguard and direct traffic at all locations where construction operations may interfere with or restrict, the smooth flow of traffic. Make arrangements and be responsible for the prompt replacement of damaged or dislocated traffic control or guidance signs, day or night.

Traffic Control Stages

Traffic Control Stage I (Scheduled to begin September 4, 2007)

Burlington Bypass: Closed to traffic.

STH 83: Open to traffic, no construction. Ensure that existing traffic control, placed under Project 3180-08-70 blocking access to the Bypass, remains in place and is maintained.

Breuer Road: Close Breuer Road at STH 142 and Hoosier Creek Road. Place fills for structure embankments. Maintain paved access to last private access prior to Structure B-51-95. Leave existing Breuer road undisturbed or use temporary asphaltic pavement to provide access for local residents through winter suspension of construction.

STH 142: Open to traffic, no construction. Ensure that existing traffic control, placed under Project 3180-08-70 blocking access to the Bypass, remains in place and is maintained.

STH 142 Ramps: Closed to traffic, no construction.

STH 11: Open to traffic, no construction. Ensure that existing traffic control, placed under Projects 3180-08-70 and 3180-14-70 blocking access to the Bypass, remains in place and is maintained.

Ketterhagen Road: Close Ketterhagen Road to traffic. Place fills for structure embankments. Maintain paved access to last private access prior to Structure B-51-101 through winter closure. Do not disturb existing Ketterhagen Road or use temporary asphaltic pavement to provide access for local residents through winter suspension of construction.

CTH A: Open to traffic, no construction. Ensure that existing traffic control, placed under Project 3180-08-70 blocking access to the Bypass, remains in place and is maintained.

CTH A Ramps: Closed to traffic, no construction.

STH 36/83 Northbound-Southbound Ramp: Closed to traffic, no construction.

Northbound STH 36/83 and STH 36/83 Northbound Ramp: Open to traffic. Reduce northbound traffic to the median lane prior to closing the STH 36/83 Northbound-Southbound Ramp. Replace drums placed for the lane closure and tapers with temporary concrete barrier wall in preparation for winter construction suspension. Ensure that all remaining existing traffic control devices, placed under Project 3180-09-70, remain in place and are maintained. Coordinate this work with Project 3180-09-70 to provide seamless switchover of traffic control.

Southbound STH 36/83 and STH 36/83 Southbound Ramp: Open to traffic. Reduce southbound traffic to the outside lane prior to the STH 36/83 Southbound Ramp and direct onto the southbound ramp. Replace drums placed for the lane

closure and tapers with temporary concrete barrier wall in preparation for winter construction suspension. Ensure that all remaining existing traffic control devices, placed under Project 3180-09-70, remain in place and are maintained. Coordinate this work with Project 3180-09-70 to provide seamless switchover of traffic control.

Stage 2A (Spring, 2008)

Burlington Bypass: Closed to traffic.

STH 83:

Road closed to traffic; detour STH 83 traffic. Construct temporary diversion channel prior to April 1, 2008. Maintain access for local residents.

Construct STH 83 from Hidden Creek Lane to northern construction limits. Provide paved access to Hidden Creek Lane. Construct STH 83 in stages to allow traffic to use existing pavement or place temporary asphaltic pavement to maintain paved access. Complete construction of STH 83 from Hidden Creek Lane to northern construction limits by June 1, 2008, with the exception of finished surface, signing and pavement marking.

Breuer Road: Breuer Road remains closed. Continue constructing the remaining portions of Breuer Road and Structure B-51-95. Maintain access for local residents; however, the paved access is no longer required after winter construction suspension.

STH 142: Same as Stage 1.

STH 142 Ramps: Closed to traffic

STH 11: Same as Stage 1.

Ketterhagen Road: Ketterhagen Road remains closed. Continue constructing the remaining portions of Ketterhagen Road and Structure B-51-101. Maintain access for local residents; however, the paved access is no longer required after winter construction suspension.

CTH A: Same as Stage 1.

CTH A Ramps: Closed to traffic.

STH 36/83 Northbound-Southbound Ramp: Closed to traffic.

Northbound STH 36/83 and STH 36/83 Northbound Ramp: Maintain traffic control placed in Stage 1.

Southbound STH 36/83 and STH 36/83 Southbound Ramp: Maintain traffic control placed in Stage 1.

Stage 2B (June 1, 2008)

Burlington Bypass: Closed to traffic.

STH 83: Road closed to traffic, detour STH 83 traffic. Complete constructing remaining portions of STH 83. Maintain access for local residents.

STH 83 from Hidden Creek Lane to northern construction limits will be open to traffic, with temporary pavement marking in place. Temporary lane closures required to place finished surface signing and pavement marking. See standard detail drawing “Traffic control for Lane Closure (Suitable for Moving Operation)” for required traffic control. Open STH 83 to traffic prior to October 31, 2008.

Breuer Road: Breuer Road remains closed. Complete construction of the remaining portions of Breuer Road and Structure B-51-95. Maintain access for local residents. At the completion of construction, when finished surface, permanent signing and pavement marking is in place, remove all traffic control and open the roadway to traffic. Open Breuer Road to traffic by August 1, 2008.

STH 142: Traffic control remains in place until completion of Stage 3 construction and the Mainline Bypass is ready to be opened to traffic.

STH 142 Ramps: Closed to traffic. Continue construction of STH 142 Ramps. Road remains closed and traffic control remains in place until completion of Stage 3 construction and the Mainline Bypass is ready to be opened to traffic.

STH 11: Traffic control remains in place until completion of Stage 3 construction and the Mainline Bypass is ready to be opened to traffic.

Ketterhagen Road: Ketterhagen Road remains closed. Complete construction of the remaining portions of Ketterhagen Road and Structure B-51-101. Maintain access for local residents. At the completion of construction, when finished surface, permanent signing and pavement marking is in place, remove all traffic control and open the roadway to traffic. Open Ketterhagen Road to traffic by August 1, 2008.

CTH A: Traffic control remains in place until completion of Stage 3 construction and the Mainline Bypass is ready to be opened to traffic.

CTH A Ramps: Closed to traffic. Continue construction of CTH A Ramp. Road to remain closed and traffic control to remain in place until completion of Stage 3 construction and the Mainline Bypass is ready to be opened to traffic.

STH 36/83 Northbound-Southbound Ramp: Traffic control to remain in place until completion of Stage 3 construction and the Mainline Bypass is ready to be opened to traffic.

Northbound STH 36/83 & STH 36/83 Northbound Ramp: Traffic control remains in place until completion of Stage 3 construction and the Mainline Bypass is ready to be opened to traffic.

Southbound STH 36/83 & STH 36/83 Southbound Ramp: Traffic control remains in place until completion of Stage 3 construction and the Mainline Bypass is ready to be opened to traffic.

Stage 3

Burlington Bypass / STH 83: Place traffic control, permanent signing and pavement marking in preparation of opening the Burlington Bypass to traffic. All traffic control items being placed in Stage 3 at this location will remain in place for up to three years. Coordination with Project 3180-11-70 is required. At the completion of Stage 3, all traffic control along the Mainline Bypass and associated sideroads can be removed. At the completion of Project 3180-10-70, the traffic control placed in Stage 3 will become the maintenance responsibility of the Project 3180-11-70 contractor.

STH 83: After completing Stage 3, remove all traffic control and open to traffic.

STH 142: After completing Stage 3, remove all traffic control.

STH 142 Ramps: After completing Stage 3, remove all traffic control and open to traffic.

STH 11: After completing Stage 3, remove all traffic control.

CTH A: After completing Stage 3, remove all traffic control.

CTH A Ramps: After completing Stage 3, remove all traffic control and open to traffic.

STH 36/83 Northbound-Southbound Ramp: After completing Stage 3, remove all traffic control and open to traffic.

Northbound STH 36/83 & STH 36/83 Northbound Ramp: After completing Stage 3, remove all traffic control and open to traffic.

Southbound STH 36/83 & STH 36/83 Southbound Ramp: After completing Stage 3, remove all traffic control and open to traffic.

5. Holiday Work Restrictions.

Do not perform work on, nor haul materials of any kind along or across any portion of the highway carrying STH 36, STH 83, STH 142 or STH 11 traffic, and entirely clear the

traveled way and shoulders of such portions of the highway of equipment, barricades, signs, lights and any other material that might impede the free flow of traffic during the following holiday periods:

From noon Friday, August 31, 2007 to 6:00 AM Tuesday, September 4, 2007;
From noon Wednesday, November 21, 2007 to 6:00 AM Monday, November 26, 2007;
From 12:01 AM Saturday, December 22, 2007 to 6:00 AM Wednesday, January 2, 2008;
From noon Friday, May 23, 2008 to 6:00 AM Tuesday, May 27, 2008;
From 6:00 AM Thursday, July 3, 2008 to 6:00 AM Monday, July 7, 2008;
From noon Friday, August 29, 2008 to 6:00 AM Tuesday, September 2, 2008.
(050205) 107-005

6. Utilities.

This contract comes under the provisions of Administrative Rule TRANS 220.
(051206)

Underground and overhead utility facilities are located within the project limits. Utility adjustments “are” or “are not” required for this construction project as noted below. Coordinate construction activities with a call to Diggers Hotline or a direct call to the utilities that have facilities in the area as required per statutes. Use caution to ensure the integrity of underground facilities and maintain code clearances from overhead facilities at all times.

Contact each utility company listed in the plans, prior to preparing bids, to obtain current information on the status of existing and any new utility relocation work.

ATC - No conflicts anticipated. Work completed under project 3180-08-70.

WE Energies Electric - The existing path of the majority of the overhead lines at STH 83 will stay the same except that new poles guys will be installed so as to increase the existing elevation of the line to cross the Bypass alignment (the exception being the streetlight pole at Station 354+37 (44' Lt) STH 83). WE Energies Electric anticipates work to be prior to construction.

We Energies Gas (WEGAS)

STH 83

WEGAS has existing gas line running from Station 343+60 to the end of proposed construction on STH 83 along the west side of the existing roadway. This line varies from approximately 30 to 75 feet west of existing centerline. Laterals cross existing STH 83 at approximately Stations 343+60, 354+63, 356+82, 358+09 361+30 and 362+90. The existing gas line and all the laterals appear to be in conflict with Project 3180-10-70. WEGAS will relocate gas line from Station

340+00 to 358+00, near the new westerly right-of-way line of STH 83, and replace service lines crossing STH 83 at Stations 354+63, 356+82, 358+09, and 362+90. WEGAS anticipates completion of its relocation work along STH 83 prior to construction.

Breuer Road

WEGAS has existing gas line running from the beginning to the end of proposed construction on Breuer Road along the west side of the existing roadway. This line varies from approximately 15 feet to 20 feet west of existing centerline. Laterals cross existing Breuer Road at approximately Stations 102+28, 109+11 and 119+42. The existing gas line and all the laterals appear to be in conflict with project 3180-10-70. WEGAS will relocate gas line from Station 96+00 to 120+00, near the new westerly right-of-way line of Breuer road. The gas service lines at 102+28 and 109+11 will be retired. The gas service line at 119+42 will be relocated. WEGAS anticipates completion of its relocation work along Breuer Road prior to construction.

Ketterhagen Road

WEGAS has existing gas line running along the south side of Ketterhagen Road from Station 91+50 to 110+75. This line was placed in 2006 at its current location due to the fact that all of the proposed roadway right-of-way was not yet purchased at that time and the line needed to be placed. WEGAS will relocate this line to the new southerly right-of-way line from Station 91+50 to Station 110+75 and replace and or tie-in affected gas service lines. WEGAS anticipates completion of its relocation work along Breuer Road prior to construction.

ANR Pipeline Company - No conflicts anticipated. Work was completed under Project 3180-14-70. Contact ANR when work takes place in their easement area so they may have personnel on site to protect their facilities.

SBC - No conflicts anticipated. Work was completed under Project 3180-08-70.

TDS Telecom (TDS)

Ketterhagen Road

TDS has existing buried cable from Station 90+00 – Station 110+75, 22-32 feet RT along Ketterhagen Road. TDS anticipates their work to be completed by May 7, 2007.

Time Warner Cable - No conflicts anticipated. Work to be coordinated with WE Energies Electric. Time Warner Cable Facilities will be placed on WE-Energies-Electric poles.

City of Burlington DPW - The following is a list of relocations and adjustments that are required to the City of Burlington water and sanitary facilities in preparation of Project 3180-10-70. Some of the work will be performed by city staff prior to and during construction. Some of the work will need to be performed by project contractor as a non-

participating item. The City of Burlington anticipates completion of this work prior to and during construction.

STH 83

Existing water valve located at Station 342+94 – minor adjustment by City Water Utility Staff in field during construction.

Existing hydrant valve at Station 343+18 – minor adjustment by City Water Utility Staff in field during construction.

Existing hydrant located at Station 343+18 – relocate from 49' left to 66' left, new elevation is 765.40, prior to road construction beginning.

Existing sanitary force main air release manhole Station 345+30 left – reconstruct to rim elevation 764.75. Completed by road contractor as a nonparticipating item.

Existing water valve manhole Station 348+94 right – Reconstruct to rim elevation 771.75. Carry back 25:1 slope to 50' right, then steepen slope to match. Completed by road contractor as a nonparticipating item.

Existing hydrant valve and hydrant at Station 349+22 right – remove and plug hydrant lead. Add new hydrant and valve at STH 349+55 40' left (hydrant) and 35' left (valve) at elevation 776.70. Complete prior to start of construction.

Existing sanitary force main air release manhole Station 355+15 right – Reconstruct to rim elevation 775.90. Completed by road contractor as a nonparticipating item.

Existing water valve manhole at Station 354+46 right – Reconstruct to rim elevation 775.97. Rim in curb – sealed and locked cover required. Completed by road contractor as a nonparticipating item.

Existing water valve manhole at Station 354+97 left – Reconstruct to rim elevation 774.05 Completed by road contractor as a nonparticipating item.

Existing hydrant valve at Station 355+12 and hydrant at Station 355+28 – Remove and plug lead.

Proposed lead, valve and hydrant assembly located at 355+30, 70' left. Served off of main on Yahnke Road. – New installation completed prior to roadway construction.

Existing water valve manhole Station 354+99 left, no impact.

Existing sanitary manhole Station 355+15 left, no impact.

Existing sanitary manhole Station 355+80 left, no impact.

Existing sanitary manhole Station 356+18 left, no impact.

Existing sanitary manhole Station 356+77 left, no impact.

Existing water valve at Station 358+16 right – Adjust in field by City Water Utility Staff during construction.

Existing water valve at Station 365+XX left - Adjust in field by City Water Utility Staff during construction.

Existing water valve manhole Station 360+85 left – Adjust manhole. Completed by road contractor as a nonparticipating item.

Existing water valve at Station 361+03 left – Adjust in field by City Water Utility Staff during construction.

Existing hydrant at Station 361+09 left – Raise 1.0 foot to 773.02. Complete prior to start of construction.

Existing sanitary force main air release manhole at Station 363+05 left – Adjust/reconstruct to 771.67 (from 770.62). Completed by road contractor as a nonparticipating item.

Existing sanitary manhole at Station 363+60 left, beyond slopes no impact.

Existing water valve box at Station 364+50 left – Adjust by City Water Utility Staff during construction.

Existing sanitary force main air release manhole at Station 367+18 left – Adjust manhole. Completed by road contractor as a nonparticipating item. Rim in curb – sealed and lock rim required.

Existing water valve manhole at Station 367+16 left – Adjust manhole. Completed by road contractor as a nonparticipating item.

Existing hydrant at Station 367+40 left – ok – located at approximately 40' left. Existing and proposed conditions are same. On foreslope of ditch.

Existing sanitary manhole at Station 367+89 left – ok – outside of slope – no impact.

The sanitary sewer lift station located in the northwest quadrant of the proposed STH 83 / Bypass Intersection currently has access off of Yahnke Road. Since Yahnke Road access is being removed from STH 83, an alternate access must be provided. Under the current 3180-10-70 project, access to the lift station will remain off of Yahnke road in a temporary condition. An alternate access will need to be provided as a participating item on a future Bypass contract.

7. Construction Over or Adjacent to Navigable Waters.

Supplement 107.19 of the standard specifications with the following:

The Fox River is classified as a navigable waterway.
(041504) 107-060

8. Erosion Control.

Supplement subsection 107.20 of the standard specifications with the following:

Implementation of the contractor's Erosion Control Implementation Plan (ECIP) cannot take place until the ECIP has been granted approval from the department. Take into account dust control during preparation of ECIP and throughout the duration of the project.

Pursue operations in a timely and diligent manner, continuing all construction operations methodically from the initial topsoil stripping operation through the subsequent grading and re-topsoiling to minimize the period of exposure to possible erosion.

Re-topsoil graded areas, as designated by the engineer, immediately after grading is completed within those areas. Seed, fertilize, and mulch all topsoiled areas within five working days after placement of topsoil.

To avoid conflicts with mowing and maintenance operations, remove all erosion mat installed during construction operations once seeding has established itself and as directed by the engineer. Removal of erosion mat is incidental to the appropriate bid item.
(082003) 107-051

9. Information to Bidders Wetlands.

The department has obtained a U.S. Army Corps of Engineers Section 404 Permit and WisDNR 401 Water Quality Certification for work being performed on this project in or adjacent to wetlands. Copy(s) of the permit and certification letter are available for viewing at the regional office or at the project field office.

Comply with the requirements of the permit and certification in addition to requirements of the contract. Perform remedial activities without extra compensation if not in compliance.

If the contractor chooses a method of construction that is not covered by the department's 404 Permit, obtain the proper additional permits required from the U.S. Army Corps of Engineers. It is the contractor's responsibility to determine if additional permits are required. Obtain the additional permits prior to beginning construction operations requiring the permits. No time extensions as discussed in subsection 108.10 of the standard specifications will be granted for the time required to apply for and obtain the

additional permits. The contractor must be aware that the U.S. Army Corps of Engineers may not grant the additional permits.

No change in payment will be granted if the contractor chooses a method of construction that does not comply with the 404 Permit. Water level is subject to change. Contractor is responsible for making his or her own determination of water levels that will exist during construction.

If sheet piling is required, determine sheet pile depths and locations in accordance to the permit. Sheet piling required shall be considered incidental to other work and will not be paid for separately.

10. Hauling Restrictions.

Conduct operations in a manner that will cause a minimum of inconvenience to the free flow of vehicles on roadways carrying STH 142, STH 11, CTH A, STH 36/83 or Yahnke Road traffic. The contractor will be allowed access to these roads at locations approved by the engineer.

When hauling across any public roads, provide the necessary flagging and signing to control the construction equipment movements. Do not impede traffic flow on the public roads with flagging operations.

11. Other Contracts.

Coordinate with the contractor for the projects listed below:

Projects 3180-08-70 and 3180-14-70 provide for grading, base layers HMA paving and or structures at the locations listed below. Grading included storm sewer cross culverts and underdrain. Projects 3180-08-70 and 3180-14-70 were let in combination prior to work under this contract.

1. Grading of Mainline Bypass eastbound and westbound roadways from Station 1129+00 to 1154+00, including the approaches to Structures B-51-93/94 over the Fox River.
2. Grading of Mainline Bypass eastbound and westbound roadways from Station 1156+00 to 1326+00.
3. Grading of Mainline Bypass eastbound and westbound roadways from Station 1334+00 to 1393+00, including the approaches to Structures B-51-102/103 over the Fox River.
4. Grading of the STH 142 and CTH A jug-handle ramps.
5. Grading and paving of HMA base layers for STH 142, including Mt Tom Road.
6. Grading and placement of base aggregate surface for the Canadian Pacific Bike Path.
7. Grading and paving of HMA base layers for STH 11.

8. Grading and paving of HMA base layers for CTH A, including River Road and Old CTH-A.
9. Structures B-51-92 STH 142 over Bypass.
10. Structure B-51-98 CTH A over Bypass.
11. Structure C-51-24 Canadian Pacific Bike Path under Bypass.

Projects 3180-09-70 provide for grading, HMA paving (base and surface layers) and or structures at the locations listed below. Grading included storm sewer cross culverts and underdrain. Projects 3180-09-70 was let separate to the projects listed above prior to work under this contract.

1. Grading of Mainline Bypass eastbound and westbound roadways Station 1393+00 to Station 1408+00 westbound and Station 1415+00 eastbound.
2. Grading and paving and completion of the entire STH 36/83/Bypass Interchange, with the exception of the mainline portion listed above. Traffic control at this interchange was left in place and will require coordination with Project 3180-10-70.
3. Grading and paving and completion of the Racine County Bike Path.
4. Placement of limestone screenings on Canadian Pacific Bike Path.
5. Structures B-51-93/94 Bypass over the Fox River.
6. Structures B-51-102/103 Bypass over the Fox River.
7. Structures B-51-113 STH 36/83 Northbound Ramp over Bypass.
8. Base aggregate dense and open were placed at various locations previously graded under previous projects. See current project Typical Sections for locations and dimensions.

Project 3180-10-70 involves the completion of the entire east half of the Burlington Bypass and associated side roads.

Project 3180-11-70 is the first of three contracts that will construct the west half of the Burlington Bypass. This project is scheduled to begin construction prior to completion of Project 3180-10-70. Coordination of traffic control is required between projects.

Weekly coordination meetings with above contractors are required throughout the duration of the contract.

12. Project Meetings.

Conduct weekly meetings, in coordination with the department, to discuss project schedule of operations and coordination of work. Invite local officials, utility representatives, and subcontractors. Hold meetings on-site.

13. Temporary Items to Remain After Construction.

Project 3180-09-70: The following temporary items installed under this contract will be removed by others under future contracts:

Cover on type 1 signs (see plan for locations), Signs Type I, Barricades Type III Permanent and Flexible Tubular Marker Posts.

14. Removing Pavement.

Perform this work in accordance to the requirements of section 204 of the standard specifications, as shown on the plans, and as hereinafter provided.

Remove existing concrete pavement in a manner that causes minimal disturbance to the underlying base material.

Use material removed under this item as aggregates or crushed materials, and recycle and use in the construction of work under this contract to the maximum extent feasible.

Any surplus salvaged material or unusable material shall become the property of the contractor and shall be disposed of by the contractor in an environmentally acceptable manner. The cost to dispose of all excess materials, including steel reinforcement, shall be included in the item of Removing Pavement.

The crushing, screening, and processing of the removed concrete pavement shall not be measured and paid for separately, but shall be considered as included in the cost of the item into which the produced aggregates are incorporated.

(051206) 204-001

15. Removing Retaining Wall, Item 204.9060.S.01.

A Description

This special provision describes removing the modular block retaining wall at the location shown in the plan in accordance with the pertinent provisions of section 204 of the standard specifications and as hereinafter provided.

B (Vacant)

C (Vacant)

D Measurement

The department will measure Removing Retaining Wall by the individual retaining wall acceptably completed.

E Payment

Supplement 204.5 to include the following:

ITEM NUMBER	DESCRIPTION	UNIT
204.9060.S.01 (100504)	Removing Retaining Wall	Each

16. Grading, Shaping and Finishing for Barrier Terminals, Item 205.9006.S.

A Description

This special provision describes the excavating, filling, grading, shaping, compacting, and finishing necessary to accommodate barrier terminals, as shown on the plans, in accordance to the pertinent requirements of the standard specifications, and as hereinafter provided.

B (Vacant)

C Construction

Construct embankment slopes as shown on the plans.

Properly dispose of all surplus and unsuitable material in accordance to 205.3.12 of the standard specifications.

D Measurement

The department will measure Grading, Shaping and Finishing for Barrier Terminals as each individual terminal acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
205.9006.S	Grading, Shaping and Finishing for Barrier Terminals	Each

Payment is full compensation for all excavating, grading, shaping and compacting; furnishing and placing fill, topsoil, fertilizer, seed, and mulch; and for furnishing all labor, tools, equipment, and incidentals necessary to complete the contract work.

(100906) 205-009

17. Backfill Granular.

Conform to the gradation requirements of Grade 2 granular backfill in accordance to subsection 209.2.1 of the standard specifications.

18. QMP Base Aggregate, Item 301.0100.S.

A Description

A.1 General

- (1) This special provision describes contractor quality control (QC) sampling and testing for base aggregates, documenting those test results, and documenting related production and placement process changes. This special provision also describes department quality verification (QV), independent assurance (IA), and dispute resolution.

- (2) Conform to sections 301, 305, and 310 of the standard specifications as modified here in this special provision. Apply this special provision to material placed under all of the Base Aggregate Dense and Base Aggregate Open Graded bid items, except do not apply this special provision to material classified as reclaimed asphaltic pavement placed under the Base Aggregate Dense bid items.
- (3) Do not apply this special provision to material placed under the Aggregate Detours, Salvaged Asphaltic Pavement Base, Breaker Run, Select Crushed, Pit Run, Subbase, or Riprap bid items.
- (4) Provide and maintain a quality control program, defined as all activities related to and documentation of the following:
 1. Production and placement control and inspection.
 2. Material sampling and testing.
- (5) Chapter 4 of the department's construction and materials manual (CMM) provides additional detailed guidance for QMP work and describes required sampling and testing procedures. The contractor may obtain the CMM from the department's extranet site at:

<http://trust.dot.state.wi.us/extntgtwy/dtidcons/constnds/cmm/cmm.htm>

A.2 Contractor Testing for Small Quantities

- (1) The department defines a small quantity, for each individual Base Aggregate bid item, as a plan quantity of 9000 tons (9000 Mg) or less of material as shown in the schedule of items under that bid item.
- (2) The requirements under this special provision apply equally to a small quantity for an individual bid item except as follows:
 1. The contractor need not submit a full quality control plan but shall provide an organizational chart to the engineer including names, telephone numbers and current certifications of all persons involved in the quality control program for material under affected bid items.
 2. Divide the aggregate into uniformly sized sublots for testing as follows:

PLAN QUANTITY	MINIMUM REQUIRED TESTING
≤ 1500 tons (1500 Mg)	One test from production, load-out, or placement at the contractor's option.
> 1500 tons (1500 Mg) and ≤ 6000 tons (6000 Mg)	Two tests of the same type, either from production, load-out, or placement at the contractor's option.
> 6000 tons (6000 Mg) and ≤ 9000 tons (9000 Mg)	Three placement tests ^{[1] [2]}

^[1] For 3-inch material, obtain samples at load-out.

- ^[2] If the actual quantity overruns 9000 tons (9000 Mg), create overrun sublots to test at a rate of one additional placement test for each 3000 tons (3000 Mg), or fraction of 3000 tons (3000 Mg), of overrun.
3. No control charts are required. Submit aggregate test results to the engineer within one business day of obtaining the sample. Assure that all properties are within the limits specified in the standard specifications for each test.
 4. Department verification testing is optional for quantities of 6000 tons (6000 Mg) or less.
- (3) Material represented by a subplot with any property outside the specification limits is nonconforming. The department may reject material or otherwise determine the final disposition of nonconforming material as specified in 106.5 of the standard specifications.

B Materials

B.1 Contractor Quality Control Program Requirements

B.1.1 Quality Control Plan

- (1) Submit a comprehensive written quality control plan to the engineer at or before the pre-construction meeting. Do not place base before the engineer reviews and comments on the plan. Construct the project as that plan provides.
- (2) Do not change the quality control plan without the engineer's review. Update the plan with changes as they become effective. Provide a current copy of the plan to the engineer and post in each of the contractor's laboratories as changes are adopted. Ensure that the plan provides the following elements:
 1. An organizational chart with names, telephone numbers, current certifications and/or titles, and roles and responsibilities of QC personnel.
 2. The process used to disseminate QC information and corrective action efforts to the appropriate persons. Include a list of recipients, the communication means that will be used, and action time frames.
 3. A list of source and processing locations, section and quarter descriptions, for all aggregate materials requiring QC testing.
 4. Test results for wear, sodium sulfate soundness, freeze/thaw soundness, and plasticity index of all aggregates requiring QC testing. Obtain this information from the district materials unit or from the engineer.
 5. Descriptions of stockpiling and hauling methods.
 6. Locations of the QC laboratory, retained sample storage, and where control charts and other documentation is posted.
 7. An outline for resolving a process control problem. Include responsible personnel, required documentation, and appropriate communication steps.

B.1.2 Personnel Requirements

- (1) Have personnel certified under the department's highway technician certification program (HTCP) perform sampling and testing as follows:

Required certification Level:	Sampling or Testing Roles:
Aggregate Technician I or IPP Aggregate Sampling Technician Assistant Certified Technician (ACT)	Aggregate Sampling ^[1]
Aggregate Technician I or IPP Assistant Certified Technician (ACT)	Aggregate Gradation Testing, Aggregate Fractured Particle Testing
Aggregate Technician IPP Assistant Certified Technician (ACT)	Aggregate Permeability Testing

^[1] Plant personnel under the direct observation of an aggregate technician certified at level one or higher may operate equipment to obtain samples.

- (2) Ensure that sampling and testing by an assistant certified technician conforms to all of the following:
 1. Sampling by an ACT is done under the direct observation of a aggregate technician certified at level one or higher.
 2. Testing by an ACT is done under the direct supervision of an aggregate technician certified at level one or higher
 3. No more than one ACT reports to an individual certified technician.
- (3) Have an aggregate technician certified at level one or higher perform all data analysis and posting.

B.1.3 Laboratory Requirements

- (1) Perform QC testing at a department qualified laboratory. Obtain information on the Wisconsin laboratory qualification program from:
 Quality Management Section
 3502 Kinsman Blvd.
 Madison, Wisconsin 53704
 Telephone: 608-246-3246
<http://www.dot.state.wi.us/business/engrserv/lab-qualification.htm>

B.1.4 Quality Control Documentation

B.1.4.1 General

- (1) Submit base aggregate production and placement documentation to the engineer within 10 business days after completing base placement. Ensure that the submittal is complete, neatly organized, and includes applicable project records and control charts. If conducting post-production testing, also include post-production documentation.

B.1.4.2 Records

- (1) Document all production and placement observations, inspection records, and control adjustments daily in a permanent field record. Also include all test results in the project records. Provide test results to the engineer within 6 hours after obtaining a sample. For 3-inch base, extend this 6-hour limit to 24 hours. Post or distribute tabulated results using a method mutually agreeable to the engineer and contractor.

B.1.4.3 Control Charts

- (1) Plot gradation, permeability, and fracture on the appropriate control chart as soon as test results are available. Format control charts according to CMM 4-15-12. Include the project number on base placement control charts. Maintain separate control charts for each base aggregate size, source or classification, and type.
- (2) Provide control charts to the engineer within 6 hours after obtaining a sample. For 3-inch base, extend this 6-hour limit to 24 hours. Post or distribute charts using a method mutually agreeable to the engineer and contractor. Update control charts daily to include the following:
 1. Contractor individual QC tests.
 2. Department QV tests.
 3. Department IA tests.
 4. Four-point running average of the QC tests.
- (3) Except as specified under B.2.2.1 for out-of-tolerance QV tests, include only QC tests in the running average. The contractor may plot process control or informational tests on control charts, but do not include these tests, in-tolerance QV tests, or IA tests in the running average.

B.1.5 Contractor Quality Control Testing

B.1.5.1 Production Testing

- (1) Test gradation and fracture during production of each base aggregate size, source or classification, and type. Sample from either the finished product conveyor belt or stockpiles using the same procedure throughout the project. Determine random sample locations according to CMM 4-15-12 and collect samples according to CMM 4-25-50.
- (2) Test gradation once per 1500 tons (1500 Mg) during initial production from a source, or if switching to a new base aggregate size or classification. For 3-inch base, test once per 3000 tons (3000 Mg) up to a maximum of 2 tests per day during initial production. Test at the initial frequency until three consecutive running average points for all the gradation sieves are within the warning limits. Subsequently, the contractor may reduce the frequency to one test per day if all gradation running averages remain within the warning limits. If any gradation running average is outside the warning limits, resume testing at the initial frequency.
- (3) Test fracture for each gradation test until the fracture running average is above the lower warning limit. Subsequently, the contractor may reduce the frequency to one test per ten gradation tests if the fracture running average remains above the warning limit.
- (4) Provide production test records for aggregate produced before the contract. The engineer will review this documentation to determine if testing conforms to the contract. The engineer may reject material if testing is nonconforming. The engineer

may subsequently approve this material for placement if the contractor provides additional post-production test results, as specified in B.1.5.2, to supplement otherwise nonconforming testing.

B.1.5.2 Post-Production Testing

B.1.5.2.1 Stockpile 3-Test Averages

- (1) Collect three random samples from each stockpile not adequately tested during production. Test each sample for fracture and gradation. Calculate a 3-test average for fracture and for the percent passing each sieve. The engineer will determine additional requirements as follows:
 1. If the fracture 3-test average or any gradation 3-test average exceeds its respective warning limits, the engineer will reject the stockpile unless the contractor elects to rework it. If electing to rework the stockpile, test the material during reworking as required for production testing under B.1.5.1. Plot the reworking test results on a separate control chart. Include the 3-test averages and their component individual tests on that control chart, but do not include them in the running average. No load-out testing is required.
 2. If the fracture 3-test average and all the gradation 3-test averages fall within their respective warning limits, the engineer will approve the stockpile subject to load-out testing. Conduct and document additional testing during load-out as specified in B.1.5.2.2. Include the 3-test averages and their component individual tests on the load-out control chart, but do not include them in the running average.

B.1.5.2.2 Load-Out Testing

- (1) For stockpiles approved without reworking under B.1.5.2.1, test gradation and fracture during load-out as follows:

DAILY LOAD-OUT in tons or Mg	TESTS PER DAY
≥500 to <1500	1
≥1500	2

- (2) Plot the load-out test results on a separate control chart.
- (3) Test fracture for each gradation test until the fracture running average is above the lower warning limit. Subsequently, the contractor may reduce the frequency to one test per ten gradation tests if the fracture running average remains above the warning limit.
- (4) Stop placing material if any load-out running average exceeds its warning limits. Collect 3 random samples from the remaining stockpile. The engineer will evaluate the remaining stockpile as specified in B.1.5.2.1. Proceed with post-production testing of the remaining stockpile as specified in B.1.5.2.1.

B.1.5.3 Placement Testing

- (1) Test gradation and fracture during placement for each base aggregate size, source or classification, and type. The contractor may test permeability of open graded base instead of gradation, but must then use permeability testing throughout the project. The engineer will not require fracture testing if all production running averages are above the warning limit. The engineer may reinstate fracture testing if verification tests fall below the warning limit.
- (2) Determine random sample locations according to CMM 4-15-12 and collect samples from the grade according to CMM 4-25-50. Each day before placement, have an aggregate technician determine random sample locations based on the contractor's estimate for that day's placement quantity and provide those sample locations to the engineer. Obtain samples after the material has been bladed, mixed, and shaped but before compacting; except collect 3-inch samples from the stockpile at load-out. Do not sample from material used to maintain local traffic or from areas of temporary base that will not have an overlying pavement. On days when placing only material used to maintain local traffic or only temporary base that will not have an overlying pavement, no placement testing is required.
- (3) Split each contractor QC sample and identify it according to CMM 4-15-12. Retain the split for seven calendar days in a dry, protected location. If requested for department comparison testing, deliver the split to the engineer within one business day.
- (4) Test gradation or permeability once per 3000 tons (3000 Mg) of estimated placement up to a maximum of 3 tests per day, or one sample per 5 days of placement whichever is most frequent. Include unsampled material in the estimate for the next day's placement as follows:
 1. If actual placement falls short of a planned random test location.
 2. If actual placement over runs and less than three tests are made that day.
- (5) The engineer may require additional sampling and testing to evaluate suspect material or the technician's sampling and testing procedures.
- (6) If required, test fracture for each gradation or permeability test until the fracture running average is above the lower warning limit. Subsequently, the contractor may reduce the frequency to one test per ten gradation or permeability tests if the fracture running average remains above the warning limit.

B.1.6 Test Methods

B.1.6.1 Gradation

- (1) Test gradation using a washed analysis conforming to the following as modified in CMM 4-25-50:

Gradation	AASHTO T 27
Material finer than the No. 200 (75 µm) sieve	AASHTO T 11

- (2) For 3-inch base, if 3 consecutive running average points for the percent passing the No. 200 (75 μ m) sieve are 8.5 percent or less, the contractor may use an unwashed analysis. Wash at least one sample out of ten. If a single running average for the percent passing the No. 200 (75 μ m) sieve exceeds 8.5 percent, resume washed analyses until 3 consecutive running average points are again 8.5 percent passing or less.
- (3) Maintain a separate control chart for each sieve size specified in section 305 or 310 of the standard specifications for each base aggregate size, source or classification, and type. Set control and warning limits based on the standard specification gradation limits as follows:
 1. Control limits are at the upper and lower specification limits.
 2. There are no upper warning limits for sieves allowing 100 percent passing and no lower control limits for sieves allowing 0 percent passing.
 3. Dense graded warning limits, except for the No. 200 (75 μ m) sieve, are 2 percent within the upper and lower control limits. Warning limits for the No. 200 (75 μ m) sieve are set 0.5 percent within the upper and lower control limits.
 4. Open graded warning limits for the 1-inch (25.0 mm), 3/8-inch (9.5 mm), and No. 4 (4.75 mm) sieves are 2 percent within the upper and lower control limits. Upper warning limits for the No. 10 (2.00 mm), No. 40 (425 μ m), and No. 200 (75 μ m) sieves are 1 percent inside the upper control limit.

B.1.6.2 Fracture

- (1) Test fracture conforming to CMM 4-25-50. The engineer will waive fractured particle testing on quarried stone.
- (2) Maintain a separate fracture control chart for each base aggregate size, source or classification, and type. Set the lower control limit at the contract specification limit, either specified in another special provision or in table 301-2 of 301.2.3.5 of the standard specifications. Set the lower warning limit two percent above the lower control limit. There are no upper limits.

B.1.6.3 Permeability

- (1) Test permeability using equipment and procedures conforming to the department's falling head permeameter test as described in CMM 4-15-32.
- (2) The individual test specification limit is a minimum of 700 feet/day (200 m/day). An individual test is the average of three permeability test values from a single sample (K_n).
- (3) Maintain a separate permeability control chart for each open graded base source. Set the running average lower control limit at 1000 feet/day (300 m/day). Set the running average lower warning limit at 1300 feet/day (400 m/day). There are no upper limits.

B.1.7 Corrective Action

B.1.7.1 General

- (1) Consider corrective action when the running average trends toward a warning limit. Take corrective action if an individual test exceeds the contract specification limit. Document all corrective actions both in the project records and on the appropriate control chart.

B.1.7.2 Production Corrective Action

- (1) Take corrective action if the running average exceeds a warning limit. Part of this required corrective action is a return to the initial testing frequencies specified in B.1.5.1. The contractor may subsequently reduce the frequency if conditions specified for reduced frequency testing under B.1.5.1 are met.

B.1.7.3 Placement Corrective Action

- (1) Do not blend additional material on the roadbed to correct gradation or permeability problems.
- (2) Notify the engineer whenever the running average exceeds a warning limit. When two consecutive running averages exceed a warning limit, the engineer and contractor will discuss appropriate corrective action. Perform the engineer's recommended corrective action and increase the testing frequency as follows:
 1. For gradation or permeability, increase the QC testing frequency to at least 1 randomly sampled test per 1000 tons (1000 Mg) placed.
 2. For fracture, increase the QC testing frequency to at least one test per gradation or permeability test.
- (3) If corrective action improves the property in question such that the running average after four additional tests is within the warning limits, the contractor may return to the testing frequency specified in B.1.5.3. If corrective action does not improve the property in question such that the running average after four additional individual tests is still in the warning band, repeat the steps outlined above starting with engineer notification.
- (4) If the running average exceeds a control limit, material starting from the first running average exceeding the control limit and ending at the first subsequent running average inside the control limit is nonconforming and subject to pay reduction.
- (5) For individual test results significantly outside the control limits, notify the engineer, stop placing base, and suspend other activities that may affect the area in question. The engineer and contractor will jointly review data, data reduction, and data analysis; evaluate sampling and testing procedures; and perform additional testing as required to determine the extent of potentially unacceptable material. The engineer may direct the contractor to remove and replace that material. Individual test results are significantly outside the control limits if meeting one or more of the following criteria:

1. A gradation control limit for any sieve is exceeded by more than five percent.
2. Permeability is less than 700 feet/day (200 m/day).
3. The fracture control limit is exceeded by more than ten percent.

B.2 Department Testing

B.2.1 General

- (1) The department will conduct verification testing to validate the quality of the product and independent assurance testing to evaluate the sampling and testing. The department will provide the contractor with a listing of names and telephone numbers of all QV and IA personnel for the project, and provide test results to the contractor within two business days after the department obtains the sample.

B.2.2 Verification Testing

B.2.2.1 General

- (1) The department will have an HTCP technician, or ACT under the direction of a certified technician, perform QV sampling and testing. Department verification testing personnel must meet the same certification level requirements specified in B.1.2 for contractor testing personnel for each test result being verified. The department will notify the contractor before sampling so the contractor can observe QV sampling.
- (2) The department will conduct QV tests of each base aggregate size, source or classification, and type during placement conforming to the following:
 1. One non-random test on the first day of placement.
 2. At least 1 random test per 30,000 tons (30 000 Mg), or fraction of 30,000 tons (30 000 Mg), placed.
- (3) The department will sample randomly, at locations independent of the contractor's QC work, collecting one sample at each QV location. The department will collect QV samples after the material has been bladed, mixed, and shaped but before compacting; except, for 3-inch aggregates, the department will collect samples from the stockpile at load-out. The department will split each sample, test half for QV, and retain half.
- (4) The department will conduct QV tests in a separate laboratory and with separate equipment from the contractor's QC tests. The department will use the same methods specified for QC testing. If the contractor chooses permeability for QC testing, the department will use permeability for QV testing.
- (5) The department will assess QV results by comparing to the appropriate specification limits. If QV test results conform to the specification, the department will take no further action. If QV test results are nonconforming, the engineer will compare those results to the nearest previous QC test result as follows:
 1. If the QV and QC results are within the tolerances specified in B.2.2.2, the department will take no further action.
 2. If QV and QC results are not within the tolerances specified in B.2.2.2, add the QV to the QC test results as if it were an additional QC test.

B.2.2.2 Verification Testing Tolerances

- (1) Differences between the contractor's QC test results and the department's QV test results are acceptable if within the following tolerances:

TEST PROPERTY	ACCEPTABLE DIFFERENCE
GRADATION	
1 in (25.0 mm)	±6 % passing
3/4 in (19.0 mm)	±6 % passing
3/8 in (9.5 mm)	±6 % passing
No. 4 (4.75 mm)	±5 % passing
No. 8 (2.36 mm)	±4 % passing
No. 10 (2.00 mm)	±4 % passing
No. 30 (600 µm)	±4 % passing
No. 40 (425 µm)	±4 % passing
No. 50 (300 µm)	±4 % passing
No. 200 (75 µm)	±2 % passing
PERMEABILITY	±20 % of the measured QV permeability
FRACTURE	±10 % of the measured QV fracture

B.2.3 Independent Assurance

- (1) Independence assurance is unbiased testing the department performs to evaluate the department's QV and the contractor's QC sampling and testing including personnel qualifications, procedures, and equipment. The department will perform an IA review according to the department's independent assurance program. That review may include one or more of the following:
1. Split sample testing.
 2. Proficiency sample testing.
 3. Witnessing sampling and testing.
 4. Test equipment calibration checks.
 5. Reviewing required worksheets and control charts.
 6. Requesting that testing personnel perform additional sampling and testing.
- (2) If the department identifies a deficiency, and after further investigation confirms it, correct that deficiency. If the contractor does not correct or fails to cooperate in resolving identified deficiencies, the engineer may suspend placement until action is taken. Resolve disputes as specified in B.4.

B.3 Acceptance

- (1) The department will accept base aggregate based on the contractor QC tests unless it is shown through QV testing or the dispute resolution process that the contractor's test results are in error.

B.4 Dispute Resolution

- (1) The engineer and contractor should make every effort to avoid conflict. If a dispute between some aspect of the contractor's and the engineer's testing program does

occur, seek a solution mutually agreeable to the project personnel. The department and contractor may review the data, examine data reduction and analysis methods, evaluate sampling and testing procedures, and perform additional testing. Use ASTM E 178 to evaluate potential statistically outlying data.

- (2) If the project personnel cannot resolve a dispute, and the dispute affects payment or could result in incorporating nonconforming product, the department will use third party testing to resolve the dispute. The department's central office laboratory, or a mutually agreed on independent testing laboratory, will provide this testing. The engineer and contractor will abide by the results of the third party tests. The party in error will pay service charges incurred for testing by an independent laboratory. The department may use third party test results to evaluate the quality of questionable materials and determine the appropriate payment. The department may reject material or otherwise determine the final disposition of nonconforming material as specified in 106.5 of the standard specifications.

C (Vacant)

D Measurement

- (1) The department will measure QMP Base Aggregate by the ton of aggregate acceptably tested. The department will measure the quantity based on the tonnage placed under the Base Aggregate bid items listed in subsection A. The department will include material placed for temporary base or to maintain local traffic even though it was not sampled during placement. The department will not include material classified as reclaimed asphaltic pavement placed under the Base Aggregate Dense bid items.

E Payment

- (1) The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
301.0100.S	QMP Base Aggregate	Ton

- (2) Payment is full compensation for all sampling, testing, and documentation required under this special provision. If the contractor fails to perform the work required under this special provision, the department may reduce the contractor's pay. The department will administer pay reduction under the Non-performance on QMP administrative item.
- (3) For material represented by a running average exceeding a control limit, the department will reduce pay by ten percent of the contract price for the affected Base Aggregate bid items listed in subsection A. The department will administer pay reduction under the Nonconforming QMP Base Aggregate Gradation or Nonconforming QMP Base Aggregate Fracture administrative items. The department will determine the quantity of nonconforming material as specified in B.1.7.3.

(100906) 301-010

19. Base Aggregate Dense 1 1/4-Inch for Lower Base Layers.

Replace 305.2.2.1(2) of the standard specifications with the following:

- (1) Use 1 1/4-inch base throughout the full base depth.
- (2) Use 3/4-inch base in the top 3 inches of the unpaved portion of shoulders. Use 3/4-inch base or 1 1/4-inch base elsewhere in shoulders.
(100906) 305-020

20. QMP Concrete Ancillary.

A Description

- (1) Conform to standard spec 390, 416, 501, 504, 509, 510, 601, 602, 603, 604, 611, 620, 636, and 654 as modified in this special provision. Apply this special provision to all concrete cast in place under these designated sections, except for sections 416 and 504. For sections 416 and 504, apply only to concrete placed under the following bid items:

416.0060	Concrete Pavement Widening
416.0065	Concrete Pavement Widening HES
416.0160 - 0199	Concrete Driveway (inch)
416.0260 - 0299	Concrete Driveway HES (inch)
416.0505	Pavement Terminal Units
416.0710	Concrete Pavement Repair
416.0715	Concrete Pavement Repair SHES
416.1010	Concrete Surface Drains
416.1015	Concrete Surface Drains HES
504.0900	Concrete Masonry Endwalls
- (2) Provide and maintain a quality control program, defined as all activities and documentation of the following:
 1. Mix design.
 2. Production control, placement control, and inspection.
 3. Sampling, testing, measurement, and correction of materials and in-place concrete.
- (3) The contractor may include ancillary concrete in a quality control program required for concrete pavement or structural concrete.
- (4) Chapter 4 of the department's construction and materials manual (CMM) provides additional detailed guidance for QMP work and describes required sampling and testing procedures. The contractor may obtain the CMM from the department's extranet site at:

<http://www.dot.wisconsin.gov/business/engrserv/index.htm>

B Quality Control Program Requirements

B.1 Personnel Requirements

- (1) Perform the material sampling, testing, and documentation required under this provision using HTCP certified technicians. Have a PCC technician certified under HTCP at level I present at the project site, prepared and equipped to perform required sampling and testing, whenever placing concrete. Provide an organizational chart to the engineer including names, telephone numbers, and current certifications of all personnel involved in the quality control program.

B.2 Laboratory Requirements

- (1) Perform the cylinder compressive strength testing at a department-qualified laboratory. Obtain information on the Wisconsin laboratory qualification program from:

Quality Management Section
3502 Kinsman Blvd.
Madison Wisconsin 53704
Telephone: 608-246-3246

<http://www.dot.state.wi.us/business/engrserv/lab-qualification.htm>

B.3 Equipment Requirements

- (1) Furnish the necessary equipment and supplies for performing quality control testing. The engineer may inspect the measuring and testing devices to confirm both calibration and condition. Calibrate all testing equipment according to CMM 4-15-12 and maintain a calibration record at a location satisfactory to the engineer.

B.4 Concrete Mixes

B.4.1 Initial Mix

- (1) Determine concrete mixes for the project. Use concrete mixes from standard spec 501. Alternatively, where one of the grade A mixes is allowed under standard spec 501.3.1.3, the contractor may use a QMP mix design approved for concrete pavement or structural concrete under this contract.
- (2) At least 5 business days before producing concrete, submit concrete mix documentation to the engineer for approval. Provide documentation ensuring that all materials conform to standard spec 501.2 unless the engineer waives specific requirements. Include documentation for mix designs as follows:
 1. Mix grade designation for standard specification mixes.
 2. Materials: type, brand, and source.
 3. Aggregates: absorption, specific gravities, wear, soundness, freeze thaw test results if required, air correction factor, and proposed gradation control limits.

B.4.2 Mix Changes

- (1) Prepare and submit modifications to a standard specification concrete mix or a contractor concrete mix design to the engineer for approval before using that modified mix. Modifications requiring the engineer's approval include changes in:

1. The source of any material.
2. The amounts of cementitious materials.
3. The adjustment of fine to total aggregate greater than ± 3 percent by weight.
4. The addition or deletion of admixtures.

B.5 Quality Control Documentation

- (1) Document all observations, inspection records, mix adjustments, cylinder identification, and test results daily according to CMM 4-15-42. Submit a copy of the ancillary concrete daily test report to the engineer each day. Submit original testing records to the engineer in a neat and orderly manner within 10 days after completing concrete production.

B.6 Contractor Testing

B.6.1 General

- (1) Perform all quality control tests necessary to control the production and construction processes applicable to this special provision. Use the test methods identified below, or other methods the engineer approves, to perform the following tests:

Aggregate gradations	AASHTO T 11 ^[1] and T 27 ^[1]
Air content	AASHTO T 152 ^[2]
Slump	AASHTO T 119 ^[2]
Temperature	AASHTO T 309
Compressive strength.....	AASHTO T 22, T 23, and T 141

 - ^[1] As modified in CMM 4-25-50.
 - ^[2] As modified in CMM 4-25-70.
- (2) The department may periodically observe contractor sampling and testing, and direct additional contractor sampling and testing for department evaluation. Ensure that all test results are available for the engineer's review at any time during normal working hours.
- (3) Randomly choose sample locations using the procedures described CMM 4-15-12. Use whichever combination of the following criteria resulting in the greatest number of tests.
 1. A minimum of one test per day per mix grade.
 2. A minimum of one test per 100 cubic yards for each grade of mix placed.
 3. For deck overlays, one test per 50 cubic yards of grade E concrete placed.

B.6.2 Compressive Strength

B.6.2.1 Concrete Sampling

- (1) Have an HTCP certified PCC technician I or IA sample, test, and document results during concrete production and placement. Cast a minimum of one set of 2 standard 6x12-inch cylinders for each test using concrete delivered to the job site. Cast all cylinders in a set from the same sample. Sample according to AASHTO T 141. Cast and standard cure the cylinders according to AASHTO T 23.

B.6.2.2 Concrete Cylinder Curing

- (1) Provide facilities for initial curing. For up to 48 hours after casting, maintain the temperature adjacent to the specimens in the range of 60 to 80 degrees F (16 to 27 degrees C) and prevent moisture loss. Between 24 and 48 hours after casting, transport the specimens to a department-qualified laboratory for standard curing according to AASHTO M201 for 28 days.

B.6.2.3 Compressive Strength Testing

- (1) Have an HTCP certified compressive strength tester, in a department-qualified laboratory, perform compressive strength testing and document the results. Determine the 28-day compressive strength in pounds per square inch of each cylinder according to AASHTO T 22. Test each cylinder to failure. Use a compression machine that automatically records the date, time, rate of loading, and maximum load of each cylinder. Include a printout of this information with the compressive strength documentation for each cylinder tested.

B.6.3 Air Content

- (1) On each day of production, test the concrete air content as early and as frequently as practicable until the concrete meets the specifications and the production process is under control.
- (2) Have an HTCP certified PCC technician I or IA test air content according to AASHTO T 152, as modified by the department. The lower and upper specification limits for air content are the values specified in standard spec 501.3.2.4.2. Document admixture dosage rates, time of day, and air temperature on the ancillary concrete daily test report whenever changing an admixture dosage rate.
- (3) Double the air content test frequency if an individual air test falls outside the following warning bands:
 1. For deck overlay grade E concrete: less than 5.5% or greater than 6.5%.
 2. For slip-formed concrete: less than 6%.
 3. For all other concrete: less than 5%.

Continue testing at increased frequency until an individual test point is back within the warning band.

- (4) If an individual air test is outside the specification limits, notify the engineer, and perform additional air tests as often as practicable on subsequent loads until the air content is inside the specification limits. The material is nonconforming when an individual test result exceeds the specification limit. Material from the load with the first test exceeding the specification limit, continuing to but not including the load with the first subsequent test within the specification limits, is nonconforming. The department may direct removal and replacement or otherwise determine the final disposition of nonconforming material as specified in standard spec 106.5.

B.6.4 Concrete Temperature

- (1) Have an HTCP certified PCC technician I or IA measure concrete temperature according to AASHTO T 309. Test concrete taken from the same sample used for air content testing. Record concrete temperatures on the air content control chart.

B.6.5 Slump

- (1) Have an HTCP certified PCC technician I or IA measure slump according to AASHTO T 119. The contractor need not test slump for concrete placed by slip-form methods unless the engineer requests. Provide material conforming to the slumps specified in standard spec 501.3.7.1.

B.6.6 Aggregate Gradations

- (1) Have an HTCP certified Aggregate Technician I or IPP perform aggregate gradation tests according to AASHTO T 11 and T 27.
- (2) The engineer may accept aggregate gradation based upon satisfactory records of previous testing of the material at the time of aggregate production. Otherwise, test aggregate gradations at the frequency listed below which results in the least number of tests.
 1. A maximum of one test per day.
 2. A minimum of one test per 400 cubic yards of cumulative concrete placed.

C Department Testing

C.1 Verification Testing

- (1) The department will have an appropriately HTCP certified technician perform verification testing. The department will sample randomly at locations independent of the contractor's QC work. In all cases, the department will conduct the verification tests with separate personnel and equipment from the contractor's QC tests. The department will perform verification testing at a frequency of 10 percent of the random concrete quality control tests or a minimum of once per project, or at greater frequency if determined to be necessary by the engineer. Department verification testing is optional for aggregate used in the concrete.
- (2) If verification tests indicate conformance with specifications, no further action is required. If verification tests indicate nonconformance with specifications, the engineer and contractor will jointly investigate any testing discrepancies. The investigation may include additional testing as well as review and observation of both the department's and contractor's sampling and testing procedures and equipment. Both parties will document all investigative work.
- (3) Correct all deficiencies. If the contractor does not respond to an engineer request to correct a deficiency or resolve a testing discrepancy, the engineer may suspend production until action is taken. Resolve disputes as specified in D.

C.2 Independent Assurance Testing

- (1) Independent assurance is unbiased testing the department performs to evaluate the department's verification and the contractor's QC sampling and testing including personnel qualifications, procedures, and equipment. The department will perform the independent assurance review according to the department's independent assurance program.
- (2) If the department identifies a deficiency, and after further investigation confirms it, correct that deficiency. If the contractor does not correct or fails to cooperate in resolving identified deficiencies, the engineer may suspend production until action is taken. Resolve disputes as specified in D.

D Dispute Resolution

- (1) The engineer and contractor should make every effort to avoid conflict. If a dispute between some aspect of the contractor's and the engineer's testing program does occur, seek a solution mutually agreeable to the project personnel. The department and contractor may review the data, examine data reduction and analysis methods, evaluate sampling and testing procedures, and perform additional testing. Use ASTM E 178 to evaluate potential statistically outlying data.
- (2) If the project personnel can not resolve a dispute and the dispute affects payment or could result in incorporating nonconforming product, the department will use third party testing to resolve the dispute. The department's central office laboratory, or a mutually agreed on independent testing laboratory, will provide this testing. The engineer and contractor will abide by the results of the third party tests. The party in error will pay service charges incurred for testing by an independent laboratory. The department may use third party test results to evaluate the quality of questionable materials and determine the appropriate payment. The department may reject material or otherwise determine the final disposition of nonconforming material as specified in standard spec 106.5.

E Acceptance

- (1) The department will accept concrete based on the contractor QC tests unless it is shown through the verification, or the dispute resolution process that the contractor's test results are in error.

F Payment

- (1) Costs for all QMP sampling, testing, and documentation required under this special provision are incidental to the work. If the contractor fails to perform the work required under this special provision, the department may reduce the contractor's pay. The department will administer pay reduction under the Non-performance of QMP administrative item.

(100906) 501-065

21. QMP Concrete Pavement, Item 415.3000.S; Incentive Strength Concrete Pavement, Item 415.2000.S.

A Description

A.1 General

- (1) Conform to standard spec 320, 415, 416, and 501 as modified in this special provision. Apply this special provision only to the following bid items:

320.0100 - 0199	Concrete Base (inch)
320.0300 - 0399	Concrete Base HES (inch)
320.0500	Concrete Base Widening
415.0060 - 0199	Concrete Pavement (inch)
415.1080 - 1199	Concrete Pavement HES (inch)
416.0050	Concrete Pavement Approach Slab
416.0055	Concrete Pavement Approach Slab HES
416.0310	Concrete Alley
416.0315	Concrete Alley HES
416.0410	Concrete Pavement Header
416.0415	Concrete Pavement Header HES
416.0805	Concrete Pavement Gaps
- (2) Provide and maintain a quality control program, defined as all activities and documentation of the following:
 1. Mix design.
 2. Production control, placement control, and inspection.
 3. Sampling, testing, measurement, and correction of materials and in-place concrete pavement.
- (3) Chapter 4 of the department's construction and materials manual (CMM) provides additional detailed guidance for QMP work and describes required sampling and testing procedures. The contractor may obtain the CMM from the department's website at:
<http://www.dot.wisconsin.gov/business/engrserv/index.htm>

A.2 Contractor Testing for Small Quantities

- (1) The department defines a small quantity, for a particular mix design and placement technique, as less than 2500 cubic yards (1912 m³) for slip-formed work or 1000 cubic yards (765 m³) work not slip-formed.
- (2) The requirements under this special provision apply equally to a small quantity for a particular mix design and placement technique except as follows:
 1. The contractor need not submit a full quality control plan but shall provide an organizational chart to the engineer including names, telephone numbers and current certifications of all persons involved in the quality control program.
 2. The engineer may accept aggregate gradation based upon satisfactory records of previous testing.

3. No concrete control charts are required. Submit test results to the engineer each day as they become available. Assure that all properties are within the limits specified in the standard specifications for each subplot tested.
4. The department will not adjust the pay for sublots with conforming compressive strength.

B Quality Control Program Requirements

B.1 Quality Control Plan

- (1) Submit a comprehensive written quality control plan. Construct the project as the plan provides. Submit the plan to the engineer no later than 10 business days before placing concrete pavement. Do not change the quality control plan without the engineer's review. Update the plan with changes as they become effective. Provide a current copy of the plan to the engineer and post in each of the contractor's laboratories before producing concrete and as changes are adopted. Ensure that the plan provides the following elements:
 1. An organizational chart including names, telephone numbers, current certifications and/or titles, and roles and responsibilities of all quality control personnel.
 2. The process by which quality control information and corrective action efforts will be disseminated to the appropriate persons. Include a list of recipients, the communication means that will be used, and action time frames.
 3. Preliminary concrete pavement mix information including anticipated producers, manufacturers, and sources of mix materials, and the name, title, and phone number of the person responsible for developing the mix design.
 4. The locations of the QC laboratories for mix design, aggregate testing, cylinder curing, concrete testing, and compressive strength testing.
 5. Anticipated concrete mix aggregate gradations and limits.
 6. The initial and routine equipment checks and documentation performed on scales, and water meters.
 7. The methods for monitoring and recording the materials used in each batch.
 8. Procedures for documenting the locations of yielding base course and subgrade.
 9. The frequency of contractor quality control testing, if planning to perform more frequently than section B.7 specifies.
 10. The format for control charts and sampling, testing, and pay adjustment data documentation, if different from the forms provided in the CMM 4-15-42.

B.2 Personnel Requirements

- (1) Perform the material sampling, testing, and documentation required under this provision using HTCP certified technicians. Have a PCC technician certified under HTCP at level I present at the project site, prepared and equipped to perform required sampling and testing, whenever placing concrete.

B.3 Laboratory Requirements

- (1) Perform the concrete mix design, aggregate testing, cylinder curing, and compressive strength testing at a department-qualified laboratory. Obtain information on the Wisconsin laboratory qualification program from:

Quality Management Section

3502 Kinsman Blvd.

Madison Wisconsin 53704

Telephone: 608-246-3246

<http://www.dot.state.wi.us/business/engrserv/lab-qualification.htm>

B.4 Equipment Requirements

- (1) Furnish the necessary equipment and supplies for performing quality control testing. The engineer may inspect the measuring and testing devices to confirm both calibration and condition. Calibrate all testing equipment according to the CMM 4-15-12 and maintain a calibration record at the laboratory.

B.5 Concrete Pavement Mixes

B.5.1 General

- (1) Determine concrete pavement mixes for the project.
- (2) For concrete base, use a grade B, B-FA, B-S, B-IS, or B-IP concrete mix conforming to standard spec 501. The contractor may substitute aggregate conforming to the gradation requirements of a contractor-developed pavement mix design approved under the contract.

B.5.1.1 Mix Development

- (1) Have a PCC technician certified under HTCP at level II develop contractor-supplied pavement mixes. Test concrete during mix development at a department-qualified laboratory.

B.5.1.2 Submittal and Review Procedures

- (1) At least 3 business days before producing concrete, submit to the engineer 2 copies of a concrete pavement mix report. Include signature blocks for both the contractor's mix developer and the department's project engineer on the mix report cover sheet. Before the engineer's review, have the mix developer sign and date each copy attesting that all information in the report is accurate and true. The engineer will review, comment, sign, and date each copy of the report. The engineer's signature will verify that the engineer had the opportunity to review the mix report, to check that it meets the concrete mix requirements, and to comment. The engineer will keep one original signed copy and return the other copy to the contractor within 3 business days of receiving the report.

B.5.2 Standard Specification Concrete Mix

- (1) Replace the word "engineer" with the word "contractor" in standard spec 501.3.2.1. and 501.3.2.3.

- (2) The contractor may elect to use concrete pavement mixes from standard spec 501. When choosing this alternate, the contractor is responsible for mix performance just as if the contractor provided independent mix designs.
- (3) Provide mix documentation ensuring that all materials conform to standard spec 501 unless the engineer waives specific requirements. Ensure that the mix limits, including aggregate gradations, are within the master limits listed in standard spec 501.3.2.2. Include documentation for the original mix designs as follows:
 1. Mix: quantities per cubic yard expressed as SSD weights and net water, water to cementitious material ratio, air content.
 2. Materials: type, brand, and source.
 3. Aggregates: absorption, specific gravities, wear, soundness, freeze thaw test results if required, air correction factor, and proposed gradation control limits.

B.5.3 Contractor Concrete Mix Design

- (1) Delete standard spec 501.2.5.3.4, 501.2.5.4.4, 501.3.1.1.2, 501.3.2.1, 501.3.2.2, and 501.3.2.3. Delete the maximum limit for percent passing the No. 200 (75 μ m) sieve from standard spec 501.2.5.3.1 and 501.2.5.4.2.

B.5.3.1 Documentation

- (1) Provide mix design documentation ensuring that all materials conform to standard spec 501.2, as modified in this special provision, unless the engineer waives specific requirements. Include documentation for contractor mix designs as follows:
 1. Mix development: test dates, the name and location of the laboratory used to develop the mix design.
 2. Mix: quantities per cubic yard expressed as SSD weights and net water, water to cementitious material ratio, air content, and 28-day or earlier compressive strength.
 3. Materials: type, brand, and source.
 4. Aggregates: absorption, specific gravities, wear, soundness, freeze thaw test results if required, air correction factor, and proposed gradation control limits.

B.5.3.2 Mix Design Physical Requirements

- (1) Use at least 5 pairs of cylinders to demonstrate the compressive strength of a mix design. The contractor may report strengths from either laboratory testing or previous field test data for a similar mix design. Ensure that the average compressive strength achieved, in 28 days or less, by the 5 pairs of cylinders is 4200 psi (29 MPa) or greater. The contractor need not provide separate laboratory mix designs and compressive strength tests for high early strength concrete.
- (2) Provide a minimum cement content of 565 pounds per cubic yard (335 kg/m³), except if using type I or III cement in a mix where the geologic composition of the coarse aggregate is primarily igneous or metamorphic materials, provide a minimum cement content of 660 pounds per cubic yard (392 kg/m³). The contractor may partially replace Portland cement with fly ash at a replacement ratio of not less than one pound (kg) of fly ash per one pound (kg) of cement up to a maximum fly ash

content of 30% of total cementitious material. Alternatively, the contractor may use slag as a partial replacement for cement at a replacement ratio of not less than one pound (kg) of slag per 1.0 one pound (kg) of cement. For slip-formed concrete pavement do not exceed a maximum slag content of 50% of the total cementitious material. For concrete pavement not slip-formed, do not exceed a maximum slag content of 30% of total cementitious material. Alternatively, the contractor may use a combination of fly ash and slag up to a maximum combined fly ash and slag content of 30 percent. Ensure that fly ash conforms to 501.2.6 and slag conforms to standard spec 501.2.7.

- (3) The target ratio of net water to cementitious material (W/Cm) for the submitted mix design shall not exceed 0.42 by weight. Net water includes free water on the aggregate surface but does not include water absorbed within the aggregate particles.
- (4) Provide aggregate conforming to the following:
 1. One hundred percent of the aggregate shall pass the 2 inch (50 mm) sieve.
 2. The percent of total aggregate passing the No. 200 (75 μ m) sieve shall not exceed 2.3 percent, by weight.
 3. The total aggregate passing the No. 4 (4.75 mm) sieve shall not exceed 42 percent, by weight; except, if the coarse aggregate is completely composed of crushed stone and/or recycled concrete, the total aggregate passing the No. 4 (4.75 mm) sieve shall not exceed 47 percent, by weight.
- (5) Do not use chloride based accelerators in mixes for all new construction.
- (6) The contractor may adjust admixture dosages without providing a new mix design.

B.5.4 Mix Changes

- (1) Prepare and submit modifications to a standard specification concrete mix or a contractor concrete mix design to the engineer for review before using that mix. Modifications requiring the engineer's review include changes in:
 1. The source of any material.
 2. The amounts of cementitious materials.
 3. The adjustment of fine to total aggregate greater than ± 3 percent by weight.
 4. The addition or deletion of admixtures.
- (2) When the department requires or allows high early strength concrete, use type III cement. Alternatively the contractor may add a minimum of an additional 95 pounds of cement per cubic yard of concrete (57 kg cement/m³ concrete) to a previously accepted mix.

B.6 Quality Control Documentation

B.6.1 Control Charts

- (1) Maintain control charts when required by the test reporting procedures. Ensure that all tests are recorded and become part of the project records. Only include the contractor's QC tests in the 4-point running average plotted on the control charts. The

contractor may plot other contractor-performed process control or informational tests on the control charts, but do not include them in 4-point running averages.

- (2) Post control charts in an engineer-approved location and update daily. Ensure that the control charts include the project number, the test number, each test element, the applicable warning and control limits, the contractor's individual test results, the running average of the last 4 data points, and the engineer's verification and independent assurance test data points. Use the control charts as part of a process control system for identifying potential problems and assignable causes. Format control charts according to CMM 4-15-12.

B.6.2 Records

- (1) Document all observations, inspection records, mix adjustments, and tests daily. Submit original testing records and control charts to the engineer in a neat and orderly manner within 10 days after completing concrete production.

B.7 Required Quality Control Testing

B.7.1 General

- (1) Perform all quality control tests necessary to control the production and construction processes applicable to this special provision and as described in the quality control plan. Use the test methods identified below, or other methods the engineer approves, to perform the following tests:

Aggregate gradations	AASHTO T-11 ^[1] & T-27 ^[1]
Aggregate materials finer than the No. 200 sieve.....	AASHTO T 11 ^[1]
Aggregate moisture.....	AASHTO T 255 ^[1]
Air content	AASHTO T 152 ^[2]
Slump	AASHTO T 119 ^[2]
Temperature	AASHTO T 309
Compressive strength.....	AASHTO T 22, T 23, T 141, M 201

^[1] As modified in CMM 4-25-50.

^[2] As modified in CMM 4-25-70.

- (2) The department may periodically observe contractor sampling and testing, and direct additional contractor sampling and testing for department evaluation. Ensure that all test results are available for the engineer's review at any time during normal working hours.

B.7.2 Aggregate Gradation Testing

B.7.2.1 Sampling and Testing

- (1) Randomly sample and test the individual aggregate gradations according to AASHTO T 11 and AASHTO T 27 as modified by the department. Have an HTCP certified aggregate sampling technician, aggregate technician I or IPP, or PCC technician IA perform all sampling. Have an HTCP certified aggregate technician I or IPP test the aggregate and document the results. Test during aggregate production as follows:

Daily Aggregate Production, Rate in tons or Mg	Minimum Testing Frequency for Each Aggregate Stockpile
≤1000	One test per cumulative total of 1000 tons or Mg; or a minimum of one test per 5 days of aggregate production
>1000 - ≤2000	2 tests per day
>2000+	3 tests per day

- (2) If the aggregate was produced before the contract and production records are not available or not acceptable to the engineer, sample and test during concrete production at a frequency greater than or equal to the following:

Daily Concrete Production in cubic yards (m ³)	Minimum Testing Frequency for Each Aggregate Stockpile
≤250 (200)	One test per cumulative total of 250 cy (200 m ³) or a minimum of one test per 5 days of concrete production
>250 (200) - ≤1000 (750)	One test per day
>1000 (750)	2 tests per day

- (3) Ensure that only results of randomly selected QC tests are included in the 4-point running average.
- (4) Wash each sample of fine aggregate. Also wash the first 4 samples of each of the coarse aggregates. If the percent passing the No. 200 (75 µm) sieve for the coarse aggregate is less than the warning limit, wash at least every 10th sample of each of the coarse aggregates. If the percent passing the No. 200 (75 µm) sieve for the coarse aggregate is greater than or equal to the warning limit, wash each sample of the coarse aggregate until 4 consecutive tests are less than the warning limit.
- (5) Use control limits for sieve sizes as identified by the contractor in the project concrete mix report or, if the concrete mix report is not published at the time of testing, in the contractor's quality control plan. Gradation warning limits are inside the upper and lower control limit values by one percentage point for all sieves except as follows:
1. The upper warning limits for percent passing the No. 100 (150 µm) and No. 200 (75 µm) sieves are inside the control limit by 0.5 percent.
 2. For sieves allowing 100 percent passing, there is no upper warning limit. For sieves with 0 percent passing, there is no lower warning limit.

B.7.2.2 Documentation

- (1) Maintain control charts at the laboratory for each aggregate stockpile. Maintain a chart for each control sieve for each material. Record contractor test results the same day tests are conducted.

B.7.2.3 Corrective Action

- (1) When the 4-point running average value approaches a warning limit, consider corrective action. Ensure that any corrective action is documented and becomes part of the project records.
- (2) Document whenever a 4-point running average exceeds the warning limits. When a second consecutive running average value exceeds the warning limits, take corrective action. Continue corrective action until 2 consecutive average points are within the warning limits.
- (3) Notify the engineer whenever an individual test value exceeds a control limit. Material is nonconforming when an individual test exceeds the control limit. The quantity of nonconforming material includes the material of the first test exceeding the control limit, continuing to but not including, the material from the first subsequent test that is within the control limits. The department may reject material or otherwise determine the final disposition of nonconforming material as specified in standard spec 106.5.

B.7.3 Aggregate Percent Passing the No. 200 Sieve Testing

B.7.3.1 Sampling and Testing

- (1) Have an HTCP certified aggregate sampling technician, aggregate technician I or IPP, or PCC technician IA perform all sampling. Ensure that an HTCP certified PCC technician IA or a technician with both PCC technician I and aggregate technician I or IPP certifications performs all testing and documentation.
- (2) Measure and record the percent passing the No. 200 (75 μ m) sieve of both the fine and course aggregates when producing concrete pavement. Conduct tests according to AASHTO T 11 as modified by the department. Test at least one sample as early as it is practical each day and as mix or material conditions change. The contractor may reduce this testing frequency, if the engineer approves, but maintain at least one test per 5 days of concrete production.
- (3) Document testing as specified in B.6.1, B.7.2.1, and B.7.2.2, by developing a combined gradation control chart for the percent passing the No. 200 (75 μ m) sieve. Use the control limits defined in the concrete pavement mix report. Ensure that only results of QC tests are included in the 4-point running average.

B.7.3.2 Corrective Action

- (1) When an individual test approaches a warning limit, consider corrective action. Document corrective actions and include that documentation in the project records.
- (2) Notify the engineer if an individual test exceeds the warning limits. If a second consecutive individual test exceeds the warning limits, the engineer and contractor will determine the contractor's course of corrective action. If the corrective action improves the property in question such that additional individual tests are within the warning limits, the contractor may continue production. If the correction does not

improve the property, and new individual tests stay in the warning band, repeat the steps outlined here in B.7.3.2(2) starting with notifying the engineer.

- (3) Notify the engineer whenever an individual test value exceeds a control limit. Material is nonconforming when an individual test exceeds the control limit. The quantity of nonconforming material includes the material of the first test exceeding the control limit, continuing to but not including, the material from the first subsequent test that is within the control limits. The department may reject material or otherwise determine the final disposition of nonconforming material as specified in standard spec 106.5.

B.7.4 Compressive Strength

- (1) The department will adjust pay and base concrete acceptance on the compressive strength of concrete cylinders. The department will not adjust pay for concrete base or for high early strength concrete. Include tests of concrete base and high early strength concrete for all other QC testing, except no 28-day cylinders are required for concrete base or for high early strength concrete.

B.7.4.1 Concrete Sampling

B.7.4.1.1 General

- (1) The department will adjust pay for compressive strength on a lot-by-lot basis. The department will accept or reject concrete on a subplot-by-subplot basis. Designate the approximate location and size of all lots before placing concrete pavement. Ensure that no single lot contains concrete of more than one mix design, as defined in B.5, or more than one placement technique. Divide each lot into 5 or more sublots. Determine the approximate number and size of sublots before placing any concrete in that lot. Do not cast more than one set of cylinders from a single truckload of concrete. Incorporate material from any partial subplot left unsampled at the end of any day into the previous subplot for acceptance. Material from any partial subplot the contractor samples will stand on its own as a partial subplot for acceptance.
- (2) Have an HTCP certified PCC technician I or IA sample, test, and document results during concrete production and placement. Cast one set of 3 standard 6X12 inch QC cylinders for each subplot using concrete delivered to the job site. Cast all subplot cylinders from the same sample. Have a certified technician determine random subplot sampling locations as described in CMM 4-15-12. Sample according to AASHTO T 141. Cast and initially cure the cylinders according AASHTO T 23.
- (3) Fabricate one set of 3 companion cylinders for department testing during each day of concrete production from a subplot the engineer designates. Use the same concrete sample as used for the contractor's QC cylinders for that subplot. Provide all materials, fabrication, initial curing, and handling required for companion cylinders for up to 3 days following fabrication.

B.7.4.1.2 Slip-Formed

- (1) A lot typically consists of the amount of concrete pavement placed during each day's paving.
- (2) Divide each lot into standard sublots. Define the standard subplot size in the quality control plan, but do not exceed 500 cubic yards (382m³).
- (3) If less than 5 random samples are collected in a day, incorporate the represented concrete into the following or previous day's pavement lot.

B.7.4.1.3 Not Slip-Formed

- (1) Do not exceed a lot size of 1000 cubic yards (765 m³).
- (2) Define at least one subplot per day per mix grade placed. Do not exceed a subplot size of 200 cubic yards (153 m³).

B.7.4.2 Concrete Cylinder Curing

- (1) Provide facilities for initial curing. For up to 48 hours after casting, maintain the temperature adjacent to the specimens in the range of 60 to 80 degrees F (16 - 27 degrees C) and prevent moisture loss. Between 24 and 48 hours after casting, transport the specimens to a department-qualified laboratory for standard curing according to AASHTO M 201 for 28 days.

B.7.4.3 Compressive Strength Testing

- (1) Have an HTCP certified compressive strength tester, in a department-qualified laboratory, perform compressive strength testing and document the results. Randomly select 2 QC cylinders to test at 28 days.
- (2) Determine the 28-day compressive strength in psi of each cylinder according to AASHTO T 22. Test each cylinder to failure. Use a compression machine that automatically records the date, time, rate of loading, and maximum load of each cylinder. Include a printout of this information with the compressive strength documentation for each cylinder tested.
- (3) Compare the strengths of the 2 randomly selected QC cylinders and determine the 28-day subplot average strength as follows:
 - If the lower strength divided by the higher strength is 0.9 or more, average the 2 QC cylinders.
 - If the lower strength divided by the higher strength is less than 0.9, break one additional cylinder and average the 2 higher strength cylinders.

B.7.4.4 Removal and Replacement

- (1) If a subplot strength is less than 2500 psi (17.2 MPa), the department may direct the contractor to core that subplot to determine its structural adequacy and whether to direct removal. Cut and test cores according to AASHTO T 24 as and where the engineer directs. Have an HTCP certified PCC technician I perform or observe the

- coring. Bear all coring and testing costs, fill all core holes with an approved grout, and provide traffic control during coring at no cost to the department.
- (2) The subplot pavement is conforming if the compressive strengths of all cores from the subplot are 2500 psi (17.2 MPa) or greater or the engineer does not require coring. The department will allow conforming material to remain in place and use the original cylinder strength results in the calculation for the lot pay adjustment as specified in G.3.
 - (3) The subplot pavement is nonconforming if the compressive strengths of any core from the subplot is less than 2500 psi (17.2 MPa). The department may direct removal and replacement or otherwise determine the final disposition of nonconforming material as specified in standard spec 106.5.

B.7.5 Air Content

- (1) On each day of production, test air content at the point of placement at start-up and as frequently as practicable until the concrete meets the specifications and the production process is under control. Subsequently, test air content for each compressive strength subplot. Have an HTCP certified PCC technician I or IA test air content according to AASHTO T 152, as modified by the department. Test concrete taken from the same sample used for QC strength cylinders, and as the engineer directs.
- (2) The lower and upper control limits for air content are the values specified in 501.3.2.4.2. of the standard specifications. The lower warning limit for air content is 0.5 percent above the lower control limit. There is no upper warning limit.

B.7.5.1 Documentation

- (1) Maintain a control chart at a fixed location on the project site. Ensure that all test results are recorded and become part of the project records. Chart all results on the same day tests are conducted. Only plot results of samples selected randomly in the 4-point running average.
- (2) Document admixture dosage rates, time of day, and air temperature on the combined gradation control chart for the percent passing the No. 200 (75 μ m) sieve whenever changing an admixture dosage rate.

B.7.5.2 Corrective Action

- (1) If an individual air test is between the lower warning limit and lower control limit, double the air content test frequency to 2 tests per compressive strength subplot. Perform one of these tests from the same concrete sample used for the QC strength cylinders. Select the second sample randomly from the half of the subplot not used for the QC strength cylinders. Determine both random test locations within a subplot before paving that subplot. Continue testing at increased frequency until an individual test point is above the lower warning limit and below the upper control limit.

- (2) When the 4-point running average value trend is towards the lower warning limit or the upper control limit, consider corrective action.
- (3) Notify the engineer if a 4-point running average is less than the lower warning limit. If a second consecutive running average is below the warning limit, the engineer and contractor will determine the contractor's course of corrective action. If the corrective action improves the property in question such that the new running average, after four additional individual tests, is between the lower warning limit and upper control limit, the contractor may continue production. If the new running average is below the lower warning limit, repeat the steps outlined here in B.7.5.2(3) starting with notifying the engineer.
- (4) If an individual air test is outside the control limits, notify the engineer, and perform additional air tests as often as it is practical on subsequent loads until the air content is inside the control limits. The material is nonconforming when an individual test exceeds the control limit. Material from the load with the first test exceeding the control limit, continuing to but not including the load with the first subsequent test within the control limits, is nonconforming. The department may direct removal and replacement or otherwise determine the final disposition of nonconforming material as specified in standard spec 106.5.

B.7.6 Concrete Temperature

- (1) Have an HTCP certified PCC technician I or IA measure concrete temperature according to AASHTO T 309. Test concrete taken from the same sample used for QC strength cylinders. Record concrete temperatures on the air content control chart.

B.7.7 Slump

- (1) Have an HTCP certified PCC technician I or IA measure slump according to AASHTO T 119. The contractor need not test slump for slip-form paving unless the engineer requests. For other placement techniques, test slump whenever an air content test or cylinders are made and as the engineer directs. Provide material conforming to the slumps specified in standard spec 415.3.6.

C Department Testing

C.1 General

- (1) The department will conduct verification testing to validate the quality of the product and independent assurance testing to evaluate the sampling and testing. The department will provide the contractor with a listing of names and telephone numbers of all verification and independent assurance personnel for the project.
- (2) Except for strength, the department will provide test results to the contractor within 2 business days after the department obtains the sample.

C.2 Verification Testing

- (1) The department will have an HTCP technician, or ACT under the direction of a certified technician, perform QV sampling and testing. Department verification

testing personnel must meet the same certification level requirements specified for contractor testing personnel for each test being verified. The department will notify the contractor before sampling so the contractor can observe QV sampling.

- (2) The department will sample randomly at locations independent of the contractor's QC work. In all cases, the department will conduct the verification tests in a separate laboratory and with separate equipment from the contractor's QC tests.
- (3) The department will perform verification testing as follows:

	Testing Frequency Guide ^[1]	Sampling Material and Location	Test Method	Alternate Test Methods
Air content	1 per lot	Plastic concrete, ahead or behind ^[2] the paver	AASHTO T 152 as modified	Hardened air content testing ^[2] after construction
28-day compressive strength	1 per 5 lots	Cylinders	AASHTO T 22, T 23 & T 141 as modified	Random cores ^[2] after construction

^[1] The engineer may increase the frequency at start-up or as necessary to validate the quality of the materials. The engineer may reduce the frequency based on a history of satisfactory contractor or material performance.

^[2] Evaluation of test results should account for systematic differences in testing methods or sampling locations.

- (4) The department will conduct verification testing for pavement thickness as specified in standard spec 415.3.18.
- (5) Plot verification tests on the contractor's quality control charts as specified in B.6.1. Do not include verification tests in the 4-point running average.
- (6) If verification tests indicate conformance with specifications, no further action is required. If verification tests indicate nonconformance with specifications, the engineer and contractor will jointly investigate any testing discrepancies. The investigation may include additional testing as well as review and observation of both the department's and contractor's sampling and testing procedures and equipment. Both parties will document all investigative work.
- (7) Correct all deficiencies. If the contractor does not respond to an engineer request to correct a deficiency or resolve a testing discrepancy, the engineer may suspend production until action is taken. Resolve disputes as specified in D.

C.3 Independent Assurance Testing

- (1) Independence assurance is unbiased testing the department performs to evaluate the department's verification and the contractor's QC sampling and testing including personnel qualifications, procedures, and equipment. The department will perform the independent assurance review according to the department's independent assurance program, which may include one or more of the following:
 1. Split sample testing.
 2. Proficiency sample testing.
 3. Witnessing sampling and testing.
 4. Test equipment calibration checks.
 5. Reviewing required worksheets and control charts.
 6. Requesting that testing personnel perform additional sampling and testing.
- (2) Plot the independent assurance tests on the contractor's quality control charts as specified in B.6.1. Do not include independent assurance tests in the 4-point running average.
- (3) If the department identifies a deficiency, and after further investigation confirms it, correct that deficiency. If the contractor does not correct or fails to cooperate in resolving identified deficiencies, the engineer may suspend production until action is taken. Resolve disputes as specified in D.

D Dispute Resolution

- (1) The engineer and contractor should make every effort to avoid conflict. If a dispute between some aspect of the contractor's and the engineer's testing program does occur, seek a solution mutually agreeable to the project personnel. The department and contractor may review the data, examine data reduction and analysis methods, evaluate sampling and testing procedures, and perform additional testing. Use ASTM E 178 to evaluate potential statistically outlying data.
- (2) If the project personnel can not resolve a dispute and the dispute affects payment or could result in incorporating nonconforming product, the department will use third party testing to resolve the dispute. The department's central office laboratory, or a mutually agreed on independent testing laboratory, will provide this testing. The engineer and contractor will abide by the results of the third party tests. The party in error will pay service charges incurred for testing by an independent laboratory. The department may use third party tests to evaluate the quality of questionable materials and determine the appropriate payment. The department may reject material or otherwise determine the final disposition of nonconforming material as specified in standard spec 106.5.

E Acceptance

- (1) The department will accept concrete pavement based on the contractor QC tests unless it is shown through the verification, or the dispute resolution process that the contractor's tests are in error.

F Measurement

- (1) The department will measure QMP Concrete Pavement by the day for QC testing acceptably completed. The department will measure, in 1/2-day increments, the time spent placing concrete under the bid items listed in A.1. The department will measure 1/2 day for 4 hours or less of concrete paving and one day for greater than 4 hours of concrete paving. The department will only measure the QMP Concrete Pavement bid item if all of the following conditions are met:
 1. The contractor is placing concrete pavement.
 2. QC sampling and testing is required under the contract.
 3. All required sampling and testing is performed.
- (2) If these conditions are met, the department will measure paving time beginning when the first truckload of concrete is discharged and ending when the last truck discharges its concrete. The department will start and stop measurement of paving time based on the start and stop of the contractor's paving operations.
- (3) If the contractor demonstrates, to the engineer's satisfaction, that it is necessary to use more than one testing crew during multiple paving operations, the department will measure time for each testing crew working concurrently.
- (4) The department will measure Incentive Strength Concrete Pavement by the dollar, adjusted as specified in G.3.

G Payment

G.1 General

- (1) The department will pay for measured quantities at the contract unit price under the following bid items:

ITEM NUMBER	DESCRIPTION	UNIT
415.3000.S	QMP Concrete Pavement	Day
415.2000.S	Incentive Strength Concrete Pavement	DOL

G.2 QMP Testing

- (1) Payment for QMP Concrete Pavement is full compensation for all sampling, testing, and documentation required under this special provision. If the contractor fails to perform the work required under this special provision, the department may reduce the contractor's pay. The department will administer pay reduction under the non-performance of QMP administrative item.

G.3 Pay Adjustment for Strength

- (1) The department will pay incentive for compressive strength under the Incentive Strength Concrete Pavement bid item. Incentive payment is not limited, either up or down, to the amount the schedule of items shows.
- (2) The department will administer disincentives for compressive strength under the Disincentive Strength Concrete Pavement administrative item.

- (3) Pay adjustment is based on contractor quality control testing unless alternate data is required to resolve disputed tests. Submit documentation for pay adjustment as soon as strengths are available using CMM 4-15-42 WS 4151.
- (4) The department will adjust the pay for each lot as follows:
1. The department will determine the lot average strength and sample standard deviation according to CMM 4-15-42 figure 1. The department will not include results from sublots with air content less than the lower control limit. The department will weight results from all other full, partial, or combined sublots equally. The department will include the subplot strength tests less than 2500 psi (17.2 MPa) if the material is left in place.
 2. The department will adjust pay based on the lot average strength minus one standard deviation as follows:

Lot Average - SD (psi)		Pay Adjustment (Dollars/SY)	Lot Average - SD (psi)		Pay Adjustment (Dollars/SY)
Greater Than or Equal To	Less Than		Greater Than or Equal To	Less Than	
	2850	-0.55	3750	3850	+0.07
2850	2950	-0.53	3850	3950	+0.13
2950	3050	-0.45	3950	4050	+0.17
3050	3150	-0.39	4050	4150	+0.20
3150	3250	-0.31	4150	4250	+0.23
3250	3350	-0.23	4250	4350	+0.24
3350	3450	-0.17	4350	4450	+0.26
3450	3550	-0.11	4450	4550	+0.27
3550	3650	-0.05	4550	4650	+0.27
3650	3750	0.00	4650		+0.28

- (5) The department will apply the disincentive pay adjustment to the total area of the strength lot. The department will not pay incentive for any quantity of concrete incorporated into the work with air content or slump outside the limits specified in B.7.5 and B.7.7.

(051206) 415-065

22. QMP HMA Pavement Nuclear Density, Item 460.2500.S.

A Description

A.1 General

Replace 460.3.3.2 (1) and 460.3.3.2(4) with the following:

- (1) This special provision describes density testing of in-place HMA pavement with the use of nuclear density gauges. Conform to section 460 of the standard specifications and as modified in this special provision.

- (2) Provide and maintain a quality control program defined as all activities and documentation of the following:
 1. Selection of test sites.
 2. Testing.
 3. Necessary adjustments in the process.
 4. Process control inspection.
- (3) Chapter 4 of the department's construction and materials manual (CMM) provides additional detailed guidance for QMP work and describes required procedures. Obtain the CMM from the department's extranet site at:
<http://trust.dot.state.wi.us/extntgtwy/dtidcons/constnds/cmm/cmm.htm>.

B Quality Control Program Requirements

B.1 Personnel Requirements

- (1) Perform HMA pavement density (QC, QV) testing with nuclear gauges under this provision using HTCP certified Nuclear Technician I operators.

B.2 Testing

- (1) Conform to ASTM D2950 and CMM 4-5-90 for density testing and gauge monitoring methods. Perform nuclear gauge measurements using gamma radiation in the backscatter position. Perform each test for 4 minutes of nuclear gauge count time.

B.3 Equipment

B.3.1 General

- (1) Furnish nuclear gauges from the department's approved product list at <http://www.atwoodsystems.com/materials> that is used for necessary testing (QC, QV). The manufacturer will perform calibration of gauge or an approved calibration service within 12 months of time used on project. Retain a copy of the manufacturer's calibration certificate with the gauge.

B.3.2 Correlation of Nuclear Gauges

B.3.2.1 Correlation of QC and QV Nuclear Gauges

- (1) Select a representative section of the compacted pavement prior to or on the first day of paving for the correlation process. The section does not have to be the same mix design.
- (2) Correlate the two or more gauges used for density measurement (QC, QV). The QC and QV gauge operators will perform the correlation on 5 test sites jointly located. Record each density measurement of each test site for the QC, QV and back up gauges.
- (3) Calculate the average of the difference in density of the 5 test sites between the QC and QV gauges. Locate an additional 5 test sites if the average difference exceeds 1 lb/ft³ (16 kg/m³). Measure and record the density on the 5 additional test sites for each gauge.

- (4) Calculate the average of the difference in density of the 10 test sites between the QC and QV gauges. Replace one or both gauges if the average difference of the 10 tests exceeds 1 lb/ft^3 (16 kg/m^3) and repeat correlation process from B.3.2.1(2).
- (5) Furnish 1 QC gauge passing the allowable correlation tolerances as the primary gauge. Perform all density testing on the project with the primary gauge.
- (6) Remove or replace a gauge if it fails to stay within the allowable tolerances set on the reference site. Re-correlation is not necessary if a back-up gauge was tested in the original correlation process.

B.3.2.2 Correlation Monitoring

- (1) Establish a project reference site approved by the department. Clearly mark a flat surface of concrete or asphalt or other material that will not be disturbed during the duration of the project. Perform correlation monitoring of the QC, QV, and all back-up gauges at the project reference site.
- (2) Conduct an initial 10 density tests using a gauge on the project reference site and calculate the average value to establish a reference value. Use the reference value as a control to monitor the calibration of the gauge for the duration of the project.
- (3) Check the gauges on the project reference site a minimum of 1 test per day if paving on the project and compare to the reference value. Maintain the reference site test data for each gauge at an agreed location.
- (4) Calculate difference in measured density verses reference values and investigate if the difference exceeds 1.5 lb/ft^3 (24 kg/m^3). Conduct 5 additional tests at the reference site once the cause of deviation is corrected and record and calculate the average. Remove the gauge from the project if the average exceeds 1.5 lbs/ft^3 (24 kg/m^3).
- (5) Perform the correlation process specified in B.3.2.1 with replacement QC or QV gauge.

B.4 Quality Control Testing and Documentation

B.4.1 Traffic Lanes, Shoulders, and Appurtenances

- (1) Conduct a minimum of 7 random QC nuclear gauge density tests per lot.
- (2) Prior to the start of paving select the frequency of QC testing for each layer of paving and inform the engineer. Maintain the selected frequency for the duration of the project unless approved by the engineer. Table 1 is provided to assist in selecting the frequency of testing for various confidence limits with a tolerance of $+1.0 \text{ lb/ft}^3$ (16 kg/m^3) but does not have to be used.

Confidence Level	Number of Tests
95	24
90	17
85	13
80	11
75	9
70	7

Table 1

- (3) Select QC test site, station and offset distance randomly as specified in CMM 4-5-90 prior to paving and provide a copy to the engineer. Locate and mark QC density test site for each lot prior to performing test. Perform density test prior to open traffic on pavement.
- (4) Calculate pavement density by averaging the nuclear density reading for the selected number of tests for a lot. Additional tests for compaction process control can be taken but not used in calculating pavement density for a lot.
- (5) Document QC density test data as specified in CMM 4-5-90. Provide the engineer the original data sheet for each lot within 24 hours of QC testing completion for that lot.

B.4.2 Side Roads, Crossovers, Turn Lanes, and Ramps (< 750 tons per layer)

- (1) A lot represents a combination of the lanes of each side road leg of an intersection for each layer.
- (2) A lot represents a turn lane, crossover, and ramp for each layer.
- (3) Perform the number of tests per lot as specified in Table 2.

Side Roads, Turn Lanes, Crossovers, Ramps: Lot/Layer tonnage	Minimum Number of Tests Required
< 250 Tons	3
251 to 500 tons	5
501 to 750 tons	7

Table 2

B.4.3 Corrective Action

- (1) Notify the engineer immediately when a lot average density value or individual test is 3.0 percent or greater, below the specified minimum in 460.3.3.1 of the standard specifications.
- (2) Remove and replace the area of the layer specified in B.4.3(1) and replace with material that meets the specified minimum density. Determine limits of the area to be removed by measuring density of the layer at 50-foot (15 m) increments both ahead and behind the point of unacceptable density and at the same offset as the original test site. Continue testing 50-foot (15 m) increments until a point of acceptable density is

found as specified in 460.5.2.2(1) of the standard specifications. Removal and replacement of material may be required if extended testing is in a previously accepted lot. Testing in a previously accepted lot will not be used to recalculate a new lot density.

- (3) Compute unacceptable pavement area using the product of the longitudinal limits of the unacceptable density and the full width of the paver pass, lying in the traffic lane or lanes. Shoulders shall be exempt from this calculation.
- (4) Retesting and acceptance of replaced pavement will be as specified in 105.3 of the standard specifications.
- (5) Tests indicating greater than 3.0 percent density below the specified minimum and further tests taken to determine the limits of unacceptable area to be removed, will be excluded from computation of lot density. Test results of the replaced pavement will not be included in the original lot density computations unless the quantity replaced represents 20 percent or greater of the lot quantity.

C Department Testing

C.1 Verification Testing

- (1) The department will have an appropriately HTCP certified technician perform verification testing. The department will test randomly at locations independent of the contractor's QC work. The department will perform verification testing at a frequency of 10 percent of the lots and a minimum of one lot per mix design. The lots selected will be within the active work zone and under the contractor's construction traffic control. The verification average density for a lot will be the average of at least 7 tests for the lot. It is strongly recommended that the same frequency of test for QC be used for QV.
- (2) Verification test results that meet required contract density will indicate QC test results are acceptable. Verification tests within 1.5 lb/ft^3 (24 kg/m^3) of the QC average lot test results will indicate the QC test results are acceptable. Verification tests resulting in a difference greater than 1.5 lb/ft^3 (24 kg/m^3) of the QC average lot test result will be resolved with dispute resolution specified in D. The engineer will notify the contractor immediately when density deficiencies or testing precision exceeding the allowable differences are observed.
- (3) The department will document QV density test data on project data sheets used for QC testing. The department will provide the contractor a copy of the sheet for each lot within 24 hours of QV testing completion.

D.2 Independent Assurance Testing

- (1) Independent assurance is unbiased testing the department performs to evaluate the department's verification and the contractor's QC sampling and testing including personnel qualifications, procedures, and equipment. The department will perform the

independent assurance review according to the department's independent assurance program.

E Dispute Resolution

- (1) Investigation of non-correlating QC and QV test results will be conducted to determine cause. Gauges will be checked on the project reference site and if one is found to be out of calibration, the gauge will be removed from the project and the other gauge's test results will be used for material acceptance.
- (2) Continue investigation in the work zone by analyzing testing, calculation, and documentation procedures if the gauges are both in calibration. If the testing discrepancy cannot be identified, the contractor may elect to accept the QV lot density test results or retesting of the lot in dispute within 48 hours of paving. Traffic control costs will be split between the department and the contractor.
- (3) If investigation finds that both gauges are in error, the contractor and engineer will reach a decision on resolution through mutual agreement.

F Final Acceptance

- (1) The department will accept QMP HMA Pavement Nuclear Density based on the contractor QC tests, unless it is shown through the verification or the dispute resolution process that the contractor's test results are in error.
- (2) The department will not accept QMP HMA Pavement Nuclear Density if primary gauge or assigned backup gauge is not used for contractor QC tests.

G Measurement

- (1) The department will measure QMP HMA Pavement Nuclear Density for payment by the ton based on the quantity of HMA pavement acceptably completed.

H Payment

H.1 General

- (1) The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
460.2500.S	QMP HMA Pavement Nuclear Density	Ton

H.2 QMP HMA Pavement Nuclear Density

- (1) Payment is full compensation for furnishing all labor, tools, equipment testing and record keeping; and for furnishing all incidental work necessary to complete the contract work.

H.2.1 Disincentive for QMP HMA Pavement Nuclear Density

- (1) The department will administer density disincentives under the Disincentive Density HMA Pavement and disincentive Density Asphaltic Material administrative items. If the lot density is less than the specified minimum the department will reduce pay

based on the contract unit price and as specified in 460.5.2.2 of the standard specifications.

- (2) The department will administer density disincentives under the Disincentive Density HMA Pavement and disincentive Density Asphaltic Material administrative items. If the lot density is not performed with the primary gauge or assigned backup the department will reduce pay based on the contract unit price and as determined by dispute resolution process.

(100906) 460-020

23. QMP Concrete Structures; Incentive Strength Concrete Structures, Item 502.0400.S.

A Description

A.1 General

- (1) Conform to standard specifications 501, 502, and 504 as modified in this special provision. Apply this special provision to all other cast in place concrete placed under the following bid items:

502.0100	Concrete Masonry Bridges
502.0200	Concrete Masonry Bridges HES
502.1100	Concrete Masonry Seal
504.0100	Concrete Masonry Culverts
504.0200	Concrete Masonry Culverts HES
504.0500	Concrete Masonry Retaining Walls
504.0600	Concrete Masonry Retaining Walls HES

- (2) Provide and maintain a quality control program, defined as all activities and documentation of the following:
 1. Mix design.
 2. Production control, placement control, and inspection.
 3. Sampling, testing, and making necessary adjustments related to the production of ready-mixed concrete conforming to the contract.

- (3) Chapter 4 of the department's construction and materials manual (CMM) provides additional detailed guidance for QMP work and describes required sampling and testing procedures. The contractor may obtain the CMM from the department's web site at:

<http://www.dot.wisconsin.gov/business/engrserv/index.htm>

- (4) The department's Materials Reporting System (MRS) software allows contractors to submit data to the department electronically, estimate pay adjustments, and print selected reports. Qualified personnel may obtain MRS software from the department's web site at:

<http://atwoodsystems.com/mrs>

A.2 Pre-Pour Meetings

- (1) Arrange at least two pre-pour meetings to discuss concrete placement. Discuss the placement schedule, personnel roles and responsibilities, testing and quality control, and how test results will be communicated. Schedule the first meeting before placing any concrete and the second before placing any bridge deck concrete. Ensure that representatives from all parties involved with concrete work, including contractor, sub-contractor, ready mix supplier, testers, and the project manager, attend these meetings.

A.3 Contractor Testing for Small Quantities

- (1) The department defines a small quantity for each individual applicable bid item, as a plan quantity of 150 cubic yards (114.7 m³) or less of concrete as shown in the schedule of items under that bid item.
- (2) The requirements under this special provision apply equally to a small quantity for an individual bid item except as follows:
 1. The contractor need not submit a full quality control plan but shall provide an organizational chart to the engineer including names, telephone numbers, and current certifications of all persons involved in the quality control program.
 2. The engineer may accept aggregate gradation based upon one or both of the following:
 - Satisfactory records of previous testing.
 - At least one test performed before beginning concrete production.
 3. Divide the concrete placed under each bid item into approximately uniformly sized sublots as follows:

QUANTITY PLACED	MINIMUM REQUIRED NUMBER OF SUBLOTS ^[1]
≤ 50 cubic yards (38.2 m ³)	One subplot
> 50 cubic yards (38.2 m ³) and ≤ 100 cubic yards (76.5 m ³)	Two sublots
> 100 cubic yards (76.5 m ³) and ≤ 150 cubic yards (114.7 m ³)	Three sublots

^[1] If the quantity placed overruns 150 cubic yards (114.7 m³), create overrun sublots to test at a rate of one additional subplot for 50 cubic yards (38.2 m³), or fraction of 50 cubic yards (38.2 m³), of overrun.

4. No concrete control charts are required. Submit test results to the engineer each day as they become available. Assure that all properties are within the limits specified in the standard specifications for each subplot tested and that the subplot compressive strength equals or exceeds f'c.

B Materials

B.1 Quality Control Plan

- (1) Submit a comprehensive written quality control plan. Construct the project as the plan provides. Submit the plan to the engineer no later than ten business days before

placing concrete. Do not begin concrete production or change the quality control plan without the engineer's review. Update the plan with changes as they become effective. Provide a current copy of the plan to the engineer and post in each of the contractor's laboratories before producing concrete and as changes are adopted. Ensure that the plan provides the following elements:

1. An organizational chart including names, telephone numbers, current certifications and/or titles, and roles and responsibilities of all QC personnel.
2. The process by which quality control information and corrective action efforts will be disseminated to the appropriate persons including materials suppliers. Include a list of recipients, the communication means that will be used, action time frames, and report formats.
3. Preliminary mix information including anticipated producers, manufacturers, and sources of mix materials, and the name, title, and phone number of the person responsible for developing the mix design.
4. The locations of the QC laboratories for mix design, aggregate testing, cylinder curing, concrete testing, and compressive strength testing. Include a description of the sampling and testing equipment.
5. Aggregate information including production and handling operations; how contamination, segregation, and degradation will be minimized; and anticipated concrete mix aggregate gradations and limits.
6. The procedures for delivering, storing, and managing all mix materials.
7. Facilities, procedures, and controls used to produce a mix conforming to the specifications and the mix design.
8. The equipment, times, and methods used to deliver the concrete mix to the work site and to the point of placement.
9. The initial and routine equipment checks and documentation performed on scales, water meters, admixture dispensers; and delivery, placing, surfacing, and curing equipment..
10. The methods for monitoring and recording the materials used in each batch.
11. The equipment and procedures for placing concrete and controlling the alignment, profile, cross slope, and thickness.
12. The procedures that will be employed to correct problems as they occur.
13. A description of the methods for finishing, texturing, and curing concrete.
14. The types, standards, and frequency for contractor quality control (QC) testing. Conform to B.7 of this special provision and include, but do not limit discussion to, the following:
 - The number of tests performed for aggregate gradations, moisture and fines; air content, temperature, slump, and compressive strength.
 - Procedures for checking and documenting steel cover including locations and testing methods.
 - Procedures for checking and documenting surface smoothness.
 - Proposed corrective actions for each tested property.
15. The lot layouts for compressive strength evaluation.
16. Provisions for responding to adverse weather conditions; such as precipitation, and hot and/or cold weather placement.

B.2 Personnel Requirements

- (1) Perform the material sampling, testing, and documentation required under this provision using HTCP certified technicians. Have a PCC technician certified under HTCP at level I present at the project site, prepared and equipped to perform required sampling and testing whenever placing concrete.

B.3 Laboratory Requirements

- (1) Perform the concrete mix design, aggregate testing, cylinder curing, and compressive strength testing at a department-qualified laboratory. Obtain information on the Wisconsin laboratory qualification program from:

Quality Management Section
3502 Kinsman Blvd.
Madison Wisconsin 53704
Telephone: 608-246-3246

<http://www.dot.state.wi.us/business/engrserv/lab-qualification.htm>

B.4 Equipment Requirements

- (1) Furnish the necessary equipment and supplies for performing quality control testing. The engineer may inspect the measuring and testing devices to confirm both calibration and condition. Calibrate all testing equipment according to the CMM 4-15-12 and maintain a calibration record at the laboratory.

B.5 Concrete Masonry Mixes

B.5.1 General

- (1) Have a PCC technician certified under HTCP at level II develop new concrete mixes for structures on the project. Test new mixes at a department-qualified laboratory. Alternatively the contractor may submit established mixes qualified exclusively by field performance.
- (2) At least three business days before producing concrete, submit to the engineer two copies of a concrete mix report. Include signature blocks for both the contractor's mix developer and the department's project engineer on the mix report cover sheet. Before the engineer's review, have the mix developer sign and date each copy attesting that all information in the report is accurate and true. The engineer will review, comment, sign, and date each copy of the report. The engineer's signature will verify that the engineer had the opportunity to review the mix report, to check that it meets the concrete mix requirements, and to comment. The engineer will keep one original signed copy and return the other copy to the contractor within three business days of receiving the report.

B.5.2 Concrete Mix Design

B.5.2.1 General

- (1) Delete standard specifications 501.2.5.3.4, 501.2.5.4.4, 501.3.2.1, 501.3.2.2, and 501.3.2.3. Delete the maximum limit for material passing the No. 200 (75 μ m) sieve (P 200) from standard specification 501.2.5.3.1 and 501.2.5.4.2.

- (2) For all bridge superstructure and substructure concrete, use a mix grade containing fly ash (A-FA), slag (A-S), both fly ash and slag (A-T), or blended cement (A-IP or A-IS).
- (3) For concrete seals, use a grade D mix and construction methods conforming to standard specifications 501 and 502.

B.5.2.2 Documentation

- (1) Provide mix design documentation ensuring that all materials conform to standard specifications 501.2, as modified in this special provision, unless the engineer waives specific requirements. Include documentation for contractor mix designs as follows:
 1. Mix development: test dates, the name and location of the laboratory used to develop the mix design.
 2. Mix: quantities per cubic yard expressed as SSD weights and net water, water to cementitious material ratio, air content, and 28-day or earlier compressive strength.
 3. Materials: type, brand, and source.
 4. Aggregates: absorption, specific gravities, wear, soundness, freeze thaw test results if required, air correction factor, and proposed gradation control limits.

B.5.2.3 Concrete Mix Physical Requirements

- (1) Qualify compressive strength according to ACI Code 318 chapter 5 subsections 5.3.1 through 5.3.3 and 5.5. Use either laboratory strength data for new mixes or field strength data for established mixes. Demonstrate that the 28-day compressive strength of the proposed mix will equal or exceed the 80 percent within limits criterion specified in E.3.
- (2) Ensure that the cementitious content for grade A concrete equals or exceeds 565 pounds per cubic yard (335 kg/m³). For all superstructure and substructure concrete, unless the engineer approves otherwise in writing, conform to one of the following:
 1. Use class C fly ash or grade 100 or 120 slag as a partial replacement for Portland cement. For binary mixes use 15% to 30% fly ash or 20% to 30% slag. For ternary mixes use 15% to 30% fly ash plus slag in combination. Percentages are stated as percent by weight of the total cementitious material in the mix.
 2. Use a type IP, IS, or I(SM) blended cement.
- (3) The target ratio of net water to cementitious material (W/Cm) for the submitted mix design shall not exceed 0.45 by weight. Net water includes free water on the aggregate surface but does not include water absorbed within the aggregate particles. Control the W/Cm ratio throughout production by adjusting batch weights for changes in the aggregate moisture as required under B.7.3.2.
- (4) Ensure that the combined aggregate gradation conforms to the following, expressed as weight percentages of the total aggregate:

1. One hundred percent passes the 2 inch (50 mm) sieve.
 2. The percent passing the 1 inch (25 mm) sieve is less than or equal to 89. The engineer may waive this requirement where the clear spacing between reinforcing bars is less than 2 inches (50 mm).
 3. The percent passing the No. 4 (4.75 mm) sieve is less than or equal to 42, except if the coarse aggregate is completely composed of crushed stone, up to 47 percent may pass the No. 4 sieve (4.75 mm) sieve.
 4. The P 200 (75 μ m) is less than or equal to 2.3 percent.
- (5) Do not use any chemical admixtures, other than air-entraining agents or water reducers from the department's approved products list, without conforming to the following:
1. Obtain the engineer's approval in advance.
 2. Document, by independent laboratory test reports, that the admixture conforms to AASHTO M 194.
- (6) Do not use mixes containing chloride based accelerators. The contractor may use mixes containing non-chloride accelerators in substructure elements only.

B.5.3 Mix Changes

- (1) Prepare and submit changes to a concrete mix to the engineer for review before using that mix. Changes requiring the engineer's review include:
 1. Source of any material.
 2. Amounts of cementitious materials.
 3. Adjustment of fine to total aggregate greater than ± 3 percent by weight.
 4. Admixtures used in the mix.
- (2) Adjusting admixture dosages does not require the engineer's review.

B.6 Quality Control Documentation

B.6.1 Control Charts

- (1) Maintain control charts when required by the test reporting procedures. Ensure that all test results are recorded and become part of the project records. Plot required test results on the control charts. Include random, non-random, and engineer requested testing but only include the contractor's randomly selected QC test results in the 4-point running average. The contractor may plot other contractor-performed process control or informational test results on the control charts, but do not include them in 4-point running averages.
- (2) Post control charts in an engineer-approved location both on the project and at the concrete production site. Update control charts daily. Ensure that the control charts include the project number, the test number, each test element, the applicable warning and control limits, the contractor's individual test results, the running average of the last 4 data points, and the engineer's verification and independent assurance test data points. Use the control charts as part of a process control system for identifying

potential problems and assignable causes. Format control charts according to CMM 4-15-12.

- (3) Submit control charts to the engineer in a neat and orderly manner within 10 days after completing concrete production.

B.6.2 Records

- (1) Document all observations, inspection records, mix adjustments, and test results daily. Submit test results to the department electronically using the MRS software. Complete all required data entry fields. Record other test results using the forms provided in CMM 4-15-42. Note other information in a permanent field record and, if appropriate, plot on control charts.
- (2) Post cylinder strength summary tables for each lot in an engineer-approved location both on the project and at the concrete production site. Update cylinder strength summary tables daily.
- (3) Submit original testing records to the engineer in a neat and orderly manner within ten days after completing concrete production.

B.7 Required Contractor Testing

B.7.1 General

- (1) Perform all contractor tests required under this special provision as well as additional contractor testing described in the quality control plan. Use the test methods identified below or other engineer-approved methods to perform the following tests:

Gradations	AASHTO T-11 ^[1] & T-27 ^[1]
P 200 (75 µm)	AASHTO T 11 ^[1]
Aggregate moisture	AASHTO T 255 ^[1]
Air content	AASHTO T 152 ^[2]
Slump	AASHTO T 119 ^[2]
Temperature	AASHTO T 309
Compressive strength.....	AASHTO T 22, T 23, T 141, M 201

^[1] As modified in CMM 4-25-50.
^[2] As modified in CMM 4-25-70.
- (2) The department may periodically observe contractor sampling and testing, and direct additional contractor sampling and testing for department evaluation. Ensure that all test results are available for the engineer's review at any time during normal working hours.

B.7.2 Aggregate Gradation Testing

B.7.2.1 Sampling and Testing Requirements

- (1) Randomly sample and test the individual aggregate gradations according to AASHTO T 11 and AASHTO T 27 as modified by the department. Have an HTCP certified aggregate sampling technician, aggregate technician I or IPP perform all sampling.

Have an HTCP certified aggregate technician I or IPP test the aggregate and document the results.

- (2) Test during aggregate production as follows:

DAILY AGGREGATE PRODUCTION in tons or Mg	MINIMUM FREQUENCY PER STOCKPILE tests per day
≤1000	1
>1000 - ≤2000	2
>2000	3

- (3) If the aggregate was produced before the contract and production records are not available or not acceptable to the engineer, test during concrete production. Test each stockpile conforming to whichever of the following is most frequent:
- Once for each 250 cubic yards (200 m³) of concrete produced for WisDOT projects.
 - Once per workweek while producing concrete for WisDOT projects.
- (4) For testing performed during aggregate production, conform to the individual gradation limits documented in the contractor's quality control plan for the coarse and fine aggregate fractions. For testing performed during concrete production, conform to the combined gradation limits documented in the contractor's quality control plan.
- (5) Ensure that only results of randomly selected QC tests are included in the 4-point running average.
- (6) Use control limits for sieve sizes as identified in contractor's quality control plan. Gradation warning limits are inside the upper and lower control limit values by one percentage point for all sieves except as follows:
1. The upper warning limits for P 100 (150 µm) and P. 200 (75 µm) are inside the control limit by 0.5 percent.
 2. For sieves allowing 100 percent passing, there is no upper warning limit. For sieves with 0 percent passing, there is no lower warning limit.
- (7) Wash each sample of fine aggregate and the first four samples of each of the coarse aggregates. If P 200 (75 µm) for the combined gradation is less than the warning limit, wash at least every 10th sample of each of the coarse aggregates. If P 200 (75 µm) for the combined gradation is greater than or equal to the warning limit, wash each sample of the coarse aggregate until 4 consecutive tests are less than the warning limit.

B.7.2.2 Documentation

- (1) Maintain control charts at the laboratory for each aggregate stockpile. Maintain a chart for each control sieve for each material. Record contractor test results the same day tests are conducted.

B.7.2.3 Corrective Action

- (1) When the 4-point running average value approaches a warning limit, consider corrective action. Ensure that any corrective action is documented and becomes part of the project records.
- (2) Document whenever a 4-point running average exceeds the warning limits. When a second consecutive running average value exceeds the warning limits, take corrective action. Continue corrective action until two consecutive average points are within the warning limits.
- (3) Notify the engineer whenever an individual test value exceeds a control limit. Material is nonconforming if an individual test result exceeds the control limit. The quantity of nonconforming material includes the material of the first test exceeding the control limit, continuing to but not including, the material from the first subsequent test that is within the control limits. The department may reject material or otherwise determine the final disposition of nonconforming material as specified in standard specifications 106.5.

B.7.3 Aggregate Sampling and Testing During Concrete Production

B.7.3.1 General

- (1) Have an HTCP certified aggregate sampling technician, aggregate technician I or IPP, or PCC technician IA perform all sampling. Ensure that an HTCP certified PCC technician IA or a technician with both PCC technician I and aggregate technician I or IPP certifications performs all testing, does calculations, and documents the results.

B.7.3.2 Aggregate Moisture Content

- (1) Determine aggregate moisture content according to AASHTO T 255. The contractor may use the same sample used for P 200 (75 μm) testing.
- (2) Measure and record the fine and coarse aggregate moisture content whenever conditions change. Test at least once for each 50 cubic yards (38.2 m^3) of concrete produced for WisDOT projects, except 1 test per day is sufficient under constant conditions. Record the time the sample was taken on the combined P 200 (75 μm) control chart.
- (3) Calculate target batch weights for each mix when production of that mix begins. Whenever the moisture content of the fine or coarse aggregate changes by more than 0.5 percent, adjust the batch weights to maintain the design W/Cm ratio.

B.7.3.3 Material Passing the No. 200 Sieve (P 200)

B.7.3.3.1 Sampling and Testing

- (1) Determine P 200 (75 μm) for both fine and coarse aggregates according to AASHTO T 11 as modified by the department.

- (2) Initially, test at least once for each 50 cubic yards (38.2 m³) of concrete produced for WisDOT projects, except 1 test per day is sufficient for constant mix conditions. When 2 consecutive 4-point running averages are below the warning limit, the engineer may allow reduced testing down to a minimum of once per 5 days of concrete production. If a subsequent individual test exceeds the warning limit, return to the initial frequency.
- (3) Document results on a combined gradation control chart for P 200 (75 µm). Use the control limits defined in the contractor's quality control plan or mix design report. Ensure that only results of QC tests are included in the 4-point running average.

B.7.3.3.2 Corrective Action

- (1) When an individual test approaches a warning limit, consider corrective action. Document corrective actions and include that documentation in the project records.
- (2) Notify the engineer if an individual test exceeds the warning limits. If a second consecutive individual test exceeds the warning limits, the engineer and contractor will determine the contractor's course of corrective action. If the corrective action improves the property in question such that additional individual tests are within the warning limits, the contractor may continue production. If the correction does not improve the property, and new individual tests stay in the warning band, repeat the steps outlined here in B.7.3.3(2) starting with notifying the engineer.
- (3) Notify the engineer whenever an individual test value exceeds a control limit. Material is nonconforming when an individual test exceeds the control limit. The quantity of nonconforming material includes the material of the first test exceeding the control limit, continuing to but not including, the material from the first subsequent test that is within the control limits. The department may reject material or otherwise determine the final disposition of nonconforming material as specified in standard specifications 106.5.

B.7.4 Compressive Strength

- (1) The department will pay for concrete strength on a lot-by-lot basis adjusting the contract price based on the compressive strength of contractor QC cylinders. The department will accept or reject concrete on a subplot-by-subplot basis evaluating material for removal and replacement based on core strengths. There is no strength requirement for grade D concrete placed under the Concrete Masonry Seal bid item.
- (2) Have an HTCP certified PCC technician I sample or observe sampling, fabricate cylinders, perform initial curing, and handle unhardened cylinders. Have a department qualified laboratory moist cure cylinders and cores. Have an HTCP certified concrete compressive strength tester, working in a department-qualified laboratory, perform cylinder and core compression tests.

B.7.4.1 Lot and Sublot Requirements

- (1) Designate the location and size of all lots for the project before placing concrete. Ensure that no lot contains concrete of more than one mix, as defined in B.5.3, and does not exceed 500 cubic yards (400 m^3). Designate separate lots for structural concrete deposited underwater.
- (2) Divide each lot into sublots 50 cubic yards (38.2 m^3) or smaller. Do not designate more than one sublot per truckload of concrete.

B.7.4.2 Sampling

- (1) Have a certified technician determine random sublot sampling locations as described in CMM 4-15-12. Sample at the point of placement and according to AASHTO T 141. Collect enough concrete to fabricate three 6-inch by 12-inch (150 mm x 300 mm) cylinders; test air content, slump, and temperature; and where needed, additional concrete to fabricate 3 companion cylinders.
- (2) Cast and initially cure cylinders according AASHTO T 23. Mark each cylinder to identify the lot and sublot it represents.
- (3) For one sublot per lot, fabricate three companion cylinders from the same sample used for casting the QC cylinders. Provide all materials, fabrication, initial curing, and handling required for companion cylinders for up to three calendar days following fabrication.

B.7.4.3 Concrete Cylinder Curing

- (1) Provide initial field curing for up to 48 hours. Between 24 and 48 hours after fabrication, transport the cylinders to a laboratory for standard curing according to AASHTO M 201.

B.7.4.4 Compressive Strength Testing

- (1) Have an HTCP certified compressive strength tester in a department-qualified laboratory, perform compressive strength testing and document the results. Randomly select 2 QC cylinders to test at 28 days for percent within limits (PWL).
- (2) Determine the compressive strength in psi for each cylinder according to AASHTO T 22. Test each cylinder to failure. Use a compression machine that automatically records the date, time, rate of loading, and maximum load for each cylinder. Include a printout of this information with the strength documentation for each cylinder tested.
- (3) Compare the strengths of the 2 randomly selected QC cylinders and determine the 28-day sublot average strength as follows:
 - If the lower strength divided by the higher strength is 0.9 or more, average the 2 QC cylinders.
 - If the lower strength divided by the higher strength is less than 0.9, break one additional cylinder and average the 2 higher strength cylinders.

B.7.4.5 Removal and Replacement

- (1) The department will evaluate the subplot for possible removal and replacement if the 28-day subplot average strength is lower than f'_c minus 500 psi (3.5 MPa). The value of f'_c is the design stress the plans show. The department may assess further strength penalty or require removal and replacement only after coring the subplot.
- (2) The engineer may initially evaluate the subplot strength using a non-destructive method. Based on the results of non-destructive testing, the department may accept the subplot at the previously determined pay for the lot, or direct the contractor to core the subplot.
- (3) If the engineer directs coring, obtain three cores from the subplot in question. Have an HTCP certified PCC technician I perform or observe core sampling according to AASHTO T 24. Determine core locations, subject to the engineer's approval, that do not interfere with structural steel. Fill all core holes with non-shrink grout.
- (4) Have an independent consultant test cores according to AASHTO T 24, except test cores dry after air-curing if the cores are from above-grade concrete elements that will be only superficially wet in service.
- (5) If the 3-core average is greater than or equal to 85 % of f'_c , and no individual core is less than 75 % of f'_c , the engineer will accept the subplot at the previously determined pay for the lot. If the 3-core average is less than 85 % of f'_c , or an individual core is less than 75 % of f'_c , the engineer may require the contractor to remove and replace the subplot or assess a penalty of \$25 per cubic yard or more.

B.7.5 Air Content

- (1) On each day of production, test air content at the point of placement at start-up and as frequently as practicable until the concrete meets the specifications and the production process is under control. Subsequently, test air content for each compressive strength subplot. Have an HTCP certified PCC technician I or IA test air content according to AASHTO T 152, as modified by the department. Test concrete taken from the same sample used for QC strength cylinders, and as the engineer directs.
- (2) The lower and upper control limits for air content are 4.5% and 7.5%. The lower warning limit for air content is 5.0%. There is no upper warning limit.

B.7.5.1 Documentation

- (1) Maintain a control chart at a fixed location on the project site. Ensure that all test results are recorded and become part of the project records. Chart all results on the same day tests are conducted. Record the results of required start-up and corrective action non-random test results on the air content control charts, but do not include them in the 4-point running average.
- (2) Document admixture dosage rates, time of day, and air temperature on the combined gradation control chart for P 200 (75 μ m) whenever changing an admixture dosage rate.

B.7.5.2 Corrective Action

- (1) If an individual air test is between the lower warning limit and lower control limit, perform non-random testing on as many subsequent loads as possible until an individual test result is above the warning limit. At that point the contractor may resume regular random testing.
- (2) When the 4-point running average value trend is towards the lower warning limit or the upper control limit, consider corrective action.
- (3) Notify the engineer if a 4-point running average is less than the lower warning limit. If a second consecutive running average is below the warning limit, the engineer and contractor will determine the contractor's course of corrective action. If the corrective action improves the property in question such that the new running average, after 4 additional individual tests, is between the lower warning limit and upper control limit, the contractor may continue production. If the new running average is below the lower warning limit, repeat the steps outlined here in B.7.5.2(3) starting with notifying the engineer.
- (4) If an individual air test is outside the control limits, notify the engineer, and perform additional air tests as often as practicable on subsequent loads until the air content is inside the control limits. The material is nonconforming when an individual test exceeds the control limit. Material from the load with the first test exceeding the control limit, continuing to but not including the load with the first subsequent test within the control limits, is nonconforming. The department may direct removal and replacement or otherwise determine the final disposition of nonconforming material as specified in standard specifications 106.5.

B.7.6 Concrete Temperature

- (1) Have an HTCP certified PCC technician I or IA measure concrete temperature according to AASHTO T 309. Test concrete taken from the same sample used for QC strength cylinders. Record concrete temperatures on the air content control chart. Conform to the hot weather concreting provisions specified in standard specifications 501.3.8.2.

B.7.7 Slump

- (1) Have an HTCP certified PCC technician I or IA measure slump according to AASHTO T 119. On each day of production, test slump at the point of placement at start-up and as frequently as practicable until the concrete meets the specifications and the production process is under control. Subsequently perform slump testing at the same frequency and from the same sample as used for strength cylinders. Make additional slump tests as the engineer directs. Measure slump to the nearest 1/4 inch (5 mm). Ensure that slump at the point of placement is 3 inches (100 mm) \pm 1 inch (25 mm), except, for concrete placed underwater, conform to standard specifications 502.3.5.3.

B.8 Department Testing

B.8.1 General

- (1) The department will conduct verification testing to validate the quality of the product and independent assurance testing to evaluate the sampling and testing. The department will provide the contractor with a listing of names and telephone numbers of all verification and independent assurance personnel for the project.
- (2) Except for strength, the department will provide test results to the contractor within two business days after the department obtains the sample.

B.8.2 Verification Testing

- (1) The department will have an HTCP technician, or ACT under the direction of a certified technician, perform QV sampling and testing. Department verification testing personnel must meet the same certification level requirements specified for contractor testing personnel for each test result being verified. The department will notify the contractor before sampling so the contractor can observe QV sampling.
- (2) The department will sample randomly at locations independent of the contractor's QC work. In all cases, the department will conduct the verification tests in a separate laboratory and with separate equipment from the contractor's QC tests.
- (3) The department will perform verification testing as follows:

	Testing Frequency Guide ^[1]	Sampling Material and Location	Test Method	Alternate Test Methods
Air Content	1 per lot	Plastic concrete	AASHTO T 152 as modified	Hardened air content testing ^[2] after construction
28-day Compressive Strength	1 per lot	Cylinders	AASHTO T 22, T 23 & T 141 as modified	Random cores ^[2] after construction

^[1] The engineer may increase the frequency at start-up or as necessary to validate the quality of the materials. The engineer may reduce the frequency based on a history of satisfactory contractor or material performance.

^[2] Evaluation of test results should account for systematic differences in testing methods or sampling locations.

- (4) Plot verification test results on the contractor's quality control charts as specified in B.6.1. Do not include verification test results in the 4-point running average.
- (5) If verification tests conform to specifications, no further action is required. If verification tests do not conform to specifications, the engineer and contractor will jointly investigate any testing discrepancies. The investigation may include additional

testing as well as review and observation of both the department's and contractor's sampling and testing procedures and equipment. Both parties will document all investigative work.

- (6) Correct all deficiencies. If the contractor does not respond to an engineer request to correct a deficiency or resolve a testing discrepancy, the engineer may suspend production until action is taken. Resolve disputes as specified in B.9.

B.8.3 Independent Assurance Testing

- (1) Independence assurance is unbiased testing the department performs to evaluate the department's verification and the contractor's QC sampling and testing including personnel qualifications, procedures, and equipment. The department will perform the independent assurance review according to the department's independent assurance program, which may include one or more of the following:
 1. Split sample testing.
 2. Proficiency sample testing.
 3. Witnessing sampling and testing.
 4. Test equipment calibration checks.
 5. Reviewing required worksheets and control charts.
 6. Requesting that testing personnel perform additional sampling and testing.
- (2) Plot the independent assurance test results on the quality control charts as specified in B.6.1. Do not include independent assurance test results in the 4-point running average.
- (3) If the department identifies a deficiency, and after further investigation confirms it, correct that deficiency. If the contractor does not correct or fails to cooperate in resolving identified deficiencies, the engineer may suspend production until action is taken. Resolve disputes as specified in B.9.

B.9 Dispute Resolution

- (1) The engineer and contractor should make every effort to avoid conflict. If a dispute between some aspect of the contractor's and the engineer's testing program does occur, seek a solution mutually agreeable to the project personnel. The department and contractor may review the data, examine data reduction and analysis methods, evaluate sampling and testing procedures, and perform additional testing. Use ASTM E 178 to evaluate potential statistically outlying data.
- (2) If the project personnel cannot resolve a dispute and the dispute affects payment or could result in incorporating nonconforming product, the department will use third party testing to resolve the dispute. The department's central office laboratory or a mutually agreed on independent testing laboratory, will provide this testing. The engineer and contractor will abide by the results of the third party tests. The party in error will pay service charges incurred for testing by an independent laboratory. The department may use third party test results to evaluate the quality of questionable materials and determine the appropriate payment. The department may reject material

or otherwise determine the final disposition of nonconforming material as specified in standard specifications 106.5.

B.10 Acceptance

- (1) The department will accept concrete masonry based on the contractor QC tests unless it is shown through the verification or the dispute resolution process that the contractor's test results are in error.

C (Vacant)

D Measurement

- (1) The department will measure Incentive Strength Concrete Structures by the dollar, adjusted as determined in E.3 for acceptably completed concrete masonry.

E Payment

E.1 General

- (1) The department will pay for measured quantities at the contract unit price under the following bid items:

ITEM NUMBER	DESCRIPTION	UNIT
502.0400.S	Incentive Strength Concrete Structures	DOL

E.2 QMP Testing

- (1) Costs for all sampling, testing, and documentation required under this special provision and all charges incurred for coring, including traffic control, are incidental to the work. If the contractor fails to perform the work required under this special provision, the department may reduce the contractor's pay. The department will administer pay reduction under the Non-performance of QMP administrative item.

E.3 Pay Adjustment for Strength

- (1) The department will pay incentive for compressive strength under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
502.0400.S	Incentive Strength Concrete Structures	DOL

- (2) Incentive payment is not limited, either up or down, to the amount the schedule of items shows.
- (3) The department will administer disincentives for compressive strength under the Disincentive Strength Concrete Structures administrative item.
- (4) The department will adjust pay for each lot using percent within limits (PWL) of the 28-day subplot average strengths for that lot. The department will measure PWL relative to the lower specification limit of 4000 psi. The department will not pay incentive for any quantity of concrete incorporated into the work with properties outside the control limits specified in subsection B of this special provision.

- (5) Submit strength results to the department electronically using the MRS software. The department will validate all contractor data before determining pay adjustments.
- (6) The department will adjust pay for each lot using equation "QMP 2.01" as follows:

PERCENT WITHIN LIMITS (PWL)	PAY ADJUSTMENT ^{[1][2]} (dollars per cubic yard)
≥99 to 100	10
≥90 to <99	0
≥50 to <90	$(7/8 \times \text{PWL}) - 78 \frac{3}{4}$
<50	-35

^[1] The department will not pay incentive if the lot standard deviation is greater than 350 psi.

^[2] For lots with less than four sublots, there is no incentive but the department will assess a disincentive based on the individual subplot average strengths. The department will reduce pay for sublots with an average strength below 4000 psi by \$35 per cubic yard.

(100906) 502-045

24. Culvert Pipe.

Revise section 520 of the standard specifications as follows.

Supplement 520.2 with the following:

Under the items of Culvert Pipe, Class III, for those culvert pipes that are designated on the plans to be installed under minor side roads or private entrances, the contractor may elect to furnish corrugated aluminum pipe (CACP) in the thickness designated and conforming to the requirements of section 525 of the standard specifications; corrugated polyethylene pipe, (CPCP) 12 to 36-inches (300 to 900 mm) diameter, conforming to the requirements of section 530 of the standard specifications; polymer coated steel spiral rib (SSR) pipe; corrugated polyvinyl chloride (CPVC) pipe, 12 to 36- inches (300 to 900 mm) diameter in lieu of reinforced concrete pipe (RCCP) or corrugated steel pipe (CSCP).

Corrugated PVC pipe and fittings shall conform to the requirements of standard specification for Poly (Vinyl Chloride) (PVC) Corrugated Sewer Pipe With a Smooth Interior and Fittings, ASTM Designation: F949. Joint connections shall include gaskets as recommended by the manufacturer.

Steel spiral rib pipe and fittings shall conform to the requirements of the standard specifications for Corrugated Steel Pipe, Polymer Precoated, for Sewers and Drains, AASHTO Designation M245, Type IR. The grade of polymer coating shall be 10/10 (250/250). The thickness of the steel sheet shall be as specified in the plans. Couplings shall be furnished and assembled with gaskets in accordance to AASHTO M246.

Supplement 520.3 with the following:

For corrugated PVC pipe and polymer coated steel spiral rib pipe:

Trench width shall be in accordance to Standard Practice for Underground Installation of Flexible Thermoplastic Sewer Pipe, ASTM Designation D 2321. Minimum trench width shall be not less than the greater of either the pipe outside diameter plus 16-inches (400 mm) or the pipe outside diameter times 1.25 plus 12-inches (300 mm).

Joints for sewer pipe shall be sealed to be soil tight in accordance to AASHTO Standard Specifications for Highway Bridges, section 26.4.2.4 (e).

Pipe with reduced diameter of more than 5 percent shall be removed and relayed, if undamaged, or replaced with a new pipe at no cost to the department.

If PVC or CPCP pipe is used, provide the appropriate size steel endwall at no additional cost beyond the cost of the endwall specified in the contract.
(090105) 520-010

25. Concrete Barrier Temporary Precast Contractor Furnished & Delivered.

This work shall be in accordance with section 603 of the standard specifications and as hereinafter provided.

Any approved concrete barrier system listed in the department's Approved Product List may be furnished as an acceptable alternate to the concrete barrier temporary system shown in standard detail drawing Concrete Barrier Temporary Precast, 12'-6".

When an alternate barrier system is used on bridge decks or locations where the drop-off exceeds two-feet, the system must be anchored as shown in the standard detailed drawing or in accordance with the manufacturer's recommendation. Additionally, the alternate barrier system may not be intermixed with the concrete barrier temporary system shown in standard detail drawing Concrete Barrier Temporary Precast, 12'-6", or the Concrete Barrier Temporary Precast 10'-0", in any single run or installation.
(041504) 603-010

26. Steel Thrie Beam Bullnose Terminal, Item 614.0220.S; Steel Thrie Beam, Item 614.0230.S.

A Description

This special provision describes constructing Steel Thrie Beam Bullnose Terminal attached to wood posts, and Steel Thrie Beam attached to wood posts, in accordance to section 614 of the standard specifications, and as hereinafter provided.

B Materials

B.1 General

Furnish and use corrugated sheet steel beams conforming to the current requirements of AASHTO M 180 Class A. Use sections manufactured from sheets with a nominal width of 29.5 inches.

Steel thrie beam shall be Type II (galvanized).

B.2 Fittings

All supports, fasteners, and other accessories, including post bolts, splice bolts, nuts, buttons, cable anchor plate, nose reinforcing cable, cable anchor bracket, steel plates, shims, tie rods, nails, and washers, shall be galvanized as specified in AASHTO M232.

C Construction

Under the Steel Thrie Beam Bullnose Terminal bid item, provide thrie beams, fabricated from steel plate to specified shape and dimensions, attached to treated wood posts and offset blocks as the plan show, unless specified otherwise.

Under the Steel Thrie Beam bid item provide steel thrie beam, fabricated from steel plate to specified shape and dimensions, attached to treated wood posts and offset blocks as the plan show, unless specified otherwise.

D Measurement

The department will measure Steel Thrie Beam Bullnose Terminal as each individual terminal, acceptably completed.

The department will measure Steel Thrie Beam by the linear foot, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid items:

ITEM NUMBER	DESCRIPTION	UNIT
614.0220.S	Steel Thrie Beam Bullnose Terminal	Each
614.0230.S	Steel Thrie Beam	LF

Payment is full compensation for furnishing all materials including bearing blocks, posts, post bolts, splice bolts, nuts, buttons, cable anchor plate, nose reinforcing cable, cable anchor bracket, thrie beam guard, shims, tie rods, washers, and all supports; setting and driving posts; performing all excavation and backfilling; properly disposing of surplus material; and for furnishing all labor, tools, equipment, and incidentals necessary to complete the contract work.

(100906) 614-025

27. Steel Plate Beam Guard Class A.

Radii tighter than 75 feet shall be shop bent by the manufacturer prior to delivering the beam guard to the project site.

(082003) 614-020

28. Marker Posts Culvert End Flexible, Item 614.0620.S.

A Description

This special provision describes furnishing and installing flexible marker posts at culvert ends as shown on the plans, and as hereinafter provided.

B Materials

Provide post that has been manufactured specifically for use as a roadside marker from fiberglass, thermoplastic composition, or co-extruded polyethylene, and has been manufactured to either a curved or tubular shape.

Provide post that will remain intact and securely anchored, and will return to its original vertical orientation within an angle of 15 degrees after a series of 10 impacts (5 cold weather and 5 hot weather in accordance to the National Transportation Product Evaluation Program) by a typical passenger car or pickup truck traveling at 55 mph.

Provide post material that will not become brittle or soft, will not be affected by ultraviolet exposure, and will remain stable in temperatures from -20 degrees Fahrenheit to 110 degrees Fahrenheit.

Provide post that is colored white except the top six to nine-inches, which shall be black. Accomplish black marking by applying non-reflective sign tape to the front and back of the post.

Provide galvanized metal soil anchors, and galvanized miscellaneous hardware.

Provide Marker Post Culvert End Flexible that is: Safe-Hit, Model SH248GP3-WX; Davidson Plastics, Model FG-500; Carsonite International, Model CDS306601 (Survivor Post) or Model CFR406601 (Curve Flex); or equal. Provide a certificate of specification compliance for models and manufacturers not listed.

C Construction

Install flexible marker posts as shown on the plans. Position curved side of the curved post to face in the direction of travel on the highway.

Use only one marker where two or more apron endwalls are adjacent to each other.

Install soil anchor and marker post in front of the object being marked as referenced from the direction of travel by the approaching highway traffic.

D Measurement

The department will measure Marker Posts Culvert End Flexible by the unit in place, and the quantity to be paid shall be the number of posts furnished, installed and accepted.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
614.0620.S	Marker Posts Culvert End Flexible	Each

Payment is full compensation for furnishing and installing the posts; and for furnishing all labor, tools, equipment and incidentals necessary to complete the contract work.
(100906) 614-010

29. Stone or Rock Ditch Checks, Item 628.7560.S.**A Description**

This special provision describes furnishing and installing stone or rock ditch checks as shown on the plans or as directed by the engineer, or both, and as hereinafter provided.

B Materials

Provide materials conforming to size requirements for size no. 2 coarse aggregate for concrete masonry or riprap in accordance to the 501.2.5.4.4 of the standard specifications. Railroad ballast or breaker run stone conforming to the following applicable gradations may also be used:

Railroad Ballast

	Percent by Weight
Sieve Size	Passing
2 Inch	100
1 Inch	20 – 55
3/8 Inch	0 – 5

Breaker Run Stone

	Percent by Weight
Sieve Size	Passing
5 Inch	100
1-1/2 Inch	0 - 50
3/8 Inch	0 - 5

Incorporate stone or rock in the ditch checks that is hard, sound, and durable, and meets the approval of the engineer.

C Construction

Place stone or rock ditch checks immediately after shaping of the ditches or slopes is completed. Place stone or rock ditch checks at right angles to the direction of flow and construct to the dimensions and in accordance to the details shown in the plans.

Remove sediment from behind the stone or rock ditch checks when it has accumulated to one half of the original height of the dam.

D Measurement

The department will measure Stone or Rock Ditch Checks in volume by the cubic yard of material incorporated in the work.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
628.7560.S	Stone or Rock Ditch Checks	CY

Payment is full compensation for furnishing, producing, crushing, loading, hauling, placing, shaping and maintaining Stone or Rock Ditch Checks; and for furnishing all labor, tools, equipment, and incidentals necessary to complete the contract work.

The quantity of sediment removed shall be multiplied by a factor of 10 and paid for as Common Excavation.
(082003) 628-050

30. Proving Period, Signs and Sign Posts.

Supplement subsection 637.3.2 of the standard specifications with the following:

An 180-day proving period shall apply to all permanent signing placed during each calendar month. The proving period shall commence on the last day of each month. During this period the engineer will make such observations as are necessary to determine failure of the sign and/or the installation. Should the end of the proving period fall within the months of December, January, or February, the engineer may extend the proving period for the installation a minimum number of days necessary for changes in weather and/or road condition to permit adequate observation of the signing in place.

If any sign or sign installation fails for any reason, except for failures caused by impacts of errant vehicles or roadway maintenance equipment, that sign or sign installation shall be repaired at the contractor's expense prior to final acceptance. For this purpose each sign in an assembly shall constitute a separate sign. The sign supports attached to the sign and placed in the ground shall constitute an installation.

Failure of the sign and/or the sign installation will be evaluated on an individual basis. The sign face including the legend shall show no effect due to weathering. The sign face

material shall show no evidence of buckling, bubbling or delaminating. The installation shall be true and plumb.

Each sign or assembly will be evaluated for failure as a unit. Any such installations determined by the engineer to have failed shall be replaced at the contractor's expense prior to final acceptance.

(051206) 638-005

31. Signs Reflective Type II.

Modify 637.2.4 of the standard specifications with the following:

Use stainless steel bolts, washers and nuts for signs mounted on sign bridges. Use clips on every joint for Sign Plate A 4-6 when mounted on a sign bridge. Inspect installation of clips and assure bolts and nuts are tightened to manufacturers recommended torque values.

Use aluminum vertical sign support beams that have a 4-inch wide flange and weigh 3.06 pounds per foot, or have a 5-inch wide flange and weigh 3.7 pounds per foot, or approved equal. Use beams a minimum of six feet in length or equal to the height of the sign to be supported, which ever is greater. Use U-bolts that are made of stainless steel, one-half inch diameter and of the proper size to fit the truss cords of each sign bridge. Install vertical sign support beams on each sign and use new U-bolts to attach each beam to the top and bottom cord of the sign bridge truss.

Replace 637.2.4.1(2)2 of the standard specifications with the following:

Clips may be either stainless steel or ASTM B 108, aluminum alloy, 356.0-T6.

Supplement 637.3.2.1(3) of the standard specifications with the following:

Provide the engineer with 3 copies of drawings of the signs proposed to be furnished under this contract for approval.

Supplement 637.3.3.3(3) of the standard specifications with the following:

Furnish and install new aluminum vertical sign support beams on each sign and new U-bolts to attach each beam to the top and bottom cord of the sign bridge truss for Type I or Type II Signs.

32. Field Facilities.

Replace subsection 642.2.2.1 (1) of the standard specifications with the following:

Provide the field office with up to three communication services, designated as follows: 1-voice, 1-fax, and 1-high speed Internet connection for computer(s) at setting no less than

384k and up to 1 MB. The high speed Internet connection must utilize either DHCP or PPPoE as the connection method and may be combined with the fax service.

Provide two programmable touch-tone telephones of which one will be a cordless type operating at no less than 2.4 GHz and one will have an answering machine unless voice mail service is available. The telephones and the communication services are for the sole purpose of the department staff.

(100906) 642-005

33. Traffic Control.

Supplement section 643 of the standard specifications with the following:

Obtain prior approval from the engineer for the location of egress or ingress of construction vehicles to prosecute the work.

The traffic requirements are subject to change at the direction of the engineer in the event of an emergency.

Submit to engineer for approval a detailed traffic control plan for any changes to the proposed traffic control standard detail drawings as shown in the plans. Submit this plan ten days prior to the pre-construction conference.

Provide 24 hours-a-day availability of equipment and forces to expeditiously restore lights, signs or other traffic control devices that are damaged or disturbed. The cost to maintain and restore the above items is incidental to the item as bid and no additional payment will be made.

Supply the name and telephone number of a local contact person for traffic control repair before starting work.

Have available at all times sufficient experienced personnel to promptly install, remove and reinstall the required traffic control devices to route traffic during the construction operations.

Conduct operations in such a manner that causes the least interference and inconvenience to the free flow of vehicles on the roadways. This includes the following:

- a. Do not park or store any vehicle, piece of equipment, or construction materials on the right-of-way without written approval of the engineer.
- b. All construction vehicles and equipment entering or leaving live traffic lanes shall yield to through traffic.
- c. All vehicles and equipment entering or leaving the live traffic lanes shall be equipped with a hazard identification beam (flashing yellow signal) capable of

being visible on a sunny day when viewed without the sun directly on or behind the device from a distance of 1000 feet. Active beam when merging into or exiting a live traffic lane.

- d. Do not disturb, remove or obliterate any traffic control signs, advisory signs, shoulder delineators or beam guard in place along the traveled roadways without the approval of the engineer. Repair or replace, at the contractor's expense, any damage done to the above during the construction operations.

34. Traffic Control Covering Signs, Item 643.0905.S.

A General

This special provision describes covering sign messages, maintaining the sign covering, and removing the sign covering, as shown on the plan and as hereinafter provided. The covered sign message shall be unreadable during daytime and nighttime hours.

B Materials

Provide covering material of sufficient durability to withstand the effects of weather. Provide porous cloth or sheet aluminum covering. If porous cloth covers are provided, only provide those that do not allow light to reflect from the sign face at night.

Tape, paper, plastic, or sheet metal covers will not be allowed.

C Construction

If porous cloth covering is provided, fold porous cloth covers over the sign edges and secure to the back of the sign. When only a portion of the sign is to be covered, cover only the area of the sign designated to be covered with the cloth cover held tightly in place using a rope system or other system as approved by the engineer. Secure the cloth so that it will not flap against the sign face.

If sheet aluminum covers are provided, rivet the covering to the sign face. Provide rivets that are a maximum of 3/16-inch in diameter. When only a portion of the sign is to be covered, provide aluminum cover sheeting that has on its face the same color as the surrounding sign.

D Measurement

The department will measure Traffic Control Covering Signs in units for each sign covered. Multiple covers on the same sign will be paid for separately. Multiple coverings and removals of sign coverings on the same sign will be paid for separately.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
643.0905.S	Traffic Control Covering Signs	Each

Payment is full compensation for furnishing, installing, maintaining, and removing sign covers; and for furnishing all labor, tools, equipment, and incidentals necessary to complete the contract work.

(050205) 643-040

35. Traffic Control Signs Portable Changeable Message, Item 643.1050.S.

A Description

- (1) This special provision describes furnishing, maintaining and installing portable changeable message signs as hereinafter provided.

B Materials

- (1) Furnish equipment that enables one person to transport and operate the sign easily without assistance.
- (2) Provide a complete Changeable Message Sign and trailer that is painted highway safety orange, except the sign case, which shall be painted black.

B.1 Sign Case

- (1) Provide a sign that is capable of displaying a minimum of three lines of message text per message (frame). Each line shall consist of a minimum of eight characters, equally spaced a minimum of three inches and a maximum of four and one-half inches apart. Characters shall be a minimum of 17 inches high and a minimum of 11 inches wide and be legible from a minimum of 850 feet during both day and night conditions. The maximum sign width shall be eleven feet six inches. Provide a sign display that consists of either a continuous matrix of pixels or individual character modules consisting of smaller matrices of pixels. Each matrix forming a character shall consist of a minimum 35 pixels in a 5 horizontal pixel by 7 vertical pixel arrangement. Each pixel shall consist of a high-intensity LED cluster. The LED lamps shall run at a minimum voltage to provide extended life. Each pixel shall be either square in shape with a minimum of two-inch sides or round in shape with a minimum two-inch diameter. The driver board shall provide means for dimming. The entire sign shall complete a message change within 100 milliseconds.
- (2) The circuit boards used in the sign case shall be constructed of components readily available from at least two other sources. Provide a schematic of the circuit boards.
- (3) Provide a sign housing that is weatherproof and is constructed of aluminum. The front face shall be covered with either a one-piece, clear, non-glare, lexan panel, or individual one-piece, clear, non-glare, lexan panels.

B.2 Raise and Lower Mechanism

- (1) Provide a sign that has a vertical mast assembly constructed of structural steel tubing. The sign shall include a built-in electric powered hydraulic pump capable of fully raising the sign within one minute. Provide signs that are equipped with a manual lifting device, which can be readily accessed. Provide signs that are designed to rise to

variable heights between its cradle and its full height; however, the bottom of the sign shall always be able to rise to a minimum height of seven feet above the ground, and capable of being locked at various heights. Provide a means to prevent tampering with the sign while raised to any locked height. The sign shall be capable of rotating 360 degrees atop the raise and lower mechanism (mast) while raised to any locked height. The mast assembly shall have a mechanism for locking the sign in place when it is extended. When extended, the sign shall be able to be locked at any display angle. Provide means to prevent tampering with the display angle once it is locked.

B.3 Controller

- (1) Provide a programmable microprocessor (controller) that shall direct and control all sign operations. Provide a controller that is furnished with a full size 101 key keyboard, which contains standard alphanumeric keys. The keyboard shall be capable of being used for operation of the controller in creating, storing, and displaying additional sign messages. The controller shall be capable of storing a minimum of 200 messages (frames). The sign shall be capable of displaying from one to six messages in sequence. The manufacturer of the sign shall preprogram and install a minimum of 150 messages. In addition, provide a controller that:
 1. Has the capacity for storage, recall and display of a minimum of 50 operator created messages.
 2. Is able to recall from memory, preview, and display message sequences at least six frames long.
 3. Is capable of storing a minimum of 25 message sequences, which can be created by the operator using any combination of preprogrammed messages and user created messages.
 4. Allows the operator to vary the message flash rate and sequence rate in 1/4-second intervals or less with the flash rate extending from zero seconds to at least four seconds.
 5. Allows the operator to generate a moving or flashing arrow symbol, which is capable of being displayed on any line of a message while text is displayed on other lines of the message.
 6. Allows the operator to generate a larger moving or flashing arrow symbol, which is capable of being displayed on the entire sign face, using all three lines. Either of these message frames containing arrow symbols shall be capable of being included in a sequence.
 7. Allows the operator to flash (blink) selected lines of messages and include these messages within a message sequence.

8. Is equipped with a display screen for previewing the actual sign message prior to display on the sign.
 9. Is removable for ease of replacement, service, or programming.
- (2) Program each controller with a password system that will deter unauthorized programming of the controller. The password system shall include at least two levels of security such that operators at one level may only change message sequences displayed using preprogrammed sequences and operators at a higher level may create and store messages or message sequences. Operators at the higher level shall also be capable of displaying message sequences.
 - (3) When the sign is not in operation, a back up battery shall supply power to the controller.
 - (4) Provide ambient light controlled continuous dimming, with a minimum range of 100% to 40% for the sign display. Provide a means for manually controlled dimming.
 - (5) Provide a control panel that has switches for raising and lowering the sign. Provide a night light for the control panel and controller screen and install it in the controller console cabinet.
 - (6) Provide a Changeable Message Sign that is fully equipped to receive commands to change standard messages and to allow monitoring of sign operations through a cellular telephone connection at the sign unit, without rewiring the cabinet connections. Provide a modem, which operates at a minimum speed of 2400 BAUD. The controller shall be capable of receiving commands via cellular telephone from a personal computer based remote station; furnished with a standard RS-232 interface such that a laptop PC may be connected with the controller to exchange data; and shall also be equipped to connect to a standard telephone land line for remote control operation.
 - (7) The command protocol with which the controller communicates externally shall be of a standard format and be capable of being reconfigured. The command protocol with which the controller communicates via an RS-232 interface shall be a standard format and be capable of being reconfigured.
 - (8) The manufacturer shall provide and install a cellular phone unit.
 - (9) The circuit boards used in the controller shall be constructed of components readily available from at least three other sources. Provide a schematic of the circuit boards.
 - (10) Provide surge protection for all electronic components.

B.4 Power Source

- (1) Provide a solar Changeable Message Sign that runs on a battery system using a solar charging system. The solar-powered battery charging system shall consist of an array of

high-efficiency, single-crystal silicon cells mounted on top of the sign panel and a voltage regulator to prevent overcharging of the battery system. The system shall use deep-cycle batteries and shall include a voltage meter and ammeter.

- (2) Provide solar cells that are capable of charging and maintaining the batteries at operational levels under all weather conditions experienced in Wisconsin. The solar array panel shall be capable of rotating 360 degrees atop the sign case and shall be capable of being locked in any position. The solar array panel shall either be tilted at an angle of 45 degrees relative to the horizon or shall be capable of tilting from 0 degrees to a minimum of 45 degrees and shall be capable of being locked in any position. A switch shall be provided to disconnect the solar power supply for safety during maintenance.
- (3) The batteries shall be housed in a waterproof, heavy-duty housing which is equipped with necessary hardware to be locked using a padlock or built in lock. The batteries shall be of a standard size and type and be available from at least three different manufacturers. The housing that contains the batteries shall be capable of accommodating batteries from at least three different manufacturers. The batteries shall provide adequate back up power for the Changeable Message Sign to operate at full operation for 20 days having ambient air temperatures of 20 degrees Fahrenheit without any sun exposure to the solar array. Certification of the sign's ability to operate for a period of 20 days without exposure to sunlight, as stated above, shall be provided by an independent laboratory. Supply a switch to disconnect the battery supply for safety during maintenance.
- (4) Provide a sign that is equipped to receive and use external 110-volt alternating current as an alternate source of power.
- (5) Provide a sign that is equipped with a charging device that operates on 110-volt alternating current and is capable of charging the deep-cycle battery system within 24 hours. The charging device shall automatically shut off when battery system is fully charged to prevent overcharging.
- (6) Equip the entire unit with an isolated ground circuit. Connect the ground wires to an isolated terminal block. The frame of the trailer shall not be a part of the ground system, except possibly for the alternating current charging and operating systems.
- (7) Provide external wiring that is of single length; has no splices; and is protected from weather and obstructions that may be encountered during transport.
- (8) Protect all break lines from obstructions encountered during transport.

B.5 Trailer

- (1) Provide a highway trailer that has a maximum width of eight feet six inches; is constructed of heavy-gauge, rectangular structural steel tubing; and is equipped with either screw-type or hydraulic leveling jacks, trailer tongue jack with wheel, fenders,

surge brakes, trailer hitch coupling with safety chains, and a rear bumper. In addition, the trailer shall meet the following requirements:

1. Have a straight axle and 2 15-inch wheels and tires with a combined rated load capacity greater than the weight of the entire sign unit and trailer.
 2. Equipped with standard highway brake lights, turn signals, and hazard lights and shall be wired into a round, six-prong connector. All wires shall be single length with no splices.
 3. Enclose the battery system and the controller console in separate rustproof metal cabinets. The cabinets shall be equipped with the necessary hardware to be locked using a padlock or built in lock. Exterior metal surfaces shall be painted federal orange. The doors and lids to the cabinets shall be equipped to be locked in the open position to prevent accidental closure.
 4. Have a 6000-pound capacity surge brake actuator.
 5. The trailer fenders shall be a heavy-duty, walk-on type.
 6. The trailer shall be provided with a walk-on deck, a minimum of 18 inches in width, along both sides of the sign case. Install the decks so that they are in front of and adjacent to both sides of the sign case when the sign case is locked in the transport mode. The walk-on decks shall be the same length as the trailer. Provide non-slip treads on these decks and on all trailer locations where service or maintenance standing or climbing will be required.
- (2) Provide a trailer hitch coupling that is Class III with a minimum capacity of 5,000 pounds and provides for hookup to a two-inch ball type hitch. The coupling shall be capable of being tightened to the ball type hitch by hand turning a wheel. Provide heavy-duty safety chains with safety type hooks and attached them to the trailer for use with the coupling and hitch assembly.
 - (3) Equip the trailer with a means of preventing theft of the trailer.
 - (4) Provide the trailer with at least four leveling jacks (described above), which will level the trailer on a 6:1 slope and support 5000 pounds each. The leveling jacks shall be connected to extendable outriggers. The outriggers shall be capable of extending a minimum of 24 inches beyond the frame of the trailer. The outriggers shall be capable of being locked in at least the following three positions:
 1. Flush with the frame of the trailer.
 2. Extended 12 inches beyond the trailer frame.
 3. Extended 24 inches beyond the trailer frame.

- (5) The leveling jacks shall be capable of being stowed when not in use such that they do not protrude beneath the frame of the trailer. The trailer and sign shall be capable of withstanding wind gusts of up to 80 miles per hour when in operation with sign raised to maximum height and leveling jacks extended. The trailer shall also be equipped with a tongue jack that has a wheel. The tongue jack shall have a capacity greater than the tongue weight of the trailer.
- (6) Provide a trailer that is capable of mounting or descending six inch curbs without the frame striking the curb.
- (7) Provide a trailer that is legal for use on Wisconsin roads in accordance to State of Wisconsin statutes.

C Construction

- (1) Install portable changeable message signs level at the locations to be determined by the engineer.
- (2) On the day the signs are to become operational, have a representative familiar with the operation and repair of the signs available at the project site. The representative shall remain available until all signs are operating satisfactorily.

D Measurement

- (1) The department will measure Traffic Control Signs Portable Changeable Message per each unit complete per day.
- (2) Any day in which the changeable message boards are not working properly for more than 6 hours will result in one day being deducted from the quantity measured for payment, plus an additional \$100 that the contractor will be liable to the department.

E Payment

- (1) The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
643.1050.S	Traffic Control Signs Portable Changeable Message	Day

- (2) Payment is full compensation for furnishing, maintaining and installing the complete unit; and for furnishing all labor, tools, equipment, services and incidentals necessary to complete the contract work.
(100906) 643-050

36. Pavement Marking Wet Reflective Tape 4-Inch, Item 646.0871.S.

A Description

This special provision describes furnishing and installing preformed wet reflective pavement marking tape as shown on the plans, in accordance with section 646 of the standard specifications, and as hereinafter provided.

B Materials

Furnish wet reflective pavement marking tape and adhesive material, if required, from the department's approved products list.

C Construction

C.1 Inlaying Tape into New Asphaltic Pavement

Inlay the material into the fresh asphalt mat at temperatures between 130 and 170 degrees Fahrenheit for a coarse mix and at temperatures between 120 and 150 degrees Fahrenheit for a fine mix. Place the tape as close behind the asphalt paver as soon as temperature permits and in accordance with the plan details. If necessary, supply a dedicated asphalt roller to the striping operation for proper inlay application.

D Measurement

The department will measure Pavement Marking Wet Reflective Tape (Width) in length by the linear foot of tape placed in accordance with the contract and accepted.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid items:

ITEM NUMBER	DESCRIPTION	UNIT
646.0871.S	Pavement Marking Wet Reflective Tape 4-Inch	LF

Payment is full compensation for cleaning and preparing the pavement surface, including heating as required by the manufacturer; furnishing and installing the material; and for furnishing all labor, tools, equipment, and incidentals necessary to complete the contract work.

(020107) 646-017

37. Construction Staking Base, Item 650.5000.

Replace the first sentence of 650.3.4 (1) of the standard specifications with the following:

Set construction stakes or marks at 25-foot intervals.

38. Electrical Service Meter Breaker Pedestal STH 11/36/83 and STH 83, Item 656.0200.01; STH 11 and STH 36/83, Item 656.0200.02.

Append 656.3.4 of the standard specifications with the following:

The department will be responsible for the electrical service installation request for any department-maintained facility. Notify the maintaining authority if the signal is not state-maintained that it is their responsibility to arrange for the electrical service installation.

Electrical utility company service installation and energy cost will be billed to and paid for by the maintaining authority.

Install the cabinet base and meter breaker pedestal first, so the electrical utility company can install the service lateral. Finish grade the service trench, replace topsoil that is lost or contaminated with other materials, fertilize, seed, and mulch all areas that are disturbed by the electrical utility company.

Append 656.5(3) of the standard specifications with the following:

Payment is full compensation for grading the service trench; replacing topsoil; and for fertilizing, seeding, and mulching to restore the disturbed area of the service trench.

39. QMP Subgrade, Item SPV.0035.01.

A General

Perform work in accordance to the pertinent requirements of section 207 of the standard specifications as modified by this contract and as hereinafter provided.

The provision of this article shall apply to subgrade cut and fill construction within the limits of assumed one-to-one slopes extending outward and downward from the outer limits of the finished subgrade shoulder lines, subgrade fill placed adjacent to and within 200 feet of a bridge abutment, and fill placed in pipe culvert trenches. Fill materials placed outside such assumed slopes of the above referenced alignments including private drives, other side roads, frontage roads and berms are not included in the Quality Management Program.

A.1 Quality Control

Provide and maintain a quality control program. The quality control program is defined as all activities relating to process control inspection, sampling and testing, and necessary adjustments in the process that are related to the construction of subgrade which meets all the requirements of this article.

A.2 Quality Assurance

The department will provide quality assurance. Quality assurance will be accomplished in five ways: 1) by conducting assurance testing of split samples of Proctor tests obtained from the soil source study and subgrade fill by the contractor at a frequency equal to or greater than ten percent of the frequency required for quality control; 2) by periodically observing sampling and testing performed by the contractor; 3) by the engineer performing field density testing of the in-place subgrade cut and fill at the exact locations of density tests taken by the quality control person and at a frequency equal to or greater than ten percent of the frequency required for quality control; 4) by monitoring required control charts exhibiting test results of control parameters; 5) by the engineer directing the contractor to take additional samples or measurements of the subgrade compaction.

In all cases, the engineer's tests will be conducted in a separate laboratory from the contractor's tests.

B Contractor's Quality Control

B.1 Personnel Requirements

Provide a Certified Grading Technician Level I to perform the necessary sampling, testing and data analysis. The certified grading technician I shall be on site during all subgrade fill placement and compaction. Certification shall be by successful completion of course work required by the department's Highway Technician Certification Program.

B.2 Laboratory Requirements

Furnish and maintain a laboratory at the site. Furnish the laboratory with the necessary equipment and supplies for performing contractor quality control testing. The laboratory shall have a minimum area of 100 square feet. The Certified Grading Technician shall have access to a telephone and suitable answering device at the laboratory or adjacent facility. The laboratory equipment shall meet the requirements of the test methods herein identified.

Allow engineer to inspect measuring and testing devices to confirm both calibration and condition. Calibrate all testing equipment in accordance to the department's "Quality Management Program, Guide/Procedure Manual" (hereinafter Procedure Manual) and maintain a record of calibration results at the laboratory.

The Procedure Manual may be obtained from the Wisconsin Department of Transportation, Bureau of Technical Services or call 608-246-3246.

B.3 Soil Source Study

Conduct and submit a soil source study prior to the beginning of grading operations. This study shall identify each distinct soil type that will be encountered on the project within the top 15 feet of cut areas and that material which will be used as borrow material. Provide the in-bank natural moisture content for each soil. Develop moisture-density curves for each identified soil type by utilizing AASHTO Designation: T 99, "The Moisture-Density Relations of Soils Using a 5.5 lb. Hammer and a 12-in. Drop, Method A or C". Determine the maximum density and corresponding optimum moisture level for each soil type. A site-specific family of Proctor curves for this contract shall be developed from the completed soil source study and be submitted to the engineer for review and approval.

Perform characterization tests on each of the soil types selected for the soil source study. The tests shall include AASHTO Designation: T 89, "Determining the Liquid Limit of Soils"; AASHTO Designation: T 90, "Determining the Plastic Limit and Plasticity Index of Soils"; AASHTO Designation: T 27, "Sieve Analysis of Fine and Coarse Aggregates"; and AASHTO Designation T 11, "Amount of Material Finer Than 0.075 mm Sieve in Aggregate". Classify each soil type selected in accordance to the AASHTO soil classification system based on the characterization tests. Do not begin grading operations until the engineer has approved the soil source study.

Use the soil types identified in the soil source study with corresponding maximum densities and optimum moisture values to determine the compaction compliance on the

project. Continue the soil source study in those areas of deep cuts (greater than 15 feet) that were not accessible during the initial study. Include data on additional soil types if project conditions change. Test results of additional soil types shall be completed and approved by the engineer prior to placement.

Each Proctor sample shall be split by the contractor and identified so as to provide comparison with the department's test results. Retain the contractor's split samples for 14 calendar days, unless otherwise directed by the engineer. Promptly deliver the department's split samples to the department's Bureau of Technical Services laboratory, 3502 Kinsman Blvd., Madison, Wisconsin 53704, unless otherwise directed by the engineer.

B.4 Quality Control Plan

Submit an acceptable written process control plan to the engineer prior to production in accordance to the Procedure Manual. The plan shall explain how the contractor proposes to control the fill materials moisture and compaction to ensure compliance.

B.5 Field Density/Moisture Control Testing

The contractor's Certified Grading Technician shall be on the project site during all contractor grading operations covered by this specification. Monitor and test all subgrade fill placement and compaction. During subgrade construction, use sampling and testing methods identified in the Procedure Manual to perform the following tests at randomly selected locations at the indicated minimum frequency:

Test	Minimum Frequency*
Field Density Test (AASHTO T-238)	1 test per 3000 cubic yards placed per grading area.
Field Moisture Content (AASHTO T-239)	1 test per 3000 cubic yards placed per grading area.
One Point Proctor Test (AASHTO T-272)	1 test per 9000 cubic yards placed per grading area.

* A grading area is defined as any individual segment of the project in which fill is being placed.

Perform a minimum of one random field density and field moisture test at each pipe culvert location. For pipe culverts larger than 43 inches diameter, perform a minimum of two random field density and field moisture tests, with each test on different lifts of fill.

Perform a minimum of two random field density and two random field moisture tests at each bridge substructure unit, such as abutments and bridge piers. Compact bridge backfill to a minimum of 95% of the maximum dry density as determined by AASHTO Designation: T 99 or T 272.

Field density and field moisture testing is required for compaction of the top six inches of the subgrade in cut areas at a minimum frequency of one test per every twenty stations.

If the special provision for Mixing and Compacting of Subgrade Cuts is included in this contract, the field density and field moisture testing is required in the top 24 inches of the subgrade in cut areas at the same frequency as listed above for subgrade fill.

Perform the field density and field moisture tests using the nuclear density meter method (AASHTO Designation: T 238, "Density of Soil and Soil-Aggregate in Place by Nuclear Methods", and AASHTO Designation: T 239, "Moisture Content of Soil and Soil-Aggregate in Place by Nuclear Methods".) Each field density test material shall be related to one of the specific soil types identified in the soil source study in determining the percent compaction. Textural identification shall be the primary method of establishing this relationship. A coarse particle correction in accordance to AASHTO designation: T 224, "Correction of Coarse Particles in Soil Compaction Test", shall be used with Method A and may be used with Method C.

Obtain and test a representative sample of the fill material at a minimum of each 9000 cubic yards in accordance to AASHTO Designation: T 272, "Family of Curves - One Point Method", Method A or C. Obtain the sample from a randomly selected field density test location. Compare the test results to the curves developed in the soils source study to determine the maximum dry density and optimum moisture applicable to that field density test. Use the appendix for AASHTO Designation: T 272 as a guide in this determination.

Meet requirements of the Radiation Protection Code, the Rules of the Wisconsin Administrative Code HSS 157 and the Nuclear Regulatory Commission (NRC).

Have available copies of names of testing personnel and current NRC license/certifications and Wisconsin Department of Industry, Labor and Human Relations (DILHR) registration.

Have available evidence of a current leak test certificate for all nuclear meters used on WisDOT projects.

Provide evidence that the manufacturer a minimum of once per year has calibrated the nuclear testing equipment.

Abide by the manufacturer's requirement that the nuclear device take a standard count for density and moisture prior to each days operation on the manufacturer's standardized block. In addition, test for calibration both the contractor's and the engineer's nuclear devices on a daily basis with a standard calibration block provided by the department.

Determine the cubic yardage for interim pay and test frequency on a total load count system agreed to by the engineer and contractor. Each test data point shall identify the

horizontal (± 2.0 feet) and vertical (± 0.5 feet) location of the test and the cubic yardage represented.

B.6 Documentation (Records)

Document all observations, records and inspection, adjustments to fill placement procedures, soil changes, and test results on a daily basis. Note the results of the observations and records of inspection as they occur in a permanent field record. Provide copies of the field density and field moisture running average calculation sheets, the one point Proctor tests, records of procedure adjustments, and soil changes to the engineer on a daily basis. Provide the original testing records and control charts to the engineer in a neat and orderly manner within ten days after the completion of the subgrade cut and fill construction.

B.7 Documentation (Control Charts)

Maintain standardized control charts for each grading area by the contractor for field density and moisture. Post the charts at the location agreed upon by the contractor and the engineer. Record test results obtained by the contractor on the control charts within two hours from the time of the field sampling. Record the density data on the standardized control charts for all randomly selected subgrade cut and fill locations tested. The two-hour time period is waived if the project family of curves does not represent the material tested.

Both the individual test point and the moving average of four data points shall be plotted on each chart. Show the contractor's test data in black and the moving average in red. Plot in green additional tests or retests that have been randomly selected. Other means of chart plotting may be used when approved by the engineer. Legends used on the control charts shall be consistent throughout the project.

B.8 Compaction Zones

The quality control criteria listed below will be based on the subgrade fill height. Classify embankment fills of six feet or less in height as upper zone material and compacted to the quality controls designated. Subgrade fills over six feet in height shall have the top six feet compacted to the upper zone quality controls designated, and those portions more than six feet below the finished subgrade shall be compacted to lower zone quality control criteria designated, except such portions occurring adjacent to and within 200 feet of a bridge abutment shall be compacted to the upper zone quality controls. Compact pipe culvert trenches in accordance to the zone the trench are located in.

Compact the mixing and compacting portion of the subgrade in cut sections to the quality control criteria for upper zone embankments.

B.9 Control Limits

The control limit for field density measurements of subgrade fill material placed in the upper zone shall be a minimum of 93% of the maximum dry density as determined by AASHTO Designation: T 99 or T 272 for the four test moving average and a minimum of 90% of the maximum dry density for any individual test.

The control limit for field density measurements of subgrade fill material placed in the lower zone shall be a minimum of 90% of the maximum dry density as determined by AASHTO Designation: T 99 or T 272, for the four test moving average and a minimum of 88% of the maximum dry density for any individual test.

The upper control limit for the field moisture content of subgrade fill material placed in either the upper or lower zone shall be 110% of the optimum moisture as determined by AASHTO Designation: T 99 or T 272 for the four test moving average. The lower control limit for the field moisture content of subgrade fill material placed in either the upper or lower zone shall be 65% of the determined optimum moisture for the four test moving average. The lower control limit for the field moisture of material having less than 5% passing the number 200 sieve shall be 40% of the determined optimum moisture for the four test moving average, with no lower limit for material having less than 3% passing the number 200 sieve.

B.10 Warning Limits

The warning limit for field density measurements of subgrade fill material placed in the upper zone shall be a minimum of 95% of the maximum dry density as determined by AASHTO Designation: T 99 or T 272, for the four test moving average. There shall be no upper limit.

The warning limit for field density measurements of subgrade fill material placed in the lower zones shall be a minimum of 92% of the maximum dry density as determined by AASHTO Designation: T 99 or T 272, for the four rest moving average.

There is no upper or lower warning limit for field moisture.

B.11 Warning Band

The warning band is defined as the area between the control limit and the warning limit.

B.12 Corrective Action

When the moving average values trend is towards the warning limit, consider corrective action. Document the corrective action. All randomly selected tests shall be part of the project files and included in the moving average calculations.

Notify the engineer when a moving average field density point falls within the warning band. If two consecutive moving average points of the field density falls within the warning band, take corrective action(s) on the subsequent fill placed. The contractor and the engineer shall discuss a corrective action(s) to bring the density for the subsequent fill above the warning limits. Corrective action performed by the contractor.

If the corrective action improves the field density such that the new moving average, after four additional individual tests, is above the warning limit, the contractor may continue subgrade cut or fill material placement.

If the new moving average point for the field density is still within the warning bands after the corrective action, the subgrade fill material in this area shall be considered unacceptable. If the embankment material is considered unacceptable, perform additional corrective actions to improve the field density until the new moving average, after four additional re-tests, falls within the warning limits.

If the field density or field moisture moving average point falls below the control limit for field density or exceeds the control limits for field moisture, the subgrade fill material in this area shall be considered unacceptable. Perform corrective actions to bring the subgrade fill material, after four additional re-tests, within warning limits for field density and inside the control limits for field moisture.

If an individual field density test falls below the control limit, the subgrade fill in this area shall be considered unacceptable. Perform corrective action(s) to bring the subgrade fill material, after a retest, within the individual test control limits.

If the contractor's control data is proven incorrect resulting in a field density or field moisture moving average point falling below the control limit for field density or exceeding the control limits for field moisture, the subgrade fill material shall be considered unacceptable. Employ the methods described above for unacceptable material.

C Department's Quality Assurance

C.1 Required Testing and Personnel Requirements

The engineer will conduct assurance tests on split samples taken by the contractor. These samples may be from the Soil Source Study or the one point Proctor(s) or sample locations chosen by the engineer from anywhere in the process. The frequency of testing for the split samples will be equal to or greater than ten percent of the tests taken by the contractor with a minimum of one sample to include each test listed in the Soil Source Study, subsection B(3). The assurance test results will be provided to the contractor within seven working days after the sample has been received by the department's Bureau of Technical Services laboratory, 3502 Kinsman Blvd., Madison, Wisconsin 53704, unless directed elsewhere by the engineer.

The frequency of testing for the field density/moisture tests will be equal to or greater than ten percent of the tests required for the contractor quality control. The results of nuclear tests will be provided to the contractor on the day of testing.

The quality assurance certified technician will test the first split sample obtained by the contractor for the one point Proctor. The engineer may select any or the entire contractor retained samples for assurance testing. All field testing and data analysis shall be performed by a Certified Grading Technician I. Certification shall be in accordance to the department's Highway Technician Certification Program. The department will provide to the contractor a chart giving the names and telephone numbers for the personnel responsible for the assurance program.

The engineer will periodically witness the field testing being performed by the contractor. If the engineer observes that the quality control field tests are not being performed in accordance to the applicable test procedures, the engineer may stop production until corrective action is taken. The engineer will notify the contractor of observed deficiencies, promptly, both verbally and in writing. The engineer will document all witnessed testing.

C.2 Testing Precision

Differences between the contractor's and the engineer's field density/moisture test results (AASHTO Designation: T 238 and 239) will be considered acceptable if the wet density is within five pounds per cubic foot and the moisture is within one pound per cubic foot of each other. The department's assurance field density/moisture Test shall be conducted at the exact location as the contractor's quality control test. Differences between the contractor's and the engineer's Proctor test (AASHTO Designation: T 99) and one-point Proctor test AASHTO Designation: T 272) results will be considered acceptable if the quality assurance test result is within 0.85 to 1.15 of the contractor's optimum moisture content and 4.5 lbs. per cubic foot of maximum dry density.

In the event comparison test results are outside the above allowable differences, the engineer will investigate the reason immediately. The engineer's investigation may include testing of other locations, review of observations of contractors testing procedures and equipment, and a comparison of test results obtained by the contractor, with those obtained by the department.

C.3 Referee Testing

If a difference in test results and/or procedures for sampling and testing exists between the contractor and the engineer that they cannot resolve, the department's laboratory or other mutually agreed upon independent testing laboratory will be asked to provide referee testing. The engineer and the contractor will abide by the results of the referee testing. The party found in error will pay service charges incurred for referee testing by an independent laboratory.

D Acceptance

The engineer will base final acceptance of this item on the results of the contractor's random testing as verified by the engineer in Section C hereinbefore described.

E Measurement

The department will measure Quality Management Program, Subgrade, by the cubic yard for the class of excavation involved (Common Excavation and Borrow Excavation), completed and accepted. The final cubic yardage shall be determined based on actual quantities measured in accordance to subsections 205.5.1 and 208 of the standard specification.

F Payment

The department will pay for the measured quantity at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0035.02	Quality Management Program, Subgrade	CY

Payment is full compensation for all work herein specified and for furnishing all labor, tools, equipment, laboratories, sampling, testing, record keeping and incidentals necessary to complete the work.

40. Concrete Base, Type 9, Monotube, Item SPV.0060.01.

Perform work in accordance to the requirements of section 654 of the standard specifications and as detailed on the plans.

41. Apron Endwalls for Underdrain Reinforced Concrete 12-Inch, Item SPV.0060.02.

A Description

This special provision describes furnishing and installing reinforced concrete apron endwalls according to subsection 612.3.8 of the standard specifications.

B Materials

Provide materials for endwalls according to section 504 of the standard specifications and plan details.

C Construction

Install endwalls according to plan details at locations the plans show.

D Measurement

The department will measure Apron Endwalls for Underdrain Reinforced Concrete 12-Inch by the individual unit acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item and in accordance to subsection 612.5 of the standard specifications:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0060.02	Apron Endwalls for Underdrain Reinforced Concrete 12-Inch	Each

Payment is full compensation for furnishing and installing all materials; and for furnishing all labor, tools, equipment and incidentals necessary to complete the work.

42. Cover Signs, Type I, Item SPV.0060.03.

A Description

This special provision describes covering sign messages, maintaining the sign covering, and removing the sign covering, as shown on the plan and as hereinafter provided. The covered sign message shall be unreadable during daytime and nighttime hours.

B Materials

Provide covering material of sufficient durability to withstand the effects of weather. Provide porous cloth or sheet aluminum covering. If porous cloth covers are provided, only provide those that do not allow light to reflect from the sign face at night.

Tape, paper, plastic, or sheet metal covers will not be allowed.

C Construction

If porous cloth covering is provided, fold porous cloth covers over the sign edges and secure to the back of the sign. When only a portion of the sign is to be covered, cover only the area of the sign designated to be covered with the cloth cover held tightly in place using a rope system or other system as approved by the engineer. Secure the cloth so that it will not flap against the sign face.

If sheet aluminum covers are provided, rivet the covering to the sign face. Provide rivets that are a maximum of 3/16-inch in diameter. When only a portion of the sign is to be covered, provide aluminum cover sheeting that has on its face the same color as the surrounding sign.

D Measurement

The department will measure Cover Signs, Type I in units for each sign covered. Multiple covers on the same sign will be paid for separately. Multiple coverings and removals of sign coverings on the same sign will be paid for separately.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0060.03	Cover Signs, Type I	Each

Payment is full compensation for furnishing, installing, maintaining, and removing sign covers; and for furnishing all labor, tools, equipment, and incidentals necessary to complete the contract work.

43. Erosion Control Filter Bags, Item SPV.0060.04.**A Description**

This special provision describes constructing dikes or barriers with filter bags as shown on the plans.

B Materials

Provide bags made of canvas or other synthetic material approved by the engineer. Use bags that will contain a minimum of one half cubic foot of stone, be of one size and shape and be securely closed.

Use stone that conforms to the requirements of subsection 310.2 of the standard specifications.

C Construction

Remove and dispose of the filter bags and all surplus material upon completion of their use under this contract.

D Measurement

The department will measure Erosion Control Filter Bags as each individual filter bag placed and accepted.

E Payment

The department will pay for the measured quantity at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0060.04	Erosion Control Filter Bags	Each

Payment is full compensation for furnishing and installing filter bags; for all excavation; for removal and disposal of the filter bags and all waste or surplus materials, including eroded materials; and for shaping and restoring the area.

Any required topsoiling, fertilizing, seeding or mulching will be paid for under the applicable item.

44. Sand Bags, Item SPV.0060.05.

A Description

This special provision describes constructing dikes or barriers with sand-filled bags as shown on the plans.

B Materials

Provide bags made of canvas, burlap, nylon or other approved material. Use bags that will contain a minimum of one half cubic foot of sand, be of one size and shape, and be securely closed.

Use sand that conforms to the requirements of subsection 501.2.5.3 of the standard specifications except that subsection 501.2.5.3.4 shall be deleted. The maximum size of particle shall pass a No. 4 sieve.

C Construction

Remove and properly dispose of the sand bags and all surplus material upon completion of its use under this contract.

D Measurement

The department will measure Sand Bags as each individual sand bag placed and accepted.

E Payment

The department will pay for the measured quantity at the contract unit price under the following bid item.

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0060.05	Sand Bags	Each

Payment is full compensation for furnishing and installing sand filled bags; for all excavation; for removal and disposal of the sand bags and all waste or surplus materials, including eroded materials; and for shaping and restoring the area.

Any required topsoiling, fertilizing, seeding or mulching will be paid for under the applicable item.

45. Traffic Signals and Street Lighting, STH 11/36/83 and STH 83, Item SPV.0105.01; STH 11 and STH 36/83, Item SPV.0105.02.

A Description

This special provision describes transporting and installing department-furnished materials for traffic signals and intersection lighting, at the intersection of STH 11/State Street and STH 36/83, and STH 11/36/83 and STH 83 Pine Street.

B Materials

Use materials furnished by the department including the traffic signal controller, the traffic signal cabinet, and traffic signal control equipment and intersection lighting equipment as listed in the plans such as pedestal bases, transformer bases, traffic signal standards, poles, trombone arms or monotubes, traffic signal faces, backplates, pedestrian push buttons, luminaire arms, utility luminaires, and traffic signal mounting hardware.

Pick up the department-furnished materials at the department's Electrical Shop located at 935 South 60th Street, West Allis. Notify the department's Electrical Field Unit at (414) 266-1170 and make arrangements for picking up the department furnished materials three working days prior to picking up the materials.

Provide all other needed materials in conformance to subsections 651.2, 652.2, 653.2, 654.2, 655.2, 656.2, 657.2, 658.2 and 659.2 of the standard specifications.

C Construction

Perform work in accordance to subsections 651.3, 652.3, 653.3, 654.3, 655.3, 656.3, 657.3, 658.3 and 659.3 of the standard specifications except as specified below.

Request a signal inspection of the completed signal installation to the project engineer at least three working days prior to the time of the requested inspection. The departments' regional electrical personnel will perform the inspection.

D Measurement

The department will measure Traffic Signals and Street Lighting (Location) as a single lump sum unit of work in place and accepted.

E Payment

The department will pay for the measured quantity at the contract unit price under the following bid items:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0105.01	Traffic Signals and Street Lighting, STH 11/36/83 and STH 83	LS
SPV.0105.02	Traffic Signals and Street Lighting, STH 11 and STH 36/83	LS

Payment is full compensation for transporting and installing the traffic signal controller, the traffic signal cabinet, the traffic signal control and intersection lighting equipment as listed in the plans; for furnishing and installing all other items necessary such as wire nuts, splice kits and/or connectors, tape, insulating varnish, ground lug fasteners, and sodium lamps for lighting to make the proposed system complete from the source of supply to the most remote unit; and for clean-up and waste disposal.

46. Temporary Diversion Channel, Item SPV.0105.03.

A Description

This special provision describes constructing a temporary diversion channel for Poplar Creek during the proposed extension of Structure B-51-22. Submit to the engineer a detailed plan with written steps indicating where and how the diversion channel will be constructed. Perform the work in accordance to the plan details, the pertinent provisions of the standard specifications, and as hereinafter provided.

B Materials

The stone lining on the bottom of the channel shall consist of hard, durable particles that are washed and uniformly graded. The stone shall pass a 6-inch screen and be retained on a 1-inch sieve.

Furnish polyethylene sheeting as indicated on the plan for lining the channel.

C Construction

Submit the diversion plan as part of the erosion control implementation plan to the engineer for approval by the region no later than 14 days prior to the preconstruction conference. Include in the diversion plan a written narrative explaining the planned diversion method and erosion control devices to be installed, and any drawings required to clarify the proposed method. Do not begin installation of the temporary culvert pipe until the region approves the diversion plans and the engineer gives the notice to proceed.

Excavate the diversion channel to the cross section shown on the plan. The minimum depth of the channel shall be 36-inches. Undercut all unsuitable soil encountered below the flow line of the channel as directed by the engineer. Any undercuts will be paid for as EBS. Line the channel with polyethylene sheeting; stake the sheeting as necessary with

stakes 12 inches or more in length. Place stone in the bottom of the channel as shown in the plan.

If dewatering is required, pump the water into an upland settling basin before allowing it to enter the stream.

No in-stream construction will be allowed between the dates of April 1 and June 1.

Upon completion of Structures C-51-22, remove all diversion devices from the waterway. Remove and dispose of the geotextile fabric above the stone bottom. Backfill the diversion channel with suitable material. Use material and construction methods that conform to the appropriate specifications in sections 205 and 208 of the standard specifications.

D Measurement

The department will measure Temporary Diversion Channel, completed in accordance to the contract and accepted, as a single complete unit of work.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0105.01	Temporary Diversion Channel	LS

Payment is full compensation for placing and excavating the diversion channel; for dewatering required to implement the diversion plan; for furnishing, installing, and staking the polyethylene sheeting; for supplying, removing and disposing of the plastic sheeting; for providing and placing the stone in the channel; for removing the diversion channel and the polyethylene sheeting; for backfilling the temporary channel; and for furnishing all labor, tools, equipment and incidentals necessary to complete the contract work.

The department will pay separately for polyethylene sheeting, Sand Bags, the temporary culvert pipe installation, salvaged topsoil, fertilizer, seed and mulch.

47. Architectural Surface Treatment, Item SPV.0165.01.

A Description

This special provision describes constructing a concrete masonry architectural surface treatment on the exposed concrete surfaces of the structure, as detailed in the plans, and as hereinafter provided.

B Materials

Use reusable form liners that are made of highway strength urethane that attach easily to the forming system, and do not compress more than 1/4-inch when poured at a rate of 10 vertical feet/hour.

Use a release agent that is compatible with the form liner and coloring materials.

Wall ties shall have set "break-backs" at a minimum of ¾-inches from the finished concrete surface.

C Construction

C.1 Equipment

Equipment and tools necessary for performing all parts of the work shall be satisfactory as to design, capacity and mechanical condition for the purposes intended. Repair, improve, replace or supplement all equipment that is not maintained in full working order, or which is proven inadequate to obtain the results prescribed.

C.2 Form Liner Preparation

Clean the form liner prior to each pour and ensure that it is free of any build-up. Visually inspect each liner for blemishes or tears, and repair if necessary per manufacturer's recommendations.

Apply form release per manufacturer's recommendations.

C.3 Form Liner Attachment

Place adjacent liners less than ¼-inch from each other, attach liner securely to forms in accordance to manufacturer's recommendations, and coordinate wall ties with form liner and form manufacturer, e.g., diameter, size, and frequency.

C.4 Surface Finishing

Ensure that the textured surface is free of laitance; sandblasting is not permitted.

Grind or fill pouring blemishes.

D Measurement

The department will measure Architectural Surface Treatment by the square foot acceptably completed.

E Payment

The department will pay for the measured quantity at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0165.01	Architectural Surface Treatment	SF

Payment is full compensation for producing the proposed architectural surface treatment including preparing the foundation; finishing and protecting the surface treatment; properly disposing of surplus material; and for furnishing all labor, tools, equipment, materials, and incidentals necessary to complete the contract work.

48. Concrete Staining, Item SPV.0165.02.

A Description

This special provision describes furnishing and applying a two-coat concrete stain to the exposed concrete surfaces of the structure as detailed in the plans, and as hereinafter provided.

B Materials

B.1 Mortar

Use mortar for sack rubbing the concrete surfaces as given in subsection 502.3.7.5 or use one of the following products or approved equal:

Preblended, Packaged Type II Cement: Tri-Mix by TK Products
Thoroseal Pearl Gray by Thoro Products

The mortar shall contain one of the following Acrylic Bonding Admixtures mixed and applied as given by the manufacturer or approved equal.

Acrylic Bonding Admixture: TK-225 by TK Products
Achro 60 by Thoro Products
Achro Set by Master Builders

B.2 Concrete Stain

Use concrete stain manufactured for use on exterior concrete surfaces, consisting of a base coat and a pigmented sealer finish coat. Use the following products, or equal as approved by the department, as part of the two-coat finish system:

Tri-Sheen Concrete Surfacers, Smooth by TK Products
Tri-Sheen Acrylic by TK Products
*TK-1450 Urethane Anti-Graffiti Primer by TK Products
Safe-Cure and Seal EPX by Chem Masters
H + C Shield Plus by Sherwin-Williams
(*Natural Look)

C Construction

Furnish, prepare, apply, cure, and store all materials according to the product manufacturer's directions specified for the type and condition of application required.

Prior to staining, allow the concrete to cure for the stain manufacturer's minimum recommended curing time or 28 days, whichever is greater.

C.1 Preparation of Concrete Surfaces

Provide a sack-rubbed finish as given in subsection 502.3.7.5, using mortar as indicated above, on concrete surfaces with open voids or honeycombing.

Following the sack rubbing, clean all concrete surfaces that are to be coated to ensure that the surface is free of all laitance, dirt, dust, grease, efflorescence, and any foreign material, so that the concrete surface will accept the coating material according to product requirements. As a minimum, clean using a 3000 psi water blast. Hold the nozzle of the water blaster approximately 6-inches from the concrete surface and move it continuously in a sweeping motion. Give special attention to smooth concrete surfaces to ensure that an acceptable surface texture is produced. Correct any surface problems resulting from the surface preparation methods. The department will not allow grit blasting of the concrete surface.

C.2 Staining Concrete Surfaces

Apply the concrete stain in accordance to the manufacturer's recommendations.

Apply the concrete stain when the temperature of the concrete surface is 45° F or higher, or as given by the manufacturer.

Use the stain color that is given on the plan. Tint the base coat to match the finish coat; ensure that the two coats are compatible with each other.

Do not begin staining the structure until earthwork operations are completed to a point where this work can begin without receiving damage. Where this work is adjacent to exposed soil or pavement areas, provide temporary covering protection from overspray or splatter.

C.3 Test Areas

Prior to applying stain to the structure, perform test applications on sample panels that measure a minimum of 48-inches x 48-inches and are constructed to demonstrate workmanship in the use of the form liner specified on the structure, if applicable. Prior to staining, allow the concrete to cure for the stain manufacturer's minimum recommended curing time or 28 days, whichever is greater. Prepare the concrete surfaces of the sample panels and apply stain using the same materials and same manner as proposed for the structure, including staining of the joints between stones produced by the form liner, if applicable. Do not apply stain to the structure until the department approves the test panels.

C.4 Surfaces to be Coated

Apply concrete stain to the surfaces as given on the plan.

D Measurement

The department will measure Concrete Staining by the square foot acceptably completed.

E Payment

The department will pay for measured quantity at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0165.02	Concrete Staining	SF

Payment is full compensation for furnishing and applying the two-coat system; preparing the concrete surface; preparing sample panels; and for furnishing all labor, tools, equipment and incidentals necessary to complete the contract work.

49. Covering Signs Type II, Item SPV.0165.03.

A Description

This special provision describes covering sign messages, maintaining the sign covering, and removing the sign covering, as shown on the plan and as hereinafter provided. The covered sign message shall be unreadable during daytime and nighttime hours.

B Materials

Provide covering material of sufficient durability to withstand the effects of weather. Provide porous cloth or sheet aluminum covering. If porous cloth covers are provided, only provide those that do not allow light to reflect from the sign face at night.

Tape, paper, plastic, or sheet metal covers will not be allowed.

C Construction

If porous cloth covering is provided, fold porous cloth covers over the sign edges and secure to the back of the sign. When only a portion of the sign is to be covered, cover only the area of the sign designated to be covered with the cloth cover held tightly in place using a rope system or other system as approved by the engineer. Secure the cloth so that it will not flap against the sign face.

If sheet aluminum covers are provided, rivet the covering to the sign face. Provide rivets that are a maximum of 3/16-inch in diameter. When only a portion of the sign is to be covered, provide aluminum cover sheeting that has on its face the same color as the surrounding sign.

D Measurement

The department will measure Covering Signs Type II in area by the square foot of sign face acceptably covered.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0165.03	Covering Signs Type II	SF

Payment is full compensation for furnishing, installing, maintaining, and removing sign covers; and for furnishing all labor, tools, equipment, and incidentals necessary to complete the contract work.

50. Test Rolling, Item SPV.0170.01.

A Description

This special provision describes the testing of the stability of the finished earth subgrade by rolling with a tri-axle dump truck, the restoration of any soft or yielding areas evidenced by the test rolling, and retesting as determined by the engineer.

B Equipment

Fully load a tri-axle dump truck to within 3 tons of the vehicle legal load limit and provide a minimum gross vehicle weight of 30 tons. Uniformly inflate all tires to the pressure recommended by the manufacturer for the applicable wheel load.

C Construction

Completely compact and shape the subgrade to approximate grade and cross section; but not yet staked for blue top grades for areas to be tested. Test roll at normal walking speed under the direction of the engineer or his representative.

Roll the earth subgrade at a width equal to the finished base course width. Make multiple passes throughout the length of the subgrade test area. Center each pass on a proposed lane or applicable shoulder. When the shoulder width is less than 8 feet, the engineer will determine the number and location of passes required such that any wheel track will be within 3 to 4 feet of the previous adjacent wheel track.

Repair and consolidate any soft or yielding areas or depressions evidenced under the action of the test rolling to withstand retesting. Excavate and replace any unstable material from the roadbed with selected materials. Correct any yielding subgrade areas discovered during the test rolling operations prior to blue top staking and finish grading operations. Perform corrective work in accordance to the standard specifications.

D Measurement

The department will measure Test Rolling by the station along the roadway centerline or reference line. The department will measure two or more separate roadways by the station along each separate roadway as designated on the plans.

E Payment

The department will pay for the measured quantity at the contract unit price under the following item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0170.01	Test Rolling	STA

Payment is full compensation for performing the Test Rolling; for any preparation of the subgrade, including the furnishing and incorporation of water, if required; for retesting as determined by the engineer and for restoration of the subgrade.

51. Geotextile Fabric Type FF, Item SPV.0180.01.

A Description

This special provision describes furnishing, installing and removing geotextile fabric and fabric hold down systems for filtering storm water as shown in the plans.

B Materials

Use type FF geotextile fabrics conforming to 645.2.1 except use a woven polypropylene fabric. Furnish type FF geotextile fabrics selected from the department's erosion control product acceptability list (PAL). Obtain copies of the erosion control PAL and prequalification procedure from the Bureau of Technical Services.

C Construction

Meet the pertinent requirements as set forth in section 645.3 of the standard specifications and as follows:

Install in accordance to the plan details for the intended use in such a manner to preclude ripping and tearing of the fabric, or otherwise rendering the fabric or assembly ineffective for its intended use.

D Measurement

The department will measure Geotextile Fabric, Type FF by the square yard of surface area of the fabric placed and accepted in accordance to the contract.

E Payment

The department will pay for the measured quantity at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0180.01	Geotextile Fabric, Type FF	SY

Payment is full compensation for furnishing, transporting, installing and removing the fabric and fabric hold down systems.

52. Washed Stone, Item SPV.0195.01.

A Description

This special provision describes furnishing and placing washed stone as shown on the plans and as hereinafter provided.

B Materials

Washed stone shall be size no. 2 meeting the requirements of subsection 501.3.6.4.5 of the standard specifications.

C (Vacant)

D Measurement

The department will measure Washed Stone by the ton of required material incorporated in the work. Furnish and deliver to the engineer a ticket, with each load, showing the net weight of the load, the type of material, the date and the project where used.

E Payment

The department will pay for the measured quantity at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0195.01	Washed Stone	TON

Payment is full compensation for furnishing, producing, crushing, screening, loading, hauling, placing, and maintaining the washed stone; for stockpiling, if required; and for furnishing all labor, tools, equipment and incidentals necessary to complete the work.

ADDITIONAL SPECIAL PROVISION 2

Apprenticeship Training.

- A. The contractor and its subcontractors agree, in the performance of this Contract, to employ apprentices in accordance with the requirements as described in Part B below, as established by the Department of Workforce Development in accordance with State of Wisconsin Executive Order No. 108, dated June 29, 2005.
- B. The contractor and subcontractors employing five (5) or more craft workers of trades with apprentice programs in the state of Wisconsin shall meet one of the following requirements:
 - 1. Employ or have employed at any time during the current or previous calendar year the maximum number of apprentices allowed by the training ratio for each trade included in the bid; or
 - 2. Employ or have employed at any time during the current or previous calendar year a skilled workforce of at least five (5) percent apprentices for projects performed under contract to DOT; or
 - 3. Employ apprentices on a contract jobsite at the maximum ratio or, where the ratio is not jobsite specific, at five (5) percent of the contract hours for work performed under contract to DOT; or
 - 4. Agree that "new hire apprentices" will be engaged at least at the maximum ratio of journey level workers to apprentices allowed under the standards established by the Department of Workforce Development.
- C. In the event of failure to meet these ratios, the contractor shall be given an opportunity to demonstrate that every good faith effort to meet this commitment has been made.
- D. No contract shall be executed or subcontract approved unless the contractor or subcontractors are currently approved as a Wisconsin Trade Trainer or has applied for approval as an Apprenticeship Trade Trainer to the Department of Workforce Development and agrees to an acceptable apprenticeship program which includes specific ratios of apprentices in skill trades which have been determined as apprentice able by the Department of Workforce Development.
- E. The contractor and subcontractor shall maintain records to demonstrate compliance with these apprenticeship requirements.
- F. Reasonable exemptions and modifications to and from any or all of these requirements will be determined by the Department of Workforce Development. A request for an exemption or modification, with justification, shall be made in writing, addressed to Department of Workforce Development, Bureau of Apprenticeship Standards, PO Box 7972, Madison, WI 53707.

ADDITIONAL SPECIAL PROVISION 4

Payment to all Subcontractors. Within 10 calendar days of receipt by a contractor of a progress payment for work performed, materials furnished, or materials stockpiled by a subcontractor, the contractor shall pay that subcontractor for all work satisfactorily performed and for all materials furnished or stockpiled.

The contractor agrees further to release retainage amounts to each subcontractor within 10 calendar days after the subcontractor's work is satisfactorily completed. In addition, whenever the Department reduces the contract retainage amount, within 10 calendar days of receipt by a contractor of a retainage payment, the contractor must reduce the total amount retained from subcontractors to no more than remains retained by the Department.

The contractor shall pay the subcontractor within the time frames described above unless the contractor complies with both of the following within 10 calendar days of receiving the Department's progress payment:

- 1) The contractor notifies the subcontractor in writing that the work is not satisfactorily completed.
- 2) The contractor requests approval from the Department to delay payment because the subcontractor has not satisfactorily completed the work.

The contractor's request for approval should include the written notification to the subcontractor and shall provide sufficient documentation of good cause to assist the engineer in making a timely decision. If the engineer does not grant approval, the contractor shall pay the subcontractor within 10 calendar days of the Department's decision.

All subcontracting agreements made by a contractor shall include the above provisions and shall be binding on all contractors and subcontractors.

The contractor certifies compliance with the requirements of this Additional Special Provision by signing the contract. This clause applies to both DBE and non-DBE subcontractors.

ADDITIONAL SPECIAL PROVISIONS 5

Fuel Cost Adjustment.

A. Description. Fuel Cost Adjustments will be applied to partial and final payments for work items categorized in Section B as a payment to the Contractor or a credit to the Department. ASP-5 shall not apply to any force account work.

B. Categories of Work Items. The following items and Fuel Usage Factors shall be used to determine Fuel Cost Adjustments:

(1) Earthwork.		Unit	Gal. Fuel Per Unit
205.0100	Excavation Common	C.Y.	0.23
205.0200	Excavation Rock	C.Y.	0.39
205.0400	Excavation Marsh	C.Y.	0.29
208.0100	Borrow	C.Y.	0.23
208.1100	Select Borrow	C.Y.	0.23
209.0100	Backfill Granular	C.Y.	0.23
350.0102	Subbase	C.Y.	0.28
350.0104	Subbase	Ton	0.14
350.0115	Subbase 6-Inch	S.Y.	0.05
350.0120	Subbase 7-Inch	S.Y.	0.05
350.0125	Subbase 8-Inch	S.Y.	0.06
350.0130	Subbase 9-Inch	S.Y.	0.07
350.0135	Subbase 10-Inch	S.Y.	0.08
350.0140	Subbase 11-Inch	S.Y.	0.09
350.0145	Subbase 12-Inch	S.Y.	0.09

C. Fuel Index. A Current Fuel Index (CFI) in dollars per gallon will be established by the Department of Transportation for each month. The CFI will be the price of No. 2 fuel oil, as reported in U.S. Oil Week, using the first issue dated that month. The CFI will be the average of prices quoted for Green Bay, Madison, Milwaukee and Minneapolis.

The base Fuel Index (BFI) for this contract is \$1.8000 per gallon.

D. Computing the Fuel Cost Adjustment. The Engineer will compute the ratio CFI/BFI each month. If the ratio falls between 0.85 and 1.15, inclusive, no fuel adjustment will be made for that month. If the ratio is less than 0.85 a credit to the Department will be computed. If the ratio is greater than 1.15 additional payment to the Contractor will be computed. Credit or additional payment will be computed as follows:

(1) The engineer will estimate the quantity of work done in that month under each of the contract items categorized in Section B.

(2) The engineer will compute the gallons of fuel used in that month for each of the contract items categorized in Section B by applying the unit fuel usage factors shown in Section B.

(3) The engineer will summarize the total gallons (Q) of fuel used in that month for the items categorized in Section B.

(4) The engineer will determine the Fuel Cost Adjustment credit or payment from the following formula:

$$FA = \left(\frac{CFI}{BFI} - 1 \right) \times Q \times BFI$$

(plus is payment to Contractor; minus is credit to Department)

Where	FA	=	Fuel Cost Adjustment (plus or minus)
	CFI	=	Current Fuel Index
	BFI	=	Base Fuel Index
	Q	=	Monthly total gallons of fuel

E. Basis of Payment. A Fuel Cost Adjustment credit to the Department will be deducted as a dollar amount each month from any sums due to the contractor. A Fuel Cost Adjustment payment to the Contractor will be made as a dollar amount each month.

Upon completion of the work under the contract, any difference between the estimated quantities and the final quantities will be determined. An average CFI, calculated by averaging the CFI for all months that fuel cost adjustment was applied, will be applied to the quantity differences. The average CFI shall be applied in accordance with the procedure set forth in Section D.

ADDITIONAL SPECIAL PROVISION 6
MODIFICATIONS TO THE STANDARD SPECIFICATIONS

Make the following revisions to the 2003 edition of the standard specifications as modified by the 2006 supplement:

501.3.7.1 Slump

Replace paragraph two with the following effective with the November 2006 letting:

- (2) For Grade E concrete, do not exceed a slump of 2 inches (50 mm).
-

657.2.1 Poles

Replace paragraph one with the following effective with the July 2006 letting:

- (1) Design support structures, consisting of poles and arms, conforming to AASHTO design and fabrication standards for structural supports for highway signs, luminaires, and traffic signals. Use a design life of 50 years. Design to withstand a 3 second gust wind speed of 90 mph (145 km/h). Do not use the methods of appendix C of those AASHTO standards.
-

678.2 Materials

Replace the entire text with the following effective with the April 2007 letting:

678.2.1 Department Furnished Materials

- (1) The department will furnish fiber optic cable and termination panels.

678.2.2 Fiber Optic Splices

- (1) Furnish fiber optic splice enclosures to be used in fiber optic splices for both mainline end-to-end splices and drop splices, as the plans show.
- (2) Furnish fiber optic splice enclosures designed for use under the most severe conditions such as moisture, vibration, impact, cable stress and flex temperature extremes as demonstrated by successfully passing the factory test procedures.

678.2.2.1 Physical Requirements

- (1) The enclosure must handle up to 4 cables in a butt configuration. The contractor may use a butt adapter to increase capacity to 6 cables.
- (2) The enclosure must prevent the intrusion of water without the use of encapsulates.
- (3) The enclosure must be capable of accommodating splice organizer trays that accept mechanical, fusion, or multi-fiber array splices. The splice enclosure shall have provisions for storing fiber splices in an orderly manner, mountings for splice organizer assemblies, and space for excess or unspliced fiber. Splice organizers shall be re-enterable. Splice cases shall hold a sufficient number of splice trays to hold up to 144 splices.
- (4) The splice case shall be UL rated.
- (5) Enclosure re-entry and subsequent reassemble shall not require specialized tools or equipment. Further, these operations shall not require the use of additional parts.
- (6) The splice enclosure shall have provisions for controlling the fiber bend radius to a minimum of 1 1/2 inches (38 mm).

678.2.2.2 Factory Testing

678.2.2.2.1 General

- (1) Ensure that the manufacturer or an independent testing laboratory performs the tests listed below in 678.2.1.2.2 through 678.2.1.2.6. Submit certificates of compliance to the department. Manufacturer certification is necessary for the model of enclosure supplied. It is not necessary to test each supplied enclosure.

678.2.2.2.2 Compression Test

- (1) The enclosure shall not deform more than 10 percent in its largest cross-sectional dimension when subjected to a uniformly distributed load of 300 pound-force (1335 N) at a temperature of -1 F (-18 C) and 100 F (38 C). Perform the test after stabilizing at the required temperature for a minimum of 2 hours. It shall consist of placing an assembled enclosure between 2 flat paralleled surfaces, with the longest enclosure dimension parallel to the surfaces. Place the weight on the upper surface for a minimum of 15 minutes. Take the measurement with weight in place.

678.2.2.2.3 Impact Test

- (1) The assembled enclosure shall be capable of withstanding an impact of 20.65 foot-pounds (28 Nm) at temperatures of -1 F (-18) and 100 F (38 C). Perform the test after stabilizing the enclosure at the required temperature for a minimum of 2 hours. The test fixture shall consist of 20-pound (9 kg) cylindrical steel impacting head with a 2-inch (50 mm) spherical radius at the point where it contacts the enclosure. Drop the enclosure from a height of 12 inches (300 mm). The enclosure shall not exhibit any cracks or fractures to the housing that would preclude it from passing the water immersion test. There shall be no permanent deformation to the original diameter or characteristic vertical dimension by more than 5 percent.

678.2.2.2.4 Cable Gripping and Sealing Test

- (1) The cable gripping and sealing hardware shall not cause an increase in fiber attenuation in excess of 0.05 dB/fiber at 1550 nm when attached to the cables and the enclosure assembly. The test shall consist of measurements from 6 fibers, one from each buffer tube or channel, or randomly selected in the case of a single fiber bundle. Take the measurements from the test fibers, before and after assembly to determine the effects of the cable gripping and sealing hardware on the optical transmission of the fibers.

678.2.2.2.5 Vibration Test

- (1) The splice organizers shall securely hold the fiber splices and store the excess fiber. Test the fiber splice organizers and splice-retaining hardware according to EIA standard FOP-II, test condition I. The individual fibers shall not show an increase in attenuation in excess of 0.1 dB/fiber.

678.2.2.2.6 Water Immersion Test

- (1) The enclosure shall be capable of preventing a 10-foot (3 m) water head from intruding into the splice compartment for a period of 7 days. Test splice enclosure by the placing of the enclosure into a pressure vessel and filling the vessel with tap water to cover the enclosure. Apply continuous pressure to the vessel to maintain a hydrostatic head equivalent to 10 feet (3 m) on the enclosure and cable. Continue this process for 30 days. Remove the enclosure and open to check for the presence of water. Any intrusion of water in the compartment containing the splices constitutes a failure.

678.2.3 Fiber Optic Terminations

- (1) Furnish fiber optic connectors from the department's approved products list.
- (2) Connectors shall be type ST.
- (3) Connectors shall utilize epoxy or hot melt adhesive and shall include a ceramic ferrule.

678.2.4 Communication System Testing

- (1) Supply all materials and equipment necessary to perform the tests as described in these specifications. All test equipment will remain property of the contractor. Use equipment consisting of, but not limited to, the following:
- Optical time domain reflectometer (OTDR).
 - Optical source/power meter.
 - Patch cabling.
 - OTDR software.
-

678.3.3 Fiber Optic Terminations

Replace paragraph two and three with the following effective with the April 2007 letting:

- (2) Terminate all fibers on the rear of the termination panel with type ST connectors.
- (3) Install fiber optic jumpers of sufficient length to connect the front side of the termination panel to the fiber equipment contained within the cabinet.
-

678.5 Payment

Replace paragraph two with the following effective with the April 2007 letting:

- (2) Payment for the Install Fiber Optic Cable Outdoor Plant bid items is full compensation for installing and testing department-furnished cabling.

Replace paragraph four with the following effective with the April 2007 letting:

- (4) Payment for Fiber Optic Termination is full compensation for providing connectors and jumper cables; and for completing the installation using department-furnished termination panels.

ADDITIONAL SPECIAL PROVISION 7

- A. Reporting 1st Tier and DBE Payments During Construction
1. Comply with reporting requirements specified in the department's Civil Rights Compliance, Contractor's User Manual, Sublets and Payments.
 2. Report payments to all DBE firms within 10 calendar days of receipt of a progress payment by the department or a contractor for work performed, materials furnished, or materials stockpiled by a DBE firm. Report the payment as specified in A(1) for all work satisfactorily performed and for all materials furnished or stockpiled.
 3. Report payments to all first tier subcontractor relationships within 10 calendar days of receipt of a progress payment by the department for work performed. Report the payment as specified in A(1) for all work satisfactorily performed.
 4. All tiers shall report payments as necessary to comply with the DBE payment requirement as specified in A(2).
 5. Require all first tier relationships, DBE firms and all other tier relationships necessary to comply with the DBE payment requirement in receipt of a progress payment by contractor to acknowledge receipt of payment as specified in A(1), (2), (3) and (4).
 6. All agreements made by a contractor shall include the provisions in A(1), (2), (3), (4) and (5), and shall be binding on all first tier subcontractor relationships and all contractors and subcontractors utilizing DBE firms on the project.
- B. Costs for conforming to this special provision are incidental to the contract.

Effective with September 2004 Letting

**WISCONSIN DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS AND TRANSPORTATION FACILITIES**

SUPPLEMENTAL REQUIRED CONTRACT PROVISIONS

- I. Wage Rates, Hours of labor and payment of Wages
- II. Payroll Requirements
- III. Postings at the Site of the Work
- IV. Affidavits
- V. Wage Rate Redistribution
- VI. Additional Classifications

I. WAGE RATES, HOURS OF LABOR AND PAYMENT OF WAGES

The schedule of "Minimum Wage Rates" attached hereto and made a part hereof furnishes the prevailing wage rates that have been determined pursuant to Section 103.50 of the Wisconsin Statutes. These wage rates are the minimum required to be paid to the various laborers, workers, mechanics and truck drivers employed by contractors and subcontractors on the construction work embraced by the contract and subject to prevailing hours and wages under Section 103.50, Stats. If necessary to employ laborers, workers, mechanics or truck drivers whose classification is not listed on the schedule, they shall be paid at rates conformable to those listed for similar classifications. Apprentices shall be paid at rates not less than those prescribed in their state indenture contracts.

While the wage rates shown are the minimum rates required by the contract to be paid during its life, this is not a representation that labor can be obtained at these rates. It is the responsibility of bidders to inform themselves as to the local labor conditions and prospective changes or adjustments of wage rates. No increase in the contract price shall be allowed or authorized on account of the payment of wage rates in excess of those listed herein.

Pursuant to Section 103.50 of the Wisconsin Statutes, the prevailing hours of labor have been determined to be up to 10 hours per day and 40 hours per calendar week Monday through Friday. If any laborer, worker, mechanic or truck driver is permitted or required to work more than the prevailing number of hours per day or per calendar week on this contract, they shall be paid for all hours in excess of the prevailing hours at a rate of at least one and one-half (1 1/2) times their hourly rate of pay. All work on Saturday, Sunday and the following holidays is to be paid at time and a half: (1) January 1, (2) the last Monday in May, (3) July 4, (4) the first Monday in September, (5) the fourth Thursday in November, (6) December 25, (7) the day before if January 1, July 4 or December 25 falls on a Saturday and (8) the day following if January 1, July 4 or December 25 falls on a Sunday.

All laborers, workers, mechanics and truck drivers shall be paid unconditionally not less often than once a week. Persons who own and operate their own trucks must receive the prevailing truck driver rate for the applicable type of truck (i.e. 2 axle, 3 or more axle, articulated, eculid or dumptor) he or she operates, plus an agreed upon amount for the use of his or her truck. Every owner-operator MUST be paid separately for their driving and for the use of their truck.

For those projects subject to the requirements of the Davis-Bacon Act, the Secretary of Labor will also have determined "Minimum Wage Rates" for work to be performed under the contract. These rates are, for all or most of the labor, worker, mechanic or truck driver classifications, identical to those established under Section 103.50 of the Wisconsin Statutes. In the event the rates are not identical, the higher of the two rates will govern.

II. PAYROLL REQUIREMENTS

All contractors and subcontractors must submit weekly Certified Payrolls and Compliance Statement verifying that all laborers, workers, mechanics and truck drivers working on the project have been paid the prevailing wage rates for all work performed under the contract required by Section 103.50 of the Wisconsin Statutes.

III. POSTINGS AT THE SITE OF THE WORK

In addition to the required postings furnished by the Department, the contractor shall post the following in at least one conspicuous place at the site of work:

- a. "NOTICE TO EMPLOYEES," which provides information required to be posted by the provisions of Section 103.50 of the Wisconsin Statutes.
- b. A copy of the State of Wisconsin Minimum Wages Rates. (Four pages.)
- c. A copy of the contractor's Equal Employment Opportunity Policy.
- d. On any project involving federal aid, in addition to the furnished postings, the contractor shall post a copy of the "Davis-Bacon Act, Minimum Wage Rates". (Three pages.)

IV. WAGE RATE REDISTRIBUTION

The amount specified as the hourly basic rate of pay and the amount(s) specified as the fringe benefit contribution(s), for all classes of laborers, workers, mechanics or truck drivers may be redistributed, when necessary, to conform to those specified in any applicable collective bargaining agreement, provided that both parties to such agreement

request and receive the approval for any such redistribution from both the Department of Transportation and the Department of Workforce Development prior to the implementation of such redistribution.

V. ADDITIONAL CLASSIFICATIONS

Any unlisted laborer or mechanic classification that is needed to perform work on this project, and is not included within the scope of any of the classifications listed in the application prevailing wage rate determination, may be added after award only if all of the following criteria have been met:

1. The affected employer(s) must make a written request to WisDOT Central Office to utilize the unlisted classification on this project.
2. The request must indicate the scope of the work to be performed by the unlisted classification and must indicate the proposed wage/fringe benefit package that the unlisted classification is to receive.
3. The work to be performed by the unlisted classification must not be performed by a classification that is included in the applicable prevailing wage rate determination.
4. The unlisted classification must be commonly employed in the area where the project is located.
5. The proposed wage/fringe benefit package must bear a reasonable relationship to those set forth in the applicable prevailing wage rate determination.
6. The request should be made prior to the actual performance of the work by the unlisted classification.
7. DWD must approve the use of the unlisted classification and the proposed wage/fringe benefit package. USDOL also must approve the use of the unlisted classification and the proposed wage/fringe benefit package on federal aid projects.
8. WisDOT and DWD may amend the proposed wage/fringe benefit package, as deemed necessary, and may set forth specific employment ratios and scope of work requirements in the approval document.

The approved wage/fringe benefit package shall be paid to all laborers, workers, mechanics or truck drivers performing work within the scope of that performed by the unlisted classification, from the first day on which such work is performed. In the event that work is performed by the unlisted classification prior to approval, the wage/fringe benefit package to be paid for such work must be in conformance with the wage/fringe

benefit package approved for such work. Under this arrangement a retroactive adjustment in wages and/or fringe benefits may be required to be made to the affected laborers, workers, mechanics or truck drivers by the affected employer(s).

Equal Rights Division
Labor Standards Bureau
P. O. Box 8928
Madison, Wisconsin 53708
(608) 266-6860

**FINAL DETERMINATION
ANNUAL PREVAILING WAGE RATE SURVEY DATA
RACINE COUNTY**

Compiled by the State of Wisconsin
Department of Workforce Development
Pursuant to s. 103.50, Stats.
For All State Highway Projects
Issued on April 30, 2007

CLASSIFICATION: Contractors are required to call the Department of Workforce Development if there are any questions regarding the proper trade or classification to be used for any worker on a public works project.

OVERTIME: Time and one-half must be paid for all hours worked over 10 hours per day and 40 hours per calendar week and for all hours worked on Saturday, Sunday and the following six (6) holidays: January 1; the last Monday in May; July 4; the 1st Monday in September; the 4th Thursday in November; December 25; the day before if January 1, July 4 or December 25 falls on a Saturday; the day following if January 1, July 4 or December 25 falls on a Sunday.

FUTURE INCREASE: If indicated for a specific trade or occupation, the full amount of such increase MUST be added to the "TOTAL" indicated for such trade or occupation on the date(s) such increase(s) becomes effective.

PREMIUM PAY: If indicated for a specific trade or occupation, the full amount of such pay MUST be added to the "HOURLY BASIC RATE OF PAY" indicated for such trade or occupation, whenever such pay is applicable.

SUBJOURNEY: Wage rates may be available for some of the classifications indicated below. Any employer that desires to use any subjourney classification on a project MUST request the applicable wage rate from the Department of Workforce Development PRIOR to the date such classification is used on such project. Form ERD-10880 is available for this purpose and can be obtained by writing to the Department of Workforce Development, Equal Rights Division, P.O. Box 8928, Madison, WI 53708.

<u>TRADE OR OCCUPATION</u>	<u>HOURLY BASIC RATE OF PAY</u>	<u>HOURLY FRINGE BENEFITS</u>	<u>TOTAL</u>
	\$	\$	\$
Bricklayer, Blocklayer or Stonemason	29.23	12.20	41.43
Carpenter	27.83	12.19	40.02
Cement Finisher	26.82	9.68	36.50
Electrician	26.80	14.88	41.68
Fence Erector	17.00	3.93	20.93
Ironworker	28.09	17.01	45.10
Future Increase(s): Add \$2.00 6/3/2007; Add \$2.00 6/2/2008; Add \$2.00 6/1/2009; Add \$ 2.00 6/7/2010; Add \$2.00 6/ 6/ 2011.			
Line Constructor (Electrical)	30.22	13.21	43.43
Painter	24.09	9.22	33.31
Pavement Marking Operator	23.46	9.45	32.91
Piledriver	25.76	17.33	43.09
Future Increase(s): Add \$1.45 on 6/4/07			
Premium Pay: Add \$.65 for Piledriver Loftsmen; Add \$.75 for Sheet Pile Loftsmen.			
Roofer or Waterproofor	26.00	10.33	36.33
Teledata Technician or Installer	21.98	8.89	30.87
Tuckpointer, Caulker or Cleaner	28.43	13.11	41.54
Underwater Diver (Except on Great Lakes)	25.76	15.88	41.64
Heavy Equipment Operator - ELECTRICAL LINE CONSTRUCTION ONLY	28.81	12.70	41.51
Light Equipment Operator -ELECTRICAL LINE CONSTRUCTION ONLY	25.33	12.34	37.67
Future Increase(s): Add \$1.13/hr. 7/1/2007; Add \$1.20/hr. 7/1/2008.			
Heavy Truck Driver - ELECTRICAL LINE CONSTRUCTION ONLY	21.15	10.57	31.72
Light Truck Driver - ELECTRICAL LINE CONSTRUCTION ONLY	19.64	10.14	29.78

<u>TRADE OR OCCUPATION</u>	<u>HOURLY BASIC RATE OF PAY</u>	<u>HOURLY FRINGE BENEFITS</u>	<u>TOTAL</u>
	\$	\$	\$
Groundman - ELECTRICAL LINE CONSTRUCTION ONLY	17.41	9.96	27.37
Future Increase(s): Add \$.78/hr. 7/1/2007; Add \$.82/hr. 7/1/2008			

TRUCK DRIVERS

Single Axle or Two Axle	14.95	4.36	19.31
Three or More Axle	20.80	12.46	33.26
Articulated, Euclid, Dumptror, Off Road Material Hauler	21.52	15.35	36.87
Future Increase(s): Add \$1.60 on 6/1/07; Add \$1.65 on 6/1/08			
Pavement Marking Vehicle	18.87	9.39	28.26
Shadow or Pilot Vehicle	14.95	4.36	19.31
Truck Mechanic	22.00	12.06	34.06
Future Increase(s): Add \$1.45 5/1/2007; Add \$1.45 5/1/2008; Add \$1.65 5/1/2009; Add \$1.65 5/1/2010.			

LABORERS

General Laborer	20.38	11.77	32.15
Asbestos Abatement Worker	14.50	1.80	16.30
Landscaper	22.04	12.45	34.49
Future Increase(s): Add \$1.45 on 6/1/07; Add \$1.50 on 6/1/08; Add \$1.35 on 6/1/09.			
Flagperson or Traffic Control Person	18.53	12.45	30.98
Future Increase(s): Add \$1.45 on 6/1/07; Add \$1.50 on 6/1/08; Add \$1.35 on 6/1/09.			
Fiber Optic Laborer (Outside, Other Than Concrete Encased)	14.00	0.32	14.32
Railroad Track Laborer	13.00	7.23	20.23

HEAVY EQUIPMENT OPERATORS

Crane, Tower Crane or Derrick, With or Without Attachments, With a Lifting Capacity of Over 100 Tons; Crane, Tower Crane or Derrick, With Boom, Leads and/or Jib Lengths Measuring 176 Feet or Over	28.97	15.35	44.32
Future Increase(s): Add \$1.60 on 6/1/07; Add \$1.65 on 6/1/08			
Crane, Tower Crane or Derrick, With or Without Attachments, With a Lifting Capacity of 100 Tons or Under; Crane, Tower Crane or Derrick, With Boom, Leads and/or Jib Lengths Measuring 175 Feet or Under; Backhoe (Track Type) Having a Mfgr.'s Rated Capacity of 130,000 Lbs. or Over; Caisson Rig; Pile Driver; Dredge (Not Performing Work on the Great Lakes)	28.47	15.35	43.82
Future Increase(s): Add \$1.60 on 6/1/07; Add \$1.65 on 6/1/08			
Backhoe (Track Type) Having a Mfgr.'s Rated Capacity of Under 130,000 Lbs.; Tractor or Truck Mounted Hydraulic Backhoe; Gradall (Cruz-Aire Type); Mechanic or Welder; Bulldozer or Endloader; Grader or Motor Patrol; Scraper (Self propelled or Tractor Drawn) 5 cu yards or more capacity; Concrete Pump, Grout Pump or Concrete Conveyor (Rotec or Bidwell Type); Concrete Breaker (Manual or Remote); Concrete Batch Plant; Power Subgrader; Concrete Spreader; Concrete Paver; Concrete Grinder or Planing Machine; Concrete Conveyor System; Concrete Slipform Placer Curb and Gutter Machine; Asphalt Plant; Asphalt Paver; Asphalt Screed; Asphalt Milling Machine; Roller (Over 5 Ton); Shouldering Machine; Boring Machine (Horizontal, Vertical or Directional); Air Track, Rotary or Percussion	27.97	15.35	43.32

<u>TRADE OR OCCUPATION</u>	<u>HOURLY BASIC RATE OF PAY</u>	<u>HOURLY FRINGE BENEFITS</u>	<u>TOTAL</u>
	\$	\$	\$
Drilling Machine; Straddle Carrier or Travel Lift; Trencher; Post Hole Digger or Driver; Tug or Launch (Not Performing Work on the Great Lakes) Future Increase(s): Add \$1.60 on 6/1/07; Add \$1.65 on 6/1/08			
Farm or Industrial Type Tractor; Greaser; Compactor (Self-Propelled); Concrete Saw (Vermeer Type); Concrete Bump Cutter or Grooving Machine; Tining or Curing Machine; Roller (5 Tons or Under); Broom or Sweeper; Environmental Burner Future Increase(s): Add \$1.60 on 6/1/07; Add \$1.65 on 6/1/08	27.97	15.35	43.32
Oiler; Crusher, Screening or Wash Plant; Air Compressor; Generator; Pump (3 Inch or Over) or Well Points; Forklift; Skid Steer Loader (With or Without Attachments); Skid Rig; Stump Chipper; Mulcher; Vibratory Hammer or Extractor Future Increase(s): Add \$1.60 on 6/1/07; Add \$1.65 on 6/1/08	27.42	15.35	42.77
Fiber Optic Cable Equipment	24.18	11.45	35.63
Work Performed on the Great Lakes Including Diver; Wet Tender or Hydraulic Dredge Engineer	30.59	15.10	45.69
Work Performed on the Great Lakes Including Crane or Backhoe Operator; Mechanic or Welder; Assistant Hydraulic Dredge Engineer; Hydraulic Dredge Leverman or Diver's Tender	31.95	15.93	47.88
Work Performed on the Great Lakes Including Deck Equipment Operator or Machineryman (Maintains Cranes Over 50 Tons or Backhoes Over 115,000 Lbs. or more); Tug, Launch or Loader, Dozer or Like Equipment When Operated on a Barge, Breakwater Wall, Slip, Dock or Scow, Deck Machinery	27.70	15.00	42.70
Work Performed on the Great Lakes Including Deck Equipment Operator; Machineryman or Fireman (Operates 4 Units or More or Maintains Cranes 50 Tons or Under or Backhoes 115,000 Lbs. or Under), Deck Hand, Deck Engineer or Assistant Tug Operator.	27.70	15.00	42.70

The following statutory provisions apply to all state highway projects based on bids as provided in s. 84.06 (2), Stats. and are set forth below pursuant to the requirements of s. 103.50 (6), Stats.

(2) PREVAILING WAGE RATES AND HOURS OF LABOR. No person described in sub. (2m) in the employ of a contractor, subcontractor, agent or other person performing any work on a project under a contract based on bids as provided in s. 84.06 (2) to which the state is a party for the construction or improvement of any highway may be permitted to work a longer number of hours per day or per calendar week than the prevailing hours of labor determined under sub. (3); nor may he or she be paid a lesser rate of wages than the prevailing wage rate in the area in which the work is to be done determined under sub. (3); except that any such person may be permitted or required to work more than such prevailing hours of labor per day and per calendar week if he or she is paid for all hours worked in excess of the prevailing hours of labor at a rate of at least 1.5 times his or her hourly basic rate of pay.

(7) PENALTIES. (a) Except as provided in pars. (b), (d) and (f), any contractor, subcontractor or agent thereof who violates this section may be fined not more than \$200 or imprisoned for not more than 6 months or both. Each day that any such violation continues shall be considered a separate offense.

(b) Whoever induces any individual who seeks to be or is employed on any project that is subject to this section to give up, waive or return any part of the wages to which the individual is entitled under the contract governing such project, or who reduces the hourly basic rate of pay normally paid to an employee for work on a project that is not subject to this section during a week in which the employee works both on a project that is subject to this section and on a project that is not subject to this section, by threat not to employ, by threat of dismissal from such employment or by any other means is guilty of an offense under s. 946.15 (1).

(c) Any person employed on a project that is subject to this section who knowingly permits a contractor, subcontractor or agent thereof to pay him or her less than the prevailing wage rate set forth in the contract governing such project, who gives up, waives or returns any part of the compensation to which he or she is entitled under the contract, or who gives up, waives or returns any part of the compensation to which he or she is normally entitled for work on a project that is not subject to this section during a week in which the person works both on a project that is subject to this section and on a project that is not subject to this section, is guilty of an offense under s. 946.15 (2).

(d) Whoever induces any individual who seeks to be or is employed on any project that is subject to this section to permit any part of the wages to which the individual is entitled under the contract governing such project to be deducted from the individual's pay is guilty of an offense under s. 946.15 (3), unless the deduction would be permitted under 29 CFR 3.5 or 3.6 from an individual who is working on a project that is subject to 40 USC 276c.

(e) Any person employed on a project that is subject to this section who knowingly permits any part of the wages to which he or she is entitled under the contract governing such project to be deducted from his or her pay is guilty of an offense under s. 946.15 (4), unless the deduction would be permitted under 29 CFR 3.5 or 3.6 from an individual who is working on a project that is subject to 40 USC 276c.

(f) Paragraph (a) does not apply to any person who fails to provide any information to the department to assist the department in determining prevailing wage rates or prevailing hours of labor under sub. (3) or (4).

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20070710018PROJECT(S):
3180-10-70FEDERAL ID(S):
N/A

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS

SECTION 0001 ROADWAY CONSTRUCTION

0010	201.0105 CLEARING	42.000				
		STA	.		.	
0020	201.0205 GRUBBING	42.000				
		STA	.		.	
0030	203.0100 REMOVING SMALL PIPE CULVERTS	12.000				
		EACH	.		.	
0040	203.0200 REMOVING OLD STRUCTURE (STATION) 01. 345+72.97	LUMP	LUMP			.
0050	204.0100 REMOVING PAVEMENT	7,612.000				
		SY	.		.	
0060	204.0115 REMOVING ASPHALTIC SURFACE BUTT JOINTS	4,040.000				
		SY	.		.	
0070	204.0120 REMOVING ASPHALTIC SURFACE MILLING	2,918.000				
		SY	.		.	
0080	204.0150 REMOVING CURB & GUTTER	1,174.000				
		LF	.		.	
0090	204.0210 REMOVING MANHOLES	1.000				
		EACH	.		.	
0100	204.0220 REMOVING INLETS	3.000				
		EACH	.		.	

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20070710018PROJECT(S):
3180-10-70FEDERAL ID(S):
N/A

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	204.0245 REMOVING STORM SEWER (SIZE) 01. 15-INCH	119.000 LF	.		.	
0120	204.0245 REMOVING STORM SEWER (SIZE) 02. 18-INCH	153.000 LF	.		.	
0130	204.0245 REMOVING STORM SEWER (SIZE) 03. 36-INCH	84.000 LF	.		.	
0140	204.9060.S REMOVING (ITEM DESCRIPTION) 01. RETAINING WALL	1.000 EACH	.		.	
0150	205.0100 EXCAVATION COMMON	45,286.000 CY	.		.	
0160	205.0400 EXCAVATION MARSH	1,068.000 CY	.		.	
0170	205.9006.S GRADING SHAPING & FINISHING FOR BARRIER TERMINALS	13.000 EACH	.		.	
0180	206.1000 EXCAVATION FOR STRUCTURES BRIDGES (STRUCTURE) 01. B-51-101	LUMP	LUMP		.	
0190	206.1000 EXCAVATION FOR STRUCTURES BRIDGES (STRUCTURE) 02. B-51-95	LUMP	LUMP		.	
0200	206.2000 EXCAVATION FOR STRUCTURES CULVERTS (STRUCTURE) 01. C-51-22	LUMP	LUMP		.	

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20070710018PROJECT(S):
3180-10-70FEDERAL ID(S):
N/A

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0210	208.0100 BORROW	350,609.000 CY	.		.	
0220	209.0100 BACKFILL GRANULAR	41,579.000 CY	.		.	
0230	210.0100 BACKFILL STRUCTURE	594.000 CY	.		.	
0240	211.0500 PREPARE FOUNDATION FOR BASE AGGREGATE	609.000 STA	.		.	
0250	213.0100 FINISHING ROADWAY (PROJECT) 01. 3180-10-70	1.000 EACH	.		.	
0260	214.0100 OBLITERATING OLD ROAD	1.000 STA	.		.	
0270	301.0100.S QMP BASE AGGREGATE	271,320.000 TON	.		.	
0280	305.0110 BASE AGGREGATE DENSE 3/4-INCH	72,190.000 TON	.		.	
0290	305.0120 BASE AGGREGATE DENSE 1 1/4-INCH	201,222.000 TON	.		.	
0300	311.0110 BREAKER RUN	1,000.000 TON	.		.	
0310	415.0070 CONCRETE PAVEMENT 7-INCH	38.000 SY	.		.	

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20070710018PROJECT(S):
3180-10-70FEDERAL ID(S):
N/A

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0320	415.2000.S INCENTIVE STRENGTH CONCRETE PAVEMENT	400.000 DOL	1.00000		400.00	
0330	415.3000.S QMP CONCRETE PAVEMENT	2.000 DAY	.		.	
0340	416.0050 CONCRETE PAVEMENT APPROACH SLAB	152.000 SY	.		.	
0350	416.0170 CONCRETE DRIVEWAY 7-INCH	203.000 SY	.		.	
0360	416.0610 PAVEMENT TIES	40.000 EACH	.		.	
0370	416.1010 CONCRETE SURFACE DRAINS	64.000 CY	.		.	
0380	455.0115 ASPHALTIC MATERIAL PG64-22	3,691.000 TON	.		.	
0390	455.0120 ASPHALTIC MATERIAL PG64-28	2,006.000 TON	.		.	
0400	455.0605 TACK COAT	13,021.000 GAL	.		.	
0410	460.1103 HMA PAVEMENT TYPE E-3	89,984.000 TON	.		.	
0420	460.2000 INCENTIVE DENSITY HMA PAVEMENT	57,599.000 DOL	1.00000		57599.00	

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20070710018PROJECT(S):
3180-10-70FEDERAL ID(S):
N/A

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0430	460.2500.S QMP HMA PAVEMENT NUCLEAR DENSITY	89,984.000 TON	.		.	
0440	460.3000 QMP HMA MIXTURE	89,984.000 TON	.		.	
0450	465.0105 ASPHALTIC SURFACE	2,971.000 TON	.		.	
0460	465.0120 ASPHALTIC SURFACE DRIVEWAYS AND FIELD ENTRANCES	548.000 TON	.		.	
0470	465.0125 ASPHALTIC SURFACE TEMPORARY	981.000 TON	.		.	
0480	465.0315 ASPHALTIC FLUMES	179.000 SY	.		.	
0490	465.0400 ASPHALTIC SHOULDER RUMBLE STRIP	104,893.000 LF	.		.	
0500	502.0100 CONCRETE MASONRY BRIDGES	936.000 CY	.		.	
0510	502.0400.S INCENTIVE STRENGTH CONCRETE STRUCTURES	908.000 DOL	1.00000		908.00	
0520	502.3200 PROTECTIVE SURFACE TREATMENT	1,976.000 SY	.		.	
0530	502.6105 MASONRY ANCHORS TYPE S 5/8-INCH	22.000 EACH	.		.	

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20070710018PROJECT(S):
3180-10-70FEDERAL ID(S):
N/A

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0540	503.0155 PRESTRESSED GIRDER TYPE I 54W-INCH	2,158.000 LF	.		.	
0550	504.0100 CONCRETE MASONRY CULVERTS	36.000 CY	.		.	
0560	505.0405 BAR STEEL REINFORCEMENT HS BRIDGES	9,350.000 LB	.		.	
0570	505.0410 BAR STEEL REINFORCEMENT HS CULVERTS	3,970.000 LB	.		.	
0580	505.0605 BAR STEEL REINFORCEMENT HS COATED BRIDGES	144,510.000 LB	.		.	
0590	505.0610 BAR STEEL REINFORCEMENT HS COATED CULVERTS	380.000 LB	.		.	
0600	506.2605 BEARING PADS ELASTOMERIC NON-LAMINATED	30.000 EACH	.		.	
0610	506.4000 STEEL DIAPHRAGMS (STRUCTURE) 01. B-51-101	16.000 EACH	.		.	
0620	506.4000 STEEL DIAPHRAGMS (STRUCTURE) 02. B-51-95	16.000 EACH	.		.	
0630	511.2110 PILING STEEL DELIVERED AND DRIVEN HP 12-INCH X 53 LB	2,410.000 LF	.		.	
0640	511.2120 PILING STEEL DELIVERED AND DRIVEN HP 14-INCH X 73 LB	1,620.000 LF	.		.	

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20070710018PROJECT(S):
3180-10-70FEDERAL ID(S):
N/A

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0650	512.1000 PILING STEEL SHEET TEMPORARY	3,570.000 SF	.		.	
0660	516.0500 RUBBERIZED MEMBRANE WATERPROOFING	51.000 SY	.		.	
0670	520.0118 CULVERT PIPE CLASS III 18-INCH	58.000 LF	.		.	
0680	520.0124 CULVERT PIPE CLASS III 24-INCH	410.000 LF	.		.	
0690	520.0318 CULVERT PIPE CLASS IV 18-INCH	137.000 LF	.		.	
0700	520.0624 CULVERT PIPE CLASS V 24-INCH	423.000 LF	.		.	
0710	520.1018 APRON ENDWALLS FOR CULVERT PIPE 18-INCH	6.000 EACH	.		.	
0720	520.1024 APRON ENDWALLS FOR CULVERT PIPE 24-INCH	14.000 EACH	.		.	
0730	520.4072 CULVERT PIPE TEMPORARY 72-INCH	110.000 LF	.		.	
0740	522.0524 CULVERT PIPE REINFORCED CONCRETE CLASS V 24-INCH	176.000 LF	.		.	
0750	522.1012 APRON ENDWALLS FOR CULVERT PIPE REINFORCED CONCRETE 12-INCH	9.000 EACH	.		.	

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20070710018PROJECT(S):
3180-10-70FEDERAL ID(S):
N/A

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0760	522.1018 APRON ENDWALLS FOR CULVERT PIPE REINFORCED CONCRETE 18-INCH	2.000 EACH	.		.	
0770	522.1024 APRON ENDWALLS FOR CULVERT PIPE REINFORCED CONCRETE 24-INCH	6.000 EACH	.		.	
0780	601.0411 CONCRETE CURB & GUTTER 30-INCH TYPE D	1,620.000 LF	.		.	
0790	601.0554 CONCRETE CURB & GUTTER 4-INCH MOUNTABLE 36-INCH TYPE D	148.000 LF	.		.	
0800	601.0558 CONCRETE CURB & GUTTER 6-INCH MOUNTABLE 36-INCH TYPE D	28,603.000 LF	.		.	
0810	602.0405 CONCRETE SIDEWALK 4-INCH	200.000 SF	.		.	
0820	602.0505 CURB RAMP DETECTABLE WARNING FIELD YELLOW	80.000 SF	.		.	
0830	603.0105 CONCRETE BARRIER SINGLE-FACED 32-INCH	509.000 LF	.		.	
0840	603.0500 CONCRETE BARRIER TEMPORARY PRECAST CONTRACTOR FURNISHED & DELIVERED	5,840.000 LF	.		.	
0850	603.0801 CONCRETE BARRIER TEMPORARY PRECAST CONTRACTOR INSTALLED	5,840.000 LF	.		.	

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20070710018PROJECT(S):
3180-10-70FEDERAL ID(S):
N/A

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0860	604.0500 SLOPE PAVING CRUSHED AGGREGATE	745.000 SY	.		.	
0870	606.0100 RIPRAP LIGHT	634.000 CY	.		.	
0880	608.0312 STORM SEWER PIPE REINFORCED CONCRETE CLASS III 12-INCH	2,040.000 LF	.		.	
0890	608.0318 STORM SEWER PIPE REINFORCED CONCRETE CLASS III 18-INCH	405.000 LF	.		.	
0900	608.0324 STORM SEWER PIPE REINFORCED CONCRETE CLASS III 24-INCH	720.000 LF	.		.	
0910	608.0412 STORM SEWER PIPE REINFORCED CONCRETE CLASS IV 12-INCH	42.000 LF	.		.	
0920	608.0424 STORM SEWER PIPE REINFORCED CONCRETE CLASS IV 24-INCH	168.000 LF	.		.	
0930	611.0201 MANHOLES TYPE 1	9.000 EACH	.		.	
0940	611.0210 MANHOLES TYPE 3	13.000 EACH	.		.	
0950	611.0301 INLETS TYPE 1	7.000 EACH	.		.	
0960	611.0302 INLETS TYPE 2	2.000 EACH	.		.	

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20070710018PROJECT(S):
3180-10-70FEDERAL ID(S):
N/A

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0970	611.0303 INLETS TYPE 3	126.000				
		EACH	.		.	
0980	611.0305 INLETS TYPE 8	4.000				
		EACH	.		.	
0990	611.0530 MANHOLE COVERS TYPE J	7.000				
		EACH	.		.	
1000	611.0606 INLET COVERS TYPE B	10.000				
		EACH	.		.	
1010	611.0609 INLET COVERS TYPE B-A	1.000				
		EACH	.		.	
1020	611.0624 INLET COVERS TYPE H	9.000				
		EACH	.		.	
1030	611.0627 INLET COVERS TYPE HM	113.000				
		EACH	.		.	
1040	611.0636 INLET COVERS TYPE HM-S	8.000				
		EACH	.		.	
1050	611.0639 INLET COVERS TYPE H-S	4.000				
		EACH	.		.	
1060	611.0642 INLET COVERS TYPE MS	6.000				
		EACH	.		.	
1070	611.0654 INLET COVERS TYPE V	3.000				
		EACH	.		.	

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20070710018PROJECT(S):
3180-10-70FEDERAL ID(S):
N/A

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
1080	611.8110 ADJUSTING MANHOLE COVERS	15.000 EACH	.		.	
1090	611.8115 ADJUSTING INLET COVERS	68.000 EACH	.		.	
1100	612.0106 PIPE UNDERDRAIN 6-INCH	176.000 LF	.		.	
1110	612.0206 PIPE UNDERDRAIN UNPERFORATED 6-INCH	100.000 LF	.		.	
1120	612.0212 PIPE UNDERDRAIN UNPERFORATED 12-INCH	309.000 LF	.		.	
1130	612.0700 DRAIN TILE EXPLORATION	5,600.000 LF	.		.	
1140	614.0115 ANCHORAGES FOR STEEL PLATE BEAM GUARD TYPE 2	3.000 EACH	.		.	
1150	614.0150 ANCHOR ASSEMBLIES FOR STEEL PLATE BEAM GUARD	8.000 EACH	.		.	
1160	614.0200 STEEL THRIE BEAM STRUCTURE APPROACH	391.400 LF	.		.	
1170	614.0220.S STEEL THRIE BEAM BULL NOSE TERMINAL	6.000 EACH	.		.	
1180	614.0230.S STEEL THRIE BEAM	400.000 LF	.		.	

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20070710018PROJECT(S):
3180-10-70FEDERAL ID(S):
N/A

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
1190	614.0305 STEEL PLATE BEAM GUARD CLASS A	5,700.000 LF	.		.	
1200	614.0370 STEEL PLATE BEAM GUARD ENERGY ABSORBING TERMINAL	20.000 EACH	.		.	
1210	614.0605 MARKER POSTS RIGHT-OF-WAY	226.000 EACH	.		.	
1220	614.0620.S MARKER POSTS CULVERT END FLEXIBLE	43.000 EACH	.		.	
1230	614.0905 CRASH CUSHIONS TEMPORARY	2.000 EACH	.		.	
1240	616.0404 FENCE CHAIN LINK SALVAGED 4-FT	22.000 LF	.		.	
1250	618.0100 MAINTENANCE AND REPAIR OF HAUL ROADS (PROJECT) 01. 3180-10-70	1.000 EACH	.		.	
1260	619.1000 MOBILIZATION	1.000 EACH	.		.	
1270	620.0300 CONCRETE MEDIAN SLOPED NOSE	2,033.000 SF	.		.	
1280	621.0100 LANDMARK REFERENCE MONUMENTS	22.000 EACH	.		.	
1290	623.0200 DUST CONTROL SURFACE TREATMENT	331,752.000 SY	.		.	

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20070710018PROJECT(S):
3180-10-70FEDERAL ID(S):
N/A

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
1300	624.0100 WATER	2,712.000 MGAL	.		.	
1310	625.0100 TOPSOIL	13,804.000 SY	.		.	
1320	625.0500 SALVAGED TOPSOIL	89,457.000 SY	.		.	
1330	627.0200 MULCHING	246,500.000 SY	.		.	
1340	628.1104 EROSION BALES	881.000 EACH	.		.	
1350	628.1504 SILT FENCE	5,536.000 LF	.		.	
1360	628.1520 SILT FENCE MAINTENANCE	5,536.000 LF	.		.	
1370	628.1905 MOBILIZATIONS EROSION CONTROL	10.000 EACH	.		.	
1380	628.1910 MOBILIZATIONS EMERGENCY EROSION CONTROL	15.000 EACH	.		.	
1390	628.2004 EROSION MAT CLASS I TYPE B	49,700.000 SY	.		.	
1400	628.2027 EROSION MAT CLASS II TYPE C	2,100.000 SY	.		.	

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20070710018PROJECT(S):
3180-10-70FEDERAL ID(S):
N/A

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
1410	628.5505 POLYETHYLENE SHEETING	2,534.000 SY	.		.	
1420	628.7005 INLET PROTECTION TYPE A	67.000 EACH	.		.	
1430	628.7010 INLET PROTECTION TYPE B	16.000 EACH	.		.	
1440	628.7015 INLET PROTECTION TYPE C	67.000 EACH	.		.	
1450	628.7504 TEMPORARY DITCH CHECKS	800.000 LF	.		.	
1460	628.7550 CULVERT PIPE DITCH CHECKS	10.000 EACH	.		.	
1470	628.7560.S STONE OR ROCK DITCH CHECKS	265.000 CY	.		.	
1480	629.0205 FERTILIZER TYPE A	1.000 CWT	.		.	
1490	629.0210 FERTILIZER TYPE B	170.000 CWT	.		.	
1500	630.0120 SEEDING MIXTURE NO. 20	3,050.000 LB	.		.	
1510	630.0130 SEEDING MIXTURE NO. 30	2,400.000 LB	.		.	

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20070710018PROJECT(S):
3180-10-70FEDERAL ID(S):
N/A

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
1520	630.0300 SEEDING BORROW PIT	370.000 LB	.		.	
1530	631.1000 SOD LAWN	1,100.000 SY	.		.	
1540	631.1100 SOD EROSION CONTROL	300.000 SY	.		.	
1550	633.0100 DELINEATOR POSTS STEEL	276.000 EACH	.		.	
1560	633.0500 DELINEATORS	276.000 EACH	.		.	
1570	634.0614 POSTS WOOD 4X6-INCH X 14-FT	150.000 EACH	.		.	
1580	634.0616 POSTS WOOD 4X6-INCH X 16-FT	161.000 EACH	.		.	
1590	634.0618 POSTS WOOD 4X6-INCH X 18-FT	66.000 EACH	.		.	
1600	634.0620 POSTS WOOD 4X6-INCH X 20-FT	18.000 EACH	.		.	
1610	634.0622 POSTS WOOD 4X6-INCH X 22-FT	5.000 EACH	.		.	
1620	634.0814 POSTS TUBULAR STEEL 2X2-INCH X 14-FT	3.000 EACH	.		.	

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20070710018PROJECT(S):
3180-10-70FEDERAL ID(S):
N/A

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
1630	637.0202 SIGNS REFLECTIVE TYPE II	4,866.000 SF	.		.	
1640	638.2602 REMOVING SIGNS TYPE II	21.000 EACH	.		.	
1650	638.3000 REMOVING SMALL SIGN SUPPORTS	21.000 EACH	.		.	
1660	642.5401 FIELD OFFICE TYPE D	1.000 EACH	.		.	
1670	642.6001 FIELD LABORATORY	1.000 EACH	.		.	
1680	643.0200 TRAFFIC CONTROL SURVEILLANCE AND MAINTENANCE (PROJECT) 01. 3180-10-70	427.000 DAYS	.		.	
1690	643.0300 TRAFFIC CONTROL DRUMS	15,881.000 DAYS	.		.	
1700	643.0420 TRAFFIC CONTROL BARRICADES TYPE III	41,366.000 DAYS	.		.	
1710	643.0453 TRAFFIC CONTROL BARRICADES PERMANENT TYPE III	28.000 EACH	.		.	
1720	643.0500 TRAFFIC CONTROL FLEXIBLE TUBULAR MARKER POSTS	111.000 EACH	.		.	

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20070710018PROJECT(S):
3180-10-70FEDERAL ID(S):
N/A

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
1730	643.0600 TRAFFIC CONTROL FLEXIBLE TUBULAR MARKER BASES	111.000 EACH	.		.	
1740	643.0705 TRAFFIC CONTROL WARNING LIGHTS TYPE A	16,840.000 DAYS	.		.	
1750	643.0800 TRAFFIC CONTROL ARROW BOARDS	3,003.000 DAYS	.		.	
1760	643.0900 TRAFFIC CONTROL SIGNS	41,364.000 DAYS	.		.	
1770	643.0905.S TRAFFIC CONTROL COVERING SIGNS	20.000 EACH	.		.	
1780	643.1050.S TRAFFIC CONTROL SIGNS PORTABLE CHANGEABLE MESSAGE	854.000 DAY	.		.	
1790	643.3000 TRAFFIC CONTROL DETOUR SIGNS	29,455.000 DAYS	.		.	
1800	645.0111 GEOTEXTILE FABRIC TYPE DF SCHEDULE A	148.000 SY	.		.	
1810	645.0120 GEOTEXTILE FABRIC TYPE HR	986.000 SY	.		.	
1820	645.0140 GEOTEXTILE FABRIC TYPE SAS	600.000 SY	.		.	
1830	646.0106 PAVEMENT MARKING EPOXY 4-INCH	179,200.000 LF	.		.	

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20070710018PROJECT(S):
3180-10-70FEDERAL ID(S):
N/A

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
1840	646.0126 PAVEMENT MARKING EPOXY 8-INCH	9,590.000 LF	.		.	
1850	646.0406 PAVEMENT MARKING SAME DAY EPOXY 4-INCH	32,600.000 LF	.		.	
1860	646.0600 REMOVING PAVEMENT MARKINGS	975.000 LF	.		.	
1870	646.0871.S PAVEMENT MARKING WET REFLECTIVE TAPE 4-INCH	15,200.000 LF	.		.	
1880	647.0166 PAVEMENT MARKING ARROWS EPOXY TYPE 2	35.000 EACH	.		.	
1890	647.0356 PAVEMENT MARKING WORDS EPOXY	28.000 EACH	.		.	
1900	647.0566 PAVEMENT MARKING STOP LINE EPOXY 18-INCH	528.000 LF	.		.	
1910	647.0606 PAVEMENT MARKING ISLAND NOSE EPOXY	51.000 EACH	.		.	
1920	647.0726 PAVEMENT MARKING DIAGONAL EPOXY 12-INCH	445.000 LF	.		.	
1930	649.0400 TEMPORARY PAVEMENT MARKING REMOVABLE TAPE 4-INCH	1,840.000 LF	.		.	
1940	650.4000 CONSTRUCTION STAKING STORM SEWER SYSTEM	29.000 EACH	.		.	

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20070710018PROJECT(S):
3180-10-70FEDERAL ID(S):
N/A

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
1950	650.4500 CONSTRUCTION STAKING SUBGRADE	8,436.000 LF	.		.	
1960	650.5000 CONSTRUCTION STAKING BASE	37,784.000 LF	.		.	
1970	650.5500 CONSTRUCTION STAKING CURB GUTTER AND CURB & GUTTER	30,371.000 LF	.		.	
1980	650.6000 CONSTRUCTION STAKING PIPE CULVERTS	6.000 EACH	.		.	
1990	650.6500 CONSTRUCTION STAKING STRUCTURE LAYOUT (STRUCTURE) 01. C-51-22	LUMP	LUMP		.	
2000	650.6500 CONSTRUCTION STAKING STRUCTURE LAYOUT (STRUCTURE) 02. B-51-95	LUMP	LUMP		.	
2010	650.6500 CONSTRUCTION STAKING STRUCTURE LAYOUT (STRUCTURE) 03. B-51-101	LUMP	LUMP		.	
2020	650.7500 CONSTRUCTION STAKING CONCRETE BARRIER	509.000 LF	.		.	
2030	650.9900 CONSTRUCTION STAKING INITIAL LAYOUT	8,436.000 LF	.		.	
2040	652.0225 CONDUIT RIGID NONMETALLIC SCHEDULE 40 2-INCH	3,297.000 LF	.		.	

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20070710018PROJECT(S):
3180-10-70FEDERAL ID(S):
N/A

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
2050	652.0235 CONDUIT RIGID NONMETALLIC SCHEDULE 40 3-INCH	1,693.000 LF	.		.	
2060	652.0800 CONDUIT LOOP DETECTOR	1,624.000 LF	.		.	
2070	653.0135 PULL BOXES STEEL 24X36-INCH	6.000 EACH	.		.	
2080	653.0140 PULL BOXES STEEL 24X42-INCH	19.000 EACH	.		.	
2090	654.0101 CONCRETE BASES TYPE 1	6.000 EACH	.		.	
2100	654.0102 CONCRETE BASES TYPE 2	3.000 EACH	.		.	
2110	654.0105 CONCRETE BASES TYPE 5	9.000 EACH	.		.	
2120	654.0217 CONCRETE CONTROL CABINET BASES TYPE 9 SPECIAL	1.000 EACH	.		.	
2130	655.0220 CABLE TRAFFIC SIGNAL 4-14 AWG	136.000 LF	.		.	
2140	655.0230 CABLE TRAFFIC SIGNAL 5-14 AWG	1,080.000 LF	.		.	
2150	655.0260 CABLE TRAFFIC SIGNAL 12-14 AWG	8,186.000 LF	.		.	

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20070710018PROJECT(S):
3180-10-70FEDERAL ID(S):
N/A

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
2160	655.0305 CABLE TYPE UF 2-12 AWG GROUNDED	3,938.000 LF	.		.	
2170	655.0515 ELECTRICAL WIRE TRAFFIC SIGNALS 10 AWG	9,208.000 LF	.		.	
2180	655.0610 ELECTRICAL WIRE LIGHTING 12 AWG	4,176.000 LF	.		.	
2190	655.0700 LOOP DETECTOR LEAD IN CABLE	11,899.000 LF	.		.	
2200	655.0800 LOOP DETECTOR WIRE	7,575.000 LF	.		.	
2210	656.0200 ELECTRICAL SERVICE METER BREAKER PEDESTAL (LOCATION) 01. STH 11/36/83 & STH 83	LUMP	LUMP		.	
2220	656.0200 ELECTRICAL SERVICE METER BREAKER PEDESTAL (LOCATION) 02. STH 11 & STH 36/83	LUMP	LUMP		.	
2230	690.0100 SAWING EXISTING PAVEMENT	678.000 LF	.		.	
2240	690.0200 SAWING CONCRETE PAVEMENT FULL DEPTH	55.000 LF	.		.	
2250	SPV.0035 SPECIAL 01. QMP SUBGRADE	437,474.000 CY	.		.	

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20070710018PROJECT(S):
3180-10-70FEDERAL ID(S):
N/A

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
2260	SPV.0060 SPECIAL 01. CONCRETE BASE TYPE 9 MONOTUBE	4.000 EACH	.		.	
2270	SPV.0060 SPECIAL 02. APRON ENDWALLS FOR UNDERDRAIN REINFORCED CONCRETE 12-INCH	4.000 EACH	.		.	
2280	SPV.0060 SPECIAL 03. COVER SIGNS TYPE 1	7.000 EACH	.		.	
2290	SPV.0060 SPECIAL 04. EROSION CONTROL FILTER BAGS	250.000 EACH	.		.	
2300	SPV.0060 SPECIAL 05. SAND BAGS	2,040.000 EACH	.		.	
2310	SPV.0105 SPECIAL 01. TRAFFIC SIGNALS & STREET LIGHTING STH 11/36/83 & STH 83	LUMP	LUMP		.	
2320	SPV.0105 SPECIAL 02. TRAFFIC SIGNALS & STREET LIGHTING STH 11 & STH 36/83	LUMP	LUMP		.	
2330	SPV.0105 SPECIAL 03. TEMPORARY DIVERSION CHANNEL	LUMP	LUMP		.	
2340	SPV.0165 SPECIAL 01. ARCHITECTURAL SURFACE TREATMENT	1,530.000 SF	.		.	
2350	SPV.0165 SPECIAL 02. CONCRETE STAINING	763.000 SF	.		.	

Wisconsin Department of Transportation

PAGE: 23

DATE: 05/07/07

SCHEDULE OF ITEMS


REVISED:

CONTRACT:
20070710018PROJECT(S):
3180-10-70FEDERAL ID(S):
N/A

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
2360	SPV.0165 SPECIAL 03. COVERING SIGNS TYPE II	446.000 SF	.		.	
2370	SPV.0170 SPECIAL 01. TEST ROLLING	679.000 STA	.		.	
2380	SPV.0180 SPECIAL 01. GEOTEXTILE FABRIC TYPE FF	1,840.000 SY	.		.	
2390	SPV.0195 SPECIAL 01. WASHED STONE	18.000 TON	.		.	
	SECTION 0001 TOTAL				.	
	TOTAL BID				.	

PLEASE ATTACH SCHEDULE OF ITEMS HERE



Wisconsin Department of Transportation

June 27, 2007

**Division of Transportation System
Development**

Bureau of Project Development
4802 Sheboygan Avenue, Rm 601
P O Box 7916
Madison, WI 53707-7916

NOTICE TO ALL CONTRACTORS:

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

**Proposal #18: 3180-10-70
Burlington Bypass
STH 83 (South) to STH 36/83 (North) – Paving
STH 11
Racine County**

Letting of July 10, 2007

This is Addendum No. 1, which provides for the following:

Special Provisions

The following special provisions are added:

Article 53, Railroad Insurance and Coordination

Article 54, Plans

Schedule of Items

The following bid item quantities are revised:

- Item 211.0500, Prepare Foundation for Base Aggregate; increased from 609 to 629 STA
- Item 301.0100.S, QMP Base Aggregate; increased from 271,320 to 275,105 TON
- Item 305.0110, Base Aggregate Dense $\frac{3}{4}$ -Inch; increased from 72,190 to 72,972 TON
- Item 305.0120, Base Aggregate Dense 1 $\frac{1}{4}$ -Inch; increased from 201,222 to 202,148 TON
- Item 455.0115, Asphaltic Material PG64-22; increased from 3,691 to 3,793 TON
- Item 455.0120, Asphaltic Material PG64-28; increased from 2,006 to 2,050 TON
- Item 455.0605, Tack Coat; increased from 13,021 to 13,352 GAL
- Item 460.1103, HMA Pavement Type E-3; increased from 89,984 to 92,246 TON
- Item 460.2500.S, QMP HMA Pavement Nuclear Density; increased from 89.984 to 92,246 TON
- Item 460.3000, QMP HMA Mixture; increased from 89.984 to 92,246 TON
- Item 465.0315, Asphaltic Flumes; increased from 179 to 180 SY
- Item 465.0400, Asphaltic Shoulder Rumble Strip; decreased from 104,893 to 102,297 LF
- Item 601.0558, Concrete Curb & Gutter 6-Inch Mountable 36-Inch Type D; increased from 28,603 to 30,762 LF
- Item 611.0201, Manholes Type 1; decreased from 9 to 7 EACH
- Item 611.0210, Manholes Type 3; decreased from 13 to 10 EACH
- Item 611.0301, Inlets Type 1; decreased from 7 to 6 EACH
- Item 611.0303, Inlets Type 3; decreased from 126 to 61 EACH
- Item 611.0627, Inlet Covers Type HM; increased from 113 to 115 EACH
- Item 611.0636, Inlet Covers Type HM-S; increased from 8 to 19 EACH
- Item 611.8110, Adjusting Manhole Covers; increased from 15 to 17 EACH
- Item 611.8115, Adjusting Inlet Covers; increased from 68 to 83 EACH
- Item 620.0300, Concrete Median Sloped Nose; increased from 2,033 to 2,082 SF
- Item 625.0100, Topsoil; increased from 13,804 to 14,128 SY
- Item 627.0200, Mulching; increased from 246,500 to 249,731 SY
- Item 628.7005, Inlet Protection Type A; decreased from 67 to 54 EACH
- Item 628.7010, Inlet Protection Type B; decreased from 16 to 15 EACH

Item 628.7015, Inlet Protection Type C; increased from 67 to 149 EACH
Item 629.0210, Fertilizer Type B; increased from 170 to 172 CWT
Item 630.0120, Seeding Mixture No. 20; decreased from 3,050 to 3,015 LB
Item 630.0130, Seeding Mixture No. 30; increased from 2,400 to 2,453 LB
Item 633.0100, Delineator Posts Steel; increased from 276 to 291 EACH
Item 633.0500, Delineators; increased from 276 to 291 EACH
Item 634.0614, Posts Wood 4x6-Inch x 14-FT; decreased from 150 to 142 EACH
Item 634.0616, Posts Wood 4x6-Inch x 16-FT; increased from 161 to 193 EACH
Item 634.0618, Posts Wood 4x6-Inch x 18-FT; decreased from 66 to 59 EACH
Item 634.0620, Posts Wood 4x6-Inch x 20-FT; increased from 18 to 19 EACH
Item 634.0622, Posts Wood 4x6-Inch x 22-FT; decreased from 5 to 4 EACH
Item 637.0202, Signs Reflective Type II; increased from 4,866 to 5,071 SF
Item 643.0420, Traffic Control Barricades Type III; increased from 41,366 to 45,209 DAYS
Item 643.0705, Traffic Control Warning Lights Type A; increased from 16,840 to 19,402 DAYS
Item 643.0900, Traffic Control Signs; increased from 41,364 to 42,218 DAYS
Item 645.0120, Geotextile Fabric Type HR; increased from 986 to 1,019 SY
Item 646.0106, Pavement Marking Epoxy 4-Inch; increased from 179,200 to 181,800 LF
Item 646.0126, Pavement Marking Epoxy 8-Inch; increased from 9,590 to 11,270 LF
Item 646.0406, Pavement Marking Same Day Epoxy 4-Inch; increased from 32,600 to 33,400 LF
Item 647.0166, Pavement Marking Arrows Epoxy Type 2; increased from 35 to 43 EACH
Item 647.0356, Pavement Marking Word Epoxy; increased from 28 to 34 EACH
Item 647.0566, Pavement Marking Stop Line Epoxy 18-Inch; increased from 528 to 563 LF
Item 647.0726, Pavement Marking Diagonal Epoxy 12-Inch; increased from 445 to 467 LF
Item 650.5000, Construction Staking Base; increased from 37,784 to 38,799 LF
Item 650.5500, Construction Staking Curb Gutter and Curb & Gutter; increased from 30,371 to 32,530 LF
Item SPV.0165.03, Covering Signs Type II; increased from 446 to 595 SF
Item SPV.0170.01, Test Rolling; increased from 679 to 699 STA

The following bid item is added:

Item 606.0200 Riprap Medium

The following bid item is deleted:

Item 606.0100 Riprap Light

Attached, dated 6/28/2007, are revised Schedule of Items Pages 3 thru 5, 8 thru 19 and 23.

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,



Richard R. Filsinger, P.E
Proposal Development Supervisor

ADDENDUM

PROJECT 3180-10-70

Addendum No.	Article No.	Description	Date
1	53	Railroad Insurance & Coordination	6/29/2007
1	54	Plans	6/29/2007

Addendum No. 1

Special Provisions

53. Railroad Insurance & Coordination.

A Description

Comply with 107.17 of the standard specifications for all work affecting Canadian National property and any existing tracks.

A.1 Railroad Insurance Requirements

In addition to 107.26 of the standard specifications, provide railroad protective liability insurance coverage as specified in 107.17.3 of the standard specifications. Insurance is filed in the name of Canadian National.

Notify evidence of the required coverage, and duration to Jacqueline Moder, Canadian National, at 1625 Depot Street, Stevens Point, WI 54481.

A.2 Work by Railroad

The railroad will perform the work described in this section, except for work described in other special provisions and will be accomplished without cost to the contractor: None.

A.3 Names and Addresses of Railroad Representatives for Consultation and Coordination

Amend section 108.4 of the standard specifications to include the railroad in the distribution of the initial bar chart, and monthly schedule updates. The bar chart shall specifically show work involving coordination with the railroad.

Canadian National: Contact Terry Lee, Manager Public Works, 1625 Depot Street, Stevens Point, WI, 54481, telephone 715-345-2503, Fax 715-345-2507, email terry.lee21@cn.ca. For flagging arrangements contact, Tom Tucker, Administration Specialist, Administration Service Center, 2800 Livernois, Suite 330, Troy, MI 48083, telephone 248-740-6227, Fax 248-740-6550, email tomtucker@cn.ca.

Contact Terry Lee for consultation on railroad requirements during construction and to coordinate construction activities.

A.4 Temporary Grade Crossing

If a temporary grade crossing is desired, submit a written request to the railroad representative, named in A.3, several weeks prior to the time needed. Approval is subject to the railroad's discretion. The department has made no arrangements for a temporary grade crossing.

A.5 Train Operation

Approximately 35 through freight trains operate daily through the construction site. Through freight trains operate at up to 10-50 mph.

54. Plans.

The following 8 ½ x 11-Inch plan sheets are attached and made part of the plans for this proposal:


Revised plan sheets 4, 8, 9, 12, 68, 69, 70, 73, 74, 75, 76, 92, 107, 127, 129, 130, 131, 132, 133, 163, 164, 166, 167, 172, 185, 382 and 383, revised to include the new SE ramp at the CTH A interchange as well as the associated acceleration lanes along the outside of the bypass in each direction and the elimination of a left turning lane in the median of the bypass.

New plan sheets 67B, 67C, 76B, 107B and 185B, added to include the new SE ramp at the CTH A interchange as well as the associated acceleration lanes along the outside of the bypass in each direction and the elimination of a left turning lane in the median of the bypass.

New plan sheet 139A which includes the previously omitted detail for the type 9 monotube concrete bases that will be used at the STH 83 intersection.

Revised Miscellaneous Quantity sheets 207 thru 217 and 220 thru 247, revised to include the new SE ramp at the CTH A interchange as well as the associated acceleration lanes along the outside of the bypass in each direction and the elimination of a left turning lane in the median of the bypass.

New Miscellaneous Quantity sheets 213B, 214B, 216B, 243B and 244B, added to include the new SE ramp at the CTH A interchange as well as the associated acceleration lanes along the outside of the bypass in each direction and the elimination of a left turning lane in the median of the bypass.



ADD #1
REV SHT 4
6/29/2007

NOTES:


- ③ = 4-INCH TOPSOIL FERTILIZER MULCH & SEED
SEE EROSION CONTROL PLAN FOR SPECIAL CONSIDERATIONS.
- ④ = CONCRETE CURB & GUTTER 6-INCH MOUNTABLE 36-INCH TYPICAL
- ⑤ = BASE AGGREGATE DENSE 3/4-INCH ONLY NEEDS TO BE PLACED ON TOP 3-INCHES OF FINISHED SHOULDER.
ENTIRE SHOULDER IS ESTIMATED AS BASE AGGREGATE DENSE 3/4-INCH IN QUANTITIES.
- ⑥ = BASE AGGREGATE DENSE 3/4-INCH IS TO BE PLACED FLUSH WITH PAVED SURFACE.
- ⑦ = SEE CROSS-SECTIONS FOR SPECIFIC R/W DIMENSIONS.
- ⑧ = PLACED UNDER PREVIOUS PROJECT
- ⑨ = EMBANKMENT RECD BEHIND CURB & GUTTER

(A) = POINT REFERRED TO ON PROFILE @ R/L OR PGL
(B) = POINT REFERRED TO ON CROSS-SECTION @ R/L OR PGL

NOTE: ALL WORK COMPLETED UNDER PREVIOUS PROJECTS IS SHOWN AS DASHED LINES UNLESS OTHERWISE NOTED. ALL DISTURBED AREAS SHALL BE MULCHED, SEEDED AND FERTILIZED. THIS WORK WILL BE SHOWN AS UNDISTRIBUTED IN THE MISCELLANEOUS QUANTITIES.

ADD #1
REV SHT 8
6/29/2007

REVISION DATE: 6/15/07



PROJECT NO: 3180-10-70	HWY: BURLINGTON BYPASS	COUNTY: RACINE	TYPICAL SECTIONS	NOT - SCALE	SHEET 8
FILE NAME : S:\007\DOT_SE\04081\DESIGN\CONPLAN\Veriment Update\Upd-10-10-RSA-UPDATES-PLAN-SET\020303_t82.dgn			PLOT DATE : 6/13/2007		PLOT BY : mlkhalil.m
			PLOT NAME :		WISDOT/CADDS SHEET 42

NOTES:

(3) = 4-INCH TOPSOIL FERTILIZER MULCH & SEED
SEE EROSION CONTROL PLAN FOR SPECIAL CONSIDERATIONS.

(4) = CONCRETE CURB & GUTTER 6-INCH MOUNTABLE 36-INCH TYPE D

(5) = BASE AGGREGATE DENSE 3/4-INCH ONLY NEEDS TO BE
PLACED ON TOP 3-INCHES OF FINISHED SHOULDER.
ENTIRE SHOULDER IS ESTIMATED AS BASE AGGREGATE
DENSE 3/4-INCH IN QUANTITIES.

(6) = SEE CROSS-SECTIONS FOR SPECIFIC R/W DIMENSIONS.
FLUSH WITH PAVED SURFACE.

(14) = A 30' X 6' STRIP OF BASE AGGREGATE DENSE 1-1/4-INCH
IS CURRENTLY IN PLACE FROM STA 1334+00 TO STA
1372+00 AND FROM STA 1378+00 TO STRUCT B-51-02
ON THE WB ROADWAY.

(A) = POINT REFERRED TO ON
PROFILE @ R/L OR P/L




(B) = POINT REFERRED TO ON
CROSS-SECTION @ R/L OR P/L

NOTE: ALL WORK CURRENTLY IN PLACE IS SHOWN AS DASHED LINES
UNLESS OTHERWISE NOTED. ALL DISTURBED AREAS SHALL
BE MULCHED, SEEDED AND FERTILIZED. THIS WORK WILL
BE SHOWN AS UNDISTRICTED IN THE MISCELLANEOUS
QUANTITIES.

* = TO BE PLACED IN PROJECT 3180-10-70.

REVISION DATE: 6/15/07
REVISION NOTE: SHEET 020303.rts.dgn
HAS BEEN REPLACED BY SHEET
020303.b.rts.dgn

ADD #1
REV SHT 9
6/29/2007



PROJECT NO: 3180-10-70

HWY: BURLINGTON BYPASS

COUNTY: RACINE

PLOT DATE: 6/13/2007

PLOT BY: RHPOLL.M


NOT - SCALE

SHEET 9

E

TYPICAL SECTIONS SHOWN ON THIS SHEET REPRESENT STATION RANGES WHERE GRADING, GRANULAR MATERIAL & FINISHING OUTSIDE OF THE SUBGRADE SHOULDER POINTS WAS COMPLETED UNDER A PREVIOUS PROJECT.

REVISION DATE: 6/15/07





NOTES:


- ① = 4-INCH SALVAGED TOPSOIL FERTILIZER MULCH & SEED SEE EROSION CONTROL PLAN FOR SPECIAL CONSIDERATIONS.
- ② = 4-INCH TOPSOIL FERTILIZER MULCH & SEED SEE EROSION CONTROL PLAN FOR SPECIAL CONSIDERATIONS.
- ③ = CONCRETE CURB & GUTTER 6-INCH MOUNTABLE 36-INCH TYPE D
- ④ = BASE AGGREGATE DENSE 3/4-INCH ONLY NEEDS TO BE PLACED ON TOP 3-INCHES OF FINISHED SHOULDER. ENTIRE SHOULDER IS ESTIMATED AS BASE AGGREGATE DENSE 3/4-INCH IN QUANTITIES.
- ⑤ = BASE AGGREGATE DENSE 3/4-INCH IS TO BE PLACED FLUSH WITH PAVED SURFACE.
- ⑥ = SEE CROSS-SECTIONS FOR SPECIFIC R/W DIMENSIONS.
- ⑦ = PLACED UNDER PREVIOUS PROJECT
- ⑧ = POINT REFERRED TO ON PROFILE @ R/L OR P/L
- ⑨ = POINT REFERRED TO ON CROSS-SECTION @ R/L OR P/L
- ⑩ = A 30' X 6' STRIP OF BASE AGGREGATE DENSE 1-1/4-INCH WAS PLACED FROM STA 51+00 TO STA 58+25.74 ON THE OUTSIDE ROADWAY OF THE CTH A NW RAMP IN A PREVIOUS PROJECT

NOTE: ALL WORK COMPLETED UNDER PREVIOUS PROJECTS IS SHOWN AS DASHED LINES UNLESS OTHERWISE NOTED. ALL DISTURBED AREAS SHALL BE MULCHED, SEED AND FERTILIZED. THIS WORK WILL BE SHOWN AS UNDISTURBED IN THE MISCELLANEOUS QUANTITIES.

ADD #1
REV SHT 12
6/29/2007



TYPICAL FINISHED SECTION - CTH A RAMP



TYPICAL FINISHED SECTION
RIVER ROAD STA 49+62.51 - STA 52+00.00
OLD CTH A STA 48+00.00 - STA 50+00.00

PROJECT NO: 3180-10-70

HWY: BURLINGTON BYPASS

COUNTY: RACINE

TYPICAL SECTIONS

NOT TO SCALE


SHEET 12



POINTS TABLE				
POINT #	STATION	OFFSET	RADIUS	ROADWAY R/L
800	1357+44.16	49.00'		R/L BYPASS
801	1358+94.15	61.00'		R/L BYPASS
804	1358+55.36	-57.00'		R/L BYPASS
805	1330+52.63	-7590.37'	7591'	R/L BYPASS

BYPASS WB R/L SUPER ELEVATION TABLE			
STATION	ROADWAY	INSIDE LANE OUTSIDE LANE RATE %	REMARK
1370+50	EB BYPASS	-2.0%	END NC
1370+50	EB BYPASS	-2.0%	ZERO SE
1370+50	EB BYPASS	-2.0%	RC
1370+50	EB BYPASS	-2.0%	BEGIN FS
1370+50	EB BYPASS	-2.0%	END FS
1370+50	EB BYPASS	-2.0%	RC
1370+50	EB BYPASS	-2.0%	ZERO SUPER
1370+50	EB BYPASS	-2.0%	END NC

BYPASS EB R/L SUPER ELEVATION TABLE			
STATION	ROADWAY	INSIDE LANE OUTSIDE LANE RATE %	REMARK
1370+50	EB BYPASS	-2.0%	END NC
1370+50	EB BYPASS	-2.0%	ZERO SE
1370+50	EB BYPASS	-2.0%	RC
1370+50	EB BYPASS	-2.0%	BEGIN FS
1370+50	EB BYPASS	-2.0%	END FS
1370+50	EB BYPASS	-2.0%	RC
1370+50	EB BYPASS	-2.0%	ZERO SUPER
1370+50	EB BYPASS	-2.0%	END NC




**ADD #1
NEW SHT 67B
6/29/2007**

REVISION DATE: 6/25/07
REVISION NOTE: SHEETS 021338_P0.DGN, 021339_P0.DGN & 021340_P0.DGN
OF THE ORIGINAL PROJECT 3180-10-70 PLAN SET HAVE BEEN
ELIMINATED AND REPLACED WITH SHEETS 021361_P0.DGN,
021362_P0.DGN, 021363_P0.DGN, 021364_P0.DGN &
021365_P0.DGN.



CTH A SE RAMP R/L SUPER ELEVATION TABLE				
STATION	RT LANE	LT LANE	RATE %	REMARK
42+37.11	-2.0%	-2.0%	-2.0%	END NC
42+73.59	-2.0%	-2.0%	-2.0%	ZERO SE
43+10.07	-2.0%	-2.0%	-2.0%	RC
43+46.15	-2.0%	-2.0%	-2.0%	BEGIN SE
47+58.66	-4.0%	-4.0%	-4.0%	END SE
47+94.74	-2.0%	-2.0%	-2.0%	RC
48+31.22	-2.0%	-2.0%	-2.0%	ZERO SE
48+67.70	-2.0%	-2.0%	-2.0%	BEGIN NC

POINTS TABLE			
POINT #	STATION	OFFSET	RADIUS
802	1362+44.15	51.00'	R/L BYPASS
803	40+43.07	13.00'	R/L CTH A SE RAMP
807	1364+85.24	63.00'	R/L BYPASS
820	40+43.07	13.00'	R/L CTH A SE RAMP
821	40+43.07	13.00'	R/L CTH A SE RAMP
822	39+64.12	-64.96'	4.5'
823	39+66.39	6.5'	4.5'
824	40+70.76	-133.00'	100'
825	40+70.76	-133.00'	100'
826	40+70.76	-133.00'	122'
826	40+70.76	-133.00'	R/L CTH A SE RAMP




**ADD #1
NEW SHT 67C
2/29/2007**

REVISION DATE: 6/15/07
REVISION NOTE: SHEETS 021338.PDDGN, 021339.PDDGN & 021340.PDDGN OF THE ORIGINAL PROJECT 3180-10-70 PLAN SET HAVE BEEN ELIMINATED AND REPLACED WITH SHEETS 021361.PDDGN, 021362.PDDGN, 021363.PDDGN, 021364.PDDGN & 021364E.PDDGN.

REVISION DATE: 6/25/07
 REVISION NOTES: SHEETS 021338_P0.DGN, 021339_P0.DGN & 021340_P0.DGN
 HAVE BEEN ELIMINATED AND REPLACED WITH SHEETS 021362_P0.DGN, 021363_P0.DGN, 021364_P0.DGN & 021365_P0.DGN.

POINT #	STATION	OFFSET	RADIUS	ROADWAY R/L
805	1365+94.47	-70.93'		R/L BYPASS
806	1367+50.00	-69.00'		R/L BYPASS
807	1364+85.24	69.00'		R/L BYPASS
808	1365+85.24	61.00'		R/L BYPASS
809	1369+50.00	-69.00'		R/L BYPASS
817	1369+60.08	69.00'		R/L BYPASS

ADD #1
REV SHT 68
6/29/2007



STATION	ROADWAY	INSIDE LANE	OUTSIDE LANE	RATE %	REMARK
1330+60	WB BYPASS	-2.0%	-2.0%		END NC
1331+15	WB BYPASS	FLAT	-2.0%		ZERO SE
1331+67	WB BYPASS	+2.0%	-2.0%		RC
1331+70	WB BYPASS	+2.1%	-2.1%		BEGIN FS
1369+85	WB BYPASS	+2.1%	-2.1%		END FS
1369+88	WB BYPASS	+2.0%	-2.0%		RC
1370+40	WB BYPASS	FLAT	-2.0%		ZERO SUPER
1370+95	WB BYPASS	-2.0%	-2.0%		END NC

STATION	ROADWAY	INSIDE LANE	OUTSIDE LANE	RATE %	REMARK
1330+60	EB BYPASS	-2.0%	-2.0%		END NC
1331+15	EB BYPASS	FLAT	-2.0%		ZERO SE
1331+67	EB BYPASS	-2.0%	+2.0%		RC
1331+70	EB BYPASS	-2.1%	+2.1%		BEGIN FS
1369+85	EB BYPASS	-2.1%	+2.1%		END FS
1369+88	EB BYPASS	-2.0%	+2.0%		RC
1370+40	EB BYPASS	-2.0%	+2.0%		ZERO SUPER
1370+95	EB BYPASS	-2.0%	-2.0%		END NC

CONSTRUCT REJECT CURB AND GUTTER ON THE LEFT SIDE OF THE SB LANE FROM STATION 51+50 TO STATION 57+00, AND ON THE LEFT SIDE OF THE NB LANE FROM STATION 51+00 TO STATION 57+50. TRANSITION TO STANDARD CURB AND GUTTER IN 25 FEET AT THE BEGINNING AND END STATIONS

POINT #	STATION	POINTS TABLE		RADIUS	ROADWAY R/L
		OFFSET	R/L BYPASS		
809	1363+50.00	-65.00	R/L BYPASS		R/L BYPASS
810	1370+35.15	-66.00	R/L BYPASS		R/L BYPASS
811	1377+25.15	-67.00	R/L BYPASS		R/L BYPASS
812	1384+15.15	-68.00	R/L BYPASS		R/L BYPASS
813	1391+05.14	-69.00	R/L BYPASS		R/L BYPASS
814	1397+55.74	-70.00	R/L BYPASS		R/L BYPASS
815	1404+45.74	-71.00	R/L BYPASS		R/L BYPASS
816	1411+35.74	-72.00	R/L BYPASS		R/L BYPASS
817	1418+25.74	-73.00	R/L BYPASS		R/L BYPASS
818	1425+15.74	-74.00	R/L BYPASS		R/L BYPASS
819	1432+05.74	-75.00	R/L BYPASS		R/L BYPASS
820	1439+00.00	-76.00	R/L BYPASS		R/L BYPASS
821	1446+00.00	-77.00	R/L BYPASS		R/L BYPASS
822	1453+00.00	-78.00	R/L BYPASS		R/L BYPASS
823	1460+00.00	-79.00	R/L BYPASS		R/L BYPASS
824	1467+00.00	-80.00	R/L BYPASS		R/L BYPASS
825	1474+00.00	-81.00	R/L BYPASS		R/L BYPASS
826	1481+00.00	-82.00	R/L BYPASS		R/L BYPASS
827	1488+00.00	-83.00	R/L BYPASS		R/L BYPASS
828	1495+00.00	-84.00	R/L BYPASS		R/L BYPASS
829	1502+00.00	-85.00	R/L BYPASS		R/L BYPASS
830	1509+00.00	-86.00	R/L BYPASS		R/L BYPASS
831	1516+00.00	-87.00	R/L BYPASS		R/L BYPASS
832	1523+00.00	-88.00	R/L BYPASS		R/L BYPASS
833	1530+00.00	-89.00	R/L BYPASS		R/L BYPASS
834	1537+00.00	-90.00	R/L BYPASS		R/L BYPASS
835	1544+00.00	-91.00	R/L BYPASS		R/L BYPASS
836	1551+00.00	-92.00	R/L BYPASS		R/L BYPASS
837	1558+00.00	-93.00	R/L BYPASS		R/L BYPASS
838	1565+00.00	-94.00	R/L BYPASS		R/L BYPASS
839	1572+00.00	-95.00	R/L BYPASS		R/L BYPASS
840	1579+00.00	-96.00	R/L BYPASS		R/L BYPASS
841	1586+00.00	-97.00	R/L BYPASS		R/L BYPASS
842	1593+00.00	-98.00	R/L BYPASS		R/L BYPASS
843	1600+00.00	-99.00	R/L BYPASS		R/L BYPASS
844	1607+00.00	-100.00	R/L BYPASS		R/L BYPASS
845	1614+00.00	-101.00	R/L BYPASS		R/L BYPASS
846	1621+00.00	-102.00	R/L BYPASS		R/L BYPASS
847	1628+00.00	-103.00	R/L BYPASS		R/L BYPASS
848	1635+00.00	-104.00	R/L BYPASS		R/L BYPASS
849	1642+00.00	-105.00	R/L BYPASS		R/L BYPASS
850	1649+00.00	-106.00	R/L BYPASS		R/L BYPASS
851	1656+00.00	-107.00	R/L BYPASS		R/L BYPASS
852	1663+00.00	-108.00	R/L BYPASS		R/L BYPASS
853	1670+00.00	-109.00	R/L BYPASS		R/L BYPASS
854	1677+00.00	-110.00	R/L BYPASS		R/L BYPASS
855	1684+00.00	-111.00	R/L BYPASS		R/L BYPASS
856	1691+00.00	-112.00	R/L BYPASS		R/L BYPASS
857	1698+00.00	-113.00	R/L BYPASS		R/L BYPASS
858	1705+00.00	-114.00	R/L BYPASS		R/L BYPASS
859	1712+00.00	-115.00	R/L BYPASS		R/L BYPASS
860	1719+00.00	-116.00	R/L BYPASS		R/L BYPASS
861	1726+00.00	-117.00	R/L BYPASS		R/L BYPASS
862	1733+00.00	-118.00	R/L BYPASS		R/L BYPASS
863	1740+00.00	-119.00	R/L BYPASS		R/L BYPASS
864	1747+00.00	-120.00	R/L BYPASS		R/L BYPASS
865	1754+00.00	-121.00	R/L BYPASS		R/L BYPASS
866	1761+00.00	-122.00	R/L BYPASS		R/L BYPASS
867	1768+00.00	-123.00	R/L BYPASS		R/L BYPASS
868	1775+00.00	-124.00	R/L BYPASS		R/L BYPASS
869	1782+00.00	-125.00	R/L BYPASS		R/L BYPASS
870	1789+00.00	-126.00	R/L BYPASS		R/L BYPASS
871	1796+00.00	-127.00	R/L BYPASS		R/L BYPASS
872	1803+00.00	-128.00	R/L BYPASS		R/L BYPASS
873	1810+00.00	-129.00	R/L BYPASS		R/L BYPASS
874	1817+00.00	-130.00	R/L BYPASS		R/L BYPASS
875	1824+00.00	-131.00	R/L BYPASS		R/L BYPASS
876	1831+00.00	-132.00	R/L BYPASS		R/L BYPASS
877	1838+00.00	-133.00	R/L BYPASS		R/L BYPASS
878	1845+00.00	-134.00	R/L BYPASS		R/L BYPASS
879	1852+00.00	-135.00	R/L BYPASS		R/L BYPASS
880	1859+00.00	-136.00	R/L BYPASS		R/L BYPASS
881	1866+00.00	-137.00	R/L BYPASS		R/L BYPASS
882	1873+00.00	-138.00	R/L BYPASS		R/L BYPASS
883	1880+00.00	-139.00	R/L BYPASS		R/L BYPASS
884	1887+00.00	-140.00	R/L BYPASS		R/L BYPASS
885	1894+00.00	-141.00	R/L BYPASS		R/L BYPASS
886	1901+00.00	-142.00	R/L BYPASS		R/L BYPASS
887	1908+00.00	-143.00	R/L BYPASS		R/L BYPASS
888	1915+00.00	-144.00	R/L BYPASS		R/L BYPASS
889	1922+00.00	-145.00	R/L BYPASS		R/L BYPASS
890	1929+00.00	-146.00	R/L BYPASS		R/L BYPASS
891	1936+00.00	-147.00	R/L BYPASS		R/L BYPASS
892	1943+00.00	-148.00	R/L BYPASS		R/L BYPASS
893	1950+00.00	-149.00	R/L BYPASS		R/L BYPASS
894	1957+00.00	-150.00	R/L BYPASS		R/L BYPASS
895	1964+00.00	-151.00	R/L BYPASS		R/L BYPASS
896	1971+00.00	-152.00	R/L BYPASS		R/L BYPASS
897	1978+00.00	-153.00	R/L BYPASS		R/L BYPASS
898	1985+00.00	-154.00	R/L BYPASS		R/L BYPASS
899	1992+00.00	-155.00	R/L BYPASS		R/L BYPASS
900	1999+00.00	-156.00	R/L BYPASS		R/L BYPASS
901	2006+00.00	-157.00	R/L BYPASS		R/L BYPASS
902	2013+00.00	-158.00	R/L BYPASS		R/L BYPASS
903	2020+00.00	-159.00	R/L BYPASS		R/L BYPASS
904	2027+00.00	-160.00	R/L BYPASS		R/L BYPASS
905	2034+00.00	-161.00	R/L BYPASS		R/L BYPASS
906	2041+00.00	-162.00	R/L BYPASS		R/L BYPASS
907	2048+00.00	-163.00	R/L BYPASS		R/L BYPASS
908	2055+00.00	-164.00	R/L BYPASS		R/L BYPASS
909	2062+00.00	-165.00	R/L BYPASS		R/L BYPASS
910	2069+00.00	-166.00	R/L BYPASS		R/L BYPASS
911	2076+00.00	-167.00	R/L BYPASS		R/L BYPASS
912	2083+00.00	-168.00	R/L BYPASS		R/L BYPASS
913	2090+00.00	-169.00	R/L BYPASS		R/L BYPASS
914	2097+00.00	-170.00	R/L BYPASS		R/L BYPASS
915	2104+00.00	-171.00	R/L BYPASS		R/L BYPASS
916	2111+00.00	-172.00	R/L BYPASS		R/L BYPASS
917	2118+00.00	-173.00	R/L BYPASS		R/L BYPASS
918	2125+00.00	-174.00	R/L BYPASS		R/L BYPASS
919	2132+00.00	-175.00	R/L BYPASS		R/L BYPASS
920	2139+00.00	-176.00	R/L BYPASS		R/L BYPASS
921	2146+00.00	-177.00	R/L BYPASS		R/L BYPASS
922	2153+00.00	-178.00	R/L BYPASS		R/L BYPASS
923	2160+00.00	-179.00	R/L BYPASS		R/L BYPASS
924	2167+00.00	-180.00	R/L BYPASS		R/L BYPASS
925	2174+00.00	-181.00	R/L BYPASS		R/L BYPASS
926	2181+00.00	-182.00	R/L BYPASS		R/L BYPASS
927	2188+00.00	-183.00	R/L BYPASS		R/L BYPASS
928	2195+00.00	-184.00	R/L BYPASS		R/L BYPASS
929	2202+00.00	-185.00	R/L BYPASS		R/L BYPASS
930	2209+00.00	-186.00	R/L BYPASS		R/L BYPASS
931	2216+00.00	-187.00	R/L BYPASS		R/L BYPASS
932	2223+00.00	-188.00	R/L BYPASS		R/L BYPASS
933	2230+00.00	-189.00	R/L BYPASS		R/L BYPASS
934	2237+00.00	-190.00	R/L BYPASS		R/L BYPASS
935	2244+00.00	-191.00	R/L BYPASS		R/L BYPASS
936	2251+00.00	-192.00	R/L BYPASS		R/L BYPASS
937	2258+00.00	-193.00	R/L BYPASS		R/L BYPASS
938	2265+00.00	-194.00	R/L BYPASS		R/L BYPASS
939	2272+00.00	-195.00	R/L BYPASS		R/L BYPASS
940	2279+00.00	-196.00	R/L BYPASS		R/L BYPASS
941	2286+00.00	-197.00	R/L BYPASS		R/L BYPASS
942	2293+00.00	-198.00	R/L BYPASS		R/L BYPASS
943	2300+00.00	-199.00	R/L BYPASS		R/L BYPASS
944	2307+00.00	-200.00	R/L BYPASS		R/L BYPASS
945	2314+00.00	-201.00	R/L BYPASS		R/L BYPASS
946	2321+00.00	-202.00	R/L BYPASS		R/L BYPASS
947	2328+00.00	-203.00	R/L BYPASS		R/L BYPASS
948	2335+00.00	-204.00	R/L BYPASS		R/L BYPASS
949	2342+00.00	-205.00	R/L BYPASS		R/L BYPASS
950	2349+00.00	-206.00	R/L BYPASS		R/L BYPASS
951	2356+00.00	-207.00	R/L BYPASS		R/L BYPASS
952	2363+00.00	-208.00	R/L BYPASS		R/L BYPASS
953	2370+00.00	-209.00	R/L BYPASS		R/L BYPASS
954	2377+00.00	-210.00	R/L BYPASS		R/L BYPASS
955	2384+00.00	-211.00	R/L BYPASS		R/L BYPASS
956	2391+00.00	-212.00	R/L BYPASS		R/L BYPASS
957	2398+00.00	-213.00	R/L BYPASS		R/L BYPASS
958	2405+00.00	-214.00	R/L BYPASS		R/L BYPASS
959	2412+00.00	-215.00	R/L BYPASS		R/L BYPASS
960	2419+00.00	-216.00	R/L BYPASS		R/L BYPASS
961	2426+00.00	-217.00	R/L BYPASS		R/L BYPASS
962	2433+00.00	-218.00	R/L BYPASS		R/L BYPASS
963	2440+00.00	-219.00	R/L BYPASS		R/L BYPASS
964	2447+00.00	-220.00	R/L BYPASS		R/L BYPASS
965	2454+00.00	-221.00	R/L BYPASS		R/L BYPASS
966	2461+00.00	-222.00	R/L BYPASS		R/L BYPASS
967	2468+00.00	-223.00	R/L BYPASS		R/L BYPASS
968	2475+00.00	-224.00	R/L BYPASS		R/L BYPASS
969	2482+00.00	-225.00	R/L BYPASS		R/L BYPASS
970	2489+00.00	-226.00	R/L BYPASS		R/L BYPASS
971	2496+00.00	-227.00	R/L BYPASS		R/L BYPASS
972	2503+00.00	-228.00	R/L BYPASS		R/L BYPASS
973	2510+00.00	-229.00	R/L BYPASS		R/L BYPASS
974	2517+00.00	-230.00	R/L BYPASS		R/L BYPASS
975	2524+00.00	-231.00	R/L BYPASS		R/L BYPASS
976	2531+00.00	-232.00	R/L BYPASS		R/L BYPASS
977	2538+00.00	-233.00	R/L BYPASS		R/L BYPASS
978	2545+00.00	-234.00	R/L BYPASS		R/L BYPASS
979	2552+00.00	-235.00	R/L BYPASS		R/L BYPASS
980	2559+00.00	-236.00	R/L BYPASS		R/L BYPASS
981	2566+00.00	-237.00	R/L BYPASS		R/L BYPASS
982	2573+00.00	-238.00	R/L BYPASS		R/L BYPASS
983	2580+00.00	-239.00	R/L BYPASS		R/L BYPASS
984	2587+00.00	-240.00	R/L BYPASS		R/L BYPASS
985	2594+00.00	-241.00	R/L BYPASS		R/L BYPASS
986	2601+00.00	-242.00	R/L BYPASS		R/L BYPASS
987	2608+00.00	-243.00	R/L BYPASS		R/L BYPASS
988	2615+00.00	-244.00	R/L BYPASS		R/L BYPASS
989	2622+00.00	-245.00	R/L BYPASS		R/L BYPASS
990	2629+00.00	-246.00	R/L BYPASS		R/L BYPASS
991	2636+00.00	-247.00	R/L BYPASS		R/L BYPASS
992	2643+00.00	-248.00	R/L BYPASS		R/L BYPASS
993	2650+00.00	-249.00	R/L BYPASS		R/L BYPASS
994	2657+00.00	-250.00	R/L BYPASS		R/L BYPASS
995	2664+00.00	-251.00	R/L BYPASS		R/L BYPASS
996	2671+00.00	-252.00	R/L BYPASS		R/L BYPASS
997	2678+00.00	-253.00	R/L BYPASS		R/L BYPASS
998	2685+00.00	-254.00	R/L BYPASS		R/L BYPASS
999	2692+00.00	-255.00	R/L BYPASS		R/L BYPASS
1000	2699+00.00	-256.00	R/L BYPASS		R/L BYPASS

STATION	ROADWAY	BYPASS		EB R/L SUPER ELEVATION		TABLE	
		INSIDE LANE	OUTSIDE LANE	RATE %	RATE %	INSIDE LANE	OUTSIDE LANE
1330+60	EB BYPASS	-2.0%	-2.0%	-2.0%	-2.0%		
1331+5	EB BYPASS	-2.0%	-2.0%	-2.0%	-2.0%		
1331+67	EB BYPASS	-2.0%	-2.0%	-2.0%	-2.0%		
1331+70	EB BYPASS	-2.1%	-2.1%	-2.1%	-2.1%		
1369+85	EB BYPASS	-2.1%	-2.1%	-2.1%	-2.1%		
1369+88	EB BYPASS	-2.0%	-2.0%	-2.0%	-2.0%		
1370+40	EB BYPASS	-2.0%	-2.0%	-2.0%	-2.0%		

BYPASS		WB R/L	SUPER ELEVATION		TABLE	
STATION	ROADWAY	THIRME	THIRME	100	THIRME	REMARK
		DATE	DATE	DATE	DATE	
1330+60	WB R/PASS	-2.0%			END NC	
1331+45	WB R/PASS	FLAT	-2.0%		ZERO SE	
1331+67	WB R/PASS	FLAT	-2.0%		RC	
1331+70	WB R/PASS	+2.4%	-2.1%		BEGIN FS	
1336+85	WB R/PASS	+2.2%	-2.1%		END FS	
1336+88	WB R/PASS	+2.0%	-2.0%		RC	
1370+40	WB R/PASS	FLAT	-2.0%		ZERO SUPER	

INTERSECTION/PAVING DETAILS: MAINLINE/CTH A NW RAMP

FILE NAME : s:\DOT\DOT_SE\04081\DESIGN\DGN\PLAN\Amendment Updates\upd-10\10-RSA-UPDATES-PLAN-SET\021364_pd.dgn

PLOT SCALE : -

WISDOT/CADDs SHEET 42

**ADD #1
REV SHT 70
6/29/2007**

POINTS TABLE			
POINT #	STATION	OFFSET	RADIUS
819	1378+0.00	49.00'	R/L BYPASS




R/L STH 36/83 NB TO SB RAMP

STA 1381+20.49.00' LT
R/L BURLINGTON BYPASS =
STA 22+05.09
R/L STH 36/83 NB-SB RAMP

R/L BURLINGTON BYPASS

24" CIRC




REVISION DATE: 6/15/07
REVISION NOTES: SHEETS 021338 PD.DGN, 021339 PD.DGN & 021340 PD.DGN
OF THE ORIGINAL PROJECT 3180-10-70 PLAN SET
ELIMINATED AND REPLACED WITH SHEETS 021361 PD.DGN,
021362 PD.DGN, 021363 PD.DGN, 021364 PD.DGN &
021364B PD.DGN.



CTH A R/L SUPER ELEVATION TABLE			
STATION	DRIVING LANE		REMARK
	LT	RT	
55+56	-2.002	-2.002	END NORMAL CROWN
56+52	2.002	-2.002	REVERSE CROWN
56+58	3.502	-3.502	BEGIN FULL SUPER
67+03	3.502	-3.502	END FULL SUPER
67+39	2.002	-2.002	REVERSE CROWN
68+35	-2.002	-2.002	BEGIN NORMAL CROWN

POINTS TABLE			
POINT #	STATION	OFFSET	RADIUS
625	50+85.00	18.00'	R/L CTH A
626	50+85.00	-24.00'	R/L CTH A
627	51+93.37	-15.95'	R/L CTH A
628	51+93.37	13.66'	R/L CTH A
629	54+78.09	12.00'	R/L CTH A
630	54+78.09	-12.00'	R/L CTH A

STA 1368+39.15 R/L BURLINGTON BYPASS =
STA 53+31.92 R/L CTH A NW RAMP



REVISION DATE: 6/15/07
REVISION NOTE: FOR AREA WITHIN REVISION CLOUD, REFER
TO SHEETS 02383.PDDGN & 02384.PDDGN.

ADD #1
REV SHT 73
6/29/2007



REVISION DATES 6/15/07
 REVISION NOTES SHEET 021344.PDDOWN OF THE ORIGINAL PROJECT 3180-10-70
 PLAN SET HAS BEEN ELIMINATED AND REPLACED WITH
 THIS SHEET 021367.PDDOWN


POINTS TABLE				ROADWAY R/L	
POINT #	STATION	OFFSET	RADIUS	R/L CTH A SE RAMP	R/L CTH A SE RAMP
827	46+70.58	11.00'		R/L CTH A SE RAMP	R/L CTH A SE RAMP
828	47+83.00	2.28'		R/L CTH A SE RAMP	R/L CTH A SE RAMP
828B	48+24.00	-4.0'		R/L CTH A SE RAMP	R/L CTH A SE RAMP
829	43+35.33	-286.11'	311'	R/L CTH A SE RAMP	R/L CTH A SE RAMP
830	49+40.97	-5.04'	3'	R/L CTH A SE RAMP	R/L CTH A SE RAMP
831	49+23.97	-76.00'	75'	R/L CTH A SE RAMP	R/L CTH A SE RAMP
832	49+23.97	64.00'	75'	R/L CTH A SE RAMP	R/L CTH A SE RAMP
833	49+23.97	33.00'	50'	R/L CTH A SE RAMP	R/L CTH A SE RAMP
833B	49+23.97	84.49'		R/L CTH A SE RAMP	R/L CTH A SE RAMP
834	49+74.74	-10.93'		R/L CTH A SE RAMP	R/L CTH A SE RAMP
835	49+72.83	-10.93'		R/L CTH A SE RAMP	R/L CTH A SE RAMP
835B	48+97.89	-108.00'	75'	R/L CTH A SE RAMP	R/L CTH A SE RAMP
835C	48+97.89	-33.00'		R/L CTH A	R/L CTH A
836	56+28.21	12.00'		R/L CTH A	R/L CTH A
837	57+90.57	25.00'		R/L CTH A	R/L CTH A
838	56+60.20	15.23'		R/L CTH A	R/L CTH A

CTH A SE RAMP R/L SUPER ELEVATION TABLE					
STATION	WB LANE	SB LANE	RATE %	REMARK	
42+37.11	-2.0%	-2.0%		END NC	
42+73.59	-2.0%	-2.0%		FLAT	
43+10.07	-2.0%	-2.0%		BEGIN SE	
43+46.15	-4.0%	-4.0%		END SE	
47+58.66	-4.0%	-4.0%		RC	
47+94.74	-2.0%	-2.0%		FLAT	
48+31.22	-2.0%	-2.0%		BEGIN NC	
48+57.70	-2.0%	-2.0%			


ADD #1
REV SHT 74
6/29/2007

END CONSTRUCTION
 STA 52+25 R/L RIVER ROAD
 (SEE HMA WEDGE REMOVAL
 AND BRIDGES DETAIL)

R/L RIVER ROAD
 STA 6H0251R/L CTH A =
 STA 50+00.00 R/L CTH A SE RAMP =
 STA 49+62.51R/L RIVER ROAD



REVISION DATE: 6/15/07
REVISION NOTE: REVISIONS ON UPPER VIEW ONLY.




POINTS TABLE

POINT #	STATION	OFFSET	RADIUS	ROADWAY R/L
650	62+19.35	-94.00'	70'	R/L CTH A
651	62+19.35	-27.00'		R/L CTH A
652	64+19.32	-24.00'		R/L CTH A
653	64+19.32	0.00'		R/L CTH A
654	65+19.30	12.00'		R/L CTH A
655	64+50.00	18.00'		R/L CTH A
656	69+55.00	18.00'		R/L CTH A
657	70+25.00	15.00'		R/L CTH A
839	49+74.74	84.49'		R/L CTH A SE RAMP

END CONSTRUCTION
STA 70+25 R/L CTH A
(SEE HMA WEDGE REMOVAL
6 SIDE ROAD MATCH POINT
AND BRIDGES DETAIL)

CTH A R/L SUPER ELEVATION TABLE

STATION	DATE	REMARK
55+56	-2.00%	END NORMAL CROWN
56+52	2.00%	REVERSE CROWN
56+58	3.50%	BEGIN FULL SUPER
67+03	3.50%	END FULL SUPER
67+39	2.00%	REVERSE CROWN
68+35	-2.00%	BEGIN NORMAL CROWN





POINT #	STATION	OFFSET	RADIUS	ROADWAY R/L
660	51+95.85	322.32	322'	R/L CTH A NW RAMP
661	53+57.21	-110.00	300'	R/L CTH A NW RAMP
662	56+78.23	301.52	300'	R/L CTH A NW RAMP


STATION	DRIVING LANE	REMARK
50+32.00	-2.00%	END NORMAL CROWN
52+01.84	4.00%	BEGIN FULL SUPER
56+51.19	4.00%	END FULL SUPER
57+44.21	-2.00%	BEGIN NORMAL CROWN


STATION	DRIVING LANE	REMARK
50+32.00	-2.00%	END NORMAL CROWN
52+00.16	-4.00%	BEGIN FULL SUPER
56+18.81	-4.00%	END FULL SUPER
57+44.21	-2.00%	BEGIN NORMAL CROWN

REVISION DATE: 6/15/07
REVISION NOTE: NW RAMP LT TURN LANE ELIMINATED.

ADD #1
REV SHT 76
6/29/2007

CONSTRUCT REJECT CURB AND GUTTER ON THE LEFT SIDE OF THE SB LANE FROM STATION 51+50 TO STATION 57+00, AND ON THE LEFT SIDE OF THE NB LANE FROM STATION 51+00 TO STATION 57+50. TRANSITION TO STANDARD CURB AND GUTTER IN 25 FEET AT THE BEGINNING AND END STATIONS





ADD #1
NEW SHT 76B
6/29/2007


POINTS TABLE

POINT #	STATION	OFFSET	RADIUS	ROADWAY R/L
827	46+70.58	11.00'		R/L CTH A SE RAMP
828	47+83.00	2.28'		R/L CTH A SE RAMP
828B	48+24.00	-4.0'		R/L CTH A SE RAMP
829	43+35.33	-286.11'	311'	R/L CTH A SE RAMP

CTH A SE RAMP R/L SUPER ELEVATION TABLE

STATION	NB LANE RATE %	SB LANE RATE %	REMARK
42+37.41	-2.0%	-2.0%	END NC
42+73.59	-2.0%	-2.0%	FLAT
43+10.07	-2.0%	-2.0%	RC
43+46.45	-4.0%	-4.0%	BEGIN SE
47+58.66	-4.0%	-4.0%	END SE
47+94.74	-2.0%	-2.0%	RC
48+31.22	-2.0%	-2.0%	FLAT
48+67.70	-2.0%	-2.0%	BEGIN NC

REVISION DATE: 6/26/07
 REVISION NOTE: THIS IS A NEW SHEET REQUIRED FOR CONSTRUCTION OF CTH A SE RAMP



ADD #1
REV SHT 92
6/29/2007

REVISION DATE: 6/15/07
REVISION NOTE: SHEET 022009.ECDGN OF THE ORIGINAL PROJECT 3180-10-70 PLAN SET HAS BEEN ELIMINATED AND REPLACED WITH SHEET 022010.ECDGN

LEGEND

EROSION CONTROL ITEMS
SHOWN HALF TONED ARE
PLACED UNDER PREVIOUS PROJECT

- ### TEMPORARY DITCH CHECK
- WETLAND
- SOD
- EROSION MAT CLASS I, TYPE B
- EROSION MAT CLASS II, TYPE C
- RIPRAP MEDIUM
- ROCK OR STONE DITCH CHECK
- EROSION BAILE, BARRIER

- [A] INLET PROTECTION TYPE A FOR ENDWALL
- [X] INLET PROTECTION TYPE A
- [X] INLET PROTECTION TYPE B
- [X] INLET PROTECTION TYPE C
- [X] INLET PROTECTION TYPE C
- [X] SILT FENCE
- [X] DIRECTION OF FLOW

PROJECT NO: 3180-10-70

HWY: BURLINGTON BYPASS

COUNTY: RACINE

EROSION CONTROL: CTH A / BYPASS

SHEET 92

E

FILE NAME : s:\DOT\DOT_SE\04081\DESIGN\GN\PLAN\Amendment Update\Upd-10-10-RSA-UPDATES-PLAN-SET\022011.eco.dgn


PLOT DATE : 6/13/2007

PLOT BY : wally.w

PLOT NAME : -

WISDOT/CADD SHEET 42

ADD #1
REV SHT 107
6/29/2007



REVISION DATE: 6/15/07
REVISION NOTE: SHEET 022513-SS.DGN OF THE ORIGINAL PROJECT 3180-10-70
PLAN SET HAS BEEN REVISED AS SHOWN.

PROJECT NO: 3180-10-70

HWY: BURLINGTON BYPASS

COUNTY: RACINE

PROPOSED DRAINAGE SYSTEM: CTH A

SHEET 107

E

FILE NAME : e:\DOT\DOT_SE\04081\DESIGN\SS.DGN\PLAN\Amendment Update\Upd-10-10-RSA-UPDATES-PLAN-SET\022513-ss10.dgn


PLOT DATE : 6/13/2007

PLOT BY : wally.w

PLOT NAME : -

PLOT SCALE : -


WISDOT/CADD SHEET 42




ADD #1
NEW SHT 107B
6/29/2007

REVISION DATE: 6/15/07
 REVISION NOTE: THIS IS A NEW SHEET TO BE INSERTED
 PRIOR TO SHEET 022511.SSD.DGN


PROJECT NO: 3180-10-70	HWY: BURLINGTON BYPASS	COUNTY: RACINE	PROPOSED DRAINAGE SYSTEM: CTH A	SHEET 107B	E
FILE NAME : s:\ndot\dot_se\04081\DESIGN\DNPLAN\Amendment	Updates\Upd-10\10-RSA-UPDATES-PLAN-SET\022511_ss.dgn	PLOT DATE : 6/13/2007	PLOT BY : wally.w	PLOT SCALE : -	WISDOT/CADD SHEET 42



ADD #1
REV SHT 127
6/29/2007




REVISION DATE: 6/15/07
 REVISION NOTE: SHEET 023220, PS.DGN, OF THE ORIGINAL PROJECT 3180-10-70
 PLAN SET HAS BEEN REVISED AS SHOWN.



**ADD #1
 REV SHT 129
 6/29/2007**

PROJECT NO: 3180-10-70	HWY: BURLINGTON BYPASS	COUNTY: RACINE	PERMANENT SIGNING	SHEET 129	E
FILE NAME : s:\DOT\DOT_SE\04081\DESIGN\PS.DGN\PLAN\Amendment Updates\Upd-10\10-RSA-UPDATES-PLAN-SET\023220-ps10.dgn					
PLOT DATE : 6/13/2007			PLOT NAME : wally.w		
PLOT SCALE : -			WISDOT/CADD SHEET 42		


REVISION DATES: 6/15/07
REVISION NOTES: SHEETS 023221.PSDGN OF THE ORIGINAL PROJECT 3180-10-70
PLAN SET HAS BEEN REVISED AS SHOWN.



**ADD #1
REV SHT 130
6/29/2007**

PROJECT NO: 3180-10-70	HWY: BURLINGTON BYPASS	COUNTY: RACINE	PERMANENT SIGNING	SHEET 130	E
FILE NAME : s:\DOT\DOT_SE\04081\DESIGN\DOWN PLAN\Amendment Update\Upd-10-10-RSA-UPDATES-PLAN-SET\023221.psd0.dgn					WISDOT/CADD'S SHEET 42
PLOT DATE : 6/13/2007			PLOT NAME : -		
PLOT BY : wally.w			PLOT SCALE : -		

REVISION DATE: 6/25/07
 REVISION NOTE: SHEET'S 023222.DWG OF THE ORIGINAL PROJECT 3180-10-70
 PLAN SET HAS BEEN REVISED.





**ADD #1
 REV SHT 131
 6/29/2007**

PROJECT NO: 3180-10-70	HWY: BURLINGTON BYPASS	COUNTY: RACINE	PERMANENT SIGNING	SHEET 131	E
FILE NAME : s:\DOT\DOT_SE\04081\DESIGN\DWG\PLAN\Amendment Update\Upd-10-10-RSA-UPDATES-PLAN-SET\023222.psl0.dgn					WISDOT/CADD SHEET 42
PLOT DATE : 6/13/2007			PLOT NAME :		PLOT SCALE : -
PLOT BY : wally.w					

NOTES:**FOUNDATION**

1. ALL CONCRETE SHALL HAVE MINIMUM COMPRESSIVE STRENGTH OF 3500 PSI AT 28 DAYS. CONCRETE SHALL BE AIR ENTRAINED (8% ± 1%). CONCRETE SHALL HAVE MAXIMUM WATER/CEMENT RATIO OF 0.4. CONCRETE SHALL BE PLACED IN LAYERS NOT EXCEEDING 12" THICK. CONCRETE SHALL BE VIBRO-COMPACTED TO THE FULL DEPTH OF EACH LAYER. CONCRETE SHALL BE CURED WITH WET BURLAP OR OTHER MEANS FOR REINFORCED CONCRETE. ACI 308, LATEST EDITION. FOUNDATION INSTALLATION SHALL BE IN ACCORDANCE WITH ACI 308, STANDARD SPECIFICATIONS FOR THE CONSTRUCTION OF CAST-IN-PLACE CONCRETE, LATEST EDITION.
2. ALL CONCRETE REINFORCING STEEL SHALL CONFORM TO ASTM A615, GRADE 60. ALL REINFORCING DETAILS SHALL CONFORM TO "MANUAL OF STANDARD PRACTICE FOR DETAILING REINFORCED CONCRETE STRUCTURES", ACI 318, LATEST EDITION, UNLESS DETAIL OTHERWISE ON THE DRAWING.
3. MINIMUM CONCRETE COVER FOR REINFORCING SHALL BE:
 - A. CONCRETE CAST AGAINST AND EXPOSED TO EARTH: 3" MIN.
 - B. EXPOSED TO EARTH BUT PLACED IN FORMS: 2" MIN.
 - C. SURFACES EXPOSED TO WEATHER: 1.5" MIN.
4. SEE POLE DRAWING FOR ANCHOR BOLT QUANTITY, SIZE, LENGTH, BOLT CIRCLE & ORIENTATION.
5. DETAILING BOLT CIRCUMFERENCE = 100 P.C. 301 IS HORIZONTAL (IS AND WITHIN 32 DEGREES). WATER TABLE IS ASSUMED TO BE BELOW BOTTOM OF FOUNDATION.
6. FOUNDATION WAS DESIGNED USING ASSUMED GROUND SLOPE NOT EXCEEDING 7H:1V. CONTRACTOR SHALL CONTACT ENGINEER FOR ANY DETAIL THEREFROM PRIOR TO CONSTRUCTION.
7. FOUNDATION WAS DESIGNED USING THE FOLLOWING SERVICE LOADS:

MOMENT (MAX)	4439 FT-LBS
DEAD LOAD	2300 FT-LBS
WIND LOAD	1400 FT-LBS
SEISMIC	3000 FT-LBS



ADD #1
NEW SHT 139A
6/29/2007

CONCRETE BASE TYPE 9 MONOTUBE

PROJECT NO: 3180-10-70

HWY: BURLINGTON BYPASS

COUNTY: RACINE

TRAFFIC SIGNAL BASE DETAIL

SHEET: 139A



E

FILE NAME:

PLOT BY:

PLOT NAME:

PLOT SCALE: 1:1




PROJECT NO: 3180-10-70	HWY: BURLINGTON BYPASS	COUNTY: RACINE	PAVEMENT MARKING	SHEET 164	E
FILE NAME : s:\NDOT\DOT_SE\04081\DESIGN\DN\PLAN\Amendment Updates\Upd-10-10-RS-UPDATES-PLAN-SET\024517.pml0.dgn					WISDOT/CADD SHEET 42
PLOT DATE : 6/13/2007			PLOT NAME : -		
PLOT BY : wally.w			PLOT SCALE : -		


ADD #1
REV SHT 132
6/29/2007



REVISION DATE: 6/15/07
REVISION NOTE: SHEETS 023223-PS.DGN OF THE ORIGINAL PROJECT 3180-10-70
PLAN SET HAS BEEN REVISED




ADD #1
REV SHT 133
6/29/2007



REVISION DATE: 6/15/07
REVISION NOTE: SHEETS 023224.PSDJON OF THE ORIGINAL PROJECT 3180-10-70
PLAN SET HAS BEEN ELIMINATED AND REPLACED WITH SHEET 023224.PSDJON


PROJECT NO: 3180-10-70	HWY: BURLINGTON BYPASS	COUNTY: RACINE	PERMANENT SIGNING	SHEET 133	E
FILE NAME : s:\ndot\dot_se\04081\DESIGN\DGN\PLAN\Amendment Update\Upd-10-10-RS-UPDATES-PLAN-SET\023228.ps.dgn					WISDOT/CADD SHEET 42
PLOT DATE : 6/13/2007			PLOT NAME : wally.w		
PLOT SCALE : -					

2



**ADD #1
REV SHT 163
6/29/2007**

REVISION DATE: 6/15/07
REVISION NOTE: SHEET 024516.PMD.GN OF THE ORIGINAL PROJECT 3180-10-70 PLAN SET
HAS BEEN ELIMINATED AND REPLACED WITH 024516.PMD.GN.



PROJECT NO: 3180-10-70

HWY: BURLINGTON BYPASS

COUNTY: RACINE

PAVEMENT MARKING

SHEET 163

FILE NAME : s:\DOT\DOT_SE\04081\DESIGN\GN\PLAN\Amendment Update\Upd-10\10-RSA-UPDATES-PLAN-SET\024516.pml0.dgn

PLOT DATE : 6/13/2007


PLOT BY : wally.w

PLOT NAME :


WISDOT/CADD SHEET 42

REVISION DATE: 6/15/07
 REVISION NOTE: SHEET 024519.PMD.GEN OF THE ORIGINAL PROJECT 3180-10-70 PLAN SET
 HAS BEEN ELIMINATED AND REPLACED WITH 024519.PMD.GEN.

ADD #1
 REV SHT 166
 6/29/2007



PROJECT NO: 3180-10-70	HWY: BURLINGTON BYPASS	COUNTY: RACINE	DATE: 6/13/2007	PLOT BY: wally.w	PLOT NAME:	PLOT SCALE: -	SHEET 166	E
FILE NAME: s:\DOT\DOT_SE\04081\DESIGN\DOT\PLAN\Amendment Update\Upd-10-10-RS-UPDATES-PLAN-SET\024519.pml0.dgn								



REVISION DATE: 6/15/07
 REVISION NO: 024520-PMODN OF THE ORIGINAL PROJECT 3180-10-70
 PLAN SET HAS BEEN ELIMINATED AND REPLACED WITH SHEET
 024524-PMODN.

ADD #1
REV SHT 167
6/29/2007

PROJECT NO: 3180-10-70	HWY: BURLINGTON BYPASS	COUNTY: RACINE	PAVEMENT MARKING	SHEET 167
FILE NAME : e:\DOT\DOT_SE\04081\DESIGN\DWG\PLAN\Amendment Update\Upd-10\10-RSA-UPDATES-PLAN-SET\024524.pm.dgn		UPD DATE : 6/13/2007	PLOT BY : wally.w	WISDOT/CADD SHEET 42


WORK ZONE:
NO CONSTRUCTION ON STH 142 & CTH A.

TRAFFIC CONTROL:
TRAFFIC PATTERN TO REMAIN THE SAME AS PREVIOUS PROJECT.
ACCESS TO STH 142 NE RAMP, STH 142 SW RAMP, CTH A SE RAMP & CTH A NW RAMP
TO BE BARRICADED.

TRAFFIC CONTROL SIGNAGE SHOWN WILL BE IN PLACE FROM PROJECT 3180-08-70 AND
TO BE MAINTAINED UNTIL THE COMPLETION OF THIS PROJECT, AFTER WHICH IT IS TO
BE REMOVED.

ADDITIONAL PERMANENT SIGNAGE WAS PLACED UNDER PROJECT 3180-08-70 TO COMPLEMENT
THE TRAFFIC CONTROL SHOWN. THIS SIGNAGE WILL BE REMOVED AT THE COMPLETION OF
THIS PROJECT. SEE PERMANENT SIGNING DETAILS FOR SPECIFIC SIGNS.

REVISION DATE: 6/25/07
REVISION NOTE: SHEET'S 025001 TO 025001 OF THE ORIGINAL PROJECT 3180-10-70
PLAN SET HAS BEEN REVISED.



GENERAL NOTES:

THE EXACT NUMBER, LOCATION AND SPACING OF ALL SIGNS AND DEVICES SHALL BE ADJUSTED TO FIT FIELD CONDITIONS AS APPROVED BY THE ENGINEER.


ALL SIGNS ARE 48"X48" UNLESS OTHERWISE NOTED.

"W" SIGNS ARE THE SAME AS "W" SIGNS EXCEPT THE BACKGROUND IS ORANGE.

ANY SIGNS TEMPORARY OR EXISTING, WHICH CONFLICT WITH TRAFFIC CONTROL "IN USE" SHALL BE REMOVED OR COVERED AS NEEDED AND AS APPROVED BY THE ENGINEER.

CHANNELIZING DEVICES PLACED ADJACENT TO THE WORK AREA SHALL BE PULLED BACK FROM THE TRAVELLED LANE WHEN WORK IS NOT IN PROGRESS.

WARNING SIGNS THAT WILL BE IN PLACE LESS THAN SEVEN CONTINUOUS DAYS AND NIGHTS MAY BE MOUNTED ON PORTABLE SUPPORTS.



② = TYPE III BARRICADE ONLY
③ = TYPE III PERMANENT BARRICADE ONLY

= DRUM WITH WARNING LIGHT TYPE C

= DRUM

= CONCRETE BARRIER TEMPORARY PRECAST

= ARROW BOARD


= MESSAGE BOARD

= CRASH CUSHION

= PLACED UNDER PREVIOUS PROJECT



① = TYPE III BARRICADE WITH SIGN AND WARNING LIGHTS



③ = TYPE III PERMANENT BARRICADE WITH SIGN AND WARNING LIGHTS

LEGEND:

↑ / ↓ = TYPE III BARRICADE (8-FOOT EQUIVALENT) WITH / WITHOUT SIGN

Ⓐ = WARNING LIGHT, TYPE A (LOW INTENSITY FLASHING)

Ⓜ = POST MOUNTED SIGN

Ⓢ = SIGN ON PORTABLE SUPPORT

Ⓡ = FLEXIBLE TUBULAR MARKERS @ 25-FOOT SPACING

→ = DIRECTION OF TRAFFIC FLOW

**ADD #1
REV SHT 172
6/29/2007**

PROJECT NO: 3180-10-70

HWY: BURLINGTON BYPASS

COUNTY: RACINE

PLOT DATE : 6/13/2007


PLOT BY : wally.w

PLOT NAME : STH 142, CTH A


TRAFFIC CONTROL: STAGE 1 & 2

SHEET 172

E



REVISION DATE: 6/15/07
REVISION NOTE: SHEETS 027214_ADDGN IS THE NEW ADDITIONAL SHEET.



CURVE DATA R CTH A SE RAMP POND GRADING

CURVE AP0001

PI = 44+69.26
N = 178546.963
E = 52489.428
DELTA = 52°35'14.89"
D = 35°35'14.79"
TAN = 147.30'
R = 161.0'
PC = 43+21.96
PT = 45+60.56
DB = N 65°29'10.15" E
DA = N 19°25'30.75" W
SE TRANS = NA
LENGTH OF RUNOFF (L) = NA

CURVE DATA R CTH A SE RAMP

CURVE C101

PI = 46+06.50
N = 178867.425
E = 52489.428
DELTA = 52°35'14.89"
D = 35°35'14.79"
TAN = 147.30'
R = 161.0'
PC = 43+21.96
PT = 45+60.56
DB = N 65°29'10.15" E
DA = N 19°25'30.75" W
SE TRANS = NA
LENGTH OF RUNOFF (L) = 84'

**ADD #1
NEW SHT 185B
6/29/2007**

PROJECT NO: 3180-10-70

HWY: BURLINGTON BYPASS

COUNTY: RACINE

ALIGNMENT DIAGRAM

PLOT BY: wally.w

PLOT SCALE: -

SHEET 185B

FILE NAME: s:\DOT\DOT_SE\04081\DESIGN\GNPLAN\Amendment Update\Upd-10-10-RS-UPDATES-PLAN-SET\027214-add.dgn

PLOT DATE: 6/13/2007













PLOT NAME:

WISDOT/CADD SHEET 42

NOTES

1. All Signs Type II - Type H Reflective - reference WIS DOT Standard Specification for HIGHWAY and STRUCTURE CONSTRUCTION latest edition.
2. Color:
Background - Green
Message - White
3. Message Series - E

Revision Date:
06/15/07



1. All Signs Type II - Type H Reflective - reference WIS DOT Standard Specification for HIGHWAY and STRUCTURE CONSTRUCTION latest edition.

2. Color:

Background - Yellow except as noted
Message - Black

3. Message Series - D

Revision Date:
06/15/07

ADD #1
REV SHT 383
6/29/2007

Eliminated

P062

PROJECT NO: 3180-10-70	HWY: BURLINGTON BYPASS	COUNTY: RACINE	PERMANENT SIGNING	SHEET NO: 383
PLOT DATE : 20-APR-2007 11:03			PLOT BY : D11JPH	PLOT SCALE : 9.993750:1.000000
FILE NAME : C:\User\SP\p\o\acrs\tr_c2\25110407.dgn			WISDOT/CADD'S SHEET 42	

FILE NAME : C:\Users\Projects\tr_d2\2511c407.dgn

PROJECT NO: 3180-10-70

PROJECT NO: 3180-10-70

PROJECT NO: 3180-10-70	HWY: BURLINGTON BYPASS
------------------------	------------------------

PROJECT NO: 3180-10-70	HWY: BURLINGTON BYPASS	COUNTY: RACINE
------------------------	------------------------	----------------

PROJECT NO: 3180-10-70	HWY: BURLINGTON BYPASS	COUNTY: RACINE
------------------------	------------------------	----------------

PROJECT NO: 3180-10-70	HWY: BURLINGTON BYPASS	COUNTY: RACINE	PERMANENT SIGNING
------------------------	------------------------	----------------	-------------------

PROJECT NO: 3180-10-70	HWY: BURLINGTON BYPASS	COUNTY: RACINE	PERMANENT SIGNING
------------------------	------------------------	----------------	-------------------

PROJECT NO: 3180-10-70	HWY: BURLINGTON BYPASS	COUNTY: RACINE	PERMANENT SIGNING
------------------------	------------------------	----------------	-------------------

PROJECT NO: 3180-10-70	HWY: BURLINGTON BYPASS	COUNTY: RACINE	PERMANENT SIGNING	SHEET NO: 383
------------------------	------------------------	----------------	-------------------	---------------

* = DENOTES ADDITIONAL QUANTITIES CAN BE FOUND ELSEWHERE.

AGGREGATE ITEMS

ROADWAY	LOCATION	301.0100.S*		305.0110		305.0120*		311.0110		623.0200		624.0100	
		OMP BASE	AGGREGATE	BASE AGGREGATE	DENSE	BASE AGGREGATE	DENSE	BREAKER RUN	TON	DUST CONTROL	SURFACE	TREATMENT	WATER
		TON		3/4-INCH	TON	1-1/4-INCH	TON	TON		SY		MGAL	
BYPASS MAINLINE	STA 1123+04.94 TO B-51-93 EB	3975		486		3490							
	STA 1123+04.94 TO B-51-94 WB	5533		448		5086							
	STRUCT. B-51-93 TO 1184+00 EB	20481		6263		14279							
	STRUCT. B-51-94 TO 1184+00 WB	20806		6217		14590							
	STA 1184+00 TO STA 1277+67 EB	36424		11587		24837							
	STA 1277+67 TO EOTL STH 11 EB	3		3									
	STA 1184+00 TO STA 1277+86 WB	35538		11582		23956							
	STA 1277+86 TO EOTL STH 11 WB												
	STH 11 INTERSECTION												
	EOTL STH 11 TO STA 1280+59 EB	17229		5445		11784							
	STA 1280+59 TO STA 1226+00 EB	3		3									
	EOTL STH 11 TO STA 1280+10 WB												
	STA 1280+10 TO STA 1226+00 WB	17846		5350		12497							
	STA 1226+00 TO STA 1383+00 EB	22346		6892		15454							
BREVER ROAD	STA 1226+00 TO STA 1383+00 WB	22448		7085		15383							
	STA 1383+00 TO STRUCT. B-51-102	2797		858		1940							
	STA 1383+00 TO STRUCT. B-51-103	2570		766		1805							
	STRUCT. B-51-102 TO STA 1415+00	7430		1494		5937							
	STRUCT. B-51-103 TO STA 1408+00	7181		2115		5067							
	UNDISTRIBUTED							1000		229239			2226
	SUBTOTAL	222610		66574		156045		1000		229239			2226
	STA 340+80 TO EOTL BYPASS	7828		679		7149							
	EOTL BYPASS TO STA 369+34.51	10605				10605							
	STH 83 DRIVES	287		23		264							
	UNDISTRIBUTED									18587			187
	SUBTOTAL	18720		702		18018				18587			187
	STA 97+00 TO STRUCT. B-51-95	2141		560		1582							
	STRUCT. B-51-95 TO STA 118+00	3562		1206		2357							
	BREVER RD DRIVES	33		17		17							
STH 142	UNDISTRIBUTED									6199			57
	SUBTOTAL	5736		1763		3956				6199			57
	STA 101+08 TO STRUCT. B-51-92	106		106									
	STRUCT. B-51-92 TO STA 143+39	157		157									
	STH 142 DRIVES	28		28									
	EOTL STH 142 TO EOTL BYPASS	5796				5796							
	EOTL BYPASS TO EOTL STH 142	6035				6035							
	EOTL STH 142 TO STA 104+25	28		28									
	UNDISTRIBUTED									29532			122
	SUBTOTAL	12150		319		11831				29532			122
	STA 115+57.26 TO STA 126+94.78	211		211									
	STA 129+70.24 TO STA 168+39.91	532		532									
	STH 11 DRIVES	325		325									
	UNDISTRIBUTED									20769			11
STH 11	SUBTOTAL	1068		1068						20769			11

CONTINUED ON NEXT SHEET

NOTE: REVISED ITEMS SHOWN AS HIGHLIGHTED TEXT
REVISION DATE: 5/25/07

NOTE: ALL QUANTITIES ARE CATEGORY 0010 UNLESS OTHERWISE NOTED

* = DENOTES ADDITIONAL QUANTITIES CAN BE FOUND ELSEWHERE.

CONTINUED

AGGREGATE ITEMS

ROADWAY	LOCATION	301.0100.S*		305.0110		305.0120*		311.0110		623.0200		416.0170	
		QMP BASE	AGGREGATE	TON	3/4-INCH	BASE AGGREGATE DENSE	1-1/4-INCH	TON	BREAKER RUN	DUST CONTROL SURFACE TREATMENT SY	WATER	CONCRETE DRIVEWAY	7-INCH SY
KETTERHAGEN ROAD	STA 91+00 TO B-51-101	2584		594				1391					
	B-51-101 TO STA 110+75	2413		666				1747					
	MCCANN DRIVE	557		176				382					
	KETTERHAGEN DRIVES	43		18				26					
UNDISTRIBUTED										6311			
SUBTOTAL		5597		1454				4146		6311			
CTH A	STA 37+89 TO STRUCT. B-51-88	132		132									
	STRUCT. B-51-88 TO STA 70+25	110		110									
	CTH A DRIVES	234		234									
	EOTL CTH A TO STA 51+00												
CTH A NW RAMP	STA 51+00 TO EOTL BYPASS	2751		2751				2751					
	EOTL CTH A TO EOTL BYPASS	3926		3926				3926					
	CTH A SE RAMP												
	OLD CTH A	1		1									
RIVER ROAD	STA 48+00 TO EOTL CTH A	103		103									
	OLD CTH A DRIVES	11		11									
	EOTL CTH A TO STA 52+25												
	UNDISTRIBUTED									25741			
SUBTOTAL		7268		591				6677		25741			
STH 36/83 NB TO SB RAMP	STA 196+00 TO STA 203+68	1956		481				1475					
	UNDISTRIBUTED									2055			
SUBTOTAL		1956		481				1475		2055			
TOTALS		275105		72972				202148	1000	338434			

CONCRETE PAVEMENT APPROACH SLAB, PAVEMENT, AND SURFACE DRAINS

STATION	OFFSET LOCATION	TON	SY	DOL	DAYS	SY	CY
103+79.63 - 104+05.93	LT BREVER ROAD	9	9				17
103+79.63 - 104+05.93	RT BREVER ROAD	9	9				17
103+90.17 - 104+05.93	C/L BREVER ROAD	20	20			38	
106+18.33 - 106+34.00	LT BREVER ROAD	5	5	10	100.00	0.5	
106+18.33 - 106+34.00	RT BREVER ROAD	5	5	10	100.00	0.5	
106+18.33 - 106+34.00	C/L BREVER ROAD	20	20			38	
100+04.16 - 100+30.37	LT KETTERHAGEN ROAD	7	7				15
100+04.16 - 100+30.37	RT KETTERHAGEN ROAD	7	7				15
100+14.70 - 100+30.37	C/L KETTERHAGEN ROAD	20	20			38	
102+54.21 - 102+69.88	LT KETTERHAGEN ROAD	4	4	9	100.00	0.5	
102+54.21 - 102+69.88	RT KETTERHAGEN ROAD	4	4	9	100.00	0.5	
102+54.21 - 102+69.88	CL KETTERHAGEN ROAD	20	20			38	
TOTAL		130	130	38	400.00	2.0	64

NOTE: ALL QUANTITIES
ARE CATEGORY 0010
UNLESS OTHERWISE
NOTED

ADD #1
REV SHT 208
6/29/2007

ADD #1
REV SHT 209
6/29/2007

PAVEMENT ITEMS

ROADWAY	455.0115 ASPHALTIC MATERIAL PG64- 22	455.0120 ASPHALTIC MATERIAL PG64- 28	455.0605 TACK COAT	465.0105 ASPHALTIC SURFACE	460.1103 HMA PAVEMENT TYPE E-3	460.2000 INCENTIVE DENSITY HMA PAVEMENT	460.2500 S QMP HMA PAVEMENT NUCLEAR DENSITY	460.3000 QMP HMA MIXTURE	465.0120 ASPHALTIC SURFACE DRIVEWAYS AND FIELD ENTRANCES
	TON	TON	GAL	TON	TON	DOL	TON	TON	TON
BYPASS MAINLINE									
STA 1123+04.94 TO B-51-93 EB	54	24	165		1231	\$788	1231	1231	
STA 1123+04.94 TO B-51-94 WB	88	36	269		1952	\$1,249	1952	1952	
STRUCT. B-51-93 TO 1184+00 EB	245	110	751		5626	\$3,601	5626	5626	
STRUCT. B-51-94 TO 1184+00 WB	247	111	756		5668	\$3,628	5668	5668	
STA 1184+00 TO STA 1277+67 EB	523	239	1604		12090	\$7,738	12090	12090	
STA 1277+67 TO EOTL STH 11 EB	6	23	23		90	\$58	90	90	
STA 1184+00 TO STA 1277+86 WB	503	232	1541		11645	\$7,453	11645	11645	
STA 1277+86 TO EOTL STH 11 WB	6	21	21		82	\$52	82	82	
STH 11 INTERSECTION	4	14	14		54	\$35	54	54	
EOTL STH 11 TO STA 1280+59 EB	6	21	21		81	\$52	81	81	
STA 1280+59 TO STA 1226+00 EB	246	114	753		5692	\$3,643	5692	5692	
EOTL STH 11 TO STA 1280+00 WB	6	21	21		84	\$54	84	84	
STA 1280+00 TO STA 1226+00 WB	262	119	802		6026	\$3,857	6026	6026	
STA 1226+00 TO STA 1383+00 EB	334	151	1023		7672	\$4,911	7672	7672	
STA 1226+00 TO STA 1383+00 WB	334	151	1022		7672	\$4,910	7672	7672	
STA 1383+00 TO STRUCT. B-51-102	37	18	111		844	\$540	844	844	
STA 1383+00 TO STRUCT. B-51-103	42	19	129		952	\$609	952	952	
STRUCT. B-51-102 TO STA 1419+00	113	54	347		2640	\$1,690	2640	2640	
STRUCT. B-51-103 TO STA 1408+00	98	46	289		2267	\$1,451	2267	2267	
SUBTOTAL	3126	1452	9672		72368	\$46,319	72368	72368	
STA 340+80 TO EOTL BYPASS	117	47	356		2577	\$1,650	2577	2577	
EOTL BYPASS TO STA 369+34.51	173	69	530		3823	\$2,447	3823	3823	
STH 83 DRIVES			14						127
SUBTOTAL	290	116	900	52	6400	\$4,097	6400	6400	127
BREVER ROAD									
STA 97+00 TO STRUCT. B-51-95			52	597					
STRUCT. B-51-95 TO STA 118+00			83	950					
BREVER RD DRIVES			1						9
SUBTOTAL			136	1547					9
STA 101+08 TO STRUCT. B-51-92		43	166		668	\$428	668	668	
STRUCT. B-51-92 TO STA 143+39		58	229		918	\$588	918	918	
STH 142 DRIVES			11						41
EOTL STH 142 TO EOTL BYPASS	92	36	282		2020	\$1,293	2020	2020	
EOTL BYPASS TO EOTL STH 142	96	36	283		2102	\$1,346	2102	2102	
EOTL STH 142 TO STA 104+25		9	35		138	\$89	138	138	
SUBTOTAL	188	184	1016		5846	\$3,744	5846	5846	41
STA 115+57.26 TO STA 126+94.78		28	111		445	\$285	445	445	
STA 129+70.24 TO STA 168+39.91		96	378		1520	\$973	1520	1520	
STH 11 DRIVES			32						127
SUBTOTAL		124	521		1965	\$1,258	1965	1965	127

NOTE: REVISED ITEMS SHOWN AS HIGHLIGHTED TEXT
REVISION DATE: 5/25/07

CONTINUED ON NEXT PAGE

NOTE: ALL QUANTITIES ARE CATEGORY 0010 UNLESS OTHERWISE NOTED

PROJECT NUMBER: 3180-10-70	HWY: BURLINGTON BYPASS	COUNTY: RACINE	MISCELLANEOUS QUANTITIES	SHEET NO: 209	E
----------------------------	------------------------	----------------	--------------------------	---------------	---

NOTE: ALL QUANTITIES ARE CATEGORY 0010 UNLESS OTHERWISE NOTED

NOTE: REVISED ITEMS SHOWN AS HIGHLIGHTED TEXT

REVISION DATE: 5/25/07

CONTINUED

PAVEMENT ITEMS

ROADWAY	LOCATION	TON	TON	GAL	TACK COAT	ASPHALTIC SURFACE	HMA PAVEMENT TYPE E-3	DOL	QMP HMA PAVEMENT NUCLEAR DENSITY	QMP HMA MIXTURE	TON	TON
KETTERHAGEN ROAD	STA 91+00 TO B-51-101			66		756						
	B-51-101 TO STA 110+75			59		688						
	MCCANN DRIVE			15								
	KETTERHAGEN DRIVES			2								
	SUBTOTAL			142		1424		591	\$379	591	591	
CTH A	STA 37+69 TO STRUCT. B-51-98		38	147				686	\$439	686	686	
	STRUCT. B-51-98 TO STA 70+25		44	171								
CTH A NW RAMP	CTH A DRIVES			15								
CTH A NW RAMP	EOTL CTH A TO STA 51+00		5	18				71	\$46	71	71	
CTH A SE RAMP	STA 51+00 TO EOTL BYPASS	66	26	202				1448	\$927	1448	1448	
CTH A SE RAMP	EOTL CTH A TO EOTL BYPASS	95	37	290				2082	\$1,333	2082	2082	
OLD CTH A	STA 48+00 TO EOTL CTH A		4	13				51	\$33	51	51	
	OLD CTH A DRIVES			1								
RIVER ROAD	EOTL CTH A TO STA 52+25		6	24				96	\$61	96	96	
	SUBTOTAL	161	160	881			5025	\$3,218	5025	5025	5025	59
STH 36/68 NB TO SB RAMP	STA 196+00 TO STA 203+68		28	84			642	\$411	642	642	642	
	SUBTOTAL	28	14	84			642	\$411	642	642	642	
TOTAL S	TOTAL S	393	2050	13352		2971	92246	55047	93246	93246	93246	548

ASPHALTIC FLUMES

STATION	OFFSET	LOCATION	SY
343+85	RT	STH 83	20
345+00	LT	STH 83	19
351+69	LT	STH 83	41
93+37	LT	KETTERHAGEN RD	20
93+78	RT	KETTERHAGEN RD	20
1369+57	LT	BYPASS	20
1369+68	RT	BYPASS	20
201+43	LT	STH 36/83 NB-SB RAMP	20
TOTAL			180

ASPHALTIC SURFACE TEMPORARY

STATION -		STATION	LOCATION	LENGTH		WIDTH		DEPTH		BASE AGGREGATE		SURFACE TEMPORARY	
				FT	FT	IN	IN	PAV'T	IN	TON	TON	TON	TON
360+48	-	369+35	STH 83	932	20	3	6	794					
111+20	-	118+00	BREVER ROAD	680	20	3	6	579					
91+00	-	96+00	KETTERHAGEN RD	500	20	3	6	426					
107+50	-	110+75	KETTERHAGEN RD	325	20	3	6	277					
TOTAL										2076	277	981	

* ADDITIONAL QUANTITY LISTED ELSEWHERE.

PAVEMENT TIES

STATION	OFFSET	LOCATION	TIES EACH
B-51-95			
103+90.17 - 104+05.93	LT	BREVER ROAD	5
103+90.17 - 104+05.93	RT	BREVER ROAD	5
106+18.33 - 106+34.00	LT	BREVER ROAD	5
106+18.33 - 106+34.00	RT	BREVER ROAD	5
SUBTOTAL			20
B-51-101			
100+14.70 - 100+30.37	LT	KETTERHAGEN ROAD	5
100+14.70 - 100+30.37	RT	KETTERHAGEN ROAD	5
102+54.21 - 102+69.88	LT	KETTERHAGEN ROAD	5
102+54.21 - 102+69.88	RT	KETTERHAGEN ROAD	5
SUBTOTAL			20
TOTAL			40

PROJECT NUMBER: 3180-10-70

HWY: BURLINGTON BYPASS

COUNTY: RACINE

MISCELLANEOUS QUANTITIES

SHEET NO: 210

FILE NAME: S:\DOT\DOT_SE\04081\WORK FOR 09\ESTIMATES\04081_MISCOQUANT_09.ppt

ORIGINATOR: JUSTIN M. ARNDT

ORIG. DATE: MARCH 3, 2006

PLOTTED DATE: 6/13/2007 11:44 AM

ASPHALTIC SURFACE RUMBLE STRIP

465.0400
ASPHALTIC
SURFACE
RUMBLE STRIP
LF

STATION	SHOULDER	LOCATION	
1125+88 - 1129+44	MEDIAN	WB BYPASS	356
1126+79 - 1132+26	MEDIAN	EB BYPASS	549
1127+94 - 1132+56	OUTSIDE	EB BYPASS	466
1131+76 - 1132+18	MEDIAN	WB BYPASS	41
1142+96 - 1277+92	MEDIAN	WB BYPASS	13,472
1143+00 - 1175+01	OUTSIDE	WB BYPASS	3,193
1143+02 - 1165+80	OUTSIDE	EB BYPASS	2,286
1143+09 - 1270+95	MEDIAN	EB BYPASS	12,811
1174+03 - 1273+93	OUTSIDE	EB BYPASS	10,033
1183+23 - 1276+86	OUTSIDE	WB BYPASS	9,319
1273+71 - 1278+91	MEDIAN	EB BYPASS	520
1279+52 - 1284+74	MEDIAN	WB BYPASS	522
1280+54 - 1389+41	MEDIAN	EB BYPASS	10,887
1281+59 - 1357+44	OUTSIDE	EB BYPASS	7,585
1363+44 - 1364+63	OUTSIDE	EB BYPASS	119
1378+00 - 1389+67	OUTSIDE	EB BYPASS	1,167
1284+81 - 1358+55	OUTSIDE	WB BYPASS	7,374
1287+50 - 1389+09	MEDIAN	WB BYPASS	10,159
1368+02 - 1373+42	MEDIAN	EB BYPASS	DELETED-544
1372+23 - 1373+42	OUTSIDE	WB BYPASS	119
1373+61 - 1389+09	MEDIAN	WB BYPASS	DELETED-1550
1374+96 - 1389+41	MEDIAN	EB BYPASS	DELETED-1444
1379+09 - 1388+80	OUTSIDE	WB BYPASS	974
1393+85 - 1411+50	MEDIAN	WB BYPASS	1,762
1393+99 - 1423+00	MEDIAN	EB BYPASS	2,872
1394+70 - 1415+33	OUTSIDE	EB BYPASS	2,020
1398+35 - 1408+98	OUTSIDE	WB BYPASS	1,083
190+11 - 209+10	OUTSIDE	NB TO SB RAMP	1,794
195+85 - 203+70	MEDIAN	NB TO SB RAMP	814
TOTAL			102,297

MARKER POSTS CULVERT END FLEXIBLE

614.0620.S
MARKER POSTS
CULVERT END
FLEXIBLE
EACH

SEE DRAINAGE TABLE FOR LOCATIONS

43

TOTAL

43

PROJECT NUMBER: 3180-10-70

HWY: BURLINGTON BYPASS

COUNTY: RACINE

REVISION DATE: 5/25/07

NOTE: REVISED ITEMS SHOWN AS HIGHLIGHTED TEXT

MICELLANEOUS QUANTITIES

SCALE: N/A

SHEET NO: 211

E

FILE NAME: E:\DOT2648Burl946acdes\gndp\60\details\946General Notes.rpt

ORIG. DATE: JULY 10, 2003

PLOTTED DATE: 6/13/2007 11:44 AM

DRAINAGE TABLE QUANTITY SUMMARY

BID ITEM #	ITEM NAME	UNIT	QUANTITY
611.0201	Manholes Type 1	EACH	7
611.0210	Manholes Type 3	EACH	10
611.0301	Inlets Type 1	EACH	6
611.0303	Inlets Type 3	EACH	61
611.0305	Inlets Type 8	EACH	4
COVERS			
611.0530	Manhole Covers Type J	EACH	7
611.0606	Inlet Covers Type B	EACH	10
611.0609	Inlet Covers Type B-A	EACH	1
611.0624	Inlet Covers Type H	EACH	9
611.0627	Inlet Covers Type HM	EACH	115
611.0636	Inlet Covers Type HM-S	EACH	19
611.0639	Inlet Covers Type H-S	EACH	4
611.0642	Inlet Covers Type M-S	EACH	6
611.0654	Inlet Covers Type V	EACH	3
PIPES			
608.0312	Storm Sewer Pipe Reinforced Concrete Class III 12-Inch	LF	2040
608.0318	Storm Sewer Pipe Reinforced Concrete Class III 18-Inch	LF	405
608.0324	Storm Sewer Pipe Reinforced Concrete Class III 24-Inch	LF	720
520.0118	Culvert Pipe Class III 18-Inch	LF	58
520.0124	Culvert Pipe Class III 24-Inch	LF	410
608.0412	Storm Sewer Pipe Reinforced Concrete Class IV 12-Inch	LF	42
608.0424	Storm Sewer Pipe Reinforced Concrete Class IV 24-Inch	LF	168
520.0318	Culvert Pipe Class IV 18-Inch	LF	137
520.0524	Culvert Pipe Reinforced Concrete Class V 24-Inch	LF	176
520.0624	Culvert Pipe Class V 24-Inch	LF	423
612.0212	Pipe Underdrain Unperforated 12-Inch	LF	309
ENDWALLS			
522.1012	Apron Endwalls for Culvert Pipe Reinforced Concrete 12-Inch	EACH	9
522.1018	Apron Endwalls for Culvert Pipe Reinforced Concrete 18-Inch	EACH	2
522.1024	Apron Endwalls for Culvert Pipe Reinforced Concrete 24-Inch	EACH	6
SPV.0060.02	Apron Endwalls for Underdrain Reinforced Concrete 12-Inch	EACH	4
520.1018	Apron Endwalls for Culvert Pipe 18-Inch	EACH	6
520.1024	Apron Endwalls for Culvert Pipe 24-Inch	EACH	14
ADJUSTING			
611.8110	Adjusting Manhole Covers	EACH	8
611.8115	Adjusting Inlet Covers	EACH	83

ADD #1
REV SHT 211
6/29/2007

QUANTITY BREAKDOWN SHOWN ON NEXT 4 SHEETS. QUANTITIES SHOWN IN THE DRAINAGE TABLE QUANTITY SUMMARY

NOTE: ALL QUANTITIES ARE CATEGORY 0010 UNLESS OTHERWISE NOTED

REVISION DATE: 5/25/07

REVISION NOTE: ITEMS HIGHLIGHTED REFLECT PLAN REVISIONS.
LAYOUT OF SHEET WAS CHANGED TO ACCOMMODATE
NOTE UPDATES

TABLE NOTE LEGEND:

- A RIM ELEVATION = FLANGE ELEVATION
- B OFFSET TO CENTER OF STRUCTURE
- C TOP OF STRUCTURE ELEVATION = RIM ELEVATION. RIM SUPPRESS 2" INTO TOP OF STRUCTURE OR L.D.
- D TOP OF STRUCTURE ELEVATION BASED ON (RIM ELEVATION - 9" CASTING - 6" ADJUSTMENT RINGS).
- E TOP OF STRUCTURE ELEVATION BASED ON (RIM ELEVATION - 10" CASTING - 6" ADJUSTMENT RINGS).
- F TOP OF STRUCTURE ELEVATION BASED ON (RIM ELEVATION - 6" CASTING - 6" ADJUSTMENT RINGS).
- G STATION & OFFSET FOR ENDWALLS IS MEASURED AT END OF ENDWALL.
- H PIPE JOINT TIES ARE NOT A PAY ITEM. FOR INFORMATION ONLY.
- I SEE SDD FOR CONCRETE SURFACE DRAIN DROP INLET TYPE AT STRUCTURES.
- J EXISTING PIPE TO REMAIN
- STRUCTURE AND COVER PLATE PLACED IN PREVIOUS PROJECT. REMOVE COVER PLATE PLACE COVER AND RINGS
- K AND SET TO FINAL PLAN RIM ELEVATION. REMOVAL AND DISPOSAL OF COVER PLATE IS INCIDENTAL TO ADJUSTMENT OF INLET OR MANHOLE
- N INLET PLACED AS REVISION TO 3180-08-70 PROJECT DURING CONSTRUCTION.
- O MARKER POST CULVERT END FLEXIBLE REQUIRED.
- P STRUCTURE REQUIRES FLAT SLAB TOP.
- Q PROVIDE OPENING IN FLAT SLAB TOP TO ACCOMMODATE A SINGLE INLET COVER TYPE "MS".
- R 30" OPENING REQUIRED ON FLAT SLAB TOP TO ACCOMMODATE INLET COVER.
- S 20" OPENING REQUIRED ON FLAT SLAB TOP TO ACCOMMODATE INLET COVER.
- T DRAINAGE STRUCTURE NUMBER LISTED IN THE COLUMN TO THE LEFT REFERS TO THE ORIGINAL PROJECT# 3180-09-08&14-70 PLAN SET SUBSEQUENT UPDATE SHEETS.
- U DRAINAGE STRUCTURE NUMBER LISTED IN THE COLUMN TO THE LEFT REFERS TO THE PROJECT 3180-08-70 RSA UPDATE PLAN SET.
- V DRAINAGE STRUCTURE NUMBER LISTED IN THE COLUMN TO THE LEFT REFERS TO THE ORIGINAL PROJECT# 3180-09-70 PLAN SET SUBSEQUENT UPDATE SHEETS.

STRUCTURES

STRICT #	ROADWAY	LOCATION	STRICT TYPE - COVERTYPE	RIM ELEV OR ELEV	BOTT INV ELEV	TOP OF STRUCTURE ELEVATION	STRUCTURE DEPTH	INLET PROTECTION TYPE	NOTES
99.0	STH 83	370+96.50	3.8 RT	768.25	760.57	767.00	6.43	NA	B.D.J
100.0	STH 83	389+00.00	7.0 RT	768.79	761.63	767.54	5.91	A	B.D.
100.1	STH 83	369+00.00	25.0' LT	768.36	763.90	767.36	3.46	C	A.B.F.
100.2	STH 83	389+00.00	25.4' LT	768.36	764.10	767.36	3.26	C	A.B.F.
100.3	STH 83	389+00.00	24.6' RT	768.47	764.10	767.47	3.37	C	A.B.F.
100.4	STH 83	388+90.00	25.0' RT	768.47	764.30	767.47	3.17	C	A.B.F.
101.0	STH 83	389+00.00	.0' RT	769.24	762.20	767.99	5.79	A	B.D.
101.1	STH 83	367+75.00	47.7' LT	765.18	762.60	765.18	2.58	A	B.C.
101.2	STH 83	388+00.00	40.0' RT	766.55	763.50	766.55	3.05	A	B.C.
102.0	STH 83	388+15.49	44.0' LT	768.95	766.43	NA	NA	SEE EC	G.O.
102.1	STH 83	388+35.51	43.8' LT	768.95	766.53	NA	NA	SEE EC	G.O.
103.0	STH 83	386+50.00	49.7' LT	764.34	764.34	NA	NA	SEE EC	G.O.
103.1	STH 83	386+50.00	25.5' LT	769.21	764.47	768.21	3.74	C	A.B.F.
103.2	STH 83	386+40.00	25.5' LT	769.24	764.77	768.24	3.47	C	A.B.F.
103.3	STH 83	386+50.00	25.5' RT	769.21	764.81	768.21	3.40	C	A.B.F.
103.4	STH 83	386+40.00	25.5' RT	769.24	765.06	768.24	3.18	C	A.B.F.
104.0	STH 83	384+67.93	45.4' LT	765.41	765.41	NA	NA	SEE EC	G.O.
104.1	STH 83	384+00.00	39.8' LT	769.00	765.61	769.00	3.39	A	B.C.P.Q
104.2	STH 83	384+00.00	25.5' LT	770.14	765.65	769.14	3.49	C	A.B.F.
104.3	STH 83	383+90.00	25.5' LT	770.22	765.95	769.22	3.27	C	A.B.F.
104.4	STH 83	384+00.00	25.5' RT	770.14	765.92	769.14	3.22	C	A.B.F.
104.5	STH 83	383+90.00	25.5' RT	770.22	766.00	769.22	3.22	C	A.B.F.
104.6	STH 83	383+00.00	25.5' RT	771.22	767.05	770.22	3.17	C	A.B.F.
105.0	STH 83	357+78.26	3.7 RT	771.77	766.27	770.52	4.25	A	A.B.F.
105.1	STH 83	357+68.00	33.2 RT	772.67	768.44	771.67	3.23	C	A.B.F.
105.2	STH 83	388+00.00	35.5' LT	771.43	767.26	770.43	3.17	C	A.B.F.
105.3	STH 83	359+25.00	25.7 RT	772.67	767.72	771.67	3.95	C	A.B.F.
105.4	STH 83	389+50.00	25.5' RT	772.82	767.97	771.82	3.85	C	A.B.F.
105.5	STH 83	389+60.00	25.5' RT	772.47	768.17	771.47	3.30	C	A.B.F.
105.6	STH 83	380+00.00	25.5' RT	772.64	768.47	771.64	3.17	C	A.B.F.
106.0	STH 83	357+07.00	8.4 RT	771.41	765.86	770.41	4.55	C	A.B.F.P.R
106.1	STH 83	357+07.00	5.7 LT	771.39	766.31	770.39	4.08	C	A.B.F.
106.2	STH 83	357+10.00	35.5' LT	770.98	766.55	769.98	3.43	C	A.B.F.
106.3	STH 83	357+00.00	35.5' LT	770.97	766.75	769.97	3.22	C	A.B.F.
106.4	STH 83	357+22.40	4.1 RT	771.23	765.94	769.90	3.96	B	A.B.E.P.S
107.0	STH 83	355+50.00	8.5 RT	772.87	765.31	771.87	6.56	C	A.B.F.
107.1	STH 83	355+50.00	6.3' LT	772.42	766.20	771.42	5.22	C	A.B.F.
107.2	STH 83	355+50.00	35.5' LT	773.06	765.70	772.06	6.36	C	A.B.F.
107.3	STH 83	355+50.00	35.5' RT	772.58	766.78	771.58	4.80	C	A.B.F.
107.4	STH 83	356+07.00	35.5' RT	771.77	767.17	770.77	3.60	C	A.B.F.
107.5	STH 83	356+17.00	35.5' RT	771.77	767.37	770.77	3.40	C	A.B.F.
107.6	STH 83	356+60.00	35.5' RT	771.85	767.67	770.85	3.18	C	A.B.F.
108.0	STH 83	354+00.00	8.5 RT	777.34	764.46	776.34	11.88	C	A.B.F.P.S
108.1	STH 83	354+00.00	106.0' LT	763.92	763.92	NA	NA	SEE EC	G.O.
108.2	STH 83	354+00.00	47.5 RT	777.25	764.80	776.25	11.45	C	A.B.F.

CONT. ON NEXT PAGE

PROJECT NUMBER: 3180-10-70

HWY: BURLINGTON BYPASS

COUNTY: RACINE

MISCELLANEOUS QUANTITIES

SCALE: N/A

SHEET NO: 212

E

CONTINUED

STRUCTURES

STRICT #	ROADWAY	LOCATION	STRICT TYPE- COVER TYPE	PROP GRND ELEV OR RIM ELEVATION	BOTT INV ELEV	TOP OF STRUCTURE ELEVATION	STRUCTURE DEPTH	PROTECTION	INLET TYPE	NOTES
108.3	STH 83	354+00.00 83.0' RT	EW	764.97	764.97	NA	NA	SEE EC	G.O.	
109.0	BYPASS	1126+15.00 102.4' LT	MH1-HM	779.14	774.10	778.14	4.04	C	A.B.F.P.S.	
109.1	BYPASS	1126+77.70 96.3' LT	INL1-B	778.96	774.40	777.63	3.23	B	G.O.	
110.0	BYPASS	1126+07.00 58.5' LT	INL3-HM	780.10	773.77	779.10	5.33	C	A.B.F.	
110.1	BYPASS	1126+84.00 58.0' LT	MH3-B	779.65	757.16	778.32	21.16	B	A.B.F.P.S.	
111.0	BYPASS	1126+07.00 19.5' LT	MH1-HM	780.24	757.49	779.24	21.75	C	A.B.F.P.S.	
111.1	BYPASS	1126+91.10 12.9' LT	INL1-B	780.11	775.60	778.78	3.18	B	A.B.E.	
112.0	BYPASS	1126+19.03 7.8' LT	MH1-HM	780.91	774.83	779.91	5.08	C	A.B.F.P.S.	
112.1	BYPASS	1126+20.00 9.1' RT	INL3-HM	780.97	776.10	779.97	3.87	C	A.B.F.	
112.2	BYPASS	1126+20.00 16.4' RT	INL3-HM	780.71	776.35	779.71	3.36	C	A.B.F.	
112.3	BYPASS	1126+30.00 17.3' RT	INL3-HM	780.93	776.65	779.93	3.28	C	A.B.F.	
112.4	BYPASS	1126+80.00 19.5' RT	INL3-HM	781.96	777.75	780.96	3.21	C	A.B.F.	
113.0	BYPASS	1124+24.43 123.3' LT	EW	763.92	763.92	NA	NA	SEE EC	G.O.	
113.1	STH 83	354+56.30 44.6' LT	INL1-B	776.68	772.08	775.35	3.27	B	A.B.E.	
113.2	STH 83	354+50.00 39.1' LT	MH1-HM	777.29	772.80	776.29	3.49	C	A.B.F.P.S.	
113.3	BYPASS	1124+83.00 58.5' LT	INL3-HM	777.29	773.10	776.29	3.19	C	A.B.F.	
114.0	BYPASS	1123+80.50 135.9' RT	EW	762.93	762.63	NA	NA	SEE EC	G.O.	
115.0	BYPASS	1124+00.00 58.0' RT	MH3-B	775.29	769.00	773.96	4.96	B	A.B.E.P.S.	
115.1	BYPASS	1124+10.00 58.5' RT	INL3-HM	775.75	771.20	774.75	3.55	C	A.B.F.	
115.2	BYPASS	1125+21.50 62.6' RT	INL1-B	778.34	773.16	777.01	3.85	B	A.B.E.	
115.3	BYPASS	1124+08.50 64.9' RT	INL3-HM	775.65	771.40	774.65	3.25	C	A.B.F.	
115.4	BYPASS	1124+00.00 19.5' RT	INL3-HM	775.49	770.27	774.49	4.22	C	A.B.F.	
115.5	BYPASS	1124+00.00 7.5' RT	INL3-HM	775.56	770.61	774.56	3.95	C	A.B.F.	
115.6	BYPASS	1124+00.00 7.5' LT	INL3-HM	775.32	771.01	774.32	3.31	C	A.B.F.	
115.7	BYPASS	1124+00.00 19.5' LT	INL3-HM	775.52	771.35	774.52	3.17	C	A.B.F.	
116.0	STH 83	351+00.93 133.3' RT	EW	765.36	765.36	NA	NA	SEE EC	G.O.	
116.1	STH 83	351+50.00 46.6' RT	INL3-HM	779.79	774.90	778.79	3.89	C	A.B.F.	
116.2	STH 83	351+51.00 39.1' RT	INL3-HM	779.31	775.10	778.31	3.21	C	A.B.F.	
117.0	STH 83	351+50.00 108.6' RT	EW	761.50	761.50	NA	NA	SEE EC	G.O.	
117.1	STH 83	351+50.00 39.4' RT	INL3-HM	776.38	771.00	775.38	4.38	C	A.B.F.	
117.2	STH 83	351+50.00 1.5' LT	INL3-HM	777.48	772.70	776.48	3.78	C	A.B.F.	
117.3	STH 83	351+50.00 8.7' LT	INL3-HM	777.18	772.90	776.18	3.28	C	A.B.F.	
117.4	STH 83	351+50.00 40.7' LT	INL3-HM	778.00	773.80	777.00	3.20	C	A.B.F.	
118.0	STH 83	348+81.12 89.8' RT	EW	759.96	759.96	NA	NA	SEE EC	G.O.	
118.1	STH 83	348+85.00 29.5' RT	INL3-HM	771.24	766.90	770.24	3.34	C	A.B.F.	
118.2	STH 83	348+95.60 30.1' RT	INL3-HM	771.53	767.30	770.53	3.23	C	A.B.F.	
118.3	STH 83	348+86.00 2.6' RT	INL3-HM	772.67	768.20	771.67	3.47	C	A.B.F.	
118.4	STH 83	348+86.00 1.1' LT	INL3-HM	772.68	768.40	771.68	3.28	C	A.B.F.	
118.5	STH 83	348+96.00 1.6' LT	INL3-HM	772.97	768.80	771.97	3.17	C	A.B.F.	
118.6	STH 83	348+85.20 28.1' LT	INL3-HM	774.10	769.90	773.10	3.20	C	A.B.F.	
119.0	STH 83	350+43.56 96.4' LT	EW	773.67	764.16	NA	NA	SEE EC	G.O.	
119.1	STH 83	349+75.86 71.1' LT	EW	773.67	768.71	NA	NA	SEE EC	G.O.	
120.0	STH 83	347+28.20 79.4' RT	EW	757.31	757.31	NA	NA	SEE EC	G.O.	
120.1	STH 83	347+28.20 25.5' RT	INL3-HM	767.68	762.19	766.68	4.49	C	A.B.F.	
120.2	STH 83	347+38.20 25.5' RT	INL3-HM	767.90	762.39	766.90	4.51	C	A.B.F.	

CONT. ON NEXT PAGE

QUANTITIES SHOWN IN THE DRAINAGE TABLE QUANTITY SUMMARY

NOTE: ALL QUANTITIES ARE CATEGORY 0010 UNLESS OTHERWISE NOTED

REVISION DATE: 5/25/07

REVISION NOTE: ITEMS HIGHLIGHTED REFLECT PLAN REVISIONS.
LAYOUT OF SHEET WAS CHANGED TO ACCOMMODATE
NOTE UPDATES

TABLE NOTE LEGEND:

- A RIM ELEVATION = FLANGE ELEVATION
B OFFSET TO CENTER OF STRUCTURE
C TOP OF STRUCTURE ELEVATION = RIM ELEVATION. RIM SUPPRESS 2" INTO TOP OF STRUCTURE OR LID.
D TOP OF STRUCTURE ELEVATION BASED ON RIM ELEVATION - 9" CASTING - 6" ADJUSTMENT RINGS).
E TOP OF STRUCTURE ELEVATION BASED ON RIM ELEVATION - 10" CASTING - 6" ADJUSTMENT RINGS).
F TOP OF STRUCTURE ELEVATION BASED ON RIM ELEVATION - 6" CASTING - 6" ADJUSTMENT RINGS).
G STATION & OFFSET FOR ENDWALLS IS MEASURED AT END OF ENDWALL.
H PIPE JOINTS ARE NOT A PAY ITEM. FOR INFORMATION ONLY.
I SEE SDD FOR CONCRETE SURFACE DRAIN DROP INLET TYPE AT STRUCTURES.
J EXISTING PIPE TO REMAIN
K STRUCTURE AND COVER PLATE PLACED IN PREVIOUS PROJECT. REMOVE COVER PLATE/PLACE COVER AND RINGS AND SET TO FINAL PLAN RIM ELEVATION. REMOVAL AND DISPOSAL OF COVER PLATE IS INCIDENTAL TO ADJUSTMENT OF INLET OR MANHOLE.
N INLET PLACED AS REVISION TO 3180-08-70 PROJECT DURING CONSTRUCTION.
O MARKER POST CULVERT END FLEXIBLE REQUIRED.
P STRUCTURE REQUIRES FLAT SLAB TOP.
Q PROVIDE OPENING IN FLAT SLAB TOP TO ACCOMMODATE A SINGLE INLET COVER TYPE "MS".
R 30" OPENING REQUIRED ON FLAT SLAB TOP TO A COMMODATE INLET COVER.
S 20" OPENING REQUIRED ON FLAT SLAB TOP TO A COMMODATE INLET COVER.
T DRAINAGE STRUCTURE NUMBER LISTED IN THE COLUMN TO THE LEFT REFERS TO THE ORIGINAL PROJECT# 3180-08&141-70 PLAN SET SUBSEQUENT UPDATE SHEETS.
U DRAINAGE STRUCTURE NUMBER LISTED IN THE COLUMN TO THE LEFT REFERS TO THE PROJECT 3180-08-70 RSA UPDATE PLAN SET.
V DRAINAGE STRUCTURE NUMBER LISTED IN THE COLUMN TO THE LEFT REFERS TO THE ORIGINAL PROJECT# 3180-09-70 PLAN SET SUBSEQUENT UPDATE SHEETS.

PROJECT NUMBER: 3180-10-70

HWY: BURLINGTON BYPASS

COUNTY: RACINE

MISCELLANEOUS QUANTITIES

SCALE: N/A

SHEET NO: 213

E

CONTINUED

STRUCTURES

STRUCT #	ROADWAY	LOCATION	STRUCT TYPE - COVER TYPE	PROP GRND		TOP OF STRUCTURE ELEVATION	STRUCTURE DEPTH	INLET PROTECTION TYPE	NOTES
				RIM ELEV OR	BOTT INV ELEV				
120.3	STH 83	346+88.00	25.0' RT	766.97	762.47	765.64	3.17	B	A.B.F.
121.0	STH 83	346+30.82	81.2' RT	761.53	755.95	NA	NA	SEE EC	G.O.
121.1	STH 83	347+12.03	77.2' RT	761.53	757.11	NA	NA	SEE EC	G.O.
122.0	STH 83	346+00.00	71.2' RT	755.65	755.65	NA	NA	SEE EC	G.O.
122.1	STH 83	346+00.00	25.5' RT	766.14	760.70	765.14	4.44	C	A.B.F.
122.2	STH 83	345+90.00	25.5' RT	766.11	761.90	765.11	3.21	C	A.B.F.
122.3	STH 83	343+59.35	44.7' RT	766.03	762.79	NA	NA	SEE EC	G.O.
122.4	STH 83	343+11.29	44.7' RT	766.03	763.03	NA	NA	SEE EC	G.O.
123.0	BREVER ROAD	99+98.00	72.9' LT	769.27	750.94	NA	NA	SEE EC	G.O.
123.1	BREVER ROAD	99+98.00	68.4' RT	769.27	752.42	NA	NA	SEE EC	G.O.
124.0	BREVER ROAD	103+84.62	16.1' LT	778.69	774.35	777.36	3.01	B	B.E.I.
124.1	BREVER ROAD	103+84.62	80.6' LT	755.71	755.71	NA	NA	SEE EC	G.O.
125.0	BREVER ROAD	103+84.62	16.1' RT	778.69	774.35	777.36	3.01	B	B.E.I.
125.1	BREVER ROAD	103+84.62	87.4' RT	753.00	753.00	NA	NA	SEE EC	G.O.
126.0	BREVER ROAD	104+22.53	75.0' LT	765.31	751.67	NA	NA	SEE EC	G.O.
126.1	BREVER ROAD	104+29.14	71.3' RT	765.31	752.60	NA	NA	SEE EC	G.O.
127.0	BREVER ROAD	106+18.33	97.6' LT	781.76	750.10	NA	NA	SEE EC	G.O.
127.1	BREVER ROAD	107+00.00	98.2' RT	781.76	750.52	NA	NA	SEE EC	G.O.
128.0	BREVER ROAD	111+37.60	82.1' LT	770.71	757.84	NA	NA	SEE EC	G.O.
128.1	BREVER ROAD	112+41.11	67.6' LT	770.71	759.18	NA	NA	SEE EC	G.O.
129.0	BREVER ROAD	117+48.92	25.9' RT	767.14	764.91	NA	NA	SEE EC	G.O.
129.1	BREVER ROAD	117+69.01	25.9' RT	767.14	765.25	NA	NA	SEE EC	G.O.
130.0	KETTERHAGEN ROAD	91+52.00	20.5' LT	830.10	824.80	828.85	4.05	A	B.D.
130.1	KETTERHAGEN ROAD	91+25.00	20.5' LT	829.14	826.00	829.14	3.14	A	B.C.
130.2	KETTERHAGEN ROAD	91+45.00	21.5' RT	829.45	826.40	829.45	3.05	A	B.C.
130.3	KETTERHAGEN ROAD	93+62.79	42.5' LT	815.06	815.06	NA	NA	SEE EC	G.O.
131.0	PRIVATE DRIVE	12+00.00	50.0' RT	807.28	794.00	NA	NA	SEE EC	G.O.
131.1	PRIVATE DRIVE	12+00.00	56.8' RT	807.28	794.94	NA	NA	SEE EC	G.O.
132.0	KETTERHAGEN ROAD	99+00.00	113.7' LT	822.13	791.35	NA	NA	SEE EC	G.O.
132.1	KETTERHAGEN ROAD	99+00.00	109.4' RT	822.13	792.50	NA	NA	SEE EC	G.O.
133.0	KETTERHAGEN ROAD	102+43.64	95.0' LT	823.84	790.66	NA	NA	SEE EC	G.O.
133.1	KETTERHAGEN ROAD	102+43.64	93.0' RT	823.84	791.60	NA	NA	SEE EC	G.O.
134.0	BYPASS	1128+00.00	102.6' RT	775.00	775.00	NA	NA	SEE EC	G.O.
134.1	BYPASS	1128+00.00	19.5' RT	784.59	780.00	783.59	3.59	C	A.B.F.
134.2	BYPASS	1128+00.00	19.5' RT	784.82	780.30	783.82	3.52	C	A.B.F.
134.3	BYPASS	1128+00.00	7.5' LT	784.93	780.64	783.93	3.29	C	A.B.F.
135.0	BREVER ROAD	115+42.30	34.4' RT	765.82	763.56	NA	NA	SEE EC	G.O.
135.1	BREVER ROAD	115+77.66	34.4' RT	765.82	764.18	NA	NA	SEE EC	G.O.
136.0	KETTERHAGEN ROAD	101+09.17	111.6' LT	791.94	791.94	NA	NA	SEE EC	G.O.
136.1	KETTERHAGEN ROAD	101+09.17	15.1' LT	822.22	817.88	820.89	3.01	B	B.E.I.
137.0	KETTERHAGEN ROAD	101+09.17	105.4' RT	794.00	794.00	NA	NA	SEE EC	G.O.
137.1	KETTERHAGEN ROAD	101+09.17	15.1' RT	822.22	817.71	820.89	3.18	B	B.E.I.

QUANTITIES SHOWN IN THE DRAINAGE TABLE QUANTITY SUMMARY

NOTE: ALL QUANTITIES ARE CATEGORY 0010 UNLESS OTHERWISE NOTED

REVISION DATE: 5/25/07

REVISION NOTE: ITEMS HIGHLIGHTED REFLECT PLAN REVISIONS.
LAYOUT OF SHEET WAS CHANGED TO ACCOMMODATE
NOTE UPDATES

TABLE NOTE LEGEND:

- A RIM ELEVATION = FINISH ELEVATION
B OFFSET TO CENTER OF STRUCTURE
C TOP OF STRUCTURE ELEVATION = RIM ELEVATION RIM SUPPRESS 2" INTO TOP OF STRUCTURE OR LID.
D TOP OF STRUCTURE ELEVATION BASED ON (RIM ELEVATION - 9" CASTING - 6" ADJUSTMENT RINGS).
E TOP OF STRUCTURE ELEVATION BASED ON (RIM ELEVATION - 10" CASTING - 6" ADJUSTMENT RINGS).
F TOP OF STRUCTURE ELEVATION BASED ON (RIM ELEVATION - 6" CASTING - 6" ADJUSTMENT RINGS).
G STATION & OFFSET FOR ENDWALLS IS MEASURED AT END OF ENDWALL.
H PIPE JOINT TIES ARE NOT A PAY ITEM FOR INFORMATION ONLY.
I SEE SDD FOR CONCRETE SURFACE DRAIN DROP INLET TYPE AT STRUCTURES.
J EXISTING PIPE TO REMAIN
K STRUCTURE AND COVER PLATE PLACED IN PREVIOUS PROJECT. REMOVE COVER PLATE PLACE COVER AND RINGS AND SET TO FINAL PLAN RIM ELEVATION. REMOVAL AND DISPOSAL OF COVER PLATE IS INCIDENTAL TO ADJUSTMENT OF INLET OR MANHOLE
N INLET PLACED AS REVISION TO 3180-08-70 PROJECT DURING CONSTRUCTION.
O MARKER POST CULVERT END FLEXIBLE REQUIRED.
P STRUCTURE REQUIRES FLAT SLAB TOP.
Q PROVIDE OPENING IN FLAT SLAB TOP TO ACCOMMODATE A SINGLE INLET COVER TYPE "MS".
R 30" OPENING REQUIRED ON FLAT SLAB TOP TO ACCOMMODATE INLET COVER.
S 20" OPENING REQUIRED ON FLAT SLAB TOP TO ACCOMMODATE INLET COVER.
T DRAINAGE STRUCTURE NUMBER LISTED IN THE COLUMN TO THE LEFT REFERS TO THE ORIGINAL PROJECT# 3180-09-08&141-70 PLAN SET SUBSEQUENT UPDATE SHEETS.
U DRAINAGE STRUCTURE NUMBER LISTED IN THE COLUMN TO THE LEFT REFERS TO THE PROJECT 3180-08-70 RSA UPDATE PLAN SET.
V DRAINAGE STRUCTURE NUMBER LISTED IN THE COLUMN TO THE LEFT REFERS TO THE ORIGINAL PROJECT# 3180-09-70 PLAN SET SUBSEQUENT UPDATE SHEETS.

PROJECT NUMBER: 3180-10-70

HWY: BURLINGTON BYPASS

COUNTY: RACINE

MISCELLANEOUS QUANTITIES

SCALE: N/A

SHEET NO: 213B

E

CONTINUED

PIPES										JOINT TIES	
LOCATION		TYPE/DIA (INCHES)	CLASS	FILL HT	LENGTH FT	PIPE LENGTH FT	ELEVATION IN.	PLAN DIS.	SLOPE %	EACH NOTES	
PIPE#	FROM TO										
P110.1	110.0 110.1	SSRRC-12	N	21.32	24	17.30	773.77	773.65	-0.69%	0	H
P111.0	111.0 110.1	SSRRC-24	N	20.50	45	38.68	757.49	757.26	-0.59%	0	H
P111.1	111.1 111.0	SSRRC-12	N	21.58	18	13.20	775.60	774.38	-9.24%	0	H
P112.0	112.0 111.0	SSRRC-24	N	20.50	18	12.70	774.83	774.38	-3.54%	0	H
P112.1	112.1 112.0	SSRRC-12	N	4.91	17	12.60	776.10	775.83	-2.14%	0	H
P112.2	112.2 112.1	SSRRC-12	N	3.70	8	4.30	776.35	776.20	-3.49%	0	H
P112.3	112.3 112.2	SSRRC-12	N	3.19	11	5.60	776.65	776.45	-3.57%	0	H
P112.4	112.4 112.3	SSRRC-12	N	3.11	50	45.50	777.75	776.75	-2.20%	0	H
P113.0	113.1 113.0	SSRRC-12	N	3.43	63	68.00	772.08	763.92	-12.00%	0	H
P113.1	113.2 113.1	SSRRC-12	N	3.43	9	4.40	772.80	772.18	-14.09%	0	H
P113.2	113.3 113.1	SSRRC-12	N	3.43	38	34.90	773.10	772.18	-2.64%	0	H
P115.0	115.0 114.0	SSRRC-18	N	4.58	75	76.63	769.00	762.63	-8.31%	0	H
P115.1	115.1 115.0	SSRRC-12	N	5.12	10	4.08	771.20	770.60	-14.70%	0	H
P115.2	115.2 115.1	SSRRC-12	N	4.01	112	107.55	773.16	771.30	-1.73%	0	H
P115.3	115.3 115.1	SSRRC-12	N	3.38	7	3.50	771.40	771.30	-2.86%	0	H
P115.4	115.4 115.0	SSRRC-12	N	5.12	39	33.33	770.27	769.50	-2.31%	0	H
P115.5	115.5 115.4	SSRRC-12	N	4.05	12	9.00	770.61	770.37	-2.67%	0	H
P115.6	115.6 115.5	SSRRC-12	N	3.78	15	12.00	771.01	770.71	-2.50%	0	H
P115.7	115.7 115.6	SSRRC-12	N	3.14	12	9.00	771.35	771.11	-2.67%	0	H
P116.1	116.1 116.0	SSRRC-12	N	3.72	94	98.00	774.90	765.36	-9.73%	0	H
P116.2	116.2 116.1	SSRRC-12	N	3.72	8	4.60	775.10	775.00	-2.17%	0	H
P117.0	117.1 117.0	SSRRC-12	N	4.21	63	67.40	771.00	761.50	-14.09%	0	H
P117.1	117.2 117.1	SSRRC-12	N	4.21	41	37.90	772.70	771.10	-4.22%	0	H
P117.2	117.3 117.2	SSRRC-12	N	3.61	8	4.20	772.90	772.80	-2.38%	0	H
P117.3	117.4 117.3	SSRRC-12	N	3.11	32	29.00	773.80	773.00	-2.76%	0	H
P118.0	118.1 118.0	SSRRC-12	N	3.17	55	58.80	768.90	759.96	-11.80%	0	H
P118.1	118.2 118.1	SSRRC-12	N	3.17	10	5.50	767.30	767.00	-5.45%	0	H
P118.2	118.3 118.1	SSRRC-12	N	3.30	27	24.00	768.20	767.00	-5.00%	0	H
P118.3	118.4 118.3	SSRRC-12	N	3.30	4	0.70	768.40	768.30	-14.29%	0	H
P118.4	118.5 118.4	SSRRC-12	N	3.11	10	5.50	768.80	768.50	-5.45%	0	H
P118.5	118.6 118.4	SSRRC-12	N	3.11	27	24.00	769.90	768.50	-5.83%	0	H
P119.0	119.1 119.0	CP-24	N	7.51	72	78.06	768.71	764.16	-5.83%	0	H
P120.0	120.1 120.0	SSRRC-12	N	4.32	48	52.40	762.19	757.31	-9.31%	0	H
P120.1	120.2 120.1	SSRRC-12	N	4.34	10	5.50	762.39	762.29	-1.82%	0	H
P120.2	120.3 120.1	SSRRC-12	N	4.32	41	35.60	762.47	762.29	-0.51%	0	H
P121.0	121.1 121.0	SSRRC-24	N	3.33	70	81.26	757.11	755.95	-1.43%	8	H
P122.0	122.1 122.0	SSRRC-12	N	4.27	40	44.20	760.80	755.85	-11.65%	0	H
P122.1	122.2 122.1	SSRRC-12	N	4.27	10	5.50	761.90	760.80	-20.00%	0	H
P122.2	122.4 122.3	CP-18	N	1.74	43	48.00	763.03	762.79	-0.50%	0	H
P123.0	123.1 123.0	CP-18	N	16.83	137	141.25	752.42	750.94	-1.05%	0	H
P124.0	124.1 124.1	PU-12	N	3.34	59	63.02	774.35	755.71	-29.58%	0	H
P125.0	125.0 125.1	PU-12	N	3.34	66	69.85	774.35	753.00	-30.57%	0	H
P126.0	126.1 126.0	CP-24	N	11.64	140	146.43	752.60	751.67	-0.64%	0	H
P127.0	127.1 127.0	CP-24	N	29.66	206	212.19	750.52	750.10	-0.20%	0	H
P128.0	128.1 128.0	CP-24	N	10.87	98	104.53	759.18	757.84	-1.28%	0	H

CONT. ON NEXT PAGE

QUANTITIES SHOWN IN THE DRAINAGE TABLE QUANTITY SUMMARY

NOTE: ALL QUANTITIES ARE CATEGORY 0010 UNLESS OTHERWISE NOTED

REVISION DATE: 5/25/07

REVISION NOTE: ITEMS HIGHLIGHTED REFLECT PLAN REVISIONS.
LAYOUT OF SHEET WAS CHANGED TO ACCOMMODATE
NOTE UPDATES

TABLE NOTE LEGEND:

- A RIM ELEVATION = FLANGE ELEVATION
B OFFSET TO CENTER OF STRUCTURE
C TOP OF STRUCTURE ELEVATION = RIM ELEVATION. RIM SUPPRESS 2" INTO TOP OF STRUCTURE OR L.D.
D TOP OF STRUCTURE ELEVATION BASED ON (RIM ELEVATION - 9" CASTING - 6" ADJUSTMENT RINGS).
E TOP OF STRUCTURE ELEVATION BASED ON (RIM ELEVATION - 10" CASTING - 6" ADJUSTMENT RINGS).
F TOP OF STRUCTURE ELEVATION BASED ON (RIM ELEVATION - 6" CASTING - 6" ADJUSTMENT RINGS).
G STATION & OFFSET FOR ENDWALLS IS MEASURED AT END OF WALL.
H PIPE JOINT TIES ARE NOT A PAY ITEM. FOR INFORMATION ONLY.
I SEE SDD FOR CONCRETE SURFACE DRAIN DROP INLET TYPE AT STRUCTURES.
J EXISTING PIPE TO REMAIN
K STRUCTURE AND COVER PLATE PLACED IN PREVIOUS PROJECT. REMOVE COVER PLATE PLACE COVER AND RINGS
L AND SET TO FINAL PLAN RIM ELEVATION. REMOVAL AND DISPOSAL OF COVER PLATE IS INCIDENTAL TO ADJUSTMENT OF INLET OR MANHOLE
M INLET PLACED AS REVISION TO 3180-08-70 PROJECT DURING CONSTRUCTION.
N MARKER POST CULVERT END FLEXIBLE REQUIRED.
O STRUCTURE REQUIRES FLAT SLAB TOP.
P PROVIDE OPENING IN FLAT SLAB TOP TO ACCOMMODATE A SINGLE INLET COVER TYPE "INS".
R 30" OPENING REQUIRED ON FLAT SLAB TOP TO ACCOMMODATE INLET COVER.
S 20" OPENING REQUIRED ON FLAT SLAB TOP TO ACCOMMODATE INLET COVER.
T DRAINAGE STRUCTURE NUMBER LISTED IN THE COLUMN TO THE LEFT REFERS TO THE ORIGINAL PROJECT# 3180-08&141-70 PLAN SET SUBSEQUENT UPDATE SHEETS.
U DRAINAGE STRUCTURE NUMBER LISTED IN THE COLUMN TO THE LEFT REFERS TO THE PROJECT 3180-08-70 RSA UPDATE PLAN SET.
V DRAINAGE STRUCTURE NUMBER LISTED IN THE COLUMN TO THE LEFT REFERS TO THE ORIGINAL PROJECT# 3180-09-70 PLAN SET SUBSEQUENT UPDATE SHEETS.

ADD #1
NEW SHT 214B
6/29/2007

PROJECT NUMBER: 3180-10-70

HWY: BURLINGTON BYPASS

COUNTY: RACINE

MISCELLANEOUS QUANTITIES

SCALE: N/A

SHEET NO: 214B

E

FILE NAME: E:\0072648B\9494\acdd\gnd\60\details\946\General Notes.rpt

ORIGINATOR: LISA FLYNN

ORG. DATE: JULY 10, 2003

PLOTTED DATE: 6/13/2007 11:44 AM

CONTINUED

PIPES												JOINT	
LOCATION													
PIPE#	FROM	TO	TYPE-DIA (INCHES)	CLASS	FILL FT	PLAN LENGTH FT	PIPE LENGTH FT	ELEVATION INV.	SLOPE DIS. %	PLAN SLOPE %	TIES EACH NOTES		
PI29.0	129.1	129.0	CP-24	--	0.23	14	20.07	765.25	764.91	-1.69%	0 H		
PI30.0	130.0	130.3	SSPRC-18	III	3.59	167	169.24	824.80	815.06	-5.76%	0 H		
PI30.1	130.1	130.0	SSPRC-18	III	3.59	26	20.42	826.00	824.90	-5.39%	0 H		
PI30.2	130.2	130.0	SSPRC-18	III	3.59	43	36.95	826.40	824.90	-4.06%	0 H		
PI31.0	131.1	131.0	CP-24	III	11.28	100	106.75	794.94	794.00	-0.88%	0 H		
PI32.0	132.1	132.0	CP-24	V	28.78	217	223.06	792.50	791.35	-0.52%	0 H		
PI33.0	133.1	133.0	CPRC-24	V	30.93	176	188.00	791.60	790.66	-0.50%	8 H		
PI34.1	134.1	134.0	SSPRC-12	III	3.42	78	81.60	780.00	775.00	-6.13%	0 H		
PI34.2	134.2	134.1	SSPRC-12	III	3.42	10	5.50	780.30	780.10	-3.64%	0 H		
PI34.3	134.3	134.1	SSPRC-12	III	3.42	27	24.00	780.64	780.10	-2.25%	0 H		
PI35.0	135.1	135.0	CP-18	--	0.76	31	35.36	764.18	763.56	-1.75%	0 H		
PI36.0	136.1	136.0	PU-12	--	3.34	95	99.17	817.88	791.94	-26.16%	0 H		
PI37.0	137.1	137.0	PU-12	--	3.51	89	91.69	817.71	794.00	-25.86%	0 H		

QUANTITIES SHOWN IN THE DRAINAGE TABLE QUANTITY SUMMARY

TABLE NOTE LEGEND:

- A RIM ELEVATION = FLANGE ELEVATION
- B OFFSET TO CENTER OF STRUCTURE
- C TOP OF STRUCTURE ELEVATION = RIM ELEVATION. RIM SUPPRESS 2" INTO TOP OF STRUCTURE OR LID.
- D TOP OF STRUCTURE ELEVATION BASED ON (RIM ELEVATION - 9" CASTING - 6" ADJUSTMENT RINGS).
- E TOP OF STRUCTURE ELEVATION BASED ON (RIM ELEVATION - 10" CASTING - 6" ADJUSTMENT RINGS).
- F TOP OF STRUCTURE ELEVATION BASED ON (RIM ELEVATION - 6" CASTING - 6" ADJUSTMENT RINGS).
- G STATION & OFFSET FOR ENDWALLS IS MEASURED AT END OF ENDWALL.
- H PIPE JOINT TIES ARE NOT A PAY ITEM. FOR INFORMATION ONLY.
- I SEE SDD FOR CONCRETE SURFACE DRAIN DROP INLET TYPE AT STRUCTURES.
- J EXISTING PIPE TO REMAIN
- K STRUCTURE AND COVER PLATE PLACED IN PREVIOUS PROJECT. REMOVE COVER PLATE PLACED COVER AND RINGS AND SET TO FINAL PLAN RIM ELEVATION. REMOVAL AND DISPOSAL OF COVER PLATE IS INCIDENTAL TO ADJUSTMENT OF INLET OR MANHOLE.
- N INLET PLACED AS REVISION TO 3180-08-70 PROJECT DURING CONSTRUCTION.
- O MARKER POST QUALITY ERT END FLEXIBLE REQUIRED.
- P STRUCTURE REQUIRES FLAT SLAB TOP.
- Q PROVIDE OPENING IN FLAT SLAB TOP TO ACCOMMODATE A SINGLE INLET COVER TYPE "MS".
- R 30" OPENING REQUIRED ON FLAT SLAB TOP TO ACCOMMODATE INLET COVER.
- S 20" OPENING REQUIRED ON FLAT SLAB TOP TO ACCOMMODATE INLET COVER.
- T DRAINAGE STRUCTURE NUMBER LISTED IN THE COLUMN TO THE LEFT REFERS TO THE ORIGINAL PROJECT# 3180-08-70 PLAN SET SUBSEQUENT UPDATE SHEETS.
- U DRAINAGE STRUCTURE NUMBER LISTED IN THE COLUMN TO THE LEFT REFERS TO THE PROJECT 3180-08-70 RSA UPDATE PLAN SET.
- V DRAINAGE STRUCTURE NUMBER LISTED IN THE COLUMN TO THE LEFT REFERS TO THE ORIGINAL PROJECT# 3180-09-70 PLAN SET SUBSEQUENT UPDATE SHEETS.

CONCRETE MEDIAN SLOPED NOSE

STATION		OFFSET	LOCATION	CONCRETE MEDIAN SLOPED NOSE
1123+98	RT	BYPASS		620.0300
1124+76	LT	BYPASS		SLOPED NOSE
1124+85	LT	BYPASS		43
1124+98	LT	BYPASS		60
1125+06	RT	BYPASS		50
1125+17	RT	BYPASS		80
1125+83	LT	BYPASS		98
1125+95	LT	BYPASS		85
1126+02	RT	BYPASS		85
1126+14	RT	BYPASS		98
1126+26	RT	BYPASS		85
1127+01	LT	BYPASS		85
1129+44	LT	BYPASS		98
1171+54	RT	BYPASS		60
1172+56	RT	BYPASS		60
1176+48	LT	BYPASS		80
1177+50	LT	BYPASS		55
1273+71	RT	BYPASS		55
1284+74	LT	BYPASS		70
1369+05	RT	BYPASS		39
1372+96	LT	BYPASS		39
1373+38	RT	BYPASS		DELETED-39
1373+64	LT	BYPASS		DELETED-40
1398+38	LT	BYPASS		DELETED-70
348+30	CL	STH 83		DELETED-70
351+44	RT	STH 83		65
351+62	LT	STH 83		49
351+68	CL	STH 83		49
353+33	CL	STH 83		50
353+39	LT	STH 83		50
353+57	RT	STH 83		60
357+18	CL	STH 83		49
358+96	CL	STH 83		62
39+64	LT	CTH A SE RAMP		40
39+96	RT	CTH A SE RAMP		57
49+41	LT	CTH A SE RAMP		76
58+12	CL	CTH A NW RAMP		42
58+13	LT	CTH A NW RAMP		49
58+66	CL	CTH A NW RAMP		74
TOTAL				50
				2082

REVISION DATE: 5/25/07

REVISION NOTE: ITEMS HIGHLIGHTED REFLECT PLAN REVISIONS.
LAYOUT OF SHEET WAS CHANGED TO ACCOMMODATE
NOTE UPDATES

NOTE: ALL QUANTITIES ARE CATEGORY 0010 UNLESS OTHERWISE NOTED

PROJECT NUMBER: 3180-10-70	HWY: BURLINGTON BYPASS	COUNTY: RACINE	MISCELLANEOUS QUANTITIES	SCALE: N/A	SHEET NO: 215	E
----------------------------	------------------------	----------------	--------------------------	------------	---------------	---

ADJUSTING STRUCTURES

STRICT #	ROADWAY	LOCATION	STRICT TYPE - COVERTYPE	PROP GRND ELEV OR EXISTING TOP OF STRUCTURE ELEVATION	REQ'D ADJUSTMENT DEPTH (FT)	INLET PROTECTIO N TYPE	STRUCTURE ID FROM 3180-08-70, 3180-14-70 & 3180-09-70	NOTES
300.1	BYPASS	1172+50.00 70.5' LT	MH1-HM	762.32	0.49	C	6.1	K.T
300.2	BYPASS	1172+60.00 70.5' LT	NL3-HM	762.35	0.50	C	6.2	K.T
300.3	BYPASS	1174+00.00 70.5' LT	NL3-HM	762.90	0.49	C	6.3	K.T
301.1	STH 142 SW RAMP	40+65.00 9.5' RT	NL3-HM	762.04	0.49	C	22.1	K.T
301.2	STH 142 SW RAMP	40+75.00 9.5' RT	NL3-HM	762.04	0.49	C	22.2	K.T
301.3	STH 142 SW RAMP	40+65.00 11.4' LT	NL3-HM	762.01	0.50	C	22.3	K.T
301.4	STH 142 SW RAMP	40+75.00 10.1' LT	NL3-HM	762.01	0.49	C	22.4	K.T
301.5	BYPASS	1172+50.00 59.5' RT	MH3-HM	762.43	0.65	C	22.5	K.T
301.6	BYPASS	1175+00.00 70.5' RT	NL3-HM	763.40	1.65	C	22.6	K.T
302.1	STH 142 SW RAMP	42+70.00 9.5' RT	NL3-HM	764.57	0.50	C	21.1	K.T
302.2	STH 142 SW RAMP	42+80.00 9.5' RT	NL3-HM	764.83	0.49	C	21.2	K.T
302.3	STH 142 SW RAMP	42+70.00 34.5' RT	NL3-HM	764.98	0.57	C	21.3	K.T
302.4	STH 142 SW RAMP	42+70.00 9.5' LT	NL3-HM	764.57	0.50	C	21.4	K.T
302.5	STH 142 SW RAMP	42+70.00 34.5' LT	NL3-HM	764.13	0.50	C	21.5	K.T
303.1	STH 142 SW RAMP	45+50.00 34.5' LT	NL3-HM	771.81	0.49	C	23.1	K.T
303.2	STH 142 SW RAMP	45+50.00 9.5' LT	NL3-HM	772.69	0.49	C	23.2	K.T
303.3	STH 142 SW RAMP	45+50.00 9.5' RT	NL3-HM	772.69	0.49	C	23.3	K.T
303.4	STH 142 SW RAMP	45+50.00 34.5' RT	NL3-HM	773.57	0.50	C	23.4	K.T
304.1	BYPASS	1176+55.00 58.6' LT	NL3-HM	764.26	0.59	C	25.1	K.T
304.2	BYPASS	1176+54.50 69.1' LT	NL3-HM	763.22	0.50	C	25.2	K.T
304.3	BYPASS	1176+14.70 76.5' LT	NL3-HM	763.69	0.50	C	25.3	K.T
305.1	STH 142 NE RAMP	59+15.00 18.7' RT	NL3-HM	764.43	0.47	C	26.1	K.T
305.3	STH 142 NE RAMP	59+15.00 9.6' LT	NL3-HM	764.49	0.49	C	26.3	K.T
305.4	STH 142 NE RAMP	59+25.00 10.6' LT	NL3-HM	764.49	0.49	C	26.4	K.T
305.5	STH 142 NE RAMP	59+15.00 34.7' LT	NL3-HM	764.05	0.49	C	26.5	K.T
305.6	STH 142 NE RAMP	59+25.00 35.7' LT	NL3-HM	763.06	0.49	C	26.6	K.T
306.1	STH 142 NE RAMP	58+00.00 34.5' RT	NL3-HM	763.66	0.49	C	27.1	K.T
306.2	STH 142 NE RAMP	58+00.00 9.5' RT	NL3-HM	765.09	0.49	C	27.2	K.T
306.3	STH 142 NE RAMP	58+00.00 9.5' LT	NL3-HM	765.09	0.49	C	27.3	K.T
306.4	STH 142 NE RAMP	57+90.00 9.5' LT	NL3-HM	765.20	0.49	C	27.4	K.T
306.5	STH 142 NE RAMP	58+00.00 34.5' LT	NL3-HM	765.49	0.50	C	27.5	K.T
307.1	STH 142 NE RAMP	54+50.00 34.5' RT	NL3-HM	770.41	0.49	C	28.1	K.T
307.2	STH 142 NE RAMP	54+50.00 9.5' RT	NL3-HM	771.29	0.49	C	28.2	K.T
307.3	STH 142 NE RAMP	54+50.00 9.5' LT	NL3-HM	771.29	0.49	C	28.3	K.T
307.4	STH 142 NE RAMP	54+50.00 34.5' LT	NL3-HM	772.17	0.50	C	28.4	K.T
308.1	BYPASS	1273+80.00 19.5' RT	NL3-HM	805.62	0.55	C	14.1	K.T
308.2	BYPASS	1273+90.00 19.5' RT	NL3-HM	805.67	0.55	C	14.2	K.T
308.3	BYPASS	1273+80.00 15.8' RT	NL3-HM	805.91	0.48	C	14.3	K.T
308.4	BYPASS	1273+80.00 .7' RT	NL3-HM	805.70	0.49	C	14.4	K.T
308.5	BYPASS	1273+80.00 19.5' LT	NL3-HM	805.61	0.54	C	14.5	K.T
309.1	BYPASS	1276+50.00 19.5' LT	NL3-HM	807.03	0.49	C	15.1	K.T
309.2	BYPASS	1276+50.00 7.5' LT	NL3-HM	807.05	0.49	C	15.2	K.T
309.3	BYPASS	1276+50.00 7.5' RT	NL3-HM	807.15	0.54	C	15.3	K.T
309.4	BYPASS	1276+50.00 19.5' RT	NL3-HM	807.02	0.49	C	15.4	K.T
310.1	BYPASS	1281+00.00 19.5' LT	MH1-HM	809.02	0.49	C	30.1	K.T

CONT. ON NEXT PAGE

QUANTITIES SHOWN IN THE DRAINAGE TABLE QUANTITY SUMMARY

NOTE: ALL QUANTITIES ARE CATEGORY 0010 UNLESS OTHERWISE NOTED

REVISION DATE: 5/25/07

REVISION NOTE: ITEMS HIGHLIGHTED REFLECT PLAN REVISIONS.
LAYOUT OF SHEET WAS CHANGED TO ACCOMMODATE
NOTE UPDATES

TABLE NOTE LEGEND:

- A RIM ELEVATION = FLANGE ELEVATION
B OFFSET TO CENTER OF STRUCTURE
C TOP OF STRUCTURE ELEVATION = RIM ELEVATION. RIM SUPPRESS 2" INTO TOP OF STRUCTURE OR L.D.
D TOP OF STRUCTURE ELEVATION BASED ON RIM ELEVATION - 9" CASTING - 6" ADJUSTMENT RINGS).
E TOP OF STRUCTURE ELEVATION BASED ON RIM ELEVATION - 10" CASTING - 6" ADJUSTMENT RINGS).
F TOP OF STRUCTURE ELEVATION BASED ON RIM ELEVATION - 6" CASTING - 6" ADJUSTMENT RINGS).
G STATION & OFFSET FOR ENDWALLS IS MEASURED AT END OF ENDWALL.
H PIPE JOINTS ARE NOT A PAY ITEM. FOR INFORMATION ONLY.
I SEE SDD FOR CONCRETE SURFACE DRAIN INLET TYPE AT STRUCTURES.
J EXISTING PIPE TO REMAIN
STRUCTURE AND COVER PLATE PLACED IN PREVIOUS PROJECT. REMOVE COVER PLATE PLACE COVER AND RINGS
K AND SET TO FINAL PLAN RIM ELEVATION. REMOVAL AND DISPOSAL OF COVER PLATE IS INCIDENTAL TO ADJUSTMENT OF INLET OR MANHOLE.
N INLET PLACED AS REVISION TO 3180-08-70 PROJECT DURING CONSTRUCTION.
O MARKER POST CULVERT END FLEXIBLE REQUIRED.
P STRUCTURE REQUIRES FLAT SLAB TOP.
Q PROVIDE OPENING IN FLAT SLAB TOP TO ACCOMMODATE A SINGLE INLET COVER TYPE "MS".
R 30" OPENING REQUIRED ON FLAT SLAB TOP TO ACCOMMODATE INLET COVER.
S 20" OPENING REQUIRED ON FLAT SLAB TOP TO ACCOMMODATE INLET COVER.

T DRAINAGE STRUCTURE NUMBER LISTED IN THE COLUMN TO THE LEFT REFERS TO THE ORIGINAL PROJECT# 3180-08&14-70 PLAN SET SUBSEQUENT UPDATE SHEETS.

U DRAINAGE STRUCTURE NUMBER LISTED IN THE COLUMN TO THE LEFT REFERS TO THE PROJECT 3180-08-70 RSA UPDATE PLAN SET.

V DRAINAGE STRUCTURE NUMBER LISTED IN THE COLUMN TO THE LEFT REFERS TO THE ORIGINAL PROJECT# 3180-09-70 PLAN SET SUBSEQUENT UPDATE SHEETS.

PROJECT NUMBER: 3180-10-70

HWY: BURLINGTON BYPASS

COUNTY: RACINE

MISCELLANEOUS QUANTITIES

SCALE: N/A

SHEET NO: 216

E

CONTINUED

ADJUSTING STRUCTURES

STRICT #	ROADWAY	LOCATION	STRICT TYPE - ELEV OR	EXISTING TOP OF STRUCTURE ELEVATION	REQ'D ADJUSTMENT DEPTH (FT)	PROTECTIO N TYPE	INLET	STRUCTURE ID FROM 3180-08-70, 3180-14-70 & 3180-09-70	NOTES
310.2	BYPASS	1280+80.00	19.5' RT	808.98	0.49	C	C	30.3	K.T
311.1	BYPASS	1283+60.00	19.5' RT	808.34	0.50	C	C	259.1	K.T
311.2	BYPASS	1283+60.00	7.5' RT	808.15	0.49	C	C	259.2	K.T
312.1	BYPASS	1284+70.00	19.5' LT	807.87	0.58	C	C	260.1	K.T
312.2	BYPASS	1284+60.00	19.5' LT	806.84	0.58	C	C	260.2	K.T
315.0	CTH A NW RAMP	57+60.00	6.0' LT	769.19	0.64	A	A	264.0	K.T
315.1	CTH A NW RAMP	57+00.00	9.5' LT	769.33	0.50	C	C	264.1	K.T
315.2	CTH A NW RAMP	56+90.00	9.5' LT	769.57	0.50	C	C	264.2	K.T
315.3	CTH A NW RAMP	57+80.00	9.5' LT	768.59	0.50	C	C	413.1	K.U
316.1	CTH A NW RAMP	57+70.00	43.2' LT	767.97	0.50	C	C	263.1	K.T
317.0	CTH A NW RAMP	57+60.00	34.5' RT	768.66	0.70	A	A	265.0	K.T
318.1	CTH A NW RAMP	54+25.00	34.5' RT	777.41	0.50	C	C	268.1	K.T
318.2	CTH A NW RAMP	54+25.00	9.5' LT	779.28	0.50	C	C	268.2	K.T
319.1	CTH A NW RAMP	51+20.00	34.5' RT	790.21	0.38	C	C	269.1	K.T
319.2	CTH A NW RAMP	51+20.00	34.5' LT	790.74	0.60	C	C	269.2	K.T
320.1	EB BYPASS	1405+00.00	34.5' RT	768.56	0.47	B	B	305.1	K.T
320.2	EB BYPASS	1405+50.00	34.5' RT	768.82	0.47	B	B	305.2	K.T
321.0	BYPASS	1284+50.00	14.5' LT	807.91	0.50	C	C	260.3	K.N.V
323.0	STH 36/83 NB TO SB RAMP	203+67.96	26.8' LT	768.55	0.50	B	B	402.0	K.N.V
324.0	STH 36/83 NB TO SB RAMP	196+00.00	20.5' LT	794.91	0.50	C	C	301.3	K.N.V
325.0	CTH A SE RAMP	40+00.81	46.9' RT	785.26	0.50	C	C	401.0	K.U
325.1	CTH A SE RAMP	40+09.55	42.0' RT	785.35	0.50	C	C	401.1	K.U
326.0	BYPASS	1363+51.95	60.4' RT	785.52	0.50	C	C	403.0	K.U
326.1	BYPASS	1364+16.63	58.6' RT	784.34	0.50	C	C	403.1	K.U
326.2	BYPASS	1364+85.24	70.5' RT	782.72	0.50	C	C	403.2	K.U
327.1	CTH A SE RAMP	42+73.59	34.5' LT	787.50	0.50	C	C	404.1	K.U
327.2	CTH A SE RAMP	42+73.59	9.5' RT	788.42	0.50	C	C	404.2	K.U
327.3	CTH A SE RAMP	42+83.59	9.5' RT	788.62	0.50	C	C	404.3	K.U
328.1	CTH A SE RAMP	45+00.00	34.5' LT	790.47	0.50	C	C	405.1	K.U
328.2	CTH A SE RAMP	45+10.00	34.5' LT	790.52	0.50	C	C	405.2	K.U
328.3	CTH A SE RAMP	45+00.00	9.5' LT	791.35	0.50	C	C	405.3	K.U
328.4	CTH A SE RAMP	45+00.00	9.5' RT	791.45	0.50	C	C	405.4	K.U
328.5	CTH A SE RAMP	45+00.00	34.5' RT	792.33	0.50	C	C	405.5	K.U
329.1	CTH A SE RAMP	48+00.00	34.5' LT	792.41	0.50	C	C	407.1	K.U
329.2	CTH A SE RAMP	48+95.89	34.5' LT	793.74	0.50	C	C	407.2	K.U
330.1	CTH A SE RAMP	48+40.00	34.5' RT	793.14	0.50	C	C	408.1	K.U
330.2	CTH A SE RAMP	48+50.00	34.5' RT	792.14	0.50	C	C	408.2	K.U
330.3	CTH A SE RAMP	48+40.00	2.5' LT	793.25	0.50	C	C	408.3	K.U
331.1	CTH A NW RAMP	57+05.73	34.5' RT	768.80	0.50	C	C	414.1	K.U
331.2	CTH A NW RAMP	56+95.73	34.5' RT	769.01	0.50	C	C	414.2	K.U
331.3	CTH A NW RAMP	57+05.73	9.5' RT	769.24	0.50	C	C	414.3	K.U
331.4	CTH A NW RAMP	56+95.73	9.5' RT	769.45	0.50	C	C	414.4	K.U

QUANTITIES SHOWN IN THE DRAINAGE TABLE QUANTITY SUMMARY

NOTE: ALL QUANTITIES ARE CATEGORY 0010 UNLESS OTHERWISE NOTED

REVISION DATE: 5/25/07

REVISION NOTE: ITEMS HIGHLIGHTED REFLECT PLAN REVISIONS.
LAYOUT OF SHEET WAS CHANGED TO ACCOMMODATE
NOTE UPDATESADJUSTMENT TO STRUCTURE# 322.0 NO LONGER
REQUIRED

TABLE NOTE LEGEND:

- A RIM ELEVATION = FLANGE ELEVATION
- B OFFSET TO CENTER OF STRUCTURE
- C TOP OF STRUCTURE ELEVATION = RIM ELEVATION. RIM SUPPRESS 2' INTO TOP OF STRUCTURE OR L.D.
- D TOP OF STRUCTURE ELEVATION BASED ON (RIM ELEVATION - 9' CASTING - 6' ADJUSTMENT RINGS).
- E TOP OF STRUCTURE ELEVATION BASED ON (RIM ELEVATION - 10' CASTING - 6' ADJUSTMENT RINGS).
- F TOP OF STRUCTURE ELEVATION BASED ON (RIM ELEVATION - 6' CASTING - 6' ADJUSTMENT RINGS).
- G STATION & OFFSET FOR ENDWALLS IS MEASURED AT END OF ENDWALL.
- H PIPE JOINTS ARE NOT A PAY ITEM. FOR INFORMATION ONLY.
- I SEE SDD FOR CONCRETE SURFACE DRAIN DROP INLET TYPE AT STRUCTURES.
- J EXISTING PPE TO REMAIN
- K STRUCTURE AND COVER PLATE PLACED IN PREVIOUS PROJECT. REMOVE COVER PLATE PLACE COVER AND RINGS AND SET TO FINAL PLAN RIM ELEVATION. REMOVAL AND DISPOSAL OF COVER PLATE IS INCIDENTAL TO ADJUSTMENT OF INLET OR MANHOLE.
- N INLET PLACED AS REVISION TO 3180-08-70 PROJECT DURING CONSTRUCTION.
- O MARKER POST CULTURE END FLEXIBLE REQUIRED.
- P STRUCTURE REQUIRES FLAT SLAB TOP.
- Q PROVIDE OPENING IN FLAT SLAB TOP TO ACCOMMODATE A SINGLE INLET COVER TYPE "MS".
- R 30" OPENING REQUIRED ON FLAT SLAB TOP TO ACCOMMODATE INLET COVER.
- S 20" OPENING REQUIRED ON FLAT SLAB TOP TO ACCOMMODATE INLET COVER.

DRAINAGE STRUCTURE NUMBER LISTED IN THE COLUMN TO THE LEFT REFERS TO THE ORIGINAL PROJECT# 3180-09-70 PLAN SET SUBSEQUENT UPDATE SHEETS.

DRAINAGE STRUCTURE NUMBER LISTED IN THE COLUMN TO THE LEFT REFERS TO THE PROJECT 3180-08-70 RSA UPDATE PLAN SET.

DRAINAGE STRUCTURE NUMBER LISTED IN THE COLUMN TO THE LEFT REFERS TO THE ORIGINAL PROJECT# 3180-09-70 PLAN SET SUBSEQUENT UPDATE SHEETS.

PROJECT NUMBER: 3180-10-70

HWY: BURLINGTON BYPASS

COUNTY: RACINE

MISCELLANEOUS QUANTITIES

SCALE: N/A

SHEET NO: 216B

E

CONCRETE CURB & GUTTER

STATION	LOCATION	RDWY	601.0554		601.0558		601.0411		650.5500			
			CONCRETE		CONCRETE		CONCRETE		CONSTRUCTION			
			CURB & GUTTER		CURB & GUTTER		CURB & GUTTER		STAKING			
			4-INCH	6-INCH	4-INCH	6-INCH	4-INCH	6-INCH	4-INCH	6-INCH		
MOUNTABLE			MOUNTABLE			MOUNTABLE			MOUNTABLE			
36-INCH TYPE D			36-INCH TYPE D			36-INCH TYPE D			36-INCH TYPE D			
LF			LF			LF			LF			
1129+05 - 1130+50	MEDIAN	EB BYPASS	-	-	1,264	-	-	-	-	1,264	-	-
1130+08 - 1130+75	MEDIAN	EB BYPASS	67	-	-	-	-	-	-	-	67	-
1123+05 - 1129+44	MEDIAN	WB BYPASS	-	-	1,102	-	-	-	-	1,102	-	-
1127+47 - 1128+50	LT	WB BYPASS	81	-	-	-	-	-	-	-	81	-
1171+54 - 1172+56	RT	EB BYPASS	-	-	122	-	-	-	-	122	-	-
1173+23 - 1178+23	RT	EB BYPASS	-	-	500	-	-	-	-	500	-	-
1172+00 - 1175+81	LT	WB BYPASS	-	-	381	-	-	-	-	381	-	-
1176+48 - 1177+50	LT	WB BYPASS	-	-	122	-	-	-	-	122	-	-
1273+71 - 1278+35	MEDIAN	EB BYPASS	-	-	869	-	-	-	-	869	-	-
1280+10 - 1286+75	MEDIAN	EB BYPASS	-	-	1,208	-	-	-	-	1,208	-	-
1271+70 - 1278+35	MEDIAN	WB BYPASS	-	-	1,208	-	-	-	-	1,208	-	-
1280+10 - 1284+74	MEDIAN	WB BYPASS	-	-	869	-	-	-	-	869	-	-
1369+05 - 1372+38	MEDIAN	EB BYPASS	-	-	1,066	-	-	-	-	1,066	-	-
1373+65 - 1375+08	MEDIAN	EB BYPASS	-	-	156	-	-	-	-	156	-	-
1369+40 - 1372+46	MEDIAN	WB BYPASS	-	-	1,044	-	-	-	-	1,044	-	-
1372+45 - 1374+25	MEDIAN	WB BYPASS	-	-	420	-	-	-	-	420	-	-
1364+35 - 1369+25	RT	EB BYPASS	-	-	490	-	-	-	-	490	-	-
1367+50 - 1369+65	LT	WB BYPASS	-	-	215	-	-	-	-	215	-	-
1398+34 - 1400+50	LT	WB BYPASS	-	-	216	-	-	-	-	216	-	-
344+00 - 344+94	LT	STH 83	-	-	94	-	-	-	-	94	-	-
344+00 - 351+66	RT	STH 83	-	-	814	-	-	-	-	814	-	-
345+06 - 351+66	LT	STH 83	-	-	687	-	-	-	-	687	-	-
346+89	DRIVE RT	STH 83	-	-	68	-	-	-	-	68	-	-
346+80 - 351+68	MEDIAN	STH 83	-	-	601	-	-	-	-	601	-	-
351+44 - 351+81	ISLAND RT	STH 83	-	-	127	-	-	-	-	127	-	-
351+62 - 352+17	ISLAND LT	STH 83	-	-	310	-	-	-	-	310	-	-
352+84 - 353+39	ISLAND RT	STH 83	-	-	310	-	-	-	-	310	-	-
353+20 - 353+57	ISLAND LT	STH 83	-	-	127	-	-	-	-	127	-	-
352+77 - 361+25	RT	STH 83	-	-	961	-	-	-	-	961	-	-
353+36 - 360+49	LT	STH 83	-	-	787	-	-	-	-	787	-	-
353+33 - 357+18	MEDIAN	STH 83	-	-	801	-	-	-	-	801	-	-
360+69	DRIVE RT	STH 83	-	-	20	-	-	-	-	20	-	-
360+85 - 361+25	LT	STH 83	-	-	75	-	-	-	-	75	-	-
361+25 - 369+35	RT	STH 83	-	-	-	-	-	-	-	810	-	-
361+25 - 369+35	RT	STH 83	-	-	-	-	-	-	-	810	-	-
50+11 - 60+17	LT	STH 142 NE RAMP	-	-	1,113	-	-	-	-	1,113	-	-
50+42 - 59+67	RT	STH 142 NE RAMP	-	-	1,890	-	-	-	-	1,890	-	-
50+66 - 60+01	MEDIAN	STH 142 NE RAMP	-	-	981	-	-	-	-	981	-	-
39+38 - 49+89	RT	STH 142 SW RAMP	-	-	1,158	-	-	-	-	1,158	-	-
39+54 - 49+34	MEDIAN	STH 142 SW RAMP	-	-	1,978	-	-	-	-	1,978	-	-
39+88 - 49+58	LT	STH 142 SW RAMP	-	-	1,026	-	-	-	-	1,026	-	-
91+26 - 93+29	LT	KETTERHAGEN RD	-	-	203	-	-	-	-	203	-	-
91+45 - 93+71	RT	KETTERHAGEN RD	-	-	226	-	-	-	-	226	-	-

NOTE: ALL QUANTITIES ARE CATEGORY 0010 UNLESS OTHERWISE NOTED

CONTINUED

CONCRETE CURB & GUTTER

STATION	LOCATION	RDWY	601.0554				601.0558				601.0411				650.5500			
			CONCRETE				CONCRETE				CONCRETE				CONSTRUCTION			
						CURB & GUTTER 4-INCH				CURB & GUTTER 6-INCH				CURB, GUTTER				
						MOUNTABLE				MOUNTABLE				AND CURB				
						36-INCH TYPE D				36-INCH TYPE D				36-INCH TYPE D				
						LF				LF				LF				
39+63 - 49+75	RT	CTH A SE RAMP	-	-	-	1,125	-	-	-	1,125	-	-	-	1,125	-	-	-	
39+63 - 49+75	LT	CTH A SE RAMP	-	-	-	1,045	-	-	-	1,045	-	-	-	1,045	-	-	-	
39+60 - 49+44	MEDIAN	CTH A SE RAMP	-	-	-	2,066	-	-	-	2,066	-	-	-	2,066	-	-	-	
50+24 - 58+14	LT	CTH A NW RAMP	-	-	-	915	-	-	-	915	-	-	-	915	-	-	-	
50+24 - 58+14	RT	CTH A NW RAMP	-	-	-	849	-	-	-	849	-	-	-	849	-	-	-	
50+58 - 58+06	MEDIAN	CTH A NW RAMP	-	-	-	1,512	-	-	-	1,512	-	-	-	1,512	-	-	-	
50+24 - 58+06	RT	CTH A NW RAMP	-	-	-	722	-	-	-	722	-	-	-	722	-	-	-	
50+58 - 58+16	MEDIAN	CTH A NW RAMP	-	-	-	1,529	-	-	-	1,529	-	-	-	1,529	-	-	-	
196+00 - 198+00	LT	STH 36/83 NB-SB RAMP	-	-	-	200	-	-	-	200	-	-	-	200	-	-	-	
201+50 - 203+68	LT	STH 36/83 NB-SB RAMP	-	-	-	237	-	-	-	237	-	-	-	237	-	-	-	
TOTAL			148				35,795				1,620				34,857			

CONCRETE SIDEWALK 4-INCH

RDWY	LOCATION	602.0405		602.0505	
		CONCRETE SIDEWALK 4-INCH	SF	CURB RAMP DETECTABLE WARNING FIELD YELLOW	SF
STH 83	SW QUADRANT	10	8	8	8
	SW ISLAND	30	8	8	8
	EB LT TURN LANE	20	8	8	8
	NW QUADRANT	10	8	8	8
	NW ISLAND	30	8	8	8
	NE QUADRANT	10	8	8	8
	NE ISLAND	30	8	8	8
	WB LT TURN LANE	20	8	8	8
	SE QUADRANT	10	8	8	8
	SE ISLAND	30	8	8	8
TOTAL		200	80		

REVISION DATE: 5/25/07

REVISION NOTE: ITEMS HIGHLIGHTED REFLECT PLAN REVISIONS.

ADD #1
REV SHT 217
6/29/2007

PROJECT NUMBER: 3180-10-70

HWY: BURLINGTON BYPASS

COUNTY: RACINE

MISCELLANEOUS QUANTITIES

SHEET NO: 217

E

MARKER POSTS RIGHT OF WAY

RIGHT-OF-WAY				614.0605			
PLAT		MARKER POSTS		RIGHT OF WAY		EACH	
SHEET	POINT	NUMBER	RIGHT OF WAY	SHEET	POINT	NUMBER	RIGHT OF WAY
4.13	8301-8304	4		4.15 (cont'd)	5304	1	
	8202	1		5301-5302	2		
	8205	1		5502	1		
	21402	1		5002-5003	2		
	20402	1		5506	1		
	21501-21503	3		4.16	4225-4229	5	
	20501-20502	2		3034	1		
	20505	1		4401-4402	2		
	20508	1		4501-4502	2		
	6902-6905	4		4701-4702	2		
	6804-6805	2		4244	1		
	21810-21811	2		4801-4803	3		
	21807	1		4806-4807	2		
	21802-21803	2		4210	1		
	21501-21503	3		4212-4215	4		
4.14	18601	1		4217-4219	3		
	3005	1		4.17	3035	1	
	3006	1		3037-3038	2		
	18602-18603	2		4002	1		
	6506	1		3007	1		
	6401	1		4104	1		
	6601	1		4238	1		
	4902	1		4.18	3802	1	
	6711-6712	2		3810	1		
	6707-6708	2		3803	1		
	18801	1		3008	1		
	6706	1		3508	1		
	6709-6710	2		3503-3504	2		
	3004	1		3506	1		
	7003	1		3812	1		
4.15	18607	1		3810	1		
	6201-6204	4		3807	1		
	6102	1		3811	1		
	6104	1		3808	1		
	5904	1		4.19	3010	1	
	5804	1		3012	1		
				3014	1		

RIGHT-OF-WAY				614.0605			
PLAT		MARKER POSTS		RIGHT OF WAY		EACH	
SHEET	POINT	NUMBER	RIGHT OF WAY	SHEET	POINT	NUMBER	RIGHT OF WAY
4.19 (cont'd)	3040	1		4.20	17403-17404	2	
	3206	1		2306-2307	2		
	3016	1		3041	1		
	3015	1		3017	1		
	3205	1		2310-2311	2		
	3205	1		2201	1		
	3039	1		2203	1		
	3013	1		3203-3204	2		
	3011	1		3207-3211	5		
	3009	1		4.21	3018-3019	2	
				2001-2002	2		
				2105-2106	2		
				3020	1		
				3042	1		
				4.22	1606	1	
				1600-1601	2		
				1504	1		
				1301	1		
				1203-1205	3		
				2102-2104	3		
				3021-3022	2		
				2003-2007	5		
				4.23	3029	1	
				3027	1		
				3024-3025	2		
				1302	1		

RIGHT-OF-WAY				614.0605			
PLAT		MARKER POSTS		RIGHT OF WAY		EACH	
SHEET	POINT	NUMBER	RIGHT OF WAY	SHEET	POINT	NUMBER	RIGHT OF WAY
4.23 (cont'd)	1304-1305	2		4.23	3040	1	
	21001	1			3206	1	
	3026	1			3016	1	
	3028	1			3015	1	
4.24	510-515	6			3205	1	
	502-503	2			3205	1	
	522-523	2			3039	1	
	531	1			3013	1	
	22311	1			3011	1	
	22310	1			3009	1	
	3030-3031	2					
	21002	1					
	21006	1					
	1107-1108	2					
	1103-1104	2					
	1101	1					
4.25	20201-20203	3					
	602	1					
	21101	1					
	20312	1					
	21014	1					
	21009	1					
	22309	1					
4.26	501	1					
	3032-3033	2					
	517-518	2					
4.27	108	1					
	15802	1					
	402	1					
	311	1					
4.28	303-310	8					
	111	1					
	103	1					
	109	1					
TOTAL		226					

REVISION DATE: 5/25/07
REVISION NOTE: ITEMS HIGHLIGHTED
REFLECT PLAN REVISIONS.

NOTE: ALL QUANTITIES ARE
CATEGORY 0010 UNLESS OTHERWISE
NOTED

RESTORATION

[illegible]

REVISION DATE: 5/25/07

REVISION NOTE: ITEMS HIGHLIGHTED REFLECT PLAN REVISIONS.

CONTINUED ON NEXT PAGE

NOTE: ALL QUANTITIES ARE CATEGORY 0010 UNLESS OTHERWISE NOTED

PROJECT NUMBER: 3180-10-70			
HWY: BURLINGTON BYPASS			
COUNTY: RACINE			
MISCELLANEOUS QUANTITIES			
SHEET NO: 221			

FILE NAME: S:\DOT\DOT_SE\04081\WORK FOR
09\ESTIMATES\04081_MISCQUANT_09.ppt

ORIGINATOR: JUSTIN M. ARNDT

ORIG. DATE: MARCH 3, 2006

PLOTTED DATE: 6/13/2007 11:44 AM

ADD #1
REV SHT 222
6/29/2007

REVISION NOTE: ITEMS HIGHLIGHTED REFLECT PLAN REVISIONS.

PLOTTED DATE: 6/13/2007 11:44 AM

ORIGINATOR: JUSTIN M. ARNDT

FILE NAME: S:\DOT\DOT_SE\04081\WORK FOR
09\ESTIMATES\04081_MISCQUANT_09.ppt

COUNTY: RACINE

MISCELLANEOUS QUANTITIES

SHEET NO: 222

625.0100	625.0500	627.0200	631.1000	629.0210	629.0205	630.0120	630.0130	630.0300	SEEDING																		
									SEEDING MIXTURE					SEEDING MIXTURE													
									NO.	20	LB	NO.	30	PIT	LB	NO.	30	PIT									
STATION										OFFSET	LOCATION	TOPSOIL		SALVAGED		MULCHING		SOD		FERTILIZER		FERTILIZER		SEEDING			
101+08 - 117+54										LT	STH 142	SY	SY	1,056		1,056		SY	SY	0.73		0.73		19.38			
101+08 - 117+54										RT	STH 142			1,056		1,056				0.73		0.73		19.38			
120+27 - 143+39										LT	STH 142			1,484		1,484				1.01		1.01		27.21			
120+27 - 143+39										RT	STH 142			1,484		1,484				1.01		1.01		27.21			
50+24 - 60+14										LT	STH 142 NE RAMP			924		924				0.63		0.63		16.95			
50+24 - 59+65										RT	STH 142 NE RAMP			769		769				0.52		0.52		14.09			
50+70 - 60+03										MEDIAN	STH 142 NE RAMP	1,888		1,888				1.30		1.30		51.61					
39+40 - 49+86										RT	STH 142 SW RAMP			977		977				0.68		0.68		17.91			
39+52 - 49+30										MEDIAN	STH 142 SW RAMP	1,949		1,949				1.34		1.34		53.30					
39+90 - 49+55										LT	STH 142 SW RAMP			789		789				0.55		0.55		14.46			
100+75 - 104+25										RT	MT TOM RD			201		201				0.14		0.14		3.67			
100+91 - 104+25										LT	MT TOM RD			191		191				0.13		0.13		3.50			
115+67 - 126+85										RT	STH 11			574		574				0.39		0.39		10.53			
115+67 - 126+85										LT	STH 11			574		574				0.39		0.39		10.53			
129+71 - 133+02										RT	STH 11			170		170				0.12		0.12		3.11			
133+65 - 161+00										RT	STH 11			1,404		1,404				0.96		0.96		25.75			
142+00 - 168+00										LT	STH 11			1,335		1,335				0.92		0.92		24.48			
91+00 - 100+34										LT	KETTERHAGEN RD	8,296		8,831		8,831				6.10		6.10		242.40			
91+00 - 100+34										RT	KETTERHAGEN RD	7,892		8,425		8,425				5.85		5.85		230.30			
102+51 - 110+75										LT	KETTERHAGEN RD	6,385		6,857		6,857				4.71		4.71		187.42			
102+51 - 110+75										RT	KETTERHAGEN RD	6,130		6,601		6,601				4.53		4.53		180.44			
37+69 - 52+32										LT	CTH A	785		785		785				0.53		0.53		14.40			
37+69 - 52+32										RT	CTH A	785		844		844				0.58		0.58		15.48			
54+52 - 70+25										LT	CTH A																
54+52 - 64+50										RT	CTH A			392		392				0.27		0.27		7.18			
48+00 - 49+79										LT	OLD CTH A			102		102				0.07		0.07		1.87			
48+00 - 49+79										RT	OLD CTH A			102		102				0.07		0.07		1.87			
40+43 - 49+00										RT	CTH A SE RAMP			800		800				0.55		0.55		14.67			
40+71 - 49+00										LT	CTH A SE RAMP			774		774				0.53		0.53		14.19			
40+43 - 49+00										MEDIAN	CTH A SE RAMP	1,767		1,767		1,767				1.21		1.21		22.70			
50+24 - 58+14										LT	CTH A NW RAMP			737		737				0.50		0.50		13.52			
50+24 - 58+14										RT	CTH A NW RAMP			737		737				0.50		0.50		13.52			
50+62 - 58+06										MEDIAN	CTH A NW RAMP			1512		1512				1.04		1.04		1.90			
50+18 - 52+00										LT	RIVER RD			104		104				0.08		0.08		1.18			
50+88 - 52+00										RT	RIVER RD			64		64				0.04		0.04		1.18			
196+00 - 204+10										RT	STH 36/83 NB-SB RAMP			747		747				0.51		0.51		14.00			
198+00 - 201+35										LT	STH 36/83 NB-SB RAMP			329		329				0.23		0.23		6.02			
UNDISTRIBUTED										BORROW PIT		13,417		250379		1100		173		1		3073		2426			
TOTAL												16253		89457		250379		1100		173		1		3073		2426	
																								370			
																								370.00			

EROSION CONTROL

STATION	OFFSET	LOCATION	EACH	LF	LF	MAINTENANCE	TYPE B	SY	CLASS I	EROSION MAT	EROSION MAT	TEMPORARY	SOD	EROSION	CONTROL	FABRIC	TYPE FF
340+80 - 352+00	LT	STH 83	278	278	1,006	93	21	21	21	21	21	21	21	21	21	21	21
340+80 - 352+00	RT	STH 83	170	170	1,109	80	42	42	42	42	42	42	42	42	42	42	42
353+00 - 369+35	LT	STH 83	526	526	748	67	11	11	11	11	11	11	11	11	11	11	11
353+00 - 369+35	RT	STH 83	889	889	152	1,105	392	392	392	392	392	392	392	392	392	392	392
97+00 - 104+50	LT	BREVER RD	762	762	1,673	144	21	21	21	21	21	21	21	21	21	21	21
97+00 - 104+50	RT	BREVER RD	536	536	5,909	16	68	68	68	68	68	68	68	68	68	68	68
106+00 - 118+00	LT	BREVER RD	605	605	5,026	21	11	11	11	11	11	11	11	11	11	11	11
106+00 - 118+00	RT	BREVER RD	5051	5051	6,474	48	389	389	389	389	389	389	389	389	389	389	389
99+00 - 100+50	LT	KETTERHAGEN RD	356	356	4,425	84	19	19	19	19	19	19	19	19	19	19	19
99+00 - 100+50	RT	KETTERHAGEN RD	307	307	4,500	108	65	65	65	65	65	65	65	65	65	65	65
102+00 - 110+75	LT	KETTERHAGEN RD	140	1,107	9,974	456	250	250	250	250	250	250	250	250	250	250	250
102+00 - 110+75	RT	KETTERHAGEN RD	501	5,536	49,700	2,100	400	400	400	400	400	400	400	400	400	400	400
1326+00 - 1334+00	LT	BYPASS															
1326+00 - 1334+00	RT	BYPASS															
UNDISTRIBUTED																	
TOTAL																	

ADD #1
REV SHT 223
6/29/2007

FIELD FACILITIES

LOCATION	642.5401	642.6001
PROJECT 3180-10-70	1	1
TOTAL	1	1

INLET PROTECTION

628.7005 *	628.7010	628.7015
INLET	INLET	INLET
PROTECTION	PROTECTION	PROTECTION
TYPE A	TYPE B	TYPE C
EACH	EACH	EACH
54	15	149
SEE DRAINAGE TABLE FOR LOCATIONS		
TOTAL		
54	15	149
* QUANTITIES LISTED ELSEWHERE		

INLET PROTECTION

628.7005 *	628.7010	628.7015	628.7550
INLET	INLET	INLET	CULVERT
PROTECTION	PROTECTION	PROTECTION	PIPE
TYPE A	TYPE B	TYPE C	DITCH CHECK
EACH	EACH	EACH	EACH
54	15	149	10
SEE DRAINAGE TABLE FOR LOCATIONS			
UNDISTRIBUTED			
TOTAL			
54	15	149	10
* QUANTITIES LISTED ELSEWHERE			

REVISION DATE: 5/25/07
REVISION NOTE: ITEMS
HIGHLIGHTED REFLECT PLAN
REVISIONS.

LANDMARK REFERENCE MONUMENTS

STATION	LOCATION	RDWY	LANDMARK REFERENCE MONUMENTS EACH
1128+99.48	PC	BYPASS R/L	1
1149+27.38	PT	BYPASS R/L	1
1237+87.99	PC	BYPASS R/L	1
1261+69.12	PT	BYPASS R/L	1
1316+73.01	PI	BYPASS R/L	1
1331+50.03	PC	BYPASS R/L	1
1370+04.32	PT	BYPASS R/L	1
1387+17.67	PC	BYPASS R/L	1
1410+56.99	PT	BYPASS R/L	1
345+00.00	PI	STH 83 R/L	1
349+21.11	PI	STH 83 R/L	1
358+57.12	PI	STH 83 R/L	1
106+20.48	PI	STH 142 R/L	1
132+33.29	PI	STH 142 R/L	1
140+24.74	PI	STH 142 R/L	1
119+45.90	PI	STH 11 R/L	1
121+86.20	PI	STH 11 R/L	1
133+78.25	PI	STH 11 R/L	1
135+50.00	PI	STH 11 R/L	1
137+90.30	PI	STH 11 R/L	1
152+90.76	PI	STH 11 R/L	1
166+33.80	PI	STH 11 R/L	1
TOTAL			22

MOBILIZATIONS

619.1000	628.1905
MOBILIZATION	MOBILIZATIONS
EACH	EROSION CONTROL
1	EACH
1	10
1	10
15	15

NOTE: ALL QUANTITIES ARE CATEGORY 0010 UNLESS OTHERWISE NOTED

RIPRAP MEDIUM AND GEOTEXTILE FABRIC TYPE HR

* QUANTITIES LISTED ELSEWHERE

REVISION NOTE: ITEMS HIGHLIGHTED REFLECT REVISIONS.

STONE OR ROCK DITCH CHECKS & GEOTEXTILE FABRIC SAS

TOTAL

DELINEATOR POSTS STEEL & DELINEATORS

633.0100		633.0500	
DELINEATOR		DELINEATORS	
POSTS	WHITE	YELLOW	
STEEL			
EACH	EACH	EACH	EACH
STATION	- STATION	LOCATION	
1129+00	- 1132+00	RT	EB BYPASS
1143+40	- 1149+50	RT	EB BYPASS
1143+30	- 1149+50	RT	WB BYPASS
52+00	- 60+00	LT	STH 142 NE RAMP
39+50	- 48+80	RT	STH 142 SW RAMP
1237+80	- 1262+30	RT	EB BYPASS
1237+80	- 1262+30	RT	WB BYPASS
1314+70	- 1318+65	RT	EB BYPASS
1314+70	- 1318+70	RT	WB BYPASS
1331+50	- 1370+20	RT	EB BYPASS
1331+50	- 1369+50	RT	WB BYPASS
51+50	- 58+00	LT	CTH A NW RAMP
39+60	- 47+83	RT	CTH A SE RAMP
1382+50	- 1389+40	LT	EB BYPASS
1394+20	- 1412+50	LT	EB BYPASS
1398+50	- 1408+60	LT	WB BYPASS
206+00	- 209+00	RT	STH 36/83 NB TO SB RAMP
213+80	- 220+80	RT	STH 36/83 NB TO SB RAMP
198+00	- 207+00	RT	STH 36/83 SB RAMP
		291	182
		109	109

PROJECT NUMBER: 3180-10-70			
HWY: BURLINGTON BYPASS		COUNTY: RACINE	
		MISCELLANEOUS QUANTITIES	
			SHEET NO: 224

NOTE: ALL QUANTITIES ARE
CATEGORY 0010 UNLESS
OTHERWISE NOTED

REVISION DATE: 5/25/07

REVISION NOTE: ITEMS
HIGHLIGHTED REFLECT PLAN
REVISIONS AND ADDITIONS.

SIGNS REMOVED FROM THIS
SHEET:
P060A,P060B,P062,P063,P065,P
066,P067A,P067B & P068

ADD #1
REV SHT 225
6/29/2007

PERMANENT SIGNING													
SIGN #	SIGN CODE	SIGN SIZE IN	634.0614 POSTS WOOD 4x6-Inch x 14 Ft EACH	634.0616 POSTS WOOD 4x6-Inch x 16 Ft EACH	634.0618 POSTS WOOD 4x6-Inch x 18 Ft EACH	634.0620 POSTS WOOD 4x6-Inch x 20 Ft EACH	634.0622 POSTS WOOD 4x6-Inch x 22 Ft EACH	634.0814 POSTS TUBULAR STEEL 2x2-Inch x 14 Ft EACH	637.0202 SIGNS REFLECTIVE TYPE II SF	638.2602 REMOVING SIGNS TYPE II EACH	638.3000 REMOVING SMALL SIGN SUPPORT EACH	SPV.0165.03 COVER SIGNS TYPE II SF	SHARED POST # OR REMARKS
P067	R6-2L	36 X 48	1						12.00				SEE DETAIL
P061	D1-1	96 X 21	2						14.00				2 MOUNTING HEIGHT
P064	W12-1	24 X 24	1						4.00				SEE DETAIL
P069	M1-94	108 X 21	2						15.75				
P070	R3-56	36 X 48		1					12.00				
P071	J3-1	36 X 81			1								Place Assembly Under Signal P071
									9.00				ASSEMBLY "11" P071
									3.13				ASSEMBLY "WEST" P071
									6.25				ASSEMBLY LT ARROW P071
P072	R6-2L	24 X 30	1						5.00				
P073	R6-2L	24 X 30	1						5.00				
P074	R6-2L	24 X 30	1						5.00				
P075	R6-2L	24 X 30	1						5.00				
P076	D1-1	96 X 21	2						14.00				
P076A	M1-94	84 X 21	2						12.25				
P077	W13-2A	48 X 90		1					30.00				10 MPH Modified for Right Turn
P078	W4-2R	48 X 48		1					16.00				
P079	W4-3	48 X 48		1					16.00				Double Post Assembly P088
P080	W1-6	60 X 30	1						12.50				ASSEMBLY "83" P088
P083	W1-6	60 X 30	1						12.50				ASSEMBLY "50" P088
P084	W4-3	48 X 48		1					16.00				ASSEMBLY "SOUTH" P088
P085	W4-2R	48 X 48		1					16.00				ASSEMBLY "TO" P088
P088	J2-2	72 X 81		2					9.00				ASSEMBLY LT TURN ARROW P088
	M1-6	36 X 36							9.00				ASSEMBLY LT TURN ARROW P088
	M1-6	36 X 36							9.00				SEE DETAIL
	M3-4	30 X 15							3.13				SEE DETAIL
	M3-3	30 X 15							3.13				
	M5-1L	30 X 30							6.25				
	M5-1L	30 X 30							6.25				
P089	M1-94	72 X 21	2						10.50				
P090	M1-94	72 X 21	2						10.50				
P091	W20-7b	48 X 48		1					16.00				
P092	W20-7b	48 X 48		1					16.00				
P093	J3-2	72 X 81		2					9.00				Double Post Assembly P093
	M1-6	36 X 36							9.00				ASSEMBLY "11" P093
	M1-6	36 X 36							9.00				ASSEMBLY "36" P093
	M3-4	30 X 15							3.13				ASSEMBLY "WEST" P093
	M3-3	30 X 15							3.13				ASSEMBLY "SOUTH" P093
	M6-1	30 X 30							6.25				ASSEMBLY FORWARD ARROW P093
	M6-1	30 X 30							6.25				ASSEMBLY FORWARD ARROW P093
	M06-1	30 X 30							6.25				ORANGE TEMP RT ARROW P093
	M06-1	30 X 30							6.25				ORANGE TEMP RT ARROW P093
	M4-5	30 X 15							3.13				SEPARATE SIGN "TO" P093
	M4-5	30 X 15							3.13				SEPARATE SIGN "TO" P093
P094	D1-1	96 X 21						1	14.00				SEE DETAIL
P095	M1-94	60 X 21						1	8.75				SEE DETAIL
P096	D1-1	108 X 21	2						15.75				SEE DETAIL
P097	R3-56	36 X 48		1					12.00				
P098	R6-2L	36 X 48		1					12.00				
P099	R6-2L	36 X 48		1					12.00				
P100A	R5-1	36 X 36							9.00				PLACE ON SIGNAL POLE
P100B	R5-1	36 X 36							9.00				PLACE ON SIGNAL POLE
P101	W12-1D	24 X 24	1						4.00				2 MOUNTING HEIGHT
P102A	R1-1F	36 X 36	1						9.00				PLACE ON SIGNAL POLE
P102B	R1-1F	36 X 36	1						9.00				PLACE ON SIGNAL POLE
P103	J3-1	36 X 81		1									Single Post Assembly P103
	M1-6	36 X 36							9.00				ASSEMBLY "83" P103
	M3-3	30 X 15							3.13				ASSEMBLY "south" P103
	M6-1	30 X 30							6.25				ASSEMBLY RIGHT ARROW P103
P104	R4-7	36 X 48	1						12.00				P103

PROJECT NUMBER: 3180-10-70

HWY: BURLINGTON BYPASS

COUNTY: RACINE

MISCELLANEOUS QUANTITIES

SHEET NO: 225

E

PERMANENT SIGNING (CONTINUED)													PROJECT NUMBER: 3180-10-70		HWY: BURLINGTON BYPASS		COUNTY: RACINE		MISCELLANEOUS QUANTITIES		SHEET NO: 226		E
SIGN #	SIGN CODE	SIGN SIZE	634.0614	634.0616	634.0618	634.0620	634.0622	634.0814	637.0202	638.2602	638.3000	SPV.0165.03	REMARKS	SHARED POST #	OR	REVISION DATE: 5/25/07	REVISION NOTE: FOR THE SIGNS SHOWN ON THIS SHEET, NO CHANGES HAVE BEEN MADE						
P105	J4-3	36 X 51	1						9.00				Single Post Assembly P105										
	M1-6	36 X 36							9.00				ASSEMBLY "R3" P105										
	M1-6	36 X 36							9.00				ASSEMBLY "36" P105 COVER										
	M1-6	36 X 36							9.00				ASSEMBLY "11" P105 COVER										
	M3-1	30 X 15							3.13				ASSEMBLY "NORTH" P105										
P106A	M3-2	30 X 15							3.13				ASSEMBLY "NORTH" P105 COVER										
P106B	R2-1	36 X 48	1						12.00				ASSEMBLY "EAST" P105 COVER										
P107	R5-1A	42 X 30	1						8.75														
P108	R3-55L	36 X 48							12.00														
P109	J3-2	72 X 81	1						9.00				Double Post Assembly P109										
	M1-6	36 X 36							9.00				ASSEMBLY "R3" P109										
	M1-6	36 X 36							9.00				ASSEMBLY "50" P109										
	M3-3	30 X 15							3.13				ASSEMBLY "SOUTH" P109										
	M4-5	30 X 15							3.13				ASSEMBLY "TO" P109										
	M6-1	30 X 30							6.25				ASSEMBLY LT ARROW P109										
	M6-1	30 X 30							6.25				ASSEMBLY LT ARROW P109										
P110A	J2-2	72 X 81	1						9.00				Double Post Assembly P110A										
	M1-6	36 X 36							9.00				ASSEMBLY "R3" P110A										
	M1-6	36 X 36							9.00				ASSEMBLY "50" P110A										
	M3-3	30 X 15							3.13				ASSEMBLY "SOUTH" P110A										
	M4-5	30 X 15							3.13				ASSEMBLY "TO" P110A										
	M5-1L	30 X 30							6.25				ASSEMBLY LT TURN ARROW P110A										
	M5-1L	30 X 30							6.25				ASSEMBLY LT TURN ARROW P110A										
P110B	J2-2	72 X 81	2						9.00				Double Post Assembly P110B										
	M1-6	36 X 36							9.00				ASSEMBLY "11" P110B										
	M1-6	36 X 36							9.00				ASSEMBLY "36" P110B										
	M3-4	30 X 15							3.13				ASSEMBLY "WEST" P110B										
	M3-3	30 X 15							3.13				ASSEMBLY "SOUTH" P110B										
	M6-1	30 X 30							6.25				ASSEMBLY FORWARD ARROW P110B										
	M6-1	30 X 30							6.25				ASSEMBLY FORWARD ARROW P110B										
	M05-1R	30 X 30							6.25				ORANGE TEMP RT TURN ARROW P110B										
	M05-1R	30 X 30							6.25				ORANGE TEMP RT TURN ARROW P110B										
	M4-5	30 X 15							3.13				SEPARATE SIGN "TO" P110B										
P111A	W3-3	36 X 36	1						9.00				SEPARATE SIGN "TO" P110B										
P111B	W3-3	36 X 36	1						9.00				16" X 16" FLAGS REQD										
P112A	R2-1	36 X 48	1						12.00				16" X 16" FLAGS REQD										
P112B	R2-1	36 X 48	1						12.00														
P113	R1-2	36 X 31	1						3.88														
P114	W13-2A	48 X 90	1						30.00				10 MPH Modified for Right Turn										
P115	D1-1	96 X 21	2						14.00				SEE DETAIL										
P115A	M1-94	84 X 21	2						12.25				SEE DETAIL										
P116A	J1-1	36 X 57	1						9.00				Single Post Assembly P116A										
	M1-6	36 X 36							4.38				ASSEMBLY "142" P116A										
P116B	J1-1	36 X 57	1						9.00				Single Post Assembly P116B										
	M1-6	36 X 36							9.00				ASSEMBLY "JCT" P116B										
	M2-1	30 X 21							4.38				ASSEMBLY "142" P116B										
P117A	J2-1	36 X 81	1						9.00				Single Post Assembly P117A										
	M1-6	36 X 36							9.00				ASSEMBLY "142" P117A										
	M4-5	30 X 15							3.13				ASSEMBLY "TO" P117A										
	M5-1R	30 X 30							6.25				ASSEMBLY RT TURN ARROW P117A										
P117B	J2-1	36 X 81	1						9.00				Single Post Assembly P117B										
	M1-6	36 X 36							9.00				ASSEMBLY "142" P117B										
	M4-5	30 X 15							3.13				ASSEMBLY "TO" P117B										
P118A	R2-1	36 X 48	1						6.25				ASSEMBLY RT TURN ARROW P117B										
P118B	R2-1	36 X 48	1						12.00														

ADD #1
REV SHT 226
6/29/2007

PERMANENT SIGNING (CONTINUED)													
SIGN #	SIGN CODE	SIGN SIZE	634.0614 POSTS WOOD 4x6-Inch x 14 Ft EACH	634.0616 POSTS WOOD 4x6-Inch x 16 Ft EACH	634.0618 POSTS WOOD 4x6-Inch x 18 Ft EACH	634.0620 POSTS WOOD 4x6-Inch x 20 Ft EACH	634.0622 POSTS WOOD 4x6-Inch x 22 Ft EACH	634.0614 POSTS TUBULAR STEEL 2x2-Inch x 14 Ft EACH	REFLECTIVE TYPE II SF	REMOVING SIGNS TYPE II EACH	REMOVING SMALL SIGN SUPPORT EACH	638.3000 COVER SIGNS TYPE II SF	SPV.0165.03
P119	J3-1	36 X 81			1				9.00				Single Post Assembly P119 ASSEMBLY "142" P119
	M1-6	36 X 36							3.13				ASSEMBLY "TO" P119
	M4-5	30 X 15							6.25				ASSEMBLY RT ARROW P119
P120	M6-1	30 X 30			1								Triple Post Assembly P120
	J4-3	108 X 51							9.00				ASSEMBLY "83" P120
	M1-6	36 X 36							9.00			9.00	ASSEMBLY "11" P120 COVER
	M1-6	36 X 36							9.00			9.00	ASSEMBLY "36" P120 COVER
	M3-3	30 X 15							3.13				ASSEMBLY "SOUTH" P120
	M3-4	30 X 15							3.13				ASSEMBLY "WEST" P120 COVER
	M3-3	30 X 15							3.13			3.13	ASSEMBLY "SOUTH" P120 COVER
P121	J4-3	108 X 51				3							Triple Post Assembly P121
	M1-6	36 X 36							9.00				ASSEMBLY "83" P121
	M1-6	36 X 36							9.00				ASSEMBLY "11" P121
	M1-6	36 X 36							9.00				ASSEMBLY "36" P121
	M4-5	30 X 15							3.13				SEPARATE SIGN "TO" P121
	M4-5	30 X 15							3.13				SEPARATE SIGN "TO" P121
	M3-1	30 X 15							3.13				SEPARATE SIGN "NORTH" P121
	M3-2	30 X 15							3.13				SEPARATE SIGN "EAST" P121
	M3-1	30 X 15							3.13				SEPARATE SIGN "NORTH" P121
	M6-1	30 X 30							6.25				SEPARATE SIGN FORWARD ARROW P121
	M6-1	30 X 30							6.25				SEPARATE SIGN FORWARD ARROW P121
P122	J3-1	36 X 81			1								Single Post Assembly P122
	M1-6	36 X 36							9.00				ASSEMBLY "142" P122
	M4-5	30 X 15							3.13				ASSEMBLY "TO" P122
	M6-1	30 X 30							6.25				ASSEMBLY RT ARROW P122
P125A	R2-1	36 X 48		1					12.00				Single Post Assembly P126A
P125B	R2-1	36 X 48		1					12.00				ASSEMBLY "142" P126A
P126A	J2-1	36 X 81			1								ASSEMBLY RT TURN ARROW P126A
	M1-6	36 X 36							9.00				ASSEMBLY "TO" P126A
	M4-5	30 X 15							3.13				ASSEMBLY "TO" P126A
P126B	J2-1	36 X 81							6.25				ASSEMBLY RT TURN ARROW P126B
	M1-6	36 X 36							9.00				Single Post Assembly P126B
	M4-5	30 X 15							3.13				ASSEMBLY "142" P126B
	M5-1R	30 X 30							6.25				ASSEMBLY "TO" P126B
P127A	J1-1	36 X 57											ASSEMBLY RT TURN ARROW P127A
	M1-6	36 X 36							9.00				Single Post Assembly P127A
	M2-1	30 X 21							4.38				ASSEMBLY "JCT" P127A
P127B	J1-1	36 X 57											Single Post Assembly P127B
	M1-6	36 X 36							9.00				ASSEMBLY "142" P127B
	M2-1	30 X 21							4.38				ASSEMBLY "JCT" P127B
P128	R3-4B	36 X 48	1						12.00				Single Post Assembly P133A
P129	R3-4B	36 X 48	1						12.00				ASSEMBLY "11" P133A
P133A	J1-1	36 X 57											ASSEMBLY "JCT" P133A
	M1-6	36 X 36							9.00				Single Post Assembly P133B
	M2-1	30 X 21							4.38				ASSEMBLY "11" P133B
P133B	J1-1	36 X 57											Single Post Assembly P133B
	M1-6	36 X 36							9.00				ASSEMBLY "JCT" P133B
	M2-1	30 X 21							4.38				16" X 16" FLAGS REQD
P134A	W3-3	36 X 36		1					9.00				16" X 16" FLAGS REQD
P134B	W3-3	36 X 36		1					9.00				Double Post Assembly P136A
P135A	W20-7b	48 X 48		1					16.00				ASSEMBLY "11" P136A
P135B	W20-7b	48 X 48		1					16.00				ASSEMBLY "WEST" P136A
P136A	J2-2	72 X 81		1									ASSEMBLY "EAST" P136A
	M1-6	36 X 36							9.00				ASSEMBLY LT TURN ARROW P136A
	M1-6	36 X 36							9.00				
	M3-4	30 X 15							3.13				
	M3-2	30 X 15							3.13				
	M5-1L	30 X 30							6.25				

NOTE: ALL QUANTITIES ARE CATEGORY 0010 UNLESS OTHERWISE NOTED

REVISION DATE: 5/25/07

REVISION NOTE: FOR THE SIGNS SHOWN ON THIS SHEET, NO CHANGES HAVE BEEN MADE

ADD #1
REV SHT 227
6/29/2007

MISCELLANEOUS QUANTITIES

COUNTY: RACINE

HWY: BURLINGTON BYPASS

PROJECT NUMBER: 3180-10-70

SHEET NO: 227

E

ORIG. DATE: 6/13/2007 11:44 AM

ORIGINATOR: JUSTIN M. ARNDT

FILE NAME: S:\DOT\DOT_SEG\0481\WORK FOR 09\ESTIMATES\0481_MISQUANT_09.ppt

PERMANENT SIGNING (CONTINUED)													
SIGN #	SIGN CODE	SIGN SIZE IN	634.0614 POSTS WOOD 4x6-inch x 14 Ft EACH	634.0616 POSTS WOOD 4x6-inch x 16 Ft EACH	634.0618 POSTS WOOD 4x6-inch x 18 Ft EACH	634.0620 POSTS WOOD 4x6-inch x 20 Ft EACH	634.0622 POSTS WOOD 4x6-inch x 22 Ft EACH	634.0814 POSTS TUBULAR STEEL 2x2-inch x 14 Ft EACH	637.0202 REFLECTIVE TYPE II SF	638.2602 REMOVING SIGNS TYPE II EACH	638.3000 REMOVING SMALL SIGN SUPPORT EACH	SPV.0165.03 COVER SIGNS TYPE II SF	REMARKS
P119	J3-1	36 X 81			1				9.00				Single Post Assembly P119
	M1-6	36 X 36							3.13				ASSEMBLY "142" P119
	M4-5	30 X 15							6.25				ASSEMBLY "TO" P119
P120	M6-1	30 X 30			1								ASSEMBLY RT ARROW P119
	J4-3	108 X 51											Triple Post Assembly P120
	M1-6	36 X 36							9.00				ASSEMBLY "83" P120
	M1-6	36 X 36							9.00				ASSEMBLY "11" P120 COVER
	M1-6	36 X 36							9.00				ASSEMBLY "36" P120 COVER
	M3-3	30 X 15							3.13				ASSEMBLY "SOUTH" P120
	M3-4	30 X 15							3.13				ASSEMBLY "WEST" P120 COVER
	M3-3	30 X 15							3.13				ASSEMBLY "SOUTH" P120 COVER
P121	J4-3	108 X 51				3							Triple Post Assembly P121
	M1-6	36 X 36							9.00				ASSEMBLY "83" P121
	M1-6	36 X 36							9.00				ASSEMBLY "11" P121
	M1-6	36 X 36							9.00				ASSEMBLY "36" P121
	M4-5	30 X 15							3.13				SEPARATE SIGN "TO" P121
	M4-5	30 X 15							3.13				SEPARATE SIGN "TO" P121
	M3-1	30 X 15							3.13				SEPARATE SIGN "NORTH" P121
	M3-1	30 X 15							3.13				SEPARATE SIGN "EAST" P121
	M3-1	30 X 15							3.13				SEPARATE SIGN "NORTH" P121
	M8-1	30 X 30							6.25				SEPARATE SIGN FORWARD ARROW P121
	M8-1	30 X 30							6.25				SEPARATE SIGN FORWARD ARROW P121
P122	J3-1	36 X 81			1								Single Post Assembly P122
	M1-6	36 X 36							9.00				ASSEMBLY "142" P122
	M4-5	30 X 15							3.13				ASSEMBLY "TO" P122
	M6-1	30 X 30							6.25				ASSEMBLY RT ARROW P122
P125A	R2-1	36 X 48		1					12.00				Single Post Assembly P126A
P125B	R2-1	36 X 48		1					12.00				ASSEMBLY "142" P126A
P126A	J2-1	36 X 81			1								ASSEMBLY "TO" P126A
	M1-6	36 X 36							9.00				ASSEMBLY "TO" P126A
	M5-1R	30 X 30							3.13				ASSEMBLY RT TURN ARROW P126A
P126B	J2-1	36 X 81			1				6.25				ASSEMBLY RT TURN ARROW P126B
	M1-6	36 X 36							9.00				ASSEMBLY "142" P126B
	M4-5	30 X 15							3.13				ASSEMBLY "TO" P126B
	M5-1R	30 X 30							6.25				ASSEMBLY RT TURN ARROW P126B
P127A	J1-1	36 X 57			1								Single Post Assembly P127A
	M1-6	36 X 36							9.00				ASSEMBLY "142" P127A
	M2-1	30 X 21							4.38				ASSEMBLY "JCT" P127A
P127B	J1-1	36 X 57			1								Single Post Assembly P127B
	M1-6	36 X 36							9.00				ASSEMBLY "142" P127B
	M2-1	30 X 21							4.38				ASSEMBLY "JCT" P127B
P128	R3-4B	36 X 48	1						4.38				Single Post Assembly P133A
P129	R3-4B	36 X 48	1						12.00				ASSEMBLY "11" P133A
P133A	J1-1	36 X 57			1								ASSEMBLY "JCT" P133A
	M1-6	36 X 36							9.00				ASSEMBLY "TO" P133A
P133B	J1-1	36 X 57			1				4.38				ASSEMBLY "JCT" P133B
	M1-6	36 X 36							9.00				ASSEMBLY "11" P133B
	M2-1	30 X 21							4.38				ASSEMBLY "JCT" P133B
P134A	W3-3	36 X 36		1					9.00				16" X 16" FLAGS RECD
P134B	W3-3	36 X 36		1					9.00				16" X 16" FLAGS RECD
P135A	W20-7b	48 X 48		1					16.00				Double Post Assembly P136A
P135B	W20-7b	48 X 48		1					16.00				ASSEMBLY "11" P136A
P136A	J2-2	72 X 81		1					9.00				ASSEMBLY "WEST" P136A
	M1-6	36 X 36							9.00				ASSEMBLY "EAST" P136A
	M1-6	36 X 36							9.00				ASSEMBLY "TO" P136A
	M3-4	30 X 15							3.13				ASSEMBLY "TO" P136A
	M3-2	30 X 15							3.13				ASSEMBLY "TO" P136A
	M5-1L	30 X 30							6.25				ASSEMBLY LT TURN ARROW P136A

NOTE: ALL QUANTITIES ARE CATEGORY 0010 UNLESS OTHERWISE NOTED

REVISION DATE: 5/25/07

REVISION NOTE: FOR THE SIGNS SHOWN ON THIS SHEET, NO CHANGES HAVE BEEN MADE

ADD #1
REV SHT 228
6/29/2007

SHEET NO: 228

MISCELLANEOUS QUANTITIES

COUNTY: RACINE

HWY: BURLINGTON BYPASS

PROJECT NUMBER: 3180-10-70

ORIG. DATE: 6/13/2007 11:44 AM

DATE: MARCH 3, 2006

ORIGINATOR: JUSTIN M. ARNOT

FILE NAME: S:\DOT\DOT_SEG\0481\WORK\FOR 09ESTIMATES\0481_MISQUANT_09.ppt

NOTE: ALL QUANTITIES ARE
CATEGORY 0010 UNLESS
OTHERWISE NOTED

REVISION DATE: 5/25/07

REVISION NOTE: FOR THE
SIGNS SHOWN ON THIS
SHEET, NO CHANGES HAVE
BEEN MADE

ADD #1
REV SHT 229
6/29/2007

PERMANENT SIGNING (CONTINUED)													
SIGN #	SIGN CODE	SIGN SIZE IN	634.0614 POSTS WOOD 4x6-Inch x 14 Ft EACH	634.0616 POSTS WOOD 4x6-Inch x 16 Ft EACH	634.0618 POSTS WOOD 4x6-Inch x 18 Ft EACH	634.0620 POSTS WOOD 4x6-Inch x 20 Ft EACH	634.0622 POSTS WOOD 4x6-Inch x 22 Ft EACH	634.0814 POSTS TUBULAR STEEL 2x2-Inch x 14 Ft EACH	637.0202 REFLECTIVE TYPE II SF	638.2602 REMOVING SIGNS TYPE II EACH	638.3000 REMOVING SMALL SIGN SUPPORT EACH	SPV.0165.03 COVER SIGNS TYPE II SF	SHARED POST # OR REMARKS
P136B	M5-1R	30 X 30		1					6.25				ASSEMBLY RT TURN ARROW P136A Double Post Assembly P136B ASSEMBLY "11" P136B ASSEMBLY "11" P136B ASSEMBLY "WEST" P136B
	M5-2	30 X 15							3.13				ASSEMBLY "EAST" P136B
P137	M5-1R	30 X 30	2						6.25				ASSEMBLY LT TURN ARROW P136B
P137A	M1-94	84 X 21	2						36.00				ASSEMBLY RT TURN ARROW P136B
P138	J3-1	36 X 81	1						12.25				SEE DETAIL
	M1-6	36 X 36							9.00				Single Post Assembly P138
	M3-4	30 X 15							3.13				ASSEMBLY "11" P138
	M6-1	30 X 30							6.25				ASSEMBLY "WEST" P138
P139	R3-55L	36 X 48	1						12.00				ASSEMBLY LT ARROW P138
P140	R5-1A	36 X 24							6.00				P139
P141	R2-1	36 X 48	1						12.00				
P142	R2-1	36 X 48	1						12.00				
P146	J3-1	36 X 81	1										Single Post Assembly P146
	M1-6	36 X 36							9.00				ASSEMBLY "11" P146
	M3-2	30 X 15							3.13				ASSEMBLY "EAST" P146
P147A	M6-1	30 X 30	1						6.25				ASSEMBLY RT ARROW P146
	J4-3	108 X 51											Triple Post Assembly P147A
	M1-6	36 X 36							9.00				ASSEMBLY "83" P147A
	M1-6	36 X 36							9.00				ASSEMBLY "11" P147A COVER
	M1-6	36 X 36							9.00				ASSEMBLY "36" P147A COVER
	M3-3	30 X 15							3.13				ASSEMBLY "SOUTH" P147A
	M3-4	30 X 15							3.13				ASSEMBLY "WEST" P147A COVER
P147B	M3-3	30 X 15							3.13				ASSEMBLY "SOUTH" P147A COVER
	J4-3	108 X 51	1										Triple Post Assembly P147B
	M1-6	36 X 36							9.00				ASSEMBLY "83" P147B
	M1-6	36 X 36							9.00				ASSEMBLY "11" P147B COVER
	M1-6	36 X 36							9.00				ASSEMBLY "36" P147B COVER
	M3-3	30 X 15							3.13				ASSEMBLY "SOUTH" P147B
P148	M3-3	30 X 15							3.13				ASSEMBLY "WEST" P147B COVER
P149A	W12-1D	24 X 24	1						3.13				ASSEMBLY "SOUTH" P147B COVER
P149B	R5-1	36 X 36	1						4.00				
	R5-1	36 X 36	1						9.00				
P150	R1-1	36 X 36	1						9.00				
P151A	R1-1F	36 X 36							9.00				P149A
P151B	R1-1F	36 X 36							9.00				P149B
P152	R4-7	36 X 48	1						12.00				
P153A	R5-1	36 X 36	1						9.00				
P153B	R5-1	36 X 36	1						9.00				
P154	R1-1	36 X 36	1						9.00				
P155A	R1-1F	36 X 36							9.00				
P155B	R1-1F	36 X 36							9.00				
P156	R4-7	36 X 48	1						12.00				P153A
P157	W12-1D	24 X 24	1						4.00				P153B
P158	J4-1	36 X 81	1						9.00				Single Post Assembly P158
	M1-6	36 X 36							9.00				ASSEMBLY "11" P158
	M3-4	30 X 15							3.13				ASSEMBLY "WEST" P158
P159	M6-1	30 X 30							6.25				SEPARATE SIGN RT ARROW P158
	J3-1	36 X 81											Place Assembly Under Signal P159
	M1-6	36 X 36							9.00				ASSEMBLY "11" P159
	M3-2	30 X 15							3.13				ASSEMBLY "EAST" P159
	M6-1	30 X 30							6.25				ASSEMBLY LT ARROW P159
P160A	J4-2	72 X 51	1										Double Post Assembly P160A

PROJECT NUMBER: 3180-10-70

HWY: BURLINGTON BYPASS

COUNTY: RACINE

MISCELLANEOUS QUANTITIES

SHEET NO: 229

E

FILE NAME: S:\DOT\DOT_SEG\081\WORK FOR
09\ESTIMATES\0481_MISC\QUANT_09.ppt

ORIGINATOR: JUSTIN M. ARNOT

ORIG. DATE: MARCH 3, 2006

PLOTTED DATE: 6/13/2007 11:44 AM

SIGNS ADDED TO THIS SHEET:
P175C

SHEET NO: 230	E
---------------	---

MISCELLANEOUS QUANTITIES

PROJECT NUMBER: 3180-10-70

FILE NAME: S:\DOT\DOT_SE\04081\WORK FOR
09\ESTIMATES\04081_MISCQUANT_09.ppt

PERMANENT SIGNING (CONTINUED)												
SIGN #	SIGN CODE	SIGN SIZE	634.0614 POSTS WOOD 4x6-inch x 14 Ft EACH	634.0616 POSTS WOOD 4x6-inch x 16 Ft EACH	634.0620 POSTS WOOD 4x6-inch x 20 Ft EACH	634.0622 POSTS WOOD 4x6-inch x 22 Ft EACH	634.0814 POSTS TUBULAR STEEL 2x2-inch x 14 Ft EACH	637.0202 SIGN REFLECTIVE TYPE II SF	638.2602 REMOVING SIGN TYPE II EACH	638.3000 REMOVING SMALL SIGN SUPPORT EACH	COVER SIGN TYPE II SF	REMARKS
P176A	J2-1	36 X 81	1					9.00				Single Post Assembly P176A ASSEMBLY "A" P176A
	M1-6	36 X 36						3.13				Separate Sign "TO" P176A
	M4-5	30 X 15						3.13				ASSEMBLY RT TURN ARROW P176A
P176B	M5-1R	30 X 81	1					3.13				Single Post Assembly P176B
	M1-6	36 X 36						9.00				ASSEMBLY "A" P176B
	M4-5	30 X 15						3.13				Separate Sign "TO" P176B
P176C	J3-1	36 X 81	1					3.13				ASSEMBLY RT TURN ARROW P176B
	M1-6	36 X 36						9.00				Single Post Assembly P176C
	M4-5	30 X 15						3.13				ASSEMBLY "A" P176C
P176D	M6-1	30 X 30						6.25				Separate Sign "TO" P176C
P176E	W4-3	48 X 48	1					12.50				ASSEMBLY RT ARROW P176C
P178A	R2-1	36 X 48	1					12.00				
P178B	R2-1	36 X 48	1					12.00				
P178C	W4-3	48 X 48	1					16.00				Double Post Assembly P179A
P179A	J4-2	72 X 51	2					9.00				ASSEMBLY "83" P179A
	M1-6	36 X 36						9.00				ASSEMBLY "36" P179A
	M1-6	36 X 36						3.13				ASSEMBLY "SOUTH" P179A
	M3-3	30 X 15						3.13				ASSEMBLY "SOUTH" P179A
	M6-1	30 X 30						6.25				SEPARATE SIGN FORWARD ARROW P179A
P179B	J4-2	72 X 51	2					3.13				SEPARATE SIGN "TO" P179A
	M1-6	36 X 36						9.00				Double Post Assembly P179B
	M1-6	36 X 36						9.00				ASSEMBLY "83" P179B
	M3-3	30 X 15						3.13				ASSEMBLY "36" P179B
	M3-3	30 X 15						3.13				ASSEMBLY "SOUTH" P179B
	M6-1	30 X 30						6.25				SEPARATE SIGN FORWARD ARROW P179B
P179C	W4-3	48 X 48	1					16.00				SEPARATE SIGN "TO" P179B
P179D	J3-1	36 X 81	1					9.00				Single Post Assembly P180A
	M1-6	36 X 36						3.13				ASSEMBLY "A" P180A
	M4-5	30 X 15						3.13				Separate Sign "TO" P180A
P181A	M6-1	30 X 30	1					6.25				ASSEMBLY LT ARROW P180A
	J3-1	36 X 81						9.00				Single Post Assembly P181A
	M1-6	36 X 36						3.13				ASSEMBLY "A" P181A
	M4-5	30 X 15						3.13				Separate Sign "TO" P181A
P181B	W1-6	60 X 30	1					6.25				ASSEMBLY RT ARROW P181A
P181C	W4-3	48 X 48	1					12.50				
P183A	J4-2	72 X 51	2					16.00				Double Post Assembly P183A
	M1-6	36 X 36						9.00				ASSEMBLY "83" P183A
	M1-6	36 X 36						9.00				ASSEMBLY "36" P183A
	M3-1	30 X 15						3.13				ASSEMBLY "NORTH" P183A
	M3-1	30 X 15						3.13				ASSEMBLY "NORTH" P183A
	M6-1	30 X 30						6.25				SEPARATE SIGN FORWARD ARROW P183A
P183B	J4-2	72 X 51	2					3.13				SEPARATE SIGN "TO" P183A
	M1-6	36 X 36						9.00				Double Post Assembly P183B
	M1-6	36 X 36						9.00				ASSEMBLY "83" P183B
	M3-1	30 X 15						3.13				ASSEMBLY "36" P183B
	M3-1	30 X 15						3.13				ASSEMBLY "NORTH" P183B
	M6-1	30 X 30						6.25				SEPARATE SIGN FORWARD ARROW P183B
P185A	J2-1	36 X 81	1					3.13				SEPARATE SIGN "TO" P183B
	M1-6	36 X 36						9.00				Single Post Assembly P185A
	M4-5	30 X 15						3.13				ASSEMBLY "A" P185A
	M5-1R	30 X 15						3.13				Separate Sign "TO" P185A
												ASSEMBLY RT TURN ARROW P185A

NOTE: ALL QUANTITIES ARE CATEGORY 0010 UNLESS OTHERWISE NOTED

REVISION DATE: 5/25/07

REVISION NOTE: ITEMS HIGHLIGHTED REFLECT PLAN REVISIONS AND ADDITIONS.

SIGNS REMOVED FROM THIS SHEET:
P177A, P177B, P180A, P180B, P180C, P182A, P182B, P184A & P184B

SIGNS ADDED TO THIS SHEET:
P176C, P176D, P176E, 178C, P179C, P179D, P181B, & P181C

ADD #1
REV SHT 231
6/29/2007

SHEET NO: 231

MISCELLANEOUS QUANTITIES

COUNTY: RACINE

HWY: BURLINGTON BYPASS

PROJECT NUMBER: 3180-10-70

ORIG. DATE: 6/13/2007 11:44 AM

DATE: MARCH 3, 2006

ORIGINATOR: JUSTIN M. ARNOT

FILE NAME: S:\001\DOT_SEG\0481\WORK FOR 09\ESTIMATES\0481_MISQUANT_09.ppt

PERMANENT SIGNING (CONTINUED)														COUNTY: RACINE		HWY: BURLINGTON BYPASS		MISCELLANEOUS QUANTITIES		SHEET NO: 232		E
SIGN #	SIGN CODE	SIGN SIZE	IN	634.0614 POSTS WOOD 4x6-Inch x 14 Ft EACH	634.0616 POSTS WOOD 4x6-Inch x 16 Ft EACH	634.0618 POSTS WOOD 4x6-Inch x 18 Ft EACH	634.0620 POSTS WOOD 4x6-Inch x 20 Ft EACH	634.0622 POSTS WOOD 4x6-Inch x 22 Ft EACH	634.0814 POSTS TUBULAR STEEL 2x2-Inch x 14 Ft EACH	637.0202 REFLECTIVE TYPE II SF	638.2602 REMOVING SIGNS TYPE II EACH	638.3000 REMOVING SMALL SIGN SUPPORT EACH	SPV.0165.03 COVER SIGNS TYPE II SF	SHARED POST # OR REMARKS								
P185B	J2-1	36 X 81	1							9.00				Single Post Assembly P185B ASSEMBLY "A" P185B								
	M1-6	36 X 36								3.13				Separate Sign "TO" P185B								
	M4-5	30 X 15								12.00				ASSEMBLY RT TURN ARROW P185B								
P186A	R2-1	36 X 48	1																			
P186B	R2-1	36 X 48	1							12.00												
P187A	J1-1	36 X 81	1							9.00				Single Post Assembly P187A ASSEMBLY "A" P187A								
	M1-6	36 X 36								4.38				Separate Sign "JCT" P187A								
P187B	M2-1	30 X 21	1							4.38				Single Post Assembly P187B ASSEMBLY "A" P187B								
	J1-1	36 X 81	1							9.00				Separate Sign "JCT" P187B								
P191	M2-1	30 X 21	1							9.00												
P192	W4-1	36 X 36	1							9.00												
P193	E5-1	60 X 48	2							20.00												
P194	W4-1	36 X 36	1							9.00												
P198	W4-2R	48 X 48	1							16.00												
E100	EXST	0	0											Existing Sign to Remain								
E101	EXST	0	0											Existing Sign to Remain								
E102	EXST	0	0											Existing Sign to Remain								
E103	EXST	0	0											Existing Sign to Remain								
E104	EXST	0	0											Existing Sign to Remain								
E105	EXST	0	0											Existing Sign to Remain								
E106	EXST	0	0											Existing Sign to Remain								
E107	EXST	0	0											Existing Sign to Remain								
P199A	R2-1	36 X 48	1							12.00				Existing Sign to Remain								
P199B	R2-1	36 X 48	1							12.00				Triple Post Assembly P200A								
R200	R2-1	0	0								1			Existing Sign to Remain								
E200	EXST	0	0											ASSEMBLY "83" P200A								
P200A	J2-3	72 X 57	2											ASSEMBLY "11" P200A								
	M1-6	24 X 24	1							4.00				ASSEMBLY "36" P200A								
	M1-6	24 X 24	1							4.00				ASSEMBLY "NORTH" P200A								
	M3-1	24 X 12	1							2.00				ASSEMBLY "EAST" P200A								
	M3-2	24 X 12	1							2.00				ASSEMBLY "NORTH" P200A								
	M5-1R	21 X 21	1							3.06				ASSEMBLY RT TURN ARROW P200A								
	M5-1R	21 X 21	1							3.06				ASSEMBLY RT TURN ARROW P200A								
	M5-1R	21 X 21	1							3.06				ASSEMBLY RT TURN ARROW P200A								
	M4-5	24 X 12	1							2.00				SEPARATE SIGN "TO" P200A								
	M4-5	24 X 12	1							2.00				SEPARATE SIGN "TO" P200A								
P200B	M4-2	24 X 12	1							2.00				SEPARATE SIGN "BY-PASS" P200A								
	J2-2	48 X 57	1							4.00				Double Post Assembly P200B								
	M1-6	24 X 24	1							4.00				ASSEMBLY "11" P200B								
	M1-6	24 X 24	1							4.00				ASSEMBLY "36" P200B								
	M3-4	24 X 12	1							2.00				ASSEMBLY "WEST" P200B								
	M3-3	24 X 12	1							2.00				ASSEMBLY "SOUTH" P200B								
	M5-1L	21 X 21	1							3.06				ASSEMBLY LT TURN ARROW P200B								
	M5-1L	21 X 21	1							3.06				ASSEMBLY LT TURN ARROW P200B								
	M08-1	21 X 21	1							3.06				ORANGE TEMP LT ARROW P200B								
	M08-1	21 X 21	1							3.06				ORANGE TEMP LT ARROW P200B								
	M4-5	24 X 12	1							2.00				SEPARATE SIGN "TO" P200B								
	M4-5	24 X 12	1							2.00				SEPARATE SIGN "TO" P200B								
	M4-2	24 X 12	1							2.00				SEPARATE SIGN "BY-PASS" P200B								
	M4-2	24 X 12	1							2.00				SEPARATE SIGN "BY-PASS" P200B								
	M4-2	24 X 12	1							2.00				SEE DETAIL								
P201	D1-2	78 X 30	2							16.25												
P202A	R4-7	36 X 48	1							12.00				P202A								
P202B	W5-54	18 X 18	1							2.25												
P203	R5-1	30 X 30	1							6.25												
P204	W12-1D	24 X 24	1							4.00												
P205A	R4-7	36 X 48	1							12.00				P222A								

NOTE: ALL QUANTITIES ARE CATEGORY 0010 UNLESS OTHERWISE NOTED

REVISION DATE: 5/25/07

REVISION NOTE: FOR THE SIGNS SHOWN ON THIS SHEET, NO CHANGES HAVE BEEN MADE

ADD #1

REV SHT 232

6/29/2007

PROJECT NUMBER: 3180-10-70

HWY: BURLINGTON BYPASS

COUNTY: RACINE

MISCELLANEOUS QUANTITIES

SHEET NO: 232

E

NOTE: ALL QUANTITIES ARE
CATEGORY 0010 UNLESS
OTHERWISE NOTED

REVISION DATE: 5/25/07

REVISION NOTE: FOR THE
SIGNS SHOWN ON THIS
SHEET, NO CHANGES HAVE
BEEN MADE

ADD #1
REV SHT 232
6/29/2007

SHEET NO: 232

MISCELLANEOUS QUANTITIES

COUNTY: RACINE

HWY: BURLINGTON BYPASS

PROJECT NUMBER: 3180-10-70

ORIG. DATE: MARCH 3, 2006

ORIGINATOR: JUSTIN M. ARNOT

FILE NAME: S:\DOT\DOT_SEG\081\WORK\FOR
09ESTIMATES\0481_MISC\QUANT_09.ppt

E

NOTE: ALL QUANTITIES ARE
CATEGORY 0010 UNLESS
OTHERWISE NOTED

REVISION DATE: 5/25/07

REVISION NOTE: FOR THE
SIGNS SHOWN ON THIS
SHEET, NO CHANGES HAVE
BEEN MADE

ADD #1
REV SHT 233
6/29/2007

PERMANENT SIGNING (CONTINUED)

SIGN #	SIGN CODE	SIGN SIZE IN	634.0614				634.0616				634.0618				634.0620				634.0622				634.0814				637.0202	638.2602	638.3000	SPV.0165.03	REMARKS																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																									
			POSTS	WOOD	4x6-inch	x 14 Ft	EACH	POSTS	WOOD	4x6-inch	x 16 Ft	EACH	POSTS	WOOD	4x6-inch	x 18 Ft	EACH	POSTS	WOOD	4x6-inch	x 20 Ft	EACH	POSTS	TUBULAR STEEL	2x2-inch	x 14 Ft						EACH	REFLECTIVE TYPE II	SF	REMOVING TYPE II	SF	REMOVING SMALL SIGN SUPPORT	EACH	COVER TYPE II	SF																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																
P205B	W5-54	18 X 18	48	X	57																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																			

NOTE: ALL QUANTITIES ARE
CATEGORY 0010 UNLESS
OTHERWISE NOTED

REVISION DATE: 5/25/07

REVISION NOTE: FOR THE
SIGNS SHOWN ON THIS
SHEET, NO CHANGES HAVE
BEEN MADE

ADD #1
REV SHT 234
6/29/2007

PERMANENT SIGNING (CONTINUED)

SIGN #	SIGN CODE	SIGN SIZE	634.0614 WOOD 4x6-Inch x 14 Ft EACH	634.0616 POSTS 4x6-Inch x 16 Ft EACH	634.0618 POSTS WOOD 4x6-Inch x 18 Ft EACH	634.0620 POSTS WOOD 4x6-Inch x 20 Ft EACH	634.0622 POSTS WOOD 4x6-Inch x 22 Ft EACH	634.0814 TUBULAR STEEL 2x2-Inch x 14 Ft EACH	637.0202 REFLECTIVE TYPE II SF	638.2602 REMOVING SIGNS TYPE II EACH	638.3000 REMOVING SMALL SIGN SUPPORT EACH	SPV.0165.03 COVER SIGNS TYPE II SF	SHARED POST # OR REMARKS
M1-6	24	X 24							4.00				ASSEMBLY "83" P216A
M3-2	24	X 12							2.00				ASSEMBLY "EAST" P216A
M3-1	24	X 12							2.00				ASSEMBLY "NORTH" P216A
M5-1L	21	X 21							3.06				ASSEMBLY "NORTH" P216A
M5-1L	21	X 21							3.06				ASSEMBLY LT TURN ARROW P216A
M4-5	24	X 12							3.06				ASSEMBLY LT TURN ARROW P216A
M4-5	24	X 12							2.00				SEPARATE SIGN "TO" P216A
M4-2	24	X 12							2.00				SEPARATE SIGN "BY-PASS" P216A
P216B	J2-3	72 X 57		2					2.00				Triple Post Assembly P216B
M1-6	24	X 24							4.00				ASSEMBLY "11" P216B COVER
M1-6	24	X 24							4.00				ASSEMBLY "36" P216B COVER
M3-4	24	X 12							4.00				ASSEMBLY "83" P216B
M3-3	24	X 12							2.00				ASSEMBLY "WEST" P216B COVER
M3-3	24	X 12							2.00				ASSEMBLY "SOUTH" P216B
M5-1R	21	X 21							2.00				ASSEMBLY RT TURN ARROW P216B COVER
M5-1R	21	X 21							3.06				ASSEMBLY RT TURN ARROW P216B COVER
M5-1	21	X 21							3.06				ASSEMBLY FORWARD ARROW P216B
M4-2	24	X 12							2.00				SEPARATE SIGN "BY-PASS" P216B
P217	R2-1	24 X 30		1					2.00				
P218	R2-1	24 X 30		1					5.00				
P219	J1-3	72 X 39		2	1				5.00				
M1-6	24	X 24							4.00				Triple Post Assembly P219
M1-6	24	X 24							4.00				ASSEMBLY "11" P219 COVER
M1-6	24	X 24							4.00				ASSEMBLY "36" P219 COVER
M2-1	30	X 21							4.00				ASSEMBLY "83" P219
M2-1	30	X 21							4.38				ASSEMBLY "JCT" P219 COVER
M2-1	30	X 21							4.38				ASSEMBLY "JCT" P219 COVER
M2-1	30	X 21							4.38				ASSEMBLY "JCT" P219
M4-2	24	X 12							4.38				SEPARATE SIGN "BY-PASS" P219
P220	W3-3	36 X 36		1					2.00				16" X 16" FLAGS REQD
P221	R1-2	36 X 31	1						9.00				
P222A	R1-1F	36 X 36		1					9.00				Mount to Signal Pole
P222B	R1-1F	36 X 36							9.00				Mount to Signal Pole
P223A	R1-1F	36 X 36							9.00				SEE DETAIL
P223B	R1-1F	36 X 36		1					9.00				
P224	R3-8V	72 X 30	1						15.00				
P225	D1-1	66 X 15	2						6.88				
P226	R5-1A	36 X 24	1						6.00				
P227	W12-1D	24 X 24	1						4.00				2' MOUNTING HEIGHT, COVER SIGN
P228	R4-7	36 X 48		1					12.00				
P229	R6-2L	36 X 48		1					12.00				
P230	R2-1	24 X 30	1						5.00				16" X 16" FLAGS REQD
R201	EXST	0								1			
R202	EXST	0											
R203	R1-1	0								1			
R204	EXST	0								1			
R205	R2-1	0								1			
R206	W2-2	0								1			
R207	R2-1	0								1			
R208	R2-1	0								1			
E300	EXST	0											Existing Sign to Remain
P300	R2-1	24 X 30	1						5.00				
P301	W5-52R	12 X 36							3.00				
P302	W5-52L	12 X 36	1						3.00				
P303	W5-52L	12 X 36	1						3.00				
P304	W5-52R	12 X 36	1						3.00				
P305	R2-1	24 X 30	1						5.00				
P306	R2-1	24 X 30	1						5.00				

PROJECT NUMBER: 3180-10-70

HWY: BURLINGTON BYPASS

COUNTY: RACINE

MISCELLANEOUS QUANTITIES

SHEET NO: 234

E

SHEET NO: 235	E
---------------	---

MISCELLANEOUS QUANTITIES

FILE NAME: S:\DOT\DOT_SE\04081\WORK FOR

NOTE: ALL QUANTITIES ARE
CATEGORY 0010 UNLESS
OTHERWISE NOTED

REVISION DATE: 5/25/07

REVISION NOTE: FOR THE
SIGNS SHOWN ON THIS
SHEET, NO CHANGES HAVE
BEEN MADE

ADD #1
REV SHT 236
6/29/2007

PERMANENT SIGNING (CONTINUED)																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																					
SIGN #	SIGN CODE	SIGN SIZE	IN	634.0614				634.0616				634.0618				634.0620				634.0622				634.0614				637.0202				638.2602				638.3000				SPV.0165.03	REMARKS																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																												
				WOOD	POSTS	4x6-Inch	x 14 Ft	WOOD	POSTS	4x6-Inch	x 16 Ft	WOOD	POSTS	4x6-Inch	x 18 Ft	WOOD	POSTS	4x6-Inch	x 20 Ft	WOOD	POSTS	4x6-Inch	x 22 Ft	TUBULAR STEEL	2x2-Inch	x 14 Ft	REFLECTIVE	SIGNS	REMOVING	SIGN	SMALL	REMOVING	COVER	COVER	SHARED																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																		
P408	M1-6	24	X	24																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																	</

FILE NAME: S:\DOT\DOT_SEG\081\WORK FOR
09ESTIMATES\0481_MISCQUANT_09.ppt

ORIGINATOR: JUSTIN M. ARNOT

ORIG. DATE: MARCH 3, 2006

PLOTTED DATE: 6/13/2007 11:44 AM

NOTE: ALL QUANTITIES ARE
CATEGORY 0010 UNLESS
OTHERWISE NOTED

REVISION DATE: 5/25/07

REVISION NOTE: FOR THE
SIGNS SHOWN ON THIS
SHEET, NO CHANGES HAVE
BEEN MADE

ADD #1
REV SHT 237
6/29/2007

PERMANENT SIGNING (CONTINUED)													
SIGN #	SIGN CODE	SIGN SIZE	634.0614 POSTS WOOD 4x6-Inch x 14 Ft EACH	634.0616 POSTS WOOD 4x6-Inch x 16 Ft EACH	634.0618 POSTS WOOD 4x6-Inch x 18 Ft EACH	634.0620 POSTS WOOD 4x6-Inch x 20 Ft EACH	634.0622 POSTS WOOD 4x6-Inch x 22 Ft EACH	634.0814 POSTS TUBULAR STEEL 2x2-Inch x 14 Ft EACH	637.0202 SIGN REFLECTIVE TYPE II SF	638.2602 REMOVING SIGN SUPPORT EACH	638.3000 REMOVING SMALL SIGN SUPPORT EACH	SPV.0165.03 COVER SIGN TYPE II SF	SHARED POST # OR REMARKS
P418	R1-1	36 X 36							9.00				MODIFIED P417
P419A	W1-60	36 X 36		1					9.00				
P419B	W13-1	18 X 18							2.25				
P420	R5-1A	36 X 24	1						6.00				
P421	D1-2	96 X 36	2						24.00				
P422A	J2-1	24 X 57		1									SEE DETAIL
	M1-6	24 X 24											Single Post Assembly P422A
	M3-2	24 X 12							4.00				ASSEMBLY "142" P422A
	M5-1L	21 X 21							2.00				ASSEMBLY "EAST" P422A
	M5-1R	21 X 21							3.06				ASSEMBLY LT TURN ARROW P422A
P422B	J2-1	24 X 57		1									Single Post Assembly P422B
	M1-6	24 X 24							4.00				ASSEMBLY "142" P422B
	M3-2	24 X 12							2.00				ASSEMBLY "EAST" P422B
	M5-1L	21 X 21							3.06				ASSEMBLY LT TURN ARROW P422B
P423A	W1-1R	36 X 36		1					9.00				
P423B	W13-1	24 X 24							4.00				10 MPH P423A
P424	W13-3	36 X 48		1					12.00				
P425	W13-3	36 X 48		1					12.00				
P426A	W1-1R	36 X 36		1					9.00				
P426B	W13-1	24 X 24							4.00				
P427A	J2-1	24 X 57		1									Single Post Assembly P427A
	M1-6	24 X 24							4.00				ASSEMBLY "142" P427A
	M3-2	24 X 12							2.00				ASSEMBLY "EAST" P427A
	M5-1R	21 X 21							3.06				ASSEMBLY RT TURN ARROW P427A
P427B	J2-1	24 X 57		1									Single Post Assembly P427B
	M1-6	24 X 24							4.00				ASSEMBLY "142" P427B
	M3-2	24 X 12							2.00				ASSEMBLY "EAST" P427B
	M5-1R	21 X 21							3.06				ASSEMBLY RT TURN ARROW P427B
P428	D1-2	96 X 36	2						24.00				
P429	R5-1A	36 X 24	1						6.00				
P430A	W1-60	36 X 36		1					9.00				MODIFIED P430A
P430B	W13-1	18 X 18							2.25				
P431	R4-7	24 X 30	1						5.00				Single Post Assembly P431
P432	R1-1	36 X 36							9.00				
P433	R1-1	36 X 36	1						9.00				
P434	J3-1	24 X 57		1									Single Post Assembly P434
	M1-6	24 X 24							4.00				ASSEMBLY "142" P434
	M3-2	24 X 12							2.00				ASSEMBLY "EAST" P434
	M6-1	21 X 21							3.06				ASSEMBLY RT TURN ARROW P434
P435	R5-1	30 X 30	1						6.25				
P436	J4-1	36 X 51		1									Single Post Assembly P436
	M1-6	36 X 36							9.00				ASSEMBLY "142" P436
	M4-6	30 X 15							3.13				ASSEMBLY "END" P436
P437	D1-1	78 X 15		2					8.13				SEE DETAIL
P438	W1-6	48 X 24	1						8.00				Angle Toward Traffic
P439	W1-6	48 X 24	1						8.00				Angle Toward Traffic
P440A	W13-1	24 X 24							4.00				10 mph P440B
P440B	W1-1R	36 X 36		1					9.00				
P441	W4-6	48 X 48		1					16.00				
P442	W1-7	48 X 24		1					8.00				
P443	W4-6	48 X 48		1					16.00				
P444	W1-60	48 X 24	1						8.00				Angle Toward Traffic
P445	W1-60	48 X 24	1						8.00				Angle Toward Traffic
P446	W1-7	48 X 24		1					8.00				
E400	EXIST	0											Existing Sign to Remain
E401	EXIST	0											Existing Sign to Remain
E402	EXIST	0											Existing Sign to Remain
E403	EXIST	0											Existing Sign to Remain
E404	EXIST	0											Existing Sign to Remain
E405	EXIST	0											Existing Sign to Remain
E406	EXIST	0											Existing Sign to Remain

PROJECT NUMBER: 3180-10-70

HWY: BURLINGTON BYPASS

COUNTY: RACINE

MISCELLANEOUS QUANTITIES

SHEET NO: 237

E

FILE NAME: S:\DOT\DOT_SEG\081\WORK FOR

ORIGINATOR: JUSTIN M. ARNOT

DATE: 6/13/2007 11:44 AM

09ESTIMATES\0481_MISC\QUANT_09.ppt

PERMANENT SIGNING (CONTINUED)														PROJECT NUMBER: 3180-10-70		HWY: BURLINGTON BYPASS		COUNTY: RACINE		MISCELLANEOUS QUANTITIES		SHEET NO: 238		E	
SIGN #	SIGN CODE	SIGN SIZE	634.0614	634.0616	634.0618	634.0620	634.0622	634.0814	637.0202	638.2602	638.3000	SPV.0165.03	SHARED POST # OR REMARKS												
			POSTS WOOD 4x6-Inch x 14 Ft EACH	POSTS WOOD 4x6-Inch x 16 Ft EACH	POSTS WOOD 4x6-Inch x 18 Ft EACH	POSTS WOOD 4x6-Inch x 20 Ft EACH	POSTS WOOD 4x6-Inch x 22 Ft EACH	POSTS TUBULAR STEEL 2x2-Inch x 14 Ft EACH	SIGNS REFLECTIVE TYPE II SF	REMOVING SIGN TYPE II EACH	REMOVING SMALL SIGN SUPPORT EACH	COVER SIGNS TYPE II SF													
E407	EXIST	0 0											Existing Sign to Remain												
E408	EXIST	0 0											Existing Sign to Remain												
E409	EXIST	0 0											Existing Sign to Remain												
E410	EXIST	0 0											Existing Sign to Remain												
E401	R3-1	0 0								1	1														
R402	R3-1	0 0								1	1														
R403	R3-2	0 0								1	1														
E411	EXIST	0 0											Existing Sign to Remain												
E412	EXIST	0 0											Existing Sign to Remain												
E413	EXIST	0 0											Existing Sign to Remain												
E414	EXIST	0 0											Existing Sign to Remain												
E415	EXIST	0 0											Existing Sign to Remain												
E416	EXIST	0 0											Existing Sign to Remain												
E417	EXIST	0 0											Existing Sign to Remain												
E418	EXIST	0 0											Existing Sign to Remain												
E419	EXIST	0 0											Existing Sign to Remain												
E420	EXIST	0 0											Existing Sign to Remain												
E421	EXIST	0 0											Existing Sign to Remain												
E422	EXIST	0 0											Existing Sign to Remain												
E423	EXIST	0 0											Existing Sign to Remain												
P500	J1-2	48 X 39											Double Post Assembly P500												
	M1-6	24 X 24							4.00				ASSEMBLY "83" P500												
	M1-6	24 X 24							4.00			4.00	ASSEMBLY "36" P500 COVER												
	M1-6	24 X 24							4.00				ASSEMBLY "11" P500 COVER												
	M2-1	21 X 15							2.19				ASSEMBLY "JCT" P500												
	M2-1	21 X 15							2.19			2.19	ASSEMBLY "JCT" P500 COVER												
	M4-2	24 X 12							2.00			2.19	ASSEMBLY "JCT" P500 COVER												
P501	W3-3	36 X 36							2.19				SEPARATE SIGN "BY-PASS" P500												
P502A	J3-3	72 X 57							9.00				16" X 16" FLAGS REQD												
	M1-6	24 X 24							4.00				Triple Post Assembly P502A												
	M1-6	24 X 24							4.00				ASSEMBLY "36" P502A												
	M1-6	24 X 24							4.00				ASSEMBLY "36" P502A												
	M3-1	24 X 12							2.00				ASSEMBLY "NORTH" P502A												
	M3-3	24 X 12							2.00				ASSEMBLY "SOUTH" P502A												
	M3-2	24 X 12							2.00				ASSEMBLY "EAST" P502A												
	M5-1L	21 X 21							3.06				ASSEMBLY LT TURN ARROW P502A												
	M5-1R	21 X 21							3.06				ASSEMBLY RT TURN ARROW P502A												
	M5-1R	21 X 21							3.06				ASSEMBLY RT TURN ARROW P502A												
	M6-1	21 X 21							3.06				ASSEMBLY FORWARD ARROW P502A												
	M4-5	24 X 12							2.00				SEPARATE SIGN "TO" P502A												
	M4-5	24 X 12							2.00				SEPARATE SIGN "TO" P502A												
P502B	J3-3	72 X 57							2.00				Triple Post Assembly P502B												
	M1-6	24 X 24							4.00				ASSEMBLY "83" P502B												
	M1-6	24 X 24							4.00				ASSEMBLY "83" P502B												
	M1-6	24 X 24							4.00				ASSEMBLY "11" P502B												
	M3-1	24 X 12							2.00				ASSEMBLY "NORTH" P502B												
	M3-3	24 X 12							2.00				ASSEMBLY "SOUTH" P502B												
	M3-4	24 X 12							2.00				ASSEMBLY "WEST" P502B												
	M5-1L	21 X 21							3.06				ASSEMBLY LT TURN ARROW P502B												
	M5-1R	21 X 21							3.06				ASSEMBLY RT TURN ARROW P502B												
	M5-1R	21 X 21							3.06				ASSEMBLY RT TURN ARROW P502B												
	M4-5	24 X 12							2.00				SEPARATE SIGN "TO" P502B												
	M4-2	24 X 12							2.00				SEPARATE SIGN "BY-PASS" P502B												
P503	D1-2	72 X 30							15.00				SEE DETAIL												
	J3-2	48 X 57							4.00				Double Post Assembly P504												
P504	M1-6	24 X 24							4.00				ASSEMBLY "36" P504												
	M1-6	24 X 24							4.00				ASSEMBLY "83" P504												
	M3-1	24 X 12							2.00				ASSEMBLY "NORTH" P504												

ADD #1

REV SHT 238

6/29/2007

NOTE: ALL QUANTITIES ARE CATEGORY 0010 UNLESS OTHERWISE NOTED

REVISION DATE: 5/25/07

REVISION NOTE: FOR THE SIGNS SHOWN ON THIS SHEET, NO CHANGES HAVE BEEN MADE

NOTE: ALL QUANTITIES ARE
CATEGORY 0010 UNLESS
OTHERWISE NOTED

REVISION DATE: 5/25/07

REVISION NOTE: FOR THE
SIGNS SHOWN ON THIS
SHEET, NO CHANGES HAVE
BEEN MADE

ADD #1
REV SHT 238
6/29/2007

COUNTY: RACINE

MISCELLANEOUS QUANTITIES

SHEET NO: 238

E

PROJECT NUMBER: 3180-10-70

HWY: BURLINGTON BYPASS

ORIG. DATE: MARCH 3, 2006

PLOTTED DATE: 6/13/2007 11:44 AM

ORIGINATOR: JUSTIN M. ARNOT

FILE NAME: S:\DOTDOT_SEG0481\WORK FOR
09ESTIMATES\0481_MISC\QUANT_09.ppt

NOTE: ALL QUANTITIES ARE
CATEGORY 0010 UNLESS
OTHERWISE NOTED

REVISION DATE: 5/25/07

REVISION NOTE: FOR THE
SHEETS SHOWN ON THIS
SHEET, NO CHANGES HAVE
BEEN MADE

ADD #1
REV SHT 239
6/29/2007

PERMANENT SIGNING (CONTINUED)															
SIGN #	SIGN CODE	SIGN SIZE	IN	634.0614 POSTS WOOD 4x6-inch x 14 Ft EACH	634.0616 POSTS WOOD 4x6-inch x 16 Ft EACH	634.0618 POSTS WOOD 4x6-inch x 18 Ft EACH	634.0620 POSTS WOOD 4x6-inch x 20 Ft EACH	634.0622 POSTS WOOD 4x6-inch x 22 Ft EACH	634.0814 POSTS TUBULAR STEEL 2x2-inch x 14 Ft EACH	637.0202		638.3000		SPV.0165.03	SHARED POST # OR REMARKS
										REFLECTIVE TYPE II SF	REMOVING SIGN TYPE II EACH	REMOVING SMALL SIGN EACH	COVER SIGN TYPE II SF		
P505	M3-1	24 X 12								2.00					ASSEMBLY "NORTH" P504
	M6-1	21 X 21								3.06					ASSEMBLY LT ARROW P504
	M4-5	24 X 12								3.06					ASSEMBLY LT ARROW P504
	J3-3	72 X 57								2.00					SEPARATE SIGN "TO" P504 Triple Post Assembly P505
	M1-6	24 X 24								4.00					ASSEMBLY "83" P505
P505	M1-6	24 X 24								4.00				4.00	ASSEMBLY "36" P505
	M1-6	24 X 24								4.00					ASSEMBLY "11" P505 COVER
	M3-3	24 X 12								2.00					ASSEMBLY "SOUTH" P505
	M3-3	24 X 12								2.00			2.00		ASSEMBLY "WEST" P505 COVER
	M6-1	21 X 21								3.06					ASSEMBLY RT ARROW P505
P510	M6-1	21 X 21								3.06				3.06	ASSEMBLY RT ARROW P505
	M4-5	24 X 12								3.06					ASSEMBLY RT ARROW P505
	J3-2	48 X 57								2.00					ORANGE TEMP "TO" P505 Triple Post Assembly P512
	M1-6	24 X 24								4.00					ASSEMBLY "83" P510
	M1-6	24 X 24								4.00					ASSEMBLY "36" P510
P512	M3-1	24 X 12								2.00					ASSEMBLY "NORTH" P510
	M3-1	24 X 12								2.00					ASSEMBLY "NORTH" P510
	M6-1	21 X 21								3.06					ASSEMBLY RT ARROW P510
	M6-1	21 X 21								3.06					ASSEMBLY RT ARROW P510
	M4-5	24 X 12								2.00					SEPARATE SIGN "TO" P510 Triple Post Assembly P512
P512	J3-3	72 X 57								4.00					ASSEMBLY "83" P512
	M1-6	24 X 24								4.00					ASSEMBLY "36" P512
	M1-6	24 X 24								4.00					ASSEMBLY "11" P512
	M3-3	24 X 12								2.00					ASSEMBLY "SOUTH" P512
	M3-4	24 X 12								2.00					ASSEMBLY "SOUTH" P512
P514	M6-1	21 X 21								3.06					ASSEMBLY "WEST" P512
	M6-1	21 X 21								3.06					ASSEMBLY LT ARROW P512
	M6-1	21 X 21								3.06					ASSEMBLY LT ARROW P512
	M6-1	21 X 21								3.06					ASSEMBLY LT ARROW P512
	M4-5	24 X 12								2.00					ORANGE TEMP FORWARD ARROW P512 ORANGE TEMP "TO" P512 SEPARATE SIGN "BY-PASS" P512
P514	J2-3	48 X 30								16.25					SEE DETAIL
	M1-6	24 X 24								4.00					Double Post Assembly P514
	M1-6	24 X 24								4.00					ASSEMBLY "36" P514
	M3-1	24 X 12								2.00					ASSEMBLY "SOUTH" P514
	M3-3	24 X 12								2.00					ASSEMBLY "NORTH" P514
P514	M5-1L	21 X 21								3.06					ASSEMBLY LT TURN ARROW P514
	M5-1R	21 X 21								3.06					ASSEMBLY RT TURN ARROW P514
	M4-5	24 X 12								2.00					SEPARATE SIGN "TO" P514
	M4-5	24 X 12								2.00					SEPARATE SIGN "TO" P514
	J3-3	72 X 57								2.00					Triple Post Assembly P514

PROJECT NUMBER: 3180-10-70

HWY: BURLINGTON BYPASS

COUNTY: RACINE

MISCELLANEOUS QUANTITIES

SHEET NO: 239

E

FILE NAME: S:\DOT\DOT_SEG\0481\WORK FOR

ORIG. DATE: MARCH 3, 2006

PLOTTED DATE: 6/13/2007 11:44 AM

09ESTIMATES0481_MISCQUANT_09.ppt

ORIGINATOR: JUSTIN M. ARNOT

NOTE: ALL QUANTITIES ARE
CATEGORY 0010 UNLESS
OTHERWISE NOTED

REVISION DATE: 5/25/07

REVISION NOTE: FOR THE
SIGNS SHOWN ON THIS
SHEET, NO CHANGES HAVE
BEEN MADE

ADD #1
REV SHT 240
6/29/2007

SIGN #	SIGN CODE	SIGN SIZE IN	PERMANENT SIGNING (CONTINUED)										REMARKS
			634.0614 POSTS WOOD 4x6-inch x 14 Ft EACH	634.0616 POSTS WOOD 4x6-inch x 16 Ft EACH	634.0618 POSTS WOOD 4x6-inch x 18 Ft EACH	634.0620 POSTS WOOD 4x6-inch x 20 Ft EACH	634.0622 POSTS WOOD 4x6-inch x 22 Ft EACH	634.0814 POSTS TUBULAR STEEL 2x2-inch x 14 Ft EACH	637.0202 REFLECTIVE TYPE II SF	638.2602 REMOVING SIGNS TYPE II EACH	638.3000 REMOVING SMALL SIGN SUPPORT EACH	SPV.0165.03 COVER SIGNS TYPE II SF	
M15		24 X 24							4.00				ASSEMBLY "83" P514
M16		24 X 24							4.00				ASSEMBLY "83" P514
M16		24 X 24							4.00				ASSEMBLY "11" P514
M3-3		24 X 12							2.00				ASSEMBLY "SOUTH" P514
M3-3		24 X 12							2.00				ASSEMBLY "NORTH" P514
M3-4		24 X 12							2.00				ASSEMBLY "WEST" P514
M5-1L		21 X 21							3.06				ASSEMBLY LT TURN ARROW P514
M5-1R		21 X 21							3.06				ASSEMBLY RT TURN ARROW P514
M5-1L		21 X 21							3.06				ASSEMBLY LT TURN ARROW P514
M5-1R		21 X 21							3.06				ASSEMBLY RT TURN ARROW P514
M06-1		21 X 21							3.06				ORANGE TEMP FORWARD ARROW P514
M4-2		24 X 12							2.00				SEPARATE SIGN "BY-PASS" P514
M04-5		24 X 12							2.00				ORANGE TEMP "TO" P514
W3-3		36 X 36		1					2.00				16" X 16" FLAGS REQD
P516		24 X 24	2						9.00				Double Post Assembly P516
M1-6		24 X 24							4.00				ASSEMBLY "83" P516
M2-1		24 X 12							4.00				ASSEMBLY "36" P516
M2-1		24 X 12							2.00				ASSEMBLY "JCT" P516
W3-5		36 X 36							2.00				ASSEMBLY "JCT" P516
P517		36 X 36		1					9.00				
P518		R1-1F	36 X 36	1					9.00				
P519		R1-1F	36 X 36	1					9.00				
P520		W5-54	18 X 18						2.25				E505
P521		W5-54	18 X 18						2.25				E511
E500		EXIST	0	0									Existing Sign to Remain
E501		EXIST	0	0									Existing Sign to Remain
E502		EXIST	0	0									Existing Sign to Remain
E503		EXIST	0	0									Existing Sign to Remain
E504		EXIST	0	0									Existing Sign to Remain
E505		EXIST	0	0									Existing Sign to Remain
E507		EXIST	0	0									Existing Sign to Remain
E508		EXIST	0	0									Existing Sign to Remain
E509		EXIST	0	0									Existing Sign to Remain
E510		EXIST	0	0									Existing Sign to Remain
E511		EXIST	0	0									Existing Sign to Remain
E513		EXIST	0	0									Existing Sign to Remain
E514		EXIST	0	0									Existing Sign to Remain
E515		EXIST	0	0									Existing Sign to Remain
E516		EXIST	0	0									Existing Sign to Remain
E517		EXIST	0	0									Existing Sign to Remain
R500		R3-2	0	0									Existing Sign to Remain
R501		R3-1	0	0						1	1		
R502		R3-1	0	0						1	1		
R503		R3-2	0	0						1	1		
R504		R4-7	0	0						1	1		
P600		W5-52R	12 X 36	1					3.00				
P601		W5-52L	12 X 36	1					3.00				
P602		W5-52L	12 X 36	1					3.00				
P603		W5-52R	12 X 36	1					3.00				
P604		R2-1	24 X 30	1					5.00				
P605		R2-1	24 X 30	1					5.00				
P606		W3-5	36 X 36	1					9.00				
R600		R2-1	0	0						1	1		
R601		R2-1	0	0						1	1		
R602		R2-5A	0	0						1	1		
P700		J1-3	72 X 36	3					4.00				Triple Post Assembly P700
M1-6		24 X 24							4.00			4.00	ASSEMBLY "83" P700
M1-6		24 X 24							4.00			4.00	ASSEMBLY "36" P700 COVER
M1-6		24 X 24							4.00			4.00	ASSEMBLY "11" P700 COVER
M2-1		21 X 15							2.19				ASSEMBLY "JCT" P700

PROJECT NUMBER: 3180-10-70

HWY: BURLINGTON BYPASS

COUNTY: RACINE

MISCELLANEOUS QUANTITIES

SHEET NO: 240

E

FILE NAME: S:\DOT\DOT_SEG\0481\WORK FOR
09\ESTIMATES\0481_MISC\QUANT_09.ppt

ORIGINATOR: JUSTIN M. ARNOT

ORIG. DATE: MARCH 3, 2006

PLOTTED DATE: 6/13/2007 11:44 AM

PERMANENT SIGNING (CONTINUED)														
SIGN #	SIGN CODE	SIGN SIZE	634.0614 WOOD x 14 Ft EACH	634.0616 WOOD x 16 Ft EACH	634.0618 WOOD x 18 Ft EACH	634.0620 WOOD x 20 Ft EACH	634.0622 WOOD x 22 Ft EACH	634.0814 TUBULAR STEEL 2x2-inch x 14 Ft EACH	637.0202 REFLECTIVE TYPE II SF	638.2602 REMOVING SIGN EACH	638.3000 REMOVING SMALL SIGN EACH	SPV.0165.03 COVER TYPE II SF	SHARED POST # OR REMARKS	
M2-1	21	X 15							2.19			2.19	ASSEMBLY "JCT" P700 COVER	
M2-1	21	X 15							2.19			2.19	ASSEMBLY "JCT" P700 COVER	
M2-2	24	X 12							2.00				SEPARATE SIGN "BY-PASS" P700	
P701A	J323	48 X 69							4.00				Triple Post Assembly P701A	
M1-6	24	X 24							4.00				ASSEMBLY "36" P701A COVER	
M1-6	24	X 24							4.00				ASSEMBLY "11" P701A COVER	
M4-5	24	X 12							2.00				ASSEMBLY "TO" P701A	
M4-5	24	X 12							2.00				ASSEMBLY "TO" P701A COVER	
M4-5	24	X 12							2.00				ASSEMBLY LT TURN ARROW P701A	
M5-1L	21	X 21							3.06				ASSEMBLY LT TURN ARROW P701A COVER	
M5-1L	21	X 21							3.06				ASSEMBLY LT TURN ARROW P701A COVER	
M3-3	24	X 12							2.00				ASSEMBLY "SOUTH" P701A	
M3-3	24	X 12							2.00				ASSEMBLY "SOUTH" P701A COVER	
M4-2	24	X 12							2.00				ASSEMBLY "BY-PASS" P701A	
J32-2	48 X 69								2.00				Double Post Assembly P701B	
M1-6	24	X 24							4.00				ASSEMBLY "36" P701B	
M1-6	24	X 24							2.00				ASSEMBLY "TO" P701B	
M4-5	24	X 12							2.00				ASSEMBLY "TO" P701B COVER	
M6-1	21	X 21							3.06				ASSEMBLY "TO" P701B COVER	
M6-1	21	X 21							3.06				ASSEMBLY FORWARD ARROW P701B	
M3-1	24	X 12							2.00				ASSEMBLY FORWARD ARROW P701B COVER	
M3-1	24	X 12							2.00				ASSEMBLY "NORTH" P701B	
M3-1	24	X 12							2.00				ASSEMBLY "NORTH" P701B COVER	
E700	EXST	0											Existing Sign to Remain	
E701	EXST	0											Existing Sign to Remain	
E702	EXST	0											Existing Sign to Remain	
E703	EXST	0											Existing Sign to Remain	
P702	W1-6	48 X 24							8.00				Angle Toward Traffic	
D1-1	96	X 21	1										SEE DETAIL	
J4-1	24	X 36							14.00				Single Post Assembly P703	
M1-6	24	X 24	1						4.00				ASSEMBLY "A" P703	
M3-4	24	X 12							2.00				ASSEMBLY "WEST" P703	
P704A	J33-3	48 X 69							4.00				Triple Post Assembly P704A	
M1-6	24	X 24							4.00				ASSEMBLY "36" P704A	
M1-6	24	X 24							4.00				ASSEMBLY "36" P704A COVER	
M4-5	24	X 12							2.00				ASSEMBLY "TO" P704A	
M4-5	24	X 12							2.00				ASSEMBLY "TO" P704A COVER	
M4-5	24	X 12							2.00				ASSEMBLY "TO" P704A COVER	
M6-1	21	X 21							3.06				ASSEMBLY LT ARROW P704A	
M6-1	21	X 21							3.06				ASSEMBLY LT ARROW P704A COVER	
M6-1	21	X 21							3.06				ASSEMBLY LT ARROW P704A COVER	
M3-3	24	X 12							2.00				ASSEMBLY "SOUTH" P704A	
M3-3	24	X 12							2.00				ASSEMBLY "SOUTH" P704A COVER	
M4-2	24	X 12							2.00				ASSEMBLY "BY-PASS" P704A COVER	
J33-2	48 X 69								2.00				Double Post Assembly P704B	
M1-6	24	X 24							4.00				ASSEMBLY "36" P704B	
M4-5	24	X 12							4.00				ASSEMBLY "TO" P704B	
M4-5	24	X 12							2.00				ASSEMBLY "TO" P704B COVER	
M6-1	21	X 21							3.06				ASSEMBLY FORWARD ARROW P704B	
M6-1	21	X 21							3.06				ASSEMBLY FORWARD ARROW P704B COVER	
M3-1	24	X 12							2.00				ASSEMBLY "NORTH" P704B	
M3-1	24	X 12							2.00				ASSEMBLY "NORTH" P704B COVER	
P705	R4-7	24 X 30	1						5.00				Single Post Assembly P706	
P706	J4-1	24 X 36	1						4.00				ASSEMBLY "A" P706	
M1-6	24	X 24							2.00				ASSEMBLY "EAST" P706	
M3-2	24	X 12												

NOTE: ALL QUANTITIES ARE CATEGORY 0010 UNLESS OTHERWISE NOTED

REVISION DATE: 5/25/07

REVISION NOTE: ITEMS HIGHLIGHTED REFLECT PLAN REVISIONS AND ADDITIONS.

SIGNS REMOVED FROM THIS SHEET: P701 & P704

SIGNS ADDED TO THIS SHEET: P701A,P701B,P704A & P704B

ADD #1
REV SHT 241
6/29/2007

SHEET NO: 241

MISCELLANEOUS QUANTITIES

COUNTY: RACINE

HWY: BURLINGTON BYPASS

PROJECT NUMBER: 3180-10-70

PLOTTED DATE: 6/13/2007 11:44 AM

ORIG. DATE: MARCH 3, 2006

ORIGINATOR: JUSTIN M. ARNOT

FILE NAME: S:\DOT\DOT_SEG\0481\WORK FOR 09ESTIMATES\0481_MISC\QUANT_09.ppt

E

PERMANENT SIGNING (CONTINUED)														
SIGN #	SIGN CODE	SIGN SIZE IN	634.0614 POSTS WOOD x 14 Ft EACH	634.0616 POSTS WOOD 4x6-inch x 16 Ft EACH	634.0618 POSTS WOOD 4x6-inch x 18 Ft EACH	634.0620 POSTS WOOD 4x6-inch x 20 Ft EACH	634.0622 POSTS WOOD 4x6-inch x 22 Ft EACH	634.0814 TUBULAR STEEL 2x2-inch x 14 Ft EACH	637.0202 REFLECTIVE TYPE II SF	638.2602 REMOVING SIGNS TYPE II EACH	638.3000 REMOVING SMALL SIGN SUPPORT EACH	SPV.0165.03 COVER TYPE II SF	SHARED POST # OR REMARKS	
P707	J33-3	48" X 69"	3	3					4.00				Triple Post Assembly P707 ASSEMBLY "83" P707 ASSEMBLY "36" P707 COVER ASSEMBLY "11" P707 COVER ASSEMBLY "TO" P707	
	M1-6	24" X 24"							4.00					
	M1-6	24" X 24"							4.00					
	M4-5	24" X 12"							2.00					
	M4-5	24" X 12"							2.00					
	M6-1	21" X 21"							3.06					
	M6-1	21" X 21"							3.06					
	M6-1	21" X 21"							3.06					
	M3-3	24" X 12"							2.00					
	M3-3	24" X 12"							2.00					
P708	M4-2	24" X 12"	1						2.00					
P709	J3-2	48" X 57"		3					9.00					
	M1-6	24" X 24"							4.00					
	M1-6	24" X 24"							4.00					
	M3-2	21" X 15"							2.19					
	M3-4	21" X 15"							2.19					
	M6-1	21" X 21"							3.06					
	M6-1	21" X 21"							3.06					
P710	R1-1	36" X 36"							9.00					
P712A	J2-2	48" X 57"	2						4.00					
	M1-6	24" X 24"							4.00					
	M3-2	21" X 15"							2.19					
	M3-4	21" X 15"							2.19					
P712B	J2-2	48" X 57"							3.06					
	M1-6	24" X 24"							4.00					
	M1-6	24" X 24"							4.00					
	M3-2	21" X 15"							2.19					
	M3-4	21" X 15"							2.19					
	M5-1L	21" X 21"							3.06					
	M5-1R	21" X 21"							3.06					
P713	J33-3	72" X 69"	3						4.00					
	M1-6	24" X 24"							4.00					
	M1-6	24" X 24"							4.00					
	M4-5	24" X 12"							2.00					
	M4-5	24" X 12"							2.00					
	M6-1	21" X 21"							3.06					
	M6-1	21" X 21"							3.06					
	M3-3	24" X 12"							2.00					
	M3-3	24" X 12"							2.00					
P717	J32-3	72" X 69"	3						4.00					
	M1-6	24" X 24"							4.00					
	M1-6	24" X 24"							4.00					
	M4-5	24" X 12"							2.00					
	M4-5	24" X 12"							2.00					
	M5-1L	21" X 21"							3.06					
	M5-1L	21" X 21"							3.06					
	M3-3	24" X 12"							2.00					

REVISION DATE: 5/25/07
REVISION NOTE: ITEMS HIGHLIGHTED REFLECT PLAN REVISIONS AND ADDITIONS.

SIGNS REMOVED FROM THIS SHEET:
P711A,P711B,P713A,P713B, P714,P715 & P716,
SIGNED TO THIS SHEET: P713

ADD #1
REV SHT 242
6/29/2007

**SIGNS ADDED TO THIS SHEET:
P724,P725,P726,P728,P729,
P730,P731 & P732**

SHEET NO: 243	E
---------------	---

FILE NAME: S:\DOT\DOT_SE\04081\WORK FOR
ORIGINATOR: JUSTIN M. ARNDT
ORG. DATE: MARCH 3, 2006
PLOTTED DATE: 6/13/2007 11:44 AM

NOTE: ALL QUANTITIES ARE
CATEGORY 0010 UNLESS
OTHERWISE NOTED

REVISION DATE: 5/25/07

REVISION NOTE: ITEMS
HIGHLIGHTED REFLECT PLAN
REVISIONS AND ADDITIONS.

SIGNS ADDED TO THIS SHEET:
P733,P735,P736,P737,P738,
P739 & P740

ADD #1
NEW SHT 243B
6/29/2007

SIGN #	SIGN CODE	SIGN SIZE IN	PERMANENT SIGNING (CONTINUED)										REMARKS
			634.0614 POSTS WOOD 4x6-Inch x 14 Ft EACH	634.0616 POSTS WOOD 4x6-Inch x 16 Ft EACH	634.0618 POSTS WOOD 4x6-Inch x 18 Ft EACH	634.0620 POSTS WOOD 4x6-Inch x 20 Ft EACH	634.0622 POSTS WOOD 4x6-Inch x 22 Ft EACH	634.0814 POSTS TUBULAR STEEL 2x2-Inch x 14 Ft EACH	637.0202 SIGN REFLECTIVE TYPE II SF	638.2602 REMOVING SIGN SUPPORT EACH	638.3000 REMOVING SMALL SIGN EACH	SPV.0165.03 COVER SIGN TYPE II SF	
P733	M4-2	24 X 36	3						2.00			2.00	ASSEMBLY "BY-PASS" P732 COVER Triple Post Assembly P733 ASSEMBLY "83" P733
	M1-6	24 X 24							4.00			4.00	ASSEMBLY "36" P733 COVER
	M1-6	24 X 24							4.00			4.00	ASSEMBLY "11" P733 COVER
	M2-1	21 X 15							2.19			2.19	ASSEMBLY "JCT" P733
	M2-1	21 X 15							2.19			2.19	ASSEMBLY "JCT" P733 COVER
	M2-1	21 X 15							2.19			2.19	ASSEMBLY "JCT" P733 COVER
	M4-2	24 X 12							2.00				SEPARATE SIGN "BY-PASS" P733 Double Post Assembly P735
P735	J32-2	48 X 69		3					4.00			4.00	ASSEMBLY "83" P735
	M1-6	24 X 24							4.00			4.00	ASSEMBLY "36" P735 COVER
	M1-6	24 X 24							2.00				ASSEMBLY "TO" P735
	M4-5	24 X 12							2.00			2.00	ASSEMBLY "TO" P735 COVER
	M5-1R	21 X 21							3.06			3.06	ASSEMBLY RT TURN ARROW P735
	M3-1	24 X 12							2.00			2.00	ASSEMBLY RT TURN ARROW P735 COVER
	M3-1	24 X 12							2.00			2.00	ASSEMBLY "NORTH" P735
P736	J33-2	48 X 69		3					4.00			4.00	Double Post Assembly P736 ASSEMBLY "83" P736
	M1-6	24 X 24							4.00			4.00	ASSEMBLY "36" P736 COVER
	M1-6	24 X 24							2.00			2.00	ASSEMBLY "TO" P736
	M4-5	24 X 12							2.00			2.00	ASSEMBLY "TO" P736 COVER
	M6-1	21 X 21							3.06			3.06	ASSEMBLY RT TURN ARROW P736
	M6-1	21 X 21							3.06			3.06	ASSEMBLY RT TURN ARROW P736 COVER
	M3-1	24 X 12							2.00			2.00	ASSEMBLY "NORTH" P736
P737	D1-1	96 X 21	2						14.00			2.00	SEE DETAIL
P738	W1-6	48 X 24	1						8.00				Angle Toward Traffic Double Post Assembly P739 ASSEMBLY "A" P739
P739	J2-2	48 X 57		2					4.00			4.00	ASSEMBLY "A" P739
	M1-6	24 X 24							2.19			2.19	ASSEMBLY "WEST" P739
	M3-2	21 X 15							2.19			2.19	ASSEMBLY "EAST" P739
	M3-4	21 X 15							3.06			3.06	ASSEMBLY LT TURN ARROW P739
	M5-1R	21 X 21							3.06			3.06	ASSEMBLY RT TURN ARROW P739
	M5-1R	21 X 21							3.06			3.06	ASSEMBLY RT TURN ARROW P739
P740	J2-2	48 X 57							4.00				Double Post Assembly ON P711A ASSEMBLY "A" P740
	M1-6	24 X 24							4.00			4.00	ASSEMBLY "A" P740
	M3-2	21 X 15							2.19			2.19	ASSEMBLY "WEST" P740
	M3-4	21 X 15							2.19			2.19	ASSEMBLY "EAST" P740
	M5-1L	21 X 21							3.06			3.06	ASSEMBLY LT TURN ARROW P740
	M5-1R	21 X 21							3.06			3.06	ASSEMBLY RT TURN ARROW P740

PROJECT NUMBER: 3180-10-70

HWY: BURLINGTON BYPASS

COUNTY: RACINE

MISCELLANEOUS QUANTITIES

SHEET NO: 243B

E

NOTE: ALL QUANTITIES ARE
CATEGORY 0010 UNLESS
OTHERWISE NOTED

REVISION DATE: 5/25/07

REVISION NOTE: ITEMS
HIGHLIGHTED REFLECT PLAN
REVISIONS AND ADDITIONS.

ADD #1
REV SHT 244
6/29/2007

PERMANENT SIGNING (CONTINUED)													
SIGN #	SIGN CODE	SIGN SIZE	634.0614 POSTS WOOD 4x6-Inch x 14 Ft	634.0616 POSTS WOOD 4x6-Inch x 16 Ft	634.0618 POSTS WOOD 4x6-Inch x 18 Ft	634.0620 POSTS WOOD 4x6-Inch x 20 Ft	634.0622 POSTS WOOD 4x6-Inch x 22 Ft	634.0814 POSTS TUBULAR STEEL 2x2-Inch x 14 Ft	637.0202 REFLECTIVE TYPE II SF	638.2602 REMOVING SIGNS TYPE II EACH	638.3000 REMOVING SMALL SUPPORT EACH	638.3000 REMOVING SMALL SUPPORT EACH	SPV.0165.03 COVER SIGNS TYPE II SF
E704	EXIST	0	1										
E705	EXIST	0											
E706	EXIST	0											
E707	EXIST	0											
E708	EXIST	0											
E709	EXIST	0											
E710	EXIST	0											
E711	EXIST	0											
E712	EXIST	0											
E713	EXIST	0											
E714	EXIST	0											
E715	EXIST	0											
P800A	R3-4B	36 X 48	1										
P800B	R3-4B	36 X 48	1										
P801A	E5-1	60 X 48		2									
P801B	E13-1	60 X 24											
P802A	W13-2A	48 X 90				1							
P802B	D1-2	48 X 36											
P803A	W1-13R	48 X 48		1									
P803B	W13-1	24 X 24											
P804A	W1-2	36 X 36											
P804B	W13-1	24 X 24											
E800	EXIST	0											
E801	EXIST	0											
E802	EXIST	0											
E803	EXIST	0											
TOTAL			142	191	59	17	4	3	5,005	21	21	595	

TRAFFIC CONTROL

TRAFFIC CONTROL													
LOCATION	STAGE	DURATION	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL
STH 36/83 INTERCHANGE	ALL	427	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL
CTH A	ALL	427	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL
KETTERHAGEN ROAD	1	122	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL
STH 11	2	305	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL
STH 142	ALL	427	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL
BREVER ROAD	ALL	427	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL
STH 83	1	122	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL
STH 83	2	305	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL
STH 83	1	0	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL
STH 83	2A	121	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL
STH 83	2B	184	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL
BYPASS AT STH 83 *	3	7	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL	TRAFFIC CONTROL
TOTAL			15881	45209	28	28	0	2	14	18	126	42218	

* = Stage 3 is the placing of permanent traffic control prior to opening up the east half of the bypass. One week is assumed from completion of permanent traffic control to project 3180-10-70 completion and sign off. Contractor for Project 3180-11-70 will assume surveillance and maintenance responsibilities after sign off of project 3180-10-70.

NOTE: ALL QUANTITIES ARE CATEGORY 0010 UNLESS OTHERWISE NOTED

TRAFFIC CONTROL SURVEILLANCE & MAINTENANCE

643.0200	
TRAFFIC CONTROL SURVEILLANCE AND MAINTENANCE	
LOCATION	DAYS
PROJECT 3180-10-70	427
427	

TRAFFIC CONTROL SIGNS PORTABLE CHANGEABLE MESSAGE

643.1050.S				
TRAFFIC CONTROL				
SIGNS PORTABLE				
CHANGEABLE				
MESSAGE				
LOCATION	NO. OF DEVICES	SERVICE DAY PERIODS	MESSAGE DAYS	
STH 36/83 (NB)	1	427	427	
BYPASS (WB)	1	427	427	
PROJECT 3180-10-70 TOTAL				854

TRAFFIC CONTROL DETOUR SIGNS

643.3000			
DETOUR		SIGNS	
LOCATION	DAYS	DURATION	NUMBER DAYS
		215	137 29,455
STH 83			
PROJECT 3180-10-70 TOTAL		137	29,455

REMOVING PAVEMENT MARKING

646.0600			
REMOVING PAVEMENT MARKING			
STATION	LOCATION	LF	DESCRIPTION
171+00 - 178+00	STH 36/83 NB RAMP	175	WHITE SKIP (12.5' LINE W/ 37.5' SPACE)
178+00 - 184+60	STH 36/83 NB RAMP	660	WHITE EDGELINE ACROSS OUTSIDE LANE
184+60 - 186+00	STH 36/83 NB RAMP	140	WHITE EDGELINE BETWEEN LANES
TOTAL		975	

TRAFFIC CONTROL FLEXIBLE TUBULAR MARKER POSTS & BASES

643.0500		643.0600
TRAFFIC CONTROL FLEXIBLE TUBULAR POSTS		TRAFFIC CONTROL FLEXIBLE TUBULAR BASES
STATION - STATION	LOCATION	EACH
1127+00 - 1150+25	BYPASS	111
		111

TRAFFIC CONTROL COVERING SIGNS

643.0905.S	
TRAFFIC CONTROL COVERING SIGNS	
LOCATION	EACH
PROJECT 3180-10-70 UNDIS TRIBUTED	20
<hr/>	
PROJECT 3180-10-70 TOTAL	20

ADD #1
NEW SHT 244B
6/29/2007

PROJECT NUMBER: 3180-10-70

HWY: BURLINGTON BYPASS

COUNTY: RACINE

MISCELLANEOUS QUANTITIES

SHEET NO: 244B

E

FILE NAME: S:\DOT\DOT_SE04081\WORK FOR
09\ESTIMATES\04081_MISC\QUANT_09.ppt

ORIGINATOR: JUSTIN M. ARNOT

ORIG. DATE: MARCH 3, 2006

PLOTTED DATE: 6/13/2007 11:44 AM

ADD #1, REV SHT 245, 6/29/2007

PAVEMENT MARKING

STATION	LOCATION	646.0106 PAVEMENT MARKING EPOXY 4-INCH (WHITE) (YELLOW)	646.0406 PAVEMENT MARKING SAME DAY EPOXY 4-INCH (YELLOW)	646.0821.S PAVEMENT MARKING RAISED PATTERN TAPE 4-INCH (WHITE)	647.0166 PAVEMENT MARKING ARROWS EPOXY TYPE 2 (WHITE)	647.0356 PAVEMENT MARKING WORDS EPOXY (WHITE)	647.0566 PAVEMENT MARKING STOP LINE EPOXY 18-INCH (WHITE)	647.0606 PAVEMENT MARKING ISLAND NOSE EPOXY (YELLOW)	647.0726 PAVEMENT MARKING DIAGONAL EPOXY 12-INCH (WHITE) (YELLOW)
340+80 - 355+00	STH 83	2,988	2,229	176	1	1	70	6	8
355+00 - 369+35	STH 83	3,276	2,870	734			40	3	9
1125+93 - 1138+00	BYPASS	2,871	2,805	604				6	
1138+00 - 1153+00	BYPASS	3,000	3,000	750					
97+00 - 108+00	BREVER ROAD	2,200	2,200						
108+00 - 118+00	BREVER ROAD	2,000	2,000						
1153+00 - 1168+00	BYPASS	3,030	3,000	750	1	1		4	
1168+00 - 1183+00	BYPASS	2,540	3,000	750	3	3			
101+08 - 113+00	STH 142	2,398	2,384						
113+00 - 128+00	STH 142	2,745	3,000	360	4	3			
128+00 - 143+39	STH 142	2,942	3,078	219	2	2	36		
100+00 - 104+25	MT TOM ROAD	848					45	1	
50+00 - 60+63	STH 142 NE RAMP	2,096	1,936	150	4	2	45		
38+92 - 50+00	STH 142 SW RAMP	2,186	2,029	152	4	2	45	1	
1183+00 - 1198+00	BYPASS	3,005	3,000	750					
1198+00 - 1213+00	BYPASS	3,000	3,000	750					
1213+00 - 1228+00	BYPASS	3,000	3,000	750					
1228+00 - 1243+00	BYPASS	3,000	3,000	750					
1243+00 - 1258+00	BYPASS	3,000	3,000	750					
1258+00 - 1273+00	BYPASS	3,030	3,000	750					
1273+00 - 1288+00	BYPASS	4,409	3,859	698	4	4	128	12	140
1288+00 - 1303+00	BYPASS	3,000	300	750					
115+67 - 125+00	STH 11	1,866	1,866					1	25
125+00 - 140+00	STH 11	2,871	3,967	487	2	2	48	9	110
140+00 - 155+00	STH 11	3,000	3,000						73
155+00 - 168+00	STH 11	2,600	2,225						
1303+00 - 1318+00	BYPASS	3,000	3,000	750					
1318+00 - 1333+00	BYPASS	3,000	3,000	750					
91+00 - 100+50	KETTERHAGEN ROAD	1,900	1,900						
100+50 - 110+75	KETTERHAGEN ROAD	2,050	2,050						
1333+00 - 1348+00	BYPASS	3,000	3,000	750					
1348+00 - 1363+00	BYPASS	2,935	3,000	438	2	2			
1363+00 - 1378+00	BYPASS	2,558	3,000	1,121	2	2			
1378+00 - 1393+00	BYPASS	3,000	3,000	100					
37+69 - 45+00	CTH A	1,401	914						
48+00 - 50+00	OLD CTH A	389	45				19		
45+00 - 60+00	CTH A	2,792	2,463	445	4	4			
50+00 - 58+75	CTH A NW RAMP	1,746	1,822	370	4	2	54	3	11
60+00 - 70+25	CTH A	1,697	2,050	200	2	2			
38+60 - 48+75	CTH A SE RAMP	2,090	2,066	378	4	2	49	3	11
49+63 - 52+27	RIVER ROAD	534	63				29		
171+00 - 184+00	STH 36/83 NB RAMP	1,300		260					
184+00 - 199+00	STH 36/83 NB RAMP	869		840				1	
192+69 - 199+00	STH 36/83 NB TO SB RAMP	631	265	371					
199+00 - 203+00	STH 36/83 NB TO SB RAMP	400	422						
1393+00 - 1399+00	BYPASS	1,194	1,193	1,178				1	
1399+00 - 1415+00	BYPASS	2,638	3,000	800					
1415+00 - 1430+00	BYPASS	245	1,500	750					
1436+13 - 1464+10	BYPASS	153	150						
TOTAL		110,500	71,300	33,400	11,270	43	34	563	51
								330	137

REVISION DATE: 5/25/07

REVISION NOTE: ITEMS
HIGHLIGHTED REFLECT PLAN
REVISIONS AND ADDITIONS.NOTE: ALL QUANTITIES ARE
CATEGORY 0010 UNLESS
OTHERWISE NOTED

PROJECT NUMBER: 3180-10-70

HWY: BURLINGTON BYPASS

COUNTY: RACINE

MISCELLANEOUS QUANTITIES

SHEET NO: 245

E

ADD #1
REV SHT 246
6/29/2007

TEMPORARY PAVEMENT MARKING

649.0400			
TEMPORARY PAVEMENT MARKING REMOVABLE TAPE 4-INCH			
STATION	LOCATION	YELLOW	
		WHITE LF	YELLOW LF
349+25 - 351+65	STH 83	--	240
350+01 - 355+05	STH 83	505	--
1130+42 - 1132+27	BYPASS	183	--
1130+78 - 1132+27	BYPASS	147	--
1132+31 - 1133+37	BYPASS	105	--
1141+40 - 1148+00	BYPASS	660	--
TOTAL		1,600	240

REVISION DATE: 5/25/07

REVISION NOTE: ITEMS HIGHLIGHTED REFLECT PLAN REVISIONS AND ADDITIONS.

NOTE: ALL QUANTITIES ARE CATEGORY 0010 UNLESS OTHERWISE NOTED

CONSTRUCTION STAKING

STATION	LOCATION	650.4000		650.4500		650.5000		650.6000		650.6500.01		650.6500.02		650.6500.03		650.7500		650.9900	
		CONSTRUCTION STAKING	CONSTRUCTION STAKING	CONSTRUCTION STAKING	CONSTRUCTION STAKING	CONSTRUCTION STAKING	CONSTRUCTION STAKING	CONSTRUCTION STAKING	CONSTRUCTION STAKING	CONSTRUCTION STAKING	CONSTRUCTION STAKING	CONSTRUCTION STAKING	CONSTRUCTION STAKING	CONSTRUCTION STAKING	CONSTRUCTION STAKING	CONSTRUCTION STAKING	CONSTRUCTION STAKING	CONSTRUCTION STAKING	
STORM SEWER SYSTEM		LF	LF	LF	LF	BASE	PIPE CULVERTS EACH	STRUCTURE LAYOUT (STRUCTURE)	STRUCTURE LAYOUT (STRUCTURE)	STRUCTURE LAYOUT (STRUCTURE)	STRUCTURE LAYOUT (STRUCTURE)	STRUCTURE LAYOUT (STRUCTURE)	STRUCTURE LAYOUT (STRUCTURE)	STRUCTURE LAYOUT (STRUCTURE)	STRUCTURE LAYOUT (STRUCTURE)	WALL	CONSTRUCTION STAKING	INITIAL LAYOUT	
1123+94 - 1132+66	BYPASS		506		872													506	
1143+04 1154+00	BYPASS				1096														
1154+00 - 1156+00	BYPASS		200		200													200	
1156+00 - 1278+35	BYPASS				12235														
1280+10 - 1326+00	BYPASS				4590														
1326+00 - 1334+00	BYPASS		800		800													800	
1334+00 - 1389+48	BYPASS				5548														
1393+34 - 1404+52	BYPASS				1118														
1404+52 - 1405+50	BYPASS				98											98			
1405+29 - 1409+40	BYPASS				350											411			
1409+00 - 1415+00	BYPASS				600														
340+80 - 369+35	STH 83	22	2855		2855													2855	
97+00 - 118+00	BREVER ROAD	2	2100		2100		3											2100	
51+20 - 60+17	STH 142 NE RAMP				897														
39+38 - 49+04	STH 142 SW RAMP				966														
91+00 - 110+75	KETTERHAGEN ROAD	5	1975		1975		2												
51+00 - 58+14	CTH A NW RAMP				714													1975	
39+60 - 49+75	CTH A SE RAMP				1015														
196+00 - 203+70	STH 36/83 NB-SB RAMP				770					1									
C-51-22	STH 83																		
B-51-95	BREVER ROAD											1							
B-51-101	KETTERHAGEN ROAD													1					
TOTAL		29	8436		38799		5	1	1	1	1	1	1	1	1	509		8436	

PROJECT NUMBER: 3180-10-70

HWY: BURLINGTON BYPASS

COUNTY: RACINE

MISCELLANEOUS QUANTITIES

SHEET NO: 246

E

FILE NAME: S:\DOT\DOT_SE04081\WORK FOR 09\ESTIMATES\0481_MISCQUANT_09.ppt

ORIGINATOR: JUSTIN M. ARNOT

ORG. DATE: MARCH 3, 2006

PLOTTED DATE: 6/13/2007 11:44 AM

SAWCUTS

STATION	OFFSET	LOCATION	690.0100		690.0200	
			SAWING EXISTING PAVEMENT	LF	SAWING CONCRETE PAVEMENT FULL DEPTH	LF
102+54	C/L	YAHNKE ROAD	49			
340+80	C/L	STH 83	18		25	
343+34	RT	STH 83	34		--	
355+75	RT	STH 83	24		--	
357+49	RT	STH 83	16		--	
360+69	RT	STH 83	24		--	
362+06	RT	STH 83	37		--	
364+41	LT	STH 83	25		--	
368+25	LT	STH 83	12		--	
369+35	C/L	STH 83	20		25	
14+50	C/L	HIDDEN CREEK LANE	42		5	
14+60	LT	HIDDEN CREEK LANE	18		--	
97+00	C/L	BREVER RD	22		--	
118+00	C/L	BREVER RD	22		--	
101+08	C/L	STH 142	30		--	
143+39	C/L	STH 142	30		--	
104+25	C/L	MT TOM RD	22		--	
115+67	C/L	STH 11	30		--	
168+00	C/L	STH 11	34		--	
168+00 - 168+40	RT	STH 11	40		--	
91+00	C/L	KETTERHAGEN RD	22		--	
91+39	LT	KETTERHAGEN RD	16		--	
110+75	C/L	KETTERHAGEN RD	22		--	
13+26	C/L	MCCAAN DRIVE	16		--	
37+69	C/L	CTH A	30		--	
70+25	C/L	CTH A	30		--	
48+00	C/L	OLD CTH A	22		--	
52+25	C/L	RIVER RD	20		--	
TOTAL			678		55	

REVISION DATE: 5/25/07

REVISION NOTE: ITEMS
HIGHLIGHTED REFLECT PLAN
REVISIONS AND ADDITIONS.NOTE: ALL QUANTITIES ARE
CATEGORY 0010 UNLESS OTHERWISE
NOTED

COVER SIGNS TYPE 1

SPV.0060.03
COVER SIGNS

STATION	LOCATION	EACH TYPE 1	DESCRIPTION	NOTE
171+00	STH 36/83	1	SIGN BRIDGE S-51-16	REMOVE EXISTING COVERING. COVER STH 36 & STH 11 SHIELDS
173+00	STH 36/83	1	TYPE 1 SIGN	REMOVE EXISTING COVERING
191+00	STH 36/83	1	SIGN BRIDGE S-51-14 (RT SIGN)	REMOVE EXISTING COVERING. COVER STH 36 & STH 11 SHIELDS & "ELKHORN"
1411+75	BYPASS	1	SIGN BRIDGE S-51-15 (RT SIGN)	REMOVE EXISTING COVERING
1411+75	BYPASS	1	SIGN BRIDGE S-51-15 (LT SIGN)	REMOVE EXISTING COVERING & "ELKHORN"
1428+77	BYPASS	1	TYPE 1 SIGN	REMOVE EXISTING COVERING. COVER STH 36 & STH 11 SHIELDS & "ELKHORN"
1519+77	BYPASS	1	TYPE 1 SIGN	REMOVE EXISTING COVERING. COVER STH 36 & STH 11 SHIELDS & "ELKHORN"
TOTAL		7		

TEST ROLLING

SPV.0170.01
TEST ROLLING
211.0500
PREPARE FOUNDATION
FOR BASE AGGREGATE

STATION -	STATION	LOCATION	STA	STA
1123+94 -	1132+66	BYPASS EB & WB	17	17
1143+04 -	1278+35	BYPASS EB & WB	271	271
1280+10 -	1389+48	BYPASS EB & WB	219	219
1393+34 -	1415+00	BYPASS EB & WB	43	43
340+80 -	369+35	STH 83	29	
97+00 -	118+00	BREVER RD	21	
51+20 -	60+17	STH 142 NE RAMP EB & WB	18	18
39+38 -	49+04	STH 142 SW RAMP EB & WB	19	19
91+00 -	110+75	KETTERHAGEN ROAD	20	
51+00 -	58+14	CTH A NW RAMP NB & SB	14	14
39+60 -	49+75	CTH A SE RAMP NB & SB	20	20
196+00 -	203+70	STH 36/83 NB-SB RAMP	8	8
TOTAL			699	629

ADD #1
REV SHT 247
6/29/2007

PROJECT NUMBER: 3180-10-70

HWY: BURLINGTON BYPASS

COUNTY: RACINE

MISCELLANEOUS QUANTITIES

SHEET NO: 247

E

FILE NAME: S:\DOT\DOT_SE04081\WORK FOR
09\ESTIMATES\04081_MISC\QUANT_09.ppt

ORIGINATOR: JUSTIN M. ARNOT

ORIG. DATE: MARCH 3, 2006

PLOTTED DATE: 6/13/2007 11:44 AM

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20070710018PROJECT(S):
3180-10-70FEDERAL ID(S):
N/A

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0210	208.0100 BORROW	350,609.000 CY	.		.	
0220	209.0100 BACKFILL GRANULAR	41,579.000 CY	.		.	
0230	210.0100 BACKFILL STRUCTURE	594.000 CY	.		.	
0240	211.0500 PREPARE FOUNDATION FOR BASE AGGREGATE	629.000 STA	.		.	
0250	213.0100 FINISHING ROADWAY (PROJECT) 01. 3180-10-70	1.000 EACH	.		.	
0260	214.0100 OBLITERATING OLD ROAD	1.000 STA	.		.	
0270	301.0100.S QMP BASE AGGREGATE	275,105.000 TON	.		.	
0280	305.0110 BASE AGGREGATE DENSE 3/4-INCH	72,972.000 TON	.		.	
0290	305.0120 BASE AGGREGATE DENSE 1 1/4-INCH	202,148.000 TON	.		.	
0300	311.0110 BREAKER RUN	1,000.000 TON	.		.	
0310	415.0070 CONCRETE PAVEMENT 7-INCH	38.000 SY	.		.	

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20070710018PROJECT(S):
3180-10-70FEDERAL ID(S):
N/A

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0320	415.2000.S INCENTIVE STRENGTH CONCRETE PAVEMENT	400.000 DOL	1.00000		400.00	
0330	415.3000.S QMP CONCRETE PAVEMENT	2.000 DAY	.		.	
0340	416.0050 CONCRETE PAVEMENT APPROACH SLAB	152.000 SY	.		.	
0350	416.0170 CONCRETE DRIVEWAY 7-INCH	203.000 SY	.		.	
0360	416.0610 PAVEMENT TIES	40.000 EACH	.		.	
0370	416.1010 CONCRETE SURFACE DRAINS	64.000 CY	.		.	
0380	455.0115 ASPHALTIC MATERIAL PG64-22	3,793.000 TON	.		.	
0390	455.0120 ASPHALTIC MATERIAL PG64-28	2,050.000 TON	.		.	
0400	455.0605 TACK COAT	13,352.000 GAL	.		.	
0410	460.1103 HMA PAVEMENT TYPE E-3	92,246.000 TON	.		.	
0420	460.2000 INCENTIVE DENSITY HMA PAVEMENT	57,599.000 DOL	1.00000		57599.00	

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20070710018PROJECT(S):
3180-10-70FEDERAL ID(S):
N/A

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0430	460.2500.S QMP HMA PAVEMENT NUCLEAR DENSITY	92,246.000 TON	.		.	
0440	460.3000 QMP HMA MIXTURE	92,246.000 TON	.		.	
0450	465.0105 ASPHALTIC SURFACE	2,971.000 TON	.		.	
0460	465.0120 ASPHALTIC SURFACE DRIVEWAYS AND FIELD ENTRANCES	548.000 TON	.		.	
0470	465.0125 ASPHALTIC SURFACE TEMPORARY	981.000 TON	.		.	
0480	465.0315 ASPHALTIC FLUMES	180.000 SY	.		.	
0490	465.0400 ASPHALTIC SHOULDER RUMBLE STRIP	102,297.000 LF	.		.	
0500	502.0100 CONCRETE MASONRY BRIDGES	936.000 CY	.		.	
0510	502.0400.S INCENTIVE STRENGTH CONCRETE STRUCTURES	908.000 DOL	1.00000		908.00	
0520	502.3200 PROTECTIVE SURFACE TREATMENT	1,976.000 SY	.		.	
0530	502.6105 MASONRY ANCHORS TYPE S 5/8-INCH	22.000 EACH	.		.	

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20070710018PROJECT(S):
3180-10-70FEDERAL ID(S):
N/A

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0760	522.1018 APRON ENDWALLS FOR CULVERT PIPE REINFORCED CONCRETE 18-INCH	2.000 EACH	.		.	
0770	522.1024 APRON ENDWALLS FOR CULVERT PIPE REINFORCED CONCRETE 24-INCH	6.000 EACH	.		.	
0780	601.0411 CONCRETE CURB & GUTTER 30-INCH TYPE D	1,620.000 LF	.		.	
0790	601.0554 CONCRETE CURB & GUTTER 4-INCH MOUNTABLE 36-INCH TYPE D	148.000 LF	.		.	
0800	601.0558 CONCRETE CURB & GUTTER 6-INCH MOUNTABLE 36-INCH TYPE D	30,762.000 LF	.		.	
0810	602.0405 CONCRETE SIDEWALK 4-INCH	200.000 SF	.		.	
0820	602.0505 CURB RAMP DETECTABLE WARNING FIELD YELLOW	80.000 SF	.		.	
0830	603.0105 CONCRETE BARRIER SINGLE-FACED 32-INCH	509.000 LF	.		.	
0840	603.0500 CONCRETE BARRIER TEMPORARY PRECAST CONTRACTOR FURNISHED & DELIVERED	5,840.000 LF	.		.	
0850	603.0801 CONCRETE BARRIER TEMPORARY PRECAST CONTRACTOR INSTALLED	5,840.000 LF	.		.	

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20070710018PROJECT(S):
3180-10-70FEDERAL ID(S):
N/A

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0860	604.0500 SLOPE PAVING CRUSHED AGGREGATE	745.000 SY	.		.	
0870	606.0200 RIPRAP MEDIUM	641.000 CY	.		.	
0880	608.0312 STORM SEWER PIPE REINFORCED CONCRETE CLASS III 12-INCH	2,040.000 LF	.		.	
0890	608.0318 STORM SEWER PIPE REINFORCED CONCRETE CLASS III 18-INCH	405.000 LF	.		.	
0900	608.0324 STORM SEWER PIPE REINFORCED CONCRETE CLASS III 24-INCH	720.000 LF	.		.	
0910	608.0412 STORM SEWER PIPE REINFORCED CONCRETE CLASS IV 12-INCH	42.000 LF	.		.	
0920	608.0424 STORM SEWER PIPE REINFORCED CONCRETE CLASS IV 24-INCH	168.000 LF	.		.	
0930	611.0201 MANHOLES TYPE 1	7.000 EACH	.		.	
0940	611.0210 MANHOLES TYPE 3	10.000 EACH	.		.	
0950	611.0301 INLETS TYPE 1	6.000 EACH	.		.	
0960	611.0302 INLETS TYPE 2	2.000 EACH	.		.	

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20070710018PROJECT(S):
3180-10-70FEDERAL ID(S):
N/A

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0970	611.0303 INLETS TYPE 3	61.000				
	EACH		.		.	
0980	611.0305 INLETS TYPE 8	4.000				
	EACH		.		.	
0990	611.0530 MANHOLE COVERS TYPE J	7.000				
	EACH		.		.	
1000	611.0606 INLET COVERS TYPE B	10.000				
	EACH		.		.	
1010	611.0609 INLET COVERS TYPE B-A	1.000				
	EACH		.		.	
1020	611.0624 INLET COVERS TYPE H	9.000				
	EACH		.		.	
1030	611.0627 INLET COVERS TYPE HM	115.000				
	EACH		.		.	
1040	611.0636 INLET COVERS TYPE HM-S	19.000				
	EACH		.		.	
1050	611.0639 INLET COVERS TYPE H-S	4.000				
	EACH		.		.	
1060	611.0642 INLET COVERS TYPE MS	6.000				
	EACH		.		.	
1070	611.0654 INLET COVERS TYPE V	3.000				
	EACH		.		.	

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20070710018PROJECT(S):
3180-10-70FEDERAL ID(S):
N/A

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
1080	611.8110 ADJUSTING MANHOLE COVERS	17.000 EACH	.		.	
1090	611.8115 ADJUSTING INLET COVERS	83.000 EACH	.		.	
1100	612.0106 PIPE UNDERDRAIN 6-INCH	176.000 LF	.		.	
1110	612.0206 PIPE UNDERDRAIN UNPERFORATED 6-INCH	100.000 LF	.		.	
1120	612.0212 PIPE UNDERDRAIN UNPERFORATED 12-INCH	309.000 LF	.		.	
1130	612.0700 DRAIN TILE EXPLORATION	5,600.000 LF	.		.	
1140	614.0115 ANCHORAGES FOR STEEL PLATE BEAM GUARD TYPE 2	3.000 EACH	.		.	
1150	614.0150 ANCHOR ASSEMBLIES FOR STEEL PLATE BEAM GUARD	8.000 EACH	.		.	
1160	614.0200 STEEL THRIE BEAM STRUCTURE APPROACH	391.400 LF	.		.	
1170	614.0220.S STEEL THRIE BEAM BULL NOSE TERMINAL	6.000 EACH	.		.	
1180	614.0230.S STEEL THRIE BEAM	400.000 LF	.		.	

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20070710018PROJECT(S):
3180-10-70FEDERAL ID(S):
N/A

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
1190	614.0305 STEEL PLATE BEAM GUARD CLASS A	5,700.000 LF	.		.	
1200	614.0370 STEEL PLATE BEAM GUARD ENERGY ABSORBING TERMINAL	20.000 EACH	.		.	
1210	614.0605 MARKER POSTS RIGHT-OF-WAY	226.000 EACH	.		.	
1220	614.0620.S MARKER POSTS CULVERT END FLEXIBLE	43.000 EACH	.		.	
1230	614.0905 CRASH CUSHIONS TEMPORARY	2.000 EACH	.		.	
1240	616.0404 FENCE CHAIN LINK SALVAGED 4-FT	22.000 LF	.		.	
1250	618.0100 MAINTENANCE AND REPAIR OF HAUL ROADS (PROJECT) 01. 3180-10-70	1.000 EACH	.		.	
1260	619.1000 MOBILIZATION	1.000 EACH	.		.	
1270	620.0300 CONCRETE MEDIAN SLOPED NOSE	2,082.000 SF	.		.	
1280	621.0100 LANDMARK REFERENCE MONUMENTS	22.000 EACH	.		.	
1290	623.0200 DUST CONTROL SURFACE TREATMENT	331,752.000 SY	.		.	

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20070710018PROJECT(S):
3180-10-70FEDERAL ID(S):
N/A

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
1300	624.0100 WATER	2,712.000 MGAL	.		.	
1310	625.0100 TOPSOIL	14,128.000 SY	.		.	
1320	625.0500 SALVAGED TOPSOIL	89,457.000 SY	.		.	
1330	627.0200 MULCHING	249,731.000 SY	.		.	
1340	628.1104 EROSION BALES	881.000 EACH	.		.	
1350	628.1504 SILT FENCE	5,536.000 LF	.		.	
1360	628.1520 SILT FENCE MAINTENANCE	5,536.000 LF	.		.	
1370	628.1905 MOBILIZATIONS EROSION CONTROL	10.000 EACH	.		.	
1380	628.1910 MOBILIZATIONS EMERGENCY EROSION CONTROL	15.000 EACH	.		.	
1390	628.2004 EROSION MAT CLASS I TYPE B	49,700.000 SY	.		.	
1400	628.2027 EROSION MAT CLASS II TYPE C	2,100.000 SY	.		.	

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20070710018PROJECT(S):
3180-10-70FEDERAL ID(S):
N/A

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
1410	628.5505 POLYETHYLENE SHEETING	2,534.000 SY	.		.	
1420	628.7005 INLET PROTECTION TYPE A	54.000 EACH	.		.	
1430	628.7010 INLET PROTECTION TYPE B	15.000 EACH	.		.	
1440	628.7015 INLET PROTECTION TYPE C	149.000 EACH	.		.	
1450	628.7504 TEMPORARY DITCH CHECKS	800.000 LF	.		.	
1460	628.7550 CULVERT PIPE DITCH CHECKS	10.000 EACH	.		.	
1470	628.7560.S STONE OR ROCK DITCH CHECKS	265.000 CY	.		.	
1480	629.0205 FERTILIZER TYPE A	1.000 CWT	.		.	
1490	629.0210 FERTILIZER TYPE B	172.000 CWT	.		.	
1500	630.0120 SEEDING MIXTURE NO. 20	3,015.000 LB	.		.	
1510	630.0130 SEEDING MIXTURE NO. 30	2,453.000 LB	.		.	

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20070710018PROJECT(S):
3180-10-70FEDERAL ID(S):
N/A

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
1520	630.0300 SEEDING BORROW PIT	370.000 LB	.		.	
1530	631.1000 SOD LAWN	1,100.000 SY	.		.	
1540	631.1100 SOD EROSION CONTROL	300.000 SY	.		.	
1550	633.0100 DELINEATOR POSTS STEEL	291.000 EACH	.		.	
1560	633.0500 DELINEATORS	291.000 EACH	.		.	
1570	634.0614 POSTS WOOD 4X6-INCH X 14-FT	142.000 EACH	.		.	
1580	634.0616 POSTS WOOD 4X6-INCH X 16-FT	193.000 EACH	.		.	
1590	634.0618 POSTS WOOD 4X6-INCH X 18-FT	59.000 EACH	.		.	
1600	634.0620 POSTS WOOD 4X6-INCH X 20-FT	19.000 EACH	.		.	
1610	634.0622 POSTS WOOD 4X6-INCH X 22-FT	4.000 EACH	.		.	
1620	634.0814 POSTS TUBULAR STEEL 2X2-INCH X 14-FT	3.000 EACH	.		.	

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20070710018PROJECT(S):
3180-10-70FEDERAL ID(S):
N/A

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
1630	637.0202 SIGNS REFLECTIVE TYPE II	5,071.000 SF	.		.	
1640	638.2602 REMOVING SIGNS TYPE II	21.000 EACH	.		.	
1650	638.3000 REMOVING SMALL SIGN SUPPORTS	21.000 EACH	.		.	
1660	642.5401 FIELD OFFICE TYPE D	1.000 EACH	.		.	
1670	642.6001 FIELD LABORATORY	1.000 EACH	.		.	
1680	643.0200 TRAFFIC CONTROL SURVEILLANCE AND MAINTENANCE (PROJECT) 01. 3180-10-70	427.000 DAYS	.		.	
1690	643.0300 TRAFFIC CONTROL DRUMS	15,881.000 DAYS	.		.	
1700	643.0420 TRAFFIC CONTROL BARRICADES TYPE III	45,209.000 DAYS	.		.	
1710	643.0453 TRAFFIC CONTROL BARRICADES PERMANENT TYPE III	28.000 EACH	.		.	
1720	643.0500 TRAFFIC CONTROL FLEXIBLE TUBULAR MARKER POSTS	111.000 EACH	.		.	

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20070710018PROJECT(S):
3180-10-70FEDERAL ID(S):
N/A

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
1730	643.0600 TRAFFIC CONTROL FLEXIBLE TUBULAR MARKER BASES	111.000 EACH	.		.	
1740	643.0705 TRAFFIC CONTROL WARNING LIGHTS TYPE A	19,402.000 DAYS	.		.	
1750	643.0800 TRAFFIC CONTROL ARROW BOARDS	3,003.000 DAYS	.		.	
1760	643.0900 TRAFFIC CONTROL SIGNS	42,218.000 DAYS	.		.	
1770	643.0905.S TRAFFIC CONTROL COVERING SIGNS	20.000 EACH	.		.	
1780	643.1050.S TRAFFIC CONTROL SIGNS PORTABLE CHANGEABLE MESSAGE	854.000 DAY	.		.	
1790	643.3000 TRAFFIC CONTROL DETOUR SIGNS	29,455.000 DAYS	.		.	
1800	645.0111 GEOTEXTILE FABRIC TYPE DF SCHEDULE A	148.000 SY	.		.	
1810	645.0120 GEOTEXTILE FABRIC TYPE HR	1,019.000 SY	.		.	
1820	645.0140 GEOTEXTILE FABRIC TYPE SAS	600.000 SY	.		.	
1830	646.0106 PAVEMENT MARKING EPOXY 4-INCH	181,800.000 LF	.		.	

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20070710018PROJECT(S):
3180-10-70FEDERAL ID(S):
N/A

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
1840	646.0126 PAVEMENT MARKING EPOXY 8-INCH	11,270.000 LF	.		.	
1850	646.0406 PAVEMENT MARKING SAME DAY EPOXY 4-INCH	33,400.000 LF	.		.	
1860	646.0600 REMOVING PAVEMENT MARKINGS	975.000 LF	.		.	
1870	646.0871.S PAVEMENT MARKING WET REFLECTIVE TAPE 4-INCH	15,200.000 LF	.		.	
1880	647.0166 PAVEMENT MARKING ARROWS EPOXY TYPE 2	43.000 EACH	.		.	
1890	647.0356 PAVEMENT MARKING WORDS EPOXY	34.000 EACH	.		.	
1900	647.0566 PAVEMENT MARKING STOP LINE EPOXY 18-INCH	563.000 LF	.		.	
1910	647.0606 PAVEMENT MARKING ISLAND NOSE EPOXY	51.000 EACH	.		.	
1920	647.0726 PAVEMENT MARKING DIAGONAL EPOXY 12-INCH	467.000 LF	.		.	
1930	649.0400 TEMPORARY PAVEMENT MARKING REMOVABLE TAPE 4-INCH	1,840.000 LF	.		.	
1940	650.4000 CONSTRUCTION STAKING STORM SEWER SYSTEM	29.000 EACH	.		.	

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20070710018PROJECT(S):
3180-10-70FEDERAL ID(S):
N/A

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
1950	650.4500 CONSTRUCTION STAKING SUBGRADE	8,436.000 LF	.		.	
1960	650.5000 CONSTRUCTION STAKING BASE	38,799.000 LF	.		.	
1970	650.5500 CONSTRUCTION STAKING CURB GUTTER AND CURB & GUTTER	32,530.000 LF	.		.	
1980	650.6000 CONSTRUCTION STAKING PIPE CULVERTS	6.000 EACH	.		.	
1990	650.6500 CONSTRUCTION STAKING STRUCTURE LAYOUT (STRUCTURE) 01. C-51-22	LUMP	LUMP		.	
2000	650.6500 CONSTRUCTION STAKING STRUCTURE LAYOUT (STRUCTURE) 02. B-51-95	LUMP	LUMP		.	
2010	650.6500 CONSTRUCTION STAKING STRUCTURE LAYOUT (STRUCTURE) 03. B-51-101	LUMP	LUMP		.	
2020	650.7500 CONSTRUCTION STAKING CONCRETE BARRIER	509.000 LF	.		.	
2030	650.9900 CONSTRUCTION STAKING INITIAL LAYOUT	8,436.000 LF	.		.	
2040	652.0225 CONDUIT RIGID NONMETALLIC SCHEDULE 40 2-INCH	3,297.000 LF	.		.	

Wisconsin Department of Transportation

PAGE: 23

DATE: 06/28/07

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20070710018PROJECT(S):
3180-10-70FEDERAL ID(S):
N/A

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
2360	SPV.0165 SPECIAL 03. COVERING SIGNS TYPE II	595.000 SF	.		.	
2370	SPV.0170 SPECIAL 01. TEST ROLLING	699.000 STA	.		.	
2380	SPV.0180 SPECIAL 01. GEOTEXTILE FABRIC TYPE FF	1,840.000 SY	.		.	
2390	SPV.0195 SPECIAL 01. WASHED STONE	18.000 TON	.		.	
	SECTION 0001 TOTAL				.	
	TOTAL BID				.	

