

DATE 09/30/91

ESTIMATE OF QUANTITIES

ITEM	ITEM DESCRIPTION	UNIT	TOTAL	8010-01-71 QUANTITY	8010-14-71 QUANTITY
20101	CLEARING	STA.	417.00	417.00	
20104	GRUBBING	STA.	417.00	417.00	
20330	REMOVING OLD CULVERTS	EACH	11.00	11.00	
20351	REMOVING OLD BRIDGE, STATION 509+01	L.S.	1.00		1.00
20419	REMOVING ASPHALTIC SURFACE, BUTT JOINTS	S.Y.	45.00	45.00	
20501	COMMON EXCAVATION	C.Y.	109,370.00	109,370.00	
20502	ROCK EXCAVATION	C.Y.	4,053.00	4,053.00	
20505	MARSH EXCAVATION	C.Y.	24,183.00	24,183.00	
20620	EXCAVATION FOR STRUCTURES, CULVERTS B-16-76	L.S.	1.00		1.00
20801	BORROW EXCAVATION	C.Y.	3,339.00	3,339.00	
20811	SELECTED BORROW EXCAVATION	C.Y.	121,775.00	121,775.00	
21201	GRANULAR SUBBASE COURSE	C.Y.	90,668.00	90,668.00	
21302	FINISHING ROADWAY, PROJECT 8010-01-71	L.S.	1.00	1.00	
30404	CRUSHED AGGREGATE BASE COURSE	TON	116,099.00	116,099.00	
40204	ASPHALTIC MATERIAL FOR TACK COAT	GAL.	2,020.00	2,020.00	
40501	ASPHALTIC MATERIAL FOR PLANT MIXES	TON	1,850.00	1,850.00	
50401	CONCRETE MASONRY, CULVERTS	C.Y.	154.00		154.00
50505	HIGH-STRENGTH BAR STEEL REINFORCEMENT, CULVERTS	LB.	18,490.00		18,490.00
50601	STRUCTURAL CARBON STEEL	LB.	210.00		210.00
52003	CULVERT PIPE, CLASS III, 18-INCH	L.F.	654.00	654.00	
52005	CULVERT PIPE, CLASS III, 24-INCH	L.F.	32.00	32.00	
52061	APRON ENDWALLS FOR CULVERT PIPE, 18-INCH	EACH	40.00	40.00	
52063	APRON ENDWALLS FOR CULVERT PIPE, 24-INCH	EACH	2.00	2.00	
52507	CORRUGATED ALUMINUM CULVERT PIPE, 24-INCH	L.F.	1,158.00	1,158.00	
52508	CORRUGATED ALUMINUM CULVERT PIPE, 30-INCH	L.F.	12.00	12.00	
52509	CORRUGATED ALUMINUM CULVERT PIPE, 36-INCH	L.F.	80.00	80.00	

Sheet 3

ITEM	ITEM DESCRIPTION	UNIT	TOTAL	8010-01-71 QUANTITY	8010-14-71 QUANTITY
52311	CORRUGATED ALUMINUM CULVERT PIPE, 48-INCH	L.F.	212.00	212.00	
52554	METAL APRON ENDWALLS FOR ALUMINUM CULVERT PIPE, 24-INCH	EACH	36.00	36.00	
52555	METAL APRON ENDWALLS FOR ALUMINUM CULVERT PIPE, 30-INCH	EACH	2.00	2.00	
52556	METAL APRON ENDWALLS FOR ALUMINUM CULVERT PIPE, 36-INCH	EACH	4.00	4.00	
52558	METAL APRON ENDWALLS FOR ALUMINUM CULVERT PIPE, 48-INCH	EACH	8.00	8.00	
60170	CONCRETE CURB AND CUTTER, 36-INCH, TYPE D	L.F.	360.00	360.00	
60601	RIPRAP	C.Y.	175.00	175.00	
61211	PIPE UNDERDRAIN, UNPERFORATED, 6-INCH	L.F.	459.00	459.00	
61236	PIPE UNDERDRAIN, WRAPPED, 6-INCH	L.F.	521.00	521.00	
61406	ANCHORAGES FOR STEEL PLATE BEAM GUARD	EACH	3.00	3.00	
61408	STEEL PLATE BEAM GUARD, CLASS A	L.F.	320.00	320.00	
61412	ANCHORAGES FOR STEEL PLATE BEAM GUARD, TYPE 1	EACH	1.00	1.00	
61422	MARKER POSTS FOR RIGHT-OF-WAY	EACH	74.00	74.00	
61802	MAINTENANCE AND REPAIR OF HAUL ROADS, PROJECT 8010-01-71	L.S.	1.00	1.00	
61910	MOBILIZATION	L.S.	1.00	1.00	
62101	LANDMARK REFERENCE MONUMENTS	EACH	50.00	50.00	
62203	ASPHALTIC FLUMES	S.Y.	11.00	11.00	
62401	WATER	MGAL	400.00	400.00	
62501	TOPSOIL	S.Y.	33,450.00	33,450.00	
62505	SALVAGED TOPSOIL	S.Y.	137,340.00	137,340.00	
62702	MULCHING	S.Y.	194,175.00	194,175.00	
62803	EROSION MAT, DELIVERED	S.Y.	3,300.00	3,300.00	
62804	EROSION MAT, INSTALLED	S.Y.	3,300.00	3,300.00	
62811	EROSION BALES, DELIVERED	EACH	80.00	80.00	
62812	EROSION BALES, INSTALLED	EACH	80.00	80.00	
62815	SILT FENCE, DELIVERED	L.F.	4,581.00	4,581.00	
62816	SILT FENCE, INSTALLED	L.F.	4,581.00	4,581.00	
62817	SILT FENCE MAINTENANCE	L.F.	4,581.00	4,581.00	
62819	MOBILIZATIONS EROSION CONTROL	EACH	2.00	2.00	
62905	FERTILIZER, TYPE B	CWT.	123.70	123.70	
62911	AGRICULTURAL LIMESTONE TREATMENT	TON	11.40	11.40	
63002	SEEDING	LB.	3,520.00	3,520.00	
64202	FIELD OFFICE, TYPE B	L.S.	1.00	1.00	
64210	FIELD LABORATORY	L.S.	1.00	1.00	
64302	TRAFFIC CONTROL PROJECT 8010-01-71	L.S.	1.00	1.00	
64401	PAVEMENT MARKING, HOT PAINT	L.F.	156,145.00	156,145.00	
64404	TEMPORARY PAVEMENT MARKING	L.F.	7,900.00	7,900.00	
64502	GEOTEXTILE FABRIC, TYPE MS	S.Y.	54,564.00	54,564.00	
64505	GEOTEXTILE FABRIC, TYPE R	S.Y.	470.00	470.00	
90001	MAINTENANCE OF RIGHT-OF-WAY MARKERS, 8010-01-71	L.S.	1.00	1.00	
90391	ASPHALTIC CONCRETE PAVEMENT, TYPE C1	TON	30,850.00	30,850.00	
90643	SAND BAGS	EACH	1,000.00	1,000.00	
90726	LOCATING NO PASSING ZONES	MI.	9.35	9.35	

Sheet 3: 1