

DATE 21MAR00

ESTIMATE OF QUANTITIES

SHEET: 3.1

LINE NUMBER	ITEM	ITEM DESCRIPTION	UNIT	TOTAL	8476-02-71 QUANTITY
0010	20101	CLEARING	STA.	5.00	5.00
0020	20104	GRUBBING	STA.	5.00	5.00
0030	20351	REMOVING OLD BRIDGE, STATION 10+00	LS	1.00	1.00
0040	20503	UNCLASSIFIED EXCAVATION	C.Y.	365.00	365.00
0050	20610	EXCAVATION FOR STRUCTURES, BRIDGES B-65-46	LS	1.00	1.00
0060	20801	BORROW EXCAVATION	C.Y.	450.00	450.00
0070	21001	STRUCTURE BACKFILL	C.Y.	350.00	350.00
0080	21301	FINISHING ROADWAY	LS	1.00	1.00
0090	30403	CRUSHED AGGREGATE BASE COURSE	C.Y.	700.00	700.00
0100	41101	ASPHALTIC SURFACE	TON	230.00	230.00
0110	50201	CONCRETE MASONRY, BRIDGES	C.Y.	169.00	169.00
0120	50265	PROTECTIVE SURFACE TREATMENT	S.Y.	349.00	349.00
0130	50305	PRESTRESSED GIRDER, I TYPE, 45-INCH	L.F.	412.00	412.00
0140	50504	HIGH STRENGTH BAR STEEL REINFORCEMENT, BRIDGES	LB.	12,360.00	12,360.00
0150	50511	COATED HIGH STRENGTH BAR STEEL REINFORCEMENT, BRIDGES	LB.	11,480.00	11,480.00
0160	50626	NON-LAMINATED ELASTOMERIC BEARING PADS	EACH	8.00	8.00
0170	50640	STEEL DIAPHRAGMS, STRUCTURE B-65-46	EACH	6.00	6.00
0180	51030	CAST IN PLACE CONCRETE PILING, DELIVERED AND DRIVEN, 10 3/4-INCH	L.F.	660.00	660.00
0190	51340	TUBULAR RAILING, TYPE F, STRUCTURE B-65-46	LS	1.00	1.00
0200	51605	RUBBERIZED MEMBRANE WATERPROOFING	S.Y.	16.00	16.00
0210	60602	HEAVY RIPRAP	C.Y.	620.00	620.00
0220	61407	STEEL THRIE BEAM STRUCTURE APPROACH	L.F.	132.00	132.00
0230	61408	STEEL PLATE BEAM GUARD, CLASS A	L.F.	28.00	28.00
0240	61435	STEEL PLATE BEAM GUARD, ENERGY ABSORBING TERMINAL	EACH	4.00	4.00
0250	61910	MOBILIZATION	LS	1.00	1.00
0260	62501	TOPSOIL	S.Y.	1,310.00	1,310.00
0270	62702	MULCHING	S.Y.	2,090.00	2,090.00
0280	62815	SILT FENCE, DELIVERED	L.F.	550.00	550.00
0290	62816	SILT FENCE, INSTALLED	L.F.	550.00	550.00
0300	62817	SILT FENCE MAINTENANCE	L.F.	550.00	550.00
0310	62819	MOBILIZATIONS, EROSION CONTROL	EACH	1.00	1.00
0320	62824	EROSION MAT, DELIVERED, CLASS I, TYPE B	S.Y.	440.00	440.00

DATE 21MAR80

ESTIMATE OF QUANTITIES

SHEET: 3.2

LINE NUMBER	ITEM	ITEM DESCRIPTION	UNIT	TOTAL	8476-82-71 QUANTITY
0330	62825	EROSION MAT, INSTALLED, CLASS I, TYPE B	S.Y.	440.00	440.00
0340	62905	FERTILIZER, TYPE B	CWT.	1.00	1.00
0350	63009	SEEDING, MIXTURE NO. 20	LB.	80.00	80.00
0360	63401	WOOD POSTS, 4X4-INCH X 10-FT.	EACH	4.00	4.00
0370	63702	SIGNS, TYPE II, REFLECTIVE	S.F.	12.00	12.00
0380	64202	FIELD OFFICE, TYPE B	LS	1.00	1.00
0390	64301	TRAFFIC CONTROL	LS	1.00	1.00
0400	64506	GEOTEXTILE FABRIC, TYPE HR	S.Y.	1,055.00	1,055.00
0410	66501	SAWING EXISTING PAVEMENT	L.F.	44.00	44.00
0420	90005	MISC 90005A CONSTRUCTION STAKING, STRUCTURE LAYOUT, B-65-46	EACH	1.00	1.00
0430	90030	MISC 90030A CONSTRUCTION STAKING, INITIAL LAYOUT	L.F.	550.00	550.00
0440	90030	MISC 90030B CONSTRUCTION STAKING, SUBGRADE	L.F.	400.00	400.00
0450	90030	MISC 90030C CONSTRUCTION STAKING, CRUSHED AGGREGATE BASE COURSE	L.F.	400.00	400.00