

DETAIL SUMMARY SHEET OF MISCELLANEOUS QUANTITIES

STATE PROJECT NUMBER	SHEET NO.
8476-02-71	3A
SUMMARY OF MISCELLANEOUS QUANTITIES	

CLEARING & GRUBBING

STATION TO STATION	CLEARING STA.	GRUBBING STA.
6+50 - 9+50 LT.	3	3
10+50 - 12+50 LT.	2	2
TOTAL	5	5

CRUSHED AGGREGATE BASE COURSE

LOCATION	BASE COURSE MATERIAL C.Y.	SHOULDER MATERIAL C.Y.
7+50 - 9+46	323	25
10+50 - 12+50	327	25
	650	50
TOTAL		700

ASPHALTIC SURFACE

LOCATION	TON
7+50 - 9+46	114
10+50 - 12+50	116
TOTAL	230

HEAVY RIPRAP

STATION TO STATION	LOCATION	C.Y.
8+80 - 9+64	FLUME LEFT	80
9+64 - 9+88	FLUME LEFT	30
	TOTAL	110

STEEL THRIE BEAM STRUCTURE APPROACH

LOCATION	L.F.
9+14.3 - 9+47.3 LT.	33
9+16.7 - 9+49.7 RT.	33
10+46.3 - 10+79.3 LT.	33
10+48.7 - 10+81.7 RT.	33
TOTAL	132

STEEL PLATE BEAM GUARD, CLASS A

LOCATION	L.F.
9+07.3 - 9+14.3 LT.	7
9+09.7 - 9+16.7 RT.	7
10+79.3 - 10+86.3 LT.	7
10+81.7 - 10+88.7 RT.	7
TOTAL	28

STEEL PLATE BEAM GUARD, ENERGY ABSORBING TERMINAL

LOCATION	EA.
8+57.3 - 9+07.3 LT.	1
8+59.7 - 9+09.7 RT.	1
10+86.3 - 11+36.3 LT.	1
10+88.7 - 11+38.7 RT.	1
TOTAL	4

TOPSOIL

LOCATION	S.Y.
6+00 - 12+50	1310

MULCHING

LOCATION	S.Y.
6+00 - 12+50	2090

SILT FENCE

LOCATION	DELIVERED L.F.	INSTALLED L.F.	MAINTAINED L.F.
7+50 LT.	15	15	15
8+40 LT.	15	15	15
8+95 LT.	15	15	15
9+25 LT.	15	15	15
7+50 RT. (WEST BANK)	320	320	320
(EAST BANK)	170	170	170
TOTAL	550	550	550

EROSION MAT, CLASS I, TYPE B

STATION TO STATION	LOCATION	DELIVERED S.Y.	INSTALLED S.Y.
6+00 - 8+80	LEFT	370	370
10+50 - 11+00	LEFT	70	70
	TOTAL	440	440

FERTILIZER, TYPE B

LOCATION	CWT
6+00 - 12+50	1.8

SEEDING MIXTURE NO. 20

LOCATION	LB.
6+00 - 12+50	80

WOOD POSTS, 4x4-INCHx10-FT.

LOCATION	EACH
9+43 LT.	1
9+46 RT.	1
10+50 LT.	1
10+53 RT.	1
TOTAL	4

SIGNS, TYPE II, REFLECTIVE

LOCATION	S.F.
9+43 LT.	3
9+46 RT.	3
10+50 LT.	3
10+53 RT.	3
TOTAL	12

GEOTEXTILE FABRIC, TYPE HR

LOCATION	S.Y.
8+80 - 9+64 LT.	160
9+64 - 9+88 LT.	45
TOTAL	205

SAWING EXISTING PAVEMENT

STATION	L.F.
7+50	22
12+50	22
TOTAL	44

CONSTRUCTION STAKING, STRUCTURE LAYOUT,

STRUCTURE B-65-46, ITEM 90005A

LOCATION	L.S.
B-65-46	1

CONSTRUCTION STAKING, INITIAL LAYOUT, ITEM 90030A

LOCATION	L.S.
6+00 - 9+50	350
10+50 - 12+50	200
TOTAL	550

CONSTRUCTION STAKING, SUBGRADE, ITEM 90030B

LOCATION	L.S.
7+50 - 9+50	200
10+50 - 12+50	200
TOTAL	400

CONSTRUCTION STAKING, CRUSHED AGGREGATE BASE COURSE, ITEM 90030C

LOCATION	L.S.
7+50 - 9+50	200
10+50 - 12+50	200
TOTAL	400