REHABILITATION STRUCTURE SURVEY REPORT

DT1696 **⊠** Grade Separation ☐ Stream Crossing ☐ Culvert ☐ Railroad ☐ Retaining Wall □ Noise Barrier Sign Structure Other: For guidance see: http://dotnet/dtid_bos/extranet/structures/reports-checklists.htm Design Project ID Construction Project ID Highway (Project Name) **EAU CLAIRE - CHIPPEWA FALLS** 1190-02-34 1190-02-64 Final Plan Due Date Preliminary Plan Due Date 05/01/2018 05/01/2018 WASHINGTON PS&E Date Letting Date County **EAU CLAIRE** 08/01/2018 02/12/2019 Structure Number Section Town Range B-18-38 35 27N 09W Station Latitude: 444619.34 Structure Located on National Highway System 62+63.03 - 63+60.69 Longitude: 912537.97 For Survey and CADD Files **Traffic Forecast Data** Horizontal Coordinate System: Average Daily Roadway Vertical Datum: Design Year Traffic (ADT) Design Speed **Functional Class** Feature On Feature On Principal 14200 70 MPH USH 53 NB 2014 Arterial Feature Under Feature Under Collector KEYSTONE CROSSING Region Contact: Adam Hetrick Consultant Contact: (Area Code) Telephone Number(s): 715-836-2855 (Area Code) Telephone Number(s): Email: adam.hetrick@dot.wi.gov Fmail: Work To Be Performed **Field Information Required** Item Number (see Pages 2-4) ☑ B. Overlay.......1-3, 10-22, 26-28, 32, 34 ☐ Concrete Overlay ☐ Asphalt Overlay ☐ Polymer Modified Asphalt Overlay ☐ Other: □ D. New Railings15–17, 20–23 I. Widening1–28, 30, 32–35 ☐ M. Slope Stabilization......1–3, 30 □ P. Other: ___

Field Information Required

If no structure number exists provide the following: Small County Map on which the location of proposed structure is shown in red and any highway relocation in green. In addition, provide Location Map of scale not less than 1" = 2000' showing the structure location and number.

\boxtimes	1.	Most recent inspection report, brief history of bridge construction date, and description of repairs with dates.
\boxtimes	2.	Outline deficient areas on existing structure plan or drawing.
	3.	Photographs of details requiring repairs or modifications, such as: bearings, x-frames, joints, etc. Photograph all deficient areas. Clearly label all photographs.
	4.	Provide proposed typical section for roadway and structure showing dimensions and cross slopes.
	5.	Survey beam seat or girder elevations at both sides of bridge at all substructure units.
	6.	Provide cross-section elevations at 10 foot intervals extending across the structure and a minimum of 100 feet beyond each end. Sections should be normal to centerline and show elevations at centerline roadway and gutter line. Take elevations along joints and at floor drains.
	7.	Show and identify starting stationing on bridge.
	8.	Record measurement, temperature of the structure, and date taken for each of the following: (a) Joint opening measured normal to joint at centerline of roadway and both curb lines. (b) Clearance between girder ends at piers. (c) Distance from front face of abutment backwall to closest point of girder end measured parallel to girder. (d) Temperature of structure determined by averaging top and under deck (if accessible) readings.
	9.	Fixed and expansion bearings - condition and orientation.
⊠1	0.	Number and width of proposed pours including construction staging sequence.
⊠1	1.	Location of existing construction joints in the deck.

Sq. Yd. <u>0</u>	
Sq. Yd. <u>0</u>	
Sq. Yd. <u>0</u>	Galvanic Anodes? NO
Sq. Ft. <u>0</u>	Galvanic Anodes? NO
Sq. Ft. <u>0</u>	Galvanic Anodes? NO
LF. <u>0</u>	Galvanic Anodes? NO
	Sq. Yd. <u>0</u> Sq. Yd. <u>0</u> Sq. Ft. <u>0</u> Sq. Ft. <u>0</u>

	Deck Condition	Superstructure Condition	Substructure Condition	Load Capacity Appraisal	Structural EVAL Appraisal
Current	6	6	7	5	6

	Inventory	Operational
Current	HS33	HS30
Calculated Date: 07/11/2013	HS23	HS39
After		
Completed by Bridge Designer		

\boxtimes	16. Utilities on/near Structure. (WisDOT policy is to avoid placing utilities on the structure.) ☐ Yes ☐ No						
	Туре	Owner and Contact Information		Opening at Abutment	Weight	Pressure	
	_	dge railing deficient? No If Yes – Replacement Rail Type:					
	18. Drains to be: ☐ Raised	☐ Closed ☐ Downspouted ☐ Ne	eW				
		nined on bridge during work? No If Yes – Include sketches					
	20. Will guard rail ☐ Yes ⊠ N	l be attached? No If Yes – Which corners? Existing guardrail to re	emain at all co	orners.			
		e performed eliminate all deficiencies? No If No – Explain:					
		aste (asbestos) to be removed? No If Yes – Explain:					
\boxtimes	23. Wing location	(s) for surface drain anchors: SE					
		No If Yes – Explain on Page 4 g, color system, containment, bid items)					
		way width: <i>(new deck / widening)</i> Ft. valk clear width: Left: Ft. Right:	_Ft.				
\boxtimes	26. Maximum inc	rease in grade line elevation 3/8 In.					
\boxtimes	27. Benchmark d	escription to be shown					
\boxtimes	28. Desired final	cross slopes on bridge <u>0.015</u> Ft./Ft.					
	 29. Underwater Inspection Report including: Streambed Cross Section With Pier, Footing and Seal Elevations Pier Elevation Drawings Pier Layout Hydrographic Survey 						
	30. Slope stabiliz Type: Slope:	ation, provide: Quantity: CY. Ft./Ft. Fill: CY.					
	-	CY.					

\boxtimes	32.	Report submitted with Preliminary Plan requires no CADD file submittal (See ESubmittal instructions).
	33.	Report submitted for development of Preliminary Plan to structure design engineer requires CADD file (if available) submittal and Report submittal to Soils Engineer if project involves foundation modifications.
	34.	Coordinate with structure design engineer before going into the field if existing structure has no available plans, if staged construction is planned, or if there are adjoining/adjacent structures that will remain in place.
	35.	If project involves substructure widening coordinate with structure and/or hydraulic design engineer to determine if information on the separation and/or stream crossing SSR will be required.


Additional Information

Elaborate on other concerns such as: DNR, Local, Utility Conflicts, Aesthetics, Railing Type and Staged Construction.

Please be as detailed and specific as possible.

- 1.) Structure built in 1966. Concrete Masonry Deck Overlay was completed in 1989 and in 2008. See attached Bridge Inspection Report.
- 2.) Deficient areas to be determined in the field by the engineer. See attached Bridge Inspection Report. A Polymer Overlay is proposed because of deficiency over the entire structure due to poor bridge deck surface. The deck has numerous hairline to medium longitudinal and transverse cracks with light leaching and delamination. There is a 9 ft x 6 inch spall at the southwest joint with no exposed rebar. The deck was scanned with Infrared Thermography in 2009 and showed 1.7% delamination.
- 3.) See attached photographs.
- 10.) This work will be constructed half at a time under traffic using single lane closures during non-peak hours with night work. Nighttime ramp closures are anticipated at some structures. All lanes and ramps will be opened to traffic daily.
- 11.) See asbuilt plans.
- 16.) No utilities on or near structure. No conflicts anticipated.
- 19.) This work will be constructed half at a time under traffic using single lane closures during non-peak hours with night work. Nighttime ramp closures are anticipated at some structures. All lanes and ramps will be opened to traffic daily.
- 22.) See attached Asbestos Inspection Report. Asbestos-containing material was found in the gasket under the railing attachment plates on the concrete parapet. If the asbestos-containing material is not disturbed during construction, the asbestos-containing material can remain.
- 27.) To be determined.
- 32.) See preliminary plans.

CDR Map



₽

ORDER	0F	SHEETS

Section No. 1

Section No. 2 Typical Sections and Details Estimate of Quantities Section No. 3 Miscellaneous Quantities Section No. 4 Right of Way Plat


Section No. 5 Plan and Profile

Section No. 6 Standard Detail Drawings

Section No. 9 Computer Earthwork Data

Section No. 9 Cross Sections

TOTAL SHEETS =



DESIGN DESIGNATION

A.A.D.T. A.A.D.T. D.H.V. D.D. DESIGN SPEED **ESALS**

CONVENTIONAL SYMBOLS PI AN CORPORATE LIMITS PROPERTY LINE LOT LINE LIMITED HIGHWAY EASEMENT EXISTING RIGHT OF WAY PROPOSED OR NEW R/W LINE SLOPE INTERCEPT

REFERENCE LINE EXISTING CULVERT PROPOSED CULVERT COMBUSTIBLE FLUIDS

MARSH AREA

WOODED OR SHRUB AREA

CULVERT (Profile View) UTILITIES ELECTRIC FIBER OPTIC SANITARY SEWER STORM SEWER TELEPHONE UTILITY PEDESTAL POWER POLE ₫ Ø TELEPHONE POLE

PROFILE

GRADE LINE

ORIGINAL GROUND

SPECIAL DITCH

GRADE ELEVATION

MARSH OR ROCK PROFILE

(To be noted as such)

STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION


PLAN OF PROPOSED IMPROVEMENT

EAU CLAIRE - CHIPPEWA FALLS

IH 94 TO 40TH AVENUE (11 BRIDGES)

USH 53

EAU CLAIRE AND CHIPPEWA COUNTIES



HORIZONTAL POSITIONS SHOWN ON THIS PLAN ARE WISCONSIN COUNTY COORDINATES, EAU CLAIRE COUNTY, NAD83 (1991), IN U.S. SURVEY FEET. VALUES ARE GRID COORDINATES, GRID BEARINGS, AND GRID DISTANCES. GRID DISTANCES MAY BE USED AS GROUND DISTANCES.

PREPARED BY WISDOT Surveyor ADAM HETRICK DAVID KOEPP REGIONAL EXAMINE TMOTHY MASON APPROVED FOR THE DEPARTMENT

STATE OF WISCONSIN

DEPARTMENT OF TRANSPORTATION

FEDERAL PROJECT

CONTRACT

PROJECT


STATE PROJECT

1190-02-64

(Signature)

TOTAL NET LENGTH OF CENTERLINE = 11.26 MILES

Ε



Lat: 44.77165895 Long: -91.42698112 Elev: 828.16 ft.

\\doteauplog1p\photolog\Rg5\053N_R5_2013\\Front\Dir_066\F_06630.jpg



Lat: 44.77176332 Long: -91.42712196 Elev: 828.39 ft.

\\doteauplog1p\photolog\Rg5\053N_R5_2013\\Front\Dir_066\F_06631.jpg



Lat: 44.77186788 Long: -91.42726377 Elev: 828.61 ft.

\\doteauplog1p\photolog\Rg5\053N_R5_2013\\Front\Dir_066\F_06632.jpg



Lat: 44.77197205 Long: -91.42740357 Elev: 828.74 ft.

\\doteauplog1p\photolog\Rg5\053N_R5_2013\\Front\Dir_066\F_06633.jpg



Lat: 44.7720775 Long: -91.42754315 Elev: 828.94 ft.

\\doteauplog1p\photolog\Rg5\053N_R5_2013\\Front\Dir_066\F_06634.jpg



Inspection Report for B-18-038

USH 53 NB over TOWN RD Jul 14,2015



Туре	Prior	Frequency (mos)	Performed
Routine	07-14-15	24	Х
Interim	12-06-11	0	
SI&A	07-11-13	48	

Latitude 44°46'19.34"N	
Longitude 91°25'37.97"W	

Owner STATE HIGHWAY DEPT
Maintainer STATE HIGHWAY DEPT

Time Log Team members

Hours Minutes 31	
------------------	--

	Name	Number	Signature	Date
Inspector				
	Frueh, Rick J	1003	Completed by HSI System Account(HSI)	
Reviewer				

page 2

Identification & Location

Feature On: USH 53 NB	Section Town Range: S35 T27N R09W	Structure Number:
Feature Under: TOWN RD	County: EAU CLAIRE(18)	B-18-038
0.6M N JCT IH 94 TO E	Municipality: TOWN-WASHINGTON(18024)	Structure Name:

Geometry Traffic

measurements in feet, except w	here noted			La	ne
Approach Roadway Width: 40	Bridge Roadway Width: 45.9	Total Length: 97.7	On		2
Approach Pavement Width:	Deck Width:	Deck Area (sq ft):	Under		2

	Lanes	ADI	ADT year	Traffic Pattern
On	2	16200	1993	ONE WAY TRAFFIC
Under	2	35	1981	TWO WAY TRAFFIC

Capacity Load Rating

Inventory rating: HS23	Overburden depth (in): 0.5	Last rating date:	Controlling: SLAB Positive Moment
Operating rating: HS39	Deck surface material: CONCRETE	Re-rate for capacity (Y/N):	Control location: 0.4 SPAN 1
Posting:	Re-rate notes:		

Hydraulic Classification

Scour Critical Code(113): (N) NO WATERWAY	Q100 (ft3/sec): 0	
High water elevation (ft): 0.0	Velocity (ft/sec): 0.0	Sufficieny #: 98.0

Span(s)

Span #	Material	Configuration	Depth (in)	Length (ft)	Main	
1	CONT CONCRETE	FLAT SLAB		30.5		
2	CONT CONCRETE	FLAT SLAB		36.5	Y	
3	CONT CONCRETE	FLAT SLAB		30.5		

Expansion joint(s) Temperature: File: New:

Vertical Clearance Measurement file (ft)

Measurement file (ft)	File Date	Measurement new (ft)
15.0		
	15.0	15.0

page 3 Structure No.:B-18-038

Elements

.iCii	nents						Quantity in Co	ndition State			
Chk	Element	Defect	Description	UOM	Total	1	2	3	4		
			Reinforced Concrete Slab	SF	4,690	4,669	21	0	0		
Х	38		Mill and overlay in 2008. Deck was scanned with Infrared Thermography in 2009 and showed 1.7% delam.								
			Delamination - Spall - Patched Area	SF		0	0	0	0		
		1080	·	1		1	1		1		
			Cracking (RC)	SF		109	21	0	0		
		1130	East deck edge (fascia) has longitudinal crac Few hairline longitudinal with light leaching.	ks and d	elam.		1				
			Concrete Overlay	SF	4,690	2,987	1,694	9	0		
	8514		Mill and overlay in 2008. Deck was scanned with Infrared Thermography in	1 2009 an	d showed 1	I.7% delan	n.				
			Debonding/Spall/Patched Area/Pothole	SF		0	0	9	0		
		3210	9 ft X 6 inch spall at southwest joint with no	exposed	rebar.		•				
			Crack (Wearing Surface)	SF		2,616	1,694	0	0		
		3220	Numerous hairline to medium longitudinal ar	nd transv	erse crack	s.	1		•		
			Reinforced Concrete Column	I EA	8	8	T 0 T	0	0		
Х	205		2 Piers.				-				
			Cracking (RC)	EA		8	0	0	0		
		1130	Couple hairline vertical cracks.	'							
			Reinforced Concrete Abutment	LF	82	74	6	2	0		
Х	215		Some scaling at north abutment.				1		•		
		1080	Delamination - Spall - Patched Area	LF		0	0	0	0		
		1000	0 1: (50)		1	40					
			Cracking (RC)	LF		12	6	2	0		
		1130	Few hairline vertical cracks on north abutme Large crack at southeast corner.	nτ.							
			Abrasion-Wear (PSC-RC)	LF		0	0	0	0		
		1190	,	'		1	1				
			Reinforced Concrete Bridge Rail	LF	236	210	26	0	0		
Χ	331			•	•	•	'		•		
			Delamination - Spall - Patched Area	LF		0	0 1	0	0		
		1080	- callingation open is also learned								
			Cracking (RC)	LF		14	26	0	0		
		1130	Few verical cracks in concrete railing.								
			Integral Wingwall	EA	4	0	4	0	0		
Χ	8400		Minor erosion around northeast wing.				1				
			Wingwall Movement	EA		0	4	0	0		
		8902	All wings are settling at the ends. All wing walls seem to be tipping away from c Northeast tipped outward about 1 1/2". Northwest tipped outward about 2". Southeast tipped outward about 2". Southwest tipped outward about 1 1/2".	oncrete p	parapet rai	ling.					

page 4 Structure No.: **B-18-038**

Assessments

, 100	COOMIC						Quantity in Co	ondition State	
Chk	Element	Defect	Description	UOM	Total	1	2	3	4
			Signs - Object Markers	EA	4	4	0	0	0
Х	9030		2 south end						
			Slope Protection- Crushed Aggregate with Bit.	EA	2	1	1	0	0
X	9043		New in 1996. South slope reoiled in 2008. South slope 4 ft block retaining wall and sidewalk (new 2008). Water seeping through block retaining wall onto pier 1, column 4. Bottom southeast slope corner behind block resettling. Few hairline vertical cracks.	sidew	alk near	ed rock is	.		
Х	9322		Approach Roadway - Concrete (non-structural)	EA	2	2	0	0	0
			Decorative Rail Alum railing is OK.	EA	2	2	0	0	0
Χ	9335		Inside of alum tube has some deep snow plow s	crapes					

NBI Ratings

	File	New
Deck	6	6
Superstructure	6	6
Substructure	7	7
Culvert	N	N
Channel	N	N
Waterway	N	N

Structure Specific Notes

The spalls at the transv. saw cuts are getting worse and we need to address it.

**No bridge plaque found.

Inspection Specific Notes
The is ponding under both structures

Inspector Site-Specific Safety Considerations

Structure Inspection Procedures

Walk around.

Special Requirements

	Chk	Comments
Traffic Control		
Access Equipment		
Other		

Special Components

Component	Year	Work Performed	Note
DECK - IOWA MIX	1989	OVERLAY - CONCRETE	

page 5 Structure No.:B-18-038

Construction History

Construction in	Story	
Year	Work Performed	FOS id
2008	OVERLAY - CONCRETE	1191-06-61
1989	OVERLAY - CONCRETE	0018-94-10
1966	NEW STRUCTURE	

Maintenance Items History

Item Recommended by	Status	Status change	Year completed
---------------------	--------	---------------	----------------

Maintenance Items

Item Priority Recommended by Status Status change



Bridge Asbestos Inspection Report

WisDOT Project ID: 1190-02-34

Structure Number: B-18-0037, B-18-0038 **Structure Name:** USH 53 over Town Road

City/County: Town of Washington, Eau Claire County

Lat/Long Coordinates: 444619.03/ 912540.6, 444619.34/ 912537.97

TRC Project Number: 235777.0000.0000

Date Inspected: October 14, 2015

Inspected By/License Number: John Roelke, All-119523

Findings:

The inspection to identify and collect samples of potential asbestos-containing material (ACM) was completed following WisDOT standard sampling procedure for bridge inspections found in FDM 21-35-45.

On both of the bridges, the gaskets located under the railing attachment plates on the parapet tested positive for asbestos greater than 1% and is therefore regulated ACM. If the ACM will be disturbed during the planned overlays, the ACM must be removed prior to any work. Standard Special Provision (STSP) 203-005 should be incorporated into the specifications. If the ACM will not be disturbed during the planned overlays, STSP 107-120 should be included in the specifications.

Sample	Sample	Sample	Analytical Results	Friable/ Non-friable or	Quantity of ACM
Number	Description	Location	Location and Method No ACM		Material
B-18-00	37				
1	Gasket	Under railing	PLM, 3%	Friable	30x7"x7" +
		attachment plate			4x20"x8" =
2	Gasket	Under railing	Not analyzed,		15 sq ft
		attachment plate	positive stop		
3	Gasket	Under railing	Not analyzed,		
		attachment plate	positive stop		
4	Caulk	Parapet expansion joint	PLM, non-detect	No ACM	0
5	Caulk	Parapet expansion joint	PLM, non-detect	No ACM	
6	Caulk	Parapet expansion joint	PLM, non-detect	No ACM	

Sample	Sample	Sample	Analytical Results	Friable/ Non-friable or	Quantity of ACM	
Number	Description	Location	and Method	No ACM	Material	
7	Caulk	Parapet expansion joint	PLM, non-detect	No ACM	0	
8	Caulk	Parapet expansion joint	PLM, non-detect	No ACM		
9	Caulk	Parapet expansion joint	PLM, non-detect	No ACM		
10	Caulk	Abutment joint	PLM, non-detect	No ACM	0	
11	Caulk	Abutment joint	PLM, non-detect	No ACM		
12	Caulk	Abutment joint	PLM, non-detect	No ACM		
B-18-00	38					
1	Gasket	Under railing	PLM, 10%	Friable	30x7"x7" +	
		attachment plate			4x20"x8" =	
2	Gasket	Under railing	Not analyzed,		15 sq ft	
		attachment plate	positive stop			
3	Gasket	Under railing	Not analyzed,			
		attachment plate	positive stop			
4	Caulk	Parapet expansion joint	PLM, non-detect	No ACM	0	
5	Caulk	Parapet expansion joint	PLM, non-detect	No ACM		
6	Caulk	Parapet expansion joint	PLM, non-detect	No ACM		
7	Caulk	Parapet expansion joint	PLM, non-detect	No ACM	0	
8	Caulk	Parapet expansion joint	PLM, non-detect	No ACM		
9	Caulk	Parapet expansion joint	PLM, non-detect	No ACM		
10	Caulk	Abutment joint	PLM, non-detect	No ACM	0	
11	Caulk	Abutment joint	PLM, non-detect	No ACM		
12	Caulk	Abutment joint	PLM, non-detect	No ACM		

If you have any questions, please contact me, at (608) 826-3628.

TRC Environmental Corporation

Danul Hunk

Daniel Haak Project Manager John Roelke Asbestos Inspector

John Rollke W


Attachments: Location Map, Photos, and Laboratory Reports



Report Distribution:

Recipient	Electronic (PDF) Copy	Paper Copy
BTS-ESS sharlene.tebeest@dot.wi.gov	X (via email)	X
REC amy.adrihan@dot.wi.gov;	X (via email)	
nicholasA.schaff@dot.wi.gov		
Project Manager david.koepp@dot.wi.gov	X (via email)	
Other		





B-18-0037









Gasket under railing attachment plate



Caulk in parapet expansion joint





Caulk in parapet expansion joint



Caulk in abutment joint

B-18-0038









Gasket under railing attachment plate



Caulk in parapet expansion joint



Caulk in abutment joint





Industrial Hygiene Laboratory 21 Griffin Road North Windsor, CT 06095 (860) 298-6308



BULK ASBESTOS ANALYSIS REPORT

CLIENT: Wisconsin Department of Transportation

Lab Log #:

0047021

Project #:

235777.0000.0000

Date Received:

10/16/2015

Date Analyzed:

10/19/2015

Site:

DOT Bridge Inspection, B-18-37

POLARIZED LIGHT MICROSCOPY by EPA 600/R-93/116

Sample No.	Color	Homogenous	Multi- Layered	Layer No.	Other Matrix Materials	Asbestos %	Asbestos Type
B-18-37 (1)	Grey	Yes	No			3%	Chrysotile
B-18-37 (2)						NA/PS	, E1 E1
B-18-37 (3)						NA/PS	-1-1
B-18-37 (4)	Grey	Yes	No			ND	None
B-18-37 (5)	Grey	Yes	No			ND	None
B-18-37 (6)	Grey	Yes	No			ND	None
B-18-37 (7)	Grey	Yes	No			ND	None
B-18-37 (8)	Grey	Yes	No			ND	None
B-18-37 (9)	Grey	Yes	No			ND	None

Page 2 of 2 47021.WI DOT.doc

Industrial Hygiene Laboratory 21 Griffin Road North Windsor, CT 06095 (860) 298-6308



POLARIZED LIGHT MICROSCOPY by EPA 600/R-93/116

Sample No. Color Homogenous Layered	Layer No.Other Matrix MaterialsAsbestos %Asbest Typ
-------------------------------------	--

Reporting limit- asbestos present at 1%

ND - asbestos was not detected

Trace - asbestos was observed at level of less than 1%

NA/PS - Not Analyzed / Positive Stop

SNA- Sample Not Analyzed- See Chain of Custody for details

Note: Polarized-light microscopy is not consistently reliable in detecting asbestos in floor coverings and similar non-friable organically bound materials. In those cases, EPA recommends, and certain states (e.g. NY) require, that negative results be confirmed by quantitative transmission electron microscopy.

The Laboratory at TRC follows the EPA's Interim Method for the Determination of Asbestos in Bulk Insulation (1982), and the EPA recommended Method for the Determination of Asbestos in Bulk Building Materials (EPA/600/R-93/116), July 1993, R.L. Perkins and B.W. Harvey which utilizes polarized light microscopy (PLM). Our analysts have completed an accredited course in asbestos identification. TRC's Laboratory is accredited under the National Voluntary Laboratory Accreditation Program (NVLAP), for Bulk Asbestos Fiber Analysis, NVLAP Code 18/A01, effective through June 30, 2016. TRC is an American Industrial Hygiene Association (AIHA) accredited lab for PLM effective through October 1, 2016. Asbestos content is determined by visual estimate unless otherwise indicated. Quality Control is performed in-house on at least 10% of samples and the QC data related to the samples is available upon written request from the client.

This report shall not be reproduced, except in full, without the written approval of TRC. This report must not be used by the client to claim product endorsement by NVLAP or any agency of the U.S. Government. This report relates only to the items tested.

Reviewed by: Analyzed by:

Date Issued

Kathleen Williamson, Laboratory Manager

Amanda Parkins, Approved Signatory

10/19/2015

Industrial Hygiene Laboratory 21 Griffin Road North Windsor, CT 06095 (860) 298-6308



BULK ASBESTOS ANALYSIS REPORT

CLIENT: Wisconsin Department of Transportation

Lab Log #:

0047035

Project #:

235777.0000.0000

Date Received:

10/16/2015

Date Analyzed:

10/20/2015

Site:

DOT Bridge Inspection, B-18-38

POLARIZED LIGHT MICROSCOPY by EPA 600/R-93/116

Sample No.	Color	Homogenous	Multi- Layered	Layer No.	Other Matrix Materials	Asbestos %	Asbestos Type
B-18-38 (1)	Grey	Yes	No			10%	Chrysotile
B-18-38 (2)						NA/PS	
B-18-38 (3)						NA/PS	==
B-18-38 (4)	Grey	Yes	No			ND	None
B-18-38 (5)	Grey	Yes	No			ND	None
B-18-38 (6)	Grey	Yes	No	=:=1		ND	None
B-18-38 (7)	Grey	Yes	No			ND	None
B-18-38 (8)	Grey	Yes	No			ND	None
B-18-38 (9)	Grey	Yes	No			ND	None
B-18-38 (10)	Grey	Yes	No	-, -,		ND	None
B-18-38 (11)	Grey	Yes	No			ND	None
B-18-38 (12)	Grey	Yes	No			ND	None

Industrial Hygiene Laboratory 21 Griffin Road North Windsor, CT 06095 (860) 298-6308



POLARIZED LIGHT MICROSCOPY by EPA 600/R-93/116

			Multi-	Layer No.	Other Matrix	Asbestos	Asbestos
Sample No.	Color	Homogenous	Layered		Materials	%	Type

Reporting limit- asbestos present at 1%

ND - asbestos was not detected

Trace - asbestos was observed at level of less than 1%

NA/PS - Not Analyzed / Positive Stop

SNA- Sample Not Analyzed- See Chain of Custody for details

Note: Polarized-light microscopy is not consistently reliable in detecting asbestos in floor coverings and similar non-friable organically bound materials. In those cases, EPA recommends, and certain states (e.g. NY) require, that negative results be confirmed by quantitative transmission electron microscopy.

The Laboratory at TRC follows the EPA's Interim Method for the Determination of Asbestos in Bulk Insulation (1982), and the EPA recommended Method for the Determination of Asbestos in Bulk Building Materials (EPA/600/R-93/116), July 1993, R.L. Perkins and B.W. Harvey which utilizes polarized light microscopy (PLM). Our analysts have completed an accredited course in asbestos identification. TRC's Laboratory is accredited under the National Voluntary Laboratory Accreditation Program (NVLAP), for Bulk Asbestos Fiber Analysis, NVLAP Code 18/A01, effective through June 30, 2016. TRC is an American Industrial Hygiene Association (AIHA) accredited lab for PLM effective through October 1, 2016. Asbestos content is determined by visual estimate unless otherwise indicated. Quality Control is performed in-house on at least 10% of samples and the QC data related to the samples is available upon written request from the client.

This report shall not be reproduced, except in full, without the written approval of TRC. This report must not be used by the client to claim product endorsement by NVLAP or any agency of the U.S. Government. This report relates only to the items tested.


William: Reviewed by:

Date Issued

Kathleen Williamson, Laboratory Manager


Amanda Parkins, Approved Signatory


10/21/2015



creenSca

X28324






oSuees

N

ĊЛ

44




creenSca

VO.


Œ

Ø



CreenSca

σv




Steens

NOV

N

 ω



⊤ → ∴

Ω

Ż

σv

