

ESTIMATE OF QUANTITIES

DATE 04/07/87

PROJECT ID: 0054-73-70
 RUSK COUNTY
 BRUCE - EAST COUNTY LINE ROAD
 U.S.H. B

ITEM	ITEM DESCRIPTION	UNIT	TOTAL	0054-73-70 QUANTITY
21301	FINISHING ROADWAY	L.S.	1.00	1.00
30403	CRUSHED AGGREGATE BASE COURSE	C.Y.	5,033.00	5,033.00
40204	BITUMINOUS MATERIAL FOR TACK COAT	GAL.	568.00	568.00
40501	BITUMINOUS MATERIAL FOR PLANT MIXES	TON	850.00	850.00
40607	SINGLE AGGREGATE BITUMINOUS PAVEMENT	TON	14,162.00	14,162.00
61801	MAINTENANCE AND REPAIR OF HAUL ROADS	L.S.	1.00	1.00
61910	MOBILIZATION	L.S.	1.00	1.00
64201	FIELD OFFICE, TYPE A	L.S.	1.00	1.00
64210	FIELD LABORATORY	L.S.	1.00	1.00
64301	TRAFFIC CONTROL	L.S.	1.00	1.00
64484	TEMPORARY PAVEMENT MARKING	L.F.	510.00	510.00
90348	PREPARATION OF FOUNDATION FOR BITUMINOUS SHOULDERS	STA.	2,097.00	2,097.00

SHEET 3