

ESTIMATE OF QUANTITIES

DATE 12/01/82

PROJECT ID: 1000-50-72
BAYFIELD COUNTY
HAZARD ELIMINATION, DISTRICT 8
/U.S.H. 2 & S.T.H. 13 INTER./
U.S.H. 2

PROJECT ID: 1180-03-71
BAYFIELD COUNTY
C.T.H. E - S.T.H. 13 ROAD
/INO - ASHLAND JCT./
U.S.H. 2

ITEM	ITEM DESCRIPTION	UNIT	TOTAL	1000-50-72 QUANTITY	1180-03-71 QUANTITY
20101	CLEARING	STA.	6.00	6.00	
20104	GRUBBING	STA.	6.00	6.00	
20351	REMOVING OLD BRIDGE, STATION 1095+92	L.S.	1.00	1.00	
20401	REMOVING PAVEMENT	S.Y.	360.00	360.00	
20403	REMOVING CURB	L.F.	12.00	12.00	
20411	REMOVING GUARDRAIL	L.F.	492.00	492.00	
20416	REMOVING INLETS	EACH	1.00	1.00	
20503	UNCLASSIFIED EXCAVATION	C.Y.	29,640.00	10.00	29,630.00
20901	GRANULAR BACKFILL	C.Y.	1,390.00		1,390.00
21102	PREPARATION OF FOUNDATION FOR BITUMINOUS PAVING, PROJECT 1180-03-71	L.S.	1.00		1.00
21201	GRANULAR SURBASE COURSE	C.Y.	990.00		990.00
21302	FINISHING ROADWAY, PROJECT 1180-03-71	L.S.	1.00		1.00
30404	CRUSHED AGGREGATE BASE COURSE	TON	45,780.00	30.00	45,750.00
40501	BITUMINOUS MATERIAL FOR PLANT MIXES	TON	1,269.00	2.00	1,267.00
41001	RECYCLED BITUMINOUS SURFACE	TON	36,245.00	40.00	36,205.00
41020	SALVAGED BITUMINOUS PAVEMENT, MILLING	TON	16,564.00	14.00	16,550.00
50409	CONCRETE MASONRY, ENDWALLS	C.Y.	3.60		3.60
52003	CULVERT PIPE, CLASS III, 18-INCH	L.F.	26.00		26.00
52005	CULVERT PIPE, CLASS III, 24-INCH	L.F.	178.00		178.00
52061	APRON ENDWALLS FOR CULVERT PIPE, 18-INCH	EACH	2.00		2.00
52063	APRON ENDWALLS FOR CULVERT PIPE, 24-INCH	EACH	4.00		4.00
52111	CORRUGATED STEEL CULVERT PIPE, 36-INCH	L.F.	130.00		130.00
52151	STEEL APRON ENDWALLS FOR CULVERT PIPE, 36-INCH	EACH	2.00		2.00
52210	REINFORCED CONCRETE CULVERT PIPE, CLASS III, 42-INCH	L.F.	32.00		32.00
52407	SALVAGED CULVERT PIPE, 24-INCH	L.F.	36.00		36.00

SHEET 3

DATE 12/01/82

ITEM	ITEM DESCRIPTION	UNIT	TOTAL	1000-50-72 QUANTITY	1180-03-71 QUANTITY
52409	SALVAGED CULVERT PIPE, 30-INCH	L.F.	36.00		36.00
52412	SALVAGED CULVERT PIPE, 42-INCH	L.F.	12.00		12.00
52413	SALVAGED CULVERT PIPE, 48-INCH	L.F.	18.00		18.00
60104	CONCRETE CURB, TYPE J	L.F.	60.00		60.00
60170	CONCRETE CURB AND GUTTER, 36-INCH, TYPE D	L.F.	925.00	158.00	767.00

60602	HEAVY RIPRAP	C.Y.	595.00		595.00
61802	MAINTENANCE AND REPAIR OF HAUL ROADS, PROJECT 1180-03-71	L.S.	1.00		1.00
61911	MOBILIZATION, PROJECT 1180-03-71	L.S.	1.00		1.00
61912	MOBILIZATION, PROJECT 1000-50-72	L.S.	1.00	1.00	
62501	TOPSOIL	S.Y.	8,000.00		8,000.00

62702	MULCHING	S.Y.	9,400.00		9,400.00
62810	EROSION BALES	EACH	20.00		20.00
62905	FERTILIZER, TYPE B	CWT.	6.00		6.00
63002	SEEDING	LB.	130.00		130.00
63101	SODDING	S.Y.	610.00	70.00	540.00

64202	FIELD OFFICE, TYPE B	L.S.	1.00		1.00
64210	FIELD LABORATORY	L.S.	1.00		1.00
64302	TRAFFIC CONTROL, PROJECT 1180-03-71	L.S.	1.00		1.00
64303	TRAFFIC CONTROL, PROJECT 1000-50-72	L.S.	1.00	1.00	
64484	TEMPORARY PAVEMENT MARKING	L.F.	10,868.00		10,868.00

90001	PIPE UNDERDRAIN INSTALLATION	L.F.	150.00		150.00
90002	BASE PATCHING, CULVERTS	S.Y.	65.00		65.00
90065	BITUMINOUS SURFACE, TRAFFIC CONTROL	TON	100.00		100.00

SHEET 3.1