




## SELECT AS-BUILT DRAWINGS



CROSS SECTION THRU ROADWAY  
3 SPAN HAUNCHED SLAB (LOOKING NORTH)



DESIGN DATA

LIVE LOAD: HS 20

ALLOWABLE DESIGN STRESSES:

CONCRETE MASONRY, GRADE "AA"  $f_c = 1,900$  P.S.I.

BAR STEEL REINFORCEMENT  $f_s = 20,000$  P.S.I.

FOUNDATION DATA:

ABUTMENTS AND PIERS TO BE SUPPORTED ON CAST-IN-PLACE CONCRETE PILING 10 3/4"  $\phi$ . DRIVE TO A MIN. BRG. VALUE OF 20 T/PILE, 55-0 EST. LENGTH AT SOUTH ABUT., 20 T/PILE, 55-0 EST. LENGTH AT NORTH ABUT., AND 55 T/PILE, 55-0 EST. LENGTH AT THE PIERS.

TRAFFIC VOLUME:

U.S.H. "53"

D.H.V. 5300 (1980)

R.D.S. 80 M.P.H.

TOWN ROAD

A.D.T. 100 (2000)

GENERAL NOTES

DRAWINGS SHALL NOT BE SCALED. BAR STEEL REINFORCEMENT SHALL BE EMBEDDED 2" CLEAR UNLESS OTHERWISE SHOWN OR NOTED.


THE FIRST DIGIT OF A THREE DIGIT BAR NO. AND THE FIRST TWO DIGITS OF A FOUR DIGIT BAR NO. SIGNIFIES THE BAR SIZE.

THE SLOPE OF THE FILL IN FRONT OF THE ABUTMENTS SHALL BE COVERED WITH SLOPE PAVING, CRUSHED AGGREGATE TO THE EXTENT SHOWN ON THIS SHEET AND IN THE ABUTMENT DETAILS.

THE FINISHED GRADED SECTION WAS USED AS THE UPPER LIMITS OF EXCAVATION FOR COMPUTATION OF EXCAVATION AT THE PIERS.

FOR UPPER LIMITS OF EXCAVATION AT THE ABUTMENTS SEE SHEETS NO. 3 & 4.


PILING AT ABUTMENTS SHALL BE PREBORED THRU FILL TO THE ORIGINAL GROUND LINE.



PROFILE GRADE TOWN ROAD

LIST OF DRAWINGS



1. GENERAL PLAN	X46260
2. SUBSURFACE EXPLORATION	X46261
3. SOUTH ABUTMENT	X46262
4. NORTH ABUTMENT	X46263
5. PIERS	X46264
6. SUPERSTRUCTURE	X46265
7. SUPERSTRUCTURE	X46266
8. EXPANSION JOINT & BEARING DETAILS	X46267
9. SLOPED FACE PARAPET "A"	X46268
10. TUBULAR RAILING TYPE "J"	X46269




ELEVATION  
NORMAL TO E TOWN RD.

TOTAL ESTIMATED QUANTITIES

BID ITEMS	UNIT	S. ABUT.	PIER 1	PIER 2	N. ABUT.	SUPER.	TOTAL
EXCAVATION FOR STRUCTURE	C.Y.	90	132	100	90	—	312
CONCRETE MASONRY	C.Y.	66	63	47	43	445	664
BAR STEEL REINFORCEMENT	L.B.	3060	10105	8885	2180	103090	127320
STRUCTURAL CARBON STEEL	L.B.	—	—	—	—	3970	3970
STRUCTURAL LOW ALLOY STEEL	L.B.	—	—	—	—	1100	1100
LUBRICATED BRONZE PLATES	L.B.	—	—	—	—	77	77
BEARING PADS	S.F.	604	1411	765	573	7	7
CAST-IN-PLACE CONC. PILING DEL. & DR. 10 3/4" $\phi$	L.F.	888	1570	888	445	—	4090
PREBORING, CAST-IN-PLACE CONC. PILING 10 3/4" $\phi$	L.F.	252	—	—	295	—	497
TUBULAR RAILING, TYPE "J"	L.F.	—	—	—	—	302	302
SLOPE PAVING, CRUSHED AGGREGATE	S.Y.	247	—	—	229	—	476
NON-BID ITEMS							
1/8" ALUMINUM OR ZINC PLATE	S.F.	—	—	—	—	90	90
FILLER	SIZE	—	1/4"	1/4"	—	1/2"	1/4" 1/2"
POLYVINYL CHLORIDE WATERSTOP	L.F.	—	—	—	—	96	96



No.	Date	Revision	By
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS			
STRUCTURE B-3-14			
U.S.H. "53" OVER TOWN ROAD			
County	BARRON	City	Village
Design Spec.	A.A.S.H.O. 69	Load	HS 20
Designed By	R.T.B.	Design Checked	F.P.R.
Drawn By	D.J.A.	Plan Checked	d.H.G.
Approved	W.A. Kline	Chief Bridge Engineer	11-17-71
GENERAL PLAN			SHEET 1 OF 10
			X46260



BILL OF BARS				EMP FOB-4(36)	35
BAR NO.	NO. REQ'D	LENGTH	BENT	98,850*	
				LOCATION	
5401	64	8-7	X	SLAB @ SO. ABUT. HAUNCH	
5402	29	6-8	X	"	" " " "
5703	3	98-10		"	" " " " - TRANS.
5509	67	48-10		"	SPAN 1 & 3 - TRANS.
51005	44	32-0		"	" " 1 - LONG.
51006	27	23-9		"	" " 1 - "
5507	86	23-2	X	"	@ PIER HAUNCH
5908	20	98-10		"	" " " " - TRANS.
5409	180	7-8	X	"	STIRRUP - SPAN 2
51110	55	49-3		"	SPAN 2 - LONG.
51111	36	33-9		"	" " 2 - "
5612	45	48-10		"	" " 2 - TRANS.
51013	43	28-6		"	" " 3 - LONG.
51014	28	19-9		"	" " 3 - LONG.
5415	29	12-3		"	" " 1 - "
5516	44	48-10		"	" " 1, 2, & 3 - TRANS.
51117	42	42-6		"	OVER PIER 1 - LONG.
51118	43	38-0		"	" " " 1 - "
5419	24	24-6		"	SPAN 2 - LONG.
5820	18	27-6		"	EDGE SPAN 2 - LONG.
51121	40	38-6		"	OVER PIER 2 - LONG
51122	39	45-6		"	" " " 2 - "
5923	28	48-10		"	@ PIER HAUNCH - TRANS.
5424	29	5-0		"	SPAN 3 - LONG.
5525	43	4-1	X	"	@ NO. ABUT. HAUNCH
5526	43	3-0	X	"	" " " "
5527	43	2-10	X	"	" " " "

CROSS SECTION THRU ROADWAY

3 SF Concrete Surface  
Repair N. Abut.

3 SF Concrete Surface  
Repair S. Abut.

Parapet in poor condition, spalls/cracks/rust stains on entire length. Approx. 40% of top and roadway surface of parapet need Concrete Surface Repair = 210 SF



No.	Date	Revision		By
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS				
STRUCTURE B-3-14				
Const. Spec	1969	Drawn By	D.T.A.	Plans Checked
SUPERSTRUCTURE		SHEET 6 OF 10		
		X46265		

# ASBESTOS REPORT



3159 VOYAGER DRIVE  
GREEN BAY, WI 54311  
920.455.8200 PHONE

## Bridge Asbestos Inspection Report

**WisDOT Project ID:** 1196-04-02

**Structure Number:** B-03-014

**Structure Name:** USH 53 SB over Carlson School Road

**City/County:** Town of Dovre, Barron County, Wisconsin

**GEI project Number:** 1901822

**Date Inspected:** April 3, 2019

**Inspected by:** Kyle C. Sandmire

**Asbestos Inspector License Number:** All- 217616

**Consultant Company:** GEI Consultants, Inc.

### Summary:

An asbestos inspection of Structure B-03-014 was conducted on April 3, 2019 by Kyle Sandmire, Asbestos Inspector License No. All-217616. Asbestos-containing material (ACM) **IS NOT** present on this structure.

The inspection to identify and collect samples of potential asbestos-containing material (ACM) was completed following WisDOT standard sampling procedures for bridge inspections found in FDM 21-35-45.

No Asbestos-containing material has been found in Structure B-03-014. Standard Special Provision (STSP) 107-127 shall be included in the plans. The contractor will be responsible for completion of the Notification of Demolition and/or Renovation (DNR form 4500-113) if required. A copy of the inspection report is available from the region office.

Sample #	Sample Description	Sample Location	Method and Analytical Results	Category I or II non-friable or No ACM	Total Amount of Material on Structure
B-03-014-1A	Black/gray caulk	Bridge deck joints	PLM, non-detect	No ACM	N/A
B-03-014-1B	Black/gray caulk	Bridge deck joints	PLM, non-detect	No ACM	N/A
B-03-014-1C	Black/gray caulk	Bridge deck joints	PLM, non-detect	No ACM	N/A
B-03-014-2A	Gray caulk	Bridge deck wall joints and abutment joints	PLM, non-detect	No ACM	N/A
B-03-014-2B	Gray caulk	Bridge deck wall joints and abutment joints	PLM, non-detect	No ACM	N/A
B-03-014-2C	Gray caulk	Bridge deck wall joints and abutment joints	PLM, non-detect	No ACM	N/A

B-03-014-3A	Silver paint	Steel plates between bridge spans and abutments	PLM, non-detect	No ACM	N/A
B-03-014-3B	Silver paint	Steel plates between bridge spans and abutments	PLM, non-detect	No ACM	N/A
B-03-014-3C	Silver paint	Steel plates between bridge spans and abutments	PLM, non-detect	No ACM	N/A
B-03-014-4A	Light blue spray foam insulation	Between bridge deck and abutment joints	PLM, non-detect	No ACM	N/A
B-03-014-4B	Light blue spray foam insulation	Between bridge deck and abutment joints	PLM, non-detect	No ACM	N/A
B-03-014-4C	Light blue spray foam insulation	Between bridge deck and abutment joints	PLM, non-detect	No ACM	N/A
B-03-014-5A	Black tar	Southern bridge deck	PLM, non-detect	No ACM	N/A
B-03-014-5B	Black tar	Southern bridge deck	PLM, non-detect	No ACM	N/A
B-03-014-5C	Black tar	Southern bridge deck	PLM, non-detect	No ACM	N/A

If you have any questions, please contact us at (920) 455-8200.

GEI CONSULTANTS, INC.



Kyle C. Sandmire  
Environmental Scientist



Paul M. Garvey  
Senior Scientist

Attachments:

B-03-014 Report Table


B-03-014 Map

B-03-014 Photo Log

B-03-014 Bulk Asbestos Sample Analysis Summary

B-03-014 Bulk Asbestos Sample Chain of Custody





**GEI**  
 Consultants  
 3159 Voyager Drive  
 Green Bay, WI 54311  
 920.455.8200

WisDOT Project 1196-04-02  
 Structure B-03-014  
 USH 53 (SB)  
 over Carlson School Road  
 Barron County

DESIGNED BY	KCS	4/10/2019
DRAWN BY	KCS	4/10/2019
APPROVED BY	PMG	4/10/2019
SCALE	1 inch = 500 feet	
FIGURE NO.	B-03-014	




## PHOTOGRAPHIC LOG

<b>PHOTOGRAPH NO: 1</b>	
<b>DIRECTION: S</b>	
<b>DESCRIPTION:</b>  Looking south at B-03-014.	


<b>PHOTOGRAPH NO: 2</b>	
<b>DIRECTION: E</b>	
<b>DESCRIPTION:</b>  Looking east at B-03-014.	




<b>PHOTOGRAPH NO: 3</b>	
<b>DIRECTION: SW</b>	
<b>DESCRIPTION:</b>  View of the bridge identification plate.	


<b>PHOTOGRAPH NO: 4</b>	
<b>DIRECTION: Down</b>	
<b>DESCRIPTION:</b>  View of the black/gray joint caulk on the bridge deck. The black/gray joint caulk is not ACM.	



<p><b>PHOTOGRAPH NO: 5</b></p>	
<p><b>DIRECTION: SE</b></p>	
<p><b>DESCRIPTION:</b></p> <p>View of the gray caulk on the bridge wall joints and abutment joints. The gray caulk is not ACM.</p>	

<p><b>PHOTOGRAPH NO: 6</b></p>	
<p><b>DIRECTION: NE</b></p>	
<p><b>DESCRIPTION:</b></p> <p>View of the silver paint on the steel plates between the bridge span and abutment. The silver paint is not ACM.</p>	

<b>PHOTOGRAPH NO: 7</b>			
<b>DIRECTION: E</b>			
<b>DESCRIPTION:</b>  View of the light blue spray foam insulation between the bridge deck and abutment joints. The light blue spray foam insulation is not ACM.			

<b>PHOTOGRAPH NO: 8</b>			
<b>DIRECTION: Down</b>			
<b>DESCRIPTION:</b>  View of the black tar on the southern bridge deck joints. The black tar is not ACM.			





Environmental Hazards Services, L.L.C.

7469 Whitepine Rd

Richmond, VA 23237

Telephone: 800.347.4010

## Asbestos Bulk Analysis Report

Report Number: 19-04-02064

Client: GEI Consultants Inc  
3159 Voyager Dr.  
Green Bay, WI 54311

Received Date: 04/12/2019

Analyzed Date: 04/16/2019

Reported Date: 04/17/2019

Project/Test Address: B-03-014; USH 53 SB Over Carlson School Road; Town of Dovre,  
WI

Client Number:  
200598

Fax Number:

# Laboratory Results

Lab Sample Number	Client Sample Number	Layer Type	Lab Gross Description	Asbestos	Other Materials
19-04-02064-001	B-3-14-1A	--	Gray Rubbery; Homogeneous	NAD	100% Non-Fibrous
19-04-02064-002	B-3-14-1B	--	Gray Rubbery; Homogeneous	NAD	100% Non-Fibrous
19-04-02064-003	B-3-14-1C	--	Gray Rubbery; Homogeneous	NAD	100% Non-Fibrous
19-04-02064-004	B-3-14-2A	--	Gray Rubbery Adhesive; Homogeneous	NAD	100% Non-Fibrous
19-04-02064-005	B-3-14-2B	--	Gray Rubbery Adhesive; Homogeneous	NAD	100% Non-Fibrous

# Environmental Hazards Services, L.L.C

Client Number: 200598

Report Number: 19-04-02064

Project/Test Address: B-03-014; USH 53 SB Over Carlson  
School Road; Town of Dovre, WI

Lab Sample Number	Client Sample Number	Layer Type	Lab Gross Description	Asbestos	Other Materials
19-04-02064-006	B-3-14-2C	--	Gray Rubbery Adhesive; Homogeneous	NAD	100% Non-Fibrous
19-04-02064-007	B-3-14-3A	--	Silver Paint; Homogeneous	NAD	100% Non-Fibrous
19-04-02064-008	B-3-14-3B	--	Silver Paint; Homogeneous	NAD	100% Non-Fibrous
19-04-02064-009	B-3-14-3C	--	Silver Paint; Homogeneous	NAD	100% Non-Fibrous
19-04-02064-010	B-3-14-4A	--	Light Blue Foam; Homogeneous	NAD	100% Non-Fibrous
19-04-02064-011	B-3-14-4B	--	Light Blue Foam; Homogeneous	NAD	100% Non-Fibrous
19-04-02064-012	B-3-14-4C	--	Light Blue Foam; Homogeneous	NAD	100% Non-Fibrous
19-04-02064-013	B-3-14-5A	--	Black Rubbery Tar like; Homogeneous	NAD	100% Non-Fibrous

# Environmental Hazards Services, L.L.C

Client Number: 200598  
Project/Test Address: B-03-014; USH 53 SB Over Carlson  
School Road; Town of Dovre, WI

Report Number: 19-04-02064

Lab Sample Number	Client Sample Number	Layer Type	Lab Gross Description	Asbestos	Other Materials
19-04-02064-014	B-3-14-5B	--	Black Rubbery Tar like; Homogeneous	NAD	100% Non-Fibrous
19-04-02064-015	B-3-14-5C	--	Black Rubbery Tar like; Homogeneous	NAD	100% Non-Fibrous

QC Sample: 30-M22009-3  
QC Blank: SRM 1866 Fiberglass  
Reporting Limit: 1% Asbestos  
Method: EPA Method 600/R-93/116, EPA Method 600/M4-82-020  
Analyst: Sami Hosn

Reviewed By Authorized Signatory:

  
Missy Kanode  
QA/QC Clerk

The condition of the samples analyzed was acceptable upon receipt per laboratory protocol unless otherwise noted on this report. Each distinct component in an inhomogeneous sample was analyzed separately and reported as a composite. Results represent the analysis of samples submitted by the client. Sample location, description, area, volume, etc., was provided by the client. This report cannot be used by the client to claim product endorsement by NVLAP or any agency of the U.S. Government. This report shall not be reproduced except in full, without the written consent of the Environmental Hazards Service, L.L.C. California Certification #2319 NY ELAP #11714 NVLAP #101882-0 VELAP 460172. All information concerning sampling location, date, and time can be found on Chain-of-Custody. Environmental Hazards Services, L.L.C. does not perform any sample collection.

Environmental Hazards Services, L.L.C. recommends reanalysis by point count (for more accurate quantification) or Transmission Electron Microscopy (TEM), (for enhanced detection capabilities) for materials regulated by EPA NESHAP (National Emission Standards for Hazardous Air Pollutants) and found to contain less than ten percent (<10%) asbestos by polarized light microscopy (PLM). Both services are available for an additional fee.

400 Point Count Analysis, where noted, performed per EPA Method 600/R-93/116 with a Reporting Limit of 0.25%.

\* All California samples analyzed by Polarized Light Microscopy, EPA Method 600/M4-82-020, Dec. 1982.

LEGEND: NAD = no asbestos detected





**EHS**  
**Laboratories**

Environmental Hazards Services, LLC


## Asbestos Chain-of-Custody Form

SHIP TO: 7469 Whitepine Rd. Richmond, VA 23237

Phone: (800) 347-4010 FAX: (804) 275-4907

ONLINE CLIENT PORTAL AVAILABLE FOR ANALYSIS RESULTS AT:

www.leadlab.com



19-04-02064

Due Date:

04/17/2019  
(Wednesday)

AE

15 PM

Company Name: GEI Consultants Inc. Account Number: 1901822

Address: 3159 Voyageur Drive City/State/Zip: Green Bay, WI 54311

Phone #: 920-241-2725 Email: ksandwich@geiconsultants.com Fax: 920-455-8225

Project Name / Testing Address: B-03-014 USH 53 SB over Carlson Street Road City/State (Required): Town of Dover, WI

Collected by: Kyle C Sandwich, AII-217616 P.O. # 1901822

TURN AROUND TIMES: IF NO TAT IS SPECIFIED, SAMPLE(S) WILL BE PROCESSED AND CHARGED AS 3 - DAY TAT.

No.	Client Sample ID	HA Area #	Collection Date	Time	PLM	PLM Point Count 400	PLM Point Count 1000	PLM NY Protocol	TEM - Bulk	Comments
1	B-3-14-14 thru 1C		4/3/2019	6:30 AM/PM	X					Expansion caulk
2	B-3-14-24 thru 2C			6:30 AM/PM	X					Gray expansion caulk
3	B-3-14-3A thru 3C			6:30 AM/PM	X					Silver Paint
4	B-3-14-4A thru 4C			6:30 AM/PM	X					lt blue spray foam
5	B-3-14-5A thru 5C			6:30 AM/PM	X					Black tar
6				AM / PM						
7				AM / PM						
8				AM / PM						
9				AM / PM						
10				AM / PM						

Released by: Kyle C. Sandwich Signature: [Signature] Date/Time: 4/4/2019 8:00

Received by: [Signature] Signature: [Signature] Date/Time: 4/12/19 2:43 PM

# BRIDGE INSPECTION REPORT



STATE OF WISCONSIN  
DEPARTMENT OF TRANSPORTATION

# Inspection Report for B-03-014

USH 53 SB over CARLSON SCHOOL DRIVE  
Jun 08,2017



Type	Prior	Frequency (mos)	Performed
Routine	06-25-15	24	X
Interim	02-25-13	0	
SIA Review	06-13-13	48	X

Latitude 45°13'17.87"N  
Longitude 91°34'56.90"W

Owner STATE HIGHWAY DEPT  
Maintainer STATE HIGHWAY DEPT

## Time Log

Hours	Minutes	Team members
1	15	wjk

## Team members

Inspector	Name	Number	Signature	Date
	Kovaleski, William J	8007	<i>William J Kovaleski</i> E-signed by Bill(dotwjk)	09-06-17



**BRIDGE INSPECTION REPORT**  
**Wisconsin Department of Transportation**  
**DT2007 2003 s.84.17 Wis. Stats.**

page 2

**Identification & Location**

Feature On: USH 53 SB	Section Town Range: S26 T32N R10W	Structure Number:
Feature Under: CARLSON SCHOOL DRIVE	County: BARRON	<b>B-03-014</b>
Location 7.1M S JCT CTH I TO E	Municipality: DOVRE	Structure Name:

**Geometry**

measurements in feet, except where noted

Approach Roadway Width: 40	Bridge Roadway Width: 40.0	Total Length: 139.7
Approach Pavement Width: 24	Deck Width: 43.8	Deck Area (sq ft): 6118

**Traffic**

	Lanes	ADT	ADT year	Traffic Pattern
On	2	5550	2014	ONE WAY TRAFFIC
Under	2	3430	1988	TWO WAY TRAFFIC

**Capacity**

**Load Rating**

Inventory rating: HS16	Overburden depth (in): 2.0	Last rating date:	Controlling: SLAB Negative Moment
Operating rating: HS27	Deck surface material: LOW SLUMP CONCRETE	Re-rate for capacity (Y/N):	Control location: 0.3 SPAN 1
Posting:	Re-rate notes:		

**Hydraulic**

**Classification**

Scour Critical Code(113): (N) NO WATERWAY	Q100 (ft3/sec): 0	
High water elevation (ft): 0.0	Velocity (ft/sec): 0.0	Sufficiency #: 91.3

**Span(s)**

Span #	Material	Configuration	Depth (in)	Length (ft)	Main
1	CONT CONCRETE	HAUNCHED SLAB		39.0	
2	CONT CONCRETE	HAUNCHED SLAB		62.5	Y
3	CONT CONCRETE	HAUNCHED SLAB		35.5	

**Expansion joint(s)**

**Temperature:**

File:	New:
-------	------

**Clearance**

Item	File Measurement (ft)	File Date	New Measurement (ft)
Highway Min Vertical Under Cardinal	14.8	25-Jun-2015	
Highway Min Vertical Under Non-Cardinal			
Horizontal Under Cardinal	51.5		
Horizontal Under Non-Cardinal			
Highway Min Vertical On Cardinal			
Horizontal On Cardinal			

**Special Components**

Component	Year	Work Performed	Note
DECK - IOWA MIX	1989	OVERLAY - CONCRETE	

**Construction History**

Year	Work Performed	FOS id
1989	OVERLAY - CONCRETE	0003-84-01
1972	NEW STRUCTURE	1196-06-71

**BRIDGE INSPECTION REPORT**  
**Wisconsin Department of Transportation**  
**DT2007 2003 s.84.17 Wis. Stats.**

page 3

Structure No.: **B-03-014**

**Maintenance Items History**

Item	Recommended by	Status	Status change	Year completed
<b>Drainage - Repair/Construct Drainage Flumes</b>	Bjorklund, Allan M (8003)	COMPLETE	01/17/13	
Monitor condition of NE drain repaired with asphalt.				
<b>Deck - Patching</b>	Harrington, Daniel J (8004)	COMPLETE	01/17/13	
approx 12 sq ft deck patch				
<b>Deck - Patching</b>	Harrington, Daniel J (8004)	COMPLETE	01/17/13	
approx 20 sf of deck patching various spalls.				

**Maintenance Items**

Item	Priority	Recommended by	Status	Status change
<b>Deck - Surface Repair Spalls</b>	HIGH	Kurtz, William G (8008)	IDENTIFIED	07/02/15
Repair SPL in Wearing Surface (50SF).				
<b>Substructure - Repair Abutment / Wings</b>	HIGH	Kurtz, William G (8008)	IDENTIFIED	07/02/15
Fill void behind NE WWALL (6SF). Repair SPL on ABUTs (2LF).				
<b>Misc - Tighten Bolts and Nuts</b>	MEDIUM	Kurtz, William G (8008)	IDENTIFIED	07/02/15
Tighten all bolts on decorative rail.				
<b>Deck - Patching</b>	MEDIUM	Kurtz, William G (8008)	IDENTIFIED	07/02/15
Repair SPL in Reinforced Concrete Deck (8SF).				
<b>Approach - Patch Concrete</b>	MEDIUM	Kurtz, William G (8008)	IDENTIFIED	07/02/15
Repair SPLs N APPR (1EA).				
<b>Misc - Cut Brush</b>	LOW	Kurtz, William G (8008)	IDENTIFIED	07/02/15
Remove brush.				

**Elements**

Chk	Element	Defect	Description	UOM	Total	Quantity in Condition State			
						1	2	3	4
X	38		<b>Reinforced Concrete Slab</b>	SF	6,119	5,984	133	2	0
		1080	Delamination - Spall - Patched Area <b>E &amp; W face - CS3 spall w rust staining adjacent to Pier 1 - leaking under parapet. East face - 6in impact edge spalls over EB lane.</b>	SF		0	4	2	0
		1130	Cracking (RC) <b>Faces - few fine to hrline vert cracks at parapet joints and Piers. Underside: SP1 - 2 Fine/hrline longitudinal CL cracks (meet at midspan to 1 crack and extends to SP2 btwn C2). SP2 - fine/hrline longitudinal CL crack. SP3 - fine/hrline longitudinal CL crack extends half span.</b>	SF		0	129	0	0
	8514		Concrete Overlay	SF	6,119	0	6,119	0	0
		3210	Debonding/Spall/Patched Area/Pothole <b>Areas of noted delam/debond - 429sf. Select areas around joints of spalls filled w asphalt.</b>	SF		0	479	0	0
		3220	Crack (Wearing Surface) <b>Fine to hrline map cracking throughout - approx. 86%.</b>	SF		0	5,640	0	0

**BRIDGE INSPECTION REPORT**  
**Wisconsin Department of Transportation**  
**DT2007 2003 s.84.17 Wis. Stats.**

page 4

Structure No.: **B-03-014**

X	205		Reinforced Concrete Column	EA	8	7	1	0	0
			Piers consist of columns with deck acting as cap.						
		1130	Cracking (RC)	EA		0	1	0	0
			Col 2 of Pier 2 - fine horiz cracks at top of north face.						
X	215		Reinforced Concrete Abutment	LF	98	79	19	0	0
		1080	Delamination - Spall - Patched Area	LF		0	9	0	0
			North - small spalls at both ADW ends - note potential material loss from east ADW. South - multiple small 3in popouts along face (rebar cover)						
		1130	Cracking (RC)	LF		0	10	0	0
			South - fine to hrlne vert cracks at Brg 2, 3, 4, 5, and Bays 2, 3, & 4.						
X	300		Strip Seal Expansion Joint	LF	49	0	49	0	0
			South approach.						
		2310	Leakage, Seal Adhesion, Damage, Cracking	LF		0	49	0	0
			Potential leaking not fully visible - loose chunks of concrete behind bearings.						
X	311		Moveable Bearing	EA	6	0	6	0	0
			South abutment. Painted 01.						
		1000	Corrosion	EA		0	6	0	0
			Lt to med rust on btm plate.						
X	331		Reinforced Concrete Bridge Rail	LF	317	113	203	1	0
		1080	Delamination - Spall - Patched Area	LF		0	2	0	0
			Small spall east rail.						
		1130	Cracking (RC)	LF		0	201	1	0
			East rail CS3 vert crack on outside face w rust staining (over P2). Multiple hrlne to fine vert cracks w some fine surface map cracking - west = 41lf, east = 160lf						
X	8400		Integral Wingwall	EA	4	2	2	0	0
		8903	Wall Deterioration	EA		0	2	0	0
			Few fine surface cracks in NE and SE.						

**BRIDGE INSPECTION REPORT**  
**Wisconsin Department of Transportation**  
**DT2007 2003 s.84.17 Wis. Stats.**

page 5

Structure No.: **B-03-014**

**Assessments**

Chk	Element	Defect	Description	UOM	Total	Quantity in Condition State			
						1	2	3	4
X	9001		<b>Drainage - Approach</b> <b>North C&amp;G inlets. South shldr grvl.</b>	EA	2	2	0	0	0
X	9030		<b>Signs - Object Markers</b>	EA	2	2	0	0	0
X	9043		<b>Slope Protection- Crushed Aggregate with Bit.</b> <b>Rocks tightly adhered. Vegetation and bleaching at edges.</b>	EA	2	2	0	0	0
X	9322		<b>Approach Roadway - Concrete (non-structural)</b> <b>Both have mult cracks.</b>	EA	2	0	1	1	0
X	9335		<b>Decorative Rail</b> <b>Type J tubular railing on parapet.</b>	EA	2	2	0	0	0

**NBI Ratings**

	File	New
Deck	4	7
Superstructure	7	7
Substructure	7	7
Culvert	N	N
Channel	N	N
Waterway	N	N

**Structure Specific Notes**

**OLD:** Overall, condition of structure is vg. Extensive map cracking throughout this 3 span haunched slab structure appears stable after epoxy crack filling. Delam 7%- 1995.  
 (99) Cracking becoming more **extensive in overlay. Underside in good condition, no cracks/ no eff.. rest of structure in excellent cond.**  
**(01) Structure is in good condition. The deck surface and parapet being the only elements need repair/ replacement. Extensive map cracking of deck surface is beginning to spall and E parapet is showing cracks with rust stains full length.**

**Inspection Specific Notes**

**Inspector Site-Specific Safety Considerations**

**Structure Inspection Procedures**

**Walk-thru**

**Special Requirements**

Chk                      Hours                      Cost                      Comments

**Routine**  
**Document Comment/Description**

NE abut ADW





Routine  
Document Comment/Description

SE abut



# STRUCTURE INVENTORY AND APPRAISAL FIELD REVIEW FORM

**B-03-014**  
**USH 53 SB over CARLSON SCHOOL DRIVE**

## LOCATION

(3) Municipality:  
 (16) Latitude(° ' "):  
 (17) Longitude(° ' "):

DOVRE
45°13'17.87"N
91°34'56.90"W

## TRAFFIC SERVICE

(28A) Lanes On:  
 (28B) Lanes Under:  
 (102) Traffic Pattern On:  
 (102) Traffic Pattern Under:  
 (19) Detour Length(mi):

2
2
-NO TRAFFIC <input checked="" type="checkbox"/> ONE WAY TRAFFIC -TWO WAY TRAFFIC
-NO TRAFFIC -ONE WAY TRAFFIC <input checked="" type="checkbox"/> TWO WAY TRAFFIC
1

## GEOMETRY

(49) Structure Length(ft):  
 (50) Sidewalk Width(ft):  
 (50) Curb Width(ft):  
 (52) Culvert Barrel Length(ft):  
 (34) Skew:  
  
 (51) Bridge Roadway Width(ft):  
 (52) Deck Width(ft):  
 Right Wingwall Length(ft):  
 Left Wingwall Length(ft):  
 (32) Approach Roadway Width(ft):  
  
 (47) Minimum Horizontal(ft):  
 (55) Minimum Right Lateral(ft):  
 (56) Minimum Left Lateral(ft):

139.7	
Left: 0.0	Right: 0.0
3.8	
Angle(°): 30	Direction: -RIGHT FORWARD <input checked="" type="checkbox"/> LEFT FORWARD
Cardinal	Non-Cardinal
40.0	40.0
43.8	43.8
40	0
Cardinal Under Clearance	Non-Cardinal Under Clearance
51.5	
11.0	
10.5	

## RAILING APPRAISAL

(36A) Bridge Rail Adequacy:  
 (36B) Transition Adequacy:  
 (36C) Approach Guardrail Adequacy:  
 (36D) Guardrail Termination Adequacy:  
 Outer Rail:

-SUB-STANDARD X-STANDARD -NOT APPLICABLE		
X-SUB-STANDARD -STANDARD -NOT APPLICABLE		
-SUB-STANDARD X-STANDARD -NOT APPLICABLE		
-SUB-STANDARD X-STANDARD -NOT APPLICABLE		
Left	Right	Type
		TYPE F (TWO SQUARE TUBES) - STEEL(8)
		TYPE F (3 SQUARE TUBES) - STEEL(65)
		TYPE F (4 SQUARE TUBES) - STEEL(72)
		TYPE M-STEEL 3 SQUARE TUBES(93)
		SLOPED FACE PARAPET LF(91)
		SLOPED FACE PARAPET HF(92)
		VERTICAL FACE PARAPET TYPE A(74)
		TYPE W-THRIE BEAM(79)
		TYPE H ON VERTICAL PARAPET(80)
		TIMBER(38)
X	X	OTHER(99) (Please specify)  Left: TYPE J (ALUMINUM) ON SLOPED PPT(45)  Right: TYPE J (ALUMINUM) ON SLOPED PPT(45)
	CONT GUARD RAIL	
	NO APP GRDRL	
	NO ATTACHMENT	
5	22 MM(7/8") BOLT (Please enter quantity)	
	25 MM(1") BOLT (Please enter quantity)	
	OTHER (Please specify)	
X	(01) ENERGY ABSORBING TERMINAL/EAT	
	(02) TURN DOWN	
	(99) OTHER (Please specify)	

Transition Type:

Approach Attachment Rail Note:  
 Guardrail Termination Type:

Guardrail Termination Note:

## ROADWAY ALIGNMENT APPRAISAL

(72) Approach Alignment Appraisal:

	3 Intolerable- Substantial speed reduction
	6 Fair- Minor speed reduction
X	8 Good- No speed reduction

BRIDGE DECK  
REPAIR QUANTITIES

12/6/2018

Ken,

Here's a summary of our new direction for the Barron County project. Wing replacements are still in the project and Al Bjorklund wants the joints replaced on the overlays.

I've also included Al's estimated quantities for deck repairs. I would like to have another conference call with Al to discuss this change in scope, let me know if you agree and we'll try to set up a time.

I'm guessing we'll need to amend your design contract.

Let me know if you have questions.

Thanks,

Brendan

1196-04-77

USH 53 (Chippewa Co Line - CTH I NB)

RSRF20

- Change SFY from 2021 to 2023
- Add ADV SFY of 2021
- Change estimate from \$14.460 M to \$12.0 M to reflect BOS-recommended bridge scope changes (see below)
- Update bridge information in FIIPS to reflect BOS-recommended bridge scope changes

**1196-04-77:**

Current FIIPS Estimate w/o delivery: 14,460,000

New FIIPS Estimate w/o delivery including BOS changes: 12,000,000

Structure Work including: Conc overlays on B-3-14,20,24,30; Conc Overlays and Joints on B-3-26, 37; Re-decks on B-3-16,18 plus any other incidental structure work.

Here are Al's guesses on deck repair quantities, [Type 1\(SY\)](#)-[Type 2\(SY\)](#)-[Full Depth\(SY\)](#)

1) 1196-04-77 (USH 53, Chippewa County Line – USH 8 SB) 2021 RSRF20 \$14.460 M

- B-03-14 (03) CONC OVLY [70-35-2](#)
- B-03-16 (06) REPLACE DECK
- B-03-18 (06) REPLACE DECK
- B-03-20 (03) CONC OVLY [100-50-15](#)
- B-03-24 (03) CONC OVLY [30-15-5](#)
- B-03-26 (58) CONC OVLY/NEW JOINTS [20-10-1](#)
- B-03-30 (03) CONC OVLY [125-60-10](#)
- B-03-37 (58) CONC OVLY/NEW JOINTS [95-45-5](#)