

SELECT AS-BUILT DRAWINGS

PROJECT NO.	SHEET NUMBER	TOTAL SHEETS
1196-4-74	33	413
FEDERAL PROJECT DESIGNATION		

TRAFFIC VOLUME

U.S.H. 53
 A.D.T. 5300 (1980)
 D.V. 1260 (2000)
 R.D.S. 80 A.M.
 C.T.H. "A"
 A.D.T. 900 (1980)
 D.V. 180 (2000)
 R.D.S. 60 A.M.

DESIGN DATA

LIVELOAD: HS20
 ALLOWABLE DESIGN STRESSES:
 CONCRETE (TENSILE) GRADE "AA" SLAB 4,100 P.S.I.
 ALL OTHER 4,100 P.S.I.
 BAR STEEL REINFORCEMENT 62,000 P.S.I.
 STRUCTURAL CARBON STEEL 70,100 P.S.I.
 STRUCTURAL LOW ALLOY STEEL 67,000 P.S.I.
 OVER 3/8" TO 1" INCLUDING 1 1/2" THICK 65,000 P.S.I.


FOUNDATION DATA:
 ABUTMENTS TO BE SUPPORTED ON HP 10x48 PILES, DEVEN TO A MIN. BRG. VALUE OF 25T / PILE. SO. ABUT. EST. 20'-0" LG.
 No. ABUT. EST. 25'-0" LG.
 PIERS TO BE SUPPORTED ON SPREAD FOOTINGS WITH A MIN. ALLOWABLE SOIL BRG. PRESSURE OF 4T / SQ. FT.

GENERAL NOTES


DRAWINGS SHALL NOT BE SCALED.
 BAR STEEL REINFORCEMENT SHALL BE EMBEDDED 8" CLEAR UNLESS OTHERWISE SHOWN OR NOTED.
 ALL FIELD CONNECTIONS SHALL BE MADE WITH 3/4" DIA. FRICTION TYPE HIGH TENSILE STRENGTH BOLTS UNLESS SHOWN OR NOTED OTHERWISE.
 THE SLOPE OF FILL IN FRONT OF THE ABUTMENTS SHALL BE COVERED WITH SLOPE PAVING CRUSHED AGGREGATE, TO THE EXTENT SHOWN ON THIS SHEET. IN THE ABUTMENT DETAILS, THE FINISHED GRADED SECTION WAS USED AS THE UPPER LIMITS OF EXCAVATION FOR COMPUTATION OF EXCAVATION QUANTITIES AT THE PIERS.
 THE UPPER LIMITS OF EXCAVATION FOR STRUCTURES FOR THE ABUTMENTS SHALL BE THE EXISTING GROUND LINE AND THE QUANTITIES WERE COMPUTED FROM THIS LINE.

LIST OF DRAWINGS

1. GENERAL PLAN	X47058
2. GENERAL ELEVATION	X47059
3. SUBSTRUCTURE EXCAVATION	X47060
4. SOUTH ABUTMENT	X47061
5. SOUTH ABUTMENT DETAILS	X47062
6. NORTH ABUTMENT	X47063
7. NORTH ABUTMENT DETAILS	X47064
8. NORTH ABUTMENT DETAILS	X47065
9. NORTH ABUTMENT DETAILS	X47066
10. PIER 1	X47067
11. PIER 2	X47068
12. SUPERSTRUCTURE OF SPANS	X47069
13. CROSS SECTIONS OF SPANS	X47070
14. GIRDERS ELEVATIONS OF SPANS	X47071
15. SUPERSTRUCTURE	X47072
16. BRIDGING DETAILS	X47073
17. EXPANSION JOINT	X47074
18. SLOPE PAVING "A"	X47075
19. TUBULAR SEALING, TYPE "J"	X47076

PLAN
(3 SPAN WELDED R GIRDERS)

AS BUILT PLAN
 DATE 1-78 BY W.J.K.



LAYOUT

No.	Date	Revision	By

STATE OF WISCONSIN
 DEPARTMENT OF TRANSPORTATION
 DIVISION OF HIGHWAYS

STRUCTURE B-3-18

U.S.H. 53 OVER C.T.H. "A"

County: BARRON State: WIS. TR. DOVRE

Design Spec. A.A.H.M.S. 1969 Year: 1969 Date: 1969

Designer: E.H.A. Checker: C.O.W. Draftsman: BUDD Date: 1969

Approved: W.A. K. Date: 2-23-78

Chief Bridge Engineer Date:

GENERAL PLAN SHEET 1 OF 19

X47058

Deck and Parapets to be replaced.

 1196-4-74
 44 413

BILL OF BARS



 DIMENSIONS IN BENDING DETAILS ARE OUT TO OUT OF BAR
 THE FIRST DIGIT OF THE BAR MARK SIGNIFIES THE BAR SIZE

MARK	NO. REQ'D	LENGTH	BENT	CUT	LOCATION
S502	623	42'-4"			SLAB TRANS - BOTTOM & TOP
S502	152	43'-10"	X		" TOP
S503	152	44'-2"	X		" BOTTOM
S504	720	35'-5"			" LONGIT - BOTTOM & TOP
S505	20	15'-0"			" SYM ABOUT E OF PIER
S506	552	4'-9"	X		RAIL PARAPET - VERT
S507	552	5'-0"	X		"
S508	10	18'-4"			" HORIZ.
S509	20	23'-8"			"
S510	10	15'-7"			"
S511	10	19'-6"			"
S512	50	23'-4"			"
S513	10	26'-4"			"
S514	10	8'-6"			"
S515	10	18'-1"			"

S. Abut. body looks good, but backwall repairs required on a lot of the length. Approx. 50 SF of Concrete Surface Repair

BOTTOM TRANSVERSE BARS IN SLAB SHALL BE SUPPORTED BY CONTINUOUS BAR CHAIRS ON OR ADJACENT TO EACH GIRDER AND 8" INDIVIDUAL BAR CHAIRS PLACED AT 3'-0" CENTERS AT APPROXIMATELY THE 1/2 POINTS BETWEEN GIRDERS. TOP LONGITUDINAL BAR STEEL SHALL BE SUPPORTED BY CONTINUOUS BAR CHAIRS AT APPROXIMATELY 4'-0" CENTERS. THE 2" VERTICAL FACE OF THE RAIL PARAPET IS TO BE MAINTAINED AT ALL POINTS.

N. Abut. body looks good, but backwall repairs in a few locations. Approx. 30 SF of Concrete Surface Repair




CUTTING DIAGRAM


NOTE "H" IS THE NUMBER OF BARS BEFORE THE CUT

MARK	C	D	E	F	G	H	SETS REQ'D
S502	SET 1	1-9	43-10	1-9	42-1	152	1 SET 1
	SET 2						1 SET 2
S503	SET 3	1-11	44-2	1-11	42-3	152	1 SET 3
	SET 4						1 SET 4

MARK AND CUT ALL BARS ALONG THIS LINE. MAKE ALL CUTS NORMAL TO BAR AXIS.




BUNDLE & MARK WITH BAR NO. & SET NO.



SECTION S1

RAIL POST SPACING PLAN



NOTE THE CONCRETE IN ANY SPAN SHALL BE PLACED WITHIN FOUR HOURS OF THE TIME THAT CONCRETE WAS PLACED OVER AN ADJACENT PIER.

No.	Date	Revision	By
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS			
STRUCTURE B-3-18			
Drawn By	1969	Checked By	GJS
SUPERSTRUCTURE			SHEET 12 OF 19
			X47069

ASBESTOS REPORT



3159 VOYAGER DRIVE
GREEN BAY, WI 54311
920.455.8200 PHONE

Bridge Asbestos Inspection Report

WisDOT Project ID: 1196-04-02
Structure Number: B-03-018
Structure Name: USH 53 SB over CTH-A
City/County: Town of Dovre, Barron County, Wisconsin
GEI project Number: 1901822
Date Inspected: April 4, 2019
Inspected by: Kyle C. Sandmire
Asbestos Inspector License Number: All- 217616
Consultant Company: GEI Consultants, Inc.

Summary:

An asbestos inspection of Structure B-03-018 was conducted on April 4, 2019 by Kyle Sandmire, Asbestos Inspector License No. All-217616. Asbestos-containing material (ACM) **IS** present on this structure.

The inspection to identify and collect samples of potential asbestos-containing material (ACM) was completed following WisDOT standard sampling procedures for bridge inspections found in FDM 21-35-45. The ACM was detected in the gray gasket material between the bridge rail plates and the bridge deck walls.

Asbestos-containing material is present in Structure B-03-018. Standard Special Provision (STSP) 107-120 shall be included in the plans. If the bridge rails are disturbed during renovation activities, then Standard Special Provision (STSP) 203-005 shall be included in the plans and abatement would be required. The contractor will be responsible for completion of the Notification of Demolition and/or Renovation (DNR form 4500-113) if required. A copy of the inspection report is available from the region office.

Sample #	Sample Description	Sample Location	Method and Analytical Results	Category I or II non-friable or No ACM	Total Amount of Material on Structure
B-03-018-1A	Spray foam insulation	Between bridge deck and abutment	PLM, non-detect	No ACM	N/A
B-03-018-1B	Spray foam insulation	Between bridge deck and abutment	PLM, non-detect	No ACM	N/A
B-03-018-1C	Spray foam insulation	Between bridge deck and abutment	PLM, non-detect	No ACM	N/A
B-03-018-2A	Gray caulk	Bridge deck wall joints	PLM, non-detect	No ACM	N/A
B-03-018-2B	Gray caulk	Bridge deck wall joints	PLM, non-detect	No ACM	N/A
B-03-018-2C	Gray caulk	Bridge deck wall joints	PLM, non-detect	No ACM	N/A

B-03-018-3A	Black tar	Bridge deck	PLM, non-detect	No ACM	N/A
B-03-018-3B	Black tar	Bridge deck	PLM, non-detect	No ACM	N/A
B-03-018-3C	Black tar	Bridge deck	PLM, non-detect	No ACM	N/A
B-03-018-4A	Silver paint	On steel I-beam spans and on steel plates between bridge span and abutment	PLM, non-detect	No ACM	N/A
B-03-018-4B	Silver paint	On steel I-beam spans and on steel plates between bridge span and abutment	PLM, non-detect	No ACM	N/A
B-03-018-4C	Silver paint	On steel I-beam spans and on steel plates between bridge span and abutment	PLM, non-detect	No ACM	N/A
B-03-018-5A	Gray gasket material	Between bridge rail plates and bridge walls	PLM, 2% Chrysotile Asbestos	Category II Non-friable	40 SF
B-03-018-5B	Gray gasket material	Between bridge rail plates and bridge walls	Not Tested – Positive Stop	See 5A	See 5A
B-03-018-5C	Gray gasket material	Between bridge rail plates and bridge walls	Not Tested – Positive Stop	See 5A	See 5A

If you have any questions, please contact us at (920) 455-8200.

GEI CONSULTANTS, INC.



Kyle C. Sandmire
Environmental Scientist



Paul M. Garvey
Senior Scientist

Attachments:


B-03-018 Report Table

B-03-018 Map

B-03-018 Photo Log

B-03-018 Bulk Asbestos Sample Analysis Summary

B-03-018 Bulk Asbestos Sample Chain of Custody



Inspected 04/4/2019
 Kyle C. Sandmire, Inspector # All-217616
 GEI Consultants Inc.
 ACM is present in the structure.

0 250 500 1,000
 Feet

Source: Esri, DigitalGlobe, GeoEye, Earthstar Geographics, CNES/Airbus DS, USDA, USGS, AeroGRID, IGN, and the GIS User Community

GEI
 Consultants
 3159 Voyager Drive
 Green Bay, WI 54311
 920.455.8200

WisDOT Project 1196-04-02
 Structure B-03-018
 USH 53 (SB)
 over CTH-A
 Barron County


DESIGNED BY	KCS	4/10/2019
DRAWN BY	KCS	4/10/2019
APPROVED BY	PMG	4/10/2019
SCALE	1 inch = 500 feet	
FIGURE NO.	B-03-018	

PHOTOGRAPHIC LOG


PHOTOGRAPH NO: 1	
DIRECTION: SE	
DESCRIPTION: Looking southeast at B-03-018.	

PHOTOGRAPH NO: 2	
DIRECTION: SE	
DESCRIPTION: Looking southeast at B-03-018.	


PHOTOGRAPH NO: 3	
DIRECTION: SW	
DESCRIPTION: View of the bridge identification plate.	


PHOTOGRAPH NO: 4	
DIRECTION: SE	
DESCRIPTION: View of the spray foam insulation between the bridge deck and abutment. The spray foam insulation is not ACM.	


PHOTOGRAPH NO: 5	
DIRECTION: SW	
DESCRIPTION: View of the gray caulk on the bridge wall joints and abutment joints. The gray caulk is not ACM.	



PHOTOGRAPH NO: 6	
DIRECTION: Down	
DESCRIPTION: View of the black tar on the bridge deck. The black tar is not ACM.	



PHOTOGRAPH NO: 7	
DIRECTION: Down	
DESCRIPTION: View of the silver paint on the steel I-beam spans and on the steel plates between the span and abutment beneath the bridge deck. The silver paint is not ACM.	

PHOTOGRAPH NO: 8	
DIRECTION: E	
DESCRIPTION: View of the gray gasket material between the bridge railing plates and the bridge walls. The gray gasket material is non-friable ACM containing 2% Chrysotile asbestos.	



Environmental Hazards Services, L.L.C.

7469 Whitepine Rd

Richmond, VA 23237

Telephone: 800.347.4010

Asbestos Bulk Analysis Report

Report Number: 19-04-02068

Client: GEI Consultants Inc
3159 Voyager Dr.
Green Bay, WI 54311

Received Date: 04/12/2019

Analyzed Date: 04/15/2019

Reported Date: 04/16/2019

Project/Test Address: B-03-018; USH 53 5B over CTH-A; Town of Dovre, WI

Client Number:

200598

Fax Number:

Laboratory Results

Lab Sample Number	Client Sample Number	Layer Type	Lab Gross Description	Asbestos	Other Materials
19-04-02068-001	B-3-18-1A	--	Yellow Foam; Homogeneous	NAD	100% Non-Fibrous
19-04-02068-002	B-3-18-1B	--	Yellow Foam; Homogeneous	NAD	100% Non-Fibrous
19-04-02068-003	B-3-18-1C	--	Yellow Foam; Homogeneous	NAD	100% Non-Fibrous
19-04-02068-004	B-3-18-2A	--	Gray Rubbery Adhesive; Homogeneous	NAD	100% Non-Fibrous
19-04-02068-005	B-3-18-2B	--	Gray Rubbery Adhesive; Homogeneous	NAD	100% Non-Fibrous

Environmental Hazards Services, L.L.C

Client Number: 200598

Report Number: 19-04-02068

Project/Test Address: B-03-018; USH 53 5B over CTH-A; Town
of Dovre, WI

Lab Sample Number	Client Sample Number	Layer Type	Lab Gross Description	Asbestos	Other Materials
19-04-02068-006	B-3-18-2C	--	Gray Rubbery Adhesive; Homogeneous	NAD	100% Non-Fibrous
19-04-02068-007	B-3-18-3A	--	Black Rubbery Tar like; Homogeneous	NAD	100% Non-Fibrous
19-04-02068-008	B-3-18-3B	--	Black Rubbery Tar like; Homogeneous	NAD	100% Non-Fibrous
19-04-02068-009	B-3-18-3C	--	Black Rubbery Tar like; Homogeneous	NAD	100% Non-Fibrous
19-04-02068-010	B-3-18-4A	--	Silver Brittle; Homogeneous	NAD	100% Non-Fibrous
19-04-02068-011	B-3-18-4B	--	Silver Brittle; Homogeneous	NAD	100% Non-Fibrous
19-04-02068-012	B-3-18-4C	--	Silver Brittle; Homogeneous	NAD	100% Non-Fibrous
19-04-02068-013	B-3-18-5A	--	Gray Brittle; Homogeneous	2% Chrysotile	98% Non-Fibrous
Total Asbestos:				2%	

Environmental Hazards Services, L.L.C

Client Number: 200598
Project/Test Address: B-03-018; USH 53 5B over CTH-A; Town
of Dovre, WI

Report Number: 19-04-02068

Lab Sample Number	Client Sample Number	Layer Type	Lab Gross Description	Asbestos	Other Materials
19-04-02068-014	B-3-18-5B	--		Did Not Analyze (Positive Stop)	
19-04-02068-015	B-3-18-5C	--		Did Not Analyze (Positive Stop)	

QC Sample: 29-M22009-2
QC Blank: SRM 1866 Fiberglass
Reporting Limit: 1% Asbestos
Method: EPA Method 600/R-93/116, EPA Method 600/M4-82-020
Analyst: Sami Hosn

Reviewed By Authorized Signatory:

Melissa Kanode

Missy Kanode
QA/QC Clerk

The condition of the samples analyzed was acceptable upon receipt per laboratory protocol unless otherwise noted on this report. Each distinct component in an inhomogeneous sample was analyzed separately and reported as a composite. Results represent the analysis of samples submitted by the client. Sample location, description, area, volume, etc., was provided by the client. This report cannot be used by the client to claim product endorsement by NVLAP or any agency of the U.S. Government. This report shall not be reproduced except in full, without the written consent of the Environmental Hazards Service, L.L.C. California Certification #2319 NY ELAP #11714 NVLAP #101882-0 VELAP 460172. All information concerning sampling location, date, and time can be found on Chain-of-Custody. Environmental Hazards Services, L.L.C. does not perform any sample collection.

Environmental Hazards Services, L.L.C. recommends reanalysis by point count (for more accurate quantification) or Transmission Electron Microscopy (TEM), (for enhanced detection capabilities) for materials regulated by EPA NESHAP (National Emission Standards for Hazardous Air Pollutants) and found to contain less than ten percent (<10%) asbestos by polarized light microscopy (PLM). Both services are available for an additional fee.

400 Point Count Analysis, where noted, performed per EPA Method 600/R-93/116 with a Reporting Limit of 0.25%.

* All California samples analyzed by Polarized Light Microscopy, EPA Method 600/M4-82-020, Dec. 1982.

LEGEND: NAD = no asbestos detected



EHS
Laboratories™

Environmental Hazards Services, LLC

Asbestos Chain-of-Custody Form

SHIP TO: 7469 Whitepine Rd. Richmond, VA 23237

Phone: (800) 347-4010 FAX: (804) 275-4907

ONLINE CLIENT PORTAL AVAILABLE FOR ANALYSIS RESULTS AT:

www.leadlab.com



19-04-02068

Due Date:

04/17/2019

(Wednesday)

AE

Company Name: GEI Consultants Inc. Account Number: 1901822

Address: 3159 Voyager Drive City/State/Zip: Green Bay, WI 54311

Phone #: 920-241-2765 Email: k.sandmire@geiconsultants.com Fax: 920-455-8225

Project Name / Testing Address: B-03-018, USH S3 SB over CTH-A City/State (Required): Town of Lore, WI

Collected by: Kyle C. Sandmire, AII-217616 P.O. # 1901822

TURN AROUND TIMES: IF NO TAT IS SPECIFIED, SAMPLE(S) WILL BE PROCESSED AND CHARGED AS 3 - DAY TAT.

No.	Client Sample ID	HA Area #	Collection Date	Time	PLM	PLM Point Count 400	PLM Point Count 1000	PLM NY Protocol	TEM - Bulk	Comments
1	B-3-18-1A thru 1C		4/4/2019	11:10 AM/PM	X					Yellow spray insulation
2	B-3-18-2A thru 2C			11:10 AM/PM	X					Gray Caule
3	B-3-18-3A thru 3C			11:10 AM/PM	X					Black tar
4	B-3-18-4A thru 4C			11:10 AM/PM	X					Silver Paint
5	B-3-18-SA thru SC			11:10 AM/PM	X					Gray gasket
6										
7										
8										
9										
10										

Released by: Kyle C. Sandmire Signature: [Signature] Date/Time: 4/4/2019 9:00am

Received by: [Signature] Signature: [Signature] Date/Time: 4/11/19 2:46pm

BRIDGE INSPECTION REPORT



STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

Inspection Report for
B-03-018

USH 53 SB over A
Aug 16, 2018



Type	Prior	Frequency (mos)	Performed
Routine	06-23-17	24	
Interim		0	X
SIA Review	06-23-17	48	

Start Coordinates
Latitude
Longitude

End Coordinates (optional)
Latitude
Longitude

Owner

Maintainer

Time Log

Team members

Hours	Minutes	
0	30	

Name	Number	Signature	Date
Inspector <input type="text" value="Bjorklund, Allan M"/>	<input type="text" value="8003"/>	<input type="text" value="Allan M Bjorklund"/> <input type="text" value="E-signed by Allan Bjorklund(dotayb)"/>	<input type="text" value="09-07-18"/>

BRIDGE INSPECTION REPORT
Wisconsin Department of Transportation
DT2007 2003 s.84.17 Wis. Stats.

page 2

Identification & Location

Feature On: USH 53 SB	Section Town Range: S05 T32N R10W	Structure Number:
Feature Under: A	County: BARRON	B-03-018
Location 1.4M S JCT CTH I TO E	Municipality: DOVRE	Structure Name:

Geometry

measurements in feet, except where noted

Approach Roadway Width: 40	Bridge Roadway Width: 40.0	Total Length: 280.7
Approach Pavement Width: 24	Deck Width: 43.8	Deck Area (sq ft): 12294

Traffic

	Lanes	ADT	ADT year	Traffic Pattern
On	2	5550	2014	ONE WAY TRAFFIC
Under	2	450	2011	TWO WAY TRAFFIC

Capacity

Load Rating

Inventory rating: HS16	Overburden depth (in): 2.0	Last rating date:	Controlling: INTERIOR DECK GIRDER Moment
Operating rating: HS28	Deck surface material: INTEGRAL CONCRETE	Re-rate for capacity (Y/N):	Control location: 6.3 SPAN 3, 45.6
Posting:	Re-rate notes:		

Hydraulic

Classification

Scour Critical Code(113): (N) NO WATERWAY	Q100 (ft3/sec): 0	
High water elevation (ft): 0.0	Velocity (ft/sec): 0.0	Sufficiency #: 93.4

Span(s)

Span #	Material	Configuration	Depth (in)	Length (ft)	Main
1	CONT STEEL	DECK GIRDER		80.0	
2	CONT STEEL	DECK GIRDER		117.5	Y
3	CONT STEEL	DECK GIRDER		72.0	

Expansion joint(s)

Temperature:

File:	New:
-------	------

Clearance

Item	File Measurement (ft)	File Date	New Measurement (ft)
Highway Min Vertical Under Cardinal	15.9	12-Jun-2007	
Highway Min Vertical Under Non-Cardinal			
Horizontal Under Cardinal	46.0		
Horizontal Under Non-Cardinal			
Highway Min Vertical On Cardinal			
Horizontal On Cardinal			

Construction History

Year	Work Performed	FOS id
2006	PAINTING	
1984	OVERLAY - CONCRETE	0003-34-12
1972	NEW STRUCTURE	1196-04-74

Maintenance Items History

Item	Recommended by	Status	Status change	Year completed
Expansion Joints - Repair	Harrington, Daniel J (8004)	COMPLETE	01/17/13	
repair Rt lane North abut broken channel iron.				

BRIDGE INSPECTION REPORT
Wisconsin Department of Transportation
DT2007 2003 s.84.17 Wis. Stats.

page 3

Structure No.: **B-03-018**

Maintenance Items

Item	Priority	Recommended by	Status	Status change
Substructure - Clean Abutment / Pier Seats	HIGH	Kurtz, William G (8008)	IDENTIFIED	06/18/15
Remove debris from W ABUT.				
Substructure - Other Work	MEDIUM	Kurtz, William G (8008)	IDENTIFIED	06/18/15
Seal all concrete columns.				

Elements

Chk	Element	Defect	Description	UOM	Total	Quantity in Condition State			
						1	2	3	4
X	12		Reinforced Concrete Deck	SF	12,295	4,322	7,933	40	0
		1080	Delamination - Spall - Patched Area 6/15/15 SPL CS3 N ABUT 40SF 6/15/15 DELAM CS2 5533 SF 2018 There is more.	SF		0	5,533	40	0
		1130	Cracking (RC) Fine surface map cracking adjacent to girders.	SF		0	2,400	0	0
		8514	Concrete Overlay extensive map cracking with small spalls. Epoxy crackfilled and sealer.	SF	12,295	3,656	8,607	32	0
		3210	Debonding/Spall/Patched Area/Pothole SPL CS3 32 SF. DEBOND CS2 1230 SF	SF		0	1,230	32	0
		3220	Crack (Wearing Surface) CRK CS2 7377 SF	SF		0	7,377	0	0
	107		Steel Open Girder	LF	1,399	1,349	50	0	0
		1000	Corrosion BOTTOM FLANGE EXTERIOR CS2 50 LF	LF		0	50	0	0
		8516	Painted Steel Steel area for painting estimate 18,183 sq ft - 1,689 sq m New Paint 06/05	SF	16,487	16,437	0	50	0
		3440	Effectiveness (Steel Protective Coatings) SAME AREA AS CORROSION CS2 50 LF	SF		16,437	0	50	0
	205		Reinforced Concrete Column	EA	10	10	0	0	0
	215		Reinforced Concrete Abutment	LF	209	164	7	38	0
			Rust staining back walls both abut. Spall on N. abut. Bay 3 and Bay4 and also under G#3. horizontal crack w/eff N abut 2011. corner of bearing seat G3 N abut broken off 2013.						
		1080	Delamination - Spall - Patched Area See 2015 notes.	LF		0	0	38	0
		1130	Cracking (RC) See 2015 notes.	LF		0	7	0	0

BRIDGE INSPECTION REPORT
Wisconsin Department of Transportation
DT2007 2003 s.84.17 Wis. Stats.

page 4

Structure No.: **B-03-018**

	304		Open Expansion Joint	LF	196	188	0	8	0
			Corrosion @ joint (99) water going thru joint. Repaired break in outside lane 03. Both joints cracked 7 LF each in outside lane, welded date of inspection. New plates 2006 both joints. 2 lf of concrete behind expansion repair spalled out filled with aspalitic epatch right lane N abut. 2011 N Abut RT lane section 12 feet long broken both ends. repaired by Barron county 2012.						
		2360	Adjacent Deck or Header Damage	LF		0	0	8	0
			N SPL CS3 8LF.						
	311		Moveable Bearing	EA	15	10	5	0	0
			painted 06/05						
		1000	Corrosion	EA		10	5	0	0
			S ABUT, N ABUT & P1 Freckle rust starting.						
	313		Fixed Bearing	EA	5	0	5	0	0
			painted 06/05						
		1000	Corrosion	EA		0	5	0	0
			P1 Freckle rust starting.						
	331		Reinforced Concrete Bridge Rail	LF	560	247	250	63	0
			spalls, loose rails, bent rails. 10 LF spall with rebar exposed east rail span 1 in 2013.						
		1080	Delamination - Spall - Patched Area	LF		0	10	63	0
			W RAIL N SPL CS3 2LF SPL CS2 10LF. E RAIL SPL CS3 60LF.						
		1130	Cracking (RC)	LF		0	240	0	0
			W RAIL CRK CS2 140LF. E RAIL CRK CS2 200LF.						
	8400		Integral Wingwall	EA	4	1	3	0	0
		8902	Wall Movement	EA		0	1	0	0
			NW 0 out 3/4" down.						
		8903	Wall Deterioration	EA		0	2	0	0
			SW CS2. SE CS3.						

Assessments

Chk	Element	Defect	Description	UOM	Total	Quantity in Condition State			
						1	2	3	4
X	9001		Drainage - Ends of Structure	EA	4	4	0	0	0
X	9030		Signs - Object Markers	EA	2	2	0	0	0
X	9033		Signs - Vertical Clearance	EA	1	1	0	0	0
X	9040		Slope Protection- Asphaltic	EA	2	2	0	0	0
X	9167		Steel Diaphragm	EA	56	54	2	0	0
			painted 06/05						
			6/15/2015 Freckled rust starting on two.						
X	9322		Approach Roadway - Concrete (non-structural)	EA	2	1	1	0	0
			both N slabs cracked, S slabs have been overlaid with bit. cracked and settled.						

BRIDGE INSPECTION REPORT
Wisconsin Department of Transportation
DT2007 2003 s.84.17 Wis. Stats.

page 5

Structure No.: **B-03-018**

X	9335		Decorative Rail	EA	2	1	0	1	0
			6/15/2015 W RAIL BENT CS3 Missing bolts (3) 6/15/2015 E RAIL Damaged supports (2) Missing nut (1).						

NBI Ratings

	File	New
Deck	5	5
Superstructure	7	7
Substructure	7	7
Culvert	N	N
Channel	N	N
Waterway	N	N

Structure Specific Notes

OLD: Three span continouse steel girder structure is in vg condition. Minor rusting of lower flanges on fascia and interior girders. Moderate rusting of fasica abutment bearings, north abutment. All other elements are in vg condition. Delam deck area 5.99% - 1996. Both abutment joints should be replaced with compression gland to prevent further deterioration of bearing assemblies. To size gland - 1.5 inches @ 35 Deg F. Steel area- 18,183 sq ft, 1689.26 sq m.
 (99) Bridge in overall good shape. Rust is spreading on lower flanges with some pack rust showing up on top flanges.
 (01) Structure is in good condition. the deck is the main element with distress, it is in the program. Paint system is deteriorating, tested for lead, test was positive, lead present. Remainder of structure is in very good condition. Vertical height clearance measured 16.11' E. Fascia c/l.lowest found.

Inspection Specific Notes

Inspector Site-Specific Safety Considerations

Structure Inspection Procedures

Walk-thru

Special Requirements

Chk	Hours	Cost	Comments
-----	-------	------	----------

Interim

Document Comment/Description

Typical underdeck deterioration



Interim

Document Comment/Description

Typical underdeck deterioration



Interim

Document Comment/Description

Typical underdeck deterioration

