

DESIGN LOADING	HS20
INVENTORY RATING	HS-XX
OPERATIONAL RATING	HS-XX
WISCONSIN STANDARD PERMIT VEHICLE (WIS-SPV)	XX KIPS


A.A.D.T. (2022) = 9,350
A.A.D.T. (2042) = 11,300

CONCRETE MASONRY - OVERLAY DECKS ————— $f'_c = 4,000$ P.S.I.

1. REHAB GENERAL PLAN

PROFILE GRADE LINE SHALL BE DETERMINED IN THE FIELD BASED ON A MINIMUM
OVERLAY THICKNESS OF 1/2" PLACED ABOVE THE DECK SURFACE AFTER SURFACE
PREPARATION. EXPECTED AVERAGE OVERLAY THICKNESS IS 2". IF EXPECTED AVERAGE
OVERLAY THICKNESS IS EXCEEDED BY MORE THAN 1/2", CONTACT THE STRUCTURES
DESIGN SECTION.

BRIDGE OFFICE CONTACT:
WILLIAM DREHER
(608) 266-8489

 **MSA** ENGINEERING | ARCHITECTURE | SURVEYING
FUNDING | PLANNING | ENVIRONMENTAL
1702 Pankratz St Madison, WI 53704
(608) 242-7779 www.msa-ps.com
© MSA Professional Services, Inc.

ACCEPTED _____
CHIEF STRUCTURES DESIGN ENGINEER DATE _____

STH 29 EB OVER CTH X			
COUNTY	CHIPPEWA	TOWN/CITY/VILLAGE	SIGNATURE

DESIGN SPEC.			
REHABILITATION - N/A			
DESIGNED BY	XXX	DESIGN CK'D.	XXX
DRAWN BY	SSD	PLANS CK'D.	KHP

REHAB		SHEET 1 OF
GENERAL PLAN		



ITEM NUMBER	BID ITEM	UNIT	WEST ABUT.	EAST ABUT.	SUPER	TOTAL
502.3200	PROTECTIVE SURFACE TREATMENT	SY	-	-	733	733
502.3210	PIGMENTED SURFACE SEALER	SY	-	-	154	154
509.0301	PREPARATION DECKS TYPE 1	SY	-	-	37	37
509.0302	PREPARATION DECKS TYPE 2	SY	-	-	15	15
509.0500	CLEANING DECKS	SY	-	-	733	733
509.2000	FULL-DEPTH DECK REPAIR	SY	-	-	1	1
509.2500	CONCRETE MASONRY OVERLAY DECKS	CY	-	-	44	44
509.9050.S	CLEANING PARAPETS	LF	-	-	387	387

* QUANTITY LISTED IS AN ESTIMATE. CONTRACTOR SHALL COORDINATE THE FIELD IDENTIFICATION OF ALL DECK REPAIR LOCATIONS WITH THE ENGINEER.

