

# WisDOT NC Region 2017 Construction Conference

Emily Kuehne and Max Kulick

Bureau of Structures

February 22, 2017



**BUREAU OF**  
**STRUCTURES**

# Structures Agenda

- ▶ Contacting BOS – When & Why
- ▶ Specification and Manual Updates
- ▶ Structures Construction Issues
- ▶ Ancillary (Wind Loaded) Structure Issues
- ▶ Fabrication & Materials Issues

# Structures Agenda

- ▶ **Contacting BOS – When & Why**
- ▶ Specification and Manual Updates
- ▶ Structures Construction Issues
- ▶ Ancillary (Wind Loaded) Structure Issues
- ▶ Fabrication & Materials Issues

# Contacting BOS – When & Why

- ▶ Anything “structural”

- excessive construction loads
- structural capacity
- pile locations, etc.

- ▶ If in doubt, call us!

- See Structures Contacts Handout





# Region Structures Maintenance

- ▶ Tom Hardinger 715-421-8323
- ▶ Anthony Stakston 715-421-8345
- ▶ Brock Gehrig 715-365-5799

# Structures Agenda

- ▶ Contacting BOS – When & Why
- ▶ **Specification and Manual Updates**
- ▶ Structures Construction Issues
- ▶ Ancillary (Wind Loaded) Structures
- ▶ Fabrication & Materials Issues

# Standard Spec Updates

- ▶ Structure Backfill: Type A, B
- ▶ Curing retaining wall parapets
- ▶ Price adjustment for piling
- ▶ Concrete sign support bases



# Standard Spec Updates

- ▶ Adhesive Anchors
  - No longer type "L" and "S" anchors
  - Mechanical anchors not allowed
  - Adhesive anchor installation
  - Pullout testing



**BUREAU OF**  
**STRUCTURES**



# Const. & Mat'ls Manual Updates

- ▶ Updated guidance for bolting
- ▶ “Slip-critical” bolted connections



**CONSTRUCTION AND MATERIALS MANUAL**  
Wisconsin Department of Transportation

**TABLE OF CONTENTS**  
Chapter 1: General Provisions

**Section 1-10 Project Management**

- 1-10.1 ..... Introductions and Definitions
  - 1-10.1.1 ..... Originator
  - 1-10.1.2 ..... Overview
  - 1-10.1.3 ..... Project Management Support
- 1-10.2 ..... Program vs. Project Management
  - 1-10.2.1 ..... Overview
- 1-10.3 ..... Program vs. Performance Management
  - 1-10.3.1 ..... Overview
- 1-10.4 ..... Project Integration Management
  - 1-10.4.1 ..... Overview
  - 1-10.4.2 ..... Processes in Project Integration Management
- 1-10.5 ..... Project Management in Construction
  - 1-10.5.1 ..... Scope Management
  - 1-10.5.2 ..... Schedule Management
  - 1-10.5.3 ..... Budget Management
  - 1-10.5.4 ..... Communication Management
  - 1-10.5.5 ..... Stakeholder Management
  - 1-10.5.6 ..... Resource Management
  - 1-10.5.7 ..... Procurement Management
  - 1-10.5.8 ..... Risk Management
  - 1-10.5.9 ..... Quality Management
  - 1-10.5.9 ..... References

**Section 1-15 Glossary**

**Section 1-30 Hazardous Materials**

- 1-30.1 ..... Hazardous Chemicals
  - 1-30.1.1 ..... Background
  - 1-30.1.2 ..... Information Sources
  - 1-30.1.3 ..... Working with Hazardous Chemicals
  - 1-30.1.4 ..... Safe Work Practices
  - 1-30.1.5 ..... Physical Hazards
  - 1-30.1.6 ..... Health Hazards
- 1-30.2 ..... Requirements for Contractors and Subcontractors
  - 1-30.2.1 ..... Hazardous Substance Found During Construction
  - 1-30.2.2 ..... Suspected Asbestos Contamination
  - 1-30.2.3 ..... Underground Storage Tanks and Suspected Groundwater Contamination
  - 1-30.2.4 ..... Coordination With Bureau of Equity and Environmental Services
  - 1-30.2.5 ..... Remediation Costs
  - 1-30.2.6 ..... Coordination of Removal
  - 1-30.2.7 ..... Assessment of Remediation
  - 1-30.2.8 ..... Location for Stockpile Material
- 1-30.3 ..... Lead Paint Wastes from Bridge Projects
  - 1-30.3.1 ..... Bridge Projects Generating More Than One 55-Gallon Drum of Lead Paint Waste
- 1-30.4 ..... Bridge Projects Generating Less Than One 55-Gallon Drum of Lead Paint Waste
  - 1-30.4.1 ..... DNR Approval


December 2016

Page 1




# Const. & Mat'ls Manual Updates

- ▶ Steel diaphragm to prestressed concrete girder web connections
  - Snug-tight plus 1/4 turn for through-bolts
  - 80 foot-pounds when connecting to a ferrule loop insert
  - Turn-of-nut or direct tension indicating (DTI) washer for steel-to-steel connections
  - Field rotational capacity testing is not required



# Construction Critical Inspection

- ▶ <http://wisconsindot.gov> → DOING BUSINESS → Engineers and consultants → Structure and road resources → Standards and manuals
- ▶ Guidance on critical inspection
  - Roadway
  - Box Culverts and Retaining Walls
  - Temporary Structures
  - Bridges



# Structures Agenda

- ▶ Contacting BOS – When & Why
- ▶ Specification and Manual Updates
- ▶ **Structures Construction Issues**
- ▶ Ancillary (Wind Loaded) Structure Issues
- ▶ Fabrication & Materials Issues





# Structures Agenda

- ▶ Contacting BOS – When & Why
- ▶ Specification and Manual Updates
- ▶ **Structures Construction Issues**
  - Wing Tip Erosion
  - Construction Loading
  - Bridge Decks – FHWA
  - Reinforcement
  - Backfill
  - Girder Damage
  - Joint Replacement
  - Bearing Anchor Bolts
  - Structural Approach Slabs
- ▶ Ancillary (Wind Loaded) Structure
- ▶ Fabrication & Materials Issues




# Wing Tip Erosion and Drainage

- ▶ Be sure grading around wing tips promotes proper drainage.
- ▶ Typically finished grade ends 6" above wing tip.
- ▶ Do not allow bituminous sealant around wing tips.
- ▶ The end of the structural approach slab is not the end of wing.





# Wing Tip Erosion and Drainage



# Construction Loads on Bridges

- ▶ Std. Spec 108.7.3 Loads on Structures
- ▶ Contractor's responsibility
- ▶ If directed by Engineer, contractor to analyze and submit to BOS for review
- ▶ Wisconsin P.E. required
- ▶ BOS will assist if unsure






# FHWA/WisDOT Joint Program Review: Bridge Deck Construction

- ▶ Purpose:
  - Determine if Standard Specifications are consistently administered throughout Regions
  - Identify best practices/opportunities for improvement
- ▶ Team Members
  - FHWA
  - WisDOT: Regions, BOS, BTS, BPD, SE Freeways



# FHWA/WisDOT Joint Program Review: Bridge Deck Construction


- ▶ Scope:
  - Full depth concrete bridge decks & Grade E overlays
  - Visited 22 active projects
    - Neighboring states IL, IA
  - Target construction operations:
    - Formwork/rebar installation
    - Dry-run
    - Pre-pour meeting
    - Deck/overlay pour
    - QC/QV testing





# FHWA/WisDOT Joint Program Review: Bridge Deck Construction

- ▶ Final Report published June, 2016
- ▶ Eight Observations:
  - *“Inspector QA roles and responsibilities aren’t well understood”*



# FHWA/WisDOT Joint Program Review: Bridge Deck Construction

- ▶ Dry runs
  - Timing – Avoid dry runs immediately before pour
  - Measurements
    - Inconsistent frequency
    - Spot-check vs. entire deck area
    - Heavy reliance on contractor measurements
    - Independent verification
  - Check finishing machine set-up
  - Use rigid straightedge under rollers, avoid 2x4's





# FHWA/WisDOT Joint Program Review: Bridge Deck Construction



- ▶ Other Opportunities for Improvement
  - Written notification to contractor to proceed with deck pour
  - Inadequate staffing
    - Critical Inspection Guide
    - Deck pours - “continuous inspection”
    - Minimum two inspectors
  - Inspector inconsistency
    - One-day Bridge Construction Inspection Training

*“Based on your forecasted evaporation rates and current forecasted evaporation rates, you are ok to proceed with the overlay pour as scheduled for tonight.”*



# Reinforcement Placement

- ▶ Correct Bar
  - Size
  - Coating
  - Bends
- ▶ Spacing
- ▶ Orientation
- ▶ Clear Distance
- ▶ Tied Firmly
- ▶ Adequate Lap Lengths
- ▶ All Bars Included




(A21) FOR PPT. BARS & DIMENSIONS, SEE "MODIFIED SINGLE SLOPE PARAPET 32SS" SHEET FOR DETAILS.



**BUREAU OF**  
**STRUCTURES**

# Stab Bars

- ▶ Only allowed when clearly stated on the plan
  - Example: Dowel bar between beam seats at fixed piers & abutments
- ▶ Otherwise, not allowed!
  - At cold joint, so creates pocket where water & salt can collect
  - Freeze thaw cycle & corrosion causes damage/spalling






# Structure Backfill – Type A & B

- ▶ Structure Backfill is now categorized as either Type A or Type B.
- ▶ The type of backfill and the limits of structure backfill are now required to be shown on the structure plans.
- ▶ **Bridge Standard 9.01** shows typical structure backfill details and notes to be used on structure plans.





# Structure Backfill – Type A & B



**BUREAU OF  
STRUCTURES**

# Girder Damage During Removals

- ▶ “Damage will occur no matter what I do when removing a bridge deck.” ➡ THIS COMMENT MAY COME FROM CONTRACTORS BUT IS NOT THE WAY WISDOT VIEWS THIS ISSUE



**BUREAU OF  
STRUCTURES**



# Girder Damage During Removals




**BUREAU OF**  
**STRUCTURES**




# Girder Damage During Removals

- ▶ Who to contact when girder damage occurs:



# Joint Replacement Issues


- ▶ Recurring Issues:
  - Check that joint is set correctly prior to deck pour
  - Too high is no good, but too low is also no good
  - Plan note says to 'set flush with concrete'





# Joint Replacement Issues



- ▶ New Issue Discovered in the Past Year
  - Construction of joints with overlays has not followed the details in the structure plans
  - THE PAVING BLOCK AT THE ABUTMENT **SHOULD NOT BE POURED UP TO THE UNDERSIDE OF THE OVERLAY, AND SUBSEQUENTLY OVERLAID**






# Joint Replacement Issues

- ▶ New Issue Discovered in the Past Year
  - New Standard Detail Created (Won't be on Plans this Construction Season but detail can be used as a field adjustment)



# Bearing Anchor Bolts

- ▶ Know the contractor's plan for Anchor Bolts
  - Cast-in vs Post-installed (grouted or epoxied)
- ▶ If Post-installed, check to ensure bar steel does not conflict
- ▶ Bar steel can, and should, be adjusted before pouring concrete if conflicts are found




**SECTION THRU PIER CAP**

# Structural Approach Slabs

- ▶ Some contractors have requested to pour the structural approach slabs in conjunction with the bridge deck

- ▶ Potential benefits:

- Schedule
- Ride
- Durability



- ▶ If you get this request, contact BOS to see if it is right for your situation



# Structures Agenda

- ▶ Contacting BOS – When & Why
- ▶ Specification and Manual Updates
- ▶ Structures Construction Issues
- ▶ **Ancillary (Wind Loaded) Structure Issues**
- ▶ Fabrication & Materials Issues

# Ancillary (Wind Loaded) Structures

- ▶ Standard Spec updates
  - 636: Concrete Sign Supports
    - Construction joint is not allowed on footing, or drilled shaft without engineer's written approval
    - Remove disposable casing before backfilling →
  - 641: Sign Bridges and Overhead Sign Supports
    - Removal of aluminum sign bridges, and reformat the section to cover aluminum components (sign supports & catwalk) only
    - Re-arrange the steel sign bridge section for better clarity
    - Design overhead sign support per plan specification, currently design with ASD and LFD methods
    - Welding aluminum members in the field is not allowed



# Ancillary (Wind Loaded) Structures

- ▶ Standard Spec updates (continue)
  - 657: Poles, Arms, Standards, and Bases
    - Contractor furnish all H.S. bolts, nuts, flat washers and DTI's
    - All standard poles are designed under AASHTO legacy standards until LRFD specifications are implemented
    - Misprinted section 657.2.2.1.4. It is a repeat of 657.2.2.1
  - 660: High Mast Lighting
    - Design high mast lighting structure per 6<sup>th</sup> edition of AASHTO design standards







# Ancillary (Wind Loaded) Structures

## ► Standard Drawings

- Updated standard drawings for Chapter 39 of the WisDOT Bridge Manual
- All new sign bridge standard insert sheets
- Updated SDD's for type 10 & 13 concrete base
- Updated SDD's for all overhead sign support concrete bases
  - new details for anchor rod assembly, top template and bottom anchor plates as shown



**TOP TEMPLATE AND  
BOTTOM ANCHOR PLATE**



**ANCHOR ROD ASSEMBLY DETAILS**

MINIMUM OF 6 ANCHOR RODS,  
EXACT NUMBER, SIZE, DIMENSION  
AND ORIENTATION AS SHOWN ON  
FABRICATION DRAWING.

# Ancillary (Wind Loaded) Structures

- ▶ Footing construction issues
  - No horizontal construction joint on cantilever structure footings




**ACCEPTABLE**  
(single pour)



separate pours

**NOT ALLOWED**

**NOT a construction joint**



**CANTILEVER TRUSS FOOTING**



**BUREAU OF  
STRUCTURES**



# Ancillary (Wind Loaded) Structures


- ▶ Recent Findings – Cantilever Truss
  - End of truss connections to be bolted.





# Ancillary (Wind Loaded) Structures

- ▶ Recent Findings - Full span truss
  - Transverse plate should be parallel to chord.
  - Bottom web should be facing up



# Ancillary (Wind Loaded) Structures

- ▶ Recent Findings – Cantilever Truss
  - End of truss connections to be bolted.



**BUREAU OF**  
**STRUCTURES**



# Ancillary (Wind Loaded) Structures

- ▶ Recent Findings –
  - Coordination in Staged projects, ensuring anchor templates are consistent with plans.





# Structures Agenda

- ▶ Contacting BOS – When & Why
- ▶ Specification and Manual Updates
- ▶ Structures Construction Issues
- ▶ Ancillary (Wind Loaded) Structure Issues
- ▶ **Fabrication & Materials Issues**

# Steel Expansion Bearings Issues

- ▶ Issues to watch for with Steel Expansion Bearings
  - Girders coming off of their bearings
  - Teflon squeezing out of the bearing assembly
  - Improper Teflon thickness (should be 1/16")
  - Improper bond of Teflon to steel plate B. See standard specification for proper bond procedure



# Steel Expansion Bearings Issues

- ▶ Issues to watch for with Steel Expansion Bearings
  - Girder anchor plate not centered on plate B at the time of girder erection
  - Unclean bearing surfaces (proper storage is key!)
  - Improper surface finish on anchor plate (ANSI 8-mirror finish)





# Steel Expansion Bearings Issues



**BUREAU OF**  
**STRUCTURES**

# Conclusion

- ▶ Call us!
- ▶ BOS looks forward to another successful construction season – THANK YOU!



BUREAU OF  
**STRUCTURES**