

LEVELS: 0W - 1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14, 15, 16, 17, 18, 19, 20, 21, 22, 23, 24, 25, 26, 27, 28, 29, 30, 31, 32, 33, 34, 35, 36, 37, 38, 39, 40, 41, 42, 43, 44, 45, 46, 47, 48, 49, 50, 51, 52, 53, 54, 55, 56, 57, 58, 59, 60, 61, 62, 63

GRADING, SHAPING & FINISHING FOR BEAM GUARD ANCHORAGES

(90329)				
GRADING, SHAPING & FINISHING FOR BEAM GUARD ANCHORAGES				
BORROW REQUIRED FOR BEAM GUARD ANCHORAGES				
CRUSHED AGGREGATE REQUIRED FOR BEAM GUARD ANCHORAGES				
STATION	LOCATION	EACH	C.Y.	C.Y.
209+90	LEFT	1	75	12
233+80	LEFT	1	50	12
239+00	RIGHT	1	50	12
248+75	RIGHT	1	50	12
249+05	RIGHT	1	50	12
274+00	RIGHT	1	75	12
		6	* 350	* 72

* Note: The quantity for the borrow and the c.a.b.c. are incidental to the item of grading, shaping & finishing for beam guard anchorages. These are shown for informational purposes only.

SIGNS, TYPE II, REFLECTIVE

(63702)		
SIGNS, TYPE II REFLECTIVE		
SIGN NUMBER	LOCATION	S.F.
1	LEFT	6.25
2	LEFT	2.25
3	RIGHT	6.25
4	RIGHT	2.25
5	LEFT	6.25
6	LEFT	2.25
7	RIGHT	8.00
8	RIGHT	6.25
9	RIGHT	2.25
10	RIGHT	9.00
11	RIGHT	4.00
12	LEFT	9.00
13	LEFT	4.00
14	LEFT	8.00
15	RIGHT	8.00
16	RIGHT	8.00
17	LEFT	2.25
18	LEFT	2.25
19	RIGHT	8.00
		104.50

SILT FENCE, DELIVERED & INSTALLED

(62815)			
SILT FENCE, DELIVERED			
(62816)			
SILT FENCE, INSTALLED			
STATION	LOCATION	L.F.	L.F.
209+90	LEFT	100	100
233+80	LEFT	100	100
239+00	RIGHT	100	100
248+75	RIGHT	50	50
249+05	RIGHT	50	50
274+00	RIGHT	100	100
		500	500

STEEL PLATE BEAM GUARD, CLASS A

(61408)			
STEEL PLATE BEAM GUARD, CLASS A			
Station	To Station	LOCATION	L.F.
210+40	233+30	LEFT	2,290
239+50	248+25	RIGHT	875
249+55	273+50	RIGHT	2,395
			5,560

WOOD POSTS, 4x6-INCH

(63411)		(63412)	
14 FL		16 FL	
(EACH)		(EACH)	
6		5	
6		5	

Note: Posts are to be distributed as needed to best fit the field conditions.

STEEL PLATE BEAM GUARD, ENERGY ABSORBING TERMINAL

(61435)			
STEEL PLATE BEAM GUARD, ENERGY ABSORBING TERMINAL			
Station	To Station	LOCATION	EACH
209+90	210+40	LEFT	1
233+30	233+80	LEFT	1
239+00	239+50	RIGHT	1
248+25	248+75	RIGHT	1
249+05	249+55	RIGHT	1
273+50	274+00	RIGHT	1
			6

PROJECT NUMBER: 5770-00-75

HIGHWAY: STH 133

COUNTY: IOWA

MISCELLANEOUS QUANTITIES

SCALE, FT.

SHEET NUMBER: 3A

E

FILE NAME: C:\USERS\projects\57700005\57700005.dgn

ORIGINATOR:

PLOT SCALE: 200.000000:1.000000

PLOT DATE: 19-DEC-2000 13:17

WISDOT/CADDIS SHEET 42