

DATE 03/09/90

ESTIMATE OF QUANTITIES

ITEM	ITEM DESCRIPTION	UNIT	TOTAL	5770-00-79 QUANTITY	5953-01-71 QUANTITY
20351	REMOVING OLD BRIDGE, STATION 200+12	L.S.	1.00	1.00	
20352	REMOVING OLD BRIDGE, STATION 200+27	L.S.	1.00		1.00
20419	REMOVING ASPHALTIC SURFACE, BUTT JOINTS	S.Y.	630.00	290.00	340.00
20503	UNCLASSIFIED EXCAVATION	C.Y.	115.00	50.00	65.00
20610	EXCAVATION FOR STRUCTURES, BRIDGES B-25-934	L.S.	1.00	1.00	
20611	EXCAVATION FOR STRUCTURES, BRIDGES B-25-935	L.S.	1.00		1.00
21302	FINISHING ROADWAY, PROJECT B-25-934	L.S.	1.00	1.00	
21303	FINISHING ROADWAY, PROJECT B-25-935	L.S.	1.00		1.00
30403	CRUSHED AGGREGATE BASE COURSE	C.Y.	64.00	34.00	30.00
40204	ASPHALTIC MATERIAL FOR TACK COAT	GAL.	75.00	40.00	35.00
41101	ASPHALTIC SURFACE	TON	120.00	50.00	70.00
50201	CONCRETE MASONRY, BRIDGES	C.Y.	76.00	53.00	23.00
50230	PROTECTIVE SURFACE TREATMENT	GAL.	12.00	4.00	8.00
50250	CONCRETE MASONRY ANCHORS, TYPE L, NO. 5 BARS	EACH	216.00	92.00	124.00
50261	CONCRETE MASONRY ANCHORS, TYPE S, 5/8-INCH	EACH	64.00	64.00	
50504	HIGH-STRENGTH BAR STEEL REINFORCEMENT, BRIDGES	LB.	1,500.00	1,500.00	
50511	COATED HIGH-STRENGTH BAR STEEL REINFORCEMENT, BRIDGES	LB.	21,570.00	5,370.00	16,200.00
50626	NON-LAMINATED ELASTOMERIC BEARING PADS	EACH	2.00		2.00
50627	LAMINATED ELASTOMERIC BEARING PADS	EACH	2.00		2.00
50901	PREPARATION, DECKS	S.Y.	105.00		105.00
50905	CLEANING, DECKS	S.Y.	105.00		105.00
50920	FULL-DEPTH DECK REPAIR	S.Y.	5.00		5.00
50925	CONCRETE MASONRY, OVERLAY, DECKS	C.Y.	17.00		17.00
51340	TUBULAR RAILING, TYPE F, STRUCTURE B-25-934	L.S.	1.00	1.00	

Sheet 3

5770-00-79
QUANTITY

5953-01-71
QUANTITY

TOTAL

UNIT

ITEM DESCRIPTION

ITEM

1.00

1.00

L.S.

51341 TUBULAR RAILING,
TYPE F, STRUCTURE
B-25-935

1.00

1.00

L.S.

51780 ROLLUTION CONTROL,
CLASS II, STRUCTURE
B-25-935

300.00

300.00

L.F.

60305 TEMPORARY PRECAST
CONCRETE BARRIER,
DELIVERED

600.00

600.00

L.F.

60307 TEMPORARY PRECAST
CONCRETE BARRIER,
INSTALLED

30.00

30.00

C.Y.

60602 HEAVY RIPRAP

3.00

7.00

EACH

61406 ANCHORAGES FOR
STEEL PLATE BEAM
GUARD

254.00

562.00

L.F.

61408 STEEL PLATE BEAM
GUARD, CLASS A

2.00

2.00

EACH

61412 ANCHORAGES FOR
STEEL PLATE BEAM
GUARD, TYPE 1

.50

1.00

L.S.

61910 MOBILIZATION

4.00

8.00

EACH

63401 WOOD POSTS,
4X4-INCH X 10-FT.

12.00

24.00

S.F.

63702 SIGNS, TYPE II,
REFLECTIVE

4.00

14.00

EACH

63822 MOVING SIGNS, TYPE
II

1.00

1.00

L.S.

64201 FIELD OFFICE, TYPE
A

1.00

1.00

L.S.

64302 TRAFFIC CONTROL,
PROJECT B-25-934

1.00

1.00

L.S.

64303 TRAFFIC CONTROL,
PROJECT B-25-935

130.00

670.00

DAYS

64318 TRAFFIC CONTROL,
BARRICADES, TYPE
III

910.00

3,340.00

DAYS

64321 TRAFFIC CONTROL,
WARNING LIGHTS,
TYPE A

1,365.00

3,975.00

DAYS

64323 TRAFFIC CONTROL,
WARNING LIGHTS,
TYPE C

1,365.00

3,975.00

DAYS

64326 TRAFFIC CONTROL,
SIGNS

300.00

500.00

L.F.

64406 PAVEMENT MARKING,
EPOXY, 4-INCH

1,200.00

1,200.00

L.F.

64481 TEMPORARY PAVEMENT
MARKING, REMOVABLE
TAPE

300.00

300.00

L.F.

64487 REMOVING PAVEMENT
MARKINGS

55.00

55.00

S.Y.

64506 GEOTEXTILE FABRIC,
TYPE HR

50.00

100.00

L.F.

64601 SAWING EXISTING
PAVEMENT

3.00

3.00

EACH

90454 BEARING REPLACEMENT

5770-00-79
QUANTITY

TOTAL

UNIT

ITEM DESCRIPTION

ITEM

1.00

1.00

L.S.

90504 STRUCTURE
REPAINTING, ORGANIC
ZINC RICH SYSTEM,
STRUCTURE B-25-935

50.00

50.00

L.F.

90771 TEMPORARY PAVEMENT
MARKING, STOP LINE,
REMOVABLE TAPE,
24-INCH

Sheet 3.1