

PROJECT DESIGNATION	SHEET NO.
5953-01-71, 5770-00-79	3A
MISCELLANEOUS QUANTITIES	

DETAIL SUMMARY SHEET OF MISCELLANEOUS QUANTITIES

REMOVING ASPHALTIC SURFACE, BUTT JOINTS

PROJECT	STATION - STATION	LOCATION	S.Y.
5953-01-71	199+50 - 200+00	SOUTH APPROACH	135
5953-01-71	200+53 - 201+03	NORTH APPROACH	205
5770-00-79	199+50 - 200+00	SOUTH APPROACH	145
5770-00-79	200+26 - 200+76	NORTH APPROACH	145

UNCLASSIFIED EXCAVATION

PROJECT	STATION - STATION	LOCATION	S.Y.
5953-01-71	199+50 - 200+00	SOUTH APPROACH	25
5953-01-71	200+53 - 201+03	NORTH APPROACH	40
5770-00-79	199+50 - 200+00	SOUTH APPROACH	25
5770-00-79	200+26 - 200+76	NORTH APPROACH	25

CRUSHED AGGREGATE BASE COURSE

PROJECT	STATION - STATION	MAINLINE BASE (C.Y.)	SHOULDERS (C.Y.)
5953-01-71	199+50 - 200+00	13	2
5953-01-71	200+53 - 201+03	17	2
5770-00-79	199+50 - 200+00	14	1
5770-00-79	200+26 - 200+76	14	1

ASPHALTIC MATERIAL FOR TACK COAT AND ASPHALTIC SURFACE

PROJECT	STATION - STATION	LOCATION	TACK GAL	SURFACE TON
5953-01-71	199+50 - 200+00	SOUTH APPROACH	15	30
5953-01-71	200+53 - 201+03	NORTH APPROACH	20	40
5770-00-79	199+50 - 200+00	SOUTH APPROACH	20	25
5770-00-79	200+26 - 200+76	NORTH APPROACH	20	25

TEMPORARY PRECAST CONCRETE BARRIER

PROJECT	STATION - STATION	LOCATION	DELIVERED (L.F.)	INSTALLED (L.F.)
5953-01-71	198+75 - 201+75	MAINLINE	300	600

STEEL PLATE BEAM GUARD, CLASS "A"

PROJECT	STRUCTURE	LOCATION	ANCHORAGES	TOTAL (L.F.)
5770-00-79	B-25-934	77 L.F. AT EACH CORNER	4 STD.	308
5953-01-71	B-25-935	77 L.F. AT SE & SW COR. 50 L.F. AT NE & NW COR.	2 STD. } 2 TYPE I }	254

MOVING SIGNS, TYPE II

LOCATION	EACH
STRUCTURE B-25-934	4
UNDISTRIBUTED	6

WOOD POSTS, 4 X 4 IN. X 10 FT.

PROJECT	LOCATION	EACH
5953-01-71	B-25-935	4
5770-00-79	B-25-934	4

SIGNS, TYPE II, REFLECTIVE

PROJECT	LOCATION	W5-52 S.F.
5953-01-71	B-25-935	12
5770-00-79	B-25-934	12

TRAFFIC CONTROL

PROJECT	BARRICADES TYPE III (DAYS)	WARNING LIGHTS TYPE "A" (DAYS)	WARNING LIGHTS TYPE "C" (DAYS)	SIGNS (DAYS)
5953-01-71	130	910	1365	1365
5770-00-79	540	2430	2610	2610

PAVEMENT MARKING, EPOXY 4-INCH

PROJECT	STATION-STATION	LOCATION	DOUBLE YELLOW C (L.F.)
5953-01-71	198+75 - 201+75	MAINLINE	300
5770-00-79	199+12 - 201+12	MAINLINE	200

TEMPORARY PAVEMENT MARKING, REMOVABLE TAPE, 4-INCH

PROJECT	LOCATION	WHITE EDGE LINE (L.F.)
5953-01-71	MAINLINE	1200

REMOVING PAVEMENT MARKING

PROJECT	STATION TO STATION	LOCATION	L.F.
5953-01-71	198+75 - 201+75	MAINLINE	300

SAWING EXISTING PAVEMENT

PROJECT	STATION	LOCATION	L.F.
5953-01-71	199+50	MAINLINE	25
5953-01-71	201+03	MAINLINE	25
5770-00-79	199+50	MAINLINE	25
5770-00-79	200+76	MAINLINE	25

24" TEMPORARY PAVEMENT MARKING, STOP LINE, REMOVABLE TAPE

PROJECT	STATION	LOCATION	L.F.
5953-01-71	198+75	STAGE I / II	25
5953-01-71	201+75	STAGE I / II	25