

DATE 21DEC05

ESTIMATE OF QUANTITIES

5770-00-74

LINE NUMBER	ITEM	ITEM DESCRIPTION	UNIT	TOTAL	QUANTITY
0010	201.0105	CLEARING	STA	4.000	4.000
0020	201.0205	GRUBBING	STA	4.000	4.000
0030	203.0100	REMOVING SMALL PIPE CULVERTS	EACH	1.000	1.000
0040	203.0200	REMOVING OLD STRUCTURE (STATION) 01. 100+00	LS	1.000	1.000
0050	204.0165	REMOVING GUARDRAIL	LF	520.000	520.000
0060	205.0100	EXCAVATION COMMON	CY	640.000	640.000
0070	206.1000	EXCAVATION FOR STRUCTURES BRIDGES (STRUCTURE) 01. B-25-153	LS	1.000	1.000
0080	208.0100	BORROW	CY	1,960.000	1,960.000
0090	210.0100	BACKFILL STRUCTURE	CY	200.000	200.000
0100	213.0100	FINISHING ROADWAY (PROJECT) 01. 5770-00-74	EACH	1.000	1.000
0110	301.0100.S	QMP BASE AGGREGATE	TON	1,950.000	1,950.000
0120	305.0110	BASE AGGREGATE DENSE 3/4-INCH	TON	180.000	180.000
0130	305.0120	BASE AGGREGATE DENSE 1 1/4-INCH	TON	1,770.000	1,770.000
0140	416.0050	CONCRETE PAVEMENT APPROACH SLAB	SY	117.000	117.000
0150	416.1010	CONCRETE SURFACE DRAINS	CY	4.000	4.000
0160	455.0105	ASPHALTIC MATERIAL PG58-28	TON	35.000	35.000
0170	455.0605	TACK COAT	GAL	55.000	55.000
0180	460.1100	HMA PAVEMENT TYPE E-0.3	TON	595.000	595.000
0190	460.3000	QMP HMA MIXTURE	TON	595.000	595.000
0200	502.0100	CONCRETE MASONRY BRIDGES	CY	509.000	509.000
0210	502.0301.S	QMP CONCRETE STRUCTURES	CY	509.000	509.000
0220	502.0400.S	INCENTIVE STRENGTH CONCRETE STRUCTURES	DOL	5,090.000	5,090.000
0230	502.3200	PROTECTIVE SURFACE TREATMENT	SY	635.000	635.000
0240	505.0405	BAR STEEL REINFORCEMENT HS BRIDGES	LB	7,090.000	7,090.000
0250	505.0605	BAR STEEL REINFORCEMENT HS COATED BRIDGES	LB	69,745.000	69,745.000
0260	511.2105	PILING STEEL DELIVERED AND DRIVEN HP 10-INCH X 42 LB	LF	1,820.000	1,820.000
0270	516.0500	RUBBERIZED MEMBRANE WATERPROOFING	SY	17.000	17.000
0280	520.0118	CULVERT PIPE CLASS III 18-INCH	LF	72.000	72.000
0290	520.1018	APRON ENDWALLS FOR CULVERT PIPE 18-INCH	EACH	2.000	2.000
0300	522.0124	CULVERT PIPE REINFORCED CONCRETE CLASS III 24-INCH	LF	50.000	50.000
0310	522.1024	APRON ENDWALLS FOR CULVERT PIPE REINFORCED CONCRETE 24-INCH	EACH	2.000	2.000
0320	606.0100	RIPRAP LIGHT	CY	4.000	4.000
0330	606.0300	RIPRAP HEAVY	CY	220.000	220.000
0340	611.9800.S	PIPE GRATES	EACH	2.000	2.000
0350	612.0106	PIPE UNDERDRAIN 6-INCH	LF	84.000	84.000
0360	612.0206	PIPE UNDERDRAIN UNPERFORATED 6-INCH	LF	88.000	88.000
0370	614.0150	ANCHOR ASSEMBLIES FOR STEEL PLATE BEAM GUARD	EACH	4.000	4.000
0380	614.0200	STEEL THRIE BEAM STRUCTURE APPROACH	LF	84.000	84.000
0390	614.0305	STEEL PLATE BEAM GUARD CLASS A	LF	250.000	250.000
0400	614.0370	STEEL PLATE BEAM GUARD ENERGY ABSORBING TERMINAL	EACH	4.000	4.000
0410	614.0620.S	MARKER POSTS CULVERT END FLEXIBLE	EACH	2.000	2.000
0420	619.1000	MOBILIZATION	EACH	1.000	1.000
0430	625.0500	SALVAGED TOPSOIL	SY	3,020.000	3,020.000
0440	627.0200	MULCHING	SY	4,230.000	4,230.000
0450	628.1504	SILT FENCE	LF	1,940.000	1,940.000
0460	628.1520	SILT FENCE MAINTENANCE	LF	3,880.000	3,880.000

DATE 21DEC05

E S T I M A T E O F Q U A N T I T I E S

LINE	NUMBER	ITEM	ITEM DESCRIPTION	UNIT	TOTAL	QUANTITY
						5770-00-74
0470	628.1905	MOBILIZATIONS EROSION CONTROL	EACH	2.000	2.000	
0480	628.1910	MOBILIZATIONS EMERGENCY EROSION CONTROL	EACH	2.000	2.000	
0490	628.2004	EROSION MAT CLASS I TYPE B	SY	1,000.000	1,000.000	
0500	628.6005	TURBIDITY BARRIERS	SY	180.000	180.000	
0510	628.7504	TEMPORARY DITCH CHECKS	LF	75.000	75.000	
0520	629.0210	FERTILIZER TYPE B	CWT	5.000	5.000	
0530	630.0120	SEEDING MIXTURE NO. 20	LB	135.000	135.000	
0540	630.0200	SEEDING TEMPORARY	LB	135.000	135.000	
0550	634.0410	POSTS WOOD 4X4-INCH X 10-FT	EACH	6.000	6.000	
0560	637.0202	SIGNS REFLECTIVE TYPE II	SF	28.000	28.000	
0570	638.2602	REMOVING SIGNS TYPE II	EACH	10.000	10.000	
0580	638.3000	REMOVING SMALL SIGN SUPPORTS	EACH	10.000	10.000	
0590	642.5000	FIELD OFFICE TYPE B (PROJECT) 01. 5770-00-74	EACH	1.000	1.000	
0600	642.6000	FIELD LABORATORY (PROJECT) 01. 5770-00-74	EACH	1.000	1.000	
0610	643.0100	TRAFFIC CONTROL (PROJECT) 01. 5770-00-74	EACH	1.000	1.000	
0620	643.0420	TRAFFIC CONTROL BARRICADES TYPE III	DAYS	810.000	810.000	
0630	643.0705	TRAFFIC CONTROL WARNING LIGHTS TYPE A	DAYS	1,260.000	1,260.000	
0640	643.0900	TRAFFIC CONTROL SIGNS	DAYS	2,430.000	2,430.000	
0650	643.2000	TRAFFIC CONTROL DETOUR (PROJECT) 01. 5770-00-74	EACH	1.000	1.000	
0660	643.3000	TRAFFIC CONTROL DETOUR SIGNS	DAYS	4,635.000	4,635.000	
0670	645.0111	GEOTEXTILE FABRIC TYPE DF SCHEDULE A	SY	66.000	66.000	
0680	645.0120	GEOTEXTILE FABRIC TYPE HR	SY	435.000	435.000	
0690	645.0130	GEOTEXTILE FABRIC TYPE R	SY	18.000	18.000	
0700	646.0106	PAVEMENT MARKING EPOXY 4-INCH	LF	3,200.000	3,200.000	
0710	650.4500	CONSTRUCTION STAKING SUBGRADE	LF	650.000	650.000	
0720	650.5000	CONSTRUCTION STAKING BASE	LF	650.000	650.000	
0730	650.6500	CONSTRUCTION STAKING STRUCTURE LAYOUT (STRUCTURE) 01. B-25-153	LS	1.000	1.000	
0740	690.0100	SAWING EXISTING PAVEMENT	LF	44.000	44.000	