

3

DATE 12APR10		ESTIMATE OF QUANTITIES			
LINE					5573-03-61
NUMBER	ITEM	ITEM DESCRIPTION	UNIT	TOTAL	QUANTITY
0010	204.0165	REMOVING GUARDRAIL	LF	872.000	872.000
0020	204.9090.S	REMOVING (ITEM DESCRIPTION) 01. CONCRETE BARRIER	LF	110.000	110.000
0030	205.9006.S	GRADING SHAPING & FINISHING FOR BARRIER TERMINALS	EACH	14.000	14.000
0040	211.0100	PREPARE FOUNDATION FOR ASPHALTIC PAVING (PROJECT) 01. 5573-03-61	LS	1.000	1.000
0050	213.0100	FINISHING ROADWAY (PROJECT) 01. 5573-03-61	EACH	1.000	1.000
0060	305.0110	BASE AGGREGATE DENSE 3/4-INCH	TON	1,650.000	1,650.000
0070	305.0500	SHAPING SHOULDERS	STA	438.000	438.000
0080	415.2000.S	INCENTIVE STRENGTH CONCRETE PAVEMENT	DOL	500.000	500.000
0090	416.0050	CONCRETE PAVEMENT APPROACH SLAB	SY	98.000	98.000
0100	440.4410.S	INCENTIVE IRI RIDE	DOL	16,600.000	16,600.000
0110	455.0105	ASPHALTIC MATERIAL PG58-28	TON	500.000	500.000
0120	455.0605	TACK COAT	GAL	1,974.000	1,974.000
0130	460.1101	HMA PAVEMENT TYPE E-1	TON	9,070.000	9,070.000
0140	460.2000	INCENTIVE DENSITY HMA PAVEMENT	DOL	5,810.000	5,810.000
0150	601.0411	CONCRETE CURB & GUTTER 30-INCH TYPE D	LF	21.000	21.000
0160	614.0150	ANCHOR ASSEMBLIES FOR STEEL PLATE BEAM GUARD	EACH	2.000	2.000
0170	614.0200	STEEL THRIE BEAM STRUCTURE APPROACH	LF	126.000	126.000
0180	614.0305	STEEL PLATE BEAM GUARD CLASS A	LF	1,175.000	1,175.000
0190	614.0370	STEEL PLATE BEAM GUARD ENERGY ABSORBING TERMINAL	EACH	14.000	14.000
0200	618.0100	MAINTENANCE AND REPAIR OF HAUL ROADS (PROJECT) 01. 5573-03-61	EACH	1.000	1.000
0210	619.1000	MOBILIZATION	EACH	1.000	1.000
0220	634.0614	POSTS WOOD 4X6-INCH X 14-FT	EACH	23.000	23.000
0230	634.0616	POSTS WOOD 4X6-INCH X 16-FT	EACH	29.000	29.000
0240	634.0618	POSTS WOOD 4X6-INCH X 18-FT	EACH	3.000	3.000
0250	634.0808	POSTS TUBULAR STEEL 2X2-INCH X 8-FT	EACH	4.000	4.000
0260	637.0202	SIGNS REFLECTIVE TYPE II	SF	416.000	416.000
0270	638.2102	MOVING SIGNS TYPE II	EACH	1.000	1.000
0280	638.2602	REMOVING SIGNS TYPE II	EACH	82.000	82.000
0290	638.3000	REMOVING SMALL SIGN SUPPORTS	EACH	62.000	62.000
0300	642.5001	FIELD OFFICE TYPE B	EACH	1.000	1.000
0310	643.0100	TRAFFIC CONTROL (PROJECT) 01. 5573-03-61	EACH	1.000	1.000
0320	643.0300	TRAFFIC CONTROL DRUMS	DAYS	300.000	300.000
0330	643.0420	TRAFFIC CONTROL BARRICADES TYPE III	DAYS	10.000	10.000
0340	643.0715	TRAFFIC CONTROL WARNING LIGHTS TYPE C	DAYS	100.000	100.000
0350	643.0900	TRAFFIC CONTROL SIGNS	DAYS	900.000	900.000
0360	646.0106	PAVEMENT MARKING EPOXY 4-INCH	LF	43,772.000	43,772.000
0370	646.0406	PAVEMENT MARKING SAME DAY EPOXY 4-INCH	LF	29,158.000	29,158.000
0380	646.0600	REMOVING PAVEMENT MARKINGS	LF	255.000	255.000
0390	646.0790.S	REMOVING RAISED PAVEMENT MARKERS	EACH	25.000	25.000
0400	648.0100	LOCATING NO-PASSING ZONES	MI	4.150	4.150
0410	649.0400	TEMPORARY PAVEMENT MARKING REMOVABLE TAPE 4-INCH	LF	2,040.000	2,040.000
0420	649.1400	TEMPORARY PAVEMENT MARKING STOP LINE REMOVABLE TAPE 24-INCH	LF	24.000	24.000
0430	650.8000	CONSTRUCTION STAKING RESURFACING REFERENCE	LF	21,934.000	21,934.000
0440	650.9910	CONSTRUCTION STAKING SUPPLEMENTAL CONTROL (PROJECT) 01. 5573-03-61	LS	1.000	1.000

3

3

DATE 12APR10		ESTIMATE OF QUANTITIES			
LINE				5573-03-61	
NUMBER	ITEM	ITEM DESCRIPTION	UNIT	TOTAL	QUANTITY
0450	661.0100	TEMPORARY TRAFFIC SIGNALS FOR BRIDGES (STRUCTURE) 01. B-56-81	LS	1.000	1.000
0460	690.0150	SAWING ASPHALT	LF	254.000	254.000
0470	ASP.1T0A	ON-THE-JOB TRAINING APPRENTICE AT \$5.00/HR	HRS	150.000	150.000
0480	ASP.1T0G	ON-THE-JOB TRAINING GRADUATE AT \$5.00/HR	HRS	200.000	200.000
0490	SPV.0180	SPECIAL 01. REMOVING ASPHALTIC SURFACE MILLING SPECIAL	SY	77,228.000	77,228.000
	SPV.0105	SPECIAL 01. PAVING NOTCH	LS	1.000	1.000
	649.0100	TEMPORARY PAVEMENT MARKING, 4-INCH	LF	46,600.000	46,600.000

3