

3

| DATE 11JUL07 |        | ESTIMATE OF QUANTITIES |                                                                      |      |             | 5573-04-72  | 5573-04-82 |
|--------------|--------|------------------------|----------------------------------------------------------------------|------|-------------|-------------|------------|
| LINE         | NUMBER | ITEM                   | ITEM DESCRIPTION                                                     | UNIT | TOTAL       | QUANTITY    | QUANTITY   |
|              | 0010   | 108.4300               | RBC PROGRESS SCHEDULE                                                | EACH | 1.000       | 1.000       |            |
|              | 0020   | 201.0105               | CLEARING                                                             | STA  | 32.000      | 31.000      | 1.000      |
|              | 0030   | 201.0205               | GRUBBING                                                             | STA  | 32.000      | 31.000      | 1.000      |
|              | 0040   | 203.0100               | REMOVING SMALL PIPE CULVERTS                                         | EACH | 31.000      | 31.000      |            |
|              | 0050   | 203.0200               | REMOVING OLD STRUCTURE (STATION) 01.<br>191+80                       | LS   | 1.000       | 1.000       |            |
|              | 0080   | 204.0150               | REMOVING CURB & GUTTER **p**                                         | LF   | 419.000     | 419.000     |            |
|              | 0090   | 204.0155               | REMOVING CONCRETE SIDEWALK                                           | SY   | 548.000     | 453.000     | 95.000     |
|              | 0100   | 204.9060.S             | REMOVING (ITEM DESCRIPTION) 01. WEIGH<br>SCALE STA 105+21 RT         | EACH | 1.000       | 1.000       |            |
|              | 0120   | 205.0100               | EXCAVATION COMMON                                                    | CY   | 105,974.000 | 105,974.000 |            |
|              | 0130   | 205.0200               | EXCAVATION ROCK                                                      | CY   | 8,840.000   | 8,682.000   | 158.000    |
|              | 0150   | 209.0100               | BACKFILL GRANULAR                                                    | CY   | 300.000     |             | 300.000    |
|              | 0180   | 213.0100               | FINISHING ROADWAY (PROJECT) 02.<br>5573-04-72                        | EACH | 1.000       | 1.000       |            |
|              | 0190   | 301.0100.S             | QMP BASE AGGREGATE                                                   | TON  | 41,483.000  | 41,483.000  |            |
|              | 0200   | 305.0110               | BASE AGGREGATE DENSE 3/4-INCH                                        | TON  | 1,762.000   | 1,762.000   |            |
|              | 0210   | 305.0120               | BASE AGGREGATE DENSE 1 1/4-INCH                                      | TON  | 40,183.000  | 39,721.000  | 462.000    |
|              | 0220   | 306.0110               | SALVAGED ASPHALTIC PAVEMENT BASE                                     | TON  | 15,358.000  | 15,358.000  |            |
|              | 0230   | 312.0110               | SELECT CRUSHED MATERIAL                                              | TON  | 29,745.000  | 29,745.000  |            |
|              | 0250   | 416.0055               | CONCRETE PAVEMENT APPROACH SLAB HES                                  | SY   | 28.000      | 28.000      |            |
|              | 0260   | 416.0160               | CONCRETE DRIVEWAY 6-INCH                                             | SY   | 372.000     | 372.000     |            |
|              | 0270   | 416.1010               | CONCRETE SURFACE DRAINS                                              | CY   | 9.000       | 9.000       |            |
|              | 0280   | 440.4410.S             | INCENTIVE IRI RIDE                                                   | DOL  | 12,792.000  | 12,792.000  |            |
|              | 0290   | 455.0105               | ASPHALTIC MATERIAL PG58-28                                           | TON  | 8.300       |             | 8.300      |
|              | 0300   | 460.1101               | HMA PAVEMENT TYPE E-1                                                | TON  | 150.000     |             | 150.000    |
|              | 0310   | 460.1905.S             | WARRANTED HMA PAVEMENT MAINLINE                                      | TON  | 15,482.000  | 15,482.000  |            |
|              | 0320   | 460.1955.S             | WARRANTED HMA PAVEMENT ANCILLARY                                     | TON  | 3,340.000   | 3,340.000   |            |
|              | 0330   | 465.0315               | ASPHALTIC FLUMES                                                     | SY   | 81.000      | 81.000      |            |
|              | 0340   | 490.0100               | SALVAGED ASPHALTIC PAVEMENT **p**                                    | SY   | 49,227.000  | 49,227.000  |            |
|              | 0420   | 521.0118               | CULVERT PIPE CORRUGATED STEEL 18-INCH                                | LF   | 655.000     | 655.000     |            |
|              | 0430   | 521.0124               | CULVERT PIPE CORRUGATED STEEL 24-INCH                                | LF   | 107.000     | 107.000     |            |
|              | 0440   | 521.1518               | APRON ENDWALLS FOR CULVERT PIPE SLOPED<br>SECTION STEEL 18-INCH      | EACH | 28.000      | 28.000      |            |
|              | 0450   | 521.1524               | APRON ENDWALLS FOR CULVERT PIPE SLOPED<br>SECTION STEEL 24-INCH      | EACH | 4.000       | 4.000       |            |
|              | 0460   | 522.0124               | CULVERT PIPE REINFORCED CONCRETE CLASS<br>III 24-INCH                | LF   | 56.000      | 56.000      |            |
|              | 0470   | 522.0130               | CULVERT PIPE REINFORCED CONCRETE CLASS<br>III 30-INCH                | LF   | 80.000      | 80.000      |            |
|              | 0480   | 522.0136               | CULVERT PIPE REINFORCED CONCRETE CLASS<br>III 36-INCH                | LF   | 62.000      | 62.000      |            |
|              | 0490   | 522.0148               | CULVERT PIPE REINFORCED CONCRETE CLASS<br>III 48-INCH                | LF   | 116.000     | 116.000     |            |
|              | 0500   | 522.0160               | CULVERT PIPE REINFORCED CONCRETE CLASS<br>III 60-INCH                | LF   | 72.000      | 72.000      |            |
|              | 0510   | 522.1012               | APRON ENDWALLS FOR CULVERT PIPE<br>REINFORCED CONCRETE 12-INCH **p** | EACH | 3.000       | 3.000       |            |
|              | 0520   | 522.1015               | APRON ENDWALLS FOR CULVERT PIPE<br>REINFORCED CONCRETE 15-INCH **p** | EACH | 1.000       | 1.000       |            |
|              | 0530   | 522.1018               | APRON ENDWALLS FOR CULVERT PIPE<br>REINFORCED CONCRETE 18-INCH **p** | EACH | 1.000       | 1.000       |            |
|              | 0540   | 522.1021               | APRON ENDWALLS FOR CULVERT PIPE<br>REINFORCED CONCRETE 21-INCH **p** | EACH | 1.000       | 1.000       |            |
|              | 0550   | 522.1024               | APRON ENDWALLS FOR CULVERT PIPE<br>REINFORCED CONCRETE 24-INCH **p** | EACH | 2.000       | 2.000       |            |

3

3

| DATE 11JUL07   |            | ESTIMATE OF QUANTITIES                                                                         |      |           |                        | 5573-04-82<br>QUANTITY | 5573-04-82<br>QUANTITY |
|----------------|------------|------------------------------------------------------------------------------------------------|------|-----------|------------------------|------------------------|------------------------|
| LINE<br>NUMBER | ITEM       | ITEM DESCRIPTION                                                                               | UNIT | TOTAL     | 5573-04-72<br>QUANTITY |                        |                        |
| 0560           | 522.1030   | APRON ENDWALLS FOR CULVERT PIPE<br>REINFORCED CONCRETE 30-INCH ***                             | EACH | 2.000     | 2.000                  |                        |                        |
| 0570           | 522.1036   | APRON ENDWALLS FOR CULVERT PIPE<br>REINFORCED CONCRETE 36-INCH ***                             | EACH | 3.000     | 3.000                  |                        |                        |
| 0580           | 522.1048   | APRON ENDWALLS FOR CULVERT PIPE<br>REINFORCED CONCRETE 48-INCH ***                             | EACH | 4.000     | 4.000                  |                        |                        |
| 0590           | 522.1060   | APRON ENDWALLS FOR CULVERT PIPE<br>REINFORCED CONCRETE 60-INCH ***                             | EACH | 2.000     | 2.000                  |                        |                        |
| 0600           | 523.0519   | APRON ENDWALLS FOR CULVERT PIPE<br>REINFORCED CONCRETE HORIZONTAL<br>ELLIPTICAL 19X30-INCH *** | EACH | 2.000     | 2.000                  |                        |                        |
| 0610           | 532.0200.S | WALL MODULAR BLOCK GRAVITY                                                                     | SF   | 985.000   | 985.000                |                        |                        |
| 0630           | 601.0411   | CONCRETE CURB & GUTTER 30-INCH TYPE D<br>***                                                   | LF   | 4,476.000 | 4,476.000              |                        |                        |
| 0640           | 601.0554   | CONCRETE CURB & GUTTER 4-INCH MOUNTABLE<br>36-INCH TYPE D ***                                  | LF   | 4,194.000 | 4,194.000              |                        |                        |
| 0650           | 602.0405   | CONCRETE SIDEWALK 4-INCH                                                                       | SF   | 5,516.000 | 4,776.000              |                        | 740.000                |
| 0660           | 602.0415   | CONCRETE SIDEWALK 6-INCH                                                                       | SF   | 170.000   |                        |                        | 170.000                |
| 0670           | 602.0505   | CURB RAMP DETECTABLE WARNING FIELD<br>YELLOW                                                   | SF   | 56.000    | 56.000                 |                        |                        |
| 0680           | 606.0200   | RIPRAP MEDIUM                                                                                  | CY   | 55.000    | 55.000                 |                        |                        |
| 0690           | 606.0300   | RIPRAP HEAVY                                                                                   | CY   | 74.000    | 74.000                 |                        |                        |
| 0700           | 608.0312   | STORM SEWER PIPE REINFORCED CONCRETE<br>CLASS III 12-INCH ***                                  | LF   | 686.000   | 686.000                |                        |                        |
| 0710           | 608.0315   | STORM SEWER PIPE REINFORCED CONCRETE<br>CLASS III 15-INCH ***                                  | LF   | 201.000   | 201.000                |                        |                        |
| 0720           | 608.0318   | STORM SEWER PIPE REINFORCED CONCRETE<br>CLASS III 18-INCH ***                                  | LF   | 458.000   | 458.000                |                        |                        |
| 0730           | 608.0321   | STORM SEWER PIPE REINFORCED CONCRETE<br>CLASS III 21-INCH ***                                  | LF   | 82.000    | 82.000                 |                        |                        |
| 0740           | 608.0324   | STORM SEWER PIPE REINFORCED CONCRETE<br>CLASS III 24-INCH ***                                  | LF   | 854.000   | 854.000                |                        |                        |
| 0750           | 608.0330   | STORM SEWER PIPE REINFORCED CONCRETE<br>CLASS III 30-INCH ***                                  | LF   | 266.000   | 266.000                |                        |                        |
| 0760           | 608.0336   | STORM SEWER PIPE REINFORCED CONCRETE<br>CLASS III 36-INCH ***                                  | LF   | 45.000    | 45.000                 |                        |                        |
| 0770           | 610.0119   | STORM SEWER PIPE REINFORCED CONCRETE<br>HORIZONTAL ELLIPTICAL CLASS HE-III<br>19X30-INCH ***   | LF   | 73.000    | 73.000                 |                        |                        |
| 0780           | 611.0201   | MANHOLES TYPE 1 ***                                                                            | EACH | 7.000     | 7.000                  |                        |                        |
| 0790           | 611.0210   | MANHOLES TYPE 3 ***                                                                            | EACH | 7.000     | 7.000                  |                        |                        |
| 0800           | 611.0303   | INLETS TYPE 3 ***                                                                              | EACH | 26.000    | 26.000                 |                        |                        |
| 0810           | 611.0305   | INLETS TYPE 8 ***                                                                              | EACH | 1.000     | 1.000                  |                        |                        |
| 0820           | 611.0530   | MANHOLE COVERS TYPE J ***                                                                      | EACH | 7.000     | 7.000                  |                        |                        |
| 0830           | 611.0612   | INLET COVERS TYPE C ***                                                                        | EACH | 1.000     | 1.000                  |                        |                        |
| 0840           | 611.0624   | INLET COVERS TYPE H ***                                                                        | EACH | 20.000    | 20.000                 |                        |                        |
| 0850           | 611.0627   | INLET COVERS TYPE HM ***                                                                       | EACH | 10.000    | 10.000                 |                        |                        |
| 0860           | 611.0642   | INLET COVERS TYPE MS ***                                                                       | EACH | 1.000     | 1.000                  |                        |                        |
| 0870           | 611.8110   | ADJUSTING MANHOLE COVERS                                                                       | EACH | 8.000     | 8.000                  |                        |                        |
| 0880           | 611.9800.S | PIPE GRATES 01. 15" STORM SEWER                                                                | EACH | 2.000     | 2.000                  |                        |                        |
| 0890           | 611.9800.S | PIPE GRATES 02. 18" STORM SEWER                                                                | EACH | 1.000     | 1.000                  |                        |                        |
| 0900           | 611.9800.S | PIPE GRATES 03. 36" STORM SEWER                                                                | EACH | 1.000     | 1.000                  |                        |                        |
| 0910           | 611.9800.S | PIPE GRATES 04. 19"X30" STORM SEWER                                                            | EACH | 2.000     | 2.000                  |                        |                        |
| 0940           | 614.0305   | STEEL PLATE BEAM GUARD CLASS A                                                                 | LF   | 1,775.000 | 1,775.000              |                        |                        |
| 0950           | 614.0370   | STEEL PLATE BEAM GUARD ENERGY ABSORBING<br>TERMINAL                                            | EACH | 7.000     | 7.000                  |                        |                        |
| 0960           | 614.0555   | SALVAGED GUARD FENCE STEEL BEAM                                                                | LF   | 21.000    | 21.000                 |                        |                        |

3



3

| DATE 11JUL07 |            | ESTIMATE OF QUANTITIES                                                   |      |             | 5573-04-72  | 5573-04-82 |
|--------------|------------|--------------------------------------------------------------------------|------|-------------|-------------|------------|
| LINE         | ITEM       | ITEM DESCRIPTION                                                         | UNIT | TOTAL       | QUANTITY    | QUANTITY   |
| 0970         | 614.0605   | MARKER POSTS RIGHT-OF-WAY                                                | EACH | 239.000     | 239.000     |            |
| 0980         | 614.0620.S | MARKER POSTS CULVERT END FLEXIBLE                                        | EACH | 12.000      | 12.000      |            |
| 0990         | 616.0204   | FENCE CHAIN LINK 4-FT                                                    | LF   | 285.000     | 285.000     |            |
| 1000         | 616.0700.S | FENCE SAFETY                                                             | LF   | 300.000     | 300.000     |            |
| 1010         | 618.0100   | MAINTENANCE AND REPAIR OF HAUL ROADS<br>(PROJECT) 02. 5573-04-72         | EACH | 1.000       | 1.000       |            |
| 1020         | 619.1000   | MOBILIZATION                                                             | EACH | 0.750       | 0.500       | 0.250      |
| 1030         | 621.0100   | LANDMARK REFERENCE MONUMENTS                                             | EACH | 1.000       | 1.000       |            |
| 1040         | 624.0100   | WATER                                                                    | MGAL | 360.000     | 360.000     |            |
| 1050         | 625.0100   | TOPSOIL                                                                  | SY   | 566.000     |             | 566.000    |
| 1060         | 625.0500   | SALVAGED TOPSOIL                                                         | SY   | 87,855.000  | 87,855.000  |            |
| 1070         | 627.0200   | MULCHING                                                                 | SY   | 109,421.000 | 108,855.000 | 566.000    |
| 1080         | 628.1504   | SILT FENCE                                                               | LF   | 14,915.000  | 14,915.000  |            |
| 1090         | 628.1520   | SILT FENCE MAINTENANCE                                                   | LF   | 29,830.000  | 29,830.000  |            |
| 1100         | 628.1905   | MOBILIZATIONS EROSION CONTROL                                            | EACH | 5.000       | 5.000       |            |
| 1110         | 628.1910   | MOBILIZATIONS EMERGENCY EROSION CONTROL                                  | EACH | 7.000       | 7.000       |            |
| 1120         | 628.2004   | EROSION MAT CLASS I TYPE B                                               | SY   | 9,908.000   | 9,908.000   |            |
| 1140         | 628.2023   | EROSION MAT CLASS II TYPE B                                              | SY   | 15,764.000  | 15,764.000  |            |
| 1150         | 628.2037   | EROSION MAT CLASS III TYPE C                                             | SY   | 4,158.000   | 4,158.000   |            |
| 1160         | 628.7005   | INLET PROTECTION TYPE A                                                  | EACH | 41.000      | 41.000      |            |
| 1170         | 628.7010   | INLET PROTECTION TYPE B                                                  | EACH | 2.000       | 2.000       |            |
| 1180         | 628.7015   | INLET PROTECTION TYPE C                                                  | EACH | 37.000      | 37.000      |            |
| 1190         | 628.7504   | TEMPORARY DITCH CHECKS                                                   | LF   | 722.000     | 722.000     |            |
| 1200         | 628.7560.S | STONE OR ROCK DITCH CHECKS                                               | CY   | 10.000      | 10.000      |            |
| 1210         | 629.0210   | FERTILIZER TYPE B                                                        | CWT  | 69.360      | 69.000      | 0.360      |
| 1220         | 630.0130   | SEEDING MIXTURE NO. 30                                                   | LB   | 1,960.000   | 1,960.000   |            |
| 1230         | 630.0140   | SEEDING MIXTURE NO. 40                                                   | LB   | 70.400      | 50.000      | 20.400     |
| 1250         | 630.0200   | SEEDING TEMPORARY                                                        | LB   | 2,954.000   | 2,939.000   | 15.000     |
| 1260         | 631.0300   | SOD WATER                                                                | MGAL | 70.000      | 70.000      |            |
| 1270         | 631.1000   | SOD LAWN                                                                 | SY   | 12,441.000  | 12,441.000  |            |
| 1290         | 634.0616   | POSTS WOOD 4X6-INCH X 16-FT                                              | EACH | 36.000      | 36.000      |            |
| 1300         | 634.0618   | POSTS WOOD 4X6-INCH X 18-FT                                              | EACH | 25.000      | 25.000      |            |
| 1310         | 637.0202   | SIGNS REFLECTIVE TYPE II **p**                                           | SF   | 443.000     | 443.000     |            |
| 1320         | 638.2102   | MOVING SIGNS TYPE II **p**                                               | EACH | 8.000       | 8.000       |            |
| 1330         | 638.2602   | REMOVING SIGNS TYPE II **p**                                             | EACH | 88.000      | 88.000      |            |
| 1340         | 638.3000   | REMOVING SMALL SIGN SUPPORTS **p**                                       | EACH | 61.000      | 61.000      |            |
| 1350         | 642.5201   | FIELD OFFICE TYPE C                                                      | EACH | 0.750       | 0.500       | 0.250      |
| 1370         | 643.0200   | TRAFFIC CONTROL SURVEILLANCE AND<br>MAINTENANCE (PROJECT) 02. 5573-04-72 | DAYS | 166.000     | 166.000     |            |
| 1380         | 643.0300   | TRAFFIC CONTROL DRUMS                                                    | DAYS | 2,250.000   | 2,250.000   |            |
| 1390         | 643.0420   | TRAFFIC CONTROL BARRICADES TYPE III                                      | DAYS | 7,968.000   | 7,968.000   |            |
| 1400         | 643.0705   | TRAFFIC CONTROL WARNING LIGHTS TYPE A                                    | DAYS | 15,272.000  | 15,272.000  |            |
| 1410         | 643.0715   | TRAFFIC CONTROL WARNING LIGHTS TYPE C                                    | DAYS | 2,250.000   | 2,250.000   |            |
| 1420         | 643.0900   | TRAFFIC CONTROL SIGNS                                                    | DAYS | 14,276.000  | 14,276.000  |            |
| 1430         | 643.0905.S | TRAFFIC CONTROL COVERING SIGNS                                           | EACH | 22.000      | 22.000      |            |
| 1440         | 643.3000   | TRAFFIC CONTROL DETOUR SIGNS                                             | DAYS | 19,090.000  | 19,090.000  |            |
| 1460         | 645.0120   | GEOTEXTILE FABRIC TYPE HR                                                | SY   | 111.000     | 111.000     |            |
| 1470         | 645.0130   | GEOTEXTILE FABRIC TYPE R                                                 | SY   | 144.000     | 144.000     |            |
| 1480         | 646.0106   | PAVEMENT MARKING EPOXY 4-INCH                                            | LF   | 64,129.000  | 64,129.000  |            |
| 1490         | 647.0110   | PAVEMENT MARKING RAILROAD CROSSINGS<br>EPOXY **p**                       | EACH | 2.000       | 2.000       |            |
| 1500         | 647.0566   | PAVEMENT MARKING STOP LINE EPOXY 18-INCH                                 | LF   | 162.000     | 162.000     |            |
| 1510         | 647.0766   | PAVEMENT MARKING CROSSWALK EPOXY 6-INCH                                  | LF   | 240.000     | 240.000     |            |
| 1520         | 648.0100   | LOCATING NO-PASSING ZONES **p**                                          | MI   | 3.800       | 3.800       |            |

3

3

| DATE 11JUL07 |        | E S T I M A T E O F Q U A N T I T I E S |                                                       |      |            | 5573-04-82             |           |
|--------------|--------|-----------------------------------------|-------------------------------------------------------|------|------------|------------------------|-----------|
| LINE         | NUMBER | ITEM                                    | ITEM DESCRIPTION                                      | UNIT | TOTAL      | 5573-04-72<br>QUANTITY | QUANTITY  |
|              | 1530   | 650.4000                                | CONSTRUCTION STAKING STORM SEWER SYSTEM               | EACH | 49.000     | 49.000                 |           |
|              | 1540   | 650.4500                                | CONSTRUCTION STAKING SUBGRADE                         | LF   | 18,167.000 | 18,167.000             |           |
|              | 1550   | 650.5000                                | CONSTRUCTION STAKING BASE                             | LF   | 18,467.000 | 18,467.000             |           |
|              | 1560   | 650.5500                                | CONSTRUCTION STAKING CURB GUTTER AND<br>CURB & GUTTER | LF   | 8,927.000  | 8,927.000              |           |
|              | 1570   | 650.6000                                | CONSTRUCTION STAKING PIPE CULVERTS                    | EACH | 6.000      | 6.000                  |           |
|              | 1590   | 690.0100                                | SAWING EXISTING PAVEMENT                              | LF   | 1,227.000  | 1,227.000              |           |
|              | 1600   | 690.0200                                | SAWING CONCRETE PAVEMENT FULL DEPTH                   | LF   | 84.000     | 84.000                 |           |
|              | 1630   | SPV.0060                                | SPECIAL 01. 8-INCH WATER VALVE AND BOX                | EACH | 8.000      |                        | 8.000     |
|              | 1640   | SPV.0060                                | SPECIAL 02. 6-INCH WATER VALVE AND BOX                | EACH | 12.000     |                        | 12.000    |
|              | 1650   | SPV.0060                                | SPECIAL 03. FIRE HYDRANT                              | EACH | 6.000      |                        | 6.000     |
|              | 1660   | SPV.0060                                | SPECIAL 04. SALVAGE AND REINSTALL<br>EXISTING HYDRANT | EACH | 1.000      |                        | 1.000     |
|              | 1670   | SPV.0060                                | SPECIAL 05. 8-INCH X 6-INCH TEE                       | EACH | 9.000      |                        | 9.000     |
|              | 1680   | SPV.0060                                | SPECIAL 06. 6-INCH X 6-INCH TEE                       | EACH | 1.000      |                        | 1.000     |
|              | 1690   | SPV.0060                                | SPECIAL 07. 8-INCH X 8-INCH TEE                       | EACH | 4.000      |                        | 4.000     |
|              | 1700   | SPV.0060                                | SPECIAL 08. 6-INCH PLUG                               | EACH | 2.000      |                        | 2.000     |
|              | 1710   | SPV.0060                                | SPECIAL 09. 8-INCH X 6-INCH REDUCER                   | EACH | 6.000      |                        | 6.000     |
|              | 1720   | SPV.0060                                | SPECIAL 10. CONNECT TO EXISTING WATER<br>MAIN         | EACH | 9.000      |                        | 9.000     |
|              | 1730   | SPV.0060                                | SPECIAL 11. REMOVE FIRE HYDRANT                       | EACH | 3.000      |                        | 3.000     |
|              | 1740   | SPV.0060                                | SPECIAL 12. ADJUST EXISTING VALVE BOX                 | EACH | 1.000      |                        | 1.000     |
|              | 1750   | SPV.0060                                | SPECIAL 13. VALVE MANHOLE                             | EACH | 1.000      |                        | 1.000     |
|              | 1760   | SPV.0060                                | SPECIAL 14. CORPORATION, CURB STOP AND<br>BOX 2-INCH  | EACH | 1.000      |                        | 1.000     |
|              | 1770   | SPV.0060                                | SPECIAL 15. CORPORATION, CURB STOP AND<br>BOX 1-INCH  | EACH | 25.000     |                        | 25.000    |
|              | 1780   | SPV.0060                                | SPECIAL 16. SANITARY SEWER WYE 8 X 4<br>INCH          | EACH | 9.000      |                        | 9.000     |
|              | 1790   | SPV.0060                                | SPECIAL 17. SANITARY MANHOLE                          | EACH | 7.000      |                        | 7.000     |
|              | 1800   | SPV.0060                                | SPECIAL 18. ADJUST SANITARY MANHOLE                   | EACH | 2.000      |                        | 2.000     |
|              | 1810   | SPV.0060                                | SPECIAL 19. CONNECT TO EXISTING MANHOLE               | EACH | 3.000      |                        | 3.000     |
|              | 1820   | SPV.0060                                | SPECIAL 20. MANHOLE FRAME, LID AND<br>CHIMNEY SEAL    | EACH | 4.000      |                        | 4.000     |
|              | 1830   | SPV.0090                                | SPECIAL 01. BORE & JACK 30-INCH STORM<br>SEWER        | LF   | 90.000     | 90.000                 |           |
|              | 1840   | SPV.0090                                | SPECIAL 02. WATER MAIN 8-INCH                         | LF   | 2,243.000  |                        | 2,243.000 |
|              | 1850   | SPV.0090                                | SPECIAL 03. WATER MAIN, RESTRAINED<br>JOINT 8-INCH    | LF   | 110.000    |                        | 110.000   |
|              | 1860   | SPV.0090                                | SPECIAL 04. WATER MAIN 6-INCH                         | LF   | 468.000    |                        | 468.000   |
|              | 1870   | SPV.0090                                | SPECIAL 05. STEEL CASING PIPE, 18-INCH                | LF   | 64.000     |                        | 64.000    |
|              | 1880   | SPV.0090                                | SPECIAL 06. WATER SERVICE COPPER 2-INCH               | LF   | 22.000     |                        | 22.000    |
|              | 1890   | SPV.0090                                | SPECIAL 07. WATER SERVICE COPPER 1-INCH               | LF   | 840.000    |                        | 840.000   |
|              | 1900   | SPV.0090                                | SPECIAL 08. SANITARY SEWER LATERAL<br>4-INCH          | LF   | 284.000    |                        | 284.000   |
|              | 1910   | SPV.0090                                | SPECIAL 09. SANITARY SEWER MAIN 8-INCH                | LF   | 1,000.000  |                        | 1,000.000 |
|              | 1920   | SPV.0165                                | SPECIAL 01. POLYSTYRENE INSULATION                    | SF   | 320.000    |                        | 320.000   |
|              | 1930   | SPV.0170                                | SPECIAL 01. TEST ROLLING                              | STA  | 169.000    | 169.000                |           |
|              | 1940   | SPV.0180                                | SPECIAL 01. SALVAGED TOPSOIL SPECIAL                  | SY   | 630.000    | 630.000                |           |

3