

EARTHWORK SUMMARY FOR STH 136

STATION	AREA (SF)			Incremental Vol (CY)			Cumulative Vol (CY)			
	Common	Fill	Rock Exc	Common	Fill	Rock Exc	Common	Fill	Rock	Mass Haul
102+00.0000	55.0	0.2	0.0							
102+50.0000	56.3	5.3	0.0	103.0	5.1	0.0	103.0	6.4	0.0	96.7
102+70.0000	64.5	5.4	0.0	44.7	4.0	0.0	147.8	11.3	0.0	136.4
103+00.0000	66.1	0.0	0.0	72.6	3.0	0.0	220.3	15.1	0.0	205.2
103+50.0000	48.2	0.3	0.0	105.8	0.3	0.0	326.1	15.5	0.0	310.7
104+50.0000	56.3	2.2	0.0	193.4	4.5	0.0	519.5	21.1	0.0	498.4
104+79.0000	75.9	10.0	0.0	71.0	6.6	0.0	590.5	29.3	0.0	561.2
105+00.0000	74.7	3.5	0.0	58.6	5.3	0.0	649.1	35.9	0.0	613.1
105+21.0000	75.3	4.0	0.0	58.4	2.9	0.0	707.4	39.6	0.0	667.8
105+50.0000	61.0	7.7	0.0	73.2	6.3	0.0	780.6	47.4	0.0	733.2
106+00.0000	64.4	5.9	0.0	116.1	12.6	0.0	896.8	63.2	0.0	833.6
106+48.0000	73.0	1.0	0.0	122.1	6.2	0.0	1018.9	70.9	0.0	948.0
107+00.0000	76.5	0.9	0.0	143.9	1.9	0.0	1162.8	73.3	0.0	1089.5
107+16.0000	75.0	0.8	0.0	44.9	0.5	0.0	1207.7	73.9	0.0	1133.8
107+50.0000	74.6	2.0	0.0	94.2	1.7	0.0	1301.9	76.1	0.0	1225.6
108+00.0000	101.9	0.0	0.0	163.4	1.9	0.0	1465.3	78.4	0.0	1386.9
108+49.0000	78.1	0.0	0.0	163.4	0.0	0.0	1628.7	78.4	0.0	1550.3
108+67.0000	77.4	0.0	0.0	51.8	0.0	0.0	1680.5	78.4	0.0	1602.1
109+00.0000	72.4	0.0	0.0	91.5	0.0	0.0	1772.1	78.4	0.0	1693.6
109+39.0000	71.3	0.0	0.0	103.8	0.0	0.0	1875.9	78.4	0.0	1797.5
109+50.0000	76.7	0.0	0.0	30.1	0.0	0.0	1906.0	78.4	0.0	1827.6
110+00.0000	101.3	0.0	0.0	164.8	0.0	0.0	2070.9	78.4	0.0	1992.4
110+31.0000	104.6	0.0	0.0	118.2	0.0	0.0	2189.1	78.4	0.0	2110.7
110+37.2400	96.5	0.0	0.0	23.2	0.0	0.0	2212.4	78.4	0.0	2133.9
110+80.0000	106.7	0.0	0.0	160.9	0.0	0.0	2373.3	78.4	0.0	2294.8
111+00.0000	93.4	0.0	0.0	74.1	0.0	0.0	2447.4	78.4	0.0	2368.9
111+30.0000	81.0	0.0	0.0	96.9	0.0	0.0	2544.2	78.4	0.0	2465.8
111+36.0000	82.8	1.4	0.0	18.2	0.2	0.0	2562.4	78.6	0.0	2483.8
111+50.0000	73.8	2.6	0.0	40.6	1.0	0.0	2603.0	79.9	0.0	2523.1
111+67.0000	70.6	2.2	0.0	45.5	1.5	0.0	2648.5	81.8	0.0	2566.7
112+00.0000	62.5	4.7	0.0	81.3	4.2	0.0	2729.8	87.1	0.0	2642.8
112+50.0000	53.0	3.3	0.0	106.9	7.4	0.0	2836.7	96.3	0.0	2740.4
113+05.0000	46.9	14.8	0.0	101.7	18.4	0.0	2938.4	119.3	0.0	2819.2
113+50.0000	57.8	7.2	0.0	87.2	18.3	0.0	3025.7	142.2	0.0	2883.5
114+00.0000	63.0	8.7	0.0	111.8	14.8	0.0	3137.5	160.7	0.0	2976.8
114+50.0000	73.1	7.6	0.0	126.0	15.1	0.0	3263.5	179.6	0.0	3083.9
114+85.0000	77.5	3.8	0.0	97.6	7.4	0.0	3361.1	188.8	0.0	3172.3
115+00.0000	54.3	12.0	0.0	36.6	4.4	0.0	3397.7	194.2	0.0	3203.4
115+50.0000	67.3	7.2	0.0	112.5	17.8	0.0	3510.2	216.5	0.0	3293.8
116+00.0000	69.8	4.6	0.0	126.9	10.9	0.0	3637.1	230.1	0.0	3407.0
116+52.0000	45.5	20.7	0.0	111.0	24.4	0.0	3748.1	260.6	0.0	3487.5
117+00.0000	36.1	4.8	0.0	72.5	22.7	0.0	3820.7	288.9	0.0	3531.7
117+27.0000	38.1	6.5	0.0	37.1	5.6	0.0	3857.7	295.9	0.0	3561.8
117+50.0000	39.7	0.0	0.0	33.1	2.8	0.0	3890.9	299.4	0.0	3591.5
118+00.0000	36.3	30.1	0.0	70.4	27.8	0.0	3961.3	334.2	0.0	3627.1
118+50.0000	40.9	11.3	0.0	71.5	38.3	0.0	4032.8	382.1	0.0	3650.6
118+59.0000	40.5	13.4	0.0	13.6	4.1	0.0	4046.3	387.3	0.0	3659.0
118+84.0000	49.4	6.7	0.0	41.6	9.3	0.0	4087.9	398.9	0.0	3669.0
119+00.0000	35.4	5.8	0.0	25.1	3.7	0.0	4113.1	403.5	0.0	3709.6
119+50.0000	42.6	6.8	0.0	72.2	11.6	0.0	4185.3	418.0	0.0	3767.3
120+05.0000	62.9	3.3	0.0	107.4	10.2	0.0	4292.7	430.8	0.0	3861.3
121+00.0000	106.0	0.0	15.9	297.0	5.7	28.0	4589.7	437.9	28.0	4151.8

EARTHWORK SUMMARY FOR STH 136

STATION	AREA (SF)			Incremental Vol (CY)			Cumulative Vol (CY)			
	Common	Fill	Rock Exc	Common	Fill	Rock Exc	Common	Fill	Rock	Mass Haul
122+00.0000	89.5	2.5	0.5	362.0	4.6	30.3	4951.7	443.7	58.3	4508.0
123+00.0000	124.6	0.0	0.0	396.5	4.6	0.9	5348.2	449.4	59.2	4898.8
123+50.0000	101.5	0.0	0.0	209.4	0.0	0.0	5557.5	449.4	59.2	5108.1
124+00.0000	100.5	0.0	0.0	187.0	0.0	0.0	5744.6	449.4	59.2	5295.2
125+00.0000	95.3	0.1	0.0	362.6	0.2	0.0	6107.1	449.7	59.2	5657.4
125+50.0000	93.0	0.5	0.0	174.3	0.6	0.0	6281.5	450.5	59.2	5831.0
126+00.0000	108.7	0.0	0.0	186.8	0.5	0.0	6468.2	451.1	59.2	6017.2
126+77.0000	62.8	0.0	0.0	244.6	0.0	0.0	6712.8	451.1	59.2	6261.7
127+00.0000	76.2	0.0	0.0	59.2	0.0	0.0	6772.1	451.1	59.2	6321.0
128+00.0000	81.6	0.0	0.0	292.3	0.0	0.0	7064.3	451.1	59.2	6613.2
129+00.0000	87.5	0.0	0.0	313.1	0.0	0.0	7377.4	451.1	59.2	6926.3
129+24.0000	54.0	0.0	0.0	62.9	0.0	0.0	7440.2	451.1	59.2	6989.2
129+74.0000	92.1	0.0	0.0	135.3	0.0	0.0	7575.5	451.1	59.2	7124.4
130+00.0000	98.1	0.0	0.0	91.6	0.0	0.0	7667.1	451.1	59.2	7216.0
131+00.0000	139.2	0.0	0.0	439.5	0.0	0.0	8106.6	451.1	59.2	7655.5
132+00.0000	177.4	0.0	0.0	586.3	0.0	0.0	8692.9	451.1	59.2	8241.8
132+12.0000	123.3	9.5	0.0	66.8	2.1	0.0	8759.7	453.7	59.2	8306.0
133+00.0000	205.1	0.0	0.0	535.1	15.4	0.0	9294.8	473.0	59.2	8821.8
134+00.0000	176.8	0.0	0.0	707.2	0.0	0.0	10002.0	473.0	59.2	9529.0
135+00.0000	180.6	0.0	0.0	661.9	0.0	0.0	10663.9	473.0	59.2	10190.9
136+00.0000	153.6	0.0	0.0	618.9	0.0	0.0	11282.7	473.0	59.2	10809.7
137+00.0000	177.8	0.0	0.0	613.6	0.0	0.0	11896.3	473.0	59.2	11423.3
137+38.0000	308.9	0.0	0.0	342.5	0.0	0.0	12238.8	473.0	59.2	11765.8
137+41.0000	161.9	0.0	0.0	26.2	0.0	0.0	12265.0	473.0	59.2	11792.0
138+00.0000	201.6	0.0	0.0	397.1	0.0	0.0	12662.1	473.0	59.2	12189.1
139+00.0000	305.1	0.0	14.3	938.4	0.1	26.5	13600.5	473.1	85.7	13127.4
140+00.0000	269.6	0.0	124.1	1064.3	0.0	256.2	14664.7	473.1	341.9	14191.7
141+00.0000	319.4	0.0	0.0	1090.6	0.0	229.7	15755.3	473.1	571.7	15282.3
141+17.0000	353.3	0.0	0.0	211.8	0.0	0.0	15967.1	473.1	571.7	15494.0
142+00.0000	311.1	0.0	0.0	1021.3	0.0	0.0	16988.4	473.1	571.7	16515.3
143+00.0000	168.2	0.5	0.0	887.6	1.0	0.0	17876.0	474.3	571.7	17401.8
144+00.0000	114.7	57.9	0.0	524.0	108.3	0.0	18400.0	609.6	571.7	17790.4
145+00.0000	123.5	0.0	0.0	441.2	107.3	0.0	18841.2	743.7	571.7	18097.5
145+61.0000	140.8	7.7	0.0	298.5	8.7	0.0	19139.8	754.6	571.7	18385.2
146+00.0000	149.7	0.0	0.0	209.8	5.5	0.0	19349.5	761.5	571.7	18588.0
146+15.0000	151.1	2.7	0.0	83.5	0.8	0.0	19433.1	762.4	571.7	18670.6
147+00.0000	137.7	6.9	0.0	454.6	15.2	0.0	19887.6	781.5	571.7	19106.1
148+00.0000	97.4	30.2	0.0	435.4	68.7	0.0	20323.0	867.4	571.7	19455.6
149+00.0000	79.4	44.8	0.0	327.4	138.9	0.0	20650.4	1041.0	571.7	19609.4
150+00.0000	106.5	21.2	0.0	344.3	122.2	0.0	20994.7	1193.8	571.7	19800.9
150+38.0000	80.8	12.3	0.0	131.8	23.5	0.0	21126.5	1223.2	571.7	19903.3
151+00.0000	172.5	0.0	0.0	290.8	14.1	0.0	21417.4	1240.8	571.7	20176.6
152+00.0000	449.6	0.0	12.6	1152.1	0.0	23.3	22569.5	1240.8	594.9	21328.7
153+00.0000	307.3	0.0	0.0	1401.7	0.0	23.3	23971.1	1240.8	618.2	22730.3
154+00.0000	67.2	26.3	0.0	693.4	48.8	0.0	24664.6	1301.8	618.2	23362.7
155+00.0000	22.4	243.9	0.0	165.9	500.5	0.0	24830.4	1927.5	618.2	22902.9
156+00.0000	33.6	446.0	0.0	103.6	1277.7	0.0	24934.0	3524.6	618.2	21409.5
157+00.0000	21.3	365.8	0.0	101.7	1503.5	0.0	25035.7	5403.9	618.2	19631.8
157+77.0000	27.6	302.7	0.0	69.7	953.3	0.0	25105.4	6595.5	618.2	18509.9
158+00.0000	0.0	151.6	0.0	11.7	193.5	0.0	25117.2	6837.4	618.2	18279.8
158+66.0000	150.1	0.0	0.0	183.4	185.3	0.0	25300.6	7069.0	618.2	18231.6
159+00.0000	321.1	0.0	114.5	296.7	0.0	72.1	25597.3	7069.0	690.3	18528.3

EARTHWORK SUMMARY FOR STH 136

STATION	AREA (SF)			Incremental Vol (CY)			Cumulative Vol (CY)			
	Common	Fill	Rock Exc	Common	Fill	Rock Exc	Common	Fill	Rock	Mass Haul
160+00.0000	807.3	0.0	38.4	2089.6	0.0	283.1	27686.9	7069.0	973.4	20617.9
161+00.0000	377.9	0.0	530.1	2194.7	0.0	1052.6	29881.7	7069.0	2026.0	22812.7
162+00.0000	201.3	0.0	574.5	1072.6	0.0	2045.5	30954.2	7069.0	4071.5	23885.2
163+00.0000	392.0	0.0	0.0	1098.8	0.0	1063.9	32053.0	7069.0	5135.4	24984.0
164+00.0000	257.3	2.7	0.0	1202.5	5.0	0.0	33255.5	7075.3	5135.4	26180.2
165+00.0000	156.6	5.1	0.0	766.6	14.5	0.0	34022.1	7093.4	5135.4	26928.7
165+43.0000	31.4	6.2	0.0	149.7	9.0	0.0	34171.8	7104.6	5135.4	27067.2
166+00.0000	32.3	4.8	0.0	67.2	11.6	0.0	34239.0	7119.1	5135.4	27119.9
167+00.0000	32.1	11.6	0.0	119.3	30.4	0.0	34358.3	7157.1	5135.4	27201.2
167+76.0000	49.9	67.7	0.0	115.3	111.6	0.0	34473.6	7296.6	5135.4	27177.0
168+00.0000	47.5	15.0	0.0	43.3	36.8	0.0	34516.9	7342.6	5135.4	27174.3
169+00.0000	141.8	0.0	0.0	350.6	27.8	0.0	34867.5	7377.4	5135.4	27490.1
169+79.0000	106.3	0.0	0.0	363.0	0.0	0.0	35230.5	7377.4	5135.4	27853.2
170+00.0000	183.8	0.0	0.0	112.8	0.0	0.0	35343.4	7377.4	5135.4	27966.0
171+00.0000	158.5	0.0	0.0	633.9	0.0	0.0	35977.3	7377.4	5135.4	28599.9
172+00.0000	152.7	0.7	0.0	576.3	1.3	0.0	36553.6	7379.0	5135.4	29174.6
173+00.0000	158.1	1.5	0.0	575.5	4.2	0.0	37129.1	7384.2	5135.4	29744.9
174+00.0000	195.0	5.8	0.0	653.9	13.7	0.0	37782.9	7401.3	5135.4	30381.6
175+00.0000	181.4	10.1	0.0	697.1	29.4	0.0	38480.0	7438.1	5135.4	31041.9
176+00.0000	164.8	14.1	0.0	641.2	44.8	0.0	39121.3	7494.1	5135.4	31627.2
177+00.0000	59.4	7.6	0.0	415.2	40.3	0.0	39536.5	7544.4	5135.4	31992.1
178+00.0000	54.6	1.7	0.0	211.0	17.2	0.0	39747.6	7565.9	5135.4	32181.7
178+69.0000	58.5	0.3	0.0	144.5	2.5	0.0	39892.0	7569.1	5135.4	32323.0
179+00.0000	127.6	0.0	0.0	106.8	0.2	0.0	39998.9	7569.3	5135.4	32429.6
179+44.0000	48.1	0.5	0.0	143.1	0.4	0.0	40142.0	7569.7	5135.4	32572.3
180+00.0000	117.4	1.1	0.0	171.6	1.6	0.0	40313.6	7571.7	5135.4	32741.9
181+00.0000	105.8	0.8	0.0	413.4	3.5	0.0	40727.1	7576.0	5135.4	33151.1
182+00.0000	102.1	0.3	0.0	385.1	2.0	0.0	41112.2	7578.5	5135.4	33533.7
183+00.0000	100.7	0.4	0.0	375.6	1.4	0.0	41487.7	7580.2	5135.4	33907.5
184+00.0000	118.3	0.0	0.0	405.4	0.8	0.0	41893.2	7581.3	5135.4	34311.9
185+00.0000	107.8	0.1	0.0	418.6	0.1	0.0	42311.8	7581.4	5135.4	34730.4
186+00.0000	113.4	0.1	0.0	409.7	0.4	0.0	42721.5	7581.9	5135.4	35139.5
187+00.0000	104.3	0.0	0.0	403.3	0.3	0.0	43124.8	7582.3	5135.4	35542.4
188+00.0000	99.8	0.2	0.0	378.0	0.4	0.0	43502.8	7582.8	5135.4	35920.0
189+00.0000	107.9	0.0	0.0	384.6	0.4	0.0	43887.4	7583.4	5135.4	36304.1
189+34.0000	71.5	0.0	0.0	112.9	0.0	0.0	44000.4	7583.4	5135.4	36417.0
190+00.0000	94.3	0.0	0.0	202.6	0.0	0.0	44202.9	7583.4	5135.4	36619.5
190+64.0000	72.0	3.2	0.0	197.1	3.8	0.0	44400.0	7588.2	5135.4	36811.8
191+00.0000	71.4	9.2	0.0	95.6	8.2	0.0	44495.6	7598.5	5135.4	36897.1
191+61.0000	50.0	28.9	0.0	137.2	43.0	0.0	44632.8	7652.2	5135.4	36980.5
191+80.0000	62.4	106.2	0.0	39.6	47.5	0.0	44672.3	7711.7	5135.4	36960.7
192+00.0000	45.2	22.7	0.0	39.9	47.8	0.0	44712.2	7771.3	5135.4	36940.9
193+00.0000	56.7	4.4	0.0	188.7	50.3	0.0	44900.9	7834.2	5135.4	37066.7
193+20.0000	52.3	9.9	0.0	40.4	5.3	0.0	44941.2	7840.8	5135.4	37100.5
194+00.0000	104.6	1.5	0.0	232.5	16.9	0.0	45173.7	7862.0	5135.4	37311.8
195+00.0000	75.2	7.0	0.0	333.1	15.7	0.0	45506.8	7881.6	5135.4	37625.2
196+00.0000	86.3	0.0	0.0	299.1	12.9	0.0	45805.9	7897.7	5135.4	37908.2
196+60.0000	63.9	6.2	0.0	166.9	6.9	0.0	45972.7	7906.3	5135.4	38066.4
197+00.0000	77.9	1.8	0.0	105.1	5.9	0.0	46077.8	7913.8	5135.4	38164.1
198+00.0000	82.8	1.7	0.0	297.7	6.5	0.0	46375.6	7921.9	5135.4	38453.7
198+88.0000	90.4	6.3	0.0	275.9	12.8	0.0	46651.4	7937.9	5135.4	38713.5
199+00.0000	116.4	0.8	0.0	53.6	1.9	0.0	46705.0	7940.2	5135.4	38764.8

EARTHWORK SUMMARY FOR STH 136

	AREA (SF)			Incremental Vol (CY)			Cumulative Vol (CY)			
STATION	Common	Fill	Rock Exc	Common	Fill	Rock Exc	Common	Fill	Rock	Mass Haul
199+85.0000	47.8	28.1	0.0	258.5	45.5	0.0	46963.5	7997.1	5135.4	38966.4
200+00.0000	51.1	17.0	0.0	27.5	12.5	0.0	46991.0	8012.8	5135.4	38978.2
201+00.0000	142.0	0.0	0.0	357.6	31.5	0.0	47348.6	8052.2	5135.4	39296.4
202+00.0000	145.7	0.0	0.0	532.8	0.1	0.0	47881.4	8052.3	5135.4	39829.1
203+00.0000	122.8	0.3	0.0	497.2	0.6	0.0	48378.6	8053.0	5135.4	40325.6
204+00.0000	116.8	0.3	0.0	443.7	1.1	0.0	48822.3	8054.4	5135.4	40767.9
205+00.0000	90.3	2.0	0.0	383.6	4.3	0.0	49205.9	8059.7	5135.4	41146.2
206+00.0000	74.4	5.6	0.0	305.0	14.0	0.0	49510.8	8077.3	5135.4	41433.6
207+00.0000	17.5	8.4	0.0	170.2	25.9	0.0	49681.1	8109.7	5135.4	41571.4
208+00.0000	93.2	29.7	0.0	205.0	70.6	0.0	49886.0	8197.9	5135.4	41688.1
209+00.0000	140.4	0.2	0.0	432.5	55.3	0.0	50318.6	8267.1	5135.4	42051.5
210+00.0000	155.7	0.1	0.0	548.4	0.5	0.0	50867.0	8267.7	5135.4	42599.3
211+00.0000	186.9	0.1	0.0	634.5	0.3	0.0	51501.5	8268.1	5135.4	43233.4
212+00.0000	200.8	0.0	0.0	718.0	0.2	0.0	52219.5	8268.3	5135.4	43951.2
212+99.0000	159.6	3.5	0.0	660.7	6.4	0.0	52880.2	8276.2	5135.4	44604.0
213+00.0000	160.0	3.4	0.0	5.9	0.1	0.0	52886.1	8276.4	5135.4	44609.7
214+00.0000	56.2	33.0	0.0	400.3	67.3	0.0	53286.5	8360.5	5135.4	44925.9
214+15.0000	53.3	71.2	0.0	30.4	29.0	0.0	53316.9	8396.7	5135.4	44920.2
215+00.0000	63.5	10.2	0.0	183.9	128.2	0.0	53500.8	8556.9	5135.4	44943.9
215+14.0000	70.4	4.9	0.0	34.7	3.9	0.0	53535.5	8561.8	5135.4	44973.7
215+29.0000	46.9	9.6	0.0	32.6	4.0	0.0	53568.1	8566.8	5135.4	45001.3
216+00.0000	86.2	5.5	0.0	174.9	19.9	0.0	53743.0	8591.6	5135.4	45151.4
217+00.0000	65.3	8.0	0.0	280.5	25.1	0.0	54023.5	8623.0	5135.4	45400.5
217+86.0000	52.7	5.4	0.0	187.9	21.3	0.0	54211.4	8649.7	5135.4	45561.8
218+00.0000	55.0	11.8	0.0	27.9	4.4	0.0	54239.4	8655.2	5135.4	45584.1
219+00.0000	69.4	6.3	0.0	230.4	33.4	0.0	54469.7	8697.0	5135.4	45772.7
220+00.0000	76.8	1.7	0.0	270.7	14.8	0.0	54740.5	8715.5	5135.4	46025.0
221+00.0000	101.2	0.2	0.0	329.6	3.4	0.0	55070.0	8719.7	5135.4	46350.3
222+00.0000	62.2	4.3	0.0	302.6	8.3	0.0	55372.6	8730.1	5135.4	46642.5
223+00.0000	39.1	7.6	0.0	187.6	22.1	0.0	55560.2	8757.7	5135.4	46802.5
223+30.0000	25.2	9.2	0.0	35.7	9.3	0.0	55595.9	8769.4	5135.4	46826.6
224+00.0000	31.5	16.3	0.0	73.5	33.1	0.0	55669.4	8810.7	5135.4	46858.7
225+00.0000	62.4	41.5	0.0	173.9	107.1	0.0	55843.4	8944.5	5135.4	46898.8
226+00.0000	71.4	50.0	0.0	247.7	169.5	0.0	56091.1	9156.4	5135.4	46934.7
227+00.0000	63.1	126.8	0.0	249.2	327.4	0.0	56340.3	9565.6	5135.4	46774.6
228+00.0000	50.9	140.2	0.0	211.1	494.4	0.0	56551.3	10183.6	5135.4	46367.7
229+00.0000	83.6	42.2	0.0	248.9	337.7	0.0	56800.3	10605.7	5135.4	46194.6
230+00.0000	169.9	0.9	0.0	469.4	79.8	0.0	57269.6	10705.5	5135.4	46564.1
230+71.0000	117.5	4.6	0.0	377.9	7.3	0.0	57647.5	10714.7	5135.4	46932.8
231+00.0000	72.2	16.8	0.0	101.9	11.5	0.0	57749.4	10729.1	5135.4	47020.4
232+00.0000	21.7	153.2	0.0	173.9	314.7	0.0	57923.3	11122.5	5135.4	46800.8
233+00.0000	188.5	159.8	0.0	389.1	579.6	0.0	58312.4	11847.0	5135.4	46465.5
234+00.0000	304.1	214.8	0.0	912.1	693.7	0.0	59224.5	12714.1	5135.4	46510.5
235+00.0000	406.1	119.2	0.0	1315.2	618.6	0.0	60539.8	13487.3	5135.4	47052.4
236+00.0000	469.2	43.1	0.0	1621.0	300.6	0.0	62160.8	13863.1	5135.4	48297.6
237+00.0000	453.1	58.0	0.0	1708.1	187.3	0.0	63868.9	14097.2	5135.4	49771.6
238+00.0000	370.0	24.5	0.0	1524.4	152.7	0.0	65393.2	14288.1	5135.4	51105.1
239+00.0000	228.9	45.5	0.0	1109.0	129.6	0.0	66502.3	14450.1	5135.4	52052.1
240+00.0000	131.1	33.5	0.0	666.6	146.3	0.0	67168.9	14633.0	5135.4	52535.9
241+00.0000	166.7	54.6	0.0	551.5	163.2	0.0	67720.4	14837.1	5135.4	52883.4
242+00.0000	279.1	69.6	0.0	825.5	230.1	0.0	68546.0	15124.7	5135.4	53421.3
243+00.0000	489.5	54.5	0.0	1423.3	229.9	0.0	69669.2	15412.1	5135.4	54557.1

EARTHWORK SUMMARY FOR STH 136

AREA (SF)			Incremental Vol (CY)			Cumulative Vol (CY)				
STATION	Common	Fill	Rock Exc	Common	Fill	Rock Exc	Common	Fill	Rock	Mass Haul
244+00.0000	475.2	19.3	0.0	1786.4	136.7	0.0	71755.6	15583.0	5135.4	56172.6
264+00.0000	65.0	3.6	0.0	10.0	0.4	0.0	71765.6	15583.6	5135.4	56182.0
265+00.0000	84.5	4.4	0.0	276.7	14.8	0.0	72042.3	15602.0	5135.4	56440.3
266+00.0000	53.7	19.6	0.0	255.8	44.3	0.0	72298.1	15657.4	5135.4	56640.7
267+00.0000	38.9	60.0	0.0	171.5	147.3	0.0	72469.5	15841.5	5135.4	56628.0
268+00.0000	58.4	92.8	0.0	180.2	282.9	0.0	72649.8	16195.1	5135.4	56454.6
269+00.0000	78.1	121.0	0.0	252.8	395.8	0.0	72902.5	16689.9	5135.4	56212.6
270+00.0000	100.2	92.4	0.0	330.2	395.1	0.0	73232.8	17183.7	5135.4	56049.1
271+00.0000	108.0	51.9	0.0	385.5	267.1	0.0	73618.3	17517.6	5135.4	56100.7
272+00.0000	157.5	11.7	0.0	491.6	117.7	0.0	74109.9	17664.7	5135.4	56445.1
273+00.0000	133.4	4.2	0.0	538.6	29.5	0.0	74648.5	17701.5	5135.4	56946.9
274+00.0000	135.7	0.0	0.0	498.2	7.9	0.0	75146.6	17711.4	5135.4	57435.3
275+00.0000	212.8	0.0	0.0	645.2	0.1	0.0	75791.8	17711.4	5135.4	58080.4
276+00.0000	223.7	7.1	0.0	808.3	13.2	0.0	76600.1	17727.9	5135.4	58872.2
277+00.0000	133.9	35.7	0.0	662.3	79.1	0.0	77262.4	17826.8	5135.4	59435.6
278+00.0000	98.5	38.5	0.0	430.3	137.4	0.0	77692.7	17998.6	5135.4	59694.1
279+00.0000	93.3	36.4	0.0	355.0	138.7	0.0	78047.7	18172.0	5135.4	59875.7
280+00.0000	93.1	53.4	0.0	345.1	166.2	0.0	78392.8	18379.8	5135.4	60013.0
281+00.0000	86.8	43.4	0.0	333.0	179.2	0.0	78725.8	18603.9	5135.4	60121.9
281+78.0000	144.1	84.9	0.0	333.4	185.4	0.0	79059.2	18835.5	5135.4	60223.6
282+00.0000	38.3	82.4	0.0	74.3	68.2	0.0	79133.5	18920.8	5135.4	60212.7
283+00.0000	47.1	84.8	0.0	158.2	309.6	0.0	79291.6	19307.8	5135.4	59983.9
284+00.0000	143.5	29.9	0.0	353.0	212.4	0.0	79644.6	19573.3	5135.4	60071.3
285+00.0000	225.5	0.0	211.6	683.2	55.5	391.9	80327.8	19642.6	5527.2	60685.2
285+25.0000	244.4	0.0	154.8	217.5	0.0	169.6	80545.4	19642.6	5696.8	60902.7
285+50.0000	332.3	0.0	182.4	267.0	0.0	166.1	80812.3	19642.6	5852.9	61169.7
285+75.0000	430.8	0.0	208.1	353.3	0.0	180.8	81165.6	19642.6	6033.7	61523.0
286+00.0000	574.6	0.0	211.5	465.5	0.0	194.3	81631.1	19642.6	6228.0	61988.5
286+25.0000	647.4	0.0	232.3	565.7	0.0	205.5	82196.9	19642.6	6433.4	62554.2
286+50.0000	672.5	0.0	250.7	611.1	0.0	223.6	82807.9	19642.6	6657.0	63165.3
286+75.0000	639.3	0.0	256.4	607.3	0.0	234.7	83415.2	19642.6	6891.8	63772.6
287+00.0000	602.1	0.0	269.5	574.7	0.0	243.5	83990.0	19642.6	7135.3	64347.3
288+00.0000	439.1	0.0	0.0	1928.1	0.0	499.1	85918.1	19642.6	7634.4	66275.4
289+00.0000	150.8	5.7	0.0	1092.3	10.5	0.0	87010.4	19655.7	7634.4	67354.7
290+00.0000	64.5	28.9	0.0	398.6	64.0	0.0	87409.0	19735.8	7634.4	67673.2
290+25.0000	56.9	28.5	0.0	56.2	26.6	0.0	87465.1	19769.0	7634.4	67696.2
290+79.7900	56.0	17.1	0.0	114.5	46.3	0.0	87579.7	19826.8	7634.4	67752.9
291+00.0000	78.8	12.5	0.0	50.4	11.1	0.0	87630.1	19840.7	7634.4	67789.4
291+25.0000	56.3	17.0	0.0	62.6	13.7	0.0	87692.7	19857.8	7634.4	67834.9
291+50.0000	61.0	24.0	0.0	54.3	19.0	0.0	87747.0	19881.5	7634.4	67865.5
291+60.0000	59.2	21.9	0.0	22.3	8.5	0.0	87769.3	19892.2	7634.4	67877.1
291+63.0000	59.5	19.5	0.0	6.6	2.3	0.0	87775.8	19895.1	7634.4	67880.8
291+75.0000	63.6	0.4	0.0	27.4	4.4	0.0	87803.2	19900.6	7634.4	67902.6
292+00.0000	47.7	0.0	0.0	51.5	0.2	0.0	87854.7	19900.8	7634.4	67953.9

Fill quantities in the cumulative column are expanded using a factor of 1.25

EARTHWORK SUMMARY FOR BELTER ST

AREA (SF)		Incremental Vol (CY)			Cumulative Vol (CY)		
STATION	Common	Fill	Common	Fill	Common	Fill	Mass Haul
7+81.9400	25.1	0.1					
8+00.0000	27.4	0.4	17.6	0.2	17.6	0.2	17.3
8+50.0000	77.3	1.3	97.0	1.6	114.5	2.2	112.3
9+00.0000	133.6	0.0	195.3	1.2	309.8	3.6	306.2
9+25.0000	111.3	1.3	113.4	0.6	423.2	4.4	418.8
9+45.0000	114.2	0.8	83.5	0.8	506.7	5.4	501.3
9+62.4500	120.4	0.0	75.8	0.2	582.5	5.7	576.8
9+71.8600	134.6	0.0	44.4	0.0	626.9	5.7	621.2
9+82.8900	89.3	0.0	45.7	0.0	672.7	5.7	667.0

Fill quantities in the cumulative column are expanded using a factor of 1.25

EARTHWORK SUMMARY FOR BENDER ST

AREA (SF)		Incremental Vol (CY)			Cumulative Vol (CY)		
STATION	Common	Fill	Common	Fill	Common	Fill	Mass Haul
8+72.0000	22.9	0.0					
9+00.0000	23.7	0.0	24.1	0.0	24.1	0.0	24.1
9+40.0000	33.9	0.0	42.7	0.0	66.8	0.0	66.8
9+60.0000	38.3	14.2	26.8	5.2	93.6	6.6	87.0

Fill quantities in the cumulative column are expanded using a factor of 1.25

EARTHWORK SUMMARY FOR CTH I

AREA (SF)		Incremental Vol (CY)			Cumulative Vol (CY)		
STATION	Common	Fill	Common	Fill	Common	Fill	Mass Haul
10+50.0000	0.0	230.2					
11+00.0000	0.0	110.7	0.0	315.6	0.0	394.5	-394.5
11+50.0000	0.1	17.7	0.1	118.9	0.1	543.2	-543.1
12+00.0000	41.0	2.2	38.1	18.4	38.1	566.2	-528.1
12+50.0000	52.0	1.9	86.2	3.8	124.3	571.0	-446.7

Fill quantities in the cumulative column are expanded using a factor of 1.25

EARTHWORK SUMMARY FOR EXCELSIOR DR

STATION	AREA (SF)		Incremental Vol (CY)		Cumulative Vol (CY)		Mass Haul
	Common	Fill	Common	Fill	Common	Fill	
8+50.0000	48.2	3.9					
9+00.0000	83.8	0.0	122.3	3.6	122.3	4.5	117.8
9+30.0000	131.9	0.0	119.8	0.0	242.1	4.5	237.6
9+50.0000	181.1	0.0	115.9	0.0	358.0	4.5	353.5

Fill quantities in the cumulative column are expanded using a factor of 1.25

EARTHWORK SUMMARY FOR HOLTZ RD

STATION	AREA (SF)		Incremental Vol (CY)		Cumulative Vol (CY)		Mass Haul
	Common	Fill	Common	Fill	Common	Fill	
10+30.0000	36.8	6.3					
10+50.0000	26.7	2.2	23.5	3.2	23.5	4.0	19.6
10+85.0000	19.2	0.0	29.8	1.5	53.3	5.8	47.5

Fill quantities in the cumulative column are expanded using a factor of 1.25

EARTHWORK SUMMARY FOR MADISON ST

STATION	AREA (SF)		Incremental Vol (CY)		Cumulative Vol (CY)		Mass Haul
	Common	Fill	Common	Fill	Common	Fill	
10+16.0000	174.1	0.0					
10+23.2400	119.5	0.0	39.4	0.0	39.4	0.0	39.4
10+47.7600	112.7	0.0	105.5	0.0	144.8	0.0	144.8
10+50.0000	104.7	0.0	9.0	0.0	153.8	0.0	153.8
11+00.0000	67.1	0.0	159.1	0.0	312.9	0.0	312.9
11+50.0000	44.7	0.0	103.5	0.0	416.4	0.0	416.4
11+65.0000	46.2	0.0	25.2	0.0	441.6	0.0	441.6
11+90.0000	38.0	0.0	39.0	0.0	480.6	0.0	480.6
12+00.0000	37.6	0.2	14.0	0.0	494.6	0.1	494.5
12+35.0000	26.3	0.0	41.4	0.1	536.0	0.2	535.8

Fill quantities in the cumulative column are expanded using a factor of 1.25

EARTHWORK SUMMARY FOR MONTGOMERY RD

STATION	AREA (SF)		Incremental Vol (CY)		Cumulative Vol (CY)		Mass Haul
	Common	Fill	Common	Fill	Common	Fill	
8+84.0000	40.0	0.1					
9+00.0000	31.7	0.5	21.3	0.2	21.3	0.2	21.0
9+21.0000	38.6	0.1	27.4	0.2	48.6	0.5	48.1
9+50.0000	62.8	0.0	54.5	0.0	103.1	0.5	102.6
9+79.0000	91.8	20.0	83.1	10.7	186.1	13.9	172.2

Fill quantities in the cumulative column are expanded using a factor of 1.25

EARTHWORK SUMMARY FOR QUARRY RD

STATION	AREA (SF)		Incremental Vol (CY)		Cumulative Vol (CY)		Mass Haul
	Common	Fill	Common	Fill	Common	Fill	
8+82.0000	31.5	0.0					
9+00.0000	12.3	0.0	14.6	0.0	14.6	0.0	14.6
9+50.0000	69.1	0.0	75.3	0.0	89.9	0.0	89.9
9+75.0000	122.8	1.8	88.9	0.8	178.8	1.0	177.8

Fill quantities in the cumulative column are expanded using a factor of 1.25